



# Code of Federal Regulations

---

## 40

**Parts 700 to 789**

Revised as of July 1, 2010

### **Protection of Environment**

---

Containing a codification of documents  
of general applicability and future effect

As of July 1, 2010

*With Ancillaries*

Published by  
Office of the Federal Register  
National Archives and Records  
Administration

A Special Edition of the Federal Register



## U.S. GOVERNMENT OFFICIAL EDITION NOTICE

### Legal Status and Use of Seals and Logos

The seal of the National Archives and Records Administration (NARA) authenticates the Code of Federal Regulations (CFR) as the official codification of Federal regulations established under the Federal Register Act. Under the provisions of 44 U.S.C. 1507, the contents of the CFR, a special edition of the Federal Register, shall be judicially noticed. The CFR is prima facie evidence of the original documents published in the Federal Register (44 U.S.C. 1510).

It is prohibited to use NARA's official seal and the stylized Code of Federal Regulations logo on any republication of this material without the express, written permission of the Archivist of the United States or the Archivist's designee. Any person using NARA's official seals and logos in a manner inconsistent with the provisions of 36 CFR part 1200 is subject to the penalties specified in 18 U.S.C. 506, 701, and 1017.

### Use of ISBN Prefix

This is the Official U.S. Government edition of this publication and is herein identified to certify its authenticity. Use of the 0-16 ISBN prefix is for U.S. Government Printing Office Official Editions only. The Superintendent of Documents of the U.S. Government Printing Office requests that any reprinted edition clearly be labeled as a copy of the authentic work with a new ISBN.



U.S. GOVERNMENT PRINTING OFFICE

U.S. Superintendent of Documents • Washington, DC 20402-0001

<http://bookstore.gpo.gov>

Phone: toll-free (866) 512-1800; DC area (202) 512-1800

# Table of Contents

|   | <i>Page</i> |
|---|-------------|
| Explanation .....   | v           |
| Title 40:   |             |
| Chapter I—Environmental Protection Agency (Continued) ..... | 3           |
| Finding Aids:   |             |
| Table of CFR Titles and Chapters .....                      | 947         |
| Alphabetical List of Agencies Appearing in the CFR .....    | 967         |
| List of CFR Sections Affected .....                         | 977         |

---

*Cite this Code:* CFR

*To cite the regulations in  
this volume use title,  
part and section num-  
ber. Thus, 40 CFR  
700.40 refers to title 40,  
part 700, section 40.*

---

## Explanation

The Code of Federal Regulations is a codification of the general and permanent rules published in the Federal Register by the Executive departments and agencies of the Federal Government. The Code is divided into 50 titles which represent broad areas subject to Federal regulation. Each title is divided into chapters which usually bear the name of the issuing agency. Each chapter is further subdivided into parts covering specific regulatory areas.

Each volume of the Code is revised at least once each calendar year and issued on a quarterly basis approximately as follows:

|                                |                 |
|--------------------------------|-----------------|
| Title 1 through Title 16.....  | as of January 1 |
| Title 17 through Title 27..... | as of April 1   |
| Title 28 through Title 41..... | as of July 1    |
| Title 42 through Title 50..... | as of October 1 |

The appropriate revision date is printed on the cover of each volume.

### LEGAL STATUS

The contents of the Federal Register are required to be judicially noticed (44 U.S.C. 1507). The Code of Federal Regulations is prima facie evidence of the text of the original documents (44 U.S.C. 1510).

### HOW TO USE THE CODE OF FEDERAL REGULATIONS

The Code of Federal Regulations is kept up to date by the individual issues of the Federal Register. These two publications must be used together to determine the latest version of any given rule.

To determine whether a Code volume has been amended since its revision date (in this case, July 1, 2010), consult the "List of CFR Sections Affected (LSA)," which is issued monthly, and the "Cumulative List of Parts Affected," which appears in the Reader Aids section of the daily Federal Register. These two lists will identify the Federal Register page number of the latest amendment of any given rule.

### EFFECTIVE AND EXPIRATION DATES

Each volume of the Code contains amendments published in the Federal Register since the last revision of that volume of the Code. Source citations for the regulations are referred to by volume number and page number of the Federal Register and date of publication. Publication dates and effective dates are usually not the same and care must be exercised by the user in determining the actual effective date. In instances where the effective date is beyond the cut-off date for the Code a note has been inserted to reflect the future effective date. In those instances where a regulation published in the Federal Register states a date certain for expiration, an appropriate note will be inserted following the text.

### OMB CONTROL NUMBERS

The Paperwork Reduction Act of 1980 (Pub. L. 96-511) requires Federal agencies to display an OMB control number with their information collection request.

Many agencies have begun publishing numerous OMB control numbers as amendments to existing regulations in the CFR. These OMB numbers are placed as close as possible to the applicable recordkeeping or reporting requirements.

#### OBSOLETE PROVISIONS

Provisions that become obsolete before the revision date stated on the cover of each volume are not carried. Code users may find the text of provisions in effect on a given date in the past by using the appropriate numerical list of sections affected. For the period before January 1, 2001, consult either the List of CFR Sections Affected, 1949–1963, 1964–1972, 1973–1985, or 1986–2000, published in eleven separate volumes. For the period beginning January 1, 2001, a “List of CFR Sections Affected” is published at the end of each CFR volume.

#### “[RESERVED]” TERMINOLOGY

The term “[Reserved]” is used as a place holder within the Code of Federal Regulations. An agency may add regulatory information at a “[Reserved]” location at any time. Occasionally “[Reserved]” is used editorially to indicate that a portion of the CFR was left vacant and not accidentally dropped due to a printing or computer error.

#### INCORPORATION BY REFERENCE

*What is incorporation by reference?* Incorporation by reference was established by statute and allows Federal agencies to meet the requirement to publish regulations in the Federal Register by referring to materials already published elsewhere. For an incorporation to be valid, the Director of the Federal Register must approve it. The legal effect of incorporation by reference is that the material is treated as if it were published in full in the Federal Register (5 U.S.C. 552(a)). This material, like any other properly issued regulation, has the force of law.

*What is a proper incorporation by reference?* The Director of the Federal Register will approve an incorporation by reference only when the requirements of 1 CFR part 51 are met. Some of the elements on which approval is based are:

- (a) The incorporation will substantially reduce the volume of material published in the Federal Register.
- (b) The matter incorporated is in fact available to the extent necessary to afford fairness and uniformity in the administrative process.
- (c) The incorporating document is drafted and submitted for publication in accordance with 1 CFR part 51.

*What if the material incorporated by reference cannot be found?* If you have any problem locating or obtaining a copy of material listed as an approved incorporation by reference, please contact the agency that issued the regulation containing that incorporation. If, after contacting the agency, you find the material is not available, please notify the Director of the Federal Register, National Archives and Records Administration, 8601 Adelphi Road, College Park, MD 20740-6001, or call 202-741-6010.

#### CFR INDEXES AND TABULAR GUIDES

A subject index to the Code of Federal Regulations is contained in a separate volume, revised annually as of January 1, entitled CFR INDEX AND FINDING AIDS. This volume contains the Parallel Table of Authorities and Rules. A list of CFR titles, chapters, subchapters, and parts and an alphabetical list of agencies publishing in the CFR are also included in this volume.

An index to the text of “Title 3—The President” is carried within that volume.

The Federal Register Index is issued monthly in cumulative form. This index is based on a consolidation of the “Contents” entries in the daily Federal Register.

A List of CFR Sections Affected (LSA) is published monthly, keyed to the revision dates of the 50 CFR titles.

#### REPUBLICATION OF MATERIAL

There are no restrictions on the republication of material appearing in the Code of Federal Regulations.

#### INQUIRIES

For a legal interpretation or explanation of any regulation in this volume, contact the issuing agency. The issuing agency’s name appears at the top of odd-numbered pages.

For inquiries concerning CFR reference assistance, call 202–741–6000 or write to the Director, Office of the Federal Register, National Archives and Records Administration, 8601 Adelphi Road, College Park, MD 20740-6001 or e-mail [fedreg.info@nara.gov](mailto:fedreg.info@nara.gov).

#### SALES

The Government Printing Office (GPO) processes all sales and distribution of the CFR. For payment by credit card, call toll-free, 866-512-1800, or DC area, 202-512-1800, M-F 8 a.m. to 4 p.m. e.s.t. or fax your order to 202-512-2250, 24 hours a day. For payment by check, write to: US Government Printing Office – New Orders, P.O. Box 979050, St. Louis, MO 63197-9000. For GPO Customer Service call 202-512-1803.

#### ELECTRONIC SERVICES

The full text of the Code of Federal Regulations, the LSA (List of CFR Sections Affected), The United States Government Manual, the Federal Register, Public Laws, Public Papers, Daily Compilation of Presidential Documents and the Privacy Act Compilation are available in electronic format via *Federalregister.gov*. For more information, contact Electronic Information Dissemination Services, U.S. Government Printing Office. Phone 202-512-1530, or 888-293-6498 (toll-free). E-mail, [gpoaccess@gpo.gov](mailto:gpoaccess@gpo.gov).

The Office of the Federal Register also offers a free service on the National Archives and Records Administration’s (NARA) World Wide Web site for public law numbers, Federal Register finding aids, and related information. Connect to NARA’s web site at [www.archives.gov/federal-register](http://www.archives.gov/federal-register). The NARA site also contains links to GPO Access.

RAYMOND A. MOSLEY,  
*Director,*  
*Office of the Federal Register.*  
*July 1, 2010.*





## THIS TITLE

Title 40—PROTECTION OF ENVIRONMENT is composed of thirty-two volumes. The parts in these volumes are arranged in the following order: parts 1–49, parts 50–51, part 52 (52.01–52.1018), part 52 (52.1019–end of part 52), parts 53–59, part 60 (60.1–end of part 60, sections), part 60 (Appendices), parts 61–62, part 63 (63.1–63.599), part 63 (63.600–63.1199), part 63 (63.1200–63.1439), part 63 (63.1440–63.6175), part 63 (63.6580–63.8830), part 63 (63.8980–end of part 63) parts 64–71, parts 72–80, parts 81–84, part 85–§86.599–99, part 86 (86.600–1–end of part 86), parts 87–99, parts 100–135, parts 136–149, parts 150–189, parts 190–259, parts 260–265, parts 266–299, parts 300–399, parts 400–424, parts 425–699, parts 700–789, parts 790–999, and part 1000 to end. The contents of these volumes represent all current regulations codified under this title of the CFR as of July 1, 2010.

Chapter I—Environmental Protection Agency appears in all thirty-two volumes. Regulations issued by the Council on Environmental Quality, including an Index to Parts 1500 through 1508, appear in the volume containing part 1000 to end. The OMB control numbers for title 40 appear in §9.1 of this chapter.

For this volume, Jonn V. Lilyea was Chief Editor. The Code of Federal Regulations publication program is under the direction of Michael L. White, assisted by Ann Worley.

# Title 40—Protection of Environment

(This book contains parts 700 to 789)

---

|   |             |
|---|-------------|
|   | <i>Part</i> |
| CHAPTER I—Environmental Protection Agency (Continued) | 700         |



# CHAPTER I—ENVIRONMENTAL PROTECTION AGENCY (CONTINUED)

EDITORIAL NOTE: Nomenclature changes to chapter I appear at 65 FR 47324, 47325, Aug. 2, 2000; 66 FR 34375, 34376, June 28, 2001.

## SUBCHAPTER R—TOXIC SUBSTANCES CONTROL ACT

| <i>Part</i> |  | <i>Page</i> |
|-------------|--|-------------|
| 700         | General .....  | 5           |
| 702         | General practices and procedures .....   | 8           |
| 704         | Reporting and recordkeeping requirements .....   | 9           |
| 707         | Chemical imports and exports .....   | 26          |
| 710         | TSCA chemical inventory regulations .....  | 31          |
| 712         | Chemical information rules .....   | 61          |
| 716         | Health and safety data reporting .....   | 83          |
| 717         | Records and reports of allegations that chemical<br>substances cause significant adverse reactions to<br>health or the environment ..... | 122         |
| 720         | Premanufacture notification .....  | 127         |
| 721         | Significant new uses of chemical substances .....  | 155         |
| 723         | Premanufacture notification exemptions .....   | 550         |
| 725         | Reporting requirements and review processes for<br>microorganisms .....  | 573         |
| 745         | Lead-based paint poisoning prevention in certain<br>residential structures .....   | 622         |
| 747         | Metalworking fluids .....  | 687         |
| 749         | Water treatment chemicals .....  | 692         |
| 750         | Procedures for rulemaking under section 6 of the<br>Toxic Substances Control Act .....   | 695         |
| 761         | Polychlorinated biphenyls (PCBs) manufacturing,<br>processing, distribution in commerce, and use<br>prohibitions .....                   | 710         |
| 763         | Asbestos .....   | 838         |
| 766         | Dibenzo-para-dioxins/dibenzofurans .....   | 933         |
| 767–789     | [Reserved]   |             |



## SUBCHAPTER R—TOXIC SUBSTANCES CONTROL ACT

### PART 700—GENERAL

#### Subparts A–B [Reserved]

#### Subpart C—Fees

|        |                            |
|--------|----------------------------|
| Sec.   |                            |
| 700.40 | Purpose and applicability. |
| 700.41 | Radon user fees.           |
| 700.43 | Definitions.               |
| 700.45 | Fee payments.              |
| 700.49 | Failure to remit fees.     |

AUTHORITY: 15 U.S.C 2625 and 2665, 44 U.S.C. 3504.

SOURCE: 53 FR 31252, Aug. 17, 1988, unless otherwise noted.

#### Subparts A–B [Reserved]

#### Subpart C—Fees

##### § 700.40 Purpose and applicability.

(a) *Purpose.* The purpose of this subpart is to collect fees from manufacturers, importers, and processors who submit notices and applications to EPA under section 5 of the Toxic Substances Control Act (15 U.S.C. 2604) to defray part of EPA's cost of administering the Act.

(b) *Applicability.* This subpart applies to all manufacturers, importers, and processors who submit certain notices and applications to EPA under section 5 of the Act.

##### § 700.41 Radon user fees.

User fees relating to radon proficiency programs authorized under the Toxic Substances Control Act appear at 40 CFR part 195.

[59 FR 13177, Mar. 18, 1994]

##### § 700.43 Definitions.

Definitions in section 3 of the Act (15 U.S.C. 2602), as well as definitions contained in §§ 704.3, 720.3, and 725.3 of this chapter, apply to this subpart unless otherwise specified in this section. In addition, the following definitions apply:

*Consolidated microbial commercial activity notice* or *consolidated MCAN* means any MCAN submitted to EPA that covers more than one microorga-

nism (each being assigned a separate MCAN number by EPA) as a result of a prenotice agreement with EPA.

*Consolidated premanufacture notice* or *consolidated PMN* means any PMN submitted to EPA that covers more than one chemical substance (each being assigned a separate PMN number by EPA) as a result of a prenotice agreement with EPA (See 48 FR 21734).

*Exemption application* means any application submitted to EPA under section 5(h)(2) of the Act.

*Exemption notice* means any notice submitted to EPA under § 723.175 of this chapter.

*Final product* means a new chemical substance (as “new chemical substance” is defined in § 720.3 of this chapter) that is manufactured by a person for distribution in commerce, or for use by the person other than as an intermediate.

*Intermediate premanufacture notice* or *intermediate PMN* means any PMN submitted to EPA for a chemical substance which is an intermediate (as “intermediate” is defined in § 720.3 of this chapter) in the production of a final product, provided that the PMN for the intermediate is submitted to EPA at the same time as, and together with, the PMN for the final product and that the PMN for the intermediate identifies the final product and describes the chemical reactions leading from the intermediate to the final product. If PMNs are submitted to EPA at the same time for several intermediates used in the production of a final product, each of those is an intermediate PMN if they all identify the final product and every other associated intermediate PMN and are submitted to EPA at the same time as, and together with, the PMN for the final product.

*Joint submitters* means two or more persons who submit a section 5 notice together.

*Microbial commercial activity notice* or *MCAN* means any notice for microorganisms submitted to EPA pursuant to section 5(a)(1) of the Act in accordance with subpart D of part 725 of this chapter.

## § 700.45

## 40 CFR Ch. I (7–1–10 Edition)

*Person* means a manufacturer, importer, or processor.

*Premanufacture notice* or *PMN* means any notice submitted to EPA pursuant to section 5(a)(1)(A) of the Act in accordance with part 720 of this chapter or § 723.250 of this chapter.

*Section 5 notice* means any PMN, consolidated PMN, intermediate PMN, significant new use notice, exemption notice, exemption application, any MCAN or consolidated MCAN submitted under section 5 of the Act.

*Significant new use notice* means any notice submitted to EPA pursuant to section 5(a)(1)(B) of the Act in accordance with part 721 of this chapter.

*Small business concern* means any person whose total annual sales in the person's fiscal year preceding the date of the submission of the applicable section 5 notice, when combined with those of the parent company (if any), are less than \$40 million.

[53 FR 31252, Aug. 17, 1988, as amended at 62 FR 17931, April 11, 1997]

### § 700.45 Fee payments.

(a) *Persons who must pay fees.* Persons submitting a section 5 notice to EPA shall remit for each such notice the appropriate fee identified in paragraph (b) of this section in accordance with the procedures in paragraph (e) of this section.

(b) *Fees.* Persons shall remit fee payments to EPA as follows:

(1) *Small business concerns.* Small business concerns shall remit a fee of \$100 for each section 5 notice submitted.

(2) *Others.* Persons other than small business concerns shall remit fees according to the type of section 5 notice as follows:

(i) *Premanufacture notices and consolidated premanufacture notices.* Persons shall remit a fee of \$2,500 for each PMN or consolidated PMN submitted.

(ii) *Intermediate premanufacture notices.* Persons shall remit a fee of \$1,000 for each intermediate PMN. However, for the PMN for the final product the person shall submit the fee in paragraph (b)(2)(i) of this section.

(iii) *Significant new use notices.* Persons shall remit a fee of \$2,500 for each significant new use notice submitted.

(iv) *Exemption applications.* Persons shall remit a fee of \$2,500 for each exemption application submitted under section 5(h)(2) of the Act.

(v) *Exemption notices.* Persons shall remit a fee of \$2,500 for each exemption notice submitted under § 723.175 of this chapter.

(vi) *MCAN and consolidated MCAN.* Persons shall remit a fee of \$2,500 for each MCAN or consolidated MCAN submitted.

(c) *No fee required.* Persons are exempt from remitting any fee for submissions under §§ 720.38, 723.50, and subparts E, F, and G of part 725 of this chapter.

(d) *Joint submitters.* Joint submitters of a section 5 notice are required to remit the appropriate fee identified in paragraph (b) of this section for each section 5 notice regardless of the number of joint submitters for that notice. To qualify for the fee identified in paragraph (b)(1) of this section, each joint submitter of a section 5 notice must qualify as a small business concern under § 700.43.

(e) *Remittance procedure.* (1) Each remittance under this section shall be in United States currency and shall be paid by money order, bank draft, wire transfer, Pay.gov service provided through the Department of the Treasury, or check drawn to the order of the Environmental Protection Agency.

(2) Each paper remittance shall be sent to the Environmental Protection Agency, Washington Finance Center, Toxic Substances Control Act User Fees, P.O. Box 979073, St. Louis, MO 63197-9000.

(3) Persons who submit a TSCA section 5 notice shall place an identifying number and a payment identity number on the front page of each TSCA section 5 notice submitted. The identifying number must include the letters "TS" followed by a combination of 6 numbers (letters may be substituted for some numbers). The payment identity number may be a check number, a wire transfer number, or a "Pay.gov" transaction number used to transmit the user fee. The same TS number and the submitter's name must appear on the corresponding fee remittance under this section. If a remittance applies to more than one TSCA section 5 notice,

## Environmental Protection Agency

## § 700.45

the person shall include the name of the submitter and a new TS number for each TSCA section 5 notice to which the remittance applies, and the amount of the remittance that applies to each notice. Any remittance not having the identifying name and numbers described in this paragraph will be returned to the remitter.

(4)(i) Each person who remits the fee identified in paragraph (b)(1) of this section for a PMN, consolidated PMN, intermediate PMN, or significant new use notice shall insert a check mark for the statement, “The company named in part 1, section A is a small business concern under 40 CFR 700.43 and has remitted a fee of \$100 in accordance with 40 CFR 700.45(b).” under “CERTIFICATION” on page 2 of the Premanufacture Notice for New Chemical Substances (EPA Form 7710-25).

(ii) Each person who remits the fee identified in paragraph (b)(1) of this section for an exemption application under TSCA section 5(h)(2) shall insert a check mark for the statement, “The company named in part 1, section A is a small business concern under 40 CFR 700.43 and has remitted a fee of \$100 in accordance with 40 CFR 700.45(b).” in the exemption application.

(iii) Each person who remits the fee identified in paragraph (b)(1) of this section for an exemption notice under § 723.175 of this chapter shall include the words, “Each company identified in this notice is a small business concern under 40 CFR 700.43 and has remitted a fee of \$100 in accordance with 40 CFR 700.45(b).” in the certification required in § 723.175(i)(1)(x) of this chapter.

(iv) Each person who remits the fee identified in paragraph (b)(1) of this section for a MCAN for a microorganism shall insert a check mark for the statement, “The company named in part 1, section A is a small business concern under 40 CFR 700.43 and has remitted a fee of \$100 in accordance with 40 CFR 700.45(b).” in the certification required in § 725.25(b) of this chapter.

(5)(i) Each person who remits a fee identified in paragraph (b)(2) of this section for a PMN, consolidated PMN, intermediate PMN, or significant new use notice shall insert a check mark for the statement, “The company named in part 1, section A has remitted

the fee specified in 40 CFR 700.45(b).” under “CERTIFICATION” on page 2 of the Premanufacture Notice for New Chemical Substances (EPA Form 7710-25).

(ii) Each person who remits a fee identified in paragraph (b)(2) of this section for an exemption application under TSCA section 5(h)(2) shall insert a check mark for the statement, “The company named in part 1, section A has remitted the fee specified in 40 CFR 700.45(b).” in the exemption application.

(iii) Each person who remits the fee identified in paragraph (b)(2) of this section for an exemption notice under § 723.175 of this chapter shall include the words, “Each company identified in this notice has remitted a fee of \$2,500 in accordance with 40 CFR 700.45(b).” in the certification required in § 723.175(i)(1)(x) of this chapter.

(iv) Each person who remits the fee identified in paragraph (b)(1) of this section for a MCAN for a microorganism shall insert a check mark for the statement, “The company named in part 1, section A is a small business concern under 40 CFR 700.43 and has remitted a fee of \$100 in accordance with 40 CFR 700.45(b).” in the certification required in § 725.25(b) of this chapter.

(f) *Fee refunds.* EPA will refund any fee paid for a section 5 notice whenever the Agency determines:

(1) That the chemical substance that is the subject of a PMN, intermediate PMN, exemption application, or exemption notice is not a new chemical substance as of the date of submission of the notice.

(2) In the case of a significant new use notice, that the notice was not required.

(3) The notice is incomplete under either § 720.65(c) or 725.33, of this chapter.

(4) That as of the date of submission of the notice: the microorganism that is the subject of a MCAN is not a new microorganism; nor is the use involving the microorganism a significant new use.

[53 FR 31252, Aug. 17, 1988, as amended at 54 FR 21429, May 18, 1989; 58 FR 34204, June 23, 1993; 62 FR 17932, April 11, 1997; 75 FR 784, Jan. 6, 2010]



**§ 700.49 Failure to remit fees.**

EPA will not consider a section 5 notice to be complete unless the appropriate certification under § 700.45(e) is included and until the appropriate remittance under § 700.45(b) has been sent to EPA as provided in § 700.45(e) and received by EPA. EPA will notify the submitter that the section 5 notice is incomplete in accordance with §§ 720.65(c) and 725.33 of this chapter.

[62 FR 17932, April 11, 1997]

**PART 702—GENERAL PRACTICES AND PROCEDURES**

**Subparts A–B [Reserved]**

**Subpart C—Citizen Suit**

Sec.

702.60 Purpose.

702.61 Service of notice.

702.62 Contents of notice.

AUTHORITY: 15 U.S.C. 2619.

SOURCE: 47 FR 2773, Jan. 19, 1982, unless otherwise noted.

**Subparts A–B [Reserved]**

**Subpart C—Citizen Suit**

**§ 702.60 Purpose.**

Section 20 of the Toxic Substances Control Act (TSCA) authorizes any person to begin a civil action to compel performance by the Environmental Protection Agency (EPA) of TSCA non-discretionary acts or duties (section 20(a)(2)) or to restrain any violation of TSCA, or of any rule promulgated under sections 4, 5, or 6, or of any order issued under section 5 of TSCA (section 20(a)(1)). The purpose of this regulation is to prescribe procedures governing the giving of a notice of intent to file suit required by section 20(b) of TSCA as a prerequisite to beginning such civil actions.

**§ 702.61 Service of notice.**

(a) *Notice as a prerequisite to suit.* Under section 20 of TSCA, no civil action may be commenced by a citizen to restrain a violation of TSCA, or a rule or order thereunder, unless at least 60 days in advance the citizen has given notice of the intent to file suit to the

Administrator and to the person who is alleged to have committed the violation. No civil action may be commenced by a citizen to compel the Administrator to perform any non-discretionary act or duty under TSCA, unless at least 60 days in advance the citizen has given notice of the intent to file suit to the Administrator. However, in the case of an alleged failure by the Administrator to file an action under section 7 of TSCA, the citizen must give notice to the Administrator only 10 days in advance of filing the civil action.

(b) *Method of service.* Notice of intent to file suit can be either personally served or served by certified mail—return receipt requested—to persons identified in paragraph (d) of this section.

(c) *Date of service.* The effective date of service of a notice given in accordance with this rule shall be the date of the return receipt, if served by mail, or the date of receipt if personally served.

(d) *Persons to be served—(1) Violations of TSCA rules or TSCA order.* (i) If the alleged violator is a private individual or a corporation, notice of intent to file suit shall be served on the individual or the owner or managing agent of the plant, facility, or activity alleged to be in violation. If the alleged violator is a corporation, a copy of the notice shall also be sent to the registered agent, if any, of such corporation in the State in which such violation is alleged to have occurred. Notice shall also be served on the Administrator of the EPA.

(ii) If the alleged violator is a State or local government entity, notice of intent to file suit shall be served on the head of the agency. Notice shall also be served on the Administrator of the EPA, and a copy shall be sent to the Attorney General of the United States.

(iii) If the alleged violator is a Federal agency, notice of intent to file suit shall be served on the head of the agency. Notice shall also be served on the Administrator of the EPA, and a copy shall be sent to the Attorney General of the United States.

(2) *Performance of non-discretionary TSCA acts or duties.* Notice of intent to file suit shall be served on the Administrator of the EPA and a copy shall be

## Environmental Protection Agency

§ 704.1

sent to the Attorney General of the United States.

(3) *Address of persons to be served.* (i) EPA Administrator: 1200 Pennsylvania Ave., NW., Washington, DC 20460. (ii) Attorney General of the United States: 10th and Constitution Avenue, NW., Washington, DC 20530.

### § 702.62 Contents of notice.

(a) *Violation of TSCA rule or TSCA order.* Notice of intent to file suit regarding an alleged violation of TSCA or any rule promulgated under sections 4, 5, or 6, or an order issued under section 5, shall include sufficient information to permit the recipient to identify:

(1) The specific provision of TSCA or of the rule or order under TSCA alleged to have been violated.

(2) The activity alleged to constitute a violation.

(3) The person or persons responsible for the alleged violation.

(4) The location of the alleged violation.

(5) The date or dates of the alleged violation as closely as the citizen is able to specify them.

(6) The full name, address, and telephone number of the citizen giving notice.

(b) *Failure to act.* Notice regarding an alleged failure of the Administrator to perform any act or duty which is not discretionary shall:

(1) Identify the specific provision of TSCA which requires an act or creates a duty.

(2) Describe with reasonable specificity the action taken or not taken by the Administrator which is alleged to constitute a failure to perform the act or duty.

(3) State the full name, address, and telephone number of the citizen giving the notice.

(c) *Identification of Counsel.* The notice shall state the name, address, and telephone number of the Legal Counsel, if any, representing the citizen giving the notice.

## PART 704—REPORTING AND RECORDKEEPING REQUIREMENTS

### Subpart A—General Reporting and Recordkeeping Provisions for Section 8(a) Information-Gathering Rules

Sec.

704.1 Scope.

704.3 Definitions.

704.5 Exemptions.

704.7 Confidential business information claims.

704.9 Where to send reports.

704.11 Recordkeeping.

704.13 Compliance and enforcement.

### Subpart B—Chemical-Specific Reporting and Recordkeeping Rules

704.25 11-Aminoundecanoic acid.

704.33 P-tert-butylbenzoic acid (P-TBBA), p-tert-butyltoluene (P-TBT) and p-tert-butylbenzaldehyde (P-TBB).

704.43 Chlorinated naphthalenes.

704.45 Chlorinated terphenyl.

704.95 Phosphonic acid, [[1,2-ethanediy]bis[nitrilobis-(methylene)]]tetrakis-(EDTMPA) and its salts.

704.102 Hexachloronorbornadiene.

704.104 Hexafluoropropylene oxide.

704.175 4,4'-methylenebis(2-chloroaniline) (MBOCA).

AUTHORITY: 15 U.S.C. 2607(a).

### Subpart A—General Reporting and Recordkeeping Provisions for Section 8(a) Information-Gathering Rules

#### § 704.1 Scope.

(a) This part specifies reporting and recordkeeping procedures under section 8(a) of the Toxic Substances Control Act (TSCA) for manufacturers, importers, and processors of chemical substances and mixtures (hereafter collectively referred to as substances) that are identified in subpart B of this part. The reporting and recordkeeping provisions in subpart A of this part apply throughout this part unless revised in any other subpart.

(b) Subpart B of this part sets out chemical-specific reporting and recordkeeping requirements under section 8(a) of TSCA.

[53 FR 51715, Dec. 22, 1988, as amended at 60 FR 31920, June 19, 1995]

**§ 704.3 Definitions.**

All definitions as set forth in section 3 of TSCA apply in this part. In addition, the following definitions are provided for the purposes of this part.

*Annual* means the corporate fiscal year.

*Article* means a manufactured item (1) which is formed to a specific shape or design during manufacture, (2) which has end use function(s) dependent in whole or in part upon its shape or design during end use, and (3) which has either no change of chemical composition during its end use or only those changes of composition which have no commercial purpose separate from that of the article, and that result from a chemical reaction that occurs upon end use of other chemical substances, mixtures, or articles; except that fluids and particles are not considered articles regardless of shape or design.

*Byproduct* means a chemical substance produced without a separate commercial intent during the manufacture, processing, use, or disposal of another chemical substance(s) or mixture(s).

*CAS Number* means Chemical Abstracts Service Registry Number.

*Coproduct* means a chemical substance produced for a commercial purpose during the manufacture, processing, use, or disposal of another chemical substance or mixture.

*Customer* means any person to whom a manufacturer, importer, or processor directly distributes any quantity of a chemical substance, mixture, mixture containing the substance or mixture, or article containing the substance or mixture, whether or not a sale is involved.

*Domestic* means within the geographical boundaries of the 50 United States, including the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, the Northern Mariana Islands, and any other territory or possession of the United States.

*Enclosed process* means a manufacturing or processing operation that is designed and operated so that there is no intentional release into the environment of any substance present in the operation. An operation with fugitive,

inadvertent, or emergency pressure relief releases remains an enclosed process so long as measures are taken to prevent worker exposure to and environmental contamination from the releases.

*EPA* means the United States Environmental Protection Agency.

*Import* means to import for commercial purposes.

*Import for commercial purposes* means to import with the purpose of obtaining an immediate or eventual commercial advantage for the importer, and includes the importation of any amount of a chemical substance or mixture. If a chemical substance or mixture containing impurities is imported for commercial purposes, then those impurities also are imported for commercial purposes.

*Import in bulk form* means to import a chemical substance (other than as part of a mixture or article) in any quantity, in cans, bottles, drums, barrels, packages, tanks, bags, or other containers, if the chemical substance is intended to be removed from the container and the substance has an end use or commercial purpose separate from the container.

*Importer* means (1) any person who imports any chemical substance or any chemical substance as part of a mixture or article into the customs territory of the United States, and includes:

(i) The person primarily liable for the payment of any duties on the merchandise, or

(ii) An authorized agent acting on his behalf (as defined in 19 CFR 1.11).

(2) Importer also includes, as appropriate:

(i) The consignee.

(ii) The importer of record.

(iii) The actual owner if an actual owner's declaration and superseding bond have been filed in accordance with 19 CFR 141.20.

(iv) The transferee, if the right to draw merchandise in a bonded warehouse has been transferred in accordance with subpart C of 19 CFR part 144.

(3) For the purposes of this definition, the customs territory of the United States consists of the 50 States, Puerto Rico, and the District of Columbia.

## Environmental Protection Agency

## § 704.3

*Impurity* means a chemical substance which is unintentionally present with another chemical substance.

*Intermediate* means any chemical substance that is consumed, in whole or in part, in chemical reactions used for the intentional manufacture of other chemical substances or mixtures, or that is intentionally present for the purpose of altering the rates of such chemical reactions.

*Known to or reasonably ascertainable by* means all information in a person's possession or control, plus all information that a reasonable person similarly situated might be expected to possess, control, or know.

*Manufacture* means to manufacture for commercial purposes.

*Manufacture for commercial purposes* means: (1) To import, produce, or manufacture with the purpose of obtaining an immediate or eventual commercial advantage for the manufacturer, and includes among other things, such "manufacture" of any amount of a chemical substance or mixture:

(i) For commercial distribution, including for test marketing.

(ii) For use by the manufacturer, including use for product research and development, or as an intermediate.

(2) Manufacture for commercial purposes also applies to substances that are produced coincidentally during the manufacture, processing, use, or disposal of another substance or mixture, including both byproducts that are separated from that other substance or mixture and impurities that remain in that substance or mixture. Such byproducts and impurities may, or may not, in themselves have commercial value. They are nonetheless produced for the purpose of obtaining a commercial advantage since they are part of the manufacture of a chemical product for a commercial purpose.

*Manufacturer* means a person who imports, produces, or manufactures a chemical substance. A person who extracts a component chemical substance from a previously existing chemical substance or a complex combination of substances is a manufacturer of that component chemical substance.

*Non-isolated intermediate* means any intermediate that is not intentionally removed from the equipment in which

it is manufactured, including the reaction vessel in which it is manufactured, equipment which is ancillary to the reaction vessel, and any equipment through which the substance passes during a continuous flow process, but not including tanks or other vessels in which the substance is stored after its manufacture. Mechanical or gravity transfer through a closed system is not considered to be intentional removal, but storage or transfer to shipping containers "isolates" the substance by removing it from process equipment in which it is manufactured.

*Own or control* means ownership of 50 percent or more of a company's voting stock or other equity rights, or the power to control the management and policies of that company. A company may own or control one or more sites. A company may be owned or controlled by a foreign or domestic parent company.

*Parent company* is a company that owns or controls another company.

*Person* includes any individual, firm, company, corporation, joint venture, partnership, sole proprietorship, association, or any other business entity; any State or political subdivision thereof; any municipality; any interstate body; and any department, agency, or instrumentality of the Federal Government.

*Possession or control* means in the possession or control of any person, or of any subsidiary, partnership in which the person is a general partner, parent company, or any company or partnership which the parent company owns or controls, if the subsidiary, parent company, or other company or partnership is associated with the person in the research, development, test marketing, or commercial marketing of the substance in question. Information is in the possession or control of a person if it is:

(1) In the person's own files including files maintained by employees of the person in the course of their employment.

(2) In commercially available data bases to which the person has purchased access.

(3) Maintained in the files in the course of employment by other agents of the person who are associated with

### § 704.3

### 40 CFR Ch. I (7-1-10 Edition)

research, development, test marketing, or commercial marketing of the chemical substance in question.

*Process* means to process for commercial purposes.

*Process for commercial purposes* means the preparation of a chemical substance or mixture after its manufacture for distribution in commerce with the purpose of obtaining an immediate or eventual commercial advantage for the processor. Processing of any amount of a chemical substance or mixture is included in this definition. If a chemical substance or mixture containing impurities is processed for commercial purposes, then the impurities also are processed for commercial purposes.

*Processor* means any person who processes a chemical substance or mixture.

*Production volume* means the quantity of a substance which is produced by a manufacturer, as measured in kilograms or pounds.

*Propose to manufacture, import, or process* means that a person has made a firm management decision to commit financial resources for the manufacture, import, or processing of a specified chemical substance or mixture.

*Site* means a contiguous property unit. Property divided only by a public right-of-way shall be considered one site. There may be more than one plant on a single site. The site for a person who imports a substance is the site of the operating unit within the person's organization which is directly responsible for importing the substance and which controls the import transaction and may in some cases be the organization's headquarters office in the United States.

*Small manufacturer or importer* means a manufacturer or importer that meets either of the following standards:

(1) *First standard.* A manufacturer or importer of a substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$40 million. However, if the annual production or importation volume of a particular substance at any individual site owned or controlled by the manufacturer or importer is greater than 45,400 kilograms (100,000 pounds), the manufacturer or importer shall not qualify as small for purposes

of reporting on the production or importation of that substance at that site, unless the manufacturer or importer qualifies as small under standard (2) of this definition.

(2) *Second standard.* A manufacturer or importer of a substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$4 million, regardless of the quantity of substances produced or imported by that manufacturer or importer.

(3) *Inflation index.* EPA shall make use of the Producer Price Index for Chemicals and Allied Products, as compiled by the U.S. Bureau of Labor Statistics, for purposes of determining the need to adjust the total annual sales values and for determining new sales values when adjustments are made. EPA may adjust the total annual sales values whenever the Agency deems it necessary to do so, provided that the Producer Price Index for Chemicals and Allied Products has changed more than 20 percent since either the most recent previous change in sales values or the date of promulgation of this rule, whichever is later. EPA shall provide FEDERAL REGISTER notification when changing the total annual sales values.

*Small quantities solely for research and development* (or "small quantities solely for purposes of scientific experimentation or analysis or chemical research on, or analysis of, such substance or another substance, including such research or analysis for the development of a product") means quantities of a chemical substance manufactured, imported, or processed or proposed to be manufactured, imported, or processed solely for research and development that are not greater than reasonably necessary for such purposes.

*Substance* means either a chemical substance or mixture unless otherwise indicated.

*Test marketing* means the distribution in commerce of no more than a predetermined amount of a chemical substance, mixture, article containing that chemical substance or mixture, or a mixture containing that substance, by a manufacturer or processor, to no

## Environmental Protection Agency

## § 704.7

more than a defined number of potential customers to explore market capability in a competitive situation during a predetermined testing period prior to the broader distribution of that chemical substance, mixture, or article in commerce.

*Total annual sales* means the total annual revenue (in dollars) generated by the sale of all products of a company. Total annual sales must include the total annual sales revenue of all sites owned or controlled by that company and the total annual sales revenue of that company's subsidiaries and foreign or domestic parent company, if any.

*TSCA* means the Toxic Substances Control Act, 15 U.S.C. 2601 et seq.

[53 FR 51715, Dec. 22, 1988]

### § 704.5 Exemptions.

A person who is subject to reporting requirements for a substance identified in this part is exempt from those requirements to the extent that the person and that person's use of the substance is described in this section. This section is superseded by any TSCA section 8(a) rule that adds to, removes, or revises the exemptions described in this section.

(a) *Articles*. A person who imports, processes, or proposes to import or process a substance identified in this part solely as part of an article is exempt from the reporting requirements of this part with regard to that substance.

(b) *Byproducts*. A person who manufactures, imports, or proposes to manufacture or import a substance identified in this part solely as a byproduct is exempt from the reporting requirements of this part.

(c) *Impurities*. A person who manufactures, imports, processes, or proposes to manufacture, import, or process a substance identified in this part solely as an impurity is exempt from the reporting requirements of this part.

(d) *Non-isolated intermediate*. A person who manufactures or proposes to manufacture a substance identified in this part solely as a non-isolated intermediate is exempt from the reporting requirements of this part.

(e) *Research and development*. A person who manufactures, imports, proc-

esses, or proposes to manufacture, import, or process a substance identified in this part only in small quantities solely for research and development is exempt from the reporting requirements of this part.

(f) *Small manufacturers and importers*. Small manufacturers and importers are exempt from the reporting requirements of this part.

[53 FR 51717, Dec. 22, 1988]

### § 704.7 Confidential business information claims.

(a) Any person submitting a notice under this rule may assert a business confidentiality claim covering all or any part of the notice. Any information covered by a claim will be disclosed by EPA only to the extent and by means of the procedures set forth in part 2 of this title.

(b) If no claim accompanies the notice at the time it is submitted to EPA, the notice will be placed in an open file available to the public without further notice to the respondent.

(c) To assert a claim of confidentiality for data contained in a notice, the respondent must submit two copies of the notice.

(1) One copy of the notice must be complete. In that copy the respondent must indicate what data, if any, are claimed as confidential by marking the specific information on each page with a label such as "confidential", "proprietary", or "trade secret".

(2) If some data in the notice are claimed as confidential, the respondent must submit a second copy. The second copy must be complete except that all information claimed as confidential in the first copy must be deleted.

(3) The first copy of the notice will be for internal use by EPA. The second copy will be placed in an open file to be available to the public.

(4) Failure to furnish a second copy of the notice when information is claimed as confidential in the first copy will be considered a presumptive waiver of the claim of confidentiality. EPA will notify the respondent by certified mail that a finding of a presumptive waiver of the claim of confidentiality has been made. The respondent has 15 days from the date of receipt of

## § 704.9

notification to submit the required second copy. Failure to submit the second copy will cause EPA to place the first copy in the public file.

(d) In submitting a claim of confidentiality, a person attests to the truth of the following four statements concerning all information which is claimed confidential:

(1) My company has taken measures to protect the confidentiality of the information, and it intends to continue to take such measures.

(2) The information is not, and has not been, reasonably obtainable without our consent by other persons (other than government bodies) by use of legitimate means (other than discovery based on a showing of special need in a judicial or quasi-judicial proceeding).

(3) The information is not publicly available elsewhere.

(4) Disclosure of the information would cause substantial harm to our competitive position.

[48 FR 23420, May 25, 1983, as amended at 53 FR 51717, Dec. 22, 1988]

### § 704.9 Where to send reports.

Reports must be submitted by certified mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: 8(a) Reporting.

[60 FR 34463, July 3, 1995, as amended at 71 FR 33641, June 12, 2006]

### § 704.11 Recordkeeping.

Each person who is subject to the reporting requirements of this part must retain the following records for 3 years following the creation or compilation of the record.

(a) A copy of each report submitted by the person in response to the requirements of this part.

(b) Materials and documentation sufficient to verify or reconstruct the values submitted in the report.

(c) A copy of each notice sent by the person, return receipt requested, to that person's customers for the purpose of notifying their customers of the customer's reporting obligations under this part.

## 40 CFR Ch. I (7-1-10 Edition)

(d) All return receipts signed by the person's customers who received the notice described in paragraph (c) of this section.

[53 FR 51717, Dec. 22, 1988, as amended at 58 FR 34204, June 23, 1993]

### § 704.13 Compliance and enforcement.

Violators of the requirements of this part may be subject to civil administrative penalties up to \$25,000 per day of violation or criminal prosecution, as provided in sections 15 and 16 of TSCA. In addition, under section 17, EPA may seek judicial relief to compel submission of required information.

[53 FR 51717, Dec. 22, 1989]

## Subpart B—Chemical-Specific Reporting and Recordkeeping Rules

### § 704.25 11-Aminoundecanoic acid.

(a) *Definitions.* (1) *11-AA* means the chemical substance 11-aminoundecanoic acid, CAS Number 2432-99-7.

(2) *Enclosed process* means a process that is designed and operated so that there is no intentional release of any substance present in the process. A process with fugitive, inadvertent, or emergency pressure relief releases remains an enclosed process so long as measures are taken to prevent worker exposure to an environmental contamination from the releases.

(3) *Internal subunit* means a subunit that is covalently linked to at least two other subunits. *Internal subunits* of polymer molecules are chemically derived from monomer molecules that have formed covalent links between two or more other molecules.

(4) *Monomer* means a chemical substance that has the capacity to form links between two or more other molecules.

(5) *Polymer* means a chemical substance that consists of at least a simple weight majority of polymer molecules but consists of less than a simple weight majority of molecules with the same molecular weight. Collectively, such polymer molecules must

be distributed over a range of molecular weights wherein differences in molecular weight are primarily attributable to differences in the number of internal subunits.

(6) *Polymer molecule* means a molecule which includes at least four covalently linked subunits, at least two of which are internal subunits.

(7) *Small processor* means a processor that meets either the standard in paragraph (a)(7)(i) of this section or the standard in paragraph (a)(7)(ii) of this section.

(i) *First standard.* A processor of a chemical substance is small if its total annual sales, when combined with those of its parent company, if any, are less than \$40 million. However, if the annual processing volume of a particular chemical substance at any individual site owned or controlled by the processor is greater than 45,400 kilograms (100,000 pounds), the processor shall not qualify as small for purposes of reporting on the processing of that chemical substance at that site, unless the processor qualifies as small under paragraph (a)(7)(ii) of this section.

(ii) *Second standard.* A processor of a chemical substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$4 million, regardless of the quantity of the particular chemical substance processed by that company.

(iii) *Inflation index.* EPA will use the Inflation Index described in the definition of *small manufacturer* set forth in §704.3, for purposes of adjusting the total annual sales values of this small processor definition. EPA will provide notice in the FEDERAL REGISTER when changing the total annual sales values of this definition.

(8) *Subunit* means an atom or group of associated atoms chemically derived from corresponding reactants.

(b) *Persons who must report.* Except as provided in paragraph (c) of this section, the following persons are subject to this section:

(1) Persons who manufacture or propose to manufacture 11-AA:

(i) For use as an intermediate in the manufacture of polymers in an enclosed process when it is expected that the 11-AA will be fully polymerized during the manufacturing process, or

(ii) For use as a component in photoprocessing solutions.

(2) Persons who import or propose to import 11-AA:

(i) For use as an intermediate in the manufacture of polymers in an enclosed process when it is expected that the 11-AA will be fully polymerized during the manufacturing process, or

(ii) For use as a component in photoprocessing solutions.

(3) Persons who process or propose to process 11-AA:

(i) For use as an intermediate in the manufacture of polymers in an enclosed process when it is expected that the 11-AA will be fully polymerized during the manufacturing process, or

(ii) For use as a component in photoprocessing solutions.

(c) *Persons not subject to this section.* The following persons are not subject to this section:

(1) Small manufacturers (includes importers) as described in §704.3.

(2) Small processors.

(3) Persons described in §704.5.

(4) Persons who, at any time during the 3-year period ending July 22, 1986, manufactured, imported, or processed 11-AA:

(i) For use as an intermediate in the manufacture of polymers in an enclosed process when it is expected that the 11-AA will be fully polymerized during the manufacturing process, or

(ii) For use as a component in photoprocessing solutions.

(d) *What information to report.* Persons identified in paragraph (b) of this section must submit a Premanufacture Notice Form (EPA Form 7710-25).

(e) *When to report.* (1) Persons who intend to manufacture, import, or process 11-AA for use as an intermediate in the manufacture of polymers in an enclosed process when it is expected that the 11-AA will be fully polymerized during the manufacturing process or for use as a component in photoprocessing solutions must notify EPA within 30 days after making a firm management decision to commit financial resources for the manufacturing, importing, or processing of 11-AA.

(2) Persons who initiated manufacturing, importing, or processing of 11-AA for use as an intermediate in the



manufacture of polymers in an enclosed process when it is expected that the 11-AA will be fully polymerized during the manufacturing process, or for use as a component in photoprocessing solutions during the time period between July 22, 1986 and July 13, 1987 must notify EPA by August 10, 1987.

(f) *Recordkeeping.* Persons subject to the reporting requirements of this section must retain documentation of information contained in their reports for a period of 5 years from the date of submission of the report.

(g) *Where to send reports.* Reports must be submitted by certified mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: 11-AA Notification.

[52 FR 19864, May 28, 1987, as amended at 60 FR 16308, Mar. 29, 1995; 60 FR 34463, July 3, 1995; 71 FR 33641, June 12, 2006]

**§ 704.33 P-tert-butylbenzoic acid (P-TBBA), p-tert-butyltoluene (P-TBT) and p-tert-butylbenzaldehyde (P-TBB).**

(a) *Definitions.* (1) *P-TBBA* means the substance p-tert-butylbenzoic acid, also identified as 4-(1,1-dimethylethyl)benzoic acid, CAS No. 98-73-7.

(2) *P-TBT* means the substance p-tert-butyltoluene, also identified as 1-(1,1-dimethylethyl)-4-methylbenzene, CAS No. 98-51-1.

(3) *P-TBB* means the substance p-tert-butylbenzaldehyde, also identified as 4-(1,1-dimethylethyl)benzaldehyde, CAS No. 939-97-9.

(4) *Small processor* means a processor that meets either the standard in paragraph (a)(4)(i) of this section or the standard in paragraph (a)(4)(ii) of this section.

(i) *First standard.* A processor of a chemical substance is small if its total annual sales, when combined with those of its parent company, if any, are less than \$40 million. However, if the annual processing volume of a particular chemical substance at any individual site owned or controlled by the processor is greater than 45,400 kilograms (100,000 pounds), the processor

shall not qualify as small for purposes of reporting on the processing of that chemical substance at that site, unless the processor qualifies as small under paragraph (a)(1)(ii) of this section.

(ii) *Second standard.* A processor of a chemical substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$4 million, regardless of the quantity of the particular chemical substance processed by that company.

(iii) *Inflation index.* EPA shall use the Inflation Index described in the definition of *small manufacturer* that is set forth in § 704.3, for purposes of adjusting the total annual sales values of this small processor definition. EPA shall provide FEDERAL REGISTER notification when changing the total annual sales values of this definition.

(b) *Persons who must report.* Except as provided in paragraph (c) of this section, the following persons are subject to the reporting requirements of this rule; a person may become subject to this rule more than once, for more than one substance or under more than one of the criteria listed in this paragraph (b).

(1) Persons who manufactured, imported, or processed P-TBBA, P-TBT, and/or P-TBB for commercial purposes during the person's latest complete corporate fiscal year prior to June 25, 1986. For purposes of this provision, processors of P-TBBA, P-TBT, and/or P-TBB shall include only those persons who processed the substances other than as non-isolated intermediates.

(2) Persons who commence manufacture or importation of P-TBBA, P-TBT, and/or P-TBB for commercial purposes after June 25, 1986. This provision is applicable to persons who cease manufacture or importation of P-TBBA, P-TBT, and/or P-TBB after June 25, 1986 and then subsequently resume manufacture or importation of the substance(s).

(3) Persons who process P-TBBA, P-TBT, and/or P-TBB for commercial purposes in any way other than as a non-isolated intermediate after June 25, 1986.

(c) *Persons not subject to this rule.* In addition to the persons described in § 704.5, small processors, as defined in paragraph (a)(4) of this section, are not subject to this rule.

(d) *Information to report.* Persons subject to this rule as described in paragraph (b) of this section shall report information to EPA as specified in this paragraph (d). Respondents to this rule shall report all information that is known to or reasonably ascertainable by the person reporting. For purposes of importer reporting under this paragraph, a site is the operating unit within the person's organization which is directly responsible for importing the substance and which controls the import transaction. The import site may in some cases be the organization's headquarters office in the United States.

(1) All manufacturers, importers, and processors specified in paragraph (b) of this section shall report their name and headquarters address.

(2) All manufacturers, importers, and processors specified in paragraph (b) of this section shall report the name, address, and office telephone number (including area code) of their principal technical contact.

(3) All manufacturers, importers, and processors specified in paragraph (b) of this section shall report the name and address of each site where P-TBBA, P-TBT, and/or P-TBB is manufactured, imported, or processed.

(4) All manufacturers, importers, and processors specified in paragraph (b)(1) of this section only shall report the information described in this paragraph (d)(4). Respondents to this paragraph (d)(4) shall report separately for each substance that they manufacture, import, or process, and for each site at which they do so. However, if the information to be reported in response to this paragraph (d)(4) is the same for different sites, the respondent need not report separately for each site but need only notify EPA that the information is the same for each site. The information to be reported under this paragraph (d)(4) shall cover the respondent's latest complete corporate fiscal year prior to June 25, 1986. Respondents to this paragraph (d)(4) shall report the following information:

(i) The total quantity (by weight) of P-TBBA, P-TBT, or P-TBB manufactured, imported, or processed for commercial purposes per site.

(ii) A narrative description of the manufacturing, importing, or processing operation(s) involving P-TBBA, P-TBT, or P-TBB at each site.

(iii) A narrative description of worker activities involving P-TBBA, P-TBT, or P-TBB at each site, including the number of workers potentially exposed to each substance and, if applicable, the number of workers potentially exposed to more than one substance.

(iv) The potential routes of worker exposure to P-TBBA, P-TBT, or P-TBB at each site (e.g., inhalation, ingestion, dermal absorption).

(v) Available monitoring data from employee breathing zones with potential exposure to P-TBBA, P-TBT, or P-TBB at each site, including a description of the method of monitoring, the number of samples taken, and the potential number of workers similarly exposed for each worker job category. Respondents to this paragraph (d)(4)(v) shall submit data showing a range of 8-hour time weighted averages (TWAs), provided that the data are available in that form. Respondents also shall submit a calculated geometric mean of these data, with an explanation of the method by which the mean was derived. However, if the monitoring data are not available in the form of 8-hour TWAs, respondents shall submit raw sample data results and the duration time of sampling for each job category.

(vi) A narrative description of any personal protective equipment and/or engineering controls used to prevent exposure to P-TBBA, P-TBT, or P-TBB at each site.

(vii) A listing of the estimated quantities of P-TBBA, P-TBT, or P-TBB released directly into air, water, or land from each site.

(viii) A narrative description of the times during the manufacturing, importing, or processing operations involving P-TBBA, P-TBT, or P-TBB when environmental release occurs at each site.

(ix) A narrative description of any engineering controls used to prevent environmental release of P-TBBA, P-TBT, or P-TBB at each site.

(x) A narrative description of all known end uses of any P-TBBA, P-TBT, or P-TBB that is manufactured,

imported, or processed by the respondent. The narrative need not include customer identity.

(xi) A narrative description of the methods used at each site for disposing of wastes generated during the manufacture, importation, or processing of P-TBBA, P-TBT, or P-TBB, including the quantity and content of such wastes (per site), the method of disposal, and an identification of the disposal site(s).

(5) All manufactureres, importers, and processors specified in paragraph (b) of this section shall report the information described in this paragraph (d)(5). Respondents to this paragraph (d)(5) shall report separately for each substance that they intend to manufacture, import, or process during the first 2 years following the date on which they become subject to this rule. The data reported under this paragraph (d)(5) shall cover that 2-year period. Respondents to this paragraph (d)(5) shall report separately for each site at which they intend to manufacture, import, or process each substance. Respondents need not comply with this paragraph (d)(5) if the information to be reported is identical to that reported by the respondent under paragraph (d)(4) of this section, provided that the respondent makes note of that fact to EPA. Respondents to this paragraph (d)(5) shall report the following information:

(i) An estimate of the total quantity (by weight) of P-TBBA, P-TBT, or P-TBB that the respondent intends to manufacture, import, or process for commercial purposes per site during each of the first 2 years following the date on which the respondent becomes subject to this rule.

(ii) A narrative description of the intended manufacturing, importing, or processing activities involving P-TBBA, P-TBT, or P-TBB at each site during the first 2 years following the date on which the respondent becomes subject to this rule. The description shall include a summary of the intended manufacturing, importing, or processing operation(s); a summary of intended worker activities involving the substances, including an estimate of the number of persons anticipated to be exposed annually to P-TBBA, P-

TBT, or P-TBB (per site) during the 2-year period, the anticipated routes of worker exposure to the substances (e.g., inhalation, ingestion, dermal absorption); and a summary of any personal protective equipment and/or engineering controls that the respondent intends to use to prevent exposure to the substances.

(iii) A narrative description of anticipated environmental releases of P-TBBA, P-TBT, or P-TBB at each site from the manufacture, importation, or processing of these substances during the first 2 years following the date on which the respondent becomes subject to this rule. The narrative shall include the anticipated quantities of each substance released directly into air, water, or land, the anticipated routes of environmental release, and any intended engineering controls to be used to prevent environmental release of the substances.

(iv) A narrative description of all anticipated end uses or P-TBBA, P-TBT, or P-TBB resulting from the respondent's manufacture, importation, or processing of the substances during the first 2 years following the date on which the respondent becomes subject to this rule. The summary need not include customer identity.

(v) A narrative summary of the anticipated disposal of wastes generated from the manufacture, importation, or processing of P-TBBA, P-TBT, or P-TBB during the first 2 years following the date on which the respondent becomes subject to this rule. The summary shall include the anticipated quantity and content of such wastes (per site), the intended method of disposal, and an identification of intended disposal site(s).

(e) *When to report.* Persons subject to this rule must submit the requisite information to EPA within 60 days of becoming subject to the rule under the standards set forth in paragraph (b) of this section.

(f) *Certification.* Persons subject to this rule must attach the following statement to any information submitted to EPA in response to this rule: "I hereby certify that, to the best of my knowledge and belief, all of the attached information is complete and accurate." This statement shall be signed

**Environmental Protection Agency**

**§ 704.43**

and dated by the company's principal technical contact.

(g) *Recordkeeping.* Persons subject to the reporting requirements of this section must retain documentation of information contained in their reports for a period of 5 years from the date of the submission of the report.

[51 FR 17339, May 12, 1986; 51 FR 18323, May 19, 1986, as amended at 52 FR 20083, May 29, 1987; 58 FR 34204, June 23, 1993]

**§ 704.43 Chlorinated naphthalenes.**

(a) *Definitions.* (1) *Extent of chlorination* means the percent by weight of chlorine.

(2) *Import* means to import in bulk form or as part of a mixture.

(3) *Isomeric ratio* means the relative amounts of each isomeric chlorinated naphthalene that composes the chemical substance; and for each isomer the relative amounts of each chlorinated naphthalene designated by the position of the chlorine atom(s) on the naphthalene.

(4) *Polychlorinated biphenyl* means any chemical substance that is limited to the biphenyl molecule and that has been chlorinated to varying degrees.

(5) *Small manufacturer* means a manufacturer (including importers) who meets either paragraph (a)(5) (i) or (ii) of this section:

(i) A manufacturer of a chemical substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$40 million. However, if the annual production volume of a particular chemical substance at any individual site owned or controlled by the manufacturer is greater than 45,400 kilograms (100,000 pounds), the manufacturer shall not qualify as small for purposes of reporting on the production of that chemical substance at that site, unless the manufacturer qualifies as small under paragraph (a)(5)(ii) of this section.

(ii) A manufacturer of a chemical substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$4 million, regardless of the quantity of the particular chemical substance produced by that manufacturer.

(iii) For imported mixtures containing a chemical substance identified in paragraph (b) of this section, the

45,400 kilograms (100,000 pounds) standard in paragraph (a)(5)(i) of this section applies only to the amount of the chemical substance in a mixture and not the other components of the mixture.

(6) *Waste* means any solid liquid, semisolid, or contained gaseous material that results from the production of a chemical substance identified in paragraph (b) of this section and which is to be disposed.

(b) *Substances for which reports must be submitted.*

| CAS registry number | Chemical substance               |
|---------------------|----------------------------------|
| 90-13-1 .....       | Naphthalene, 1-chloro-           |
| 91-58-7 .....       | Naphthalene, 2-chloro-           |
| 1321-64-8 .....     | Naphthalene, pentachloro-        |
| 1321-65-9 .....     | Naphthalene, trichloro-          |
| 1335-87-1 .....     | Naphthalene, hexachloro-         |
| 1335-88-2 .....     | Naphthalene, tetrachloro-        |
| 1825-30-5 .....     | Naphthalene, 1,5-dichloro-       |
| 1825-31-6 .....     | Naphthalene, 1,4-dichloro-       |
| 2050-69-3 .....     | Naphthalene, 1,2-dichloro-       |
| 2050-72-8 .....     | Naphthalene, 1,6-dichloro-       |
| 2050-73-9 .....     | Naphthalene, 1,7-dichloro-       |
| 2050-74-0 .....     | Naphthalene, 1,8-dichloro-       |
| 2050-75-1 .....     | Naphthalene, 2,3-dichloro-       |
| 2065-70-5 .....     | Naphthalene, 2,6-dichloro-       |
| 2198-75-6 .....     | Naphthalene, 1,3-dichloro-       |
| 2198-77-8 .....     | Naphthalene, 2,7-dichloro-       |
| 2234-13-1 .....     | Naphthalene, octachloro-         |
| 25586-43-0 .....    | Naphthalene, chloro-             |
| 32241-08-0 .....    | Naphthalene, heptachloro-        |
| 70776-03-3 .....    | Naphthalene, chloro derivatives. |

(c) *Persons who must report.* (1) Persons who are manufacturing or importing a chemical substance identified in paragraph (b) of this section on October 8, 1984.

(2) Persons who propose to import a chemical substance identified in paragraph (b) of this section on or after October 8, 1984.

(3) Persons who manufacture a chemical substance identified in paragraph (b) of this section after October 8, 1984.

(4) A person is required to report only once for each chemical substance identified in paragraph (b) of this section.

(d) *Persons exempt from reporting.* (1) Small manufacturers.

(2) Persons described in § 704.5.

(e) *What information to report.* Persons described in paragraph (c) of this section must notify EPA of current or prospective manufacture or import. The notice must include, to the extent that it is known to or reasonably ascertainable by the person making the report, the following information:

(1) Company name and address.

## § 704.45

(2) Name, address, and telephone number of the principal technical contact.

(3) For chemical substances proposed to be imported, the proposed date of import.

(4) A description of the use(s) or intended use(s) for the chemical substance.

(5) A description of the isomeric ratio and extent of chlorination of the chemical substance and the impurity level of polychlorinated biphenyls.

(6) The quantity (by weight) manufactured or imported within 12 months prior to October 8, 1984, if any, and the estimated quantity (by weight) to be manufactured or imported for the first 3 years following the date of the report or the date of the intended start of import whichever occurs later.

(7) The number of persons exposed to the chemical substance during manufacture, import, processing, distribution in commerce, use, and disposal.

(8) If a manufacturer's waste contains one or more of the chemical substances identified in paragraph (b) of this section, the manufacturer must:

(i) Provide the quantity (by weight) of the chemical substances identified in paragraph (b) of this section present in the waste.

(ii) Identify the constituents of the waste and their concentrations.

(iii) State the rate of waste generation as a percentage of production volume.

(iv) Describe where in the manufacturing process the waste is generated, and

(v) Describe the method for disposal of the waste.

(f) *When to report.* (1) Persons who are manufacturing or importing a chemical substance identified in paragraph (b) of this section on October 8, 1984 must notify EPA by November 6, 1984.

(2) Persons who propose to import a chemical substance identified in paragraph (b) of this section on or after October 8, 1984 must notify EPA by November 6, 1984, or 15 days after making the management decision described in § 704.3, whichever is later in time.

(3) Persons who manufacture a chemical substance identified in paragraph (b) of this section after October 8, 1984

## 40 CFR Ch. I (7-1-10 Edition)

must notify EPA within 30 days after the initial date of manufacture.

[49 FR 33653, Aug. 24, 1984; 49 FR 45133, Nov. 15, 1984; 50 FR 1215, Jan. 10, 1985; 51 FR 19839, June 3, 1986; 52 FR 20083, May 29, 1987. Redesignated at 53 FR 51717, Dec. 22, 1988]

### § 704.45 Chlorinated terphenyl.

(a) *Definitions.* (1) *Chlorinated terphenyl* means a chemical substance, CAS No. 61788-33-6, comprised of chlorinated ortho-, meta-, and paraterphenyl.

(2) *Extent of chlorination* means the percent by weight of chlorine for each isomer (ortho, meta, and para).

(3) *Isomeric ratio* means the ratios of ortho-, meta-, and paraterphenyls.

(4) *Polychlorinated biphenyl* means any chemical substance that is limited to the biphenyl molecule that has been chlorinated to varying degrees.

(5) *Small manufacturer* means a manufacturer (importers are defined as manufacturers under TSCA) who meets either of the following standards under this rule:

(i) *First standard.* A manufacturer of an existing chemical substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$40 million. However, if the annual production volume of a particular chemical substance at any individual site owned or controlled by the manufacturer is greater than 45,400 kilograms (100,000 pounds), the manufacturer shall not qualify as small for purposes of reporting on the production of that chemical substance at the site, unless the manufacturer qualified as small under paragraph (a)(5)(ii) of this section.

(ii) *Second standard.* A manufacturer of an existing chemical substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$4 million, regardless of the quantity of chemicals produced by that manufacturer.

(b) *Persons who must report.* Except for small manufacturers and as provided in § 704.5, the following persons are subject to the rule:

(1) Persons who manufacture or propose to manufacture chlorinated terphenyl.

**Environmental Protection Agency**

**§ 704.95**

(2) Persons who import (importers) or propose to import chlorinated terphenyl as a chemical substance in bulk or as part of a mixture.

(c) *What information to report.* Persons subject to this rule as described in paragraph (b) of this section must notify EPA of current or proposed manufacture or import of chlorinated terphenyl. The notice must include, to the extent that it is known to the person making the report or is reasonably ascertainable, the following information:

- (1) Company name and address.
- (2) Name, address, and telephone number of principal technical contact.
- (3) A description of the use(s) or intended use(s) for chlorinated terphenyl.
- (4) A description of the isomeric ratio and extent of chlorination of the chlorinated terphenyl and the impurity level of polychlorinated biphenyls.
- (5) The quantity (by weight) manufactured or imported within 12 months prior to the effective date of the rule, if any, and the estimated quantity (by weight) to be manufactured or imported for the first three years following the date of the report or the date of the intended start of production, whichever occurs later.
- (6) The proposed date for the initiation of manufacturing or importation of chlorinated terphenyl, if appropriate.

(d) *When to report.* Persons who are manufacturing or importing chlorinated terphenyl on the effective date of the rule must notify EPA within 30 days of the effective date of the rule. Persons who propose to manufacture or import chlorinated terphenyl must notify EPA within 15 days after making the management decision described in § 704.3 "Proposed to manufacture or import".

[49 FR 11184, Mar. 26, 1984, as amended at 49 FR 32068, Aug. 10, 1984; 50 FR 2048, Jan. 15, 1985; 52 FR 20083, May 29, 1987. Redesignated at 53 FR 51717, Dec. 22, 1988; 58 FR 34204, June 23, 1993]

**§ 704.95 Phosphonic acid, [1,2-ethanediyl-bis[nitrilobis-(methylene)]tetrakis- (EDTMPA) and its salts.**

(a) *Substances for which reporting is required.* The chemical substances for

which reporting is required under this section are:

| CAS No.    | Chemical name  |
|------------|--|
| 1429-50-1  | Phosphonic acid, [1,2-ethanediyl-bis[nitrilobis (methylene)] tetrakis- (EDTMPA)  |
| 15142-96-8 | Phosphonic acid, [1,2-ethanediyl-bis[nitrilobis(methylene)] tetrakis-, hexasodium salt   |
| 34274-30-1 | Phosphonic acid, [1,2-ethanediyl-bis[nitrilobis(methylene)] tetrakis-, potassium salt  |
| 57011-27-5 | Phosphonic acid, [1,2-ethanediyl-bis[nitrilobis (methylene)] tetrakis-, ammonium salt  |
| 67924-23-6 | Cobaltate (6-), [[[1,2-ethanediylbis [nitrilobis (methylene)] tetrakis-[phosphonato]] (8-)-, pentapotassium hydrogen, (OC-6-21)-                       |
| 67969-67-9 | Cobaltate (6-), [[[1,2-ethanediylbis [nitrilobis (methylene)] tetrakis- [phosphonato]] (8-)-N,N',O,O',O''',O''''-], pentasodium hydrogen, (OC-6-21)-   |
| 67989-89-3 | Cuprate (6-), [[[1,2-ethanediylbis [nitrilobis (methylene)] tetrakis- [phosphonato]] (8-)-, pentapotassium hydrogen, (OC-6-21)-                        |
| 68025-39-8 | Cobaltate (6-), [[[1,2-ethanediylbis [nitrilobis (methylene)] tetrakis- [phosphonato]] (6-)-N,N',O,O',O''',O''''-], pentaammonium hydrogen, (OC-6-21)- |
| 68188-96-5 | Phosphonic acid, [1,2-ethanediylbis [nitrilobis (methylene)] tetrakis-, tetrapotassium salt  |
| 68309-98-8 | Cadmate (6-), [[[1,2-ethanediylbis [nitrilobis (methylene)] tetrakis- [phosphonato]] (8-)-, pentapotassium hydrogen, (OC-6-21)-                        |
| 68901-17-7 | Phosphonic acid, [1,2-ethanediylbis [nitrilobis (methylene)] tetrakis-, octaammonium salt  |
| 68958-86-1 | Nickelate (6-), [[[1,2-ethanediylbis [nitrilobis (methylene)] tetrakis- [phosphonato]] (8-)-, pentaammonium hydrogen, (OC-6-21)-                       |
| 68958-87-2 | Nickelate (6-), [[[1,2-ethanediylbis [nitrilobis (methylene)] tetrakis- [phosphonato]] (8-)-, pentapotassium hydrogen, (OC-6-21)-                      |
| 68958-88-3 | Nickelate (6-), [[[1,2-ethanediylbis [nitrilobis (methylene)] tetrakis [phosphonato]] (8-)-, pentasodium hydrogen, (OC-6-21)-                          |

(b) *Persons who must report.* Unless exempt as provided in § 704.5, reports must be submitted by:

(1) Persons who manufacture or import any of the substances identified in paragraph (a) of this section.

(2) Persons who propose to manufacture or propose to import any of the substances identified in paragraph (a) of this section. For the purposes of importer reporting under this section, an import site is the operating unit within the person's organization which is directly responsible for importing the substance and which controls the import transaction; the import site may in some cases be the organization's headquarters office in the United States.

(c) *What information to report.* Persons identified in paragraph (b) of this section must report to EPA, for each of the substances identified in paragraph



## Environmental Protection Agency

## § 704.102

meets either paragraph (a)(4)(i) or (ii) of this section:

(i) A business is small if its total annual sales, when combined with those of its parent (if any), are less than \$40 million. However, if the annual manufacture, importation, or processing volume of a particular chemical substance at any individual site owned or controlled by the business is greater than 45,400 kilograms (100,000 pounds), the business shall not qualify as small for purposes of reporting on the manufacture, importation, or processing of that chemical substance at that site, unless the business qualifies as small under paragraph (a)(4)(ii) of this section.

(ii) A business is small if its total annual sales, when combined with those of its parent company (if any), are less than \$4 million, regardless of the quantity of the particular chemical substance manufactured, imported, or processed by that business.

(iii) For imported and processed mixtures containing HEX-BCH, the 45,400 kilograms (100,000 pounds) standard in paragraph (a)(4)(i) of this section applies only to the amount of HEX-BCH in a mixture and not the other components of the mixture.

(5) *8-hour time weighted average* means the cumulative exposure for an 8-hour work shift computed as follows:

$$E = \frac{C_a T_a + C_b T_b + \dots + C_n T_n}{8}$$

Where:

E is the equivalent exposure for the working shift.

$C_i$  is the concentration (i.e., parts per million) during any period of time ( $T_i$ ) where the concentration remains constant.

$T_i$  is the duration in hours of the exposure at the concentration  $C_i$ .

(6) *Year* means corporate fiscal year.

(b) *Persons who must report.* (1) Reports must be submitted by:

(i) Persons who are manufacturing, importing, or processing HEX-BCH for use as an intermediate in the production or isodrin or endrin on or after January 2, 1986; and

(ii) Persons who propose to manufacture, import, or process HEX-BCH for use as an intermediate in the production of isodrin or endrin, on or after January 2, 1986.

(2) Persons described in paragraph (b)(1) of this section who engage or propose to engage in more than one activity (i.e., manufacture and processing) must report the information required in paragraph (d) separately for each activity.

(c) *Persons exempt from reporting.* (1) Small businesses.

(2) Persons described in §704.5(a) and (c).

(d) *Information to report.* (1) Initial reports must include, to the extent that it is known to or reasonably ascertainable by the person reporting, the following information:

(i) Company name and address.

(ii) Name, address, and telephone number of the principal contact.

(iii) Name and address of plant sites where HEX-BCH is or is proposed to be manufactured, imported, or processed, noting for each plant site which activity takes or would take place at each site.

(iv) If applicable, the intended date for initiating the manufacture, import, or processing of HEX-BCH.

(v) If applicable, the actual quantity (by weight) of HEX-BCH manufactured, imported, or processed during the most recently concluded year.

(vi) The estimated quantity (by weight) of HEX-BCH to be manufactured, imported, or processed each year during the first 3 years following the date of the report or the date of the intended start of manufacture, import, or processing, whichever occurs later.

(vii) For each year described in paragraphs (d)(1) (v) and (vi) of this section: the number or expected number of employees exposed to HEX-BCH during the manufacture, import, processing, distribution in commerce, use, and disposal; the routes of exposure; and the 8-hour time weighted average of exposure.

(viii) If employees are exposed or expected to be exposed to HEX-BCH, state for each reported route of exposure, whether personal protective equipment is used or expected to be used, and a description of the personal protective equipment.

(ix) The actual or anticipated quantity, content, method of disposal, and disposal site of any wastes generated or expected to be generated during the



**§ 704.104**

**40 CFR Ch. I (7-1-10 Edition)**

manufacture, importation, or processing of HEX-BCH.

(2) Subsequent reports must provide, to the extent known to or reasonably ascertainable by the person reporting, the information in paragraph (d)(1) of this section and a statement explaining why the subsequent report is required.

(e) *When to report.* (1) Persons who are manufacturing, importing, or processing HEX-BCH on January 2, 1986, must submit an initial report to EPA by February 3, 1986.

(2) Persons who propose to manufacture, import, or process HEX-BCH on or after January 2, 1986, must submit an initial report to EPA by February 3, 1986, or 30 days after making the management decision described in § 704.3 “Propose to manufacture, import, or process,” whichever is later in time.

(3) Persons described in paragraph (b) of this section, who have submitted a report described in paragraph (d) of this section, must submit a subsequent report within 30 days of any of the following events. Based on the most recently submitted report:

(i) The manufacture, importation, or processing of HEX-BCH begins at a plant site different than that reported pursuant to paragraph (d)(1)(iii) of this section.

(ii) The actual quantity (by weight) of HEX-BCH manufactured, imported, or processed in a given year is greater than or equal to 200 percent of the estimated value for that year reported pursuant to paragraph (d)(1)(vi) of this section.

(iii) The total number of employees exposed to HEX-BCH is greater than 130 percent of the projected value reported pursuant to paragraph (d)(1)(vii) of this section.

(iv) The route of exposures to HEX-BCH differs from that reported pursuant to paragraph (d)(1)(vii) of this section.

(v) The actual 8-hour time weighted average exposure for any activity exceeds the projection reported pursuant to paragraph (d)(1)(vii) of this section by more than 100 percent.

(vi) The method of disposal or disposal site reported pursuant to paragraph (d)(1)(ix) of this section has changed.

(vii) Three years have passed since the most recent submission of a report and the person is still engaged in the manufacture, importation, or processing of HEX-BCH.

(f) *Certification of review.* Each person who submits a report under this section must for 3 years following the submission date of the most recent submission, review their activities at the end of each year to determine whether any reportable event specified in paragraph (e)(3) of this section has occurred. If a review shows that none of these events has occurred, the person is required to certify this fact in writing.

(g) *Recordkeeping.* Any person subject to the reporting requirements of this section must:

(1) Retain documentation of information contained in their reports. This documentation must be maintained for a period of 3 years from the date of the submission of the report; and

(2) Retain the certification required by paragraph (f) of this section for 3 years from the date of its creation.

[50 FR 47536, Nov. 19, 1985, as amended at 52 FR 20083, May 29, 1987. Redesignated at 53 FR 51717, Dec. 22, 1988; 58 FR 34204, June 23, 1993]

**§ 704.104 Hexafluoropropylene oxide.**

(a) *Definitions.* (1) “HFPO” means the chemical substance hexafluoropropylene oxide, CAS Number 428-59-1. [Listed in TSCA Inventory as oxirane, trifluoro(trifluoromethyl)-]

(2) “Enclosed process” means a process that is designed and operated so that there is no intentional release of any substance present in the process. A process with fugitive, inadvertent, or emergency pressure relief releases remains an enclosed process so long as measures are taken to prevent worker exposure to and environmental contamination from the releases.

(3) “Small processor” means a processor that meets either the standard in paragraph (a)(3)(i) of this section or the standard in paragraph (a)(3)(ii) of this section.

(i) *First standard.* A processor of a chemical substance is small if its total annual sales, when combined with those of its parent company, if any, are less than \$40 million. However, if the

## Environmental Protection Agency

## § 704.175

annual processing volume of a particular chemical substance at any individual site owned or controlled by the processor is greater than 45,400 kilograms (100,000 pounds), the processor shall not qualify as small for purposes of reporting on the processing of that chemical substance at that site, unless the processor qualifies as small under paragraph (a)(3)(ii) of this section.

(ii) *Second standard.* A processor of a chemical substance is small if its total annual sales, when combined with those of its parent company (if any), are less than \$4 million, regardless of the quantity of the particular chemical substance processed by that company.

(iii) *Inflation index.* EPA will use the Inflation Index described in the definition of "small manufacturer" that is set forth in §704.3 for purposes of adjusting the total annual sales values of this small processor definition. EPA will provide FEDERAL REGISTER notification when changing the total annual sales values of this definition.

(b) *Persons who must report.* Except as provided in paragraph (c) of this section, the following persons are subject to this section:

(1) Persons who manufacture or propose to manufacture HFPO for use as an intermediate in the manufacture of fluorinated substances in an enclosed process.

(2) Persons who import or propose to import HFPO for use as an intermediate in the manufacture of fluorinated substances in an enclosed process.

(3) Persons who process or propose to process HFPO as an intermediate in the manufacture of fluorinated substances in an enclosed process.

(c) *Persons not subject to this rule.* The following persons are not subject to this rule:

(1) Small processors.

(2) Persons described in §704.5 (a) through (d).

(3) Persons who have already submitted to EPA a completed copy of the Preliminary Assessment Information Manufacturer's Report (EPA Form 7710-35, as described at §712.28 of this chapter) for HFPO are not required to report under this section with respect to activities previously reported on.

(d) *What information to report.* Persons identified in paragraph (b) of this section must submit a Premanufacture Notice Form (EPA Form 7710-25).

(e) *When to report.* (1) Persons who are manufacturing, importing, or processing, or who propose to manufacture, import, or process HFPO for use as an intermediate in the manufacture of fluorinated substances in an enclosed process as of December 10, 1987, must report by February 8, 1988.

(2) Persons who propose to manufacture, import, or process HFPO for use as an intermediate in the manufacture of fluorinated substances in an enclosed process after December 10, 1987, must report within 30 days after making a firm management decision to commit financial resources for the manufacturing, importing, or processing of HFPO.

(f) *Recordkeeping.* Persons subject to the reporting requirements of this section must retain documentation of information contained in their reports for a period of 5 years from the date of submission of the reports.

(g) *Where to send reports.* Reports must be submitted by certified mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: HFPO Reporting.

[52 FR 41299, Oct. 27, 1987, as amended at 58 FR 34204, June 23, 1993; 60 FR 16308, Mar. 29, 1995; 60 FR 31920, June 19, 1995; 60 FR 34463, July 3, 1995; 71 FR 33641, June 12, 2006]

### § 704.175 4,4'-methylenebis(2-chloroaniline) (MBOCA).

(a) *Substance subject to reporting.* The chemical substance 4,4'-methylenebis(2-chloroaniline) (CAS No. 101-14-4) is subject to reporting under this section. The substance also is identified as 4,4'-methylenebis(2-chlorobenzeneamine) and MBOCA.

(b) *Persons who must report.* Except as provided in paragraph (c) of this section, the following persons are subject to this rule.

(1) Persons who propose to manufacture MBOCA in the United States on or after June 2, 1986.

(2) Persons who are manufacturing MBOCA in the United States as of June 2, 1986.

(3) Persons manufacturing MBOCA in the United States on or after June 2, 1986 who propose to change their manner or method of manufacturing the substance from a manner or method of manufacturing that previously was reported under this section.

(c) *Persons not subject to this rule.* The following persons are exempt from the reporting requirements of this section:

(1) Persons who import MBOCA into the customs territory of the United States and do not otherwise manufacture the substance in the United States.

(2) Persons who complied with the requirements of this section prior to June 2, 1986 and received written notification of compliance from EPA.

(d) *What information to report.* Persons who are subject to this rule as described in paragraph (b) of this section must report information to EPA by completing the following parts of the notice form contained in appendix A to part 720 of this chapter: Parts I.A., I.B., I.C.1., I.C.3., and II.A.; also, part III as appropriate. Persons subject to the requirements of this section also must submit a narrative description of any processing and packaging of MBOCA that occurs at the manufacturing plant site, including the number of workers potentially exposed to MBOCA during on-site processing and packaging of MBOCA and a description of any personal protective equipment and/or engineering controls that would be used to prevent release of and exposure to MBOCA during on-site processing and packaging. Persons subject to the requirements of this section are not required to submit information on processing or use of MBOCA away from the manufacturing plant site. Respondents to this rule shall report all information that is known to or reasonably ascertainable by the person reporting.

(e) *When to report.* (1) Persons specified in paragraph (b)(1) of this section must report by July 2, 1986 or within 30 days after making a firm management decision to commit financial resources for the manufacture of MBOCA, whichever is later in time.

(2) Persons specified in paragraph (b)(2) of this section must report by July 2, 1986.

(3) Persons specified in paragraph (b)(3) of this section must report within 30 days of making a firm management decision to commit financial resources to change their manner or method of manufacturing the substance from a manner or method of manufacturing that previously was reported under this section.

[51 FR 13223, Apr. 18, 1986, as amended at 52 FR 20083, May 29, 1987; 58 FR 34204, June 23, 1993]

## PART 707—CHEMICAL IMPORTS AND EXPORTS

### Subpart A [Reserved]

### Subpart B—General Import Requirements and Restrictions

Sec.

707.20 Chemical substances import policy.

### Subpart C [Reserved]

### Subpart D—Notices of Export Under Section 12(b)

707.60 Applicability and compliance.

707.63 Definitions.

707.65 Submission to agency.

707.67 Contents of notice.

707.70 EPA notice to foreign governments.

707.72 Termination of reporting requirements.

707.75 Confidentiality.

AUTHORITY: 15 U.S.C. 2611(b) and 2612.

SOURCE: 45 FR 82850, Dec. 16, 1980, unless otherwise noted.

### Subpart A [Reserved]

### Subpart B—General Import Requirements and Restrictions

#### §707.20 Chemical substances import policy.

(a) *Scope.* (1) This statement addresses the policy of the Environmental Protection Agency (EPA) on importation of chemical substances, mixtures, and articles under section 13 of the Toxic Substances Control Act (TSCA; 15 U.S.C. 2601 et seq.). In particular, it

addresses aspects of the regulation promulgated by the United States Customs Service (Customs), Department of the Treasury (19 CFR 12.118 through 12.127, and 127.28 [amended]) to implement section 13 of TSCA, 15 U.S.C. 2612. Section 13 requires the Secretary of the Treasury to refuse entry into the Customs territory of the United States of a chemical substance, mixture, or article if it does not comply with rules in effect under TSCA, or if it is offered for entry in violation of TSCA or rules or orders under TSCA.

(2) In addition to this statement of policy, EPA will continue, as necessary, to address problems associated with imports in rulemaking and other actions under individual sections of TSCA, i.e., sections 4, 5, 6, 7, 8, and 12. Sections 5, 6, and 7 apply directly to imports subject to the section 13 requirements. Section 12 may apply to export of a shipment that is refused entry under section 13. Importers may have obligations under sections 4 and 8; section 4 and 8 requirements for importers would not apply to individual chemical shipments and thus are not included under section 13 requirements. Interested persons should refer to the records of these individual rulemaking actions for specific information and guidance.

(b) *Objectives.* (1) TSCA is intended to be comprehensive, and assure protection of health and the environment from unreasonable risks associated with chemicals whether the chemicals are imported or produced domestically. This intent is manifested by the inclusion of importation in the Act's definition of the term "manufacture": "[M]anufacture means to import \* \* \*, produce, or manufacture" (15 U.S.C. 2602(7)). Thus, importers are responsible for insuring that chemical importation complies with TSCA just as domestic manufacturers are responsible for insuring that chemical manufacture complies with TSCA.

(2)(i) The section 13 rule requires importers to sign the following statement for each import of chemical substances subject to TSCA: "I certify that all chemical substances in this shipment comply with all applicable rules or orders under TSCA and that I am not offering a chemical substance for entry

in violation of TSCA or any applicable rule or order under TSCA." The certification will document that, in accordance with TSCA, the importer has taken the necessary steps to insure compliance.

(ii) The section 13 rule requires importers of chemicals not subject to TSCA (e.g., pesticides) to certify that compliance with TSCA is not required. Importers must certify this by signing the statement: "I certify that all chemicals in this shipment are not subject to TSCA." This is appropriate when a chemical import is not clearly identified as a pesticide or other chemical not subject to TSCA.

(3) The United States is involved in a major effort toward international harmonization in the control of chemicals. At such time as international agreement is reached on this issue, EPA would be prepared to modify its policy if necessary. EPA believes that its international harmonization efforts in the control of chemicals will protect health and the environment while fulfilling its obligations under the Trade Agreements Act of 1979.

(c) *The section 13 rule—(1) General certification.* (i) The rule promulgated under section 13 of TSCA by Customs, in consultation with EPA, implements the requirement of section 13 that chemical substances, mixtures, or articles not in compliance with TSCA, or whose importation is not in compliance with TSCA, shall be denied entry into the customs territory of the United States. The rule requires that importers certify by a statement, on the entry document or invoice, that any shipment of a chemical substance subject to TSCA, imported in bulk or as part of a mixture, complies with TSCA, and that it is not offered for entry in violation of TSCA or any rule or order under TSCA, or that the chemicals imported are not subject to TSCA.

(ii) The certification applies to TSCA sections 5, 6, and 7.

(iii) EPA expects that this certification will be based upon actual knowledge of the importer in most cases. However, EPA realizes that sometimes importers may not have actual knowledge of the chemical composition of imported mixtures. In these cases, the importer should attempt to discover

## § 707.20

the chemical constituents of the shipment by contacting another party to the transaction (e.g., his principal or the foreign manufacturer). This person may be able to identify the components of the mixture, or at least state that the substances comply with TSCA. The greater the effort an importer makes to learn the identities of the imported substances and their compliance with TSCA, the smaller his chance of committing a violation by importing a noncomplying shipment. If a shipment is ultimately determined to have violated TSCA, the good faith efforts of the importer to verify compliance, as evidenced by documents contained in his files, may obviate or mitigate the assessment of a civil penalty under section 16 of TSCA.

(2) *EPA enforcement.* (i) EPA and Customs will monitor chemical imports to determine if shipments and their import comply with the certification requirements and the substantive mandates of TSCA. Customs will refuse entry to any shipment until such time as the certification is properly submitted. Customs will also detain a shipment if there are reasonable grounds to believe that such shipment or its import violates TSCA or regulations or orders thereunder. A violative shipment must either be brought into compliance, exported, destroyed, or voluntarily abandoned within the time periods prescribed in 19 CFR 12.124 of the section 13 rule.

(ii) When EPA determines that a shipment should be detained, EPA will identify the reasons for the detention and the necessary actions for an importer to bring the shipment into compliance with TSCA. If EPA has given this information to Customs before the district director issues the detention notice, the information will become part of the detention notice. The importer should contact one of the following EPA regional offices for guidance as to the proper procedures to correct any deficiencies in the shipment.

### REGION I

John F. Kennedy Federal Building, Boston, MA 02203 (617-223-0586)

### REGION II

26 Federal Plaza, New York, NY 10278 (201-321-6669)

## 40 CFR Ch. I (7-1-10 Edition)

### REGION III

Curtis Building, 6th and Walnut Streets, Philadelphia, PA 19106 (215-597-7668)

### REGION IV

345 Courtland Street, NE., Atlanta, GA 30365 (404-881-3864)

### REGION V

77 West Jackson Boulevard, Chicago, IL 60604 (312-353-2291)

### REGION VI

1201 Elm Street, Dallas, TX 75270 (214-767-2734)

### REGION VII

324 East 11th Street, Kansas City, MO 64106 (816-374-3036)

### REGION VIII

1860 Lincoln Street, Denver, CO 80295 (303-837-3926)

### REGION IX

215 Fremont Street, San Francisco, CA 94105 (415-974-8119)

### REGION X

1200 Sixth Avenue, Seattle, WA 98101 (206-442-2871)

(iii) If Customs detains or refuses entry of a shipment (other than for failure to make the general certification) and the importer takes measures necessary to bring the shipment into conformity with the requirements of TSCA, EPA officials will reassess the shipment to determine its current compliance status. When a shipment is no longer in violation, EPA will notify the district director and the importer. The district director will then release the shipment. This notice will also serve as a determination to permit entry under 19 CFR 12.123(c) if a shipment is brought into compliance before the 19 CFR 12.123(c) decisionmaking process has been completed. If compliance is achieved after a 19 CFR 12.123(c) determination (adverse to the importer) has been made, the EPA notice to the district director will serve as a reversal of the decision to refuse entry.

(3) *EPA assistance.* Assistance in determining whether a chemical shipment is in compliance with TSCA can be obtained from the Director, Environmental Assistance Division (7408), Office of Pollution Prevention and

## Environmental Protection Agency

## § 707.60

Toxics, U.S. Environmental Protection Agency, Room E-543B, 1200 Pennsylvania Ave., NW., Washington, DC 20460, Telephone: (202) 554-1404, TDD: (202) 544-0551.

[48 FR 55464, Dec. 13, 1983, as amended at 60 FR 34463, July 3, 1995; 62 FR 1834, Jan. 14, 1997]

### Subpart C [Reserved]

### Subpart D—Notices of Export Under Section 12(b)

#### § 707.60 Applicability and compliance.

(a) Section 12(b) of the Toxic Substances Control Act requires any person who exports or intends to export a chemical substance or mixture to notify the Environmental Protection Agency of such exportation to a particular country if any of the following actions have been taken under the Act with respect to that chemical substance or mixture:

(1) Data are required under section 4 or 5(b),

(2) An order has been issued under section 5,

(3) A rule has been proposed or promulgated under section 5 or 6, or

(4) An action is pending, or relief has been granted under section 5 or 7.

(b) No notice of export will be required for articles, except PCB articles, unless the Agency so requires in the context of individual section 5, 6, or 7 actions.

(c)(1) Except as provided in paragraphs (c)(2) and (3) of this section no notice of export is required for the export of a chemical substance or mixture for which export notification is otherwise required, where such chemical substance or mixture is present in a concentration of less than 1% (by weight or volume).

(2) No notice of export is required for the export of a chemical substance or mixture that is a known or potential human carcinogen where such chemical substance or mixture is present in a concentration of less than 0.1% (by weight or volume). A chemical is considered to be a known or potential human carcinogen, for purposes of TSCA section 12(b) export notification, if that chemical is:

(i) A chemical substance or mixture listed as a “known to be human carcinogen” or “reasonably anticipated to be human carcinogen” in the Report on Carcinogens (latest edition) issued by the U.S. Department of Health and Human Services, Public Health Service, National Toxicology Program,

(ii) A chemical substance or mixture is classified as “carcinogenic to humans” (Group 1), “probably carcinogenic to humans” (Group 2A), or “probably carcinogenic to humans” (Group 2B) in the Monographs and Supplements on the Evaluation of Carcinogenic Risks to Humans issued by the World Health Organization International Agency for Research on Cancer (IARC), Lyons, France (latest editions), or

(iii) Alpha-naphthylamine (Chemical Abstract Service Registry Number (CAS No.) 134-32-7) or 4-nitrobiphenyl (CAS No. 92-93-3).

(3) No notice of export is required for the export of polychlorinated biphenyl chemicals (PCBs) (see definition in 40 CFR 761.3), where such chemical substances are present in a concentration of less than or equal to 50 ppm (by weight or volume).

(d) Any person who exports or intends to export PCBs or PCB articles (see definition in 40 CFR 761.3), for any purpose other than disposal, shall notify EPA of such intent or exportation under TSCA section 12(b), except as specified in §707.60(c)(3). PCBs and PCB articles have the definitions published in 40 CFR 761.3.

(e) Any person who would be prohibited by a TSCA section 5 or 6 regulation from exporting a chemical substance or mixture, but who is granted an exemption by EPA to export that chemical substance or mixture, shall notify EPA under TSCA section 12(b) of such intent to export or exportation.

(f) Failure to comply with TSCA section 12(b) as set forth in this part will be considered a violation of TSCA section 15(3), and will subject the exporter to the penalty, enforcement, and seizure provisions of TSCA sections 16 and 17.

[45 FR 82850, Dec. 16, 1980, as amended at 71 FR 66244, Nov. 14, 2006; 71 FR 68751, Nov. 28, 2006]

## § 707.63

## 40 CFR Ch. I (7–1–10 Edition)

### § 707.63 Definitions.

The definitions set forth in the Toxic Substances Control Act, section 3, apply for this part. In addition, the following abbreviations and definitions are provided for purposes of this rule:

(a) *EPA* means the Environmental Protection Agency.

(b) *Exporter* means the person who, as the principal party in interest in the export transaction, has the power and responsibility for determining and controlling the sending of the chemical substance or mixture to a destination out of the customs territory of the United States.

(c) *Regulated chemical* means any chemical substance or mixture for which export notice is required under § 707.60.

(d) *TSCA* means the Toxic Substances Control Act.

### § 707.65 Submission to agency.

(a) For each action under TSCA triggering export notification, exporters must notify EPA of their export or intended export of each subject chemical substance or mixture for which export notice is required under § 707.60 in accordance with the following:

(1) The notice must be in writing;

(2)(i) The notice must be for the first export or intended export by an exporter to a particular country in a calendar year when the chemical substance or mixture is the subject of an order issued, an action that is pending, or relief that has been granted under TSCA section 5(f), a rule that has been proposed or promulgated under TSCA section 6, or an action that is pending or relief that has been granted under TSCA section 7.

(ii) The notice must only be for the first export or intended export by an exporter to a particular country when the chemical substance or mixture is the subject of an order issued, an action that is pending, or relief that has been granted under TSCA section 5(e), a rule that has been proposed or promulgated under TSCA section 5(a)(2), or when the submission of data is required under TSCA section 4 or 5(b). Under this paragraph, notice of export to a particular country is not required if an exporter previously submitted to

EPA a notice of export to that country prior to January 16, 2007.

(3) The notice must be postmarked within seven days of forming the intent to export or on the date of export, whichever is earlier. A notice of intent to export must be based on a definite contractual obligation, or an equivalent intra-company agreement, to export the regulated chemical.

(b) If the EPA action that prompts the notice is a proposed rule, the requirement to submit export notices to EPA shall begin thirty days after publication of the action in the FEDERAL REGISTER.

(c) Notices shall be marked “TSCA Section 12(b) Notice” and sent to EPA by mail or delivered by hand or courier. Send notices by mail to: Document Control Office (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 (Attention: TSCA Section 12(b) Notice). Hand delivery of TSCA section 12(b) notices should be made to: OPPT Document Control Office (DCO), EPA East., Rm. 6428, Environmental Protection Agency, 1201 Constitution Ave., NW., Washington, DC (Attention: TSCA Section 12(b) Notice). The DCO is open from 8 a.m. to 4 p.m., Monday through Friday, excluding legal holidays. The telephone number for the DCO is (202) 564-8930. Such deliveries are only accepted during the DCO’s normal hours of operation.

[45 FR 82850, Dec. 16, 1980, as amended at 53 FR 12522, Apr. 15, 1988; 58 FR 40242, July 27, 1993; 60 FR 34463, July 3, 1995; 71 FR 33641, June 12, 2006; 71 FR 66244, Nov. 14, 2006]

### § 707.67 Contents of notice.

The notice to EPA shall include:

(a) The name of the regulated chemical as it appears in the section 4, 5, 6, and/or 7 action. If a category is regulated, the name of the individual regulated chemical within that category, as well as the category, must be given. The name shall be that which appears in Volume I of the EPA Chemical Substance Inventory, or its supplements, if the chemical appears there.

(b) The name and address of the exporter.

(c) The country (countries) of import.

(d) The date(s) of export or intended export.

(e) The section (4, 5, 6, and/or 7) of TSCA under which EPA has taken action.

[45 FR 82850, Dec. 16, 1980, as amended at 71 FR 66245, Nov. 14, 2006]

**§ 707.70 EPA notice to foreign governments.**

(a)(1) Notice by EPA to the importing country shall be sent no later than 5 working days after receipt by the TSCA Document Processing Center of the first annual notification from any exporter for each chemical substance or mixture that is the subject of an order issued, an action that is pending, or relief that has been granted under TSCA section 5(f), a rule that has been proposed or promulgated under TSCA section 6, or an action that is pending or relief that has been granted under TSCA section 7.

(2) Notice by EPA to the importing country shall be sent no later than 5 working days after receipt by the TSCA Document Processing Center of the first notification from any exporter for each chemical substance or mixture that is the subject of an order issued, an action that is pending, or relief that has been granted under TSCA section 5(e), a rule that has been proposed or promulgated under TSCA section 5(a)(2), or for which the submission of data is required under TSCA section 4 or 5(b).

(b) Notices shall:

(1) Identify the regulated chemical.

(2) Summarize the regulatory action taken, or indicate the availability of data under section 4 or 5(b) of TSCA.

(3) Identify an EPA official to contact for further information.

(4) Include a copy of the pertinent FEDERAL REGISTER notice.

(c) Notices shall be sent to the country's ambassador in Washington, DC, or other official designated by the foreign government, and to the United States Department of State.

[45 FR 82850, Dec. 16, 1980, as amended at 58 FR 40242, July 27, 1993; 71 FR 66245, Nov. 14, 2006]

**§ 707.72 Termination of reporting requirements.**

(a) The reporting requirements of subpart D of this part are terminated for certain specific chemical substances and mixtures as set forth in this paragraph.

(1) When data required under part 766 of this chapter have been submitted to EPA for a specific chemical substance produced by a specific process, and the data show no positive test result as defined in §766.3 of this chapter, reporting is no longer required by persons who export or intend to export that substance produced by that process.

(2) [Reserved]

(b) [Reserved]

[52 FR 21437, June 5, 1987]

**§ 707.75 Confidentiality.**

(a) A person may assert a claim of confidentiality for any information which is submitted to EPA in a notice.

(b) Any claim of confidentiality must accompany the information at the time it is submitted to EPA. In the notice, the submitter must clearly identify the information that is claimed confidential by marking the specific information on each page with a label such as "confidential business information", "proprietary", or "trade secret".

(c) Notwithstanding any claim of confidentiality, information outlined in §707.70 will be included in the EPA notice to the foreign government. With this exception, EPA will disclose information that is covered by a claim of confidentiality asserted in accordance with this section only to the extent permitted by, and in accordance with, the procedures set forth in TSCA and part 2 of this chapter.

(d) If a person does not assert a claim of confidentiality for information at the time a notice is submitted to EPA, the Agency may make the information public, including placement in a public file, without further notice to the person.

**PART 710—TSCA CHEMICAL INVENTORY REGULATIONS**

**Subpart A—General Provisions**

Sec.  
710.1 Scope and compliance.



## § 710.1

## 40 CFR Ch. I (7–1–10 Edition)

- 710.3 Definitions.
- 710.4 Scope of the inventory.

### Subpart B—2002 Inventory Update Reporting

- 710.23 Definitions.
- 710.25 Chemical substances for which information must be reported.
- 710.26 Chemical substances for which information is not required.
- 710.28 Persons who must report.
- 710.29 Persons not subject to this subpart.
- 710.30 Activities for which reporting is not required.
- 710.32 Reporting information to EPA.
- 710.33 When to report.
- 710.35 Duplicative reporting.
- 710.37 Recordkeeping requirements.
- 710.38 Confidentiality.
- 710.39 How do I submit the required information?

### Subpart C—Inventory Update Reporting for 2006 and Beyond

- 710.43 Definitions.
- 710.45 Chemical substances for which information must be reported.
- 710.46 Chemical substances for which information is not required.
- 710.48 Persons who must report.
- 710.49 Persons not subject to this subpart.
- 710.50 Activities for which reporting is not required.
- 710.52 Reporting information to EPA.
- 710.53 When to report.
- 710.55 Duplicative reporting.
- 710.57 Recordkeeping requirements.
- 710.58 Confidentiality.
- 710.59 Availability of reporting form and instructions.

AUTHORITY: 15 U.S.C. 2607(a).

### Subpart A—General Provisions

#### § 710.1 Scope and compliance.

(a) This part establishes regulations governing reporting and recordkeeping by certain persons who manufacture, import, or process chemical substances for commercial purposes under section 8(a) of the Toxic Substances Control Act (15 U.S.C. 2607(a)) (TSCA). Section 8(a) authorizes the Administrator to require reporting of information necessary for administration of the Act and requires EPA to issue regulations for the purpose of compiling and keeping current an inventory of chemical substances manufactured or processed for a commercial purpose, as required by section 8(b) of the Act. Following an initial reporting period, EPA published

an initial inventory of chemical substances manufactured, processed, or imported for commercial purposes. In accordance with section 8(b), EPA periodically amends the inventory to include new chemical substances which are manufactured or imported for a commercial purpose and reported under section 5(a)(1) of the Act. EPA also revises the categories of chemical substances and makes other amendments as appropriate.

(b) The regulations in this part apply to the activities associated with the compilation of the TSCA Chemical Inventory and the update of information on a subset of the chemical substances included on the Inventory. The Inventory Update regulations were amended in 2002; however, these amendments apply to updates after 2002, not to the 2002 update. In order to prevent confusion as to which regulations apply to which update, EPA has preserved the provisions that apply to the 2002 update in subpart B. The new and revised requirements that apply to updates after 2002 appear in subpart C. Prior to January 1, 2003, the regulations in subpart B of this part are effective for purposes of Inventory update activities. As of January 1, 2003, subpart C is effective for purposes of Inventory update activities. The Agency intends to remove subpart B from the CFR once the 2002 update is complete.

(c) Section 15(3) of TSCA makes it unlawful for any person to fail or refuse to submit information required under these reporting regulations. In addition, section 15(3) makes it unlawful for any person to fail to keep, and permit access to, records required by these regulations. Section 16 provides that any person who violates a provision of section 15 is liable to the United States for a civil penalty and may be criminally prosecuted. Pursuant to section 17, the Government may seek judicial relief to compel submission of section 8(a) information and to otherwise restrain any violation of section 15. (EPA does not intend to concentrate its enforcement efforts on insignificant clerical errors in reporting.)

(d) Each person who reports under these regulations must maintain records that document information reported under these regulations and, in

## Environmental Protection Agency

## § 710.3

accordance with the Act, permit access to, and the copying of, such records by EPA officials.

[68 FR 887, Jan. 7, 2003]

### § 710.3 Definitions.

In addition to the definitions in § 704.3 of this chapter, the following definitions apply to this part:

(a) The following terms will have the meaning contained in the Federal Food, Drug, and Cosmetic Act, 21 U.S.C. 321 *et seq.*, and the regulations issued under such Act: *Cosmetic, device, drug, food, and food additive*. In addition, the term *food* includes poultry and poultry products, as defined in the Poultry Products Inspection Act, 21 U.S.C. 453 *et seq.*; meats and meat food products, as defined in the Federal Meat Inspection Act, 21 U.S.C. 60 *et seq.*; and eggs and egg products, as defined in the Egg Products Inspection Act, 21 U.S.C. 1033 *et seq.*

(b) The term *pesticide* will have the meaning contained in the Federal Insecticide, Fungicide, and Rodenticide Act, 7 U.S.C. 136 *et seq.*, and the regulations issued thereunder.

(c) The following terms will have the meaning contained in the Atomic Energy Act of 1954, 42 U.S.C. 2014 *et seq.*, and the regulations issued thereunder: *Byproduct material, source material, and special nuclear material*.

(d) The following definitions also apply to this part:

*Act* means the Toxic Substances Control Act, 15 U.S.C. 2601 *et seq.*

*Administrator* means the Administrator of the U.S. Environmental Protection Agency, any employee or authorized representative of the Agency to whom the Administrator may either herein or by order delegate his/her authority to carry out his/her functions, or any other person who will by operation of law be authorized to carry out such functions.

An *article* is a manufactured item:

- (1) Which is formed to a specific shape or design during manufacture,
- (2) Which has end use function(s) dependent in whole or in part upon its shape or design during end use, and
- (3) Which has either no change of chemical composition during its end use or only those changes of composition which have no commercial purpose

separate from that of the article and that may occur as described in § 710.4(d)(5); except that fluids and particles are not considered articles regardless of shape or design.

*Byproduct* means a chemical substance produced without separate commercial intent during the manufacture or processing of another chemical substance(s) or mixture(s).

*Chemical substance* means any organic or inorganic substance of a particular molecular identity, including any combination of such substances occurring in whole or in part as a result of a chemical reaction or occurring in nature, and any chemical element or uncombined radical; except that “chemical substance” does *not* include:

- (1) Any mixture,
- (2) Any pesticide when manufactured, processed, or distributed in commerce for use as a pesticide,
- (3) Tobacco or any tobacco product, but not including any derivative products,
- (4) Any source material, special nuclear material, or byproduct material,
- (5) Any pistol, firearm, revolver, shells, and cartridges, and
- (6) Any food, food additive, drug, cosmetic, or device, when manufactured, processed, or distributed in commerce for use as a food, food additive, drug, cosmetic, or device.

*Commerce* means trade, traffic, transportation, or other commerce:

- (1) Between a place in a State and any place outside of such State, or
- (2) Which affects trade, traffic, transportation, or commerce described in paragraph (1) of this definition.

*Distribute in commerce* and *distribution in commerce*, when used to describe an action taken with respect to a chemical substance or mixture or article containing a substance or mixture, mean to sell or the sale of the substance, mixture, or article in commerce; to introduce or deliver for introduction into commerce, or the introduction or delivery for introduction into commerce of the substance, mixture, or article; or to hold or the holding of the substance, mixture, or article after its introduction into commerce.

*EPA* means the U.S. Environmental Protection Agency.

*Importer* means any person who imports any chemical substance or any chemical substance as part of a mixture or article into the customs territory of the U.S. and includes:

(1) The person primarily liable for the payment of any duties on the merchandise, or

(2) An authorized agent acting on his/her behalf (as defined in 19 CFR 1.11).

*Impurity* means a chemical substance which is unintentionally present with another chemical substance.

*Intermediate* means any chemical substance:

(1) Which is intentionally removed from the equipment in which it is manufactured, and

(2) Which either is consumed in whole or in part in chemical reaction(s) used for the intentional manufacture of other chemical substance(s) or mixture(s), or is intentionally present for the purpose of altering the rate of such chemical reaction(s).

NOTE: The *equipment in which it was manufactured* includes the reaction vessel in which the chemical substance was manufactured and other equipment which is strictly ancillary to the reaction vessel, and any other equipment through which the chemical substance may flow during a continuous flow process, but does not include tanks or other vessels in which the chemical substance is stored after its manufacture.

*Manufacture* means to manufacture, produce, or import for commercial purposes.

*Manufacture or import "for commercial purposes"* means to manufacture, produce, or import with the purpose of obtaining an immediate or eventual commercial advantage, and includes, for example, the manufacture or import of any amount of a chemical substance or mixture:

(1) For commercial distribution, including for test marketing, or

(2) For use by the manufacturer, including use for product research and development, or as an intermediate.

*Mixture* means any combination of two or more chemical substances if the combination does not occur in nature and is not, in whole or in part, the result of a chemical reaction; except that "mixture" does include:

(1) Any combination which occurs, in whole or in part, as a result of a chem-

ical reaction if the combination could have been manufactured for commercial purposes without a chemical reaction at the time the chemical substances comprising the combination were combined and if, after the effective date or premanufacture notification requirements, none of the chemical substances comprising the combination is a new chemical substance, and

(2) Hydrates of a chemical substance or hydrated ions formed by association of a chemical substance with water.

*New chemical substance* means any chemical substance which is not included in the inventory compiled and published under section 8(b) of the Act.

*Non-isolated intermediate* means any intermediate that is not intentionally removed from the equipment in which it is manufactured, including the reaction vessel in which it is manufactured, equipment which is ancillary to the reaction vessel, and any equipment through which the substance passes during a continuous flow process, but not including tanks or other vessels in which the substance is stored after its manufacture.

*Person* means any natural or juridical person including any individual, corporation, partnership, or association, any State or political subdivision thereof, or any municipality, any interstate body and any department, agency, or instrumentality of the Federal Government.

*Process* means the preparation of a chemical substance or mixture, after its manufacture, for distribution in commerce:

(1) In the same form or physical state as, or in a different form or physical state from, that in which it was received by the person so preparing such substance or mixture, or

(2) As part of a mixture or article containing the chemical substance or mixture.

*Process "for commercial purposes"* means to process:

(1) For distribution in commerce, including for test marketing purposes, or

(2) For use as an intermediate.

*Processor* means any person who processes a chemical substance or mixture.

*Site* means a contiguous property unit. Property divided only by a public

## Environmental Protection Agency

## § 710.4

right-of-way will be considered one site. There may be more than one manufacturing plant on a single site. For the purposes of imported chemical substances, the site will be the business address of the importer.

*Small quantities for purposes of scientific experimentation or analysis or chemical research on, or analysis of, such substance or another substance, including any such research or analysis for the development of a product* (hereinafter sometimes shortened to *small quantities for research and development*) means quantities of a chemical substance manufactured, imported, or processed or proposed to be manufactured, imported, or processed that:

(1) Are no greater than reasonably necessary for such purposes, and

(2) After the publication of the revised inventory, are used by, or directly under the supervision of, a technically qualified individual(s).

NOTE: Any chemical substances manufactured, imported, or processed in quantities less than 1,000 lbs. (454 kg) annually will be presumed to be manufactured, imported, or processed for research and development purposes. No person may report for the inventory any chemical substance in such quantities unless that person can certify that the substance was not manufactured, imported, or processed solely in small quantities for research and development, as defined in this section.

*State* means any State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, the Canal Zone, American Samoa, the Northern Mariana Islands, or any other territory or possession of the United States.

*Technically qualified individual* means a person:

(1) Who because of his/her education, training, or experience, or a combination of these factors, is capable of appreciating the health and environmental risks associated with the chemical substance which is used under his/her supervision,

(2) Who is responsible for enforcing appropriate methods of conducting scientific experimentation, analysis, or chemical research in order to minimize such risks, and

(3) Who is responsible for the safety assessments and clearances related to the procurement, storage, use, and dis-

posal of the chemical substance as may be appropriate or required within the scope of conducting the research and development activity. The responsibilities in this paragraph may be delegated to another individual, or other individuals, as long as each meets the criteria in paragraph (1) of this definition.

*Test marketing* means the distribution in commerce of no more than a predetermined amount of a chemical substance, mixture, or article containing that chemical substance or mixture, by a manufacturer or processor to no more than a defined number of potential customers to explore market capability in a competitive situation during a predetermined testing period prior to the broader distribution of that chemical substance, mixture, or article in commerce.

*United States*, when used in the geographic sense, means all of the States, territories, and possessions of the United States.

[68 FR 888, Jan. 7, 2003, as amended at 69 FR 40791, July 7, 2004]

### § 710.4 Scope of the inventory.

(a) *Chemical substances subject to these regulations.* Only chemical substances which are manufactured, imported, or processed "for a commercial purpose," as defined in § 710.3(d), are subject to these regulations.

(b) *Naturally occurring chemical substances automatically included.* Any chemical substance which is naturally occurring and:

(1) Which is (i) unprocessed or (ii) processed only by manual, mechanical, or gravitational means; by dissolution in water; by flotation; or by heating solely to remove water; or

(2) Which is extracted from air by any means, will automatically be included in the inventory under the category "Naturally Occurring Chemical Substances." Examples of such substances are: raw agricultural commodities; water, air, natural gas, and crude oil; and rocks, ores, and minerals.

(c) *Substances excluded by definition or section 8(b) of TSCA.* The following substances are excluded from the inventory:

## §710.4

## 40 CFR Ch. I (7–1–10 Edition)

(1) Any substance which is not considered a “chemical substance” as provided in subsection 3(2)(B) of the Act and in the definition of “chemical substance” in §710.3(d);

(2) Any mixture as defined in §710.3(d);

NOTE: A chemical substance that is manufactured as part of a mixture is subject to these reporting regulations. This exclusion applies only to the mixture and not to the chemical substances of which the mixture is comprised. The term “mixture” includes alloys, inorganic glasses, ceramics, frits, and cements, including Portland cement.

(3) Any chemical substance which is manufactured, imported, or processed solely in small quantities for research and development, as defined in §710.3(d); and

(4) Any chemical substance not manufactured, processed or imported for a commercial purpose since January 1, 1975.

(d) *Chemical substances excluded from the inventory.* The following chemical substances are excluded from the inventory. Although they are considered to be manufactured or processed for a commercial purpose for the purpose of section 8 of the Act, they are not manufactured or processed for distribution in commerce as chemical substances *per se* and have no commercial purpose separate from the substance, mixture, or article of which they may be a part.

NOTE: In addition, chemical substances excluded here will not be subject to premanufacture notification under section 5 of the Act.

(1) Any impurity.

(2) Any byproduct which has no commercial purpose.

NOTE: A byproduct which has commercial value only to municipal or private organizations who (i) burn it as a fuel, (ii) dispose of it as a waste, including in a landfill or for enriching soil, or (iii) extract component chemical substances which have commercial value, may be reported for the inventory, but will not be subject to premanufacture notification under section 5 of the Act if not included.

(3) Any chemical substance which results from a chemical reaction that occurs incidental to exposure of another chemical substance, mixture, or article to environmental factors such as air, moisture, microbial organisms, or sunlight.

(4) Any chemical substance which results from a chemical reaction that occurs incidental to storage of another chemical substance, mixture, or article.

(5) Any chemical substance which results from a chemical reaction that occurs upon end use of other chemical substances, mixtures, or articles such as adhesives, paints, miscellaneous cleansers or other housekeeping products, fuels and fuel additives, water softening and treatment agents, photographic films, batteries, matches, and safety flares, and which is not itself manufactured for distribution in commerce or for use as an intermediate.

(6) Any chemical substance which results from a chemical reaction that occurs upon use of curable plastic or rubber molding compounds, inks, drying oils, metal finishing compounds, adhesives, or paints; or other chemical substances formed during manufacture of an article destined for the marketplace without further chemical change of the chemical substance except for those chemical changes that may occur as described elsewhere in this §710.4(d).

(7) Any chemical substance which results from a chemical reaction that occurs when (i) a stabilizer, colorant, odorant, antioxidant, filler, solvent, carrier, surfactant, plasticizer, corrosion inhibitor, antifoamer or de-foamer, dispersant, precipitation inhibitor, binder, emulsifier, de-emulsifier, dewatering agent, agglomerating agent, adhesion promoter, flow modifier, pH neutralizer, sequesterant, coagulant, flocculant, fire retardant, lubricant, chelating agent, or quality control reagent functions as intended or (ii) a chemical substance, solely intended to impart a specific physico-chemical characteristic, functions as intended.

(8) Chemical substances which are not intentionally removed from the equipment in which they were manufactured.

NOTE: See note to definition of “intermediate” at §710.3(d) for explanation of “equipment in which it was manufactured.”

[42 FR 64572, Dec. 23, 1977, as amended at 68 FR 889, Jan. 7, 2003]

**Subpart B—2002 Inventory Update Reporting****§ 710.23 Definitions.**

In addition to the definitions in § 704.3 of this chapter and § 710.3, the following definitions also apply to subpart B of this part.

*Master Inventory File* means EPA's comprehensive list of chemical substances which constitute the Chemical Substances Inventory compiled under section 8(b) of the Act. It includes substances reported under subpart A of this part and substances reported under part 720 of this chapter for which a Notice of Commencement of Manufacture or Import has been received under § 720.120 of this chapter.

*Non-isolated intermediate* means any intermediate that is not intentionally removed from the equipment in which it is manufactured, including the reaction vessel in which it is manufactured, equipment which is ancillary to the reaction vessel, and any equipment through which the substance passes during a continuous flow process, but not including tanks or other vessels in which the substance is stored after its manufacture.

*Site-limited* means a chemical substance is manufactured and processed only within a site and is not distributed for commercial purposes as a substance or as part of a mixture or article outside the site. Imported substances are never site-limited.

[68 FR 889, Jan. 7, 2003]

**§ 710.25 Chemical substances for which information must be reported.**

Any chemical substance which is in the Master Inventory File at the beginning of a reporting period described in § 710.33, unless the chemical substance is specifically excluded by § 710.26.

[51 FR 21447, June 12, 1986]

**§ 710.26 Chemical substances for which information is not required.**

The following categories of chemical substances are excluded from the reporting requirements of this subpart. However, a chemical substance described in paragraphs (a), (b), or (c) of this section is not excluded from the

reporting requirements of this subpart if that substance is the subject of a rule proposed or promulgated under section 4, 5(a)(2), 5(b)(4), or 6 of the Act, or is the subject of an order issued under section 5(e) or 5(f) of the Act, or is the subject of relief that has been granted under a civil action under section 5 or 7 of the Act.

(a) *Inorganic chemical substances.* Any chemical substance which does not contain carbon or contains carbon only in the form of carbonate [=CO<sub>3</sub>], cyano [-CN], cyanato [-OCN], isocyanato [-NC], or isocyanato [-NCO] groups, or the chalcogen analogues of such groups.

(b) *Polymers.* (1) Any chemical substance described with the word fragments “\*polym\*”, “\*alkyd\*”, or “\*oxylated\*” in the Chemical Abstracts Service Index or Preferred Nomenclature in the Chemical Substance Identities section of the 1985 edition of the Inventory or in the Master Inventory File, where the asterisk (\*) indicates that any sets of characters may precede, or follow, the character string defined.

(2) Any chemical substance which is identified in the 1985 edition of the Inventory or the Master Inventory File as siloxane and silicone, silsesquioxane, a protein (albumin, casein, gelatin, gluten, hemoglobin), an enzyme, a polysaccharide (starch, cellulose, gum), rubber, or lignin. This exclusion, however, does not apply to a chemical substance which has been hydrolyzed, depolymerized, or chemically modified to the extent that the final product is no longer polymeric in structure.

(c) *Microorganisms.* Any combination of chemical substances that is a living organism, such as bacteria, eimeria, fungi, and yeasts. Any chemical substance produced from such a living organism is reportable unless otherwise excluded.

(d) *Naturally occurring chemical substances.* Any naturally occurring chemical substance, as described in § 710.4(b). The applicability of this exclusion is determined in each case by the specific activities of the person who manufactures the substance in question. Some chemical substances can be manufactured both as described in § 710.4(b) and

## § 710.28

by means other than those described in § 710.4(b). If a person described in § 710.28 manufactures a chemical substance by means other than those described in § 710.4(b), the person must report regardless of whether the substance also could have been produced as described in § 710.4(b). Any chemical substance that is produced from such a naturally occurring chemical substance described in § 710.4(b) is reportable unless otherwise excluded.

[51 FR 21447, June 12, 1986]

### § 710.28 Persons who must report.

Except as provided in §§ 710.29 and 710.30, the following persons are subject to the requirements of this subpart. Persons must determine whether they must report under this § 710.28 for each chemical substance that they manufacture at an individual site.

(a) *Persons subject to initial reporting.* Any person who manufactured for commercial purposes 10,000 pounds (4,540 kilograms) or more of a chemical substance described in § 710.25 at any single site owned or controlled by that person at any time during the person's latest complete corporate fiscal year before August 25, 1986.

(b) *Persons subject to recurring reporting.* Any person who manufactured for commercial purposes 10,000 pounds (4,540 kilograms) or more of a chemical substance described in § 710.25 at any single site owned or controlled by that person at any time during the person's latest complete corporate fiscal year before August 25, 1990, or before August 25 at four-year intervals thereafter.

(c) *Special provisions for importers.* For purposes of paragraphs (a) and (b) of this section, the site for a person who imports a chemical substance described in § 710.25 is the site of the operating unit within the person's organization which is directly responsible for importing the substance and which controls the import transaction. The import site may in some cases be the organization's headquarters in the U.S. (See also § 710.35(b).)

[51 FR 21447, June 12, 1986]

## 40 CFR Ch. I (7-1-10 Edition)

### § 710.29 Persons not subject to this subpart.

A person described in § 710.28 is not subject to the requirements of this subpart if that person qualifies as a small manufacturer as that term is defined in § 704.3 of this chapter. Notwithstanding this exclusion, a person who qualifies as a small manufacturer is subject to this subpart with respect to any chemical substance that is the subject of a rule proposed or promulgated under section 4, 5(b)(4), or 6 of the Act, or is the subject of an order in effect under section 5(e) of the Act, or is the subject of relief that has been granted under a civil action under section 5 or 7 of the Act.

[51 FR 21447, June 12, 1986]

### § 710.30 Activities for which reporting is not required.

A person described in § 710.28 is not subject to the requirements of this subpart with respect to any chemical substance described in § 710.25 that the person manufactured or imported under the following circumstances:

(a) The person manufactured or imported the chemical substance described in § 710.25 solely in small quantities for research and development,

(b) The person imported the chemical substance described in § 710.25 as part of an article,

(c) The person manufactured the chemical substance described in § 710.25 in a manner described in § 720.30(g) or (h) of this chapter.

[51 FR 21447, June 12, 1986]

### § 710.32 Reporting information to EPA.

Any person who must report under this part must submit the information prescribed in this section for each chemical substance described in § 710.25 that the person manufactured for commercial purposes in an amount of 10,000 pounds (4,540 kilograms) or more at a single site during a corporate fiscal year described in § 710.28. (The site for a person who imports a chemical substance is the site of the operating unit within the person's organization which is directly responsible for importing the substance and which controls the import transaction, and may in some

## Environmental Protection Agency

## § 710.33

cases be the organization's headquarters office in the U.S.). A respondent to this subpart must report information in writing or by magnetic media as prescribed in this section, to the extent that such information is known to or reasonably ascertainable by that person. A respondent to this subpart must report information that applies to the specific corporate fiscal year for which the person is required to report.

(a) *Reporting in writing.* Any person who chooses to report information to EPA in writing must do so by completing the reporting form available from EPA at the address set forth in § 710.39(b). The form must include all information prescribed in paragraph (c) of this section. Persons reporting in writing must submit a separate form for each site for which the person is required to report.

(b) *Reporting by magnetic media.* Any person who chooses to report information to EPA by means of magnetic media must submit the information prescribed in paragraph (c) of this section. Magnetic media submitted in response to this subpart must meet EPA specifications, as described in the instruction booklet available from EPA at the address set forth in § 710.39(b).

(c) *Information to be reported.* Persons reporting information under this subpart must report the following:

(1) The name, company, address, city, State, Zip code, and telephone number of a person who will serve as technical contact for the respondent company, and will be able to answer questions about the information submitted by the company to EPA. Persons reporting by means of magnetic media must submit this information on the reporting form available from EPA at the address set forth in § 710.39.

(2) A certification statement signed and dated by an authorized official of the respondent company. Persons reporting by means of magnetic media must submit this information on the reporting form available from EPA at the address set forth in § 710.39.

(3) The specific chemical name and Chemical Abstracts Service (CAS) Registry Number of each chemical substance for which reporting is required under this subpart. A respondent to

this subpart may use other chemical identification numbers in lieu of CAS Registry Numbers when a CAS Registry Number is not known to the respondent as provided in the instruction booklet identified in § 710.39(b), including EPA-designated Accession Numbers for confidential substances, EPA-assigned numbers for *bona fide* or Premanufacture Notification submissions, or Test Market Exemption Applications, or original Inventory form numbers.

(4) The name, street address, city, State, and Zip code of each site at which 10,000 pounds (4,540 kilograms) or more of a chemical substance for which reporting is required under this subpart is manufactured or imported. (The site for a person who imports a chemical substance is the site of the operating unit within the person's organization which is directly responsible for importing the substance and which controls the import transaction, and may in some cases be the organization's headquarters office in the U.S.) A respondent to this subpart must include the appropriate Dun and Bradstreet Number for each plant site reported.

(5) A statement for each substance for which information is being submitted indicating whether the substance is manufactured in the United States or imported into the United States.

(6) A statement for each substance for which information is being submitted indicating whether the substance is site-limited.

(7) The total volume (in pounds) of each subject chemical substance manufactured or imported at each site. This amount must be reported to two significant figures of accuracy provided that the reported figures are within  $\pm 10$  percent of the actual volume.

[55 FR 39587, Sept. 27, 1990, as amended at 60 FR 31921, June 19, 1995]

### § 710.33 When to report.

All information reported to EPA in response to the requirements of this subpart must be submitted during an applicable reporting period. The following reporting periods are prescribed for this subpart.



## § 710.35

(a) *Initial reporting period.* The first reporting period is from August 25, 1986 to December 23, 1986. Any person described in § 710.28(a) must report during this period for each chemical substance described in § 710.25 that the person manufactured during the corporate fiscal year described in § 710.28(a).

(b) *Recurring reporting periods.* The first recurring reporting period is from August 25, 1990 to December 23, 1990. Subsequent reporting periods, except as provided in paragraph (c) of this section, are from August 25 to December 23 at 4-year intervals thereafter. Any person described in § 710.28(b) must report during the appropriate reporting period for each chemical substance described in § 710.25 that the person manufactured during the applicable corporate fiscal year described in § 710.28(b).

(c) *Reporting in 1998.* The 1998 reporting period is from August 25, 1998 until January 31, 1999. Any person described in § 710.28(b) must report during this reporting period for each chemical substance described in § 710.25 that the person manufactured during the applicable corporate fiscal year described in § 710.28(b). This reporting period is applicable to 1998 reporting only.

[51 FR 21447, June 12, 1986; 51 FR 22521, June 20, 1986, as amended at 63 FR 71600, Dec. 29, 1998]

## § 710.35 Duplicative reporting.

(a) *With regard to section 8(a) rules.* Any person subject to the requirements of this part who previously has complied with reporting requirements of a rule under section 8(a) of the Act by submitting the information described in § 710.32 for a chemical substance described in § 710.25 to EPA, and has done so within one year of the start of a reporting period described in § 710.33, is not required to report again on the manufacture of that substance at that site during that reporting period.

(b) *With regard to importers.* This part requires that only one report be submitted on each import transaction involving a chemical substance described in § 710.25. When two or more persons are involved in a particular import transaction and each person meets the Agency's definition of "importer" as set forth in §§ 710.2(l) and 704.3 of this

## 40 CFR Ch. I (7-1-10 Edition)

chapter, they may determine among themselves who should submit the required report; if no report is submitted as required under this part, EPA will hold each such person liable for failure to report.

[51 FR 21447, June 12, 1986, as amended at 60 FR 31921, June 19, 1995]

## § 710.37 Recordkeeping requirements.

Each person who is subject to the reporting requirements of this part must maintain records that document any information reported to EPA. For substances that are manufactured or imported at less than 10,000 pounds annually, volume records must be maintained as evidence to support a decision not to submit a report. Records relevant to reporting during a reporting period described in § 710.33 must be retained for a period of four years beginning with the effective date of that reporting period.

[51 FR 21447, June 12, 1986, as amended at 58 FR 34204, June 23, 1993; 60 FR 31921, June 19, 1995]

## § 710.38 Confidentiality.

(a) Any person submitting information under this part may assert a business confidentiality claim for the information. The procedures for asserting confidentiality claims are described in the instruction booklet identified in § 710.39. Information claimed as confidential in accordance with this section and those instructions will be treated and disclosed in accordance with the procedures in part 2 of this chapter.

(b) A person may assert a claim of confidentiality for the chemical identity of a specific chemical substance only if the identity of that substance is treated as confidential in the Master Inventory File as of the time the report is submitted for that substance under this part.

(c) To assert a claim of confidentiality for the chemical identity of a specific chemical substance, the person must take the following steps:

(1) The person must submit with the report detailed written answers to the following questions signed and dated by an authorized official.

## Environmental Protection Agency

## § 710.39

(i) What harmful effects to your competitive position, if any, do you think would result from the identity of the chemical substance being disclosed in connection with reporting under this part? How could a competitor use such information? Would the effects of disclosure be substantial? What is the causal relationship between the disclosure and the harmful effects?

(ii) How long should confidential treatment be given? Until a specific date, the occurrence of a specific event, or permanently? Why?

(iii) Has the chemical substance been patented? If so, have you granted licenses to others with respect to the patent as it applies to the chemical substance? If the chemical substance has been patented and therefore disclosed through the patent, why should it be treated as confidential?

(iv) Has the identity of the chemical substance been kept confidential to the extent that your competitors do not know it is being manufactured or imported for a commercial purpose by anyone?

(v) Is the fact that the chemical substance is being manufactured or imported for a commercial purpose available to the public, for example in technical journals, libraries, or State, local, or Federal agency public files?

(vi) What measures have you taken to prevent undesired disclosure of the fact that this chemical substance is being manufactured or imported for a commercial purpose?

(vii) To what extent has the fact that this chemical substance is manufactured or imported for commercial purposes been revealed to others? What precautions have been taken regarding these disclosures? Have there been public disclosures or disclosures to competitors?

(viii) Does this particular chemical substance leave the site of manufacture in any form, as product, effluent, emission, etc.? If so, what measures have you taken to guard against discovery of its identity?

(ix) If the chemical substance leaves the site in a product that is available to the public or your competitors, can the substance be identified by analysis of the product?

(x) For what purpose do you manufacture or import the substance?

(xi) Has EPA, another Federal agency, or any Federal court made any pertinent confidentiality determinations regarding this chemical substance? If so, please attach copies of such determinations.

(2) If any of the information contained in the answers to the questions is asserted to contain confidential business information, the person must mark that information as "trade secret," "confidential," or other appropriate designation.

(d) If no claim of confidentiality accompanies information at the time it is submitted to EPA under this part or if substantiation required under paragraph (c) of this section is not submitted with the reporting form, EPA may make the information available to the public without further notice to the submitter.

[51 FR 21447, June 12, 1986, as amended at 55 FR 39588, Sept. 27, 1990; 60 FR 31921, June 19, 1995]

### § 710.39 How do I submit the required information?

(a) *Use the proper EPA form.* You must use the EPA form identified as "Form U" to submit written information in response to the requirements of this subpart. Copies of the Form U are available from EPA at the address set forth in paragraph (c) of this section and from the EPA Internet Home Page at <http://www.epa.gov/oppt/iur/iur02/index.htm>.

(b) *Follow the reporting instructions.* You should follow the detailed instructions for completing the reporting form and preparing a magnetic media report, which are given in the EPA publication entitled "Instructions for Reporting for Partial Updating of the TSCA Chemical Inventory Data Base," via the Internet or the TSCA Hotline.

(c) *Obtain the reporting package and copies of the form.* EPA is mailing the reporting package to those companies that reported in 1998. Failure to receive a reporting package does not obviate or otherwise affect the requirement to submit a timely report. If you did not receive a reporting package, but are required to report, you may obtain a copy of the reporting package and the

## § 710.43

reporting form from EPA by submitting a request for this information as follows:

(1) *By phone.* Call the EPA TSCA Hotline at (202) 554-1404.

(2) *By e-mail.* Send an e-mail request for this information to the EPA TSCA Hotline at [TSCA-Hotline@epamail.epa.gov](mailto:TSCA-Hotline@epamail.epa.gov).

(3) *By mail.* Send a written request for this information to the following address: TSCA Hotline, Mail Code 7408M, ATTN: Inventory Update Rule, Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460.

(d) *Submit the completed reports.* You must submit your completed reporting form(s) and/or magnetic media to EPA at the following address: OPPT Document Control Officer, Mail Code 7407M, ATTN: Inventory Update Rule, Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460.

[63 FR 45953, Aug. 28, 1998, as amended at 68 FR 890, Jan. 7, 2003]

### Subpart C—Inventory Update Reporting for 2006 and Beyond

SOURCE: 68 FR 890, Jan. 7, 2003, unless otherwise noted.

#### § 710.43 Definitions.

In addition to the definitions in § 704.3 of this chapter and § 710.3, the following definitions also apply to subpart C of this part:

*Commercial use* means the use of a chemical substance or mixture in a commercial enterprise providing saleable goods or services (e.g., dry cleaning establishment, painting contractor).

*Consumer use* means the use of a chemical substance that is directly, or as part of a mixture, sold to or made available to consumers for their use in or around a permanent or temporary household or residence, in or around a school, or in or around recreational areas.

*Industrial use* means use at a site at which one or more chemical substances

## 40 CFR Ch. I (7–1–10 Edition)

or mixtures are manufactured (including imported) or processed.

*Intended for use by children* means the chemical substance or mixture is used in or on a product that is specifically intended for use by children age 14 or younger. A chemical substance or mixture is intended for use by children when the submitter answers “yes” to at least one of the following questions for the product into which the submitter’s chemical substance or mixture is incorporated:

(1) Is the product commonly recognized (i.e., by a reasonable person) as being intended for children age 14 or younger?

(2) Does the manufacturer of the product state through product labeling or other written materials that the product is intended for or will be used by children age 14 or younger?

(3) Is the advertising, promotion, or marketing of the product aimed at children age 14 or younger?

*Known to or reasonably ascertainable by* means all information in a person’s possession or control, plus all information that a reasonable person similarly situated might be expected to possess, control, or know.

*Master Inventory File* means EPA’s comprehensive list of chemical substances which constitute the Chemical Substances Inventory compiled under section 8(b) of the Act. It includes substances reported under subpart A of this part and substances reported under part 720 of this chapter for which a Notice of Commencement of Manufacture or Import has been received under § 720.120 of this chapter.

*Readily obtainable information* means information which is known by management and supervisory employees of the submitter company who are responsible for manufacturing, processing, distributing, technical services, and marketing of the reportable chemical substance. Extensive file searches are not required.

*Reasonably likely to be exposed* means an exposure to a chemical substance which, under foreseeable conditions of manufacture (including import), processing, distribution in commerce, or use of the chemical substance, is more likely to occur than not to occur. Such exposures would normally include, but

## Environmental Protection Agency

## § 710.46

would not be limited to, activities such as charging reactor vessels, drumming, bulk loading, cleaning equipment, maintenance operations, materials handling and transfers, and analytical operations. Covered exposures include exposures through any route of entry (inhalation, ingestion, skin contact, absorption, etc.), but excludes accidental or theoretical exposures.

*Repackaging* means the physical transfer of a chemical substance or mixture, as is, from one container to another container or containers in preparation for distribution of the chemical substance or mixture in commerce.

*Reportable chemical substance* means a chemical substance described in § 710.45.

*Reporting year* means the calendar year in which information to be reported to EPA during an IUR submission period is generated, i.e., calendar year 2005 and the calendar year at 5-year intervals thereafter.

*Site-limited* means a chemical substance is manufactured and processed only within a site and is not distributed for commercial purposes as a substance or as part of a mixture or article outside the site. Imported substances are never site-limited. Although a site-limited chemical substance is not distributed for commercial purposes outside the site at which it is manufactured and processed, the substance is considered to have been manufactured and processed for commercial purposes.

*Submission period* means the period in which the information generated during the reporting year is submitted to EPA.

*Use* means any utilization of a chemical substance or mixture that is not otherwise covered by the terms *manufacture* or *process*. Relabeling or redistributing a container holding a chemical substance or mixture where no repackaging of the chemical substance or mixture occurs does not constitute use or processing of the chemical substance or mixture.

[68 FR 890, Jan. 7, 2003, as amended at 69 FR 40791, July 7, 2004; 70 FR 75068, Dec. 19, 2005]

### § 710.45 Chemical substances for which information must be reported.

Any chemical substance which is in the Master Inventory File at the beginning of a submission period described in § 710.53, unless the chemical substance is specifically excluded by § 710.46.

### § 710.46 Chemical substances for which information is not required.

The following groups or categories of chemical substances are exempted from some or all of the reporting requirements of this subpart, with the following exception: A chemical substance described in paragraph (a)(1), (a)(2), or (a)(4), or (b) of this section is not exempted from any of the reporting requirements of this subpart if that substance is the subject of a rule proposed or promulgated under section 4, 5(a)(2), 5(b)(4), or 6 of the Act, or is the subject of an order issued under section 5(e) or 5(f) of the Act, or is the subject of relief that has been granted under a civil action under section 5 or 7 of the Act.

(a) *Full exemptions.* The following categories of chemical substances are exempted from the reporting requirements of this subpart.

(1) *Polymers.* (i) Any chemical substance described with the word fragments “\*polym\*”, “\*alkyd\*”, or “\*oxylated\*” in the Chemical Abstracts Service Index or Preferred Nomenclature in the Chemical Substance Identities section of the Master Inventory File, where the asterisk (\*) indicates that any sets of characters may precede, or follow, the character string defined.

(ii) Any chemical substance which is identified in the Master Inventory File as siloxane and silicone, silsesquioxane, a protein (albumin, casein, gelatin, gluten, hemoglobin), an enzyme, a polysaccharide (starch, cellulose, gum), rubber, or lignin.

(iii) This exclusion does not apply to a polymeric substance that has been hydrolyzed, depolymerized, or otherwise chemically modified, except in cases where the intended product of this reaction is totally polymeric in structure.

§710.46

40 CFR Ch. I (7–1–10 Edition)

(2) *Microorganisms.* Any combination of chemical substances that is a living organism, and that meets the definition of “microorganism” at §725.3 of this chapter. Any chemical substance produced from a living microorganism is reportable under this subpart unless otherwise excluded.

(3) *Naturally occurring chemical substances.* Any naturally occurring chemical substance, as described in §710.4(b). The applicability of this exclusion is determined in each case by the specific activities of the person who manufactures the substance in question. Some chemical substances can be manufactured both as described in §710.4(b) and by means other than those described in §710.4(b). If a person described in §710.48 manufactures a chemical substance by means other than those described in §710.4(b), the person must report regardless of whether the substance also could have been produced as described in §710.4(b). Any chemical substance that is produced from such a naturally occurring chemical substance described in §710.4(b) is reportable unless otherwise excluded.

(4) *Certain forms of natural gas.* Chemical substances with the following Chemical Abstract Service (CAS) Registry Numbers: CAS No. 64741–48–6, Natural gas (petroleum), raw liquid mix; CAS No. 68919–39–1, Natural gas condensates; CAS No. 8006–61–9, Gasoline natural; CAS No. 68425–31–0, Gasoline (natural gas), natural; CAS No. 8006–14–2, Natural gas; and CAS No. 68410–63–9, Natural gas, dried.

(b) *Partial exemptions.* The following groups of chemical substances are partially exempted from the reporting requirements of this subpart (i.e., the information described in §710.52(c)(4) need not be reported for these substances). Such chemical substances are not excluded from the other reporting requirements under this subpart. A chemical substance described in paragraph (b)(3) of this section qualifies for a partial reporting exemption during the 2006 submission period; in subsequent submission periods, the chemical substances described in paragraph (b)(3) of this section will be subject to full reporting under this subpart (i.e., all of the information described in this

subpart must be reported), unless otherwise exempted.

(1) *Petroleum process streams.* EPA has designated the following chemical substances, listed by CAS Number, as partially exempt from reporting under the IUR.

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED “PETROLEUM PROCESS STREAMS” FOR PURPOSES OF INVENTORY UPDATE REPORTING

| CAS No.    | Product   |
|------------|---|
| 7732–18–5  | Water   |
| 8002–05–9  | Petroleum   |
| 8002–74–2  | Paraffin waxes and hydrocarbon waxes                    |
| 8006–20–0  | Fuel gases, low and medium B.T.U.                       |
| 8008–20–6  | Kerosine (petroleum)                                    |
| 8009–03–8  | Petrolatum  |
| 8012–95–1  | Paraffin oils   |
| 8030–30–6  | Naphtha   |
| 8032–32–4  | Ligroine  |
| 8042–47–5  | White mineral oil (petroleum)                           |
| 8052–41–3  | Stoddard solvent  |
| 8052–42–4  | Asphalt   |
| 61789–60–4 | Pitch   |
| 63231–60–7 | Paraffin waxes and hydrocarbon waxes, microcryst.       |
| 64741–41–9 | Naphtha (petroleum), heavy straight-run                 |
| 64741–42–0 | Naphtha (petroleum), full-range straight-run            |
| 64741–43–1 | Gas oils (petroleum), straight-run                      |
| 64741–44–2 | Distillates (petroleum), straight-run middle            |
| 64741–45–3 | Residues (petroleum), atm. tower                        |
| 64741–46–4 | Naphtha (petroleum), light straight-run                 |
| 64741–47–5 | Natural gas condensates (petroleum)                     |
| 64741–49–7 | Condensates (petroleum), vacuum tower                   |
| 64741–50–0 | Distillates (petroleum), light paraffinic               |
| 64741–51–1 | Distillates (petroleum), heavy paraffinic               |
| 64741–52–2 | Distillates (petroleum), light naphthenic               |
| 64741–53–3 | Distillates (petroleum), heavy naphthenic               |
| 64741–54–4 | Naphtha (petroleum), heavy catalytic cracked            |
| 64741–55–5 | Naphtha (petroleum), light catalytic cracked            |
| 64741–56–6 | Residues (petroleum), vacuum                            |
| 64741–57–7 | Gas oils (petroleum), heavy vacuum                      |
| 64741–58–8 | Gas oils (petroleum), light vacuum                      |
| 64741–59–9 | Distillates (petroleum), light catalytic cracked        |
| 64741–60–2 | Distillates (petroleum), intermediate catalytic cracked |
| 64741–61–3 | Distillates (petroleum), heavy catalytic cracked        |
| 64741–62–4 | Clarified oils (petroleum), catalytic cracked           |
| 64741–63–5 | Naphtha (petroleum), light catalytic reformed           |
| 64741–64–6 | Naphtha (petroleum), full-range alkylate                |
| 64741–65–7 | Naphtha (petroleum), heavy alkylate                     |
| 64741–66–8 | Naphtha (petroleum), light alkylate                     |
| 64741–67–9 | Residues (petroleum), catalytic reformer fractionator   |
| 64741–68–0 | Naphtha (petroleum), heavy catalytic reformed           |
| 64741–69–1 | Naphtha (petroleum), light hydrocracked                 |
| 64741–70–4 | Naphtha (petroleum), isomerization                      |
| 64741–73–7 | Distillates (petroleum), alkylate                       |
| 64741–74–8 | Naphtha (petroleum), light thermal cracked              |
| 64741–75–9 | Residues (petroleum), hydrocracked                      |
| 64741–76–0 | Distillates (petroleum), heavy hydrocracked             |
| 64741–77–1 | Distillates (petroleum), light hydrocracked             |
| 64741–78–2 | Naphtha (petroleum), heavy hydrocracked                 |
| 64741–79–3 | Coke (petroleum)  |

**Environmental Protection Agency**

**§ 710.46**

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.    | Product   |
|------------|---|
| 64741-80-6 | Residues (petroleum), thermal cracked                               |
| 64741-81-7 | Distillates (petroleum), heavy thermal cracked                      |
| 64741-82-8 | Distillates (petroleum), light thermal cracked                      |
| 64741-83-9 | Naphtha (petroleum), heavy thermal cracked                          |
| 64741-84-0 | Naphtha (petroleum), solvent-refined light                          |
| 64741-85-1 | Raffinates (petroleum), sorption process                            |
| 64741-86-2 | Distillates (petroleum), sweetened middle                           |
| 64741-87-3 | Naphtha (petroleum), sweetened                                      |
| 64741-88-4 | Distillates (petroleum), solvent-refined heavy paraffinic           |
| 64741-89-5 | Distillates (petroleum), solvent-refined light paraffinic           |
| 64741-90-8 | Gas oils (petroleum), solvent-refined                               |
| 64741-91-9 | Distillates (petroleum), solvent-refined middle                     |
| 64741-92-0 | Naphtha (petroleum), solvent-refined heavy                          |
| 64741-95-3 | Residual oils (petroleum), solvent deasphalted                      |
| 64741-96-4 | Distillates (petroleum), solvent-refined heavy naphthenic           |
| 64741-97-5 | Distillates (petroleum), solvent-refined light naphthenic           |
| 64741-98-6 | Extracts (petroleum), heavy naphtha solvent                         |
| 64741-99-7 | Extracts (petroleum), light naphtha solvent                         |
| 64742-01-4 | Residual oils (petroleum), solvent-refined                          |
| 64742-03-6 | Extracts (petroleum), light naphthenic distillate solvent           |
| 64742-04-7 | Extracts (petroleum), heavy paraffinic distillate solvent           |
| 64742-05-8 | Extracts (petroleum), light paraffinic distillate solvent           |
| 64742-06-9 | Extracts (petroleum), middle distillate solvent                     |
| 64742-07-0 | Raffinates (petroleum), residual oil decarbonization                |
| 64742-08-1 | Raffinates (petroleum), heavy naphthenic distillate decarbonization |
| 64742-09-2 | Raffinates (petroleum), heavy paraffinic distillate decarbonization |
| 64742-10-5 | Extracts (petroleum), residual oil solvent                          |
| 64742-11-6 | Extracts (petroleum), heavy naphthenic distillate solvent           |
| 64742-12-7 | Gas oils (petroleum), acid-treated                                  |
| 64742-13-8 | Distillates (petroleum), acid-treated middle                        |
| 64742-14-9 | Distillates (petroleum), acid-treated light                         |
| 64742-15-0 | Naphtha (petroleum), acid-treated                                   |
| 64742-16-1 | Petroleum resins  |
| 64742-18-3 | Distillates (petroleum), acid-treated heavy naphthenic              |
| 64742-19-4 | Distillates (petroleum), acid-treated light naphthenic              |
| 64742-20-7 | Distillates (petroleum), acid-treated heavy paraffinic              |
| 64742-21-8 | Distillates (petroleum), acid-treated light paraffinic              |
| 64742-22-9 | Naphtha (petroleum), chemically neutralized heavy                   |
| 64742-23-0 | Naphtha (petroleum), chemically neutralized light                   |
| 64742-24-1 | Sludges (petroleum), acid   |
| 64742-25-2 | Lubricating oils (petroleum), acid-treated spent                    |
| 64742-26-3 | Hydrocarbon waxes (petroleum), acid-treated                         |

| CAS No.    | Product  |
|------------|--|
| 64742-27-4 | Distillates (petroleum), chemically neutralized heavy paraffinic |
| 64742-28-5 | Distillates (petroleum), chemically neutralized light paraffinic |
| 64742-29-6 | Gas oils (petroleum), chemically neutralized                     |
| 64742-30-9 | Distillates (petroleum), chemically neutralized middle           |
| 64742-31-0 | Distillates (petroleum), chemically neutralized light            |
| 64742-32-1 | Lubricating oils (petroleum), chemically neutralized spent       |
| 64742-33-2 | Hydrocarbon waxes (petroleum), chemically neutralized            |
| 64742-34-3 | Distillates (petroleum), chemically neutralized heavy naphthenic |
| 64742-35-4 | Distillates (petroleum), chemically neutralized light naphthenic |
| 64742-36-5 | Distillates (petroleum), clay-treated heavy paraffinic           |
| 64742-37-6 | Distillates (petroleum), clay-treated light paraffinic           |
| 64742-38-7 | Distillates (petroleum), clay-treated middle                     |
| 64742-39-8 | Neutralizing agents (petroleum), spent sodium carbonate          |
| 64742-40-1 | Neutralizing agents (petroleum), spent sodium hydroxide          |
| 64742-41-2 | Residual oils (petroleum), clay-treated                          |
| 64742-42-3 | Hydrocarbon waxes (petroleum), clay-treated microcryst.          |
| 64742-43-4 | Paraffin waxes (petroleum), clay-treated                         |
| 64742-44-5 | Distillates (petroleum), clay-treated heavy naphthenic           |
| 64742-45-6 | Distillates (petroleum), clay-treated light naphthenic           |
| 64742-46-7 | Distillates (petroleum), hydrotreated middle                     |
| 64742-47-8 | Distillates (petroleum), hydrotreated light                      |
| 64742-48-9 | Naphtha (petroleum), hydrotreated heavy                          |
| 64742-49-0 | Naphtha (petroleum), hydrotreated light                          |
| 64742-50-3 | Lubricating oils (petroleum), clay-treated spent                 |
| 64742-51-4 | Paraffin waxes (petroleum), hydrotreated                         |
| 64742-52-5 | Distillates (petroleum), hydrotreated heavy naphthenic           |
| 64742-53-6 | Distillates (petroleum), hydrotreated light naphthenic           |
| 64742-54-7 | Distillates (petroleum), hydrotreated heavy paraffinic           |
| 64742-55-8 | Distillates (petroleum), hydrotreated light paraffinic           |
| 64742-56-9 | Distillates (petroleum), solvent-dewaxed light paraffinic        |
| 64742-57-0 | Residual oils (petroleum), hydrotreated                          |
| 64742-58-1 | Lubricating oils (petroleum), hydrotreated spent                 |
| 64742-59-2 | Gas oils (petroleum), hydrotreated vacuum                        |
| 64742-60-5 | Hydrocarbon waxes (petroleum), hydrotreated microcryst.          |
| 64742-61-6 | Slack wax (petroleum)  |
| 64742-62-7 | Residual oils (petroleum), solvent-dewaxed                       |
| 64742-63-8 | Distillates (petroleum), solvent-dewaxed heavy naphthenic        |
| 64742-64-9 | Distillates (petroleum), solvent-dewaxed light naphthenic        |
| 64742-65-0 | Distillates (petroleum), solvent-dewaxed heavy paraffinic        |
| 64742-67-2 | Foots oil (petroleum)  |

§ 710.46

40 CFR Ch. I (7–1–10 Edition)

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED “PETROLEUM PROCESS STREAMS” FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED “PETROLEUM PROCESS STREAMS” FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.    | Product   |
|------------|---|
| 64742–68–3 | Naphthenic oils (petroleum), catalytic dewaxed heavy                    |
| 64742–69–4 | Naphthenic oils (petroleum), catalytic dewaxed light                    |
| 64742–70–7 | Paraffin oils (petroleum), catalytic dewaxed heavy                      |
| 64742–71–8 | Paraffin oils (petroleum), catalytic dewaxed light                      |
| 64742–72–9 | Distillates (petroleum), catalytic dewaxed middle                       |
| 64742–73–0 | Naphtha (petroleum), hydrodesulfurized light                            |
| 64742–75–2 | Naphthenic oils (petroleum), complex dewaxed heavy                      |
| 64742–76–3 | Naphthenic oils (petroleum), complex dewaxed light                      |
| 64742–78–5 | Residues (petroleum), hydrodesulfurized atmospheric tower               |
| 64742–79–6 | Gas oils (petroleum), hydrodesulfurized                                 |
| 64742–80–9 | Distillates (petroleum), hydrodesulfurized middle                       |
| 64742–81–0 | Kerosine (petroleum), hydrodesulfurized                                 |
| 64742–82–1 | Naphtha (petroleum), hydrodesulfurized heavy                            |
| 64742–83–2 | Naphtha (petroleum), light steam-cracked                                |
| 64742–85–4 | Residues (petroleum), hydrodesulfurized vacuum                          |
| 64742–86–5 | Gas oils (petroleum), hydrodesulfurized heavy vacuum                    |
| 64742–87–6 | Gas oils (petroleum), hydrodesulfurized light vacuum                    |
| 64742–88–7 | Solvent naphtha (petroleum), medium aliph.                              |
| 64742–89–8 | Solvent naphtha (petroleum), light aliph.                               |
| 64742–90–1 | Residues (petroleum), steam-cracked                                     |
| 64742–91–2 | Distillates (petroleum), steam-cracked                                  |
| 64742–92–3 | Petroleum resins, oxidized  |
| 64742–93–4 | Asphalt, oxidized   |
| 64742–94–5 | Solvent naphtha (petroleum), heavy arom.                                |
| 64742–95–6 | Solvent naphtha (petroleum), light arom.                                |
| 64742–96–7 | Solvent naphtha (petroleum), heavy aliph.                               |
| 64742–97–8 | Distillates (petroleum), oxidized heavy                                 |
| 64742–98–9 | Distillates (petroleum), oxidized light                                 |
| 64742–99–0 | Residual oils (petroleum), oxidized                                     |
| 64743–00–6 | Hydrocarbon waxes (petroleum), oxidized                                 |
| 64743–01–7 | Petrolatum (petroleum), oxidized  |
| 64743–02–8 | Alkenes, C>10 alpha-  |
| 64743–03–9 | Phenols (petroleum)   |
| 64743–04–0 | Coke (petroleum), recovery  |
| 64743–05–1 | Coke (petroleum), calcined  |
| 64743–06–2 | Extracts (petroleum), gas oil solvent                                   |
| 64743–07–3 | Sludges (petroleum), chemically neutralized                             |
| 64754–89–8 | Naphthenic acids (petroleum), crude                                     |
| 64771–71–7 | Paraffins (petroleum), normal C-10                                      |
| 64771–72–8 | Paraffins (petroleum), normal C5-20                                     |
| 67254–74–4 | Naphthenic oils   |
| 67674–12–8 | Residual oils (petroleum), oxidized, compounds with triethanolamine     |
| 67674–13–9 | Petrolatum (petroleum), oxidized, partially deacidified                 |
| 67674–15–1 | Petrolatum (petroleum), oxidized, Me ester                              |
| 67674–16–2 | Hydrocarbon waxes (petroleum), oxidized, partially deacidified          |
| 67674–17–3 | Distillates (petroleum), oxidized light, compounds with triethanolamine |
| 67674–18–4 | Distillates (petroleum), oxidized light, Bu esters                      |
| 67891–79–6 | Distillates (petroleum), heavy arom.                                    |

| CAS No.    | Product  |
|------------|--|
| 67891–80–9 | Distillates (petroleum), light arom.   |
| 67891–81–0 | Distillates (petroleum), oxidized light, potassium salts   |
| 67891–82–1 | Hydrocarbon waxes (petroleum), oxidized, compounds with ethanolamine                                     |
| 67891–83–2 | Hydrocarbon waxes (petroleum), oxidized, compounds with isopropanolamine                                 |
| 67891–85–4 | Hydrocarbon waxes (petroleum), oxidized, compounds with triisopropanolamine                              |
| 67891–86–5 | Hydrocarbon waxes (petroleum), oxidized, compds. with diisopropanolamine                                 |
| 68131–05–5 | Hydrocarbon oils, process blends   |
| 68131–49–7 | Aromatic hydrocarbons, C6-10, acid-treated, neutralized  |
| 68131–75–9 | Gases (petroleum), C3-4  |
| 68153–22–0 | Paraffin waxes and Hydrocarbon waxes, oxidized   |
| 68187–57–5 | Pitch, coal tar-petroleum  |
| 68187–58–6 | Pitch, petroleum, arom.  |
| 68187–60–0 | Hydrocarbons, C4, ethane-propane-cracked   |
| 68307–98–2 | Tail gas (petroleum), catalytic cracked distillate and catalytic cracked naphtha fractionation absorber  |
| 68307–99–3 | Tail gas (petroleum), catalytic polymn. naphtha fractionation stabilizer                                 |
| 68308–00–9 | Tail gas (petroleum), catalytic reformed naphtha fractionation stabilizer, hydrogen sulfide-free         |
| 68308–01–0 | Tail gas (petroleum), cracked distillate hydrotreater stripper   |
| 68308–02–1 | Tail gas (petroleum), distn., hydrogen sulfide-free  |
| 68308–03–2 | Tail gas (petroleum), gas oil catalytic cracking absorber  |
| 68308–04–3 | Tail gas (petroleum), gas recovery plant   |
| 68308–05–4 | Tail gas (petroleum), gas recovery plant deethanizer   |
| 68308–06–5 | Tail gas (petroleum), hydrodesulfurized distillate and hydrodesulfurized naphtha fractionator, acid-free |
| 68308–07–6 | Tail gas (petroleum), hydrodesulfurized vacuum gas oil stripper, hydrogen sulfide-free                   |
| 68308–08–7 | Tail gas (petroleum), isomerized naphtha fractionation stabilizer  |
| 68308–09–8 | Tail gas (petroleum), light straight-run naphtha stabilizer, hydrogen sulfide-free                       |
| 68308–10–1 | Tail gas (petroleum), straight-run distillate hydrodesulfurizer, hydrogen sulfide-free                   |
| 68308–11–2 | Tail gas (petroleum), propane-propylene alkylation feed prep deethanizer                                 |
| 68308–12–3 | Tail gas (petroleum), vacuum gas oil hydrodesulfurizer, hydrogen sulfide-free                            |
| 68308–27–0 | Fuel gases, refinery   |
| 68333–22–2 | Residues (petroleum), atmospheric  |
| 68333–23–3 | Naphtha (petroleum), heavy coker   |
| 68333–24–4 | Hydrocarbon waxes (petroleum), oxidized, compds. with triethanolamine                                    |
| 68333–25–5 | Distillates (petroleum), hydrodesulfurized light catalytic cracked                                       |
| 68333–26–6 | Clarified oils (petroleum), hydrodesulfurized catalytic cracked  |
| 68333–27–7 | Distillates (petroleum), hydrodesulfurized intermediate catalytic cracked                                |
| 68333–28–8 | Distillates (petroleum), hydrodesulfurized heavy catalytic cracked                                       |

**Environmental Protection Agency**

**§ 710.46**

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.    | Product   |
|------------|---|
| 68333-29-9 | Residues (petroleum), light naphtha solvent extracts  |
| 68333-30-2 | Distillates (petroleum), oxidized heavy thermal cracked   |
| 68333-81-3 | Alkanes, C4-12  |
| 68333-88-0 | Aromatic hydrocarbons, C9-17  |
| 68334-30-5 | Fuels, diesel   |
| 68409-99-4 | Gases (petroleum), catalytic cracked overheads  |
| 68410-00-4 | Distillates (petroleum), crude oil  |
| 68410-05-9 | Distillates (petroleum), straight-run light   |
| 68410-12-8 | Distillates (petroleum), steam-cracked, C5-10 fraction, high-temp. stripping products with light steam-cracked petroleum naphtha C5 fraction polymers |
| 68410-71-9 | Raffinates (petroleum), catalytic reformer ethylene glycol-water countercurrent exts.   |
| 68410-96-8 | Distillates (petroleum), hydrotreated middle, intermediate boiling  |
| 68410-97-9 | Distillates (petroleum), light distillate hydrotreating process, low-boiling  |
| 68410-98-0 | Distillates (petroleum), hydrotreated heavy naphtha, deisohexanizer overheads   |
| 68411-00-7 | Alkenes, C>8  |
| 68425-29-6 | Distillates (petroleum), naphtha-raffinate pyrolyzate-derived, gasoline-blending  |
| 68425-33-2 | Petrolatum (petroleum), oxidized, barium salt   |
| 68425-34-3 | Petrolatum (petroleum), oxidized, calcium salt  |
| 68425-35-4 | Raffinates (petroleum), reformer, Lurgi unit-sepd.  |
| 68425-39-8 | Alkenes, C>10 .alpha.-, oxidized  |
| 68441-09-8 | Hydrocarbon waxes (petroleum), clay-treated microcryst., contg. polyethylene, oxidized  |
| 68459-78-9 | Alkenes, C18-24 .alpha.-, dimers  |
| 68475-57-0 | Alkanes, C1-2   |
| 68475-58-1 | Alkanes, C2-3   |
| 68475-59-2 | Alkanes, C3-4   |
| 68475-60-5 | Alkanes, C4-5   |
| 68475-61-6 | Alkenes, C5, naphtha-raffinate pyrolyzate-derived   |
| 68475-70-7 | Aromatic hydrocarbons, C6-8, naphtha-raffinate pyrolyzate-derived   |
| 68475-79-6 | Distillates (petroleum), catalytic reformed depentanizer  |
| 68475-80-9 | Distillates (petroleum), light steam-cracked naphtha  |
| 68476-26-6 | Fuel gases  |
| 68476-27-7 | Fuel gases, amine system residues   |
| 68476-28-8 | Fuel gases, C6-8 catalytic reformer   |
| 68476-29-9 | Fuel gases, crude oil distillates   |
| 68476-30-2 | Fuel oil, no. 2   |
| 68476-31-3 | Fuel oil, no. 4   |
| 68476-32-4 | Fuel oil, residues-straight-run gas oils, high-sulfur   |
| 68476-33-5 | Fuel oil, residual  |
| 68476-34-6 | Fuels, diesel, no. 2  |
| 68476-39-1 | Hydrocarbons, aliph.-arom.-C4-5-olefinic  |
| 68476-40-4 | Hydrocarbons, C3-4  |
| 68476-42-6 | Hydrocarbons, C4-5  |
| 68476-43-7 | Hydrocarbons, C4-6, C5-rich   |
| 68476-44-8 | Hydrocarbons, C>3   |
| 68476-45-9 | Hydrocarbons, C5-10 arom. conc., ethylene-manuf.-by-product   |
| 68476-46-0 | Hydrocarbons, C3-11, catalytic cracker distillates  |

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.    | Product  |
|------------|--|
| 68476-47-1 | Hydrocarbons, C2-6, C6-8 catalytic reformer  |
| 68476-49-3 | Hydrocarbons, C2-4, C3-rich  |
| 68476-50-6 | Hydrocarbons, C≥5, C5-6-rich   |
| 68476-52-8 | Hydrocarbons, C4, ethylene-manuf.-by-product   |
| 68476-53-9 | Hydrocarbons, C≥20, petroleum wastes   |
| 68476-54-0 | Hydrocarbons, C3-5, polymn. unit feed  |
| 68476-55-1 | Hydrocarbons, C5-rich  |
| 68476-56-2 | Hydrocarbons, cyclic C5 and C6   |
| 68476-77-7 | Lubricating oils, refined used   |
| 68476-81-3 | Paraffin waxes and Hydrocarbon waxes, oxidized, calcium salts  |
| 68476-84-6 | Petroleum products, gases, inorg.  |
| 68476-85-7 | Petroleum gases, liquefied   |
| 68476-86-8 | Petroleum gases, liquefied, sweetened  |
| 68477-25-8 | Waste gases, vent gas, C1-6  |
| 68477-26-9 | Wastes, petroleum  |
| 68477-29-2 | Distillates (petroleum), catalytic reformer fractionator residue, high-boiling                                       |
| 68477-30-5 | Distillates (petroleum), catalytic reformer fractionator residue, intermediate-boiling                               |
| 68477-31-6 | Distillates (petroleum), catalytic reformer fractionator residue, low-boiling  |
| 68477-33-8 | Gases (petroleum), C3-4, isobutane-rich  |
| 68477-34-9 | Distillates (petroleum), C3-5, 2-methyl-2-butene-rich  |
| 68477-35-0 | Distillates (petroleum), C3-6, piperylene-rich   |
| 68477-36-1 | Distillates (petroleum), cracked steam-cracked, C5-18 fraction   |
| 68477-38-3 | Distillates (petroleum), cracked steam-cracked petroleum distillates   |
| 68477-39-4 | Distillates (petroleum), cracked stripped steam-cracked petroleum distillates, C8-10 fraction                        |
| 68477-40-7 | Distillates (petroleum), cracked stripped steam-cracked petroleum distillates, C10-12 fraction                       |
| 68477-41-8 | Gases (petroleum), extractive, C3-5, butadiene-butene-rich   |
| 68477-42-9 | Gases (petroleum), extractive, C3-5, butene-isobutylene-rich   |
| 68477-44-1 | Distillates (petroleum), heavy naphthenic, mixed with steam-cracked petroleum distillates C5-12 fraction             |
| 68477-47-4 | Distillates (petroleum), mixed heavy olefin vacuum, heart-cut  |
| 68477-48-5 | Distillates (petroleum), mixed heavy olefin vacuum, low-boiling  |
| 68477-53-2 | Distillates (petroleum), steam-cracked, C5-12 fraction   |
| 68477-54-3 | Distillates (petroleum), steam-cracked, C8-12 fraction   |
| 68477-55-4 | Distillates (petroleum), steam-cracked, C5-10 fraction, mixed with light steam-cracked petroleum naphtha C5 fraction |
| 68477-58-7 | Distillates (petroleum), steam-cracked petroleum distillates, C5-18 fraction   |
| 68477-59-8 | Distillates (petroleum), steam-cracked petroleum distillates cyclopentadiene conc.                                   |
| 68477-60-1 | Extracts (petroleum), cold-acid  |
| 68477-61-2 | Extracts (petroleum), cold-acid, C4-6  |
| 68477-62-3 | Extracts (petroleum), cold-acid, C3-5, butene-rich   |
| 68477-63-4 | Extracts (petroleum), reformer recycle   |
| 68477-64-5 | Gases (petroleum), acetylene manuf. off  |
| 68477-65-6 | Gases (petroleum), amine system feed   |



§ 710.46

40 CFR Ch. I (7–1–10 Edition)

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED “PETROLEUM PROCESS STREAMS” FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED “PETROLEUM PROCESS STREAMS” FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.    | Product   |
|------------|---|
| 68477–66–7 | Gases (petroleum), benzene unit hydrodesulfurizer off                                 |
| 68477–67–8 | Gases (petroleum), benzene unit recycle, hydrogen-rich                                |
| 68477–68–9 | Gases (petroleum), blend oil, hydrogen-nitrogen-rich                                  |
| 68477–69–0 | Gases (petroleum), butane splitter overheads  |
| 68477–70–3 | Gases (petroleum), C2-3   |
| 68477–71–4 | Gases (petroleum), catalytic-cracked gas oil depropanizer bottoms, C4-rich acid-free  |
| 68477–72–5 | Gases (petroleum), catalytic-cracked naphtha debutanizer bottoms, C3-5-rich           |
| 68477–73–6 | Gases (petroleum), catalytic cracked naphtha depropanizer overhead, C3-rich acid-free |
| 68477–74–7 | Gases (petroleum), catalytic cracker  |
| 68477–75–8 | Gases (petroleum), catalytic cracker, C1-5-rich                                       |
| 68477–76–9 | Gases (petroleum), catalytic polymd. naphtha stabilizer overhead, C2-4-rich           |
| 68477–77–0 | Gases (petroleum), catalytic reformed naphtha stripper overheads                      |
| 68477–79–2 | Gases (petroleum), catalytic reformer, C1-4-rich                                      |
| 68477–80–5 | Gases (petroleum), C6-8 catalytic reformer recycle                                    |
| 68477–81–6 | Gases (petroleum), C6-8 catalytic reformer  |
| 68477–82–7 | Gases (petroleum), C6-8 catalytic reformer recycle, hydrogen-rich                     |
| 68477–83–8 | Gases (petroleum), C3-5 olefinic-paraffinic alkylation feed                           |
| 68477–84–9 | Gases (petroleum), C2-return stream   |
| 68477–85–0 | Gases (petroleum), C4-rich  |
| 68477–86–1 | Gases (petroleum), deethanizer overheads  |
| 68477–87–2 | Gases (petroleum), deisobutanizer tower overheads                                     |
| 68477–88–3 | Gases (petroleum), deethanizer overheads, C3-rich                                     |
| 68477–89–4 | Distillates (petroleum), depentanizer overheads                                       |
| 68477–90–7 | Gases (petroleum), depropanizer dry, propene-rich                                     |
| 68477–91–8 | Gases (petroleum), depropanizer overheads   |
| 68477–92–9 | Gases (petroleum), dry sour, gas-concn.-unit-off                                      |
| 68477–93–0 | Gases (petroleum), gas concn. reabsorber distn.                                       |
| 68477–94–1 | Gases (petroleum), gas recovery plant depropanizer overheads                          |
| 68477–95–2 | Gases (petroleum), Girbatol unit feed   |
| 68477–96–3 | Gases (petroleum), hydrogen absorber off  |
| 68477–97–4 | Gases (petroleum), hydrogen-rich  |
| 68477–98–5 | Gases (petroleum), hydrotreater blend oil recycle, hydrogen-nitrogen rich             |
| 68477–99–6 | Gases (petroleum), isomerized naphtha fractionator, C4-rich, hydrogen sulfide-free    |
| 68478–00–2 | Gases (petroleum), recycle, hydrogen-rich   |
| 68478–01–3 | Gases (petroleum), reformer make-up, hydrogen-rich                                    |
| 68478–02–4 | Gases (petroleum), reforming hydrotreater   |
| 68478–03–5 | Gases (petroleum), reforming hydrotreater, hydrogen-methane-rich                      |
| 68478–04–6 | Gases (petroleum), reforming hydrotreater make-up, hydrogen-rich                      |

| CAS No.    | Product  |
|------------|--|
| 68478–05–7 | Gases (petroleum), thermal cracking distn.   |
| 68478–08–0 | Naphtha (petroleum), light steam-cracked, C5-fraction, oligomer conc.                                    |
| 68478–10–4 | Naphtha (petroleum), light steam-cracked, debenzenized, C8-16-cycloalkadiene conc.                       |
| 68478–12–6 | Residues (petroleum), butane splitter bottoms  |
| 68478–13–7 | Residues (petroleum), catalytic reformer fractionator residue distn.                                     |
| 68478–15–9 | Residues (petroleum), C6-8 catalytic reformer  |
| 68478–16–0 | Residual oils (petroleum), deisobutanizer tower  |
| 68478–17–1 | Residues (petroleum), heavy coker gas oil and vacuum gas oil   |
| 68478–18–2 | Residues (petroleum), heavy olefin vacuum  |
| 68478–19–3 | Residual oils (petroleum), propene purifn. splitter  |
| 68478–20–6 | Residues (petroleum), steam-cracked petroleum distillates cyclopentadiene conc., C4-cyclopentadiene-free |
| 68478–22–8 | Tail gas (petroleum), catalytic cracked naphtha stabilization absorber                                   |
| 68478–24–0 | Tail gas (petroleum), catalytic cracker, catalytic reformer and hydrodesulfurizer combined fractionator  |
| 68478–25–1 | Tail gas (petroleum), catalytic cracker re-fractionation absorber  |
| 68478–26–2 | Tail gas (petroleum), catalytic reformed naphtha fractionation stabilizer                                |
| 68478–27–3 | Tail gas (petroleum), catalytic reformed naphtha separator   |
| 68478–28–4 | Tail gas (petroleum), catalytic reformed naphtha stabilizer  |
| 68478–29–5 | Tail gas (petroleum), cracked distillate hydrotreater separator  |
| 68478–30–8 | Tail gas (petroleum), hydrodesulfurized straight-run naphtha separator                                   |
| 68478–31–9 | Tail gas (petroleum), isomerized naphtha fractionates, hydrogen sulfide-free                             |
| 68478–32–0 | Tail gas (petroleum), saturate gas plant mixed stream, C4-rich   |
| 68478–33–1 | Tail gas (petroleum), saturate gas recovery plant, C1-2-rich   |
| 68478–34–2 | Tail gas (petroleum), vacuum residues thermal cracker  |
| 68512–61–8 | Residues (petroleum), heavy coker and light vacuum   |
| 68512–62–9 | Residues (petroleum), light vacuum   |
| 68512–78–7 | Solvent naphtha (petroleum), light arom., hydrotreated   |
| 68512–91–4 | Hydrocarbons, C3-4-rich, petroleum distillates   |
| 68513–02–0 | Naphtha (petroleum), full-range coker  |
| 68513–03–1 | Naphtha (petroleum), light catalytic reformed, arom.-free  |
| 68513–11–1 | Fuel gases, hydrotreater fractionation, scrubbed   |
| 68513–12–2 | Fuel gases, saturate gas unit fractionator-absorber overheads  |
| 68513–13–3 | Fuel gases, thermal cracked catalytic cracking residue   |
| 68513–14–4 | Gases (petroleum), catalytic reformed straight-run naphtha stabilizer overheads                          |
| 68513–15–5 | Gases (petroleum), full-range straight-run naphtha dehexanizer off                                       |

**Environmental Protection Agency**

**§ 710.46**

**CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued**

| CAS No.    | Product  |
|------------|--|
| 68513-16-6 | Gases (petroleum), hydrocracking depropanizer off, hydrocarbon-rich        |
| 68513-17-7 | Gases (petroleum), light straight-run naphtha stabilizer off               |
| 68513-18-8 | Gases (petroleum), reformer effluent high-pressure flash drum off          |
| 68513-19-9 | Gases (petroleum), reformer effluent low-pressure flash drum off           |
| 68513-62-2 | Disulfides, C5-12-alkyl  |
| 68513-63-3 | Distillates (petroleum), catalytic reformed straight-run naphtha overheads |
| 68513-65-5 | Butane, branched and linear  |
| 68513-66-6 | Residues (petroleum), alkylation splitter, C4-rich                         |
| 68513-67-7 | Residues (petroleum), cyclooctadiene bottoms                               |
| 68513-68-8 | Residues (petroleum), deethanizer tower                                    |
| 68513-69-9 | Residues (petroleum), steam-cracked light                                  |
| 68513-74-6 | Waste gases, ethylene oxide absorber-reactor                               |
| 68514-15-8 | Gasoline, vapor-recovery   |
| 68514-29-4 | Hydrocarbons, amylene feed debutanizer overheads nonextractable raffinate  |
| 68514-31-8 | Hydrocarbons, C1-4   |
| 68514-32-9 | Hydrocarbons, C10 and C12, olefin-rich                                     |
| 68514-33-0 | Hydrocarbons, C12 and C14, olefin-rich                                     |
| 68514-34-1 | Hydrocarbons, C9-14, ethylene-manuf.-by-product                            |
| 68514-35-2 | Hydrocarbons, C14-30, olefin-rich  |
| 68514-36-3 | Hydrocarbons, C1-4, sweetened  |
| 68514-37-4 | Hydrocarbons, C4-5-unsatd.   |
| 68514-38-5 | Hydrocarbons, C4-10-unsatd.  |
| 68514-39-6 | Naphtha (petroleum), light steam-cracked, isoprene-rich                    |
| 68514-79-4 | Petroleum products, hydrofiner-powerformer reformates                      |
| 68515-25-3 | Benzene, C1-9-alkyl derivs.  |
| 68515-26-4 | Benzene, di-C12-14-alkyl derivs.   |
| 68515-27-5 | Benzene, di-C10-14-alkyl derivs., fractionation overheads, heavy ends      |
| 68515-28-6 | Benzene, di-C10-14-alkyl derivs., fractionation overheads, light ends      |
| 68515-29-7 | Benzene, di-C10-14-alkyl derivs., fractionation overheads, middle cut      |
| 68515-30-0 | Benzene, mono-C20-48-alkyl derivs.   |
| 68515-32-2 | Benzene, mono-C12-14-alkyl derivs., fractionation bottoms                  |
| 68515-33-3 | Benzene, mono-C10-12-alkyl derivs., fractionation bottoms, heavy ends      |
| 68515-34-4 | Benzene, mono-C12-14-alkyl derivs., fractionation bottoms, heavy ends      |
| 68515-35-5 | Benzene, mono-C10-12-alkyl derivs., fractionation bottoms, light ends      |
| 68515-36-6 | Benzene, mono-C12-14-alkyl derivs., fractionation bottoms, light ends      |
| 68516-20-1 | Naphtha (petroleum), steam-cracked middle arom.                            |
| 68526-52-3 | Alkenes, C6  |
| 68526-53-4 | Alkenes, C6-8, C7-rich   |
| 68526-54-5 | Alkenes, C7-9, C8-rich   |
| 68526-55-6 | Alkenes, C8-10, C9-rich  |
| 68526-56-7 | Alkenes, C9-11, C10-rich   |
| 68526-57-8 | Alkenes, C10-12, C11-rich  |
| 68526-58-9 | Alkenes, C11-13, C12-rich  |
| 68526-77-2 | Aromatic hydrocarbons, ethane cracking scrubber effluent and flare drum    |
| 68526-99-8 | Alkenes, C6-9 .alpha.-   |
| 68527-00-4 | Alkenes, C8-9 .alpha.-   |

**CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued**

| CAS No.    | Product   |
|------------|---|
| 68527-11-7 | Alkenes, C5   |
| 68527-13-9 | Gases (petroleum), acid, ethanalamine scrubber  |
| 68527-14-0 | Gases (petroleum), methane-rich off   |
| 68527-15-1 | Gases (petroleum), oil refinery gas distn. off  |
| 68527-16-2 | Hydrocarbons, C1-3  |
| 68527-18-4 | Gas oils (petroleum), steam-cracked   |
| 68527-19-5 | Hydrocarbons, C1-4, debutanizer fraction  |
| 68527-21-9 | Naphtha (petroleum), clay-treated full-range straight-run                                     |
| 68527-22-0 | Naphtha (petroleum), clay-treated light straight-run  |
| 68527-23-1 | Naphtha (petroleum), light steam-cracked arom.  |
| 68527-26-4 | Naphtha (petroleum), light steam-cracked, debenzenized  |
| 68527-27-5 | Naphtha (petroleum), full-range alkylate, butane-contg.                                       |
| 68553-00-4 | Fuel oil, no. 6   |
| 68553-14-0 | Hydrocarbons, C8-11   |
| 68602-79-9 | Distillates (petroleum), benzene unit hydrotreater dipentanizer overheads                     |
| 68602-81-3 | Distillates, hydrocarbon resin prodn. higher boiling  |
| 68602-82-4 | Gases (petroleum), benzene unit hydrotreater depentanizer overheads                           |
| 68602-83-5 | Gases (petroleum), C1-5, wet  |
| 68602-84-6 | Gases (petroleum), secondary absorber off, fluidized catalytic cracker overheads fractionater |
| 68602-96-0 | Distillates (petroleum), oxidized light, strong acid components, compds. with diethanolamine  |
| 68602-97-1 | Distillates (petroleum), oxidized light, strong acid components, sodium salts                 |
| 68602-98-2 | Distillates (petroleum), oxidized light, strong acid components                               |
| 68602-99-3 | Distillates (petroleum), oxidized light, strong acid-free                                     |
| 68603-00-9 | Distillates (petroleum), thermal cracked naphtha and gas oil                                  |
| 68603-01-0 | Distillates (petroleum), thermal cracked naphtha and gas oil, C5-dimer-contg.                 |
| 68603-02-1 | Distillates (petroleum), thermal cracked naphtha and gas oil, dimerized                       |
| 68603-03-2 | Distillates (petroleum), thermal cracked naphtha and gas oil, extractive                      |
| 68603-08-7 | Naphtha (petroleum), arom.-contg.   |
| 68603-09-8 | Hydrocarbon waxes (petroleum), oxidized, calcium salts  |
| 68603-10-1 | Hydrocarbon waxes (petroleum), oxidized, Me esters, barium salts                              |
| 68603-11-2 | Hydrocarbon waxes (petroleum), oxidized, Me esters, calcium salts                             |
| 68603-12-3 | Hydrocarbon waxes (petroleum), oxidized, Me esters, sodium salts                              |
| 68603-13-4 | Petrolatum (petroleum), oxidized, ester with sorbitol   |
| 68603-14-5 | Residual oils (petroleum), oxidized, calcium salts  |
| 68603-31-6 | Alkenes, C10, tert-amylene concentrator by-product  |
| 68603-32-7 | Alkenes, C15-20 .alpha.-, isomerized  |
| 68606-09-7 | Fuel gases, expander off  |
| 68606-10-0 | Gasoline, pyrolysis, debutanizer bottoms  |
| 68606-11-1 | Gasoline, straight-run, topping-plant   |

§ 710.46

40 CFR Ch. I (7–1–10 Edition)

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED “PETROLEUM PROCESS STREAMS” FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.    | Product   |
|------------|---|
| 68606–24–6 | Hydrocarbons, C4, butene concentrator by-product                                      |
| 68606–25–7 | Hydrocarbons, C2-4  |
| 68606–26–8 | Hydrocarbons, C3  |
| 68606–27–9 | Gases (petroleum), alkylation feed  |
| 68606–28–0 | Hydrocarbons, C5 and C10-aliph. and C6-8-arom.  |
| 68606–31–5 | Hydrocarbons, C3-5, butadiene purifn. by-product                                      |
| 68606–34–8 | Gases (petroleum), depropanizer bottoms fractionation off                             |
| 68606–36–0 | Hydrocarbons, C5-unsatd. rich, isoprene purifn. by-product                            |
| 68607–11–4 | Petroleum products, refinery gases  |
| 68607–30–7 | Residues (petroleum), topping plant, low-sulfur                                       |
| 68608–56–0 | Waste gases, from carbon black manuf.   |
| 68647–60–9 | Hydrocarbons, C>4   |
| 68647–61–0 | Hydrocarbons, C4-5, tert-amylene concentrator by-product                              |
| 68647–62–1 | Hydrocarbons, C4-5, butene concentrator by-product, sour                              |
| 68650–36–2 | Aromatic hydrocarbons, C8, o-xylene-lean  |
| 68650–37–3 | Paraffin waxes (petroleum), oxidized, sodium salts                                    |
| 68782–97–8 | Distillates (petroleum), hydrofined lubricating-oil                                   |
| 68782–98–9 | Extracts (petroleum), clarified oil solvent, condensed-ring-arom.-contg.              |
| 68782–99–0 | Extracts (petroleum), heavy clarified oil solvent, condensed-ring-arom.-contg.        |
| 68783–00–6 | Extracts (petroleum), heavy naphthenic distillate solvent, arom. conc.                |
| 68783–01–7 | Extracts (petroleum), heavy naphthenic distillate solvent, paraffinic conc.           |
| 68783–02–8 | Extracts (petroleum), intermediate clarified oil solvent, condensed-ring-arom.-contg. |
| 68783–04–0 | Extracts (petroleum), solvent-refined heavy paraffinic distillate solvent             |
| 68783–05–1 | Gases (petroleum), ammonia-hydrogen sulfide, water-satd.                              |
| 68783–06–2 | Gases (petroleum), hydrocracking low-pressure separator                               |
| 68783–07–3 | Gases (petroleum), refinery blend   |
| 68783–08–4 | Gas oils (petroleum), heavy atmospheric   |
| 68783–09–5 | Naphtha (petroleum), catalytic cracked light distd.                                   |
| 68783–12–0 | Naphtha (petroleum), unsweetened  |
| 68783–13–1 | Residues (petroleum), coker scrubber, condensed-ring-arom.-contg.                     |
| 68783–15–3 | Alkenes, C6-7 .alpha.-  |
| 68783–61–9 | Fuel gases, refinery, sweetened   |
| 68783–62–0 | Fuel gases, refinery, unsweetened   |
| 68783–64–2 | Gases (petroleum), catalytic cracking   |
| 68783–65–3 | Gases (petroleum), C2-4, sweetened  |
| 68783–66–4 | Naphtha (petroleum), light, sweetened   |
| 68814–47–1 | Waste gases, refinery vent  |
| 68814–67–5 | Gases (petroleum), refinery   |
| 68814–87–9 | Distillates (petroleum), full-range straight-run middle                               |
| 68814–89–1 | Extracts (petroleum), heavy paraffinic distillates, solvent-deasphalted               |
| 68814–90–4 | Gases (petroleum), platformer products separator off                                  |
| 68814–91–5 | Alkenes, C5-9 .alpha.-  |
| 68855–57–2 | Alkenes, C6-12 .alpha.-   |
| 68855–58–3 | Alkenes, C10-16 .alpha.-  |
| 68855–59–4 | Alkenes, C14-18 .alpha.-  |

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED “PETROLEUM PROCESS STREAMS” FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.    | Product   |
|------------|---|
| 68855–60–7 | Alkenes, C14-20 .alpha.-  |
| 68911–58–0 | Gases (petroleum), hydrotreated sour kerosine depentanizer stabilizer off               |
| 68911–59–1 | Gases (petroleum), hydrotreated sour kerosine flash drum                                |
| 68915–96–8 | Distillates (petroleum), heavy straight-run   |
| 68915–97–9 | Gas oils (petroleum), straight-run, high-boiling  |
| 68918–69–4 | Petrolatum (petroleum), oxidized, zinc salt   |
| 68918–73–0 | Residues (petroleum), clay-treating filter wash   |
| 68918–93–4 | Paraffin waxes and Hydrocarbon waxes, oxidized, alkali metal salts                      |
| 68918–98–9 | Fuel gases, refinery, hydrogen sulfide-free   |
| 68918–99–0 | Gases (petroleum), crude oil fractionation off  |
| 68919–00–6 | Gases (petroleum), dehexanizer off  |
| 68919–01–7 | Gases (petroleum), distillate unfiner desulfurization stripper off                      |
| 68919–02–8 | Gases (petroleum), fluidized catalytic cracker fractionation off                        |
| 68919–03–9 | Gases (petroleum), fluidized catalytic cracker scrubbing secondary absorber off         |
| 68919–04–0 | Gases (petroleum), heavy distillate hydrotreater desulfurization stripper off           |
| 68919–05–1 | Gases (petroleum), light straight run gasoline fractionation stabilizer off             |
| 68919–06–2 | Gases (petroleum), naphtha unfiner desulfurization stripper off                         |
| 68919–07–3 | Gases (petroleum), platformer stabilizer off, light ends fractionation                  |
| 68919–08–4 | Gases (petroleum), preflash tower off, crude distr.                                     |
| 68919–09–5 | Gases (petroleum), straight-run naphtha catalytic reforming off                         |
| 68919–10–8 | Gases (petroleum), straight-run stabilizer off  |
| 68919–11–9 | Gases (petroleum), tar stripper off   |
| 68919–12–0 | Gases (petroleum), unfiner stripper off   |
| 68919–15–3 | Hydrocarbons, C6-12, benzene-recovery   |
| 68919–16–4 | Hydrocarbons, catalytic alkylation, by-products, C3-6                                   |
| 68919–17–5 | Hydrocarbons, C12-20, catalytic alkylation by-products                                  |
| 68919–19–7 | Gases (petroleum), fluidized catalytic cracker splitter residues                        |
| 68919–20–0 | Gases (petroleum), fluidized catalytic cracker splitter overheads                       |
| 68919–37–9 | Naphtha (petroleum), full-range reformed  |
| 68920–06–9 | Hydrocarbons, C7-9  |
| 68920–07–0 | Hydrocarbons, C<10-linear   |
| 68920–64–9 | Disulfides, di-C1-2-alkyl   |
| 68921–07–3 | Distillates (petroleum), hydrotreated light catalytic cracked                           |
| 68921–08–4 | Distillates (petroleum), light straight-run gasoline fractionation stabilizer overheads |
| 68921–09–5 | Distillates (petroleum), naphtha unfiner stripper                                       |
| 68921–67–5 | Hydrocarbons, ethylene-manuf.-by-product distr. residues                                |
| 68952–76–1 | Gases (petroleum), catalytic cracked naphtha debutanizer                                |
| 68952–77–2 | Tail gas (petroleum), catalytic cracked distillate and naphtha stabilizer               |

## Environmental Protection Agency

## § 710.46

### CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.    | Product   |
|------------|---|
| 68952-78-3 | Tail gas (petroleum), catalytic hydrodesulfurized distillate fractionation stabilizer, hydrogen sulfide-free        |
| 68952-79-4 | Tail gas (petroleum), catalytic hydrodesulfurized naphtha separator   |
| 68952-80-7 | Tail gas (petroleum), straight-run naphtha hydrodesulfurizer  |
| 68952-81-8 | Tail gas (petroleum), thermal-cracked distillate, gas oil and naphtha absorber                                      |
| 68952-82-9 | Tail gas (petroleum), thermal cracked hydrocarbon fractionation stabilizer, petroleum coking                        |
| 68953-80-0 | Benzene, mixed with toluene, dealkylation product   |
| 68955-27-1 | Distillates (petroleum), petroleum residues vacuum  |
| 68955-28-2 | Gases (petroleum), light steam-cracked, butadiene conc.   |
| 68955-31-7 | Gases (petroleum), butadiene process, inorg.  |
| 68955-32-8 | Natural gas, substitute, steam-reformed desulfurized naphtha  |
| 68955-33-9 | Gases (petroleum), sponge absorber off, fluidized catalytic cracker and gas oil desulfurizer overhead fractionation |
| 68955-34-0 | Gases (petroleum), straight-run naphtha catalytic reformer stabilizer overhead                                      |
| 68955-35-1 | Naphtha (petroleum), catalytic reformed   |
| 68955-36-2 | Residues (petroleum), steam-cracked, resinous   |
| 68955-76-0 | Aromatic hydrocarbons, C9-16, biphenyl deriv.-rich  |
| 68955-96-4 | Disulfides, dialkyl and di-Ph, naphtha sweetening   |
| 68956-47-8 | Fuel oil, isoprene reject absorption  |
| 68956-48-9 | Fuel oil, residual, wastewater skimmings  |
| 68956-52-5 | Hydrocarbons, C4-8  |
| 68956-54-7 | Hydrocarbons, C4-unsatd.  |
| 68956-55-8 | Hydrocarbons, C5-unsatd.  |
| 68956-70-7 | Petroleum products, C5-12, reclaimed, wastewater treatment  |
| 68988-79-4 | Benzene, C10-12-alkyl derivs., distn. residues  |
| 68988-99-8 | Phenols, sodium salts, mixed with sulfur compounds, gasoline alk. scrubber residues                                 |
| 68989-88-8 | Gases (petroleum), crude distn. and catalytic cracking  |
| 68990-35-2 | Distillates (petroleum), arom., hydrotreated, dicyclopentadiene-rich  |
| 68991-49-1 | Alkanes, C10-13, arom.-free desulfurized  |
| 68991-50-4 | Alkanes, C14-17, arom.-free desulfurized  |
| 68991-51-5 | Alkanes, C10-13, desulfurized   |
| 68991-52-6 | Alkenes, C10-16   |
| 69013-21-4 | Fuel oil, pyrolysis   |
| 69029-75-0 | Oils, reclaimed   |
| 69430-33-7 | Hydrocarbons, C6-30   |
| 70024-88-3 | Ethene, thermal cracking products   |
| 70528-71-1 | Distillates (petroleum), heavy distillate solvent ext. heart-cut  |
| 70528-72-2 | Distillates (petroleum), heavy distillate solvent ext. vacuum overheads   |
| 70528-73-3 | Residues (petroleum), heavy distillate solvent ext. vacuum  |
| 70592-76-6 | Distillates (petroleum), intermediate vacuum  |
| 70592-77-7 | Distillates (petroleum), light vacuum   |
| 70592-78-8 | Distillates (petroleum), vacuum   |

### CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.     | Product   |
|-------------|---|
| 70592-79-9  | Residues (petroleum), atm. tower, light   |
| 70693-00-4  | Hydrocarbon waxes (petroleum), oxidized, sodium salts   |
| 70693-06-0  | Aromatic hydrocarbons, C9-11  |
| 70913-85-8  | Residues (petroleum), solvent-extd. vacuum distilled atm. residuum  |
| 70913-86-9  | Alkanes, C18-70   |
| 70955-08-7  | Alkanes, C4-6   |
| 70955-09-8  | Alkenes, C13-14 .alpha.-  |
| 70955-10-1  | Alkenes, C15-18 .alpha.-  |
| 70955-17-8  | Aromatic hydrocarbons, C12-20   |
| 71243-66-8  | Hydrocarbon waxes (petroleum), clay-treated, microcryst., oxidized, potassium salts                           |
| 71302-82-4  | Hydrocarbons, C5-8, Houdry butadiene manuf. by-product  |
| 71329-37-8  | Residues (petroleum), catalytic cracking depropanizer, C4-rich  |
| 71808-30-5  | Tail gas (petroleum), thermal cracking absorber   |
| 72230-71-8  | Distillates (petroleum), cracked steam-cracked, C5-17 fraction  |
| 72623-83-7  | Lubricating oils (petroleum), C>25, hydrotreated bright stock-based   |
| 72623-84-8  | Lubricating oils (petroleum), C15-30, hydrotreated neutral oil-based, contg. solvent deasphalted residual oil |
| 72623-85-9  | Lubricating oils (petroleum), C20-50, hydrotreated neutral oil-based, high-viscosity                          |
| 72623-86-0  | Lubricating oils (petroleum), C15-30, hydrotreated neutral oil-based  |
| 72623-87-1  | Lubricating oils (petroleum), C20-50, hydrotreated neutral oil-based  |
| 73138-65-5  | Hydrocarbon waxes (petroleum), oxidized, magnesium salts  |
| 92045-43-7  | Lubricating oils (petroleum), hydrocracked nonarom. solvent deparaffined                                      |
| 92045-58-4  | Naphtha (petroleum), isomerization, C6-fraction   |
| 92062-09-4  | Slack wax (petroleum), hydrotreated   |
| 93762-80-2  | Alkenes, C15-18   |
| 98859-55-3  | Distillates (petroleum), oxidized heavy, compds. with diethanolamine  |
| 98859-56-4  | Distillates (petroleum), oxidized heavy, sodium salts   |
| 101316-73-8 | Lubricating oils (petroleum), used, non-catalytically refined   |
| 164907-78-2 | Extracts (petroleum), asphaltene-low vacuum residue solvent   |
| 164907-79-3 | Residues (petroleum), vacuum, asphaltene-low  |
| 178603-63-9 | Gas oils (petroleum), vacuum, hydrocracked, hydroisomerized, hydrogenated, C10-25                             |
| 178603-64-0 | Gas oils (petroleum), vacuum, hydrocracked, hydroisomerized, hydrogenated, C15-30, branched and cyclic        |
| 178603-65-1 | Gas oils (petroleum), vacuum, hydrocracked, hydroisomerized, hydrogenated, C20-40, branched and cyclic        |
| 178603-66-2 | Gas oils (petroleum), vacuum, hydrocracked, hydroisomerized, hydrogenated, C25-55, branched and cyclic        |
| 212210-93-0 | Solvent naphtha (petroleum), heavy arom., distn. residues   |
| 221120-39-4 | Distillates (petroleum), cracked steam-cracked, C5-12 fraction  |

§ 710.46

40 CFR Ch. I (7-1-10 Edition)

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES TERMED "PETROLEUM PROCESS STREAMS" FOR PURPOSES OF INVENTORY UPDATE REPORTING—Continued

| CAS No.     | Product  |
|-------------|--|
| 445411-73-4 | Gas oils (petroleum), vacuum, hydrocracked, hydroisomerized, hydrogenated, C10-25, branched and cyclic |

(2) *Specific exempted chemical substances*—(i) *Exemption*. EPA has determined that, at this time, the information in § 710.52(c)(4) associated with the chemicals listed in paragraph (b)(2)(iv) of this section is of low current interest.

(ii) *Considerations*. In making its determination of whether this partial exemption should apply to a particular chemical substance, EPA will consider the totality of information available for the chemical substance in question, including but not limited to, one or more of the following considerations:

(A) Whether the chemical qualifies or has qualified in past IUR collections for the reporting of the information described in § 710.52(c)(4) (i.e., at least one site manufactures 300,000 pounds or more of the chemical).

(B) The chemical substance's chemical and physical properties or potential for persistence, bioaccumulation, health effects, or environmental effects (considered independently or together).

(C) The information needs of EPA, other federal agencies, tribes, states, and local governments, as well as members of the public.

(D) The availability of other complementary risk screening information.

(E) The availability of comparable processing and use information.

(F) Whether the potential risks of the chemical substance are adequately managed.

(iii) *Amendments*. EPA may amend the chemical list in paragraph (b)(2)(iv) of this section on its own initiative or in response to a request from the public based on EPA's determination of whether the information in § 710.52(c)(4) is of low interest.

(A) Any person may request that EPA amend the chemical list in paragraph (b)(2)(iv) of this section. Your request must be in writing and must be submitted to the address provided in § 710.59(d). Requests must identify the

chemical in question, as well as its CAS number or other chemical identification number as identified in § 710.52(c)(3)(i), and must contain a written rationale for the request that provides sufficient specific information, addressing the considerations listed in § 710.46(b)(2)(ii), including cites and relevant documents, to demonstrate to EPA that the collection of the information in § 710.52(c)(4) for the chemical in question either is or is not of low current interest. If a request related to a particular chemical is resubmitted, any subsequent request must clearly identify new information contained in the request. EPA may request other information that it believes necessary to evaluate the request. EPA will issue a written response to each request within 120 days of receipt of the request, and will maintain copies of these responses in a public docket that will be established for each reporting cycle.

(B) As needed, the Agency will initiate rulemaking to make revisions to the list in paragraph (b)(2)(iv) of this section.

(C) To assist EPA in reaching a decision regarding a particular request prior to a given reporting year, requests must be submitted to EPA no later than 12 months prior to the start of the reporting year, i.e., by January 1, 2004, or by each January 1 at 5-year intervals thereafter.

(iv) *List of chemical substances*. EPA has designated the following chemical substances, listed by CAS Number, as partially exempt from reporting under the IUR.

CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES UNDER § 710.46(b)(2)

| CAS No. | Chemical  |
|---------|---|
| 50-70-4 | D-Glucitol  |
| 50-81-7 | L-Ascorbic acid   |
| 50-99-7 | D-Glucose   |
| 56-81-5 | 1,2,3-Propanetriol  |
| 56-87-1 | L-Lysine  |
| 57-50-1 | .alpha.-D-Glucopyranoside, .beta.-D-fructofuranosyl   |
| 58-95-7 | 2H-1-Benzopyran-6-ol, 3,4-dihydro-2,5,7,8-tetramethyl-2-[(4R,8R)-4,8,12-trimethyltridecyl]-, acetate, (2R)- |
| 59-02-9 | 2H-1-Benzopyran-6-ol, 3,4-dihydro-2,5,7,8-tetramethyl-2-[(4R,8R)-4,8,12-trimethyltridecyl]-, (2R)-          |
| 59-51-8 | Methionine  |
| 69-65-8 | D-Mannitol  |
| 87-79-6 | L-Sorbose   |

**Environmental Protection Agency**

**§ 710.48**

**CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES UNDER § 710.46(b)(2)—Continued**

| CAS No.    | Chemical  |
|------------|---|
| 87-99-0    | Xylitol   |
| 96-10-6    | Aluminum, chlorodiethyl-  |
| 97-93-8    | Aluminum, triethyl-   |
| 100-99-2   | Aluminum, tris(2-methylpropyl)-   |
| 123-94-4   | Octadecanoic acid, 2,3-dihydroxypropyl ester  |
| 124-38-9   | Carbon dioxide  |
| 137-08-6   | .beta.-Alanine, N-[(2R)-2,4-dihydroxy-3,3-dimethyl-1-oxobutyl]-, calcium salt (2:1) |
| 142-47-2   | L-Glutamic acid, monosodium salt  |
| 150-30-1   | Phenylalanine   |
| 563-43-9   | Aluminum, dichloroethyl-  |
| 1070-00-4  | Aluminum, trioctyl-   |
| 1116-70-7  | Aluminum, tributyl-   |
| 1116-73-0  | Aluminum, trihexyl-   |
| 1191-15-7  | Aluminum, hydrobis(2-methylpropyl)-   |
| 1317-65-3  | Limestone   |
| 1333-74-0  | Hydrogen  |
| 1592-23-0  | Octadecanoic acid, calcium salt   |
| 7440-37-1  | Argon   |
| 7440-44-0  | Carbon  |
| 7727-37-9  | Nitrogen  |
| 7782-42-5  | Graphite  |
| 7782-44-7  | Oxygen  |
| 8001-21-6  | Sunflower oil   |
| 8001-22-7  | Soybean oil   |
| 8001-23-8  | Safflower oil   |
| 8001-26-1  | Linseed oil   |
| 8001-29-4  | Cottonseed oil  |
| 8001-30-7  | Corn oil  |
| 8001-31-8  | Coconut oil   |
| 8001-78-3  | Castor oil, hydrogenated  |
| 8001-79-4  | Castor oil  |
| 8002-03-7  | Peanut oil  |
| 8002-13-9  | Rape oil  |
| 8002-43-5  | Lecithins   |
| 8002-75-3  | Palm oil  |
| 8006-54-0  | Lanolin   |
| 8016-28-2  | Lard, oil   |
| 8016-70-4  | Soybean oil, hydrogenated   |
| 8021-99-6  | Charcoal, bone  |
| 8029-43-4  | Syrups, hydrolyzed starch   |
| 9004-53-9  | Dextrin   |
| 9005-25-8  | Starch  |
| 9050-36-6  | Maltodextrin  |
| 11103-57-4 | Vitamin A   |
| 12075-68-2 | Aluminum, di-.mu.-chlorochlorotriethylidi-  |
| 12542-85-7 | Aluminum, trichlorotrimethylidi-  |
| 16291-96-6 | Charcoal  |
| 26836-47-5 | D-Glucitol, monooctadecanoate   |
| 61789-44-4 | Fatty acids, castor-oil   |
| 61789-97-7 | Tallow  |
| 61789-99-9 | Lard  |
| 64147-40-6 | Castor oil, dehydrated  |
| 64755-01-7 | Fatty acids, tallow, calcium salts  |
| 65996-63-6 | Starch, acid-hydrolyzed   |
| 65996-64-7 | Starch, enzyme-hydrolyzed   |
| 67701-01-3 | Fatty acids, C12-18   |
| 68002-85-7 | Fatty acids, C14-22 and C16-22-unsatd.  |
| 68131-37-3 | Syrups, hydrolyzed starch, dehydrated   |
| 68188-81-8 | Grease, poultry   |
| 68308-36-1 | Soybean meal  |
| 68308-54-3 | Glycerides, tallow mono-, di- and tri-, hydrogenated                                |
| 68334-00-9 | Cottonseed oil, hydrogenated  |
| 68334-28-1 | Fats and glyceridic oils, vegetable, hydrogenated                                   |
| 68409-76-7 | Bone meal, steamed  |
| 68424-45-3 | Fatty acids, linseed-oil  |

**CAS NUMBERS OF PARTIALLY EXEMPT CHEMICAL SUBSTANCES UNDER § 710.46(b)(2)—Continued**

| CAS No.     | Chemical   |
|-------------|--|
| 68424-61-3  | Glycerides, C16-18 and C18-unsatd. mono- and di- |
| 68425-17-2  | Syrups, hydrolyzed starch, hydrogenated          |
| 68439-86-1  | Bone, ash  |
| 68442-69-3  | Benzene, mono-C10-14-alkyl derivs.               |
| 68476-78-8  | Molasses   |
| 68514-27-2  | Grease, catch basin                              |
| 68514-74-9  | Palm oil, hydrogenated                           |
| 68525-87-1  | Corn oil, hydrogenated                           |
| 68648-87-3  | Benzene, C10-16-alkyl derivs.                    |
| 68918-42-3  | Soaps, stocks, soya                              |
| 68952-94-3  | Soaps, stocks, vegetable-oil                     |
| 68956-68-3  | Fats and glyceridic oils, vegetable              |
| 68989-98-0  | Fats and glyceridic oils, vegetable, residues    |
| 73138-67-7  | Lard, hydrogenated                               |
| 120962-03-0 | Canola oil                                       |
| 129813-58-7 | Benzene, mono-C10-13-alkyl derivs.               |
| 129813-59-8 | Benzene, mono-C12-14-alkyl derivs.               |
| 129813-60-1 | Benzene, mono-C14-16-alkyl derivs.               |

(3) *Inorganic chemical substances.* For purposes of this subpart, an inorganic chemical substance is any chemical substance which does not contain carbon or contains carbon only in the form of carbonate [=CO<sub>3</sub>], cyano [--CN], cyanato [--OCN], isocyno [--NC], or isocyanato [--NCO] groups or the chalcogen analogues of such groups. During the 2006 submission period, manufacturers are excluded only from the reporting requirements under § 710.52(c)(4) for inorganic chemical substances. During the 2006 submission period, manufacturers of inorganic chemical substances are not excluded from the other reporting requirements under this part. During submission periods following the 2006 submission period, manufacturers of inorganic chemical substances are subject to all of the reporting requirements in this subpart.

[68 FR 890, Jan. 7, 2003, as amended at 69 FR 40791, July 7, 2004; 70 FR 60221, Oct. 17, 2005; 70 FR 74700, Dec. 16, 2005; 70 FR 75068, Dec. 19, 2005; 71 FR 8470, Feb. 17, 2006]

**§ 710.48 Persons who must report.**

Except as provided in §§ 710.49 and 710.50, the following persons are subject to the requirements of this subpart. Persons must determine whether they must report under this section for each chemical substance that they manufacture (including import) at an individual site.

## § 710.49

(a) *Persons subject to recurring reporting.* Any person who manufactured (including imported) for commercial purposes 25,000 lbs. (11,340 kg) or more of a chemical substance described in § 710.45 at any single site owned or controlled by that person at any time during calendar year 2005 or during the calendar year at 5-year intervals thereafter is subject to reporting.

(b) *Special provisions for importers.* For purposes of this section, the site for a person who imports a chemical substance described in § 710.45 is the site of the operating unit within the person's organization which is directly responsible for importing the substance and which controls the import transaction. The import site may in some cases be the organization's headquarters in the United States (see also § 710.55(b)).

[68 FR 890, Jan. 7, 2003, as amended at 70 FR 75069, Dec. 19, 2005]

## § 710.49 Persons not subject to this subpart.

A person described in § 710.48 is not subject to the requirements of this subpart if that person qualifies as a small manufacturer as that term is defined in § 704.3 of this chapter. Notwithstanding this exclusion, a person who qualifies as a small manufacturer is subject to this subpart with respect to any chemical substance that is the subject of a rule proposed or promulgated under section 4, 5(b)(4), or 6 of the Act, or is the subject of an order in effect under section 5(e) of the Act, or is the subject of relief that has been granted under a civil action under section 5 or 7 of the Act.

## § 710.50 Activities for which reporting is not required.

A person described in § 710.48 is not subject to the requirements of this subpart with respect to any chemical substance described in § 710.45 that the person solely manufactured or imported under the following circumstances:

(a) The person manufactured or imported the chemical substance described in § 710.45 solely in small quantities for research and development.

(b) The person imported the chemical substance described in § 710.45 as part of an article.

## 40 CFR Ch. I (7–1–10 Edition)

(c) The person manufactured the chemical substance described in § 710.45 in a manner described in § 720.30(g) or (h) of this chapter.

## § 710.52 Reporting information to EPA.

Any person who must report under this subpart, as described in § 710.48, must submit the information described in this section for each chemical substance described in § 710.45 that the person manufactured (including imported) for commercial purposes in an amount of 25,000 lbs. (11,340 kg) or more at any one site during calendar year 2005 or during the calendar year at 5-year intervals thereafter. (See § 710.48(b) for the "site" for importers). A separate form must be submitted for each chemical substance at each site for which the submitter is required to report. A submitter of information under this subpart must report information as described in paragraphs (c)(1), (c)(2), and (c)(3) of this section to the extent that such information is *known to or reasonably ascertainable by* that person whereas a submitter must report information as described in paragraph (c)(4) of this section only to the extent that such information is *readily obtainable* by that person. A submitter under this subpart must report information that applies to the calendar year for which the person is required to report (i.e., calendar year 2005 and the calendar year at 5-year intervals thereafter).

(a) *Reporting in writing.* Any person who chooses to report information to EPA in writing must do so by completing the reporting form available from EPA at the address set forth in § 710.59. The form must include all information described in paragraph (c) of this section. Persons reporting in writing must submit a separate form for each site for which the person is required to report.

(b) *Reporting by magnetic media.* Any person who chooses to report information to EPA by means of magnetic media must submit the information described in paragraph (c) of this section. Magnetic media submitted in response to this subpart must meet EPA specifications, as described in the instruction booklet available from EPA at the address set forth in § 710.59.

(c) *Information to be reported.* Manufacturers (including importers) of a reportable chemical substance in an amount of 25,000 lbs. (11,340 kg) or more at a site during a reporting year must report the information described in paragraphs (c)(1), (c)(2), and (c)(3) of this section. Manufacturers (including importers) of a reportable chemical substance in an amount of 300,000 lbs. (136,077 kg) or more at a site during a reporting year must report the information described in paragraph (c)(4) of this section in addition to the information described in paragraphs (c)(1), (c)(2), and (c)(3) of this section. As described in §710.46(b)(3), manufacturers of certain inorganic chemical substances are not required to report the information described in paragraph (c)(4) of this section during the 2006 submission period, but are required to report this information during subsequent submission periods. As described in §710.46(b)(1) and (b)(2), manufacturers of certain chemicals are not required to report the information described in paragraph (c)(4) of this section.

(1) *A certification statement signed and dated by an authorized official of the submitter company.* Persons reporting by means of magnetic media must submit this information on the reporting form available as described in §710.59.

(2) *Company and plant site information.* The following company and plant site information must be reported for each site at which at least 25,000 lbs. (11,340 kg) of a reportable chemical substance is manufactured (including imported) during calendar year 2005 or during the calendar year at 5-year intervals thereafter (see §710.48(b) for the "site" for importers):

(i) The name of a person who will serve as technical contact for the submitter company, and who will be able to answer questions about the information submitted by the company to EPA, the company name and Dun and Bradstreet Number, the contact person's full mailing address, the contact person's telephone number and the contact person's e-mail address.

(ii) The name and full street address of each site. A submitter under this subpart must include the appropriate Dun and Bradstreet Number for each

plant site reported, and the county or parish (or other jurisdictional indicator) in which the plant site is located.

(3) *Specific information for chemicals manufactured in amounts of 25,000 lbs. or more.* The following chemical-specific information must be reported for each reportable chemical substance manufactured at (including imported into) each site in amounts of 25,000 lbs. (11,340 kg) or more during calendar year 2005 or during the calendar year at 5-year intervals thereafter:

(i) The specific chemical name and CAS Number of each reportable chemical substance at each site. A submitter under this subpart may use an EPA-designated Accession Number for confidential substances, or a premanufacture notice (PMN) case number (see §720.65 of this chapter) in lieu of a CAS Number when a CAS Number is not known to or reasonably ascertainable by the submitter. In addition to reporting the number itself, submitters must specify the type of number they are reporting by selecting from among the following codes:

CODES TO SPECIFY TYPE OF CHEMICAL IDENTIFYING NUMBER

| Codes   | Number Type         |
|---------|---------------------|
| A ..... | Accession Number    |
| C ..... | CAS Registry Number |
| P ..... | PMN Number          |

(ii) A statement indicating, for each reportable chemical substance at each site, whether the substance is manufactured in the United States, imported into the United States, or both manufactured in the United States and imported into the United States.

(iii) A designation indicating, for each reportable chemical substance at each site, whether the substance is site-limited.

(iv) The total volume (in pounds) of each reportable chemical substance manufactured and imported at each site. The total manufactured volume (not including imported volume) and the total imported volume must be separately reported. This amount must be reported to two significant figures of accuracy provided that the reported figures are within ±10% of the actual volume.



§ 710.52

40 CFR Ch. I (7-1-10 Edition)

(v) The total number of workers reasonably likely to be exposed to each reportable chemical substance at each site. For each reportable substance at each site, the submitter must select from among the ranges of workers listed in the following table and report the corresponding code (i.e., W1 through W8):

CODES FOR REPORTING NUMBER OF WORKERS REASONABLY LIKELY TO BE EXPOSED

| Codes    | Range                                       |
|----------|---|
| W1 ..... | Less than 10 workers                        |
| W2 ..... | At least 10 but less than 25 workers        |
| W3 ..... | At least 25 but less than 50 workers        |
| W4 ..... | At least 50 but less than 100 workers       |
| W5 ..... | At least 100 but less than 500 workers      |
| W6 ..... | At least 500 but less than 1,000 workers    |
| W7 ..... | At least 1,000 but less than 10,000 workers |
| W8 ..... | At least 10,000 workers                     |

(vi) The maximum concentration, measured by percentage of weight, of each reportable chemical substance at the time it is sent off-site from each site. If the chemical is site-limited, you must report the maximum concentration, measured by percentage of weight, of the reportable chemical substance at the time it is reacted on-site to produce a different chemical substance. This information must be reported regardless of the physical form(s) in which the substance is sent off-site/reacted on-site. For each substance at each site, select the maximum concentration of the substance from among the ranges listed in the following table and report the corresponding code (i.e., M1 through M5):

CODES FOR REPORTING MAXIMUM CONCENTRATION OF CHEMICAL SUBSTANCE

| Codes    | Concentration Range (% weight) |
|----------|--------------------------------|
| M1 ..... | Less than 1% by weight         |
| M2 ..... | From 1 to 30% by weight        |
| M3 ..... | From 31 to 60% by weight       |
| M4 ..... | From 61 to 90% by weight       |
| M5 ..... | Greater than 90% by weight     |

(vii) The physical form(s) of the reportable chemical substance as it is sent off-site from each site. If the chemical is site-limited, you must report the physical form(s) of the reportable chemical substance at the time it is reacted on-site to produce a different chemical substance. For each substance at each site, the submitter must

report as many physical forms as apply from among the physical forms listed below:

- (A) Dry powder.
- (B) Pellets or large crystals.
- (C) Water- or solvent-wet solid.
- (D) Other solid.
- (E) Gas or vapor.
- (F) Liquid.

(viii) Submitters must report the percentage, rounded off to the closest 10%, of total production volume of the reportable chemical substance, reported in response to paragraph (c)(3)(iv) of this section, that is associated with each physical form reported under paragraph (c)(3)(vii) of this section.

(4) *Specific information for chemical substances manufactured in amounts of 300,000 lbs. or more.* In addition to the information required under paragraphs (c)(1), (c)(2), and (c)(3) of this section, the following information must be reported for each reportable chemical substance manufactured (including imported) in an amount of 300,000 lbs. (136,077 kg) or more at any one site during calendar year 2005 or during the calendar year at 5-year intervals thereafter. Persons subject to paragraph (c)(4) of this section must report the information described in paragraphs (c)(4)(i) and (c)(4)(ii) of this section for each reportable chemical substance at sites under their control and at sites that receive a reportable chemical substance from the submitter directly or indirectly (including through a broker/distributor, from a customer of the submitter, etc.). Information reported in response to this paragraph must be reported only to the extent that it is readily obtainable by the submitter. Information required to be reported under this paragraph is limited to domestic (i.e., within the custom territory of the United States) processing and use activities. If information responsive to a given data requirement under this paragraph, including information in the form of an estimate, is not readily obtainable, the submitter is not required to respond to the requirement.

(i) *Industrial processing and use information.* (A) A designation indicating the type of industrial processing or use operation(s) at each site that receives a

**Environmental Protection Agency**

**§ 710.52**

reportable substance from the submitter site directly or indirectly (whether the recipient site(s) are controlled by the submitter site or not). For each chemical substance, report the letters which correspond to the appropriate processing or use operation(s). A particular designation may need to be reported more than once, to the extent that a submitter reports more than one NAICS code (under paragraph (c)(4)(i)(B) of this section) that applies to a given designation under this paragraph.

| Designation | Operation  |
|-------------|--|
| PC .....    | Processing as a reactant   |
| PF .....    | Processing - incorporation into formulation, mixture or reaction product |
| PA .....    | Processing - incorporation into article                                  |
| PK .....    | Processing - repackaging   |
| U .....     | Use - non-incorporative activities                                       |

(B) The five-digit North American Industrial Classification System (NAICS) codes which best describe the industrial activities associated with each industrial processing or use operation reported under paragraph (c)(4)(i)(A) of this section. Information about how to find these codes is provided in the instruction booklet available from EPA at the address set forth in §710.59. A particular NAICS code may need to be reported more than once, to the extent that a submitter reports more than one industrial function code (under paragraph (c)(4)(i)(C) of this section) that applies to a given NAICS code under this paragraph.

(C) For each NAICS code reported under paragraph (c)(4)(i)(B) of this section, code(s) from the following list must be selected to designate the industrial function category(ies) that best represents the specific manner in which the chemical substance is used. A particular industrial function category may need to be reported more than once, to the extent that a submitter reports more than one industrial processing or use operation/NAICS code combination (under paragraphs (c)(4)(i)(A) and (c)(4)(i)(B) of this section) that applies to a given industrial function category under this paragraph. If more than 10 unique combinations of industrial processing or use operations/NAICS codes/industrial function categories apply to a chemical

substance, submitters need only report the 10 unique combinations for the chemical substance that cumulatively represent the largest percentage of the submitter's production volume for that chemical, measured by weight.

**CODES FOR REPORTING INDUSTRIAL FUNCTION CATEGORIES**

| Codes     | Category   |
|-----------|--|
| U01 ..... | Adsorbents and absorbents  |
| U02 ..... | Adhesives and binding agents   |
| U03 ..... | Aerosol propellants  |
| U04 ..... | Agricultural chemicals (non-pesticidal)  |
| U05 ..... | Anti-adhesive agents   |
| U06 ..... | Bleaching agents   |
| U07 ..... | Coloring agents, dyes  |
| U08 ..... | Coloring agents, pigments  |
| U09 ..... | Corrosion inhibitors and anti-scaling agents   |
| U10 ..... | Fillers  |
| U11 ..... | Fixing agents  |
| U12 ..... | Flame retardants   |
| U13 ..... | Flotation agents   |
| U14 ..... | Fuels  |
| U15 ..... | Functional fluids  |
| U16 ..... | Intermediates  |
| U17 ..... | Lubricants   |
| U18 ..... | Odor agents  |
| U19 ..... | Oxidizing agents   |
| U20 ..... | pH-regulating agents   |
| U21 ..... | Photosensitive chemicals   |
| U22 ..... | Plating agents and metal surface treating agents   |
| U23 ..... | Processing aid, not otherwise listed   |
| U24 ..... | Process regulators, used in vulcanization or polymerization processes  |
| U25 ..... | Process regulators, other than polymerization or vulcanization processes   |
| U26 ..... | Reducing agents  |
| U27 ..... | Solvents (for cleaning or degreasing)  |
| U28 ..... | Solvents (which become part of product formulation or mixture)   |
| U29 ..... | Solvents (for chemical manufacture and processing and are not part of product at greater than one percent by weight) |
| U30 ..... | Stabilizers  |
| U31 ..... | Surface active agents  |
| U32 ..... | Viscosity adjustors  |
| U33 ..... | Other  |

(D) The estimated percentage, rounded off to the closest 10%, of total production volume of the reportable chemical substance associated with each combination of industrial processing or use operation, NAICS code and industrial function category. Where a particular combination of industrial processing or use operation, NAICS code and industrial function category accounts for 5% or less of the submitter's site's total production volume of a reportable chemical substance, the percentage must not be rounded off to zero % if the production volume attributable to that industrial processing or

§ 710.52

40 CFR Ch. I (7–1–10 Edition)

use operation, NAICS code and industrial function category combination is 300,000 lbs. (136,077 kg) or more during the reporting year. Instead, in such a case, submitters must report the percentage, rounded off to the closest 1%, of the submitter's site's total production volume of the reportable chemical substance associated with the particular combination of industrial processing or use operation, NAICS code and industrial function category.

(E) For each combination of industrial processing or use operation, NAICS code and industrial function category, the submitter must estimate the number of sites at which each reportable chemical substance is processed or used. For each combination associated with each substance, the submitter must select from among the ranges of sites listed in the following table and report the corresponding code (i.e., S1 through S7):

CODES FOR REPORTING NUMBERS OF SITES

| Codes    | Range                                     |
|----------|---|
| S1 ..... | less than 10 sites                        |
| S2 ..... | at least 10 but less than 25 sites        |
| S3 ..... | at least 25 but less than 100 sites       |
| S4 ..... | at least 100 but less than 250 sites      |
| S5 ..... | at least 250 but less than 1,000 sites    |
| S6 ..... | at least 1,000 but less than 10,000 sites |
| S7 ..... | 10,000 or more sites                      |

(F) For each combination of industrial processing or use operation, NAICS code and industrial function category, the submitter must estimate the number of workers reasonably likely to be exposed to each reportable chemical substance. For each combination associated with each substance, the submitter must select from among the worker ranges listed in paragraph (c)(3)(v) of this section and report the corresponding code (i.e., W1 through W8).

(ii) *Commercial and consumer use information.* (A) Using the codes listed in this paragraph, submitters must designate the commercial and consumer product category or categories that best describe the commercial and consumer products in which each reportable chemical substance is used (whether the recipient site(s) are controlled by the submitter site or not). If more than 10 codes apply to a chemical substance, submitters need only report

the 10 codes for the chemical substance that cumulatively represent the largest percentage of the submitter's production volume for that chemical, measured by weight:

CODES FOR REPORTING COMMERCIAL AND CONSUMER PRODUCT CATEGORIES

| Codes     | Category                                  |
|-----------|---|
| C01 ..... | Adhesives and sealants                    |
| C02 ..... | Agricultural products (non-pesticidal)    |
| C03 ..... | Artists' supplies                         |
| C04 ..... | Automotive care products                  |
| C05 ..... | Electrical and electronic products        |
| C06 ..... | Fabrics, textiles and apparel             |
| C07 ..... | Glass and ceramic products                |
| C08 ..... | Lawn and garden products (non-pesticidal) |
| C09 ..... | Leather products                          |
| C10 ..... | Lubricants, greases and fuel additives    |
| C11 ..... | Metal products                            |
| C12 ..... | Paints and coatings                       |
| C13 ..... | Paper products                            |
| C14 ..... | Photographic supplies                     |
| C15 ..... | Polishes and sanitation goods             |
| C16 ..... | Rubber and plastic products               |
| C17 ..... | Soaps and detergents                      |
| C18 ..... | Transportation products                   |
| C19 ..... | Wood and wood furniture                   |
| C20 ..... | Other                                     |

(B) Submitters must determine, within each commercial and consumer product category reported under paragraph (c)(4)(ii)(A) of this section, whether any amount of each reportable chemical substance manufactured (including imported) by the submitter is present in (for example, a plasticizer chemical used to make pacifiers) or on (for example, as a component in the paint on a toy) any consumer products intended for use by children up to the age of 14, regardless of the concentration of the substance remaining in or on the product. Submitters must select from the following options: the chemical substance is used in or on any consumer products intended for use by children, the chemical substance is not used in or on any consumer products intended for use by children, or information as to whether the chemical substance is used in or on any consumer products intended for use by children is not readily obtainable.

(C) The estimated percentage, rounded off to the closest 10%, of the submitter's site's total production volume of the reportable chemical substance associated with each commercial and consumer product category. Where a particular commercial and consumer product category accounts for 5% or

less of the total production volume of a reportable chemical substance, the percentage must not be rounded off to zero % if the production volume attributable to that commercial and consumer product category is 300,000 lbs. (136,077 kg) or more during the reporting year. Instead, in such a case, submitters must report the percentage, rounded off to the closest 1%, of the submitter's site's total production volume of the reportable chemical substance associated with the particular commercial and consumer product category.

(D) Where the reportable chemical substance is used in commercial or consumer products, the estimated typical maximum concentration, measured by weight, of the chemical substance in each commercial and consumer product category reported under paragraph (c)(4)(ii)(A) of this section. For each substance in each commercial and consumer product category reported under paragraph (c)(4)(ii)(A) of this section, submitters must select from among the ranges of concentrations listed in the table in paragraph (c)(3)(vi) of this section and report the corresponding code (i.e., M1 through M5).

[68 FR 890, Jan. 7, 2003, as amended at 69 FR 40791, July 7, 2004; 70 FR 75069, Dec. 19, 2005; 71 FR 52498, Sept. 6, 2006]

#### § 710.53 When to report.

All information reported to EPA in response to the requirements of this subpart must be submitted during an applicable submission period. The first submission period is from August 25, 2006, to March 23, 2007. Subsequent recurring submission periods are from June 1 to September 30 at 5-year intervals after the first submission period. Any person described in § 710.48(a) must report during each submission period for each chemical substance described in § 710.45 that the person manufactured (including imported) during the preceding calendar year (i.e., the "reporting year").

[70 FR 75069, Dec. 19, 2005, as amended at 71 FR 76206, Dec. 20, 2006]

#### § 710.55 Duplicative reporting.

(a) *With regard to section 8(a) rules.* Any person subject to the requirements of this part who previously has complied with reporting requirements of a rule under section 8(a) of the Act by submitting the information described in § 710.52 for a chemical substance described in § 710.45 to EPA, and has done so within 1 year of the start of a submission period described in § 710.53, is not required to report again on the manufacture of that substance at that site during that submission period.

(b) *With regard to importers.* This part requires that only one report be submitted on each import transaction involving a chemical substance described in § 710.45. When two or more persons are involved in a particular import transaction and each person meets the Agency's definition of "importer" as set forth in §§ 710.3 and 704.3 of this chapter, they may determine among themselves who should submit the required report; if no report is submitted as required under this part, EPA will hold each such person liable for failure to report.

#### § 710.57 Recordkeeping requirements.

Each person who is subject to the reporting requirements of this subpart must retain records that document any information reported to EPA. Records relevant to reporting during a submission period must be retained for a period of 5 years beginning on the last day of the submission period. Submitters are encouraged to retain their records longer than 5 years to ensure that past records are available as a reference when new submissions are being generated.

[70 FR 75070, Dec. 19, 2005]

#### § 710.58 Confidentiality.

(a) Any person submitting information under this subpart may assert a business confidentiality claim for the information at the time it is submitted. These claims will apply only to the information submitted with the claim. New confidentiality claims, if necessary, must be asserted with regard to information submitted during the next submission period. Guidance for asserting confidentiality claims is

## §710.58

## 40 CFR Ch. I (7-1-10 Edition)

provided in the instruction booklet identified in §710.59. Information claimed as confidential in accordance with this section will be treated and disclosed in accordance with the procedures in part 2 of this chapter.

(b) *Chemical identity.* A person may assert a claim of confidentiality for the chemical identity of a specific chemical substance only if the identity of that substance is treated as confidential in the Master Inventory File as of the time the report is submitted for that substance under this subpart. The following steps must be taken to assert a claim of confidentiality for the identity of a reportable chemical substance:

(1) The submitter must submit with the report detailed written answers to the following questions signed and dated by an authorized official.

(i) What harmful effects to your competitive position, if any, do you think would result from the identity of the chemical substance being disclosed in connection with reporting under this subpart? How could a competitor use such information? Would the effects of disclosure be substantial? What is the causal relationship between the disclosure and the harmful effects?

(ii) How long should confidential treatment be given? Until a specific date, the occurrence of a specific event, or permanently? Why?

(iii) Has the chemical substance been patented? If so, have you granted licenses to others with respect to the patent as it applies to the chemical substance? If the chemical substance has been patented and therefore disclosed through the patent, why should it be treated as confidential?

(iv) Has the identity of the chemical substance been kept confidential to the extent that your competitors do not know it is being manufactured or imported for a commercial purpose by anyone?

(v) Is the fact that the chemical substance is being manufactured (including imported) for a commercial purpose available to the public, for example in technical journals, libraries, or State, local, or Federal agency public files?

(vi) What measures have been taken to prevent undesired disclosure of the fact that the chemical substance is

being manufactured (including imported) for a commercial purpose?

(vii) To what extent has the fact that this chemical substance is manufactured (including imported) for commercial purposes been revealed to others? What precautions have been taken regarding these disclosures? Have there been public disclosures or disclosures to competitors?

(viii) Does this particular chemical substance leave the site of manufacture (including import) in any form, e.g., as product, effluent, emission? If so, what measures have been taken to guard against the discovery of its identity?

(ix) If the chemical substance leaves the site in a product that is available to the public or your competitors, can the substance be identified by analysis of the product?

(x) For what purpose do you manufacture (including import) the substance?

(xi) Has EPA, another Federal agency, or any Federal court made any pertinent confidentiality determinations regarding this chemical substance? If so, please attach copies of such determinations.

(2) If any of the information contained in the answers to the questions listed in paragraph (b)(1) of this section is asserted to contain confidential business information, the submitter must clearly identify the information that is claimed confidential by marking the specific information on each page with a label such as "confidential business information," "proprietary," or "trade secret."

(c) *Site identity.* A submitter may assert a claim of confidentiality for a site only if the linkage of the site with a reportable chemical is confidential and not publicly available. The following steps must be taken to assert a claim of confidentiality for a site identity:

(1) The submitter must submit with the report detailed written answers to the following questions signed and dated by an authorized official:

(i) Has site information been linked with a chemical identity in any other Federal, state or local reporting scheme? For example, is the chemical identity linked to a facility in a filing

under the Emergency Planning and Community Right-to-Know Act (EPCRA) section 311, namely through a Material Safety Data Sheet (MSDS)? If so, identify all such schemes. Was the linkage claimed as confidential in any of these instances?

(ii) What harmful effect, if any, to your competitive position do you think would result from the identity of the site and the chemical substance being disclosed in connection with reporting under this subpart? How could a competitor use such information? Would the effects of disclosure be substantial? What is the causal relationship between the disclosure and the harmful effects?

(2) If any of the information contained in the answers to the questions listed in paragraph (c)(1) of this section is asserted to contain confidential business information, the submitter must clearly identify the information that is claimed confidential by marking the specific information on each page with a label such as “confidential business information,” “proprietary,” or “trade secret.”

(d) If no claim of confidentiality is indicated on the reporting form submitted to EPA under this subpart, or if confidentiality claim substantiation required under paragraphs (b) and (c) of this section is not submitted with the reporting form, EPA may make the information available to the public without further notice to the submitter.

[68 FR 890, Jan. 7, 2003, as amended at 69 FR 40791, July 7, 2004]

**§ 710.59 Availability of reporting form and instructions.**

(a) *Use the proper EPA form.* You must use the EPA form identified as “Form U” to submit written information in response to the requirements of this subpart. Instructions for obtaining copies of Form U are in paragraph (c) of this section.

(b) *Follow the reporting instructions.* You should follow the detailed instructions for completing and submitting an electronic or hard copy report. Instructions given in the EPA publication titled, “Instructions for Reporting for the 2006 Partial Updating of the TSCA Chemical Inventory Database,” are available as described in paragraph (c)

of this section. EPA encourages reporting sites subject to this part to submit the required information to EPA electronically.

(c) *Obtain the reporting package and copies of the form.* You can obtain the reporting form or software, reporting instructions, and other associated documents as follows:

(1) *By website.* Go to the EPA Inventory Update Reporting Internet home page at <http://www.epa.gov/oppt/iur> and follow the appropriate links. EPA encourages reporting sites subject to this subpart to visit this home page.

(2) *By phone.* Call the EPA TSCA Hotline at (202) 554-1404.

(3) *By e-mail.* Send an e-mail request for this information to the EPA TSCA Hotline at [TSCA-Hotline@epa.gov](mailto:TSCA-Hotline@epa.gov).

(4) *By mail.* Send a written request for this information to the following address: TSCA Hotline, Mail Code 7408M, ATTN: Inventory Update Reporting, Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001.

[71 FR 52498, Sept. 6, 2006]

**PART 712—CHEMICAL INFORMATION RULES**

**Subpart A—General Provisions**

Sec.

712.1 Scope and compliance.

712.3 Definitions.

712.5 Method of identification of substances for reporting purposes.

712.7 Report of readily obtainable information for subparts B and C.

712.15 Confidentiality.

**Subpart B—Manufacturers Reporting—Preliminary Assessment Information**

712.20 Manufacturers and importers who must report.

712.25 Exempt manufacturers and importers.

712.28 Form and instructions.

712.30 Chemical lists and reporting periods.

AUTHORITY: 15 U.S.C. 2607(a).

SOURCE: 47 FR 26998, June 22, 1982, unless otherwise noted.

### Subpart A—General Provisions

#### § 712.1 Scope and compliance.

(a) This part establishes procedures for chemical manufacturers and processors to report production, use, and exposure-related information on listed chemical substances. Subpart A establishes requirements that apply to all reporting under this part. Subpart B covers manufacturers' and processors' reporting.

(b) Chemical substances, mixtures, and categories of substances or mixtures which have been recommended by the Interagency Testing Committee for testing consideration by the Agency but not designated for Agency response within 12 months, will be added to § 712.30 using the procedure specified in § 712.30(c) only to the extent that the total number of designated and recommended chemicals has not exceeded 50 in any 1 year. Additional recommended but not designated chemicals may be added after proposal, and consideration of public comment.

[47 FR 26998, June 22, 1982, as amended at 50 FR 34809, Aug. 28, 1985; 60 FR 31921, June 19, 1995]

#### § 712.3 Definitions.

The definitions in section 3 of TSCA, 15 U.S.C. 2602, apply for this part. In addition, the following definitions apply:

(a) *Byproduct* means any chemical substance or mixture produced without a separate commercial intent during the manufacture, processing, use, or disposal of another chemical substance or mixture.

(b) *EPA* means the U.S. Environmental Protection Agency.

(c) *Import in bulk form* means to import a chemical substance (other than as part of a mixture or article) in any quantity, in cans, bottles, drums, barrels, packages, tanks, bags, or other containers used for purposes of transportation or containment, if the chemical substance has an end use or commercial purpose separate from the container.

(d) *Importer* means anyone who imports a chemical substance, including a chemical substance as part of a mixture or article, into the customs territory of the U.S. and includes the per-

son liable for the payment of any duties on the merchandise, or an authorized agent on his behalf. Importer also includes, as appropriate:

(1) The consignee.

(2) The importer of record.

(3) The actual owner if an actual owner's declaration and superseding bond has been filed in accordance with 19 CFR 141.20.

(4) The transferee, if the right to withdraw merchandise in a bonded warehouse has been transferred in accordance with subpart C of 19 CFR part 144. For the purposes of this definition, the customs territory of the U.S. consists of the 50 states, Puerto Rico, and the District of Columbia.

(e) *Impurity* means a chemical substance unintentionally present with another chemical substance or mixture.

(f) *Intermediate* means any chemical substance that is consumed, in whole or in part, in chemical reactions used for the intentional manufacture of other chemical substances or mixtures, or that is intentionally present for the purpose of altering the rates of such chemical reactions. (See also paragraph (j) of this section.)

(g) *Known to or reasonably ascertainable by* means all information in a person's possession or control, plus all information that a reasonable person similarly situated might be expected to possess, control, or know, or could obtain without unreasonable burden.

(h) *Manufacture for commercial purposes* means to import, produce, or manufacture with the purpose of obtaining an immediate or eventual commercial advantage for the manufacturer and includes, among other things, such "manufacture" of any amount of a chemical substance or mixture:

(1) For commercial distribution, including for test marketing.

(2) For use by the manufacturer, including use for product research and development, or as an intermediate. Manufacture for commercial purposes also applies to substances that are produced coincidentally during the manufacture, processing, use, or disposal of another substance or mixture, including byproducts and coproducts that are separated from that other substance or

mixture, and impurities that remain in that substance or mixture. Byproducts and impurities may not in themselves have commercial value. They are nonetheless produced for the purpose of obtaining a commercial advantage since they are part of the manufacture of a chemical produced for a commercial purpose.

(i) *Mixture* means any combination of two or more chemical substances if the combination does not occur in nature and is not, in whole or in part, the result of a chemical reaction; except that *mixture* does include (1) any combination which occurs, in whole or in part, as a result of a chemical reaction if the combination could have been manufactured for commercial purposes without a chemical reaction at the time the chemical substances comprising the combination were combined, and if all of the chemical substances comprising the combination are included in the EPA, TSCA Chemical Substance Inventory after the effective date of the premanufacture notification requirement under 40 CFR part 720, and (2) hydrates of a chemical substance or hydrated ions formed by association of a chemical substance with water. The term mixture includes alloys, inorganic glasses, ceramics, frits, and cements, including Portland cement.

(j) *Non-isolated intermediate* means any intermediate that is not intentionally removed from the equipment in which it is manufactured, including the reaction vessel in which it is manufactured, equipment which is ancillary to the reaction vessel, and any equipment through which the substance passes during a continuous flow process, but not including tanks or other vessels in which the substance is stored after its manufacture. (See also paragraph (f) of this section.)

(k) *Owned or controlled by the parent company* means the parent owns or controls 50 percent or more of the other company's voting stock or other equity rights, or has the power to control the management and policies of the other company.

(l) *Person* means any natural person, firm, company, corporation, joint venture, partnership, sole proprietorship, association, or any other business entity, any State or political subdivision

thereof, any municipality, any interstate body, and any department, agency, or instrumentality of the Federal government.

(m) *Process for commercial purposes* means the preparation of a chemical substance or mixture, after its manufacture, for distribution in commerce with the purpose of obtaining an immediate or eventual commercial advantage for the processor. Processing of any amount of a chemical substance or mixture is included. If a chemical or mixture containing impurities is processed for commercial purposes, then those impurities are also processed for commercial purposes.

(n) *Site* means a contiguous property unit. Property divided only by a public right-of-way shall be considered one site. There may be more than one manufacturing plant on a single site.

(o) *Test marketing* means distributing in commerce a limited amount of a chemical substance or mixture, or article containing such substance or mixture, to a defined number of potential customers, during a predetermined testing period, to explore market capability prior to broader distribution in commerce.

(p) *TSCA* means the Toxic Substances Control Act, 15 U.S.C. 2601 et seq.

#### § 712.5 Method of identification of substances for reporting purposes.

(a) *Report on TSCA-regulable quantities*. Unless specifically otherwise required, respondents must report only about quantities of a chemical that is defined as a chemical substance under TSCA section 3(2).

(b) *Chemicals from natural sources*. A manufacturer of a chemical substance which is extracted from an ore, from oil, or from any other natural source must report only about the manufacturing steps for, and the uses of, that chemical, not about production of the natural source material or other crude precursors derived from the natural source material.

For example, persons who manufacture a chemical substance such as "sweetened naphtha, 64741-87-3," but do not refine the naphtha to produce "hexane, 110-54-3" would not report on hexane. Only the production of "hexane" as an isolated product must be reported—not previous production of more crude, complex substances such as naphtha



## §712.7

from which hexane is extracted. Thus, persons who produce crude oil, ores, and other crude natural materials, but do not carry them through further manufacturing steps that produce a listed chemical have no reporting responsibilities under this Part. Note, however, that any method of extraction, refinement, or purification of a listed chemical substance is considered to be manufacturing for the purposes of this rule.

(c) *Chemical substances as marketed.* This part requires reporting about chemical substances as they are marketed or used in practice. The following preparations of a chemical substance must be reported as the substance itself, not as a mixture, since these preparations are regarded as the substance in practice.

(1) The chemical substance in aqueous solution.

(2) The chemical substance containing an additive (such as a stabilizer or other chemical) to maintain the integrity or physical form of the substance.

(3) The chemical substance in any grade of purity.

### §712.7 Report of readily obtainable information for subparts B and C.

TSCA section 8(a) authorizes EPA to require persons to report information that is known to or reasonably ascertainable by them. For purposes of subpart B, however, a lesser standard applies. Companies must report information that is readily obtainable by management and supervisory employees responsible for manufacturing, processing, distributing, technical services, and marketing. Extensive file searches are not required.

[47 FR 26998, June 22, 1982, as amended at 60 FR 31921, June 19, 1995]

### §712.15 Confidentiality.

(a) Any person submitting information under this part may assert business confidentiality claims for the information as described in the pertinent reporting form and its instructions. Any information covered by a claim will be disclosed by EPA only as provided in the procedures set forth at 40 CFR part 2.

(b) Persons must certify to the validity of a claim of confidentiality they make for information reported under

## 40 CFR Ch. I (7-1-10 Edition)

this part, as specified on the reporting form.

(c) If no claim accompanies the information at the time it is submitted to EPA or if certification as to the claim is not made on the reporting form, EPA may place the information in an open file available to the public without further notice to the submitter.

## Subpart B—Manufacturers Reporting—Preliminary Assessment Information

### §712.20 Manufacturers and importers who must report.

Except as described in §712.25, at the time a chemical substance is listed in §712.3, the following persons must submit the “Manufacturer’s Report—Preliminary Assessment Information” (as described in §712.28) for each plant site at which they manufactured or imported the chemical substance during the reporting period specified in §712.30:

(a) Persons who manufactured one or more of the chemical substances listed in §712.30 for commercial purposes.

(b) Persons who imported in bulk form one or more of the chemical substances listed in §712.30 for commercial purposes.

### §712.25 Exempt manufacturers and importers.

(a) Persons who manufactured or imported the chemical substance during the reporting period, solely for purposes of scientific experimentation, analysis, or research, including research or analysis for product development, are not subject to reporting under §712.20.

(b) Persons who, during the reporting period, manufactured or imported fewer than 500 kilograms (1100 pounds) of the chemical substance at a single plant site are not subject to reporting for that site under §712.20.

(c) Persons who qualify as small manufacturers or importers in respect to a specific chemical substance listed in §712.30 are exempt. However, this exemption does not apply with respect to any chemical in §712.30 designated by an asterisk. A manufacturer is qualified as small and is exempt from submitting a report under this subpart for

## Environmental Protection Agency

## § 712.30

a chemical substance manufactured at a particular plant site if both of the following criteria are met:

(1) Total annual sales taken together of all sites owned or controlled by the foreign or domestic parent company were below \$30 million for the reporting period;

(2) Total production of the listed substance for the reporting period was below 45,400 kilograms (100,000 pounds) at the plant site.

(d) Persons are not subject to reporting under § 712.20 if they manufactured or imported the chemical substance during the reporting period only in the following forms:

(1) As a byproduct that was not used or sold or that was formed as described in 40 CFR 710.4(d) (3) through (7).

(2) As a non-isolated intermediate.

(3) As an impurity.

[47 FR 26998, June 22, 1982; 47 FR 28382, June 30, 1982]

### § 712.28 Form and instructions.

(a) Manufacturers and importers subject to this subpart must submit a single EPA Form No. 7710-35, "Manufacturer's Report—Preliminary Assessment Information," for each plant site manufacturing or importing a chemical substance listed in § 712.30.

(b) Reporting companies may submit their reports through individual plant sites or company headquarters as they choose. A separate form must be submitted for each plant site manufacturing the chemical substance.

(c) You must submit forms by one of the following methods:

(1) Mail, preferably certified, to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: 8(a) PAIR Reporting.

(2) Hand delivery to OPPT Document Control Office (DCO), EPA East, Rm. 6428, 1201 Constitution Ave., NW., Washington, DC, ATTN: 8(a) PAIR Reporting. The DCO is open from 8 a.m. to 4 p.m., Monday through Friday, excluding legal holidays. The telephone number for the DCO is (202)564-8930.

(d) Form 7710-35, Manufacturer's Report—Preliminary Assessment Information or PAIR form and instructions

may be obtained by telephoning or writing the Environmental Assistance Division. The telephone number and the address of the Environmental Assistance Division is: Phone Number (202) 554-1404, TDD (202) 554-0551. Address: Environmental Assistance Division (7406), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460.

[47 FR 26998, June 22, 1982, as amended at 52 FR 20083, May 29, 1987; 53 FR 12523, Apr. 15, 1988; 60 FR 31921, June 19, 1995; 60 FR 34463, July 3, 1995; 71 FR 47126, Aug. 16, 2006]

### § 712.30 Chemical lists and reporting periods.

(a)(1) Persons subject to this subpart B must submit a Preliminary Assessment Information Manufacturer's Report for each chemical substance or mixture that is listed or designated in this section.

(2) Unless a respondent has already prepared a Manufacturer's Report in conformity with conditions set forth in paragraph (a)(3) of this section, the information in each Manufacturer's Report must cover the respondent's latest complete corporate fiscal year as of the effective date. The effective date will be 30 days after the FEDERAL REGISTER publishes a rule amendment making the substance or mixture subject to this subpart B.

(3) Persons subject to this subpart B need not comply with the requirements of paragraph (a)(2) of this section if they meet either one of the following conditions:

(i) The respondent has previously and voluntarily provided EPA with a Manufacturer's Report on a chemical substance or mixture subject to this subpart B, which contains data for a one-year period ending no more than three years prior to the effective date described in paragraph (a)(2) of this section. Respondents meeting this condition must notify EPA by letter of their desire to have the voluntary submission used in lieu of a current data submission and must verify the completeness and current accuracy of the voluntarily submitted data. Such letters must contain the following language: "I hereby certify that, to the best of

my knowledge and belief, all information entered on this form is complete and accurate. I agree to permit access to, and the copying of records by, a duly authorized representative of the EPA Administrator, in accordance with the Toxic Substances Control Act, to document any information reported on the form." Notification letters must be submitted prior to the reporting deadline.

(ii) The respondent has previously submitted a Manufacturer's Report on a chemical substance or mixture subject to this subpart B to the Interagency Testing Committee, but not to EPA, and that Report contained data for a one-year period ending less than three years prior to the effective date described in paragraph (a)(2) of this section. Respondents meeting this condition must submit a copy of the Manufacturer's Report to EPA, and must submit an accompanying letter notifying EPA of the respondent's intent that the submission be used in lieu of a current Manufacturer's Report. The notification letter must verify the completeness and current accuracy of the voluntarily submitted data. Such a letter must contain the following language: "I hereby certify that, to the best of my knowledge and belief, all information entered on this form is complete and accurate. I agree to permit access to, and the copying of records by, a duly authorized representative of the EPA Administrator, in accordance with the Toxic Substances Control Act, to document any information reported on the form." The submission must be made prior to the reporting deadline.

(b) Except as provided in paragraph (c) of this section, chemical substances and designated mixtures will be added after a notice of proposed amendment of this subpart is published in the FEDERAL REGISTER. There will be a 30 day public comment period on each notice; after consideration of the comments, a final amendment will identify the substances and mixtures added.

(c)(1) Chemical substances, mixtures, and categories of substances or mixtures that have been added by the Interagency Testing Committee, established under section 4(e) of TSCA, to the section 4(e) Priority List, for testing consideration by the Agency, will

be added to this section 30 days after EPA issues for publication in the FEDERAL REGISTER a rule amendment listing these chemical substances, mixtures and categories. A Preliminary Assessment Information—Manufacturer's Report must be submitted for each chemical substance and mixture within 60 days after the effective date of the listing. At the discretion of the Assistant Administrator for Prevention, Pesticides and Toxic Substances, a listed substance, mixture or category may be withdrawn, for good cause, from the rule's reporting requirements prior to the effective date. Any information submitted showing why a substance, mixture or category should be removed from the rule must be received by EPA within 14 days after the date of publication of the notice under this paragraph. If a substance, mixture or category is removed, a FEDERAL REGISTER notice announcing this decision will be published no later than the effective date of the amendment.

(2) You must submit information by one of the following methods:

(i) Mail, preferably certified, to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: 8(a) Auto-ITC.

(ii) Hand delivery to OPPT Document Control Office (DCO), EPA East, Rm. 6428, 1201 Constitution Ave., NW., Washington, DC, ATTN: 8(a) Auto-ITC. Reporting. The DCO is open from 8 a.m. to 4 p.m., Monday through Friday, excluding legal holidays. The telephone number for the DCO is (202)564-8930.

(d) Manufacturers and importers of the substances listed below must submit a Preliminary Assessment Information Manufacturer's Report for each site at which they manufacture or import each substance by the reporting date shown in the table below. The substances are listed in Chemical Abstracts Service Registry Number order. Typically EPA lists the trivial or common name first, then, following the symbol "- -", EPA lists the substance by its TSCA Chemical Substance Inventory name. Whenever EPA lists a single name, the name may be either

**Environmental Protection Agency**

**§ 712.30**

the TSCA Chemical Substance Inventory name, a trivial name, or a common name. Generally, when a single name is listed, it is the TSCA Chemical Substances Inventory name.

| CAS No.    | Substance   | Effective date | Reporting date |
|------------|---|----------------|----------------|
| 78-10-4    | Ethyl silicate  | 8/23/00        | 10/23/00       |
| 90-30-2    | N-Phenyl-1-naphthylamine  | 9/30/91        | 11/27/91       |
| 100-40-3   | 4-Vinylcyclohexene  | 1/11/90        | 3/12/90        |
| 108-95-5   | Thiophenol  | 1/26/94        | 3/28/94        |
| 109-87-5   | Methylal  | 8/23/00        | 10/23/00       |
| 118-79-6   | 2,4,6-tribromophenol  | 1/11/90        | 3/12/90        |
| 133-49-3   | Pentachlorothiophenol   | 8/27/01        | 10/24/01       |
| 136-35-6   | 1-Triazene, 1,3-diphenyl-   | 7/11/03        | 9/9/03         |
| 143-33-9   | Sodium cyanide  | 10/29/90       | 12/27/90       |
| 496-46-8   | Glycoluril  | 8/23/00        | 10/23/00       |
| 632-79-1   | Tetrabromophthalic anhydride  | 1/11/90        | 3/12/90        |
| 637-92-3   | Ethyl tert-butyl ether  | 12/28/94       | 2/27/95        |
| 994-05-8   | Tert-amyl methyl ether  | 12/28/94       | 2/27/95        |
| 1163-19-5  | Decabromodiphenyl ether   | 1/11/90        | 3/12/90        |
| 1198-55-6  | Tetrachloropyrocatechol   | 8/27/01        | 10/24/01       |
| 1806-24-2  | p-toluidine, 5-chloro-.alpha.,.alpha.,.alpha.-trifluoro-2-nitro-N-phenyl-                   | 8/27/01        | 10/24/01       |
| 3194-55-6  | Hexabromocyclododecane  | 1/11/90        | 3/12/90        |
| 3278-89-5  | Benzene, 1,3,5-tribromo-2-(2-propenyloxy)-  | 7/11/03        | 9/9/03         |
| 3296-90-0  | Dibromoneopentyl glycol   | 1/11/90        | 3/12/90        |
| 12185-10-3 | White phosphorus  | 1/26/94        | 3/28/94        |
| 16691-43-3 | 3-Amino-5-mercapto-1,2,4-triazole   | 8/23/00        | 10/23/00       |
| 29091-20-1 | Benzenamine, 3-chloro-2,6-dinitro-N,N-dipropyl-4-(trifluoromethyl)-                         | 7/11/03        | 9/9/03         |
| 32534-81-9 | Pentabromodiphenyl ether  | 1/11/90        | 3/12/90        |
| 32536-52-0 | Octabromodiphenyl ether   | 1/11/90        | 3/12/90        |
| 32588-76-4 | Ethylene Bis-(tetrabromophthalimide)  | 1/11/90        | 3/12/90        |
| 37853-59-1 | 1,2-Bis(tribromophenoxy) ethane   | 1/11/90        | 3/12/90        |
| 41291-34-3 | Ethylene(5,6-dibromonorbornane-2,3-dicarboximide)   | 1/11/90        | 3/12/90        |
| 52907-07-0 | Ethylene bis(5,6-dibromonorbornane-2,3-dicarboximide)                                       | 1/26/94        | 3/28/94        |
| 57137-10-7 | Tribrominated polystyrene   | 1/11/90        | 3/12/90        |
| 61262-53-1 | Ethylene bis(pentabromophenoxide)   | 1/11/90        | 3/12/90        |
| 68928-76-7 | Stannane, dimethylbis[(1-oxoneodecyl)oxy]-  | 7/11/03        | 9/9/03         |
| 88185-22-2 | Benzoic acid, 3-[2-chloro-4-(trifluoromethyl)phenoxy]-, 2-ethoxy-1-methyl-2-oxoethyl ester. | 8/27/01        | 10/24/01       |

(e) Manufacturers and importers of the substances listed below by category must submit a Preliminary Assessment Information Manufacturers Report for each site at which they manufacture or import each substance by the reporting

date shown in the table below. The categories are listed in alphabetic order with the chemical substances within each category listed by ascending numerical CAS number.

| CAS No.   | Substance   | Effective date | Reporting date |
|-----------|---|----------------|----------------|
| Aldehydes |   |                |                |
| 66-77-3   | 1-Naphthalenecarboxaldehyde                                     | 9/30/91        | 11/27/91       |
| 75-07-0   | Acetaldehyde  | 9/30/91        | 11/27/91       |
| 75-87-6   | Acetaldehyde, trichloro-  | 9/30/91        | 11/27/91       |
| 78-84-2   | Propanal, 2-methyl-   | 9/30/91        | 11/27/91       |
| 78-85-3   | 2-Propenal, 2-methyl-   | 9/30/91        | 11/27/91       |
| 80-54-6   | Benzenepropanal,4-(1,1-dimethylethyl)-.alpha.-methyl-           | 9/30/91        | 11/27/91       |
| 84-83-3   | Acetaldehyde, (1,3-dihydro-1,3,3-trimethyl-2H-indol-2-ylidene). |                |                |
| 89-98-5   | Benzaldehyde, 2-chloro-   | 9/30/91        | 11/27/91       |
| 90-02-8   | Benzaldehyde, 2-hydroxy-  | 9/30/91        | 11/27/91       |
| 93-02-7   | Benzaldehyde, 2,5-dimethoxy-                                    | 9/30/91        | 11/27/91       |
| 93-53-8   | Benzeneacetaldehyde, .alpha.-methyl-                            | 9/30/91        | 11/27/91       |
| 95-01-2   | Benzaldehyde, 2,4-dihydroxy-                                    | 9/30/91        | 11/27/91       |
| 97-51-8   | Benzaldehyde, 2-hydroxy-5-nitro-                                | 9/30/91        | 11/27/91       |
| 98-01-1   | 2-Furancarboxaldehyde   | 9/30/91        | 11/27/91       |
| 98-03-3   | 2-Thiophenecarboxaldehyde                                       | 9/30/91        | 11/27/91       |
| 100-10-7  | Benzaldehyde, 4-(dimethylamino)-                                | 9/30/91        | 11/27/91       |
| 100-50-5  | 3-Cyclohexene-1-carboxaldehyde                                  | 9/30/91        | 11/27/91       |
| 100-52-7  | Benzaldehyde  | 9/30/91        | 11/27/91       |
| 101-39-3  | 2-Propenal, 2-methyl-3-phenyl-                                  | 9/30/91        | 11/27/91       |

| CAS No.    | Substance   | Effective date | Reporting date |
|------------|---|----------------|----------------|
| Aldehydes  |   |                |                |
| 101-86-0   | Octanal, 2-(phenylmethylene)- .....                                     | 9/30/91        | 11/27/91       |
| 103-95-7   | Benzenepropional, alpha-methyl-4-(1-methylethyl)- .....                 | 9/30/91        | 11/27/91       |
| 104-09-6   | Benzeneacetaldehyde, 4-methyl- .....                                    | 9/30/91        | 11/27/91       |
| 104-55-2   | 2-Propenal, 3-phenyl- .....   | 9/30/91        | 11/27/91       |
| 104-87-0   | Benzaldehyde, 4-methyl- .....   | 9/30/91        | 11/27/91       |
| 104-88-1   | Benzaldehyde, 4-chloro- .....   | 9/30/91        | 11/27/91       |
| 106-23-0   | 6-Octenal, 3,7-dimethyl- .....  | 9/30/91        | 11/27/91       |
| 106-26-3   | 2,6-Octadienal, 3,7-dimethyl-, (Z)- .....                               | 9/30/91        | 11/27/91       |
| 106-72-9   | 5-Heptenal, 2,6-dimethyl- .....   | 9/30/91        | 11/27/91       |
| 107-02-8   | 2-Propenal .....  | 9/30/91        | 11/27/91       |
| 107-20-0   | Acetaldehyde, chloro- .....   | 9/30/91        | 11/27/91       |
| 107-22-2   | Ethanedial .....  | 9/30/91        | 11/27/91       |
| 107-75-5   | Octanal, 7-hydroxy-3,7-dimethyl- .....                                  | 9/30/91        | 11/27/91       |
| 110-41-8   | Undecanal, 2-methyl- .....  | 9/30/91        | 11/27/91       |
| 110-62-3   | Pentanal .....  | 9/30/91        | 11/27/91       |
| 111-30-8   | Pentanedial .....   | 9/30/91        | 11/27/91       |
| 111-71-7   | Heptanal .....  | 9/30/91        | 11/27/91       |
| 112-31-2   | Decanal .....   | 9/30/91        | 11/27/91       |
| 112-44-7   | Undecanal .....   | 9/30/91        | 11/27/91       |
| 112-45-8   | 10-Undecenal .....  | 9/30/91        | 11/27/91       |
| 112-54-9   | Dodecanal .....   | 9/30/91        | 11/27/91       |
| 120-14-9   | Benzaldehyde, 3,4-dimethoxy- .....                                      | 9/30/91        | 11/27/91       |
| 120-21-8   | Benzaldehyde, 4-(diethylamino)- .....                                   | 9/30/91        | 11/27/91       |
| 120-57-0   | 1,3-Benzodioxole-5-carboxaldehyde .....                                 | 9/30/91        | 11/27/91       |
| 121-32-4   | Benzaldehyde, 3-ethoxy-4-hydroxy- .....                                 | 9/30/91        | 11/27/91       |
| 121-33-5   | Benzaldehyde, 4-hydroxy-3-methoxy- .....                                | 9/30/91        | 11/27/91       |
| 122-40-7   | Heptanal, 2-(phenylmethylene)- .....                                    | 9/30/91        | 11/27/91       |
| 122-78-1   | Benzeneacetaldehyde .....   | 9/30/91        | 11/27/91       |
| 123-05-7   | Hexanal, 2-ethyl- .....   | 9/30/91        | 11/27/91       |
| 123-08-0   | Benzaldehyde, 4-hydroxy- .....  | 9/30/91        | 11/27/91       |
| 123-11-5   | Benzaldehyde, 4-methoxy- .....  | 9/30/91        | 11/27/91       |
| 123-38-6   | Propanal .....  | 9/30/91        | 11/27/91       |
| 124-13-0   | Octanal .....   | 9/30/91        | 11/27/91       |
| 124-19-6   | Nonanal .....   | 9/30/91        | 11/27/91       |
| 126-15-8   | 4a(4H)-Dibenzofurancarboxaldehyde, 1,5a,6,9,9a,9b-hexahydro- .....      | 9/30/91        | 11/27/91       |
| 135-02-4   | Benzaldehyde, 2-methoxy- .....  | 9/30/91        | 11/27/91       |
| 141-27-5   | 2,6-Octadienal, 3,7-dimethyl-, (E)- .....                               | 9/30/91        | 11/27/91       |
| 143-14-6   | 9-Undecenal .....   | 9/30/91        | 11/27/91       |
| 455-19-6   | Benzaldehyde, 4-(trifluoromethyl)- .....                                | 9/30/91        | 11/27/91       |
| 505-57-7   | 02-Hexenal .....  | 9/30/91        | 11/27/91       |
| 552-89-6   | Benzaldehyde, 2-nitro- .....  | 9/30/91        | 11/27/91       |
| 590-86-3   | Butanal, 3-methyl- .....  | 9/30/91        | 11/27/91       |
| 597-31-9   | Propanal, 3-hydroxy-2,2-dimethyl- .....                                 | 9/30/91        | 11/27/91       |
| 939-97-9   | Benzaldehyde, 4-(1,1-dimethylethyl)- .....                              | 9/30/91        | 11/27/91       |
| 1121-60-4  | 2-Pyridinecarboxaldehyde .....  | 9/30/91        | 11/27/91       |
| 1200-14-2  | Benzaldehyde, 4-butyl .....   | 9/30/91        | 11/27/91       |
| 1331-92-6  | 2-Propenal, 3-phenyl-, monopentyl deriv. ....                           | 9/30/91        | 11/27/91       |
| 1334-78-7  | Benzaldehyde, methyl- .....   | 9/30/91        | 11/27/91       |
| 1423-46-7  | 3-Cyclohexene-1-carboxaldehyde, 2,4,6-trimethyl- .....                  | 9/30/91        | 11/27/91       |
| 1504-74-1  | 2-Propenal, 3-(2-methoxyphenyl)- .....                                  | 9/30/91        | 11/27/91       |
| 2591-86-8  | 1-Piperidinecarboxaldehyde .....  | 9/30/91        | 11/27/91       |
| 3132-99-8  | Benzaldehyde, 3-bromo- .....  | 9/30/91        | 11/27/91       |
| 3268-49-3  | Propanal, 3-(methylthio)- .....   | 9/30/91        | 11/27/91       |
| 3613-30-7  | Octanal, 7-methoxy-3,7-dimethyl- .....                                  | 9/30/91        | 11/27/91       |
| 4501-58-0  | 3-Cyclopentene-1-acetaldehyde, 2,2,3-trimethyl- .....                   | 9/30/91        | 11/27/91       |
| 5435-64-3  | Hexanal, 3,5,5-trimethyl- .....   | 9/30/91        | 11/27/91       |
| 5780-07-4  | 1,3-Benzodioxole-5-carboxaldehyde, 7-methoxy- .....                     | 9/30/91        | 11/27/91       |
| 5949-05-3  | 6-Octenal, 3,7-dimethyl-, (S)- .....                                    | 9/30/91        | 11/27/91       |
| 5988-91-0  | Octanal, 3,7-dimethyl- .....  | 9/30/91        | 11/27/91       |
| 10031-82-0 | Benzaldehyde, 4-ethoxy- .....   | 9/30/91        | 11/27/91       |
| 13586-68-0 | 2-Propenal, 3- 4-(1,1-dimethylethyl)phenyl-2-methyl- .....              | 9/30/91        | 11/27/91       |
| 17754-90-4 | Benzaldehyde, 4-(diethylamino)-2-hydroxy- .....                         | 9/30/91        | 11/27/91       |
| 26266-68-2 | Hexenal, 2-ethyl- .....   | 9/30/91        | 11/27/91       |
| 27939-60-2 | 3-Cyclohexene-1-carboxaldehyde, dimethyl- .....                         | 9/30/91        | 11/27/91       |
| 28602-27-9 | Benzaldehyde, (dimethylamino)- .....                                    | 9/30/91        | 11/27/91       |
| 31906-04-4 | 3-Cyclohexene-1-carboxaldehyde, 4-(4-hydroxy-4-methylpentyl)- .....     | 9/30/91        | 11/27/91       |
| 37677-14-8 | 3-Cyclohexene-1-carboxaldehyde, 4-(4-methyl-3-pentenyl)- .....          | 9/30/91        | 11/27/91       |
| 39515-51-0 | Benzaldehyde, 3-phenoxy- .....  | 9/30/91        | 11/27/91       |
| 52475-86-2 | 3-Cyclohexene-1-carboxaldehyde, 1-methyl-4-(4-methyl-3-pentenyl)- ..... | 9/30/91        | 11/27/91       |
| 66327-54-6 | 3-Cyclohexene-1-carboxaldehyde, 1-methyl-4-(4-methylpentyl)- .....      | 9/30/91        | 11/27/91       |

Environmental Protection Agency

§ 712.30

| CAS No.   | Substance   | Effective date | Reporting date |
|---|---|----------------|----------------|
| Aldehydes   |   |                |                |
| Alkyl-, Chloro-, and Hydroxymethyl Diaryl Ethers            |   |                |                |
| 3061-36-7   | 1,4-Diphenoxybenzene .....  | 04/12/93       | 06/10/93       |
| 3586-14-9   | Benzene, 1-methyl-3-phenoxy- .....  | 04/12/93       | 06/10/93       |
| 13826-35-2  | Benzenemethanol, 3-phenoxy-, .....  | 04/12/93       | 06/10/93       |
| 28299-41-4  | Benzene, 1,1',-oxybis[methyl- .....   | 04/12/93       | 06/10/93       |
| 28984-89-6  | 1,1'-Biphenyl, phenoxy- .....   | 04/12/93       | 06/10/93       |
| 42874-96-4  | 2-Chloro-1-(3-methylphenoxy)-4-(trifluoromethyl)benzene .....                     | 04/12/93       | 06/10/93       |
| 50594-77-9  | Phenol, 3-[2-chloro-4-(trifluoromethyl)phenoxy]-, acetate .....                   | 04/12/93       | 06/10/93       |
| 50789-44-1  | Benzenemethanol, 3-phenoxy-, acetate .....  | 04/12/93       | 06/10/93       |
| 51632-16-7  | Benzene, 1-(bromomethyl)-3-phenoxy- .....   | 04/12/93       | 06/10/93       |
| 61702-88-3  | Benzene, 1,1'-oxybis[(1,1,3,3-tetramethylbutyl)- .....                            | 04/12/93       | 06/10/93       |
| 63734-62-3  | Benzoic acid, 3-[2-chloro-4-(trifluoromethyl)phenoxy]-, .....                     | 04/12/93       | 06/10/93       |
| 69834-19-1  | Benzene, 1,1'-oxybis[dodecyl- .....   | 04/12/93       | 06/10/93       |
| 72252-48-3  | Benzoic acid, 3-[2-chloro-4-(trifluoromethyl)phenoxy]-, potassium salt .....      | 04/12/93       | 06/10/93       |
| Alkylphenols, Alkylphenol ethoxylates, and Polyalkylphenols |   |                |                |
| 80-46-6   | 4-tert-Pentylphenol .....   | 3/29/96        | 5/29/96        |
| 88-18-6   | 2-tert-Butylphenol .....  | 3/29/96        | 5/29/96        |
| 94-06-4   | 4-(1-Methylbutyl)phenol .....   | 3/29/96        | 5/29/96        |
| 98-54-4   | 4-tert-Butylphenol .....  | 3/29/96        | 5/29/96        |
| 99-71-8   | 4-sec-Butylphenol .....   | 3/29/96        | 5/29/96        |
| 104-40-5  | 4-Nonylphenol .....   | 3/29/96        | 5/29/96        |
| 104-43-8  | 4-Dodecylphenol .....   | 3/29/96        | 5/29/96        |
| 136-81-2  | Phenol, 2-pentyl- .....   | 8/4/00         | 10/3/00        |
| 140-66-9  | Phenol, 4-(1,1,3,3-tetramethylbutyl)- .....                                       | 8/4/00         | 10/3/00        |
| 949-13-3  | 2-Octylphenol .....   | 3/29/96        | 5/29/96        |
| 1300-16-9   | Nonylphenol (mixed isomers) .....   | 3/29/96        | 5/29/96        |
| 1322-69-6   | (1,1,3,3-Tetramethylbutyl)phenol (mixed isomers) .....                            | 3/29/96        | 5/29/96        |
| 1331-57-3   | Dodecylphenol (mixed isomers) .....   | 3/29/96        | 5/29/96        |
| 1638-22-8   | 4-n-Butylphenol .....   | 3/29/96        | 5/29/96        |
| 1806-26-4   | 4-Octylphenol .....   | 3/29/96        | 5/29/96        |
| 1987-50-4   | Phenol, 4-heptyl- .....   | 8/4/00         | 10/3/00        |
| 2315-66-4   | Decaethylene glycol 4-isooctylphenyl ether .....                                  | 3/29/96        | 5/29/96        |
| 2446-69-7   | Phenol, 4-hexyl- .....  | 8/4/00         | 10/3/00        |
| 2497-58-7   | Hexaethylene glycol 4-isooctylphenyl ether .....                                  | 3/29/96        | 5/29/96        |
| 2589-78-8   | Phenol, 4-hexadecyl- .....  | 8/4/00         | 10/3/00        |
| 3180-09-4   | 2-Butylphenol .....   | 3/29/96        | 5/29/96        |
| 3279-27-4   | Phenol, 2-(1,1-dimethylpropyl)- .....   | 8/4/00         | 10/3/00        |
| 3884-95-5   | 2-(1,1,3,3-Tetramethylbutyl)phenol .....  | 3/29/96        | 5/29/96        |
| 9002-93-1   | Polyethylene glycol 4-(tert-octyl)phenyl ether .....                              | 3/29/96        | 5/29/96        |
| 9004-87-9   | Poly(oxy-1,2-ethanediyl), $\alpha$ -(isooctylphenyl)- $\omega$ -hydroxy- .....    | 8/4/00         | 10/3/00        |
| 9014-92-0   | Poly(oxy-1,2-ethanediyl), $\alpha$ -(dodecylphenyl)- $\omega$ -hydroxy- .....     | 8/4/00         | 10/3/00        |
| 9036-19-5   | Polyethylene glycol mono(octyl)phenyl ether .....                                 | 3/29/96        | 5/29/96        |
| 9063-89-2   | Poly(oxy-1,2-ethanediyl), $\alpha$ -(octylphenyl)- $\omega$ -hydroxy- .....       | 8/4/00         | 10/3/00        |
| 11066-49-2  | Isononylphenol (mixed isomers) .....  | 3/29/96        | 5/29/96        |
| 14938-35-3  | 4-Pentylphenol .....  | 3/29/96        | 5/29/96        |
| 17404-66-9  | 4-(1-Methyloctyl)phenol .....   | 3/29/96        | 5/29/96        |
| 25154-52-3  | Nonylphenol (mixed isomers) .....   | 3/29/96        | 5/29/96        |
| 25401-86-9  | Phenol, 2-hexadecyl- .....  | 8/4/00         | 10/3/00        |
| 25735-67-5  | Phenol, 4-sec-pentyl- .....   | 8/4/00         | 10/3/00        |
| 26401-47-8  | Poly(oxy-1,2-ethanediyl), $\alpha$ -(4-dodecylphenyl)- $\omega$ -hydroxy- .....   | 8/4/00         | 10/3/00        |
| 26401-74-1  | Phenol, 2-sec-pentyl- .....   | 8/4/00         | 10/3/00        |
| 27157-66-0  | Phenol, decyl- .....  | 8/4/00         | 10/3/00        |
| 27178-34-3  | tert-Butylphenol (mixed isomers) .....  | 3/29/96        | 5/29/96        |
| 27193-28-8  | (1,1,3,3-Tetramethylbutyl)phenol (mixed isomers) .....                            | 3/29/96        | 5/29/96        |
| 27193-86-8  | Dodecylphenol (mixed isomers) .....   | 3/29/96        | 5/29/96        |
| 27985-70-2  | (1-Methylheptyl)phenol (mixed isomers) .....                                      | 3/29/96        | 5/29/96        |
| 29932-96-5  | (1,1,3,3-Tetramethylbutyl)phenol (mixed isomers) .....                            | 3/29/96        | 5/29/96        |
| 30105-54-5  | (1,1,3,3-Tetramethylbutyl)phenol (mixed isomers) .....                            | 3/29/96        | 5/29/96        |
| 31195-95-6  | Isobutylphenol (mixed isomers) .....  | 3/29/96        | 5/29/96        |
| 54932-78-4  | 4-(2,2,3,3-Tetramethylbutyl)phenol .....  | 3/29/96        | 5/29/96        |
| 59911-95-4  | Poly(oxy-1,2-ethanediyl), $\alpha$ -(4-hexadecylphenyl)- $\omega$ -hydroxy- ..... | 8/4/00         | 10/3/00        |
| 61723-87-3  | Poly(oxy-1,2-ethanediyl), $\alpha$ -(tridecylphenyl)- $\omega$ -hydroxy- .....    | 8/4/00         | 10/3/00        |
| 62744-41-6  | (1,1,3,3-Tetramethylbutyl)phenol (mixed isomers) .....                            | 3/29/96        | 5/29/96        |
| 68081-86-7  | Phenol, nonyl derivs. ....  | 8/4/00         | 10/3/00        |
| 68784-24-7  | Phenol, C18-30-alkyl derivs. ....   | 8/4/00         | 10/3/00        |
| 68891-67-8  | Phenol, polypropene derivs. ....  | 8/4/00         | 10/3/00        |
| 68908-55-4  | Phenol, polybutene derivs. ....   | 8/4/00         | 10/3/00        |
| 68954-70-1  | Phenol, polyethyl derivs. ....  | 8/4/00         | 10/3/00        |

| CAS No.   | Substance   | Effective date | Reporting date |
|---|---|----------------|----------------|
| Alkylphenols, Alkylphenol ethoxylates, and Polyalkylphenols |   |                |                |
| 68987–90–6  | Poly(oxy-1,2-ethanediyl), $\alpha$ -(octylphenyl)- $\omega$ -hydroxy-, branched ..... | 3/29/96        | 5/29/96        |
| 70682–80–3  | Phenol, tetradecyl- .....   | 8/4/00         | 10/3/00        |
| 71902–25–5  | Phenol, octenylated .....   | 8/4/00         | 10/3/00        |
| 72624–02–3  | Phenol, heptyl derivs. ....   | 8/4/00         | 10/3/00        |
| 74499–35–7  | Phenol, (tetrapropenyl) derivs. ....  | 8/4/00         | 10/3/00        |
| 84605–25–4  | Phenol, 1-methylhexyl derivs. ....  | 8/4/00         | 10/3/00        |
| 84852–15–3  | Branched 4-nonylphenol (mixed isomers) .....  | 3/29/96        | 5/29/96        |
| 91672–41–2  | Phenol, 2-nonyl-, branched .....  | 8/4/00         | 10/3/00        |
| 112375–88–9   | Phenol, polyisobutylene derivs. ....  | 8/4/00         | 10/3/00        |
| 112375–89–0   | Phenol, poly(2,4,4-trimethylpentene) derivs .....                                     | 8/4/00         | 10/3/00        |
| Alkyl phosphates  |   |                |                |
| 78–40–0   | Phosphoric acid, triethyl ester .....   | 10/29/90       | 12/27/90       |
| 78–42–2   | Phosphoric acid, tris(2-ethylhexyl)ester .....  | 10/29/90       | 12/27/90       |
| 78–51–3   | Ethanol, 2-butoxy-, phosphate (3:1) .....   | 10/29/90       | 12/27/90       |
| 107–66–4  | Phosphoric acid, dibutyl ester .....  | 10/29/90       | 12/27/90       |
| 126–71–6  | Phosphoric acid, tris(2-methylpropyl) ester .....                                     | 10/29/90       | 12/27/90       |
| 126–73–8  | Phosphoric acid tributyl ester .....  | 10/29/90       | 12/27/90       |
| 298–07–7  | Phosphoric acid, bis(2-ethylhexyl)ester .....   | 10/29/90       | 12/27/90       |
| 812–00–0  | Phosphoric acid, monomethyl ester .....   | 10/29/90       | 12/27/90       |
| 1070–03–7   | Phosphoric acid, mono(2-ethylhexyl)ester .....  | 10/29/90       | 12/27/90       |
| 1498–51–7   | Phosphorodichloridic acid, ethylester .....   | 10/29/90       | 12/27/90       |
| 1623–15–0   | Phosphoric acid, monobutyl ester .....  | 10/29/90       | 12/27/90       |
| 1623–24–1   | Phosphoric acid, mono(1-methylethyl)ester .....                                       | 10/29/90       | 12/27/90       |
| 2958–09–0   | Phosphoric acid, monoctadecyl ester .....   | 10/29/90       | 12/27/90       |
| 3900–04–7   | Phosphoric acid, monohexyl ester .....  | 10/29/90       | 12/27/90       |
| 3991–73–9   | Phosphoric acid, monoocetyl ester .....   | 10/29/90       | 12/27/90       |
| 7057–92–3   | Phosphoric acid, didodecyl ester .....  | 10/29/90       | 12/27/90       |
| 7332–46–9   | Ethanol, 2-(2-butoxyethoxy)-, phosphate (3:1) .....                                   | 10/29/90       | 12/27/90       |
| 12645–31–7  | Phosphoric acid, 2-ethylhexyl ester .....   | 10/29/90       | 12/27/90       |
| 12751–23–4  | Phosphoric acid, dodecyl ester .....  | 10/29/90       | 12/27/90       |
| 27215–10–7  | Phosphoric acid, diisooctyl ester .....   | 10/29/90       | 12/27/90       |
| Brominated flame retardants                                 |   |                |                |
| 87–10–5   | Benzamide, 3,5-dibromo-N-(4-bromophenyl)-2-hydroxy- .....                             | 10/29/90       | 12/27/90       |
| 87–83–2   | Benzene, pentabromomethyl- .....  | 10/29/90       | 12/27/90       |
| 87–84–3   | Cyclohexane, 1,2,3,4,5-pentabromo-6-chloro- .....                                     | 10/29/90       | 12/27/90       |
| 96–13–9   | 1-Propanol, 2,3-dibromo- .....  | 10/29/90       | 12/27/90       |
| 593–60–2  | Ethene, bromo- .....  | 10/29/90       | 12/27/90       |
| 615–58–7  | Phenol, 2,4-dibromo- .....  | 10/29/90       | 12/27/90       |
| 4162–45–2   | Ethanol, 2,2'-((1-methylethylidene)bis((2,6-dibromo-4,1-phenylene)oxy))bis- .....     | 10/29/90       | 12/27/90       |
| 25327–89–3  | Benzene, 1,1'-(1-methylethylidene)bis(3,5-dibromo-4-(2-propenyloxy)- .....            | 10/29/90       | 12/27/90       |
| 30554–72–4  | Cyclohexane, tetrabromodichloro- .....  | 10/29/90       | 12/27/90       |
| 30554–73–5  | Cyclohexane, tribromotrichloro- .....   | 10/29/90       | 12/27/90       |
| 36483–57–5  | 1-Propanol, 2,2-dimethyl-, tribromo deriv. ....                                       | 10/29/90       | 12/27/90       |
| 55205–38–4  | 2-Propenoic acid, (1-methylethylidene)bis(2,6-dibromo-4,1-phenylene) ester .....      | 10/29/90       | 12/27/90       |
| 68955–41–9  | Alkanes, C10-18, bromochloro- .....   | 10/29/90       | 12/27/90       |
| 69882–11–7  | Phenol, 2,4(or 2,6)-dibromo-, homopolymer .....                                       | 10/29/90       | 12/27/90       |
| 88497–56–7  | Benzene, ethenyl-, homopolymer, brominated .....                                      | 10/29/90       | 12/27/90       |
| Chloralkyl phosphates                                       |   |                |                |
| 34621–99–3  | 1,2-Ethanediyltetrakis(2-chloro-1-methylethylene) phosphate .....                     | 6/14/93        | 8/12/93        |
| 38051–10–4  | 2,2-Bis(chloromethyl)-1,3-propanediyltetrakis(2-chloroethyl) phosphate .....          | 6/14/93        | 8/12/93        |
| 53461–82–8  | Oxydi-2,1-ethanediyltetrakis(2-chloroethyl) phosphate .....                           | 6/14/93        | 8/12/93        |
| 76649–15–5  | 2-Chloro-1-methylethylbis(2-chloropropyl) phosphate.                                  |                |                |
| Cyanoacrylates  |   |                |                |
| 137–05–3  | 2-Propenoic acid, 2-cyano-, methyl ester .....  | 1/26/94        | 3/28/94        |
| 1069–55–2   | 2-Propenoic acid, 2-cyano-, isobutyl ester .....                                      | 1/26/94        | 3/28/94        |
| 6197–30–4   | 2-Propenoic acid, 2-cyano-3,3-diphenyl-, 2-ethylhexyl ester .....                     | 1/26/94        | 3/28/94        |
| 6606–65–1   | 2-Propenoic acid, 2-cyano-, butyl ester .....   | 1/26/94        | 3/28/94        |
| 7085–85–0   | 2-Propenoic acid, 2-cyano-, ethyl ester .....   | 1/26/94        | 3/28/94        |
| 7324–02–9   | 2-Propenoic acid, 2-cyano-, 2-propenyl ester .....                                    | 1/26/94        | 3/28/94        |
| 10586–17–1  | 2-Propenoic acid, 2-cyano-, 1-methylethyl ester .....                                 | 1/26/94        | 3/28/94        |
| 21982–43–4  | 2-Propenoic acid, 2-cyano-, ethoxyethyl ester .....                                   | 1/26/94        | 3/28/94        |
| 23023–91–8  | 2-Propenoic acid, 2-cyano-, 2,2,2-trifluoromethyl ester .....                         | 1/26/94        | 3/28/94        |
| 27816–23–5  | 2-Propenoic acid, 2-cyano-, 2-methoxyethyl ester .....                                | 1/26/94        | 3/28/94        |

Environmental Protection Agency

§ 712.30

| CAS No.          | Substance  | Effective date | Reporting date |
|------------------|--|----------------|----------------|
| Cyanoacrylates   |  |                |                |
| 64992-16-1       | Ethanaminium, 2-[[2-cyano-3-[4-(diethylamino)phenyl]-1-oxo-2-propenyl]oxy]-N,N,N-trimethyl-, chloride. | 1/26/94        | 3/28/94        |
| Indium Chemicals |  |                |                |
| 923-34-2         | Triethylindium .....   | 8/27/01        | 10/24/01       |
| 1303-11-3        | Indium arsenide .....  | 8/27/01        | 10/24/01       |
| 1312-41-0        | Indium antimonide .....  | 8/27/01        | 10/24/01       |
| 1312-43-2        | Indium (III) oxide .....   | 8/27/01        | 10/24/01       |
| 1312-45-4        | Indium (III) telluride .....   | 8/27/01        | 10/24/01       |
| 4194-69-8        | Indium (III) citrate .....   | 8/27/01        | 10/24/01       |
| 7440-74-6        | Indium .....   | 8/27/01        | 10/24/01       |
| 7783-52-0        | Indium (III) fluoride .....  | 8/27/01        | 10/24/01       |
| 10025-82-8       | Indium (III) chloride .....  | 8/27/01        | 10/24/01       |
| 12018-95-0       | Copper indium diselenide .....   | 8/27/01        | 10/24/01       |
| 12030-14-7       | Indium (II) sulfide .....  | 8/27/01        | 10/24/01       |
| 12030-24-9       | Indium (III) sulfide .....   | 8/27/01        | 10/24/01       |
| 12056-07-4       | Indium selenide .....  | 8/27/01        | 10/24/01       |
| 12672-70-7       | Indium chloride .....  | 8/27/01        | 10/24/01       |
| 12672-71-8       | Indium oxide .....   | 8/27/01        | 10/24/01       |
| 13464-82-9       | Indium (III) sulfate .....   | 8/27/01        | 10/24/01       |
| 13465-09-3       | Indium (III) bromide .....   | 8/27/01        | 10/24/01       |
| 13465-10-6       | Indium (I) chloride .....  | 8/27/01        | 10/24/01       |
| 13510-35-5       | Indium (III) iodide .....  | 8/27/01        | 10/24/01       |
| 13709-93-8       | Indium (III) borate .....  | 8/27/01        | 10/24/01       |
| 13770-61-1       | Indium (III) nitrate .....   | 8/27/01        | 10/24/01       |
| 13966-94-4       | Indium (I) iodide .....  | 8/27/01        | 10/24/01       |
| 14166-78-0       | Indium (III) fluoride .....  | 8/27/01        | 10/24/01       |
| 14280-53-6       | Indium (I) bromide .....   | 8/27/01        | 10/24/01       |
| 14405-45-9       | Indium tris(acetylacetonate) .....   | 8/27/01        | 10/24/01       |
| 20661-21-6       | Indium (III) hydroxide .....   | 8/27/01        | 10/24/01       |
| 22398-80-7       | Indium (I) phosphide .....   | 8/27/01        | 10/24/01       |
| 25114-58-3       | Indium (III) acetate .....   | 8/27/01        | 10/24/01       |
| 25617-98-5       | Indium nitride .....   | 8/27/01        | 10/24/01       |
| 27765-48-6       | Indium (III) tetrafluoroborate .....   | 8/27/01        | 10/24/01       |
| 50926-11-9       | Indium tin oxide .....   | 8/27/01        | 10/24/01       |
| 55326-87-9       | Indium hydroxide .....   | 8/27/01        | 10/24/01       |
| 66027-93-8       | Indium (III) sulfamate .....   | 8/27/01        | 10/24/01       |
| 66027-94-9       | Hydroxybis(trifluoroacetato-O)indium .....   | 8/27/01        | 10/24/01       |
| 67816-06-2       | Indium (III) 2-ethylhexanoate .....  | 8/27/01        | 10/24/01       |
| 68310-35-0       | Indium (III) neodecanoate .....  | 8/27/01        | 10/24/01       |
| 71243-84-0       | Indium tin oxide (In <sub>1.69</sub> Sn <sub>0.1502</sub> O <sub>2.85</sub> ) .....                    | 8/27/01        | 10/24/01       |
| IRIS Chemicals   |  |                |                |
| 51-28-5          | 2,4 Dinitrophenol .....  | 9/30/91        | 11/27/91       |
| 95-65-8          | 3,4 Dinethylphenol .....   | 9/30/91        | 11/27/91       |
| Isocyanates      |  |                |                |
| 91-97-4          | 1,1'-Biphenyl, 4,4'-diisocyanato-3,3'-dimethyl- .....  | 10/29/90       | 12/27/90       |
| 100-28-7         | Benzene, 1-isocyanato-4-nitro- .....   | 10/29/90       | 12/27/90       |
| 101-68-8         | Benzene, 1,1'-methylenebis(4-isocyanato- .....   | 10/29/90       | 12/27/90       |
| 102-36-3         | Benzene, 1,2-dichloro-4-isocyanato- .....  | 10/29/90       | 12/27/90       |
| 103-71-9         | Benzene, isocyanato- .....   | 10/29/90       | 12/27/90       |
| 104-12-1         | Benzene, 1-chloro-4-isocyanato- .....  | 10/29/90       | 12/27/90       |
| 104-49-4         | Benzene, 1,4-diisocyanato- .....   | 10/29/90       | 12/27/90       |
| 109-90-0         | Ethane, isocyanato- .....  | 10/29/90       | 12/27/90       |
| 110-78-1         | Propane, 1-isocyanato- .....   | 10/29/90       | 12/27/90       |
| 111-36-4         | Butane, 1-isocyanato- .....  | 10/29/90       | 12/27/90       |
| 112-96-9         | Octadecane, 1-isocyanato- .....  | 10/29/90       | 12/27/90       |
| 123-61-5         | Benzene, 1,3-diisocyanato- .....   | 10/29/90       | 12/27/90       |
| 329-01-1         | Benzene, 1-isocyanato-3-(trifluoromethyl)- .....   | 10/29/90       | 12/27/90       |
| 614-68-6         | Benzene, 1-isocyanato-2-methyl- .....  | 10/29/90       | 12/27/90       |
| 622-58-2         | Benzene, 1-isocyanato-4-methyl- .....  | 10/29/90       | 12/27/90       |
| 624-83-9         | Methane, isocyanato- .....   | 10/29/90       | 12/27/90       |
| 1476-23-9        | 1-Propene, 3-isocyanato- .....   | 10/29/90       | 12/27/90       |
| 2422-91-5        | Benzene, 1,1',1''-methylidynetris(4-isocyanato- .....  | 10/29/90       | 12/27/90       |
| 2493-02-9        | Benzene, 1-bromo-4-isocyanato- .....   | 10/29/90       | 12/27/90       |
| 2909-38-8        | Benzene, 1-chloro-3-isocyanato- .....  | 10/29/90       | 12/27/90       |
| 2949-22-6        | Acetic acid, isocyanato-, ethyl ester .....  | 10/29/90       | 12/27/90       |
| 3173-53-3        | Cyclohexane, isocyanato- .....   | 10/29/90       | 12/27/90       |



| CAS No.   | Substance  | Effective date | Reporting date |
|---|--|----------------|----------------|
| OSHA Chemicals in Need of Dermal Absorption Testing |  |                |                |
| 4035–89–6   | Imidodicarbonic diamide,N,N',2-tris(6-isocyanatohexyl)- .....  | 10/29/90       | 12/27/90       |
| 4098–71–9   | Cyclohexane, 5-isocyanato-1-(isocyanatomethyl)-1,3,3-trimethyl- .....  | 10/29/90       | 12/27/90       |
| 4151–51–3   | Phenol, 4-isocyanato-, phosphorothioate (3:1) (ester) .....  | 10/29/90       | 12/27/90       |
| 5124–30–1   | Cyclohexane, 1,1'-methylenebis(4-isocyanato- .....   | 10/29/90       | 12/27/90       |
| 5873–54–1   | Benzene, 1-isocyanato-2-((4-isocyanatophenyl)methyl)- .....  | 10/29/90       | 12/27/90       |
| 10031–75–1  | Benzene, 1,1'-(diisocyanatomethylene)bis- .....  | 10/29/90       | 12/27/90       |
| 15646–96–5  | Hexane, 1,6-diisocyanato-2,4,4-trimethyl- .....  | 10/29/90       | 12/27/90       |
| 16938–22–0  | Hexane, 1,6-diisocyanato-2,2,4-trimethyl- .....  | 10/29/90       | 12/27/90       |
| 25854–16–4  | Benzene, bis(isocyanatomethyl)- .....  | 10/29/90       | 12/27/90       |
| 26447–40–5  | Benzene, 1,1'-methylenebis(isocyanato- .....   | 10/29/90       | 12/27/90       |
| 26603–40–7  | 1,3,5-Triazine-2,4,6(1H,3H,5H-trione, 1,3,5-tris(3-isocyanatomethylphenyl)- .....                                    | 10/29/90       | 12/27/90       |
| 26747–90–0  | 1,3-Diazetidone-2,4-dione, 1,3-bis(3-isocyanatomethylphenyl)- .....  | 10/29/90       | 12/27/90       |
| 28178–42–9  | Benzene, 2-isocyanato-1,3-bis(1-methylethyl)- .....  | 10/29/90       | 12/27/90       |
| 28556–81–2  | Benzene, 2-isocyanato-1,3-dimethyl- .....  | 10/29/90       | 12/27/90       |
| 30674–80–7  | 2-Propenoic acid, 2-methyl-,2-isocyanatoethyl ester .....  | 10/29/90       | 12/27/90       |
| 34893–92–0  | Benzene, 1,3-dichloro-5-isocyanato- .....  | 10/29/90       | 12/27/90       |
| 68239–06–5  | Cyclohexane, 2-heptyl-3,4-bis(9-isocyanatononyl)-1-pentyl- .....   | 10/29/90       | 12/27/90       |
| 73597–26–9  | 2-Propenoic acid, 2-methyl-, 2-(((5-isocyanato-1,3,3-trimethylcyclohexyl) methyl)amino)carbonyloxy)ethyl ester. .... | 10/29/90       | 12/27/90       |
| Methyl ethylene glycol ethers and esters            |  |                |                |
| 3121-61-7   | Ethylene glycol monomethyl ether acrylate .....  | 1/26/94        | 3/28/94        |
| 23783-42-8  | Tetraethylene glycol monomethyl ether .....  | 1/26/94        | 3/28/94        |
| Nonylphenol ethoxylates                             |  |                |                |
| 7311–27–5   | Ethanol, 2-[2-[2-(p-nonylphenoxy)ethoxy]ethoxy]ethoxy]- .....  | 2/10/00        | 4/10/00        |
| 9016–45–9   | Poly(oxy-1,2-ethanediyl), alpha-(nonylphenyl)-omega-hydroxy- .....   | 2/10/00        | 4/10/00        |
| 20427–84–3  | Ethanol, 2-[2-(p-nonylphenoxy)ethoxy]- .....   | 2/10/00        | 4/10/00        |
| 20636–48–0  | 3,6,9,12-Tetraoxatetradecan-1-ol, 14-(4-nonylphenoxy)- .....   | 2/10/00        | 4/10/00        |
| 26027–38–3  | Poly(oxy-1,2-ethanediyl), alpha-(4-nonylphenyl)-omega-hydroxy- .....   | 2/10/00        | 4/10/00        |
| 26264–02–8  | 3,6,9,12-Tetraoxatetradecan-1-ol, 14-(nonylphenoxy)- .....   | 2/10/00        | 4/10/00        |
| 26571–11–9  | 3,6,9,12,15,18,21,24-Octaoxahexacosan-1-ol, 26-(nonylphenoxy)- .....   | 2/10/00        | 4/10/00        |
| 27176–93–8  | Ethanol, 2-[2-(nonylphenoxy)ethoxy]- .....   | 2/10/00        | 4/10/00        |
| 27177–01–1  | 3,6,9,12,15-Pentaoxaheptadecan-1-ol, 17-(nonylphenoxy)- .....  | 2/10/00        | 4/10/00        |
| 27177–05–5  | 3,6,9,12,15,18,21-Heptaooxacosan-1-ol, 23-(nonylphenoxy)- .....  | 2/10/00        | 4/10/00        |
| 27177–08–8  | 3,6,9,12,15,18,21,24,27-Nonaoxanonacosan-1-ol, 29-(nonylphenoxy)- .....  | 2/10/00        | 4/10/00        |
| 27986–36–3  | Ethanol, 2-(nonylphenoxy)- .....   | 2/10/00        | 4/10/00        |
| 37205–87–1  | Poly(oxy-1,2-ethanediyl), alpha-(isononylphenyl)-omega-hydroxy- .....  | 2/10/00        | 4/10/00        |
| 51938–25–1  | Poly(oxy-1,2-ethanediyl), alpha-(2-nonylphenyl)-omega-hydroxy- .....   | 2/10/00        | 4/10/00        |
| 65455–72–3  | 3,6,9,12,15,18,21,24,27-Nonaoxanonacosan-1-ol, 29-(isononylphenoxy)- .....   | 2/10/00        | 4/10/00        |
| 68412–54–4  | Poly(oxy-1,2-ethanediyl), alpha-(nonylphenyl)-omega-hydroxy-, branched .....   | 2/10/00        | 4/10/00        |
| 98113–10–1  | NP9 .....  | 2/10/00        | 4/10/00        |
| 127087–87–0   | Poly(oxy-1,2-ethanediyl), alpha-(4-nonylphenyl)-omega-hydroxy-, branched .....                                       | 2/10/00        | 4/10/00        |
| 152143–22–1   | Poly(oxy-1,2-ethanediyl), alpha-(4-nonylphenyl)-omega-hydroxy-, branched, phosphates. ....                           | 2/10/00        | 4/10/00        |
| OSHA Chemicals in Need of Dermal Absorption Testing |  |                |                |
| 60–29–7   | Ethyl ether .....  | 1/26/94        | 3/28/94        |
| 61–82–5   | Amitrole .....   | 3/11/94        | 5/10/94        |
| 74–96–4   | Ethyl bromide .....  | 3/11/94        | 5/10/94        |
| 75–05–8   | Acetonitrile .....   | 8/4/95         | 10/3/95        |
| 75–12–7   | Formamide .....  | 8/4/95         | 10/3/95        |
| 75–15–0   | Carbon disulfide .....   | 3/11/94        | 5/10/94        |
| 75–25–2   | Bromoform .....  | 3/11/94        | 5/10/94        |
| 75–34–3   | 1,1-Dichloroethane .....   | 3/11/94        | 5/10/94        |
| 75–35–4   | Vinylidene chloride .....  | 8/4/95         | 10/3/95        |
| 75–65–0   | tert-Butyl alcohol .....   | 1/26/94        | 3/28/94        |
| 76–22–2   | Camphor .....  | 1/26/94        | 3/28/94        |
| 77–73–6   | Dicyclopentadiene .....  | 8/4/95         | 10/3/95        |
| 77–78–1   | Dimethyl sulfate .....   | 3/11/94        | 5/10/94        |
| 78–59–1   | Isophorone .....   | 8/4/95         | 10/3/95        |
| 78–87–5   | Propylene dichloride .....   | 8/4/95         | 10/3/95        |
| 78–92–2   | sec-Butyl alcohol .....  | 1/26/94        | 3/28/94        |
| 79–20–9   | Methyl acetate .....   | 1/26/94        | 3/28/94        |
| 79–46–9   | 2-Nitropropane .....   | 3/11/94        | 5/10/94        |
| 88–72–2   | o-Nitrotoluene .....   | 3/11/94        | 5/10/94        |
| 89–72–5   | o-sec-Butylphenol .....  | 3/11/94        | 5/10/94        |
| 90–04–0   | o-Anisidine .....  | 3/11/94        | 5/10/94        |
| 91–20–3   | Naphthalene .....  | 8/4/95         | 10/3/95        |

Environmental Protection Agency

§ 712.30

| CAS No.   | Substance   | Effective date | Reporting date |
|---|---|----------------|----------------|
| OSHA Chemicals in Need of Dermal Absorption Testing |   |                |                |
| 92-52-4   | Biphenyl .....                                    | 8/4/95         | 10/3/95        |
| 95-13-6   | Indene .....                                      | 3/11/94        | 5/10/94        |
| 95-49-8   | o-Chlorotoluene .....                             | 3/11/94        | 5/10/94        |
| 95-50-1   | o-Dichlorobenzene .....                           | 8/4/95         | 10/3/95        |
| 96-18-4   | 1,2,3-Trichloropropane .....                      | 8/4/95         | 10/3/95        |
| 97-77-8   | Disulfiram .....                                  | 1/26/94        | 3/28/94        |
| 98-29-3   | t-Butylcatechol .....                             | 8/4/95         | 10/3/95        |
| 99-08-1   | m-Nitrotoluene .....                              | 8/4/95         | 10/3/95        |
| 99-65-0   | m-Dinitrobenzene .....                            | 3/11/94        | 5/10/94        |
| 99-99-0   | p-Nitrotoluene .....                              | 8/4/95         | 10/3/95        |
| 100-00-5  | p-Nitrochlorobenzene .....                        | 3/11/94        | 5/10/94        |
| 100-01-6  | p-Nitroaniline .....                              | 3/11/94        | 5/10/94        |
| 100-44-7  | Benzyl chloride .....                             | 3/11/94        | 5/10/94        |
| 100-25-4  | p-Dinitrobenzene .....                            | 1/26/94        | 3/28/94        |
| 100-63-0  | Phenylhydrazine .....                             | 3/11/94        | 5/10/94        |
| 105-46-4  | sec-Butyl acetate .....                           | 1/26/94        | 3/28/94        |
| 106-42-3  | p-Xylene .....                                    | 1/26/94        | 3/28/94        |
| 106-46-7  | p-Dichlorobenzene .....                           | 8/4/95         | 10/3/95        |
| 106-49-0  | p-Toluidine .....                                 | 3/11/94        | 5/10/94        |
| 107-06-2  | Ethylene dichloride .....                         | 8/4/95         | 10/3/95        |
| 107-31-3  | Methyl formate .....                              | 1/26/94        | 3/28/94        |
| 107-66-4  | Dibutyl phosphate .....                           | 1/26/94        | 3/28/94        |
| 108-03-2  | 1-Nitropropane .....                              | 1/26/94        | 3/28/94        |
| 108-44-1  | m-Toluidine .....                                 | 3/11/94        | 5/10/94        |
| 108-87-2  | Methylcyclohexane .....                           | 1/26/94        | 3/28/94        |
| 108-90-7  | Chlorobenzene .....                               | 3/11/94        | 5/10/94        |
| 108-93-0  | Cyclohexanol .....                                | 8/4/95         | 10/3/95        |
| 109-66-0  | Pentane .....                                     | 1/26/94        | 3/28/94        |
| 109-99-9  | Tetrahydrofuran .....                             | 3/11/94        | 5/10/94        |
| 110-12-3  | Methyl isoamyl ketone .....                       | 8/4/95         | 10/3/95        |
| 110-83-8  | Cyclohexene .....                                 | 1/26/94        | 3/28/94        |
| 111-84-2  | Nonane .....                                      | 1/26/94        | 3/28/94        |
| 120-80-9  | Catechol .....                                    | 8/4/95         | 10/3/95        |
| 121-14-2  | 2,4-Dinitrotoluene .....                          | 3/11/94        | 5/10/94        |
| 121-69-7  | Dimethylaniline .....                             | 8/4/95         | 10/3/95        |
| 122-39-4  | Diphenylamine .....                               | 3/11/94        | 5/10/94        |
| 123-42-2  | Diacetone alcohol .....                           | 8/4/95         | 10/3/95        |
| 123-92-2  | Isoamyl acetate .....                             | 1/26/94        | 3/28/94        |
| 126-99-8  | beta-Chloroprene .....                            | 3/11/94        | 5/10/94        |
| 127-19-5  | Dimethyl acetamide .....                          | 8/4/95         | 10/3/95        |
| 142-82-5  | Heptane (n-Heptane) .....                         | 1/26/94        | 3/28/94        |
| 150-76-5  | p-Methoxyphenol .....                             | 3/11/94        | 5/10/94        |
| 287-92-3  | Cyclopentane .....                                | 1/26/94        | 3/28/94        |
| 528-29-0  | o-Dinitrobenzene .....                            | 3/11/94        | 5/10/94        |
| 532-27-4  | a-Chloroacetophenone .....                        | 1/26/94        | 3/28/94        |
| 540-59-0  | 1,2-Dichloroethylene .....                        | 3/11/94        | 5/10/94        |
| 540-88-5  | tert-Butyl acetate .....                          | 1/26/94        | 3/28/94        |
| 542-92-7  | Cyclopentadiene .....                             | 8/4/95         | 10/3/95        |
| 626-17-5  | m-Phthalodinitrile .....                          | 3/11/94        | 5/10/94        |
| 628-63-7  | n-Amyl acetate .....                              | 1/26/94        | 3/28/94        |
| 768-52-5  | N-Isopropylaniline .....                          | 3/11/94        | 5/10/94        |
| 1300-73-8   | Xylidine .....                                    | 3/11/94        | 5/10/94        |
| 6423-43-4   | Propylene glycol dinitrate .....                  | 3/11/94        | 5/10/94        |
| 7631-90-5   | Sodium bisulfite .....                            | 1/26/94        | 3/28/94        |
| 7681-57-4   | Sodium metabisulfite .....                        | 1/26/94        | 3/28/94        |
| 25013-15-4  | Vinyl toluene .....                               | 3/11/94        | 5/10/94        |
| 34590-94-8  | Dipropylene glycol methyl ether .....             | 8/4/95         | 10/3/95        |
| Propylene glycol ethers and esters                  |   |                |                |
| 108-65-6  | Propylene glycol monomethyl ether acetate .....   | 1/26/94        | 3/28/94        |
| 110-98-5  | Dipropylene glycol .....                          | 1/26/94        | 3/28/94        |
| 770-35-4  | 1-Phenoxy-2-propanol .....                        | 1/26/94        | 3/28/94        |
| 20324-32-7  | 1-(2-Methoxy-1-methylethoxy)-2-propanol .....     | 1/26/94        | 3/28/94        |
| 20324-33-8  | Tripropylene glycol methyl ether .....            | 1/26/94        | 3/28/94        |
| 28677-93-2  | Methoxy-1-propanol .....                          | 1/26/94        | 3/28/94        |
| 29387-86-8  | Propylene glycol monobutyl ether .....            | 1/26/94        | 3/28/94        |
| 29911-28-2  | Dipropylene glycol butyl ether .....              | 1/26/94        | 3/28/94        |
| 42978-66-5  | Tripropylene glycol diacrylate .....              | 1/26/94        | 3/28/94        |
| 57018-52-7  | Propylene glycol mono-tert-butyl ether .....      | 1/26/94        | 3/28/94        |
| 88917-22-0  | Dipropylene glycol monomethyl ether acetate ..... | 1/26/94        | 3/28/94        |

| CAS No.  | Substance  | Effective date | Reporting date |
|--|--|----------------|----------------|
| Propylene glycol ethers and esters                           |  |                |                |
| Pyridinamines  |  |                |                |
| 462–08–8   | 3-Pyridinamine .....   | 1/6/05         | 3/7/05         |
| 504–24–5   | 4-Pyridinamine .....   | 1/6/05         | 3/7/05         |
| 504–29–0   | 2-Pyridinamine .....   | 1/6/05         | 3/7/05         |
| Siloxanes  |  |                |                |
| 107–46–0   | Hexamethyldisiloxane .....   | 10/12/93       | 2/28/94        |
| 107–50–6   | Tetradecamethylcycloheptasiloxane .....                              | 10/12/93       | 2/28/94        |
| 107–51–7   | Octamethyltrisiloxane .....  | 10/12/93       | 2/28/94        |
| 107–52–8   | Tetradecamethylhexasiloxane .....                                    | 10/12/93       | 2/28/94        |
| 107–53–9   | Tetracosamethylundecasiloxane .....                                  | 10/12/93       | 2/28/94        |
| 141–62–8   | Decamethyltetrasiloxane .....  | 10/12/93       | 2/28/94        |
| 141–63–9   | Dodecamethylpentasiloxane .....                                      | 10/12/93       | 2/28/94        |
| 540–97–6   | Dodecamethylcyclohexasiloxane .....                                  | 10/12/93       | 2/28/94        |
| 541–01–5   | Hexadecamethylheptasiloxane .....                                    | 10/12/93       | 2/28/94        |
| 541–02–6   | Decamethylcyclopentasiloxane .....                                   | 10/12/93       | 2/28/94        |
| 541–05–9   | Hexamethylcyclotrisiloxane .....                                     | 10/12/93       | 2/28/94        |
| 546–56–5   | Octaphenylcyclohexasiloxane .....                                    | 10/12/93       | 2/28/94        |
| 556–67–2   | Octamethylcyclohexasiloxane .....                                    | 10/12/93       | 2/28/94        |
| 556–68–3   | Hexadecamethylcyclooctasiloxane .....                                | 10/12/93       | 2/28/94        |
| 556–69–4   | Octadecamethyloctasiloxane .....                                     | 10/12/93       | 2/28/94        |
| 556–70–7   | Docosamethyldecasiloxane .....                                       | 10/12/93       | 2/28/94        |
| 556–71–8   | Octadecamethylcyclononasiloxane .....                                | 10/12/93       | 2/28/94        |
| 999–97–3   | Hexamethyldisilazane .....   | 10/12/93       | 2/28/94        |
| 2370–88–9  | Tetramethylcyclohexasiloxane .....                                   | 10/12/93       | 2/28/94        |
| 2374–14–3  | Trifluoropropylmethylcyclohexasiloxane .....                         | 10/12/93       | 2/28/94        |
| 2471–08–1  | Hexacosamethyldodecasiloxane .....                                   | 10/12/93       | 2/28/94        |
| 2471–09–2  | Octacosamethyltridecasiloxane .....                                  | 10/12/93       | 2/28/94        |
| 2471–10–5  | Triacontamethyltetradecasiloxane .....                               | 10/12/93       | 2/28/94        |
| 2471–11–6  | Dotriacontamethylpentadecasiloxane .....                             | 10/12/93       | 2/28/94        |
| 2554–06–5  | Methylvinylcyclosiloxane .....                                       | 10/12/93       | 2/28/94        |
| 2627–95–4  | Tetramethyldivinylsiloxane .....                                     | 10/12/93       | 2/28/94        |
| 2652–13–3  | Eicosamethylnonasiloxane .....                                       | 10/12/93       | 2/28/94        |
| 70131-67-8   | Siloxanes and silicones, di-Me, hydroxy-terminated .....             | 10/12/93       | 2/28/94        |
| 9004–73–3  | Methylpolysiloxane .....   | 10/12/93       | 2/28/94        |
| 18766–38–6   | Docosamethylcycloundecasiloxane .....                                | 10/12/93       | 2/28/94        |
| 18772–36–6   | Eicosamethylcyclodecasiloxane .....                                  | 10/12/93       | 2/28/94        |
| 18844–04–7   | Hexatriacontamethylheptadecasiloxane .....                           | 10/12/93       | 2/28/94        |
| 18919–94–3   | Tetracosamethylcyclododecasiloxane .....                             | 10/12/93       | 2/28/94        |
| 23523–12–8   | Hexatriacontamethylcyclooctadecasiloxane .....                       | 10/12/93       | 2/28/94        |
| 23523–14–0   | Triacontamethylcyclopentadecasiloxane .....                          | 10/12/93       | 2/28/94        |
| 23732–94–7   | Hexacosamethylcyclotridecasiloxane .....                             | 10/12/93       | 2/28/94        |
| 36938–50–8   | Tetraatriacontamethyl hexadecasiloxane .....                         | 10/12/93       | 2/28/94        |
| 36938–52–0   | Octatriacontamethyl octadecasiloxane .....                           | 10/12/93       | 2/28/94        |
| 63148–62–9   | Dimethyl silicones and siloxanes .....                               | 10/12/93       | 2/28/94        |
| 67762–90–7   | Dimethyl silicones and siloxane, reaction products with silica ..... | 10/12/93       | 2/28/94        |
| 67762–94–1   | Dimethylmethylvinylsiloxane .....                                    | 10/12/93       | 2/28/94        |
| 68037–59–2   | Dimethylhydriopolysiloxane .....                                     | 10/12/93       | 2/28/94        |
| 68037–74–1   | Dimethylpolysiloxanes .....  | 10/12/93       | 2/28/94        |
| 68083–14–7   | Dimethyldiphenylsiloxane .....                                       | 10/12/93       | 2/28/94        |
| 69430–24–6   | Cyclopolydimethylsiloxane .....                                      | 10/12/93       | 2/28/94        |
| 115361-68-7  | Dimethylmethyl 3,3,3-trifluoropropyl siloxane .....                  | 10/12/93       | 2/28/94        |
| 149050-40-8  | Octacosamethylcyclohexadecasiloxane .....                            | 10/12/93       | 2/28/94        |
| 150026-95-2  | Dotriacontamethylcyclohexadecasiloxane .....                         | 10/12/93       | 2/28/94        |
| 150026-96-3  | Tetraatriacontamethylcycloheptadecasiloxane .....                    | 10/12/93       | 2/28/94        |
| 150026-97-4  | Octatriacontamethylcyclononadecasiloxane .....                       | 10/12/93       | 2/28/94        |
| 150026-98-5  | Tetracontamethylcycloicosasiloxane .....                             | 10/12/93       | 2/28/94        |
| 150026-99-6  | Tetracontamethylnonadecasiloxane .....                               | 10/12/93       | 2/28/94        |
| 150027-00-2  | Dotetracontamethyleicosasiloxane .....                               | 10/12/93       | 2/28/94        |
| not available  | Polymethyloctadecylsiloxane .....                                    | 10/12/93       | 2/28/94        |
| Substantially produced chemicals in need of subchronic tests |  |                |                |
| 80-51-3  | p,p'-Oxybis(benzenesulfonylhydrazide) .....                          | 9/30/91        | 11/27/91       |
| 81-84-5  | Naphthalenedicarboxylic anhydride .....                              | 9/30/91        | 11/27/91       |
| 84-51-5  | 2-Ethylanthraquinone .....   | 9/30/91        | 11/27/91       |
| 87-02-5  | 7-Amino-4-hydroxy-2-naphthalenesulfonic acid .....                   | 9/30/91        | 11/27/91       |
| 90-15-3  | 1-Naphthol .....   | 9/30/91        | 11/27/91       |
| 92-70-6  | 3-Hydroxy-2-naphthoic acid .....                                     | 9/30/91        | 11/27/91       |
| 94-28-0  | Triethylene glycol bis(2-ethylhexanoate) .....                       | 9/30/91        | 11/27/91       |

Environmental Protection Agency

§ 712.30

| CAS No.  | Substance   | Effective date | Reporting date |
|--|---|----------------|----------------|
| Substantially produced chemicals in need of subchronic tests |   |                |                |
| 95-32-9  | 2-(4-Morpholinylidithio)-benzothiazole .....  | 9/30/91        | 11/27/91       |
| 97-88-1  | N-Butyl methacrylate .....  | 9/30/91        | 11/27/91       |
| 98-48-6  | 1,3-Benzenedisulfonic Acid .....  | 9/30/91        | 11/27/91       |
| 99-54-7  | 3,4-Dichloronitrobenzene .....  | 9/30/91        | 11/27/91       |
| 99-63-8  | Isophthaloyl chloride .....   | 9/30/91        | 11/27/91       |
| 100-20-9   | Terephthaloyl chloride .....  | 9/30/91        | 11/27/91       |
| 100-29-8   | 4-Ethoxynitrobenzene .....  | 9/30/91        | 11/27/91       |
| 102-01-2   | Acetoacetanilide .....  | 9/30/91        | 11/27/91       |
| 106-31-0   | Butyric anhydride .....   | 9/30/91        | 11/27/91       |
| 106-63-8   | Isobutyl acrylate .....   | 9/30/91        | 11/27/91       |
| 111-96-6   | Diethylene glycol dimethyl ether .....  | 9/30/91        | 11/27/91       |
| 112-15-2   | Ethanol, 2-(2-ethoxyethoxy)-, acetate .....   | 9/30/91        | 11/27/91       |
| 116-81-4   | Bromamine acid .....  | 9/30/91        | 11/27/91       |
| 119-33-5   | 4-Methyl-2-nitro-phenol .....   | 9/30/91        | 11/27/91       |
| 121-60-8   | 4-(Acetylamino)benzenesulfonyl chloride .....   | 9/30/91        | 11/27/91       |
| 123-54-6   | 2,4-Pentanedione .....  | 9/30/91        | 11/27/91       |
| 123-62-6   | Propanoic anhydride .....   | 9/30/91        | 11/27/91       |
| 142-16-5   | Bis(2-ethylhexyl)-2-butenedioate .....  | 9/30/91        | 11/27/91       |
| 311-89-7   | Perfluorotributylamine .....  | 9/30/91        | 11/27/91       |
| 355-42-0   | Perfluoro-N-hexane .....  | 9/30/91        | 11/27/91       |
| 594-42-3   | Trichloromethanesulfonyl chloride .....   | 9/30/91        | 11/27/91       |
| 616-21-7   | 1,2-Dichlorobutane .....  | 9/30/91        | 11/27/91       |
| 626-17-5   | 1,3-Dicyanobenzene .....  | 9/30/91        | 11/27/91       |
| 760-23-6   | 3,4-Dichlorobutene .....  | 9/30/91        | 11/27/91       |
| 929-06-6   | 2-(2-Aminoethoxy)-ethanol .....   | 6/30/92        | 9/28/92        |
| 1047-16-1  | Quinacridone .....  | 9/30/91        | 11/27/91       |
| 1111-78-0  | Ammonium carbamate .....  | 9/30/91        | 11/27/91       |
| 3089-11-0  | Hexa(methoxymethyl) melamine .....  | 9/30/91        | 11/27/91       |
| Sulphones  |   |                |                |
| 67-71-0  | Dimethylsulfone .....   | 9/30/91        | 11/27/91       |
| 77-79-2  | 3-Sulfolene .....   | 9/30/91        | 11/27/91       |
| 80-07-9  | Sulfonyl bis-(4-chlorobenzene) .....  | 9/30/91        | 11/27/91       |
| 80-08-0  | 4,4'-Diaminodiphenyl sulfone .....  | 9/30/91        | 11/27/91       |
| 80-09-1  | Bisphenol S .....   | 9/30/91        | 11/27/91       |
| 98-30-6  | 2-Amino-4-(methylsulfonyl)phenol .....  | 9/30/91        | 11/27/91       |
| 126-33-0   | Sulfolane .....   | 9/30/91        | 11/27/91       |
| 127-63-9   | Diphenylsulfone .....   | 9/30/91        | 11/27/91       |
| 2580-77-0  | 2,2'-Sulfonyl bis-ethanol .....   | 9/30/91        | 11/27/91       |
| 3278-22-6  | 1,1'-[Methylene bis(sulfonyl)]bisethene .....   | 9/30/91        | 11/27/91       |
| 5246-57-1  | 2-[(3-Aminophenyl)sulfonyl]ethanol .....  | 9/30/91        | 11/27/91       |
| 16588-67-3   | 3-[N-Ethyl-4-[[6-(methylsulfonyl)-2-benzothiazolyl] azo]-m-toluidino]- propionitrile .....        | 9/30/91        | 11/27/91       |
| 17557-67-4   | 6-(Methylsulfonyl)-2-benzothiazolamine .....  | 9/30/91        | 11/27/91       |
| 17601-96-6   | 2-Amino-4-[(2-hydroxyethyl) sulfonyl]phenol .....   | 9/30/91        | 11/27/91       |
| 17688-68-5   | 4-Phenylthiomorpholine, 1,1-dioxide .....   | 9/30/91        | 11/27/91       |
| 17741-62-7   | 4-[4-[(2,6-Dichloro-4-nitrophenyl) azo]phenyl]thiomorpholine, 1,1-dioxide .....                   | 9/30/91        | 11/27/91       |
| 18760-44-6   | 3-(Decyloxy)tetrahydrothiophene 1,1-dioxide .....   | 9/30/91        | 11/27/91       |
| 20018-09-1   | 1-(Diiodomethyl) sulfonyl-4-methyl benzene .....  | 9/30/91        | 11/27/91       |
| 26750-50-5   | 1,1'-[Oxybis(methylenesulfonyl)] bisethene .....  | 9/30/91        | 11/27/91       |
| 36724-43-3   | 2,2'-[Oxybis(methylenesulfonyl)]bisethanol .....  | 9/30/91        | 11/27/91       |
| 41123-59-5   | 1,1'-[Methylenebis(sulfonyl)]bis-2-chloroethane .....   | 9/30/91        | 11/27/91       |
| 41123-69-7   | 2,2'-[Methylenebis(sulfonyl)]bisethanol .....   | 9/30/91        | 11/27/91       |
| 41687-30-3   | 2-[(3-Nitrophenyl)sulfonyl]ethanol .....  | 9/30/91        | 11/27/91       |
| 52218-35-6   | 2-[[6-Amino-2-naphthalenyl)sulfonyl]ethanol .....   | 9/30/91        | 11/27/91       |
| 53061-10-2   | 1,1'-[Oxybis(methylenesulfonyl)]bis-2-chloroethane .....  | 9/30/91        | 11/27/91       |
| 63134-33-8   | 4-[[4-(Phenylmethoxy)phenyl]sulfonyl]phenol .....   | 9/30/91        | 11/27/91       |
| Tungsten compounds   |   |                |                |
| 1314-35-8  | Tungsten oxide (WO <sub>3</sub> ) .....   | 1/6/05         | 3/7/05         |
| 7440-33-7  | Tungsten .....  | 1/6/05         | 3/7/05         |
| 7783-03-1  | Tungstate (WO <sub>4</sub> <sup>2-</sup> ), dihydrogen, (T-4)- .....                              | 1/6/05         | 3/7/05         |
| 7783-82-6  | Tungsten fluoride (WF <sub>6</sub> ), (OC-6-11)- .....  | 1/6/05         | 3/7/05         |
| 7790-60-5  | Tungstate (WO <sub>4</sub> <sup>2-</sup> ), dipotassium, (T-4)- .....                             | 1/6/05         | 3/7/05         |
| 7790-85-4  | Cadmium tungsten oxide (CdWO <sub>4</sub> ) .....   | 1/6/05         | 3/7/05         |
| 10213-10-2   | Tungstate (WO <sub>4</sub> <sup>2-</sup> ), disodium, dihydrate, (T-4)- .....                     | 1/6/05         | 3/7/05         |
| 11105-11-6   | Tungsten oxide (WO <sub>3</sub> ), hydrate .....  | 1/6/05         | 3/7/05         |
| 11120-01-7   | Sodium tungsten oxide .....   | 1/6/05         | 3/7/05         |
| 11120-25-5   | Tungstate (W <sub>12</sub> (OH) <sub>2</sub> O <sub>40</sub> <sup>10-</sup> ), decaammonium ..... | 1/6/05         | 3/7/05         |



Environmental Protection Agency

§ 712.30

| CAS No.  | Substance   | Effective date     | Reporting date    |
|--|---|--------------------|-------------------|
| Voluntary HPV Challenge Program orphan (unsponsored) chemicals |   |                    |                   |
| 81-16-3  | 1-Naphthalenesulfonic acid, 2-amino- .....  | September 29, 2006 | November 28, 2006 |
| 81-84-5  | 1H,3H-Naphtho[1,8-cd]pyran-1,3-dione .....  | September 29, 2006 | November 28, 2006 |
| 83-41-0  | Benzene, 1,2-dimethyl-3-nitro- .....  | September 29, 2006 | November 28, 2006 |
| 84-69-5  | 1,2-Benzenedicarboxylic acid, bis(2-methylpropyl) ester .....                                     | September 29, 2006 | November 28, 2006 |
| 85-40-5  | 1H-Isindole-1,3(2H)-dione, 3a,4,7,7a-tetrahydro- .....  | September 29, 2006 | November 28, 2006 |
| 91-68-9  | Phenol, 3-(diethylamino)- .....   | September 29, 2006 | November 28, 2006 |
| 94-96-2  | 1,3-Hexanediol, 2-ethyl- .....  | September 29, 2006 | November 28, 2006 |
| 96-22-0  | 3-Pentanone .....   | September 29, 2006 | November 28, 2006 |
| 97-00-7  | Benzene, 1-chloro-2,4-dinitro- .....  | September 29, 2006 | November 28, 2006 |
| 98-09-9  | Benzenesulfonyl chloride .....  | September 29, 2006 | November 28, 2006 |
| 98-16-8  | Benzenamine, 3-(trifluoromethyl)- .....   | September 29, 2006 | November 28, 2006 |
| 98-56-6  | Benzene, 1-chloro-4-(trifluoromethyl)- .....  | September 29, 2006 | November 28, 2006 |
| 101-34-8   | 9-Octadecenoic acid, 12-(acetyloxy)-, 1,2,3-propanetriyl ester, (9Z,9'Z,9'',12R,12'R,12'')- ..... | September 29, 2006 | November 28, 2006 |
| 104-66-5   | Benzene, 1,1'-[1,2-ethanediylbis(oxy)]bis- .....  | September 29, 2006 | November 28, 2006 |
| 104-93-8   | Benzene, 1-methoxy-4-methyl- .....  | September 29, 2006 | November 28, 2006 |
| 107-39-1   | 1-Pentene, 2,4,4-trimethyl- .....   | September 29, 2006 | November 28, 2006 |
| 107-40-4   | 2-Pentene, 2,4,4-trimethyl- .....   | September 29, 2006 | November 28, 2006 |
| 110-18-9   | 1,2-Ethanediamine, N,N,N',N'-tetramethyl- .....   | September 29, 2006 | November 28, 2006 |
| 110-33-8   | Hexanedioic acid, dihexyl ester .....   | September 29, 2006 | November 28, 2006 |
| 111-44-4   | Ethane, 1,1'-oxybis[2-chloro- .....   | September 29, 2006 | November 28, 2006 |
| 111-85-3   | Octane, 1-chloro- .....   | September 29, 2006 | November 28, 2006 |
| 111-91-1   | Ethane, 1,1'-[methylenebis(oxy)]bis[2-chloro- .....   | September 29, 2006 | November 28, 2006 |
| 118-90-1   | Benzoic acid, 2-methyl- .....   | September 29, 2006 | November 28, 2006 |
| 119-33-5   | Phenol, 4-methyl-2-nitro- .....   | September 29, 2006 | November 28, 2006 |
| 121-69-7   | Benzenamine, N,N-dimethyl- .....  | September 29, 2006 | November 28, 2006 |
| 121-82-4   | 1,3,5-Triazine, hexahydro-1,3,5-trinitro- .....   | September 29, 2006 | November 28, 2006 |
| 124-63-0   | Methanesulfonyl chloride .....  | September 29, 2006 | November 28, 2006 |
| 127-68-4   | Benzenesulfonic acid, 3-nitro-, sodium salt .....   | September 29, 2006 | November 28, 2006 |
| 131-57-7   | Methanone, (2-hydroxy-4-methoxyphenyl)phenyl- .....   | September 29, 2006 | November 28, 2006 |
| 137-20-2   | Ethanesulfonic acid, 2-[methyl[(9Z)-1-oxo-9-octadeceny]amino]-, sodium salt .....                 | September 29, 2006 | November 28, 2006 |
| 138-25-0   | 1,3-Benzenedicarboxylic acid, 5-sulfo-, 1,3-dimethyl ester .....                                  | September 29, 2006 | November 28, 2006 |
| 139-40-2   | 1,3,5-Triazine-2,4-diamine, 6-chloro-N,N'-bis(1-methylethyl)- .....                               | September 29, 2006 | November 28, 2006 |
| 140-93-2   | Carbonodithioic acid, O-(1-methylethyl) ester, sodium salt .....                                  | September 29, 2006 | November 28, 2006 |
| 142-73-4   | Glycine, N-(carboxymethyl)- .....   | September 29, 2006 | November 28, 2006 |
| 330-54-1   | Urea, N'-(3,4-dichlorophenyl)-N,N-dimethyl- .....   | September 29, 2006 | November 28, 2006 |

| CAS No.  | Substance  | Effective date     | Reporting date    |
|--|--|--------------------|-------------------|
| Voluntary HPV Challenge Program orphan (unsponsored) chemicals |  |                    |                   |
| 460–00–4   | Benzene, 1-bromo-4-fluoro- .....   | September 29, 2006 | November 28, 2006 |
| 506–51–4   | 1-Tetracosanol .....   | September 29, 2006 | November 28, 2006 |
| 506–52–5   | 1-Hexacosanol .....  | September 29, 2006 | November 28, 2006 |
| 513–74–6   | Carbamodithioic acid, monoammonium salt .....  | September 29, 2006 | November 28, 2006 |
| 515–40–2   | Benzene, (2-chloro-1,1-dimethylethyl)- .....   | September 29, 2006 | November 28, 2006 |
| 529–33–9   | 1-Naphthalenol, 1,2,3,4-tetrahydro- .....  | September 29, 2006 | November 28, 2006 |
| 529–34–0   | 1(2H)-Naphthalenone, 3,4-dihydro- .....  | September 29, 2006 | November 28, 2006 |
| 542–92–7   | 1,3-Cyclopentadiene .....  | September 29, 2006 | November 28, 2006 |
| 557–61–9   | 1-Octacosanol .....  | September 29, 2006 | November 28, 2006 |
| 563–72–4   | Ethanedioic acid, calcium salt (1:1) .....   | September 29, 2006 | November 28, 2006 |
| 590–19–2   | 1,2-Butadiene .....  | September 29, 2006 | November 28, 2006 |
| 592–45–0   | 1,4-Hexadiene .....  | September 29, 2006 | November 28, 2006 |
| 598–72–1   | Propanoic acid, 2-bromo- .....   | September 29, 2006 | November 28, 2006 |
| 617–94–7   | Benzenemethanol, .alpha.,.alpha.-dimethyl- .....   | September 29, 2006 | November 28, 2006 |
| 628–13–7   | Pyridine, hydrochloride .....  | September 29, 2006 | November 28, 2006 |
| 628–96–6   | 1,2-Ethanediol, dinitrate .....  | September 29, 2006 | November 28, 2006 |
| 645–62–5   | 2-Hexenal, 2-ethyl- .....  | September 29, 2006 | November 28, 2006 |
| 693–95–8   | Thiazole, 4-methyl- .....  | September 29, 2006 | November 28, 2006 |
| 756–80–9   | Phosphorodithioic acid, O,O-dimethyl ester .....   | September 29, 2006 | November 28, 2006 |
| 870–72–4   | Methanesulfonic acid, hydroxy-, monosodium salt .....  | September 29, 2006 | November 28, 2006 |
| 928–72–3   | Glycine, N-(carboxymethyl)-, disodium salt .....   | September 29, 2006 | November 28, 2006 |
| 939–97–9   | Benzaldehyde, 4-(1,1-dimethylethyl)- .....   | September 29, 2006 | November 28, 2006 |
| 1000–82–4  | Urea, (hydroxymethyl)- .....   | September 29, 2006 | November 28, 2006 |
| 1002–69–3  | Decane, 1-chloro- .....  | September 29, 2006 | November 28, 2006 |
| 1111–78–0  | Carbamic acid, monoammonium salt .....   | September 29, 2006 | November 28, 2006 |
| 1401–55–4  | Tannins .....  | September 29, 2006 | November 28, 2006 |
| 1445–45–0  | Ethane, 1,1,1-trimethoxy- .....  | September 29, 2006 | November 28, 2006 |
| 1498–51–7  | Phosphorodichloridic acid, ethyl ester .....   | September 29, 2006 | November 28, 2006 |
| 1738–25–6  | Propanenitrile, 3-(dimethylamino)- .....   | September 29, 2006 | November 28, 2006 |
| 1912–24–9  | 1,3,5-Triazine-2,4-diamine, 6-chloro-N-ethyl-N'-(1-methylethyl)- .....   | September 29, 2006 | November 28, 2006 |
| 2152–64–9  | Benzenamine, N-phenyl-4-[[4-(phenylamino)phenyl][4-(phenylimino)-2,5-cyclohexadien-1-ylidene]methyl]-, monohydrochloride ..... | September 29, 2006 | November 28, 2006 |
| 2210–79–9  | Oxirane, [(2-methylphenoxy)methyl]- .....  | September 29, 2006 | November 28, 2006 |
| 2372–45–4  | 1-Butanol, sodium salt .....   | September 29, 2006 | November 28, 2006 |
| 2409–55–4  | Phenol, 2-(1,1-dimethylethyl)-4-methyl- .....  | September 29, 2006 | November 28, 2006 |
| 2425–54–9  | Tetradecane, 1-chloro- .....   | September 29, 2006 | November 28, 2006 |

Environmental Protection Agency

§ 712.30

| CAS No.  | Substance  | Effective date     | Reporting date    |
|--|--|--------------------|-------------------|
| Voluntary HPV Challenge Program orphan (unsponsored) chemicals |  |                    |                   |
| 2494-89-5  | Ethanol, 2-[(4-aminophenyl)sulfonyl]-, hydrogen sulfate (ester)  | September 29, 2006 | November 28, 2006 |
| 2524-03-0  | Phosphorochloridothioic acid, O,O-dimethyl ester   | September 29, 2006 | November 28, 2006 |
| 2691-41-0  | 1,3,5,7-Tetrazocine, octahydro-1,3,5,7-tetranitro-   | September 29, 2006 | November 28, 2006 |
| 2814-20-2  | 4(1H)-Pyrimidinone, 6-methyl-2-(1-methylethyl)-  | September 29, 2006 | November 28, 2006 |
| 2905-62-6  | Benzoyl chloride, 3,5-dichloro-  | September 29, 2006 | November 28, 2006 |
| 2915-53-9  | 2-Butenedioic acid (2Z)-, dioctyl ester  | September 29, 2006 | November 28, 2006 |
| 3039-83-6  | Ethenesulfonic acid, sodium salt   | September 29, 2006 | November 28, 2006 |
| 3132-99-8  | Benzaldehyde, 3-bromo-   | September 29, 2006 | November 28, 2006 |
| 3386-33-2  | Octadecane, 1-chloro-  | September 29, 2006 | November 28, 2006 |
| 3779-63-3  | 1,3,5-Triazine-2,4,6(1H,3H,5H)-trione, 1,3,5-tris(6-isocyanatohexyl)-  | September 29, 2006 | November 28, 2006 |
| 3965-55-7  | 1,3-Benzenedicarboxylic acid, 5-sulfo-, 1,3-dimethyl ester, sodium salt  | September 29, 2006 | November 28, 2006 |
| 4035-89-6  | Imidodicarbonic diamide, N,N',2-tris(6-isocyanatohexyl)-   | September 29, 2006 | November 28, 2006 |
| 4170-30-3  | 2-Butenal  | September 29, 2006 | November 28, 2006 |
| 4316-73-8  | Glycine, N-methyl-, monosodium salt  | September 29, 2006 | November 28, 2006 |
| 4860-03-1  | Hexadecane, 1-chloro-  | September 29, 2006 | November 28, 2006 |
| 5026-74-4  | Oxiranemethanamine, N-[4-(oxiranylmethoxy)phenyl]-N-(oxiranylmethyl)-  | September 29, 2006 | November 28, 2006 |
| 5216-25-1  | Benzene, 1-chloro-4-(trichloromethyl)-   | September 29, 2006 | November 28, 2006 |
| 5460-09-3  | 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-, monosodium salt  | September 29, 2006 | November 28, 2006 |
| 5915-41-3  | 1,3,5-Triazine-2,4-diamine, 6-chloro-N-(1,1-dimethylethyl)-N'-ethyl-   | September 29, 2006 | November 28, 2006 |
| 6473-13-8  | 2-Naphthalenesulfonic acid, 6-[(2,4-diaminophenyl)azo]-3-[[4-[[7-[(2,4-diaminophenyl)azo]-1-hydroxy-3-sulfo-2-naphthalenyl]azo]phenyl]amino]-3-sulfo-phenyl]azo]-4-hydroxy-, trisodium salt. | September 29, 2006 | November 28, 2006 |
| 7795-95-1  | 1-Octanesulfonyl chloride  | September 29, 2006 | November 28, 2006 |
| 8001-58-9  | Creosote   | September 29, 2006 | November 28, 2006 |
| 10265-69-7   | Glycine, N-phenyl-, monosodium salt  | September 29, 2006 | November 28, 2006 |
| 13749-94-5   | Ethanimidothioic acid, N-hydroxy-, methyl ester  | September 29, 2006 | November 28, 2006 |
| 13826-35-2   | Benzenemethanol, 3-phenoxy-  | September 29, 2006 | November 28, 2006 |
| 17103-31-0   | Urea, sulfate (2:1)  | September 29, 2006 | November 28, 2006 |
| 17321-47-0   | Phosphoramidothioic acid, O,O-dimethyl ester   | September 29, 2006 | November 28, 2006 |
| 17976-43-1   | 2,4,6,8,3,5,7-Benzotetraoxatriplumbacycloundecin-3,5,7-triylidene, 1,9-dihydro-1,9-dioxo-  | September 29, 2006 | November 28, 2006 |
| 19438-61-0   | 1,3-Isobenzofurandione, 5-methyl-  | September 29, 2006 | November 28, 2006 |
| 19525-59-8   | Glycine, N-phenyl-, monopotassium salt   | September 29, 2006 | November 28, 2006 |
| 20068-02-4   | 2-Butenenitrile, 2-methyl-, (2Z)-  | September 29, 2006 | November 28, 2006 |
| 20227-53-6   | Phosphorous acid, 2-(1,1-dimethylethyl)-4-[1-[3-(1,1-dimethylethyl)-4-hydroxyphenyl]-1-methylethyl]phenyl bis(4-nonylphenyl) ester.  | September 29, 2006 | November 28, 2006 |
| 21351-39-3   | Urea, sulfate (1:1)  | September 29, 2006 | November 28, 2006 |
| 22527-63-5   | Propanoic acid, 2-methyl-, 3-(benzoyloxy)-2,2,4-trimethylpentyl ester  | September 29, 2006 | November 28, 2006 |
| 24615-84-7   | 2-Propenoic acid, 2-carboxyethyl ester   | September 29, 2006 | November 28, 2006 |



| CAS No.  | Substance   | Effective date     | Reporting date    |
|--|---|--------------------|-------------------|
| Voluntary HPV Challenge Program orphan (unsponsored) chemicals |   |                    |                   |
| 24794–58–9   | Formic acid, compd. with 2,2',2[ethanol] (1:1)  | September 29, 2006 | November 28, 2006 |
| 25154–38–5   | Piperazineethanol   | September 29, 2006 | November 28, 2006 |
| 25168–05–2   | Benzene, chloromethyl-  | September 29, 2006 | November 28, 2006 |
| 25168–06–3   | Phenol, (1-methylethyl)-  | September 29, 2006 | November 28, 2006 |
| 25321–41–9   | Benzenesulfonic acid, dimethyl-   | September 29, 2006 | November 28, 2006 |
| 25383–99–7   | Octadecanoic acid, 2-(1-carboxyethoxy)-1-methyl-2-oxoethyl ester, sodium salt   | September 29, 2006 | November 28, 2006 |
| 25646–71–3   | Methanesulfonamide, N-[2-[(4-amino-3-methylphenyl)ethylamino]ethyl]-, sulfate (2:3)   | September 29, 2006 | November 28, 2006 |
| 26377–29–7   | Phosphorodithioic acid, O,O-dimethyl ester, sodium salt   | September 29, 2006 | November 28, 2006 |
| 26401–27–4   | Phosphorous acid, isooctyl diphenyl ester   | September 29, 2006 | November 28, 2006 |
| 26680–54–6   | 2,5-Furandione, dihydro-3-(octenyl)-  | September 29, 2006 | November 28, 2006 |
| 27193–28–8   | Phenol, (1,1,3,3-tetramethylbutyl)-   | September 29, 2006 | November 28, 2006 |
| 28106–30–1   | Benzene, ethenylethyl-  | September 29, 2006 | November 28, 2006 |
| 28188–24–1   | Octadecanoic acid, 2-(hydroxymethyl)-2-[[1-(1-oxooctadecyl)oxy]methyl]-1,3-propanediyl ester  | September 29, 2006 | November 28, 2006 |
| 28908–00–1   | Benzothiazole, 2-[(chloromethyl)thio]-  | September 29, 2006 | November 28, 2006 |
| 30574–97–1   | 2-Butenenitrile, 2-methyl-, (2E)-   | September 29, 2006 | November 28, 2006 |
| 34689–46–8   | Phenol, methyl-, sodium salt  | September 29, 2006 | November 28, 2006 |
| 35203–06–6   | Benzenamine, 2-ethyl-6-methyl-N-methylene-  | September 29, 2006 | November 28, 2006 |
| 35203–08–8   | Benzenamine, 2,6-diethyl-N-methylene-   | September 29, 2006 | November 28, 2006 |
| 37734–45–5   | Carbochlorodithioic acid, S-(phenylmethyl) ester  | September 29, 2006 | November 28, 2006 |
| 37764–25–3   | Acetamide, 2,2-dichloro-N,N-di-2-propenyl-  | September 29, 2006 | November 28, 2006 |
| 38185–06–7   | Benzenesulfonic acid, 4-chloro-3,5-dinitro-, potassium salt   | September 29, 2006 | November 28, 2006 |
| 38321–18–5   | Ethanol, 2-(2-butoxyethoxy)-, sodium salt   | September 29, 2006 | November 28, 2006 |
| 39515–51–0   | Benzaldehyde, 3-phenoxy-  | September 29, 2006 | November 28, 2006 |
| 40630–63–5   | 1-Octanesulfonyl fluoride   | September 29, 2006 | November 28, 2006 |
| 40876–98–0   | Butanedioic acid, oxo-, diethyl ester, ion(1-), sodium  | September 29, 2006 | November 28, 2006 |
| 51632–16–7   | Benzene, 1-(bromomethyl)-3-phenoxy-   | September 29, 2006 | November 28, 2006 |
| 52184–19–7   | Phenol, 2,4-bis(1,1-dimethylpropyl)-6-[(2-nitrophenyl)azo]-   | September 29, 2006 | November 28, 2006 |
| 52556–42–0   | 1-Propanesulfonic acid, 2-hydroxy-3-(2-propenyloxy)-, monosodium salt   | September 29, 2006 | November 28, 2006 |
| 52663–57–7   | Ethanol, 2-butoxy-, sodium salt   | September 29, 2006 | November 28, 2006 |
| 56803–37–3   | Phosphoric acid, (1,1-dimethylethyl)phenyl diphenyl ester   | September 29, 2006 | November 28, 2006 |
| 57693–14–8   | Chromate(3-), bis[3-(hydroxy-.kappa.O)-4-[[2-(hydroxy-.kappa.O)-1-naphthalenyl]azo-.kappa.N1]-7-nitro-1-naphthalenesulfonato(3-)-], trisodium | September 29, 2006 | November 28, 2006 |
| 61788–44–1   | Phenol, styrenated  | September 29, 2006 | November 28, 2006 |
| 61788–76–9   | Alkanes, chloro   | September 29, 2006 | November 28, 2006 |
| 61789–85–3   | Sulfonic acids, petroleum   | September 29, 2006 | November 28, 2006 |
| 63302–49–8   | Phosphorochloridous acid, bis(4-nonylphenyl) ester  | September 29, 2006 | November 28, 2006 |

Environmental Protection Agency

§ 712.30

| CAS No.  | Substance  | Effective date     | Reporting date    |
|--|--|--------------------|-------------------|
| Voluntary HPV Challenge Program orphan (unsponsored) chemicals |  |                    |                   |
| 64743-02-8   | Alkenes, C>10 .alpha.- .....   | September 29, 2006 | November 28, 2006 |
| 64743-03-9   | Phenols (petroleum) .....  | September 29, 2006 | November 28, 2006 |
| 65996-79-4   | Solvent naphtha (coal) .....   | September 29, 2006 | November 28, 2006 |
| 65996-82-9   | Tar oils, coal .....   | September 29, 2006 | November 28, 2006 |
| 65996-83-0   | Extracts, coal tar oil alk. ....   | September 29, 2006 | November 28, 2006 |
| 65996-86-3   | Extract oils (coal), tar base .....  | September 29, 2006 | November 28, 2006 |
| 65996-87-4   | Extract residues (coal), tar oil alk. ....   | September 29, 2006 | November 28, 2006 |
| 65996-89-6   | Tar, coal, high-temp. ....   | September 29, 2006 | November 28, 2006 |
| 65996-91-0   | Distillates (coal tar), upper .....  | September 29, 2006 | November 28, 2006 |
| 65996-92-1   | Distillates (coal tar) .....   | September 29, 2006 | November 28, 2006 |
| 68081-86-7   | Phenol, nonyl derivs. ....   | September 29, 2006 | November 28, 2006 |
| 68082-78-0   | Lard, oil, Me esters .....   | September 29, 2006 | November 28, 2006 |
| 68153-60-6   | Fatty acids, tall-oil, reaction products with diethylenetriamine, acetates .....                     | September 29, 2006 | November 28, 2006 |
| 68187-41-7   | Phosphorodithioic acid, O,O-di-C1-14-alkyl esters .....  | September 29, 2006 | November 28, 2006 |
| 68187-57-5   | Pitch, coal tar-petroleum .....  | September 29, 2006 | November 28, 2006 |
| 68187-59-7   | Coal, anthracite, calcined .....   | September 29, 2006 | November 28, 2006 |
| 68188-18-1   | Paraffin oils, chlorosulfonated, saponified .....  | September 29, 2006 | November 28, 2006 |
| 68308-74-7   | Amides, tall-oil fatty, N,N-di-Me .....  | September 29, 2006 | November 28, 2006 |
| 68309-16-0   | Fatty acids, tall-oil, 2-(2-hydroxyethoxy)ethyl esters .....   | September 29, 2006 | November 28, 2006 |
| 68309-27-3   | Fatty acids, tall-oil, sulfonated, sodium salts .....  | September 29, 2006 | November 28, 2006 |
| 68334-01-0   | Disulfides, alkylaryl dialkyl diaryl, petroleum refinery spent caustic oxidn. products ..            | September 29, 2006 | November 28, 2006 |
| 68441-66-7   | Decanoic acid, mixed esters with dipentaerythritol, octanoic acid and valeric acid ...               | September 29, 2006 | November 28, 2006 |
| 68442-60-4   | Acetaldehyde, reaction products with formaldehyde, by-products from .....                            | September 29, 2006 | November 28, 2006 |
| 68442-77-3   | 2-Butenediamide, (2E)-, N,N'-bis[2-(4,5-dihydro-2-nortall-oil alkyl-1H-imidazol-1-yl)ethyl] derivs.. | September 29, 2006 | November 28, 2006 |
| 68457-74-9   | Phenol, isobutylenated methylstyrenated .....  | September 29, 2006 | November 28, 2006 |
| 68513-62-2   | Disulfides, C5-12-alkyl .....  | September 29, 2006 | November 28, 2006 |
| 68515-89-9   | Barium, carbonate nonylphenol complexes .....  | September 29, 2006 | November 28, 2006 |
| 68527-22-0   | Naphtha (petroleum), clay-treated light straight-run .....   | September 29, 2006 | November 28, 2006 |
| 68584-25-8   | Benzenesulfonic acid, C10-16-alkyl derivs., compds. with triethanolamine .....                       | September 29, 2006 | November 28, 2006 |
| 68602-81-3   | Distillates, hydrocarbon resin prodn. higher boiling .....   | September 29, 2006 | November 28, 2006 |
| 68608-59-3   | Ethane, 1,2-dichloro-, manuf. of, by-products from, distn. lights .....                              | September 29, 2006 | November 28, 2006 |
| 68609-05-2   | Cyclohexane, oxidized, non-acidic by-products, distn. lights .....                                   | September 29, 2006 | November 28, 2006 |
| 68610-90-2   | 2-Butenedioic acid (2E)-, di-C8-18-alkyl esters .....  | September 29, 2006 | November 28, 2006 |
| 68649-42-3   | Phosphorodithioic acid, O,O-di-C1-14-alkyl esters, zinc salts .....                                  | September 29, 2006 | November 28, 2006 |
| 68650-36-2   | Aromatic hydrocarbons, C8, o-xylene-lean .....   | September 29, 2006 | November 28, 2006 |

§ 712.30

40 CFR Ch. I (7–1–10 Edition)

| CAS No.  | Substance  | Effective date     | Reporting date    |
|--|--|--------------------|-------------------|
| Voluntary HPV Challenge Program orphan (unsponsored) chemicals |  |                    |                   |
| 68782–97–8   | Distillates (petroleum), hydrofined lubricating-oil .....  | September 29, 2006 | November 28, 2006 |
| 68815–50–9   | Octadecanoic acid, reaction products with 2-[(2-aminoethyl)amino]ethanol .....                                 | September 29, 2006 | November 28, 2006 |
| 68909–77–3   | Ethanol, 2,2'-oxybis-, reaction products with ammonia, morpholine derivs. residues                             | September 29, 2006 | November 28, 2006 |
| 68915–05–9   | Fatty acids, tall-oil, low-boiling, reaction products with ammonia-ethanolamine reaction by-products.          | September 29, 2006 | November 28, 2006 |
| 68915–39–9   | Cyclohexane, oxidized, aq. ext., sodium salt .....   | September 29, 2006 | November 28, 2006 |
| 68918–16–1   | Tar, coal, dried and oxidized .....  | September 29, 2006 | November 28, 2006 |
| 68919–17–5   | Hydrocarbons, C12–20, catalytic alkylation by-products .....   | September 29, 2006 | November 28, 2006 |
| 68937–29–1   | 1,6-Hexanediol, distn. residues .....  | September 29, 2006 | November 28, 2006 |
| 68937–70–2   | Carboxylic acids, C6–18 and C8–15-di- .....  | September 29, 2006 | November 28, 2006 |
| 68937–72–4   | Carboxylic acids, di-, C4–11 .....   | September 29, 2006 | November 28, 2006 |
| 68953–80–0   | Benzene, mixed with toluene, dealkylation product .....  | September 29, 2006 | November 28, 2006 |
| 68955–37–3   | Acid chlorides, tallow, hydrogenated .....   | September 29, 2006 | November 28, 2006 |
| 68955–76–0   | Aromatic hydrocarbons, C9–16, biphenyl deriv.-rich .....   | September 29, 2006 | November 28, 2006 |
| 68987–41–7   | Benzene, ethylenated .....   | September 29, 2006 | November 28, 2006 |
| 68987–66–6   | Ethene, hydrated, by-products from .....   | September 29, 2006 | November 28, 2006 |
| 68988–22–7   | 1,4-Benzenedicarboxylic acid, dimethyl ester, manuf. of, by-products from .....                                | September 29, 2006 | November 28, 2006 |
| 68990–61–4   | Tar, coal, high-temp., high-solids .....   | September 29, 2006 | November 28, 2006 |
| 68990–65–8   | Fats and Glyceridic oils, vegetable, reclaimed .....   | September 29, 2006 | November 28, 2006 |
| 70084–98–9   | Terpenes and Terpenoids, C10–30, distn. residues .....   | September 29, 2006 | November 28, 2006 |
| 70693–50–4   | Phenol, 2,4-bis(1-methyl-1-phenylethyl)-6-[(2-nitrophenyl)azo]- .....  | September 29, 2006 | November 28, 2006 |
| 70851–08–0   | Amides, coco, N-[3-(dimethylamino)propyl], alkylation products with sodium 3-chloro-2-hydroxypropanesulfonate. | September 29, 2006 | November 28, 2006 |
| 71077–05–9   | Ethanol, 2,2'-oxybis-, reaction products with ammonia, morpholine product tower residues.                      | September 29, 2006 | November 28, 2006 |
| 72162–15–3   | 1-Decene, sulfurized .....   | September 29, 2006 | November 28, 2006 |
| 72854–27–4   | Tannins, reaction products with sodium bisulfite, sodium polysulfide and sodium sulfite.                       | September 29, 2006 | November 28, 2006 |
| 73665–18–6   | Extract residues (coal), tar oil alk., naphthalene distn. residues .....                                       | September 29, 2006 | November 28, 2006 |
| 83864–02–2   | Nickel, bis[(cyano-C)triphenylborato(1-)-N]bis(hexanedinitrile-N,N')- .....                                    | September 29, 2006 | November 28, 2006 |
| 84501–86–0   | Hexanedioic acid, esters with high-boiling C6–10-alkene hydroformylation products                              | September 29, 2006 | November 28, 2006 |
| 90640–80–5   | Anthracene oil .....   | September 29, 2006 | November 28, 2006 |
| 90640–86–1   | Distillates (coal tar), heavy oils .....   | September 29, 2006 | November 28, 2006 |
| 119345–02–7  | Benzene, 1,1'-oxybis-, tetrapropylene derivs. ....   | September 29, 2006 | November 28, 2006 |
| 125997–20–8  | Phosphoric acid, mixed 3-bromo-2,2-dimethylpropyl and 2-bromoethyl and 2-chloroethyl esters.                   | September 29, 2006 | November 28, 2006 |

(Secs 8(a) and 8(d), 90 Stat. 2027, 2029; 15 U.S.C. 2607 (a) and (d))

[47 FR 26998, June 22, 1982]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 712.30, see the List of CFR Sections Affected, which appears in the Finding Aids section of the printed volume and on GPO Access.

EFFECTIVE DATE NOTE: At 59 FR 14115, Mar. 25, 1994, in § 712.30 paragraph (x), the chemical substances under the category "propylene glycol ethers esters" and all related dates were stayed, effective March 25, 1994. At 60 FR 31921, June 19, 1995, § 712.30 was amended in part by redesignating paragraph (x) as paragraph (e).

## PART 716—HEALTH AND SAFETY DATA REPORTING

### Subpart A—General Provisions

- Sec.
- 716.1 Scope and compliance.
- 716.3 Definitions.
- 716.5 Persons who must report.
- 716.10 Studies to be reported.
- 716.20 Studies not subject to the reporting requirements.
- 716.21 Chemical specific reporting requirements.
- 716.25 Adequate file search.
- 716.30 Submission of copies of studies.
- 716.35 Submission of lists of studies.
- 716.40 EPA requests for submission of further information.
- 716.45 How to report on substances and mixtures.
- 716.50 Reporting physical and chemical properties.
- 716.55 Confidentiality claims.
- 716.60 Reporting schedule.
- 716.65 Reporting period.

### Subpart B—Specific Chemical Listings

- 716.105 Additions of substances and mixtures to which this subpart applies.
- 716.120 Substances and listed mixtures to which this subpart applies.

AUTHORITY: 15 U.S.C. 2607(d).

SOURCE: 51 FR 32726, Sept. 15, 1986, unless otherwise noted.

### Subpart A—General Provisions

#### § 716.1 Scope and compliance.

(a) This subpart sets forth requirements for the submission of lists and copies of health and safety studies on chemical substances and mixtures selected for priority consideration for testing rules under section 4(a) of the Toxic Substances Control Act (TSCA) and on other chemical substances and mixtures for which EPA requires health and safety information in fulfilling the purposes of TSCA.

(b) Section 15(3) of TSCA makes it unlawful for any person to fail or refuse to submit information required under this subpart. Section 16 provides that a violation of section 15 renders a

person liable to the United States for a civil penalty and possible criminal prosecution. Under section 17, the district courts of the United States have jurisdiction to restrain any violation of section 15.

#### § 716.3 Definitions.

The definitions in section 3 of TSCA apply to this subpart. In addition, the following definitions are provided for the purposes of this subpart:

*Byproduct* means a chemical substance produced without a separate commercial intent during the manufacture, processing, use, or disposal of another chemical substance(s) or mixture(s).

*Co-product* means a chemical substance produced for a commercial purpose during the manufacture, processing, use, or disposal of another chemical substance(s) or mixture(s).

*Copy of study* means the written presentation of the purpose and methodology of a study and its results.

*EPA* means the United States Environmental Protection Agency.

*Health and safety study* or *study* means any study of any effect of a chemical substance or mixture on health or the environment or on both, including underlying data and epidemiological studies, studies of occupational exposure to a chemical substance or mixture, toxicological, clinical, and ecological or other studies of a chemical substance or mixture, and any test performed under TSCA.

(1) It is intended that the term *health and safety study* be interpreted broadly. Not only is information which arises as a result of a formal, disciplined study included, but other information relating to the effects of a chemical substance or mixture on health or the environment is also included. Any data that bear on the effects of a chemical substance on health or the environment would be included. Chemical identity is part of, or underlying data to, a health and safety study.

(2) Examples are:

(i) Long- and short-term tests of mutagenicity, carcinogenicity, or teratogenicity; data on behavioral disorders; dermatotoxicity; pharmacological effects; mammalian absorption, distribution, metabolism, and excretion; cumulative, additive, and synergistic effects; and acute, subchronic, and chronic effects.

(ii) Tests for ecological or other environmental effects on invertebrates, fish, or other animals, and plants, including: Acute toxicity tests, chronic toxicity tests, critical life-stage tests, behavioral tests, algal growth tests, seed germination tests, plant growth or damage tests, microbial function tests, bioconcentration or bioaccumulation tests, and model ecosystem (microcosm) studies.

(iii) Assessments of human and environmental exposure, including workplace exposure, and impacts of a particular chemical substance or mixture on the environment, including surveys, tests, and studies of: Biological, photochemical, and chemical degradation; structure/activity relationships; air, water, and soil transport; biomagnification and bioconcentration; and chemical and physical properties, e.g., boiling point, vapor pressure, evaporation rates from soil and water, octanol/water partition coefficient, and water solubility.

(iv) Monitoring data, when they have been aggregated and analyzed to measure the exposure of humans or the environment to a chemical substance or mixture.

*Import* means to import for commercial purposes.

*Import for commercial purposes* means to import with the purpose of obtaining an immediate or eventual commercial advantage for the importer, and includes the importation of any amount of a chemical substance or mixture. If a chemical substance or mixture containing impurities is imported for commercial purposes, then those impurities are also imported for commercial purposes.

*Importer* means any person who imports a chemical substance, including a chemical substance as a part of a mixture or article, into the customs territory of the United States and includes the person primarily liable for the pay-

ment of any duties on the merchandise or an authorized agent acting on his behalf (as defined in 19 CFR 1.11). Importer also includes, as appropriate:

(1) The consignee.

(2) The importer of record.

(3) The actual owner, if an actual owner's declaration and superseding bond has been filed in accordance with 19 CFR 141.20.

(4) The transferee, if the right to draw merchandise in a bonded warehouse has been transferred in accordance with subpart C of 19 CFR part 144. For the purpose of this definition, the customs territory of the United States consists of the 50 States, Puerto Rico, and the District of Columbia.

*Impurity* means a chemical substance which is unintentionally present with another chemical substance.

*Listed mixture* means any mixture listed in §716.120.

*Manufacture* means to manufacture for commercial purposes.

*Manufacture for commercial purposes* means: (1) To produce, with the purpose of obtaining an immediate or eventual commercial advantage for the manufacturer, and includes among other things such "manufacture" of any amount of a chemical substance or mixture:

(i) For commercial distribution, including for test marketing.

(ii) For use by the manufacturer, including use for product research and development, or as an intermediate.

(2) Manufacture for commercial purposes also applies to substances that are produced coincidentally during the manufacture, processing, use, or disposal of another substance or mixture, including byproducts and impurities. Such byproducts and impurities may, or may not, in themselves have commercial value. They are nonetheless produced for the purpose of obtaining a commercial advantage since they are part of the manufacture of a chemical product for a commercial purpose.

*Manufacturer* means a person who produces or manufactures a chemical substance. A person who extracts a component chemical substance from a previously existing chemical substance or a complex combination of substances is a manufacturer of that component chemical substance.

## Environmental Protection Agency

## § 716.10

*Person* includes any individual, firm, company, corporation, joint-venture, partnership, sole proprietorship, association, or any other business entity, any State or political subdivision thereof, any municipality, any interstate body, and any department, agency, or instrumentality of the Federal government.

*Process* means to process for commercial purposes.

*Process for commercial purposes* means the preparation of a chemical substance or mixture, after its manufacture, for distribution in commerce with the purpose of obtaining an immediate or eventual commercial advantage for the processor. Processing of any amount of a chemical substance or mixture is included. If a chemical substance or mixture containing impurities is processed for commercial purposes, then those impurities are also processed for commercial purposes.

*Propose to manufacture, import, or process* means that a person has made a management decision to commit financial resources toward the manufacture, importation, or processing of a substance or mixture.

*Substance* means *chemical substance* as defined at section 3(2)(A) of TSCA, 15 U.S.C. 2602(2)(A).

*TSCA* means the Toxic Substances Control Act (15 U.S.C. 2601 *et seq.*).

### § 716.5 Persons who must report.

(a) Except as provided in paragraphs (b) and (c) of this section, only those persons described in this section are required to report under this part. Persons who must report include manufacturers (including importers) who fall within the North American Industry Classification System (NAICS) (in effect as of January 1, 1997) Subsector 325 (chemical manufacturing and allied products) or Industry Group 32411 (petroleum refineries), who:

(1) In the 10 years preceding the effective date on which a substance or mixture is added to § 716.120, either had proposed to manufacture (including import), or had manufactured (including imported) the listed substance or listed mixture (including as a known byproduct), are required to report during the reporting period specified in § 716.65.

(2) As of the effective date on which a substance or mixture is added to § 716.120, and who propose to manufacture (including import), or who are manufacturing (including importing) the listed substance or listed mixture (including as a known byproduct), are required to report during the reporting period specified in § 716.65.

(3) After the effective date on which a substance or mixture is added to § 716.120, and who propose to manufacture (including import) the listed substance or listed mixture (including as a known byproduct), are required to report during the reporting period specified in § 716.65.

(b) A rule promulgated under the authority of 15 U.S.C. 2607(d) may require that any person who does not fall within NAICS (in effect as of January 1, 1997) Subsector 325 or Industry Group 32411, and who had proposed to manufacture (including import) or process, had manufactured (including imported) or processed, proposes to manufacture (including import) or process, or is manufacturing (including importing) or processing a substance or mixture listed in § 716.120 must report under this part.

(c) Processors and persons who propose to process a substance or mixture otherwise subject to the reporting requirements imposed by this part are not subject to this part unless EPA specifically states otherwise in a particular notice or rule promulgated under the authority of 15 U.S.C. 2607(d).

[63 FR 15773, Apr. 1, 1998]

### § 716.10 Studies to be reported.

(a) In general, health and safety studies, as defined in § 716.3, on any substance or listed mixture listed in § 716.120, that are unpublished are reportable, i.e., must be submitted or listed. However, this requirement has limitations according to the nature of the material studied, so that:

(1) All studies of substances and listed mixtures are reportable. However, in the case of physical and chemical properties, only those studies listed in § 716.50 must be submitted.

(2) Studies of mixtures known to contain substances or listed mixtures listed in § 716.120 are reportable except for

## § 716.20

## 40 CFR Ch. I (7–1–10 Edition)

studies of physical and chemical properties and the studies exempted at § 716.20(a)(6) (i) through (vi).

(3) Studies of substances or listed mixtures that a person who is reporting has manufactured, imported, or processed or proposed to manufacture, import, or process only as impurities are not generally reportable under § 716.20(a)(9).

(4) Underlying data, such as medical or health records, individual files, lab notebooks, and daily monitoring records supporting studies do not have to be submitted initially. EPA may request underlying data later under § 716.40.

(b) [Reserved]

### § 716.20 Studies not subject to the reporting requirements.

(a) Excluding paragraph (a)(3) of this section, the following types of studies are exempt from the copy and list submission requirements of §§ 716.30 and 716.35.

(1) Studies which have been published in the scientific literature.

(2) Studies previously submitted to the EPA Office of Pollution Prevention and Toxics. These studies are limited to section 8(e) submissions, studies submitted during section 4 proceedings, studies submitted with premanufacture notices or significant new use notices, and studies submitted “for your information” (FYI submissions) in support of EPA’s TSCA Existing Chemicals Program. Studies which have been initiated pursuant to a TSCA section 4(a) test rule, for which the person has submitted a letter of intent to conduct testing in accordance with the provisions of § 790.25 of part 790 of this chapter, are exempt from the list submission requirements of § 716.35.

(3) Except for those studies described in paragraph (a)(2) of this section, studies previously submitted to any Federal agency with no claims of confidentiality are exempt only from the copy submission requirements of § 716.30, and must be listed in accordance with the provisions of § 716.35.

(4) Studies conducted or initiated by or for another person who is subject to, and who will report the studies under §§ 716.30 and 716.35.

(5) Studies of chemical substances which are not on the TSCA Chemical Substances Inventory. This exemption applies only to those substances within categories listed under § 716.120(c).

(6) The following types of studies when the subject of the study is a mixture known to contain a substance or listed mixture listed under § 716.120.

- (i) Acute oral toxicity studies.
- (ii) Acute dermal toxicity studies.
- (iii) Acute inhalation toxicity studies.
- (iv) Primary eye irritation studies.
- (v) Primary dermal irritation studies.
- (vi) Dermal sensitization studies.
- (vii) Physical and chemical properties.

If the substance or listed mixture is an impurity, no reporting is required (see paragraph (a)(9) of this section).

(7) Analyzed aggregations of monitoring data based on monitoring data acquired more than 5 years preceding the date the substance or listed mixture was added to the list under § 716.120.

(8) Analyzed aggregations of monitoring data on mixtures known to contain one or more substances or listed mixtures listed in § 716.120, when the monitoring data are not analyzed to determine the exposure or concentration levels of the substances or listed mixture listed under § 716.120.

(9) Studies on a substance or listed mixture listed under § 716.120 that the person who is reporting has manufactured, imported, or processed or proposed to manufacture, import, or process only as an impurity. When reporting of such studies is to be required, that reporting will be separately proposed in the FEDERAL REGISTER.

(10) Studies of chemical substances or listed mixtures previously submitted by trade associations in accordance with the provisions of § 716.30.

(b) The following types of studies on substances or listed mixtures listed under § 716.120 are exempt from the copy and list submission requirements of §§ 716.30 and 716.35.

(1) For the listed ureaformaldehyde resins (CAS Nos. 9011-05-6 and 68611-64-3), studies on agronomic plant growth or damage which demonstrate only that the resins stimulate plant growth

## Environmental Protection Agency

## § 716.21

or cause plant damage when applied as a fertilizer.

(2) For the specified chemicals in § 716.120(d) under the category "Siloxanes," acute oral, dermal, and inhalation toxicity studies and primary eye and dermal irritation studies.

(3) For the listed chemicals under § 716.120(d) in the category "OSHA Chemicals in Need of Dermal Absorption Testing," studies on ecological effects.

(4) For the chemicals listed at § 716.120 with a special exemption referencing this paragraph, studies on mixtures containing the listed substance at levels below 1 percent of the mixture, except when a purpose of the study includes the investigation of the effects of the listed substance at levels below 1 percent.

(5) Rulemaking proceedings that add substances and mixtures to § 716.120 will specify the types of health and/or environmental effects studies that must be reported and will specify the chemical grade/purity requirements that must be met or exceeded in individual studies. Chemical grade/purity requirements will be specified on a per chemical basis or for a category of chemicals for which reporting is required.

[51 FR 32726, Sept. 15, 1986, as amended at 58 FR 47649, Sept. 10, 1993; 58 FR 68315, Dec. 27, 1993; 60 FR 34884, July 5, 1995; 63 FR 15773, Apr. 1, 1998]

### § 716.21 Chemical specific reporting requirements.

(a) Health and safety studies reportable under part 716 for the following chemical substances, mixtures, or categories of chemical substances, as listed in § 716.120, must be submitted or listed only as specified in this section:

(1) For 3H-1,2,4-triazole-3-thione, 5-amino-1,2-dihydro- and imidazo[4,5-d]imidazole-2,5-(1H,3H)-dione, tetrahydro-, all unpublished environmental effects studies and health effects studies on pharmacokinetics, genotoxicity, subchronic toxicity, immunotoxicity, carcinogenicity, reproductive effects, and developmental toxicity where the purity of 3H-1,2,4-triazole-3-thione, 5-amino-1,2-dihydro- or imidazo[4,5-d]imidazole-2,5-(1H,3H)-dione, tetrahydro- is greater than or

equal to 90% of the test substance by weight must be submitted.

(2) For benzenamine, 3-chloro-2,6-dinitro-N,N-dipropyl-4-(trifluoromethyl)-, all unpublished environmental effects studies including bioconcentration, environmental fate studies on biodegradation, and health effects studies on pharmacokinetics, subchronic toxicity, mutagenicity, reproductive effects, and developmental toxicity, and carcinogenicity where the purity of benzenamine, 3-chloro-2,6-dinitro-N,N-dipropyl-4-(trifluoromethyl)- is greater than or equal to 90% of the test substance by weight must be submitted.

(3) For stannane, dimethylbis[(1-oxoneodecyl)oxy]-, all unpublished environmental effects studies including bioconcentration, environmental fate studies on hydrolysis and biodegradation and health effects studies on pharmacokinetics, subchronic toxicity, mutagenicity, neurotoxicity, reproductive effects, and developmental toxicity, and carcinogenicity where the purity of stannane, dimethylbis[(1-oxoneodecyl)oxy]- is greater than or equal to 90% of the test substance by weight must be submitted.

(4) For benzene, 1,3,5-tribromo-2-(2-propenyloxy)-, all unpublished environmental effects studies including bioconcentration, environmental fate studies on biodegradation and health effects studies on pharmacokinetics, subchronic toxicity, neurotoxicity, reproductive effects, and developmental toxicity, and carcinogenicity where the purity of benzene, 1,3,5-tribromo-2-(2-propenyloxy)- is greater than or equal to 90% of the test substance by weight must be submitted.

(5) For 1-triazene, 1,3-diphenyl-, all unpublished health effects studies on pharmacokinetics, genotoxicity, subchronic and chronic toxicity, reproductive effects, and developmental toxicity where the purity of 1-triazene, 1,3-diphenyl- is greater than or equal to 90% of the test substance by weight must be submitted.

(6) For the 9 chemicals in the indium compound category, all unpublished health effects studies on pharmacokinetics, genotoxicity, subchronic and chronic toxicity, reproductive effects, and developmental toxicity where the



## § 716.25

## 40 CFR Ch. I (7–1–10 Edition)

purity of the indium compound is greater than or equal to 90% of the test substance by weight must be submitted.

(7) For all voluntary HPV Challenge Program orphan (un-sponsored) chemicals:

(i) All unpublished environmental fate studies, meeting the criteria set forth in paragraph (a)(7)(iv) of this section, on water solubility; adsorption/desorption on particulate surfaces, e.g., soil; vapor pressure; octanol/water partition coefficient; density/relative density (specific gravity); particle size distribution for insoluble solids; dissociation constant; degradation by photochemical mechanisms—aquatic and atmospheric; degradation by chemical mechanisms—hydrolytic, reductive, and oxidative; degradation by biological mechanisms—aerobic and anaerobic. Studies of physical and chemical properties meeting the criteria set forth in paragraph (a)(7)(iv) of this section must be reported if performed for the purpose of determining the environmental or biological fate of a substance, and only if they investigated one or more of the properties listed in this paragraph. In addition, all unpublished studies meeting the criteria set forth in paragraph (a)(7)(iv) of this section on melting point and boiling point must be submitted.

(ii) All unpublished health effects studies meeting the criteria set forth in paragraph (a)(7)(iv) of this section including pharmacokinetics, genotoxicity, acute toxicity, subacute toxicity, subchronic toxicity, chronic toxicity, reproductive toxicity, developmental toxicity, immunotoxicity, neurotoxicity, and oncogenicity/carcinogenicity.

(iii) All unpublished environmental effects studies meeting the criteria set forth in paragraph (a)(7)(iv) of this section including acute and chronic toxicity studies of aquatic and terrestrial vertebrates and invertebrates and aquatic plants.

(iv) Only studies where the voluntary HPV Challenge Program orphan (un-sponsored) chemical is  $\geq 90\%$  of the test substance by weight should be submitted. In addition, only studies that were conducted using TSCA, Federal Insecticide, Fungicide, and Rodenticide

Act (FIFRA), Organization for Economic Cooperation and Development (OECD) or other internationally accepted test guidelines or voluntary consensus standards should be submitted. Studies performed where the voluntary HPV Challenge Program orphan (un-sponsored) chemical is  $< 90\%$  of the test substance by weight are not requested at this time.

(8)(i) Reporting requirements apply only to manufacturers (including importers) of consumer products intended for use by children who also manufacture (including import) lead or lead compounds. For the category “lead and lead compounds,” all unpublished health and safety studies that:

(A) Relate to the lead content of consumer products that are “intended for use by children” as that term is defined at 40 CFR 710.43 (excluding children’s metal jewelry), or

(B) Assess children’s exposure to lead from such products (including studies of bioavailability).

(ii) With regard to purity, studies showing any measurable lead content in such products must be submitted.

(b) [Reserved]

[69 FR 24522, May 4, 2004, as amended at 71 FR 47135, Aug. 16, 2006; 73 FR 5115, Jan. 29, 2008]

### § 716.25 Adequate file search.

The scope of a person’s responsibility to search records is limited to records in the location(s) where the required information is typically kept, and to records kept by the person or the person’s individual employee(s) who is/are responsible for keeping such records or advising the person on the health and environmental effects of chemicals. Persons are not required to search for reportable information dated before January 1, 1977, to comply with this subpart unless specifically required to do so in a rule.

[63 FR 15773, Apr. 1, 1998]

### § 716.30 Submission of copies of studies.

(a)(1) Except as provided in §§ 716.5, 716.20, and 716.50, persons must send to EPA copies of any health and safety studies in their possession for the substances or mixtures listed in § 716.120.

## Environmental Protection Agency

## § 716.35

Persons are responsible for submitting copies on only the substances or listed mixtures which they: Have manufactured, imported, or processed or proposed to manufacture, import, or process (including as known byproducts) within the 10 years preceding the effective date for reporting on the substances or listed mixtures; manufacture, import, or process on the effective date for reporting on the substances or listed mixtures; and propose to manufacture, import, or process following the effective date for reporting on the substances or listed mixtures. Persons who list studies as ongoing or initiated under § 716.35(a) (1) and (2) must submit them when they are completed.

(2) [Reserved]

(b) Submissions under paragraph (a) of this section must be identified either on the face of the study or otherwise by the applicable chemical name and CAS number (if any) listed in § 716.120(a) (1) and (2), and must be accompanied by a cover letter containing the name, job title, address and telephone number of the submitting official, and the name and address of the manufacturing or processing establishment on whose behalf the submission is made. In the cover letter, submitters must identify any impurity or additive known to have been present in the substance or listed mixtures as studied unless its presence is specifically noted in the study itself. The cover letter accompanying a study submitted by a trade association must also state that the submission is to satisfy reporting requirements under this part.

(c) You must submit copies of health and safety studies and the accompanying cover letters by one of the following methods:

(1) Mail, preferably certified, to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: 8(d) Health and Safety Reporting Rule (Notification/Reporting).

(2) Hand delivery to OPPT Document Control Office (DCO), EPA East, Rm. 6428, 1201 Constitution Ave., NW., Washington, DC, ATTN: 8(d) Health and Safety Reporting Rule (Notifica-

tion/Reporting). The DCO is open from 8 a.m. to 4 p.m., Monday through Friday, excluding legal holidays. The telephone number for the DCO is (202) 564-8930. Such deliveries are only accepted during the DCO's normal hours of operation.

[51 FR 32726, Sept. 15, 1986, as amended at 52 FR 20084, May 29, 1987; 52 FR 44828, Nov. 20, 1987; 53 FR 12523, Apr. 15, 1988; 60 FR 34463, July 3, 1995; 63 FR 15773, Apr. 1, 1998; 71 FR 47135, Aug. 16, 2006]

### § 716.35 Submission of lists of studies.

(a) Except as provided in §§ 716.5, 716.20, and 716.50, persons subject to this rule must send lists of studies to EPA for each of the listed substances or listed mixtures (including as a known byproduct) in § 716.120 which they are manufacturing, importing, or processing, or which they propose to manufacture (including import) or process.

(1) *Ongoing studies.* As of the date a person becomes subject to this part, a list of ongoing health and safety studies being conducted by or initiated for them, noting for each entry: The beginning date of the study, the purpose of the study, the types of data to be collected, the anticipated date of completion, and the name and address of the laboratory conducting the study.

(2) *Initiated studies.* After the date a person becomes subject to this part, a list of studies initiated by or for them, noting for each entry: The beginning date of the study, the purpose of the study, the types of data to be collected, the anticipated date of completion, and the name and address of the laboratory conducting the study.

(3) *Studies which are known but without possession of copies.* As of the date a person becomes subject to this part, a list of unpublished health and safety studies known to them of which they do not have copies. The name and address of any person known to them to possess a copy of the unpublished study must accompany each entry on the list. For purposes of this section only, an unpublished study will be considered to be "known to" a person, if the study can be discovered by a file search in accordance with § 716.25.

(4) *Studies previously sent to Federal agencies without confidentiality claims.* A

## § 716.40

list of unpublished studies which have been sent to a Federal Agency with no claims of confidentiality. The submission must for each study: Identify the study by title, state the name and address to whom the study was sent, and the month and year in which the study was submitted. Any study identified will be treated as if it were submitted under section 8(d) and will be available for public disclosure under section 14(b) of TSCA. Persons subject to this requirement may submit either a list of unpublished health and safety studies previously submitted to any Federal agency without claims of confidentiality in accordance with § 716.35(a)(4), or copies of each such study in accordance with § 716.30.

(b) Submission under paragraph (a) of this section must be identified either on the face of the study or otherwise by the applicable chemical name and CAS number (if any) listed in § 716.120(a) (1) and (2), and must be accompanied by a cover letter containing the name, job title, address and telephone numbers of the submitting official, and the name and address of the manufacturing or processing establishment on whose behalf the submission is made.

(c) You must submit lists of health and safety studies by one of the following methods:

(1) Mail, preferably certified, to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: 8(d) Health and Safety Reporting Rule (Notification/Reporting).

(2) Hand delivery to OPPT Document Control Office (DCO), EPA East, Rm. 6428, 1201 Constitution Ave., NW., Washington, DC, ATTN: 8(d) Health and Safety Reporting Rule (Notification/Reporting). The DCO is open from 8 a.m. to 4 p.m., Monday through Friday, excluding legal holidays. The telephone number for the DCO is (202) 564-8930. Such deliveries are only accepted

## 40 CFR Ch. I (7-1-10 Edition)

during the DCO's normal hours of operation.

[51 FR 32726, Sept. 15, 1986, as amended at 52 FR 20084, May 29, 1987; 52 FR 44828, Nov. 20, 1987; 53 FR 12523, Apr. 15, 1988; 53 FR 46746, Nov. 18, 1988; 60 FR 34463, July 3, 1995; 63 FR 15774, Apr. 1, 1998; 71 FR 47135, Aug. 16, 2006]

### § 716.40 EPA requests for submission of further information.

EPA may, by letter, request a person to submit or make available for review the following information after the initial reporting under §§ 716.30 and 716.35. If the requested submissions are not made, EPA may subpoena them under section 11 of TSCA, 15 U.S.C. 2610.

(a) Submission of underlying data of the kind described in § 716.10(a)(4) by persons who submit copies of studies under § 716.30 or list studies under § 716.35(a)(1) or § 716.35(a)(2).

(b) Submission of preliminary reports of ongoing studies by persons who list the studies under § 716.35(a)(1) or § 716.35(a)(2).

(c) Submission of copies of studies by persons listed under § 716.35(a)(3) as possessing them.

### § 716.45 How to report on substances and mixtures.

Section 716.120 lists substances and mixtures, in order by Chemical Abstract Service Registry Number and by alphabetical order. Studies of listed substances and listed mixtures shall be reported as follows:

(a) When a substance is individually listed under § 716.120(a), studies of the substance and studies of mixtures known to contain the substance must be reported as studies of that substance.

(b) When two or more substances are listed as a mixture under § 716.120(b), studies of the listed mixture and studies of any mixture known to contain the listed mixture must be reported as studies of the listed mixture.

(c) Studies of the following preparations of a substance must be reported as studies of the substance itself, not as studies of mixtures known to contain the substance.

(1) The substance in aqueous solution.

(2) The substance containing a small amount of an additive, such as a stabilizer, emulsifier, or other chemical added for purposes of maintaining the integrity or physical form of the substance.

(3) The substance of the grade/purity specified in each rule promulgated under 15 U.S.C. 2607(d).

[51 FR 32726, Sept. 15, 1986, as amended at 63 FR 15774, Apr. 1, 1998]

**§ 716.50 Reporting physical and chemical properties.**

Studies of physical and chemical properties must be reported under this subpart if performed for the purpose of determining the environmental or biological fate of a substance, and only if they investigated one or more of the following properties:

- (a) Water solubility.
- (b) Adsorption/desorption on particulate surfaces, e.g., soil.
- (c) Vapor pressure.
- (d) Octanol/water partition coefficient.
- (e) Density/relative density (specific gravity).
- (f) Particle size distribution for insoluble solids.
- (g) Dissociation constant.
- (h) Degradation by photochemical mechanisms—aquatic and atmospheric.
- (i) Degradation by chemical mechanisms—hydrolytic, reductive, and oxidative.
- (j) Degradation by biological mechanisms—aerobic and anaerobic.

**§ 716.55 Confidentiality claims.**

(a)(1) Section 14(b) of TSCA provides that EPA may not withhold from disclosure, on the grounds that they are confidential business information, health and safety studies of any substance or mixture that has been offered for commercial distribution (including for test marketing purposes and for use in research and development), any substance or mixture for which testing is required under TSCA section 4, or any substance for which notice is required under TSCA section 5, except to the extent that disclosure of data from such studies would reveal—

(i) Processes used in the manufacturing, importing, or processing of the substance or mixture, or

(ii) The portion of a mixture comprised by any of the substances in the mixture.

(2) Any respondent who wishes to assert a claim that part of a study should be withheld from disclosure because disclosure would reveal a confidential process or quantitative mixture composition should briefly state the basis of the claim, e.g., by saying “reveals confidential mixture proportion data,” and clearly identify the material subject to the claim.

(3) Any respondent may assert a confidentiality claim for company name or address, financial statistics, and product codes used by a company. This information will not be subject to the disclosure requirements of section 14(b) of TSCA.

(4) Information other than company name or address, financial statistics, and product codes used by a company, which is contained in a study, the disclosure of which would clearly be an unwarranted invasion of personal privacy (such as individual medical records), will be considered confidential by EPA as provided in Title 5, United States Code, section 552(b)(6).

(b) To assert a claim of confidentiality for data contained in a submitted document, the respondent must submit two copies of the document:

(1) One copy must be complete. In that copy, the respondent must indicate what data, if any, are claimed as confidential by bracketing or underlining the specific information. Each page containing data claimed as confidential must also contain a brief statement for the basis of the claim as well as a label such as “confidential,” “proprietary,” or “trade secret.”

(2) The second copy must be complete, except that all information claimed as confidential in the first copy must be deleted. The second copy will be immediately subject to public disclosure.

(3) Failure to furnish a second copy when information is claimed as confidential in the first copy will be considered a presumptive waiver of the claim of confidentiality. EPA will notify the respondent by certified mail that a finding of a presumptive waiver of the claim of confidentiality has been made. The respondent will be given 30

## § 716.60

days from the date of his or her receipt of this notification to submit the required second copy. If the respondent fails to submit the second copy within the 30 days, EPA will place the first copy in the public file.

(c) If no claim of confidentiality accompanies a document at the time it is submitted to EPA, the document will be placed in an open file available to the public without further notice to the respondent.

### § 716.60 Reporting schedule.

(a) *General requirements.* Except as provided in § 716.5 and paragraphs (b) and (c) of this section, submissions under §§ 716.30 and 716.35 must be postmarked on or before 60 days after the effective date of the listing of a substance or mixture in § 716.120 or within 60 days of proposing to manufacture (including import) or process a listed substance or listed mixture (including as a known byproduct) if first done after the effective date of the substance or mixture being listed in § 716.120.

(b)(1) *Submission of lists of initiated studies.* Persons subject to the listing requirements of § 716.35(a)(2) must inform EPA of the initiated study within 30 days of its initiation.

(2) *Submission of copies of completed studies.* Persons must submit copies of studies listed as ongoing or initiated under § 716.35(a) (1) and (2) within 30 days of completing the study.

(c) *Requests for extensions of time.* Respondents who cannot meet a deadline under this section may apply for a reasonable extension of time. Extension requests must be postmarked on or before 40 days after the effective date of the listing of a substance or mixture in § 716.120. The Director of EPA's Office of Pollution Prevention and Toxics will grant or deny extension requests.

(d) *Submission methods.* You must submit a request for an extension of time in writing by one of the following methods:

(1) Mail, preferably certified, to the Director, Office of Pollution Prevention and Toxics (OPPT) (7401M), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: Section 8(d) Extension.

## 40 CFR Ch. I (7-1-10 Edition)

(2) Hand delivery to OPPT Document Control Office (DCO), EPA East, Rm. 6428, 1201 Constitution Ave., NW., Washington, DC, ATTN: Section 8(d) Extension. The DCO is open from 8 a.m. to 4 p.m., Monday through Friday, excluding legal holidays. The telephone number for the DCO is (202) 564-8930. Such deliveries are only accepted during the DCO's normal hours of operation.

[51 FR 32726, Sept. 15, 1986, as amended at 60 FR 34464, July 3, 1995; 63 FR 15774, Apr. 1, 1998; 71 FR 47135, Aug. 16, 2006]

### § 716.65 Reporting period.

Unless otherwise required in a rule promulgated under 15 U.S.C. 2607(d) relating to a listed chemical substance or listed mixture [hereinafter "rule"], the reporting period for a listed chemical substance or listed mixture will terminate 60 days after the effective date on which the listed chemical substance or listed mixture is added to 40 CFR 716.120. EPA may require reporting for a listed chemical substance or listed mixture beyond the 60 day period in a rule promulgated under 15 U.S.C. 2607(d), however EPA will not extend any reporting period later than 2 years after the effective date on which a listed chemical substance or listed mixture is added to 40 CFR 716.120. After the applicable reporting period terminates, any person subject to the rule under 40 CFR 716.5 (a)(2) or (a)(3) and who has submitted to EPA lists of ongoing or initiated studies under 40 CFR 716.35 (a)(1) or (a)(2) must submit a copy of any such study within 30 days after its completion, regardless of the study's completion date.

[63 FR 15774, Apr. 1, 1998]

## Subpart B—Specific Chemical Listings

### § 716.105 Additions of substances and mixtures to which this subpart applies.

The requirements of this subpart will be extended periodically to cover additional substances and mixtures. Two procedures will be used to add substances and mixtures.

**Environmental Protection Agency**

**§ 716.120**

(a) Except as provided in paragraph (b) of this section, substances and mixtures will be added to §716.120 after publication in the FEDERAL REGISTER of a notice of proposed amendment to this subpart. There will be at least a 30-day public comment period on the notice. After consideration of the comments, EPA will amend §716.120 by final rule to add the substances and listed mixtures.

(b) Except as provided in paragraph (c) of this section, chemical substances, mixtures, and categories of chemical substances that have been added to the TSCA section 4(e) Priority List by the Interagency Testing Committee, established under section 4 of TSCA, will be added to §716.120 but only to the extent that the total number of designated and recommended substances, mixtures and categories of chemical substances has not exceeded 50 in any 1 year. The addition of such chemical substances, mixtures, and categories of chemical substances to §716.120 will be effective 30 days after publication of a notice to that effect in the FEDERAL REGISTER.

(c) Prior to the effective date of an amendment under paragraph (b) of this section, the Assistant Administrator for Prevention, Pesticides and Toxic Substances may for good cause withdraw a chemical substance, mixture, or category of chemical substances from §716.120. Any information submitted showing why a chemical substance, mixture, or category of chemical substances should be withdrawn from the amendment must be received by EPA within 14 days after the date of publication of the notice under paragraph (b) of this section. If a chemical substance, mixture, or category of chemical substances is withdrawn, a FEDERAL REGISTER notice announcing this decision will be published no later than the effective date of the amendment under paragraph (b) of this section.

(d) Persons who wish to submit information that shows why a chemical should be withdrawn must submit their comments in writing by one of the following methods:

(1) Mail, preferably certified, to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: 8(d) Auto-ITC.

(2) Hand delivery to OPPT Document Control Office (DCO), EPA East, Rm. 6428, 1201 Constitution Ave., NW., Washington, DC, ATTN: 8(d) Auto-ITC. The DCO is open from 8 a.m. to 4 p.m., Monday through Friday, excluding legal holidays. The telephone number for the DCO is (202) 564-8930. Such deliveries are only accepted during the DCO's normal hours of operation.

[51 FR 32726, Sept. 15, 1986, as amended at 60 FR 34464, July 3, 1995; 71 FR 47135, Aug. 16, 2006]

**§ 716.120 Substances and listed mixtures to which this subpart applies.**

Substances listed in this section appear in order by Chemical Abstract Service Registry Number. Chemical mixtures and categories are listed separately and by alphabetical order. Chemical substances listed within a category are provided only as examples of the category, and are not included on the list of substances. When a chemical substance in the substance or category list had been listed previously by a trivial (or common) name, it appears first, followed by the Chemical Abstract Service (CAS) name appearing in the TSCA Chemical Substance Inventory.

(a) *List of substances.* The following chemical substances are subject to all the provisions of part 716. Manufacturers, importers, and processors of a listed substance are subject to the reporting requirements of subpart A for that substance.

| CAS No. | Substance  | Special exemptions | Effective date | Sunset date |
|---------|--|--------------------|----------------|-------------|
| 62-74-8 | Acetic acid, fluoro-, sodium salt .....              | .....              | 03/07/86       | 03/07/96    |
| 67-63-0 | 2-Propanol .....                                     | .....              | 12/15/86       | 12/15/96    |
| 67-66-3 | Methane, trichloro- .....                            | .....              | 06/01/87       | 06/01/97    |
| 67-72-1 | Ethane, hexachloro- .....                            | .....              | 04/29/83       | 01/13/86    |
| 68-12-2 | Dimethyl formamide-Formamide, N,N-dimethyl- .....    | .....              | 4/13/89        | 12/19/95    |
| 71-55-6 | 1,1,1-Trichloroethane—Ethane, 1,1,1-trichloro- ..... | .....              | 10/04/82       | 10/04/92    |

| CAS No. | Substance   | Special exemptions | Effective date | Sunset date |
|---------|---|--------------------|----------------|-------------|
| 74–83–9 | Methane, bromo- .....   | .....              | 06/01/87       | 06/01/97    |
| 74–87–3 | Chloromethane—Methane, chloro- .....  | .....              | 10/04/82       | 10/04/92    |
| 74–95–3 | Methane, dibromo- .....   | .....              | 6/1/87         | 12/19/95    |
| 74–97–5 | Methane, bromochloro- .....   | .....              | 6/1/87         | 12/19/95    |
| 75–00–3 | Ethane, chloro- .....   | .....              | 06/01/87       | 06/01/97    |
| 75–02–5 | Vinyl fluoride—Ethene, fluoro- .....  | .....              | 10/04/82       | 10/04/92    |
| 75–04–7 | Ethanamine .....  | .....              | 6/1/87         | 12/19/95    |
| 75–05–8 | Acetonitrile .....  | .....              | 10/04/82       | 10/04/92    |
| 75–09–2 | Methylene chloride—Methane, dichloro- .....   | .....              | 10/04/82       | 10/04/92    |
| 75–12–7 | Formamide .....   | .....              | 04/29/83       | 04/29/93    |
| 75–21–8 | Oxirane .....   | .....              | 10/04/82       | 10/04/92    |
| 75–25–2 | Methane, tribromo- .....  | .....              | 06/01/87       | 06/01/97    |
| 75–27–4 | Methane, bromodichloro- .....   | .....              | 6/1/87         | 12/19/95    |
| 75–29–6 | Propane, 2-chloro- .....  | .....              | 6/1/87         | 12/19/95    |
| 75–34–3 | Ethane, 1,1-dichloro- .....   | .....              | 06/01/87       | 06/01/97    |
| 75–37–6 | 1,1-Difluoroethane—Ethane, 1,1-difluoro- .....  | .....              | 4/13/89        | 12/19/95    |
| 75–38–7 | Vinylidene fluoride—Ethene, 1,1-difluoro- .....                                       | .....              | 10/04/82       | 10/04/92    |
| 75–43–4 | Dichloromonofluoromethane—Methane, dichlorofluoro- .....                              | .....              | 4/13/89        | 12/19/95    |
| 75–45–6 | Chlorodifluoromethane—Methane, chlorodifluoro- .....                                  | .....              | 4/13/89        | 6/30/98     |
| 75–52–5 | Nitromethane—Methane, nitro- .....  | .....              | 4/13/89        | 12/19/95    |
| 75–56–9 | Oxirane, methyl- .....  | .....              | 10/04/82       | 10/04/92    |
| 75–68–3 | 1-Chloro-1,1-difluoroethane—Ethane, 1-chloro-1,1-difluoro- .....                      | .....              | 4/13/89        | 12/19/95    |
| 75–86–5 | Propanenitrile, 2-hydroxy-2-methyl- .....   | .....              | 3/7/86         | 12/19/95    |
| 75–88–7 | Ethane, 2-chloro- 1,1,1-trifluoro .....   | .....              | 10/15/90       | 11/09/93    |
| 76–13–1 | 1,1,2-Trichloro-1,2,2-trifluoroethane—Ethane, 1,1,2-trichloro-1,2,2-trifluoro-1. .... | .....              | 4/13/89        | 12/19/95    |
| 77–47–4 | Hexachlorocyclopentadiene—1,3-Cyclopentadiene, 1,2,3,4,5,5-hexachloro- .....          | .....              | 10/04/82       | 10/04/92    |
| 77–58–7 | Dibutyltin dilaurate—Stannane, dibutylbis[(1-oxododecyl)oxy]- .....                   | .....              | 01/03/83       | 01/03/93    |
| 78–59–1 | Isophorone—2-Cyclohexen-1-one, 3,5,5-trimethyl- .....                                 | .....              | 10/04/82       | 10/04/92    |
| 78–83–1 | 1-Propanol, 2-methyl- .....   | .....              | 03/07/86       | 03/07/96    |
| 78–87–5 | 1,2-Dichloropropane—Propane, 1,2-dichloro- .....                                      | .....              | 10/04/82       | 10/04/92    |
| 78–88–6 | 1-Propene, 2,3-dichloro- .....  | .....              | 6/1/87         | 12/19/95    |
| 78–93–3 | Methyl ethyl ketone—2-Butanone .....  | .....              | 10/04/82       | 10/04/92    |
| 78–97–7 | Propanenitrile, 2-hydroxy- .....  | .....              | 6/1/87         | 12/19/95    |
| 78–99–9 | Propane, 1,1-dichloro- .....  | .....              | 3/7/86         | 12/19/95    |
| 79–00–5 | Ethane, 1,1,2-trichloro- .....  | .....              | 06/01/87       | 06/01/97    |
| 79–06–1 | Acrylamide—2-Propenamide .....  | .....              | 10/04/82       | 10/04/92    |
| 79–24–3 | Nitroethane—Ethane, nitro- .....  | .....              | 4/13/89        | 12/19/95    |
| 79–94–7 | Tetrabromobisphenol A—Phenol, 4,4'-(methylene)bis[2,6-dibromo- .....                  | .....              | 06/20/85       | 06/20/95    |
| 80–05–7 | Bisphenol A—Phenol, 4,4'-(1-methylethylidene)bis- .....                               | .....              | 06/28/84       | 06/28/94    |
| 80–15–9 | Hydroperoxide, 1-methyl-1-phenylethyl .....   | .....              | 3/7/86         | 12/19/95    |
| 80–62–6 | Methyl methacrylate—2-Propenoic acid, 2-methyl-, methyl ester. ....                   | .....              | 4/13/89        | 6/30/98     |
| 84–65–1 | Anthraquinone—9,10-Anthracenedione .....  | .....              | 12/28/84       | 11/09/93    |
| 85–22–3 | Pentabromoethylbenzene—Benzene, pentabromoethyl- .....                                | .....              | 12/28/84       | 12/28/94    |
| 85–68–7 | Benzyl butyl phthalate—1,2-Benzenedicarboxylic acid, butyl phenylmethyl ester. ....   | .....              | 04/29/83       | 04/29/93    |
| 86–74–8 | 9H-Carbazole .....  | .....              | 03/07/86       | 03/07/96    |
| 87–68–3 | Hexachloro-1,3-butadiene—1,3-Butadiene, 1,1,2,3,4,4-hexachloro- .....                 | .....              | 10/04/82       | 10/04/92    |
| 88–04–0 | p-Chloro-m-xylene—Phenol, 4-chloro-3,5-dimethyl- .....                                | .....              | 4/13/89        | 12/19/95    |
| 90–30–2 | N-Phenyl-1-naphthylamine .....  | .....              | 9/30/91        | 12/19/95    |
| 90–42–6 | [1,1'-Bicyclohexyl]-2-one .....   | .....              | 06/01/87       | 11/09/93    |
| 91–08–7 | Benzene, 1,3-diisocyanato-2-methyl- .....   | .....              | 6/1/87         | 12/19/95    |
| 91–20–3 | Naphthalene .....   | .....              | 06/01/87       | 06/01/97    |
| 91–58–7 | Naphthalene, 2-chloro- .....  | .....              | 10/04/82       | 10/04/92    |
| 92–52–4 | 1,1'-Biphenyl .....   | .....              | 04/29/83       | 04/29/93    |
| 92–69–3 | [1,1'-Biphenyl]-4-ol .....  | .....              | 6/1/87         | 12/19/95    |
| 92–84–2 | 10H-Phenothiazine .....   | .....              | 06/01/87       | 06/01/97    |
| 92–87–5 | [1,1'-Biphenyl]-4,4'-diamine .....  | .....              | 06/01/87       | 06/01/97    |
| 95–14–7 | 1,2,3-Benzotriazole-1H—Benzotriazole .....  | .....              | 4/13/89        | 12/19/95    |
| 95–47–6 | o-Xylene—Benzene, 1,2-dimethyl- .....   | .....              | 10/04/82       | 10/04/92    |
| 95–48–7 | o-Cresol—Phenol, 2-methyl- .....  | .....              | 10/04/82       | 10/04/92    |
| 95–49–8 | 2-Chlorotoluene—Benzene, 1-chloro-2-methyl- .....                                     | .....              | 04/29/83       | 04/29/93    |
| 95–53–4 | Benzenamine, 2-methyl- .....  | .....              | 3/7/86         | 12/19/95    |
| 95–63–6 | 1,2,4-Trimethylbenzene—Benzene, 1,2,4-trimethyl- .....                                | .....              | 04/29/83       | 04/29/93    |
| 96–18–4 | Propane, 1,2,3-trichloro- .....   | .....              | 06/01/87       | 06/01/97    |
| 96–29–7 | 2-Butanone, oxime .....   | .....              | 12/15/86       | 12/19/95    |

Environmental Protection Agency

§ 716.120

| CAS No.  | Substance  | Special exemptions | Effective date | Sunset date |
|----------|--|--------------------|----------------|-------------|
| 96-37-7  | Methylcyclopentane—Cyclopentane, methyl-   |                    | 06/20/85       | 11/09/93    |
| 97-18-7  | Phenol, 2,2'-thiobis[4,6-dichloro-   |                    | 6/1/87         | 12/19/95    |
| 97-23-4  | Phenol, 2,2'-methylenebis[4-chloro-  |                    | 6/1/87         | 12/19/95    |
| 97-88-1  | Butyl methacrylate-2-Propenoic acid, 2-methyl-,butyl ester.                              |                    | 4/13/89        | 12/19/95    |
| 98-01-1  | 2-Furancarboxaldehyde  |                    | 06/01/87       | 06/01/97    |
| 98-06-6  | Benzene, (1,1-dimethylethyl)-  |                    | 6/1/87         | 12/19/95    |
| 98-09-9  | Benzenesulfonyl chloride   |                    | 3/7/86         | 12/19/95    |
| 98-51-1  | <i>p</i> -tert-Butyltoluene—Benzene, 1-(1,1-dimethylethyl)-4-methyl-                     |                    | 06/25/86       | 06/25/96    |
| 98-56-6  | 4-Chlorobenzotrifluoride—Benzene, 1-chloro-4-(trifluoromethyl)-                          |                    | 04/29/83       | 04/29/93    |
| 98-73-7  | <i>p</i> -tert-Butylbenzoic acid—Benzoic acid, 4-(1,1-dimethylethyl)-                    |                    | 6/25/86        | 12/19/95    |
| 98-82-8  | Cumene—Benzene, (1-methylethyl)-   |                    | 12/28/84       | 12/28/94    |
| 98-83-9  | Benzene, (1-methylethyl)-  |                    | 06/01/87       | 11/09/93    |
| 98-95-3  | Nitrobenzene—Benzene, nitro-   |                    | 10/04/82       | 10/04/92    |
| 100-02-7 | <i>p</i> -Nitrophenol—Phenol, 4-nitro-   |                    | 4/13/89        | 6/30/98     |
| 100-40-3 | 4-Vinylcyclohexene   |                    | 1/11/90        | 11/09/93    |
| 100-41-4 | Benzene, ethyl-  |                    | 06/19/87       | 06/19/97    |
| 100-48-1 | 4-Pyridinecarbonitrile   |                    | 06/01/87       | 06/01/87    |
| 100-54-9 | 3-Pyridinecarbonitrile   |                    | 06/01/87       | 12/29/88    |
| 100-70-9 | 2-Pyridinecarbonitrile   |                    | 06/01/87       | 11/09/93    |
| 101-68-8 | Benzene, 1,1'-methylenebis[4-isocyanato-   |                    | 06/01/87       | 06/01/97    |
| 101-77-9 | Benzenamine, 4,4'-methylenebis-  |                    | 10/04/82       | 10/04/92    |
| 101-84-8 | Diphenyl oxide—Benzene, 1,1'-oxybis-   |                    | 4/13/89        | 6/30/98     |
| 102-71-6 | Triethanolamine-Ethanol, 2,2',2'-nitrioltris-  |                    | 4/13/89        | 12/19/95    |
| 104-49-4 | Benzene, 1,4-diisocyanato-   |                    | 06/01/87       | 11/09/93    |
| 104-51-8 | Benzene, butyl-  |                    | 6/1/87         | 12/19/95    |
| 104-76-7 | 1-Hexanol, 2-ethyl-  |                    | 6/1/87         | 12/19/95    |
| 105-60-2 | 2 <i>H</i> -Azepin-2-one, hexahydro-   |                    | 06/01/87       | 06/01/97    |
| 106-42-3 | <i>p</i> -Xylene—Benzene, 1,4-dimethyl-  |                    | 10/04/82       | 10/04/92    |
| 106-43-4 | Benzene, 1-chloro-4-methyl-  |                    | 6/1/87         | 12/19/95    |
| 106-44-5 | <i>p</i> -Cresol—Phenol, 4-methyl-   |                    | 10/04/82       | 10/04/92    |
| 106-49-0 | Benzenamine, 4-methyl-   |                    | 03/07/86       | 03/07/96    |
| 106-50-3 | <i>p</i> -Phenylenediamine—1,4-Benzenediamine  |                    | 10/04/82       | 10/04/92    |
| 106-51-4 | Quinone—2,5-Cyclohexadiene-1,4-dione   |                    | 10/04/82       | 10/04/92    |
| 106-88-7 | Oxirane, ethyl-  |                    | 10/04/82       | 10/04/92    |
| 106-89-8 | Oxirane, (chloromethyl)-   |                    | 10/04/82       | 10/04/92    |
| 107-06-2 | Ethane, 1,2-dichloro-  |                    | 06/01/87       | 06/01/97    |
| 107-10-8 | 1-Propanamine  |                    | 3/7/86         | 12/19/95    |
| 107-19-7 | 2-Propyn-1-ol  |                    | 3/7/86         | 12/19/95    |
| 107-98-2 | 1-Methoxy-2-propanol—2-Propanol, 1-methoxy-  |                    | 4/13/89        | 6/30/98     |
| 108-05-4 | Vinyl acetate—Acetic acid ethenyl ester  |                    | 02/10/86       | 02/10/96    |
| 108-10-1 | Methyl isobutyl ketone—2-Pentanone, 4-methyl-  |                    | 10/04/82       | 10/04/92    |
| 108-31-6 | Maleic anhydride—2,5-Furandione  |                    | 09/10/84       | 09/10/94    |
| 108-38-3 | <i>m</i> -Xylene—Benzene, 1,3-dimethyl-  |                    | 10/04/82       | 10/04/92    |
| 108-39-4 | <i>m</i> -Cresol—Phenol, 3-methyl-   |                    | 10/04/82       | 10/04/92    |
| 108-60-1 | Propane, 2,2'-oxybis[1-chloro-   |                    | 6/1/87         | 12/19/95    |
| 108-67-8 | 1,3,5-Trimethylbenzene—Benzene, 1,3,5-trimethyl-   |                    | 02/13/84       | 02/13/94    |
| 108-86-1 | Benzene, bromo-  |                    | 6/1/87         | 12/19/95    |
| 108-88-3 | Toluene—Benzene, methyl-   |                    | 10/04/82       | 10/04/92    |
| 108-89-4 | 4-Methylpyridine—Pyridine, 4-methyl-   |                    | 09/10/84       | 09/10/94    |
| 108-94-1 | Cyclohexanone  |                    | 10/04/82       | 10/04/92    |
| 108-95-2 | Phenol   |                    | 06/01/87       | 06/01/97    |
| 108-95-5 | Thiophenol   |                    | 1/26/94        | 12/19/95    |
| 108-98-5 | Benzenethiol   |                    | 03/07/86       | 03/07/96    |
| 108-99-6 | 3-Methylpyridine—Pyridine, 3-methyl-   |                    | 09/10/84       | 09/10/94    |
| 109-06-8 | 2-Methylpyridine—Pyridine, 2-methyl-   |                    | 09/10/84       | 09/10/94    |
| 109-77-3 | Propanedinitrile   |                    | 3/7/86         | 12/19/95    |
| 109-87-5 | Methane, Dimethoxy-  |                    | 6/1/87         | 12/19/95    |
| 109-89-7 | Ethanamine, <i>N</i> -ethyl-   |                    | 06/01/87       | 06/01/97    |
| 110-75-8 | Ethene, (2-chloroethoxy)-  |                    | 3/7/86         | 12/19/95    |
| 110-82-7 | Cyclohexane  |                    | 12/19/85       | 12/19/95    |
| 110-86-1 | Pyridine   |                    | 10/04/82       | 10/04/92    |
| 111-21-7 | Ethylene bisoxyethylene diacetate—Ethanol, 2,2'-[1,2-ethanedilybis(oxy)]bis-, diacetate. |                    | 01/13/84       | 12/29/88    |
| 111-40-0 | Diethylenetriamine—1,2-Ethanediamine, <i>N</i> -(2-aminoethyl)-                          |                    | 04/29/83       | 04/29/93    |
| 111-42-2 | Diethanolamine—Ethanol, 2,2'-iminobis-   |                    | 4/13/89        | 6/30/98     |
| 111-69-3 | Hexanedinitrile  |                    | 6/1/87         | 12/19/95    |
| 111-76-2 | 2-Butoxyethanol—Ethanol, 2-butoxy-   |                    | 4/13/89        | 6/30/98     |
| 111-77-3 | Diethylene glycol monomethyl ether-Ethanol, 2-(2-methoxyethoxy)-                         |                    | 4/13/89        | 12/19/95    |



| CAS No.  | Substance   | Special exemptions | Effective date | Sunset date |
|----------|---|--------------------|----------------|-------------|
| 111-90-0 | Diethylene glycol monoethyl ether-Ethanol, 2-(2-ethoxyethoxy)-  |                    | 4/13/89        | 12/19/95    |
| 111-91-1 | Ethane, 1,1'-[methylenebis(oxy)]bis[2-chloro-   |                    | 3/7/86         | 12/19/95    |
| 111-92-2 | 1-Butanamine, N-butyl-  |                    | 6/1/87         | 12/19/95    |
| 112-35-6 | Triethyleneglycol monomethyl ether—Ethanol, 2-[2-(2-methoxyethoxy)ethoxy]-                                      |                    | 06/20/85       | 06/20/95    |
| 112-50-5 | Triethyleneglycol monoethyl ether—Ethanol, 2-[2-(2-ethoxyethoxy)ethoxy]-  |                    | 06/20/85       | 06/20/95    |
| 112-90-3 | Oleylamine—9-Octadecen-1-amine, (Z)-  |                    | 01/13/84       | 01/13/94    |
| 115-28-6 | Chlorendic acid—Bicyclo[2.2.1] hept-5-ene-2,3-dicarboxylic acid, 1,4,5,6,7,7-hexachloro-                        |                    | 04/29/83       | 01/13/86    |
| 115-96-8 | Ethanol, 2-chloro-, phosphate (3:1)   |                    | 12/16/88       | 11/09/93    |
| 118-79-6 | 2,4,6-Tribromophenol  |                    | 1/11/90        | 6/30/98     |
| 120-20-7 | Anthracene  |                    | 06/01/87       | 06/01/97    |
| 120-32-1 | 2-Benzyl-4-chlorophenol-Phenol, 4-chloro-2-chlorophenol(phenyl methyl)-   |                    | 4/13/89        | 12/19/95    |
| 121-44-8 | Ethanamine, N,N-diethyl-  |                    | 01/13/84       | 01/13/94    |
| 121-47-1 | Benzenesulfonic acid, 3-amino-  |                    | 06/01/87       | 12/29/88    |
| 122-09-8 | Benzeneethanamine, alpha,alpha-dimethyl-  |                    | 3/7/86         | 12/19/95    |
| 122-66-7 | Hydrazine, 1,2-diphenyl-  |                    | 06/01/87       | 06/01/97    |
| 122-99-6 | 2-Phenoxyethanol—Ethanol, 2-phenoxy-  |                    | 07/01/83       | 07/01/93    |
| 123-31-9 | Hydroquinone—1,4-Benzenediol  |                    | 10/04/84       | 10/04/94    |
| 123-61-5 | Benzene, 1,3-diisocyanato-  |                    | 06/01/87       | 11/09/93    |
| 123-72-8 | Butanal   |                    | 12/16/88       | 12/19/95    |
| 124-16-3 | 1-Butoxyethoxy-2-propanol-2-Propanol, 1-(2-butoxyethoxy)-   |                    | 4/13/89        | 12/19/95    |
| 124-17-4 | 2-(2-Butoxyethoxy)ethyl acetate—Ethanol, 2-(2-butoxyethoxy)-, acetate.  |                    | 01/13/82       | 01/13/92    |
| 124-48-1 | Methane, dibromochloro-   |                    | 06/01/87       | 06/01/97    |
| 126-73-8 | Phosphoric acid, tributyl ester   |                    | 06/18/86       | 06/18/96    |
| 126-99-8 | Chloroprene—1,3-Butadiene, 2-chloro-  |                    | 12/28/84       | 12/28/94    |
| 127-18-4 | Ethene, tetrachloro-  |                    | 06/01/87       | 06/01/97    |
| 128-39-2 | Phenol, 2,6-bis(1,1-dimethylethyl)-   |                    | 12/19/85       | 11/09/93    |
| 128-86-9 | 2,6-Anthracenedisulfonic acid, 4,8-diamino-9,10-dihydro-1,5-dihydroxy-9,10-dioxo-                               |                    | 12/21/87       | 11/09/93    |
| 129-00-0 | Pyrene  |                    | 06/01/87       | 06/01/97    |
| 131-17-9 | Diallyl phthalate-1,2-Benzenedicarboxylic acid, di-2-propenyl ester.  |                    | 4/13/89        | 12/19/95    |
| 135-98-8 | Benzene, (1-methylpropyl)-  |                    | 6/1/87         | 12/19/95    |
| 136-35-6 | 1-Triazene, 1,3-diphenyl-   | § 716.21(a)(5)     | 6/3/04         | 8/2/04      |
| 137-20-2 | Soldium N-methyl-N-oleoyltaurine—Ethanesulfonic acid, 2-[methyl (1-oxo-9-octadecenyl)amino]-, sodium salt, (Z)- |                    | 12/28/84       | 12/28/94    |
| 137-26-8 | Thioperoxydicarbonic diamide, tetramethyl-  |                    | 6/1/87         | 12/19/95    |
| 139-25-3 | Benzene, 1,1'-methylenebis[4-isocyanato-3-methyl-   |                    | 06/01/87       | 11/09/93    |
| 140-08-9 | Tris(2-chloroethyl)phosphite—Ethanol, 2-chloro-, phosphite (3:1).   |                    | 04/29/83       | 01/13/86    |
| 140-66-9 | 4-(1,1,3,3-Tetramethylbutyl) phenol—Phenol, 4-(1,1,3,3-tetramethylbutyl)-                                       |                    | 01/30/83       | 12/29/88    |
| 140-88-5 | Ethyl acrylate—2-Propenoic acid, ethyl ester  |                    | 4/13/89        | 6/30/98     |
| 141-79-7 | Mesityl oxide—3-Penten-2-one, 4-methyl-   |                    | 10/04/82       | 10/04/92    |
| 142-28-9 | Propane, 1,3-dichloro-  |                    | 3/7/86         | 12/19/95    |
| 142-84-7 | 1-Propanamine, N-propyl-  |                    | 03/07/86       | 12/5/90     |
| 143-22-6 | Triethyleneglycol monobutyl ether—Ethanol, 2-[2-(2-butoxyethoxy)ethoxy]-  |                    | 06/20/85       | 06/20/95    |
| 143-33-9 | Sodium cyanide  |                    | 10/29/90       | 12/19/95    |
| 149-30-4 | Mercaptobenzothiazole—2(3H-Benzothiazolethione  |                    | 12/28/84       | 12/28/94    |
| 149-57-5 | 2-Ethylhexanoic acid—Hexanoic acid, 2-ethyl-  |                    | 06/28/84       | 06/28/94    |
| 306-83-2 | Ethane, 2,2-dichloro-1,1,1-trifluoro  |                    | 10/15/90       | 11/09/93    |
| 328-84-7 | 3,4-Dichlorobenzotrifluoride—Benzene, 1,2-dichloro-4-(trifluoromethyl)-   |                    | 05/08/85       | 11/09/93    |
| 354-33-6 | Ethane, pentafluoro   |                    | 10/15/90       | 11/09/93    |
| 357-57-3 | Strychnidin-10-one, 2,3-dimethoxy-  |                    | 3/7/86         | 12/19/95    |
| 428-59-1 | Oxirane, trifluoro(trifluoromethyl)-  |                    | 10/04/82       | 10/04/92    |
| 496-46-8 | Imidazo[4,5-d]imidazole-2,5-(1H,3H)-dione, tetrahydro-  | § 716.21(a)(1)     | 6/3/04         | 8/2/04      |
| 472-41-3 | Phenol, 4-(3,4-dihydro-2,2,4-trimethyl-2H-1-benzopyran-4-yl)-   |                    | 06/01/87       | 12/29/88    |
| 506-96-7 | Acetyl bromide  |                    | 6/1/87         | 12/19/95    |
| 526-73-8 | 1,2,3-Trimethylbenzene—Benzene, 1,2,3-trimethyl-  |                    | 02/13/84       | 11/09/93    |
| 530-50-7 | Hydrazine, 1,1-diphenyl-  |                    | 6/1/87         | 12/19/95    |
| 534-07-6 | 2-Propanone, 1,3-dichloro-  |                    | 6/1/87         | 12/19/95    |
| 540-54-5 | Propane, 1-chloro-  |                    | 6/1/87         | 12/19/95    |
| 540-84-1 | Pentane, 2,2,4-trimethyl-   |                    | 6/1/87         | 12/19/95    |

Environmental Protection Agency

§ 716.120

| CAS No.   | Substance  | Special exemptions     | Effective date | Sunset date |
|-----------|--|------------------------|----------------|-------------|
| 542-75-6  | 1-Propene, 1,3-dichloro- .....   | .....                  | 06/01/87       | 06/01/97    |
| 556-67-2  | Octamethylcyclotetrasiloxane—Cyclotetrasiloxane, octamethyl- .....                                     | .....                  | 12/28/84       | 12/28/94    |
| 563-54-2  | 1-Propene, 1,2-dichloro- .....   | .....                  | 03/07/86       | 12/29/88    |
| 563-58-6  | 1-Propene, 1,1-dichloro- .....   | .....                  | 03/07/86       | 12/29/88    |
| 580-51-8  | [1,1'-Biphenyl]-3-ol .....   | .....                  | 06/01/87       | 11/09/93    |
| 584-84-9  | Benzene, 2,4-diisocyanato-1-methyl- .....  | .....                  | 06/01/87       | 06/01/97    |
| 591-08-2  | Acetamide, N-(aminothioxomethyl)- .....  | .....                  | 3/7/86         | 12/19/95    |
| 594-20-7  | Propane, 2,2-dichloro- .....   | .....                  | 3/7/86         | 12/19/95    |
| 598-21-0  | Acetyl bromide, bromo- .....   | .....                  | 6/1/87         | 12/19/95    |
| 598-31-2  | 2-Propanone, 1-bromo- .....  | .....                  | 3/7/86         | 12/19/95    |
| 616-23-9  | 1-Propanol, 2,3-dichloro- .....  | .....                  | 3/7/86         | 12/19/95    |
| 620-14-4  | <i>m</i> -Ethyltoluene—Benzene, 1-ethyl-3-methyl- .....  | .....                  | 04/29/83       | 04/29/93    |
| 622-96-8  | <i>p</i> -Ethyltoluene—Benzene, 1-ethyl-4-methyl- .....  | .....                  | 04/29/83       | 04/29/93    |
| 630-20-6  | Ethane, 1,1,1,2-tetrachloro- .....   | .....                  | 6/1/87         | 12/19/95    |
| 632-79-1  | Tetrabromophthalic anhydride .....   | .....                  | 1/11/90        | 12/19/95    |
| 637-92-3  | Ethyl- <i>tert</i> -butyl ether .....  | § 716.20(b)(3) applies | 12/28/94       | 6/30/98     |
| 646-06-0  | 1,3-Dioxolane .....  | .....                  | 01/03/83       | 01/03/93    |
| 677-21-4  | Trifluoromethylethene—1-Propene, 3,3,3-trifluoro- .....  | .....                  | 04/29/83       | 01/13/86    |
| 685-91-6  | Acetamide, <i>N,N</i> -diethyl- .....  | .....                  | 06/01/87       | 11/09/93    |
| 692-42-2  | Arsine, diethyl- .....   | .....                  | 3/7/86         | 12/19/95    |
| 696-28-6  | Arsonous dichloride, phenyl- .....   | .....                  | 3/7/86         | 12/19/95    |
| 757-58-4  | Tetraphosphoric acid, hexaethyl ester .....  | .....                  | 3/7/86         | 12/19/95    |
| 811-97-2  | Ethane, 1,1,2-tetrafluoro- .....   | .....                  | 10/15/90       | 11/09/93    |
| 812-03-3  | Propane, 1,1,1,2-tetrachloro- .....  | .....                  | 6/1/87         | 12/19/95    |
| 822-06-0  | Hexane, 1,6-diisocyanato- .....  | .....                  | 6/1/87         | 12/19/95    |
| 828-00-2  | 1,3-Dioxan-4-ol, 2,6-dimethyl-, acetate .....  | .....                  | 6/1/87         | 12/19/95    |
| 930-22-3  | Oxirane, ethenyl- .....  | .....                  | 10/04/82       | 10/04/92    |
| 939-97-9  | <i>p-tert</i> -Butylbenzaldehyde—Benzaldehyde, 4-(1,1-dimethylethyl)- .....                            | .....                  | 06/25/86       | 11/09/93    |
| 994-05-8  | <i>Tert</i> -amyl methyl ether .....   | § 716.20(b)(3) applies | 12/28/94       | 06/30/98    |
| 1000-82-4 | Methylolurea—Urea, (hydroxymethyl)- .....  | .....                  | 07/01/83       | 07/01/93    |
| 1070-78-6 | Propane, 1,1,1,3-tetrachloro- .....  | .....                  | 6/1/87         | 12/19/95    |
| 1163-19-5 | Decabromodiphenyl ether .....  | .....                  | 1/11/90        | 06/30/98    |
| 1185-81-5 | Dibutyltin bis(lauryl mercaptide)—Stannane, dibutylbis(dodecylthio). .....                             | .....                  | 01/03/83       | 01/03/93    |
| 1208-52-2 | Benzenamine, 2-[(4-aminophenyl)methyl]- .....  | .....                  | 06/01/87       | 11/09/93    |
| 1300-71-6 | Phenol, dimethyl- .....  | .....                  | 6/1/87         | 12/19/95    |
| 1309-64-4 | Antimony trioxide .....  | .....                  | 10/04/82       | 10/04/92    |
| 1321-38-6 | Benzene, diisocyanatomethyl-(unspecified isomer) .....   | .....                  | 06/01/87       | 11/09/93    |
| 1321-64-8 | Naphthalene, pentachloro- .....  | .....                  | 10/04/82       | 10/04/92    |
| 1321-65-9 | Naphthalene, trichloro- .....  | .....                  | 10/04/82       | 10/04/92    |
| 1331-47-1 | [1,1'-Biphenyl]-4,4'-diamino, dichloro- .....  | .....                  | 06/01/87       | 11/09/93    |
| 1333-41-1 | Methyl pyridine—Pyridine, methyl- .....  | .....                  | 09/10/84       | 12/29/88    |
| 1335-87-1 | Naphthalene, hexachloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 1335-88-2 | Naphthalene, tetrachloro- .....  | .....                  | 10/04/82       | 10/04/92    |
| 1345-04-6 | Antimony trisulfide .....  | .....                  | 10/04/82       | 10/04/92    |
| 1464-53-5 | 2,2'-Bioxirane .....   | .....                  | 10/04/82       | 10/04/92    |
| 1634-04-4 | Propane, 2-methoxy-2-methyl- .....   | .....                  | 12/15/86       | 12/15/96    |
| 1649-08-7 | Ethane, 1,2-dichloro-1,1-difluoro .....  | .....                  | 10/15/90       | 12/19/95    |
| 1717-00-6 | Ethane, 1,1-dichloro-1-fluoro- .....   | .....                  | 10/15/90       | 11/09/93    |
| 1825-30-5 | Naphthalene, 1,5-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 1825-31-6 | Naphthalene, 1,4-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 1888-71-7 | 1-Propene, 1,1,2,3,3,3-hexachloro- .....   | .....                  | 3/7/87         | 12/19/95    |
| 2050-69-3 | Naphthalene, 1,2-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2050-72-8 | Naphthalene, 1,6-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2050-73-9 | Naphthalene, 1,7-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2050-74-0 | Naphthalene, 1,8-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2050-75-1 | Naphthalene, 2,3-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2065-70-5 | Naphthalene, 2,6-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2198-75-6 | Naphthalene, 1,3-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2198-77-8 | Naphthalene, 2,7-dichloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2234-13-1 | Naphthalene, octachloro- .....   | .....                  | 10/04/82       | 10/04/92    |
| 2536-05-2 | Benzene, 1,1'-methylenebis[2-isocyanato- .....   | .....                  | 06/01/87       | 11/09/93    |
| 2556-36-7 | Cyclohexane, 1,4-diisocyanato .....  | .....                  | 06/01/87       | 11/09/93    |
| 2763-96-4 | 3(2H)-Isoxazolone, 5-(aminomethyl)- .....  | .....                  | 3/7/86         | 2/19/95     |
| 2778-42-9 | Benzene, 1,3-bis(1-isocyanato-1-methylethyl)- .....  | .....                  | 06/01/87       | 11/09/93    |
| 2861-02-1 | 2,6-Anthracenedisulfonic acid, 4,8-diamino-9,10-dihydro-1,5-dihydroxy-9,10-dioxo-, disodium salt ..... | .....                  | 12/21/87       | 12/19/95    |
| 2873-89-0 | Ethane, 2-chloro-1,1,1,2-tetrafluoro- .....  | .....                  | 10/15/90       | 11/09/93    |
| 3083-25-8 | Oxirane, (2,2,2-trichloroethyl)- .....   | .....                  | 10/04/82       | 10/04/92    |
| 3173-72-6 | Naphthalene, 1,5-diisocyanato- .....   | .....                  | 6/1/87         | 12/19/95    |
| 3194-55-6 | Hexabromocyclododecane .....   | .....                  | 1/11/90        | 12/19/95    |

| CAS No.    | Substance  | Special exemptions     | Effective date | Sunset date |
|------------|--|------------------------|----------------|-------------|
| 3278–89–5  | Benzene, 1,3,5-tribromo-2-(2-propenyloxy)-   | § 716.21(a)(4)         | 6/3/04         | 8/2/04      |
| 3288–58–2  | Phosphorodithioic acid, O,O-diethyl-S-methyl ester   |                        | 3/7/86         | 12/19/95    |
| 3296–90–0  | 1,3-Propanediol, 2,2-bis(bromomethyl)-   |                        | 6/1/87         | 12/19/95    |
| 3319–31–1  | Tris(2-ethylhexyl) trimellitate—1,2,4-Benzenetricarboxylic acid, tris(2-ethylhexyl)ester.                                  |                        | 01/03/83       | 01/03/93    |
| 3322–93–8  | 1,2-Dibromo-4-(1,2-dibromoethyl) cyclohexane—Cyclohexane, 1,2-dibromo-4-(1,2-dibromoethyl)-                                |                        | 06/28/84       | 12/29/88    |
| 3389–71–7  | 1,2,3,4,7,7-Hexachloronorbomadiene—Bicyclo[2.2.1]hepta-2,5-diene, 1,2,3,4,7,7-hexachloro-                                  |                        | 01/13/84       | 01/13/94    |
| 3618–72–2  | Acetamide, N-[5-[bis(2-(acetyloxy)ethyl)amino]-2-[(2-bromo-4,6-dinitrophenyl)azo]-4-methoxyphenyl]-                        |                        | 06/19/87       | 11/09/93    |
| 3618-73-3  | Acetamide, N-[5-[bis(2-(acetyloxy)ethyl)amino]-2-[(2-chloro-4,6-dinitrophenyl)azo]-4-methoxyphenyl]-                       |                        | 06/19/87       | 11/09/93    |
| 3956–55–6  | Acetamide, N-[5-[bis(2-(acetyloxy)ethyl)amino]-2-[(2-bromo-4,6-dinitrophenyl)azo]-4-ethoxyphenyl]-                         |                        | 12/15/86       | 11/09/93    |
| 4098–71–9  | Cyclohexane, 5-isocyanato-1-(isocyanatomethyl)-1,3,3-trimethyl-  |                        | 06/01/87       | 06/01/97    |
| 4170–30–3  | 2-Butenal  |                        | 3/7/86         | 12/19/95    |
| 5124–30–1  | Cyclohexane, 1,1'-methylenebis[4-isocyanato-   |                        | 06/01/87       | 06/01/97    |
| 5131–66–8  | 1-Butoxy-2-propanol-2-Propanol, 1-butoxy-  |                        | 4/13/89        | 12/19/95    |
| 5344–82–1  | Thiourea, (2-chlorophenyl)-  |                        | 3/7/86         | 12/19/95    |
| 5873–54–1  | Benzene, 1-isocyanato-2-[4-isocyanatophenyl]methyl]-   |                        | 06/01/87       | 11/09/93    |
| 6145–73–9  | 1-Propanol, 2-chloro-, phosphate (3:1)   |                        | 12/16/88       | 11/09/93    |
| 6247–34–3  | 2-Anthracenesulfonic acid, 4-[[4-(acetylamino)phenyl]amino]-1-amino-9,10-dihydro-9,10-dioxo-                               |                        | 12/21/87       | 11/09/93    |
| 6422–86–2  | Bis(2-ethylhexyl) terephthalate—1,4-Benzenedicarboxylic acid, bis(2-ethylhexyl) ester.                                     |                        | 01/03/83       | 01/03/93    |
| 6424–85–7  | 2-Anthracenesulfonic acid, 4-[[4-(acetylamino)phenyl]amino]-1-amino-9,10-dihydro-9,10-dioxo-, monosodium salt.             |                        | 12/21/87       | 12/19/95    |
| 7320–37–8  | Oxirane, tetradecyl-   |                        | 10/04/82       | 10/04/92    |
| 7440–28–0  | Thallium   |                        | 06/01/87       | 06/01/97    |
| 7440–36–0  | Antimony   |                        | 10/04/82       | 10/04/92    |
| 7440–48–4  | Cobalt   |                        | 06/01/87       | 06/01/97    |
| 7723–14–0  | White phosphorus   |                        | 04/12/93       | 06/30/98    |
| 9011–05–6  | Urea, polymer with formaldehyde  | § 716.20(b)(1) applies | 06/03/85       | 06/03/95    |
| 9016–87–9  | Isocyanic acid, polymethylenepolyphenylene ester   |                        | 6/1/87         | 12/19/95    |
| 10347–54–3 | Cyclohexane, 1,4-bis(isocyanatomethyl)-  |                        | 06/01/87       | 06/01/87    |
| 10436–39–2 | 1-Propene, 1,1,2,3-tetrachloro-  |                        | 6/1/87         | 12/19/95    |
| 12001–85–3 | Naphthenic acids, zinc salts   |                        | 6/1/87         | 12/19/95    |
| 12185–10–3 | White phosphorus   |                        | 01/26/94       | 06/30/98    |
| 12217–79–7 | 9,10-Anthracenedione, 1,5-diamino-chloro-4,8-dihydroxy-  |                        | 12/21/87       | 11/09/93    |
| 13414–54–5 | Methallyl 2-nitrophenyl ether—Benzene, 1-[(2-methyl-2-propenyl)oxy]-2-nitro-   |                        | 02/13/84       | 11/09/93    |
| 13414–55–6 | 7-Nitro-2,2-dimethyl-2,3-dihydro-benzofuran—Benzofuran, 2,3-dihydro-2,2-dimethyl-7-nitro-                                  |                        | 02/13/84       | 02/13/94    |
| 13674–84–5 | 2-Propanol, 1-chloro-, phosphate (3:1)   |                        | 12/16/88       | 11/09/93    |
| 13674–87–8 | 2-Propanol, 1,3-dichloro-, phosphate (3:1)   |                        | 12/16/88       | 12/19/95    |
| 15646–96–5 | Hexane, 1,6-diisocyanato-2,4,4-trimethyl-  |                        | 06/01/87       | 11/09/93    |
| 16691–43–3 | 3H-1,2,4-Triazole-3-thione, 5-amino-1,2-dihydro-   | § 716.21(a)(1)         | 6/3/04         | 8/2/04      |
| 16938–22–0 | Hexane, 1,6-diisocyanato-2,2,4-trimethyl-  |                        | 06/01/87       | 11/09/93    |
| 17418–58–5 | 9,10-Anthracenedione, 1-amino-4-hydroxy-2-phenoxy-   |                        | 12/21/87       | 12/19/95    |
| 18495–30–2 | Propane, 1,1,2,3-tetrachloro-  |                        | 06/01/87       | 12/29/88    |
| 18633–25–5 | Oxirane, tridecyl-   |                        | 10/04/82       | 10/04/92    |
| 19660–16–3 | 2-Propenoic acid, 2,3-dibromopropyl ester  |                        | 06/01/87       | 12/29/88    |
| 21429–43–6 | Acetamide, N-[5-[bis(2-(acetyloxy)ethyl)amino]-2-[(2-chloro-4,6-dinitrophenyl)azo]-4-methoxyphenyl]-                       |                        | 06/19/87       | 11/09/93    |
| 25168–06–3 | Isopropyl phenol—Phenol, (1-methylethyl)-  |                        | 04/13/89       | 11/09/93    |
| 25168–21-2 | Dibutyltin bis (isooctyl maleate)—2-Butenoic acid, 4,4'-[[dibutylstannylene]bis(oxy)]bis-[4-oxo-, diisooctyl ester, (Z,Z)- |                        | 01/03/83       | 01/03/93    |
| 25498–49-1 | Tripropylene glycol monomethyl ether-Propanol, [2-(2-methoxy methylethoxy)methylethoxy]-                                   |                        | 4/13/89        | 12/19/95    |
| 25550–14–5 | Benzene, ethylmethyl- (mixed isomers)  |                        | 04/29/83       | 04/29/93    |
| 25550–98–5 | Phosphorous acid, diisodecyl phenyl ester  |                        | 12/19/85       | 12/19/95    |
| 25551–13–7 | Trimethylbenzene—Benzene, trimethyl- (mixed isomers).  |                        | 02/13/84       | 02/13/94    |
| 25640–78–2 | Isopropyl biphenyl—1,1'-Biphenyl, (1-methylethyl)-   |                        | 06/28/84       | 11/09/93    |

Environmental Protection Agency

§ 716.120

| CAS No.    | Substance   | Special exemptions     | Effective date | Sunset date |
|------------|---|------------------------|----------------|-------------|
| 25852-70-4 | Monobutyltin tris (isooctyl) mercapto-acetate—Acetic acid, 2,2',2''-[(butylstannylidene)tris(thio)]tris-, triisooctyl ester.  |                        | 01/03/83       | 01/03/93    |
| 26447-40-5 | Benzene, 1,1'-methylenebis[isocyanato-  |                        | 06/01/87       | 06/01/97    |
| 26471-62-5 | Benzene, 1,3-diisocyanatomethyl-  |                        | 06/01/87       | 06/01/97    |
| 26530-20-1 | 3(2 <i>H</i> )-Isothiazolone, 2-octyl-  |                        | 06/01/87       | 12/29/88    |
| 26952-23-8 | 1-Propene, dichloro-  |                        | 6/1/87         | 12/19/95    |
| 29091-20-1 | Benzenamine, 3-chloro-2,6-dinitro-N,N-dipropyl-4-(trifluoromethyl)-.  | § 716.21(a)(2)         | 6/3/04         | 8/2/04      |
| 29385-43-1 | Tolyl triazole-1 <i>H</i> -Benzotriazole, methyl-   |                        | 4/13/89        | 12/19/95    |
| 32052-51-0 | Isocyanic acid, trimethylcyclohexyl ester   |                        | 06/01/87       | 11/09/93    |
| 32534-81-9 | Pentabromodiphenyl ether  |                        | 1/11/90        | 06/30/98    |
| 32536-52-0 | Octabromodiphenyl ether   |                        | 1/11/90        | 06/30/98    |
| 32588-76-4 | Ethylene Bis-(tetrabromophthalimide)  |                        | 1/11/90        | 12/19/95    |
| 33125-86-9 | Phosphoric acid, 1,2-ethanediy l tetrakis (2-chloroethyl) ester.  |                        | 12/16/88       | 11/09/93    |
| 34590-94-8 | Dipropylene glycol monomethyl ether—Propanol, (2-methoxymethylethoxy)-.   |                        | 4/13/89        | 6/30/98     |
| 37853-59-1 | 1,2-Bis(tribromophenoxy) ethane   |                        | 1/11/90        | 06/30/98    |
| 38661-72-2 | Cyclohexane, 1,3-bis(isocyanatomethyl)-   |                        | 06/01/87       | 11/09/93    |
| 41291-34-3 | Ethylene(5,6-dibromonorbornane-2,3-dicarboximide)   |                        | 1/11/90        | 12/19/95    |
| 52907-07-0 | Ethylene bis(5,6-dibromonorbornane-2,3-dicarboximide).  |                        | 1/26/94        | 12/19/95    |
| 57137-10-7 | Tribrominated polystyrene   |                        | 1/11/90        | 12/19/95    |
| 61262-53-1 | Ethylene bis(pentabromophenoxide)   |                        | 1/11/90        | 12/19/95    |
| 61788-33-8 | Terphenyl, chlorinated  |                        | 10/04/82       | 12/29/88    |
| 61789-36-4 | Calcium naphthenate—Naphthenic acids, calcium salts.  |                        | 07/01/83       | 07/01/93    |
| 61789-51-3 | Cobalt naphthenate—Naphthenic acids, cobalt salts ..  |                        | 07/01/83       | 07/01/93    |
| 61790-14-5 | Lead naphthenate—Naphthenic acids, lead salts .....   |                        | 07/01/83       | 07/01/93    |
| 64742-95-6 | Solvent naphtha (petroleum), light arom   |                        | 2/13/84        | 2/13/94     |
| 68081-84-5 | Oxirane, mono[(C <sub>10-16</sub> -alkyloxy) methyl] derivatives ...  |                        | 10/04/82       | 10/04/92    |
| 68122-86-1 | Imidazolium compounds, 4,5-dihydro-1-methyl-2-nortallow alkyl-1-(2-tallow amidoethyl), methyl sulfates.   |                        | 6/20/88        | 12/19/95    |
| 68153-35-5 | Ethanaminium, 2-amino- <i>N</i> -(2-aminoethyl)- <i>N</i> -(2-hydroxyethyl)- <i>N</i> -methyl-, <i>N,N'</i> -ditallow acyl derivatives, methyl sulfates (salts).    |                        | 06/20/88       | 11/09/93    |
| 68298-46-4 | 7-Amino-2,2-dimethyl-2,3-dihydrobenzofuran—7-Benzofuranamine,2,3-dihydro-2,2-dimethyl-  |                        | 02/13/84       | 12/29/88    |
| 68389-88-8 | Poly(oxy-1,2-ethanediy l), α-[2-[bis(2-aminoethyl)methylammonio]ethyl]-ω-hydroxy-, <i>N,N'</i> -dicoco acyl derivatives, methyl sulfates (salts).                   |                        | 06/20/88       | 11/09/93    |
| 68389-89-9 | Poly(oxy-1,2-ethanediy l), α-[2-[bis(2-aminoethyl)methylammonio]ethyl]-ω-hydroxy-, <i>N,N'</i> -bis(hydrogenated tallow acyl) derivatives, methyl sulfates (salts). |                        | 06/20/88       | 11/09/93    |
| 68410-69-5 | Poly(oxy-1,2-ethanediy l), alpha-[2-[bis(2-aminoethyl)methylammonio]ethyl]-w-hydroxy-, <i>N,N'</i> -ditallow acyl derivatives, methyl sulfates (salts).             |                        | 6/20/88        | 12/19/95    |
| 68413-04-7 | Poly[oxy(methyl-1,2-ethanediy l)], α-[2-[bis(2-aminoethyl)methylammonio] methylethyl]-ω-hydroxy-, <i>N,N'</i> -ditallow acyl derivatives, methyl sulfates (salts).  |                        | 06/20/88       | 11/09/93    |
| 68554-06-3 | Poly(oxy-1,2-ethanediy l), α-[3-[bis(2-aminoethyl)methylammonio]-2-hydroxy-propyl]-ω-hydroxy-, <i>N</i> -coco acyl derivatives, methyl sulfates (salts).            |                        | 06/20/88       | 11/09/93    |
| 68611-64-3 | Urea, reaction products with formaldehyde   | § 716.20(b)(1) applies | 06/03/85       | 11/09/93    |
| 68928-76-7 | Stannane, dimethylbis[(1-oxoneodecyl)oxy]-  | § 716.21(a)(3)         | 6/3/04         | 8/2/04      |
| 69009-90-1 | Diisopropyl biphenyl—1,1'-Biphenyl, bis(1-methylethyl)-.  |                        | 06/28/84       | 12/29/88    |
| 70914-09-9 | Poly(oxy-1,2-ethanediy l), α-[2-[bis(2-aminoethyl)methylammonio]ethyl]-ω-hydroxy-, <i>N,N'</i> -di[C <sub>14-18</sub> acyl] derivatives, methyl sulfates (salts).   |                        | 06/20/88       | 06/20/88    |
| 75790-84-0 | Benzene, 2-isocyanato-4-[(4-isocyanatophenyl)methyl]-1-methyl-  |                        | 06/01/87       | 11/09/93    |
| 75790-87-3 | Benzene, 1-isocyanato-2-[(4-isocyanato-phenyl)thio]-  |                        | 06/01/87       | 11/09/93    |

§ 716.120


40 CFR Ch. I (7-1-10 Edition)

(b) [Reserved]


(c) *By category.* The following categories are listed in alphabetical order. Chemical substances listed within a category are provided only as examples of the category. All chemical substances within a category are subject to all the provisions of part 716 for the time period from the effective date of the category until the sunset date.

Manufacturers, importers, and processors of any chemical substance within a category are subject to the reporting requirements of subpart A for that category, except when the sunset date for the particular substance predates the sunset date for the category, or when the exemption of § 716.20(b) of this part applies.

| Category   | CAS No. (examples for category) | Special exemptions | Effective date | Sunset date |
|--|---------------------------------|--------------------|----------------|-------------|
| Alkyl epoxides—including all noncyclic aliphatic hydrocarbons with one or more epoxy functional groups. .... | .....                           | .....              | 10/4/82        | 12/29/88    |




| Category   | CAS No. (examples for category) | Special exemptions | Effective date        | Sunset date |
|--|---------------------------------|--------------------|-----------------------|-------------|
| R <sub>1</sub> =R <sub>2</sub> =R <sub>3</sub> =R <sub>4</sub> =H or alkyl. Groups R <sub>1</sub> –R <sub>4</sub> may contain one or more epoxide functions. |                                 |                    |                       |             |
| Oxirane, decyl- .....  | 2855–19–8                       | .....              | 10/04/82              | 12/29/88    |
| Oxirane, 2, 2 - dimethyl - .....   | 558 – 30 – 5                    | .....              | 10/04/82              | 12/29/88    |
| Oxirane, 2, 3 - dimethyl - .....   | 3266 – 23 – 7                   | .....              | 10/04/82              | 12/29/88    |
| Oxirane, dodecyl .....   | 3234 – 28 – 4                   | .....              | 10/04/82              | 12/29/88    |
| Oxirane, heptadecyl - .....  | 67860 – 04 – 2                  | .....              | 10/04/82              | 12/29/88    |
| Oxirane, octyl- .....  | 2404 – 44 – 6                   | .....              | 10/04/82,<br>12/29/88 |             |
| Oxirane, pentadecyl - .....  | 22092 – 38 – 2                  | .....              | 10/04/82              | 12/29/88    |
| Alkyl phthalates — all alkyl esters of 1, 2-benzenedicarboxylic acid ( <i>ortho</i> -phthalic acid). ....  | .....                           | .....              | 10/04/82              | 10/04/92    |



| Category   | CAS No. (ex-<br>amples for cat-<br>egory) | Special ex-<br>emptions | Effective<br>date | Sunset date |
|--|---|-------------------------|-------------------|-------------|
| R <sub>1</sub> =R <sub>2</sub> =alkyl.   |   |                         |                   |             |
| 1,2-Benzenedicarboxylic acid, bis(2-ethylhexyl) ester .....  | 117-81-7                                  | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, bis(1-methylheptyl) ester .....  | 131-15-7                                  | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, bis(2-methylpropyl) ester .....  | 84-69-5                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, 2-butoxy-2-oxyethyl butyl ester .....  | 85-70-1                                   | .....                   | 10/04/82          | 01/13/86    |
| 1,2-Benzenedicarboxylic acid, butyl cyclohexyl ester .....   | 84-64-0                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, butyl 2-ethylhexyl ester .....   | 85-69-8                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, butyl octyl ester .....  | 84-78-6                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, decyl hexyl ester .....  | 25724-58-7                                | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, decyl octyl ester .....  | 119-07-3                                  | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, dibutyl ester .....  | 84-74-2                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, dicyclohexyl ester .....   | 84-61-7                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, diethyl ester .....  | 84-66-2                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, dihexyl ester .....  | 84-75-3                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, diisodecyl ester .....   | 26761-40-0                                | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, diisononyl ester .....   | 28553-12-0                                | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, diisooctyl ester .....   | 27554-26-3                                | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, demethyl ester .....   | 131-11-3                                  | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, dinonyl ester .....  | 84-76-4                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, dioctyl ester .....  | 117-84-0                                  | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, diundecyl ester .....  | 119-06-2                                  | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, isodecyl tridecyl ester .....  | 3648-20-2                                 | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, 2-ethylhexyl-8-methylnonyl ester .....   | 89-13-4                                   | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, hexyl isodecyl ester .....   | 61702-81-6                                | .....                   | 10/04/82          | 10/04/92    |
| 1,2-Benzenedicarboxylic acid, isodecyl tridecyl ester .....  | 61886-60-0                                | .....                   | 10/04/82          | 10/04/92    |
| Alkyltin compounds .....   |   |                         |                   |             |
| Dibutyltin S,S'-bis(isooctyl mercaptoacetate)—Acetic acid, 2,2'-[(dibutylstannylene)bis(thio)]bis-, diisooctyl ester .....   | 25168-24-5                                | .....                   | 01/03/83          | 12/29/88    |
| Dibutyltin S,S'-bis(isooctyl mercaptoacetate)—Acetic acid, 2,2'-[(dimethylstannylene)bis(thio)]bis-, diisooctyl ester .....  | 26636-01-1                                | .....                   | 01/03/83          | 12/29/88    |
| Mono methyltin tris(isooctylmercaptoacetate) Acetic acid, 2,2',2''-[(methylstannylidene)tris(thio)]tris-triisooctyl ester .. | 54849-38-6                                | .....                   | 01/03/83          | 12/29/88    |
| Aniline and chloro-, bromo-, and/or nitroanilines .....  |   |                         |                   |             |
| Benzenamine .....  | 62-53-3                                   | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 4-bromo- .....  | 106-40-1                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2-bromo-6-chloro-4-nitro- .....   | 99-29-6                                   | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2-bromo-,4,6-dinitro- .....   | 1817-73-8                                 | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2-chloro- .....   | 95-51-2                                   | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 3-chloro- .....   | 108-42-9                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 4-chloro- .....   | 106-47-8                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2-chloro-4,6-dinitro- .....   | 3531-19-9                                 | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 4-chloro-2,6-dinitro- .....   | 5388-62-5                                 | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 3-chloro-, hydrochloride .....  | 141-85-5                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2-chloro-4-nitro- .....   | 121-87-9                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2-chloro-5-nitro- .....   | 6283-25-6                                 | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 4-chloro-2-nitro- .....   | 89-63-4                                   | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 4-chloro-3-nitro- .....   | 635-22-3                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2,6-dibromo-4-nitro- .....  | 827-94-1                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2,3-dichloro- .....   | 608-27-5                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2,4-dichloro- .....   | 554-00-7                                  | .....                   | 10/04/82          | 10/04/92    |
| Benzenamine, 2,5-dichloro- .....   | 95-82-9                                   | .....                   | 10/04/82          | 10/04/92    |

| Category  | CAS No. (examples for category) | Special exemptions | Effective date | Sunset date |
|---|---------------------------------|--------------------|----------------|-------------|
| Benzenamine, 3,4-dichloro- .....  | 95-76-1 .....                   | .....              | 10/04/82       | 10/04/92    |
| Benzenamine, 3,5-dichloro- .....  | 626-43-7 .....                  | .....              | 10/04/82       | 10/04/92    |
| Benzenamine, 2,6-dichloro-4-nitro- .....  | 99-30-9 .....                   | .....              | 10/04/82       | 10/04/92    |
| Benzenamine, 2,4-dinitro- .....   | 97-02-9 .....                   | .....              | 10/04/82       | 10/04/92    |
| Benzenamine, 2-nitro- .....   | 88-74-4 .....                   | .....              | 10/04/82       | 10/04/92    |
| Benzenamine, 3-nitro- .....   | 99-09-2 .....                   | .....              | 10/04/82       | 10/04/92    |
| Benzenamine, 4-nitro- .....   | 100-01-6 .....                  | .....              | 10/04/82       | 10/04/92    |
| Benzenamine, 2,4,6-tribromo- .....  | 147-82-0 .....                  | .....              | 10/04/82       | 10/04/92    |
| Benzenamine, 2,4,6-trichloro- .....   | 634-93-5 .....                  | .....              | 10/04/82       | 10/04/92    |
| Aryl phosphates—phosphate esters of phenol or of alkyl-substituted phenols. Triaryl and mixed alkyl and aryl esters are included but trialkyl esters are excluded ..... | .....                           | .....              | 10/04/82       | 10/04/92    |



| Category   | CAS No. (examples for category) | Special exemptions | Effective date | Sunset date |
|--|---------------------------------|--------------------|----------------|-------------|
| $R_1$ =phenyl, either unsubstituted or substituted with one or more alkyl or aralkyl groups $R_2=R_3$ alkyl; or phenyl, either unsubstituted or substituted with one or more alkyl or aralkyl groups |                                 |                    |                |             |
| Phenol, dimethyl-, phosphate (3:1) .....   | 25155-23-1 .....                | .....              | 10/04/82       | 10/04/92    |
| Phenol, 4-(1,1-dimethylethyl)-, phosphate (3:1) .....  | 78-33-1 .....                   | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, dibutyl phenyl ester .....  | 2528-36-1 .....                 | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, diisodecyl phenyl ester .....   | 51363-64-5 .....                | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, (1,1-dimethylethyl) phenyl diphenyl ester .....   | 56803-37-3 .....                | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, 2-ethylhexyl diphenyl ester .....   | 1241-94-7 .....                 | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, isodecyl diphenyl ester .....   | 29761-21-5 .....                | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, (1-methylethyl)phenyl diphenyl ester .....  | 28108-99-8 .....                | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, methylphenyl diphenyl ester .....   | 25444-49-5 .....                | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, (1-methyl-1-phenylethyl)phenyl diphenyl ester .....   | 34364-42-6 .....                | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, triphenyl ester .....   | 115-86-6 .....                  | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, tris(methylphenyl) ester .....  | 1330-78-5 .....                 | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, tris(2-methylphenyl) ester .....  | 78-30-8 .....                   | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, tris(3-methylphenyl) ester .....  | 563-04-2 .....                  | .....              | 10/04/82       | 10/04/92    |
| Phosphoric acid, tris(4-methylphenyl) ester .....  | 78-32-0 .....                   | .....              | 10/04/82       | 10/04/92    |
| Asbestos—asbestiform varieties of chrysolite (serpentine); crocidolite (riebeckite); amosite (cummingtonite—grunerite); anthophyllite; tremolite; and actinolite. ....                               | .....                           | .....              | 10/04/82       | 10/04/92    |
| Asbestos .....   | 1332-21-4 .....                 | .....              | 10/04/82       | 10/04/92    |
| Asbestiform minerals .....   | 12001-29-5 .....                | .....              | 10/04/82       | 10/04/92    |
| Asbestiform minerals .....   | 17068-78-9 .....                | .....              | 10/04/82       | 10/04/92    |
| Asbestiform minerals .....   | 12172-73-5 .....                | .....              | 10/04/82       | 10/04/92    |
| Bisazobiphenyl dyes derived from benzidine and its congeners, <i>ortho</i> -toluidine (dimethylbenzidine) and dianisidine (dimethoxybenzidine) .....   | .....                           | .....              | 10/04/82       | 10/04/92    |
| Benzoic acid, 2-[[2-amino-6-[[4'-(-carboxy-4-hydroxyphenyl)azo]-3,3'-dimethoxy[1,1'-biphenyl]-4-yl]azo]-5-hydroxy-7-sulfo-1-naphthalenylazo]-5-nitro-, trisodium salt .....                          | 6739-62-4 .....                 | .....              | 10/04/82       | 10/04/92    |


Environmental Protection Agency

§ 716.120

| Category   | CAS No. (ex-<br>amples for cat-<br>egory) | Special ex-<br>emptions | Effective<br>date | Sunset date |
|--|---|-------------------------|-------------------|-------------|
| Benzoic acid, 5-[[4'-(2-amino-8-hydroxy-6-sulfo-1-naphthalenyl) azo] [1,1'-biphenyl]-4-yl]-azo]-2-hydroxy-, disodium salt  | 2429-84-7                                 |                         | 10/04/82          | 10/04/92    |
| Benzoic acid, 5-[[4'-(7-amino-1-hydroxy-3-sulfo-2-naphthalenyl)azo] [1,1'-biphenyl]-4-yl]-azo]-2-hydroxy-, disodium salt   | 2429-82-5                                 |                         | 10/04/82          | 10/04/92    |
| Benzoic acid, 5-[[4'-(1-amino-4-sulfo-2-naphthalenyl)azo] [1,1'-biphenyl]-4-yl]-azo]-2-hydroxy-, disodium salt   | 2429-79-0                                 |                         | 10/04/82          | 10/04/92    |
| Benzoic acid, 5-[[4'-[[2,6-diamino-3-[[8-hydroxy-3,6-disulfo-7-[[4-sulfo-1-naphthalenyl)azo]-2-naphthalenyl]azo]-5-methylphenyl]azo] [1,1'-biphenyl]-4-yl]-azo]-2-hydroxy-, tetrasodium salt | 2429-81-4                                 |                         | 10/04/82          | 10/04/92    |
| Benzoic acid, 5-[[4'-[[2,6-diamino-3-methyl-5-sulfo-phenyl]azo]-3,3'-dimethyl[1,1'-biphenyl]-4-yl]-azo]-2-hydroxy-, disodium salt  | 6637-88-3                                 |                         | 10/04/82          | 10/04/92    |
| Benzoic acid, 5-[[4'-[[2,6-diamino-3-methyl-5-[[4-sulfo-phenyl]azo]phenyl]azo][1,1'-biphenyl]-4-yl]-azo]-2-hydroxy-, disodium salt   | 2586-58-5                                 |                         | 10/04/82          | 10/04/92    |
| Benzoic acid, 5-[[4'-[[2,6-diamino-3-methyl-5-[[4-sulfo-phenyl]azo]phenyl]azo][1,1'-biphenyl]-4-yl]-azo]-2-hydroxy-3-methyl-, disodium salt  | 6360-54-9                                 |                         | 10/04/82          | 10/04/92    |
| Benzoic acid, 5-[[4'-[[2,4-dihydroxy-3-[[4-sulfo-phenyl]azo]phenyl]azo] [1,1'-biphenyl]-4-yl]-azo]-2-hydroxy-, disodium salt   | 2893-80-3                                 |                         | 10/04/82          | 10/04/92    |
| Benzoic acid, 3,3'-[[3,7-disulfo-1,5-naphthalenediyl]bis[azo(6-hydroxy-3,1-phenylene)azo(6(or 7)-sulfo-4,1-naphthalenediyl)azo][1,1'-biphenyl]-4,4'-diyl]azo]bis[6-hydroxy-, hexasodium salt | 8014-91-3                                 |                         | 10/04/82          | 10/04/92    |
| [1,1'-Biphenyl]-4,1'-bis diazonium), 3,3'-dimethoxy-   | 20282-70-6                                |                         | 10/04/82          | 10/04/92    |
| Butanamide, <i>N,N'</i> -(3,3'-dimethyl [1,1'-biphenyl]-4,4'-diyl)bis[3-oxo-   | 91-96-3                                   |                         | 10/04/82          | 10/04/92    |
| C.I. Direct Blue 218   | 10401-50-0                                |                         | 10/04/82          | 10/04/92    |
| Cuprate(2-), [5-[[4'-[[2,6-dihydroxy-3-[[2-hydroxy-5-sulfo-phenyl]azo]phenyl]azo][1,1'-biphenyl]-4-yl]-azo]-2-hydroxybenzoato(4-)]-, disodium  | 16071-86-6                                |                         | 10/04/82          | 10/04/92    |
| Cuprate(3-), [μ-[7-[[3,3'-dihydroxy-4'-[[1-hydroxy-6-(phenylamino)-3-sulfo-2-naphthalenyl]azo] [1,1'-biphenyl]-4-yl]-azo]-8-hydroxy-1,6-naphthalenedisulfonato(7-))]di-, trisodium           | 6656-03-7                                 |                         | 10/04/82          | 10/04/92    |
| Cuprate(4-), [μ-[[6,6'-[[3,3'-dihydroxy[1,1'-biphenyl]-4,4'-diyl]bis(azo)]bis[4-amino-5-hydroxy-1,3-naphthalenedisulfonato(8-))]di-, tetrasodium   | 16143-79-6                                |                         | 10/04/82          | 10/04/92    |
| 2-Naphthalenecarboxamide, <i>N,N'</i> -(3,3'-dimethoxy[1,1'-biphenyl]-4,4'-diyl)bis[3-hydroxy-   | 91-92-9                                   |                         | 10/04/82          | 10/04/92    |
| 1,3-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-6-[[4'-[[2-hydroxy-1-naphthalenyl)azo]-3,3'-dimethoxy[1,1'-biphenyl]-4-yl]-azo]-, disodium salt  | 2586-57-4                                 |                         | 10/04/82          | 10/04/92    |
| 1,3-Naphthalenedisulfonic acid, 6,6'-[[3,3'-dimethoxy[1,1'-biphenyl]-4,4'-diyl]bis(azo)]bis[4-amino-5-hydroxy-, tetrasodium salt   | 2610-05-1                                 |                         | 10/04/82          | 10/04/92    |
| 1,3-Naphthalenedisulfonic acid, 8-[[4'-[[4-ethoxyphenyl)azo] [1,1'-biphenyl]-4-yl]-azo]-7-hydroxy-, disodium salt  | 3530-19-6                                 |                         | 10/04/82          | 10/04/92    |
| 1,3-Naphthalenedisulfonic acid, 8-[[4'-[[4-ethoxyphenyl)azo]-3,3'-dimethyl [1,1'-biphenyl]-4-yl]-azo]-7-hydroxy-, disodium salt  | 6358-29-8                                 |                         | 10/04/82          | 10/04/92    |
| 1,3-Naphthalenedisulfonic acid, 7-hydroxy-8-[[4'-[[4-(4-methylphenyl) sulfonyloxy]phenyl]-azo] [1,1'-biphenyl]-4-yl]-azo]-, disodium salt  | 3567-65-5                                 |                         | 10/04/82          | 10/04/92    |
| 2,7-Naphthalenedisulfonic acid, 5-amino-3-[[4'-((7-amino-1-hydroxy-3-sulfo-2-naphthalenyl)-azo) [1,1'-biphenyl]-4-yl]-azo]-4-hydroxy-, trisodium salt  | 2429-73-4                                 |                         | 10/04/82          | 10/04/92    |
| 2,7-Naphthalenedisulfonic acid, 4-amino-3-[[4'-[[2,4-diamino-5-methylphenyl)azo] [1,1'-biphenyl]-4-yl]-azo]-5-hydroxy-6-phenylazo)-, disodium salt   | 2429-83-6                                 |                         | 10/04/82          | 10/04/92    |
| 2,7-Naphthalenedisulfonic acid, 4-amino-3-[[4'-[[2,4-diaminophenyl)azo] [1,1'-biphenyl]-4-yl]-azo] 5-hydroxy-6-phenylazo)-, disodium salt  | 1937-37-7                                 |                         | 10/04/82          | 10/04/92    |
| 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-6[[4'-[[4-hydroxyphenyl)azo] [1,1'-biphenyl]-4-yl]-azo]-3-[[4-nitrophenyl)azo]-, disodium salt   | 4335-09-5                                 |                         | 10/04/82          | 10/04/92    |




| Category  | CAS No. (examples for category) | Special exemptions | Effective date | Sunset date |
|---|---------------------------------|--------------------|----------------|-------------|
| 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-3-[[4'-(4-hydroxyphenyl)azo][1,1'-biphenyl]-4-yl]azo)-(phenylazo)-, disodium salt .....                                       | 3626–28–6                       | .....              | 10/04/82       | 10/04/92    |
| 2,7-Naphthalenedisulfonic acid, 3,3'-[[1,1'-biphenyl]-4,4'-diylbis(azo)]bis[5-amino-4-hydroxy-, tetrasodium salt .....  | 2602–46–2                       | .....              | 10/04/82       | 10/04/92    |
| 2,7-Naphthalenedisulfonic acid, 3,3'-[[3,3'-dimethoxy[1,1'-biphenyl]-4,4'-diyl]bis(azo)]bis[5-amino-4-hydroxy-, tetrasodium salt .....  | 2429–74–5                       | .....              | 10/04/82       | 10/04/92    |
| 2,7-Naphthalenedisulfonic acid, 3,3'-[[3,3'-dimethyl-[1,1'-biphenyl]-4,4'-diyl]bis(azo)]bis[5-amino-4-hydroxy-, tetrasodium salt .....  | 72–57–1                         | .....              | 10/04/82       | 10/04/92    |
| 2,7-Naphthalenedisulfonic acid, 3,3'-[[3,3'-dimethyl-[1,1'-biphenyl]-4,4'-diyl]bis(azo)]bis[4,5-dihydroxy-, tetrasodium salt .....  | 2150–54–1                       | .....              | 10/04/82       | 10/04/92    |
| 1-Naphthalenesulfonic acid, 3-[[4'[(6-amino-1-hydroxy-3-sulfo-2-naphthalenyl)azo]-3,3'-dimethoxy[1,1'-biphenyl]-4-yl]azo]-4-hydroxy-, disodium salt .....                       | 6449–35–0                       | .....              | 10/04/82       | 10/04/92    |
| 1-Naphthalenesulfonic acid, 3,3'-[[1,1'-biphenyl]-4,4'-diyl-4,4'-diyl]bis(azo)]bis[4-amino-, disodium salt .....  | 573–58–0                        | .....              | 10/04/82       | 10/04/92    |
| 1-Naphthalenesulfonic acid, 3,3'-[[3,3'-dimethoxy-[1,1'-biphenyl]-4,4'-diyl]bis(azo)]bis[4-hydroxy-, disodium salt .....  | 2429–71–2                       | .....              | 10/04/82       | 10/04/92    |
| 1-Naphthalenesulfonic acid, 3,3'-[[3,3'-dimethyl[1,1'-biphenyl]-4,4'-diyl]bis(azo)]bis[4-amino-, disodium salt .....  | 992–59–6                        | .....              | 10/04/82       | 10/04/92    |
| Chlorinated benzenes, mono-, di-, tri-, tetra-, and penta- .....  | .....                           | .....              | 10/04/82       | 10/04/92    |
| Benzene, chloro- .....  | 108–90–7                        | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,2-dichloro- .....  | 95–50–1                         | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,3-dichloro- .....  | 541–73–1                        | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,4-dichloro- .....  | 106–46–7                        | .....              | 10/04/82       | 10/04/92    |
| Benzene, pentachloro- .....   | 608–93–5                        | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,2,3,4-tetrachloro- .....   | 634–66–2                        | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,2,3,5-tetrachloro- .....   | 634–90–2                        | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,2,4,5-tetrachloro- .....   | 95–94–3                         | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,2,3-trichloro- .....   | 87–61–6                         | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,2,4-trichloro- .....   | 120–82–1                        | .....              | 10/04/82       | 10/04/92    |
| Benzene, 1,3,5-trichloro- .....   | 108–70–3                        | .....              | 10/04/82       | 10/04/92    |
| Chlorinated naphthalenes—chlorinated derivatives of naphthalene (empirical formula) C <sub>10</sub> H <sub>x</sub> Cl <sub>y</sub> where x=y=8. ....                            | .....                           | .....              | 10/04/82       | 12/29/88    |
| Naphthalene, chloro- .....  | 25586–43–0                      | .....              | 10/04/82       | 12/29/88    |
| Naphthalene, chloro derivatives .....   | 70776–03–3                      | .....              | 10/04/82       | 12/29/88    |
| Naphthalene, 1-chloro- .....  | 90–13–1                         | .....              | 10/04/82       | 12/29/88    |
| Naphthalene, heptachloro- .....   | 32241–08–0                      | .....              | 10/04/82       | 12/29/88    |
| Chlorinated paraffins—chlorinated paraffin oils and chlorinated paraffin waxes, with chlorine content of 35 percent through 70 percent by weight. ....                          | .....                           | .....              | 10/04/82       | 10/04/92    |
| Alkanes, chloro- .....  | 61788–76–9                      | .....              | 10/04/82       | 10/04/92    |
| Alkanes, C <sub>6–18</sub> , chloro- .....  | 68920–70–7                      | .....              | 10/04/82       | 10/04/92    |
| Paraffin waxes and hydrocarbon waxes, chlorinated .....   | 63449–39–8                      | .....              | 10/04/82       | 10/04/92    |
| Ethyltoluenes—This category consists of ethyltoluene (mixed isomers) and the ortho (1,2-), meta (1,3-) and para (1,4-) isomers .....  | .....                           | .....              | 04/29/83       | 12/29/88    |
| Benzene, 1-ethyl-2-methyl- .....  | 611–14–3                        | .....              | 04/29/83       | 12/29/88    |
| Fluoroalkenes—This category is defined as fluoroalkenes of the general formula: C <sub>n</sub> H <sub>2n-x</sub> F <sub>x</sub> where n equals 2 to 3 and X equals 1 to 6. .... | .....                           | .....              | 04/29/83       | 04/29/93    |
| Ethene, tetrafluoro- .....  | 116–14–3                        | .....              | 04/29/83       | 04/29/93    |
| Ethene, trifluoro- .....  | 359–11–5                        | .....              | 04/29/83       | 01/13/86    |
| 1-Propene, 1,1,2,3,3,3-hexafluoro- .....  | 116–15–4                        | .....              | 04/29/83       | 04/29/93    |
| Glycidol (oxiranemethanol) and its derivatives .....  | .....                           | .....              | 10/04/82       | 10/04/92    |



| Category  | CAS No. (examples for category) | Special exemptions | Effective date | Sunset date |
|---|---------------------------------|--------------------|----------------|-------------|
| R=H; alkyl, alkenyl or alkynyl; aryl; acyl. where R=alkyl, alkenyl, alkynyl, aryl, or acyl; any substituents or functional groups may be present with the alkyl, etc., groups |                                 |                    |                |             |
| 1,2-Cyclohexanedicarboxylic acid, bis(oxiranylmethyl) ester ..  | 5493-45-8                       | .....              | 10/04/82       | 10/04/92    |
| Disiloxane, 1,1,3,3-tetramethyl-1,3-bis[3-oxiranylmethoxy]propyl]- ..   | 126-80-7                        | .....              | 10/04/82       | 10/04/92    |
| 2,4-Imidazolidinedione, 5,5-dimethyl-3-[2-(oxiranylmethoxy)propyl]-1-(oxiranylmethyl)- ..   | 32568-89-1                      | .....              | 10/04/82       | 10/04/92    |
| 2,4-Imidazolidinedione, 3,3'-[2-(oxiranylmethoxy)-1,3-propanediyl]bis[5,5-dimethyl-1-(oxiranyl-methyl)- ..  | 38304-52-8                      | .....              | 10/04/82       | 10/04/92    |
| Neodecanoic acid, oxiranylmethyl ester ..   | 26761-45-5                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[1,4-butanediylbis(oxymethylene)]bis ..   | 2425-79-8                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, (butoxymethyl)- ..   | 2426-08-6                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[1,4-cyclohexanedilbis(methyleneoxymethylene)]bis- ..   | 14228-73-0                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(2,4-dibromophenoxy)methyl]- ..   | 20217-01-0                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(1,2-dibromopropoxy)methyl]- ..   | 35243-89-1                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(1,1-dimethylethoxy)methyl]- ..   | 7665-72-7                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [[4-(1,1-dimethylethyl)phenoxy]methyl]- ..   | 3101-60-8                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[(2,2-dimethyl-1,3-propanediyl)bis(oxymethylene)]bis- ..  | 17557-23-2                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(dodecyloxy)methyl]- ..   | 2461-18-9                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[1,2-ethanediylbis(oxymethylene)]bis- ..  | 2224-15-9                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2',2'',2'''-[1,2-ethanediylidenetetrakis-(4,1-phenyleneoxymethylene)]tetrakis- ..  | 7328-97-4                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, (ethoxymethyl)- ..   | 4016-11-9                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(2-ethylhexyl)oxy]methyl]- ..   | 2461-15-6                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(hexadecyloxy)methyl]- ..   | 15965-99-8                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2',2''-[1,2,6-hexanetriyltris-(oxymethylene)]tris- ..  | 68959-23-9                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, (methoxymethyl)- ..  | 930-37-0                        | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[methylenebis(phenyleneoxymethylene)]bis- ..  | 39817-09-9                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[methylenebis(2,1-phenyleneoxymethylene)]bis- ..  | 54208-63-8                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(1-methylethoxy)methyl]- ..   | 4016-14-2                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[(1-methylethylidene)bis[4,1-phenyl-eneoxy[1-(butoxymethyl)-2,1-ethanediyl]oxymethylene]]bis- ..  | 71033-08-4                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[1-methylethylidene) bis(4,1-phenyl-eneoxymethylene)]bis- ..  | 1675-54-3                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[(1-methylethylidene)bis(4,1-phenyl-eneoxymethylene)]bis-, homopolymer ..   | 25085-99-8                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[(1-methylethylidene)bis[4,1-phenyleneoxy-3,1-propanediyl-4,1-phenylene(1-methylethylidene)-4,1-phenyleneoxymethylene]]bis- ..                                  | 72319-24-5                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(methylphenoxy)methyl]- ..  | 26447-14-3                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(2-methylphenoxy)methyl]- ..  | 2210-79-9                       | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [[4-(1-methyl-1-phenylethyl)phenoxy]-methyl]- ..   | 61578-04-9                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, mono[C <sub>6</sub> -C <sub>12</sub> -alkyloxy]methyl]derivatives ..   | 68987-80-4                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, mono[C <sub>8</sub> -C <sub>12</sub> -alkyloxy]methyl]derivatives ..   | 68609-96-1                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, mono[C <sub>10</sub> -C <sub>16</sub> -alkyloxy]methyl]derivatives ..  | 68081-84-5                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, mono[(C <sub>10</sub> -C <sub>14</sub> -alkyloxy)methyl]derivatives ..   | 68609-97-2                      | .....              | 10/04/82       | 10/04/92    |
| Oxirane, [(4-nitrophenoxy)methyl]- ..   | 5255-75-4                       | .....              | 10/04/82       | 10/04/92    |

| Category  | CAS No. (examples for category) | Special exemptions | Effective date | Sunset date |
|---|---------------------------------|--------------------|----------------|-------------|
| Oxirane, [(4-nonylphenoxy)methyl]-  | 6178–32–1                       |                    | 10/04/82       | 10/04/92    |
| Oxirane, [(9-octadecyloxy)methyl]-, (Z)-  | 60501–41–9                      |                    | 10/04/82       | 10/04/92    |
| Oxirane, [(octadecyloxy)methyl]-  | 16245–97–9                      |                    | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-(oxiranylmethoxy)-1,3-phenylene]bis(methylene)]bis-   | 13561–08–5                      |                    | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[[[2-oxiranylmethoxy)phenyl]methylene]bis(4,1-phenyleneoxy)methylene]]bis-                          | 67786–03–2                      |                    | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[oxybis(methylene)]bis-   | 2238–07–5                       |                    | 10/04/82       | 10/04/92    |
| Oxirane, (phenoxy)methyl-   | 122–60–1                        |                    | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[1,3-phenylenebis (oxymethylene)]bis-   | 2425–01–6                       |                    | 10/04/82       | 10/04/92    |
| Oxirane, 2,2'-[1,4-phenylenebis (oxymethylene)]bis-   | 101–90–6                        |                    | 10/04/82       | 10/04/92    |
| Oxirane, 2,2',2'1/4-[1,2,3-propanetriyl tris(oxymethylene)]tris-  | 13236–02–7                      |                    | 10/04/82       | 10/04/92    |
| Oxirane, [(2-propenyloxy)methyl]-   | 106–92–3                        |                    | 10/04/82       | 10/04/92    |
| Oxirane, 2,2',2'1/4-[propylidynetris (4,1-phenyleneoxy)methylene]]tris-   | 68517–02–2                      |                    | 10/04/82       | 10/04/92    |
| Oxirane, [(tetradecyloxy)methyl]-   | 38954–75–5                      |                    | 10/04/82       | 10/04/92    |
| Oxiranecarboxylic acid, 3-methyl-3-phenyl-, ethyl ester   | 77–83–8                         |                    | 10/04/82       | 10/04/92    |
| Poly(oxy-1,2-ethanediyl)-, α-[4-oxiranylmethoxy]benzoyl]-, ω-[[4-oxiranylmethoxy]benzoyl]oxy]-                    | 69943–75–5                      |                    | 10/04/82       | 10/04/92    |
| 2-Propenoic acid, 2-methyl-, oxiranylmethyl ester   | 106–91–2                        |                    | 10/04/82       | 10/04/92    |
| 2-Propenoic acid, oxiranylmethyl ester  | 106–90–1                        |                    | 10/04/82       | 10/04/92    |
| Silane, [(3-chloropropyl)(dimethoxy)]3-(oxiranylmethoxy)propyl]-  | 71808–64–5                      |                    | 10/04/82       | 10/04/92    |
| Silane, diethoxymethyl[3-(oxiranyl-methoxy)propyl]-   | 2897–60–1                       |                    | 10/04/82       | 10/04/92    |
| Silane, ethoxydimethyl[3-(oxiranyl-methoxy)propyl]-   | 17963–04–1                      |                    | 10/04/82       | 10/04/92    |
| Silane, trimethoxy[3-(oxiranyl-methoxy)propyl]-   | 2530–83–8                       |                    | 10/04/82       | 10/04/92    |
| Tetrasiloxane, 1,1,1,3,5,7,7-octamethyl-3,5-bis[3-(oxiranylmethoxy)propyl]-                                       | 69155–42–6                      |                    | 10/04/82       | 10/04/92    |
| Trisiloxane, 1,1,1,3,5,5,5-heptamethyl-3-[3-(oxiranylmethoxy)propyl]-   | 7422–52–8                       |                    | 10/04/82       | 10/04/92    |
| Halogenated alkyl epoxides—halogenated noncyclic aliphatic hydrocarbons with one or more epoxy functional groups. |                                 |                    | 10/04/82       | 12/29/88    |



| Category  | CAS No. (examples for category) | Special exemptions | Effective date    | Sunset date    |
|---|---------------------------------|--------------------|-------------------|----------------|
| R <sub>1</sub> =X or C <sub>n</sub> H <sub>2n-1</sub> -X <sub>y</sub> (y=1 to 1n=1)         |                                 |                    |                   |                |
| R <sub>2</sub> =H or X or C <sub>n</sub> H <sub>2n-1</sub> -X <sub>y</sub> (y=0 to 2n=1)    |                                 |                    |                   |                |
| R <sub>3</sub> =H or X or C <sub>n</sub> H <sub>2n-1</sub> -X <sub>y</sub> (y=0 to 2n=1)    |                                 |                    |                   |                |
| R <sub>4</sub> =H or X or C <sub>n</sub> H <sub>2n-1</sub> -X <sub>y</sub> (y=0 to 2n=1)    |                                 |                    |                   |                |
| X=halogen. Groups R <sub>1</sub> –R <sub>4</sub> may contain one or more epoxide functions. |                                 |                    |                   |                |
| Lead and lead compounds   |                                 | § 716.21 (a)(8)    | February 28, 2008 | April 28, 2008 |
| Lead  | 7439– 92 – 1                    | § 716.21 (a)(8)    | February 28, 2008 | April 28, 2008 |
| Acetic acid, lead (2+) salt   | 301 – 04 – 2                    | § 716.21 (a)(8)    | February 28, 2008 | April 28, 2008 |

Environmental Protection Agency

§ 716.120

| Category  | CAS No. (ex-<br>amples for cat-<br>egory) | Special ex-<br>emptions | Effective<br>date    | Sunset date       |
|---|---|-------------------------|----------------------|-------------------|
| Carbonic acid, lead (2+) salt (1:1) .....   | 598 – 63 – 0                              | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Lead chloride (PbCl <sub>2</sub> ) .....  | 7758 – 95 – 4                             | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Chromic acid (H <sub>2</sub> CrO <sub>4</sub> ), lead (2+) salt (1:1) .....   | 7758 – 97 – 6                             | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Lead oxide (PbO <sub>2</sub> ) .....  | 1309 – 60 – 0                             | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Borate (1-), tetrafluoro-, lead (2+) (2:1) .....  | 13814 – 96 –<br>5                         | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Phosphoric acid, lead (2+) salt (2:3) .....   | 7446 – 27 – 7                             | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Silicic acid, lead salt, basic .....  | 53466 – 66 –<br>3                         | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Octadecanoic acid, lead salt (1:?) .....  | 7428 – 48 – 0                             | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Sulfuric acid, lead salt (1:?), basic .....   | 63653 – 42 –<br>9                         | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Lead sulfide (PbS) .....  | 1314 – 8 7 – 0                            | § 716.21<br>(a)(8)      | February<br>28, 2008 | April 28,<br>2008 |
| Oxirane, (bromomethyl)- .....   | 3132-463-7                                | .....                   | 10/04/82             | 12/29/88          |
| Oxirane, (2,2,3,3,4,4,5,5,6,6,7,7,7-tridecafluoroheptyl)- .....   | 38565-52-5                                | .....                   | 10/04/82             | 12/29/88          |
| Phenylenediamines (Benzenediamines). This category is defined<br>as all nitrogen unsubstituted phenylenediamines and their salts<br>with zero to two substituents on the ring selected from the<br>same of different members of the group of halo, nitro, hydroxy,<br>hydroxy-lower alkoxy, lower-alkyl, and lower alkoxy. For this<br>purpose, the term "lower" is defined as a group containing be-<br>tween one and four carbons. .... | .....                                     | .....                   | 04/29/83             | 04/29/93          |
| 1,2-Benzenediamine .....  | 95 – 54 – 5                               | .....                   | 4/29/83              | 4/29/93           |
| 1,3-Benzenediamine .....  | 108 – 45 – 2                              | .....                   | 4/29/83              | 4/29/93           |
| 1,2 - Benzenediamine, 4-butyl- .....  | 3663 – 23 – 8                             | .....                   | 4/29/83              | 12/29/88          |
| 1,2 - Benzenediamine, 4-butyl- .....  | 95 – 83 – 0                               | .....                   | 4/29/83              | 4/29/83           |
| 1,3-Benzenediamine, 4-chloro- .....   | 5131-60-2                                 | .....                   | 04/29/83             | 04/29/93          |
| 1,4-Benzenediamine, 2-chloro-, dihydrochloride .....  | 615-46-3                                  | .....                   | 04/29/83             | 12/29/88          |
| 1,2-Benzenediamine, 5-chloro-3-nitro- .....   | 42389-30-0                                | .....                   | 04/29/83             | 12/29/88          |
| 1,2-Benzenediamine, 4-chloro-, sulfate (1:1) .....  | 68459-98-3                                | .....                   | 04/29/83             | 12/29/88          |
| 1,3-Benzenediamine, 4-chloro-, sulfate (1:1) .....  | 68239-80-5                                | .....                   | 04/29/83             | 12/29/88          |
| 1,4-Benzenediamine, 2-chloro-, sulfate .....  | 6219-71-2                                 | .....                   | 04/29/83             | 12/29/88          |
| 1,4-Benzenediamine, 2,5-dichloro- .....   | 20103-09-7                                | .....                   | 04/29/83             | 12/29/88          |
| 1,2-Benzenediamine, dihydrochloride .....   | 615-28-1                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,3-Benzenediamine, dihydrochloride .....   | 541-69-5                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,4-Benzenediamine, dihydrochloride .....   | 624-18-0                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,4-Benzenediamine, ethanedioate (1:1) .....  | 62654-17-5                                | .....                   | 04/29/83             | 04/29/93          |
| 1,2-Benzenediamine, 4-ethoxy- .....   | 1197-37-1                                 | .....                   | 04/29/83             | 12/29/88          |
| 1,3-Benzenediamine, 4-ethoxy-dihydrochloride .....  | 67801-06-3                                | .....                   | 04/29/83             | 12/29/88          |
| 1,3-Benzenediamine, 4-ethoxy-, sulfate (1:1) .....  | 68015-98-5                                | .....                   | 04/29/83             | 12/29/88          |
| 1,3-Benzenediamine, ar-ethyl-ar-methyl- .....   | 68966-84-7                                | .....                   | 04/29/83             | 12/29/88          |
| 1,4-Benzenediamine, 2-methoxy .....   | 5307-02-8                                 | .....                   | 04/29/83             | 04/29/93          |
| 1,2-Benzenediamine, 4-methoxy-, dihydrochloride .....   | 614-94-8                                  | .....                   | 04/29/83             | 12/29/88          |
| 1,3-Benzenediamine, 4-methoxy-, sulfate .....   | 6219-67-6                                 | .....                   | 04/29/83             | 12/29/88          |
| 1,3-Benzenediamine, 4-methoxy-, sulfate (1:1) .....   | 39156-41-7                                | .....                   | 04/29/83             | 04/29/93          |
| Benzenediamine, ar-methyl- .....  | 25376-45-8                                | .....                   | 04/29/83             | 04/29/93          |
| 1,2-Benzenediamine, 3-methyl- .....   | 2687-25-4                                 | .....                   | 04/29/83             | 04/29/93          |
| 1,2-Benzenediamine, 4-methyl- .....   | 496-72-0                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,3-Benzenediamine, 2-methyl- .....   | 823-40-5                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,3-Benzenediamine, 4-methyl- .....   | 95-80-7                                   | .....                   | 04/29/83             | 04/29/93          |
| 1,3-Benzenediamine, 5-methyl- .....   | 108-71-4                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,4-Benzenediamine, 2-methyl- .....   | 95-70-5                                   | .....                   | 04/29/83             | 04/29/93          |
| 1,4-Benzenediamine, 2-methyl-, dihydrochloride- .....   | 615-45-2                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,4-Benzenediamine, 2-methyl-, sulfate .....  | 6369-59-1                                 | .....                   | 04/29/83             | 04/29/93          |
| 1,4-Benzenediamine, 2-methyl-, sulfate (1:1) .....  | 615-50-9                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,2-Benzenediamine, 4-nitro- .....  | 99-56-9                                   | .....                   | 04/29/83             | 04/29/93          |
| 1,3-Benzenediamine, 4-nitro-, .....   | 5131-58-8                                 | .....                   | 04/29/83             | 12/29/88          |
| 1,3-Benzenediamine, 5-nitro-, .....   | 5042-55-7                                 | .....                   | 04/29/83             | 12/29/88          |
| 1,4-Benzenediamine, 2-nitro-, .....   | 5307-14-2                                 | .....                   | 04/29/83             | 04/29/93          |
| 1,2-Benzenediamine, 4-nitro-, dihydrochloride .....   | 6219-77-8                                 | .....                   | 04/29/83             | 12/29/88          |
| 1,4-Benzenediamine, 2-nitro-, dihydrochloride .....   | 18266-52-9                                | .....                   | 04/29/83             | 12/29/88          |
| 1,2-Benzenediamine, 4-nitro-, sulfate (1:1) .....   | 68239-82-7                                | .....                   | 04/29/83             | 12/29/88          |
| 1,4-Benzenediamine, 2-nitro-, sulfate (1:1) .....   | 68239-83-8                                | .....                   | 04/29/83             | 12/29/88          |
| 1,3-Benzenediamine, sulfate (1:1) .....   | 541-70-8                                  | .....                   | 04/29/83             | 04/29/93          |
| 1,4-Benzenediamine, sulfate (1:1) .....   | 16245-77-5                                | .....                   | 04/29/83             | 04/29/93          |

| Category  | CAS No. (ex-amples for cat-egory) | Special ex-emption | Effective date | Sunset date |
|---|-----------------------------------|--------------------|----------------|-------------|
| Ethanol, 2-(2,4-diaminophenoxy)-, dihydrochloride ..... | 66422-95-5                        | .....              | 04/29/83       | 12/29/88    |
| Phenol, 2,4-diamino-, dihydrochloride .....             | 137-09-7                          | .....              | 04/29/83       | 04/29/93    |
| Phenol, 2,4-diamino-6-methyl- .....                     | 15872-73-8                        | .....              | 04/29/83       | 12/29/88    |
| Phenol, 2,4-diamino-6-methyl-, hydrochloride .....      | 65879-44-9                        | .....              | 04/29/83       | 12/29/88    |

(d) *Listed members of categories.* The following categories are listed in alphabetical order with the chemical substances identified in each category also listed alphabetically. Only those

chemical substances specifically listed within a category are subject to all provisions of part 716 for the time period from the effective date of the rule until the sunset date.

| Category  | CAS No.          | Special Exemptions | Effective Date | Sunset Date |
|---|------------------|--------------------|----------------|-------------|
| <b>Aldehydes:</b>   |                  |                    |                |             |
| Acetaldehyde .....  | 75-07-0 .....    | .....              | 9/30/91        | 6/30/98     |
| Acetaldehyde, chloro- .....   | 107-20-0 .....   | .....              | 9/30/91        | 6/30/98     |
| Acetaldehyde, (1,3-dihydro-1,3,3-trimethyl-2H-indol-2-ylidene) .....    | 84-83-3 .....    | .....              | 9/30/91        | 6/30/98     |
| Acetaldehyde, trichloro- .....  | 75-87-6 .....    | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde .....  | 100-52-7 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 3-bromo- .....  | 3132-99-8 .....  | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 4-butyl- .....  | 1200-14-2 .....  | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 2-chloro- .....   | 89-98-5 .....    | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 4-chloro- .....   | 104-88-1 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 4-(diethylamino)- .....                                   | 120-21-8 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 4-(diethylamino)-2-hydroxy- .....                         | 17754-90-4 ..... | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 2,4-dihydroxy- .....                                      | 95-01-2 .....    | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 2,5-dimethoxy- .....                                      | 93-02-7 .....    | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 3,4-dimethoxy- .....                                      | 120-14-9 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, (dimethylamino)- .....                                    | 28602-27-9 ..... | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 4-(dimethylamino)- .....                                  | 100-10-7 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 4-ethoxy- .....   | 10031-82-0 ..... | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 3-ethoxy-4-hydroxy- .....                                 | 121-32-4 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 2-hydroxy- .....  | 90-02-8 .....    | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 4-hydroxy- .....  | 123-08-0 .....   | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 4-hydroxy-3-methoxy- .....                                | 121-33-5 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 2-hydroxy-5-nitro- .....                                  | 97-51-8 .....    | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 2-methoxy- .....  | 135-02-4 .....   | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 4-methoxy- .....  | 123-11-5 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, methyl- .....   | 1334-78-7 .....  | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 4-methyl- .....   | 104-87-0 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 2-nitro- .....  | 552-89-6 .....   | .....              | 9/30/91        | 12/19/95    |
| Benzaldehyde, 3-phenoxy- .....  | 39515-51-0 ..... | .....              | 9/30/91        | 6/30/98     |
| Benzaldehyde, 4-(trifluoromethyl)- .....                                | 455-19-6 .....   | .....              | 9/30/91        | 12/19/95    |
| Benzeneacetaldehyde .....   | 122-78-1 .....   | .....              | 9/30/91        | 6/30/98     |
| Benzeneacetaldehyde, alpha-methyl- .....                                | 93-53-8 .....    | .....              | 9/30/91        | 12/19/95    |
| Benzeneacetaldehyde, 4-methyl- .....                                    | 104-09-6 .....   | .....              | 9/30/91        | 12/19/95    |
| Benzenepropanal, 4-(1,1-dimethylethyl)- $\alpha$ -methyl- .....         | 80-54-6 .....    | .....              | 9/30/91        | 6/30/98     |
| Benzenepropanal, $\alpha$ -methyl-4-(1-methylethyl)- .....              | 103-95-7 .....   | .....              | 9/30/91        | 6/30/98     |
| 1,3-Benzodioxole-5-carboxaldehyde .....                                 | 120-57-0 .....   | .....              | 9/30/91        | 6/30/98     |
| 1,3-Benzodioxole-5-carboxaldehyde, 7-methoxy- .....                     | 5780-07-4 .....  | .....              | 9/30/91        | 12/19/95    |
| Butanal, 3-methyl- .....  | 590-86-3 .....   | .....              | 9/30/91        | 6/30/98     |
| 3-Cyclohexene-1-carboxaldehyde .....                                    | 100-50-5 .....   | .....              | 9/30/91        | 6/30/98     |
| 3-Cyclohexene-1-carboxaldehyde, dimethyl- .....                         | 27939-60-2 ..... | .....              | 9/30/91        | 6/30/98     |
| 3-Cyclohexene-1-carboxaldehyde, 4-(4-hydroxy-4-methylpentyl)- .....     | 31906-04-4 ..... | .....              | 9/30/91        | 6/30/98     |
| 3-Cyclohexene-1-carboxaldehyde, 1-methyl-4-(4-methyl-3-pentenyl)- ..... | 52475-86-2 ..... | .....              | 9/30/91        | 6/30/98     |
| 3-Cyclohexene-1-carboxaldehyde, 1-methyl-4-(4-methylpentyl)- .....      | 66327-54-6 ..... | .....              | 9/30/91        | 6/30/98     |
| 3-Cyclohexene-1-carboxaldehyde, 4-(4-methyl-3-pentenyl)- .....          | 37677-14-8 ..... | .....              | 9/30/91        | 12/19/95    |
| 3-Cyclohexene-1-carboxaldehyde, 2,4,6-trimethyl- .....                  | 1423-46-7 .....  | .....              | 9/30/91        | 12/19/95    |
| 3-Cyclopentene-1-acetaldehyde, 2,2,3-trimethyl- .....                   | 4501-58-0 .....  | .....              | 9/30/91        | 6/30/98     |
| Decanal .....   | 112-31-2 .....   | .....              | 9/30/91        | 6/30/98     |
| 4a(4H)-Dibenzofurancarboxaldehyde, 1,5a,6,9,9a,9b-hexahydro- .....      | 126-15-8 .....   | .....              | 9/30/91        | 6/30/98     |
| Dodecanal .....   | 112-54-9 .....   | .....              | 9/30/91        | 6/30/98     |

Environmental Protection Agency

§ 716.120

| Category   | CAS No.    | Special Exemptions | Effective Date | Sunset Date |
|--|------------|--------------------|----------------|-------------|
| Ethanedial   | 107-22-2   |                    | 9/30/91        | 6/30/98     |
| Heptanal   | 111-71-7   |                    | 9/30/91        | 6/30/98     |
| Heptanal, 2-(phenylmethylene)-   | 122-40-7   |                    | 9/30/91        | 6/30/98     |
| 5-Heptenal, 2,6-dimethyl-  | 106-72-9   |                    | 9/30/91        | 12/19/95    |
| Hexanal, 2-ethyl-  | 123-05-7   |                    | 9/30/91        | 6/30/98     |
| Hexanal, 3,5,5-trimethyl-  | 5435-64-3  |                    | 9/30/91        | 12/19/95    |
| 2-Hexenal  | 505-57-7   |                    | 9/30/91        | 12/19/95    |
| Hexenal, 2-ethyl-  | 26266-68-2 |                    | 9/30/91        | 6/30/98     |
| Indium Compounds:  |            |                    |                |             |
| Acetic acid, indium(3+) salt   | 25114-58-3 | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| Indium   | 7440-74-6  | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| Indium chloride (InCl3)  | 10025-82-8 | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| Indium hydroxide (In(OH)3)   | 20661-21-6 | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| Indium oxide (In2O3)   | 1312-43-2  | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| Indium phosphide (InP)   | 22398-80-7 | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| Indium tin oxide   | 50926-11-9 | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| Sulfamic acid, indium(3+) salt   | 66027-93-8 | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| Sulfuric acid, indium(3+) salt (3:2)                                   | 13464-82-9 | § 716.21(a)(6)     | 6/3/04         | 8/2/04      |
| 1-Naphthalene carboxaldehyde   | 66-77-3    |                    | 9/30/91        | 12/19/95    |
| Nonanal  | 124-19-6   |                    | 9/30/91        | 6/30/98     |
| 2,6-Octadienal, 3,7-dimethyl-, (E)                                     | 141-27-5   |                    | 9/30/91        | 12/19/95    |
| 2,6-Octadienal, 3,7-dimethyl-, (Z)                                     | 106-26-3   |                    | 9/30/91        | 12/19/95    |
| Octanal  | 124-13-0   |                    | 9/30/91        | 6/30/98     |
| Octanal, 3,7-dimethyl-   | 5988-91-0  |                    | 9/30/91        | 12/19/95    |
| Octanal, 7-hydroxy-3,7-dimethyl-                                       | 107-75-5   |                    | 9/30/91        | 6/30/98     |
| Octanal, 7-methoxy-3,7-dimethyl-                                       | 3613-30-7  |                    | 9/30/91        | 6/30/98     |
| Octanal, 2-(phenylmethylene)-  | 101-86-0   |                    | 9/30/91        | 6/30/98     |
| 6-Octenal, 3,7-dimethyl-   | 106-23-0   |                    | 9/30/91        | 6/30/98     |
| 6-Octenal, 3,7-dimethyl-, (S)-   | 5949-05-3  |                    | 9/30/91        | 12/19/95    |
| Pentanal   | 110-62-3   |                    | 9/30/91        | 6/30/98     |
| Pentanedial  | 111-30-8   |                    | 9/30/91        | 6/30/98     |
| 1-Piperidinecarboxaldehyde   | 2591-86-8  |                    | 9/30/91        | 6/30/98     |
| Propanal   | 123-38-6   |                    | 9/30/91        | 6/30/98     |
| Propanal, 3-hydroxy-2,2-dimethyl-                                      | 597-31-9   |                    | 9/30/91        | 6/30/98     |
| 2-Propenal, 2-methyl-  | 78-85-3    |                    | 9/30/91        | 12/19/95    |
| Propanal, 3-(methylthio)-  | 3268-49-3  |                    | 9/30/91        | 6/30/98     |
| 2-Propenal   | 107-02-8   |                    | 9/30/91        | 6/30/98     |
| 2-Propenal, 3- 4-(1,1-dimethylethyl)phenyl -2-methyl-                  | 13586-68-0 |                    | 9/30/91        | 6/30/98     |
| 2-Propenal, 3-(2-methoxyphenyl)-                                       | 1504-74-1  |                    | 9/30/91        | 6/30/98     |
| 2-Propenal, 2-methyl-  | 78-85-3    |                    | 9/30/91        | 6/30/98     |
| 2-Propenal, 2-methyl-3-phenyl-   | 101-39-3   |                    | 9/30/91        | 6/30/98     |
| 2-Propenal, 3-phenyl-  | 104-55-2   |                    | 9/30/91        | 6/30/98     |
| 2-Propenal, 3-phenyl-, monopentyl deriv.                               | 1331-92-6  |                    | 9/30/91        | 6/30/98     |
| 2-Pyridinecarboxaldehyde   | 1121-60-4  |                    | 9/30/91        | 12/19/95    |
| 2-Thiophene carboxaldehyde   | 98-03-3    |                    | 9/30/91        | 12/19/95    |
| Undecanal  | 112-44-7   |                    | 9/30/91        | 6/30/98     |
| Undecanal, 2-methyl-   | 110-41-8   |                    | 9/30/91        | 6/30/98     |
| 9-Undecenal  | 143-14-6   |                    | 9/30/91        | 12/19/95    |
| 10-Undecenal   | 112-45-8   |                    | 9/30/91        | 6/30/98     |
| Alkyl-, Chloro-, and Hydroxymethyl Diaryl Ethers:                      |            |                    |                |             |
| Benzene, 1-(bromomethyl)-3-phenoxy-                                    | 51632-16-7 |                    | 04/12/93       | 06/30/98    |
| Benzenemethanol, 3-phenoxy-  | 13826-35-2 |                    | 04/12/93       | 06/30/98    |
| Benzenemethanol, 3-phenoxy-, acetate                                   | 50789-44-1 |                    | 4/12/93        | 12/19/95    |
| Benzene, 1-methyl-3-phenoxy-   | 3586-14-9  |                    | 04/12/93       | 06/30/98    |
| Benzene, 1,1'-oxybis[dodecyl]-   | 69834-19-1 |                    | 4/12/93        | 12/19/95    |
| Benzene, 1,1'-oxybis[methyl]-  | 28299-41-4 |                    | 04/12/93       | 06/30/98    |
| Benzene, 1,1'-oxybis[(1,1,3,3-tetramethylbutyl)-                       | 61702-88-3 |                    | 4/12/93        | 12/19/95    |
| Benzoic acid, 3-[2-chloro-4-(trifluoromethyl)phenoxy]-, ...            | 63734-62-3 |                    | 04/12/93       | 06/30/98    |
| Benzoic acid, 3-[2-chloro-4-(trifluoromethyl)phenoxy], potassium salt. | 72242-48-3 |                    | 04/12/93       | 06/30/98    |
| 1,1'-Biphenyl, phenoxy-  | 28984-89-6 |                    | 04/12/93       | 06/30/98    |
| 2-Chloro-1-(3-methylphenoxy)-4-(trifluoromethyl)benzene.               | 42874-96-4 |                    | 04/12/93       | 06/30/98    |
| 1,4-Diphenoxybenzene   | 3061-36-7  |                    | 4/12/93        | 12/19/95    |
| Phenol, 3-[2-chloro-4-(trifluoromethyl)phenoxy]-, acetate              | 50594-77-9 |                    | 04/12/93       | 06/30/98    |
| Alkyl Phosphates:  |            |                    |                |             |
| Ethanol, 2-butoxy-, phosphate (3:1)                                    | 78-51-3    |                    | 10/29/90       | 12/19/95    |
| Ethanol, 2-(2-butoxyethoxy)-, phosphate (3:1)                          | 7332-46-9  |                    | 10/29/90       | 11/09/93    |
| Phosphoric acid, bis(2-ethylhexyl) ester                               | 298-07-7   |                    | 10/29/90       | 12/19/95    |
| Phosphoric acid, dibutyl ester   | 107-66-4   |                    | 10/29/90       | 06/30/98    |
| Phosphoric acid, didodecyl ester                                       | 7057-92-3  |                    | 10/29/90       | 11/09/93    |
| Phosphoric acid, diisooctyl ester                                      | 27215-10-7 |                    | 10/29/90       | 11/09/93    |
| Phosphoric acid, dodecyl ester   | 12751-23-4 |                    | 10/29/90       | 11/09/93    |

§ 716.120

40 CFR Ch. I (7–1–10 Edition)

| Category  | CAS No.         | Special Exemptions        | Effective Date | Sunset Date |
|---|-----------------|---------------------------|----------------|-------------|
| Phosphoric acid, 2-ethylhexyl ester .....   | 12645–31–7 ...  | .....                     | 10/29/90       | 11/09/93    |
| Phosphoric acid, monobutyl ester .....  | 1623–15–0 ..... | .....                     | 10/29/90       | 11/09/93    |
| Phosphoric acid, mono(2-ethylhexyl)ester .....                                      | 1070–03–7 ..... | .....                     | 10/29/90       | 11/09/93    |
| Phosphoric acid, monohexyl ester .....  | 3900–04–7 ..... | .....                     | 10/29/90       | 11/09/93    |
| Phosphoric acid, monomethyl ester .....   | 812–00–0 .....  | .....                     | 10/29/90       | 11/09/93    |
| Phosphoric acid, mono(1-methylethyl)ester .....                                     | 1623–24–1 ..... | .....                     | 10/29/90       | 11/09/93    |
| Phosphoric acid, monoethyl ester .....  | 3991–73–9 ..... | .....                     | 10/29/90       | 11/09/93    |
| Phosphoric acid, monoctadecyl ester .....   | 2958–09–0 ..... | .....                     | 10/29/90       | 11/09/93    |
| Phosphoric acid, triethyl ester .....   | 78–40–0 .....   | .....                     | 10/29/90       | 12/19/95    |
| Phosphoric acid, tris(2-ethylhexyl) ester .....                                     | 78–42–2 .....   | .....                     | 10/29/90       | 12/19/95    |
| Phosphoric acid, tris(2-methylpropyl) ester .....                                   | 126–71–6 .....  | .....                     | 10/29/90       | 11/09/93    |
| Phosphorodichloridic acid, ethyl ester .....  | 1498–51–7 ..... | .....                     | 10/29/90       | 11/09/93    |
| Alkylphenols and Alkylphenol Ethoxyates:  |                 |                           |                |             |
| tert-Butylphenol (mixed isomers) .....  | 27178–34–3 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 2-Butylphenol .....   | 3180–09–4 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 2-tert-Butylphenol .....  | 88–18–6 .....   | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-n-Butylphenol .....   | 1638–22–8 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-sec-Butylphenol .....   | 99–71–8 .....   | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-tert-Butylphenol .....  | 98–54–4 .....   | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Decaethylene glycol 4-isocetylphenyl ether .....                                    | 2315–66–4 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-Dodecylphenol .....   | 104–43–8 .....  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Dodecylphenol (mixed isomers) .....   | 1331–57–3 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Dedecylphenol (mixed isomers) .....   | 27193–86–8 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Hexaethylene glycol 4-isocetylphenyl ether .....                                    | 2497–58–7 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Isobutylphenol (mixed isomers) .....  | 31195–95–6 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Isononylphenol (mixed isomers) .....  | 11066–49–2 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-(1-Methylbutyl)phenol .....   | 94–06–4 .....   | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| (1-Methylheptyl)phenol (mixed isomers) .....  | 27985–70–2 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-(1-Methyloctyl)phenol .....   | 17404–66–9 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Nonylphenol (mixed isomers) .....   | 1300–16–9 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
|   | 25154–52–3 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-Nonylphenol .....   | 104–40–5 .....  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Branched 4-nonylphenol (mixed isomers) .....  | 84852–15–3 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 2-Octylphenol .....   | 949–13–3 .....  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-Octylphenol .....   | 1806–26–4 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-Pentylphenol .....  | 14938–35–3 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 4-tert-Pentylphenol .....   | 80–46–6 .....   | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Polyethylene glycol mono(octyl)phenyl ether .....                                   | 9036–19–5 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Polyethylene glycol 4-(tert-octyl)phenyl ether .....                                | 9002–93–1 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| Poly(oxy-1,2-ethanediyl), $\alpha$ -(octylphenyl)- $\omega$ -hydroxy-,<br>branched. | 68987–90–6 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| 2-(1,1,3,3-Tetramethylbutyl)phenol .....  | 3884–95–5 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
| (1,1,3,3-Tetramethylbutyl)phenol (mixed isomers) .....                              | 1322–69–6 ..... | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |
|   | 27193–28–8 ...  | § 716.20(b)(4)<br>applies | 3/29/96        | 6/30/98     |

Environmental Protection Agency

§ 716.120

| Category   | CAS No.        | Special Exemptions     | Effective Date | Sunset Date |
|--|----------------|------------------------|----------------|-------------|
|  | 29932-96-5 ... | § 716.20(b)(4) applies | 3/29/96        | 6/30/98     |
|  | 30105-54-5 ... | § 716.20(b)(4) applies | 3/29/96        | 6/30/98     |
|  | 62744-41-6 ... | § 716.20(b)(4) applies | 3/29/96        | 6/30/98     |
| 4-(2,2,3,3-Tetramethylbutyl)phenol .....   | 54932-78-4 ... | § 716.20(b)(4) applies | 3/29/96        | 6/30/98     |
| <b>Brominated flame retardants:</b>  |                |                        |                |             |
| Alkanes, C10-18, bromochloro- .....  | 68955-41-9 ... |                        | 10/29/90       | 12/19/95    |
| Benzamide, 3,5-dibromo-N-(4-bromophenyl)-2-hydroxy- .....  | 87-10-5 ...    |                        | 10/29/90       | 12/19/95    |
| Benzene, ethenyl-, homopolymer, brominated .....   | 88497-56-7 ... |                        | 10/29/90       | 11/09/93    |
| Benzene, 1,1'-(1-methylethylidene)bis (3,5-dibromo-4-(2-propenyloxy)- .....                                  | 25327-89-3 ... |                        | 10/29/90       | 11/09/93    |
| Benzene, pentabromomethyl- .....   | 87-83-2 ...    |                        | 10/29/90       | 12/19/95    |
| Cyclohexane, 1,2,3,4,5-pentabromo-6-chloro- .....  | 87-84-3 ...    |                        | 10/29/90       | 12/19/95    |
| Cyclohexane, tetrabromodichloro- .....   | 30554-72-4 ... |                        | 10/29/90       | 12/19/95    |
| Cyclohexane, tribromotrifluoro- .....  | 30554-73-5 ... |                        | 10/29/90       | 12/19/95    |
| Ethanol, 2,2'-((1-methylethylidene)bis ((2,6-dibromo-4,1-phenyleneoxy) bis- .....                            | 4162-45-2 ...  |                        | 10/29/90       | 12/19/95    |
| Ethene, bromo- .....   | 593-60-2 ...   |                        | 10/29/90       | 06/30/98    |
| Phenol, 2,4-dibromo- .....   | 615-58-7 ...   |                        | 10/29/90       | 12/19/95    |
| Phenol, 2,4(or 2,6)-dibromo-homopolymer .....  | 69882-11-7 ... |                        | 10/29/90       | 12/19/95    |
| 1-Propanol, 2,3-dibromo- .....   | 96-13-9 ...    |                        | 10/29/90       | 12/19/95    |
| 1-Propanol, 2,2-dimethyl-tribromo deriv .....  | 36483-57-5 ... |                        | 10/29/90       | 12/19/95    |
| 2-Propenoic acid,(1-methylethylidene)bis (2,6-dibromo-4,1-phenylene) ester. .....                            | 55205-38-4 ... |                        | 10/29/90       | 12/19/95    |
| <b>Chloroalkyl phosphates:</b>   |                |                        |                |             |
| 2,2-Bis(chloromethyl)-1,3-propanediyltetrakis(2-chloroethyl) phosphate. .....                                | 38051-10-4 ... |                        | 6/14/93        | 12/19/95    |
| 2-Chloro-1-methylethylbis(2-chloropropyl) phosphate- .....   | 76649-15-5 ... |                        | 6/14/93        | 12/19/95    |
| 1,2-Ethanediy tetrakis(2-chloro-1-methylethylene) phosphate. .....   | 34621-99-3 ... |                        | 6/14/93        | 12/19/95    |
| Oxydi-2,1-ethanediy tetrakis(2-chloroethyl) phosphate ..   | 53461-82-8 ... |                        | 6/14/93        | 12/19/95    |
| <b>Cyanoacrylates:</b>   |                |                        |                |             |
| 2-Propenoic acid, 2-cyano-, methyl ester .....   | 137-05-3 ...   |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-, isobutyl ester .....   | 1069-55-2 ...  |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-3,3-diphenyl-, 2-ethylhexyl ester. .....   | 6197-30-4 ...  |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-, butyl ester .....  | 6606-65-1 ...  |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-, ethyl ester .....  | 7085-85-0 ...  |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-, 2-propenyl ester .....   | 7324-02-9 ...  |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-, 1-methylethyl ester .....  | 10586-17-1 ... |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-, ethoxy ethyl ester .....   | 21982-43-4 ... |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-, 2,2,2-trifluoromethyl ester ...  | 23023-91-8 ... |                        | 1/26/94        | 12/19/95    |
| 2-Propenoic acid, 2-cyano-, 2-methoxyethyl ester .....   | 27816-23-5 ... |                        | 1/26/94        | 12/19/95    |
| Ethanaminium, 2-[[2-cyano-3-[4-(diethylamino)phenyl]-1-oxo-2-propenyl]oxy]-N,N,N-trimethyl-, chloride. ..... | 64992-16-1 ... |                        | 1/26/94        | 12/19/95    |
| <b>Indium Compounds:</b>   |                |                        |                |             |
| Acetic acid, indium(3+) salt .....   | 25114-58-3 ... | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| Indium .....   | 7440-74-6 ...  | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| Indium chloride (InCl <sub>3</sub> ) .....   | 10025-82-8 ... | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| Indium hydroxide (In(OH) <sub>3</sub> ) .....  | 20661-21-6 ... | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| Indium oxide (In <sub>2</sub> O <sub>3</sub> ) .....   | 1312-43-2 ...  | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| Indium phosphide (InP) .....   | 22398-80-7 ... | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| Indium tin oxide .....   | 50926-11-9 ... | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| Sulfamic acid, indium(3+) salt .....   | 66027-93-8 ... | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| Sulfuric acid, indium(3+) salt (3:2) .....   | 13464-82-9 ... | § 716.21(a)(6)         | 6/3/04         | 8/2/04      |
| <b>IRIS Chemicals:</b>   |                |                        |                |             |
| 3,4-Dimethylphenol .....   | 95-65-8 ...    |                        | 9/30/91        | 12/19/95    |
| 2,4-Dinitrophenol .....  | 51-28-5 ...    |                        | 9/30/91        | 12/19/95    |
| <b>Isocyanates:</b>  |                |                        |                |             |
| Acetic acid, isocyanato-, ethyl ester .....  | 2949-22-6 ...  |                        | 10/29/90       | 11/09/93    |
| Benzene, bis(isocyanatomethyl)- .....  | 25854-16-4 ... |                        | 10/29/90       | 11/09/93    |
| Benzene, 1-bromo-4-isocyanato- .....   | 2493-02-9 ...  |                        | 10/29/90       | 11/09/93    |
| Benzene, 1-chloro-3-isocyanato- .....  | 2909-38-8 ...  |                        | 10/29/90       | 11/09/93    |
| Benzene, 1-chloro-4-isocyanato- .....  | 104-12-1 ...   |                        | 10/29/90       | 06/30/98    |
| Benzene, 1,2-dichloro-4-isocyanato- .....  | 102-36-3 ...   |                        | 10/29/90       | 06/30/98    |
| Benzene, 1,3-dichloro-5-isocyanato- .....  | 34893-92-0 ... |                        | 10/29/90       | 11/09/93    |
| Benzene, 1,1'-(diisocyanatomethylene)bis- .....  | 10031-75-1 ... |                        | 10/29/90       | 11/09/93    |
| Benzene, isocyanato- .....   | 103-71-9 ...   |                        | 10/29/90       | 06/30/98    |
| Benzene, 2-isocyanato-1,3-bis(1-methylethyl)- .....  | 28178-42-9 ... |                        | 10/29/90       | 11/09/93    |
| Benzene, 2-isocyanato-1,3-dimethyl-, ester .....   | 28556-81-2 ... |                        | 10/29/90       | 11/09/93    |



| Category   | CAS No.    | Special Exemptions              | Effective Date | Sunset Date |
|--|------------|---------------------------------|----------------|-------------|
| Benzene, 1-isocyanato-2-methyl-  | 614-68-6   |                                 | 10/29/90       | 11/09/93    |
| Benzene, 1-isocyanato-4-methyl-  | 622-58-2   |                                 | 10/29/90       | 11/09/93    |
| Benzene, 1-isocyanato-4-nitro-   | 100-28-7   |                                 | 10/29/90       | 11/09/93    |
| Benzene, 1-isocyanato-3-(trifluoromethyl)-   | 329-01-1   |                                 | 10/29/90       | 06/30/98    |
| Benzene, 1,1',1''-methylidynetris(4-isocyanato-  | 2422-91-5  |                                 | 10/29/90       | 11/09/93    |
| Butane, 1-isocyanato-  | 111-36-4   |                                 | 10/29/90       | 06/30/98    |
| Cyclohexane, 2-heptyl-3,4-bis (9-isocyanatononyl)-1-pentyl-  | 68239-06-5 |                                 | 10/29/90       | 11/09/93    |
| Cyclohexane, isocyanato-   | 3173-53-3  |                                 | 10/29/90       | 11/09/93    |
| 1,3-Diazetidone-2,4-dione, 1,3-bis(3-isocyanato methylphenyl)-   | 26747-90-0 |                                 | 10/29/90       | 11/09/93    |
| Ethane, isocyanato-  | 109-90-0   |                                 | 10/29/90       | 12/19/95    |
| Imidodicarbonic diamide, N,N'-2-tris(6-isocyanatohexyl)-   | 4035-89-6  |                                 | 10/29/90       | 11/09/93    |
| Methane, isocyanato-   | 624-83-9   |                                 | 10/29/90       | 12/19/95    |
| Octadecane, 1-isocyanato-  | 112-96-9   |                                 | 10/29/90       | 11/09/93    |
| Phenol, 4-isocyanato-, phosphorothioate (3:1) (ester)  | 4151-51-3  |                                 | 10/29/90       | 11/09/93    |
| Propane, 1-isocyanato-   | 110-78-1   |                                 | 10/29/90       | 11/09/93    |
| 1-Propene, 3-isocyanato-   | 1476-23-9  |                                 | 10/29/90       | 11/09/93    |
| 2-Propenoic acid, 2-methyl-, 2- isocyanatoethyl ester  | 30674-80-7 |                                 | 10/29/90       | 12/19/95    |
| 2-Propenoic acid, 2-methyl-2-(((5-isocyanato-1,3,3-trimethylcyclohexyl)methyl)amino) carbonyloxyethyl ester. | 73597-26-9 |                                 | 10/29/90       | 11/09/93    |
| 1,3,5,-Triazine-2,4,6(1H,3H,5H)-trione, 1,3,5-tris(3-isocyanatomethylphenyl)-                                | 26603-40-7 |                                 | 10/29/90       | 11/09/93    |
| Methyl ethylene glycol ethers and esters:  |            |                                 |                |             |
| Ethylene glycol monomethyl ether acrylate  | 3121-61-7  |                                 | 1/26/94        | 12/19/95    |
| Tetraethylene glycol monomethyl ether  | 23783-42-8 |                                 | 1/26/94        | 12/19/95    |
| OSHA Chemicals in Need of Dermal Absorption Testing:   |            |                                 |                |             |
| Amitrole   | 61-82-5    | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |
| <i>n</i> -Amyl acetate   | 628-63-7   | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| <i>o</i> -Anisidine  | 90-04-0    | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |
| Benzyl chloride  | 100-44-7   | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |
| <i>sec</i> -Butyl acetate  | 105-46-4   | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| <i>tert</i> -Butyl acetate   | 540-88-5   | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| <i>sec</i> -Butyl alcohol  | 78-92-2    | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| <i>tert</i> -Butyl alcohol   | 75-65-0    | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| <i>t</i> -Butylcatechol  | 98-29-3    | § 716.20(b)(3) and (b)(4) apply | 8/4/95         | 6/30/98     |
| <i>o</i> - <i>sec</i> -butylphenol   | 89-72-5    |                                 | 3/11/94        | 6/30/98     |
| Camphor  | 76-22-2    | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| Carbon disulfide   | 75-15-0    | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |
| Catechol   | 120-80-9   | § 716.20(b)(3) and (b)(4) apply | 8/4/95         | 6/30/98     |
| <i>a</i> -Chloroacetophenone   | 532-27-4   | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| Chlorobenzene  | 108-90-7   | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |
| <i>o</i> -Chlorotoluene  | 95-49-8    | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |
| Cyclohexene  | 110-83-8   | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| Cyclohexanol   | 108-93-0   | § 716.20(b)(3) and (b)(4) apply | 8/4/95         | 6/30/98     |
| Cyclopentadiene  | 542-92-7   | § 716.20(b)(3) and (b)(4) apply | 8/4/95         | 6/30/98     |
| Cyclopentane   | 287-92-3   | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| Diacetone alcohol  | 123-42-2   | § 716.20(b)(3) and (b)(4) apply | 8/4/95         | 6/30/98     |
| Dibutyl phosphate  | 107-66-4   | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| 1,2-Dichloroethylene   | 540-59-0   | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |

Environmental Protection Agency

§ 716.120

| Category                         | CAS No.         | Special Exemptions                 | Effective Date | Sunset Date |
|----------------------------------|-----------------|------------------------------------|----------------|-------------|
| Dicyclopentadiene .....          | 77-73-6 .....   | § 716.20(b)(3)<br>and (b)(4) apply | 8/4/95         | 6/30/98     |
| Dimethyl acetamide .....         | 127-19-5 .....  | § 716.20(b)(3)<br>and (b)(4) apply | 8/4/95         | 6/30/98     |
| Dimethylaniline .....            | 121-69-7 .....  | § 716.20(b)(3)<br>and (b)(4) apply | 8/4/95         | 6/30/98     |
| Dimethyl sulfate .....           | 77-78-1 .....   | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| m-Dinitrobenzene .....           | 99-65-0 .....   | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| o-Dinitrobenzene .....           | 528-29-0 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| p-Dinitrobenzene .....           | 100-25-4 .....  | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| 2,4-Dinitrotoluene .....         | 121-14-2 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| Diphenylamine .....              | 122-39-4 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| Disulfiram .....                 | 97-77-8 .....   | § 716.20(b)(3)<br>applies          | 1/26/94        | 1/26/94     |
| Ethyl bromide .....              | 74-96-4 .....   | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| Ethyl ether .....                | 60-29-7 .....   | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Heptane (n-Heptane) .....        | 142-82-5 .....  | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Indene .....                     | 95-13-6 .....   | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| Isoamyl acetate .....            | 123-92-2 .....  | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| N-Isopropylaniline .....         | 768-52-5 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| p-Methoxyphenol .....            | 150-76-5 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| Methyl acetate .....             | 79-20-9 .....   | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Methylcyclohexane .....          | 108-87-2 .....  | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Methyl formate .....             | 107-31-3 .....  | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Methyl isoamyl ketone .....      | 110-12-3 .....  | § 716.20(b)(3)<br>and (b)(4) apply | 8/4/95         | 6/30/98     |
| p-Nitroaniline .....             | 100-01-6 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| p-Nitrochlorobenzene .....       | 100-00-5 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| 1-Nitropropane .....             | 108-03-2 .....  | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| 2-Nitropropane .....             | 79-46-9 .....   | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| m-Nitrotoluene .....             | 99-08-1 .....   | § 716.20(b)(3)<br>and (b)(4) apply | 8/4/95         | 6/30/98     |
| o-Nitrotoluene .....             | 88-72-2 .....   | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| p-Nitrotoluene .....             | 99-99-0 .....   | § 716.20(b)(3)<br>and (b)(4) apply | 8/4/95         | 6/30/98     |
| Nonane .....                     | 111-84-2 .....  | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Pentane .....                    | 109-66-0 .....  | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Phenylhydrazine .....            | 100-63-0 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| Propylene glycol dinitrate ..... | 6423-43-4 ..... | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| Sodium bisulfite .....           | 7631-90-5 ..... | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Sodium metabisulfite .....       | 7681-57-4 ..... | § 716.20(b)(3)<br>applies          | 1/26/94        | 6/30/98     |
| Tetrahydrofuran .....            | 109-99-9 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |
| m-Toluidine .....                | 108-44-1 .....  | § 716.20(b)(3)<br>applies          | 3/11/94        | 6/30/98     |

§ 716.120

40 CFR Ch. I (7–1–10 Edition)

| Category   | CAS No.           | Special Exemptions              | Effective Date | Sunset Date |
|--|-------------------|---------------------------------|----------------|-------------|
| Vinylidene chloride .....  | 75-35-4 .....     | § 716.20(b)(3) and (b)(4) apply | 8/4/95         | 6/30/98     |
| Vinyl toluene .....  | 25013-15-4 .....  | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |
| <i>p</i> -Xylene .....   | 106-42-3 .....    | § 716.20(b)(3) applies          | 1/26/94        | 6/30/98     |
| Xylidine .....   | 1300-73-8 .....   | § 716.20(b)(3) applies          | 3/11/94        | 6/30/98     |
| Propylene glycol ethers and esters:                                  |                   |                                 |                |             |
| Dipropylene glycol .....   | 110-96-5 .....    |                                 | 1/26/94        | 12/19/95    |
| Dipropylene glycol butyl ether .....                                 | 29911-28-2 .....  |                                 | 1/26/94        | 12/19/95    |
| Dipropylene glycol monomethyl ether acetate .....                    | 88917-22-0 .....  |                                 | 1/26/94        | 12/19/95    |
| 1-(2-Methoxy-1-methylethoxy)-2-propanol .....                        | 20324-32-7 .....  |                                 | 1/26/94        | 12/19/95    |
| Methoxy-1-propanol .....   | 28677-93-2 .....  |                                 | 1/26/94        | 12/19/95    |
| 1-Phenoxy-2-propanol .....   | 770-35-4 .....    |                                 | 1/26/94        | 12/19/95    |
| Propylene glycol monobutyl ether .....                               | 29387-86-8 .....  |                                 | 1/26/94        | 12/19/95    |
| Propylene glycol monomethyl ether acetate .....                      | 108-65-6 .....    |                                 | 1/26/94        | 12/19/95    |
| Propylene glycol mono- <i>tert</i> -butyl ether .....                | 57018-52-7 .....  |                                 | 1/26/94        | 12/19/95    |
| Tripropylene glycol diacrylate .....                                 | 42978-66-5 .....  |                                 | 1/26/94        | 12/19/95    |
| Tripropylene glycol methyl ether .....                               | 20324-33-8 .....  |                                 | 1/26/94        | 12/19/95    |
| Siloxanes:   |                   |                                 |                |             |
| Cyclopolydimethylsiloxane .....                                      | 69430-24-6 .....  |                                 | 10/12/93       | 06/30/98    |
| Decamethylcyclopentasiloxane .....                                   | 541-02-6 .....    |                                 | 10/12/93       | 06/30/98    |
| Decamethyltetrasiloxane .....  | 141-62-8 .....    |                                 | 10/12/93       | 06/30/98    |
| Dimethyldiphenylsiloxane .....                                       | 68083-14-7 .....  |                                 | 10/12/93       | 06/30/98    |
| Dimethylhydropolysiloxane .....                                      | 68037-59-2 .....  |                                 | 10/12/93       | 06/30/98    |
| Dimethylmethyl 3,3,3-trifluoropropyl siloxane .....                  | 115361-68-7 ..... |                                 | 10/12/93       | 06/30/98    |
| Dimethylmethylvinylsiloxane .....                                    | 67762-94-1 .....  |                                 | 10/12/93       | 06/30/98    |
| Dimethylpolysiloxanes .....  | 68037-74-1 .....  | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Dimethyl silicones and siloxanes .....                               | 63148-62-9 .....  |                                 | 10/12/93       | 06/30/98    |
| Dimethyl silicones and siloxane, reaction products with silica ..... | 67762-90-7 .....  | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Docosamethylcycloundecasiloxane .....                                | 18766-38-6 .....  | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Docosamethyldecasiloxane .....                                       | 556-70-7 .....    | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Dodecamethylcyclohexasiloxane .....                                  | 540-97-6 .....    |                                 | 10/12/93       | 06/30/98    |
| Dodecamethylpentasiloxane .....                                      | 141-63-9 .....    |                                 | 10/12/93       | 06/30/98    |
| Dotetracontamethyleicosasiloxane .....                               | 150027-00-2 ..... | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Dotriacontamethylcyclohexadecasiloxane .....                         | 150026-95-2 ..... | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Dotriacontamethylpentadecasiloxane .....                             | 2471-11-6 .....   | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Eicosamethylcyclodecasiloxane .....                                  | 18772-36-6 .....  | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Eicosamethylnonasiloxane .....                                       | 2652-13-3 .....   | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Hexacosamethylcyclotridecasiloxane .....                             | 23732-94-7 .....  | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Hexacosamethyldodecasiloxane .....                                   | 2471-08-1 .....   | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Hexadecamethylcyclooctasiloxane .....                                | 556-68-3 .....    | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Hexadecamethylheptasiloxane .....                                    | 541-01-5 .....    | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Hexamethylcyclotrisiloxane .....                                     | 541-05-9 .....    |                                 | 10/12/93       | 06/30/98    |
| Hexamethyldisilazane .....   | 999-97-3 .....    |                                 | 10/12/93       | 06/30/98    |
| Hexamethyldisiloxane .....   | 107-46-0 .....    |                                 | 10/12/93       | 06/30/98    |
| Hexatriacontamethylcyclooctadecasiloxane .....                       | 23523-12-8 .....  | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Hexatriacontamethylheptadecasiloxane .....                           | 18844-04-7 .....  | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Methylpolysiloxane .....   | 9004-73-3 .....   |                                 | 10/12/93       | 06/30/98    |
| Methylvinylcyclosiloxane .....                                       | 2554-06-5 .....   |                                 | 10/12/93       | 06/30/98    |
| Siloxanes and silicones, di-Me, hydroxy-terminated .....             | 70131-67-8 .....  | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Octacosamethylcyclotetradecasiloxane .....                           | 149050-40-8 ..... | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Octacosamethyltridecasiloxane .....                                  | 2471-09-2 .....   | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |
| Octadecamethylcyclononasiloxane .....                                | 556-71-8 .....    | § 716.20(b)(2) applies          | 10/12/93       | 06/30/98    |

Environmental Protection Agency

§ 716.120

| Category  | CAS No.          | Special Exemptions        | Effective Date | Sunset Date |
|---|------------------|---------------------------|----------------|-------------|
| Octadecamethylcyclotetrasiloxane .....                        | 556-69-4 .....   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Octamethyltrisiloxane .....                                   | 107-51-7 .....   |                           | 10/12/93       | 06/30/98    |
| Octaphenylcyclotetrasiloxane .....                            | 546-56-5 .....   |                           | 10/12/93       | 06/30/98    |
| Octatriacontamethylcyclononadecasiloxane .....                | 150026-97-4 ..   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Octatriacontamethylcyclotetradecasiloxane .....               | 36938-52-0 ...   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Polymethylcyclotetrasiloxane .....                            | not available .. | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Tetracontamethylcycloheptadecasiloxane .....                  | 150026-98-5 ..   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Tetracontamethylnonadecasiloxane .....                        | 150026-99-6 ..   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Tetracosamethylcyclododecasiloxane .....                      | 18919-94-3 ...   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Tetracosamethylundecasiloxane .....                           | 107-53-9 .....   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Tetradecamethylcycloheptasiloxane .....                       | 107-50-6 .....   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Tetradecamethylhexasiloxane .....                             | 107-52-8 .....   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Tetramethylcyclotetrasiloxane .....                           | 2370-88-9 ....   |                           | 10/12/93       | 06/30/98    |
| Tetramethyldivinylidrasiloxane .....                          | 2627-95-4 .....  |                           | 10/12/93       | 06/30/98    |
| Tetatriacontamethylcycloheptadecasiloxane .....               | 150026-96-3 ..   |                           | 10/12/93       | 06/30/98    |
| Tetatriacontamethylhexadecasiloxane .....                     | 36938-50-8 ...   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Triaccontamethylcyclopentadecasiloxane .....                  | 23523-14-0 ...   | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Triaccontamethyltetradecasiloxane .....                       | 2471-10-5 .....  | § 716.20(b)(2)<br>applies | 10/12/93       | 06/30/98    |
| Trifluoropropylmethylcyclotrisiloxane .....                   | 2374-14-3 .....  |                           | 10/12/93       | 06/30/98    |
| Substantially produced chemicals in need of subchronic tests: |                  |                           |                |             |
| Acetoacetanilide .....  | 102-01-2 .....   |                           | 9/30/91        | 12/19/95    |
| 4-(Acetylamino)benzenesulfonyl chloride .....                 | 121-60-8 .....   |                           | 9/30/91        | 6/30/98     |
| 2-(2-Aminoethoxy)-ethanol .....                               | 929-06-6 .....   |                           | 6/30/92        | 6/30/98     |
| 7-Amino-4-hydroxy-2-naphthalenesulfonic acid .....            | 87-02-5 .....    |                           | 9/30/91        | 12/19/95    |
| Ammonium carbamate .....                                      | 1111-78-0 .....  |                           | 9/30/91        | 12/19/95    |
| 1,3-Benzenedisulfonic acid .....                              | 98-48-6 .....    |                           | 9/30/91        | 12/19/95    |
| Bis(2-ethylhexyl)-2-butenedioate .....                        | 142-16-5 .....   |                           | 9/30/91        | 12/19/95    |
| Bromamine acid .....  | 116-81-4 .....   |                           | 9/30/91        | 12/19/95    |
| Butyric anhydride .....                                       | 106-31-0 .....   |                           | 9/30/91        | 12/19/95    |
| Ethanol, 2-(2-ethoxyethoxy)-, acetate .....                   | 112-15-2 .....   |                           | 9/30/91        | 6/30/98     |
| 1,2-Dichlorobutane .....                                      | 616-21-7 .....   |                           | 9/30/91        | 12/19/95    |
| 3,4-Dichlorobutene .....                                      | 760-23-6 .....   |                           | 9/30/91        | 12/19/95    |
| 3,4-Dichloronitrobenzene .....                                | 99-54-7 .....    |                           | 9/30/91        | 6/30/98     |
| 1,3-Dicyanobenzene .....                                      | 626-17-5 .....   |                           | 9/30/91        | 6/30/98     |
| Diethylene glycol dimethyl ether .....                        | 111-96-6 .....   |                           | 9/30/91        | 6/30/98     |
| 4-Ethoxynitrobenzene .....                                    | 100-29-8 .....   |                           | 9/30/91        | 6/30/98     |
| 2-Ethylantraquinone .....                                     | 84-51-5 .....    |                           | 9/30/91        | 12/19/95    |
| Hexa(methoxymethyl) melamine .....                            | 3089-11-0 .....  |                           | 9/30/91        | 6/30/98     |
| 3-Hydroxy-2-naphthoic acid .....                              | 92-70-6 .....    |                           | 9/30/91        | 12/19/95    |
| Isobutyl acrylate .....                                       | 106-63-8 .....   |                           | 9/30/91        | 12/19/95    |
| Isophthaloyl chloride .....                                   | 9-63-8 .....     |                           | 9/30/91        | 12/19/95    |
| 4-Methyl-2-nitro-phenol .....                                 | 119-33-5 .....   |                           | 9/30/91        | 6/30/98     |
| 2-(4-Morpholinylidithio)-benzothiazole .....                  | 95-32-9 .....    |                           | 9/30/91        | 12/19/95    |
| Naphthalenedicarboxylic anhydride .....                       | 81-84-5 .....    |                           | 9/30/91        | 6/30/98     |
| 1-Naphthol .....  | 90-15-3 .....    |                           | 9/30/91        | 12/19/95    |
| <i>p,p'</i> -Oxybis(benzenesulfonylhydrazide) .....           | 80-51-3 .....    |                           | 9/30/91        | 6/30/98     |
| 2,4-Pentanedione .....  | 123-54-6 .....   |                           | 9/30/91        | 12/19/95    |
| Perfluoro-N-hexane .....                                      | 355-42-0 .....   |                           | 9/30/91        | 12/19/95    |
| Perfluorotributylamine .....                                  | 311-89-7 .....   |                           | 9/30/91        | 12/19/95    |
| Propanoic anhydride .....                                     | 123-62-6 .....   |                           | 9/30/91        | 12/19/95    |
| Quinacridone .....  | 1047-16-1 .....  |                           | 9/30/91        | 12/19/95    |
| Terephthaloyl chloride .....                                  | 100-20-9 .....   |                           | 9/30/91        | .....       |
| Trichloromethanesulfonyl chloride .....                       | 594-42-3 .....   |                           | 9/30/91        | 6/30/98     |
| Triethylene glycol bis(2-ethylhexanoate) .....                | 94-28-0 .....    |                           | 9/30/91        | 12/19/95    |
| Sulphones:  |                  |                           |                |             |
| 2-Amino-4-[(2-hydroxyethyl) sulfonyl]phenol .....             | 17601-96-6 ...   |                           | 9/30/91        | 12/19/95    |
| 2-Amino-4-(methylsulfonyl)phenol .....                        | 98-30-6 .....    |                           | 9/30/91        | 12/19/95    |
| 2-[(6-Amino-2-naphthalenyl) sulfonyl]ethanol .....            | 52218-35-6 ..    |                           | 9/30/91        | 12/19/95    |

| Category  | CAS No.    | Special Exemptions | Effective Date     | Sunset Date       |
|---|------------|--------------------|--------------------|-------------------|
| 2-[(3-Aminophenyl)sulfonyl]ethanol  | 5246-57-1  |                    | 9/30/91            | 12/19/95          |
| Bisphenol S   | 80-09-1    |                    | 9/30/91            | 12/19/95          |
| 3-(Decyloxy)tetrahydrothiophene 1,1-dioxide   | 18760-44-6 |                    | 9/30/91            | 12/19/95          |
| 4,4'-Diaminodiphenyl sulfone  | 80-08-0    |                    | 9/30/91            | 12/19/95          |
| 4-[4-[(2,6-Dichloro-4-nitrophenyl)azo]phenyl]thiomorpholine, 11,1-dioxide   | 17741-62-7 |                    | 9/30/91            | 12/19/95          |
| 1-(Diiodomethyl)sulfonyl-4-methyl benzene   | 20018-09-1 |                    | 9/30/91            | 12/19/95          |
| Dimethylsulfone   | 67-71-0    |                    | 9/30/91            | 12/19/95          |
| Diphenylsulfone   | 127-63-9   |                    | 9/30/91            | 12/19/95          |
| 3-[N-Ethyl-4-[[6-(methylsulfonyl)-2-benzothiazolyl]azo]-m-toluidino]propionitrile   | 16588-67-3 |                    | 9/30/91            | 12/19/95          |
| 1,1'-[Methylenebis(sulfonyl)]bis-2-chloroethane   | 41123-59-5 |                    | 9/30/91            | 12/19/95          |
| 2,2'-[Methylenebis(sulfonyl)]bisethanol   | 41123-69-7 |                    | 9/30/91            | 12/19/95          |
| 1,1'-[Methylenebis(sulfonyl)]bisethene  | 3278-22-6  |                    | 9/30/91            | 12/19/95          |
| 6-Methylsulfonyl-2-benzothiazolamine  | 17557-67-4 |                    | 9/30/91            | 12/19/95          |
| 2-[(3-Nitrophenyl)sulfonyl]ethanol  | 41687-30-3 |                    | 9/30/91            | 12/19/95          |
| 1,1'-[Oxybis(methylene-sulfonyl)]bis-2-chloroethane   | 53061-10-2 |                    | 9/30/91            | 12/19/95          |
| 2,2'-[Oxybis(methylene-sulfonyl)] bisethanol  | 36724-43-3 |                    | 9/30/91            | 12/19/95          |
| 1,1'-[Oxybis(methylene-sulfonyl)] bisethene   | 26750-50-5 |                    | 9/30/91            | 12/19/95          |
| 4-[[4-(Phenylmethoxy)phenyl]sulfonyl] phenol  | 63134-33-8 |                    | 9/30/91            | 12/19/95          |
| 4-Phenylthiomorpholine, 1,1-dioxide   | 17688-68-5 |                    | 9/30/91            | 12/19/95          |
| Sulfolane   | 126-33-0   |                    | 9/30/91            | 12/19/95          |
| 3-Sulfolene   | 77-79-2    |                    | 9/30/91            | 12/19/95          |
| Sulfonyl bis(4-chlorobenzene)   | 80-07-9    |                    | 9/30/91            | 12/19/95          |
| 2,2'-Sulfonyl bisethanol  | 2580-77-0  |                    | 9/30/91            | 12/19/95          |
| Voluntary HPV Challenge Program orphan (unsponsored) chemicals:   |            |                    |                    |                   |
| Acetaldehyde, reaction products with formaldehyde, by-products from.  | 68442-60-4 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Acetamide, 2,2-dichloro-N,N-di-2-propenyl-  | 37764-25-3 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Acid chlorides, tallow, hydrogenated  | 68955-37-3 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Alkanes, chloro   | 61788-76-9 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Alkenes, C>10 .alpha.-  | 64743-02-8 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Amides, coco, N-[3-(dimethylamino)propyl], alkylation products with sodium 3-chloro-2-hydroxypropanesulfonate.            | 70851-08-0 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Amides, tall-oil fatty, N,N-di-Me   | 68308-74-7 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Anthracene oil  | 90640-80-5 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Aromatic hydrocarbons, C8, o-xylene-lean  | 68650-36-2 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Aromatic hydrocarbons, C9-16, biphenyl deriv.-rich  | 68955-76-0 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Barium, carbonate nonylphenol complexes   | 68515-89-9 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzaldehyde, 3-bromo-  | 3132-99-8  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzaldehyde, 3-phenoxy-  | 39515-51-0 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzaldehyde, 4-(1,1-dimethylethyl)-  | 939-97-9   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenamine, 2,6-diethyl-N-methylene-   | 35203-08-8 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenamine, 2-ethyl-6-methyl-N-methylene-  | 35203-06-6 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenamine, 3-(trifluoromethyl)-   | 98-16-8    | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenamine, N,N-dimethyl-  | 121-69-7   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenamine, N-phenyl-4-[[4-(phenylamino)phenyl][4-(phenylimino)-2,5-cyclohexadien-1-ylidene]methyl]-, monohydrochloride. | 2152-64-9  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, (2-chloro-1,1-dimethylethyl)-  | 515-40-2   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, 1-(bromomethyl)-3-phenoxy-   | 51632-16-7 | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, 1,1'-[1,2-ethanediy]bis(oxy)]bis-  | 104-66-5   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |

Environmental Protection Agency

§ 716.120

| Category   | CAS No.         | Special Exemptions | Effective Date     | Sunset Date       |
|--|-----------------|--------------------|--------------------|-------------------|
| Benzene, 1,1'-oxybis-, tetrapropylene derivs. ....   | 119345-02-7     | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, 1,2-dimethyl-3-nitro- .....   | 83-41-0 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, 1-bromo-4-fluoro- .....   | 460-00-4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, 1-chloro-2,4-dinitro- .....   | 97-00-7 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, 1-chloro-4-(trichloromethyl)- .....   | 5216-25-1 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, 1-chloro-4-(trifluoromethyl)- .....   | 98-56-6 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, 1-methoxy-4-methyl- .....   | 104-93-8 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, chloromethyl- .....   | 25168-05-2 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, ethenylethyl- .....   | 28106-30-1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, ethylenated .....   | 68987-41-7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzene, mixed with toluene, dealkylation product .....  | 68953-80-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3-Benzenedicarboxylic acid, 5-sulfo-, 1,3-dimethyl ester.  | 138-25-0 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3-Benzenedicarboxylic acid, 5-sulfo-, 1,3-dimethyl ester, sodium salt.                             | 3965-55-7 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,2-Benzenedicarboxylic acid, bis(2-methylpropyl) ester  | 84-69-5 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,4-Benzenedicarboxylic acid, dimethyl ester, manuf. of, by-products from.                           | 68988-22-7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenemethanol, ,alpha,..,alpha.-dimethyl- .....  | 617-94-7 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenemethanol, 3-phenoxy- .....  | 13826-35-2 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenesulfonic acid, 3-nitro-, sodium salt .....  | 127-68-4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenesulfonic acid, 4-chloro-3,5-dinitro-, potassium salt.   | 38185-06-7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenesulfonic acid, C10-16-alkyl derivs., compds. with triethanolamine.                            | 68584-25-8 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenesulfonic acid, dimethyl- .....  | 25321-41-9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzenesulfonyl chloride .....   | 98-09-9 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,2-Benzisothiazol-3(2H)-one, 1,1-dioxide .....  | 81-07-2 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzoic acid, 2-methyl- .....  | 118-90-1 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2,4,6,8,3,5,7-Benzotetraoxatriplumbacycloundecin-3,5,7-triylidene, 1,9-dihydro-1,9-dioxo-            | 17976-43-1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzothiazole, 2-[(chloromethyl)thio]- .....   | 28908-00-1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Benzoyl chloride, 3,5-dichloro- .....  | 2905-62-6 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,2-Butadiene .....  | 590-19-2 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Butanedioic acid, oxo-, diethyl ester, ion(1-), sodium .....   | 40876-98-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Butanol, sodium salt .....   | 2372-45-4 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Butenal .....  | 4170-30-3 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Butenediamide, (2E)-, N,N'-bis[2-(4,5-dihydro-2-nortall-oil alkyl-1H-imidazol-1-yl)ethyl] derivs.. | 68442-77-3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Butenedioic acid (2E)-, di-C8-18-alkyl esters .....  | 68610-90-2 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Butenedioic acid (2Z)-, dioctyl ester .....  | 2915-53-9 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Butenenitrile, 2-methyl-, (2E)- .....  | 30574-97-1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Butenenitrile, 2-methyl-, (2Z)- .....  | 20068-02-4 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |

§ 716.120

40 CFR Ch. I (7–1–10 Edition)

| Category   | CAS No.         | Special Exemptions | Effective Date     | Sunset Date       |
|--|-----------------|--------------------|--------------------|-------------------|
| Carbamic acid, monoammonium salt .....   | 1111–78–0 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Carbamodithioic acid, monoammonium salt .....  | 513–74–6 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Carbonochlorodithioic acid, S-(phenylmethyl) ester .....   | 37734–45–5 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Carbonodithioic acid, O-(1-methylethyl) ester, sodium salt.  | 140–93–2 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Carboxylic acids, di-, C4–11 .....   | 68937–72–4 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Chromate(3-), bis[3-(hydroxy-.kappa.O)-4-[[2-(hydroxy-.kappa.O)-1-naphthalenyl]azo-.kappa.N1]-7-nitro-1-naphthalenesulfonato(3-)]-, trisodium. | 57693–14–8 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Coal, anthracite, calcined .....   | 68187–59–7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Creosote .....   | 8001–58–9 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Cyclohexane, oxidized, aq. ext., sodium salt .....   | 68915–39–9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Cyclohexane, oxidized, non-acidic by-products, distn. lights.  | 68609–05–2 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3-Cyclopentadiene .....  | 542–92–7 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Decane, 1-chloro- .....  | 1002–69–3 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Decanoic acid, mixed esters with dipentaerythritol, octanoic acid and valeric acid.  | 68441–66–7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Decene, sulfurized .....   | 72162–15–3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Distillates (coal tar) .....   | 65996–92–1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Distillates (coal tar), heavy oils .....   | 90640–86–1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Distillates (coal tar), upper .....  | 65996–91–0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Distillates (petroleum), hydrofined lubricating-oil .....  | 68782–97–8 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Distillates, hydrocarbon resin prodn. higher boiling .....   | 68602–81–3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Disulfides, alkylaryl dialkyl diaryl, petroleum refinery spent caustic oxidn. products.  | 68334–01–0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Disulfides, C5–12-alkyl .....  | 68513–62–2 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethane, 1,1,1-trimethoxy- .....  | 1445–45–0 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethane, 1,1'-[methylenebis(oxy)]bis[2-chloro- .....  | 111–91–1 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethane, 1,1'-oxybis[2-chloro- .....  | 111–44–4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethane, 1,2-dichloro-, manuf. of, by-products from, distn. lights.   | 68608–59–3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,2-Ethanediamine, N,N,N',N'-tetramethyl- .....  | 110–18–9 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethanedioic acid, calcium salt (1:1) .....   | 563–72–4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,2-Ethanediol, dinitrate .....  | 628–96–6 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethanesulfonic acid, 2-[methyl[(9Z)-1-oxo-9-octadeceny]amino]-, sodium salt.   | 137–20–2 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethanimidodithioic acid, N-hydroxy-, methyl ester .....  | 13749–94–5 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethanol, 2-(2-butoxyethoxy)-, sodium salt .....  | 38321–18–5 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethanol, 2,2'-oxybis-, reaction products with ammonia, morpholine derivs. residues.  | 68909–77–3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethanol, 2,2'-oxybis-, reaction products with ammonia, morpholine product tower residues.  | 71077–05–9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethanol, 2-[(4-aminophenyl)sulfonyl]-, hydrogen sulfate (ester).   | 2494–89–5 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethanol, 2-butoxy-, sodium salt .....  | 52663–57–7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Ethene, hydrated, by-products from .....   | 68987–66–6 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |

Environmental Protection Agency

§ 716.120

| Category  | CAS No.         | Special Exemptions | Effective Date     | Sunset Date       |
|---|-----------------|--------------------|--------------------|-------------------|
| Ethenesulfonic acid, sodium salt .....  | 3039-83-6 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Extract oils (coal), tar base .....   | 65996-86-3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Extract residues (coal), tar oil alk. ....  | 65996-87-4 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Extract residues (coal), tar oil alk., naphthalene distn. residues.                                   | 73665-18-6 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Extracts, coal tar oil alk. ....  | 65996-83-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Fats and Glyceric oils, vegetable, reclaimed .....  | 68990-65-8 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Fatty acids, tall-oil, 2-(2-hydroxyethoxy)ethyl esters .....  | 68309-16-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Fatty acids, tall-oil, low-boiling, reaction products with ammonia-ethanolamine reaction by-products. | 68915-05-9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Fatty acids, tall-oil, reaction products with diethylenetriamine, acetates.                           | 68153-60-6 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Fatty acids, tall-oil, sulfonated, sodium salts .....   | 68309-27-3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Formic acid, compd. with 2,2',2[ethanol] (1:1) .....  | 24794-58-9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2,5-Furandione, dihydro-3-(octenyl)- .....  | 26680-54-6 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Glycine, N-(carboxymethyl)- .....   | 142-73-4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Glycine, N-(carboxymethyl)-, disodium salt .....  | 928-72-3 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Glycine, N-methyl-, monosodium salt .....   | 4316-73-8 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Glycine, N-phenyl-, monopotassium salt .....  | 19525-59-8 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Glycine, N-phenyl-, monosodium salt .....   | 10265-69-7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Hexacosanol .....   | 506-52-5 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Hexadecane, 1-chloro- .....   | 4860-03-1 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,4-Hexadiene .....   | 592-45-0 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Hexanedioic acid, dihexyl ester .....   | 110-33-8 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Hexanedioic acid, esters with high-boiling C6-10-alkene hydroformylation products.                    | 84501-86-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3-Hexanediol, 2-ethyl- .....  | 94-96-2 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,6-Hexanediol, distn. residues .....   | 68937-29-1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Hexenal, 2-ethyl- .....   | 645-62-5 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1H-Isoindole-1,3(2H)-dione, 3a,4,7,7a-tetrahydro- .....   | 85-40-5 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Hydrocarbons, C12-20, catalytic alkylation by-products  | 68919-17-5 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Imidodicarbonic diamide, N,N',2-tris(6-isocyanatohexyl)-  | 4035-89-6 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3-Isobenzofurandione, 5-methyl- .....   | 19438-61-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Lard, oil, Me esters .....  | 68082-78-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Methanesulfonamide, N-[2-[(4-amino-3-methylphenyl)ethylamino]ethyl]-, sulfate (2:3).                  | 25646-71-3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Methanesulfonic acid, hydroxy-, monosodium salt .....   | 870-72-4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Methanesulfonyl chloride .....  | 124-63-0 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Methanone, (2-hydroxy-4-methoxyphenyl)phenyl- .....   | 131-57-7 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Naphtha (petroleum), clay-treated light straight-run .....  | 68527-22-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-, monosodium salt.                                  | 5460-09-3 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |



§ 716.120

40 CFR Ch. I (7–1–10 Edition)

| Category  | CAS No.         | Special Exemptions | Effective Date     | Sunset Date       |
|---|-----------------|--------------------|--------------------|-------------------|
| 1-Naphthalenesulfonic acid, 2-amino- .....  | 81–16–3 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Naphthalenesulfonic acid, 6-[(2,4-diaminophenyl)azo]-3-[[4-[[4-[[7-[(2,4-diaminophenyl)azo]-1-hydroxy-3-sulfo-2-naphthalenyl]azo]phenyl]amino]-3-sulfophenyl]azo]-4-hydroxy-, trisodium salt. | 6473–13–8 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Naphthalenol, 1,2,3,4-tetrahydro- .....   | 529–33–9 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1(2H)-Naphthalenone, 3,4-dihydro- .....   | 529–34–0 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1H,3H-Naphtho[1,8-cd]pyran-1,3-dione .....  | 81–84–5 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Nickel, bis[(cyano)triphenylborato(1-)-N]bis(hexanedinitrile-N,N')-.  | 83864–02–2 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Octacosanol .....   | 557–61–9 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Octadecane, 1-chloro- .....   | 3386–33–2 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Octadecanoic acid, 2-(1-carboxyethoxy)-1-methyl-2-oxoethyl ester, sodium salt.  | 25383–99–7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Octadecanoic acid, 2-(hydroxymethyl)-2-[[1-oxooctadecyl]oxy]methyl]-1,3-propanediyl ester.  | 28188–24–1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Octadecanoic acid, reaction products with 2-[(2-aminoethyl)amino]ethanol.   | 68815–50–9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 9-Octadecenoic acid, 12-(acetyloxy)-, 1,2,3-propanetriyl ester, (9Z,9'Z,9'',12R,12'R,12'')-.  | 101–34–8 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Octane, 1-chloro- .....   | 111–85–3 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Octanesulfonyl chloride .....   | 7795–95–1 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Octanesulfonyl fluoride .....   | 40630–63–5 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Oxirane, [(2-methylphenoxy)methyl]- .....   | 2210–79–9 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Oxiranemethanamine, N-[4-(oxiranylmethoxy)phenyl]-N-(oxiranylmethyl)-.  | 5026–74–4 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Paraffin oils, chlorosulfonated, saponified .....   | 68188–18–1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 3-Pentanone .....   | 96–22–0 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Pentene, 2,4,4-trimethyl- .....   | 107–39–1 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Pentene, 2,4,4-trimethyl- .....   | 107–40–4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, (1,1,3,3-tetramethylbutyl)- .....   | 27193–28–8 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, (1-methylethyl)- .....  | 25168–06–3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, 2-(1,1-dimethylethyl)-4-methyl- .....   | 2409–55–4 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, 2,4-bis(1,1-dimethylpropyl)-6-[(2-nitrophenyl)azo]-.  | 52184–19–7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, 2,4-bis(1-methyl-1-phenylethyl)-6-[(2-nitrophenyl)azo]-.  | 70693–50–4 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, 3-(diethylamino)- .....   | 91–68–9 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, 4-methyl-2-nitro- .....   | 119–33–5 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, isobutylated methylstyrenated .....   | 68457–74–9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, methyl-, sodium salt .....  | 34689–46–8 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, nonyl derivs. ....  | 68081–86–7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenol, styrenated .....  | 61788–44–1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phenols (petroleum) .....   | 64743–03–9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphoramidothioic acid, O,O-dimethyl ester .....  | 17321–47–0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphoric acid, (1,1-dimethylethyl)phenyl diphenyl ester.  | 56803–37–3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |

Environmental Protection Agency

§ 716.120

| Category  | CAS No.         | Special Exemptions | Effective Date     | Sunset Date       |
|---|-----------------|--------------------|--------------------|-------------------|
| Phosphoric acid, mixed 3-bromo-2,2-dimethylpropyl and 2-bromoethyl and 2-chloroethyl esters.  | 125997-20-8     | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorochlorodithioic acid, O,O-dimethyl ester .....  | 2524-03-0 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorochloridous acid, bis(4-nonylphenyl) ester .....  | 63302-49-8 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorodichloridic acid, ethyl ester .....  | 1498-51-7 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorodithioic acid, O,O-di-C1-14-alkyl esters .....   | 68187-41-7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorodithioic acid, O,O-di-C1-14-alkyl esters, zinc salts.  | 68649-42-3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorodithioic acid, O,O-dimethyl ester .....  | 756-80-9 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorodithioic acid, O,O-dimethyl ester, sodium salt   | 26377-29-7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorous acid, 2-(1,1-dimethylethyl)-4-[1-[3-(1,1-dimethylethyl)-4-hydroxyphenyl]-1-methylethyl]phenyl bis(4-nonylphenyl) ester. | 20227-53-6 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Phosphorous acid, isoctyl diphenyl ester .....  | 26401-27-4 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Piperazineethanol .....   | 25154-38-5 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Pitch, coal tar-petroleum .....   | 68187-57-5 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Propane, 2,2-dimethoxy- .....   | 77-76-9 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Propanenitrile, 3-(dimethylamino)- .....  | 1738-25-6 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Propanesulfonic acid, 2-hydroxy-3-(2-propenyloxy)-, monosodium salt.  | 52556-42-0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Propanoic acid, 2-bromo- .....  | 598-72-1 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Propanoic acid, 2-methyl-, 3-(benzoyloxy)-2,2,4-trimethylpentyl ester.  | 22527-63-5 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 2-Propenoic acid, 2-carboxyethyl ester .....  | 24615-84-7 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Pyridine, hydrochloride .....   | 628-13-7 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 4(1H)-Pyrimidinone, 6-methyl-2-(1-methylethyl)- .....   | 2814-20-2 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Solvent naphtha (coal) .....  | 65996-79-4 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Sulfonic acids, petroleum .....   | 61789-85-3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Tannins .....   | 1401-55-4 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Tannins, reaction products with sodium bisulfite, sodium polysulfide and sodium sulfite.  | 72854-27-4 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Tar oils, coal .....  | 65996-82-9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Tar, coal, dried and oxidized .....   | 68918-16-1 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Tar, coal, high-temp. .....   | 65996-89-6 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Tar, coal, high-temp., high-solids .....  | 68990-61-4 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Terpenes and Terpenoids, C10-30, distn. residues .....  | 70084-98-9 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1-Tetracosanol .....  | 506-51-4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Tetradecane, 1-chloro- .....  | 2425-54-9 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3,5,7-Tetrazocine, octahydro-1,3,5,7-tetranitro- .....  | 2691-41-0 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Thiazole, 4-methyl- .....   | 693-95-8 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Thiourea .....  | 62-56-6 .....   | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3,5-Triazine, hexahydro-1,3,5-trinitro- .....   | 121-82-4 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3,5-Triazine-2,4,6(1H,3H,5H)-trione, 1,3,5-tris(6-isocyanatohexyl)-.  | 3779-63-3 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |

| Category  | CAS No.         | Special Exemptions | Effective Date     | Sunset Date       |
|---|-----------------|--------------------|--------------------|-------------------|
| 1,3,5-Triazine-2,4-diamine, dimethylethyl-N'-ethyl-<br>6-chloro-N-(1,1- | 5915–41–3 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3,5-Triazine-2,4-diamine, methylethyl)-<br>6-chloro-N,N'-bis(1-       | 139–40–2 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| 1,3,5-Triazine-2,4-diamine, methylethyl)-<br>6-chloro-N-ethyl-N'-(1-    | 1912–24–9 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Urea, (hydroxymethyl)- .....  | 1000–82–4 ..... | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Urea, N'-(3,4-dichlorophenyl)-N,N-dimethyl- .....                       | 330–54–1 .....  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Urea, sulfate (1:1) .....   | 21351–39–3 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |
| Urea, sulfate (2:1) .....   | 17103–31–0 ...  | § 716.21(a)(7)     | September 29, 2006 | November 28, 2006 |

[53 FR 38645, Sept. 30, 1988]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 716.120, see the List of CFR Sections Affected, which appears in the Finding Aids section of the printed volume and on GPO Access.

EFFECTIVE DATE NOTE: At 59 FR 14115, Mar. 25, 1994, in § 716.120 paragraph (d), the chemical substances under the category “propylene glycol ethers and esters” and all related dates, were stayed effective March 25, 1994.

## PART 717—RECORDS AND REPORTS OF ALLEGATIONS THAT CHEMICAL SUBSTANCES CAUSE SIGNIFICANT ADVERSE REACTIONS TO HEALTH OR THE ENVIRONMENT

### Subpart A—General Provisions

Sec.

717.1 Scope and compliance.

717.3 Definitions.

717.5 Persons subject to this part.

717.7 Persons not subject to this part.

717.10 Allegations subject to this part.

717.12 Significant adverse reactions that must be recorded.

717.15 Recordkeeping requirements.

717.17 Inspection and reporting requirements.

717.19 Confidentiality.

AUTHORITY: 15 U.S.C. 2607(c).

SOURCE: 48 FR 38187, Aug. 22, 1983, unless otherwise noted.

### Subpart A—General Provisions

#### § 717.1 Scope and compliance.

Section 8 (c) of the Toxic Substances Control Act (TSCA) requires manufacturers, processors, and distributors of chemical substances and mixtures:

(a) To keep “records of significant adverse reactions to health or the environment, as determined by the Admin-

istrator by rule, alleged to have been caused by the substance or mixture.”

(b) To “permit inspection and submit copies of such records”, upon request of any designated representative of the Administrator. This rule implements section 8(c) of TSCA. It describes the records to be kept and prescribes the conditions under which certain firms must submit or make the records available to a duly designated representative of the Administrator.

#### § 717.3 Definitions.

The definitions set forth in section 3 of TSCA and the following definitions apply to this part:

(a) *Allegation* means a statement, made without formal proof or regard for evidence, that a chemical substance or mixture has caused a significant adverse reaction to health or the environment.

(b) *Firm* or *company* means any person, that is subject to this part, as defined in § 717.5.

(c)(1) *Known human effects* means a commonly recognized human health effect of a particular substance or mixture as described either in:

(i) Scientific articles or publications abstracted in standard reference sources.

(ii) The firm’s product labeling or material safety data sheets (MSDS).

## Environmental Protection Agency

## § 717.5

(2) However, an effect is not a “known human effect” if it:

(i) Was a significantly more severe toxic effect than previously described.

(ii) Was a manifestation of a toxic effect after a significantly shorter exposure period or lower exposure level than described.

(iii) Was a manifestation of a toxic effect by an exposure route different from that described.

(d) *Manufacture* or *process* means to manufacture or process for commercial purposes.

(e)(1) *Manufacture for commercial purposes* means to import, produce, or manufacture with the purpose of obtaining an immediate or eventual commercial advantage for the manufacturer, and includes, among other things, such “manufacture” of any amount of a chemical substance or mixture:

(i) For distribution in commerce, including for test marketing.

(ii) For use by the manufacturer, including use for product research and development, or as an intermediate.

(2) *Manufacture for commercial purposes* also applies to substances that are produced coincidentally during the manufacture, processing, use, or disposal of another substance or mixture, including both byproducts that are separated from that other substances or mixture and impurities that remain in that substance or mixture. Such byproducts and impurities may, or may not, in themselves have commercial value. They are nonetheless produced for the purpose of obtaining a commercial advantage since they are part of the manufacture of a chemical product for a commercial purpose.

(f) *Person* includes any individual, firm, company, corporation, joint venture, partnership, sole proprietorship, association, or any other business entity, any State or political subdivision thereof, and any department, agency, or instrumentally of the Federal Government.

(g) *Process for commercial purposes* means the preparation of a chemical substance or mixture, after its manufacture, for distribution in commerce with the purpose of obtaining an immediate or eventual commercial advantage for the processor. Processing of

any amount of a chemical substance or mixture is included. If a chemical substance or mixture containing impurities is processed for commercial purposes, then those impurities are also processed for commercial purposes.

(h) *Retailer* means a person who distributes in commerce a chemical substance, mixture, or article to ultimate purchasers who are not commercial entities.

(i) *Significant adverse reactions* are reactions that may indicate a substantial impairment of normal activities, or long-lasting or irreversible damage to health or the environment.

(j) *Site* means a contiguous property unit. Property divided only by a public right-of-way is considered one site. There may be multiple manufacturing, processing, or distribution activities occurring within a single site.

(k) *Substance* means a chemical substance or mixture unless otherwise indicated.

### § 717.5 Persons subject to this part.

(a) *Manufacturers.* (1) All manufacturers of chemical substances are subject to this part except as provided in § 717.7(a). If manufacture of a chemical substance occurs at any site owned or controlled by a firm then that firm is subject to this part.

(2) A manufacturer must collect:

(i) Any allegation identifying a chemical substance it manufactures and any allegation identifying the operations in the manufacture of any chemical substance it manufactures.

(ii) Any allegation identifying any of its own processing or distribution in commerce activities with respect to any chemical substance it manufactures.

(iii) Any allegation identifying emissions, effluents, or other discharges from activities described in this paragraph.

(iv) Any allegation identifying a substance produced coincidentally during processing, use, storage or disposal of a chemical substance it manufactures.

(3) For the purpose of this part, owned or controlled means ownership of 50 percent or more of a firm’s voting stock or other equity rights, or the power to control the management and policies of that firm.

(b) *Processors.* (1) A person who processes chemical substances, who is not also a manufacturer of those chemical substances, is subject to this part if (i) the person processes chemical substances to produce mixtures, or (ii) the person repackages chemical substances or mixtures.

(2) As a processor subject to this part such person must collect:

(i) Any allegation identifying any mixture it produces and distributes in commerce and any allegation identifying any chemical substance or mixture it repackages and distributes in commerce.

(ii) Any allegation identifying any of its own further processing or distribution in commerce activities of the products described in paragraph (b)(2)(i) of this section.

(iii) Any allegation identifying emissions, effluents, or other discharges from activities described in this paragraph.

(iv) Any allegation identifying a substance produced coincidentally during the processing, use, storage or disposal of the products described in paragraph (b)(2)(i) of this section.

(c) *SIC code.* SIC codes applicable to this part are published in Standard Industrial Classification Manual—1972 and the 1977 Supplement. This manual and supplement may be obtained from the U.S. Government Printing Office, Washington, D.C. 20402—stock number 4101-0006 and stock number 003-005-0170-0 respectively. Where there is a conflict between the SIC code use of a term and the definition of that term in this part, the definition in this part applies.

[48 FR 38187, Aug 22, 1983, as amended at 50 FR 46769, Nov. 13, 1985]

**§717.7 Persons not subject to this part.**

(a) *Manufacturers.* (1) Persons or site activities are exempt from this part if the means by which they manufacture a chemical substance solely involves mining or other solely extractive functions, e.g., those companies or sites within a company whose sole function is to mine mineral ores, extract petroleum or natural gas, quarry non-metallic minerals (including extraction of salts from seawater or brines), mine or

otherwise extract coal, or separate gases from the atmosphere. This exemption may include, but is not necessarily limited to, firms engaged in activities as described in SIC Division B—Mining and SIC Code 2813—Industrial Gases.

(2) A person is not subject to this part if the chemical substances that person causes to be produced are limited to:

(i) Chemical substances that result from chemical reactions that occur incidental to exposure of another chemical substance, mixture, or article to environmental factors such as air, moisture, microbial organisms, or sunlight.

(ii) Chemical substances that result from chemical reactions that occur incidental to storage or disposal of other chemical substances, mixtures, or articles.

(iii) Chemical substances that result from chemical reactions that occur upon end use of other chemical substances, mixtures, or articles such as adhesives, paints, miscellaneous cleaners or other housekeeping products, fuel additives, water softening and treatment agents, photographic films, batteries, matches, or safety flares, and that are not themselves manufactured or imported for distribution in commerce for use as chemical intermediates.

(iv) Chemical substances that result from chemical reactions that occur upon use of curable plastic or rubber molding compounds, inks, drying oils, metal finishing compounds, adhesives, or paints, or other chemical substance formed during the manufacture of an article destined for the marketplace without further chemical change of the chemical substance.

(v) Chemical substances that result from chemical reactions that occur when (A) a stabilizer, colorant, odorant, antioxidant, filler, solvent, carrier, surfactant, plasticizer, corrosion inhibitor, antifoamer or defoamer, dispersant, precipitation-inhibitor, binder, emulsifier, deemulsifier, dewatering agent, agglomerating agent, adhesion promoter, flow modifier, pH adjuster, sequestrant, coagulant, flocculant, fire retardant, lubricant, chelating agent, or quality control reagent functions as

## Environmental Protection Agency

## § 717.12

intended, or (B) a chemical substance, which is intended solely to impart a specific physicochemical characteristic, functions as intended.

(b) [Reserved]

(c) *Sole distributors.* A person solely engaged in the distribution of chemical substances is exempt from this part, unless such person is also a manufacturer or processor subject to this part. For example, a "distributor" who repackages chemical substances or mixtures is considered to be a processor and, thus, is not a sole distributor. Sole distributors may include, but are not limited to, those firms that distribute chemical substances as described in the wholesale trade SIC codes 5161—Chemicals and Allied Products, 5171—Petroleum Bulk Stations and Terminals, and 5172—Petroleum and Petroleum Products Wholesalers, Except Bulk Stations and Terminals.

(d) *Retailers.* A person who is a retailer is exempt from this part unless such person is also a manufacturer or a processor subject to this part.

[48 FR 38187, Aug 22, 1983, as amended at 50 FR 46770, Nov. 13, 1985]

### § 717.10 Allegations subject to this part.

(a) Allegations subject to this part are those allegations received on or after November 21, 1983 by persons subject to this part.

(b) Allegations subject to this part are those that:

(1) Are submitted either in writing and are signed by the alleger, or are submitted orally. In the case of an oral allegation, the firm must transcribe the allegation into written form, or it must inform the alleger that such allegation may be subject to this part and request that the alleger submit such allegation to the firm in writing and signed.

(2) Implicate a substance that caused the stated significant adverse reaction by one of the following:

(i) Naming the specific substance.

(ii) Naming a mixture that contains a specific substance.

(iii) Naming an article that contains a specific substance.

(iv) Naming a company process or operation in which substances are involved.

(v) Identifying an effluent, emission, or other discharge from a site of manufacturing, processing or distribution of a substance.

(c) Allegations subject to this part may be made to a firm by any person, such as an employee of the firm, individual consumer, a neighbor of the firm's plant, another firm on behalf of its employees or an organization on behalf of its members.

(d) EPA intends that firms should, to the maximum practical extent, provide allegers with information regarding the ultimate disposition of their allegations. For example, firms could provide a brief notice to the alleger stating that a record was created under this part based upon their allegation, or that a record was not created and briefly explain the reasons why not.

### § 717.12 Significant adverse reactions that must be recorded.

(a) Except as provided in paragraph (b) of this section, significant adverse reactions to human health that must be recorded include but are not limited to:

(1) Long-lasting or irreversible damage, such as cancer or birth defects.

(2) Partial or complete impairment of bodily functions, such as reproductive disorders, neurological disorders or blood disorders.

(3) An impairment of normal activities experienced by all or most of the persons exposed at one time.

(4) An impairment of normal activities which is experienced each time an individual is exposed.

(b) Firms are not required to record significant adverse reactions that are known human effects as defined in § 717.3(c).

(c) Except as provided in paragraph (d) of this section, significant adverse reactions to the environment that must be recorded, even if restricted to the environs of a plant or disposal site, include but are not limited to:

(1) Gradual or sudden changes in the composition of animal life or plant life, including fungal or microbial organisms, in an area.

(2) Abnormal number of deaths of organisms (e.g., fish kills).

(3) Reduction of the reproductive success or the vigor of a species.

## § 717.15

## 40 CFR Ch. I (7-1-10 Edition)

(4) Reduction in agricultural productivity, whether crops or livestock.

(5) Alterations in the behavior or distribution of a species.

(6) Long lasting or irreversible contamination of components of the physical environment, especially in the case of ground water, and surface water and soil resources that have limited self-cleansing capability.

(d) Firms are not required to record a significant adverse reaction to the environment if the alleged cause of that significant adverse reaction can be directly attributable to an accidental spill or other accidental discharge, emission exceeding permitted limits, or other incident of environmental contamination that has been reported to the Federal Government under any applicable authority.

[48 FR 38187, Aug. 22, 1983, as amended at 49 FR 23183, June 5, 1984; 58 FR 34204, June 23, 1993]

### § 717.15 Recordkeeping requirements.

(a) *Establishment and location of records.* A firm subject to this part shall establish and maintain records of significant adverse reactions alleged to have been caused by chemical substances or mixtures manufactured or processed by the firm. Such records shall be kept at the firm's headquarters or at any other appropriate location central to the firm's chemical operations.

(b) *Content of records.* The record shall consist of the following:

(1) The original allegation as received.

(2) An abstract of the allegation and other pertinent information as follows:

(i) The name and address of the plant site which received the allegation.

(ii) The date the allegation was received at that site.

(iii) The implicated substance, mixture, article, company process or operation, or site discharge.

(iv) A description of the alleege (e.g., "company employee," "individual consumer," "plant neighbor"). If the allegation involves a health effect, the sex and year of birth of the individual should be recorded, if ascertainable.

(v) A description of the alleged health effect(s). The description must relate how the effect(s) became known

and the route of exposure, if explained in the allegation.

(vi) A description of the nature of the alleged environmental effect(s), identifying the affected plant and/or animal species, or contaminated portion of the physical environment.

(3) The results of any self-initiated investigation with respect to an allegation. (EPA does not require persons subject to this part to investigate allegations received, and no provision of this part shall be construed to imply that EPA recommends, encourages or requires such investigation.)

(4) Copies of any further required records or reports relating to the allegation. For example, if an employee allegation results in a requirement for the firm to record the case on Occupational Safety and Health Form 101 or appropriate substitute (see 29 CFR part 1904 for requirements under the Occupational Safety and Health Act of 1970), a copy of that OSHA record must be included in the allegation record.

(c) *File structure.* Records must be retrievable by the alleged cause of the significant adverse reaction, which cause may be one of the following:

(1) A specific chemical identity.

(2) A mixture.

(3) An article.

(4) A company process or operation.

(5) A site emission, effluent or other discharge.

(d) *Retention period.* Records of significant adverse reactions to the health of employees shall be retained for a period of 30 years from the date such reactions were first reported to or known by the person maintaining such records. This provision requires persons subject to this part to retain for 30 years an employee health related allegation, arising from any employment related exposure, whether or not such allegation was submitted by or on the behalf of that recordkeeper's own employee. Any other record of significant adverse reactions shall be maintained for a period of five years from the date the information contained in the record was first reported to or known by the person maintaining the record.

(e) *Transfer of records.* (1) If a firm ceases to do business, the successor must receive and keep all the records that must be kept under this part.

(2) If a firm ceases to do business and there is no successor to receive and keep the records for the prescribed period, these records must be transmitted to EPA. See §717.17(c) for the address to which such records must be sent.

[48 FR 38187, Aug. 22, 1983, as amended at 49 FR 23183, June 5, 1984; 58 FR 34204, June 23, 1993]

#### §717.17 Inspection and reporting requirements.

(a) *Inspection.* Firms must make records of allegations available for inspection by any duly designated representative of the Administrator.

(b) *Reporting.* Each person who is required to keep records under this part must submit copies of those records to the Agency as required by the EPA Administrator or appropriate designee. EPA will notify those responsible for reporting by letter or will announce any such requirements for submitting copies of records by a notice in the FEDERAL REGISTER. Such letter or notice will be signed by the Administrator or appropriate designee, and will specify which records or portion of records must be submitted. The reporting period will be specified by the letter or notice but in no case will such reporting period be less than 45 days from the date of the letter or the effective date of the notice.

(c) *How to report.* When required to report, firms must submit copies of records (preferably by certified mail) to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: 8(c) Allegations.

[48 FR 38187, Aug. 22, 1983, as amended at 49 FR 23183, June 5, 1984; 52 FR 20084, May 29, 1987; 53 FR 12523, Apr. 15, 1988; 58 FR 34204, June 23, 1993; 60 FR 34464, July 3, 1995; 71 FR 33641, June 12, 2006]

#### §717.19 Confidentiality.

(a) Any person submitting copies of records may assert a business confidentiality claim covering all or part of the submitted information. Any information covered by a claim will be disclosed by EPA only as provided in procedures set forth at part 2 of this title.

(b) If no claim accompanies a document at the time it is submitted to EPA, the document will be placed in an open file available to the public without further notice to the respondent.

(c) To assert a claim of confidentiality for information contained in a submitted record, the respondent must submit two copies of the document.

(1) One copy must be complete. In that copy, the respondent must indicate what information, if any, is claimed as confidential by marking the specific information on each page with a label such as “confidential”, “proprietary”, or “trade secret” and briefly state the basis of the claim.

(2) If some information is claimed as confidential, the respondent must submit a second copy of the record. The second copy must be complete, except that all information claimed as confidential in the first copy must be deleted.

(3) The first copy will be for internal use by EPA. The second copy will be placed in an open file to be available to the public.

(4) Failure to furnish a second copy when information is claimed as confidential in the first copy will be considered a presumptive waiver of the claim of confidentiality. EPA will notify the respondent by certified mail that a finding of a presumptive waiver of the claim of confidentiality has been made. The respondent will be given 30 days from the date of receipt of notification to submit the required second copy. If the respondent fails to submit the second copy within the 30 days, EPA will place the first copy in the public file.

## PART 720—PREMANUFACTURE NOTIFICATION

### Subpart A—General Provisions

Sec.  
720.1 Scope.  
720.3 Definitions.

### Subpart B—Applicability

720.22 Persons who must report.  
720.25 Determining whether a chemical substance is on the Inventory.  
720.30 Chemicals not subject to notification requirements.



## § 720.1

- 720.36 Exemption for research and development.
- 720.38 Exemptions for test marketing.

### Subpart C—Notice Form

- 720.40 General.
- 720.45 Information that must be included in the notice form.
- 720.50 Submission of test data and other data concerning the health and environmental effects of a substance.
- 720.57 Imports.

### Subpart D—Disposition of Notices

- 720.60 General.
- 720.62 Notice that notification is not required.
- 720.65 Acknowledgement of receipt of a notice; errors in the notice; incomplete submissions; and false and misleading statements.
- 720.70 Notice in the FEDERAL REGISTER.
- 720.75 Notice review period.
- 720.78 Recordkeeping.

### Subpart E—Confidentiality and Public Access to Information

- 720.80 General provisions.
- 720.85 Chemical identity.
- 720.87 Categories or proposed categories of uses of a new chemical substance.
- 720.90 Data from health and safety studies.
- 720.95 Public file.

### Subpart F—Commencement of Manufacture or Import

- 720.102 Notice of commencement of manufacture or import.

### Subpart G—Compliance and Inspections

- 720.120 Compliance.
- 720.122 Inspections.

AUTHORITY: 15 U.S.C. 2604, 2607, and 2613.

SOURCE: 48 FR 21742, May 13, 1983, unless otherwise noted.

### Subpart A—General Provisions

#### § 720.1 Scope.

This part establishes procedures for the reporting of new chemical substances by manufacturers and importers under section 5 of the Toxic Substances Control Act, 15 U.S.C. 2604. This part applies to microorganisms only to the extent provided by part 725 of this chapter. The rule defines the persons and chemical substances subject to the reporting requirements, prescribes the contents of section 5 no-

## 40 CFR Ch. I (7–1–10 Edition)

tices, and establishes procedures for submitting notices. The rule also establishes EPA policy regarding claims of confidentiality for, and public disclosure of, various categories of information submitted in connection with section 5 notices.

[48 FR 21742, May 13, 1983, as amended at 58 FR 34204, June 23, 1993; 62 FR 17932, April 11, 1997]

#### § 720.3 Definitions.

(a)(1) For the purposes of this part, the terms *cosmetic*, *device*, *drug*, *food*, and *food additive* have the meanings contained in the Federal Food, Drug, and Cosmetic Act, 21 U.S.C. 321 *et seq.*, and the regulations issued under it. In addition, the term “food” includes poultry and poultry products, as defined in the Poultry Products Inspection Act, 21 U.S.C. 453 *et seq.*; meats and meat food products, as defined in the Federal Meat Inspection Act, 21 U.S.C. 60 *et seq.*; and eggs and egg products, as defined in the Egg Products Inspection Act, 21 U.S.C. 1033 *et seq.*

(2) The term *pesticide* has the meaning contained in the Federal Insecticide, Fungicide, and Rodenticide Act, 7 U.S.C. 136 *et seq.* and the regulations issued under it.

(3) The terms *byproduct material*, *source material*, and *special nuclear material* have the meanings contained in the Atomic Energy Act of 1954, 42 U.S.C. 2014 *et seq.* and the regulations issued under it.

(b) *Act* means the Toxic Substances Control Act, 15 U.S.C. 2601 *et seq.*

(c) *Article* means a manufactured item (1) which is formed to a specific shape or design during manufacture, (2) which has end use function(s) dependent in whole or in part upon its shape or design during end use, and (3) which has either no change of chemical composition during its end use or only those changes of composition which have no commercial purpose separate from that of the article and that may occur as described in § 720.36(g)(5), except that fluids and particles are not considered articles regardless of shape or design.

(d) *Byproduct* means a chemical substance produced without a separate

commercial intent during the manufacture, processing, use, or disposal of another chemical substance or mixture.

(e) *Chemical substance* means any organic or inorganic substance of a particular molecular identity, including any combination of such substances occurring in whole or in part as a result of a chemical reaction or occurring in nature, and any chemical element or uncombined radical, except that "chemical substance" does not include:

- (1) Any mixture.
- (2) Any pesticide when manufactured, processed, or distributed in commerce for use as a pesticide.
- (3) Tobacco or any tobacco product.
- (4) Any source material, special nuclear material, or byproduct material.
- (5) Any pistol, firearm, revolver, shells, or cartridges.

(6) Any food, food additive, drug, cosmetic, or device, when manufactured, processed, or distributed in commerce for use as a food, food additive, drug, cosmetic, or device.

(f) *Commerce* means trade, traffic, transportation, or other commerce (1) between a place in a State and any place outside of such State, or (2) which affects trade, traffic, transportation, or commerce between a place in a State and any place outside of such State.

(g) *Customs territory of the United States* means the 50 States, Puerto Rico, and the District of Columbia.

(h) *Director* means the Director of the EPA Office of Pollution Prevention and Toxics.

(i) *Distribute in commerce* means to sell in commerce, to introduce or deliver for introduction into commerce, or to hold after introduction into commerce.

(j) *EPA* means the U.S. Environmental Protection Agency.

(k) *Health and safety study* or *study* means any study of any effect of a chemical substance or mixture on health or the environment or on both, including underlying data and epidemiological studies, studies of occupational exposure to a chemical substance or mixture, toxicological, clinical, and ecological, or other studies of a chemical substance or mixture, and any test performed under the Act.

Chemical identity is always part of a health and safety study.

(1) Not only is information which arises as a result of a formal, disciplined study included, but other information relating to the effects of a chemical substance or mixture on health or the environment is also included. Any data that bear on the effects of a chemical substance on health or the environment would be included.

(2) Examples include:

(i) Long- and short-term tests of mutagenicity, carcinogenicity, or teratogenicity; data on behavioral disorders; dermatotoxicity; pharmacological effects; mammalian absorption, distribution, metabolism, and excretion; cumulative, additive, and synergistic effects; acute, subchronic, and chronic effects; and structure/activity analyses.

(ii) Tests for ecological or other environmental effects on invertebrates, fish, or other animals, and plants, including: Acute toxicity tests, chronic toxicity tests, critical life stage tests, behavioral tests, algal growth tests, seed germination tests, plant growth or damage tests, microbial function tests, bioconcentration or bioaccumulation tests, and model ecosystem (microcosm) studies.

(iii) Assessments of human and environmental exposure, including workplace exposure, and impacts of a particular chemical substance or mixture on the environment, including surveys, tests, and studies of: Biological, photochemical, and chemical degradation; air, water, and soil transport; biomagnification and bioconcentration; and chemical and physical properties, e.g., boiling point, vapor pressure, evaporation rates from soil and water, octanol/water partition coefficient, and water solubility.

(iv) Monitoring data, when they have been aggregated and analyzed to measure the exposure of humans or the environment to a chemical substance or mixture.

(v) Any assessments of risk to health and the environment resulting from the manufacture, processing, distribution in commerce, use, or disposal of the chemical substance.

### § 720.3

### 40 CFR Ch. I (7–1–10 Edition)

(1) *Importer* means any person who imports a chemical substance, including a chemical substance as part of a mixture or article, into the customs territory of the United States. “Importer” includes the person primarily liable for the payment of any duties on the merchandise or an authorized agent acting on his or her behalf. The term also includes, as appropriate:

(1) The consignee.

(2) The importer of record.

(3) The actual owner if an actual owner’s declaration and superseding bond has been filed in accordance with 19 CFR 141.20; or

(4) The transferee, if the right to draw merchandise in a bonded warehouse has been transferred in accordance with subpart C of 19 CFR part 144. (See “principal importer.”)

(m) *Impurity* means a chemical substance which is unintentionally present with another chemical substance.

(n) *Intermediate* means any chemical substance that is consumed, in whole or in part, in chemical reactions used for the intentional manufacture of another chemical substance(s) or mixture(s), or that is intentionally present for the purpose of altering the rates of such chemical reactions.

(o) *Inventory* means the list of chemical substances manufactured or processed in the United States that EPA compiled and keeps current under section 8(b) of the Act.

(p) *Known to or reasonably ascertainable by* means all information in a person’s possession or control, plus all information that a reasonable person similarly situated might be expected to possess, control, or know.

(q) *Manufacture* means to produce or manufacture in the United States or import into the customs territory of the United States.

(r) *Manufacture or import for commercial purposes* means:

(1) To import, produce, or manufacture with the purpose of obtaining an immediate or eventual commercial advantage for the manufacturer or importer, and includes, among other things, “manufacture” of any amount of a chemical substance or mixture:

(i) For commercial distribution, including for test marketing.

(ii) For use by the manufacturer, including use for product research and development or as an intermediate.

(2) The term also applies to substances that are produced coincidentally during the manufacture, processing, use, or disposal of another substance or mixture, including byproducts that are separated from that other substance or mixture and impurities that remain in that substance or mixture. Byproducts and impurities without separate commercial value are nonetheless produced for the purpose of obtaining a commercial advantage, since they are part of the manufacture of a chemical substance for commercial purposes.

(s) *Manufacture solely for export* means to manufacture or import for commercial purposes a chemical substance solely for export from the United States under the following restrictions on activities in the United States:

(1) Distribution in commerce is limited to purposes of export or processing solely for export as defined in § 721.3 of this chapter.

(2) The manufacturer or importer, and any person to whom the substance is distributed for purposes of export or processing solely for export (as defined in § 721.3 of this chapter), may not use the substance except in small quantities solely for research and development in accordance with § 720.36.

(t) *Manufacturer* means a person who imports, produces, or manufactures a chemical substance. A person who extracts a component chemical substance from a previously existing chemical substance or a complex combination of substances is a manufacturer of that component chemical substance. A person who contracts with a manufacturer to manufacture or produce a chemical substance is also a manufacturer if (1) the manufacturer manufactures or produces the substance exclusively for that person, and (2) that person specifies the identity of the substance and controls the total amount produced and the basic technology for the plant process.

(u) *Mixture* means any combination of two or more chemical substances if the combination does not occur in nature

## Environmental Protection Agency

## § 720.3

and is not, in whole or in part, the result of a chemical reaction; except "mixture" does include (1) any combination which occurs, in whole or in part, as a result of a chemical reaction if the combination could have been manufactured for commercial purposes without a chemical reaction at the time the chemical substances comprising the combination were combined, and if all of the chemical substances comprising the combination are not new chemical substances, and (2) hydrates of a chemical substance or hydrated ions formed by association of a chemical substance with water, so long as the nonhydrated form is itself not a new chemical substance.

(v) *New chemical substance* means any chemical substance which is not included on the Inventory.

(w) *Nonisolated intermediate* means any intermediate that is not intentionally removed from the equipment in which it is manufactured, including the reaction vessel in which it is manufactured, equipment which is ancillary to the reaction vessel, and any equipment through which the chemical substance passes during a continuous flow process, but not including tanks or other vessels in which the substance is stored after its manufacture.

(x) *Person* means any natural person, firm, company, corporation, joint-venture, partnership, sole proprietorship, association, or any other business entity, any State or political subdivision thereof, any municipality, any interstate body, and any department, agency or instrumentality of the Federal Government.

(y) *Possession or control* means in possession or control of the submitter, or of any subsidiary, partnership in which the submitter is a general partner, parent company, or any company or partnership which the parent company owns or controls, if the subsidiary, parent company, or other company or partnership is associated with the submitter in the research, development, test marketing, or commercial marketing of the chemical substance in question. (A parent company owns or controls another company if the parent owns or controls 50 percent or more of the other company's voting stock. A parent company owns or controls any

partnership in which it is a general partner). Information is included within this definition if it is:

(1) In files maintained by submitter's employees who are:

(i) Associated with research, development, test marketing, or commercial marketing of the chemical substance in question.

(ii) Reasonably likely to have such data.

(2) Maintained in the files of other agents of the submitter who are associated with research, development, test marketing, or commercial marketing of the chemical substance in question in the course of their employment as such agents.

(z) *Principal importer* means the first importer who, knowing that a new chemical substance will be imported rather than manufactured domestically, specifies the identity of the chemical substance and the total amount to be imported. Only persons who are incorporated, licensed, or doing business in the United States may be principal importers.

(aa) *Process* means the preparation of a chemical substance or mixture, after its manufacture, for distribution in commerce (1) in the same form or physical state as, or in a different form or physical state from, that in which it was received by the person so preparing such substance or mixture, or (2) as part of a mixture or article containing the chemical substance or mixture.

(bb) *Processor* means any person who processes a chemical substance or mixture.

(cc) *Small quantities solely for research and development* (or "small quantities solely for purposes of scientific experimentation or analysis or chemical research on, or analysis of, such substance or another substance, including such research or analysis for the development of a product") means quantities of a chemical substance manufactured, imported, or processed or proposed to be manufactured, imported, or processed solely for research and development that are not greater than reasonably necessary for such purposes.

(dd) *State* means any State of the United States and the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, the

## § 720.22

Canal Zone, American Samoa, the Northern Mariana Islands, and any other territory or possession of the United States.

(ee) *Technically qualified individual* means a person or persons (1) who, because of education, training, or experience, or a combination of these factors, is capable of understanding the health and environmental risks associated with the chemical substance which is used under his or her supervision, (2) who is responsible for enforcing appropriate methods of conducting scientific experimentation, analysis, or chemical research to minimize such risks, and (3) who is responsible for the safety assessments and clearances related to the procurement, storage, use, and disposal of the chemical substance as may be appropriate or required within the scope of conducting a research and development activity.

(ff) *Test data* means data from a formal or informal test or experiment, including information concerning the objectives, experimental methods and materials, protocols, results, data analyses, recorded observations, monitoring data, measurements, and conclusions from a test or experiment.

(gg) *Test marketing* means the distribution in commerce of no more than a predetermined amount of a chemical substance, mixture, or article containing that chemical substance or mixture, by a manufacturer or processor, to no more than a defined number of potential customers to explore market capability in a competitive situation during a predetermined testing period prior to the broader distribution of that chemical substance, mixture, or article in commerce.

(hh) *United States*, when used in the geographic sense, means all of the States.

(ii) *Central Data Exchange* or *CDX* means EPA's centralized electronic document receiving system, or its successors.

(jj) *e-PMN software* means electronic-PMN software created by EPA for use in preparing and submitting Premanufacture Notices (PMNs) and other TSCA section 5 notices and support documents electronically to the Agency.

## 40 CFR Ch. I (7–1–10 Edition)

(kk) *Optical disc* means compact disc (CD) or digital video disc (DVD).

(ll) *Support documents* means materials and information submitted to EPA in support of a TSCA section 5 notice, including but not limited to, correspondence, amendments, and test data. The term “support documents” does not include orders under TSCA section 5(e) (either consent orders or orders imposed pursuant to TSCA section 5(e)(2)(B)).

[48 FR 21742, May 13, 1983, as amended at 51 FR 15101, Apr. 22, 1986; 75 FR 784, Jan. 6, 2010]

### Subpart B—Applicability

#### § 720.22 Persons who must report.

(a)(1) Any person who intends to manufacture a new chemical substance in the United States for commercial purposes must submit a notice unless the substance is excluded under § 720.30.

(2) If a person contracts with a manufacturer to manufacture or produce a new chemical substance, and (i) the manufacturer manufactures or produces the substance exclusively for that person, and (ii) that person specifies the identity of the substance, and controls the total amount produced and the basic technology for the plant process, that person must submit the notice. If it is unclear who must report, EPA should be contacted to determine who must submit the notice.

(3) Only manufacturers that are incorporated, licensed, or doing business in the United States may submit a notice.

(b)(1) Any person who intends to import a new chemical substance into the United States for commercial purposes must submit a notice, unless the substance is excluded under § 720.30 or unless the substance is imported as part of an article.

(2) When several persons are involved in an import transaction, the notice must be submitted by the principal importer. If no one person fits the principal importer definition in a particular transaction, the importer should contact EPA to determine who must submit the notice for that transaction.

**§ 720.25 Determining whether a chemical substance is on the Inventory.**

(a) A new chemical substance is any chemical substance that is not currently listed on the Inventory.

(b)(1) A chemical substance is listed in the public portion of the Inventory by a specific chemical name (either a Chemical Abstracts (CA) Index Name or a CA Preferred Name) and a Chemical Abstracts Service (CAS) Registry Number if its identity is not confidential. If its identity is confidential, it is listed in the public portion of the Inventory by a TSCA Accession Number and a generic chemical name that masks the specific substance identity. The confidential substance is listed by its specific chemical name only in the confidential portion of the Inventory, which is not available to the public. A person who intends to manufacture or import a chemical substance not listed by specific chemical name in the public portion of the Inventory may ask EPA whether the substance is included in the confidential Inventory. EPA will answer such an inquiry only if EPA determines that the person has a *bona fide* intent to manufacture or import the chemical substance for commercial purposes.

(2) To establish a *bona fide* intent to manufacture or import a chemical substance, the person who proposes to manufacture or import the substance must submit to EPA:

(i) Except as provided in paragraphs (b)(3) (i) and (ii) of this section, the specific chemical identity of the substance that the person intends to manufacture or import, using the currently, correct CA name for the substance and the other correct chemical identity information in accordance with §§ 720.45(a) (1), (2), and (3).

(ii) A signed statement that the person intends to manufacture or import that chemical substance for commercial purposes.

(iii)(A) A brief description of the research and development activities conducted to date related to the substance, including the year in which the person first started to conduct research or development activity on the substance, and the general types of research and development activities conducted thus far (e.g., synthesis, sub-

stance isolation/purification, formulating, product development, process development, end-use application, toxicity testing, etc.). The person must also indicate whether any pilot plant or production-scale plant evaluations have been conducted involving the manufacture or processing of the substance.

(B) If an importer is unable to provide the information requested in paragraph (b)(2)(iii)(A) of this section from the foreign manufacturer or supplier, the following information shall be submitted:

(1) A brief statement indicating how long the substance has been in commercial use outside of the United States.

(2) The name of a country in which it has been commercially used.

(3) Whether the importer believes that the substance has already been used commercially, in any country, for the same purpose or application that the importer is intending.

(iv) A specific description of the major intended application or use of the substance.

(v) An infrared spectrum of the substance, or alternative spectra or other data which identify the substance if infrared analysis is not suitable for the substance or does not yield a reasonable amount of structural information. When using alternative spectra or instrumental analysis, the person must submit a spectrum or instrumental readout for the substance.

(vi) The estimated date (month/year) in which the person intends to submit a Premanufacture Notice (PMN) for this substance if EPA informs the notice submitter that the substance is not on the Inventory.

(vii) The address of the facility under the control of the submitter at which the manufacture or processing of the substance would most likely occur. For an imported substance, the facility under the control of the importer at which processing of the substance would likely occur, if any.

(viii)(A) For substances intended to be manufactured in the United States, a description of the most probable manufacturing process that would be used by the submitter to produce the

## § 720.25

## 40 CFR Ch. I (7-1-10 Edition)

substance for non-exempt commercial purposes.

(B) For substances intended to be imported, a brief description of how the submitter is most likely to process or use the substance for a commercial purpose. If the substance is not expected to be processed or used at any facility under the importer's control, a statement to this effect must be included along with a description of how the substance will be processed or used at sites controlled by others, if this information is known or reasonably ascertainable.

(3)(i) If an importer cannot provide the chemical identity information required by paragraph (b)(2) (i) and (v) of this section because it is claimed confidential by its foreign manufacturer or supplier, the foreign manufacturer or supplier must supply the required information directly to EPA in accordance with § 720.45(a) (1), (2), and (3) and reference the importer's notice. If the appropriate supporting document from the foreign party is not received within 30 days after EPA receives the importer's notice, the notice will be considered incomplete.

(ii) If a manufacturer cannot provide all of the required information in accordance with § 720.45(a) (1), (2), and (3) because the new chemical substance is manufactured using a reactant that has a specific chemical identity claimed as confidential by its supplier, the notice must contain chemical identity information that is as complete as known by the manufacturer. In addition, a letter of support for the notice must then be sent to EPA by the chemical supplier of the confidential reactant, providing the specific chemical identity of the proprietary reactant. The letter of support must reference the manufacturer's notice. If the appropriate supporting document from the supplier is not received within 30 days after EPA receives the manufacturer's notice, the notice will be considered incomplete.

(4) EPA will review the information submitted by the proposed manufacturer or importer under this paragraph to determine whether it has a *bona fide* intent to manufacture or import the chemical substance. If necessary, EPA will compare this information either to

the information requested for the confidential chemical substance under § 710.7(e)(2)(v) of this chapter or the information requested under § 720.85(b)(3)(iii).

(5) If the proposed manufacturer or importer has shown a *bona fide* intent to manufacture or import the substance, and provide sufficient unambiguous chemical identity information so EPA can make a conclusive determination of the chemical substance's Inventory status, EPA will search the confidential Inventory and inform the proposed manufacturer or importer whether the chemical substance is on the confidential Inventory.

(6) If the chemical substance is found on the confidential Inventory, EPA will notify the person(s) who originally reported the chemical substance that another person has demonstrated a *bona fide* intent to manufacture or import the substance and therefore was told that the chemical substance is on the Inventory.

(7) A disclosure of a confidential chemical identity to a person with a *bona fide* intent to manufacture or import the particular chemical substance will not be considered a public disclosure of confidential business information under section 14 of the Act.

(8) EPA will answer an inquiry on whether a particular chemical substance is on the confidential Inventory within 30 days after receipt of a complete submission under paragraph (b)(2) of this section.

(9) If the required chemical identity information has not been reported correctly or completely in the notice (except as provided under paragraph (b)(3)(ii) of this section) or if any other required data or information has been omitted or is incomplete, EPA will consider the whole notice to be incomplete. As soon as an incomplete notice is identified as such by EPA, the Agency will immediately return the notice directly to the submitter. The submitter must then resubmit the whole, completed *bona fide* notice to EPA in order to have the Agency perform the desired Inventory search and respond to the notice.

[48 FR 21742, May 13, 1983, as amended at 58 FR 34204, June 23, 1993; 60 FR 16309, Mar. 29, 1995]

**§ 720.30 Chemicals not subject to notification requirements.**

The following substances are not subject to the notification requirements of this part:

(a) Any substance which is not a "chemical substance" as defined in § 720.3(e).

(b) Any mixture as defined in § 720.3(u).<sup>1</sup>

(c) Any new chemical substance which will be manufactured or imported in small quantities solely for research and development under § 720.36.

(d) Any new chemical substance which will be manufactured or imported solely for test-marketing purposes under an exemption granted under § 720.38.

(e) Any new chemical substance manufactured solely for export if, when the substance is distributed in commerce:

(1) The substance is labeled in accordance with section 12(a)(1)(B) of the Act.

(2) The manufacturer knows that the person to whom the substance is being distributed intends to export it or process it solely for export as defined in § 721.3 of this chapter.

(f) Any new chemical substance which is manufactured or imported under the terms of a rule promulgated under section 5(h)(4) of the Act.

(g) Any byproduct if its only commercial purpose is for use by public or private organizations that (1) burn it as a fuel, (2) dispose of it as a waste, including in a landfill or for enriching soil, or (3) extract component chemical substances from it for commercial purposes. (This exclusion only applies to the byproduct; it does not apply to the component substances extracted from the byproduct.)

(h) The chemical substances described below: (Although they are manufactured for commercial purposes under the Act, they are not manufactured for distribution in commerce as chemical substances per se and have no commercial purpose separate from the

substance, mixture, or article of which they are a part.)

(1) Any impurity.

(2) Any byproduct which is not used for commercial purposes.

(3) Any chemical substance which results from a chemical reaction that occurs incidental to exposure of another chemical substance, mixture, or article to environmental factors such as air, moisture, microbial organisms, or sunlight.

(4) Any chemical substance which results from a chemical reaction that occurs incidental to storage or disposal of another chemical substance, mixture, or article.

(5) Any chemical substance which results from a chemical reaction that occurs upon end use of another chemical substance, mixture, or article such as an adhesive, paint, miscellaneous cleanser or other housekeeping product, fuel additive, water softening and treatment agent, photographic film, battery, match, or safety flare, and which is not itself manufactured or imported for distribution in commerce or for use as an intermediate.

(6) Any chemical substance which results from a chemical reaction that occurs upon use of curable plastic or rubber molding compounds, inks, drying oils, metal finishing compounds, adhesives, or paints, or any other chemical substance formed during the manufacture of an article destined for the marketplace without further chemical change of the chemical substance except for those chemical changes that occur as described elsewhere in this paragraph.

(7) Any chemical substance which results from a chemical reaction that occurs when (i) a stabilizer, colorant, odorant, antioxidant, filler, solvent, carrier, surfactant, plasticizer, corrosion inhibitor, antifoamer or defoamer, dispersant, precipitation inhibitor, binder, emulsifier, deemulsifier, dewatering agent, agglomerating agent, adhesion promoter, flow modifier, pH neutralizer, sequesterant, coagulant, flocculant, fire retardant, lubricant, chelating agent, or quality control reagent functions as intended, or (ii) a chemical substance, which is intended solely to impart a specific

<sup>1</sup>A new chemical substance that is manufactured or imported as part of a mixture is subject to the requirements of this part. This exclusion applies only to a mixture as a whole and not to any chemical substances which are part of the mixture.



physiochemical characteristic, functions as intended.

(8) Any nonisolated intermediate.

(i) Any chemical substance which is manufactured solely for non-commercial research and development purposes. Non-commercial research and development purposes include scientific experimentation, research, or analysis conducted by academic, government, or independent not-for-profit research organizations (e.g., universities, colleges, teaching hospitals, and research institutes), unless the activity is for eventual commercial purposes.

[48 FR 21742, May 13, 1983, as amended at 51 FR 15101, Apr. 22, 1986]

**§ 720.36 Exemption for research and development.**

(a) This part does not apply to a chemical substance if the following conditions are met:

(1) The chemical substance is manufactured or imported only in small quantities solely for research and development.

(2) The manufacturer or importer notifies all persons in its employ or to whom it directly distributes the chemical substance, who are engaged in experimentation, research, or analysis on the chemical substance, including the manufacture, processing, use, transport, storage, and disposal of the substance associated with research and development activities, of any risk to health, identified under paragraph (b) of this section, which may be associated with the substance. The notification must be made in accordance with paragraph (c) of this section.

(3) The chemical substance is used by, or directly under the supervision of, a technically qualified individual.

(b)(1) To determine whether notification under paragraph (a)(2) of this section is required, the manufacturer or importer must review and evaluate the following information to determine whether there is reason to believe there is any potential risk to health which may be associated with the chemical substance:

(i) Information in its possession or control concerning any significant adverse reaction by persons exposed to the chemical substance which may rea-

sonably be associated with such exposure.

(ii) Information provided to the manufacturer or importer by a supplier or any other person concerning a health risk believed to be associated with the substance.

(iii) Health and environmental effects data in its possession or control concerning the substance.

(iv) Information on health effects which accompanies any EPA rule or order issued under sections 4, 5, or 6 of the Act that applies to the substance and of which the manufacturer or importer has knowledge.

(2) When the research and development activity is conducted solely in a laboratory and exposure to the chemical substance is controlled through the implementation of prudent laboratory practices for handling chemical substances of unknown toxicity, and any distribution, except for purposes of disposal, is to other such laboratories for further research and development activity, the information specified in paragraph (b)(1) of this section need not be reviewed and evaluated. (For purposes of this paragraph, a laboratory is a contained research facility where relatively small quantities of chemical substances are used on a non-production basis, and where activities involve the use of containers for reactions, transfers, and other handling of substances designed to be easily manipulated by a single individual.)

(c)(1) The manufacturer or importer must notify the persons identified in paragraph (a)(2) of this section by means of a container labeling system, conspicuous placement of notices in areas where exposure may occur, written notification to each person potentially exposed, or any other method of notification which adequately informs persons of health risks which the manufacturer or importer has reason to believe may be associated with the substance, as determined under paragraph (b)(1) of this section.

(2) If the manufacturer or importer distributes a chemical substance manufactured or imported under this section to persons not in its employ, the manufacturer or importer must in written form:

## Environmental Protection Agency

## § 720.38

(i) Notify those persons that the substance is to be used only for research and development purposes.

(ii) Provide the notice of health risks specified in paragraph (c)(1) of this section.

(3) The adequacy of any notification under this section is the responsibility of the manufacturer or importer.

(d) A chemical substance is not exempt from reporting under this part if any amount of the substance, including as part of a mixture, is processed, distributed in commerce, or used, for any commercial purpose other than research and development, except where the chemical substance is processed, distributed in commerce, or used only as an impurity or as part of an article.

(e) Quantities of the chemical substance, or of mixtures or articles containing the chemical substance, remaining after completion of research and development activities may be:

(1) Disposed of as a waste in accordance with applicable Federal, state, and local regulations, or

(2) Used for the following commercial purposes:

(i) Burning it as a fuel.

(ii) Reacting or otherwise processing it to form other chemical substances for commercial purposes, including extracting component chemical substances.

(f) Quantities of research and development substances existing solely as impurities in a product or incorporated into an article, in accordance with paragraph (d) of this section, and quantities of research and development substances used solely for commercial purposes listed in paragraph (e) of this section, are not subject to the requirements of paragraphs (a), (b), and (c) of this section, once research and development activities have been completed.

(g) A person who manufactures or imports a chemical substance in small quantities solely for research and development is not required to comply with the requirements of this section if the person's exclusive intention is to perform research and development activities solely for the purpose of determining whether the substance can be used as a pesticide.

[51 FR 15102, Apr. 22, 1986]

### § 720.38 Exemptions for test marketing.

(a) Any person may apply for an exemption to manufacture or import a new chemical substance for test marketing. EPA may grant the exemption if the person demonstrates that the chemical substance will not present an unreasonable risk to injury to health or the environment as a result of the test marketing.

(b) Persons applying for a test-marketing exemption should provide the following information:

(1) All existing data regarding health and environmental effects of the chemical substance, including physical/chemical properties or, in the absence of such data, a discussion of toxicity based on structure-activity relationships (SAR) and relevant data on chemical analogues.

(2) The maximum quantity of the chemical substance which the applicant will manufacture or import for test marketing.

(3) The maximum number of persons who may be provided the chemical substance during test marketing.

(4) The maximum number of persons who may be exposed to the chemical substance as a result of test marketing, including information regarding duration and route of such exposures.

(5) A description of the test-marketing activity, including its length and how it can be distinguished from full-scale commercial production and research and development.

(c) In accordance with section 5(h)(6) of the Act, after EPA receives an application for exemption under this section, the Agency will file with the Office of the Federal Register a notice containing a summary of the information provided in the application, to the extent it has not been claimed confidential.

(d) No later than 45 days after EPA receives an application, the Agency will either approve or deny the application. Thereafter, EPA will publish a notice in the FEDERAL REGISTER explaining the reasons for approval or denial.

(e) In approving an application for exemption, EPA may impose any restrictions necessary to ensure that the

## § 720.40

substance will not present an unreasonable risk of injury to health and the environment as a result of test marketing.

[48 FR 21742, May 13, 1983, as amended at 58 FR 34204, June 23, 1993]

### Subpart C—Notice Form

#### § 720.40 General.

(a) *Use of the notice form; electronic submissions.* (1) Each person who is required by subpart B of this part to submit a notice must complete, sign, and submit a notice containing the information in the form and manner specified in this paragraph. The information submitted and all attachments (unless the attachment appears in the open scientific literature) must be in English. All information submitted must be true and correct.

(2) All notices must be submitted on EPA Form 7710-25. Notices, and any support documents related to these notices, may only be submitted in a manner set forth in this paragraph.

(i) *Paper-based submissions.* Notices, and any support documents related to these notices, may be submitted on paper on or before April 6, 2011. All paper-based notices must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print EPA Form 7710-25 for submission to EPA. Paper notices, and any support documents related to such notices, must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(A) Support documents for notices that are submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Envi-

## 40 CFR Ch. I (7-1-10 Edition)

ronmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(B) [Reserved]

(ii) *Submissions on optical disc*—(A) Notices may be submitted as electronic files on optical disc on or before April 6, 2012. All notices submitted as electronic files on optical disc must be generated using e-PMN reporting software and be completed through the finalization step of the software. Optical discs containing electronic notices must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(B) Persons submitting on optical disc must also complete and submit on paper the Certification and Submitter Identification sections of EPA Form 7710-25.

(iii) *Submissions via CDX.* Notices and any related support documents may be submitted electronically to EPA via CDX. Prior to submission to EPA via CDX, such notices must be generated and completed on EPA Form 7710-25 using e-PMN reporting software. To obtain a version of e-PMN software that contains an encryption module you must register with CDX. A version without encryption may be downloaded without registering with CDX.

(iv) You can obtain the e-PMN software as follows:

(A) *Website.* Go to EPA's TSCA New Chemicals Program website at <http://www.epa.gov/oppt/newchems> and follow the appropriate links.

(B) *Telephone.* Call the EPA CDX Help Desk at 1-888-890-1995.

(C) *E-mail.* [HelpDesk@epacdx.net](mailto:HelpDesk@epacdx.net).

(b) *When to submit a notice.* Each person who is required to submit a notice must submit the notice at least 90 calendar days before manufacture or import of the new chemical substance for commercial purposes begins.

(c) *Where to submit a notice or support documents.* For submitting notices or support documents via CDX, use the e-PMN software. Paper notices or support documents must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of

## Environmental Protection Agency

## § 720.40

Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004. Optical discs containing electronic notices or support documents must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004. Persons submitting on optical disc must also complete and submit on paper the Certification and Submitter Identification sections of EPA Form 7710-25.

(d) *General notice requirements.* (1) Each person who submits a notice must provide the information described in § 720.45 and specified on the notice form, to the extent such information is known to or reasonably ascertainable by the person. In accordance with § 720.50, the notice must also include any test data in the person's possession or control, and descriptions of other data which are known to or reasonably ascertainable by the person and which concern the health and environmental effects of the new chemical substance.

(2) If information is claimed as confidential pursuant to § 720.80, a person who submits a notice to EPA in the manner set forth in § 720.40(a)(2)(i), (ii), or (iii) must also provide EPA with a sanitized copy.

(e) *Agency or joint submissions*—(1) A manufacturer or importer may designate an agent to assist in submitting the notice. If so, only the manufacturer or importer, and not the agent, signs the certification on the form.

(2) A manufacturer or importer may authorize another person, (e.g., a supplier or a toll manufacturer) to report some of the information required in the notice to EPA on its behalf. The manufacturer or importer should indicate in a cover letter accompanying the notice which information will be supplied by another person and must identify that other person as a joint submitter where indicated on their notice form. The other person supplying information (i.e., the joint submitter) may submit

the information to EPA using either the notice form or a Letter of Support, except that if the joint submitter is not incorporated, licensed, or doing business in the United States, the joint submitter must submit the information to EPA in a Letter of Support only, not in a notice form. The joint submitter must indicate in the notice or Letter of Support the identity of the manufacturer or importer. Any person who submits a notice form or Letter of Support for a joint submission must sign and certify the notice form or Letter of Support.

(3) Only the Authorized Official (AO) of a company can submit all TSCA section 5 documents.

(i) The AO can authorize other persons to submit only support documents on their behalf.

(ii) To authorize a support registrant to submit support documents, both the AO and support registrant must sign the "Authorization and Verification for Section 5 Notice Support Submitter by Company Authorizing Official" available from the CDX website at [http://cdx.epa.gov/epa\\_home.asp](http://cdx.epa.gov/epa_home.asp).

(f) *New information.* During the notice review period, if the submitter possesses, controls, or knows of new information that materially adds to, changes, or otherwise makes significantly more complete the information included in the notice, the submitter must that information to the address listed on the notice form within ten days of receiving the new information, but no later than five days before the end of the notice review period. The new submission must clearly identify the submitter and the notice to which the new information is related. If the new information becomes available during the last five days of the notice review period, the submitter must immediately inform its EPA contract for that notice by telephone.

(g) *Chemical substances subject to a section 4 test rule.* (1) Except as provided in paragraph (g)(3) of this section, if (i) A person intends to manufacture or import a new chemical substance which is subject to the notification requirements of this part, and (ii) The chemical substance is subject to a test rule promulgated under section 4 of the Act before the notice is submitted, section

## § 720.45

5(b)(1) of the Act requires the person to submit the test data required by the testing rule with the notice. The person must submit the data in the form and manner specified in the test rule and in accordance with § 720.50. If the person does not submit the test data, the submission is incomplete and EPA will follow the procedures in § 720.65.

(2) If EPA has granted the submitter an exemption under section 4(c) of the Act from the requirement to conduct tests and submit data, the submitter may not submit a notice until EPA receives the test data.

(3) If EPA has granted the submitter an exemption under section 4(c) of the Act and if another person previously has submitted the test data to EPA, the exempted person may either submit the test data or provide the following information as part of the notice:

(i) The name, title, and address of the person who submitted the test data to EPA.

(ii) The date the test data were submitted to EPA.

(iii) A citation for the test rule.

(iv) A description of the exemption and a reference identifying it.

(h) *Chemical substances subject to a section 5(b)(4) rule.* (1) If a person (i) intends to manufacture or import a new chemical substance which is subject to the notification requirements of this part and which is subject to a rule issued under section 5(b)(4) of the Act; and (ii) is not required by a rule issued under section 4 of the Act to submit test data for the substance before the submission of a notice, the person must submit to EPA data described in paragraph (h)(2) of this section at the time the notice is submitted.

(2) Data submitted under paragraph (h)(1) of this section must be data which the person submitting the notice believes show that the manufacture, processing, distribution in commerce, use and disposal of the substance, or any combination of such activities, will not present an unreasonable risk of injury to health or the environment.

[48 FR 21742, May 13, 1983, as amended at 58 FR 34204, June 23, 1993; 60 FR 16309, Mar. 29, 1995; 75 FR 784, Jan. 6, 2010]

## 40 CFR Ch. I (7–1–10 Edition)

### § 720.45 Information that must be included in the notice form.

Each person who submits a notice must include the information specified in the notice form to the extent it is known to or reasonably ascertainable by the submitter. However, no person is required to include information which relates solely to exposure of human or ecological populations outside of the United States. The notice form requires the following information relating to the manufacture, processing, distribution in commerce, use, and disposal of the new chemical substance:

(a)(1) The specific chemical identity of the substance that the person intends to manufacture or import, which includes the following:

(i) The currently correct Chemical Abstracts (CA) name for the substance, based on the Ninth Collective Index (9CI) of CA nomenclature rules and conventions, and consistent with listings for similar substances in the Inventory. For each substance having a chemical composition that can be represented by a specific, complete chemical structure diagram (a Class 1 substance), a CA Index Name must be provided. For each chemical substance that cannot be fully represented by a complete, specific chemical structure diagram (a Class 2 substance), or if the substance is a polymer, a CA Index Name or CA Preferred Name must be provided (whichever is appropriate based on CA 9CI nomenclature rules and conventions). In addition, for a Class 2 substance, the notice must identify the immediate chemical precursors and reactants by specific chemical name and Chemical Abstracts Service Registry Number (CASRN), if the number is available. Tradenames or generic names of chemical precursors or reactants are not acceptable as substitutes for specific chemical names.

(ii) The currently correct CASRN for the substance if a CASRN already exists for the substance.

(iii) For a Class 1 substance and for any Class 2 substance for which a definite molecular formula is known or reasonably ascertainable, the correct molecular formula.

## Environmental Protection Agency

## § 720.45

(iv) For a Class 1 substance, a complete, correct chemical structure diagram; for a Class 2 substance or polymer, a correct representative or partial chemical structure diagram, as complete as can be known, if one can be reasonably ascertained.

(2) For a polymer, the submitter must also report the following:

(i) The specific chemical name and CASRN, if the number is available, of each monomer and other reactant used, at any weight percent, to manufacture the polymer. Tradenames or generic names of chemical reactants or monomers are not acceptable as substitutes for specific chemical names.

(ii) The typical percent by weight of each monomer and other reactant in the polymer (weight of the monomer or other reactant expressed as a percentage of the weight of the polymeric chemical substance manufactured), and the maximum residual amount of each monomer present in the polymer.

(iii) For monomers and other reactants used at 2 weight percent or less (based on the dry weight of the polymer manufactured), indicate on the PMN form any such monomers and other reactants that should be included as part of the polymer description on the Inventory, where the weight percent is based on either (A) the weight of monomer or other reactant actually charged to the reaction vessel, or (B) the minimum weight of monomer or other reactant required in theory to account for the actual weight of monomer or other reactant molecules or fragments chemically incorporated (chemically combined) in the polymeric substance manufactured.

(iv) For a determination that 2 weight percent or less of a monomer or other reactant is incorporated (chemically combined) in a polymeric substance manufactured, as specified in paragraphs (a)(2)(iii)(B) of this section, analytical data or appropriate theoretical calculations (if it can be documented that analytical measurement is not feasible or not necessary) to support this determination must be maintained at the site of manufacture or import of the polymer.

(v) Measured or estimated values of the minimum number-average molecular weight of the polymer and the

amount of low molecular weight species below 500 and below 1,000 molecular weight, with a description of how the measured or estimated values were obtained.

(3) The person must use one of the following two methods to develop or obtain the specified chemical identity information reported under paragraphs (a) (1) and (2) of this section and must identify the method used in the notice:

(i) *Method 1.* Obtain the correct chemical identity information required by paragraphs (a) (1) and (2) of this section directly from the Chemical Abstracts Service (CAS), specifically from the CAS Registry Services Inventory Expert Service, prior to submitting a notice to EPA. A copy of the chemical identification report obtained from CAS must be submitted with the notice.

(ii) *Method 2.* Obtain the correct chemical identity information required by paragraphs (a) (1) and (2) from any source. The notice will be incomplete according to §720.65(c)(1)(vi) if the person uses Method 2 and any chemical identity information is determined to be incorrect by EPA.

(4) If an importer submitting the notice cannot provide all the information specified in paragraphs (a) (1) and (2) of this section because it is claimed as confidential by the foreign supplier of the substance, the importer must have the foreign supplier follow the procedures in paragraph (a)(3) of this section and provide the correct chemical identity information specified in paragraphs (a) (1) and (2) of this section directly to EPA in a joint submission or as a letter of support to the notice, which clearly references the importer's notice and PMN User Fee Identification Number. The statutory review process will commence upon receipt of both the notice and the complete, correct information.

(5) If a manufacturer cannot provide all the information specified in paragraphs (a) (1) and (2) of this section because the new chemical substance is manufactured using a reactant having a specific chemical identity claimed as confidential by its supplier, the manufacturer must submit a notice directly to EPA containing all the information known by the manufacturer about the

## § 720.50

## 40 CFR Ch. I (7–1–10 Edition)

chemical identity of the reported substance and its proprietary reactant. In addition, the manufacturer must ensure that the supplier of the confidential reactant submit a letter of support directly to EPA providing the specific chemical identity of the confidential reactant, including the CAS number, if available, and the appropriate PMN or exemption number, if applicable. The letter of support must reference the manufacturer's name and PMN User Fee Identification Number under § 700.45(c)(3) of this chapter. The statutory review period will commence upon receipt of both the notice and the letter of support.

(b) The impurities anticipated to be present in the substance by name, CAS Registry number, and weight percent of the total substance.

(c) Known synonyms or trade names of the new chemical substance.

(d) A description of the byproducts resulting from the manufacture, processing, use, and disposal of the new chemical substance.

(e) The estimated maximum amount to be manufactured or imported during the first year of production and the estimated maximum amount to be manufactured or imported during any 12-month period during the first three years of production.

(f) A description of intended categories of use by function and application, the estimated percent of production volume devoted to each category of use, and the percent of the new substance in the formulation for each commercial or consumer use.

(g) For sites controlled by the submitter:

(1) The identity of sites where the new substance will be manufactured, processed, or used.

(2) A process description of each manufacture, processing, and use operation which includes a diagram of the major unit operations and chemical conversions, the identity and entry point of all feedstocks, and the points of release of the new chemical substance.

(3) Worker exposure information, including worker activities, physical form of the new substance to which workers may be exposed, the number of workers, and the duration of activities.

(4) Information on release of the new substance to the environment, including the quantity and media of release and type of control technology used.

(h) For sites not controlled by the submitter, a description of each type of processing and use operation involving the new chemical substance, including identification of the estimated number of processing or use sites, situations in which worker exposure to and/or environmental release of the new chemical substance will occur, the number of workers exposed and the duration of exposure, and controls which limit worker exposure and environmental release.

[48 FR 21742, May 13, 1983, as amended at 60 FR 16310, Mar. 29, 1995]

### **§ 720.50 Submission of test data and other data concerning the health and environmental effects of a substance.**

(a) *Test data on the new chemical substance in the possession or control of the submitter.* (1) Except as provided in paragraph (d) of this section, each notice must contain all test data in the submitter's possession or control which are related to the effects on health or the environment of any manufacture, processing, distribution in commerce, use, or disposal of the new chemical substance or any mixture or article containing the new chemical substance, or any combination of such activities. This includes test data concerning the new chemical substance in a pure, technical grade, or formulated form.

(2) A full report or standard literature citation must be submitted for the following types of test data:

- (i) Health effects data.
- (ii) Ecological effects data.
- (iii) Physical and chemical properties data.
- (iv) Environmental fate characteristics.
- (v) Monitoring data and other test data related to human exposure to or environmental release of the chemical substance.

(3)(i) If the data do not appear in the open scientific literature, the submitter must provide a full report. A full report includes the experimental

## Environmental Protection Agency

## § 720.50

methods and materials, results, discussion and data analysis, conclusions, references, and the name and address of the laboratory that developed the data.

(ii) If the data appear in the open scientific literature, the submitter need only provide a standard literature citation. A standard literature citation includes author, title, periodical name, date of publication, volume, and page numbers.

(4)(i) If a study, report, or test is incomplete when a person submits a notice, the submitter must identify the nature and purpose of the study; name and address of the laboratory developing the data; progress to date; types of data collected; significant preliminary results; and anticipated completion date.

(ii) If a test or experiment is completed before the notice review period ends, the person must submit the study, report, or test to the address listed on the notice form, as specified in paragraph (a)(3)(i) of this section, within ten days of receiving it, but no later than five days before the end of the review period. If the test or experiment is completed during the last five days of the review period, the submitter must immediately inform its EPA contact for that notice by telephone.

(5) For test data in the submitter's possession or control which are not listed in paragraph (a)(2) of this section, a person is not required to submit a complete report. The person must submit a summary of the data. If EPA so requests, the person must submit a full report within ten days of the request, but no later than five days before the end of the review period.

(6) All test data described by paragraph (a) are subject to these requirements, regardless of their age, quality, or results.

(b) *Other data concerning the health and environmental effects of the new chemical substance that are known to or reasonably ascertainable by the submitter.*

(1) Except as provided in paragraph (d) of this section, any person who submits a notice must describe the following data, including any data from a health and safety study, if the data are related to the effects on health or the environment of any manufacture, proc-

essing, distribution in commerce, use, or disposal of the new chemical substance, of any mixture or article containing the new chemical substance, or of any combination of such activities:

(i) Any data, other than test data, in the submitter's possession or control.

(ii) Any data, including test data, which are not in the submitter's possession or control, but which are known to or reasonably ascertainable by the submitter. For the purposes of this section, data are known to or reasonably ascertainable by the submitter if the data are known to any of its employees or other agents who are associated with the research and development, test marketing, or commercial marketing of the substance.

(2) Data that must be described include data concerning the new chemical substance in a pure, technical grade, or formulated form.

(3) The description of data reported under this paragraph must include:

(i) If the data appear in the open scientific literature, a standard literature citation, which includes the author, title, periodical name, date of publication, volume, and pages.

(ii) If the data are not contained in the open scientific literature, a description of the type of data and summary of the results, if available, and the names and addresses of persons the submitter believes may have possession or control of the data.

(4) All data described by this paragraph are subject to these requirements, regardless of their age, quality, or results; and regardless of whether they are complete at the time the notice is submitted.

(c) [Reserved]

(d) *Data that need not be submitted*—(1) *Data previously submitted to EPA.* (i) A person need not submit any data previously submitted to EPA with no claims of confidentiality if the notice includes the office or person to whom the data were submitted, the date of submission, and, if appropriate, a standard literature citation as specified in paragraph (a)(3)(ii) of this section.

(ii) For data previously submitted to EPA with a claim of confidentiality, the person must resubmit the data



## § 720.57

with the notice and any claim of confidentiality, under § 720.80.

(2) *Efficacy data.* This part does not require submission of any data related solely to product efficacy. This does not exempt a person from submitting any of the data specified in paragraph (a), (b), or (c) of this section.

(3) *Non-U.S. exposure data.* This part does not require submission of any data which relates only to exposure of humans or the environment outside the United States. This does not exclude nonexposure data such as data on health effects (including epidemiological studies), ecological effects, physical and chemical properties, or environmental fate characteristics.

[48 FR 21742, May 13, 1983, as amended at 51 FR 15102, Apr. 22, 1986]

## § 720.57 Imports.

(a) Except as otherwise provided in this section, the provisions of this subpart C apply to each person who submits a notice for a new chemical substance which he or she intends to import for a commercial purpose. In addition, each importer must comply with this section.

(b) EPA will hold the principal importer, or the importer that EPA determines must submit the notice when there is no principal importer under § 720.22(b)(2), liable for complying with this part, for completing the notice form and for the completeness and truthfulness of all information which it submits.

## Subpart D—Disposition of Notices

### § 720.60 General.

This subpart establishes procedures that EPA will follow in reviewing notices.

### § 720.62 Notice that notification is not required.

When EPA receives a notice, EPA will review it to determine whether the chemical substance is subject to the requirements of this part. If EPA determines that the chemical substance is not subject to these requirements, EPA will notify the submitter that section 5 of the Act does not prevent the manufacture or import of the substance and

## 40 CFR Ch. I (7–1–10 Edition)

that the submission is not a notice under this part.

[48 FR 21742, May 13, 1983, as amended at 58 FR 34204, June 23, 1993]

### § 720.65 Acknowledgement of receipt of a notice; errors in the notice; incomplete submissions; and false and misleading statements.

(a) *Notification to the submitter.* EPA will acknowledge receipt of each notice by sending a letter via CDX or U.S. mail to the submitter that identifies the premanufacture notice number assigned to the new chemical substance and date on which the review period begins. The review period will begin on the date the notice is received by the Office of Pollution Prevention and Toxics Document Control Officer. The acknowledgment does not constitute a finding by EPA that the notice, as submitted, is in compliance with this part.

(b) *Errors in the notice.* (1) Within 30 days of receipt of the notice, EPA may request that the submitter remedy errors in the notice. The following are examples of such errors:

(i) Failure to date the notice form.

(ii) Typographical errors that cause data to be misleading or answers to any questions to be unclear.

(iii) Contradictory information.

(iv) Ambiguous statements or information.

(2) In the request to correct the notice, EPA will explain the action which the submitter must take to correct the notice.

(3) If the submitter fails to correct the notice within 15 days of receipt of the request, EPA may extend the notice period under section (5)(c) of the Act, in accordance with § 720.75(c).

(c) *Incomplete submissions.* (1) A submission is not complete, and the notification period does not begin, if:

(i) The wrong person submits the notice form.

(ii) The submitter does not sign the notice form.

(iii) Some or all of the information in the notice or the attachments are not in English, except for published scientific literature.

(iv) The submitter does not submit the notice in the manner set forth in § 720.40(a)(2).

## Environmental Protection Agency

## § 720.70

(v) The submitter does not provide information that is required by section 5(d)(1) (B) and (C) of the Act and § 720.50.

(vi) The submitter does not provide information required on the notice form and by § 720.45 or indicate that it is not known to or reasonably ascertainable by the submitter.

(vii) The submitter does not submit a second copy of the submission with all confidential information deleted for the public file, as required by § 720.80(b)(2).

(viii) The submitter does not include any information required by section 5(b)(1) of the Act and pursuant to a rule promulgated under section 4 of the Act, as required by § 720.40(g).

(ix) The submitter does not submit data which the submitter believes show that the chemical substance will not present an unreasonable risk of injury to health or the environment, if EPA has listed the chemical substance under section 5(b)(4) of the Act, as required in § 720.40(h).

(x) The submitter does not include an identifying number and a payment identity number as required by 40 CFR 700.45(e)(3).

(2)(i) If EPA receives an incomplete submission, the Director, or his or her delegate, will notify the submitter within 30 days of receipt that the submission is incomplete and that the notice review period will not begin until EPA receives a complete notice.

(ii) If EPA obtains additional information during the notice review period that indicates the original submission was incomplete, the Director, or his or her delegate, may declare the submission incomplete within 30 days after EPA obtains the additional information and so notify the submitter.

(3) The notification that a submission is incomplete under paragraph (c)(2) (i) or (ii) of this section will include:

(i) A statement of the basis of EPA's determination that the submission is incomplete.

(ii) The requirements for correcting the incomplete submission.

(iii) Information on procedures under paragraph (c)(4) of this section for filing objections to the determination or

requesting modification of the requirements for completing the submission.

(4) Within ten days after receipt of notification by EPA that a submission is incomplete, the submitter may file written objections requesting that EPA accept the submission as a complete notice or modify the requirements necessary to complete the submission.

(5)(i) EPA will consider the objections filed by the submitter. The Director, or his or her delegate, will determine whether the submission was complete or incomplete, or whether to modify the requirements for completing the submission. EPA will notify the submitter in writing of EPA's response within ten days of receiving the objections.

(ii) If the Director, or his or her delegate, determines, in response to the objection, that the submission was complete, the notice review period will be deemed suspended on the date EPA declared the notice incomplete, and will resume on the date that the notice is declared complete. The submitter need not correct the notice as EPA originally requested. If EPA can complete its review within 90 days from the date of the original submission, the Director, or his or her delegate, may inform the submitter that the running of the review period will resume on the date EPA originally declared it incomplete.

(iii) If the Director, or his or her delegate, modifies the requirements for completing the submission or concurs with EPA's original determination, the notice review period will begin when EPA receives a complete notice.

(d) *Materially false or misleading statements.* If EPA discovers at any time that person submitted materially false or misleading statements in the notice, EPA may find that the notice was incomplete from the date it was submitted, and take any other appropriate action.

[48 FR 21742, May 13, 1983, as amended at 75 FR 785, Jan. 6, 2010]

### § 720.70 Notice in the Federal Register.

(a) *Filing of FEDERAL REGISTER notice.* In accordance with section 5(d)(2) of the Act, after EPA receives a notice, EPA will file with the Office of the Federal Register a notice including the

## § 720.75

## 40 CFR Ch. I (7–1–10 Edition)

information specified in paragraph (b) of this section.

(b) *Contents of notice.* (1) In the public interest, the specific chemical identity listed in the notice will be published in the FEDERAL REGISTER unless the submitter has claimed chemical identity confidentiality. If the submitter claims confidentiality, a generic name will be published in accordance with § 720.85(a)(3).

(2) The categories of use of the new chemical substance will be published as reported in the notice unless this information is claimed confidential. If confidentiality is claimed, the generic information which is submitted under § 720.87(b) will be published.

(3) A list of data submitted in accordance with § 720.50(a) will be published. In addition, for test data submitted in accordance with § 720.40(g), a summary of the data will be published.

(4) The submitter's identity will be published, unless the submitter has claimed it confidential.

### § 720.75 Notice review period.

(a) *Length of notice review period.* The notice review period specified in section 5(a) of the Act runs for 90 days from the date the Document Control Officer for the Office of Pollution Prevention and Toxics receives a complete notice, or the date EPA determines the notice is complete under § 720.65(c), unless the Agency extends the period under section 5(c) of TSCA and paragraph (c) of this section.

(b) *Suspension of the running of the notice review period.* (1) A submitter may voluntarily suspend the running of the notice review period if the Director or his or her delegate agrees. If the Director does not agree, the review period will continue to run, and EPA will notify the submitter. A submitter may request a suspension at any time during the notice review period. The suspension must be for a specified period of time.

(2) A request for suspension may only be submitted in a manner set forth in this paragraph. The request for suspension also may be made orally, including by telephone, to the submitter's EPA contact for that notice, subject to paragraph (b)(3) of this section.

(i) *Older notices.* Requests for suspension for premanufacture notices submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(ii) *Newer notices.* For notices submitted on or after April 6, 2010, EPA will accept requests for suspension only if submitted in accordance with this paragraph:

(A) Requests for suspension may be submitted on paper on or before April 6, 2011. All paper-based requests for suspension must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print the request for suspension for submission to EPA. Paper requests for suspension must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(B) Requests for suspension may be submitted as electronic files on optical disc on or before April 6, 2012. All requests for suspension submitted as electronic files on optical disc generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print the request for suspension for submission to EPA. Paper requests for suspension must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted

## Environmental Protection Agency

## § 720.75

via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(C) Requests for suspension may be submitted electronically to EPA via CDX. Such requests must be generated and completed using e-PMN reporting software. See § 720.40(a)(2)(iv) for information on how to obtain e-PMN software.

(3) An oral request for suspension may be granted by EPA for a maximum of 15 days only. Requests for a longer suspension must only be submitted in the manner set forth in this paragraph.

(4) If the submitter has not made a previous oral request, the running of the notice review period is suspended as of the date of receipt of the written paper request, electronic request on optical disc, or CDX submission by EPA.

(c) *Extension of notice review period.* (1) At any time during the notice review period, EPA may determine that good cause exists to extend the notice review period specified in paragraph (a) of this section.

(2) If EPA makes such a determination, EPA will:

(i) Notify the submitter that EPA is extending the notice review period for a specified length of time, and state the reasons for the extension.

(ii) Issue a notice for publication in the FEDERAL REGISTER which states that EPA is extending the notice review period and gives the reasons for the extension.

(3) The initial extension may be for a period of up to 90 days. If the initial extension is for less than 90 days, EPA may make additional extensions. However, the total period of extensions may not exceed 90 days for any notice.

(4) The following are examples of situations in which EPA may find that good cause exists for extending the notice review period:

(i) EPA has reviewed the notice and determined that there is a significant possibility that the chemical substance will be regulated under section 5(e) or section 5(f) of the Act, but EPA is unable to initiate regulatory action within the initial 90-day period.

(ii) EPA has reviewed the submission and is seeking additional information.

(iii) EPA has received significant additional information during the notice review period.

(iv) The submitter has failed to correct a notice after receiving EPA's request under § 720.65(b).

(d) *Notice of expiration of notice review period.* EPA will notify the submitter that the notice review period has expired or that EPA has completed its review of the notice. Expiration of the review period does not constitute EPA approval or certification of the new chemical substance, and does not mean that EPA may not take regulatory action against the substance in the future. After expiration of the statutory notice review period, in the absence of regulatory action by EPA under section 5(e), 5(f), or 6(a) of the Act, the submitter may manufacture or import the chemical substance even if the submitter has not received notice of expiration.

(e) *Withdrawal of a notice by the submitter.* (1) A submitter may withdraw a notice during the notice review period by submitting a statement of withdrawal in a manner set forth in this paragraph. The withdrawal is effective upon receipt of the written paper request, electronic request on optical disc, or CDX submission by EPA.

(i) *Older notices.* Statements of withdrawal for premanufacture notices submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(ii) *Newer notices.* For notices submitted on or after April 6, 2010, EPA will accept statements of withdrawal only if submitted in accordance with this paragraph:

(A) Statements of withdrawal may be submitted on paper on or before April 6, 2011. All paper-based statements of withdrawal must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must

be used to print the statement of withdrawal for submission to EPA. Paper statements of withdrawal must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(B) Statements of withdrawal may be submitted as electronic files on optical disc on or before April 6, 2012. All statements of withdrawal submitted as electronic files on optical disc must be generated using e-PMN reporting software and be completed through the finalization step of the software. Optical discs containing electronic statements of withdrawal must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(C) Statements of withdrawal may be submitted electronically to EPA via CDX. Prior to submission to EPA via CDX, such statements of withdrawal must be generated and completed using e-PMN reporting software. See § 720.40(a)(2)(iv) for information on how to obtain e-PMN software.

(2) If a manufacturer or importer which withdrew a notice later resubmits a notice for the same chemical substance, a new notice review period begins.

[48 FR 21742, May 13, 1983, as amended at 53 FR 12523, Apr. 15, 1988; 58 FR 34204, June 23, 1993; 60 FR 34464, July 3, 1995; 71 33641, June 12, 2006; 75 FR 786, Jan. 6, 2010]

#### § 720.78 Recordkeeping.

(a) Any person who submits a notice under this part must retain documentation of information in the notice, including (1) other data, as defined in § 720.50(b), in the submitter's possession or control; and (2) records of production volume for the first three years of production or import, the date of commencement of manufacture or import, and documentation of this information. This information must be retained for

five years from the date of commencement of manufacture or import.

(b)(1) Persons who manufacture or import a chemical substance under § 720.36 must retain the following records:

(i) Copies of, or citations to, information reviewed and evaluated under § 720.36(b)(1) to determine the need to make any notification of risk.

(ii) Documentation of the nature and method of notification under § 720.36(c)(1) including copies of any labels or written notices used.

(iii) Documentation of prudent laboratory practices used instead of notification and evaluation under § 720.36(b)(2).

(iv) The names and addresses of any persons other than the manufacturer or importer to whom the substance is distributed, the identity of the substance to the extent known, the amount distributed, and copies of the notifications required under § 720.36(c)(2). These records are not required when substances are distributed as impurities or incorporated into an article, in accordance with paragraph (d) of this section.

(2) A person who manufactures or imports a chemical substance under § 720.36 and who manufactures or imports the substance in quantities greater than 100 kilograms per year must retain records of the identity of the substance to the extent known, the production volume of the substance, and the person's disposition of the substance. The person is not required to maintain records of the disposition of products containing the substance as an impurity or of articles incorporating the substances.

(3) Records under this paragraph must be retained for 5 years after they are developed.

(c) Any person who obtains a test-marketing exemption under this part must retain documentation of information in the application and documentation of compliance with any restrictions imposed by EPA when it granted the application. This information must be retained for five years from the final date of manufacture or import under the exemption.

[48 FR 21742, May 13, 1983; 48 FR 33872, July 26, 1983, as amended at 51 FR 15102, Apr. 22, 1986; 58 FR 34204, June 23, 1993]

### Subpart E—Confidentiality and Public Access to Information

#### § 720.80 General provisions.

(a) A person may assert a claim of confidentiality for any information which he or she submits to EPA under this part.

(b) Any claim of confidentiality must accompany the information when it is submitted to EPA.

(1)(i) For information submitted on the notice form, the claim(s) must be asserted on the form in the manner prescribed on the notice form.

(ii) When a person submits information in an attachment, the claim(s) must be asserted in the attachment as described on the notice form.

(2) If any information is claimed as confidential, the person must submit, in addition to the copies specified by § 720.40, a sanitized copy of the notice form (or electronic submission) and any attachments.

(i) The notice and attachments must be complete. The submitter must designate that information which is claimed as confidential in the manner prescribed on the notice form, via EPA's e-PMN software. See § 720.40(a)(2)(iv) for information on how to obtain e-PMN software.

(ii) The sanitized copy must be complete except that all information claimed as confidential in the original must be deleted. EPA will place this sanitized copy in the public file.

(iii) If the person does not provide the sanitized copy, or information in a health and safety study (except information claimed as confidential in accordance with § 720.90), the submission will be deemed incomplete and the notice review period will not begin until EPA receives the sanitized copy or the health and safety study information is included, in accordance with § 720.65(c)(1)(vii).

(c) EPA will disclose information that is subject to a claim of confidentiality asserted under this section only to the extent permitted by the Act, this subpart, and part 2 of this title.

(d) If a notice submitter does not assert a claim of confidentiality for information at the time it is submitted to EPA, EPA may make the information public and place it in the public

file without further notice to the submitter.

[48 FR 21742, May 13, 1983, as amended at 58 FR 34204, June 23, 1993; 60 FR 16311, Mar. 29, 1995; 75 FR 786, Jan. 6, 2010]

#### § 720.85 Chemical identity.

(a) *Claims applicable to the period prior to commencement of manufacture or import.* (1)(i) A person who submits information to EPA under this part may assert a claim of confidentiality for the chemical identity of the new chemical substance. This claim will apply only to the period prior to the commencement of manufacture or import for commercial purposes. A submitter may assert this claim only if the submitter believes that public disclosure prior to commencement of manufacture or import of the fact that anyone intends to manufacture or import the specific chemical substance for commercial purposes would reveal confidential business information.

(ii) If the notice includes a health and safety study concerning the new chemical substance and if the claim for confidentiality with respect to the chemical identity is denied in accordance with § 720.90(c), EPA will deny a claim asserted under this paragraph.

(2) Any person who asserts a claim of confidentiality for chemical identity under this paragraph must provide one of the following items at the time the notice is submitted:

(i) The generic name which was accepted by EPA in the prenotice consultation conducted under paragraph (a)(3) of this section.

(ii) One generic name that is only as generic as necessary to protect the confidential chemical identity of the particular chemical substance. The name should reveal the specific chemical identity to the maximum extent possible. The generic name will be subject to EPA review and approval at the time a notice of commencement is submitted.

(3)(i) Any person who intends to assert a claim of confidentiality for the chemical identity of a new chemical substance may seek a determination by EPA of an appropriate generic name for the substance before submitting a notice. For this purpose, the person should submit to EPA:

(A) The chemical identity of the substance.

(B) A proposed generic name(s) which in only as generic as necessary to protect the confidential chemical identity of the new chemical substance. The name(s) should reveal the chemical identity of the substance to the maximum extent possible.

(ii) Within 30 days, EPA will inform the submitter either that one of the proposed generic names is adequate or that none is adequate and further consultation is necessary.

(4) If a submitter claims chemical identity to be confidential under this paragraph, and if the submitter complies with paragraph (a)(2) of this section, EPA will issue for publication in the FEDERAL REGISTER notice described in § 720.70 the generic name proposed by the submitter or one agreed upon by EPA and the submitter.

(b) *Claims applicable to the period after commencement of manufacture or import.*

(1) Any claim of confidentiality under paragraph (a) of this section is applicable only until the substance is manufactured or imported for commercial purposes and becomes eligible for inclusion on the Inventory. To maintain the confidential status of the chemical identity when the substance is added to the Inventory, a submitter must reassert the confidentiality claim and substantiate the claim in the notice of commencement of manufacture required under § 720.102. A submitter may not claim the chemical identity confidential for the period after commencement of manufacture or import unless the submitter claimed the chemical identity confidential for the period prior to commencement of manufacture or import under paragraph (a) of this section.

(2)(i) A person who believes that public disclosure of the fact that anyone manufactures or imports the new chemical substance for commercial purposes would reveal confidential business information may assert a claim of confidentiality under this paragraph.

(ii) If the notice includes a health and safety study concerning the new chemical substance, and if the claim for confidentiality with respect to the chemical identity is denied in accord-

ance with § 720.90(c), EPA will deny a claim asserted under this paragraph.

(3) Any person who asserts a confidentiality claim for chemical identity must:

(i) Comply with the requirements of paragraph (a)(3) of this section regarding submission of a generic name.

(ii) Agree that EPA may disclose to a person with a *bona fide* intent to manufacture or import the chemical substance the fact that the particular chemical substance is included on the confidential Inventory for purposes of notification under section 5(a)(1)(A) of the Act.

(iii) Have available for the particular chemical substance, and agree to furnish to EPA upon request:

(A) An elemental analysis.

(B) Either an X-ray diffraction pattern (for inorganic substances), a mass spectrum (for most other substances), or an infrared spectrum of the particular chemical substance, or if such data do not resolve uncertainties with respect to the identity of the chemical substance, additional or alternative spectra or other data to identify the chemical substance.

(iv) Provide a detailed written substantiation of the claim, by answering the following questions:

(A) What harmful effects to your competitive position, if any, do you think would result if EPA publishes on the Inventory the identity of the chemical substance? How could a competitor use such information given the fact that the identity of the substance otherwise would appear on the Inventory of chemical substances with no link between the substance and your company or industry? How substantial would the harmful effects of disclosure be? What is the casual relationship between the disclosure and the harmful effects?

(B) For what period of time should confidential treatment be given? Until a specific date, the occurrence of a specific event, or permanently? Why?

(C) Has the chemical substance been patented? If so, have you granted licenses to others with respect to the patent as it applies to the chemical substance? If the chemical substance has been patented and therefore disclosed through the patent, why should

## Environmental Protection Agency

## § 720.85

it be treated as confidential for purposes of the Inventory?

(D) Has the identity of the chemical substance been kept confidential to the extent that your competitors do not know it is being manufactured or imported for a commercial purpose by anyone?

(E) Is the fact that someone is manufacturing or importing this chemical substance for commercial purposes available to the public, e.g., in technical journals or other publications; in libraries; or in State, local, or Federal agency public files?

(F) What measures have you taken to prevent undesired disclosure of the fact that you are manufacturing or importing this substance for a commercial purpose?

(G) To what extent has the fact that you are manufacturing or importing this chemical substance for a commercial purpose been disclosed to others? What precautions have you taken in regard to these disclosures? Has this information been disclosed to the public or to competitors?

(H) In what form does this particular chemical substance leave the site of manufacture, e.g., as part of a product; in an effluent or emission stream? If so, what measures have you taken to guard against discovery of its identity?

(I) If the chemical substance leaves the site of manufacture in a product that is available to either the public or your competitors, can they identify the substance by analyzing the product?

(J) For what purpose do you manufacture or import the substance?

(K) Has EPA, another Federal agency, or any Federal court made any pertinent confidentiality determinations regarding this chemical substance? If so, copies of such determinations must be included in the substantiation.

(L) If the notice includes a health and safety study concerning the new chemical substance, the submitter must also answer the questions in § 720.90(b)(2).

(4) If the submitter does not meet the requirements of this paragraph, EPA will deny the claim of confidentiality.

(5)(i) EPA will publish a generic name on the public Inventory if:

(A) The submitter asserts a claim of confidentiality in accordance with this paragraph.

(B) No claim for confidentiality of the specific chemical identity as part of a health and safety study has been denied in accordance with part 2 of this title or § 720.90.

(ii) Publication of a generic name on the public Inventory does not create a category for purposes of the Inventory. Any person who has a *bona fide* intent to manufacture or import a chemical substance which is described by a generic name on the public Inventory may submit an inquiry to EPA under § 720.25(b) to determine whether the particular chemical substance is included on the confidential Inventory.

(iii) Upon receipt of a request described in § 720.25(b), EPA may require the submitter which originally asserted confidentiality for a chemical substance to submit to EPA the information listed in paragraph (b)(3)(iii) of this section.

(iv) Failure to submit any of the information required under paragraph (b)(3)(iii) of this section within ten days of a request by EPA under this paragraph is a waiver of the original submitter's confidentiality claim. In this event, EPA may place the specific chemical identity on the public Inventory without further notice to the original submitter.

(6) If a submitter asserts a claim of confidentiality under this paragraph, EPA will examine the generic chemical name proposed by the submitter.

(i) If EPA determines that the generic name proposed by the submitter is only as generic as necessary to protect the confidential identity of the particular chemical substance, EPA will place that generic name on the public Inventory.

(ii) If EPA determines that the generic name proposed by the submitter is more generic than necessary to protect the confidential identity, EPA will propose in writing, for review by the submitter, an alternative generic name that will reveal the chemical identity of the chemical substance to the maximum extent possible.

(iii) If the generic name proposed by EPA is acceptable to the submitter,



EPA will place that generic name on the public Inventory.

(iv) If the generic name proposed by EPA is not acceptable to the submitter, the submitter must explain in detail why disclosure of that generic name would reveal confidential business information and propose another generic name which is only as generic as necessary to protect the confidential identity. If EPA does not receive a response from the submitter within 30 days after the submitter receives the proposed name, EPA will place EPA's chosen generic name on the public Inventory. If the submitter does provide the information requested, EPA will review the response. If the submitter's proposed generic name is acceptable, EPA will publish that generic name on the public Inventory. If the submitter's proposed generic name is not acceptable, EPA will notify the submitter of EPA's choice of a generic name. Thirty days after this notification, EPA will place the chosen generic name on the public Inventory.

**§ 720.87 Categories or proposed categories of uses of a new chemical substance.**

(a) A person who submits information to EPA under this part on the categories or proposed categories of use of a new chemical substance may assert a claim of confidentiality for this information.

(b) A submitter that asserts such a claim must:

(1) Report the categories or proposed categories of use of the chemical substance.

(2) Provide, in nonconfidential form, a description of the uses that is only as generic as necessary to protect the confidential business information. The generic use description will be included in the FEDERAL REGISTER notice described in § 720.70.

(c) The person must submit the information required by paragraph (b) of this section in the manner specified in the notice form.

**§ 720.90 Data from health and safety studies.**

(a) *Information other than specific chemical identity.* Except as provided in paragraph (b) of this section, EPA will

deny any claim of confidentiality with respect to information included in a health and safety study, unless the information would disclose confidential business information concerning:

(1) Processes used in the manufacture or processing of a chemical substance or mixture.

(2) In the case of a mixture, the portion of the mixture comprised by any of the chemical substances in the mixture.

(3) Information which is not in any way related to the effects of a substance on human health or the environment, such as the name of the submitting company, cost or other financial data, product development or marketing plans, and advertising plans, for which the person submits a claim of confidentiality in accordance with § 720.80.

(b) *Specific chemical identity*—(1) *Claims applicable to period prior to commencement of manufacture.* A claim of confidentiality for the period prior to commencement of manufacture or import for the chemical identity of a chemical substance for which a health and safety study was submitted must be asserted in conjunction with a claim asserted under § 720.85(a).

(2) *Claims applicable to period after commencement of manufacture or import for commercial purposes.* To maintain the confidential status of the chemical identity of a chemical substance for which a health and safety study was submitted after commencement of manufacture or import, the claim must be reasserted and substantiated in conjunction with a claim under § 720.85(b). In addition to the questions set forth in § 720.85(b)(3)(iv) of this part, the submitter must answer the following questions:

(i) Would disclosure of the chemical identity disclose processes used in the manufacture or processing of a chemical substance or mixture? Describe how this would occur. In responding to the question in § 720.85(b)(3)(iv)(A), explain what harmful competitive effects would occur from disclosure of this process information.

(ii) Would disclosure of the chemical identity disclose the portion of a mixture comprised by any of the substances in the mixture? Describe how

## Environmental Protection Agency

## § 720.102

this would occur. In responding to the question in § 720.85(b)(3)(iv)(A), explain what harmful competitive effects would occur from disclosure of this information.

(iii) Do you assert that disclosure of the chemical identity is not necessary to interpret any of the health and safety studies you have submitted? If so, explain how a less specific identity would be sufficient to interpret the studies.

(c) *Denial of confidentiality claim.* EPA will deny a claim of confidentiality for chemical identity under paragraph (b) of this section, unless:

(1) The information would disclose processes used in the manufacture or processing of a chemical substance or mixture.

(2) In the case of a mixture, the information would disclose the portion of the mixture comprised by any of the substances in the mixture.

(3) The specific chemical identity is not necessary to interpret a health and safety study.

(d) *Use of generic names.* When EPA discloses a health and safety study containing a specific chemical identity, which the submitter has claimed confidential, and if the Agency has not denied the claim under paragraph (c) of this section, EPA will identify the chemical substance by the generic name selected under § 720.85.

[48 FR 21742, May 13, 1983, as amended at 58 FR 34204, June 23, 1993]

### § 720.95 Public file.

All information submitted with a notice, including any health and safety study and other supporting documentation, will become part of the public file for that notice, unless such materials are claimed confidential. In addition, EPA may add materials to the public file, subject to subpart E of this part. Any of the nonconfidential material described in this subpart will be available for public inspection in the Non-Confidential Information Center (NCIC) (7407), Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, Room B-607 NEM, 401 M St., SW., Washington, DC 20460, between the hours of 12 p.m. and

4 p.m. weekdays excluding legal holidays.

[48 FR 21742, May 13, 1983, as amended at 53 FR 12523, Apr. 15, 1988; 60 FR 16311, Mar. 29, 1995; 60 FR 34464, July 3, 1995]

## Subpart F—Commencement of Manufacture or Import

### § 720.102 Notice of commencement of manufacture or import.

(a) *Applicability.* Any person who commences the manufacture or import of a new chemical substance for a non-exempt commercial purpose for which that person previously submitted a section 5(a) notice under this part must submit a notice of commencement of manufacture or import.

(b) *When to report.* (1) If manufacture or import for commercial purposes begins on or after the effective date of this rule, the submitter must submit the notice to EPA on, or no later than 30 calendar days, after the first day of such manufacture or import.

(2) If manufacture or import for commercial purposes began or will begin before the effective date of this rule, the submitter must submit the notice by the effective date of this rule.

(c) *Information to be reported on form.*

(1) The notice must be submitted on EPA Form 7710-56, which is available as part of EPA's e-PMN software. See § 720.40(a)(2)(iv) for information on how to obtain e-PMN software. The form must be signed and dated by an Authorized Official (AO). All information specified on the form must be provided. The notice must contain the following information:

(i) The specific chemical identity of the PMN substance.

(ii) A generic chemical name (if the chemical identity is claimed as confidential by the submitter).

(iii) The premanufacture notice (PMN) number assigned by EPA.

(iv) The date of commencement for the submitter's manufacture or import for a non-exempt commercial purpose (indicating whether the substance was initially manufactured in the United States or imported). The date of commencement is the date of completion of non-exempt manufacture of the first amount (batch, drum, etc.) of new chemical substance identified in the

## § 720.120

## 40 CFR Ch. I (7–1–10 Edition)

submitter's PMN. For importers, the date of commencement is the date the new chemical substance clears United States customs.

(v) The name and address of the submitter.

(vi) The name of the authorized official.

(vii) The name and telephone number of a technical contact in the United States.

(viii) The address of the site where commencement of manufacture occurred.

(ix) Clear indications of whether the chemical identity, submitter identity, and/or other information are claimed as confidential by the submitter.

(2) If the submitter claims the chemical identity confidential, and wants the identity to be listed on the confidential portion of the Inventory, the claim must be reasserted and substantiated in accordance with § 720.85(b). Otherwise, EPA will list the specific chemical identity on the public Inventory. Submitters who did not claim the chemical identity, submitter identity, or other information to be confidential in the PMN cannot claim this information as confidential in the notice of commencement.

(d) *Where to submit.* All notices of commencement must be submitted to EPA on EPA Form 7710–56. Notices may only be submitted in a manner set forth in this paragraph.

(1) *Older notices.* Notices of commencement for premanufacture notices submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460–0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(2) *Newer notices.* For premanufacture notices submitted on or after April 6, 2010, EPA will accept notices of commencement only if submitted in accordance with this paragraph:

(i) Notices of commencement may be submitted on paper on or before April 6, 2011. All paper-based notices of com-

mencement must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print the notice of commencement for submission to EPA. Paper notices of commencement must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460–0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(ii) Notices of commencement may be submitted as electronic files on optical disc on or before April 6, 2012. All notices of commencement submitted as electronic files on optical disc must be generated using e-PMN reporting software and be completed through the finalization step of the software. Optical discs containing electronic notices of commencement must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(iii) Notices of commencement may be submitted electronically to EPA via CDX on or after April 6, 2010. After April 6, 2012 all notices of commencement must be submitted electronically to EPA via CDX. Prior to submission to EPA via CDX, such notices of commencement must be generated and completed using e-PMN reporting software. See § 720.40(a)(2)(iv) for information on how to obtain e-PMN software.

[48 FR 21742, May 13, 1983, as amended at 48 FR 41140, Sept. 13, 1983; 51 FR 15103, Apr. 22, 1986; 53 FR 12523, Apr. 15, 1988; 60 FR 16311, Mar. 29, 1995; 60 FR 34464, July 3, 1995; 65 FR 39304, June 26, 2000; 71 FR 33641, June 12, 2006; 75 FR 786, Jan. 6, 2010]

### Subpart G—Compliance and Inspections

#### § 720.120 Compliance.

(a) Failure to comply with any provision of this part is a violation of section 15 of the Act (15 U.S.C 2614).

## Environmental Protection Agency

## Pt. 721

(b) A person who manufactures or imports a new chemical substance before a notice is submitted and the notice review period expires is in violation of section 15 of the Act even if that person was not required to submit the notice under § 720.22.

(c) Using for commercial purposes a chemical substance or mixture which a person knew or had reason to know was manufactured, processed, or distributed in commerce in violation of section 5 of this rule is a violation of section 15 of the Act (15 U.S.C. 2614).

(d) Failure or refusal to establish and maintain records or to permit access to or copying of records, as required by the Act, is a violation of section 15 of the Act (15 U.S.C. 2614).

(e) Failure or refusal to permit entry or inspection as required by section 11 is a violation of section 15 of the Act (15 U.S.C. 2614).

(f) Violators may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation. Persons who submit materially misleading or false information in connection with the requirements of any provision of this rule may be subject to penalties calculated as if they never filed their notices.

(g) EPA may seek to enjoin the manufacture or processing of a chemical substance in violation of this rule or act to seize any chemical substance manufactured or processed in violation of this rule or take other actions under the authority of section 7 of this Act (15 U.S.C. 2606) or section 17 or this Act (15 U.S.C. 2616).

### § 720.122 Inspections.

EPA will conduct inspections under section 11 of the Act to assure compliance with section 5 of the Act and this rule, to verify that information submitted to EPA under this rule is true and correct, and to audit data submitted to EPA under this rule.

## PART 721—SIGNIFICANT NEW USES OF CHEMICAL SUBSTANCES

### Subpart A—General Provisions

- Sec.  
721.1 Scope and applicability.  
721.3 Definitions.  
721.5 Persons who must report.

- 721.11 Applicability determination when the specific chemical identity is confidential.  
721.20 Exports and imports.  
721.25 Notice requirements and procedures.  
721.30 EPA approval of alternative control measures.  
721.35 Compliance and enforcement.  
721.40 Recordkeeping.  
721.45 Exemptions.  
721.47 Conditions for research and development exemption.

### Subpart B—Certain Significant New Uses

- 721.50 Applicability.  
721.63 Protection in the workplace.  
721.72 Hazard communication program.  
721.80 Industrial, commercial, and consumer activities.  
721.85 Disposal.  
721.90 Release to water.  
721.91 Computation of estimated surface water concentrations: Instructions.

### Subpart C—Recordkeeping Requirements

- 721.100 Applicability.  
721.125 Recordkeeping requirements.

### Subpart D—Expedited Process for Issuing Significant New Use Rules for Selected Chemical Substances and Limitation or Revocation of Selected Significant New Use Rules

- 721.160 Notification requirements for new chemical substances subject to section 5(e) orders.  
721.170 Notification requirements for selected new chemical substances that have completed premanufacture review.  
721.185 Limitation or revocation of certain notification requirements.

### Subpart E—Significant New Uses for Specific Chemical Substances

- 721.225 2-Chloro-N-methyl-N-substituted acetamide (generic name).  
721.267 N-[2-[(substituted dinitrophenyl)azo]diallylamino-4-substituted phenyl] acetamide (generic name).  
721.275 Halogenated-N-(2-propenyl)-N-(substituted phenyl) acetamide.  
721.285 Acetamide, N-[4-(pentyloxy)phenyl]-, acetamide, N-[2-nitro-4-(pentyloxy)phenyl]-, and acetamide, N-[2-amino-4-(pentyloxy)phenyl]-.  
721.303 Substituted acetate (generic).  
721.304 Acetic acid, [(5-chloro-8-quinolinyloxy)-, 1-methyl hexyl ester.  
721.305 Di-substituted acetophenone (generic).  
721.320 Acrylamide-substituted epoxy.  
721.321 Substituted acrylamides and acrylic acid copolymer (generic).

## Pt. 721

## 40 CFR Ch. I (7-1-10 Edition)

- 721.323 Substituted acrylamide.
- 721.324 Alkoxyated acrylate polymer (generic).
- 721.329 Halogenated benzyl ester acrylate (generic).
- 721.330 Aromatic acrylate (generic).
- 721.333 Dimethyl alkylamine salt (generic).
- 721.336 Perfluoroalkylethyl acrylate copolymer (generic name).
- 721.338 Salt of an acrylate copolymer (generic).
- 721.405 Polyether acrylate.
- 721.430 Oxo-substituted aminoalkanoic acid derivative.
- 721.435 Alkylphenylpolyetheralkanolamines (generic).
- 721.445 Substituted ethyl alkenamide.
- 721.450 Hydrofluorochloroalkene (generic).
- 721.463 Acrylate of polymer based on isophorone diisocyanate (generic).
- 721.465 Alkoxyated alkylpolyol acrylates, adduct with alkylamine (generic).
- 721.480 Aminoester of polyalkenylated alkylidicarboxylic acid (generic).
- 721.484 Fluorinated acrylic copolymer (generic name).
- 721.505 Halogenated acrylonitrile.
- 721.520 Alanine, N-(2-carboxyethyl)-N-alkyl-, salt.
- 721.522 Oxirane, methyl-, polymer with oxirane, mono(3,5,5-trimethylhexyl) ether.
- 721.524 Alcohols, C<sub>6-12</sub>, ethoxyated, reaction product with maleic anhydride.
- 721.525 1-propanol, 3-propoxy-.
- 721.530 Substituted aliphatic acid halide (generic name).
- 721.532 Substituted hydroxyalkane acetate (generic).
- 721.533 Propane, 1,1,1,3,3-pentachloro-.
- 721.535 Halogenated alkane (generic).
- 721.536 Halogenated phenyl alkane.
- 721.537 Organosilane ester.
- 721.538 Phenol, 4-(1,1-dimethylethyl)-, homopolymer.
- 721.539 Poly(oxy-1,2-ethanediyl),  $\alpha$ -sulfo- $\omega$ -[1-[(4-nonylphenoxy)methyl]-2-(2-propenyloxy)ethoxy]-, branched, ammonium salts.
- 721.540 Alkylphenoxyalkoxyamine (generic name).
- 721.545 Polyalkenylalkylphenol (generic).
- 721.550 Alkyl alkenoate, azobis-.
- 721.555 Alkyl amino nitriles (generic).
- 721.558 Salt of a fatty alkylamine derivative (generic).
- 721.562 Substituted alkylamine salt.
- 721.575 Substituted alkyl halide.
- 721.600 3-Alkyl-2-(2-anilino)vinyl thiazolium salt (generic name).
- 721.625 Alkylated diarylamine, sulfurized (generic name).
- 721.630 Salt of a modified tallow alkylenediamine (generic).
- 721.632 Silicoaluminophosphates, compd. with organic amine (generic).
- 721.633 Aluminosilicates, phospho-.
- 721.638 Silyl amine, potassium salt (generic).
- 721.639 Amine aldehyde condensate.
- 721.640 Amine substituted metal salts.
- 721.641 Alkylpoly(oxyalkylene)amine.
- 721.642 Amines, N-(C<sub>14-18</sub> and C<sub>16-18</sub> unsaturated alkyl)] dipropylene-tri-, tripropylenetetra-, and tetrapropylene-penta-.
- 721.643 Ethoxyated alcohol, phosphated, amine salt.
- 721.644 Amines, C<sub>12-14</sub>-tert-alkyl, sulfonates.
- 721.646 Aminofluoran derivative (generic name).
- 721.647 Alkoxyated alkyl amine (generic).
- 721.648 Alkyl dialkylamino phenylsulfonyl alkenoate (generic).
- 721.650 11-Aminoundecanoic acid.
- 721.655 Ethoxyated alkyl quaternary ammonium compound.
- 721.715 Trisubstituted anthracene.
- 721.720 Alkoxyated fatty acid amide, alkylsulfate salt.
- 721.750 Aromatic amine compound.
- 721.757 Polyoxyalkylene substituted aromatic azo colorant.
- 721.775 Brominated aromatic compound (generic name).
- 721.785 Halogenated alkane aromatic compound (generic name).
- 721.805 Benzenamine, 4,4'-[1,3-phenylenebis(1-methylethyl idene)]bis[2,6-dimethyl-.
- 721.825 Certain aromatic ether diamines.
- 721.840 Alkyl substituted diaromatic hydrocarbons.
- 721.843 Substituted phenylazophenylazo phenol (generic).
- 721.875 Aromatic nitro compound.
- 721.910 Propanetriol polyalkylenepolyolamine aryl aldimine (generic).
- 721.925 Substituted aromatic (generic).
- 721.950 Sodium salt of an alkylated, sulfonated aromatic (generic name).
- 721.977 Aryloxyarene.
- 721.980 Sodium salt of azo acid dye.
- 721.981 Substituted naphtholoazo-substituted naphthalenyl-substituted azonaphthol chromium complex.
- 721.982 Calcium, bis(2,4-pentanedionato-O,O').
- 721.983 Sulfonyl azide intermediate (generic).
- 721.984 Amino-hydroxy sulfonaphthylazo-disubstituted phenyl azo benzene carboxylate salt (generic).
- 721.987 Dialkylaminophenyl imino pyrazole acid ester (generic).
- 721.988 Pyrazolone azomethine dye (generic).
- 721.990 1,4-Benzedicarboxylic acid, dimethyl ester, polymer with 1,4-butanediol, cyclized.
- 721.1000 Benzenamine, 3-chloro-2,6-dinitro-N,N-dipropyl-4-(trifluoromethyl)-.

Environmental Protection Agency

Pt. 721

- 721.1025 Benzenamine, 4-chloro-2-methyl-; benzenamine, 4-chloro-2-methyl-, hydrochloride; and benzenamine, 2-chloro-6-methyl-.
- 721.1050 Benzenamine, 2,5-dibutoxy-4-(4-morpholinyl)-, sulfate.
- 721.1055 Benzeneamine, 3,5-difluoro-.
- 721.1068 Benzenamine, 4-isocyanato-*N,N*-bis(4-isocyanatophenyl)-2,5-dimethoxy-.
- 721.1070 Benzenamine, 4-methoxy-2-methyl-*N*-(3-methylphenyl).
- 721.1075 Benzenamine, 4-(1-methylbutoxy)-, hydrochloride.
- 721.1085 Benzenamine, 4,4'-methylenebis[*N*-ethyl-*N*-methyl-].
- 721.1105 Benzenamine, 4,4'-methylenebis[2-methyl-6-(1-methylethyl)]-.
- 721.1120 Benzenamine, 4,4'-[1,4-phenylenebis(1-methylethylidene)]bis[2,6-dimethyl-].
- 721.1150 Substituted polyglycidyl benzenamine.
- 721.1155 1,4-benzenediol, 2-(1,1,3,3-tetramethylbutyl)-and Bis(dimethylamino substituted)carbomonocycle.
- 721.1187 Bis(imidoethylene) benzene.
- 721.1193 Benzene, 2-bromo-1,4-dimethoxy-.
- 721.1210 Benzene, (2-chloroethoxy)-.
- 721.1225 Benzene, 1,2-dimethyl-, polypropene derivatives, sulfonated, potassium salts.
- 721.1230 Benzene, ethenyl-, ar-bromo derivatives.
- 721.1240 Benzene, (2-bromoethyl)-, ar-bromo derivatives.
- 721.1300 [(Dinitrophenyl)azo]-[2,4-diamino-5-methoxybenzene] derivatives.
- 721.1325 Benzene, 1-(1-methylbutoxy)-4-nitro-.
- 721.1350 Benzene, (1-methylethyl)(2-phenylethyl)-.
- 721.1372 Substituted nitrobenzene.
- 721.1375 Disubstituted nitrobenzene (generic name).
- 721.1425 Pentabromoethylbenzene.
- 721.1430 Pentachlorobenzene.
- 721.1435 1,2,4,5-Tetrachlorobenzene.
- 721.1440 1,3,5-Trinitrobenzene.
- 721.1450 1,3-Benzenediamine, 4-(1,1-dimethylethyl)-ar-methyl.
- 721.1500 1,2-Benzenediamine, 4-ethoxy, sulfate.
- 721.1550 Benzenediazonium, 4-(dimethylamino)-, salt with 2-hydroxy-5-sulfobenzoic acid (1:1).
- 721.1555 Substituted phenyl azo substituted benzenediazonium salt.
- 721.1568 Substituted benzenediazonium.
- 721.1576 1,3-Benzenedicarboxylic acid, bis[[4-(ethenyloxy)methyl] cyclohexyl] methyl ester.
- 721.1577 1,4-Benzenedicarboxylic acid, bis [4-(ethenyloxy) butyl] ester.
- 721.1578 1,4-Benzenedicarboxylic acid, bis[[4-(ethenyloxy)methyl] cyclohexyl] methyl ester.
- 721.1579 1,2,4-Benzenetricarboxylic acid, tris [4-(ethenyloxy) butyl] ester.
- 721.1580 Disubstituted benzene ether, polymer with substituted phenol (generic).
- 721.1612 Substituted 2-nitro- and 2-aminobenzenesulfonamide.
- 721.1620 Benzenesulfonamide, alkylphenyl substituted phenyl substituted carbonyl- (generic).
- 721.1625 Alkylbenzene sulfonate, amine salt.
- 721.1630 1,2-Ethanediol bis(4-methylbenzenesulfonate); 2,2-oxybis-ethane bis(4-methylbenzenesulfonate); ethanol, 2,2'-[oxybis(2,1-ethanediyl oxy)]bis-, bis(4-methylbenzenesulfonate); ethanol, 2,2'-[oxybis (2,1-ethane diylxy)] bis-, bis(4-methylbenzenesulfonate); ethanol, 2,2'-[[1-(2-propenyloxy) methyl]-1,2-ethanediyl] bis(oxy)]bis-, bis(4-methylbenzene sulfonate); and ethanol, 2-[1-[[2-[[2-[[4-methylphenyl)sulfonyl]oxy]ethoxy] ethoxy]methyl]-2-(2-propenyloxy)ethoxy]-, 4-methylbenzenesulfonate.
- 721.1637 1,2-Propanediol, 3-(2-propenyloxy)-, bis(4-methylbenzene sulfonate); 2-propanol, 1-[2-[[4-methylphenyl)sulfonyl]oxy]ethoxy]-3-(2-propenyloxy)-4-methylbenzenesulfonate; and 2-propanol, 1-[2-[[2-[[4-methylphenyl)sulfonyl]oxy]ethoxy]ethoxy]-3-(2-propenyloxy)-, 4-methylbenzenesulfonate.
- 721.1640 3,6,9,12,-Tetraoxatetradecane-1,14-diol, bis(4-methylbenzenesulfonate); 3,6,9,13-tetraoxahexadec-15-ene-1,11-diol, bis(4-methylbenzenesulfonate); 3,6,9,12,16-pentaoxanonadec-18-ene-1,14-diol, bis(4-methyl benzenesulfonate); and 3,6,9,12-tetraoxatetradecane-1,14-diol, 7-[(2-propenyloxy)methyl]-, bis(4-methylbenzenesulfonate).
- 721.1643 Benzenesulfonic acid, amino substituted phenylazo-.
- 721.1645 Benzenesulfonic acid, 4-methyl-, reaction products with oxirane mono[(C<sub>10-16</sub>-alkyloxy)methyl] derivatives and 2,2,4(or 2,4,4)-trimethyl-1,6-hexanediamine.
- 721.1648 Substituted benzenesulfonic acid salt (generic).
- 721.1650 Alkylbenzenesulfonic acid and sodium salts.
- 721.1655 Alkylbenzenesulfonic acid (generic).
- 721.1660 Benzidine-based chemical substances.
- 721.1675 Disulfonic acid rosin amine salt of a benzidine derivative (generic name).
- 721.1680 Substituted benzoic acid (generic).
- 721.1700 Halonitrobenzoic acid, substituted (generic name).
- 721.1705 Benzoic acid, 3-amino-, diazotized, coupled with 6-amino-4-hydroxy-2-naphthalenesulfonic acid, diazotized, (3-aminophenyl)phosphonic acid and diazotized 2,5-diethoxybenzenamine.

- 721.1725 Benzoic acid, 3,3'-methylenebis [6 amino-, di-2-propenyl ester.
- 721.1728 Benzoic acid, 2-(3-phenylbutylidene)amino-, methyl ester.
- 721.1729 Boric acid ( $H_3BO_3$ ), mixed esters with polyethylene glycol mono-Bu ether and polyethylene glycol mono Me ether.
- 721.1730 Poly(oxy-1,2-ethanediyl),  $\alpha$ -butyl- $\omega$ -hydroxy, ester with boric acid ( $H_3BO_3$ ).
- 721.1731 Poly(oxy-1,2-ethanediyl),  $\alpha$ -methyl- $\omega$ -hydroxy, ester with boric acid ( $H_3BO_3$ ).
- 721.1732 Nitrobenzoic acid octyl ester.
- 721.1734 Substituted benzonitrile (generic).
- 721.1735 Alkylbisoxoalkyl (substituted-1,1-dimethylethylphenyl) benzotriazole (generic name).
- 721.1738 Substituted benzotriazole (generic name).
- 721.1745 Ethoxybenzothiazole disulfide.
- 721.1747 Substituted benzophenone (generic).
- 721.1750 1*H*-Benzotriazole, 5-(pentyloxy)- and 1*H*-benzotriazole, 5-(pentyloxy)-, sodium and potassium salts.
- 721.1755 Methylenebisbenzotriazole.
- 721.1760 Substituted benzotriazole derivatives.
- 721.1765 2-Substituted benzotriazole.
- 721.1767 Substituted 6,6'-(1-methylethylidene)bis[3,4-dihydro-3-phenyl-1,3-benzoxazine] (generic).
- 721.1775 6-Nitro-2(3*H*)-benzoxazolone.
- 721.1790 Polybrominated biphenyls.
- 721.1800 3,3',5,5'-Tetramethylbiphenyl-4,4'-diol.
- 721.1805 Substituted bisaniline.
- 721.1820 Bisphenol derivative.
- 721.1825 Bisphenol A, epichlorohydrin, polyalkylene polyol and polyisocyanate derivative.
- 721.1850 Toluene sulfonamide bisphenol A epoxy adduct.
- 721.1852 Di-alkyl borane (generic).
- 721.1875 Boric acid, alkyl and substituted alkyl esters (generic name).
- 721.1878 Alkali metal alkyl borohydride (generic).
- 721.1880 Borate(1-), tris(acetato- $\kappa$ .O)hydro-, sodium, (T-4)-.
- 721.1900 Substituted bromothiophene.
- 721.1907 Butanamide, 2,2'-[3'dichloro[1,1'-biphenyl]-4,4'-diyl]bisazobis *N*-2,3-dihydro-2-oxo-1*H*-benzimidazol-5-yl)-3-oxo-.
- 721.1920 1,4-Bis(3-hydroxy-4-benzoylphenoxy)butane.
- 721.1925 Substituted carboheterocyclic butane tetracarboxylate (generic).
- 721.1930 Butanoic acid, antimony (3=) salt.
- 721.1950 2-Butenedioic acid (*Z*), mono(2-((1-oxopropenyloxy)ethyl) ester).
- 721.2025 Substituted phenylimino carbamate derivative.
- 721.2060 Disubstituted benzenedicarboxylic acid (generic).
- 721.2075 Carbamodithioic acid, methyl-, compound with methanamine (1:1).
- 721.2076 D-Glucuronic acid, polymer with 6-deoxy-L-mannose and D-glucose, acetate, calcium magnesium potassium sodium salt.
- 721.2077 Substituted carbazate (generic).
- 721.2078 1-Piperidinecarboxylic acid, 2-[(dichloro-hydroxy-carbomonocycle)hydrazono]-, methyl ester (generic).
- 721.2079 Dichloro, hydroxy, hydrazino-carbomonocycle (generic).
- 721.2081 Dichloro, hydroxy, hydrazino-carbomonocycle-monohydrochloride (generic).
- 721.2083 Polysubstituted carbomonocyclic hydroxylamine (generic).
- 721.2084 Carbon oxyfluoride (Carbonic difluoride).
- 721.2085 Hydroxyalkylquinoline dioxoindandialkylcarboxamide.
- 721.2086 Coco acid triamine condensate, polycarboxylic acid salts.
- 721.2087 3-furancarboxaldehyde, tetrahydro-.
- 721.2088 Carboxylic acids, (C6-C9) branched and linear.
- 721.2089 Tetrasubstituted aminocarboxylic acid.
- 721.2091 Chloroalkane.
- 721.2092 3-Methylcholanthrene.
- 721.2093 Alkenyl carboxylate, metal salt (generic).
- 721.2094 *N,N*-di(alkyl heteromonocycle)amino chlorotriazine.
- 721.2095 Chromate(3), bis 2-[[substituted-3-[(5-sulfo-1-naphthalenyl)azo]phenyl]azo]substituted monocycle, trisodium (generic name).
- 721.2097 Azo chromium complex dyestuff preparation (generic name).
- 721.2098 Aliphatic polycarboxylic acid metal salt (generic).
- 721.2120 Cyclic amide.
- 721.2121 Thiosubstituted carbonate ester (generic).
- 721.2122 Substituted phenyl azo substituted sulfo carbopolycycle.
- 721.2140 Carbopolycyclic azoalkylaminoalkylcarbomonocyclic ester, halogen acid salt.
- 721.2145 Ceteareth-25 sorbate.
- 721.2155 Alkoxyamino-alkyl-coumarin (generic).
- 721.2175 Salt of cyclodiamine and mineral acid.
- 721.2222 Cyclohexanamine, *N,N*-dimethyl-, compd. with alpha-isotridecyl-omega-hydroxypoly(oxy-1,2-ethanediyl) phosphate.
- 721.2250 1,4-Cyclohexanediamine, *cis*- and *trans*-.
- 721.2260 1,2-Cyclohexanedicarboxylic acid, 2,2-bis[[[2-[(oxiranylmethoxy) carbonyl]cyclohexyl]carbonyl]oxy]methyl]-1,3-propanediyl bis(oxiranylmethyl) ester.
- 721.2265 Polyalkylene oxide dialkylamine (generic).

Environmental Protection Agency

Pt. 721

- 721.2270 Aliphatic dicarboxylic acid salt.  
 721.2275 *N,N,N',N'*-Tetrakis(oxiranyl methyl)-1,3-cyclohexane dimethanamine.  
 721.2280 Cyclopropanecarboxaldehyde.  
 721.2287 DDT  
 (Dichlorodiphenyltrichloroethane).  
 721.2340 Dialkenylamide (generic name).  
 721.2345 Alkyletherpropyl dialkylamines.  
 721.2350 Alkyltri, tetra, and pentaamines.  
 721.2355 Diethylstilbestrol.  
 721.2380 Disubstituted diamino anisole.  
 721.2385 Fluoroalkyl diester (generic).  
 721.2410 Alkoxyated  
 alkyl diethylenetriamine, alkyl sulfate salts.  
 721.2420 Alkoxyated dialkyldiethylenetriamine, alkyl sulfate salt.  
 721.2465 Xanthylum, 9-(2-(ethoxycarbonyl)phenyl)-3,6-bis(ethylamino)-2,7-dimethyl-, ethyl sulfate.  
 721.2475 Dimetridazole.  
 721.2480 Isoalkyldimethylamine (generic).  
 721.2485 1,3-Dioxolane, 2-ethenyl-.  
 721.2520 Alkylated diphenyls.  
 721.2527 Substituted diphenylazo dye (generic name).  
 721.2532 Substituted diphenylmethane (generic).  
 721.2535 Benzene, 1,1'-methylanebis[4-isocyanato-, homopolymer, Bu alc.-blocked].  
 721.2540 Diphenylmethane diisocyanate (MDI) modified.  
 721.2560 Alkylated diphenyl oxide (generic name).  
 721.2565 Alkylated sulfonated diphenyl oxide, alkali and amine salts.  
 721.2570 Alkylated diphenyls (generic).  
 721.2575 Disubstituted diphenylsulfone.  
 721.2577 Copper complex of (substituted sulfonaphthyl azo substituted phenyl) disulfonaphthyl azo, amine salt (generic).  
 721.2580 C.I. Disperse Red 152 (generic).  
 721.2582 Reaction product of alkylene diamine, MDI, substituted carbomonocyclic amine and alkylamine (generic).  
 721.2584 Dodecanoic acid, 12-amino-.  
 721.2585 Sodium salts of dodecylphenol (generic).  
 721.2600 Epibromohydrin.  
 721.2625 Reaction product of alkanediol and epichlorohydrin.  
 721.2673 Aromatic epoxide resin (generic).  
 721.2675 Perfluoroalkyl epoxide (generic name).  
 721.2685 Polyisobutene epoxide (generic).  
 721.2725 Trichlorobutylene oxide.  
 721.2752 Epoxy resin containing phosphorus (generic).  
 721.2755 Cycloaliphatic epoxy resin (generic).  
 721.2800 Erionite fiber.  
 721.2805 Acrylate ester.  
 721.2825 Alkyl ester (generic name).  
 721.2900 Substituted aminobenzoic acid ester (generic name).  
 721.2920 *tert*-Amyl peroxy alkylene ester (generic name).  
 721.2925 Brominated aromatic ester.  
 721.2950 Carboxylic acid glycidyl esters.  
 721.3000 Dicarboxylic acid monoester.  
 721.3020 1,1-Dimethylpropyl peroxyester (generic name).  
 721.3025 Fatty acids C<sub>12-18</sub>, C<sub>18</sub> unsaturated, C<sub>12-18</sub> alkyl esters (generic).  
 721.3031 Boric acid (H<sub>3</sub>BO<sub>3</sub>), zinc salt (2=3).  
 721.3032 Boric acid (H<sub>3</sub>BO<sub>2</sub>), zinc salt.  
 721.3034 Methylamine esters.  
 721.3062 Haloarylalkylketoester (generic).  
 721.3063 Substituted phenyl azo substituted phenyl esters (generic name).  
 721.3080 Substituted phosphate ester (generic).  
 721.3085 Brominated phthalate ester.  
 721.3100 Oligomeric silicic acid ester compound with a hydroxylalkylamine.  
 721.3110 Polycarboxylic acid ester (generic).  
 721.3130 Sulfuric acid, mono-C<sub>9-11</sub>-alkyl esters, sodium salts.  
 721.3135 Phosphorous modified epoxy resin (generic).  
 721.3140 Vinyl epoxy ester.  
 721.3152 Ethanaminium, *N*-ethyl-2-hydroxy-*N,N*-bis(2-hydroxyethyl)-, diester with C<sub>12-18</sub> fatty acids, ethyl sulfates (salts).  
 721.3155 3,8-Dioxa-4,7-disiladecane, 4,4,7,7-tetraethoxy-.  
 721.3160 1-Chloro-2-bromoethane.  
 721.3220 Pentachloroethane.  
 721.3248 Ethane, 1,2,2-trichlorodifluoro-.  
 721.3260 Ethanediimidic acids.  
 721.3310 Poly[oxy(methyl-1,2-ethanediyl)], $\alpha$ -(1-oxo-2-propenyl)- $\omega$ -[(tetrahydro-2-furanyl)methoxy]-.  
 721.3320 Ethanol, 2-amino-, compound with *N*-hydroxy-*N*-nitrosobenzenamine (1:1).  
 721.3340 Ethanol, 2,2'-(hexylamino)bis-.  
 721.3350 *N*-Nitrosodiethanolamine.  
 721.3360 Substituted ethanolamine.  
 721.3364 Aliphatic ether.  
 721.3374 Alkylenediolalkyl ether.  
 721.3380 Anilino ether.  
 721.3420 Brominated arylalkyl ether.  
 721.3430 4-Bromophenyl phenyl ether.  
 721.3435 Butoxy-substituted ether alkane.  
 721.3437 Dialkyl ether.  
 721.3438 Chlorohydroxyalkyl butyl ether (generic).  
 721.3440 Haloalkyl substituted cyclic ethers.  
 721.3465 Stilbene diglycidyl ether.  
 721.3480 Halogenated biphenyl glycidyl ethers.  
 721.3485 Hydrofluorocarbon alkyl ether.  
 721.3486 Polyglycerin mono(4-nonylphenyl) ether.  
 721.3488 Poly(oxy-1,2-ethanediyl), alpha substituted-omega-hydroxy-, C<sub>16-20</sub> alkyl ethers.  
 721.3500 Perhalo alkoxy ether.  
 721.3520 Aliphatic polyglycidyl ether.  
 721.3550 Dipropylene glycol dimethyl ether.



## Pt. 721

## 40 CFR Ch. I (7-1-10 Edition)

- 721.3560 Derivative of tetrachloroethylene.
- 721.3565 Ethylenediamine, substituted, sodium salt.
- 721.3620 Fatty acid amine condensate, polycarboxylic acid salts.
- 721.3625 Fatty acid amine salt (generic name).
- 721.3627 Branched synthetic fatty acid.
- 721.3629 Triethanolamine salts of fatty acids.
- 721.3635 Octadecanoic acid, ester with 1,2-propanediol, phosphate, anhydride with silicic acid (H<sub>4</sub>SiO<sub>4</sub>).
- 721.3680 Ethylene oxide adduct of fatty acid ester with pentaerythritol.
- 721.3700 Fatty acid, ester with styrenated phenol, ethylene oxide adduct.
- 721.3710 Polyether modified fatty acids (generic).
- 721.3720 Fatty amide.
- 721.3740 Bisalkylated fatty alkyl amine oxide
- 721.3760 Fluorene-containing diaromatic amines.
- 721.3764 Fluorene substituted aromatic amine.
- 721.3780 Substituted and disubstituted tetrafluoro alkenes (generic).
- 721.3790 Polyfluorocarboxylates.
- 721.3800 Formaldehyde, condensed polyoxyethylene fatty acid, ester with styrenated phenol, ethylene oxide adduct.
- 721.3805 Formaldehyde, reaction products with 1,3-benzenedimethanamine and bisphenol A.
- 721.3807 Formaldehyde, polymer with phenol and 1,2,3-propanetriol, methylated.
- 721.3810 Formaldehyde, polymers with substituted phenols (generic).
- 721.3812 Substituted phenols and formaldehyde polymer, alkylated (generic).
- 721.3815 Furan, 2-(ethoxymethyl)-tetrahydro-
- 721.3818 Furan, octafluorotetrahydro-
- 721.3820 L-Glutamic acid, N-(1-oxododecyl)-, disodium salt.
- 721.3821 L-Gutamic acid, N-(1-oxododecyl)-.
- 721.3830 Formaldehyde, reaction products with an alkylated phenol and an aliphatic amine (generic).
- 721.3835 Chloroformate (generic).
- 721.3840 Tetraglycidalamines (generic name).
- 721.3845 Alkyl substituted aromatic glycidyl ether (generic).
- 721.3848 Glycine, N-(carboxymethyl)-N-dodecyl-, monosodium salt.
- 721.3860 Glycol monobenzoate.
- 721.3880 Polyalkylene glycol substituted acetate.
- 721.3900 Alkyl polyethylene glycol phosphate, potassium salt.
- 721.4000 Polyoxy alkylene glycol amine.
- 721.4040 Glycols, polyethylene-, 3-sulfo-2-hydroxypropyl-*p*-(1,1,3,3-tetramethylbutyl)phenyl ether, sodium salt.
- 721.4060 Alkylene glycol terephthalate and substituted benzoate esters (generic name).
- 721.4080 MNNG (N-methyl-N'-nitro-N-nitrosoguanidine).
- 721.4085 Guanidine, pentaethyl-
- 721.4090 Ethanaminium, N-[bis(diethylamino)-methylene]-N-ethyl-, bromide.
- 721.4095 Quaternary ammonium alkyltherpropyl trialkylamine halides.
- 721.4096 Substituted anilino halobenzamide (generic).
- 721.4097 7-Oxabicyclo[4.1.0]heptane-3-carboxylic acid, methyl ester.
- 721.4098 Substituted heteroaromatic-2[[4-(dimethylamino) phenyl]azo]-3-methyl-, salts (generic).
- 721.4100 Tris(disubstituted alkyl) heterocycle.
- 721.4105 Bicyclo[2.2.1]hept-2-ene, 5-butyl-
- 721.4106 Bicyclo[2.2.1]hept-2-ene, 5-hexyl-
- 721.4107 Bicyclo[2.2.1]hept-2-ene, 5-octyl-
- 721.4108 Bicyclo[2.2.1]hept-2-ene, 5-decyl-
- 721.4110 Allyloxysubstituted heterocycle.
- 721.4128 Dimethyl-3-substituted heteromonocycle.
- 721.4133 Dimethyl-3-substituted heteromonocyclic amine.
- 721.4136 Alkyl heteropolycyclic-aniline (generic).
- 721.4140 Hexachloronorbornadiene.
- 721.4155 Hexachloropropene.
- 721.4158 Hexadecanoic acid, ethenyl ester.
- 721.4160 Hexafluoropropylene oxide.
- 721.4180 Hexamethylphosphoramide.
- 721.4215 Hexanedioic acid, diethenyl ester.
- 721.4250 Hexanoic acid, 2-ethyl-, ethenyl ester.
- 721.4255 1,4,7,10,13,16-Hexaoxacyclooctadecane, 2-[(2-propenyl oxy)methyl]-.
- 721.4257 Hydrazine, (2-fluorophenyl).
- 721.4258 Substituted naphthalene hydrazide (generic).
- 721.4259 Aliphatic polyisocyanate homopolymer.
- 721.4260 Hydrazine, [4-(1-methylbutoxy)phenyl]-, monohydrochloride.
- 721.4265 Hydrazinecarboxamide, N-(3,5-difluorophenyl)-.
- 721.4270 Nitrophenoxylalkanoic acid substituted thiazino hydrazide (generic name).
- 721.4280 Substituted hydrazine.
- 721.4300 Hydrazinecarboxamide, N,N'-1,6-hexanedylbis [2,2-dimethyl-].
- 721.4320 Hydrazinecarboxamide, N,N'-(methylenedi-4,1-phenylene)bis [2,2-dimethyl-].
- 721.4340 Substituted thiazino hydrazine salt (generic name).
- 721.4360 Certain hydrogen containing chlorofluorocarbons.
- 721.4365 Substituted ethoxylated hydrocarbon (generic).
- 721.4380 Modified hydrocarbon resin.

**Environmental Protection Agency**

**Pt. 721**

- 721.4385 Hydrofluoric acid, reaction products with heptane.
- 721.4390 Trisubstituted hydroquinone diester.
- 721.4420 Substituted hydroxylamine.
- 721.4460 Amidinothiopropionic acid hydrochloride.
- 721.4461 Hydrofluoric acid, reaction products with octane (generic).
- 721.4462 Hydrochlorofluorocarbon.
- 721.4463 Hydrochlorofluorocarbon.
- 721.4464 Mixture of hydrofluoro alkanes and hydrofluoro alkene.
- 721.4465 Hydrofluoroalkane.
- 721.4467 Quaternary ammonium hydroxide.
- 721.4468 1H-Imidazole, 2-ethyl-4,5-dihydro-4-methyl-.
- 721.4469 Imidazolethione.
- 721.4470 2,4-Imidazolidinedione, bromochloro-5,5-dimethyl-.
- 721.4472 Phenyl, alkyl, hydroxyalkyl substituted imidazole (generic).
- 721.4473 Dialkylamidoimidazoline.
- 721.4476 Substituted imines.
- 721.4480 2-Imino-1,3-thiazin-4-one-5,6-dihydromonohydrochloride.
- 721.4484 Halogenated indane (generic name).
- 721.4486 Propanoic acid, 2-methyl-, (1R,2R,4R)-1,7,7-trimethylbicyclo[2.2.1]hept-2-yl ester, rel-.
- 721.4490 Capped aliphatic isocyanate.
- 721.4494 Polycyclic isocyanate.
- 721.4497 Aliphatic polyisocyanates (generic name).
- 721.4500 Isopropylamine distillation residues and ethylamine distillation residues.
- 721.4520 Isopropylidene, bis(1,1-dimethylpropyl) derivative.
- 721.4550 Diperoxy ketal.
- 721.4565 Modified hydroxystyrene homopolymer (generic).
- 721.4568 Methylpolychloro aliphatic ketone.
- 721.4575 L-aspartic acid, *N,N'*-[(1E) - 1,2-ethenediylbis[(3-sulfo-4, 1-phenylene)imino [6-(phenylamino)-1,3,5-triazine-4,2- diyl]]]bis-, hexasodium salt.
- 721.4585 Lecithins, phospholipase A2-hydrolyzed.
- 721.4587 Lithium manganese oxide (LiMn2O4) (generic name).
- 721.4589 Propanedioic acid, [(4-methoxyphenyl)methylene]-, bis(1,2,2,6,6-pentamethyl-4-piperidinyl) ester (9CI).
- 721.4590 Mannich-based adduct.
- 721.4594 Substituted azo metal complex dye.
- 721.4596 Diazo substituted carbomonocyclic metal complex.
- 721.4600 Recovered metal hydroxide.
- 721.4610 Mixed metal oxides (generic).
- 721.4620 Dialkylamino alkanoate metal salt.
- 721.4660 Alcohol, alkali metal salt.
- 721.4663 Fluorinated carboxylic acid alkali metal salts.
- 721.4668 Hydrated alkaline earth metal salts of metalloid oxyanions.
- 721.4680 Metal salts of complex inorganic oxyacids (generic name).
- 721.4685 Substituted purine metal salt (generic name).
- 721.4700 Metalated alkylphenol copolymer (generic name).
- 721.4720 Disubstituted phenoxazine, chlorometalate salt.
- 721.4740 Alkali metal nitrites.
- 721.4792 2-Propenoic acid, 2-methyl-, C<sub>11-14</sub>-isoalkyl esters, C<sub>13</sub>-rich.
- 721.4794 Polypiperidinol-acrylate methacrylate.
- 721.4820 Methane, bromodifluoro-.
- 721.4840 Substituted triphenylmethane.
- 721.4880 Methanol, trichloro-, carbonate (2:1).
- 721.4885 Methanone, [5-[[[3-(2H-benzotriazol-2-yl)-2-hydroxy-5-(1,1,3,3-tetramethylbutyl)phenyl]methyl]-2-hydroxy-4-(octyloxy) phenyl]phenyl-.
- 721.4925 Methyl n-butyl ketone.
- 721.5050 2,2'-[(1-Methylethylidene)bis[4,1-phenyloxy[1-(butoxymethyl)-(2,1-ethanediyloxy)methylene]]]bisoxirane, reaction product with a diamine.
- 721.5075 Mixed methyltin mercaptoester sulfides.
- 721.5175 Mitomycin C.
- 721.5185 Morpholine, 4-(1-oxo-2-propenyl)-.
- 721.5192 Substituted 1,6-dihydroxy naphthalene.
- 721.5200 Disubstituted phenylazo trisubstituted naphthalene.
- 721.5225 Naphthalene,1,2,3,4-tetrahydro(1-phenylethyl) (specific name).
- 721.5250 Trimethyl spiropolyheterocyclic naphthalene compound.
- 721.5252 2-Naphthalenecarboxylic acid, 4,4'-methylenebis [3-hydroxy-, zinc salt.
- 721.5253 2-Naphthalenecarboxylic acid, 4,4'-methylenebis [3-hydroxy-, strontium salt.
- 721.5255 2-Naphthalenol, mono and dioctyl derivs.
- 721.5260 1,3,6-Naphthalenetrisulfonic acid, 7-[[2-[(aminocarbonyl)amino]-4-[[4-[[2-[2-(ethenylsulfonyl)ethoxy]ethyl]amino]-6-fluoro-1,3,5-triazin-2-yl]amino]phenyl]azo], trisodium salt.
- 721.5262 2,7-Naphthalenedisulfonic acid, 5-[[4-chloro-6-[substituted] amino]-1,3,5-triazin-2-yl]amino]-4-hydroxy-3-[(1-sulfo-2-naphthalenyl)azo]-, trisodium salt (generic).
- 721.5275 2-Naphthalenecarboxamide-N-aryl-3-hydroxy-4-arylozo (generic name).
- 721.5276 2-Naphthalenol, heptyl-1-[[[4-phenylazo]phenyl]azo]-, *ar'*, *ar''*-Me derivs.
- 721.5278 Substituted naphthalenesulfonic acid, alkali salt.
- 721.5279 2,7-Naphthalenedisulfonic acid, 4-amino-3-[[4'-amino-4-[(3-butoxy-2-hydroxypropyl)amino]phebyl]azo]-3,3'-dimethyl[1,1'-biphenyl]-4-yl]azo]-5-hydroxy-6-(phenylazo)-, disodium salt.

- 721.5280 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-, coupled with diazotized 4-butylbenzenamine, diazotized 4,4'-cyclohexylidenebis[benzenamine] and m-phenylenediamine, sodium salt.
- 721.5281 2-Naphthalenesulfonic acid, 3-[[4-[(2,4-dimethyl-6-sulfophenyl)azo]-2-methoxy-5-methylphenyl]azo]-4-hydroxy-7-(phenylamino)-, sodium salt, compd. With 2,2',2''-nitrioltris [ethanol] (9CI).
- 721.5282 Trisodium chloro [(trisubstituted heteromonocycle amino) propylamino]triazinylamino hydroxyazo naphthalenetrisulfonate.
- 721.5283 Cobaltate (5-), bis[4-[[6-[(4-amino-6-chloro-1,3,5-triazin-2-yl)amio]-1-hydroxy-3-sulfo-2-naphthalenyl]azo]-3-hydroxy-7-nitro-1-naphthalenesulfonato(4-)-], pentasodium.
- 721.5284 Chromate (5-), bis[4-hydroxy-7-[(2-hydroxy-1-naphthalenyl)azo]-3-[(2-hydroxy-3-nitro-5-sulfophenyl)azo]-2-naphthalenesulfonato(4-)-], pentasodium.
- 721.5285 Ethoxylated substituted naphthol.
- 721.5286 Benzenediazonium, [(((substituted)azo]phenyl)sulfonyl]amino]-, coupled with aminophenol, diazotized aminobenzoic acid, diazotized (substituted) benzenesulfonic acid and naphthalenol (generic).
- 721.5288 Chromate(2-), [3-hydroxy-4-[(2-hydroxy-1-naphthenyl)azo]-7-nitro-1-substituted][N-[7-hydroxy-8-[(2-hydroxy-5-nitrophenyl)azo]-1-substituted]-, salt (generic).
- 721.5290 Phenylazoalkoxy naphthylamines (generic).
- 721.5293 Poly(oxy-1,2-ethanediyl), alpha-(9Z)-9-octadecenyl-.omega.-hydroxy-, phosphate, ammonium salt.
- 721.5310 Neononanoic acid, ethenyl ester.
- 721.5315 Nickel, cobalt mixed metal oxide (generic).
- 721.5325 Nickel acrylate complex.
- 721.5330 Nickel salt of an organo compound containing nitrogen.
- 721.5340 Substituted benzothiazole-azo-substituted benzoquinoline nickel complex (generic).
- 721.5350 Substituted nitrile (generic name).
- 721.5356 Ethanol, 2,2'2''-nitrioltris-, compound with alpha-2,4,6-tris (1-phenylethyl)phenyl]-omega-hydroxypoly (oxy-1,2-ethanediyl) phosphate.
- 721.5358 2-propanol, 1,1',1'-nitrioltris-, compds. with ethanol 2-[2-(C<sub>12-14</sub>-alkyloxy) ethoxy] derivs. hydrogen sulfates.
- 721.5360 Substituted nitrobenzene (generic).
- 721.5375 Nitrothiophenecarboxylic acid, ethyl ester, bis[(((substituted) amino]alkylphenyl)azo] (generic name).
- 721.5378 9-Phosphabicyclo[3.3.1]nonane,9,9'-(1,2-ethanediyl)bis- (9CI).
- 721.5380 Mixed alkyl phenolic novolak resin (generic).
- 721.5385 Octanoic acid, hydrazide.
- 721.5400 3,6,9,12,15,18,21-Heptaooxatetra-trioctanoic acid, sodium salt.
- 721.5425  $\alpha$ -Olefin sulfonate, potassium salts.
- 721.5450  $\alpha$ -Olefin sulfonate, sodium salt.
- 721.5452 Alkali metal salt of halogenated organoborate (generic).
- 721.5454 Methylum, triphenyl-, tetrakis(pentafluorophenyl) borate (1-).
- 721.5460 Organosolv lignin.
- 721.5465 Amine salt of organic acid (generic).
- 721.5475 1-Oxa-4-azaspiro[4.5]decane, 4-dichloroacetyl-.
- 721.5500 7-Oxabicyclo[4.1.0]heptane, 3-ethenyl, homopolymer, ether with 2-ethyl-2-(hydroxymethyl)-1,3-propanediol (3:1), epoxidized.
- 721.5525 Substituted spiro oxazine.
- 721.5540 1*H*,3*H*,5*H*-oxazolo [3,4-*c*] oxazole, dihydro-7*a*-methyl-.
- 721.5545 3-(Dichloroacetyl)-5-(2-furanyl)-2,2-dimethyl-oxazolidine.
- 721.5546 Halogen substituted oxetanes (generic).
- 721.5547 Antimony double oxide.
- 721.5548 Mixed metal oxide (generic).
- 721.5549 Lithiated metal oxide.
- 721.5550 Substituted dialkyl oxazolone (generic name).
- 721.5560 Formaldehyde, polymer with (chloromethyl) oxirane and phenol, reaction products with 6*H*-dibenz[*c,e*][1,2]oxaphosphorin-6-oxide.
- 721.5575 Oxirane, 2,2'-(1,6-hexanedyl)bis (oxymethylene) bis-.
- 721.5580 Oxirane, 2,2'-[methylenebis[(2,6-dimethyl-4,1-phenylene)oxymethylene]]bis-.
- 721.5585 4,4'-(1-methylethylidene)bisphenol, polymer with (chloromethyl)oxirane and a diamine (generic).
- 721.5590 Oxirane, [(((1*R*,2*S*,5*R*)-5-methyl-2-(1-methylethyl)cyclohexyl]oxy)methyl]-.
- 721.5600 Substituted oxirane.
- 721.5625 Oxiranemethanamine, *N,N'*-[methylenebis(2-ethyl-4,1-phenylene)]bis[N-(oxiranymethyl)]-.
- 721.5645 Pentane 1,1,1,2,3,4,4,5,5,5-decafluoro.
- 721.5650 Pentanediol light residues.
- 721.5700 Pentanenitrile, 3-amino-.
- 721.5708 2-Pentene, 1,1,1,2,3,4,4,5,5,5-decafluoro-.
- 721.5710 Phenacetin.
- 721.5713 Phenol - biphenyl polymer condensate (generic).
- 721.5740 Phenol, 4,4'-methylenebis (2,6-dimethyl-.
- 721.5760 Phenol, 4,4'-[methylenebis (oxy-2,1-ethanediylthio)]bis-.
- 721.5762 Aromatic aldehyde phenolic resin (generic).
- 721.5763 Methylenebisbenzotriazolyl phenols.

**Environmental Protection Agency**

**Pt. 721**

- 721.5769 Mixture of nitrated alkylated phenols.
- 721.5775 Phenol, 5-amino-2,4-dichloro-, hydrochloride.
- 721.5780 Phenol, 4,4'-(oxybis(2,1-ethanedithio)bis-
- 721.5800 Sulfurized alkylphenol.
- 721.5820 Aminophenol.
- 721.5840 Ethylated aminophenol.
- 721.5860 Methylphenol, bis(substituted)alkyl.
- 721.5867 Substituted phenol.
- 721.5880 Sulfur bridged substituted phenols (generic name).
- 721.5900 Trisubstituted phenol (generic name).
- 721.5905 Modified phenolic resin (generic).
- 721.5908 Modified phenolic resin (generic).
- 721.5912 Phenoxazin-5-ium, 3-dialkylamino-7-arylamino-, salt (generic).
- 721.5913 Phenothiazine derivative.
- 721.5914 Polysubstituted bis phenylazonaphthalene disulfonic acid (generic).
- 721.5915 Polysubstituted phenylazopoly-substitutedphenyl dye.
- 721.5917 Phenyl azo dye (generic).
- 721.5920 Phenyl(disubstitutedpolycyclic).
- 721.5925 Bis heterocyclic phenylene derivative (generic).
- 721.5930 Phenylenebis(imino (chlorotriazinyl)-imino (substituted naphthyl)azo (substituted phenyl)azo, sodium salt (generic name).
- 721.5935 Alkylated nitroso-phenylenediamine (generic).
- 721.5960 *N,N'*-Bis(2-(2-(3-alkyl)thiazoline)vinyl)-1,4-phenylenediamine methyl sulfate double salt (generic name).
- 721.5965 Substituted S-phenylthiazole (generic).
- 721.5970 Phosphated polyarylphenol ethoxylate, potassium salt.
- 721.5980 Dialkyl phosphorodithioate phosphate compounds.
- 721.5985 Fatty alkyl phosphate, alkali metal salt (generic).
- 721.5995 Polyalkyl phosphate.
- 721.6000 Tris (2,3-dibromopropyl) phosphate.
- 721.6005 Rare earth phosphate (generic).
- 721.6020 Phosphine, dialkylphenyl.
- 721.6045 Phosphinothioic acid, bis(2,4,4-trimethylpentyl)- (9CI).
- 721.6060 Alkylaryl substituted phosphite.
- 721.6070 Alkyl phosphonate ammonium salts.
- 721.6075 Phosphonic acid, 1,1-methylenebis-tetrakis(1-methylethyl) ester.
- 721.6078 Substituted ethoxyethylamine phosphonate.
- 721.6080 Phosphonium salt (generic name).
- 721.6085 Phosphonocarboxylate salts.
- 721.6090 Phosphoramidate.
- 721.6097 Phosphoric acid derivative (generic name).
- 721.6100 Phosphoric acid, C<sub>6-12</sub>-alkyl esters, compounds with 2-(dibutylamino) ethanol.
- 721.6110 Alkyldi(alkyloxyhydroxypropyl) derivative, phosphoric acid esters, potassium salts.
- 721.6120 Phosphoric acid, 1,2-ethanediyl tetrakis(2-chloro-1-methylethyl) ester.
- 721.6140 Dialkyldithiophosphoric acid, aliphatic amine salt.
- 721.6160 Piperazinone, 1,1',1''-[1,3,5-triazine-2,4,6-triyltris[(cyclohexylimino)-2,1-ethanediyl]]tris-[3,3,4,5,5-pentamethyl]-.
- 721.6165 Polysubstituted piperidine.
- 721.6167 Piperdinium, 1,1-dimethyl-, chloride.
- 721.6170 Siloxanes and silicones, Me hydrogen, reaction products with 2,2,6,6-tetramethyl-4-(2-propenyloxy)piperidine.
- 721.6175 2-Piperdinone, 1,3-dimethyl-,.
- 721.6176 2-Piperdinone, 1,5-dimethyl-,.
- 721.6178 Alkylaminated polyolefin (generic).
- 721.6180 Polyalkylene glycol polyamide ester phosphate (generic).
- 721.6181 Fatty acid, reaction product with substituted oxirane, formaldehyde-phenol polymer glycidyl ether, substituted propylamine and polyethylenepolyamines (generic).
- 721.6183 Amides, from ammonium hydroxide - maleic anhydride polymer and hydrogenated tallow alkyl amines, sodium salts, compds. with ethanolamine.
- 721.6186 Polyamine dithiocarbamate.
- 721.6193 Polyalkylene polyamine.
- 721.6196 Hydrochloride salt of a fatty polyalkylene polyamine (generic).
- 721.6200 Fatty acid polyamine condensate, phosphoric acid ester salts.
- 721.6205 Hexamethylenediamine adduct of substituted piperidinyloxy (generic).
- 721.6220 Aryl sulfonate of a fatty acid mixture, polyamine condensate.
- 721.6440 Polyamine ureaformaldehyde condensate (specific name).
- 721.6470 Polyaminopolyacid.
- 721.6475 Alkyl polycarboxylic acids, esters with ethoxylated fatty alcohols.
- 721.6477 Alkyl polycarboxylic acids, esters with ethoxylated fatty alcohols, reaction products with maleic anhydride.
- 721.6479 Tetrahydroheteropolycycle (generic).
- 721.6485 Hydroxy terminated polyester.
- 721.6490 Alkyl phenyl polyetheramines.
- 721.6493 Amidoamine modified polyethylene glycol (generic).
- 721.6495 Aliphatic polyisocyanate.
- 721.6498 Modified polyisocyanates (generic).
- 721.6505 Polymers of C<sub>13</sub>C<sub>15</sub> oxoalcohol ethoxalates.
- 721.6515 Polymer of polyalkylenepolyol and trisubstituted phenol (generic).
- 721.6520 Acrylamide, polymer with substituted alkylacrylamide salt (generic name).

- 721.6540 Acrylamide, polymers with tetraalkyl ammonium salt and polyalkyl, aminoalkyl methacrylamide salt.
- 721.6560 Acrylic acid, polymer with substituted ethene.
- 721.6620 Alkanaminium, polyalkyl-[(2-methyl-1-oxo-2-propenyl)oxy] salt, polymer with acrylamide and substituted alkyl methacrylate.
- 721.6660 Polymer of alkanepolyol and polyalkylpolyisocyanatocarbomonocycle, acetone oxime-blocked (generic name).
- 721.6680 Alkanoic acid, butanediol and cyclohexanealkanol polymer (generic name).
- 721.6900 Polymer of bisphenol A diglycidal ether, substituted alkenes, and butadiene.
- 721.6920 Butyl acrylate, polymer with substituted methyl styrene, methyl methacrylate, and substituted silane.
- 721.6980 Dimer acids, polymer with polyalkylene glycol, bisphenol A-diglycidyl ether, and alkylene polyols polyglycidyl ethers (generic name).
- 721.7000 Polymer of disodium maleate, allyl ether, and ethylene oxide.
- 721.7020 Distillates (petroleum), C(3-6), polymers with styrene and mixed terpenes (generic name).
- 721.7046 Formaldehyde, polymer with substituted phenols, glycidyl ether.
- 721.7160 2-Oxepanone, polymer with 4,4'-(1-methylethylidene)bisphenol and 2,2-[(1-methylethylidene)bis(4,1-phenyleneoxymethylene)]bisoxirane, graft.
- 721.7200 Perfluoroalkyl aromatic carbamate modified alkyl methacrylate copolymer.
- 721.7210 Epoxidized copolymer of phenol and substituted phenol.
- 721.7220 Polymer of substituted phenol, formaldehyde, epichlorohydrin, and disubstituted benzene.
- 721.7250 Polyaziridinyl ester of an aliphatic alcohol (generic).
- 721.7255 Polyethyleneamine crosslinked with substituted polyethylene glycol (generic).
- 721.7260 Polymer of polyethylenepolyamine and alkanediol diglycidyl ether.
- 721.7270 1-propanaminium, 3-amino-, *N,N,N*-trimethyl-*N*-soya acyl derivs., chloride.
- 721.7280 1,3-Propanediamine, *N,N'*-1,2-ethanediylbis-, polymer with 2,4,6-trichloro-1,3,5-triazine, reaction products with *N*-butyl-2,2,6,6-tetramethyl-4-piperidinamine.
- 721.7285 Amines, *N*-cocoalkyltrimethylenedi-, citrates.
- 721.7286 Amines, *N*-tallowalkyltripropylene tetra-, citrates.
- 721.7290 Propanoic acid, 2-(trimethoxysilyl)-, ethyl ester.
- 721.7375 Potassium salt of polyolefin acid.
- 721.7378 Substituted polyoxyethylene.
- 721.7440 Polyalkylenepolyol alkylamine. (generic name).
- 721.7450 Aromatic amine polyols.
- 721.7480 Isocyanate terminated polyols.
- 721.7500 Nitrate polyether polyol (generic name).
- 721.7600 Alkyl(heterocyclic) phenylazo hetero monocyclic polyone (generic name).
- 721.7620 Alkyl(heterocyclic) phenylazo hetero monocyclic polyone, ((alkylimidazolyl) methyl) derivative (generic name).
- 721.7655 Alkylsulfonium salt.
- 721.7700 Poly(oxy-1,2-ethanediyl),  $\alpha$ -hydro- $\omega$ -(oxiranymethoxy)-, ether with 2-ethyl-2-(hydroxymethyl)-1,3-propanediol (3:1).
- 721.7710 Polyepoxy polyol.
- 721.7720 Poly(oxy-1,2-ethanediyl),  $\alpha,\alpha'$ -[(1-methylethylidene) di-4,1-phenylene] bis [ $\omega$ -(oxiranymethoxy)-].
- 721.7770 Alkylphenoxypoly(oxyethylene) sulfuric acid ester, substituted amine salt.
- 721.7780 Poly[oxy(methyl-1,2-ethanediyl)],  $\alpha,\alpha'$ -(2,2-dimethyl-1,3-propanediyl)bis[ $\omega$ -(oxiranymethoxy)-].
- 721.7785 Substituted alkyl aminomethylene polyphosphonic acid, salt (generic).
- 721.8079 Isophorone diisocyanate neopentyl glycol adipate polyurethane prepolymer.
- 721.8082 Polyester polyurethane acrylate.
- 721.8085 Reaction product of substituted aromatic diol, formaldehyde and alkanolamine, propoxylated (generic).
- 721.8090 Polyurethane polymer.
- 721.8095 Silylated polyurethane.
- 721.8100 Potassium *N,N*-bis (hydroxyethyl) cocoamine oxide phosphate, and potassium *N,N*-bis (hydroxyethyl) tallowamine oxide phosphate.
- 721.8130 Propanamide, -(2-hydroxyethyl)-3-methoxy-.
- 721.8140 Substituted propane (generic).
- 721.8145 Propane, 1,1,1,2,2,3,3-heptafluoro-3-methoxy-.
- 721.8153 Di-substituted propanedione (generic).
- 721.8155 Propanenitrile, 3-[amino, *N*-tallowalkyl] dipropylene tri- and tripropylene tri- and propanenitrile, 3-[amino, (C<sub>14-18</sub> and C<sub>16-18</sub> unsaturated alkyl)] trimethylenedi-, dipropylene tri-, and tripropylene tetra-.
- 721.8160 Propanoic acid, 2,2-dimethyl-, ethenyl ester.
- 721.8175 1-Propanol, 3-mercapto-.
- 721.8225 2-Propanamide, *N*-[3-dimethylamino]propyl-.
- 721.8250 1-Propanol, 3,3'-oxybis[2,2-bis(bromomethyl)-].
- 721.8340 Mono esters from 2-propanoic acid (generic).
- 721.8350 2-Propanoic acid, 7-oxabicyclo[4.1.0]hept-3-ylmethyl ester.
- 721.8450 2-Propanoic acid, 2-methyl-, 2-[3-(2H-benzotriazol-2-yl)-4-hydroxyphenyl]ethyl ester.

Environmental Protection Agency

Pt. 721

- 721.8485 2-Propenoic acid, 2-methyl-, (octahydro-4,7-methano-1H-indene-5-diy)bis(methylene) ester.
- 721.8500 2-Propenoic acid, 2-methyl-, 7-oxabicyclo [4.1.0]hept-3-ylmethyl ester.
- 721.8657 Cerium, hydroxy oleate propionate complexes.
- 721.8658 Modified polymer of vinyl acetate and quaternary ammonium compound (generic).
- 721.8660 Propionic acid methyl ester (generic).
- 721.8670 Alkylcyano substituted pyridazo benzoate.
- 721.8673 [(Disubstituted phenyl)azo dihydro hydroxy alkyl oxo alkyl-substituted-pyridines (generic name).
- 721.8675 Halogenated pyridines.
- 721.8700 Halogenated alkyl pyridine.
- 721.8750 Halogenated substituted pyridine.
- 721.8775 Substituted pyridines.
- 721.8780 Substituted pyridine azo substituted phenyl.
- 721.8825 Substituted methylpyridine and substituted 2-phenoxy pyridine.
- 721.8850 Disubstituted halogenated pyridinol.
- 721.8875 Substituted halogenated pyridinol.
- 721.8900 Substituted halogenated pyridinol, alkali salt.
- 721.8920 4,6-Disubstituted pyrimidine (generic).
- 721.8940 Chromate(3-), bis[3-[[6-amino-1,4-dihydro-2-[[[4-(2-hydroxy-1-naphthalenyl)azo] phenyl]sulfonyl] amino]-4-(oxo-.kappa.O)-5-pyrimidinyl]azo-.kappa.N1] -4-hydroxy-.kappa.O)-5-nitrobenzenesulfonato(3-)]-, trisodium.
- 721.8950 Chromate(3-), bis[3-[[6-amino-1,4-dihydro-2-[[[4-(2-hydroxy-1-naphthalenyl)azo] phenyl]sulfonyl] amino]-4-(oxo-.kappa.O)-5-pyrimidinyl]azo-.kappa.N1]-4-hydroxy-.kappa.O)-5-nitrobenzenesulfonato(3-)]-, sodium triethanolamine salts.
- 721.8965 1H-Pyrole-2, 5-dione, 1-(2,4,6-tribromophenyl)-.
- 721.9000 N-Nitrosopyrrolidine.
- 721.9005 2-Pyrrolidinone, 1,1'-(2-methyl-1,5-pentanediy)bis-.
- 721.9010 2-pyrrolidone, 1-ethenyl-3-ethylidene-, (E)-.
- 721.9075 Quaternary ammonium salt of fluorinated alkylaryl amide.
- 721.9078 6-Methoxy-1H-benz[de]isoquinoline-2 [3H]-dione derivative (generic).
- 721.9079 Dihydro quinacridone derivative (generic).
- 721.9080 Nitro methyl quinoline.
- 721.9100 Substituted quinoline.
- 721.9220 Reaction products of secondary alkyl amines with a substituted benzenesulfonic acid and sulfuric acid (generic name).
- 721.9265 Reaction product of dichlorobenzidine and substituted alkylamide.
- 721.9270 Reaction product of epoxy with anhydride and glycerol and glycol.
- 721.9280 Reaction product of ethoxylated fatty acid oils and a phenolic pentaerythritol tetraester.
- 721.9285 Reaction products of formalin (37%) with amine C<sub>12</sub>.
- 721.9300 Reaction products of substituted hydroxyalkanes and polyalkylpolyisocyanatocarbomonocycle.
- 721.9400 Reaction product of phenolic pentaerythritol tetraesters with fatty acid esters and oils, and glyceride triesters.
- 721.9460 Tall oil fatty acids, reaction products with polyamines, alkyl substituted.
- 721.9470 Reserpine.
- 721.9480 Resorcinol, formaldehyde substituted carbomonocycle resin (generic).
- 721.9484 Dimer acid/rosin amidoamine reaction product (generic).
- 721.9485 Dimer acid/polymerized rosin amidoamine reaction product (generic).
- 721.9486 Roxin amidoamine (generic).
- 721.9487 Polymerized rosin amidoamine (generic).
- 721.9488 Substituted resorcinols.
- 721.9490 Coco alklydimethyl amine salts (generic).
- 721.9492 Polymers of styrene, cyclohexyl methacrylate and substituted methacrylate.
- 721.9495 Acrylosilane resins.
- 721.9497 Trifunctional ketoximino silane.
- 721.9499 Modified silicone resin.
- 721.9500 Silane, (1,1-dimethylethoxy) dimethoxy(2-methyl propyl)-.
- 721.9501 Silane, triethoxy[3-oxiranylmethoxy]propyl]-.
- 721.9502 Siloxanes and silicones, aminoalkyl, fluoroethyl, hydroxy-terminated salt (generic).
- 721.9503 Silane, (3,3,4,4,5,5,6,6,7,7,8,8,9,9,10,10,10-heptafluorodecyl)trimethoxy-.
- 721.9504 Silane, triethoxy (3,3,4,4,5,5,6,6,7,7,8,8,8-tridecafluoroethyl)-.
- 721.9505 Silanes substituted macrocycle polyethyl.
- 721.9506 Halogenated arylsilane (generic).
- 721.9507 Polyester silane.
- 721.9508 Perfluorinatedalkyl polyhydroxysilane (generic).
- 721.9509 Perfluorinatedalkyl polyalkoxysilane (generic).
- 721.9511 Silicic acid (H<sub>4</sub>SiO<sub>2</sub>O<sub>7</sub>), magnesium, strontium salt(1:1:2), dysprosium and europium-doped.
- 721.9513 Modified magnesium silicate polymer (generic).
- 721.9514 Ethyl silicate, reaction products with modified alkoxysilane salt (generic).
- 721.9515 Aminofunctional alkoxy alkyl siloxane.

- 721.9516 Siloxanes and silicones, 3-[(2-aminoethyl amino)propyl Me, di-Me, reaction products with polyethylene-polypropylene glycol Bu glycidal ether.
- 721.9517 Siloxanes and silicones, de-Me, 3-[4-[[[3-(dimethyl amino) propyl] amino]carbonyl]-2-oxo-1-pyrrolidinyl] propyl Me.
- 721.9518 *Sinorhizobium meliloti* strain RMBPC-2.
- 721.9520 Methylated-para-rosaniline salt of a trisulfonated triarylmethane dye (generic).
- 721.9526 Sodium perthiocarbonate.
- 721.9527 Bis(1,2,2,6,6-pentamethyl-4-piperidin-4-ol) ester of cycloaliphatic spiroketal.
- 721.9530 Bis(2,2,6,6-tetramethylpiperidinyl) ester of cycloalkyl spiroketal.
- 721.9535 1,4-Dioxa-7,9-dithia-8-stannacycloundecane-5,11-dione, 8,8-dioctyl-.
- 721.9538 Lithium salt of sulfophenyl azo phenyl azo disulfostilbene (generic).
- 721.9540 Polysulfide mixture.
- 721.9545 Substituted phenyl azo substituted sulfocarbopolycle, sodium salt.
- 721.9550 Sulfonamide.
- 721.9570 Halophenyl sulfonamide salt.
- 721.9572 Substituted alkyl sulfonamide (generic).
- 721.9573 Substituted perfluoroalkyl sulfonamide (generic).
- 721.9575 Chromate(3-), bis[3-[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-7-[[2-oxo-1-[(phenylamino)carbonyl] propyl]azo]-2-naphthalenesulfonato(3-)-], trisodium (9CI).
- 721.9576 Chromate(3-), bis[7-[(aminohydroxyphenyl)azo]-3-[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-2-naphthalene-sulfonato (3-)-], trisodium (9CI).
- 721.9577 Chromate(3-), bis[7-[(aminohydroxyphenyl)azo]-3-[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-2-naphthalene sulfonato (3-)-, -[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-7-[[2-hydroxy-1-[(phenylamino) carbonyl]-1-propenyl]azo]-2-naphthalenesulfonato(3-)-], trisodium (9CI).
- 721.9580 Ethyl methanesulfonate.
- 721.9582 Certain perfluoroalkyl sulfonates.
- 721.9595 Alkyl benzene sulfonic acids and alkyl sulfates, amine salts (generic).
- 721.9597 Salt of a substituted sulfonated aryl azo compound (generic).
- 721.9620 Aromatic sulfonic acid compound with amine.
- 721.9630 Polyfluorosulfonic acid salt.
- 721.9635 Terpene residue distillates.
- 721.9640 Salt of an acrylic acid - acrylamide terpolymer (generic).
- 721.9650 Tetramethylammonium salts of alkylbenzenesulfonic acid.
- 721.9656 Thiaalkanethiol.
- 721.9657 Disubstituted thiadiazole.
- 721.9658 Thiadiazole derivative.
- 721.9659 Disubstituted thiadiazosulfone.
- 721.9660 Methylthiouracil.
- 721.9661 Diphenol tars (generic).
- 721.9662 Thieno[3,4-b]-1,4-dioxin, 2,3-dihydro-(9CI).
- 721.9663 Poly(oxy-1,2-ethanediyl), alpha, alpha'-[thiobis (1-oxo-3,1-propanediyl)]bis [omega-hydroxy-,bis (C<sub>11-15</sub> and C<sub>11-15-isalkyl</sub>) ethers.
- 721.9664 9H-Thioxanthen-9-one,2,4-diethyl.
- 721.9665 Organotin catalysts.
- 721.9668 Organotin lithium compound.
- 721.9670 Tetraaryltin (generic).
- 721.9671 Triaryltin (generic).
- 721.9672 Amides, tall-oil fatty, N-[2-[2-hydroxyethyl]amino]ethyl], reaction products with sulfur dioxide; fatty acids, tall-oil, reaction products with 1-piperazineethanamine and sulfur dioxide; fatty acids, tall-oil reaction products with sulfur dioxide and triethylenetetramine.
- 721.9674 Sulfonated-copper phthalocyanine salt of a triarylmethane dye (generic).
- 721.9675 Titanate [Ti<sub>6</sub> O<sub>13</sub> (2-)], dipotassium.
- 721.9680 Alkaline titania silica gel (generic name).
- 721.9685 Mixed trialkylamines (generic).
- 721.9700 Monosubstituted alkoxyaminotriazines (generic name).
- 721.9717 Azo monochloro triazine reactive dye.
- 721.9719 Tris carbamoyl triazine (generic).
- 721.9720 Disubstituted alkyl triazines (generic name).
- 721.9730 1,3,5-Triazin-2-amine, 4-dimethylamino-6-substituted-.
- 721.9740 Brominated triazine derivative.
- 721.9750 2-Chloro-4,6-bis(substituted)-1,3,5-triazine, dihydrochloride.
- 721.9790 Benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[5-[[4-[bis(2-hydroxypropyl) amino]-6-[(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-, disodium salt, compd. with 2,2',2'-nitriolo-tris[ethanol] (1:2); Benzenesulfonic acid, 5-[[4-[bis(2-hydroxyethyl)amino]-6-[(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-2-[2-[4-[[4-[bis(2-hydroxypropyl)amino]-6-[(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-2-sulfophenyl]ethenyl]-, disodium salt, compd. with 2,2',2'-nitriolo-tris[ethanol] (1:2).
- 721.9795 Benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[[4,6-dichloro-1,3,5-triazin-2-yl] amino]-, disodium salt, substituted with dialkyl amines (generic).
- 721.9798 Benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[5-[[4-substituted-6-substituted-1,3,5-triazin-2-yl]amino]-, sodium salt (generic).
- 721.9800 Poly(substituted triazinyl) piperazine (benzenic name).

Environmental Protection Agency

Pt. 721

- 721.9820 Substituted triazole.
- 721.9825 Phenyl substituted triazolinones.
- 721.9830 1-Tridecyn-3-ol, 3-methyl.
- 721.9840 Tungstate (W12(OH)2O386-) hexasodium (9CI).
- 721.9850 2,4,8,10-Tetraoxa-3,9-diphosphaspiro[5.5]undecane, 3,9-bis[2,4,6-tris(1,1-dimethylethyl)phenoxy]-.
- 721.9892 Alkylated urea.
- 721.9900 Urea, condensate with poly[oxy(methyl-1,2ethanediyl)]- $\alpha$ -(2-aminomethylethyl)- $\mu$ -(2-aminoethylethoxy) (generic name).
- 721.9920 Urea, (hexahydro-6-methyl-2-oxopyrimidinyl)-.
- 721.9925 Aminoethylethylene urea methacrylamide.
- 721.9928 Urea, tetraethyl-.
- 721.9929 Polyurea (generic).
- 721.9930 Urethane.
- 721.9952 Alkoxyated aliphatic diisocyanate allyl ether (generic).
- 721.9957 N-Nitroso-N-methylurethane.
- 721.9959 Polyurethane polymer (generic).
- 721.9965 Fatty acids, C<sub>10-13</sub> - branched, vinyl esters.
- 721.9969 3,6-Bis(dialkylamino) -9-[2-alkoxycarbonyl] phenyl-xanthylium salt (generic).
- 721.9970 o-Xylene compound (generic name).
- 721.9973 Zirconium dichlorides (generic).
- 721.10000 Certain polybrominated diphenylethers.
- 721.10001 2-Ethoxyethanol, 2-ethoxyethanol acetate, 2-methoxyethanol, and 2-methoxyethanol acetate.
- 721.10002 2-Thiazolidinone.
- 721.10003 Manganese heterocyclic tetraamine complex (generic).
- 721.10004 2-Butenoic acid, 4,4'-[(dibutylstannylene)bis(oxy)]bis[4-oxo-, (2Z,2'Z)-, di-C<sub>8-10</sub>-isoalkyl esters, C<sub>9</sub>-rich.
- 721.10005 2-Butenoic acid, 4,4'-[(dibutylstannylene)bis(oxy)]bis [4-oxo-, (2Z,2'Z)-, di-C<sub>9-11</sub>-isoalkyl esters, C<sub>10</sub>-rich.
- 721.10006 Mixed metal oxide (generic).
- 721.10007 Alcohols, C<sub>12-14</sub>- secondary, ethoxylated propoxylated.
- 721.10008 Manganese strontium oxide (MnSrO<sub>3</sub>).
- 721.10009 Manganese yttrium oxide (MnYO<sub>3</sub>).
- 721.10010 Barium manganese oxide (BaMnO<sub>3</sub>).
- 721.10011 Barium calcium manganese strontium oxide.
- 721.10012 Manganate (MnO<sub>2</sub><sup>1-</sup>), calcium (2:1).
- 721.10013 Manganese yttrium oxide (Mn<sub>2</sub>YO<sub>5</sub>).
- 721.10014 Halogenated naphthalic anhydride (generic).
- 721.10015 Halogenated benzimidazole (generic).
- 721.10016 Dibenzimidazothianaphthalene (generic).
- 721.10017 Amine terminated bisphenol A diglycidyl ether polymer (generic).
- 721.10018 Calcium hydroxide oxide silicate (Ca<sub>6</sub>(OH)<sub>2</sub>O<sub>2</sub>(Si<sub>2</sub>O<sub>5</sub>)<sub>3</sub>).
- 721.10019 Benzoic acid, 2-chloro-5-nitro-, 1,1-dimethyl-2-oxo-2-(2-propenyloxy) ethyl ester.
- 721.10020 Benzoic acid, 5-amino-2-chloro-, 1,1-dimethyl-2-oxo-2-(2-propenyloxy) ethyl ester.
- 721.10021 Magnesium potassium titanium oxide.
- 721.10022 Benzenamine, N-phenyl-, ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs.
- 721.10023 Benzenamine, N-phenyl-, ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs.
- 721.10024 10H-Phenothiazine, ar-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs.
- 721.10025 10H-Phenothiazine, ar, ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs.
- 721.10026 Cashew, nutshell liq., ethoxylated.
- 721.10027 Ethoxylated alkylsulfate, substituted alkylamine salt (generic).
- 721.10028 Disubstituted benzene metal salts (generic).
- 721.10029 Isocyanate compound, modified with methoxysilane (generic).
- 721.10030 Pyrimido[5,4-g]pteridine-2,4,6,8-tetramine, 4-methylbenzenesulfonate, base-hydrolyzed.
- 721.10031 Lithium potassium titanium oxide.
- 721.10032 Acrylic acid, polymer with substituted acrylamides (generic).
- 721.10033 Zinc, [ethanedioato(2)-, kappa. O<sup>1</sup>, . kappa. O<sup>2</sup>]-.
- 721.10034 Substituted pyridine coupled with diazotized substituted nitrobenzotrile, diazotized substituted benzenamine and substituted pyridinecarbonitrile (generic).
- 721.10035 Alkylbenzene sulfonate (generic).
- 721.10036 Acetaldehyde based polymer (generic).
- 721.10037 Complex halogenated salt of tris(ethylatedaminocarbocyclic)methane (generic).
- 721.10038 Trimellitic anhydride, polymer with substituted glycol, alkyl phenols and ethoxylated nonylphenol (generic).
- 721.10039 Diethoxybenzenamine derivative, diazotized, coupled with aminonaphthalenesulfonic acid derivative, ammonium salt (generic).
- 721.10040 Substituted acridine naphtha substituted benzamide (generic).
- 721.10041 1-Butanone, 2-(dimethylamino)-2-[(4-methylphenyl)methyl]-1-[4-(4-morpholinyl)phenyl]-.
- 721.10042 2-Propanol, 1-[bis(2-hydroxyethyl)amino]-.
- 721.10043 Dineopentyl-4-substituted phthalate (generic).
- 721.10044 Metal oxide, modified with alkyl and vinyl terminated polysiloxanes (generic).



- 721.10045 Diazotized substituted heteromonocycle coupled with naphthalene sulfonic acid derivative, nickel complex, alkaline salt (generic).
- 721.10046 Polyaromatic amine phosphate (generic).
- 721.10047 Polyphosphoric acids, compds. with piperazine.
- 721.10048 Substituted anthraquinone (generic).
- 721.10049 Phenol, 4,4'-cyclohexylidene bis[2-methyl-].
- 721.10050 Disubstituted-*N*-hydroxybenzenecarboximidamide (generic).
- 721.10051 Spiro naphthoxazine (generic).
- 721.10052 Aminoalkyl substituted alkylphenol (generic).
- 721.10053 Alkyl silane methacrylate (generic).
- 721.10054 Phenol, polymer with formaldehyde, 3-[(2-aminocyclohexyl)amino]-2-hydroxypropyl ethers.
- 721.10055 1-Propanaminium, 3-amino-*N*-(carboxymethyl)-*N,N*-dimethyl-, *N*-soya acyl derivs., inner salts.
- 721.10056 Benzenemethanaminium, *N*-(3-aminopropyl)-*N,N*-dimethyl-, *N*-soya acyl derivs., chlorides.
- 721.10057 Dodecanedioic acid, 1, 12-dihydrazide.
- 721.10058 Reaction product of alkylphenol, aromatic cyclicamine, alkyl diglycidyl dibenzene, and formaldehyde (generic).
- 721.10059 Reaction product of alkylphenyl glycidyl ether, polyalkylenepolyamine, and alkyl diglycidyl dibenzene (generic).
- 721.10060 Reaction product of alkylphenyl glycidyl ether, polyalkylenepolyamine, alkyl diglycidyl dibenzene, and polyalkylcyclicdiamine (generic).
- 721.10061 Pentane, 1,1,1,2,2,3,4,5,5,5-decafluoro-3-methoxy-4-(trifluoromethyl)-.
- 721.10062 2,5-Furandione, polymer with oxybis[propanol], benzoate.
- 721.10063 Halo substituted hydroxy nitrophenyl amide (generic).
- 721.10064 2-Propenoic acid, 2-[2-(ethenyloxy)ethoxy]ethyl ester.
- 721.10065 1-Tetradecanesulfonic acid, (dimethylphenyl)-.
- 721.10066 1-Hexanesulfonic acid, (dimethylphenyl)-.
- 721.10067 Ether amine phosphonate salt (generic).
- 721.10068 Elemental mercury.
- 721.10069 Ether amine phosphonate (generic).
- 721.10070 1,3-Butanediol, 3-methyl-.
- 721.10071 9H-Thioxanthene, 10-[1,1'-biphenyl]-4-yl-2-(1-methylethyl)-9-oxo-, hexafluorophosphate (1-) (1:1).
- 721.10072 Benzene, 1,1'-methylenebis[4-isocyanato-, polymer with benzenedicarboxylic acid, butyl dialkyl ester, poly[oxy(methyl-1,2-ethanediyl)], .alpha.-hydro-.omega.-hydroxy-, oxirane, alkyl-, polymer with oxirane, ether with propanepolyol and Sartomer's HLBH P-3000 and Lexorez 1180 (generic).
- 721.10073 Modified alkyl acrylamide (generic).
- 721.10074 Acetic acid, 2-chloro-, 1-(3,3-dimethylcyclohexyl)ethyl ester.
- 721.10075 Carbon black, 4-[[2-(Sulfooxy)ethyl]substituted] phenyl- modified, sodium salts (generic).
- 721.10076 Substituted benzenediamine (generic).
- 721.10077 3H-1,2,4-Triazol-3-one, 1,2-dihydro-.
- 721.10078 Butanamide, 2-[(2-methoxy-4-nitrophenyl)azo]-*N*-(2-methoxyphenyl)-3-oxo-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl)substituted]phenyl derivs., hydrochlorides (generic).
- 721.10079 Quino[2,3-*b*]acridine-7, 14-dione, 5,12-dihydro-2,9-dimethyl-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl)substituted]phenyl derivs., hydrochlorides (generic).
- 721.10080 Carbon black, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl) substituted] phenyl-modified, hydrochlorides (generic).
- 721.10081 Aromatic urethane acrylate oligomer (generic).
- 721.10082 Amine modified monomer acrylate (generic).
- 721.10083 Copper, [29H, 31H-phthalocyaninato (2-)-N29, N30, N31, N32]-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl) substituted] phenyl derivs., hydrochlorides (generic).
- 721.10084 Modified thionocarbamate (generic).
- 721.10085 Substituted polyaryl sulfonium polyhalide phosphate salt (generic).
- 721.10086 Ethane, 2-(difluoromethoxy)-1,1,1-trifluoro-.
- 721.10087 Substituted alkyl phosphine oxide (generic).
- 721.10088 Thiophene, 2,5-dibromo-3-hexyl-.
- 721.10089 Modified salicylic acid, zirconium complex (generic).
- 721.10090 Tertiary amine salt of glycol succinate (generic).
- 721.10091 2(1H)-Pyrimidinone, tetrahydro-1,3-dimethyl-.
- 721.10092 Poly(oxy-1,2-ethanediyl), .alpha.-sulfo-.omega.-[[1-[(2-propen-1-yloxy)methyl]undecyl]oxy]-, ammonium salt (1:1); Poly(oxy-1,2-ethanediyl), .alpha.-sulfo-.omega.-[[1-[(2-propen-1-yloxy)methyl]tridecyl]oxy]-, ammonium salt (1:1).
- 721.10093 Alkylamides, ethoxylated (generic).
- 721.10094 Decene, branched and linear.
- 721.10095 Oxetane, 3,3'-[oxybis(methylene)] bis[3-ethyl-].
- 721.10096 Benzene, 1,4-bis (methoxymethyl)-.
- 721.10097 Disubstituted benzenesulfonic acid, alkali metal salt (generic).

**Environmental Protection Agency**

**Pt. 721**

- 721.10098 Disubstituted benzoic acid, alkali metal salt (generic).
- 721.10099 Dialkyl dimethyl ammonium carbonate (generic).
- 721.10100 Dialkyl dimethyl ammonium carbonate (2:1) (generic).
- 721.10101 Copolymer of alkyl acrylate and ethyleneglycol dimethacrylate (generic).
- 721.10102 Diphosphoric acid, compd. with piperazine (1:1).
- 721.10103 Naphtha (Fischer-Tropsch), C4-11-alkane, branched and linear.
- 721.10104 Halophosphate mixed metal complex (generic).
- 721.10105 Polyfluoroalkylether (generic).
- 721.10106 Silica, [(ethenylsilylidyne)tris(oxy)] - modified.
- 721.10107 Naphthalenedisulfonic acid, [amino-hydroxy-(substituted)azo-sulfonaphthaleneyl]azo]-hydroxy-[(methoxy-sulfophenyl)azo], metal salt (generic).
- 721.10108 Naphthalenedisulfonic acid, hydroxy-[[[(hydroxyl-disulfonaphthaleneyl)azo]-alkyl(C=1-5)-(sulfoalkoxy)cyclic]azo]-substituted azo-, metal salt (generic).
- 721.10109 Hexanoic acid, 2-ethyl-, mixed triesters with benzoic acid and trimethylolpropane.
- 721.10110 Hexanoic acid, 2-ethyl-, mixed diesters with benzoic acid and neopentyl glycol.
- 721.10111 Hexanoic acid, 2-ethyl-, mixed diesters with benzoic acid and diethylene glycol.
- 721.10112 Ethanone, 2-chloro-1-(1-chlorocyclopropyl)-.
- 721.10113 Thioether epoxy (generic).
- 721.10114 Polyhydroxyaminoether salts (generic).
- 721.10115 1-Hexadecanaminium, N,N-dibutyl-N-(2-hydroxyethyl)-, bromide (1:1).
- 721.10116 Blocked polymeric isocyanate (generic).
- 721.10117 Heteromonocyclo-beta-(2,4-dichlorophenyl)-1-propanol (generic).
- 721.10118 Substituted aryl acetonitrile (generic).
- 721.10119 Siloxane modified silica nanoparticles (generic).
- 721.10120 Siloxane modified alumina nanoparticles (generic).
- 721.10121 Poly[oxy(methyl-1,2-ethanediyl)], .alpha.-methyl-.omega.-(4-nonylphenoxy)-, branched.
- 721.10122 2-Propenoic acid, 2-methyl-, 1,1'-[2-ethyl-2-[[[(2-methyl-1-oxo-2-propen-1-yl)oxy]methyl]-1,3-propanediyl] ester, polymer with 1,3-butadiene, ethenylbenzene and 2-hydroxyethyl 2-methyl-2-propenoate.
- 721.10123 [1,2,4-Triazolo[1,5-a]pyrimidin-2-amine, 5,7-dimethoxy-].
- 721.10124 Brominated polyaromatic compound (generic).
- 721.10125 Alkenedioic acid, dialkyl ester, reaction products with polyaminocarbomonocycle and alkenoic acid alkyl ester (generic).
- 721.10126 Alkyl amino substituted triazine amino substituted benzenesulfonic acid reaction product with naphthalenesulfonato azo substituted phenyl azo substituted benzenesulfonic acid copper compound (generic).
- 721.10127 Alkenyl dimethyl betaine (generic).
- 721.10128 Modified imidazole (generic).
- 721.10129 Alkylamine ethoxylated (generic).
- 721.10130 Quino[2,3-b]acridine-7,14-dione, 5,12-dihydro-ar-[4-[[2-(sulfooxy)ethyl]substituted]phenyl]-, monosodium salt (generic).
- 721.10131 Isononanamide, N-(2-ethylhexyl)-.
- 721.10132 Phosphoramidic acid, carbomonocyclic-, diphenylester (generic).
- 721.10133 2-Propenoic acid, 2-methyl, 2-hydroxyethyl ester, homopolymer.
- 721.10134 Formaldehyde, polymer with dialkylphenylamine, dialkylphenol and trimethylhexanediamine (generic).
- 721.10135 Phosphinic acid, P,P-diethyl-, zinc salt (2:1).
- 721.10136 2-Propenoic acid, 2-methyl-, 2-hydroxyethyl ester, reaction products with hexakis(alkoxyalkyl)melamine (generic).
- 721.10137 Halogenated phenoxy aromatic (generic).
- 721.10138 3-Isoxazolecarboxylic acid, 4,5-dihydro-5,5-diphenyl-, ethyl ester.
- 721.10139 Ethanone, 1-(1-chlorocyclopropyl)-.
- 721.10140 Phosphoric acid, tin (2+) salt (2:3).
- 721.10141 Oils, ginger, zingiber purpureum.
- 721.10142 Oxabicycloalkane carboxylic acid alkanediyl ester (generic).
- 721.10143 Amines, bis (C11-14-branched and linear alkyl).
- 721.10144 Modified thiocarbamate (generic).
- 721.10145 Modified reaction products of alkyl alcohol, halogenated alkane, substituted epoxide, and amino compound (generic).
- 721.10146 Partially fluorinated condensation polymer (generic).
- 721.10147 Acrylate derivative of alkoxyalkylalkane ester and mixed metal oxides (generic).
- 721.10148 Acryloxy alkanedioic alkane derivative with mixed metal oxides (generic).
- 721.10149 Carbon black, (3-methylphenyl)-modified, substituted (generic).
- 721.10150 Carbon black, (4-methylphenyl)-modified, substituted (generic).
- 721.10151 Modified styrene, divinylbenzene polymer (generic).
- 721.10152 Oxirane, substituted silylmethyl-, hydrolysis products with alkanol zirconium(4+) salt and silica, acetates (generic).
- 721.10153 Modified methyl methacrylate, 2-hydroxyethyl methacrylate polymer (generic).

**§ 721.1**

721.10154 Quaternary ammonium compounds, dicoco alkyldimethyl, chlorides, reaction products with silica.

721.10157 Benzeneethanol,halo-,halocycloalkyl-,hydrazinealkyl- (generic).

721.10158 2-Pentanone, 3,5-dichloro-.

721.10159 1-Docosanamine, N,N-dimethyl-.

721.10160 Poly(oxy-1,2-ethanediyl), .alpha.- [(13Z)-1-oxo-13-docosen-1-yl]-.omega.- [[(13Z)-1-oxo-13-docosen-1-yl]oxy]-.

721.10161 Substituted silyl methacrylate (generic).

721.10162 1,3 Dioxolane-4-butanol, 2-ethenyl-.

721.10163 Chloro fluoro alkane (generic).

721.10164 Benzenecarboximidamide, N-hydroxy-4-nitro-.

721.10165 Carbonotrithioic acid, bis(phenylmethyl) ester.

721.10166 1,3-Cyclohexanedione, 2-[2-chloro-4-(methylsulfonyl)-3-[(2,2,2-trifluoroethoxy)methyl]benzoyl]-, ion(1-), potassium salt (1:1).

721.10167 Tetrafluoro nitrotoluene (generic).

721.10168 Cesium tungsten oxide.

721.10169 Cyclopentane, methoxy-.

721.10170 Polyoxyethylene polyalkylarylphenylether sulfate ammonium salt (generic).

721.10171 1H-benz(e)indolium, 1,1,2,3-tetramethyl-, 4-methylbenzenesulfonic acid (1:1).

721.10172 Alkylamide derivative (generic).

721.10173 Silanamine,1,1,1-triethoxy-N,N-diethyl-.

721.10174 1-Propanaminium, 3-amino-N-(carboxymethyl)-N,N-dimethyl-, N-peanut-oil acyl derivs., inner salts.

721.10175 1-Propanaminium, N-(3-aminopropyl)-2-hydroxy-N,N-dimethyl-3-sulfo-, N-(C12-18 and C18-unsatd. acyl) derivs., inner salts.

721.10176 Amides, peanut-oil, N-[3-(dimethylamino)propyl].

721.10177 Phosphoric acid, yttrium(3+) salt (1:1).

721.10178 Distillates (Fischer-Tropsch), hydroisomerized middle, C10-13-branched alkane fraction.

721.10179 Copolymers of phenol and aromatic hydrocarbon (generic).

721.10180 Trifunctional acrylic ester (generic).

721.10181 Halide salt of an alkylamine (generic).

721.10184 Aliphatic triamine (generic).

721.10185 1,2-Propanediol, 3-(diethylamino)-, polymers with 5-isocyanato-1-(isocyanatomethyl)-1,3,3-trimethylcyclohexane, propylene glycol and reduced Me esters of reduced polymd. oxidized tetrafluoroethylene, 2-ethyl-1-hexanol-blocked, acetates (salts).

721.10186 Ethylhexyl oxetane (generic).

721.10187 4-Morpholinepropanamine, N-(1,3-dimethylbutylidene)-.

**40 CFR Ch. I (7-1-10 Edition)**

721.10188 Fatty acids, tall-oil, reaction products with 4-methyl-2-pentanone and aliphatic polyamine (generic).

721.10189 Fatty acids, tall-oil, reaction products with (butoxymethyl) oxirane formaldehyde-phenol polymer glycidyl ether, morpholinepropanamine, propylene glycol diamine and aliphatic polyamine, N-(1,3 -dimethylbutylidene) derivs (generic).

721.10190 Formaldehyde, polymer with aliphatic diamine and phenol, reaction products with 4-methyl-2-pentanone (generic).

721.10191 Amides, coco, N-[3-(dibutylamino)propyl].

721.10192 Amides, coco, N-[3-(dibutylamino)propyl], acrylates.

721.10193 1-Butanaminium, N-(3-aminopropyl)-N-butyl-N-(2-carboxyethyl)-, N-coco acyl derivs., inner salts.

721.10194 Dialkylcocoamidoalkylpropionate (generic).

721.10195 Dialkylcornoilamidoalkylamine (generic).

721.10196 Dialkylcornoilamidoacrylate (generic).

721.10197 Dialkylcornoilamidoalkylbetaine (generic).

721.10198 Dialkylcornoilamidopropionate (generic).

721.10199 Substituted aliphatic amine (generic).

721.10200 Benzenacetonitrile, cyclohexylidene-alkyl substituted (generic).

AUTHORITY: 15 U.S.C. 2604, 2607, and 2625(c).

**Subpart A—General Provisions****§ 721.1 Scope and applicability.**

(a) This part identifies uses of chemical substances, except for microorganisms regulated under part 725 of this chapter, which EPA has determined are significant new uses under the authority of section 5(a)(2) of the Toxic Substances Control Act. In addition, it specifies procedures for manufacturers, importers, and processors to report on those significant new uses. This subpart A contains general provisions applicable to this part. subpart B of this part identifies generic requirements for certain significant new uses cross referenced in specific provisions of subpart E of this part. subpart C of this part identifies generic reporting requirements for certain significant new uses cross referenced in specific provisions of subpart E of this part. subpart

## Environmental Protection Agency

## § 721.3

E of this part identifies chemical substances and their significant new uses.

(b) This subpart A contains provisions governing submission and review of notices for the chemical substances and significant new uses identified in subpart E of this part. The provisions of this subpart A apply to the chemical substances and significant new uses identified in subpart E of this part, except to the extent that they are specifically modified or supplanted by specific requirements in subpart E of this part. In the event of a conflict between the provisions of this subpart A and the provisions of subpart E of this part, the provisions of subpart E of this part shall govern.

(c) The provisions of part 720 of this chapter apply to this part 721. For purposes of this part 721, wherever the phrase "new chemical substance" appears in part 720 of this chapter, it shall mean the chemical substance subject to this part 721. In the event of a conflict between the provisions of part 720 of this chapter and the provisions of this part 721, the provisions of this part 721 shall govern.

[53 FR 28358, July 27, 1988, as amended at 62 FR 17932, Apr. 11, 1997]

### § 721.3 Definitions.

The definitions in section 3 of the Act, 15 U.S.C. 2602, and § 720.3 of this chapter apply to this part. In addition, the following definitions apply to this part:

*Acutely toxic effects* A chemical substance produces acutely toxic effects if it kills within a short time period (usually 14 days):

(1) At least 50 percent of the exposed mammalian test animals following oral administration of a single dose of the test substance at 25 milligrams or less per kilogram of body weight ( $LD_{50}$ ).

(2) At least 50 percent of the exposed mammalian test animals following dermal administration of a single dose of the test substance at 50 milligrams or less per kilogram of body weight ( $LD_{50}$ ).

(3) At least 50 percent of the exposed mammalian test animals following administration of the test substance for 8 hours or less by continuous inhalation at a steady concentration in air at 0.5

milligrams or less per liter of air ( $LC_{50}$ ).

*CAS Number* means Chemical Abstracts Service Registry Number assigned to a chemical substance on the Inventory.

*Chemical name* means the scientific designation of a chemical substance in accordance with the nomenclature system developed by the International Union of Pure and Applied Chemistry or the Chemical Abstracts Service's rules of nomenclature, or a name which will clearly identify a chemical substance for the purpose of conducting a hazard evaluation.

*Chemical protective clothing* means items of clothing that provide a protective barrier to prevent dermal contact with chemical substances of concern. Examples can include, but are not limited to: full body protective clothing, boots, coveralls, gloves, jackets, and pants.

*Commercial use* means the use of a chemical substance or any mixture containing the chemical substance in a commercial enterprise providing saleable goods or a service to consumers (e.g., a commercial dry cleaning establishment or painting contractor).

*Common name* means any designation or identification such as code name, code number, trade name, brand name, or generic chemical name used to identify a chemical substance other than by its chemical name.

*Consumer* means a private individual who uses a chemical substance or any product containing the chemical substance in or around a permanent or temporary household or residence, during recreation, or for any personal use or enjoyment.

*Consumer product* means a chemical substance that is directly, or as part of a mixture, sold or made available to consumers for their use in or around a permanent or temporary household or residence, in or around a school, or in recreation.

*Customer* means any person to whom a manufacturer, importer, or processor distributes any quantity of a chemical substance, or of a mixture containing the chemical substance, whether or not a sale is involved.

*Director of the Office of Pollution Prevention and Toxics* means the Director

of the EPA Office of Pollution Prevention and Toxics or any EPA employee delegated by the Office Director to carry out the Office Director's functions under this part.

*Employer* means any manufacturer, importer, processor, or user of chemical substances or mixtures.

*Environmentally transformed* A chemical substance is "environmentally transformed" when its chemical structure changes as a result of the action of environmental processes on it.

*Facility* means all buildings, equipment, structures, and other stationary items which are located on a single site or on contiguous or adjacent sites and which are owned or operated by the same person (or by any person which controls, is controlled by, or under common control with such person).

*Identity* means any chemical or common name used to identify a chemical substance or a mixture containing that substance.

*Immediate use* A chemical substance is for the "immediate use" of a person if it is under the control of, and used only by, the person who transferred it from a labeled container and will only be used by that person within the work shift in which it is transferred from the labeled container.

*Impervious* Chemical protective clothing is "impervious" to a chemical substance if the substance causes no chemical or mechanical degradation, permeation, or penetration of the chemical protective clothing under the conditions of, and the duration of, exposure.

*Manufacturing stream* means all reasonably anticipated transfer, flow, or disposal of a chemical substance, regardless of physical state or concentration, through all intended operations of manufacture, including the cleaning of equipment.

*Metalworking fluid* means a liquid of any viscosity or color containing intentionally added water and used in metal machining operations for the purpose of cooling, lubricating, or rust inhibition.

*MSDS* means material safety data sheet, the written listing of data for the chemical substance as required under §721.72(c).

*NIOSH* means the National Institute for Occupational Safety and Health of

the U.S. Department of Health and Human Services.

*Non-enclosed process* means any equipment system (such as an open-top reactor, storage tank, or mixing vessel) in which a chemical substance is manufactured, processed, or otherwise used where significant direct contact of the bulk chemical substance and the workplace air may occur.

*Non-industrial use* means use other than at a facility where chemical substances or mixtures are manufactured, imported, or processed.

*Personal protective equipment* means any chemical protective clothing or device placed on the body to prevent contact with, and exposure to, an identified chemical substance or substances in the work area. Examples include, but are not limited to, chemical protective clothing, aprons, hoods, chemical goggles, face splash shields, or equivalent eye protection, and various types of respirators. Barrier creams are not included in this definition.

*Powder or dry solid form* means a state where all or part of the substance would have the potential to become fine, loose, solid particles.

*Principal importer* means the first importer who, knowing that a chemical substance will be imported for a significant new use rather than manufactured in the United States, specifies the chemical substance and the amount to be imported. Only persons who are incorporated, licensed, or doing business in the United States may be principal importers.

*Process for commercial purposes* means the preparation of a chemical substance or mixture containing the chemical substance, after manufacture of the substance, for distribution in commerce with the purpose of obtaining an immediate or eventual commercial advantage for the processor. Processing of any amount of a chemical substance or mixture containing the chemical substance is included in this definition. If a chemical substance or mixture containing impurities is processed for commercial purposes, the impurities also are processed for commercial purposes.

*Process solely for export* means to process for commercial purposes solely for export from the United States

under the following restrictions on activity in the United States: Processing must be performed at sites under the control of the processor; distribution in commerce is limited to purposes of export; and the processor may not use the chemical substance except in small quantities solely for research and development.

*Process stream* means all reasonably anticipated transfer, flow, or disposal of a chemical substance, regardless of physical state or concentration, through all intended operations of processing, including the cleaning of equipment.

*Recipient* means any person who purchases or otherwise obtains a chemical substance directly from a person who manufactures, imports, or processes the substance.

*Serious acute effects* means human injury or human disease processes that have a short latency period for development, result from short-term exposure to a chemical substance, or are a combination of these factors and which are likely to result in death or severe or prolonged incapacitation.

*Serious chronic effects* means human injury or human disease processes that have a long latency period for development, result from long-term exposure to a chemical substance, or are a combination of these factors and which are likely to result in death or severe or prolonged incapacitation.

*Short-term test indicative of carcinogenic potential* means either any limited bioassay that measures tumor or preneoplastic induction, or any test indicative of interaction of a chemical substance with DNA (i.e., positive response in assays for gene mutation, chromosomal aberrations, DNA damage and repair, or cellular transformation).

*Short-term test indicative of the potential to cause a developmentally toxic effect* means either any *in vivo* preliminary development toxicity screen conducted in a mammalian species, or any *in vitro* developmental toxicity screen, including any test system other than the intact pregnant mammal, that has been extensively evaluated and judged reliable for its ability to predict the potential to cause developmentally toxic effects in intact systems across a broad

range of chemicals or within a class of chemicals that includes the substance of concern.

*Significant adverse environmental effects* means injury to the environment by a chemical substance which reduces or adversely affects the productivity, utility, value, or function of biological, commercial, or agricultural resources, or which may adversely affect a threatened or endangered species. A substance will be considered to have the potential for significant adverse environmental effects if it has one of the following:

(1) An acute aquatic EC<sub>50</sub> of 1 mg/L or less.

(2) An acute aquatic EC<sub>50</sub> of 20 mg/L or less where the ratio of aquatic vertebrate 24-hour to 48-hour EC<sub>50</sub> is greater than or equal to 2.0.

(3) A Maximum Acceptable Toxicant Concentration (MATC) of less than or equal to 100 parts per billion (100 ppb).

(4) An acute aquatic EC<sub>50</sub> of 20 mg/L or less coupled with either a measured bioconcentration factor (BCF) equal to or greater than 1,000x or in the absence of bioconcentration data a log P value equal to or greater than 4.3.

*Site* means a contiguous property unit. Property divided only by a public right-of-way is one site. There may be more than one manufacturing plant on a single site.

*Site-limited intermediate* means an intermediate manufactured, processed, and used only within a site and not distributed in commerce other than as an impurity or for disposal. Imported intermediates cannot be "site-limited."

*Spray application* means any method of projecting a jet of vapor of finely divided liquid onto a surface to be coated; whether by compressed air, hydraulic pressure, electrostatic forces, or other methods of generating a spray.

*Use stream* means all reasonably anticipated transfer, flow, or disposal of a chemical substance, regardless of physical state or concentration, through all intended operations of industrial, commercial, or consumer use.

*Waters of the United States* has the meaning set forth in 40 CFR 122.2.

*Work area* means a room or defined space in a workplace where a chemical substance is manufactured, processed,

## § 721.5

## 40 CFR Ch. I (7–1–10 Edition)

or used and where employees are present.

*Workplace* means an establishment at one geographic location containing one or more work areas.

[53 FR 28358, July 27, 1988, as amended at 54 FR 31306, July 27, 1989; 58 FR 63516, Dec. 1, 1993]

### § 721.5 Persons who must report.

(a) The following persons must submit a significant new use notice as specified under the provisions of section 5(a)(1)(B) of the Act, part 720 of this chapter, and § 721.25:

(1) A person who intends to manufacture, import, or process for commercial purposes a chemical substance identified in a specific section in subpart E of this part, and intends to engage in a significant new use of the substance identified in that section.

(2) A person who intends to manufacture, import, or process for commercial purposes a chemical substance identified in a specific section in subpart E of this part, and intends to distribute the substance in commerce. A person described in this paragraph is not required to submit a significant new use notice if that person can document one or more of the following as to each recipient of the substance from that person:

(i) That the person has notified the recipient, in writing, of the specific section in subpart E of this part which identifies the substance and its designated significant new uses.

(ii) That the recipient has knowledge of the specific section in subpart E of this part which identifies the substance and its designated significant new uses.

(iii) That the recipient cannot undertake any significant new use described in the specific section in subpart E of this part.

(b) A person described in paragraph (a)(2) of this section must submit a significant new use notice if that person has knowledge at the time of commercial distribution of the substance identified in the specific section in subpart E of this part that a recipient intends to engage in a designated significant new use of that substance without submitting a notice under this part.

(c) A person who processes a chemical substance identified in a specific

section in subpart E of this part for a significant new use of that substance is not required to submit a significant new use notice if that person can document each of the following:

(1) That the person does not know the specific chemical identity of the chemical substance being processed.

(2) That the person is processing the chemical substance without knowledge that the substance is identified in subpart E of this part.

(d)(1) If at any time after commencing distribution in commerce of a chemical substance identified in a specific section in subpart E of this part a person described in paragraph (a)(2) of this section has knowledge that a recipient of the substance is engaging in a significant new use of that substance designated in that section without submitting a notice under this part, the person is required to cease supplying the chemical substance to that recipient and to submit a significant new use notice for that chemical substance and significant new use, unless the person is able to document each of the following:

(i) That the person has notified the recipient and EPA enforcement authorities (at the address in paragraph (d)(1)(iii) of this section), in writing within 15 working days of the time the person develops knowledge that the recipient is engaging in a significant new use, that the recipient is engaging in a significant new use without submitting a significant new use notice.

(ii) That, within 15 working days of notifying the recipient as described in paragraph (d)(1)(i) of this section, the person received from the recipient, in writing, a statement of assurance that the recipient is aware of the terms of the applicable section in subpart E of this part and will not engage in the significant new use.

(iii) That the person has promptly provided EPA enforcement authorities with a copy of the recipient's statement of assurance described in paragraph (d)(1)(ii) of this section. The copy must be sent to the Office of Enforcement and Compliance Assurance, Office of Compliance (2224A), U.S. Environmental Protection Agency, Ariel Rios, 1200 Pennsylvania Ave., N.W., Washington, DC, 20044.

## Environmental Protection Agency

## § 721.11

(2) If EPA notifies the manufacturer, importer, or processor that the recipient is engaging in a significant new use after providing the statement of assurance described in paragraph (d)(1)(ii) of this section and without submitting a notice under this part, the manufacturer, importer, or processor shall immediately cease distribution to that recipient until the manufacturer, importer, or processor or the recipient has submitted a significant new use notice under this part and the notice review period has ended.

(3) If, after receiving a statement of assurance from a recipient under paragraph (d)(1)(ii) of this section, a manufacturer, importer, or processor has knowledge that the recipient is engaging in a significant new use without submitting a notice under this part, the manufacturer, importer, or processor must immediately cease distributing the substance to that recipient and notify EPA enforcement authorities at the address identified in paragraph (d)(1)(iii) of this section. The manufacturer, importer, or processor may not resume distribution to that recipient until any one of the following has occurred:

(i) The manufacturer, importer, or processor has submitted a significant new use notice under this part and the notice review period has ended.

(ii) The recipient has submitted a significant new use notice under this part and the notice review period has ended.

(iii) The manufacturer, importer, or processor has received notice from EPA enforcement authorities that it may resume distribution to that recipient.

(e) Any significant new use notice relating to import of a substance must be submitted by the principal importer.

[53 FR 28359, July 27, 1988, as amended at 60 FR 34464, July 3, 1995]

### **§ 721.11 Applicability determination when the specific chemical identity is confidential.**

(a) A person who intends to manufacture, import, or process a chemical substance which is described by a generic chemical name is subpart E of this part may ask EPA whether the substance is subject to the requirements of this part. EPA will answer such an inquiry only if EPA determines

that the person has a *bona fide* intent to manufacture, import, or process the chemical substance for commercial purposes.

(b) To establish a *bona fide* intent to manufacture, import, or process a chemical substance, the person who intends to manufacture, import, or process the chemical substance must submit the following information in writing to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: SNUR Bonafide submissions.

(1) The specific chemical identity of the chemical substance that the person intends to manufacture, import, or process.

(2) A signed statement that the person intends to manufacture, import, or process the chemical substance for commercial purposes.

(3) A description of the research and development activities conducted to date, and the purpose for which the person will manufacture, import, or process the chemical substance.

(4) An elemental analysis.

(5) Either an X-ray diffraction pattern (for inorganic substances), a mass spectrum (for most other substances), or an infrared spectrum of the particular chemical substance, or, if such data do not resolve uncertainties with respect to the identity of the chemical substance, additional or alternative spectra or other data to identify the substance.

(c) If an importer or processor cannot provide all the information required in paragraph (b) of this section because it is claimed as confidential business information by the importer's or processor's manufacturer or supplier, the manufacturer or supplier may supply the information directly to EPA.

(d) EPA will review the information submitted by the manufacturer, importer, or processor under paragraph (b) of this section to determine whether the person has shown a *bona fide* intent to manufacture, import, or process the chemical substance. If necessary, EPA will compare this information either to the information requested for the confidential chemical



## § 721.20

substance under § 710.7(e)(2)(v) of this chapter or the information requested under § 720.85(b)(3)(iii) of this chapter.

(e) If the manufacturer, importer, or processor has shown a *bona fide* intent to manufacture, import, or process the substance and has provided sufficient unambiguous chemical identity information to enable EPA to make a conclusive determination as to the identity of the substance, EPA will inform the manufacturer, importer, or processor whether the chemical substance is subject to this part and, if so, which section in subpart E of this part applies.

(f) A disclosure to a person with a *bona fide* intent to manufacture, import, or process a particular chemical substance that the substance is subject to this part will not be considered public disclosure of confidential business information under section 14 of the Act.

(g) EPA will answer an inquiry on whether a particular chemical substance is subject to this part within 30 days after receipt of a complete submission under paragraph (b) of this section.

[53 FR 28359, July 27, 1988, as amended at 60 FR 34464, July 3, 1995; 71 FR 33641, June 12, 2006]

## § 721.20 Exports and imports.

Persons who intend to export a chemical substance identified in subpart E of this part, or in any proposed rule which would amend subpart E of this part, are subject to the export notification provisions of section 12(b) of the Act. The regulations that interpret section 12(b) appear at 40 CFR part 707. Persons who import a substance identified in a specific section in subpart E of this part are subject to the import certification requirements under section 13 of the Act, which are codified at 19 CFR 12.118 through 12.127 and 127.28. The EPA policy in support of the import certification requirements appears at 40 CFR part 707.

[53 FR 28360, July 27, 1988]

## § 721.25 Notice requirements and procedures.

(a) Each person who is required to submit a significant new use notice

## 40 CFR Ch. I (7–1–10 Edition)

under this part must submit the notice at least 90 calendar days before commencing manufacture, import, or processing of a chemical substance identified in subpart E of this part for a significant new use. The submitter must comply with any applicable requirement of section 5(b) of the Act, and the notice must include the information and test data specified in section 5(d)(1) of the Act. The notice must be submitted on EPA Form 7710–25, and must comply with the requirements of part 720 of this chapter, except to the extent that they are inconsistent with this part 721.

(b) If two or more persons are required to submit a significant new use notice for the same chemical substance and significant new use identified in subpart E of this part, they may submit a joint notice to EPA. Persons submitting a joint notice must individually complete the certification section of part I of the required notification form. Persons who are required to submit individually, but elect to submit jointly, remain individually liable for the failure to submit required information which is known to or reasonably ascertainable by them and test data in their possession or control.

(c) EPA will process the notice in accordance with the procedures of part 720 of this chapter, except to the extent they are inconsistent with this part.

(d) Any person submitting a significant new use notice in response to the requirements of this part 721 shall not manufacture, import, or process a chemical substance identified in subpart E of this part for a significant new use until the notice review period, including all extensions and suspensions, has expired.

[53 FR 28360, July 27, 1988, as amended at 60 FR 16311, Mar. 29, 1995; 75 FR 787, Jan. 6, 2010]

## § 721.30 EPA approval of alternative control measures.

(a) In certain sections of subpart E of this part, significant new uses for the identified substances are described as the failure to establish and implement programs providing for the use of either: specific measures to control worker exposure to or release of substances which are identified in such sections, or alternative measures to

## Environmental Protection Agency

## § 721.35

control worker exposure or environmental release which EPA has determined provide substantially the same degree of protection as the specified control measures. Persons who manufacture, import, or process a chemical substance identified in such sections and who intend to employ alternative measures to control worker exposure or environmental release must submit a request to EPA for a determination of equivalency before commencing manufacture, import, or processing involving the alternative control measures.

(b) Persons submitting a request for a determination of equivalency to EPA under this part, unless allowed by 40 CFR 720.40(a)(2)(i), (ii), or (iii), must submit the request to EPA via EPA's Central Data Exchange (CDX) using EPA-provided e-PMN software in the manner set forth in 40 CFR 720.40(a)(2). See 40 CFR 720.40(a)(2)(iv) for information on how to obtain e-PMN software. Support documents related to these requests must be submitted in the manner set forth in 40 CFR 720.40(a)(2)(i), (ii), or (iii). If submitted by paper, requests must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001; ATTN: SNUR Equivalency Determination or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004; ATTN: SNUR Equivalency Determination. Optical discs containing electronic requests must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004; ATTN: SNUR Equivalency Determination. A request for a determination of equivalency must contain:

- (1) The name of the submitter.
- (2) The specific chemical identity of the substance.
- (3) The citation for the specific section in subpart E of this part which pertains to the substance for which the request is being submitted.

(4) A detailed description of the activities involved.

(5) The specifications of the alternative worker exposure control measures or environmental release control measures.

(6) An analysis justifying why such alternative control measures provide substantially the same degree of protection as the specific control measures identified in the specific section in subpart E of this part which pertains to the substance for which the request is being submitted.

(7) The data and information described in §720.50 (a) and (b) of this chapter unless such data and information have already been submitted to the Office of Pollution Prevention and Toxics, EPA.

(c) Requests for determinations of equivalency will be reviewed by EPA within 45 days. Determinations under this paragraph will be made by the Director, Office of Pollution Prevention and Toxics, or designee. Notice of the results of such determinations will be mailed to the submitter.

(d) If EPA notifies the submitter under paragraph (c) of this section that EPA has determined that the alternative control measures provide substantially the same degree of protection as the specified control measures identified in the specified section of subpart E of this part which pertains to the substance for which the request is being submitted, the submitter may commence manufacture, import, or processing in accordance with the specifications for alternative worker exposure control measures or environmental release control measures identified in the submitter's request, and may alter any corresponding notification to workers to reflect such alternative controls. Deviations from the activities described in the EPA notification constitute a significant new use and are subject to the requirements of this part.

[53 FR 28360, July 27, 1988, as amended at 60 FR 34464, July 3, 1995; 71 FR 33641, June 12, 2006; 75 FR 787, Jan. 6, 2010]

### § 721.35 Compliance and enforcement.

(a) Failure to comply with any provision of this part is a violation of section 15(1) of the Act (15 U.S.C. 2614).

## § 721.40

## 40 CFR Ch. I (7-1-10 Edition)

(b) Using for commercial purposes a chemical substance which a person knew or had reason to know was manufactured, imported, or processed in violation of this part is a violation of section 15(2) of the Act (15 U.S.C. 2614).

(c) Failure or refusal to permit access to or copying of records, as required by section 11 of the Act, is a violation of section 15(3) of the Act (15 U.S.C. 2614).

(d) Failure or refusal to permit entry or inspection, as required by section 11 of the Act, is a violation of section 15(4) of the Act.

(e) Violators of the Act or of this part may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation. The submission of false or misleading information in connection with the requirement of any provision of this part may subject persons to penalties calculated as if they never filed a notice.

(f) Under the authority of sections 7 and 17 of the Act, EPA may:

(1) Seek to enjoin the manufacture, import, or processing of a chemical substance in violation of this part.

(2) Act to seize any chemical substance which is being manufactured, imported, or processed in violation of this part.

(3) Take any other appropriate action.

[53 FR 28361, July 27, 1988]

### § 721.40 Recordkeeping.

Any person subject to the requirements of this part must retain documentation of information contained in that person's significant new use notice. This documentation must be maintained for a period of 5 years from the date of the submission of the significant new use notice.

[53 FR 28361, July 27, 1988]

### § 721.45 Exemptions.

The persons identified in § 721.5 are not subject to the notification requirements of § 721.25 for a chemical substance identified in subpart E of this part, unless otherwise specified in a specific section in subpart E, if:

(a) The person has applied for and has been granted an exemption for test marketing the substance for a signifi-

cant new use identified in subpart E of this part in accordance with section 5(h)(1) of the Act and § 720.38 of this chapter.

(b) The person manufactures, imports, or processes the substance for a significant new use identified in subpart E of this part in small quantities solely for research and development in accordance with § 721.47.

(c) The person has applied for and been granted an exemption under section 5(h)(5) of the Act.

(d) The person manufactures, imports, or processes the substance only as an impurity.

(e) The person manufactures, imports, or processes the substance only as a byproduct which is used only by public or private organizations that (1) burn it as a fuel, (2) dispose of it as a waste, including in a landfill or for enriching soil, or (3) extract component chemical substances from it for commercial purposes.

(f) The person imports or processes the substance as part of an article.

(g) The person manufactures or processes the substance solely for export and, when distributing the substance in commerce, labels the substance in accordance with section 12(a)(1)(B) of the Act.

(h) The person submits a significant new use notice for the substance prior to the promulgation date of the section in subpart E of this part which identifies the substance, and the person receives written notification of compliance from EPA prior to the effective date of such section. The notice submitter must comply with any applicable requirement of section 5(b) of the Act. The notice must include the information and test data specified in section 5(d)(1) of the Act and must be submitted on the notice form in Appendix A to part 720 of this chapter. For purposes of this exemption, the specific section in subpart E of this part which identifies the substance and §§ 721.1, 721.3, 721.11, 721.35, and 721.40 apply; after the effective date of the section in subpart E of this part which identifies the substance, § 721.5 applies and § 721.20 continues to apply. EPA will provide the notice submitter with written notification of compliance only if one of the following occurs:

## Environmental Protection Agency

## § 721.47

(1) EPA is unable to make the finding that the activities described in the significant new use notice will or may present an unreasonable risk of injury to health or the environment under reasonably foreseeable circumstances.

(2) EPA and the person negotiate a consent order under section 5(e) of the Act, such order to take effect on the effective date of the section in subpart E of this part which identifies the substance.

(i) The person is operating under the terms of a consent order issued under section 5(e) of the Act applicable to that person. If a provision of such section 5(e) order is inconsistent with a specific significant new use identified in subpart E of this part, abiding by the provision of the section 5(e) order exempts the person from submitting a significant new use notice for that specific significant new use.

[53 FR 28361, July 27, 1988]

### **§ 721.47 Conditions for research and development exemption.**

(a) A person who manufactures, imports, or processes a chemical substance identifies in subpart E of this part for a significant new use identified in subpart E of this part is not subject to the notification requirements of § 721.25 if the following conditions are met:

(1) The person manufactures, imports, or processes the substance for the significant new use in small quantities solely for research and development.

(2) The manufacturer, importer, or processor notifies all persons in its employ or to whom it directly distributes the chemical substance, who are engaged in experimentation, research, or analysis on the chemical substance, including the manufacture, processing, use, transport, storage, and disposal of the substance associated with research and development activities, of any risk to health, identified under paragraph (b) of this section, which may be associated with the substance. The notification must be made in accordance with paragraph (c) of this section.

(3) The chemical substance is used by, or directly under the supervision of, a technically qualified individual.

(b)(1) To determine whether notification under paragraph (a)(2) of this section is required, the manufacturer, importer, or processor must review and evaluate the following information to determine whether there is reason to believe there is any risk to health which may be associated with the chemical substance:

(i) Information in its possession or control concerning any significant adverse reaction by persons exposed to the chemical substance which may reasonably be associated with such exposure.

(ii) Information provided to the manufacturer, importer, or processor by a supplier or any other person concerning a health risk believed to be associated with the substance.

(iii) Health and environmental effects data in its possession or control concerning the substance.

(iv) Information on health effects which accompanies any EPA rule or order issued under section 4, 5, or 6 of the Act that applies to the substance and of which the manufacturer, importer, or processor has knowledge.

(2) When the research and development activity is conducted solely in a laboratory and exposure to the chemical substance is controlled through the implementation of prudent laboratory practices for handling chemical substances of unknown toxicity, and any distribution, except for purposes of disposal, is to other such laboratories for further research and development activity, the information specified in paragraph (b)(1) of this section need not be reviewed and evaluated. (For purposes of this paragraph (b)(2), a laboratory is defined as a contained research facility where relatively small quantities of chemical substances are used on a pro-production basis, and where activities involve the use of containers for reactions, transfers, and other handling of substances designed to be easily manipulated by a single individual).

(c)(1) The manufacturer, importer, or processor must notify the persons identified in paragraph (a)(2) of this section by means of a container labeling system, conspicuous placement of notices in areas where exposure may occur,

## § 721.50

written notification to each person potentially exposed, or any other method of notification which adequately informs persons of health risks which the manufacturer, importer, or processor has reason to believe may be associated with the substance, as determined under paragraph (b)(1) of this section.

(2) If the manufacturer, importer, or processor distributes a chemical substance manufactured, imported, or processed under this section to persons not in its employ, the manufacturer, importer, or processor must in written form:

(i) Notify those persons that the substance is to be used only for research and development purposes.

(ii) Provide the notice of health risks specified in paragraph (c)(1) of this section.

(3) The adequacy of any notification under this section is the responsibility of the manufacturer, importer, or processor.

(d) Quantities of the chemical substance, or of mixtures or articles containing the chemical substance, remaining after completion of research and development activities may be:

(1) Disposed of as a waste in accordance with applicable Federal, State, and local regulations, to the extent the disposal activity is not identified as a significant new use for the substance in subpart E of this part, or

(2) Used for a commercial purpose, to the extent the use is not identified as a significant new use of the substance in subpart E of this part.

(e)(1) Persons who manufacture, import, or process a chemical substance under this section must retain the following records:

(i) Copies of or citations to information reviewed and evaluated under paragraph (b)(1) of this section to determine the need to make any notification of risk.

(ii) Documentation of the nature and method of notification under paragraph (c)(1) of this section including copies of any labels or written notices used.

(iii) Documentation of prudent laboratory practices used instead of notification and evaluation under paragraph (b)(2) of this section.

(iv) The names and addresses of any persons other than the manufacturer,

## 40 CFR Ch. I (7–1–10 Edition)

importer, or processor to whom the substance is distributed, the identity of the substance, the amount distributed, and copies of the notifications required under paragraph (c)(2) of this section.

(2) [Reserved]

[53 FR 28361, July 27, 1988, as amended at 58 FR 34204, June 23, 1993]

### Subpart B—Certain Significant New Uses

SOURCE: 54 FR 31308, July 27, 1989, unless otherwise noted.

#### § 721.50 Applicability.

This subpart B identifies certain significant new uses of chemical substances identified in subpart E of this part. The provisions of this subpart B apply only when referenced as applying to a chemical substance identified in subpart E of this part.

#### § 721.63 Protection in the workplace.

(a) Whenever a substance is identified in subpart E of this part as being subject to this section, a significant new use of the substance in any manner or method of manufacturing, importing, or processing associated with any use of the substance without establishing a program whereby:

(1) Each person who is reasonably likely to be dermally exposed in the work area to the chemical substance through direct handling of the substance or through contact with equipment on which the substance may exist, or because the substance becomes airborne in the form listed in paragraph (a)(6) of this section, and cited in subpart E of this part for the chemical substance, is provided with, and is required to wear, personal protective equipment that provides a barrier to prevent dermal exposure to the substance in the specific work area where it is selected for use. Each such item of personal protective equipment must be selected and used in accordance with 29 CFR 1910.132 and 1910.133.

(2) In addition to any other personal protective equipment selected in paragraph (a)(1) of this section, the following items are required:

(i) Gloves.

## Environmental Protection Agency

## § 721.63

(ii) Full body chemical protective clothing.

(iii) Chemical goggles or equivalent eye protection.

(iv) Clothing which covers any other exposed areas of the arms, legs, and torso. Clothing provided under this paragraph need not be tested or evaluated under the requirements of paragraph (a)(3) of this section.

(3) The employer is able to demonstrate that each item of chemical protective clothing, including gloves, selected provides an impervious barrier to prevent dermal exposure during normal and expected duration and conditions of exposure within the work area by any one or a combination of the following:

(i) Testing the material used to make the chemical protective clothing and the construction of the clothing to establish that the protective clothing will be impervious for the expected duration and conditions of exposure. The testing must subject the chemical protective clothing to the expected conditions of exposure, including the likely combinations of chemical substances to which the clothing may be exposed in the work area.

(ii) Evaluating the specifications from the manufacturer or supplier of the chemical protective clothing, or of the material used in construction of the clothing, to establish that the chemical protective clothing will be impervious to the chemical substance alone and in likely combination with other chemical substances in the work area.

(4) Each person who is reasonably likely to be exposed to the chemical substance by inhalation in the work area in one or more of the forms listed in paragraph (a)(6) of this section and cited in subpart E of this part for the chemical substance, is provided with, and is required to wear, at a minimum, a NIOSH- approved respirator from one of the categories listed in paragraph (a)(5) of this section, and the respirator is used in accordance with 29 CFR 1910.134 and 30 CFR part 11.

(5) The following NIOSH approved respirators meet the minimum requirements for paragraph (a)(4) of this section:

(i) Category 19C Type C supplied-air respirator operated in pressure demand or other positive pressure mode and equipped with a full facepiece.

(ii) Category 19C Type C supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a tight-fitting facepiece.

(iii) Category 19C Type C supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or helmet or tight-fitting facepiece.

(iv) Category 21C air-purifying respirator equipped with a full facepiece and high efficiency particulate filters.

(v) Category 21C powered air-purifying respirator equipped with a tight-fitting facepiece and high efficiency particulate filters.

(vi) Category 21C powered air-purifying respirator equipped with a loose-fitting hood or helmet and high efficiency particulate filters.

(vii) Category 21C air-purifying respirator equipped with a high efficiency particulate filter including disposable respirators.

(viii) Category 23C air-purifying respirator equipped with a full facepiece and combination cartridges approved for paints, lacquers, and enamels. (Approval label may preclude use for some paints, lacquers, or enamels.)

(ix) Category 23C powered air-purifying respirator equipped with a tight-fitting facepiece and combination cartridges approved for paints, lacquers, and enamels. (Approval label may preclude use for some paints, lacquers, or enamels.)

(x) Category 23C powered air-purifying respirator equipped with a loose-fitting hood or helmet and combination cartridges approved for paints, lacquers, and enamels. (Approval label may preclude use for some paints, lacquers, or enamels.)

(xi) Category 23C air-purifying respirator equipped with combination cartridges approved for paints, lacquers, and enamels, including disposable respirators. (Approval label may preclude use for some paints, lacquers, or enamels.)

(xii) Category 23C air-purifying respirator equipped with a full facepiece and organic gas/vapor cartridges.

§ 721.72

40 CFR Ch. I (7-1-10 Edition)

(xiii) Category 23C powered air-purifying respirator equipped with a tight-fitting facepiece and organic gas/vapor cartridges.

(xiv) Category 23C powered air-purifying respirator equipped with a loose-fitting hood or helmet and organic gas/vapor cartridges.

(xv) Category 23C air-purifying respirator equipped with organic gas/vapor cartridges, including disposable respirators.

(6) When cited in subpart E of this part for a substance, the following airborne form(s) of the substance apply to paragraphs (a) (1) and (4) of this section:

- (i) Dust.
- (ii) Mist.
- (iii) Fume.
- (iv) Smoke.
- (v) Vapor.
- (vi) Gas.

(b) If a substance identified in subpart E of this part is present in the work area only as a mixture, an employer is exempt from the provisions of this section if the concentration of the substance in the mixture does not exceed a concentration set in subpart E of this part. The exemption does not apply if the employer has reason to believe that during intended use or processing in the work area, the substance in the mixture may be concentrated above the level set in subpart E of this part.

(c)(1) If at any time after commencing distribution in commerce of a chemical substance that is identified in subpart E of this part as subject to this section, the person has knowledge that a recipient of the substance is engaging in an activity that is not consistent with the implementation of a program specified in paragraph (a) of this section, the person is considered to have knowledge that the recipient is engaging in a significant new use and is required to follow the procedures in § 721.5(d) unless the person is able to document the following:

(i) That the person has notified the recipient in writing within 15 working days of the time the person first has knowledge that the recipient is engaging in an activity that is not consistent with the implementation of a program specified in paragraph (a) of

this section, and that the person has knowledge of the failure of implementation.

(ii) That within 15 working days of notifying the recipient that the recipient is engaging in an activity that is not consistent with the implementation of a program specified in paragraph (a) of this section the person has received from the recipient, in writing, a statement of assurance that the recipient has established the program required under paragraph (a) of this section, and will take appropriate measures to avoid activities that are inconsistent with implementation of the program required under paragraph (a) of this section.

(2) If, after receiving a statement of assurance from a recipient under paragraph (c)(1)(ii) of this section, a manufacturer, importer, or processor has knowledge that the recipient is engaging in an activity that is not consistent with the implementation of the program specified in paragraph (a) of this section, that person is considered to have knowledge that the person is engaging in a significant new use and is required to follow the procedures in § 721.5(d).

**§ 721.72 Hazard communication program.**

Whenever a substance is identified in subpart E of this part as being subject to this section, a significant new use of that substance in any manner or method of manufacture, import, or processing associated with any use of that substance without establishing a hazard communication program as described in this section.

(a) *Written hazard communication program.* Each employer shall develop and implement a written hazard communication program for the substance in each workplace. The written program will, at a minimum, describe how the requirements of this section for labels, MSDSs, and other forms of warning material will be satisfied. The employer must make the written hazard communication program available, upon request, to all employees, contractor employees, and their designated representatives. The employer

may rely on an existing hazard communication program, including an existing program established under the Occupational Health and Safety Administration (OSHA) Hazard Communication Standard (29 CFR 1900.1200), to comply with this paragraph provided that the existing hazard communication program satisfies the requirements of this paragraph. The written program shall include the following:

(1) A list of each substance identified in subpart E of this part as subject to this section known to be present in the work area. The list must be maintained in the work area and must use the identity provided on the appropriate MSDS for each substance required under paragraph (c) of this section. The list may be compiled for the workplace or for individual work areas.

(2) The methods the employer will use to inform employees of the hazards of non-routine tasks involving the substance, for example, the cleaning of reactor vessels, and the hazards associated with the substance contained in unlabeled pipes in their work area.

(3) The methods the employer will use to inform contractors of the presence of the substance in the employer's workplace and of the provisions of this part applicable to the substance if employees of the contractor work in the employer's workplace and are reasonably likely to be exposed to the substance while in the employer's workplace.

(b) *Labeling.* (1) Each employer shall ensure that each container of the substance in the workplace is labeled in accordance with this paragraph (b)(1).

(i) The label shall, at a minimum, contain the following information:

(A) A statement of health hazard(s) and precautionary measure(s) for the substance, if any, identified in subpart E of this part or by the employer.

(B) The identity by which the substance may be commonly recognized.

(C) A statement of environmental hazard(s) and precautionary measure(s) for the substance, if any, identified in subpart E of this part or by the employer.

(D) A statement of exposure and precautionary measure(s), if any, identified in subpart E of this part or by the employer.

(ii) The employer may use signs, placards, process sheets, batch tickets, operating procedures, or other such written materials in lieu of affixing labels to individual stationary process containers, as long as the alternative method identifies the containers to which it is applicable and conveys information specified by paragraph (b)(1)(i) of this section. Any written materials must be readily accessible to the employees in their work areas throughout each work shift.

(iii) The employer need not label portable containers into which the substance is transferred from labeled containers, and which are intended only for the immediate use of the employee who performs the transfer.

(iv) The employer shall not remove or deface an existing label on incoming containers of the substance unless the container is immediately relabeled with the information specified in paragraph (b)(1)(i) of this section.

(2) Each employer shall ensure that each container of the substance leaving its workplace for distribution in commerce is labeled in accordance with this paragraph.

(i) The label shall, at a minimum, contain the following information:

(A) The information required under paragraph (b)(1)(i) of this section.

(B) The name and address of the manufacturer or a responsible party who can provide additional information on the substance for hazard evaluation and any appropriate emergency procedures.

(ii) The label shall not conflict with the requirements of the Hazardous Materials Transportation Act (18 U.S.C. 1801 et. seq.) and regulations issued under that Act by the Department of Transportation.

(3) The label, or alternative forms of warning, shall be legible and prominently displayed.

(4) The label, or alternative forms of warning, shall be in English; however, the information may be repeated in other languages.

(5) If the label or alternative form of warning is to be applied to a mixture containing a substance identified in subpart E of this part as subject to this section in combination with another substance identified in subpart E of



this part and/or a substance defined as a "hazardous chemical" under the Occupational Safety and Health Administration (OSHA) Hazard Communication Standard (29 CFR 1900.1200), the employer may prescribe on the label, MSDS, or alternative form of warning, the measures to control worker exposure or environmental release which the employer determines provide the greatest degree of protection. However, should these control measures differ from the applicable measures required under subpart E of this part, the employer must seek a determination of equivalency for such alternative control measures pursuant to §721.30 before prescribing them under this paragraph.

(c) *Material safety data sheets.* (1) Each employer must obtain or develop a MSDS for the substance.

(2) Each MSDS shall contain, at a minimum, the following information:

(i) The identity used on the container label of the substance under this section, and, if not claimed confidential, the chemical and common name of the substance. If the chemical and common name are claimed confidential, a generic chemical name must be used.

(ii) Physical and chemical characteristics of the substance known to the employer (such as vapor pressure, flash point).

(iii) The physical hazards of the substance known to the employer, including the potential for fire, explosion, and reactivity.

(iv) The potential human and environmental hazards as specified in subpart E of this part for the substance.

(v) Signs and symptoms of exposure, and any medical conditions which are expected to be aggravated by exposure to the substance known to the employer.

(vi) The primary routes of exposure to the substance.

(vii) Precautionary measures to control worker exposure and/or environmental release identified in subpart E of this part for the substance, or alternative control measures which EPA has determined under §721.30 provide substantially the same degree of protection as the identified control measures.

(viii) Any generally applicable precautions for safe handling and use of the substance which are known to the employer, including appropriate hygienic practices, protective measures during repair and maintenance of contaminated equipment, and procedures for response to spills and leaks.

(ix) Any generally applicable control measures which are known to the employer, such as appropriate engineering controls, work practices, or personal protective equipment.

(x) Emergency first aid procedures known to the employer.

(xi) The date of preparation of the MSDS or of its last revision.

(xii) The name, address, and telephone number of the individual preparing or distributing the MSDS, or a responsible party who can provide additional information on the substance for hazard evaluation and any appropriate emergency procedures.

(3) If no relevant information is found or known for any given category on the MSDS, the employer must mark the MSDS to indicate that no applicable information was found.

(4) Where multiple mixtures containing the substance have similar compositions (i.e., the chemical ingredients are essentially the same, but the specific composition varies from mixture to mixture) and similar hazards, the employer may prepare one MSDS to apply to all of these multiple mixtures.

(5) If the employer becomes aware of any significant new information regarding the hazards of the substance or ways to protect against the hazards, this new information must be added to the MSDS within 3 months from the time the employer becomes aware of the new information. If the substance is not currently being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to the MSDS before the substance is reintroduced into the workplace.

(6) The employer must ensure that persons receiving the substance from the employer are provided an appropriate MSDS with their initial shipment and with the first shipment after an MSDS is revised. The employer may either provide the MSDS with the

## Environmental Protection Agency

## § 721.72

shipped containers or send it to the person prior to or at the time of shipment.

(7) The employer must maintain a copy of the MSDS in its workplace, and must ensure that it is readily accessible during each work shift to employees when they are in their work areas.

(8) The MSDS may be kept in any form, including as operating procedures, and may be designed to cover groups of substances in a work area where it may be more appropriate to address the potential hazards of a process rather than individual substances. However, in all cases, the required information must be provided for each substance and must be readily accessible during each work shift to employees when they are in their work areas.

(9) The MSDS must be printed in English; however, the information may be repeated in other languages.

(d) *Employee information and training.* Each employer must ensure that employees are provided with information and training on the substance identified in subpart E of this part. This information and training must be provided at the time of each employee's initial assignment to a work area containing the substance and whenever the substance subject to this section is introduced into the employee's work area for the first time.

(1) Information provided to employees under this paragraph shall include:

(i) The requirements of this section.

(ii) Any operations in the work area where the substance is present.

(iii) The location and availability of the written hazard communication program required under paragraph (a) of this section, including the list of substances identified in subpart E of this part as subject to this section, and MSDSs required by paragraph (c) of this section.

(2) Training provided to employees shall include:

(i) Methods and observations that may be used to detect the presence or release of the substance in or from an employee's work area (such as monitoring conducted by the employer, continuous monitoring devices, visual appearance, or odor of the substance when being released).

(ii) The potential human health and environmental hazards of the substance as specified in subpart E of this part.

(iii) The measures employees can take to protect themselves and the environment from the substance, including specific procedures the employer has implemented to protect employees and the environment from exposure to the substance, including appropriate work practices, emergency procedures, personal protective equipment, engineering controls, and other measures to control worker exposure and/or environmental release required under subpart E of the part, or alternative control measures which EPA has determined under § 721.30 provide substantially the same degree of protection as the specified control measures.

(iv) The requirements of the hazard communication program developed by the employer under this section, including an explanation of the labeling system and the MSDS required by this section and guidance on obtaining and using appropriate hazard information.

(e) *Low concentrations in mixtures.* If a substance identified in subpart E of this part is present in the work area only as a mixture, an employer is exempt from the provisions of this section if the concentration of the substance in the mixture does not exceed a concentration set in subpart E of this part. The exemption does not apply if the employer has reason to believe that during intended use or processing in the work area, the substance in the mixture may be concentrated above the level set in subpart E of this part.

(f) *Existing hazard communication program.* The employer need not take additional actions if existing programs and procedures satisfy the requirements of this section.

(g) *Human health, environmental hazard, exposure, and precautionary statements.* Whenever referenced in subpart E of this part for a substance, the following human health and environmental hazard, exposure, and precautionary statements shall appear on each label as specified in paragraph (b) of this section and the MSDS as specified in paragraph (c) of this section. Additional statements may be included as long as they are true and do not

§ 721.72

40 CFR Ch. I (7-1-10 Edition)

alter the meaning of the required statements.

(1) Human health hazard statements: This substance may cause:

- (i) Skin irritation.
- (ii) Respiratory complications.
- (iii) Central nervous system effects.
- (iv) Internal organ effects.
- (v) Birth defects.
- (vi) Reproductive effects.
- (vii) Cancer.
- (viii) Immune system effects.
- (ix) Developmental effects.

(2) Human health hazard precautionary statements: When using this substance:

- (i) Avoid skin contact.
- (ii) Avoid breathing substance.
- (iii) Avoid ingestion.
- (iv) Use respiratory protection.
- (v) Use skin protection.

(3) Environmental hazard statements: This substance may be:

- (i) Toxic to fish.
- (ii) Toxic to aquatic organisms.

(4) Environmental hazard precautionary statements: Notice to users:

- (i) Disposal restrictions apply.
- (ii) Spill clean-up restrictions apply.
- (iii) Do not release to water.

(5) Each human health or environmental hazard precautionary statement identified in subpart E of this part for the label on the substance container must be followed by the statement, "See MSDS for details."

(h) *Human health, environmental hazard exposure and precautionary statements.* (1) Whenever referenced in subpart E of this part for a substance, the following human health, environmental hazard, exposure, and precautionary statements shall appear on each label as specified in paragraph (b) of this section. Additional statements may be included as long as they are true and do not alter the meaning of the required statements.

(i) *Precautionary statements.* (A) The health effects of this chemical substance have not been determined.

(B) When using this substance, use skin protection.

(C) Use respiratory protection when there is a reasonable likelihood of exposure in the work area from dust, mist, or smoke from spray application.

(D) Chemicals similar in structure to this substance have been found to cause cancer in laboratory animals.

(ii) *Human health hazard statements.* This substance may cause:

- (A) Skin irritation
- (B) Respiratory complications
- (C) Central nervous system effects
- (D) Internal organ effects
- (E) Birth defects
- (F) Reproductive effects
- (G) Cancer
- (H) Immune system effects
- (I) Developmental effects

(iii) *Human health hazard precautionary statements.* When using this substance:

- (A) Avoid skin contact
- (B) Avoid breathing substance
- (C) Avoid ingestion
- (D) Use respiratory protection
- (E) Use skin protection

(iv) *Environmental hazard statements.* This substance may be:

- (A) Toxic to fish
- (B) Toxic to aquatic organisms

(v) *Environmental hazard precautionary statements.* Notice to Users:

- (A) Disposal restrictions apply
- (B) Spill clean-up restrictions apply
- (C) Do not release to water.

(vi) *Additional statements.* Each human health or environmental precautionary statement identified in subpart E of this part for the label on the substance container must be followed by the statement, "See MSDS for details."

(2) Whenever referenced in subpart E of this part for a substance, the following human health, environmental hazard, exposure, and precautionary statements shall appear on each MSDS as specified in paragraph (c) of this section. Additional statements may be included as long as they are true and do not alter the meaning of the required statements.

(i) *Precautionary statements.* (A) The health effects of this chemical substance have not been determined.

(B) When using this substance, use skin protection.

(C) Use respiratory protection when there is a reasonable likelihood of exposure in the work area from dust, mist, or smoke from spray application.

## Environmental Protection Agency

## § 721.80

(D) Chemicals similar in structure to this substance have been found to cause cancer in laboratory animals.

(ii) *Human health hazard statements.* This substance may cause:

- (A) Skin irritation
- (B) Respiratory complications
- (C) Central nervous system effects
- (D) Internal organ effects
- (E) Birth defects
- (F) Reproductive effects
- (G) Cancer
- (H) Immune system effects
- (I) Developmental effects

(iii) *Human health hazard precautionary statements.* When using this substance:

- (A) Avoid skin contact
- (B) Avoid breathing substance
- (C) Avoid ingestion
- (D) Use respiratory protection
- (E) Use skin protection

(iv) *Environmental hazard statements.* This substance may be:

- (A) Toxic to fish
- (B) Toxic to aquatic organisms

(v) *Environmental hazard precautionary statements.* Notice to Users:

- (A) Disposal restrictions apply
- (B) Spill clean-up restrictions apply
- (C) Do not release to water.

[54 FR 31308, July 27, 1989, as amended at 55 FR 45996, Oct. 31, 1990; 58 FR 34204, June 23, 1993]

### § 721.80 Industrial, commercial, and consumer activities.

Whenever a substance is identified in subpart E of this part as being subject to this section, a significant new use of the substance is:

- (a) Use in non-enclosed processes.
- (b) Any manner or method of manufacture in non-enclosed processes associated with any use.
- (c) Any manner or method of processing in non-enclosed processes associated with any use.
- (d) Use beyond the site of manufacture or import.
- (e) Processing beyond the site of manufacture or import.
- (f) Any manner or method of manufacture (excluding import) of the substance associated with any use.
- (g) Use other than as an intermediate.
- (h) Use other than as a site-limited intermediate.

(i) Use as an intermediate where the concentration of the intermediate substance in the product intended for distribution in commerce exceeds the concentration specified in subpart E of this part for the substance.

(j) Use other than as described in the premanufacture notice referenced in subpart E of this part for the substance.

(k) Use other than allowed by the section 5(e) consent order referenced in subpart E of this part for the substance.

(l) Non-industrial use.

(m) Commercial use.

(n) Non-commercial use.

(o) Use in a consumer product.

(p) Aggregate manufacture and importation volume for any use greater than that specified in subpart E of this part for the substance.

(q) Aggregate manufacture and importation volume for any use greater than that allowed by the section 5(e) consent order referenced in subpart E of this part for the substance.

(r) Aggregate manufacture and importation volume for any use greater than that specified in subpart E of this part for the substance unless the manufacturer or importer has submitted the results of the health or environmental effects studies identified in subpart E of this part for the substance and those studies comply with the procedures and criteria for developing and evaluating data identified in subpart E of this part for the substance.

(s) Annual manufacture and importation volume for any use greater than that specified in subpart E of this part for the substance.

(t) Annual manufacture and importation volume for any use greater than that allowed by the section 5(e) consent order referenced in subpart E of this part for the substance.

(u) Annual manufacture and importation volume for any use greater than that specified in subpart E of this part for the substance unless the manufacturer or importer has submitted the results of the health or environmental effects studies identified in subpart E of this part for the substance and those studies comply with the procedures and criteria for developing and evaluating

**§ 721.85**

**40 CFR Ch. I (7-1-10 Edition)**

data identified in subpart E of this part for the substance.

(v) Use in the form of:

- (1) A powder.
- (2) A solid.
- (3) A liquid.
- (4) A gas.

(w) Any manner or method of manufacture of the substance in the following form associated with any use:

- (1) A powder.
- (2) A solid.
- (3) A liquid.
- (4) A gas.

(x) Any manner or method of processing of the substance in the following form associated with any use:

- (1) A powder.
- (2) A solid.
- (3) A liquid.
- (4) A gas.

(y) Use involving an application method that generates:

- (1) A vapor, mist, or aerosol.
- (2) A dust.

**§ 721.85 Disposal.**

Whenever a substance is identified in subpart E of this part as being subject to this section, a significant new use of the substance is any method of:

(a) Disposal of the process stream associated with any use of the substance or with any manner or method of manufacturing associated with any use of the substance other than by the following. This provision does not supercede any applicable Federal, State, or local laws and regulations.

- (1) Incineration.
- (2) Landfill.
- (3) Deep well injection.

(b) Disposal of the process stream associated with any use or with any manner or method of processing associated with any use other than by the following. This provision does not supercede any applicable Federal, State, or local laws and regulations.

- (1) Incineration.
- (2) Landfill.
- (3) Deep well injection.

(c) Disposal of the use stream associated with any use, other than by the

following. This provision does not supercede any applicable Federal, State, or local laws and regulations.

- (1) Incineration.
- (2) Landfill.
- (3) Deep well injection.

(d) Disposal of the substance associated with any use of the substance, or with any manner or method of manufacture or processing in association with any use. This provision does not supercede any applicable Federal, State, or local laws and regulations.

**§ 721.90 Release to water.**

Whenever a substance is identified in subpart E of this part as being subject to this section, a significant new use of the substance is:

(a) Any predictable or purposeful release of a manufacturing stream associated with any use of the substance, from any site:

(1) Into the waters of the United States.

(2) Into the waters of the United States without application of one or more of the following treatment technologies as specified in subpart E of this part either by the discharger or, in the case of a release through publicly-owned treatment works, by a combination of treatment by the discharger and the publicly-owned treatment works:

- (i) Chemical precipitation and settling.
- (ii) Biological treatment (activated sludge or equivalent) plus clarification.
- (iii) Steam stripping.
- (iv) Resin or activated carbon adsorption.
- (v) Chemical destruction or conversion.
- (vi) Primary wastewater treatment.

(3) Into the waters of the United States without primary wastewater treatment, and secondary wastewater treatment as defined in 40 CFR part 133.

(4) Into the waters of the United States if the quotient from the following formula:

$$\frac{\text{number of kilograms/day/site released}}{\text{receiving stream flow (million liters/day)}} \times 1000 = N \text{ parts per billion}$$

**Environmental Protection Agency**

**§ 721.90**

exceeds the level specified in subpart E of this part when calculated using the methods described in §721.91. In lieu of calculating the above quotient, monitoring or alternative calculations may be used to predict the surface water concentration which will result from the intended release of the substance, if the monitoring procedures or calculations have been approved for such purpose by EPA. EPA will review and act on written requests to approve monitoring procedures or alternative calculations within 90 days after such requests are received. EPA will inform submitters of the disposition of such requests in writing, and will explain the reasons therefor when they are denied.

(b) Any predictable or purposeful release of a process stream containing the substance associated with any use of the substance from any site:

(1) Into the waters of the United States.

(2) Into the waters of the United States without application of one or

more of the following treatment technologies as specified in subpart E of this part either by the discharger or, in the case of a release through publicly-owned treatment works, by a combination of treatment by the discharger and the publicly-owned treatment works:

- (i) Chemical precipitation and settling.
- (ii) Biological treatment (activated sludge or equivalent) plus clarification.
- (iii) Steam stripping.
- (iv) Resin or activated carbon adsorption.
- (v) Chemical destruction or conversion.
- (vi) Primary wastewater treatment.

(3) Into the waters of the United States without primary wastewater treatment, and secondary wastewater treatment as defined in 40 CFR part 133.

(4) Into the waters of the United States if the quotient from the following formula:

$$\frac{\text{number of kilograms/day/site released}}{\text{receiving stream flow (million liters/day)}} \times 1000 = N \text{ parts per billion}$$

exceeds the level specified in subpart E of this part when calculated using the methods described in §721.91. In lieu of calculating the above quotient, monitoring or alternative calculations may be used to predict the surface water concentration which will result from the intended release of the substance, if the monitoring procedures or calculations have been approved for such purpose by EPA. EPA will review and act on written requests to approve monitoring procedures or alternative calculations within 90 days after such requests are received. EPA will inform submitters of the disposition of such requests in writing, and will explain the reasons therefor when they are denied.

(c) Any predictable or purposeful release of a use stream containing the substance associated with any use of the substance from any site:

(1) Into the waters of the United States.

(2) Into the waters of the United States without application of one or more of the following treatment technologies as specified in subpart E of this part either by the discharger or, in the case of a release through publicly-owned treatment works, by a combination of treatment by the discharger and the publicly-owned treatment works:

- (i) Chemical precipitation and settling.
- (ii) Biological treatment (activated sludge or equivalent) plus clarification.
- (iii) Steam stripping.
- (iv) Resin or activated carbon adsorption.
- (v) Chemical destruction or conversion.
- (vi) Primary wastewater treatment.

(3) Into the waters of the United States without primary wastewater treatment, and secondary wastewater treatment as defined in 40 CFR part 133.

(4) Into the waters of the United States if the quotient from:

$$\frac{\text{number of kilograms/day/site released}}{\text{receiving stream flow (million liters/day)}} \times 1000 = N \text{ parts per billion}$$

exceeds the level specified in subpart E of this part, when calculated using the methods described in §721.91. In lieu of calculating the above quotient, however, monitoring or alternative calculations may be used to predict the surface water concentration expected to result from intended release of the substance, if the monitoring procedures or calculations have been approved for such purpose by EPA. EPA will review and act on written requests to approve monitoring procedures or alternative calculations within 90 days after such requests are received. EPA will inform submitters of the disposition of such requests in writing, and will explain the reasons therefor when they are denied.

**§721.91 Computation of estimated surface water concentrations: Instructions.**

These instructions describe the use of the equation specified in §721.90(a)(4) and (b)(4) to compute estimated surface water concentrations which will result from release of a substance identified in subpart E of this part. The equation shall be computed for each site using the stream flow rate appropriate for the site according to paragraph (b) of this section, and the highest number of kilograms calculated to be released for that site on a given day according to paragraph (a) of this section. Two variables shall be considered in computing the equation, the number of kilograms released, and receiving stream flow.

(a) *Number of kilograms released.* (1) To calculate the number of kilograms of substance to be released from manufacturing, processing, or use operations, as specified in the numerator of the equation, develop a process description diagram which describes each manufacturing, processing, or use operation involving the substance. The process description must include the major unit operation steps and chemical conversions. A unit operation is a functional

step in a manufacturing, processing, or use operation where substances undergo chemical changes and/or changes in location, temperature, pressure, physical state, or similar characteristics. Include steps in which the substance is formulated into mixtures, suspensions, solutions, etc.

(2) Indicate on each diagram the entry point of all feedstocks (e.g., reactants, solvents, and catalysts) used in the operation. Identify each feedstock and specify its approximate weight regardless of whether the process is continuous or batch.

(3) Identify all release points from which the substance or wastes containing the substance will be released into air, land, or water. Indicate these release points on the diagram. Do not include accidental releases or fugitive emissions.

(4) For releases identified in the diagram that are destined for water, estimate the amount of substance that will be released before the substance enters control technology. The kilograms of substance released may be estimated based on:

(i) The mass balance of the operation, i.e., totaling inputs and outputs, including wastes for each part of the process such that outputs equal inputs. The amount released to water may be the difference between the amount of the substance in the starting material (or formed in a reaction) minus the amount of waste material removed from each part of the process and not released to water and the amount of the substance in the final product.

(ii) Physical properties such as water solubility where a known volume of water being discharged is assumed to contain the substance at concentrations equal to its solubility in water. This approach is particularly useful where the waste stream results from separation of organic/water phases or

filtration of the substance from an aqueous stream to be discharged.

(iii) Measurements of flow rates of the process/use stream and known concentrations of the substance in the stream.

(5) After releases of a substance to water are estimated for each operation on a site, total the releases of the substance to water from all operations at that site. The value (number of kilograms) specified in the numerator of the equation should reflect total kilograms of substance released to water per day from all operations at a single site.

(6) Use the highest expected daily release of the substance for each site.

(b) *Receiving stream flow.* (1) The receiving stream flow shall be expressed in million liters per day (MLD). The flow rate data to be used must be for the point of release on the water body that first receives release of the substance whether by direct discharge from a site, or by indirect discharge through a Publicly-Owned Treatment Works (POTW) for each site. The flow rate reported shall be the lowest 7-day average stream flow with a recurrence interval of 10 years (7-Q-10). If the 7-Q-10 flow rate is not available for the actual point of release, the stream flow rate should be used from the U.S. Geological Survey (USGS) gauging station that is nearest the point of release that is expected to have a flow rate less than or equal to the receiving stream flow at the point of release.

(2) Receiving stream flow data may be available from the National Pollutant Discharge Elimination System (NPDES) permit for the site or the POTW releasing the substance to surface water, from the NPDES permit-writing authority for the site or the POTW, or from USGS publications, such as the water-data report series.

(3) If receiving stream flow data are not available for a stream, either the value of 10 MLD or the daily flow of wastewater from the site or the POTW releasing the substance must be used as an assumed minimum stream flow. Similarly, if stream flow data are not available because the location of the point of release of the substance to surface water is a lake, estuary, bay, or ocean, then the flow rate to be used

must be the daily flow of wastewater from the site or the POTW releasing the substance to surface water. Wastewater flow data may be available from the NPDES permit or NPDES authority for the site or the POTW releasing the substance to water.

### Subpart C—Recordkeeping Requirements

#### § 721.100 Applicability.

This subpart C identifies certain additional recordkeeping requirements applicable to manufacturers, importers, and processors of substances identified in subpart E of this part for each specific substance. The provisions of this subpart C apply only when referenced in subpart E of this part for a substance and significant new use identified in that subpart E. If the provisions in this subpart C conflict with general provisions of subpart A of this part, the provisions of this subpart C shall apply.

[54 FR 31313, July 27, 1989]

#### § 721.125 Recordkeeping requirements.

At the time EPA adds a substance to subpart E of this part, EPA will specify appropriate recordkeeping requirements which correspond to the significant new use designations for the substance selected from subpart B of this part. Each manufacturer, importer, and processor of the substance shall maintain the records for 5 years from the date of their creation. In addition to the records specified in § 721.40, the records whose maintenance this section requires may include the following:

(a) Records documenting the manufacture and importation volume of the substance and the corresponding dates of manufacture and import.

(b) Records documenting volumes of the substance purchased in the United States by processors of the substance, names and addresses of suppliers, and corresponding dates of purchase.

(c) Records documenting the names and addresses (including shipment destination address, if different) of all persons outside the site of manufacture, importation, or processing to whom



**§ 721.160**

**40 CFR Ch. I (7-1-10 Edition)**

the manufacturer, importer, or processor directly sells or transfers the substance, the date of each sale or transfer, and the quantity of the substance sold or transferred on such date.

(d) Records documenting establishment and implementation of a program for the use of any applicable personal protective equipment required under § 721.63.

(e) Records documenting the determinations required by § 721.63(a)(3) that chemical protective clothing is impervious to the substance.

(f) Records documenting establishment and implementation of the hazard communication program required under § 721.72.

(g) Copies of labels required under § 721.72(b).

(h) Copies of material safety data sheets required under § 721.72(c).

(i) Records documenting compliance with any applicable industrial, commercial, and consumer use limitations under § 721.80.

(j) Records documenting compliance with any applicable disposal requirements under § 721.85, including the method of disposal, location of disposal sites, dates of disposal, and volume of the substance disposed. Where the estimated disposal volume is not known to or reasonably ascertainable by the manufacturer, importer, or processor, that person must maintain other records which demonstrate establishment and implementation of a program that ensures compliance with any applicable disposal requirements.

(k) Records documenting establishment and implementation of procedures that ensure compliance with any applicable water discharge limitations under § 721.90.

[54 FR 31313, July 27, 1989]

**Subpart D—Expedited Process for Issuing Significant New Use Rules for Selected Chemical Substances and Limitation or Revocation of Selected Significant New Use Rules**

SOURCE: 54 FR 31314, July 27, 1989, unless otherwise noted.

**§ 721.160 Notification requirements for new chemical substances subject to section 5(e) orders.**

(a) *Selection of substances.* (1) In accordance with the expedited process specified in this section, EPA will issue significant new use notification requirements and other specific requirements for each new chemical substance that is the subject of a final order issued under section 5(e) of the Act, except for an order that prohibits manufacture and import of the substance, unless EPA determines that significant new use notification requirements are not needed for the substance.

(2) If EPA determines that significant new use notification requirements are not needed for a substance that is subject to a final order issued under section 5(e) of the Act, except for an order that prohibits manufacture or import of the substance, EPA will issue a notice in the FEDERAL REGISTER explaining why the significant new use requirements are not needed.

(b) *Designation of requirements.* (1) The significant new use notification and other specific requirements will be based on and be consistent with the provisions included in the final order issued for the substance under section 5(e) of the Act. EPA may also designate additional activities as significant new uses which will be subject to notification. Designation of additional activities as significant new uses will be done in accordance with the criteria and procedures under § 721.170, or through a separate rulemaking proceeding.

(2) Significant new use requirements and other specific requirements designated under this section will be listed in subpart E of this part. For each substance, subpart E will identify:

(i) The chemical name.

(ii) The activities designated as significant new uses.

(iii) Other specific requirements applicable to the substance, including recordkeeping requirements or any other requirements included in the final section 5(e) order.

(c) *Procedures for issuing significant new use rules.* (1) EPA will issue significant new use rules under this section by one of the following three processes: direct final rulemaking, interim final

rulemaking, or notice and comment rulemaking. EPA will use the direct final rulemaking process to issue significant new use rules unless it determines that, in a particular case, one of the other processes is more appropriate.

(2) FEDERAL REGISTER documents issued to propose or establish significant new uses under this section will contain the following:

(i) The chemical identity of the substance or, if its specific identity is claimed confidential, an appropriate generic chemical name and an accession number assigned by EPA.

(ii) The premanufacture notice number.

(iii) The CAS number, where available and not claimed confidential.

(iv) A summary of EPA's findings under section 5(e)(1)(A) of the Act for the final order issued under section 5(e).

(v) Designation of the significant new uses subject to, or proposed to be subject to, notification and any other applicable requirements.

(vi) Any modifications of subpart A of this part applicable to the specific substance and significant new uses.

(vii) If the FEDERAL REGISTER document establishes a final rule, or notifies the public that a final rule will not be issued after public comment has been received, the document will describe comments received and EPA's response.

(3) *Direct final rulemaking.* (i) When EPA uses the direct final rulemaking procedure to issue a significant new use rule, it will issue a final rule in the FEDERAL REGISTER following its decision to develop a significant new use rule under this section for a specific new chemical substance.

(ii) The FEDERAL REGISTER document will state that, unless written notice is received by EPA within 30 days of publication that someone wishes to submit adverse or critical comments, the rule will be effective 60 days from the date of publication. The written notice of intent to submit adverse or critical comments should state which SNUR(s) will be the subject of the adverse or critical comments, if several SNURs are established through the direct final rule. If notice is received within 30

days that someone wishes to submit adverse or critical comments, the section(s) of the direct final rule containing the SNUR(s) for which a notice of intent to comment was received will be withdrawn by EPA issuing a document in the final rule section of the FEDERAL REGISTER, and a proposal will be published in the proposed rule section of the FEDERAL REGISTER. The proposal will establish a 30-day comment period.

(iii) If EPA, having considered any timely comments submitted in response to the proposal, decides to establish notification requirements under this section, EPA will issue a final rule adding the substance to subpart E of this part and designating the significant new uses subject to notification.

(4) *Notice and comment rulemaking.* (i) When EPA uses a notice and comment procedure to issue a significant new use rule, EPA will issue a proposal in the FEDERAL REGISTER following its decision to develop a significant new use rule under this section for a specific new chemical substance. Persons will be given 30 days to comment on whether EPA should establish notification requirements for the substance under this part.

(ii) If EPA, having considered any timely comments, decides to establish notification requirements under this section, EPA will issue a final rule adding the substance to subpart E of this part and designating the significant new uses subject to notification.

(5) *Interim final rulemaking.* (i) When EPA uses the interim final rulemaking procedure to issue a significant new use rule, EPA will issue an interim final rule in the final rule section of the FEDERAL REGISTER following its decision to develop a significant new use rule for a specific new chemical substance. The document will state EPA's reasons for using the interim final rulemaking procedure.

(A) The significant new use rule will take effect on the date of publication.

(B) Persons will be given 30 days from the date of publication to submit comments.

(ii) Interim final rules issued under this section shall cease to be in effect

§ 721.170

40 CFR Ch. I (7-1-10 Edition)

180 days after publication unless, within the 180-day period, EPA issues a final rule in the FEDERAL REGISTER responding to any written comments received during the 30-day comment period specified in paragraph (c)(5)(i)(B) of this section and promulgating final significant new use notification requirements and other requirements for the substance.

(d) *Schedule for issuing significant new use rules.* (1) Unless EPA determines that a significant new use rule should not be issued under this section, EPA will issue a proposed rule, a direct final rule, or an interim final rule within 180 days of receipt of a valid notice of commencement under § 720.102 of this chapter for any substance for which the notice of commencement was received on or after October 10, 1989.

(2) Unless EPA determines that a significant new use rule should not be issued under this section, EPA will issue a proposed rule, a direct final rule, or an interim final rule within 1 year of October 10, 1989, for any substance for which the valid notice of commencement under § 720.102 of this chapter was received before October 10, 1989.

(3) If EPA receives adverse or critical significant comments following publication of a proposed or interim final rule, EPA will either withdraw the rule or issue a final rule addressing the comments received.

**§ 721.170 Notification requirements for selected new chemical substances that have completed premanufacture review.**

(a) *Selection of substances.* In accordance with the expedited process specified in this section, EPA may issue significant new use notification and recordkeeping requirements for any new chemical substance for which a premanufacture notice has been submitted under part 720 of this chapter if EPA determines that activities other than those described in the premanufacture notice may result in significant changes in human exposure or environmental release levels and/or that concern exists about the substance's health or environmental effects.

(b) *Concern criteria.* EPA may determine that concern exists about a substance's health or environmental effects if EPA makes any one of the following findings:

(1)(i) The substance may cause carcinogenic effects because the substance:

(A) Has been shown by valid test data to cause carcinogenic effects in humans or in at least one species of laboratory animal.

(B) Has been shown to be a possible carcinogen based on the weight of the evidence in short-term tests indicative of the potential to cause carcinogenic effects.

(C) Is closely analogous, based on toxicologically relevant similarities in molecular structure and physical properties, to another substance that has been shown by test data to cause carcinogenic effects in humans or in at least one species of laboratory animal, provided that if there is more than one such analogue, the greatest weight will be given to the relevant data for the most appropriate analogues.

(D) Is known or can reasonably be anticipated, based on valid scientific data or established scientific principles, to be metabolized in humans or transformed in the environment to a substance which may have the potential to cause carcinogenic effects under the criteria in paragraphs (b)(1)(i) (A), (B), or (C) of this section.

(ii) No substance may be regulated based on a finding under paragraph (b)(1) of this section unless EPA has also made the finding under § 721.170(c)(2)(ii).

(2) The substance has been shown by valid test data to cause acutely toxic effects in at least one species of laboratory animal or is closely analogous, based on toxicologically relevant similarities in molecular structure and physical properties, to another substance that has been shown by valid test data to cause acutely toxic effects in at least one species of laboratory animal, provided that if there is more than one such analogue, the greatest weight will be given to the relevant data for the most appropriate analogues.

(3) The substance may cause serious chronic effects, serious acute effects,

## Environmental Protection Agency

## § 721.170

or developmentally toxic effects under reasonably anticipated conditions of exposure because the substance:

(i) Has been shown by valid test data to cause serious chronic effects, serious acute effects, or developmentally toxic effects in humans or in at least one species of laboratory animal at dose levels that could be of concern under reasonably anticipated conditions of exposure.

(ii) Is closely analogous, based on toxicologically relevant similarities in molecular structure and physical properties, to another chemical substance that has been shown by valid test data to cause serious chronic effects, serious acute effects, or developmentally toxic effects in humans or in at least one species of laboratory animal at dose levels that could be of concern under reasonably anticipated conditions of exposure, provided that if there is more than one such analogue, the greatest weight will be given to the relevant data for the most appropriate analogues.

(iii) Is known or can reasonably be anticipated, based on valid scientific data or established scientific principles, to be metabolized in humans or transformed in the environment to a substance which may have the potential to cause serious chronic effects, serious acute effects, or developmentally toxic effects under the criteria in paragraph (b)(3) (i) and (ii) of this section.

(iv) Has been shown to potentially cause developmentally toxic effects based on the weight of the evidence in short-term tests indicative of the potential to cause developmentally toxic effects.

(4) The substance may cause significant adverse environmental effects under reasonably anticipated conditions of release because the substance:

(i) Has been shown by valid test data to cause significant adverse environmental effects at dose levels that could be of concern under reasonably anticipated conditions of release.

(ii) Is closely analogous, based on toxicologically relevant similarities in molecular structure and physical properties, to another substance that has been shown by valid test data to cause significant adverse environmental effects at dose levels that could be of

concern under reasonably anticipated conditions of release, provided that if there is more than one such analogue, the greatest weight will be given to the relevant data for the most appropriate analogues.

(iii) Has been determined, based on calculations using the substance's physical and chemical properties, to be potentially able to cause significant adverse environmental effects at dose levels that could be of concern under reasonably anticipated conditions of release.

(iv) Is known or can reasonably be anticipated, based on valid scientific data or established scientific principles, to be environmentally transformed to a substance which may have the potential to cause significant adverse environmental effects under the criteria in paragraph (b)(4) (i), (ii), and (iii) of this section.

(5) Concern exists about the health or environmental effects of one or more impurities or byproducts of the substance because the impurity or byproduct meets one or more of the criteria in paragraph (b) (1) through (4) of this section and either:

(i) The impurity or byproduct is a new chemical substance and may be present in concentrations that could cause adverse health or environmental effects under reasonably anticipated conditions of exposure or release.

(ii) Reasonably anticipated manufacture, processing, or use activities involving the substance for which a premanufacture notice has been submitted may result in significantly increased human exposure to or environmental release of the impurity or byproduct compared to exposure or release levels resulting from existing activities involving the impurity or byproduct.

(c) *Designation of requirements.* (1) When EPA decides to establish significant new use reporting requirements under this section, EPA may designate as a significant new use any one or more of the activities set forth in subpart B of this part. In addition, EPA may designate specific recordkeeping requirements described under subpart C of this part that are applicable to the substance.

(2) EPA may designate as a significant new use only those activities that (i) are different from those described in the premanufacture notice for the substance, including any amendments, deletions, and additions of activities to the premanufacture notice, and (ii) may be accompanied by changes in exposure or release levels that are significant in relation to the health or environmental concerns identified under paragraph (b) of this section.

(d) *Procedures for issuing significant new use rules.* (1) Significant new use requirements designated under this section will be listed in subpart E of this part. For each substance, subpart E of this part will identify:

(i) The chemical name.

(ii) The activities designated as significant new uses, which may include one or more of the activities described in paragraph (c) of this section.

(iii) Other specific requirements applicable to the substance.

(2) When EPA determines that a substance is a candidate for a significant new use rule under this section, it will notify the person that submitted the premanufacture notice for the substance no later than 7 calendar days before the expiration of the notice review period under §720.75 of this chapter. In providing this notice, EPA will describe the health or environmental concerns identified under paragraph (b) of this section and the activities under consideration for designation as significant new uses. Such notice may be by telephone, but in this event will be confirmed in writing no later than 30 days after completion of the notice review period.

(3) FEDERAL REGISTER documents issued to propose or establish significant new uses under this section will contain the following:

(i) The chemical identity of the substance or, if its specific identity is claimed confidential, an appropriate generic chemical name and an accession number assigned by EPA.

(ii) The premanufacture notice number.

(iii) The CAS number, where available and not claimed confidential.

(iv) A summary of the basis for action under this section.

(v) Designation of the significant new uses subject to, or proposed to be subject to, notification and any other applicable requirements.

(vi) Any modifications of subpart A of this part applicable to the specific substance and significant new uses.

(vii) If the FEDERAL REGISTER document establishes a final rule, or notifies the public that a final rule will not be issued after public comment has been received, the document will describe comments received and EPA's response.

(4) EPA will issue significant new use rules under this section by one of the following three processes: direct final rulemaking, interim final rulemaking, or notice and comment rulemaking. EPA will use the direct final rulemaking process to issue significant new use rules unless it determines that, in a particular case, one of the other processes is more appropriate.

(i)(A) When EPA uses the direct final rulemaking procedure to issue a significant new use rule it will issue a direct final rule in the final rule section of the FEDERAL REGISTER following its decision to develop a significant new use rule under this section for a specific new chemical substance.

(B) The FEDERAL REGISTER document will state that, unless written notice is received by EPA within 30 days after the date of publication that someone wishes to submit adverse or critical comments, the SNUR will be effective 60 days from date of publication. The written notice of intent to submit adverse or critical comments should state which SNUR(s) will be the subject of the adverse or critical comments, if several SNURs are established through the direct final rule. If notice is received within 30 days after the date of publication that someone wishes to submit adverse or critical comments, the section(s) of the direct final rule containing the SNUR(s) for which a notice of intent to comment was received will be withdrawn by EPA issuing a document in the final rule section of the FEDERAL REGISTER, and EPA will issue a proposed rule in the proposed rule section of the FEDERAL REGISTER. The proposed rule will establish a 30-day comment period.

(C) If EPA, having considered any timely comments submitted in response to the proposal, decides to establish notification requirements under this section, EPA will issue a final rule adding the substance to subpart E of this part and designating the significant new uses subject to notification.

(ii)(A) When EPA uses a notice and comment procedure to issue a significant new use rule, EPA will issue a proposed rule in the FEDERAL REGISTER following its decision to develop a significant new use rule under this section for a specific new chemical substance. Persons will be given 30 days to comment on whether EPA should establish notification requirements for the substance under this part.

(B) If EPA, having considered any timely comments, decides to establish notification requirements under this section, EPA will issue a final rule adding the substance to subpart E of this part and designating the significant new uses subject to notification.

(iii)(A) When EPA uses the interim final rulemaking procedure to issue a significant new use rule, EPA will issue an interim final rule in the final rule section of the FEDERAL REGISTER following its decision to develop a significant new use rule for a specific new chemical substance. The document will state EPA's reasons for using the interim final rulemaking procedure.

(1) The significant new use rule will take effect on the date of publication.

(2) Persons will be given 30 days from the date of publication to submit comments.

(B) An interim final rule issued under this section shall cease to be in effect 180 days after publication unless, within the 180-day period, EPA issues a final rule in the FEDERAL REGISTER responding to any written comments received during the 30-day comment period specified in paragraph (d)(4)(iii)(A)(2) of this section and promulgating final significant new use notification requirements and other requirements for the substance.

(e) *Schedule for issuing significant new use rules.* (1) EPA will issue a proposed rule, an interim final rule, or a direct final rule within 270 days of receipt of the notice of commencement under

§ 720.102 of this chapter for any substance for which the notice of commencement was received on or after October 10, 1989.

(2) If EPA receives adverse or critical comments within the designated comment period following publication of a proposed rule or an interim final rule, EPA will either withdraw the rule or issue a final rule addressing the comments received.

[54 FR 31314, July 27, 1989, as amended at 60 FR 16316, Mar. 29, 1995]

**§ 721.185 Limitation or revocation of certain notification requirements.**

(a) *Criteria for modification or revocation.* EPA may at any time modify or revoke significant new use notification requirements for a chemical substance which has been added to subpart E of this part using the procedures under § 721.160 or § 721.170. Such action may be taken under this section if EPA makes one of the following determinations, unless other information shows that the requirements should be retained:

(1) Test data or other information obtained by EPA provide a reasonable basis for concluding that activities designated as significant new uses of the substance will not present an unreasonable risk of injury to human health or the environment.

(2) EPA has promulgated a rule under section 4 or 6 of the Act, or EPA or another agency has taken action under another law for the substance that eliminates the need for significant new use notification under section 5(a)(2) of the Act.

(3) EPA has received significant new use notices for some or all of the activities designated as significant new uses of the substance and, after reviewing such notices, concluded that there is no need to require additional notice from persons who propose to engage in identical or similar activities.

(4) EPA has examined new information, or has reexamined the test data or other information or analysis supporting its decision to add the substance to subpart E of this part under § 721.170 and has concluded that the substance does not meet the criteria under § 721.170(b).

(5) For a substance added to subpart E of this part under § 721.160, EPA has

## § 721.225

examined new information, or has reexamined the test data or other information or analysis supporting its finding under section 5(e)(1)(A)(ii)(I) of the Act, and has concluded that a rational basis no longer exists for the findings that activities involving the substance may present an unreasonable risk of injury to human health or the environment required under section 5(e)(1)(A) of the Act.

(6) For a substance added to subpart E of this part under § 721.160, certain activities involving the substance have been designated as significant new uses pending the completion of testing, and adequate test data developed in accordance with applicable procedures and criteria have been submitted to EPA.

(b) *Procedures for limitation or revocation.* Modification or revocation of significant new use notification requirements for a substance that has been added to subpart E of this part using the procedures described under § 721.160 or § 721.170 may occur either at EPA's initiative or in response to a written request.

(1) Any affected person may request modification or revocation of significant new use notification requirements for a substance that has been added to subpart E of this part using the procedures described in § 721.160 or § 721.170 by writing to the Director of the Office of Pollution Prevention and Toxics and stating the basis for such request. All requests should be sent to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001. ATTN: Request to amend significant new use rule. The request must be accompanied by information sufficient to support the request.

(2) The Director of the Office of Pollution Prevention and Toxics will consider the request, make a determination whether to initiate rulemaking to modify the requirements, and notify the requester of that determination by certified letter. If the request is denied, the letter will explain why EPA has concluded that the significant new use notification requirements for that substance should remain in effect.

## 40 CFR Ch. I (7-1-10 Edition)

(3) If EPA concludes that significant new use notification requirements for a substance should be limited or revoked, EPA will propose the changes in the FEDERAL REGISTER, briefly describe the grounds for the action, and provide interested parties an opportunity to comment.

[54 FR 31314, July 27, 1989, as amended at 58 FR 34204, June 23, 1993; 60 FR 34464, July 3, 1995; 71 FR 33641, June 12, 2006]

### Subpart E—Significant New Uses for Specific Chemical Substances

#### § 721.225 2-Chloro-N-methyl-N-substituted acetamide (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 2-chloro-N-methyl-N-substituted acetamide (PMN P-84-393) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63(a)(1), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iv), (g)(2)(i), and (g)(2)(v). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDSs are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified § 721.80(g).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements as specified in § 721.125 (a) through (g) and (i) are applicable to manufacturers, importers, and processors of this substance.

## Environmental Protection Agency

## § 721.285

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 32412, Aug. 9, 1990, as amended at 57 FR 20424, May 13, 1992. Redesignated at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.267 N-[2-[(substituted dinitrophenyl)azo]diallylamino-4-substituted phenyl] acetamide (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as N-[2-[(substituted dinitrophenyl)azo]diallylamino-4-substituted phenyl] acetamide (PMN P-95-513) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63734, Dec. 2, 1996]

### § 721.275 Halogenated-N-(2-propenyl)-N-(substituted phenyl) acetamide.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated-N-(2-propenyl)-N-(substituted phenyl) acetamide (P-83-1085) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (e), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25988, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.285 Acetamide, N-[4-(pentyloxy)phenyl]-, acetamide, N-[2-nitro-4-(pentyloxy)phenyl]-, and acetamide, N-[2-amino-4-(pentyloxy)phenyl]-.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as acetamide, N-[4-(pentyloxy)phenyl]- (PMN P-92-31), acetamide, N-[2-nitro-4-(pentyloxy)phenyl]- (PMN P-92-32), and acetamide, N-[2-amino-4-(pentyloxy)phenyl]- (PMN P-92-33) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 90 ppb for PMNs P-92-31 and P-92-32, and N = 30 ppb for P-92-33). When calculating the surface water concentrations according to the instructions in § 721.90(a)(4), the statement that the amount of the substance that will be released will be calculated before the substance enters control technology does not apply. Instead, if the waste stream containing the substance will be treated before release, then the amount of the substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 25 percent removal efficiency may be attributed to such treatment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to



### § 721.303

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51702, Oct. 4, 1993]

### § 721.303 Substituted acetate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted acetate (PMN P-99-0365) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81398, Dec. 26, 2000]

### § 721.304 Acetic acid, [(5-chloro-8-quinolinyloxy)-, 1-methyl hexyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as acetic acid, [(5-chloro-8-quinolinyloxy)-, 1-methylhexyl ester (PMN P-01-170; CAS No. 99607-70-2) is subject to reporting under this section for the significant new use described in paragraph (a)(1) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63(a)(1), (a)(3), (a)(4), and (a)(5)(iv).

### 40 CFR Ch. I (7-1-10 Edition)

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70173, Dec. 17, 2003]

### § 721.305 Di-substituted acetophenone (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as di-substituted acetophenone (PMN P-97-93) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(2)(i), (g)(2)(v). The following statement shall appear on each label as specified in § 721.72(b) and the MSDS as specified in § 721.72(c): This substance is expected to be dermally absorbed and may cause effects to the liver, kidney, adrenal glands, and the heart.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

## Environmental Protection Agency

## § 721.323

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 44574, Aug. 20, 1998]

### § 721.320 Acrylamide-substituted epoxy.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as acrylamide-substituted epoxy (PMN P-92-660) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(2)(iv), (a)(3), (a)(4), (a)(5)(i), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51681, Oct. 4, 1993]

### § 721.321 Substituted acrylamides and acrylic acid copolymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted acrylamides and acrylic acid copolymer (PMN P-00-0490)

is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15079, Mar. 28, 2003]

### § 721.323 Substituted acrylamide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as substituted acrylamide (PMN P-90-1687) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(iii), (a)(3), (a)(4), (a)(6)(ii), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c). Section 721.63 (a)(5)(i), (a)(5)(ii), and (a)(5)(iii) apply to manufacturing operations only; § 721.63(a)(5)(ix), (a)(5)(x), and (a)(5)(xi) apply to processing and use operations only.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5). The following additional statement shall appear on each label and MSDS as required by this paragraph: This substance may cause nervous system effects.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section.

## § 721.324

## 40 CFR Ch. I (7–1–10 Edition)

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51702, Oct. 4, 1993]

### § 721.324 Alkoxyated acrylate polymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkoxyated acrylate polymer (PMN P-98-807) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 366, Jan. 5, 2000]

### § 721.329 Halogenated benzyl ester acrylate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated benzyl ester acrylate (PMN P-90-1527) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (b), and (c) (concentration set at 1.0 percent). The reporting require-

ment for § 721.63(a)(5)(i) applies only during manufacture. The reporting requirement for § 721.63 (a)(5)(ii), (a)(5)(iv), and (a)(5)(v) applies only during processing.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g), (g)(1)(iv), (g)(2)(ii), (g)(2)(iv), and (g)(5). The following statement shall appear on each label as specified in § 721.72(b) and the Material Safety Data Sheet (MSDS) as specified in § 721.72 (c): The substance may cause internal organ effects (kidney and blood). The requirements of this section do not apply when the PMN substance is bound or embedded into a plastic, resin matrix, or pellet.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 366, Jan. 5, 2000]

### § 721.330 Aromatic acrylate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an aromatic acrylate (PMN P-01-420) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a),

## Environmental Protection Agency

## § 721.405

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70174, Dec. 17, 2003]

### § 721.333 Dimethyl alkylamine salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as a Dimethyl alkylamine salt (PMNs P-99-0368 and P-99-0369) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81398, Dec. 26, 2000]

### § 721.336 Perfluoroalkylethyl acrylate copolymer (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a perfluoroalkylethyl acrylate copolymer (PMN P-94-241) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63734, Dec. 2, 1996]

### § 721.338 Salt of an acrylate copolymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as salt of an acrylate copolymer (PMNs P-00-0333 and P-00-0334) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(2), (w)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15079, Mar. 28, 2003]

### § 721.405 Polyether acrylate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyether acrylate (PMN P-95-666) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## § 721.430

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3419, Jan. 22, 1998]

## § 721.430 Oxo-substituted aminoalkanoic acid derivative.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as oxo-substituted amino alkanolic acid derivative (PMN No. P-92-692) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a) through (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (a)(2), and (a)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32236, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

## 40 CFR Ch. I (7-1-10 Edition)

## § 721.435 Alkylphenylpolyetheralkanolamines (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkylphenylpolyetheralkanolamines (PMNs P-97-880/881/882) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44574, Aug. 20, 1998]

## § 721.445 Substituted ethyl alkenamide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted ethyl alkenamide (PMN No. P-86-1315) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(ii), (g)(1)(vii), (g)(2)(i), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Use other than polymerizing all residual materials from the manufacture, processing, and equipment rinsing of the PMN substance so that no monomers of the PMN substance are released to the environment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## Environmental Protection Agency

## § 721.480

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[58 FR 32236, June 8, 1993]

### § 721.450 Hydrofluorochloroalkene (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a hydrofluorochloroalkene (PMN P-97-593) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44574, Aug. 20, 1998]

### § 721.463 Acrylate of polymer based on isophorone diisocyanate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as acrylate of polymer based on isophorone diisocyanate (PMN P-00-0626) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), (c)(4) (N=3 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15079, Mar. 28, 2003]

### § 721.465 Alkoxyated alkylpolyol acrylates, adduct with alkylamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkoxyated alkylpolyol acrylates, adduct with alkylamine (PMNs P-98-0082, P-98-0083, and P-98-0084) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15079, Mar. 28, 2003]

### § 721.480 Aminoester of polyalkenylated alkyldicarboxylic acid (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Aminoester of polyalkenylated alkyldicarboxylic acid (PMN P-99-0115) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## § 721.484

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81398, Dec. 26, 2000]

### § 721.484 Fluorinated acrylic copolymer (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a fluorinated acrylic copolymer (PMN P-95-1208) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), (x)(1), and (y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63735, Dec. 2, 1996]

### § 721.505 Halogenated acrylonitrile.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated acrylonitrile, (PMN P-90-299) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## 40 CFR Ch. I (7-1-10 Edition)

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(ii), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(iii), (g)(1)(iv), (g)(1)(v), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (h).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 15792, Apr. 17, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.520 Alanine, N-(2-carboxyethyl)-N-alkyl-, salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alanine, N-(2-carboxyethyl)-N-alkyl-, salt (P-89-336) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), (c)(4) (where N = 100). The requirement of 40 CFR 721.91(a)(4) that the amount of the substance estimated to be released to water is calculated before entering control technology is not retained. Instead, if the waste stream containing the PMN substance will be treated using biological treatment (activated sludge or equivalent) plus clarification,

## Environmental Protection Agency

## § 721.525

then the amount of PMN substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 90 percent removal efficiency may be attributed to such treatment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 15789, Apr. 17, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.522 Oxirane, methyl-, polymer with oxirane, mono(3,5,5-trimethylhexyl) ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as oxirane, methyl-, polymer with oxirane, mono(3,5,5-trimethylhexyl) ether (PMN P-99-0669; CAS No. 204336-40-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 15080, Mar. 28, 2003]

### § 721.524 Alcohols, C<sub>6-12</sub>, ethoxylated, reaction product with maleic anhydride.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alcohols, C<sub>6-12</sub>, ethoxylated, reaction product with maleic anhydride (PMN P-88-1108) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 300).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3419, Jan. 22, 1998]

### § 721.525 1-propanol, 3-propoxy-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-propanol, 3-propoxy- (PMN P-00-0827; CAS No. 4161-22-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i) and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(o) and (j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),



## § 721.530

## 40 CFR Ch. I (7–1–10 Edition)

(b), (c), (d), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 15080, Mar. 28, 2003]

### § 721.530 Substituted aliphatic acid halide (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance substituted aliphatic acid halide (PMN P-84-491) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i) through (a)(5)(iii), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) (concentration set at 0.1 percent), (f) and (g)(1)(vii), (g)(2)(i) through (g)(2)(v), and (g)(4)(i). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1) and (c)(1). (In lieu of incineration, persons subject to this section may dispose of wastes containing the substance by chemically treating liquid wastes so that the first hydrolysis product is less than 10 ppm prior to discharge or purifying the waste stream so that the first hydrolysis product is less than 10 ppm. Those purified waste streams may be reused or sold. All of the substance removed by these processes must be incinerated

or treated and released as described in this paragraph (a)(2)(iv).)

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (e) through (f), (i) and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32412, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.532 Substituted hydroxyalkane acetate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted hydroxyalkane acetate (PMN P-00-0618) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 15080, Mar. 28, 2003]

### § 721.533 Propane, 1,1,1,3,3-pentachloro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

## § 721.536

chemical substance identified as propane, 1,1,1,3,3-pentachloro- (PMN P-99-1327; CAS No. 23153-23-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15080, Mar. 28, 2003]

### § 721.535 Halogenated alkane (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated alkane (PMN P-01-433) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70174, Dec. 17, 2003]

### § 721.536 Halogenated phenyl alkane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generi-

cally as halogenated phenyl alkane (PMN P-89-867) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply once the substance has been incorporated into a resin.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(5)(v), (6)(i), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance. As an alternative to the respiratory requirements in this section manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (g)(1)(vii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) [Reserved]

(v) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51681, Oct. 4, 1993]

## § 721.537 Organosilane ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an organosilane ester (PMN P-96-1661/P-95-1654) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(r) (370,000 kilogram (kg)) (90-day subchronic inhalation study in rats—(40 CFR 799.9346) (62 FR 43828, August 15, 1997) (FRL-5719-5). A person may not manufacture or import the substance beyond the aggregate production volume limit, unless that person conducts this study on the substance and submits all final reports and underlying data in accordance with the procedures and criteria specified in paragraphs (a)(2)(i)(A), (a)(2)(i)(B), (a)(2)(i)(C), and (a)(2)(i)(D) of this section.

(A) Each study required to be performed pursuant to this section must be scientifically valid. *Scientific valid* means that the study was conducted according to:

(1) The test guidelines specified in paragraph (a)(2)(i) of this section.

(2) An EPA-approved protocol.

(3) TSCA Good Laboratory Practice Standards at 40 CFR part 792.

(4) Using methodologies generally accepted at the time the study is initiated.

(5) Any deviation from these requirements must be approved in writing by EPA.

(B) Before starting to conduct any of the studies in paragraph (a)(2)(i) of this section, the person must obtain approval of test protocols from EPA by submitting written protocols. EPA will respond to the person within 4 weeks of receiving the written protocols. Published test guidelines specified in paragraph (a)(2)(i) of this section (e.g., 40 CFR part 797 or part 798) provide general guidance for development of test protocols, but are not themselves acceptable protocols.

(C) The person shall:

(1) Conduct each study in good faith with due care.

(2) Promptly furnish to EPA the results of any interim phase of each study.

(3) Submit, in triplicate (with an additional sanitized copy, if confidential business information is involved), the final report of each study and all underlying data (“the report and data”) to EPA no later than 14 weeks prior to exceeding the applicable production volume limit. The final report shall contain the contents specified in 40 CFR 792.185.

(D)(1) Except as described in paragraph (a)(2)(i)(D)(2) of this section, if, within 6 weeks of EPA’s receipt of a test report and data, the person receives written notice that EPA finds that the data generated by a study are scientifically invalid, the person is prohibited from further manufacture and import of the PMN substance beyond the applicable production volume limit.

(2) The person may continue to manufacture and import the PMN substance beyond the applicable production limit only if so notified, in writing, by EPA in response to the person’s compliance with either of the following paragraphs (a)(2)(i)(D)(2)(i) or (a)(2)(i)(D)(2)(ii) of this section.

(i) The person may reconduct the study. If there is sufficient time to reconduct the study and submit the report and data to EPA at least 14 weeks before exceeding the production limit as required by paragraph (a)(2)(i)(C)(3) of this section, the person shall comply with paragraph (a)(2)(i)(C)(3) of this section. If there is insufficient time for the person to comply with paragraph (a)(2)(ii)(C)(3) of this section, the person may exceed the production limit and shall submit the report and data in triplicate to EPA within a reasonable period of time, all as specified by EPA in the notice described in paragraph (a)(2)(i)(D)(1) of this section. EPA will respond to the person in writing, within 6 weeks of receiving the person’s report and data.

(ii) The person may, within 4 weeks of receiving from EPA the notice described in paragraph (a)(2)(i)(D)(1) of this section, submit to EPA a written report refuting EPA’s finding. EPA will

## Environmental Protection Agency

## § 721.539

respond to the person in writing, within 4 weeks of receiving the person's report.

(E) The person is not required to conduct a study specified in paragraph (a)(2)(i) of this section if notified in writing by EPA that it is unnecessary to conduct that study.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3419, Jan. 22, 1998]

### § 721.538 Phenol, 4-(1,1-dimethylethyl)-, homopolymer.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as phenol, 4-(1,1-dimethylethyl)-, homopolymer (PMN P-95-243; CAS No. 30813-81-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(3) of this section.

(2) *High molecular weight exemption.* A batch of the chemical substance may be exempt from the provisions of this rule if the average number molecular weight of the substance is greater than 1,000 and the low molecular weight species below 1,000 and 500 are less than 25 percent and 10 percent, respectively. To be eligible for this exemption, the batch must be individually measured.

(3) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (d), (f), (g)(3)(i), (g)(4)(i), and (g)(5). The label and material safety data sheet (MSDS) as required by this paragraph shall also include the following statement: This substance is toxic to aquatic invertebrate.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4) and (b)(4) (N = 9). When calculating the surface water

concentrations according to the instructions in § 721.91, the statement that the amount of the substance that will be released will be calculated before the substance enters control technology does not apply. Instead, if the waste stream containing the substance will be treated using primary and secondary wastewater treatment with control of suspended solids, before release, then the amount of the substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 95 percent removal efficiency may be attributed to such treatment. These requirements do not apply to the sites specifically exempted in the TSCA section 5(e) consent order for this substance.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3420, Jan. 22, 1998]

### § 721.539 Poly(oxy-1,2-ethanediyl), $\alpha$ -sulfo- $\omega$ -[1-[(4-nonylphenoxy)methyl]-2-(2-propenyloxy)ethoxy]-, branched, ammonium salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as Poly(oxy-1,2-ethanediyl),  $\alpha$ -sulfo- $\omega$ -[1-[(4-nonylphenoxy)methyl]-2-(2-propenyloxy)ethoxy]-, branched, ammonium salts (PMN P-96-1240; CAS No. 184719-88-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

**§ 721.540**

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3420, Jan. 22, 1998]

**§ 721.540 Alkylphenoxypolyalkoxyamine (generic name).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylphenoxypolyalkoxyamine (PMN P-86-1489) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (f), and (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) *Release to water.* Section 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (f), (g), (h), and (k).

(2) *Limitations or revocation of certain requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 26097, June 26, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.545 Polyalkenylalkylphenol (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a Polyalkenylalkylphenol (PMN P-99-0472) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

**40 CFR Ch. I (7-1-10 Edition)**

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81398, Dec. 26, 2000]

**§ 721.550 Alkyl alkenoate, azobis-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkyl alkenoate, azobis- (PMN P-88-2470) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i) through (a)(5)(iii), (a)(6)(ii), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), and (g)(5). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## Environmental Protection Agency

## § 721.562

this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e), (f), (g), and (h).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 46771, Nov. 6, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.555 Alkyl amino nitriles (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkyl amino nitriles (PMNs P-96-1674 and P-96-1675) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(iii), (a)(4), (a)(5)(i), (a)(6)(ii), (a)(6)(v), and (c). A full face shield is required if splashing or spraying occurs.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (c)(1) and (c)(2)(iv). The MSDS required by this paragraph shall include the following statement: Ocular exposure may cause death.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 65709, Nov. 30, 1998]

### § 721.558 Salt of a fatty alkylamine derivative (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a salt of a fatty alkylamine derivative (PMN P-96-1426) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44575, Aug. 20, 1998]

### § 721.562 Substituted alkylamine salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted alkylamine salt (PMN P-85-941) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where n = 70).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45080, Aug. 30, 1995]

**§ 721.575 Substituted alkyl halide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted alkyl halide (PMN P-83-1222) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i) through (a)(5)(iii), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(ii), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a), and (c), respectively. The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b), and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e), and (f).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 46772, Nov. 6, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.600 3-Alkyl-2-(2-anilino)vinyl thiazolinium salt (generic name).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as 3-alkyl-2-(2-anilino)

lino)vinylthiazolinium salt (PMN P-84-1007) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e), (f) [concentration set at 1 percent], (g)(1)(iii), (g)(1) (may be lethal if inhaled or in contact with eyes), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[55 FR 26102, June 26, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.625 Alkylated diarylamine, sulfurized (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylated diarylamine, sulfurized (PMN P-89-506) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q)

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26099, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.630 Salt of a modified tallow alkylenediamine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a salt of a modified tallow alkylenediamine (PMN P-96-1425) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44575, Aug. 20, 1998]

**§ 721.632 Silicoaluminophosphates, compd. with organic amine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generi-

cally as Silicoaluminophosphates, compd. with organic amine (PMN P-98-1274) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (b) and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the New Chemical Exposure Limit (NCEL) provisions listed in the section TSCA 5(e) consent order for these substances. The NCEL is 0.1 mg/m<sup>3</sup> as an 8-hour time weighted average verified by actual monitoring data.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (g)(1)(ii), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81398, Dec. 26, 2000]

**§ 721.633 Aluminosilicates, phospho-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as Aluminosilicates, phospho- (PMN P-98-1275; CAS No. 201167-69-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (b), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the



**§ 721.638**

**40 CFR Ch. I (7–1–10 Edition)**

NCEL provisions listed in the TSCA section 5(e) consent order for these substances. The NCEL is 0.1 mg/m<sup>3</sup> as an 8-hour time weighted average verified by actual monitoring data.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (g)(1)(ii), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81399, Dec. 26, 2000]

**§ 721.638 Silyl amine, potassium salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as silyl amine, potassium salt (PMN P-00-1086) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitation or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15080, Mar. 28, 2003]

**§ 721.639 Amine aldehyde condensate.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an amine aldehyde condensate (PMN P-94-1810) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45080, Aug. 30, 1995]

**§ 721.640 Amine substituted metal salts.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as amine substituted metal salts (PMNs P-96-1337/1338/1339) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 4).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3421, Jan. 22, 1998]

## Environmental Protection Agency

## § 721.644

### § 721.641 Alkylpoly(oxyalkylene)amine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkylpoly(oxyalkylene)amine (PMN P-96-1430) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3421, Jan. 22, 1998]

### § 721.642 Amines, N-(C<sub>14-18</sub> and C<sub>16-16</sub> unsaturated alkyl) dipropylene-tri-, tripropylenetetra-, and tetrapropylenepenta-.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances amines, N-(C<sub>14-18</sub> and C<sub>16-18</sub> unsaturated alkyl) dipropylenetri-, (PMN P-94-1244), tripropylenetetra- (PMN P-94-1245), and tetrapropylenepenta- (PMN P-94-1246) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11041, Mar. 1, 1995]

### § 721.643 Ethoxylated alcohol, phosphated, amine salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as an ethoxylated alcohol, phosphated, amine salt (PMN P-96-1478) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 8).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3421, Jan. 22, 1998]

### § 721.644 Amines, C<sub>12-14</sub>-tert-alkyl, sulfonates.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as amines, C<sub>12-14</sub>-tert-alkyl, sulfonates (PMN P-98-400; CAS No. 197527-19-8) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

## § 721.646

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 366, Jan. 5, 2000]

### § 721.646 Aminofluoran derivative (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as aminofluoran derivative (PMN P-95-512) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63735, Dec. 2, 1996]

### § 721.647 Alkoxyated alkyl amine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkoxyated alkyl amine (PMN P-01-578) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

## 40 CFR Ch. I (7-1-10 Edition)

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 70174, Dec. 17, 2003]

### § 721.648 Alkyl dialkylamino phenylsulfonyl alkenoate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkyl dialkylamino phenylsulfonyl alkenoate (PMN P-00-0816) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15080, Mar. 28, 2003]

### § 721.650 11-Aminoundecanoic acid.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance 11-aminoundecanoic acid, CAS Number 2432-99-7, is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is any use other than as.

(i) An intermediate in the manufacture of polymers in an enclosed process when it is expected that the 11-aminoundecanoic acid will be fully polymerized during the manufacturing process, or

(ii) A component in photoprocessing solutions.

(b) *Specific requirements.* The provisions of Subpart A of this part apply to this section except as modified by this paragraph.

(1) *Definitions.* In addition to the definitions in § 721.3, the following definitions apply to this section:

(i) *Enclosed process* means a process that is designed and operated so that there is no intentional release of any substance present in the process. A process with fugitive, inadvertent, or emergency pressure relief releases remains an enclosed process so long as measures are taken to prevent worker exposure to and environmental contamination from the releases.

(ii) *Internal subunit* means a subunit that is covalently linked to at least two other subunits. *Internal subunits* of polymer molecules are chemically derived from monomer molecules that have formed covalent links between two or more other molecules.

(iii) *Monomer* means a chemical substance that has the capacity to form links between two or more other molecules.

(iv) *Polymer* means a chemical substance that consists of at least a simple weight majority of polymer molecules but consists of less than a simple weight majority of molecules with the same molecular weight. Collectively, such polymer molecules must be distributed over a range of molecular weights wherein differences in molecular weight are primarily attributable to differences in the number of internal subunits.

(v) *Polymer molecule* means a molecule which includes at least four covalently linked subunits, at least two of which are internal subunits.

(vi) *Subunit* means an atom or group of associated atoms chemically derived from corresponding reactants.

(2) [Reserved]

[52 FR 19865, May 28, 1987. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 53 FR 29946, May 24, 1993]

**§ 721.655 Ethoxylated alkyl quaternary ammonium compound.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an ethoxylated alkyl quaternary ammonium compound (PMN P-96-

573) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3421, Jan. 22, 1998]

**§ 721.715 Trisubstituted anthracene.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as trisubstituted anthracene (PMN P-91-689) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set 0.1 percent), (f), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (First limit set at 500 kg; second limit set at 25,000 kg).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 10 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) and (k) are applicable to

## § 721.720

manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27481, May 27, 1994]

### § 721.720 Alkoxyated fatty acid amide, alkylsulfate salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkoxyated fatty acid amide, alkylsulfate salt (PMN P-97-136) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3422, Jan. 22, 1998]

### § 721.750 Aromatic amine compound.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance aromatic amine compound (PMN P-86-334) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent) and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(i) through (g)(2)(iii), and (g)(2)(v). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of

## 40 CFR Ch. I (7-1-10 Edition)

a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b) and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e) and (f).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 39899, Sept. 28, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.757 Polyoxyalkylene substituted aromatic azo colorant.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polyoxyalkylene substituted aromatic azo colorant (PMN P-92-1131) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (w)(1) and (w)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51681, Oct. 4, 1993]

## Environmental Protection Agency

## § 721.805

### § 721.775 Brominated aromatic compound (generic name).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as a brominated aromatic compound (PMN P-84-824) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(1), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(2)(v). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j) (use as an additive flame retardant for plastics) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (g), (i), and (k).

(2) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

(3) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[55 FR 26098, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.785 Halogenated alkane aromatic compound (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a halogenated alkane aromatic compound (PMN P-94-1747) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(5)(v), (6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (g)(1)(vii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[61 FR 63735, Dec. 2, 1996]

### § 721.805 Benzenamine, 4,4'-[1,3-phenylenebis(1-methylethylidene)]bis[2,6-dimethyl-

(a) Chemical substances and significant new uses subject to reporting. (1) The chemical substance benzenamine, 4,4'-[1,3-phenylenebis(1-methyl ethylidene)]bis[2,6-dimethyl- (CAS Registry Number 2716-12-3; PMN P-86-501) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## § 721.825

## 40 CFR Ch. I (7-1-10 Edition)

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv) through (a)(5)(xv), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), (c)(1), (a)(2), (b)(2), and (c)(2).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(vi), (b)(2)(vi), and (c)(2)(vi).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified in § 721.125 (a) through (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 31330, July 15, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.825 Certain aromatic ether diamines.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The following chemical substances are subject to reporting under this section for the significant new uses described in paragraphs (a)(2), (a)(3), and (a)(4) of this section: Benzenamine, 4,4'-[[1,1'-biphenyl]-2,5-diylbis(oxy)]bis- (CAS Number 94148-67-1, Premanufacture notice (PMN) P-85-335); 1,2,4,5-benzenetetracarboxylic acid, diethyl ester, compound with 4,4'-[[1,1'-biphenyl]-2,5-diylbis(oxy)]bis[benzenamine] (1:1) (PMN P-85-336); and 1,2,4,5-benzenetetracarboxylic acid, 1,4-diethyl ester, compound with 4,4'-[[1,1'-

biphenyl]-2,5-diylbis(oxy)]bis[benzenamine] (1:1), polymer with 4,4'-[[1,1'-biphenyl]-2,5-diylbis(oxy)]bis[benzenamine]-1,5-diethyl-1,2,4,5-benzenetetracarboxylate (1:1), reaction products with phthalic anhydride (PMN P-86-1153).

(2) The significant new use for P-85-335 is: Manufacture, import, or processing in a quantity of 100,000 pounds per year, or greater, for any use.

(3) The significant new use for P-85-336 is: Any use.

(4) The significant new use for P-86-1153 is: Manufacture, import, or processing in a quantity of 225,000 pounds per year, or greater, for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes a substance identified in paragraph (a)(3) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[59 FR 43296, Aug. 23, 1994]

## § 721.840 Alkyl substituted diaromatic hydrocarbons.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkyl substituted diaromatic hydrocarbons (PMN P-91-710) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

## Environmental Protection Agency

## § 721.910

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46464, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.843 Substituted phenylazophenylazo phenol (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted phenylazophenylazo, phenol (PMN P-00-0420) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15081, Mar. 28, 2003]

### § 721.875 Aromatic nitro compound.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance aromatic nitro compound (PMN P-86-335) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv) through (a)(5)(vii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), and (g)(2)(i) through (g)(2)(v). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written haz-

ard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b) and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e), and (f).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 39899, Sept. 28, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.910 Propanetriol polyalkylenepolyolamine aryl aldimine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as propanetriol polyalkylenepolyolamine aryl aldimine (PMN P-99-0873) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15081, Mar. 28, 2003]



## § 721.925

## 40 CFR Ch. I (7–1–10 Edition)

### § 721.925 Substituted aromatic (generic).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted aromatic (PMN P-84-954) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(2)(i), and (g)(2)(v). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b) and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (level set at 0.25 ppm).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[55 FR 26098, June 26, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.950 Sodium salt of an alkylated, sulfonated aromatic (generic name).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as a sodium salt of an alkylated, sulfonated aromatic (PMN P-84-591) is

subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j) (use as a dye leveler) and (q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26098, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.977 Aryloxyarene.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as aryloxyarene (PMN P-92-314) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(iii), and (g)(5). The label and MSDS as required by this paragraph shall also include the following statement: This substance may be toxic to sediment organisms.

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

## Environmental Protection Agency

## § 721.982

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3422, Jan. 22, 1998]

### § 721.980 Sodium salt of azo acid dye.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a sodium salt of azo acid dye (PMN P-95-633) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3422, Jan. 22, 1998]

### § 721.981 Substituted naphtholoazo-substituted naphthalenyl-substituted azonaphthol chromium complex.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted naphtholoazo-substituted naphthalenyl-substituted azonaphthol chromium complex (PMN P-93-1631) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(2), (w)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3422, Jan. 22, 1998]

### § 721.982 Calcium, bis(2,4-pentanedionato-O,O').

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance calcium, bis(2,4-pentanedionato-O,O') (PMN P-93-214, CAS no. 19372-44-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply if the substance is embedded or encapsulated in a plastic matrix.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set a 1.0 percent); and (c). As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(ix), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (d), (f) through (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27482, May 27, 1994]

**§ 721.983**

**40 CFR Ch. I (7–1–10 Edition)**

**§ 721.983 Sulfonyl azide intermediate (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as sulfonyl azide intermediate (PMN P-99-1202) is subject to reporting under this section for the significant new use described in paragraph (a)(1) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(1), (b)(1), and (c)(1).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f), (v)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70174, Dec. 17, 2003]

**§ 721.984 Amino-hydroxy sulfonaphthylazo-disubstituted phenyl azo benzene carboxylate salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as amino-hydroxy sulfonaphthylazo-disubstituted phenyl azo benzene carboxylate salt (PMN P-00-0351) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(2), (w)(2), (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15081, Mar. 28, 2003]

**§ 721.987 Dialkylaminophenyl imino pyrazole acid ester (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkylaminophenyl imino pyrazole acid ester (PMN P-98-45) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44575, Aug. 20, 1998]

**§ 721.988 Pyrazolone azomethine dye (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a pyrazolone azomethine dye (PMN P-98-91) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

## Environmental Protection Agency

## § 721.1025

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44575, Aug. 20, 1998]

### § 721.990 1,4-Benzenedicarboxylic acid, dimethyl ester, polymer with 1,4-butanediol, cyclized.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,4-benzenedicarboxylic acid, dimethyl ester, polymer with 1,4-butanediol, cyclized (PMN P-00-0789; CAS No. 263244-54-8) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15081, Mar. 28, 2003]

### § 721.1000 Benzenamine, 3-chloro-2,6-dinitro-N,N-dipropyl-4-(trifluoromethyl)-.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as benzenamine, 3-chloro-2,6-dinitro-N,N-dipropyl-4-(trifluoromethyl)- (P-86-83) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), and (g)(2)(v). The provision of § 721.72(d) requiring that employees be

provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information in an MSDS or label does not apply when an MSDS and label are not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 720.80(h).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(3), (b)(1), (b)(3), (c)(1), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (f), (i), and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 25989, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.1025 Benzenamine, 4-chloro-2-methyl-; benzenamine, 4-chloro-2-methyl-, hydrochloride; and benzenamine, 2-chloro-6-methyl-.

(a) *Chemical substances and significant new use subject to reporting.* (1) The chemical substances benzenamine, 4-chloro-2-methyl- (CAS Number 95-69-2); benzenamine, 4-chloro-2-methyl-, hydrochloride (CAS Number 3165-93-3); and benzenamine, 2-chloro-6-methyl- (CAS Number 87-63-8) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph:

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes a substance identified in paragraph (a)(1) of this section

## § 721.1050

and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[54 FR 12447, Mar. 27, 1989; 54 FR 17707, Apr. 25, 1989. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.1050 Benzenamine, 2,5-dibutoxy-4-(4-morpholinyl)-, sulfate.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as benzenamine, 2,5-dibutoxy-4-(4-morpholinyl), sulfate (PMN P-90-1809; CAS number 130169-66-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(i) and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iii) *Release to water.* Requirements as specified in § 721.90(a)(1), unless the substance is released to the Passaic Valley Sewerage Commission publicly-owned treatment works (NPDES Number NJ0021016) which discharges to the New York Bay.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), (f) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44061, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.1055 Benzenamine, 3,5-difluoro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenamine, 3,5-difluoro- (PMN P-97-648; CAS No. 372-39-4) is subject to re-

## 40 CFR Ch. I (7-1-10 Edition)

porting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), (a)(5)(i), (a)(6)(i), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the TSCA section 5(e) consent order for this substance. This NCEL is set at 0.4 mg/m<sup>3</sup>.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(iii), (g)(1)(iv), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i) and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 367, Jan. 5, 2000]

### § 721.1068 Benzenamine, 4-isocyanato-N,N-bis(4-isocyanatophenyl)-2,5-dimethoxy-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenamine, 4-isocyanato-N,N-bis(4-isocyanatophenyl)-2,5-dimethoxy- (PMN P-92-168) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

## Environmental Protection Agency

## § 721.1085

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(ii), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (22,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51682, Oct. 4, 1993]

### § 721.1070 Benzenamine, 4-methoxy-2-methyl-N-(3-methylphenyl).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as benzenamine, 4-methoxy-2-methyl-N-(3-methylphenyl) (PMN P-01-152; CAS No. 93072-06-1) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=5).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70174, Dec. 17, 2003]

### § 721.1075 Benzenamine, 4-(1-methylbutoxy)-, hydrochloride.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenamine, 4-(1-methylbutoxy)-, hydrochloride (PMN P-90-559) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Modifications or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44062, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.1085 Benzenamine,4,4'-methylenebis[N-ethyl-N-methyl-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a Benzenamine,4,4'-methylenebis[N-ethyl-N-methyl- (PMN P-99-0557; CAS No. 76176-94-8) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

§ 721.1105

40 CFR Ch. I (7–1–10 Edition)

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81399, Dec. 26, 2000]

§ 721.1105 **Benzenamine, 4,4'-methylenebis[2-methyl-6-(1-methylethyl)]-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenamine, 4,4'-methylenebis[2-methyl-6-(1-methylethyl)]- (PMN P-96-93; CAS No. 16298-38-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3422, Jan. 22, 1998]

§ 721.1120 **Benzenamine, 4,4'-[1,4-phenylenebis(1-methylethylidene)]bis[2,6-dimethyl-**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance benzenamine, 4,4'-[1,4-phenylenebis(1-methylethylidene)]bis- (CAS Registry Number 2716-10-1; PMN P-86-503) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iii) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), (c)(1), (a)(2), (b)(2), and (c)(2).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(2)(vi), (b)(2)(vi), and (c)(2)(vi).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), (j), and (k) are applicable to manufacturers, importers, and processors of these substances .

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 31330, July 15, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

§ 721.1150 **Substituted polyglycidyl benzenamine.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The following chemical substance, referred to by premanufacture notice number and its generic chemical name, is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section: Substituted polyglycidyl benzeneamine, P-83-394.

(2) The significant new uses are:

(i) Use in spray applications.

(ii) Manufacture or processing without establishing a program whereby:

(A) During all stages of manufacture and processing of the substance, and during response to emergencies and spills involving the substance, any person employed by or under the control of the manufacturer or processor who may potentially be dermally exposed to the substance wears:

## Environmental Protection Agency

## § 721.1155

(1) Gloves which cover the arm up to the elbow and which have been determined to be impervious to the substance under conditions of exposure (gloves may be determined to be impervious by standard testing methods or by reliance on the manufacturer's specifications for those gloves selected);

(2) A face shield of at least 8 inches in length; and

(3) Clothing which covers any other exposed areas of the arms, legs, and torso.

(B) All workers described in paragraph (a)(ii)(A) of this section are informed in writing, or by presenting the information as part of a training program in a safety meeting where attendance is recorded, of the following: To avoid all contact with this substance; that structurally similar chemicals have been found to cause cancer, reproductive effects, kidney and liver effects in laboratory animals, and allergic reactions in humans; that this substance is a severe skin and eye irritant; and that the use of impervious gloves, face shields and other clothing to cover exposed areas of the arms, the legs, and the torso is required.

(C) A label is affixed to each container of the substance or of a formulation containing the substance which (in a print size no smaller than ten point type) contains, at a minimum, the following information:

WARNING: CONTACT WITH SKIN AND EYES IS HARMFUL

—Severe skin and eye irritant.

—Similar chemicals cause cancer, reproductive effects, and kidney and liver changes in laboratory animals. They have also caused allergic reactions in humans.

—Prevent all contact with skin, eyes, and clothing.

—Wear impervious gloves, face shield, and protective clothing. Promptly remove and wash contaminated non-impervious clothing before re-use.

—Wash thoroughly after handling and before eating, drinking, or smoking.

STORAGE INSTRUCTIONS:

—Keep closure tight and upright to prevent leakage.

—Keep container closed during shipment and when not in use.

—In case of spillage absorb with sand or vermiculite and flush with plenty of water.

FIRST AID:

—In case of eye contact, immediately flush with plenty of water and get immediate medical attention.

—In case of skin contact, immediately wash with soap and water and get immediate medical attention.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* In addition to the requirements of § 721.17, manufacturers, importers, and processors of the chemical substance identified in paragraph (a)(1) of this section must maintain the following records for five years from their creation:

(i) The names of persons informed, the date they are informed, and the means by which they are informed in accordance with paragraph (a)(2)(ii)(B) of this section.

(ii) The names of any transferee and the dates of any transfers of containers which are labeled in accordance with paragraph (a)(2)(ii)(C) of this section.

(iii) The method used to determine that the protective gloves are impervious to the substance and date and the results of that determination.

(2) [Reserved]

[49 FR 43653, Oct. 31, 1984. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.1155 1,4-benzenediol, 2-(1,1,3,3-tetramethylbutyl)- and Bis(dimethylamino substituted)carbomonocycle.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 1,4-benzenediol, 2-(1,1,3,3-tetramethylbutyl)- and Bis(dimethylamino substituted)carbomonocycle (PMN P-96-92) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.



§721.1187

40 CFR Ch. I (7-1-10 Edition)

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 3422, Jan. 22, 1998]

§721.1187 **Bis(imidoethylene) benzene.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance bis(imidoethylene)benzene (PMN P-93-1447) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(f).

(ii) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in §721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[60 FR 11041, Mar. 1, 1995]

§721.1193 **Benzene, 2-bromo-1,4-dimethoxy-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzene, 2-bromo-1,4-dimethoxy- (PMN P-95-17, CAS No. 25245-34-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(g).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements specified in §721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[60 FR 45081, Aug. 30, 1995]

§721.1210 **Benzene, (2-chloroethoxy)-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzene, (2-chloroethoxy)- (PMN P-87-1471) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in §721.63 (a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3) (applies to gloves only), (a)(4), (a)(5)(iii), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in §721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(j).

(iv) *Disposal.* Requirements as specified in §721.85 (a)(1), (b)(1) and (c)(1). Disposal other than as described in the premanufacture notice referenced in paragraph (a)(1) of this section.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in §721.125 (a) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

## Environmental Protection Agency

## § 721.1230

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44062, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.1225 Benzene, 1,2-dimethyl-, polypropene derivatives, sulfonated, potassium salts.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as benzene, 1,2-dimethyl-, polypropene derivatives, sulfonated, potassium salts (PMN P-89-711) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent, and (f). The following environmental hazard statement shall appear on each label as specified in § 721.72(b) of this section and the MSDS as specified in § 721.72(c) of this section: EPA is requiring aquatic toxicity testing and fate testing for a substance in this product. These requirements are based on EPA's determination that the substance causes toxicity to fish and aquatic organisms based on data on the substance and similar sulfonate compounds. EPA has further determined that discharge of this substance may cause toxicity to fish and aquatic organisms at concentrations as low as 25 ppb. Water releases of the substance are subject to an EPA Significant New Use Rule (SNUR) under 40 CFR part 721 which requires that EPA be notified 90 days prior to use resulting in surface water concentrations in excess of this level.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 25 ppb). The requirement of 40 CFR 721.91(a)(4) that the amount of the substance estimated to be released to water is calculated before entering control technology is not retained. If the waste stream containing the substance will be treated using biological treatment (activated

sludge or equivalent) plus clarification, then the amount of substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 50 percent removal efficiency may be attributed to such treatment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 15789, Apr. 17, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.1230 Benzene, ethenyl-, ar-bromo derivatives.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzene, ethenyl-, ar-bromo derivatives (PMN P-84-660; CAS No. 125904-11-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this SNUR do not apply when the substance is present only in a mixture or in a polymer matrix, if the combined concentration of this substance and the substance identified in § 721.1240 as benzene, (2-bromoethyl)-, ar-bromo derivatives (PMN P-84-704; CAS No. 125904-10-1), present as residual monomers in the mixture or polymer matrix, does not exceed 0.5% by weight or volume. This exemption does not apply if there is reason to believe that during intended use, processing, or other handling, these substances combined may be re-concentrated above the 0.5% level in the mixture or polymer matrix.

## § 721.1240

## 40 CFR Ch. I (7-1-10 Edition)

(2) The significant new uses are: (i) *Protection in the workplace*. Requirements as specified in § 721.63 (a)(1) (including when the substance becomes airborne in any form), (a)(3), (a)(4) (when the substance becomes airborne in any form), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(5)(xv) and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions in the TSCA section 5(e) consent order for this substance.

(ii) *Hazard communication program*. Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80 (a), (b), (j) (flame retardant), and (l).

(iv) *Disposal*. It is a significant new use to dispose of the substance other than as follows:

(A) The following forms of the substance - the substance as a commercial chemical product or manufacturing chemical intermediate; the substance as an off-specification commercial chemical product or manufacturing chemical intermediate; the substance as a residue remaining in a container or in an inner liner removed from a container that has held the substance, unless the container is empty as defined in 40 CFR 261.7(b)(3); any residue or contaminated soil, water, or other debris resulting from the cleanup of a spill into or on any land or water of the substance as a commercial chemical product or manufacturing chemical intermediate; or any residue or contaminated soil, water, or other debris resulting from the cleanup of a spill into or on any land or water, of the substance as an off-specification commercial chemical product or manufacturing chemical intermediate; and any waste stream containing greater than 1.0% of this substance and the substance identified in § 721.1240 combined - shall be disposed of as follows: Requirements as specified in § 721.85 (a)(1), (b)(1), (c)(1), (a)(2), (b)(2), and (c)(2); the landfill shall be operated in accordance

with Subtitle C of the Resource Conservation and Recovery Act.

(B) Any forms of the substance other than those described in paragraph (a)(2)(iv)(A) of this section, including waste streams containing 1.0% or less of this substance and the substance identified in § 721.1240, shall be disposed of as follows: § 721.85 (a)(1), (b)(1), (c)(1), (a)(2), (b)(2), (c)(2), (a)(3), (b)(3), (c)(3), carbon adsorption followed by either physical destruction, or as specified in § 721.90; the landfill shall be operated in accordance with the Resource Conservation and Recovery Act.

(v) *Release to water*. Requirements as specified in § 721.90 (a)(2)(iv), (b)(2)(iv), (c)(2)(iv), (a)(2)(v), (b)(2)(v), (c)(2)(v), (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[67 FR 17647, Apr. 11, 2002]

### § 721.1240 Benzene, (2-bromoethyl)-, ar-bromo derivatives.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified as benzene, (2-bromoethyl)-, ar-bromo derivatives (PMN P-84-704; CAS No. 125904-10-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this SNUR do not apply when the substance is present only in a mixture or in a polymer matrix, if the combined concentration of this substance and the substance identified in § 721.1230 as benzene, ethenyl-, ar-bromo derivatives (PMN P-84-660; CAS No. 125904-11-2) present as residual monomers in the mixture or polymer matrix, does not exceed 0.5% by weight or volume. This exemption does not apply if there is reason to believe that during intended use, processing, or other handling,

## Environmental Protection Agency

## § 721.1300

these substances combined may be re-concentrated above the 0.5% level in the mixture or polymer matrix.

(2) The significant new uses are: (i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) (including when the substance becomes airborne in any form), (a)(3), (a)(4) (when the substance becomes airborne in any form), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(5)(xv), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions in the TSCA section 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (a), (b), (c), (h) (in the manufacture of the substance identified in § 721.1230), and (l).

(iv) *Disposal.* It is a significant new use to dispose of the substance other than as follows:

(A) The following forms of the substance - the substance as a commercial chemical product or manufacturing chemical intermediate; the substance as an off-specification commercial chemical product or manufacturing chemical intermediate; the substance as a residue remaining in a container or in an inner liner removed from a container that has held the substance, unless the container is empty as defined in 40 CFR 261.7(b)(3); any residue or contaminated soil, water, or other debris resulting from the cleanup of a spill into or on any land or water of the substance as a commercial chemical product or manufacturing chemical intermediate, or any residue or contaminated soil, water, or other debris resulting from the cleanup of a spill into or on any land or water, of the substance as an off-specification commercial chemical product or manufacturing chemical intermediate; and any waste stream containing greater than 1.0% of this substance and the substance identified in § 721.1230 combined - shall be disposed of as follows: Re-

quirements as specified in § 721.85 (a)(1), (b)(1), (c)(1), (a)(2), (b)(2), and (c)(2); the landfill shall be operated in accordance with Subtitle C of the Resource Conservation and Recovery Act.

(B) Any forms of the substance other than those described in paragraph (a)(2)(iv)(A) of this section, including waste streams containing 1.0% or less of this substance and the substance identified in § 721.1240, shall be disposed of as follows: § 721.85 (a)(1), (b)(1), (c)(1), (a)(2), (b)(2), (c)(2), (a)(3), (b)(3), (c)(3), carbon adsorption followed by either physical destruction, or as specified in § 721.90; the landfill shall be operated in accordance with the Resource Conservation and Recovery Act.

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(iv), (b)(2)(iv), (c)(2)(iv), (a)(2)(v), (b)(2)(v), (c)(2)(v), (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[67 FR 17648, Apr. 11, 2002]

### § 721.1300 [(Dinitrophenyl)azo]-[2,4-diamino-5-methoxybenzene] derivatives.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as [(dinitrophenyl)azo]-[2,4-diamino-5-methoxybenzene] derivatives (P-83-817 and P-83-818) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

§ 721.1325

40 CFR Ch. I (7-1-10 Edition)

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25990, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

§ 721.1325 Benzene, 1-(1-methylbutoxy)-4-nitro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzene, 1-(1-methylbutoxy)-4-nitro- (PMN P-90-560) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(ix), (g)(2)(i), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (p) (production limit set at 43,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Modifications or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44062, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

§ 721.1350 Benzene, (1-methylethyl)(2-phenylethyl)-

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as benzene, (1-methylethyl)(2-phenylethyl)-, (PMN P-88-894) is subject to reporting under this section for the significant

new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3), (b) (concentration set at 1.0 percent), and (c). However, the personal protective clothing required in paragraph (a)(2)(iv) must be tested or evaluated under the requirements of paragraph (a)(3). Furthermore, the imperviousness of gloves required under paragraph (a)(2)(i) may not be demonstrated according to paragraph (a)(3)(ii), but rather must be tested according to paragraph (a)(3)(i) with the following additional requirements: There must be no permeation of the PMN substance greater than 16 ppb after 8 hours of testing in accordance with the American Society for Testing and Materials (ASTM) F739-85 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases." Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iv), (g)(2)(i), (g)(2)(iii), (g)(2)(v), (g)(3)(ii), (g)(4)(i) and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q). In addition, a significant use of the substance is any manner or method of manufacturing, processing, or use other than as an insulating oil for capacitors or transformers.

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), (c)(1), (a)(2), (b)(2), (c)(2), (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

## Environmental Protection Agency

## § 721.1425

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 40210, Aug. 13, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.1372 Substituted nitrobenzene.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a substituted nitrobenzene (PMN P-92-1125) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 50 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51682, Oct. 4, 1993]

### § 721.1375 Disubstituted nitrobenzene (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance disubstituted nitrobenzene (PMN P-84-860) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) (concentration set at 0.1 percent), (f) and (g)(1)(vii), (g)(2)(i), (g)(2)(v). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS

are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when a MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (e), (f) and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 32416, Aug. 9, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.1425 Pentabromoethylbenzene.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance pentabromoethylbenzene (CAS Number 85-22-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph:

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[54 FR 18286, Apr. 28, 1989. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.1430

## 40 CFR Ch. I (7-1-10 Edition)

### § 721.1430 Pentachlorobenzene.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance pentachlorobenzene (CAS No. 608-93-5) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63516, Dec. 1, 1993]

### § 721.1435 1,2,4,5-Tetrachlorobenzene.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance 1,2,4,5-tetrachlorobenzene (CAS No. 95-94-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63516, Dec. 1, 1993]

### § 721.1440 1,3,5-Trinitrobenzene.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance 1,3,5-trinitrobenzene (CAS No. 95-35-4) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63516, Dec. 1, 1993]

### § 721.1450 1,3-Benzenediamine, 4-(1,1-dimethylethyl)-ar-methyl.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The following chemical substance, referred to by its PMN number and chemical name, is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section: P-85-929; 1,3-Benzenediamine, 4-(1,1-dimethylethyl)-ar-methyl.

(2) The significant new uses are:

(i) Use other than for applications where the substance will be completely reacted (cured or used as a chemical intermediate).

(ii) Any method of disposal other than by landfill, incineration, or for wastewater from vent scrubbers, steam vacuum ejectors, pad washings, equipment washouts, and stormwater run-offs, wastewater treatment in permitted industrial wastewater treatment facilities. Each method of disposal must meet all applicable local, State, and Federal laws and regulations.

(iii) Any manner or method of manufacturing, importing, or processing without establishing a program whereby:

(A) Any person who may be exposed dermally to the substance wears:

(1) Gloves which have been determined to be impervious to the substance under the conditions of exposure, including the duration of exposure. This determination is made either by testing the gloves under the conditions of exposure or by evaluating the specifications provided by the manufacturer of the gloves. Testing or

evaluation of specifications includes consideration of permeability, penetration, and potential chemical and mechanical degradation by the substance and associated chemical substances.

(2) Clothing which covers any other exposed areas of the arms, legs, and torso.

(3) Chemical safety goggles or equivalent eye protection.

(B) Any person who may be exposed to the substance through inhalation during manufacture, in addition to the dermal protective equipment described in paragraph (a)(2)(iii)(A) of this section, wears at a minimum, a National Institute for Occupational Safety and Health approved, category 23C respirator, organic vapor type. Use of the respirator must be according to 29 CFR 1910.134 and 30 CFR part 11. If a full-face type respirator is selected and worn, the chemical safety goggles requirement in paragraph (a)(2)(iii)(A)(3) of this section is waived.

(C)(I) All persons who may be exposed to the substance are informed, in writing, and by presenting the information as part of a training program in safety meetings at which attendance is recorded, by means of the following statement:

WARNING: Avoid all contact. Chemicals similar in structure to [insert appropriate name] have been found to cause chronic organ and systemic effects and cancer in laboratory animals. To protect yourself, you must wear chemical safety goggles or equivalent eye protection, impervious gloves, and protective clothing while handling this material.

(2) During manufacture, the warning statement in paragraph (a)(2)(iii)(C)(I) of this section shall include the additional following statement:

Respirators are required during clean-up or loading of bulk material.

(D) All persons that receive the PMN substance are notified by means of a Material Safety Data Sheet ("MSDS") which includes, at a minimum, the language specified in paragraph (a)(2)(iii)(C)(I) of this section, and specifies the requirements for protective equipment in paragraph (a)(2)(iii)(A) and (a)(2)(iii)(B) of this section.

(E) Each container of the substance distributed in commerce has affixed to it a label which includes a Warning Statement which consists, at a minimum, of the language specified in paragraph (a)(2)(iii)(C)(I) of this section. The first word of the Warning Statement is capitalized, and the type size of the first word is no smaller than 6-point type for a label 5 square inches or less in area, 10-point type for a label above 5 but no greater than 10 square inches in area, 12-point type for a label above 10 but no greater than 15 square inches in area, 14-point type for a label above 15 but no greater than 30 square inches in area, or 18-point type for a label over 30 square inches in area. The type size of the remainder of the Warning Statement is no smaller than 6-point type. All required label text is of sufficient prominence, and is placed with such conspicuousness relative to other label text and graphic material, to ensure that the Warning Statement is read and understood by the ordinary individual under customary conditions of purchase and use.

(iv) Manufacturing and importing the substance for any use at greater than the aggregate volumes allowed under the consent order issued for Premanufacture Notice P-85-929, without submitting to EPA the corresponding scientifically valid toxicity test data required under that order, developed according to EPA's Good Laboratory Practice standards at 40 CFR part 792 and EPA's testing guidelines at 40 CFR 798.2650 and 798.3300.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Determining whether a use is a significant new use.* (i) Any person who intends to manufacture or import the substance identified in paragraph (a)(1) of this section shall, before commencing any manufacture or import, submit to EPA the information required under § 721.11(b).

(ii) EPA will review this information to determine whether the person has a *bona fide* intent to manufacture or import the substance. If EPA determines that the person has a *bona fide* intent to manufacture or import the substance, EPA will tell the person the



**§ 721.1500**

**40 CFR Ch. I (7-1-10 Edition)**

specific production volumes which would constitute a significant new use under paragraph (a)(2)(iv) of this section.

(iii) A disclosure to a person with a *bona fide* intent to manufacture or import the substance of the specific production volumes which would constitute a significant new use under paragraph (a)(2)(iv) of this section will not be considered public disclosure of confidential business information under section 14 of the Act.

(2) *Recordkeeping.* In addition to the requirements of § 721.40, manufacturers, importers, and processors must maintain the following records for 5 years after the date they are created:

(i) Any determination that gloves are impervious to the substance.

(ii) Names of persons who have attended safety meetings in accordance with paragraph (a)(2)(iii)(C) of this section, the dates of such meetings, and copies of any written information provided in accordance with paragraph (a)(2)(iii)(C) of this section.

(iii) Copies of any MSDSs used.

(iv) Names and addresses of all persons to whom the substance is sold or transferred including shipment destination address if different, the date of each transfer, and the quantity of substance sold or transferred on such date.

(v) Copies of any labels used.

(vi) Any names used for the substance and the corresponding dates of use.

(vii) Quantities of the substance manufactured or imported, with the corresponding dates of manufacture or import.

(viii) Quantities of the substance purchased in the United States by processors of the substance, names and addresses of suppliers, and corresponding dates of purchase.

(ix) Information on disposal of the substance, including dates waste material is disposed of, location of disposal sites, volume of disposed solid material, estimated volume of any disposed liquid wastes containing the substance, and method of disposal.

[55 FR 20795, May 21, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.1500 1,2-Benzenediamine, 4-ethoxy, sulfate.**

(a) *Chemical substance and significant new use subject to reporting.* (1) The following chemical substance referred to by its chemical name is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section: 1,2-benzenediamine, 4-ethoxy, sulfate, PMN P-83-105.

(2) The significant new use is: Manufacture, import, or processing in powder or dry solid form.

(b) [Reserved]

(Sec. 5, Pub. L. 94-469, 90 Stat. 2012 (15 U.S.C. 2604))

[49 FR 43061, Oct. 26, 1984. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.1550 Benzenediazonium, 4-(dimethylamino)-, salt with 2-hydroxy-5-sulfobenzoic acid (1:1).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenediazonium, 4-(dimethylamino)-, salt with 2-hydroxy-5-sulfobenzoic acid (1:1) (CAS No. 124737-31-1) (P-90-1366) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (a)(6)(ii), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), and (g)(5). In addition, the following human health hazard statement shall appear on each label as specified at § 721.72(b) and the MSDS as specified at § 721.72(c). Additional statements may be included as long as they are true and do not alter the meaning of the required statement. Human health hazard statements: This substance may cause severe acute toxicity and death or serious neurotoxic effects.

## Environmental Protection Agency

§ 721.1576

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (volume set at 31,000 kg).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 80 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a) through (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 40211, Aug. 13, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.1555 Substituted phenyl azo substituted benzenediazonium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted phenyl azo substituted benzenediazonium salt (PMN P-92-652) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51682, Oct. 4, 1993]

### § 721.1568 Substituted benzenediazonium.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted benzenediazonium (PMN P-93-533) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51682, Oct. 4, 1993]

### § 721.1576 1,3-Benzenedicarboxylic acid, bis[[4-[(ethenyloxy)methyl]cyclohexyl]methyl] ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,3-benzenedicarboxylic acid, bis[[4-[(ethenyloxy)methyl]cyclohexyl]methyl] ester (PMN P-98-1162; CAS No. 119581-93-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

**§ 721.1577**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 367, Jan. 5, 2000]

**§ 721.1577 1,4-Benzenedicarboxylic acid, bis [4-(ethenyloxy) butyl] ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,4-benzenedicarboxylic acid, bis[4-(ethenyloxy) butyl] ester (PMN P-98-1163; CAS No. 117397-31-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 367, Jan. 5, 2000]

**§ 721.1578 1,4-Benzenedicarboxylic acid, bis[[4-(ethenyloxy)methyl] cyclohexyl] methyl] ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,4-benzenedicarboxylic acid, bis[[4-(ethenyloxy)methyl] cyclohexyl] methyl] ester (PMN P-98-1164; CAS No. 209072-72-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

**40 CFR Ch. I (7-1-10 Edition)**

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 367, Jan. 5, 2000]

**§ 721.1579 1,2,4-Benzenetricarboxylic acid, tris [4-(ethenyloxy) butyl] ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,2,4-benzenetricarboxylic acid, tris [4-(ethenyloxy) butyl] ester (PMN P-98-1165; CAS No. 196109-17-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 367, Jan. 5, 2000]

**§ 721.1580 Disubstituted benzene ether, polymer with substituted phenol (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as disubstituted benzene ether, polymer with substituted phenol (PMN P-98-155) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

## Environmental Protection Agency

## § 721.1620

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44575, Aug. 20, 1998]

### § 721.1612 Substituted 2-nitro- and 2-aminobenzenesulfonamide.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as substituted 2-nitro- and 2-aminobenzenesulfonamide (PMNs P-88-1937 and P-88-1938) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a) through (d), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5). The following additional statements shall appear on each label and MSDS required by this paragraph: This substance may be toxic to terrestrial organisms and plants. Notice to user: Release to water restrictions apply.

(ii) *Disposal.* Requirements as specified in § 721.85. A significant new use of these substances is any release of the substances to land.

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 100 ppb for P-88-1937 and N = 10 ppb for P-88-1938). When calculating the surface water concentrations according to the instructions in § 721.91(a)(4), the statement that the amount of the substances that will be released will be calculated before the substances enter control technology does not apply. Instead, if the waste stream containing the PMN substances will be treated before release, the amount of the PMN substances reasonably likely to be removed from the waste stream by treatment may be subtracted in calculating the number of kilograms released. No more than 50

percent removal efficiency may be attributed to such treatment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (j), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27482, May 27, 1994]

### § 721.1620 Benzenesulfonamide, alkylphenyl substituted phenyl substituted carbonyl- (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as benzenesulfonamide alkylphenyl substituted phenyl substituted carbonyl- (PMN P-00-368) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63(a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1.0%), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the TSCA section 5(e) consent order for this chemical substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72(a), (b), (c), (d), (e) (concentration set at 1.0%), (f), (g)(1)(iv), (g)(2)(ii), (g)(2)(iv), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=30).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (d), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

§ 721.1625

40 CFR Ch. I (7-1-10 Edition)

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70174, Dec. 17, 2003]

§ 721.1625 Alkylbenzene sulfonate, amine salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylbenzene sulfonate, amine salt (PMN P-90-456) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 19242, Apr. 25, 1991; 56 FR 29903, July 1, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

§ 721.1630 1,2-Ethanediol bis(4-methylbenzenesulfonate); 2,2-oxybis-ethane bis(4-methylbenzenesulfonate); ethanol, 2,2'-[oxybis(2,1-ethanediyl oxy)]bis-, bis(4-methylbenzenesulfonate); ethanol, 2,2'-[oxybis (2,1-ethane diyloxy)] bis-, bis(4-methylbenzenesulfonate); ethanol, 2,2'-[[1-(2-propenyloxy methyl)-1,2-ethanediyl] bis(oxy)]bis-, bis(4-methylbenzene sulfonate); and ethanol, 2-[1-[[2-[2-[[4-methylphenyl)sulfonyl] oxy]ethoxy] ethoxy]methyl]-2-(2-propenyloxy)ethoxy]-, 4-methylbenzenesulfonate.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances 1,2-ethanediol bis(4-methylbenzenesulfonate) (PMN P-93-1193, CAS no. 6315-52-2), 2,2-oxybis-ethane bis(4-methylbenzenesulfonate) (PMN P-93-1194, CAS no. 7460-82-4), ethanol, 2,2'-[oxybis(2,1-

ethanediyl)bis-, bis(4-methylbenzene-sulfonate) (PMN P-93-1195, CAS no. 19249-03-7), ethanol, 2,2'-[oxybis(2,1-ethanediyl)oxy] bis-, bis(4-methylbenzene sulfonate) (PMN P-93-1196, CAS no. 37860-51-8), ethanol, 2,2'-[[1-(2-propenyloxy) methyl]-1,2-ethanediyl]bis(oxy)]bis-, bis(4-methylbenzene sulfonate) (PMN P-93-1203, CAS no. 114719-15-2), and ethanol, 2-[1-[[2-[2- [[(4-methylphenyl) sulfonyl] oxy]ethoxy] ethoxy]methyl]-2-(2-propenyloxy)ethoxy]-, 4-methylbenzenesulfonate (PMN P-93-1204, CAS no. 124029-00-1) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27482, May 27, 1994]

§ 721.1637 1,2-Propanediol, 3-(2-propenyloxy)-, bis(4-methylbenzene sulfonate); 2-propanol, 1-[2-[[4-methylphenyl)sulfonyl] oxy]ethoxy]-3-(2-propenyloxy)-4-methylbenzenesulfonate; and 2-propanol, 1-[2-[[4-methylphenyl)sulfonyl]oxy] ethoxy]ethoxy]-3-(2-propenyloxy)-, 4-methylbenzenesulfonate.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances 1,2-propanediol, 3-(2-propenyloxy)-, bis(4-methylbenzenesulfonate) (PMN P-93-1198, CAS no. 114719-19-6), 2-propanol, 1-[2-[[4-methylphenyl)sulfonyl]oxy]ethoxy]-3-(2-propenyloxy)-4-methylbenzenesulfonate (PMN P-93-1199, CAS no. 124213-39-4), and 2-propanol, 1-[2-[[4-methylphenyl)sulfonyl]oxy]

## Environmental Protection Agency

## § 721.1645

ethoxy]ethoxy]-3-(2-propenyloxy)-, 4-methylbenzenesulfonate (PMN P-93-1200, CAS no. 124028-99-5) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27482, May 27, 1994]

### § 721.1640 3,6,9,12,-

**Tetraoxatetradecane-1,14-diol, bis(4-methylbenzenesulfonate); 3,6,9,13-tetraoxahexadec-15-ene-1,11-diol, bis(4-methylbenzenesulfonate); 3,6,9,12,16-pentaoxonadec-18-ene-1,14-diol, bis(4-methylbenzenesulfonate); and 3,6,9,12-tetraoxatetradecane-1,14-diol, 7-[(2-propenyloxy)methyl]-, bis(4-methylbenzenesulfonate).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances 3,6,9,12-tetraoxatetradecane-1,14-diol, bis(4-methylbenzenesulfonate) (PMN P-93-1197, CAS no. 41024-91-3), 3,6,9,13-tetraoxahexadec-15-ene-1,11-diol, bis(4-methylbenzenesulfonate) (PMN P-93-1201), 3,6,9,12,16-pentaoxonadec-18-ene-1,14-diol, bis(4-methylbenzenesulfonate) (PMN P-93-1202), and 3,6,9,12-tetraoxatetradecane-1,14-diol, 7-[(2-propenyloxy)methyl]-, bis(4-methylbenzenesulfonate) (PMN P-93-1205) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27483, May 27, 1994]

### § 721.1643 Benzenesulfonic acid, amino substituted phenylazo-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a benzenesulfonic acid, amino substituted phenylazo- (PMN P-95-86) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(w)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45081, Aug. 30, 1995]

### § 721.1645 Benzenesulfonic acid, 4-methyl-, reaction products with oxirane mono[(C<sub>10-16</sub>-alkyloxy)methyl] derivatives and 2,2,4(or 2,4,4)-trimethyl-1,6-hexanediamine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance benzenesulfonic acid, 4-methyl-, reaction products with oxirane mono[(C<sub>10-16</sub>-alkyloxy)methyl] derivatives and 2,2,4(or 2,4,4)-trimethyl-1,6-hexanediamine (PMN P-93-1047,

**§ 721.1648**

CAS no. 147170-38-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27483, May 27, 1994]

**§ 721.1648 Substituted benzenesulfonic acid salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted benzenesulfonic acid (PMN P-99-1304) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 70175, Dec. 17, 2003]

**40 CFR Ch. I (7-1-10 Edition)**

**§ 721.1650 Alkylbenzenesulfonic acid and sodium salts.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkyl benzenesulfonic acid and sodium salts (PMNs P-88-1783, P-88-2231, P-88-2237, and P-88-2530) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

**Environmental Protection Agency**

**§ 721.1660**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44062, Sept. 23, 1993, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.1655 Alkylbenzenesulfonic acid (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylbenzenesulfonic acid (PMN P-98-679) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 367, Jan. 5, 2000]

**§ 721.1660 Benzidine-based chemical substances.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The benzidine-based chemical substances listed in table 1 of this section are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are any use other than as a reagent to test for hydrogen peroxide in milk; a reagent to test for hydrogen sulfate, hydrogen cyanide, and nicotine; a stain in microscopy; a reagent for detecting blood; an analytical standard; and also for Colour Index (C.I.) Direct Red 28 (Congo Red, CAS No. 573-58-0) as an indicator dye.

(b) *List of substances.* The following table 1 lists the benzidine-based chemical substances covered by this section.

TABLE 1—BENZIDINE-BASED CHEMICAL SUBSTANCES

| CAS number | C.I. name             | C.I. number | Chemical Name  |
|------------|-----------------------|-------------|--|
| 92-87-5    | Benzidine             | 0N/A        | [1,1'-Biphenyl]-4,4'-diamine   |
| 531-85-1   | Benzidine · 2HCL      | N/A         | [1,1'-Biphenyl]-4,4'-diamine, dihydrochloride  |
| 573-58-0   | C.I. Direct Red 28    | 22120       | 1-Naphthalenesulfonic acid, 3,3'-[[1,1'-biphenyl]-4,4'-diylbis(azo)]bis[4-amino-, disodium salt  |
| 1937-37-7  | C.I. Direct Black 38  | 30235       | 2,7-Naphthalenedisulfonic acid, 4-amino-3-[[4'-[(2,4-diaminophenyl)azo][1,1'-biphenyl]-4-yl]azo]-5-hydroxy-6-(phenylazo)-, disodium salt   |
| 2302-97-8  | C.I. Direct Red 44    | 22500       | 1-Naphthalenesulfonic acid, 8,8'-[[1,1'-biphenyl]-4,4'-diylbis(azo)]bis[7-hydroxy-, disodium salt  |
| 2429-73-4  | C.I. Direct Blue 2    | 22590       | 2,7-Naphthalenedisulfonic acid, 5-amino-3-[[4'-[(7-amino-1-hydroxy-3-sulfo-2-naphthalenyl)azo][1,1'-biphenyl]-4-yl]azo]-4-hydroxy-, trisodium salt   |
| 2429-79-0  | C.I. Direct Orange 8  | 22130       | Benzoic acid, 5-[[4'-[(1-amino-4-sulfo-2-naphthalenyl)azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-, disodium salt  |
| 2429-81-4  | C.I. Direct Brown 31  | 35660       | Benzoic acid, 5-[[4'-[[2,6-diamino-3-[[8-hydroxy-3,6-disulfo-7-[(4-sulfo-1-naphthalenyl)azo]-2-naphthalenyl]azo]-5-methylphenyl]azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-, tetrasodium salt |
| 2429-82-5  | C.I. Direct Brown 2   | 22311       | Benzoic acid, 5-[[4'-[(7-amino-1-hydroxy-3-sulfo-2-naphthalenyl)azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-, disodium salt  |
| 2429-83-6  | C.I. Direct Black 4   | 30245       | 2,7-Naphthalenedisulfonic acid, 4-amino-3-[[4'-[(2,4-diamino-5-methylphenyl)azo][1,1'-biphenyl]-4-yl]azo]-5-hydroxy-6-(phenylazo)-, disodium salt  |
| 2429-84-7  | C.I. Direct Red 1     | 22310       | Benzoic acid, 5-[[4'-[(2-amino-8-hydroxy-6-sulfo-1-naphthalenyl)azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-, disodium salt  |
| 2586-58-5  | C.I. Direct Brown 1:2 | 30110       | Benzoic acid, 5-[[4'-[[2,6-diamino-3-methyl-5-[(4-sulfo-1-naphthalenyl)azo]phenyl]azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-, disodium salt  |
| 2602-46-2  | C.I. Direct Blue 6    | 22610       | 2,7-Naphthalenedisulfonic acid, 3,3'-[[1,1'-biphenyl]-4,4'-diylbis(azo)]bis[5-amino-4-hydroxy-, tetrasodium salt   |
| 2893-80-3  | C.I. Direct Brown 6   | 30140       | Benzoic acid, 5-[[4'-[[2,4-dihydroxy-3-[(4-sulfo-1-naphthalenyl)azo]phenyl]azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-, disodium salt   |



TABLE 1—BENZIDINE-BASED CHEMICAL SUBSTANCES—Continued

| CAS number | C.I. name             | C.I. number | Chemical Name  |
|------------|-----------------------|-------------|--|
| 3530–19–6  | C.I. Direct Red 37    | 22240       | 1,3-Naphthalenedisulfonic acid, 8-[[4'-[(4-ethoxyphenyl)azo][1,1'-biphenyl]-4-yl]azo]-7-hydroxy-, disodium salt  |
| 3567–65–5  | C.I. Acid Red 85      | 22245       | 1,3-Naphthalenedisulfonic acid, 7-hydroxy-8-[[4'-[[4-[(4-methylphenyl)sulfonyl]oxy]phenyl]azo][1,1'-biphenyl]-4-yl]azo]-, disodium salt  |
| 3626–28–6  | C.I. Direct Green 1   | 30280       | 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-3-[[4'-[(4-hydroxyphenyl)azo][1,1'-biphenyl]-4-yl]azo]-6-(phenylazo)-, disodium salt   |
| 3811–71–0  | C.I. Direct Brown 1   | 30045       | Benzoic acid, 5-[[4'-[[2,4-diamino-5-[(4-sulfophenyl)azo]phenyl]azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-, disodium salt  |
| 4335–09–5  | C.I. Direct Green 6   | 30295       | 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-6-[[4'-[(4-hydroxyphenyl)azo][1,1'-biphenyl]-4-yl]azo]-3-[(4-nitrophenyl)azo]-, disodium salt  |
| 6358–80–1  | C.I. Acid Black 94    | 30336       | 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-3-[[4'-[[4-hydroxy-2-[(2-methylphenyl)amino]phenyl]azo][1,1'-biphenyl]-4-yl]azo]-6-[(4-sulfophenyl)azo]-, trisodium salt                 |
| 6360–29–8  | C.I. Direct Brown 27  | 31725       | Benzoic acid, 5-[[4'-[[4-(4-amino-7-sulfo-1-naphthalenyl)azo]-6-sulfo-1-naphthalenyl]azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-, trisodium salt  |
| 6360–54–9  | C.I. Direct Brown 154 | 30120       | Benzoic acid, 5-[[4'-[[2,6-diamino-3-methyl-5-[(4-sulfophenyl)azo]phenyl]azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxy-3-methyl-, disodium salt  |
| 8014–91–3  | C.I. Direct Brown 74  | 36300       | Benzoic acid, 3,3'-[(3,7-disulfo-1,5-naphthalenediyl)bis[azo(6-hydroxy-3,1-phenylene)azo(6(or7)-sulfo-4,1-naphthalenediyl)azo[1,1'-biphenyl]-4,4'-diylazo)]bis[6-hydroxy-, hexasodium salt |
| 16071–86–6 | C.I. Direct Brown 95  | 30145       | Cuprate(2-), [5-[[4'-[[2,6-dihydroxy-3-[(2-hydroxy-5-sulfophenyl)azo]phenyl]azo][1,1'-biphenyl]-4-yl]azo]-2-hydroxybenzoato(4-)-, disodium   |

[61 FR 52295, Oct. 7, 1996]

**§ 721.1675 Disulfonic acid rosin amine salt of a benzidine derivative (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as disulfonic acid rosin amine salt of a benzidine derivative (PMN P-87-1337) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions

of § 721.185 apply to this significant new use rule.

[55 FR 33304, Aug. 15, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.1680 Substituted benzoic acid (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted benzoic acid (PMN P-01-423) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

## Environmental Protection Agency

§ 721.1725

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70175, Dec. 17, 2003]

### § 721.1700 Halonitrobenzoic acid, substituted (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance halonitrobenzoic acid, substituted (PMN P-86-1098) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv) through (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b), (c), (d), (e) (concentration set at 1.0 percent), (f) and (g)(1)(vi), (g)(2)(i) through (g)(2)(v), and (g)(5). The provision of § 721.72(d) requiring that employees to be provided with information on the location and availability of a written hazard communication program does not apply when the written program is not required under § 721.72(a).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (e) through (g) and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32416, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.1705 Benzoic acid, 3-amino-, diazotized, coupled with 6-amino-4-hydroxy-2-naphthalenesulfonic acid, diazotized, (3-aminophenyl)phosphonic acid and diazotized 2,5-diethoxybenzenamine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as benzoic acid, 3-amino-, diazotized, coupled with 6-amino-4-hydroxy-2-naphthalenesulfonic acid, diazotized, (3-amino-phenyl)phosphonic acid and diazotized 2,5-diethoxybenzenamine (PMN P-96-1216; CAS No. 163879-69-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3423, Jan. 22, 1998]

### § 721.1725 Benzoic acid, 3,3'-methylenebis [6 amino-, di-2-propenyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The following chemical substance, referred to by its CAS Number and chemical name, is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section: 61386-02-5, Benzoic acid, 3,3'-methylenebis [6 amino-, di-2-propenyl ester.

(2) The significant new uses are: (i) Any use other than the use described in Premanufacture Notice P-82-438.

(ii) Any manner or method of manufacturing or processing the substance for the use described in Premanufacture Notice P-82-438 different than the

§721.1728

40 CFR Ch. I (7-1-10 Edition)

manner or method described in Premanufacture Notice P-82-438.

(b) *Special provisions.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Determining whether a specific use is subject to this rule.* (i) A person who intends to manufacture, import, or process the chemical substance identified in paragraph (a)(1) of this section may ask EPA whether the use for which the person intends to manufacture, import, or process the substance is a significant new use under paragraph (a)(2)(i) of this section. EPA will answer such an inquiry only if EPA determines that the person has a *bona fide* intent to manufacture, import, or process the chemical substance.

(ii) To establish a *bona fide* intent to manufacture, import, or process the chemical substance, the person must submit to EPA:

(A) All materials and statements required under §721.6.

(B) The specific use for which the person intends to manufacture, import, or process the chemical substance.

(iii) EPA will review the information submitted by the person under this paragraph to determine whether the person has a *bona fide* intent to manufacture, import, or process the chemical substance.

(iv) If EPA determines that the person has a *bona fide* intent to manufacture, import, or process the chemical substance, EPA will tell the person whether the use for which the person intends to manufacture, import, or process the substance is a significant new use under paragraph (a)(2)(i) of this section. If EPA tells the person that the intended use is not a significant new use under paragraph (a)(2)(i) of this section, EPA will tell the person what activities would constitute a significant new use under paragraph (a)(2)(ii) of this section.

(v) A disclosure to a person with a *bona fide* intent to manufacture, import, or process the chemical substance of the significant new uses subject to this section will not be considered public disclosure of confidential business information under section 14 of the Act.

(vi) EPA will answer an inquiry on whether a particular use is subject to this section within 30 days after receipt of a complete submission under paragraph (b)(1) of this section.

(2) [Reserved]

[51 FR 16687, May 6, 1986. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

§ 721.1728 Benzoic acid, 2-(3-phenylbutylidene)amino-, methyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzoic acid, 2-(3-phenylbutylidene)amino-, methyl ester (PMN P-85-1211) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(p) (10,600 kg).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[58 FR 51682, Oct. 4, 1993]

§ 721.1729 Boric acid (H<sub>3</sub>BO<sub>3</sub>), mixed esters with polyethylene glycol mono-Bu ether and polyethylene glycol mono Me ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as boric acid (H<sub>3</sub>BO<sub>3</sub>), mixed esters with polyethylene glycol mono-Bu ether and polyethylene glycol mono Me ether (PMN P-97-635; CAS No. 183290-62-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in §721.63 (a)(2)(i) and (a)(3).

## Environmental Protection Agency

## § 721.1734

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=300).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 368, Jan. 5, 2000]

### § 721.1730 Poly(oxy-1,2-ethanediyl), $\alpha$ -butyl- $\omega$ -hydroxy, ester with boric acid ( $H_3BO_3$ ).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as poly(oxy-1,2-ethanediyl),  $\alpha$ -butyl- $\omega$ -hydroxy, ester with boric acid ( $H_3BO_3$ ) (PMN P-97-636; CAS No. 106008-93-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i) and (a)(3).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=300).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 368, Jan. 5, 2000]

### § 721.1731 Poly(oxy-1,2-ethanediyl), $\alpha$ -methyl- $\omega$ -hydroxy, ester with boric acid ( $H_3BO_3$ ).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as poly(oxy-1,2-ethanediyl),  $\alpha$ -methyl- $\omega$ -hydroxy, ester with boric acid ( $H_3BO_3$ ) (PMN P-97-637; CAS No. 106008-94-0) is

subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i) and (a)(3).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=300).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 368, Jan. 5, 2000]

### § 721.1732 Nitrobenzoic acid octyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as nitrobenzoic acid octyl ester (PMN P-93-343) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 1 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51682, Oct. 4, 1993]

### § 721.1734 Substituted benzonitrile (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## § 721.1735

## 40 CFR Ch. I (7–1–10 Edition)

chemical substance identified generically as a substituted benzonitrile (PMN P-97-1029) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), and (a)(6)(v).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), (e), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44576, Aug. 20, 1998]

## § 721.1735 Alkylbisoxoalkyl (substituted-1,1-dimethylethylphenyl) benzotriazole (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance alkylbisoxoalkyl (substituted-1,1-dimethylethylphenyl) benzotriazole (PMN P-86-1771) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv) through (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (d), (e) (concentration set at 1.0 percent), (f) and (g)(1)(iv), (g)(2)(i) through (g)(2)(v), and (g)(5). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of a written hazard communication program does not apply when the written

program is not required under § 721.72(a).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) (light stabilizer for polymers) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (e) through (g), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 21413, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.1738 Substituted benzotriazole (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted benzotriazole (PMN P-94-1744) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(6)(i), (b) (concentration set at 1.0%), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0%), (f), (g)(1)(iv), (g)(1)(vi), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements specified in § 721.125(a)

## Environmental Protection Agency

## § 721.1750

through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[61 FR 63736, Dec. 2, 1996]

### § 721.1745 Ethoxybenzothiazole disulfide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as ethoxybenzothiazole disulfide (PMN P-90-1384) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i) through (vii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (d) and (f) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44063, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.1747 Substituted benzophenone (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted benzophenone (PMN P-02-262) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirement as specified § 721.90(b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70175, Dec. 17, 2003]

### § 721.1750 1H-Benzotriazole, 5-(pentyloxy)- and 1H-benzotriazole, 5-(pentyloxy)-, sodium and potassium salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances 1H-benzotriazole, 5-(pentyloxy)- (PMN P-92-34, CAS no. 133145-29-6), 1H-benzotriazole, 5-(pentyloxy)-, sodium salt (PMN P-92-35), and 1H-benzotriazole, 5-(pentyloxy)-, potassium salt (PMN P-92-36) are subject to reporting for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of these substances is any manner or method of manufacture, import, or processing associated with any use of these substances without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for these substances, the employer becomes aware that these substances may present a risk of injury to the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If these substances are not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information

## § 721.1755

## 40 CFR Ch. I (7–1–10 Edition)

to an MSDS before the substances are reintroduced into the workplace.

(B) The employer must ensure that persons who will receive, or who have received these substances from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial consumer activities.* Requirements as specified in § 721.80(p) (limit set at 9,500 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance. The following recordkeeping requirements are applicable to manufacturers, importers, and processors of these substances, as specified in § 721.125 (a), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 32237, June 8, 1993]

## § 721.1755 Methylenebisbenzotriazole.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance methylenebisbenzotriazole (P-93-578) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* During both manufacture and use of the substance, requirements as specified in § 721.63 (a)(4), (a)(6)(i), (b) (concentration set at 1.0 percent) and (c). During manufacture of the PMN substance § 721.63(a)(5)(i); during use of the PMN substance § 721.63 (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), and (a)(5)(vii).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iv), (g)(1)(vi), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[60 FR 11041, Mar. 1, 1995]

## § 721.1760 Substituted benzotriazole derivatives.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as substituted benzotriazole derivatives (PMNs P-93-374 and P-93-375) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(iv), (g)(1)(vi), (g)(2)(i), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g), (v)(1), (w)(1), and (x)(1).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of these substances.

## Environmental Protection Agency

## § 721.1775

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11041, Mar. 1, 1995]

### § 721.1765 2-Substituted benzotriazole.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 2-substituted benzotriazole (PMN P-90-335) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iv), (g)(1)(vi), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), (c)(4), (where N = 80). However, contrary to § 721.91(a)(4), if the waste stream containing the PMN substance will be treated using biological treatment (activated sludge or equivalent) plus clarification, then the amount of PMN substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 75 percent removal efficiency may be attributed to such treatment.

(b) *Special requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19235, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993; 60 FR 30468, June 9, 1995; 63 FR 45955, Aug. 28, 1998]

### § 721.1767 Substituted 6,6'-(1-methylethylidene)bis[3,4-dihydro-3-phenyl-1,3-benzoxazine] (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted 6,6'-(1-methylethylidene)bis[3,4-dihydro-3-phenyl-1,3-benzoxazine] (PMN P-00-0993) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15081, Mar. 28, 2003]

### § 721.1775 6-Nitro-2(3H)-benzoxazolone.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance 6-nitro-2(3H)-benzoxazolone (PMN P-84-963) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), and



## § 721.1790

## 40 CFR Ch. I (7-1-10 Edition)

(g)(2)(v). The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b) and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), (x)(1), and (y)(2).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (d), (e), (f), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[55 FR 26100, June 26, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.1790 Polybrominated biphenyls.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as 1,1'-(Biphenyl, 4,4'-dibromo- (CAS No. 92-86-4); 1,1'-(Biphenyl, 2-bromo- (CAS No. 2052-07-5); 1,1'-(Biphenyl, 3-bromo- (CAS No. 2113-57-7); 1,1'-(Biphenyl, 2,2', 3,3', 4,4', 5,5', 6,6'-decabromo- (CAS No. 13654-09-6); Nonabromobiphenyl (CAS No. 27753-52-2); Octabromobiphenyl (CAS No. 27858-07-7); and Hexabromobiphenyl (CAS No. 36355-01-8) are subject to reporting under this section for the significant new uses described in paragraph (a)(1)(i) of this section.

(i) The significant new use is: Any use.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes a substance identified in paragraph (a)(1) of this section and intends to distribute the substance

in commerce must submit a significant new use notice.

(B) [Reserved]

(2) The chemical substance identified as 1,1'-(Biphenyl, 4-bromo- (CAS No. 92-66-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2)(i) of this section.

(i) The significant new uses are:

(A) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (j), and (s) (10,000 kilograms).

(B) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(C) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

(b) [Reserved]

[63 FR 45955, Aug. 28, 1998]

### § 721.1800 3,3',5,5'-Tetramethylbiphenyl-4,4'-diol.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as 3,3',5,5'-tetramethylbiphenyl-4,4'-diol (PMN P-88-972) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(vii), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1 percent), (f), (g)(1)(iv), (g)(1)(ix), (g)(2)(ii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) (monomer for epoxy

## Environmental Protection Agency

## § 721.1825

resins and engineering plastics or an antioxidantizing agent for lubricating oils) and (p) (level set at 42,000 kg and 366,000 kg).

(iv) *Disposal*. Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2).

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[55 FR 33308, Aug. 15, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.1805 Substituted bisaniline.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as a substituted bisaniline (PMN P-96-1410) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water*. Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 4).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[63 FR 3423, Jan. 22, 1998]

### § 721.1820 Bisphenol derivative.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as bisphenol derivative (PMN No. P-92-509) is subject to reporting under this section for the significant new

uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace*. Requirements as specified in § 721.63 (a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program*. Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1) (systemic effects—depression in body weight gain and blood effects), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv) (when in dust or mist form), and (g)(5).

(iii) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80(q).

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a) through (d), and (f) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section*. The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32237, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

### § 721.1825 Bisphenol A, epichlorohydrin, polyalkylenepolyol and polyisocyanato derivative.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as bisphenol A, epichlorohydrin, polyalkylenepolyol and polyisocyanato derivative (PMN P-89-750) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace*. Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program*. Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1

## § 721.1850

## 40 CFR Ch. I (7–1–10 Edition)

percent), (f) and (g)(1)(vi), (g)(1)(vii), (g)(2)(i) through (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q) (The production limit applies to the aggregate production volume of both P-89-750 and P-89-760. P-89-760 is the preferred substance for use in performing these tests. Results from such testing can be used to evaluate the toxicity of P-89-750 as well).

(iv) *Disposal.* Requirements as specified in § 721.85 (b)(1), (b)(2), (c)(1), and (c)(2).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(ii) (Oil and grease separation may be used as an alternative treatment), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), (j), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 46772, Nov. 6, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.1850 Toluene sulfonamide bisphenol A epoxy adduct.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as toluene sulfonamide bisphenol A epoxy adduct (PMN P-90-113) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows. (A) If, as a result of the test data required

under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is re-introduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (c), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 15791, Apr. 17, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.1852 Di-alkyl borane (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as di-alkyl borane (PMN P-00-1087) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

## Environmental Protection Agency

§ 721.1880

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=200 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i) and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15081, Mar. 28, 2003]

### § 721.1875 Boric acid, alkyl and substituted alkyl esters (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance boric acid, alkyl and substituted alkyl esters (PMN P-86-1252) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3), (b) [concentration set at 0.1 percent], and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (d), (e) [concentration set at 0.1 percent], (f), and (g)(1)(i), (g)(1)(iv), (g)(1)(vii), (g)(1)(viii), and (g)(1)(ix), (g)(2)(i) and (g)(2)(v), (g)(4)(i) and (g)(4)(iii), and (g)(5). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on a MSDS does not apply when a MSDS was not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (b)(1).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26108, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.1878 Alkali metal alkyl borohydride (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkali metal alkyl borohydride (PMN P-00-1089) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15082, Mar. 28, 2003]

### § 721.1880 Borate(1-), tris(acetato-kappa.O)hydro-, sodium, (T-4)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as borate(1-), tris(acetato-kappa.O)hydro-, sodium, (T-4)- (PMN P-00-0922; CAS No.

## § 721.1900

56553–60–7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=300 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15082, Mar. 28, 2003]

## § 721.1900 Substituted bromothiophene.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted bromothiophene (P-83–769) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), and (a)(6)(i).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(1)(i)(D) and (g)(2)(iv). The provision of § 721.72(g) requiring placement of specific information in an MSDS does not apply when an MSDS is not required under § 721.72(c).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a), (b), (c), (d), (f), and (g).

## 40 CFR Ch. I (7–1–10 Edition)

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25990, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.1907 Butanamide, 2,2'-[3'dichloro[1,1'-biphenyl]-4,4'-diyl]bisazobis N-2,3-dihydro-2-oxo-1H-benzimidazol-5-yl)-3-oxo-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as butanamide, 2,2'-[3'dichloro[1,1'-biphenyl]-4,4'-diyl]bisazobis N-2,3-dihydro-2-oxo-1H-benzimidazol-5-yl)-3-oxo- (PMN P-93-1111) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5). The following additional statements shall appear on each label and Material Safety Data Sheet (MSDS) as specified by this paragraph: This substance decomposes in polymers or sheet metal coatings at temperatures greater than 280 °C to give 3,3' DCB a suspect human carcinogen.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f) and processing or use at temperatures above 280 °C.

(iii) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1). When the substance is processed or used as a colorant for dyeing plastics, this section does not apply.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 5742, Feb. 4, 1998]

**§ 721.1920 1,4-Bis(3-hydroxy-4-benzoylphenoxy)butane.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,4-bis(3-hydroxy-4-benzoylphenoxy)butane (PMN P-93-483) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 1 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51683, Oct. 4, 1993]

**§ 721.1925 Substituted carboheterocyclic butane tetracarboxylate (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted carboheterocyclic butane tetracarboxylate (PMNs P-90-440 and P-95-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply when particle sizes of the chemical substance is greater than 250 microns.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(iv), (g)(1)(vi), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, and specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 19242, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993; 67 FR 12885, Mar. 20, 2002]

**§ 721.1930 Butanoic acid, antimony (3=) salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as butanoic acid, antimony (3=) salt (PMN P-94-1143; CAS No. 53856-17-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (g)(1)(i), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(v), and (g)(5). The label and MSDS as required by this paragraph shall also include the following statement: This substance may cause neurologic effects. This substance may cause cardiovascular effects. This substance may cause ocular irritation.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (675,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

**§ 721.1950**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3423, Jan. 22, 1998]

**§ 721.1950 2-Butenedioic acid (Z), mono(2-((1-oxopropenyloxy)ethyl) ester .**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as 2-butenedioic acid (Z), mono(2-((1-oxopropenyloxy)ethyl) ester (PMN P-85-543) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(xi), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f) (g)(1)(iii), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v) and (g)(5). The provision of § 721.72(d) requiring that employees to be provided with information on the location and availability of a written hazard communication program does not apply when the written program is not required under § 721.72(a).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44063, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

**40 CFR Ch. I (7-1-10 Edition)**

**§ 721.2025 Substituted phenylimino carbamate derivative.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted phenylimino carbamate derivative (PMN P-91-487) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46464, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

**§ 721.2060 Disubstituted benzenedicarboxylic acid (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a disubstituted benzenedicarboxylic acid (PMN P-01-77) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Release to water.* Requirements as specified § 721.90(a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

## Environmental Protection Agency

## § 721.2077

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70175, Dec. 17, 2003]

### § 721.2075 Carbamodithioic acid, methyl-, compound with methanamine (1:1).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as carbamodithioic acid, methyl-, compound with methanamine (1:1) (P-84-1042), is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(1)(vi), and (g)(2)(i). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information in an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 720.80(k).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(2), (b)(2), and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (g), (i), and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 25990, June 5, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.2076 D-Glucuronic acid, polymer with 6-deoxy-L-mannose and D-glucose, acetate, calcium magnesium potassium sodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as D-Glucuronic acid, polymer with 6-deoxy-L-mannose and D-glucose, acetate, calcium magnesium potassium sodium salt (PMN P-00-7; CAS No.125005-87-0) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (oilfield drilling fluid, oilfield spacer fluid, oilfield cementing, cementitious packaged products, concrete applications, and foam applications).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70175, Dec. 17, 2003]

### § 721.2077 Substituted carbazate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted carbazate (PMN P-97-267) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (c)(1) and (c)(2)(iv). The MSDS required by



§ 721.2078

40 CFR Ch. I (7-1-10 Edition)

this paragraph shall include the following statements: Overexposure to this material may cause severe acute toxicity including death. This concern is particularly true with respect to direct contact to the eyes. Exposure to the eyes may cause severe acute toxicity including death.

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (a), (b), (c), and (j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 65710, Nov. 30, 1998]

§ 721.2078 **1-Piperidinecarboxylic acid, 2-[(dichloro-hydroxy-carbomonocycle)hydrazono]-, methyl ester (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as 1-piperidinecarboxylic acid, 2-[(dichloro-hydroxy-carbomonocycle)hydrazono]-, methyl ester (PMN P-96-756) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g), (l), and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 44576, Aug. 20, 1998]

§ 721.2079 **Dichloro, hydroxy, hydrazino-carbomonocycle (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as dichloro, hydroxy, hydrazino-carbomonocycle (PMN P-96-757) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g), (l), and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 44576, Aug. 20, 1998]

## Environmental Protection Agency

## § 721.2085

### § 721.2081 Dichloro, hydroxy, hydrazino-carbomonocycle-monohydrochloride (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as dichloro, hydroxy, hydrazino-carbomonocycle-monohydrochloride (PMN P-96-758) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g), (l), and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 44576, Aug. 20, 1998]

### § 721.2083 Polysubstituted carbomonocyclic hydroxylamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polysubstituted carbomonocyclic hydroxylamine (PMN P-97-878) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4),

(a)(5)(ii), (a)(5)(iv), (a)(5)(v), and (a)(6)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), and (d) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44576, Aug. 20, 1998]

### § 721.2084 Carbon oxyfluoride (Carbonic difluoride).

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance carbon oxyfluoride (CAS No. 353-50-4), also referred to as carbonic difluoride, is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63516, Dec. 1, 1993]

### § 721.2085 Hydroxyalkylquinoline dioxoindandialkylcarboxamide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a hydroxyalkylquinoline dioxoindandialkylcarboxamide (PMN P-94-682) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

**§ 721.2086**

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11042, Mar. 1, 1995]

**§ 721.2086 Coco acid triamine condensate, polycarboxylic acid salts.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as coco acid triamine condensate, polycarboxylic acid salts. (PMN P-92-446) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46464, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

**§ 721.2087 3-furancarboxaldehyde, tetrahydro-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a 3-furancarboxaldehyde, tetrahydro- (PMN P-98-1048; CAS No. 79710-86-4) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

**40 CFR Ch. I (7-1-10 Edition)**

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 368, Jan. 5, 2000]

**§ 721.2088 Carboxylic acids, (C6-C9) branched and linear.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as carboxylic acids, (C6-C9) branched and linear (PMNs P-93-313, 314, 315, and 316) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(iii) and (g)(5).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 300 ppb for P-93-313, 314, and 315 and N = 50 ppb for P-93-316).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11042, Mar. 1, 1995]

**§ 721.2089 Tetrasubstituted aminocarboxylic acid.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a tetrasubstituted aminocarboxylic acid (PMN P-85-619) is subject to reporting under this section

## Environmental Protection Agency

§ 721.2094

for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in §721.72 (a), (b), (c), (d), (f), (g)(1)(vii), (g)(2)(iii), (g)(3)(ii), (g)(4)(ii), (g)(4)(iii), and (g)(5).

(ii) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a) through (h) and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[60 FR 45081, Aug. 30, 1995]

### § 721.2091 Chloroalkane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a chloroalkane (PMN P-96-273) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 3423, Jan. 22, 1998]

### § 721.2092 3-Methylcholanthrene.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance 3-methylcholanthrene (CAS No. 56-49-5) is subject to reporting under this sec-

tion for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in §721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63516, Dec. 1, 1993]

### § 721.2093 Alkenyl carboxylate, metal salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkenyl carboxylate, metal salt (PMN P-99-0848) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(j) (an emulsifier for metalworking fluids) and (q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of §721.1725(b)(1) apply to this section.

[68 FR 15082, Mar. 28, 2003]

### § 721.2094 N,N'-di(alkyl heteromonocycle)amino chlorotriazine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as N,N'-di(alkyl

§ 721.2095

heteromonocycle)amino chlorotriazine (PMN P-93-1369) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i) (this respirator meets the minimum requirement for persons exposed via inhalation during manufacture), (a)(5)(ii), (a)(5)(iv), (a)(5)(v) (these three respirators meet the minimum requirements for persons exposed via inhalation during processing and use), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72(a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(1)(viii), (g)(1)(ix), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3424, Jan. 22, 1998]

§ 721.2095 Chromate(3-), bis 2-[[substituted-3-[(5-sulfo-1-naphthalenyl)azo]phenyl]azo]substituted monocycle, trisodium (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as chromate(3-), bis 2-[[substituted-3-[(5-sulfo-1-naphthalenyl)azo]phenyl]azo]substituted monocycle,

40 CFR Ch. I (7-1-10 Edition)

trisodium (PMN P-95-1242) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(1), (w)(1), and (y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63736, Dec. 2, 1996]

§ 721.2097 Azo chromium complex dye-stuff preparation (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an azo chromium complex dye-stuff preparation (PMN P-95-240) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80 (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63736, Dec. 2, 1996]

§ 721.2098 Aliphatic polycarboxylic acid metal salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

## § 721.2122

chemical substance identified generically as an aliphatic polycarboxylic acid metal salt (PMN P-01-7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(v)(1), (x)(1), and (f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70176, Dec. 17, 2003]

### § 721.2120 Cyclic amide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a cyclic amide (PMN P-92-131) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 70 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46465, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.2121 Thiosubstituted carbonate ester (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generi-

cally as Thiosubstituted carbonate ester (PMN P-99-0654) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81399, Dec. 26, 2000]

### § 721.2122 Substituted phenyl azo substituted sulfo carbopolycycle.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted phenyl azo substituted sulfo carbopolycycle (PMN P-96-702) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(r) (204,000 kg) (activated sludge adsorption isotherm- OPPTS 835.1110 test guideline (public draft; 61 FR 16486, April 15, 1996) (FRL-5363-1), daphnid acute toxicity-§ 797.1300, fish acute toxicity-§ 797.1400, murine immune allergic response study (*Toxicology and Applied Pharmacology* 112:190-197 (1992))). A person may not manufacture or import the substance beyond the following aggregate production volume limits, unless that person conducts the following corresponding studies on the substance and submits all final reports and underlying data in accordance with the procedures and criteria specified in paragraphs (a)(2)(i)(A), (a)(2)(i)(B), (a)(2)(i)(C), and (a)(2)(i)(D) of this section.

(A) Each study required to be performed pursuant to this section must

§721.2140

40 CFR Ch. I (7–1–10 Edition)

be scientifically valid. *Scientifically valid* means that the study was conducted according to:

(1) The test guidelines specified in paragraph (a)(2)(i) of this section.

(2) An EPA-approved protocol.

(3) TSCA Good Laboratory Practice Standards at 40 CFR part 792.

(4) Using methodologies generally accepted at the time the study is initiated.

(5) Any deviation from these requirements must be approved in writing by EPA.

(B) Before starting to conduct any of the studies in paragraph (a)(2)(i) of this section, the person must obtain approval of test protocols from EPA by submitting written protocols. EPA will respond to the person within 4 weeks of receiving the written protocols. Published test guidelines specified in paragraph (a)(2)(i) of this section (e.g., 40 CFR part 797 or part 798) provide general guidance for development of test protocols, but are not themselves acceptable protocols.

(C) The person shall:

(1) Conduct each study in good faith with due care.

(2) Promptly furnish to EPA the results of any interim phase of each study.

(3) Submit, in triplicate (with an additional sanitized copy, if confidential business information is involved), the final report of each study and all underlying data (“the report and data”) to EPA no later than 14 weeks prior to exceeding the applicable production volume limit. The final report shall contain the contents specified in 40 CFR 792.185.

(D)(1) Except as described in paragraph (a)(2)(i)(D)(2) of this section, if, within 6 weeks of EPA’s receipt of a test report and data, the person receives written notice that EPA finds that the data generated by a study are scientifically invalid, the person is prohibited from further manufacture and import of the PMN substance beyond the applicable production volume limit.

(2) The person may continue to manufacture and import the PMN substance beyond the applicable production limit only if so notified, in writing, by EPA in response to the person’s

compliance with either of the following paragraph (a)(2)(i)(D)(2)(i) or (a)(2)(i)(D)(2)(ii) of this section.

(i) The person may reconduct the study. If there is sufficient time to reconduct the study and submit the report and data to EPA at least 14 weeks before exceeding the production limit as required by paragraph (a)(2)(i)(C)(3) of this section, the person shall comply with paragraph (a)(2)(i)(C)(3) of this section. If there is insufficient time for the person to comply with paragraph (a)(2)(i)(C)(3) of this section, the person may exceed the production limit and shall submit the report and data in triplicate to EPA within a reasonable period of time, all as specified by EPA in the notice described in paragraph (a)(2)(i)(D)(1) of this section. EPA will respond to the person in writing, within 6 weeks of receiving the person’s report and data.

(ii) The person may, within 4 weeks of receiving from EPA the notice described in paragraph (a)(2)(i)(D)(1) of this section, submit to EPA a written report refuting EPA’s finding. EPA will respond to the person in writing, within 4 weeks of receiving the person’s report.

(E) The person is not required to conduct a study specified in paragraph (a)(2)(i) of this section if notified in writing by EPA that it is unnecessary to conduct that study.

(i) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 3424, Jan. 22, 1998]

**§721.2140 Carbopolycyclic azoalkyl-aminoalkylcarbomonocyclic ester, halogen acid salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

## § 721.2175

chemical substance generically identified as carbopolycyclic azoalkylaminoalkylcarbomonocyclic ester, halogen acid salt (PMN P-88-1682) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (f), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4) and (c)(4) (where N = 1 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44063, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.2145 Cetareth-25 sorbate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as cetareth-25 sorbate (PMN P-96-941) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manu-

facturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3425, Jan. 22, 1998]

### § 721.2155 Alkoxyamino-alkyl-coumarin (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkoxyamino-alkyl-coumarin. (PMN P-00-0108) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15082, Mar. 28, 2003]

### § 721.2175 Salt of cyclodiamine and mineral acid.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a salt of cyclodiamine and mineral acid (PMN P-91-838) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a),



## § 721.2222

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46465, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.2222 Cyclohexanamine, *N,N*-dimethyl-, compd. with alpha-isotridecyl-omega-hydroxypoly(oxy-1,2-ethanediyl) phosphate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as cyclohexanamine, *N,N*-dimethyl-, compd. with alpha-isotridecyl-omega-hydroxypoly(oxy-1,2-ethanediyl) phosphate (PMN P-96-1176; CAS No. 164383-18-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3425, Jan. 22, 1998]

### § 721.2250 1,4-Cyclohexanediamine, *cis*- and *trans*-.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as 1,4-cyclohexanediamine, *cis*- and *trans*- (PMNs P-87-1881 and P-87-1882; CAS numbers 15827-56-2 and 2615-25-0) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(iii), (g)(5).

## 40 CFR Ch. I (7-1-10 Edition)

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44064, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.2260 1,2-Cyclohexanedicarboxylic acid, 2,2-bis[[[2-(oxiranylethoxy) carbonyl]cyclohexyl]carbonyl]oxy]methyl]-1,3-propanediyl bis(oxiranylethoxy) ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 1,2-cyclohexanedicarboxylic acid, 2,2-bis[[[2-(oxiranylethoxy) carbonyl]cyclohexyl]carbonyl]oxy]methyl]-1,3-propanediyl bis(oxiranylethoxy) ester (PMN P-92-471) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(ii), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(ii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## Environmental Protection Agency

## § 721.2280

(b), (c), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51702, Oct. 4, 1993]

### § 721.2265 Polyalkylene oxide dialkylamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Polyalkylene oxide dialkylamine (PMN P-99-0423) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81399, Dec. 26, 2000]

### § 721.2270 Aliphatic dicarboxylic acid salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as aliphatic dicarboxylic acid salt (PMN P-92-1352) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 1,000 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51683, Oct. 4, 1993]

### § 721.2275 N,N,N,N'-Tetrakis(oxiranylmethyl)-1,3-cyclohexane dimethanamine.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as N,N,N,N'-tetrakis(oxiranylmethyl)-1,3-cyclohexanedimethanamine (P-84-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25991, June 5, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.2280 Cyclopropanecarboxaldehyde.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as

**§ 721.2287**

**40 CFR Ch. I (7-1-10 Edition)**

cyclopropanecarboxaldehyde (PMN P-96-33) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(v), (b) (concentration set at 1.0 percent), and (c). Each person who is reasonably likely to be exposed by inhalation to the PMN substance in vapor form during loading of rail cars is provided with, and is required to wear, at a minimum, a National Institute for Occupational Safety and Health (NIOSH) approved category 19C Type C supplied-air respirator operated in pressure demand or other positive pressure mode and equipped with a full facepiece with an assigned protection factor (APF) of 200. As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the new chemical exposure limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the TSCA section 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iv), (g)(1)(ix), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3425, Jan. 22, 1998]

**§ 721.2287 DDT  
(Dichlorodiphenyltrichloroethane).**

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance DDT (dichlorodiphenyltrichloroethane) (CAS No. 50-29-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63516, Dec. 1, 1993]

**§ 721.2340 Dialkenylamide (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a dialkenylamide (P-87-502) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(5)(xv), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2) and (c)(1), (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## Environmental Protection Agency

## § 721.2380

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26099, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.2345 Alkyletherpropyl dialkylamines.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified as alkyletherpropyl dialkylamines (PMNs P-96-1510/1511/1512/1513/1514) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3425, Jan. 22, 1998]

### § 721.2350 Alkyltri, tetra, and pentaamines.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkyltri, tetra, and pentaamines (PMNs P-96-406/407/408) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3425, Jan. 22, 1998]

### § 721.2355 Diethylstilbestrol.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance diethylstilbestrol (CAS No. 56-53-1) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63516, Dec. 1, 1993]

### § 721.2380 Disubstituted diamino anisole.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The following chemical substance referred to by its premanufacture notice number and generic chemical name is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section: P-83-822, disubstituted diamino anisole.

(2) The significant new uses are:

(i) Use other than as an intermediate.

(ii) Manufacture, import, or processing for use as an intermediate without establishing a program whereby:

**§ 721.2385**

(A) Persons employed by or under the control of the manufacturer, importer, or processor who may be exposed to the substance (including those persons involved in maintenance, packaging, and storage operations) wear protective gloves determined to be impervious to the substance by testing the gloves under the conditions of exposure or by evaluating the specifications provided by the manufacturer of the gloves, and

(B) Packages containing the substance (including those storing the substance between manufacturing or importing and processing stages) are labeled to indicate that the substance should be handled only while using gloves determined to be impervious to the substance.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* In addition to the requirements of § 721.17, manufacturers, importers, and processors of the chemical substance identified in paragraph (a)(1) of this section must maintain the following records for 5 years from their creation:

- (i) The results of any determination that gloves are impervious.
- (ii) The names of persons required to wear gloves.
- (iii) Copies of labels described in paragraph (a)(2)(ii)(B) of this section.

(2) [Reserved]

[50 FR 34465, Aug. 26, 1985. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.2385 Fluoroalkyl diester (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as fluoroalkyl diester (PMNs P-98-1046 and P-98-1047) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

**40 CFR Ch. I (7-1-10 Edition)**

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 368, Jan. 5, 2000]

**§ 721.2410 Alkoxyated alkyldiethylenetriamine, alkyl sulfate salts.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkoxyated dialkyldiethylenetriamine, alkyl sulfate salts (PMN P-94-325, 326, and 327) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(o).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11042, Mar. 1, 1995]

**§ 721.2420 Alkoxyated dialkyldiethylenetriamine, alkyl sulfate salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkoxyated dialkyldiethylenetriamine, alkyl sulfate salt (PMN P-91-288) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46465, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

**§ 721.2465 Xanthylum, 9-(2-(ethoxycarbonyl)phenyl)-3,6-bis(ethylamino)-2,7-dimethyl-, ethyl sulfate.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as xanthylum, 9-(2-(ethoxycarbonyl)phenyl)-3,6-bis(ethylamino)-2,7-dimethyl-, ethyl sulfate (PMN P-00-1195; CAS No. 26694-69-9) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f) and (j) (a basic dye for complex basic dye pigment manufacture).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15082, Mar. 28, 2003]

**§ 721.2475 Dimetridazole.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as dimetridazole (P-90-1308) is subject to reporting under this section

for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v) and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44064, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.2480 Isoalkyldimethylamine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as isoalkyldimethylamine (PMN P-96-1320) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 3).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

**§ 721.2485**

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44577, Aug. 20, 1998]

**§ 721.2485 1,3-Dioxolane, 2-ethenyl-**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as 1,3-Dioxolane, 2-ethenyl- (PMN P-96-1006; CAS No. 3984-22-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(3)(i), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(v), (b) (concentration set at 1.0 percent), and (c). The impermeousness of each item pursuant to (a)(2)(i) and (a)(2)(ii) must be demonstrated by actual testing under (a)(3)(i) and not by manufacturer specifications. Permeation testing shall be conducted according to the ASTM F739 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases." Results shall be recorded as a cumulative permeation rate as a function of time, and shall be documented in accordance with ASTM F739 using the format specified in ASTM F1194-89 "Guide for Documenting the Results of Chemical Permeation Testing on Protective Clothing Materials." Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift. The manufacturer, importer, or processor must submit all test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(ii), (g)(2)(iii), and (g)(5). The following statements shall appear on each label as specified in § 721.72(b) and the MSDS as specified in § 721.72(c): This substance may cause fatality. When using this substance avoid dermal con-

**40 CFR Ch. I (7-1-10 Edition)**

tact. When using this substance use respiratory protection or engineering and process controls to mitigate respiratory exposure. When using this substance use dermal protection to prevent dermal exposure.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), and (h) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44577, Aug. 20, 1998]

**§ 721.2520 Alkylated diphenyls.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkylated diphenyls (PMN Nos. P-90-237, P-90-248, and P-90-249) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 1 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[58 FR 32237, June 8, 1993]

**§ 721.2527 Substituted diphenylazo dye (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted diphenylazo dye

## Environmental Protection Agency

## § 721.2560

(PMN P-95-514) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63736, Dec. 2, 1996]

### § 721.2532 Substituted diphenylmethane (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted diphenylmethane (PMN P-97-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44577, Aug. 20, 1998]

### § 721.2535 Benzene, 1,1'-methylenebis[4-isocyanato-, homopolymer, Bu alc.-blocked.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzene, 1,1'-methylenebis[4-isocyanato-,

homopolymer, Bu alc.-blocked (PMN P-95-1386; CAS No. 186321-98-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3425, Jan. 22, 1998]

### § 721.2540 Diphenylmethane diisocyanate (MDI) modified.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a diphenylmethane diisocyanate (MDI) modified (PMN P-92-294) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), (x)(2), (y)(1), and (y)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46465, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.2560 Alkylated diphenyl oxide (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The



## § 721.2565

chemical substance alkylated diphenyl oxide (PMN P-84-1079) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3), (b) [concentration set at 1.0 percent], and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (d), (e) [concentration set at 1.0 percent], (f), and (g)(1)(vi) and (g)(1)(ix), (g)(2)(i) and (g)(2)(v), and (g)(5). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when a MSDS was not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g). The term intermediate as used in § 721.80(g) is defined as an intermediate for making sulfonated surfactants.

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26109, June 26, 1990, as amended at 57 FR 54305, Nov. 18, 1992. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.2565 Alkylated sulfonated diphenyl oxide, alkali and amine salts.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as alkylated sulfonated diphenyl oxide, alkali salt (PMN P-93-352) and

## 40 CFR Ch. I (7-1-10 Edition)

alkylated sulfonated diphenyl oxide, amine salt (PMN P-93-353) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 20 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51683, Oct. 4, 1993]

## § 721.2570 Alkylated diphenyls (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkylated diphenyls (PMNs P-97-869/870/871) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44577, Aug. 20, 1998]

## § 721.2575 Disubstituted diphenylsulfone.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

§ 721.2582

chemical substance identified generically as disubstituted diphenylsulfone (PMN P-92-1119) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63(a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(iii), and (g)(5). The following additional statements shall appear on each label and MSDS as required by this paragraph: This substance may cause blood effects.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (o), and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51683, Oct. 4, 1993]

### § 721.2577 Copper complex of (substituted sulfonaphthyl azo substituted phenyl) disulfonaphthyl azo, amine salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as copper complex of (substituted sulfonaphthyl azo substituted phenyl) disulfonaphthyl azo, amine salt (PMNs P-00-0364 and P-00-0365) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15082, Mar. 28, 2003]

### § 721.2580 C.I. Disperse Red 152 (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as C.I. disperse red 152 (PMN P-97-820) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44577, Aug. 20, 1998]

### § 721.2582 Reaction product of alkylene diamine, MDI, substituted carbomonocyclic amine and alkylamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as reaction product of alkylene diamine, MDI, substituted carbomonocyclic amine and alkylamine (PMN P-98-1262) is subject to reporting under this section for the

significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15083, Mar. 28, 2003]

#### § 721.2584 Dodecanoic acid, 12-amino-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as dodecanoic acid, 12-amino- (PMN P-98-0823; CAS No. 693-57-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (g). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provision listed in the 5(e) consent order for this substance. The NCEL is 1.0 mg/m<sup>3</sup> as an 8-hour time-weighted average verified by actual monitoring data.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e), (f), (g)(1)(ii), (g)(1)(vii), (g)(2)(ii), and (g)(2)(iv).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g), (r) (6,000,000 kg.), and a carcinogenicity study (OPPTS 870.4200). A person may not manufacture or import the substance beyond the aggregate production volume limit, unless that person conducts this study on the substance and submits all final reports and underlying data in accordance with the procedures and criteria

specified in paragraphs (a)(2)(iii)(A), (a)(2)(iii)(B), (a)(2)(iii)(C), and (a)(2)(iii)(D) of this section.

(A) Each study required to be performed pursuant to this section must be scientifically valid. *Scientifically valid* means that the study was conducted according to:

(1) The test guidelines specified in paragraph (a)(2)(iii) of this section.

(2) An EPA-approved protocol.

(3) TSCA Good Laboratory Practice Standards at 40 CFR part 792.

(4) Using methodologies generally accepted at the time the study is initiated.

(5) Any deviation from these requirements must be approved in writing by EPA.

(B) Before starting to conduct any of the studies in paragraph (a)(2)(iii) of this section, the person must obtain approval of test protocols from EPA by submitting written protocols. EPA will respond to the person within 4 weeks of receiving the written protocols. Published test guidelines specified in paragraph (a)(2)(iii) of this section (e.g., 40 CFR part 797 or part 798) provide general guidance for development of test protocols, but are not themselves acceptable protocols.

(C) The person shall:

(1) Conduct each study in good faith with due care.

(2) Promptly furnish to EPA the results of any interim phase of each study.

(3) Submit, in triplicate (with an additional sanitized copy, if confidential business information is involved), the final report of each study and all underlying data (“the report and data”) to EPA no later than 14 weeks prior to exceeding the applicable production volume limit. The final report shall contain the contents specified in 40 CFR 792.185.

(D)(1) Except as described in paragraph (a)(2)(iii)(D)(2) of this section, if, within 6 weeks of EPA’s receipt of a test report and data, the person receives written notice that EPA finds that the data generated by a study are scientifically invalid, the person is prohibited from further manufacture and import of the PMN substance beyond the applicable production volume limit.

## Environmental Protection Agency

## § 721.2625

(2) The person may continue to manufacture and import the PMN substance beyond the applicable production limit only if so notified, in writing, by EPA in response to the person's compliance with either of the following paragraphs (a)(2)(iii)(D)(2)(i) or (a)(2)(iii)(D)(2)(ii) of this section.

(i) The person may reconduct the study. If there is sufficient time to re-conduct the study and submit the report and data to EPA at least 14 weeks before exceeding the production limit as required by paragraph (a)(2)(iii)(C)(3) of this section, the person shall comply with paragraph (a)(2)(iii)(C)(3) of this section. If there is insufficient time for the person to comply with paragraph (a)(2)(iii)(C)(3) of this section, the person may exceed the production limit and shall submit the report and data in triplicate to EPA within a reasonable period of time, all as specified by EPA in the notice described in paragraph (a)(2)(iii)(D)(I) of this section. EPA will respond to the person in writing, within 6 weeks of receiving the person's report and data.

(ii) The person may, within 4 weeks of receiving from EPA the notice described in paragraph (a)(2)(iii)(D)(I) of this section, submit to EPA a written report refuting EPA's finding. EPA will respond to the person in writing, within 4 weeks of receiving the person's report.

(E) The person is not required to conduct a study specified in paragraph (a)(2)(iii) of this section if notified in writing by EPA that it is unnecessary to conduct that study.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15083, Mar. 28, 2003]

### § 721.2585 Sodium salts of dodecylphenol (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

chemical substances identified generically as sodium salts of dodecylphenol (PMNs P-97-1060/1061/1062) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44577, Aug. 20, 1998]

### § 721.2600 Epibromohydrin.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance epibromohydrin, CAS Number 3132-64-7, [Listed in TSCA Inventory as oxirane,(bromoethyl)-] is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is any use.

(b) *Special requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[52 FR 41300, Oct. 27, 1987. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.2625 Reaction product of alkanediol and epichlorohydrin.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## § 721.2673

chemical substance identified generically as reaction product of alkanediol and epichlorohydrin (PMN P-89-760) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), and (g)(1)(vi), (g)(1)(vii), (g)(2)(i) through (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l), and (q). (The production limit applies to the aggregate production volume of both P-89-750 and P-89-760. Results from testing this substance can be used to evaluate the toxicity P-89-750 as well.)

(iv) *Disposal.* Requirements as specified in § 721.85 (b)(1), (b)(2), (c)(1), and (c)(2).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(ii) (Oil and grease separation may be used as an alternative treatment.), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), (j), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 46772, Nov. 6, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.2673 Aromatic epoxide resin (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generi-

## 40 CFR Ch. I (7-1-10 Edition)

cally as aromatic epoxide resin (PMN P-99-1399) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15083, Mar. 28, 2003]

## § 721.2675 Perfluoroalkyl epoxide (generic name).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as perfluoroalkyl epoxide (PMN P-86-562) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i) and (g)(2)(v). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2).

## Environmental Protection Agency

## § 721.2752

(v) *Release to water.* § 721.90 (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (g), (i), (j), and (k).

(2) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

(3) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 26099, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.2685 Polyisobutene epoxide (generic).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as polyisobutene epoxide (PMNs P-99-951 and P-99-952) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 70176, Dec. 17, 2003]

### § 721.2725 Trichlorobutylene oxide.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance trichlorobutylene oxide (TCBO), CAS Number 3083-25-8,

[Listed in TSCA Inventory as oxirane, (2,2,2-trichloroethyl)-] is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is any use.

(b) *Special requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[52 FR 41300, Oct. 27, 1987. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.2752 Epoxy resin containing phosphorus (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an epoxy resin containing phosphorus (PMN P-00-912) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.575(b)(1) apply to this section.

[68 FR 70176, Dec. 17, 2003]

**§ 721.2755**

**40 CFR Ch. I (7–1–10 Edition)**

**§ 721.2755 Cycloaliphatic epoxy resin (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as cycloaliphatic epoxy resin (PMN P-98-105) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(viii), (a)(5)(ix), (a)(5)(x), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 0.3 mg/m<sup>3</sup>.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 368, Jan. 5, 2000]

**§ 721.2800 Erionite fiber.**

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance, erionite fiber (CAS No. 66733-21-9 (when an exact molecular formula is known) and 12510-42-8 (when an exact molecular formula is not known)), is subject to reporting under this section for the significant

new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by the following paragraphs:

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) *Exemptions.* Section 721.45 applies to this section except for § 721.45(f). A person who intends to import or process the substance identified in paragraph (a)(1) of this section as part of an article is subject to the notification provisions of § 721.25.

[56 FR 56472, Nov. 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.2805 Acrylate ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an acrylate ester (PMN P-96-824) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3426, Jan. 22, 1998]

## Environmental Protection Agency

## § 721.2920

### § 721.2825 Alkyl ester (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance alkyl ester (PMN P-84-968) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent) and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(ix), (g)(2)(i), (g)(2)(v), and (g)(5). The provision of § 721.72(d) requiring that employees to be provided with information on the location and availability of a written hazard communication program does not apply when the written program is not required under § 721.72(a). The provision of § 721.72(g) requiring placement of specific information on a label does not apply when a label is not required under § 721.72(b).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (e), (f), (i) and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32414, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.2900 Substituted aminobenzoic acid ester (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

chemical substance substituted aminobenzoic acid ester (PMN P-84-951) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii) and (g)(2)(v). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on a MSDS does not apply when a MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (e), (f), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32415, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.2920 *tert*-Amyl peroxy alkylene ester (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance *tert*-amyl peroxy alkylene ester (PMN P-85-1180) is subject to reporting under this section for



## § 721.2925

## 40 CFR Ch. I (7–1–10 Edition)

the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (d), (e) (concentration set at 1.0 percent), (f) and (g)(1)(vii), (g)(2)(i), (g)(2)(v), (g)(4)(i), and (g)(5). The provision of § 721.72(d) requiring that employees to be provided with information on the location and availability of a written hazard communication program does not apply when the written program is not required under § 721.72(a).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2) and (a)(3), (b)(1), (b)(2) and (b)(3).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(vi), (b)(2)(vi) and (c)(2)(vi).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32413, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.2925 Brominated aromatic ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a brominated aromatic ester (PMN P-95-1128) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(1), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) [Reserved]

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3426, Jan. 22, 1998]

## § 721.2950 Carboxylic acid glycidyl esters.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as carboxylic acid glycidyl ester (PMN P-92-776) is subject to reporting under this section for the significant new uses described in this paragraph.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(vi), (g)(1)(vii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

## Environmental Protection Agency

## § 721.3000

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(D) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) and (k) are applicable to manufacturers, importers, and processors of this substance.

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(C) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

(2) The chemical substance identified as carboxylic acid glycidyl ester (PMN P-92-777) is subject to reporting under this section for the significant new uses described in this paragraph.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(i) (§ 721.63(a)(5)(i) applies only during processing operations), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(vi), (g)(1)(vii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(D) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) *Specific requirements.* The provisions of subpart A of this part apply to

this section except as modified by this paragraph.

(A) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) and (k) are applicable to manufacturers, importers, and processors of this substance.

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(C) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

(b) [Reserved]

[59 FR 27483, May 27, 1994]

### § 721.3000 Dicarboxylic acid monoester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The following chemical substance referred to by its premanufacture notice number and its generic chemical name is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section: dicarboxylic acid monoester, P-83-255.

(2) The significant new uses are:

(i) Any manufacture in the United States for commercial purposes.

(ii) Failure to require the use of gloves determined to be impervious to the substance, and/or failure to require the use of clothing to prevent dermal contact for any person involved in any processing or use operation where dermal contact may occur. (Gloves may be determined to be impervious to the substance either by testing the gloves under the conditions of use or by relying on the manufacturer's specifications.)

(iii) Distribution in commerce by any person, including importers, processors, and distributors, without affixing to each container of any formulation containing the substance a label that includes, in letters no smaller than 10 point type, the following statements:

WARNING! HARMFUL IF INHALED OR ABSORBED THROUGH THE SKIN. MAY CAUSE REPRODUCTIVE EFFECTS.

—Do not get in eye, on skin, or clothing.

—Do not breathe (vapor, mist, spray, dust).

—Use with adequate ventilation.

—Wear impervious gloves and protective equipment to prevent contact or exposure.

## § 721.3020

## 40 CFR Ch. I (7–1–10 Edition)

- Promptly remove contaminated non-impervious clothing, wash before reuse.
- Discard contaminated leather shoes.
- Wash thoroughly after handling, and before eating, drinking, or smoking.
- Keep container closed.

FIRST AID: In case of contact.

EYES: Immediately flush with water for at least 15 minutes.

SKIN: Promptly wash thoroughly with mild soap and water.

INHALATION: Remove to fresh air. If breathing is difficult, give oxygen.

INGESTION: If conscious, give water and induce vomiting.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* In addition to the requirements of § 721.17, importers and processors of the chemical substance identified in paragraph (a)(1) of this section must maintain the following records for five years from their creation:

(i) The names of persons required to wear protective clothing.

(ii) The name and address of each person to whom the substance is sold or transferred and the date of such sale or transfer.

(2) [Reserved]

[49 FR 43064, Oct. 26, 1984. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.3020 1,1-Dimethylpropyl peroxy-ester (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 1,1-dimethylpropyl peroxyester (PMN P-85-680) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), and (a)(6)(v), (b) [concentration set at 0.1 percent], and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) [concentration set at 0.1 percent], (f), and (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v), and (g)(4)(i).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(3) and (b)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26111, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.3025 Fatty acids C<sub>12-18</sub>, C<sub>18</sub> unsaturated, C<sub>12-18</sub> alkyl esters (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as fatty acids C<sub>12-18</sub>, C<sub>18</sub> unsaturated, C<sub>12-18</sub> alkyl esters (PMNs P-94-697 through P-94-895) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (750,000 kilograms).

(ii) *Hazard communication program.* A significant new use of these substances is any manner or method of manufacture, import, or processing associated with any use of these substances without providing risk notification as follows:

(A) If as a result of the test data required under the TSCA section 5(e) consent order for these substances, the employer becomes aware that these substances may present a risk of injury to human health or the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time

## Environmental Protection Agency

## § 721.3034

the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substances are reintroduced into the workplace.

(B) The employer must ensure that persons who will receive or who have received the substances from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A), are provided an MSDS as described in §721.72(c) containing the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[65 FR 369, Jan. 5, 2000]

### § 721.3031 Boric acid (H<sub>3</sub>BO<sub>3</sub>), zinc salt (2=3).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as boric acid (H<sub>3</sub>BO<sub>3</sub>), zinc salt (2=3) (PMN P-97-552; CAS No. 10192-46-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(4), (b)(4), and (c)(4) (N = 3).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 44578, Aug. 20, 1998]

### § 721.3032 Boric acid (H<sub>3</sub>BO<sub>2</sub>), zinc salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as boric acid (H<sub>3</sub>BO<sub>2</sub>), zinc salt (PMN P-97-553; CAS No. 14720-55-9) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(4), (b)(4), and (c)(4) (N = 3).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 44578, Aug. 20, 1998]

### § 721.3034 Methylamine esters.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as methylamine esters (PMN P-94-982) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

## § 721.3062

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11042, Mar. 1, 1995]

### § 721.3062 Haloarylalkylketoester (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a haloarylalkylketoester. (PMN P-00-966) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=200).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70176, Dec. 17, 2003]

### § 721.3063 Substituted phenyl azo substituted phenyl esters (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as substituted phenyl azo substituted phenyl esters (PMNs P-95-655, P-95-782 and P-95-871) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(w)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufactur-

## 40 CFR Ch. I (7-1-10 Edition)

ers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[61 FR 63736, Dec. 2, 1996]

### § 721.3080 Substituted phosphate ester (generic).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted phosphate ester (PMN P-85-730) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Release to water.* Section 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) Determining whether a specific use is subject to this section. The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26100, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.3085 Brominated phthalate ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as brominated phthalate ester (PMN P-90-581) is subject to reporting

## Environmental Protection Agency

## § 721.3110

under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(ii) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of these substances without providing risk notification as follows.

(A) If as a result of the test data required under the TSCA section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health or the environment the employer must incorporate this new information, and any information on methods for protecting against such risk, into a MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substances are reintroduced into the workplace.

(B) The employer must ensure that persons who will receive, or who have received the substance from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3426, Jan. 22, 1998]

### § 721.3100 Oligomeric silicic acid ester compound with a hydroxylalkylamine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as oligomeric silicic acid ester compound with a hydroxylalkylamine (PMN P-91-118) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(a).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46465, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.3110 Polycarboxylic acid ester (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polycarboxylic acid ester (PMN P-97-1108) is subject to reporting under this section for the significant new use described in paragraph (a)(1) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a),

## § 721.3130

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70176, Dec. 17, 2003]

## § 721.3130 Sulfuric acid, mono-C<sub>9-11</sub>-alkyl esters, sodium salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as sulfuric acid, mono-C<sub>9-11</sub>-alkyl esters, sodium salts (PMN P-01-149; CAS No. 84501-49-5) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (5,000 kilogram (kg)).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70176, Dec. 17, 2003]

## § 721.3135 Phosphorous modified epoxy resin (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a phosphorous modified epoxy resin (PMNs P-00-992 and P-01-471) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90(a)(4), (b)(4), and (c)(4) (N=6).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## 40 CFR Ch. I (7-1-10 Edition)

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70176, Dec. 17, 2003]

## § 721.3140 Vinyl epoxy ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance vinyl epoxy ester (PMN P-85-527) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent) and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(vii), (g)(2)(i) through (g)(2)(iii), (g)(2)(v), (g)(4)(i), and (g)(5). The provision of § 721.72(d) requiring that employees to be provided with information on the location and availability of a written hazard communication program does not apply when the written program is not required under § 721.72(a).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) (as an injection molding coating), and (y).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(2), (b)(2), and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e), (f), (g), (h), and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 39900, Sept. 28, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## Environmental Protection Agency

## § 721.3160

### § 721.3152 **Ethanaminium, N-ethyl-2-hydroxy-N,N-bis(2-hydroxyethyl)-, diester with C<sub>12-18</sub> fatty acids, ethyl sulfates (salts).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance ethanaminium, N-ethyl-2-hydroxy-N,N-bis(2-hydroxyethyl)-, diester with C<sub>12-18</sub> fatty acids, ethyl sulfates (salts) (P-94-24) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health or the environment the employer must incorporate this new information, and any information on methods for protecting against such risk, into a material safety data sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive, or who have received, this substance from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (1,900,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[60 FR 45081, Aug. 30, 1995]

### § 721.3155 **3,8-Dioxa-4,7-disiladecane, 4,4,7,7-tetraethoxy-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 3,8-dioxa-4,7-disiladecane, 4,4,7,7-tetraethoxy- (PMN P-95-1326; CAS No. 16068-37-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3426, Jan. 22, 1998]

### § 721.3160 **1-Chloro-2-bromoethane.**

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance 1-chloro-2-bromoethane (CAS No. 107-04-0) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.



## § 721.3220

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[53 FR 2845, Feb. 2, 1988. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.3220 Pentachloroethane.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance pentachloroethane, CAS Number 76-01-7, is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[51 FR 32079, Sept. 9, 1986. Redesignated at 53 FR 2845, Feb. 2, 1988 and correctly redesignated at 56 FR 29903, July 1, 1991. Further redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.3248 Ethane, 1,2,2-trichlorodifluoro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as ethane, 1,2,2-trichlorodifluoro- (CAS No. 354-21-2, PMN No. P-92-595) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

## 40 CFR Ch. I (7-1-10 Edition)

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[58 FR 32237, June 8, 1993]

## § 721.3260 Ethanediimidic acids.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified as ethanediimidic acids (PMNs P-90-1472 and P-90-1473), are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e), (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(4)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1) and (b)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44065, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

Environmental Protection Agency

§ 721.3350

**§ 721.3310 Poly[oxy(methyl-1,2-ethanediy)], $\alpha$ -(1-oxo-2-propenyl)- $\omega$ -[(tetrahydro-2-furanyl)methoxy]-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as poly[oxy(methyl-1,2-ethanediy)], $\alpha$ -(1-oxo-2-propenyl)- $\omega$ -[(tetrahydro-2-furanyl)methoxy]- (PMN P-98-150; CAS No.149303-87-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80. Manufacture of the PMN substance with an average number of moles of propoxy group between 5 and 14.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[65 FR 369, Jan. 5, 2000]

**§ 721.3320 Ethanol, 2-amino-, compound with N-hydroxy-N-nitrosobenzeneamine (1:1).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as ethanol, 2-amino-, compound with N-hydroxy-N-nitrosobenzeneamine (1:1) (P-86-542), is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in §721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in §721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), and (g)(2)(v).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in §720.80(k) (monomer stabilizer).

(iv) *Disposal.* Requirements as specified in §721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in §721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this significant new use rule.

[56 FR 25990, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.3340 Ethanol, 2,2'-(hexylamino)bis-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as ethanol, 2,2'-(hexylamino)bis- (PMN P-91-1346) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified at §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[57 FR 31968, July 20, 1992, as amended at 58 FR 34204, June 23, 1993]

**§ 721.3350 N-Nitrosodiethanolamine.**

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance N-nitrosodiethanolamine (CAS No. 1116-54-7) is subject to reporting under this

### § 721.3360

### 40 CFR Ch. I (7–1–10 Edition)

section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

### § 721.3360 Substituted ethanolamine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted ethanolamine (PMN P-91-490) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), (x)(2), (y)(1), and (y)(2).

(ii) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N = 1 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46466, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.3364 Aliphatic ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an aliphatic ether (PMN P-93-1381) is subject to reporting under this section for the significant new uses de-

scribed in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27484, May 27, 1994]

### § 721.3374 Alkylenediolalkyl ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as an alkylenediolalkyl ether (PMN P-93-362) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51684, Oct. 4, 1993]

### § 721.3380 Anilino ether.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as anilino ether (P-83-910) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## Environmental Protection Agency

## § 721.3435

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(1)(i)(D) and (g)(2)(v). The provision of § 721.72(g) requiring placement of specific information in an MSDS does not apply when an MSDS is not required under § 721.72(c).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a), (b), (c), (d), (f), and (g).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25989, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.3420 Brominated arylalkyl ether.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as brominated arylalkyl ether (P-83-906) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(1)(i)(D) and (g)(2)(v). The provision of § 721.72(g) requiring placement of specific information in an MSDS does not apply when an MSDS is not required under § 721.72(c).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a), (b), (c), (d), (f), and (g).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25990, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.3430 4-Bromophenyl phenyl ether.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance 4-bromophenyl phenyl ether (CAS No. 101-55-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

### § 721.3435 Butoxy-substituted ether alkane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as butoxy-substituted ether alkane (PMN P-92-755) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (b) (concentration set at 1.0 percent), and (c). In addition, the employer must be able to demonstrate that the gloves selected for handling the chemical substance provide an impervious barrier to prevent dermal exposure during normal and expected duration and conditions of exposure within the work area by testing the material used to make the gloves and the construction of the gloves to establish that they will be impervious for the expected duration and conditions of exposure. The testing

must subject the gloves to the expected conditions of exposure, including the likely combinations of chemical substances to which the gloves may be exposed in the work area. There must be no permeation of the gloves by the chemical substance (or an EPA-approved analogue) greater than 0.16 µg/cm<sup>2</sup>/min after 8 h of testing in accordance with the most recent versions of the American Society for Testing and Materials (ASTM) F739 “Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases” and ASTM F1194 “Guide for Documenting the Results of Chemical Permeation Testing of Protective Clothing Materials.” The employer must submit all test data to the Agency and must receive written Agency approval of the test results for each type of glove tested prior to use of such gloves. Nitrile gloves with a minimum thickness of 0.5588 mm have already been tested and found to satisfy the terms of this section. Gloves contaminated with the PMN substance shall be disposed of after every work shift.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(ix), (g)(2)(i), (g)(2)(v), and (g)(5). In addition, the human health hazard statements shall include a statement that this substance may cause systemic toxicity and blood effects.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) and records documenting compliance with the glove permeability testing requirements of this section are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51684, Oct. 4, 1993]

#### § 721.3437 Dialkyl ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkyl ether (PMN P-93-1308) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 180 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11042, Mar. 1, 1995]

#### § 721.3438 Chlorohydroxyalkyl butyl ether (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as chlorohydroxyalkyl butyl ether (PMN P-99-1295) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=3).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70177, Dec. 17, 2003]

**§ 721.3440 Haloalkyl substituted cyclic ethers.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances haloalkyl substituted cyclic ethers (PMN P-85-368 and P-85-369) are subject to reporting under this section for the significant new uses described in this paragraph.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii) and (a)(6)(v) and (a)(6)(vi), (b) [concentration set at 1.0 percent], and (c).

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (d), (e) [concentration set at 1.0 percent], (f), and (g)(1)(iii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv) and (g)(2)(v), and (g)(5). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when a MSDS was not required under § 721.72(c). The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b) and (c), respectively.

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(D) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (a)(2), (b)(1) and (b)(2), and (c)(1) and (c)(2).

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of the substances, as specified in § 721.125 (a) through (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(C) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

(2) The chemical substance haloalkyl substituted cyclic ether (PMN P-85-367) is subject to reporting under this section for the significant new uses described in this paragraph.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), and (a)(6)(v) and (a)(6)(vi), (b) [concentration set at 0.1 percent], and (c).

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (d), (e) [concentration set at 0.1 percent], (f), and (g)(1)(iii), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv) and (g)(2)(v), and (g)(5). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when a MSDS was not required under § 721.72(c). The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b) and (c), respectively.

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(D) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1) and (b)(2), and (c)(1) and (c)(2).

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(C) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

(b) [Reserved]

[55 FR 26109, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.3465 Stilbene diglycidyl ether.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as stilbene diglycidyl ether (PMN P-96-1427) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

§ 721.3480

40 CFR Ch. I (7-1-10 Edition)

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory protection requirements of this section, manufacturers, importers, and processors of this substance may follow the terms of the new chemical exposure limits section in the TSCA section 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(ii), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5). The label and MSDS as required by this paragraph shall also include the following statement: When using this substance use respiratory protection or maintain workplace airborne concentrations at or below an 8-hour time-weighted average of 0.5 milligram (mg)/meter (m<sup>3</sup>).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3426, Jan. 22, 1998]

§ 721.3480 **Halogenated biphenyl glycidyl ethers.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as halogenated biphenyl glycidyl ethers (PMNs P-90-1844, P-90-1845, and P-90-1846) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1),

(a)(3), (a)(4), (a)(5)(i), (a)(6)(i), (b) (concentration set at 0.1 percent) and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii) and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(l).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44065, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

§ 721.3485 **Hydrofluorocarbon alkyl ether.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a hydrofluorocarbon alkyl ether (PMN P-95-1578) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. Non-spray uses are exempt from the provisions of this rule.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iii), and (a)(6)(v).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3427, Jan. 22, 1998]

## Environmental Protection Agency

## § 721.3500

### § 721.3486 Polyglycerin mono(4-nonylphenyl) ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyglycerin mono(4-nonylphenyl) ether (PMN P-94-2230) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45082, Aug. 30, 1995]

### § 721.3488 Poly(oxy-1,2-ethanediyl), alpha substituted-omega-hydroxy-, C<sub>16-20</sub> alkyl ethers.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as poly(oxy-1,2-ethanediyl), alpha substituted-omega-hydroxy-, C<sub>16-20</sub> alkyl ethers (PMN P-87-323) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 20).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3427, Jan. 22, 1998]

### § 721.3500 Perhalo alkoxy ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as perhalo alkoxy ether (PMN P-83-1227) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i) through (a)(5)(iii), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(ii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a), and (c), respectively. The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b), and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e), and (f).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 46772, Nov. 6, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]



**§ 721.3520 Aliphatic polyglycidyl ether.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance aliphatic polyglycidyl ether (PMN P-89-1036) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv) through (a)(5)(vii), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c) through (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 39900, Sept. 28, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.3550 Dipropylene glycol dimethyl ether.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as dipropylene glycol dimethyl ether (PMN P-93-507; CAS No. 111109-77-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. This class 2 substance is exempt from the notification requirements of this rule if it contains less than 5 percent by

weight of the specific isomer, propane, 2,2'-oxybis[1-methoxy- (CAS No. 189354-80-1), which is one of the possible products of the manufacturing process for PMN P-93-507.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(o).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), and (e) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[62 FR 59583, Nov. 4, 1997; 62 FR 63035, Nov. 26, 1997]

**§ 721.3560 Derivative of tetrachloroethylene.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The following chemical substance referred to by its premanufacture notice number and generic chemical name is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section: Derivative of tetrachloroethylene, P-82-684.

(2) The significant new uses are: (i) Manufacture or processing without requiring use of the following by persons employed by or under the control of the manufacturer or processor who are involved in, and in the immediate area of, any operation where dermal contact and/or inhalation of the substance may occur:

(A) A respirator, approved by the National Institute for Occupational Safety and Health (NIOSH) to provide protection against dusts having an air contamination level not less than 0.05 mg per cubic meter of air and fitted according to procedures established by the Occupational Safety and Health Administration and Mine Safety and Health Administration regulations and set

## Environmental Protection Agency

§ 721.3620

forth at 29 CFR 1910.134, and 30 CFR part 11, respectively, and

(B) Gloves which are determined to be impervious to the substance under the conditions of potential exposure (gloves must be determined to be impervious to the substance either by testing the gloves under the conditions of exposure, including the duration of exposure, or by evaluating the data and specifications supplied by the glove manufacturer or others, in the context of the conditions of exposure including the duration of exposure, associated chemical substances, chemical and mechanical stresses, and potential durations of exposures.

(ii) Manufacture or processing without requiring that any container of the substance or of a formulation containing the substance be:

(A) Packaged to prevent any leakage of the substance to the environment.

(B) Labeled on the package that the substance should be handled only while using NIOSH approved respirators and impervious gloves.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* In addition to the requirements of §721.17, manufacturers and processors of the substance identified in paragraph (a)(1) of this section must maintain the following records for five years from the date of their creation:

(i) The names of persons required to wear protective equipment in accordance with paragraph (a)(2) of this section.

(ii) The names and addresses of any person to whom the substance is sold or transferred and the dates of such sale or transfer.

(iii) Records of respirator fit tests for each person required to wear a respirator in accordance with paragraph (a)(2) of this section.

(iv) The method for determining that the gloves described in paragraph (a)(2) of this section are impervious to the substance, the date(s) of such determination, and the results of that determination.

(2) [Reserved]

(Secs. 5, 8, Pub. L. 94-469, 90 Stat. 2012 (15 U.S.C. 2604, 2607))

[49 FR 42932, Oct. 25, 1984. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29947, May 24, 1993]

### § 721.3565 Ethylenediamine, substituted, sodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as ethylenediamine, substituted, sodium salt (PMN P-97-328) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 3427, Jan. 22, 1998]

### § 721.3620 Fatty acid amine condensate, polycarboxylic acid salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a fatty acid amine condensate, polycarboxylic acid salts. (PMN P-92-445) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in §721.125 (a),

## § 721.3625

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46466, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.3625 Fatty acid amine salt (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as fatty acid amine salt (PMN P-88-1889) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (f), and (g)(3)(ii). The provisions of § 721.72(g) would require the following warning language on the label: Minimize releases to the environment.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90(a)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 33305, Aug. 15, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.3627 Branched synthetic fatty acid.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a branched synthetic fatty acid (PMN P-94-422) is subject to re-

## 40 CFR Ch. I (7-1-10 Edition)

porting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (g), and (l).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11043, Mar. 1, 1995]

### § 721.3629 Triethanolamine salts of fatty acids.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as triethanolamine salts of fatty acids (PMN Nos. P-92-156, P-92-157, and P-92-159) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of these substances is any manner or method of manufacture, import, or processing associated with any use of these substances without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for these substances, the employer becomes aware that these substances may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If these substances are not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substances are reintroduced into the workplace.

## Environmental Protection Agency

## § 721.3700

(B) The employer must ensure that persons who will receive, or who have received these substances from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32238, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

### § 721.3635 Octadecanoic acid, ester with 1,2-propanediol, phosphate, anhydride with silicic acid (H<sub>4</sub>SiO<sub>4</sub>).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as octadecanoic acid, ester with 1,2-propanediol, phosphate, anhydride with silicic acid (H<sub>4</sub>SiO<sub>4</sub>) (PMN P-96-1520; CAS No. 17771-31-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(i), and (g)(5). The following statement shall appear on each label as specified in § 721.72(b) and the MSDS as specified in § 721.72(c): Do not release into the environment in quantities that allow surface water concentrations to exceed 6 ppb.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (15 months).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 6).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44578, Aug. 20, 1998]

### § 721.3680 Ethylene oxide adduct of fatty acid ester with pentaerythritol.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as ethylene oxide adduct of fatty acid ester with pentaerythritol (PMN P-91-442) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46466, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.3700 Fatty acid, ester with styrenated phenol, ethylene oxide adduct.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as fatty acid, ester with

## § 721.3710

styrenated phenol, ethylene oxide adduct (P-90-364) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), and (g)(5).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 400 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44065, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

## § 721.3710 Polyether modified fatty acids (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a Polyether modified fatty acids (PMN P-99-0435) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81399, Dec. 26, 2000]

## 40 CFR Ch. I (7-1-10 Edition)

## § 721.3720 Fatty amide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a fatty amide (PMN P-91-87) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46466, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

## § 721.3740 Bisalkylated fatty alkyl amine oxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as bisalkylated fatty alkyl amine oxide (PMN P-90-643) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 80 ppb).

(ii) [Reserved].

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

## Environmental Protection Agency

## § 721.3780

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19238, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.3760 Fluorene-containing diaromatic amines.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as fluorene-containing diaromatic amines (PMN P-88-998 and P-88-999) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where n = 1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45082, Aug. 30, 1995]

### § 721.3764 Fluorene substituted aromatic amine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a fluorene substituted aromatic amine (PMN P-91-43) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c). However, these requirements do not apply after the PMN substance is adhered onto film or incorporated into prepreg form (resin impregnated substrate).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5) during manufacture.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[62 FR 42692, Aug. 8, 1997]

### § 721.3780 Substituted and disubstituted tetrafluoro alkenes (generic).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted and disubstituted tetrafluoro alkene (PMN P-84-105) is subject to reporting under this section for the significant new uses described in paragraph (a)(1)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 1%), and (c).

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (d), (e) (concentration set at 1%), (f), (g)(1)(i), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). In addition, the precautionary statements described under § 721.72(g) shall include: This substance may cause eye irritation.

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## § 721.3790

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (g) and (i).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(2) The chemical substance identified generically as disubstituted tetrafluoro alkene (PMN P-84-106) is subject to reporting under this section for the significant new uses described in paragraph (a)(2)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 1%), and (c).

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (d), (e) (concentration set at 1%), (f), (g)(1)(i), (g)(1)(iv), (g)(1)(v), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). In addition, the precautionary statements described under § 721.72(g) shall include: This substance may cause eye irritation.

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Specific requirements.* The provisions of Subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (g) and (i).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) The chemical substance identified generically as disubstituted tetrafluoro alkene (PMN P-84-107) is subject to reporting under this section for the significant new uses described in paragraph (a)(3)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 1%), and (c).

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (d), (e) (concentration set at 1%), (f), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). In addition, the

## 40 CFR Ch. I (7-1-10 Edition)

precautionary statements described under § 721.72(g) shall include: This substance may cause eye irritation.

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (g) and (i).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[67 FR 17649, Apr. 11, 2002]

## § 721.3790 Polyfluorocarboxylates.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as polyfluorocarboxylates (PMNs P-94-322 and P-94-323) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11043, Mar. 1, 1995]

## § 721.3800 Formaldehyde, condensed polyoxyethylene fatty acid, ester with styrenated phenol, ethylene oxide adduct.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as formaldehyde, condensed polyoxyethylene fatty acid, ester with

## Environmental Protection Agency

## § 721.3810

styrenated phenol, ethylene oxide adduct (PMN P-90-360) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in §721.72 (a), (b), (c), (d), (f), (g)(3)(ii), and (g)(5).

(ii) *Release to water.* Requirements as specified in §721.90 (a)(4), (b)(4) and (c)(4) (where N = 400 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in §721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[57 FR 44066, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.3805 Formaldehyde, reaction products with 1,3-benzenedimethanamine and bisphenol A.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as formaldehyde, reaction products with 1,3-benzenedimethanamine and bisphenol A (PMN P-00-0738; CAS No. 259871-68-6) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[68 FR 15084, Mar. 28, 2003]

### § 721.3807 Formaldehyde, polymer with phenol and 1,2,3-propanetriol, methylated.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as formaldehyde, polymer with phenol and 1,2,3-propanetriol, methylated (PMN P-99-0044; CAS No. 209810-57-1) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(4), (b)(4), and (c)(4) (N=3 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[68 FR 15084, Mar. 28, 2003]

### § 721.3810 Formaldehyde, polymers with substituted phenols (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Formaldehyde, polymers with substituted phenols (PMN P-99-0558) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.



**§ 721.3812**

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81400, Dec. 26, 2000]

**§ 721.3812 Substituted phenols and formaldehyde polymer, alkylated (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted phenols and formaldehyde polymer, alkylated (PMN P-00-0542) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (a resin for can and tube coatings).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15084, Mar. 28, 2003]

**§ 721.3815 Furan, 2-(ethoxymethyl)-tetrahydro-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance furan, 2-(ethoxymethyl) tetrahydro- (P-93-721) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If, as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human

**40 CFR Ch. I (7-1-10 Edition)**

health or the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive, or who have received this substance from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[60 FR 11043, Mar. 1, 1995]

**§ 721.3818 Furan, octafluorotetrahydro-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as furan, octafluorotetrahydro- (PMN P-99-0965; CAS No. 773-14-8) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## Environmental Protection Agency

## § 721.3830

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (a heat transfer agent).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15084, Mar. 28, 2003]

### § 721.3820 L-Glutamic acid, N-(1-oxododecyl)-, disodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as L-Glutamic acid, N-(1-oxododecyl)-, disodium salt (PMN P-99-0207; CAS No. 50622-20-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81400, Dec. 26, 2000]

### § 721.3821 L-Glutamic acid, N-(1-oxododecyl)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as L-Glutamic acid, N-(1-oxododecyl)- (PMN P-99-0208; CAS No. 3397-65-7) is subject to

reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81400, Dec. 26, 2000]

### § 721.3830 Formaldehyde, reaction products with an alkylated phenol and an aliphatic amine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Formaldehyde, reaction products with an alkylated phenol and an aliphatic amine (PMN P-99-0531) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81400, Dec. 26, 2000]

**§ 721.3835**

**40 CFR Ch. I (7–1–10 Edition)**

**§ 721.3835 Chloroformate (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a chloroformate (PMN P-01-1) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Releases to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70177, Dec. 17, 2003]

**§ 721.3840 Tetraglycidalamines (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as tetraglycidalamines (PMN P-86-500 and P-86-502) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(6)(i), (a)(5)(xi) and (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c). The respirator required under § 721.63 (a)(5)(vi) is applicable only when the PMN substance is in the form of a dust. The respirator required under § 721.63 (a)(5)(xi) is applicable only when the PMN substance is in the form of a mist.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (o).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2) and (c)(1), (c)(2).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(vi), (b)(2)(vi) and (c)(2)(vi).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 26101, June 26, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.3845 Alkyl substituted aromatic glycidyl ether (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkyl substituted aromatic glycidyl ether (PMN P-97-661) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(v), (g) (4) (iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), and (k) are

## Environmental Protection Agency

## § 721.3880

applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 369, Jan. 5, 2000]

### § 721.3848 Glycine, *N*-(carboxymethyl)-*N*-dodecyl-, monosodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as glycine, *N*-(carboxymethyl)-*N*-dodecyl-, monosodium salt (PMN P-00-469; CAS No. 141321-68-8) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), (c)(4) (N=30 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15084, Mar. 28, 2003]

### § 721.3860 Glycol monobenzoate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as generically as glycol monobenzoate (P-90-1357) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent

order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 40211, Aug. 13, 1991, as amended at 56 FR 46729, Sept. 16, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.3880 Polyalkylene glycol substituted acetate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polyalkylene glycol substituted acetate (PMN P-91-1269) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

## § 721.3900

## 40 CFR Ch. I (7–1–10 Edition)

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive this substance from the employer, or who have received this substance from the employer within 5 years from the date the employer becomes aware of this new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44066, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.3900 Alkyl polyethylene glycol phosphate, potassium salt.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkyl polyethylene glycol phosphate, potassium salt (P-90-481), is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows.

(A) If, as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## Environmental Protection Agency

## § 721.4040

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (c), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 15792, Apr. 17, 1991; 56 FR 29903, July 1, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.4000 Polyoxy alkylene glycol amine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polyoxy alkylene glycol amine (PMN P-91-1372) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified at § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified at § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 31968, July 20, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.4040 Glycols, polyethylene-, 3-sulfo-2-hydroxypropyl-*p*-(1,1,3,3-tetramethylbutyl)phenyl ether, sodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as glycols, polyethylene-, 3-sulfo-2-hydroxypropyl-*p*-(1,1,3,3-tetramethylbutyl)phenyl ether, sodium salt (P-90-1565) is subject to reporting under this

section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health or the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described at § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (volume set at 1,115,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 40212, Aug. 13, 1991, as amended at 56 FR 46729, Sept. 16, 1991. Redesignated at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.4060**

**§ 721.4060 Alkylene glycol terephthalate and substituted benzoate esters (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylene glycol terephthalate and substituted benzoate esters (PMN P-89-596) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q)

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c) and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26101, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.4080 MNNG (N-methyl-N'-nitro-N-nitrosoguanidine).**

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance MNNG (N-methyl-N'-nitro-N-nitrosoguanidine) (CAS No. 70-25-7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and proc-

**40 CFR Ch. I (7-1-10 Edition)**

essors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

**§ 721.4085 Guanidine, pentaethyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as guanidine, pentaethyl- (PMN P-94-1018; CAS No. 13439-89-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), and (a)(3).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (e) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3427, Jan. 22, 1998]

**§ 721.4090 Ethanaminium, N-[bis(diethylamino)-methylene]-N-ethyl-, bromide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as ethanaminium, N-[bis(diethylamino)-methylene]-N-ethyl-, bromide (PMN P-94-1019; CAS No. 89610-32-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## Environmental Protection Agency

§ 721.4098

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3427, Jan. 22, 1998]

### § 721.4095 Quaternary ammonium alkyltherpropyl trialkylamine halides.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as quaternary ammonium alkyltherpropyl trialkylamine halides (PMNs P-96-1280/81/1504/1505/1506/1507/1508) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3428, Jan. 22, 1998]

### § 721.4096 Substituted anilino halobenzamide (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted anilino halobenzamide (PMN P-99-1288) is subject to reporting under this section for the significant new use described in paragraph (a)(1) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70177, Dec. 17, 2003]

### § 721.4097 7-Oxabicyclo[4.1.0]heptane-3-carboxylic acid, methyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 7-oxabicyclo[4.1.0]heptane-3-carboxylic acid, methyl ester (PMN P-98-101) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44578, Aug. 20, 1998]

### § 721.4098 Substituted heteroaromatic-2[[4-(dimethylamino)phenyl]azo]-3-methyl-, salts (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as substituted heteroaromatic-2[[4-(dimethylamino)phenyl]azo]-3-methyl-, salts (PMNs P-97-582 and P-97-583) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to



## § 721.4100

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44578, Aug. 20, 1998]

## § 721.4100 Tris(disubstituted alkyl heterocycle).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as tris(disubstituted alkyl) heterocycle (P-90-142) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iv), (a)(6)(i), (b) (concentration set at 0.1 percent) and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(2)(iv), (g)(5). The hazard communication requirements do not apply when the chemical substance is present in a plastic, an elastomer, a rubber matrix, or in a solution.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q). Any amount of the PMN substance imported in a plastic, an elastomer, a rubber matrix, or in a solution, such that inhalation is precluded, shall not be included in the production limit calculations.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

## 40 CFR Ch. I (7-1-10 Edition)

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 40212, Aug. 13, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.4105 Bicyclo[2.2.1]hept-2-ene, 5-butyl-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as Bicyclo[2.2.1]hept-2-ene, 5-butyl- (PMN P-98-315; CAS No. 22094-81-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 369, Jan. 5, 2000]

## § 721.4106 Bicyclo[2.2.1]hept-2-ene, 5-hexyl-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as Bicyclo[2.2.1]hept-2-ene, 5-hexyl- (PMN P-98-316; CAS No. 22094-83-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## Environmental Protection Agency

§ 721.4128

(b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 370, Jan. 5, 2000]

### § 721.4107 Bicyclo[2.2.1]hept-2-ene, 5-octyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as Bicyclo[2.2.1]hept-2-ene, 5-octyl- (PMN P-98-317; CAS No. 22094-84-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 370, Jan. 5, 2000]

### § 721.4108 Bicyclo[2.2.1]hept-2-ene, 5-decyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as Bicyclo[2.2.1]hept-2-ene, 5-decyl- (PMN P-98-318; CAS No. 22094-85-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

(b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 370, Jan. 5, 2000]

### § 721.4110 Allyloxysubstituted heterocycle.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an allyloxysubstituted heterocycle (PMN P-93-1471) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 70 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11043, Mar. 1, 1995]

### § 721.4128 Dimethyl-3-substituted heteromonocycle.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dimethyl-3-substituted heteromonocycle (PMN No. P-91-1322) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(6)(ii), (a)(6)(iii), (a)(6)(v), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(iv),

## § 721.4133

## 40 CFR Ch. I (7–1–10 Edition)

(g)(2)(i), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (d) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32238, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

## § 721.4133 Dimethyl-3-substituted heteromonocyclic amine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dimethyl-3-substituted heteromonocycle (PMN No. P-91-1323) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(2)(iv), (a)(3), (a)(6)(ii), (a)(6)(iii), (a)(6)(v), (b) (concentration set at 1.0 percent).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (d) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32238, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

## § 721.4136 Alkyl heteropolycyclic-aniline (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkyl heteropolycyclic-aniline (PMN P-00-0067) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15084, Mar. 28, 2003]

## § 721.4140 Hexachloronorbornadiene.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 1,2,3,4,7,7-hexachloronorbornadiene, CAS Number 3389-71-7, is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Use other than as an intermediate in the production of isodrin or endrin.

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## Environmental Protection Agency

## § 721.4160

this section except as modified by this paragraph.

(1) *Definitions.* In addition to the definitions in § 721.3, the following definitions apply:

(i) “Endrin” means the pesticide 2,7:3,6-Dimethanonaphth[2,3-b]oxirene, 3,4,5,6,9,9-hexachloro-1a,2,2a,3,6,6a,7,7a-octahydro-, (1a alpha, 2beta, 2abeta, 3alpha, 6alpha, 6abeta, 7beta, 7aalpha)-, CAS Number 72-20-8.

(ii) “Isodrin” means the pesticide 1,4:5,8-Dimethano-naphthalene, 1,2,3,4,10,10-hexachloro-1,4,4a,5,8,8a-hexahydro-, (1alpha, 4alpha, 4abeta, 5beta, 8beta, 8abeta)-, CAS Number 465-73-6.

(2) [Reserved]

[50 FR 47538, Nov. 19, 1985. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.4155 Hexachloropropene.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance hexachloropropene (CAS No. 1888-71-7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

### § 721.4158 Hexadecanoic acid, ethenyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hexadecanoic acid, ethenyl ester (PMN P-97-302; CAS No. 693-38-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i) and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3428, Jan. 22, 1998]

### § 721.4160 Hexafluoropropylene oxide.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance hexafluoropropylene oxide (HFPO), CAS Number 428-59-1 [Listed in TSCA Inventory as oxirane, trifluoro(trifluoromethyl)-] is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is any use other than as an intermediate in the manufacture of fluorinated substances in an enclosed process.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Definitions.* In addition to the definitions in § 721.3, the following definitions apply to this section:

(i) *Enclosed process* means a process that is designed and operated so that there is no intentional release of any substance present in the process. A process with fugitive, inadvertent, or emergency relief releases remains an enclosed process so long as measures are taken to prevent worker exposure to and environmental contamination from the releases.

(ii) [Reserved]

(2) [Reserved]

[52 FR 41300, Oct. 27, 1987. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.4180 Hexamethylphosphoramide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance hexamethylphosphoramide, CAS Number 680-31-9, is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new use is: Any use.

(b) *Special provisions.* The provisions of subpart A of the part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[51 FR 9453, Mar. 19, 1986. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.4215 Hexanedioic acid, diethenyl ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hexanedioic acid, diethenyl ester (PMN P-90-1564) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply once the substance has been incorporated into a polymer matrix with the level of residual monomer below 0.1 percent.

(2) The significant new uses are: (i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (There must be no permeation of the PMN substance greater than 0.05  $\mu\text{g}/\text{min} \cdot \text{cm}^2$  after 8 hours of testing in accordance with the most current version of the American Society for Testing and Materials (ASTM) F739 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases." For conditions of exposure which are intermittent, gloves may be tested in accordance with the most current version of ASTM F1383 "Standard Test Method

for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases Under Conditions of Intermittent Contact," provided the contact time in testing is greater than or equal to the expected duration of dermal contact, and the purge time used in testing is less than or equal to the expected duration of noncontact during the intermittent cycle of dermal exposure in the workplace. If ASTM F1383 is used for testing, manufacturers, importers, and processors must submit to the Agency a description of worker activities involving the PMN substance which includes daily frequencies and durations of potential worker exposures. The results of all glove permeation testing must be reported in accordance with the most current version of ASTM F1194 "Guide for Documenting the Results of Chemical Permeation Testing of Protective Clothing Materials." Manufacturers, importers, and processors must submit all test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves. The following gloves have been tested in accordance with the ASTM F739 method and found by EPA to satisfy the requirements for continuous use: North/B-161-R/Butyl rubber gloves (These gloves are acceptable for the solid form of the substance only.), 0.04 cm thick; and Ansell Edmont/4H/PE/EVOH/PE Laminate gloves, 0.006 cm thick. (Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift.), (a)(2)(ii) (With the exception of laboratory activities, full body chemical protective clothing is required for any worker activity in which the substance is reasonably likely to contact the worker in the following state(s): Open liquid pool or solid of greater than 5 kg; liquid spray or splash; mist; aerosol dust; or any worker activity which have potential for contact with the PMN chemical for more than 10 min/h. At a minimum, a chemical protective apron is required for any worker activity with potential for contact with the PMN chemical which is not covered by this paragraph), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii) (if cartridge service life testing is not available), (a)(5)(xii) or

## Environmental Protection Agency

## § 721.4250

(a)(5)(xiii) (if data on cartridge service life testing has been reviewed and approved in writing by EPA), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), and (a)(6)(v). As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in §721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (h)(1)(vi) (The following additional statements shall appear on each label required by this paragraph: The health effects of this material have not been fully determined but are currently being tested. EPA is concerned however, that this material may have serious chronic health and environmental effects. When using this material, use eye and skin protection, which includes gloves which have been determined to be impervious to this substance. Use respiratory protection, unless workplace airborne concentrations are maintained at or below an 8-h time weighted average (TWA) of 1 ppm, when there is a likelihood of exposure in the work area from dust, mist, smoke or vapors.), (h)(2)(ii)(F), (h)(2)(ii)(G), (h)(2)(ii)(I), (h)(2)(iii)(A), (h)(2)(iii)(B), (h)(2)(iii)(C), (h)(2)(iii)(E), (h)(2)(iv)(A), (h)(2)(iv)(B). The following additional statements shall appear on each MSDS required by this paragraph: This substance may cause moderate skin irritation. This substance may cause neurotoxicity. When using this substance, use respiratory protection, unless workplace airborne concentrations are maintained at or below an 8-h TWA of 1 ppm.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(q).

(iv) *Release to water.* Requirements as specified in §721.90 (a)(4), (b)(4), and (c)(4) (where N = 80 ppb). When calculating the surface water concentrations according to the instructions in §721.91(a)(4), the statement that the amount of the substance that will be released will be calculated before the substance enters control technology

does not apply. Instead, if the waste stream containing the substance will be treated before release, then the amount of the substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 75 percent removal efficiency may be attributed to such treatment. In addition, when the substance is released in combination with the substances hexanoic acid, 2-ethyl-, ethenyl ester, neononanoic acid, ethenyl-, and propanoic acid, 2,2-dimethyl-, ethenyl ester, the quotient from the formula referenced in this section shall not exceed the average of the quotient applicable to the other substances weighted by the proportion of each substance present in the total daily amount released.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance. Manufacturers, importers, and processors of the substance must document that the PMN substance has been incorporated into a polymer matrix with the level of residual monomer below 0.1 percent if this section does not apply as described in paragraph (a)(1) of this section.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of §721.1725(b)(1) apply to this section.

[58 FR 51703, Oct. 4, 1993]

### § 721.4250 Hexanoic acid, 2-ethyl-, ethenyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hexanoic acid, 2-ethyl-, ethenyl ester (PMN P-91-826) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply once the substance has been incorporated into a

polymer matrix with the level of residual monomer below 0.1 percent.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i) (There must be no permeation of the substance greater than 0.02 µg/min · cm<sup>2</sup> after 8 hours of testing in accordance with the most current version of the American Society for Testing and Materials (ASTM) F739 “Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases.” For conditions of exposure which are intermittent, gloves may be tested in accordance with the most current version of ASTM F1383 “Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases Under Conditions of Intermittent Contact,” provided the contact time in testing is greater than or equal to the expected duration of dermal contact, and the purge time used in testing is less than or equal to the expected duration of noncontact during the intermittent cycle of dermal exposure in the workplace. If ASTM F1383 is used for testing, manufacturers, importers, and processors must submit to the Agency a description of worker activities involving the substance which includes daily frequencies and durations of potential worker exposures. The results of all glove permeation testing must be reported in accordance with the most current version of ASTM F1194 “Guide for Documenting the Results of Chemical Permeation Testing of Protective Clothing Materials.” Manufacturers, importers, and processors must submit all test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves. The following gloves have been tested in accordance with the ASTM F739 method and found by EPA to satisfy the requirements for continuous use: North/F101/Vitron gloves, 0.03 cm thick; and Ansell/Edmont/4H/PE/EVOH/PE Laminate gloves, 0.006 cm thick. (Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift.), (a)(2)(ii) (With the exception of laboratory activities, full body chemical protective clothing is required for

any worker activity in which the substance is reasonably likely to contact the worker in the following state(s): Open liquid pool or solid of greater than 5 kg; liquid spray or splash; mist; aerosol dust; or any worker activity which have potential for contact with the PMN chemical for more than 10 min/h. At a minimum, a chemical protective apron is required for any worker activity with potential for contact with the PMN chemical which is not covered by this paragraph), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii) (if cartridge service life testing is not available), (a)(5)(xii) or (a)(5)(xiii) (if data on cartridge service life testing has been reviewed and approved in writing by EPA), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), and (a)(6)(v). As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (h)(1)(vi) (The following additional statements shall appear on each label required by this paragraph: The health effects of this material have not been fully determined but are currently being tested. EPA is concerned however, that this material may have serious chronic health and environmental effects. When using this material, use eye and skin protection, which includes gloves which have been determined to be impervious to this substance. Use respiratory protection, unless workplace airborne concentrations are maintained at or below an 8-h time weighted average (TWA) of 1 ppm, when there is a likelihood of exposure in the work area from dust, mist, smoke or vapors.), (h)(2)(ii)(F), (h)(2)(ii)(G), (h)(2)(ii)(I), (h)(2)(iii)(A), (h)(2)(iii)(B), (h)(2)(iii)(C), (h)(2)(iii)(E), (h)(2)(iv)(A), (h)(2)(iv)(B). The following additional statements shall appear on each MSDS required by this paragraph: This substance may cause moderate skin irritation. This substance may cause neurotoxicity. When using this substance, use respiratory protection,

## Environmental Protection Agency

§ 721.4257

unless workplace airborne concentrations are maintained at or below an 8-h TWA of 1 ppm.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 7 ppb). When calculating the surface water concentrations according to the instructions in § 721.91(a)(4), the statement that the amount of the substance that will be released will be calculated before the substance enters control technology does not apply. Instead, if the waste stream containing the substance will be treated before release, then the amount of the substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 75 percent removal efficiency may be attributed to such treatment. In addition, when the substance is released in combination with the substances hexanedioic acid, diethenyl ester, neononanoic acid, ethenyl ester, and propanoic acid, 2,2-dimethyl-, ethenyl ester, the quotient from the formula referenced in this section shall not exceed the average of the quotient applicable to the other substances weighted by the proportion of each substance present in the total daily amount released.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance. Manufacturers, importers, and processors of the substance must document that the substance has been incorporated into a polymer matrix with the level of residual monomer below 0.1 percent if this section does not apply as described in paragraph (a)(1) of this section.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51704, Oct. 4, 1993, as amended at 58 FR 68311, Dec. 27, 1993]

### § 721.4255 1,4,7,10,13,16-Hexaoxacyclooctadecane, 2-[(2-propenyloxy)methyl]-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 1,4,7,10,13,16-hexaoxacyclooctadecane, 2-[(2-propenyloxy)methyl]- (PMN P-93-1208, CAS no. 84812-04-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27484, May 27, 1994]

### § 721.4257 Hydrazine, (2-fluorophenyl).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hydrazine, (2-fluorophenyl) (PMN P-95-2101; CAS No. 2368-80-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a)



**§ 721.4258**

and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3428, Jan. 22, 1998]

**§ 721.4258 Substituted naphthalene hydrazide (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted naphthalene hydrazide (PMN P-01-69) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirement as specified § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70177, Dec. 17, 2003]

**§ 721.4259 Aliphatic polyisocyanate homopolymer.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an aliphatic polyisocyanate homopolymer (PMN P-96-1239) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manu-

**40 CFR Ch. I (7-1-10 Edition)**

facturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3428, Jan. 22, 1998]

**§ 721.4260 Hydrazine, [4-(1-methylbutoxy)phenyl]-, monohydrochloride.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hydrazine, [4-(1-methylbutoxy)phenyl]-, monohydrochloride (PMN P-90-558; CAS number 124993-63-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(iii), and (g)(5). In addition, the following human health hazard statement shall appear on each label and MSDS required by this section: This substance may cause eye irritation.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (p) (production limit set at 15,500 kg).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i) and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Modification or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44066, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

## Environmental Protection Agency

§ 721.4280

### § 721.4265 Hydrazinecarboxamide, *N*-(3,5-difluorophenyl-).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hydrazinecarboxamide, *N*-(3,5-difluorophenyl-) (PMN P-97-649; CAS No. 167412-23-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) (applies only when the substance is in a solution), (a)(4), (a)(5)(i), (a)(6)(i), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is set at 0.4 mg/m<sup>3</sup>.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(iii), (g)(1)(iv), (g)(1)(v), (g)(1)(vii), (g)(1)(ix), (g)(2)(i) (applies only when the substance is in a solvent), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v) (applies only when the substance is in a solvent), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 370, Jan. 5, 2000]

### § 721.4270 Nitrophenoxylalkanoic acid substituted thiazino hydrazide (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

chemical substance nitrophenoxylalkanoic acid substituted thiazino hydrazide (PMN P-88-270) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv) through (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b), (c), (d), (e) (concentration set at 1.0 percent), (f) and (g)(1)(iv) (also acute toxicity), (g)(2)(i) through (g)(2)(v), (g)(4)(i) and (g)(5). The provision of § 721.72(d) requiring that employees to be provided with information on the location and availability of a written hazard communication program does not apply when the written program is not required under § 721.72(a).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g) (industrial intermediates only).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1) and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 32415, Aug. 9, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.4280 Substituted hydrazine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted hydrazine (PMN P-90-594) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

§ 721.4300

40 CFR Ch. I (7-1-10 Edition)

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2), (g)(3), (g)(4)(i), (g)(4)(iii), and (g)(5). In addition, the human health hazard statement shall include mutagenicity.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), and (c)(1).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 40213, Aug. 13, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.4300 Hydrazinecarboxamide, N,N'-1,6-hexanediyldis [2,2-dimethyl-]**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hydrazinecarboxamide, N,N'-1,6-hexanediyldis [2,2-dimethyl- (P-87-1192)] is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(3), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (k) (any application which, if there are releases to water or discharges to land, will not result in releases to facilities with a National Pollutant Discharge Elimination System permit), and (l).

(iv) *Release to water.* Requirements as specified in § 721.90 (b)(4), (c)(4), (where N = 30).

(A) Selling or transferring the substance to any person for use where the substance is released to surface waters without notifying in writing the parties listed in subparagraph (B) of the identities of all such persons. Such notification shall be sent within 15 days of the date of the first sale or transfer and shall contain the following information:

(1) The name and address (including shipment destination address, if different) of the person to whom the substance is sold or transferred.

(2) The date on which sale or transfer commenced.

(3) The chemical identity of the substance.

(4) The name of the stream or river into which the specific buyer or transferee is expected to discharge the substance.

(5) Notification that the substance is subject to a Significant New Use Rule issued under section 5 of the Toxic Substances Control Act.

(6) A summary of the water release restrictions contained in paragraph (a)(iv) of this section.

(7) A request that the party notify the following office of any information which indicates that the in-stream concentration of the PMN substance specified in paragraph (a)(iv) of this section has been exceeded: Chief, New Chemicals Branch, Chemical Control Division (7405), Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, Room E-447, 1200 Pennsylvania Ave., NW., Washington, DC 20460.

(B) The parties to be notified are as follows.

(1) The Director, Water Management Division (or, in the case of Regions 5 and 10, Water Division) at the headquarters of the EPA region in which

## Environmental Protection Agency

## § 721.4340

the specific buyer or transferee is located.

(2) The Agency, Department, or Office of the State or U.S. Territory with jurisdiction over point source water discharges in the State or Territory in which the specific buyer or transferee is located (EPA is available for consultation regarding the identity and address of the appropriate Agency, etc.)

(3) The Publicly Owned Treatment Works (POTW) authority, if any, expected to receive the discharge of the PMN substance from the specific buyer or transferee.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), (i), and records documenting notification to parties identified in § 721.90.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 15792, Apr. 17, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993; 60 FR 34464, July 3, 1995]

### § 721.4320 Hydrazinecarboxamide, *N,N'*-(methylenedi-4,1-phenylene)bis[2,2-dimethyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance hydrazinecarboxamide, *N,N'*-(methylenedi-4,1-phenylene)bis[2,2-dimethyl- (PMN P-88-522) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii) through (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72

(b)(2), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv) (and blood effects), (g)(1)(vii), (g)(2)(iv), (g)(2)(v), (g)(4)(iii), and (g)(5). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (l).

(iv) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e), (f), (g), (h), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 46773, Nov. 6, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.4340 Substituted thiazino hydrazine salt (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance substituted thiazino hydrazine salt (PMN P-88-63) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii) through (a)(5)(vii), and (a)(6)(i), (b) [concentration set at 0.1 percent], and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) [concentration set at 0.1 percent], (f), and (g)(1)(iv) and

## § 721.4360

(g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (1).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (a)(2) and (b)(1) and (b)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 26112, June 26, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.4360 Certain hydrogen containing chlorofluorocarbons.

(a) Chemical substances and significant new uses subject to reporting.

(1) The chemical substances ethane, 2-chloro-1,1,1-trifluoro- (CAS Number 75-88-7) and ethane, 1,2-dichloro-1,1-difluoro- (CAS Number 1649-08-7) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Use other than as an intermediate.

(b) [Reserved]

[55 FR 35632, Aug. 31, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.4365 Substituted ethoxylated hydrocarbon (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Substituted ethoxylated hydrocarbon (PMN P-99-0313) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(4), (b)(4), and (c)(4) (N=1 ppb).

(ii) [Reserved]

## 40 CFR Ch. I (7-1-10 Edition)

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81400, Dec. 26, 2000]

## § 721.4380 Modified hydrocarbon resin.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a modified hydrocarbon resin (P-91-1418) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive this substance from the employer, or who have received the substance from the employer within 5 years from the date the employer becomes aware of the information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section

## Environmental Protection Agency

## § 721.4420

within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44067, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.4385 Hydrofluoric acid, reaction products with heptane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a hydrofluoric acid, reaction products with heptane (PMN P-98-1036; CAS No. 207409-71-0) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 370, Jan. 5, 2000]

### § 721.4390 Trisubstituted hydroquinone diester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

chemical substance identified generically as trisubstituted hydroquinone diester (PMN No. P-92-329) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4) (where N = 30 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (j), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[58 FR 32239, June 8, 1993]

### § 721.4420 Substituted hydroxylamine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted hydroxylamine (PMN P-84-492) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), and (g)(2)(i) through (g)(2)(iii). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a), and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

**§ 721.4460**

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4) (chemically treated liquid wastes must contain no more than 10 ppm of the substance prior to discharge), (b)(4) (chemically treated liquid wastes must contain no more than 10 ppm of the substance prior to discharge), and (c)(4) (chemically treated liquid wastes must contain no more than 10 ppm of the substance prior to discharge).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e), (f), and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 46773, Nov. 6, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.4460 Amidinothiopropionic acid hydrochloride.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as amidinothiopropionic acid hydrochloride (PMN P-91-102) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

**40 CFR Ch. I (7-1-10 Edition)**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46466, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

**§ 721.4461 Hydrofluoric acid, reaction products with octane (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a hydrofluoric acid, reaction products with octane (PMN P-99-0052) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81400, Dec. 26, 2000]

**§ 721.4462 Hydrochlorofluorocarbon.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a hydrochlorofluorocarbon (PMN P-95-1317) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## Environmental Protection Agency

## § 721.4467

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3428, Jan. 22, 1998]

### § 721.4463 Hydrochlorofluorocarbon.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a hydrochlorofluorocarbon (PMN P-94-1453) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45082, Aug. 30, 1995]

### § 721.4464 Mixture of hydrofluoro alkanes and hydrofluoro alkene.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as a mixture of hydrofluoro alkanes and hydrofluoro alkene (PMNs P-96-945/946/947/948) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements specified as in § 721.125 (a),

(b), (c), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3428, Jan. 22, 1998]

### § 721.4465 Hydrofluoroalkane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a hydrofluoroalkane (PMN P-96-1288) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3428, Jan. 22, 1998]

### § 721.4467 Quaternary ammonium hydroxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a quaternary ammonium hydroxide (PMN P-95-1806) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),



**§ 721.4468**

**40 CFR Ch. I (7–1–10 Edition)**

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3429, Jan. 22, 1998]

**§ 721.4468 1H-Imidazole, 2-ethyl-4,5-dihydro-4-methyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1H-imidazole, 2-ethyl-4,5-dihydro-4-methyl- (PMN P-97-217; CAS No. 931-35-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 40).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3429, Jan. 22, 1998]

**§ 721.4469 Imidazolethione.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an imidazolethione (PMNs P-91-1131 and P-90-564) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. Formulations or mixtures containing the PMN substance in concentrations at or below 10 percent by weight or volume are exempt from the provisions of this rule.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(ix), (g)(2)(i), (g)(2)(v), and (g)(5). The label and MSDS as required by this paragraph shall also include the following statements: This substance may cause thyroid cancer. This substance may cause thyroid effects.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), and (h) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3429, Jan. 22, 1998]

**§ 721.4470 2,4-Imidazolidinedione, bromochloro-5,5-dimethyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 2,4-imidazolidinedione, bromochloro-5,5-dimethyl- (PMN P-94-34) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(3), (w)(3), and (x)(3).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 10 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11043, Mar. 1, 1995]

**§ 721.4472 Phenyl, alkyl, hydroxyalkyl substituted imidazole (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as phenyl, alkyl, hydroxyalkyl substituted imidazole (PMNs P-98-843 and P-86-65) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), and (g)(1)(iii).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(r) (56,000 kg) (acute oral study (OPPTS 870.1100 test guideline) followed by a (90-day subchronic inhalation study in rats (40 CFR 799.9346). A person may not manufacture or import the substance beyond the aggregate production volume limit, unless that person conducts this study on the substance and submits all final reports and underlying data in accordance with the procedures and criteria specified in paragraphs (a)(2)(iii)(A), (a)(2)(iii)(B), (a)(2)(iii)(C), and (a)(2)(iii)(D) of this section.

(A) Each study required to be performed pursuant to this section must be scientifically valid. *Scientifically valid* means that the study was conducted according to:

(1) The test guidelines specified in paragraph (a)(2)(iii) of this section.

(2) An EPA-approved protocol.

(3) TSCA Good Laboratory Practice Standards at 40 CFR part 792.

(4) Using methodologies generally accepted at the time the study is initiated.

(5) Any deviation from these requirements must be approved in writing by EPA.

(B) Before starting to conduct any of the studies in paragraph (a)(2)(iii) of this section, the person must obtain approval of test protocols from EPA by submitting written protocols. EPA will respond to the person within 4 weeks of

receiving the written protocols. Published test guidelines specified in paragraph (a)(2)(iii) of this section (e.g., 40 CFR part 797 or part 798) provide general guidance for development of test protocols, but are not themselves acceptable protocols.

(C) The person shall:

(1) Conduct each study in good faith with due care.

(2) Promptly furnish to EPA the results of any interim phase of each study.

(3) Submit, in triplicate (with an additional sanitized copy, if confidential business information is involved), the final report of each study and all underlying data ("the report and data") to EPA no later than 14 weeks prior to exceeding the applicable production volume limit. The final report shall contain the contents specified in 40 CFR 792.185.

(D)(1) Except as described in paragraph (a)(2)(iii)(D)(2), if, within 6 weeks of EPA's receipt of a test report and data, the person receives written notice that EPA finds that the data generated by a study are scientifically invalid, the person is prohibited from further manufacture and import of the PMN substance beyond the applicable production volume limit.

(2) The person may continue to manufacture and import the PMN substance beyond the applicable production limit only if so notified, in writing, by EPA in response to the person's compliance with either of the following paragraphs (a)(2)(iii)(D)(2)(i) or (a)(2)(iii)(D)(2)(ii) of this section.

(i) The person may reconduct the study. If there is sufficient time to reconduct the study and submit the report and data to EPA at least 14 weeks before exceeding the production limit as required by paragraph (a)(2)(iii)(C)(3) of this section, the person shall comply with paragraph (a)(2)(iii)(C)(3) of this section. If there is insufficient time for the person to comply with paragraph (a)(2)(iii)(C)(3) of this section, the person may exceed the production limit and shall submit the report and data in triplicate to EPA within a reasonable period of time, all as specified by EPA in the notice described in paragraph (a)(2)(iii)(D)(1) of this section. EPA will

## § 721.4473

respond to the person in writing, within 6 weeks of receiving the person's report and data.

(ii) The person may, within 4 weeks of receiving from EPA the notice described in paragraph (a)(2)(iii)(D)(I) of this section, submit to EPA a written report refuting EPA's finding. EPA will respond to the person in writing, within 4 weeks of receiving the person's report.

(E) The person is not required to conduct a study specified in paragraph (a)(2)(iii) of this section if notified in writing by EPA that it is unnecessary to conduct that study.

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 370, Jan. 5, 2000]

## § 721.4473 Dialkylamidoimidazoline.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as dialkylamidoimidazoline (PMN P-94-1864) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

## 40 CFR Ch. I (7-1-10 Edition)

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45082, Aug. 30, 1995]

## § 721.4476 Substituted imines.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as substituted imines (PMNs P-95-1557/1558) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3429, Jan. 22, 1998]

## § 721.4480 2-Imino-1,3-thiazin-4-one-5,6-dihydrimonohydrochloride.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-imino-1,3-thiazin-4-one-5,6-dihydrimonohydrochloride (PMN P-91-101) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a),

## Environmental Protection Agency

§ 721.4490

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46466, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.4484 Halogenated indane (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a halogenated indane (PMN P-94-351) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply to P-94-351 after incorporation into a plastic, resin matrix, or pelletized so humans are not reasonably likely to be exposed.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements during manufacture as specified in § 721.63 (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements during manufacture as specified in § 721.72 (a), (b), (c), (d), (e), (f), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[61 FR 63737, Dec. 2, 1996, as amended at 62 FR 27694, May 21, 1997]

### § 721.4486 Propanoic acid, 2-methyl-, (1R,2R,4R)-1,7,7-trimethylbicyclo[2.2.1]hept-2-yl ester, rel-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified as propanoic acid, 2-methyl-, (1R,2R,4R)-1,7,7-trimethylbicyclo[2.2.1]hept-2-yl ester, rel- (PMNs P-98-0497 and P-98-0509; CAS No. 85586-67-0) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (15,000 kg/yr).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15084, Mar. 28, 2003]

### § 721.4490 Capped aliphatic isocyanate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a capped aliphatic isocyanate (PMN P-86-1146) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(xi), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (d), (e) (concentration set at 0.1 percent), (f), (h)(1)(ii)(G), (h)(1)(iii)(A), (h)(1)(iii)(B), (h)(1)(iii)(D), and (h)(1)(iii)(E).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

## § 721.4494

(iv) *Disposal*. Requirements as specified in § 721.90 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2).

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b) through (g), (i), and (j) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[58 FR 51685, Oct. 4, 1993]

## § 721.4494 Polycyclic isocyanate.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified as a polycyclic isocyanate (PMN P-94-437) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace*. Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 1.0%), and (c).

(ii) *Hazard communication program*. Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5). In addition the following human health and environmental hazard and precautionary statements shall appear on each label as specified in paragraph (b) of this section and the MSDS as specified in paragraph (c) of this section: This substance may cause skin sensitization. This substance may cause pulmonary sensitization.

(iii) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80(q).

(iv) *Release to water*. Requirements as specified in § 721.90 (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a) through (i) and (k) are applicable to

## 40 CFR Ch. I (7-1-10 Edition)

manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section*. The provisions of § 721.1725(b)(1) apply to this section.

[61 FR 63737, Dec. 2, 1996]

## § 721.4497 Aliphatic polyisocyanates (generic name).

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substances identified generically as aliphatic polyisocyanates (P-91-1210 and P-92-714) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. Non-spray uses are exempt from the provisions of this rule.

(2) The significant new uses are:

(i) *Protection in the workplace*. Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(viii), (a)(5)(ix), (a)(5)(x), (a)(5)(xi), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program*. Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5). Manufacturers, importers, and processors who implement the product stewardship provisions of the section 5(e) consent order for these substances are exempt from the requirements of §§ 721.63 and 721.72.

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a) through (h) are applicable to manufacturers, importers, and processors of this substance. Manufacturers, importers, and processors who implement the product stewardship provisions or keep records as required by the section 5(e) consent order for these substances are exempt from the requirements of § 721.125.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

## Environmental Protection Agency

## § 721.4550

(3) *Applicability of § 721.5.* The provisions of § 721.5 do not apply to manufacturers, importers, and processors, implementing the product stewardship provisions in the section 5(e) consent order for these substances.

[61 FR 63737, Dec. 2, 1996]

### § 721.4500 Isopropylamine distillation residues and ethylamine distillation residues.

(a) *Chemical substances and significant new use subject to reporting.* (1) The following chemical substances referred to by their Chemical Abstracts Service (CAS) register numbers and chemical names are subject to reporting under this section for the significant new use identified in paragraph (a)(2) of this section: CAS No. 79771-08-7, isopropylamine distillation residues, and CAS No. 79771-09-98, ethylamine distillation residues.

(2) The significant new use is use in metalworking fluids.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Notice Requirements and Procedures.* Section 721.10 applies to this section, except persons submitting a notice must complete only Parts I and III of the notice form.

(2) [Reserved]

(Sec. 5, Pub. L. 94-469, 90 Stat. 2012 (15 U.S.C. 2604))

[49 FR 46378, Nov. 26, 1984. Redesignated at 51 FR 23539, June 30, 1986, and 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.4520 Isopropylidene, bis(1,1-dimethylpropyl) derivative.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as isopropylidene, bis(1,1-dimethylpropyl) derivative (PMN P-85-648) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3) (applies to gloves only), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(2)(i), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(2)(ii), (b)(2)(ii), and (c)(2)(ii).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44067, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.4550 Diperoxy ketal.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as diperoxy ketal (PMN-92-1394) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

**§ 721.4565**

**40 CFR Ch. I (7–1–10 Edition)**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51705, Oct. 4, 1993]

**§ 721.4565 Modified hydroxystyrene homopolymer (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Modified hydroxystyrene homopolymer (PMN P-99-0610) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81401, Dec. 26, 2000]

**§ 721.4568 Methylpolychloro aliphatic ketone.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as methylpolychloro aliphatic ketone (PMN No. P-91-1321) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(6)(ii), (a)(6)(iii), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c). The employer is able to demonstrate that the gloves selected for handling P-

91-1321 provide an impervious barrier to prevent dermal exposure during normal and expected duration and conditions of exposure within the work area by testing the material used to make the gloves and the construction of the gloves to establish that they will be impervious for the expected duration and conditions of exposure. The testing must subject the gloves to the expected conditions of exposure, including the likely combinations of chemical substances to which the gloves may be exposed in the work area. There must be no permeation of P-91-1321 greater than 0.017 mg/cm<sup>2</sup>/min after 8 h of testing in accordance with the most recent versions of the American Society for Testing and Materials (ASTM) F739 “Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases” and ASTM F1194 “Guide for Documenting the Results of Chemical Permeation Testing of Protective Clothing Materials.” The employer must submit all test data to the Agency and must receive written Agency approval of the test results for each type of glove tested prior to use of such gloves. Neoprene gloves with a minimum thickness of 1.50 mm have already been tested and found to satisfy the terms of this rule. Nitrile gloves with a minimum thickness of 0.61 mm also satisfy the terms of this rule, as long as the duration of exposure to P-91-1321 is less than 2 h per work shift. If the duration of exposure is longer than 2 h, nitrile gloves shall be discarded and replaced every 2 h. Unless otherwise indicated, gloves contaminated with P-91-1321 shall be disposed of after every work shift.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(v), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90(a)(1), (b)(1), (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## Environmental Protection Agency

## § 721.4587

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (d) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32239, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

### § 721.4575 L-aspartic acid, N,N'- [(1E) - 1,2 - ethenediylbis[(3-sulfo-4, 1-phenylene)imino [6-(phenylamino)-1,3,5-triazine-4,2-diy]]]bis-, hexasodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as l-aspartic acid, N,N'- [(1E) - 1,2 - ethenediylbis[(3-sulfo-4, 1-phenylene)imino[6-(phenylamino)-1,3,5-triazine-4,2-diy]]]bis-, hexasodium salt (PMN P-99-1167; CAS No. 205764-98-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), (x)(1), and (f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15085, Mar. 28, 2003]

### § 721.4585 Lecithins, phospholipase A2-hydrolyzed.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as lecithins, phospholipase A2-hydrolyzed (PMN P-93-333) is subject to reporting under this section for the sig-

nificant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), and (g)(3)(ii).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 10 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[59 FR 27484, May 27, 1994]

### § 721.4587 Lithium manganese oxide (LiMn2O4) (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as lithium manganese oxide (LiMn2O4) (P-96-175) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of these substances without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for these substances, the employer becomes aware that these substances may present a risk of injury to human health or the environment the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information.



## § 721.4589

If these substances are not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substances are reintroduced into the workplace.

(B) The employer must ensure that persons who will receive, or who have received their substances from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[61 FR 63738, Dec. 2, 1996]

## § 721.4589 Propanedioic acid, [(4-methoxyphenyl)methylene]-, bis(1,2,2,6,6-pentamethyl-4-piperdiny) ester (9CI).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as propanedioic acid, [(4-methoxyphenyl)methylene]-, bis(1,2,2,6,6-pentamethyl-4-piperdiny) ester (9CI) (PMN P-95-1411; CAS No. 147783-69-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

## 40 CFR Ch. I (7-1-10 Edition)

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3429, Jan. 22, 1998, as amended at 67 FR 12882, Mar. 20, 2002]

## § 721.4590 Mannich-based adduct.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as a Mannich-based adduct (PMN P-93-66) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 8 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51705, Oct. 4, 1993]

## § 721.4594 Substituted azo metal complex dye.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted azo metal complex dye (PMN P-94-499) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## Environmental Protection Agency

## § 721.4600

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11044, Mar. 1, 1995]

### § 721.4596 Diazo substituted carbomonocyclic metal complex.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a diazo substituted carbomonocyclic metal complex (PMN P-94-1039) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11044, Mar. 1, 1995]

### § 721.4600 Recovered metal hydroxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a recovered metal hydroxide (PMN P-91-809) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive this substance from the employer, or who have received this substance from the employer within 5 years from the date the employer becomes aware of the new information described under paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44067, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.4610**

**40 CFR Ch. I (7-1-10 Edition)**

**§ 721.4610 Mixed metal oxides (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as mixed metal oxides (PMN P-98-0002) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions listed in the TSCA 5(e) consent order for this substance. The NCEL is 0.05 mg/m<sup>3</sup> as an 8-hour time weighted average verified by actual monitoring data.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f) (g)(1)(ii), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), and (g)(2)(iv).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81401, Dec. 26, 2000]

**§ 721.4620 Dialkylamino alkanolate metal salt.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkylamino alkanolate metal salt (P-90-274), is subject to reporting under this section for the significant

new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows. (A) If, as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (production limit set at 573,300 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (c), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 15789, Apr. 17, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## Environmental Protection Agency

§ 721.4680

### § 721.4660 Alcohol, alkali metal salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as alcohol, alkali metal salt (PMN P-91-151) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 5 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 40213, Aug. 13, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.4663 Fluorinated carboxylic acid alkali metal salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified as fluorinated carboxylic acid alkali metal salts (PMNs P-95-979/980/981) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80 (v)(2), (w)(2), and (x)(2).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4), (N = 100 ppb for P-95-979), (N = 30 ppb for P-95-980), and (N = 3 ppb for P-95-981).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63738, Dec. 2, 1996]

### § 721.4668 Hydrated alkaline earth metal salts of metalloid oxyanions.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hydrated alkaline earth metal salts of metalloid oxyanions (PMN P-94-1557) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(5)(viii), (a)(6)(i), (b), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e), (f), (g)(1)(vi), (g)(1)(ix), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[61 FR 63738, Dec. 2, 1996]

### § 721.4680 Metal salts of complex inorganic oxyacids (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as metal salts of complex inorganic oxyacids (PMNs P-89-576 and P-89-577) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

**§ 721.4685**

**40 CFR Ch. I (7–1–10 Edition)**

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 33305, Aug. 15, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.4685 Substituted purine metal salt (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted purine metal salt (PMN P-95-175) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 8)

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63739, Dec. 2, 1996]

**§ 721.4700 Metalated alkylphenol copolymer (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance metalated alkylphenol copolymer (PMN P-87-723)

is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (b)(1)(i)(C), (b)(1)(ii), (b)(1)(iii), (b)(1)(iv), (b)(2), (c)(1), (f), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (industrial coating material).

(iii) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(3), (b)(1), (b)(3), (c)(1), and (c)(3).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements as specified in § 721.125 (a) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 32416, Aug. 9, 1990, as amended at 57 FR 20424, May 13, 1992. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.4720 Disubstituted phenoxazine, chlorometalate salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as disubstituted phenoxazine, chlorometalate salt (PMN P-90-0002) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a),

## Environmental Protection Agency

## § 721.4820

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46467, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.4740 Alkali metal nitrites.

(a) *Chemical substances and significant new use subject to reporting.* (1) The category of chemical substances which are nitrites of the alkali metals (Group IA in the periodic classification of chemical elements) lithium, sodium, potassium, rubidium, cesium, and francium, is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Use as an ingredient in metalworking fluids (as defined in 40 CFR 721.3) containing amines.

(b) [Reserved]

[58 FR 27944, May 12, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.4792 2-propenoic acid, 2-methyl-, C<sub>11-14</sub>-isoalkyl esters, C<sub>13</sub>-rich.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propenoic acid, 2-methyl-, C<sub>11-14</sub>-isoalkyl esters, C<sub>13</sub>-rich (PMN P-99-1189; CAS No. 85736-97-6) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (a monomer for casting automotive parts adhesives or impregnation fluid).

(ii) *Release to water.* Requirements as specified in § 721.90(c)(4) (N=1 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15085, Mar. 28, 2003]

### § 721.4794 Polypiperidinol-acrylate methacrylate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polypiperidinol-acrylate methacrylate (PMN P-88-1304) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set 1.0 percent), (f), (g)(1)(vi), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v). The following additional statement shall appear on each label and MSDS required by this paragraph: This substance may cause acute and chronic toxicity.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27484, May 27, 1994]

### § 721.4820 Methane, bromodifluoro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as methane, bromodifluoro- is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

**§ 721.4840**

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(v), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(ii), (g)(2)(iii), and (g)(5). In addition, the following statements shall appear on the label and MSDS: This substance may cause cardiotoxicity. Evacuate area before the concentration of this substance in the area reaches 1 percent. Residential use is prohibited due to cardiotoxic dangers. General consumer use is prohibited, with the exception of outdoor automotive use and outdoor marine use. Following discharge and evacuation, use protective gear (self-contained breathing apparatus) before reentering an area in which the airborne concentration of the PMN substance exceeds 1 percent.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (Use in portable fire extinguishers intended for consumer use except for outdoor automotive use and outdoor marine use; use in fire extinguisher units with an Underwriters Laboratory (UL) rating of less than 5BC; use in other than rechargeable fire extinguisher units; use in occupied areas from which personnel cannot be evacuated before the concentration of the PMN substance exceeds 1 percent or egress cannot occur within 30 seconds; or use without protective gear (self-contained breathing apparatus) being made available in the event that, following discharge of the PMN substance and evacuation of the area, personnel must reenter an area in which the airborne concentration of the PMN substance exceeds 1 percent.)

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (f) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

**40 CFR Ch. I (7–1–10 Edition)**

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19238, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993; 59 FR 39296, Aug. 2, 1994]

**§ 721.4840 Substituted triphenylmethane.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted triphenylmethane (PMN P-87-1553) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), (x)(1) and (y)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 40216, Aug. 13, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.4880 Methanol, trichloro-, carbonate (2:1).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as methanol, trichloro-, carbonate (2:1) (CAS No. 32315-10-9) (PMN P-90-1535) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(5). The following additional human hazard precautionary statement shall appear on the label:

## Environmental Protection Agency

## § 721.5050

This substance may react to form phosgene gas. When using this substance, handle with extreme caution.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (f), (g), and (h).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 40213, Aug. 13, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.4885 Methanone, [5-[3-(2H-benzotriazol-2-yl)-2-hydroxy-5-(1,1,3,3-tetramethylbutyl)phenyl]methyl]-2-hydroxy-4-(octyloxy) phenyl]phenyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as methanone, [5-[3-(2H-benzotriazol-2-yl)-2-hydroxy-5-(1,1,3,3-tetramethylbutyl)phenyl]methyl]-2-hydroxy-4-(octyloxy)phenyl]phenyl- (PMN P-96-942; CAS No.162245-07-0) is subject to the reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c). As an alternative to the respiratory protection requirements of this section, manufacturers, importers, and processors of this substance may follow the terms of the new chemical exposure limits section in the TSCA section 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(iv), (g)(1)(vi), (g)(1)(viii), (g)(2)(ii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3430, Jan. 22, 1998]

### § 721.4925 Methyl n-butyl ketone.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance methyl n-butyl ketone, CAS Number 591-78-6, is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[52 FR 11825, Apr. 13, 1987. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.5050 2,2'-[(1-Methylethylidene)bis[4,1-phenyloxy[1-(butoxymethyl)-(2,1-ethanediyl)oxymethylene]]bisoxirane, reaction product with a diamine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The



§ 721.5075

40 CFR Ch. I (7-1-10 Edition)

chemical substance identified generically as 2,2'-[(1-methylethylidene)bis[4,1-phenyloxy[1-(butoxymethyl)-(2,1-ethanediyloxy)methylene]]bisoxirane, reaction product with a diamine (PMN P-91-934), is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46467, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

§ 721.5075 Mixed methyltin mercaptoester sulfides.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as mixed methyltin mercaptoester sulfides (PMN P-92-177) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(i), (g)(1)(iii), (g)(1)(iv), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iii) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (a)(2) (only in a facility permitted to landfill Resources Conservation and Recovery Act (RCRA) hazardous wastes with the landfill operated in accordance with subtitle C of RCRA).

(iv) [Reserved]

(v) *Release to water.* Requirements as specified in § 721.90(a)(4) (where N = 2 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51685, Oct. 4, 1993]

§ 721.5175 Mitomycin C.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance mitomycin C (CAS No. 5007-7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

§ 721.5185 Morpholine, 4-(1-oxo-2-propenyl)-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as morpholine, 4-(1-oxo-2-propenyl)- (PMN P-95-169; CAS No. 5117-12-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iv), (a)(3)(i), (a)(3)(ii),

## Environmental Protection Agency

## § 721.5192

(a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(5)(xv), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c). The following material has been tested in accordance with the American Society for Testing Materials (ASTM) F739 method and found by EPA to satisfy the consent order's and § 721.63(a)(2)(i) requirements for dermal protection to 100 percent PMN substance. The following gloves have been tested in accordance with the ASTM F739 and found to satisfy the requirement for use by EPA: Safety 4/4H EVOH/PE laniinate, Ansell Edmont Neoprene number 865, and Solvex Nitrile Rubber number 275. Gloves and other dermal protection may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift. For additional dermal protection materials, a company must submit all test data to the Agency and must receive written Agency approval for each type of material tested prior to use of that material as worker dermal protection. However, for the purposes of determining the imperviousness of gloves, up to 1 year after the commencement of commercial manufacture or import, the employer may use the method described in § 721.63 (a)(3)(ii), thereafter, they must use the method described in § 721.63 (a)(3)(i).

(ii) [Reserved]

(iii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(v), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), (g)(4)(iii), and (g)(5).

(iv) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (a), (c), (f), (p): First trigger (1 year), second (1,500,000), and third (2,000,000) or 1 year whichever is greater then 7,750,000 or 5 years after the commencement of commercial manufacture, whichever comes later and § 721.80(y)(1).

(v) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). Disposal by landfill must go to a RCRA hazardous waste landfill.

(vi) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), (j), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 371, Jan. 5, 2000]

### § 721.5192 Substituted 1,6-dihydroxy naphthalene.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted 1,6-dihydroxy naphthalene (PMN P-87-1036) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (k), and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (a)(2).

(v) *Release to water.* Requirements as specified in § 721.90(a)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

**§ 721.5200**

**40 CFR Ch. I (7–1–10 Edition)**

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[60 FR 45083, Aug. 30, 1995]

**§ 721.5200 Disubstituted phenylazo trisubstituted naphthalene.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as disubstituted phenylazo trisubstituted naphthalene (PMN P-91-328) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g), (v)(1), (w)(1), (x)(1), and (y)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46467, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

**§ 721.5225 Naphthalene,1,2,3,4-tetrahydro(1-phenylethyl) (specific name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance naphthalene,1,2,3,4-tetrahydro(1-phenylethyl) (PMN P-85-1331) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (e) [concentration set at 1.0 percent], (f), and (g)(3)(i) and (g)(3)(ii), (g)(4)(i) and (g)(4)(iii), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iii) *Disposal.* Requirements as specified in § 721.85 (a) (1) and (2), (b)(1) and (b)(2), and (c)(1) and (c)(2).

(iv) [Reserved]

(v) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where n = 1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26110, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993; 62 FR 42692, Aug. 8, 1997]

**§ 721.5250 Trimethyl spiropolyheterocyclic naphthalene compound.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as trimethyl spiropolyheterocyclic naphthalene compound (PMN P-91-1456) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified at § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 31968, July 20, 1992, as amended at 58 FR 34204, June 23, 1993]

## Environmental Protection Agency

§ 721.5260

### § 721.5252 2-Naphthalenecarboxylic acid, 4,4'-methylenebis [3-hydroxy-, zinc salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-Naphthalenecarboxylic acid, 4,4'-methylenebis [3-hydroxy-, zinc salt (P-99-1342; CAS No. 235083-88-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=10).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Record keeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70177, Dec. 17, 2003]

### § 721.5253 2-Naphthalenecarboxylic acid, 4,4'-methylenebis [3-hydroxy-, strontium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-Naphthalenecarboxylic acid, 4,4'-methylenebis [3-hydroxy-, strontium salt (PMN P-99-1341; CAS No. 235083-90-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=10).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Record keeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70177, Dec. 17, 2003]

### § 721.5255 2-Naphthalenol, mono and dioctyl derivs.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-naphthalenol, mono and dioctyl derivs (PMN P-95-1288) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 1). When calculating the surface water concentrations according to the instructions in § 721.91, the statement that the amount of the substance that will be released will be calculated before the substance enters control technology does not apply. Instead, if the waste stream containing the substance will be treated before release, then the amount of the substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 90 percent removal efficiency may be attributed to such treatment.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3430, Jan. 22, 1998]

### § 721.5260 1,3,6-Naphthalenetrisulfonic acid, 7-[[2-(aminocarbonyl)amino]-4-[[4-[[2-[2-(ethenylsulfonyl)ethoxy]ethyl]amino]-6-fluoro-1,3,5-triazin-2-yl]amino]phenyl]azo], trisodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,3,6-

§ 721.5262

Naphthalenetrisulfonic acid, 7-[[2-[(aminocarbonyl)amino]-4-[[4-[[2-[2-(ethenylsulfonyl)ethoxy]ethyl]amino]-6-fluoro-1,3,5-triazin-2-yl]amino]phenyl]azo], trisodium salt (PMN P-00-0806; CAS No. 106359-91-5) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15085, Mar. 28, 2003]

§ 721.5262 **2,7-Naphthalenedisulfonic acid, 5-[[4-chloro-6-[substituted]amino]-1,3,5-triazin-2-yl]amino]-4-hydroxy-3-[(1-sulfo-2-naphthalenyl)azo], trisodium salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 2,7-Naphthalenedisulfonic acid, 5-[[4-chloro-6-[substituted] amino]-1,3,5-triazin-2-yl]amino]-4-hydroxy-3-[(1-sulfo-2-naphthalenyl)azo]-, trisodium salt (PMN P-00-0803) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

40 CFR Ch. I (7-1-10 Edition)

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15085, Mar. 28, 2003]

§ 721.5275 **2-Naphthalenecarboxamide-N-aryl-3-hydroxy-4-arylozo (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 2-naphthalenecarboxamide-N-aryl-3-hydroxy-4-arylozo (PMN P-87-1265) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iii) through (a)(5)(vii), and (a)(6)(i), (b) [concentration set at 0.1 percent], and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) [concentration set at 0.1 percent], (f), and (g)(1)(i), (g)(1)(v), and (g)(1)(vii), and (g)(2)(ii) and (g)(2)(iv).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26110, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

§ 721.5276 **2-Naphthalenol, heptyl-1-[[4-(phenylazo)phenyl]azo]-, ar',ar''-Me derivs.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-naphthalenol, heptyl-1-[[4-(phenylazo)phenyl] azo]-, ar',ar''-Me

## Environmental Protection Agency

§ 721.5280

derives (PMN P-95-538) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63739, Dec. 2, 1996]

### § 721.5278 Substituted naphthalenesulfonic acid, alkali salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted naphthalenesulfonic acid, alkali salt (PMN P-95-85) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45083, Aug. 30, 1995]

### § 721.5279 2,7-Naphthalenedisulfonic acid, 4-amino-3-[[4'-amino-4-(3-butoxy-2-hydroxypropyl)amino]phebyl]azo]-3,3'-dimethyl[1,1'-biphenyl]-4-yl]azo]-5-hydroxy-6-(phenylazo)-, disodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2,7-naphthalenedisulfonic acid, 4-amino-3-[[4'-amino-4-(3-butoxy-2-hydroxypropyl)amino]phebyl]azo]-3,3'-dimethyl[1,1'-biphenyl]-4-yl]azo]-5-hydroxy-6-(phenylazo)-, disodium salt (PMN P-97-131; CAS No. 103580-64-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(1), (w)(1), and (x)(1).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 40).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3430, Jan. 22, 1998]

### § 721.5280 2,7-Naphthalenedisulfonic acid, 4-amino-5-hydroxy-, coupled with diazotized 4-butylbenzenamine, diazotized 4,4'-cyclohexylidenebis[benzenamine] and m-phenylenediamine, sodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2,7-naphthalenedisulfonic acid, 4-amino-5-hydroxy-, coupled with diazotized 4-butylbenzenamine, diazotized 4,4'-cyclohexylidenebis[benzenamine] and m-phenylenediamine, sodium salt (PMN P-97-193; CAS No. 182238-09-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

§ 721.5281

(2) The significant new uses are:  
(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3430, Jan. 22, 1998]

**§ 721.5281 2-Naphthalenesulfonic acid, 3-[[4-[(2,4-dimethyl-6-sulfophenyl)azo]-2-methoxy-5-methylphenyl]azo]-4-hydroxy-7-(phenylamino)-, sodium salt, compd. With 2,2',2'-nitriлотris [ethanol] (9CI).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-Naphthalenesulfonic acid, 3-[[4-[(2,4-dimethyl-6-sulfophenyl)azo]-2-methoxy-5-methylphenyl]azo]-4-hydroxy-7-(phenylamino)-, sodium salt, compd. With 2,2',2'-nitriлотris [ethanol] (9CI) (PMN P-95-1235; CAS No. 94213-53-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3430, Jan. 22, 1998]

40 CFR Ch. I (7-1-10 Edition)

**§ 721.5282 Trisodium chloro [(trisubstituted heteromonocycle amino) propylamino]triazinylamino hydroxyazo naphthalenetrisulfonate.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a trisodium chloro[(trisubstituted heteromonocycleamino) propylamino]triazinyl aminohydroxyazo naphthalenetrisulfonate (PMN P-94-2177) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45083, Aug. 30, 1995]

**§ 721.5283 Cobaltate (5-), bis[4-[[6-[(4-amino-6-chloro-1,3,5-triazin-2-yl)amio]-1-hydroxy-3-sulfo-2-naphthalenyl]azo]-3-hydroxy-7-nitro-1-naphthalenesulfonato(4-)-], pentasodium.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as cobaltate (5-), bis[4-[[6-[(4-amino-6-chloro-1,3,5-triazin-2-yl)amio]-1-hydroxy-3-sulfo-2-naphthalenyl]azo]-3-hydroxy-7-nitro-1-naphthalenesulfonato(4-)-], pentasodium (PMN P-99-0990; CAS No. 91144-26-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## Environmental Protection Agency

§ 721.5286

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(ii), (a)(5)(xii), and (a)(5)(xiii).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (a spray applied automotive coating).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15085, Mar. 28, 2003]

### § 721.5284 Chromate (5-), bis[4-hydroxy-7-[(2-hydroxy-1-naphthalenyl)azo]-3-[(2-hydroxy-3-nitro-5-sulfophenyl)azo]-2-naphthalenesulfonato(4-)], pentasodium.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a Chromate (5-), bis[4-hydroxy-7-[(2-hydroxy-1-naphthalenyl)azo]-3-[(2-hydroxy-3-nitro-5-sulfophenyl)azo]-2-naphthalenesulfonato(4-)], pentasodium (PMN P-99-0114; CAS No. 159574-72-8) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81401, Dec. 26, 2000]

### § 721.5285 Ethoxylated substituted naphthol.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an ethoxylated substituted naphthol (PMN P-88-2484) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 200 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51685, Oct. 4, 1993]

### § 721.5286 Benzenediazonium, [(((substituted) azo]phenyl)sulfonyl]amino]-, coupled with aminophenol, diazotized aminobenzoic acid, diazotized (substituted) benzenesulfonic acid and naphthalenol (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as benzenediazonium, [(((substituted)

azo]phenyl)sulfonyl]amino]-, coupled with aminophenol, diazotized aminobenzoic acid, diazotized (substituted) benzenesulfonic acid and naphthalenol (PMN P-00-0045) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.



**§ 721.5288**

**40 CFR Ch. I (7–1–10 Edition)**

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15086, Mar. 28, 2003]

**§ 721.5288 Chromate(2-), [3-hydroxy-4-(2-hydroxy-1-naphthenyl)azo]-7-nitro-1-substituted][N-[7-hydroxy-8-(2-hydroxy-5-nitrophenyl)azo]-1-substituted]-, salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as chromate(2-), [3-hydroxy-4-(2-hydroxy-1-naphthenyl)azo]-7-nitro-1-substituted][N-[7-hydroxy-8-(2-hydroxy-5-nitrophenyl)azo]-1-substituted]-, salt (PMN P-99-783) is subject to reporting under this section for the significant new use described in paragraph (a)(1) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70178, Dec. 17, 2003]

**§ 721.5290 Phenylazoalkoxy naphthylamines (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as phenylazoalkoxy naphthylamines (PMNs P-97-42 and P-97-43) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and

(c)(4) (N = 50 for P-97-42) (N = 40 for P-97-43).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44578, Aug. 20, 1998]

**§ 721.5293 Poly(oxy-1,2-ethanediyl), alpha-(9Z)-9-octadecenyl-omega-hydroxy-, phosphate, ammonium salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as poly(oxy-1,2-ethanediyl), alpha-(9Z)-9-octadecenyl-omega-hydroxy-, phosphate, ammonium salt (PMN P-99-920; CAS No. 58857-49-1) is subject to reporting under this section for the significant new use described in paragraph (a)(1) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70178, Dec. 17, 2003]

**§ 721.5310 Neonanoic acid, ethenyl ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as neonanoic acid, ethenyl ester (PMN P-92-129) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this

section do not apply once the substance has been incorporated into a polymer matrix with the level of residual monomer below 0.1 percent.

(2) The significant new uses are: (i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i) (There must be no permeation of the substance greater than 0.02 µg/min · cm<sup>2</sup> after 8 hours of testing in accordance with the most current version of the American Society for Testing and Materials (ASTM) F739 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases." For conditions of exposure which are intermittent, gloves may be tested in accordance with the most current version of ASTM F1383 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases Under Conditions of Intermittent Contact," provided the contact time in testing is greater than or equal to the expected duration of dermal contact, and the purge time used in testing is less than or equal to the expected duration of noncontact during the intermittent cycle of dermal exposure in the workplace. If ASTM F1383 is used for testing, manufacturers, importers, and processors must submit to the Agency a description of worker activities involving the substance which includes daily frequencies and durations of potential worker exposures. The results of all glove permeation testing must be reported in accordance with the most current version of ASTM F1194 "Guide for Documenting the Results of Chemical Permeation Testing of Protective Clothing Materials." Manufacturers, importers, and processors must submit all test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves. The following gloves have been tested in accordance with the ASTM F739 method and found by EPA to satisfy the requirements for continuous use: North/F101/Vitron gloves, 0.03 cm thick; and Ansell/Edmont/4H/PE/EVOH/PE Laminate gloves, 0.006 cm thick. Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift.), (a)(2)(ii) (With the exception of

laboratory activities, full body chemical protective clothing is required for any worker activity in which the substance is reasonably likely to contact the worker in the following state(s): Open liquid pool or solid of greater than 5 kg; liquid spray or splash; mist; aerosol dust; or any worker activity which have potential for contact with the substance for more than 10 min/h. At a minimum, a chemical protective apron is required for any worker activity with potential for contact with the substance which is not covered by this paragraph), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii) (if cartridge service life testing is not available), (a)(5)(xii) or (a)(5)(xiii) (if data on cartridge service life testing has been reviewed and approved in writing by EPA), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), and (a)(6)(v). As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (h)(1)(vi) (The following additional statements shall appear on each label required by this paragraph: The health effects of this material have not been fully determined but are currently being tested. EPA is concerned however, that this material may have serious chronic health and environmental effects. When using this material, use eye and skin protection, which includes gloves which have been determined to be impervious to this substance. Use respiratory protection, unless workplace airborne concentrations are maintained at or below an 8-h time weighted average (TWA) of 1 ppm, when there is a likelihood of exposure in the work area from dust, mist, smoke or vapors.), (h)(2)(ii)(F), (h)(2)(ii)(G), (h)(2)(ii)(I), (h)(2)(iii)(A), (h)(2)(iii)(B), (h)(2)(iii)(C), (h)(2)(iii)(E), (h)(2)(iv)(A), (h)(2)(iv)(B) (The following additional statements shall appear on each MSDS required by this paragraph: This substance may cause moderate skin irritation. This substance may

## § 721.5315

cause neurotoxicity. When using this substance, use respiratory protection, unless workplace airborne concentrations are maintained at or below an 8-h TWA of 1 ppm.)

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 5 ppb). When calculating the surface water concentrations according to the instructions in § 721.91(a)(4), the statement that the amount of the substance that will be released will be calculated before the substance enters control technology does not apply. Instead, if the waste stream containing the substance will be treated before release, then the amount of the substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 75 percent removal efficiency may be attributed to such treatment. In addition, when the substance is released in combination with the substances hexanedioic acid, diethenyl ester, hexanoic acid, 2-ethyl-, ethenyl ester, and propanoic acid, 2,2-dimethyl-, ethenyl ester, the quotient from the formula referenced in this section shall not exceed the average of the quotient applicable to the other substances weighted by the proportion of each substance present in the total daily amount released.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance. Manufacturers, importers, and processors of the substance must keep records documenting that the PMN substance has been incorporated into a polymer matrix with the level of residual monomer below 0.1 percent if this section does not apply as described in paragraph (a)(1) of this section.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

## 40 CFR Ch. I (7–1–10 Edition)

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51705, Oct. 4, 1993, as amended at 58 FR 68311, Dec. 27, 1993]

### § 721.5315 Nickel, cobalt mixed metal oxide (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as nickel, cobalt mixed metal oxide. (PMN P-02-90) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f) and (j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 70178, Dec. 17, 2003]

### § 721.5325 Nickel acrylate complex.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance nickel acrylate complex (PMN P-85-1034) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(i) through (g)(2)(iii), (g)(2)(v), (g)(4)(i), and (g)(5). The provision of § 721.72(d) requiring that employees to

## Environmental Protection Agency

## § 721.5340

be provided with information on the location and availability of a written hazard communication program does not apply when the written program is not required under § 721.72(a).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (e), (f), (g), and (h).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 39901, Sept. 28, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5330 Nickel salt of an organo compound containing nitrogen.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as nickel salt of an organo compound containing nitrogen (PMN P-92-686) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(ii), (g)(1)(vii), (g)(1)(viii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5). The following additional statements shall appear on each label and MSDS as required by this paragraph: This substance may cause skin sensitization. This substance may cause blood effects.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (b), (c), and (k).

(iv) *Disposal.* Requirements as specified in § 721.85(a)(2) (landfill operated in accordance with subtitle C of the Resource Conservation and Recovery Act (RCRA) to receive nickel wastes), § 721.85(b)(2) (landfill operated in accordance with subtitle C of RCRA to receive nickel wastes), and § 721.85(c)(2) (landfill operated in accordance with subtitle C of RCRA to receive nickel wastes).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 40 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51685, Oct. 4, 1993]

### § 721.5340 Substituted benzothiazole-azo-substituted benzoquinoline nickel complex (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as substituted benzothiazole-azo-substituted benzoquinoline nickel complex (PMN P-99-897) is subject to reporting under this section for the significant new use described in paragraph (a)(1) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

## § 721.5350

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70178, Dec. 17, 2003]

### § 721.5350 Substituted nitrile (generic name).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted nitrile (PMN P-83-603) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(v), (b) (concentration set at 1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(1), (d), (e) (concentration set at 1 percent), (f), (g)(1)(iii), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), and (g)(4)(i). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS was not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (level set at 1 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (g), (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

## 40 CFR Ch. I (7-1-10 Edition)

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 33305, Aug. 15, 1990; 55 FR 52275, Dec. 21, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5356 Ethanol, 2,2'2"-nitrilotris-, compound with alpha-2,4,6-tris (1-phenylethyl)phenyl]-omega-hydroxypoly (oxy-1,2-ethanediyl) phosphate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as ethanol, 2,2'2"-nitrilotris-, compound with alpha-[2,4,6-tris(1-phenylethyl)phenyl]-omega-hydroxypoly (oxy-1,2-ethanediyl) phosphate (PMN P-98-185) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (j) (pesticide inert).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44579, Aug. 20, 1998]

### § 721.5358 2-propanol, 1,1',1'-nitrilotris-, compds. with ethanol 2-[2-(C<sub>12-14</sub>-alkyloxy) ethoxy] derivs. hydrogen sulfates.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propanol, 1,1',1'-nitrilotris-, compds. with ethanol 2-[2-(C<sub>12-14</sub>-alkyloxy) ethoxy] derivs. hydrogen sulfates (PMN P-99-928; CAS No. 222975-06-6) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## Environmental Protection Agency

§ 721.5378

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (surfactant used in toilet bowl cleaner).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of 721.185 apply to this section.

[68 FR 70178, Dec. 17, 2003]

### § 721.5360 Substituted nitrobenzene (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted nitrobenzene (PMN P-97-1028) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), and (a)(6)(v).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), (e), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44579, Aug. 20, 1998]

### § 721.5375 Nitrothiophenecarboxylic acid, ethyl ester, bis[[[(substituted)] amino]alkylphenyl]azo] (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance nitrothiophenecarboxylic acid, ethyl ester, bis [[[(substituted)] amino]alkylphenyl]azo] (PMN P-87-304) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (k), (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26110, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5378 9-Phosphabicyclo[3.3.1]nonane,9,9'-(1,2-ethanediyl)bis- (9C1).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 9-Phosphabicyclo[3.3.1]nonane,9,9'-(1,2-ethanediyl)bis- (9C1) (PMN P-99-0754; CAS No.153280-11-6) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(2), (w)(2), and (y)(2).

(ii) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

**§ 721.5380**

**40 CFR Ch. I (7–1–10 Edition)**

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81401, Dec. 26, 2000]

**§ 721.5380 Mixed alkyl phenolic novolak resin (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as mixed alkyl phenolic novolak resin (PMN P-98-718) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 372, Jan. 5, 2000]

**§ 721.5385 Octanoic acid, hydrazide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as octanoic acid, hydrazide (PMN P-92-1086) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (b)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (j) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51706, Oct. 4, 1993]

**§ 721.5400 3,6,9,12,15,18,21-Heptaoxatetatriaocanoic acid, sodium salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 3,6,9,12,15,18,21-heptaoxatettriaocanoic acid, sodium salt is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new use is:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions

## Environmental Protection Agency

## § 721.5452

of § 721.185 apply to this significant new use rule.

[56 FR 19237, Apr. 25, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.5425 $\alpha$ -Olefin sulfonate, potassium salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as an  $\alpha$ -olefin sulfonate, potassium salt (PMN P-91-100) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 40215, Aug. 13, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.5450 $\alpha$ -Olefin sulfonate, sodium salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as  $\alpha$ -olefin sulfonate, sodium salt (PMN P-88-2210) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance

may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(1)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44068, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5452 Alkali metal salt of halogenated organoborate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkali metal salt of halogenated organoborate (PMN P-00-0638) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).



**§ 721.5454**

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15086, Mar. 28, 2003]

**§ 721.5454 Methylium, triphenyl-, tetrakis(pentafluorophenyl) borate (1-).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified as methylium, triphenyl-, tetrakis(pentafluorophenyl) borate (1-) (PMN P-00-0637; CAS No. 136040-19-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15086, Mar. 28, 2003]

**§ 721.5460 Organosolv lignin.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as an organosolv lignin (PMN P-95-1584; CAS No. 8068-03-9) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is any manufacture, processing, or use of the

**40 CFR Ch. I (7-1-10 Edition)**

substance with a number average molecular weight less than 700 daltons.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 65710, Nov. 30, 1998]

**§ 721.5465 Amine salt of organic acid (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as amine salt of organic acid (PMN P-98-1172) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 372, Jan. 5, 2000]

**§ 721.5475 1-Oxa-4-azaspiro[4.5]decane, 4-dichloroacetyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-oxa-4-azaspiro[4.5]decane, 4-dichloroacetyl- (PMN P-86-1648, CAS number 71526-07-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

## Environmental Protection Agency

§ 721.5525

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3) (applies to gloves only), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (k).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (j) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44068, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5500 7-Oxabicyclo[4.1.0]heptane, 3-ethenyl, homopolymer, ether with 2-ethyl-2-(hydroxymethyl)-1,3-propanediol (3:1), epoxidized.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 7-oxabicyclo[4.1.0]heptane, 3-ethenyl, homopolymer, ether with 2-ethyl-2-(hydroxymethyl)-1,3-propanediol (3:1), epoxidized (PMN P-88-1898) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(viii), (a)(5)(ix), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i) through (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 39902, Sept. 28, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5525 Substituted spiro oxazine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted spiro oxazine (PMN P-92-283) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified at § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

**§ 721.5540**

**40 CFR Ch. I (7–1–10 Edition)**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 31969, July 20, 1992, as amended at 58 FR 34204, June 23, 1993]

**§ 721.5540 1H,3H,5H-oxazolo [3,4-c] oxazole, dihydro-7a-methyl-**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as 1H,3H,5H-oxazolo [3,4-c] oxazole, dihydro-7a-methyl- (PMN P-91-1324) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(iii) and (a)(3).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 500 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), (e), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 26691, May 18, 1995]

**§ 721.5545 3-(Dichloroacetyl)-5-(2-furanyl)-2,2-dimethyl-oxazolidine.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 3-(dichloroacetyl)-5-(2-furanyl)-2,2-dimethyl-oxazolidine (PMN P-93-1694) (CAS no. 121776-57-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(6)(i), (b) (concentration set at 0.1%), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1%), (f), (g)(1)(iv), (g)(1)(vii), (g)(1)(ix),

(g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (b), (c), (k) (as a seed safener), and (o).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63739, Dec. 2, 1996]

**§ 721.5546 Halogen substituted oxetanes (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as halogen substituted oxetanes. (PMNs P-98-1033 through P-98-1035) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(ii) *Hazard communication program.* A significant new use of these chemical substances is any manner or method of manufacture, import, or processing associated with any use of these chemical substances without providing risk notification as follows:

(A) If as a result of the test data required under the TSCA section 5(e) consent order for these chemical substances, the employer becomes aware that these chemical substances may present a risk of injury to human health or the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this chemical substance is not being manufactured, imported, processed, or used in the employer's workplace, the

## Environmental Protection Agency

## § 721.5549

employer must add the new information to an MSDS before the chemical substances are reintroduced into the workplace.

(B) The employer must ensure that persons who will receive or who have received the chemical substances from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (h), and (i) are applicable to manufacturers, importers, and processors of these chemical substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 70178, Dec. 17, 2003]

### § 721.5547 Antimony double oxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as antimony double oxide (PMNs P-95-677 and P-95-724) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), (g)(2)(ii), (g)(2)(iii), (g)(3)(ii), and (g)(5). The label and MSDS as required by this paragraph shall also include the following statements: These substances may cause lung toxicity. When using these substances avoid any applications of these substances which could cause inhalation exposures. When using these substances keep in liquid form only.

(ii) *Industrial, commercial, and consumer activities.* Requirements as speci-

fied in § 721.80 (f), (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), (x)(2), (y)(1), and (y)(2). Manufacturing, processing or use in any form which could cause inhalation exposures.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3431, Jan. 22, 1998]

### § 721.5548 Mixed metal oxide (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a mixed metal oxide (PMN P-97-956) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iii), (a)(5)(iv), and (a)(6)(i).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), and (d) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44579, Aug. 20, 1998]

### § 721.5549 Lithiated metal oxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as lithiated metal oxide (LiNiO<sub>2</sub>) (PMN P-96-19; CAS No. 12031-65-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(6)(i), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the TSCA section 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f) (g)(1)(iv), (g)(1)(vii), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 30).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (d), (e), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3431, Jan. 22, 1998]

**§ 721.5550 Substituted dialkyl oxazolone (generic name).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted dialkyl oxazolone (PMN P-86-1634) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(xi), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 33306, Aug. 15, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.5560 Formaldehyde, polymer with (chloromethyl) oxirane and phenol, reaction products with 6H-dibenz[c,e][1,2]oxaphosphorin-6-oxide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as formaldehyde, polymer with (chloromethyl) oxirane and phenol, reaction products with 6H-dibenz[c,e][1,2]oxaphosphorin-6-oxide. (PMN P-00-991; CAS No. 300371-38-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=6).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a),

## Environmental Protection Agency

§ 721.5580

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70179, Dec. 17, 2003]

### § 721.5575 Oxirane, 2,2'-(1,6-hexanediylbis(oxymethylene)) bis-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as oxirane, 2,2'-(1,6-hexanediylbis(oxymethylene))bis- (PMNs P-88-2179 and P-89-539) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), and (b) (concentration set at 0.1 percent).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (b)(1), (b)(2), (c)(1), and (c)(2).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(ii), (b)(1), and (c)(1). The following may be used as an alternative to the technologies in § 721.90(a)(2)(ii): Oil and grease separation.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (k).

(2) *Limitation of revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19238, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5580 Oxirane, 2,2'-[methylenebis(2,6-dimethyl-4,1-phenylene)oxymethylene]]bis-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as oxirane, 2,2'-[methylenebis(2,6-dimethyl-4,1-phenylene)oxymethylene]]bis- (PMN P-97-1011; CAS No. 93705-66-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 0.35 milligram/meter<sup>3</sup> (mg/m<sup>3</sup>).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(ii), (g)(2)(iv), (g)(3)(i), (g)(3)(ii), (g)(4)(i), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

**§ 721.5585**

**40 CFR Ch. I (7–1–10 Edition)**

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 44579, Aug. 20, 1998]

**§ 721.5585 4,4'-(1-methylethylidene)bisphenol, polymer with (chloromethyl)oxirane and a diamine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 4,4'-(1-methylethylidene)bisphenol, polymer with (chloromethyl) oxirane and a diamine (PMN P-97-0916) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) Hazard communication program. Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=2 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81401, Dec. 26, 2000]

**§ 721.5590 Oxirane, [[[1R,2S,5R)-5-methyl-2-methylethyl]cyclohexyl]oxy[methyl]-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as oxirane, [[[1R,2S,5R)-5-methyl-2-(1-methylethyl)cyclohexyl]oxy]methyl]- (PMN P-00-0330; CAS No. 249297-16-3) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15086, Mar. 28, 2003]

**§ 721.5600 Substituted oxirane.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted oxirane (PMN P-83-1157) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i) through (a)(5)(iii), (a)(6)(v), (a)(6)(vi), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(ii), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b) and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable

## Environmental Protection Agency

§ 721.5650

to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (d), (e), (f), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 46774, Nov. 6, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.5625 Oxiranemethanamine, *N,N'*-[methylenebis(2-ethyl-4,1-phenylene)]bis[*N*-(oxiranylmethyl)]-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as oxiranemethanamine, *N,N'*-[methylenebis(2-ethyl-4,1-phenylene)]bis[*N*-(oxiranylmethyl)]- (PMN P-91-411; CAS number 130728-76-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (o), and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44070, Sept. 23, 1992. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5645 Pentane 1,1,1,2,3,4,4,5,5,5,-decafluoro.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as pentane 1,1,1,2,3,4,4,5,5,5,-decafluoro (PMN P-95-638 and SNUN P-97-79; CAS No. 138495-42-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) and uses other than as described in the significant new use notice.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3431, Jan. 22, 1998]

### § 721.5650 Pentanediol light residues.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as pentanediol light residues (PMN P-95-1750) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(o).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.



## § 721.5700

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3431, Jan. 22, 1998]

### § 721.5700 Pentanenitrile, 3-amino-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as pentanenitrile, 3-amino- (PMN P-91-222; CAS number 75405-06-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), during both drumming and transfer of the substance requirements as specified in § 721.63 (a)(5)(i), (a)(5)(ii), and (a)(5)(iii) apply, and during transfer (but not drumming) of the substance, requirements as specified in § 721.63 (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), and (a)(5)(xv) apply following submittal by the company, and written approval by the EPA, of the results of cartridge service life testing performance in accordance with *Interim Recommendations for Determining Organic Vapor Cartridge Service Life for Category 23C Respirators* (available through the TSCA Assistance Office), or equivalent, which demonstrates the effectiveness of the organic vapor cartridge, (a)(6)(v), (b) (concentration set at 1.0 percent), and (c). The requirements specified in § 721.63(a) (4) and (5) apply only during drumming activities and during transfer of liquid PMN substance from a process vessel into a tank, truck, or rail car.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i) are applicable to manufac-

## 40 CFR Ch. I (7-1-10 Edition)

turers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44069, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5708 2-Pentene, 1,1,1,2,3,4,4,5,5,5-decafluoro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-Pentene, 1,1,1,2,3,4,4,5,5,5-decafluoro- (PMN P-95-637; CAS No. 72804-49-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3431, Jan. 22, 1998]

### § 721.5710 Phenacetin.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance phenacetin (CAS No. 62-442) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable

## Environmental Protection Agency

## § 721.5760

to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

### § 721.5713 Phenol - biphenyl polymer condensate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a phenol - biphenyl polymer condensate (PMN P-00-1220) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70179, Dec. 17, 2003]

### § 721.5740 Phenol, 4,4'-methylenebis (2,6-dimethyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as Phenol, 4,4'-methylenebis (2,6-dimethyl- (PMNs P-88-864, P-90-211, and P-94-921; CAS No. 5384-21-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (b) (concentration set at 1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1 percent), (f), (g)(1)(iv), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(iii), and (g)(5). The label and MSDS as required by this paragraph shall also include the fol-

lowing statements: This substance may cause blood effects. This substance may cause chronic effects.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g), (l), and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 33306, Aug. 15, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993; 63 FR 45956, Aug. 28, 1998]

### § 721.5760 Phenol, 4,4'-[methylenebis (oxy-2,1-ethanediylthio)]bis-

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance phenol, 4,4'-[methylenebis(oxy 2,1-ethanediylthio)]bis- (PMN P-87-1760) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (f), (g)(3)(ii), and (g)(4)(iii). The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(ii) *Release to water.* Requirements as specified in § 721.90(a)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: Recordkeeping

## § 721.5762

requirements specified in § 721.125 (a), (b), (c), (f), (g), and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[55 FR 33306, Aug. 15, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.5762 Aromatic aldehyde phenolic resin (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as aromatic aldehyde phenolic resin (PMN P-01-573) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(1), (b)(1), and (c)(1)

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70179, Dec. 17, 2003]

### § 721.5763 Methylenebisbenzotriazolyl phenols.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as methylenebisbenzotriazolyl phenols (P-94-1042) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c). Requirements as specified in § 721.63(a)(5)(i) apply during manufacture of the PMN substance. Requirements as specified in § 721.63 (a)(5)(iii) through (a)(5)(vii) apply during use of the PMN substance.

## 40 CFR Ch. I (7-1-10 Edition)

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iv), (g)(1)(vi), (g)(2)(iii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (1) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (d) and (f) through (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.575(b)(1) apply to this section.

[60 FR 45083, Aug. 30, 1995]

### § 721.5769 Mixture of nitrated alkylated phenols.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a mixture of nitrated alkylated phenols (PMN P-93-987) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where n = 1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45083, Aug. 30, 1995]

### § 721.5775 Phenol, 5-amino-2,4-dichloro-, hydrochloride.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

## § 721.5800

chemical substance identified as phenol, 5-amino-2,4-dichloro-, hydrochloride (PMN P-98-198) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(i), (w)(i), and (x)(i).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44579, Aug. 20, 1998]

### § 721.5780 Phenol, 4,4'-(oxybis(2,1-ethanedithio)bis-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance phenol, 4,4'-(oxybis(2,1-ethanedithio)bis- (PMN P-89-651) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(ix), (g)(2)(iv), and (g)(2)(v).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(r) (82,000 kg; 141,000 kg; and 272,000 kg with testing required at each interval).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and proc-

essors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 39902, Sept. 28, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.5800 Sulfurized alkylphenol.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance described generically as sulfurized alkylphenol (PMN P-89-708) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(1)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## § 721.5820

this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 4578, Feb. 6, 1992. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.5820 Aminophenol.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as aminophenol (P-83-909) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(1)(i)(D) and (g)(2)(v). The provision of § 721.72(g) requiring placement of specific information in an MSDS does not apply when an MSDS is not required under § 721.72(c).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a), (b), (c), (d), (f), and (g).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25989, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.5840 Ethylated aminophenol.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as ethylated aminophenol (P-83-908) is subject to reporting under this section for the significant new uses de-

## 40 CFR Ch. I (7-1-10 Edition)

scribed in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(1)(i)(D) and (g)(2)(v). The provision of § 721.72(g) requiring placement of specific information in an MSDS does not apply when an MSDS is not required under § 721.72(c).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a), (b), (c), (d), (f), and (g).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25989, June 5, 1991. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.5860 Methylphenol, bis(substituted)alkyl.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as methylphenol, bis(substituted)alkyl (P-84-417) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(ii), (g)(1)(iv), (g)(2)(i), and (g)(2)(v).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 720.80 (k) (antioxidant/stabilizer for polymers) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable

## Environmental Protection Agency

## § 721.5900

to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 25991, June 5, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.5867 Substituted phenol.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as substituted phenol (PMNs P-89-1125, P-91-87, P-92-41, P-92-511, P-94-1527, and P-94-1755) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (ingredient in a photoresist formulation).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 23679, Apr. 30, 1998]

### § 721.5880 Sulfur bridged substituted phenols (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance sulfur bridged substituted phenols (PMN P-89-396) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iv) (specifically liver and blood effects), (g)(2)(i), (g)(2)(v), and (g)(5).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The recordkeeping requirements as specified in § 721.125 (a) and (c) through (h) are applicable to manufacturers and importers of this substance. Any statements requiring processors to keep records in § 721.125 do not apply.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32417, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993; 59 FR 40260, Aug. 8, 1994]

### § 721.5900 Trisubstituted phenol (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance trisubstituted phenol (PMN P-85-605) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii) through (a)(5)(vii) and (a)(6)(i), (b) [concentration set at 0.1 percent], and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (d), (e) [concentration set at 0.1 percent], (f), (g)(1)(vii), and (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when a MSDS was not required under § 721.72(c). The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72 (b) and (c), respectively.

**§ 721.5905**

**40 CFR Ch. I (7–1–10 Edition)**

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26111, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.5905 Modified phenolic resin (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a modified phenolic resin (PMN P-01-441) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70179, Dec. 17, 2003]

**§ 721.5908 Modified phenolic resin (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified phenolic resin (PMN P-01-561) is subject to reporting under this section for the significant new use

described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70180, Dec. 17, 2003]

**§ 721.5912 Phenoxazin-5-ium, 3-dialkylamino-7-arylamino-, salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Phenoxazin-5-ium, 3-dialkylamino-7-arylamino-, salt (PMN P-99-0723) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81402, Dec. 26, 2000]

**§ 721.5913 Phenothiazine derivative.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a phenothiazine derivative (PMN P-96-813) is subject to reporting under this section for the significant

## Environmental Protection Agency

## § 721.5920

new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, and importers of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3432, Jan. 22, 1998]

### § 721.5914 Polysubstituted bis phenylazonaphthalene disulfonic acid (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a Polysubstituted bis phenylazonaphthalene disulfonic acid. (PMN P-99-0479) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81402, Dec. 26, 2000]

### § 721.5915 Polysubstituted phenylazopolysubstitutedphenyl dye.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polysubstituted phenylazopolysubstitutedphenyl dye

(PMN P-93-658) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80 (w)(1), (w)(2), (x)(1), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51706, Oct. 4, 1993]

### § 721.5917 Phenyl azo dye (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a phenyl azo dye (PMN P-02-17) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(v)(2), (w)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70180, Dec. 17, 2003]

### § 721.5920 Phenyl(disubstitutedpolycyclic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as phenyl(disubstitutedpolycyclic) (PMN



## § 721.5925

P-92-1337) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Release to water*. Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 10 ppb).

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[58 FR 51706, Oct. 4, 1993]

## § 721.5925 Bis heterocyclic phenylene derivative (generic).

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as bis heterocyclic phenylene derivative (PMN P-01-0432) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80(p) (20,000 kg/yr).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[68 FR 15086, Mar. 28, 2003]

## § 721.5930 Phenylenebis(imino(chlorotriazinyl)imino(substituted naphthyl)azo(substituted phenyl)azo, sodium salt (generic name).

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generi-

## 40 CFR Ch. I (7-1-10 Edition)

cally as phenylenebis(imino(chlorotriazinyl)imino(substituted naphthyl)azo (substituted phenyl) azo, sodium salt (PMN P-95-274) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[61 FR 63739, Dec. 2, 1996]

## § 721.5935 Alkylated nitroso-phenylenediamine (generic).

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as alkylated nitroso-phenylenediamine (PMN P-00-636) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace*. Requirements as specified in § 721.63(a)(1) and (a)(3).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125(a), (b), (c), (d), and (e) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[68 FR 70180, Dec. 17, 2003]

**Environmental Protection Agency**

**§ 721.5970**

**§ 721.5960 *N,N'*-Bis(2-(2-(3-alkyl)thiazoline) vinyl)-1,4-phenylenediamine methyl sulfate double salt (generic name).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as *N,N'*-Bis(2-(2-(3-alkyl)thiazoline) vinyl)-1,4-phenylenediamine methyl sulfate double salt (PMN P-84-913) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e), (f) (concentration set at 1 percent), (g)(1)(iii), (g)(1), (may be lethal if inhaled or in contact with eyes), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[55 FR 26098, June 26, 1990. Redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.5965 Substituted S-phenylthiazole (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted s-phenylthiazole (PMN P-97-1046) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44580, Aug. 20, 1998]

**§ 721.5970 Phosphated polyaryphenol ethoxylate, potassium salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as phosphated polyaryphenol ethoxylate, potassium salt (PMN P-93-1222) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (where N = 600 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27485, May 27, 1994]

**§ 721.5980**

**40 CFR Ch. I (7–1–10 Edition)**

**§ 721.5980 Dialkyl phosphorodithioate phosphate compounds.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as dialkyl phosphorodithioate phosphate compounds (P-90-1642 through 1649) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of these substances is any manner or method of manufacture, import, or processing associated with any use of these substances without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for these substances, the employer becomes aware that any of these substances may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described at § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If these substances are not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before these substances are reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, these substances from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 40214, Aug. 13, 1991, as amended at 56 FR 46729, Sept. 16, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.5985 Fatty alkyl phosphate, alkali metal salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a fatty alkyl phosphate, alkali metal salt (PMN P-99-0385) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81402, Dec. 26, 2000]

**§ 721.5995 Polyalkyl phosphate.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyalkyl phosphate (PMN P-95-1772) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Releases to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 1 ppb).

(ii) [Reserved]

## Environmental Protection Agency

## § 721.6020

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3432, Jan. 22, 1998]

EFFECTIVE DATE NOTE: At 75 FR 29431, May 26, 2010, § 721.5995 was removed, effective July 26, 2010.

### § 721.6000 Tris (2,3-dibromopropyl) phosphate.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance tris (2,3-dibromopropyl) phosphate (CAS Number 126-72-7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Any use.

(b) *Special provisions.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[52 FR 2703, Jan. 26, 1987. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.6005 Rare earth phosphate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as rare earth phosphate (PMNs P-99-1191 and P-99-1192) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15086, Mar. 28, 2003]

### § 721.6020 Phosphine, dialkylphenyl.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as phosphine dialkylphenyl (P-83-1023) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (d), (e) (concentration set at 1 percent), (f), (g)(1)(iii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), and (g)(2)(v). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information in an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Disposal.* Requirements as specified in § 721.85 (a)(2); (b)(2); and (c)(2).

(iv) *Release to Water.* Requirements as specified in § 721.90 (a)(3), (b)(3), and (c)(3).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable

**§ 721.6045**

to manufacturers, importers, and processors of this substance: § 721.125 (a) through (g), (i), (j), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 25991, June 5, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.6045 Phosphinothioic acid, bis(2,4,4-trimethylpentyl)- (9CI).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as phosphinothioic acid, bis(2,4,4-trimethylpentyl)- (9CI) (PMN P-96-1652; CAS No. 132767-86-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 10). When calculating the surface water concentrations according to the instructions in § 721.91, the statement that the amount of the substance that will be released will be calculated before the substance enters control technology does not apply. Instead, if the waste stream containing the substance will be treated using carbon adsorption treatment before release, then the amount of the substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 99 percent removal efficiency may be attributed to such treatment.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3432, Jan. 22, 1998]

**40 CFR Ch. I (7-1-10 Edition)**

**§ 721.6060 Alkylaryl substituted phosphite.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylaryl substituted phosphite (PMN P-91-899) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified at § 721.125(a) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

## Environmental Protection Agency

## § 721.6080

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 31969, July 20, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.6070 Alkyl phosphonate ammonium salts.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkyl phosphonate ammonium salts (PMNs P-93-725 and P-93-726) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 400 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51707, Oct. 4, 1993]

### § 721.6075 Phosphonic acid, 1,1-methylenebis-tetrakis(1-methylethyl) ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as phosphonic acid, 1,1-methylenebis-tetrakis(1-methylethyl) ester (PMN P-95-168) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(2)(i), (g)(2)(v), and (g)(5). The label and MSDS required by this paragraph shall also include the

following statement: This substance may cause mutagenicity.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (h) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3432, Jan. 22, 1998]

### § 721.6078 Substituted ethoxyethylamine phosphonate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted ethoxyethylamine phosphonate (PMN P-95-1950) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3433, Jan. 22, 1998]

### § 721.6080 Phosphonium salt (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance phosphonium salt (PMN Number P-84-820) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1)

**§ 721.6085**

**40 CFR Ch. I (7-1-10 Edition)**

and (a)(3), (b) [concentration set at 1.0 percent], and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (d), (e) [concentration set at 1.0 percent], (f), and (g)(1)(iii) and (g)(2)(i) and (g)(2)(v). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when a MSDS was not required under § 721.72(c). The provisions of § 721.72(g) requiring placement of specific information on a label and MSDS do not apply when a label and MSDS are not required under § 721.72(b) and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26111, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.6085 Phosphonocarboxylate salts.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as phosphonocarboxylate salts (PMNs P-93-722, P-93-723, and P-93-724) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 1000 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51707, Oct. 4, 1993]

**§ 721.6090 Phosphoramidate.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as phosphoramidate (P-89-538) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive, or who have received this substance from the employer within 5 years from the date the employer becomes aware of the new information described under paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

## Environmental Protection Agency

## § 721.6120

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51686, Oct. 4, 1993]

### § 721.6097 Phosphoric acid derivative (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a phosphoric acid derivative (PMN P-95-284) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63739, Dec. 2, 1996]

### § 721.6100 Phosphoric acid, C<sub>6-12</sub>-alkyl esters, compounds with 2-(dibutylamino) ethanol.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as phosphoric acid, C<sub>6-12</sub>-alkyl esters, compounds with 2-(dibutylamino)ethanol (PMN P-90-384) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 700 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c) and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 19239, Apr. 25, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.6110

#### Alkyldi(alkyloxyhydroxypropyl) derivative, phosphoric acid esters, potassium salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkyldi(alkyloxyhydroxypropyl) derivative, phosphoric acid esters, potassium salts (PMN P-91-818) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (o).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45084, Aug. 30, 1995]

### § 721.6120 Phosphoric acid, 1,2-ethanediyl tetrakis(2-chloro-1-methylethyl) ester.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The



§ 721.6140

40 CFR Ch. I (7-1-10 Edition)

chemical substance identified as phosphoric acid, 1,2-ethanediyl tetrakis(2-chloro-1-methylethyl) ester (PMN P-861263) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii), (a)(6)(v), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (use other than as a flame retardant for polyurethane foams).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[55 FR 33307, Aug. 15, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

§ 721.6140 **Dialkyldithiophosphoric acid, aliphatic amine salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a dialkyldithiophosphoric acid, aliphatic amine salt (P-90-1839) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons will receive this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44069, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

§ 721.6160 **Piperazinone, 1,1',1''-[1,3,5-triazine-2,4,6-triyltris(cyclohexylimino)-2,1-ethanediyl]]tris-[3,3,4,5,5-pentamethyl]-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as piperazinone, 1,1',1''-[1,3,5-triazine-2,4,6-

## Environmental Protection Agency

§ 721.6170

triyiltris [(cyclohexylimino)-2,1-ethanediy]]tris-[3,3,4,5,5-pentamethyl]- (PMN P-89-589; CAS number 130277-45-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iv) through (vii), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d) (e) (concentration set at 1.0 percent), (f), (g)(1)(iv), (g)(1)(vi), (g)(1)(viii), (g)(2)(ii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (d), and (f) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44069, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.6165 Polysubstituted piperidine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polysubstituted piperidine (PMN P-93-568) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 30).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3433, Jan. 22, 1998]

### § 721.6167 Piperdinium, 1,1-dimethyl-, chloride.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as piperdinium, 1,1-dimethyl-, chloride. (PMN P-02-207; CAS No. 24307-26-4) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) *Release to water.* Requirements as specified in § 721.90(a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 70180, Dec. 17, 2003]

### § 721.6170 Siloxanes and silicones, Me hydrogen, reaction products with 2,2,6,6-tetramethyl-4-(2-propenyloxy)piperidine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as siloxanes and silicones, Me hydrogen, reaction products with 2,2,6,6-tetramethyl-4-(2-propenyloxy)piperidine (PMN P-95-1891; CAS No. 182635-99-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

**§ 721.6175**

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3433, Jan. 22, 1998]

**§ 721.6175 2-Piperdinone, 1,3-dimethyl-**  
”

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-Piperdinone, 1,3-dimethyl-, (PMN P-97-520 and SNUN 00-397; CAS No. 1690-76-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(iii), (g)(1)(iv), (g)(1)(ix), (g)(2)(i), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (use or processing other than: in enclosed systems (such as hydrocarbon extraction, polymer synthesis, wire enamel resin); electronic industry cleaning solvent; and other precision industry cleaning (such as automobile manufacturing, aerospace, and optics)), (o), and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

**40 CFR Ch. I (7-1-10 Edition)**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this substance.

[63 FR 44580, Aug. 20, 1998, as amended at 67 FR 12882, Mar. 20, 2002]

**§ 721.6176 2-Piperdinone, 1,5-dimethyl-**  
”

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-Piperdinone, 1,5-dimethyl-, (PMN P-97-521 and SNUN 00-398; CAS No. 86917-58-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(iii), (g)(1)(iv), (g)(1)(ix), (g)(2)(i), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (use or processing other than: in enclosed systems (such as hydrocarbon extraction, polymer synthesis, wire enamel resin); electronic industry cleaning solvent; and other precision industry cleaning (such as automobile manufacturing, aerospace, and optics)), (o), and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this substance.

[63 FR 44580, Aug. 20, 1998, as amended at 67 FR 12882, Mar. 20, 2002]

## Environmental Protection Agency

§ 721.6183

### § 721.6178 Alkylaminated polyolefin (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylaminated polyolefin (PMN P-99-1287) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15087, Mar. 28 2003]

### § 721.6180 Polyalkylene glycol polyamide ester phosphate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polyalkylene glycol polyamide ester phosphate (PMN P-98-0903) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81402, Dec. 26, 2000]

### § 721.6181 Fatty acid, reaction product with substituted oxirane, formaldehyde-phenol polymer glycidyl ether, substituted propylamine and polyethylenepolyamines (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as fatty acid, reaction product with substituted oxirane, formaldehyde-phenol polymer glycidyl ether, substituted propylamine and polyethylenepolyamines (PMN P-98-1125) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15087, Mar. 28, 2003]

### § 721.6183 Amides, from ammonium hydroxide - maleic anhydride polymer and hydrogenated tallow alkyl amines, sodium salts, compds. with ethanolamine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as amides, from ammonium hydroxide - maleic anhydride polymer and hydrogenated tallow alkyl amines, sodium salts, compds. with ethanolamine (PMN P-00-0691; CAS No. 208408-03-1) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=80 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

**§ 721.6186**

**40 CFR Ch. I (7–1–10 Edition)**

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15087, Mar. 28, 2003]

**§ 721.6186 Polyamine dithiocarbamate.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyamine dithiocarbamate (PMN No. P-91–1328) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 50 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[58 FR 32239, June 8, 1993]

**§ 721.6193 Polyalkylene polyamine.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as a polyalkylene polyamine (PMN P-89–963) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), (g)(4) (users minimize release to water), and (g)(5) are applicable to manufacturers and importers.

(ii) *Release to water.* Requirements as specified in § 721.90(a)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers and importers of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[62 FR 64740, Dec. 9, 1997]

**§ 721.6196 Hydrochloride salt of a fatty polyalkylene polyamine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Hydrochloride salt of a fatty polyalkylene polyamine (PMN P-99–0618) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81402, Dec. 26, 2000]

**§ 721.6200 Fatty acid polyamine condensate, phosphoric acid ester salts.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as fatty acid polyamine condensate, phosphate ester salts (PMNs P-90–1984 and P-90–1985) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## Environmental Protection Agency

## § 721.6220

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46467, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.6205 Hexamethylenediamine adduct of substituted piperidinyloxy (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as hexamethylenediamine adduct of substituted piperidinyloxy (PMN P-99-0510) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(i), (a)(2)(i), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(5)(viii), (a)(5)(ix), (a)(5)(x), (a)(5)(xi), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(5)(xv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), and (a)(6)(vi), (b) (concentration set at 1.0 percent), and (c). The imperviousness of each item pursuant to paragraph (a)(2)(i) must be demonstrated by actual testing under paragraph (a)(3) and not by manufacturer specifications. Permeation testing shall be conducted according to the American Society for Testing and Materials (ASTM) F739 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases" or its equivalent. Results shall be recorded as a cumulative permeation rate as a function of time, and shall be documented in accordance with ASTM F739 using the format specified in ASTM 1194-89 "Guide for Documenting the Results of Chemical Permeation Test-

ing on Protective Clothing Materials" or its equivalent. Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift. The manufacturer, importer, or processor must submit all test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves. The following gloves have been tested in accordance with the ASTM F739 method and found to satisfy the requirements for use by EPA: Latex (at least 14 mils thick), Nitrile (at least 16 mils thick), and Silvershield (at least 3 mils thick). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 0.2 ug/m<sup>3</sup> as an 8-hour time weighted average verified by actual monitoring data.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iv), (g)(1)(vi), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 15087, Mar. 28, 2003]

### § 721.6220 Aryl sulfonate of a fatty acid mixture, polyamine condensate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an aryl sulfonate of a fatty acid mixture, polyamine condensate (PMN P-91-584) is subject to reporting

## § 721.6440

under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 46467, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

## § 721.6440 Polyamine ureaformaldehyde condensate (specific name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance polyamine ureaformaldehyde condensate (PMN P-87-1456) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4) [concern level of 1 ppb], (b)(4) [concern level of 1 ppb], and (c)(4) [concern level of 1 ppb].

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 26112, June 26, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.6470 Polyaminopolyacid.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## 40 CFR Ch. I (7-1-10 Edition)

chemical substance identified generically as a polyaminopolyacid (PMN No. P-92-491) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 500 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[58 FR 32240, June 8, 1993]

## § 721.6475 Alkyl polycarboxylic acids, esters with ethoxylated fatty alcohols.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkyl polycarboxylic acids, esters with ethoxylated fatty alcohols (PMNs P-96-554/555/556/557/558/559) are subject to reporting under this section for the significant new uses described in paragraph (a)(1)(i) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Chemical substance and significant new uses subject to reporting.* The chemical substances identified generically as alkyl polycarboxylic acids, esters

## Environmental Protection Agency

§ 721.6479

with ethoxylated fatty alcohols (PMN P-96-560/561/564/565) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(i) The significant new uses are:

(A) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(B) [Reserved]

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3433, Jan. 22, 1998]

### § 721.6477 Alkyl polycarboxylic acids, esters with ethoxylated fatty alcohols, reaction products with maleic anhydride.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkyl polycarboxylic acids, esters with ethoxylated fatty alcohols, reaction products with maleic anhydride (PMNs P-96-399/400/401/402/403/404) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3434, Jan. 22, 1998]

### § 721.6479 Tetrahydroheteropolycycle (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Tetrahydroheteropolycycle (PMN P-97-0766) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1)(i), (a)(2)(i), (a)(3), (a)(4), (a)(5)(ii) (if no data on cartridge service life testing has been reviewed and approved by EPA), (a)(5)(xii) (if data on cartridge service life testing has been reviewed and approved by EPA), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), and (a)(6)(vi), (b) (concentration set at 1.0 percent), and (c). The imperviousness of each item pursuant to paragraph (a)(2)(i) must be demonstrated by actual testing under paragraph (a)(3) and not by manufacturer specifications. Permeation testing shall be conducted according to the American Society for Testing Materials (ASTM) F739 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases." Results shall be recorded as a cumulative permeation rate as a function of time, and shall be documented in accordance with ASTM F739 using the format specified in ASTM 1194-89 "Guide for Documenting the Results of Chemical Permeation Testing on Protective Clothing Materials." Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift. The manufacturer, importer, or processor must submit all test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves. The following gloves have been tested in accordance with the ASTM F739 method and found to satisfy the requirements for use by EPA: Latex (at least 14 mils thick), Nitrile (at least 16 mils thick), and Silvershield (at least 3 mils thick). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions



**§ 721.6485**

listed in the TSCA section 5(e) consent order for this substance. The NCEL is 1.0 ug/m<sup>3</sup> as an 8-hour time weighted average verified by actual monitoring data.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (12,300 kilograms).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81402, Dec. 26, 2000]

**§ 721.6485 Hydroxy terminated polyester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a hydroxy terminated polyester (PMN P-95-1213) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3434, Jan. 22, 1998]

**40 CFR Ch. I (7-1-10 Edition)**

**§ 721.6490 Alkyl polyetheramines. phenyl**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkyl phenyl polyetheramines (PMNs P-95-1650/1651/1652/1653) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3434, Jan. 22, 1998]

**§ 721.6493 Amidoamine modified polyethylene glycol (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an amidoamine modified polyethylene glycol (PMN P-99-0645) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81403, Dec. 26, 2000]

## Environmental Protection Agency

§ 721.6498

### § 721.6495 Aliphatic polyisocyanate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an aliphatic polyisocyanate (PMN P-95-1347) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3434, Jan. 22, 1998]

### § 721.6498 Modified polyisocyanates (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified polyisocyanates (PMN P-96-1428) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 0.05 mg/m<sup>3</sup>.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), and (g)(5). The following statements shall appear on each label as specified in § 721.72(b) and the MSDS as specified in § 721.72(c): Warnings. Exposure to diisocyanates may cause the

following human health effects: Skin irritation and allergic reactions, respiratory irritation, respiratory sensitization, and lung toxicity; some diisocyanates also may cause cancer. The likelihood that these effects will occur depends on a number of factors; among them, the level of exposure, frequency of exposure, part of the body exposed, and sensitivity of the exposed individual. Symptoms of allergic reaction and respiratory sensitization include rashes, cough, shortness of breath, asthma, chest tightness and other breathing difficulties. There is uncertainty as to the mechanism by which sensitization occurs. In sensitized individuals, exposure to even small amounts of diisocyanates (below government-recommended workplace exposure levels) may cause allergic respiratory reactions like asthma and severe breathing difficulties. It is especially important to note that contact with skin may lead to respiratory sensitization or cause other allergic reactions. In some cases, the effects of diisocyanate exposure may be immediate and life-threatening; in others, the effects may be delayed and occur hours after the exposure has ended. Repeated or prolonged exposure to diisocyanates may also cause irritation to eyes, skin, respiratory tract and lungs, as well as adverse chronic lung effects, like decreased lung capacity and function. Individuals experiencing shortness of breath, tightness in the chest or other problems breathing should seek immediate medical attention. When using this substance the following protective measures should be used: In workplaces where individuals handle diisocyanates or coatings or other formulations that contain them, an industrial hygiene and safety program should be operative. Important components of this program include: Hazard communication and training on safe handling practices; use of efficient and well-maintained application equipment, engineering controls and personal protective equipment; housekeeping procedures including spill prevention and cleanup practices; and, if feasible, means to measure airborne levels of polyisocyanates and diisocyanates. During spray applications, workers should take precautions

§ 721.6505

40 CFR Ch. I (7-1-10 Edition)

to avoid breathing vapors, mists or aerosols. Inhalation exposures should be limited to < 0.05 mg/m<sup>3</sup> as an 8-hour time-weighted average (TWA) for combined polyisocyanates and diisocyanates. Engineering controls should serve as the first, most effective means of reducing airborne polyisocyanate and diisocyanate concentrations; an appropriate National Institute for Occupational Safety and Health/Mine Safety and Health Administration (NIOSH/MSHA) approved respirator should be used as a secondary tool to lower exposures. Currently, downdraft spray booths and high-volume low-pressure (HVLP) spray guns appear to offer the most efficient technology to reduce inhalation exposures; a maintenance program should always be used to ensure optimal operating efficiencies. To limit dermal contact, individuals should wear impermeable gloves, protective clothing and goggles or glasses with side shields.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 44580, Aug. 20, 1998]

§ 721.6505 **Polymers of C<sub>13</sub>C<sub>15</sub> oxoalcohol ethoxolates.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as polymers of C<sub>13</sub>C<sub>15</sub> oxoalcohol ethoxolates (PMNs P-96-950/951) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3434, Jan. 22, 1998]

§ 721.6515 **Polymer of polyalkylenepolyol and trisubstituted phenol (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polymer of polyalkylenepolyol and trisubstituted phenol (PMN P-98-1016) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81403, Dec. 26, 2000]

§ 721.6520 **Acrylamide, polymer with substituted alkylacrylamide salt (generic name).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as acrylamide, polymer with substituted alkylacrylamide salt (PMN P-87-794) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

## Environmental Protection Agency

## § 721.6620

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(p) (limit set at 216,700 kg).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: Recordkeeping requirements specified in §721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[55 FR 33303, Aug. 15, 1990. Redesignated at 55 FR 52276, Dec. 21, 1990. Further redesignated at 58 FR 29946, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.6540 Acrylamide, polymers with tetraalkyl ammonium salt and polyalkyl, aminoalkyl methacrylamide salt.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as acrylamide, polymers with tetraalkyl ammonium salt and polyalkyl, amino alkyl methacrylamide salt (PMNs P-88-2100 and P-88-2169) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is:

(i) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[57 FR 46468, Oct. 8, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.6560 Acrylic acid, polymer with substituted ethene.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as acrylic acid, polymer with substituted ethene (PMN P-91-521) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(4), (b)(4), and (c)(4) (N = 200 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[57 FR 46468, Oct. 8, 1992, as amended at 53 FR 34204, June 23, 1993]

### § 721.6620 Alkanaminium, polyalkyl-[(2-methyl-1-oxo-2-propenyl)oxy] salt, polymer with acrylamide and substituted alkyl methacrylate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkanaminium, polyalkyl-[(2-methyl-1-oxo-2-propenyl)oxy] salt, polymer with acrylamide and substituted alkyl methacrylate (PMN P-87-252) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(p) (production limit set at 680,000 kg).

(ii) *Release to water.* Requirements as specified in §721.85 (a)(4), (b)(4) and (c)(4) (concentration set at 40 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in §721.125 (a),

**§ 721.6660**

**40 CFR Ch. I (7–1–10 Edition)**

(b), (c), (i), and (j) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44070, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.6660 Polymer of alkanepolyol and polyalkylpolyisocyanatocarbomonocycle, acetone oxime-blocked (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polymer of alkanepolyol and polyalkylpolyisocyanatocarbomonocycle, acetone oxime-blocked (PMN P-88-1658) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26100, June 26, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.6680 Alkanoic acid, butanediol and cyclohexanealkanol polymer (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance alkanoic acid, butanediol, and cyclohexanealkanol

polymer (PMN P-89-672) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows.

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q) (293,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (h) and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

## Environmental Protection Agency

§ 721.6980

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32417, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.6900 Polymer of bisphenol A diglycidal ether, substituted alkenes, and butadiene.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as polymer of bisphenol A diglycidal ether, substituted alkenes, and butadiene (PMNs P-90-244 and P-90-245) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 15791, Apr. 17, 1991. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.6920 Butyl acrylate, polymer with substituted methyl styrene, methyl methacrylate, and substituted silane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as butyl acrylate, polymer with substituted methyl styrene, methyl methacrylate, and substituted silane (PMN P-91-272) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(i), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 per cent), (f), (g)(1)(i), (g)(1)(ii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (volume set at 90,000 kg), (volume set at 512,000 kg), (volume set at 1,235,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44070, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

### § 721.6980 Dimer acids, polymer with polyalkylene glycol, bisphenol A-diglycidyl ether, and alkylolenepolyols polyglycidyl ethers (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance dimer acids, polymer with polyalkylene glycol, bisphenol A-diglycidyl ether, and alkylolenepolyols polyglycidyl ethers (PMN P-86-628) is subject to reporting under this section for the significant

## § 721.7000

## 40 CFR Ch. I (7–1–10 Edition)

new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3), (b) [concentration set at 0.1 percent], and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (d), (e) [concentration set at 0.1 percent], (f), and (g)(1)(vi) and (g)(1)(vii), (g)(2)(i) and (g)(2)(v), (g)(4)(i), and (g)(5). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when a MSDS was not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) and (y).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (a)(2) and (b)(1) and (b)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26109, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7000 Polymer of disodium maleate, allyl ether, and ethylene oxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polymer of disodium maleate, allyl ether, and ethylene oxide (P-91-1086) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture,

import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44071, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7020 Distillates (petroleum), C(3-6), polymers with styrene and mixed terpenes (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

## § 721.7046

chemical substance distillates (petroleum), C(3-6), polymers with styrene and mixed terpenes (PMN P-89-676) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows.

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (h) and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32414, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7046 Formaldehyde, polymer with substituted phenols, glycidyl ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as formaldehyde, polymer with substituted phenols, glycidyl ether (PMN P-93-955) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply once the substance is a component of a highly densified tablet formulation of an epoxy molding compound.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c). Requirements as specified in § 721.63 (a)(5)(i) apply during manufacturing only. Requirements as specified in § 721.63(a)(5)(i) through (a)(5)(vii) apply during processing for workers exposed greater than 17 days per year or during use.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(2)(i) through (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (b), (l), and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) and (k) are applicable to manufacturers, importers, and processors of this substance.



## § 721.7160

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[60 FR 45084, Aug. 30, 1995, as amended at 62 FR 42692, Aug. 8, 1997]

### § 721.7160 2-Oxepanone, polymer with 4,4'-(1-methylethylidene)bisphenol and 2,2-[(1-methylethylidene)bis(4,1-phenyleneoxymethylene)]bisoxirane, graft.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 2-oxepanone, polymer with 4,4'-(1-methylethylidene)bisphenol and 2,2-[(1-methylethylidene)bis(4,1-phenyleneoxymethylene)]bisoxirane, graft (PMN P-88-2582) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(viii), (a)(5)(ix), (a)(5)(x), (a)(5)(xi), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

## 40 CFR Ch. I (7–1–10 Edition)

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 33306, Aug. 15, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7200 Perfluoroalkyl aromatic carbamate modified alkyl methacrylate copolymer.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as perfluoroalkyl aromatic carbamate modified alkyl methacrylate copolymer (PMN P-87-1555) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent for cancer; 1.0 percent for other effects), (f), (g)(1)(ii), (g)(2)(ii), and (g)(5). In addition, the following human health hazard statement shall appear on each label and MSDS required by this section: This substance may cause lung effects.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (o) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (f) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44071, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7210 Epoxidized copolymer of phenol and substituted phenol.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as epoxidized copolymer of phenol and substituted phenol (PMN P-91-598) is

## Environmental Protection Agency

## § 721.7250

subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply once the substance is a component of a highly densified tablet formulation of an epoxy molding compound.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a) through (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44071, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993; 62 FR 42692, Aug. 8, 1997]

### § 721.7220 Polymer of substituted phenol, formaldehyde, epichlorohydrin, and disubstituted benzene.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polymer of substituted phenol, formaldehyde, epichlorohydrin, and disubstituted benzene (PMN P-89-1104) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(v), (g)(4)(i), and (g)(5). The following additional human hazard precautionary statement shall appear on each label as specified in § 721.72(b): Disposal restrictions apply.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), and (c)(1).

(v) *Release to water.* Requirements as specified in § 721.90(c)(2)(v), or diatomaceous earth filtration.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19242, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7250 Polyaziridinyl ester of an aliphatic alcohol (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyaziridinyl ester of an aliphatic alcohol (PMN P-01-97) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

**§ 721.7255**

**40 CFR Ch. I (7–1–10 Edition)**

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.575(b)(1) apply to this section.

[68 FR 70180, Dec. 17, 2003]

**§ 721.7255 Polyethyleneamine crosslinked with substituted polyethylene glycol (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polyethyleneamine crosslinked with substituted polyethylene glycol with substituted polyethylene glycol (PMN P-01-833) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (absorbent polymer).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70180, Dec. 17, 2003]

**§ 721.7260 Polymer of polyethylene-polyamine and alkanediol diglycidyl ether.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polymer of polyethylenepolyamine and alkanediol diglycidyl ether (PMN P-89-810) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows.

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health or the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) which includes a written listing of safety data for this substance within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS containing a written listing of safety data for this chemical and the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (2,000,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (c), and (h) (In addition, each manufacturer, importer and processor of this substance shall maintain for five years from the date of their creation, copies of material safety data sheets required under paragraph (a)(2)(i)(A) of this section).

(2) *Limitations or revocation of certain notification requirements.* The provisions

## Environmental Protection Agency

## § 721.7285

of § 721.185 apply to this significant new use rule.

[55 FR 46774, Nov. 6, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.7270 1-propanaminium, 3-amino-, N,N,N-trimethyl-N-soya acyl derivs., chloride.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-propanaminium, 3-amino-, N,N,N-trimethyl-N-soya acyl derivs., chloride (PMN P-01-646; CAS No. 391232-99-8) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725 apply to this section.

[68 FR 70181, Dec. 17, 2003]

### § 721.7280 1,3-Propanediamine, N,N'-1,2-ethanedylbis-, polymer with 2,4,6-trichloro-1,3,5-triazine, reaction products with N-butyl-2,2,6,6-tetramethyl-4-piperidinamine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,3-propanediamine, N,N'-1,2-ethanedylbis-, polymer with 2,4,6-trichloro-1,3,5-triazine, reaction products with N-butyl-2,2,6,6-tetramethyl-4-piperidinamine (PMN P-89-632) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) Protection in the workplace. Requirements as specified in § 721.63 (a)(1),

(a)(2)(iii), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a) through (f), (g)(1)(iv), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 33308, Aug. 15, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993; 60 FR 65582, Dec. 20, 1995]

### § 721.7285 Amines, N-cocoalkyltrimethylenedi-, citrates.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as amines, N-cocoalkyltrimethylenedi-, citrates. (PMN P-93-880; CAS No. 189120-63-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of this substance.

**§ 721.7286**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44581, Aug. 20, 1998]

**§ 721.7286 Amines, N-tallowalkyltripropylene- tetra-, citrates.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified as amines, N-tallowalkyltripropylene- tetra-, citrates (PMN P-93-881; CAS No. 189120-62-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44581, Aug. 20, 1998]

**§ 721.7290 Propanoic acid, 2-(trimethoxysilyl)-, ethyl ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as propanoic acid, 2-(trimethoxysilyl)-, ethyl ester (PMN P-01-22; CAS No. 137787-41-8) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90(a)(4), (b)(4), and (c)(4) (N=10).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

**40 CFR Ch. I (7-1-10 Edition)**

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70181, Dec. 17, 2003]

**§ 721.7375 Potassium salt of polyolefin acid.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a potassium salt of polyolefin acid (PMN P-97-417) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3434, Jan. 22, 1998]

**§ 721.7378 Substituted polyoxyethylene.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted polyoxyethylene (PMN P-93-1654) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (use as an emulsifier for paint and adhesives).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## Environmental Protection Agency

§ 721.7480

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3434, Jan. 22, 1998]

### § 721.7440 Polyalkylenepolyol alkylamine. (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polyalkylenepolyol alkylamine (PMN P-89-483) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(ix), (g)(2)(i), (g)(2)(iii), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 33307, Aug. 15, 1990, as amended at 55 FR 52276, Dec. 21, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7450 Aromatic amine polyols.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as aromatic amine polyols (PMNs P-93-212 and P-93-213) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51686, Oct. 4, 1993]

### § 721.7480 Isocyanate terminated polyols.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as isocyanate terminated polyols (P-90-404, P-90-405, and P-90-406) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(ii), (b) (concentration set at 1.0 percent) and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5). The following additional human health hazard statements shall appear on each label and MSDS required by this paragraph: The substance may cause eye irritation, lung effects, dermal sensitization, pulmonary sensitization, or systemic effects.

## § 721.7500

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (volume set at 245,000 kg; aggregate manufacture and import volume for PMNs P-90-404, P-90-405, and P-90-406 combined).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 40214, Aug. 13, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.7500 Nitrate polyether polyol (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance nitrate polyether polyol (PMN P88-2540) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows.

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into a Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the em-

## 40 CFR Ch. I (7-1-10 Edition)

ployer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (h) and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32418, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

## § 721.7600 Alkyl(heterocyclicyl) phenylazohetero monocyclic polyone (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance alkyl (heterocyclicyl) phenylazohetero monocyclic polyone (PMN P-85-1370) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv) through (a)(5)(vii), (a)(6)(i) through (a)(6)(iii), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (d), (e) (concentration set at 1.0 percent), (f) and (g)(1)(ix), (g)(2)(i) through (g)(2)(v) and (g)(4). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(g) (as intermediates to manufacture dyes for coloring pulp or paper only) and (q).

(iv) *Disposal.* Requirements as specified in §721.85 (a)(1), (b)(1) and (c)(1).

(v) *Release to water.* Requirements as specified in §721.90 (a)(2)(iv), (b)(2)(iv) and (c)(2)(iv).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in §721.125 (a) through (f), (i), (j) and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this significant new use rule.

[55 FR 32418, Aug. 9, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.7620 Alkyl(heterocyclic) phenylazohetero monocyclic polyone, (alkylimidazolyl methyl) derivative (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance alkyl (heterocyclic) phenylazohetero monocyclic polyone, ((alkylimidazolyl) methyl) derivative (PMN P-86-136) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in §721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv) through (a)(5)(vii), (a)(6)(i), (a)(6)(ii) and (a)(6)(iii), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in §721.72 (b)(2), (d), (e) (concentration set at 1.0 percent), (f) and (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). The provisions of §721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under §721.72 (a) and (c), re-

spectively. The provision of §721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under §721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80 (g), (k) and (q). The term intermediate as used in §721.80(g) is defined as intermediate for manufacture of dyes for coloring pulp or paper.

(iv) *Disposal.* Requirements as specified in §721.85 (a)(1), (b)(1) and (c)(1).

(v) *Release to water.* Requirements as specified in §721.90 (a)(2), (b)(2) and (c)(2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in §721.125 (a) through (c), (e), (f), (i) and (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of §721.1725(b)(1) apply to this section.

[55 FR 32418, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.7655 Alkylsulfonium salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylsulfonium salt (PMN P-93-1166) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in §721.90 (a)(4), (b)(4), and (c)(4) (where N = 50 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a),



## § 721.7700

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27485, May 27, 1994]

### § 721.7700 Poly(oxy-1,2-ethanediyl), $\alpha$ -hydro- $\omega$ -(oxiranylmethoxy)-, ether with 2-ethyl-2-(hydroxymethyl)-1,3-propanediol (3:1).

(a) Chemical substance and significant new uses subject to reporting. (1) The chemical substance identified as poly(oxy-1,2-ethanediyl), $\alpha$ -hydro- $\omega$ -(oxiranylmethoxy)-, ether with 2-ethyl-2-(hydroxymethyl)-1,3-propanediol (3:1) (PMN P-88-2188) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), and (b) (concentration set at 0.1 percent).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (b)(1), (b)(2), (c)(1), and (c)(2).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(ii), (b)(1), and (c)(1). The following may be used as alternative to the technologies in § 721.90(a)(2)(ii): Oil and grease separation.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (k).

(2) *Limitation of revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

## 40 CFR Ch. I (7-1-10 Edition)

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19240, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7710 Polyepoxy polyol.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyepoxy polyol (PMN P-93-364) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27485, May 27, 1994]

### § 721.7720 Poly(oxy-1,2-ethanediyl), $\alpha,\alpha'$ -[(1-methylethylidene) di-4,1-phenylene] bis [ $\omega$ -(oxiranylmethoxy)-.

(a) Chemical substance and significant new uses subject to reporting. (1) The chemical substance identified as poly(oxy-1,2-ethanediyl),  $\alpha,\alpha'$ -[(1-methylethylidene) di-4,1-phenylene] bis [ $\omega$ -(oxiranylmethoxy)- (PMN P-88-2181) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), and (b) (concentration set at 0.1 percent).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii),

## Environmental Protection Agency

## § 721.7780

(g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (b)(1), (b)(2), (c)(1), and (c)(2).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(ii), (b)(1), and (c)(1). The following may be used as an alternative to the technologies in § 721.90(a)(2)(ii): Oil and grease separation.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (k).

(2) *Limitation of revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19240, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.7770

#### **Alkylphenoxypoly(oxyethylene) sulfuric acid ester, substituted amine salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as alkyl phenoxypoly(oxyethylene) sulfuric acid ester, substituted amine salt (PMN P-92-396) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(iii) *Release to water.* Requirements as specified in § 721.90(a)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51707, Oct. 4, 1993]

### § 721.7780 Poly[oxy(methyl-1,2-ethanediyl)], $\alpha,\alpha'$ -(2,2-dimethyl-1,3-propanediyl)bis[ $\omega$ -(oxiranymethoxy)-

(a) Chemical substance and significant new uses subject to reporting. (1) The chemical substance identified as poly[oxy(methyl-1,2-ethanediyl)],  $\alpha,\alpha'$ -(2,2-dimethyl-1,3-propanediyl)bis[ $\omega$ -(oxiranymethoxy)- (PMN P-88-2180) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii), (a)(5)(ix), (a)(6)(ii), and (b) (concentration set at 0.1 percent).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vi), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (b)(1), (b)(2), (c)(1), and (c)(2).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(2)(ii), (b)(1), and (c)(1). The following may be used as an alternative to the technologies in § 721.90(a)(2)(ii): Oil and grease separation.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable

§ 721.7785

40 CFR Ch. I (7-1-10 Edition)

to manufacturers, importers, and processors of this substance: § 721.125 (a) through (k).

(2) *Limitation of revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19239, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

§ 721.7785 **Substituted alkyl aminomethylene polyphosphonic acid, salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted alkylamino methylene polyphosphonic acid, salt (PMN P-97-1095) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44581, Aug. 20, 1998]

§ 721.8079 **Isophorone diisocyanate neopentyl glycol adipate polyurethane prepolymer.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as isophorone diisocyanate neopentyl glycol adipate polyurethane prepolymer (PMN P-94-1743) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. Non-spray uses are exempt from the provisions of this rule.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(viii), (a)(5)(ix), (a)(5)(x), (a)(5)(xi), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), and (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5). Manufacturers, importers, and processors who implement the product stewardship provisions of the TSCA section 5(e) consent order for these substances are exempt from the requirements of § 721.63 and § 721.72.

(iii) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance. Manufacturers, importers, and processors who implement the product stewardship provisions and keep records as required by the TSCA section 5(e) consent order for these substances are exempt from the requirements of § 721.125.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

(4) *Applicability of § 721.5.* The provisions of § 721.5 do not apply to manufacturers, importers, and processors, implementing the product stewardship provisions in the TSCA section 5(e) consent order for this substance.

[63 FR 3435, Jan. 22, 1998]

§ 721.8082 **Polyester polyurethane acrylate.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

§ 721.8095

chemical substance identified generically as polyester polyurethane acrylate (PMN P-93-498) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51686, Oct. 4, 1993]

### § 721.8085 Reaction product of substituted aromatic diol, formaldehyde and alkanolamine, propoxylated (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as reaction product of substituted aromatic diol, formaldehyde and alkanolamine, propoxylated (PMN P-00-0202) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15088, Mar. 28, 2003]

### § 721.8090 Polyurethane polymer.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyurethane polymer (P-94-47) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(viii) through (a)(5)(xi), (a)(6)(ii), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(2)(i) through (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[60 FR 45084, Aug. 30, 1995]

### § 721.8095 Silylated polyurethane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a silylated polyurethane (PMN P-95-1356) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## § 721.8100

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3435, Jan. 22, 1998]

### § 721.8100 Potassium N,N-bis (hydroxyethyl) cocoamine oxide phosphate, and potassium N,N-bis (hydroxyethyl) tallowamine oxide phosphate.

(a) *Chemical substances and significant new use subject to reporting.* (1) The following chemical substances, identified by their chemical names and CAS Number are subject to reporting under this part for the significant new use identified in paragraph (a)(2) of this section: Potassium N,N-bis (hydroxyethyl) cocoamine oxide phosphate (CAS Number 855712-26-1), and potassium N,N-bis (hydroxyethyl) tallowamine oxide phosphate (CAS Number 855712-27-2).

(2) The significant new use is: Use in a consumer product at concentrations greater than five percent by weight.

(b) *Specific Requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Definitions.* In addition to the definitions in § 721.3, the following definitions apply to this section:

“Consumer” means any natural person who uses products for personal rather than business purposes.

“Consumer product” means any chemical substance which is directly, or as part of a mixture, sold or made available to consumers for their use in or around a permanent or temporary household or residence, in or around a school, or in recreation.

(2) *Persons who must report.* The provisions of § 721.5 apply to determine persons who must report under this section, except § 721.5(a)(2) does not apply to a person who intends to distribute either of the substances in commerce as part of a mixture at concentrations of five percent or less by weight of the mixture.

(3) *Notice requirements and procedures.* Section 721.10 applies to this section,

## 40 CFR Ch. I (7–1–10 Edition)

except a person submitting a notice must complete only Parts I and II of the notice form.

[49 FR 35018, Sept. 5, 1984. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.8130 Propanamide, -(2-hydroxyethyl)-3-methoxy-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as propanamide, -(2-hydroxyethyl)-3-methoxy- (PMN P-01-144; CAS No. 35544-45-7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (organic stripper additive).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70181, Dec. 17, 2003]

### § 721.8140 Substituted propane (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted propane (PMN P-01-298) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (polymer additive).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## Environmental Protection Agency

§ 721.8155

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70181, Dec. 17, 2003]

### § 721.8145 Propane,1,1,1,2,2,3,3-heptafluoro-3-methoxy-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as propane,1,1,1,2,2,3,3-heptafluoro-3-methoxy- (PMN P-01-320; CAS No. 375-03-1) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified § 721.80(j) (heating transfer fluid and a refrigerant) and (s) (100,000 kg)

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70181, Dec. 17, 2003]

### § 721.8153 Di-substituted propanedione (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as di-substituted propanedione (PMN P-97-94) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(2)(i), (g)(2)(v). The following statement shall appear on each label as specified in § 721.72(b) and the MSDS as specified in § 721.72(c): This substance is expected to be dermally absorbed and may cause effects to the liver, kidney, adrenal glands, and the heart.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 44581, Aug. 20, 1998]

### § 721.8155 Propanenitrile, 3-[amino, N-tallowalkyl] dipropylene- and tripropylene- and propanenitrile, 3-[amino, (C<sub>14-18</sub> and C<sub>16-18</sub> unsaturated alkyl)] trimethylenedi-, dipropylene-, and tripropylene-

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as propanenitrile, 3-[amino, N-tallowalkyl] dipropylene- (PMN P-94-1238), propanenitrile, 3-[amino, N-tallowalkyl] tripropylene- (PMN P-94-1239), propanenitrile, 3-[amino, (C<sub>14-18</sub> and C<sub>16-18</sub> unsaturated alkyl)] trimethylenedi- (PMN P-94-1241), propanenitrile, 3-[amino, (C<sub>14-18</sub> and C<sub>16-18</sub> unsaturated alkyl)] dipropylene- (PMN P-94-1242), and propanenitrile, 3-[amino, (C<sub>14-18</sub> and C<sub>16-18</sub> unsaturated alkyl)] tripropylene- (PMN P-94-1243) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## §721.8160

(i) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in §721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[60 FR 11044, Mar. 1, 1995]

### §721.8160 Propanoic acid, 2,2-dimethyl-, ethenyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as propanoic acid, 2,2-dimethyl-, ethenyl ester (PMN P-89-1058) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this section do not apply once the substance has been incorporated into a polymer matrix with the level of residual monomer below 0.1 percent.

(2) The significant new uses are: (i) *Protection in the workplace.* Requirements as specified in §721.63 (a)(1), (a)(2)(i) (There must be no permeation of the substance greater than 0.02 µg/min · cm<sup>2</sup> after 8 hours of testing in accordance with the most current version of the American Society for Testing and Materials ASTM F739 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases." For conditions of exposure which are intermittent, gloves may be tested in accordance with the most current version of ASTM F1383 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases Under Conditions of Intermittent Contact," provided the contact time in testing is greater than or equal to the expected duration of dermal contact, and the purge time used in testing is less than or equal to the expected duration of noncontact during the intermittent cycle of dermal expo-

## 40 CFR Ch. I (7-1-10 Edition)

sure in the workplace. If ASTM F1383 is used for testing, manufacturers, importers, and processors must submit to the Agency a description of worker activities involving the substance which includes daily frequencies and durations of potential worker exposures. The results of all glove permeation testing must be reported in accordance with the most current version of ASTM F1194 "Guide for Documenting the Results of Chemical Permeation Testing of Protective Clothing Materials." Manufacturers, importers, and processors must submit all test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves. The following gloves have been tested in accordance with the ASTM F739 method and found by EPA to satisfy the requirements for continuous use: Ansell Edmont/15-554/PVA, 0.08 cm thick; and Ansell Edmont/4h/PE/EVOH/PE laminate gloves, 0.006 cm thick. Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift. The following gloves have been tested in accordance with the ASTM 1383 method and found by EPA to satisfy the requirements for intermittent use: North/B-161-R/Butyl rubber gloves, 0.04 cm thick, time period tested 2 min/h. The gloves listed may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift unless based on its review of data from the ASTM 1383 method, the company's personal protective equipment required under this paragraph, and other appropriate information, the Agency approves, in writing, a time period of greater duration.), (a)(2)(ii) (With the exception of laboratory activities, full body chemical protective clothing is required for any worker activity in which the substance is reasonably likely to contact the worker in the following state(s): Open liquid pool or solid of greater than 5 kg; liquid spray or splash; mist; aerosol dust; or any worker activity which has the potential for contact with the substance for more than 10 min/h. At a minimum, a chemical protective apron is required for any worker activity with potential for contact

with the substance which is not covered by this paragraph), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii) (if cartridge service life testing is not available), (a)(5)(xii) or (a)(5)(xiii) (if data on cartridge service life testing has been reviewed and approved in writing by EPA), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), and (a)(6)(v). As an alternative to the respiratory requirements in this section, manufacturers, importers, and processors may use the New Chemical Exposure Limits provisions, including sampling and analytical methods which have previously been approved by EPA for this substance, found in the 5(e) consent order for this substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (h)(1)(vi) (The following additional statements shall appear on each label required by this paragraph: The health effects of this material have not been fully determined but are currently being tested. EPA is concerned however, that this material may have serious chronic health and environmental effects. When using this material, use eye and skin protection, which includes gloves which have been determined to be impervious to this substance. Use respiratory protection, unless workplace airborne concentrations are maintained at or below an 8-h time weighted average (TWA) of 1 ppm, when there is a likelihood of exposure in the work area from dust, mist, smoke or vapor), (h)(2)(ii)(F), (h)(2)(ii)(G), (h)(2)(ii)(I), (h)(2)(iii)(A), (h)(2)(iii)(B), (h)(2)(iii)(C), (h)(2)(iii)(E), (h)(2)(iv)(A), (h)(2)(iv)(B)). The following additional statements shall appear on each MSDS required by this paragraph: This substance may cause moderate skin irritation. This substance may cause neurotoxicity. When using this substance, use respiratory protection, unless workplace airborne concentrations are maintained at or below an 8-h TWA of 1 ppm.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 40 ppb). When calculating the surface water concentrations according to the instructions in § 721.91,

the statement in paragraph (a)(4) that the amount of the substance that will be released will be calculated before the substance enters control technology does not apply. Instead, if the waste stream containing the substance will be treated before release, then the amount of the substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 75 percent removal efficiency may be attributed to such treatment. In addition, when the substance is released in combination with the substances hexanedioic acid, diethenyl ester, hexanoic acid, 2-ethyl-, ethenyl ester, and neononanoic acid, ethenyl ester, the quotient from the formula referenced in this section shall not exceed the average of the quotient applicable to the other substances weighted by the proportion of each substance present in the total daily amount released.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance. Manufacturers, importers, and processors of the substance must document that the substance has been incorporated into a polymer matrix with the level of residual monomer below 0.1 percent if this section does not apply as described in paragraph (a)(1) of this section.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 51707, Oct. 4, 1993]

#### § 721.8175 1-Propanol, 3-mercapto-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-propanol, 3-mercapto (PMN P-85-433; CAS No. 19721-22-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.



(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(v), (b) (concentration set at 1%), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1%), (f), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (a)(3), (b)(1), (b)(2), (b)(3), (c)(1), (c)(2), and (c)(3). In addition, a method of disposal described in § 721.85 (a), (b), and (c) shall include: Release to an evaporation pond.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a) through (j).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[67 FR 17649, Apr. 11, 2002]

**§ 721.8225 2-Propenamide, N-[3-dimethylamino)propyl]-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propenamide, N-[3-dimethylamino)propyl]- (PMN P-86-1602) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63(a)(1), (a)(2)(i), (a)(3), (a)(6)(ii), (b) (concentration set at 0.1 percent) and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72(a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(v), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(v), (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (o) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (where N = 300 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i) and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 40215, Aug. 13, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.8250 1-Propanol, 3,3'-oxybis[2,2-bis(bromomethyl)-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-propanol, 3,3'-oxybis[2,2-bis(bromomethyl)- (PMN P-87-1273) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63(a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3)(applies to gloves only), (a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (a)(6)(ii), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72(a), (b)(2), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), and (g)(5). In addition, the human health hazard statement shall include a statement that this substance may cause acute and chronic toxicity.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (p). In addition, use other than as a flame retardant additive is a significant new use.

## Environmental Protection Agency

## § 721.8450

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in §721.125 (a) through (i), and (j) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of §721.1725(b)(1) apply to this section.

[57 FR 44072, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.8340 Mono esters from 2-propenoic acid (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as mono esters from 2-propenoic acid (PMN P-01-85) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified §721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[68 FR 70181, Dec. 17, 2003]

### § 721.8350 2-Propenoic acid, 7-oxabicyclo[4.1.0]hept-3-ylmethyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 2-propenoic acid, 7-oxabicyclo[4.1.0]hept-3-ylmethyl ester (PMN P-89-31) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in §721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii), (a)(5)(xv), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in §721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(vi), (g)(1)(vii), (g)(2)(i) through (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(o).

(iv) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in §721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this significant new use rule.

[55 FR 46774, Nov. 6, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993; 62 FR 42692, Aug. 8, 1997]

### § 721.8450 2-Propenoic acid, 2-methyl-, 2-[3-(2H-benzotriazol-2-yl)-4-hydroxyphenyl]ethyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propenoic acid, 2-methyl-, 2-[3-(2H-benzotriazol-2-yl)-4-hydroxyphenyl]ethyl ester, (PMN P-90-333) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in §721.63 (a)(1), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in §721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii),

**§ 721.8485**

**40 CFR Ch. I (7–1–10 Edition)**

(g)(1)(iv), (g)(1)(vi), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), (c)(4), ( where N = 80 ). However, contrary to § 721.91(a)(4), if the waste stream containing the PMN substance will be treated using biological treatment (activated sludge or equivalent) plus clarification, then the amount of PMN substance reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than 75 percent removal efficiency may be attributed to such treatment.

(b) *Special requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 19241, Apr. 25, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993; 60 FR 30468, June 9, 1995; 63 FR 45956, Aug. 28, 1998]

**§ 721.8485 2-Propenoic acid, 2-methyl-, (octahydro-4,7-methano-1H-indene-5-diyl)bis(methylene) ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propenoic acid, 2-methyl-, (octahydro-4,7-methano-1H-indene-5-diyl)bis(methylene) ester (PMN P-99-1075; CAS No. 43048-08-4) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90(b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of these chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70182, Dec. 17, 2003]

**§ 721.8500 2-Propenoic acid, 2-methyl-, 7-oxabicyclo [4.1.0]hept-3-ylmethyl ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance 2-propenoic acid, 2-methyl-, 7-oxabicyclo[4.1.0]hept-3-ylmethyl ester (PMN P-89-30) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(viii), (a)(5)(xv), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(vi), (g)(1)(vii), (g)(2)(i) through (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(o).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 46775, Nov. 6, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## Environmental Protection Agency

## § 721.8670

### § 721.8657 Cerium, hydroxy oleate propionate complexes.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as Cerium, hydroxy oleate propionate complexes (PMN P-99-0026) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=7 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81403, Dec. 26, 2000]

### § 721.8658 Modified polymer of vinyl acetate and quaternary ammonium compound (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified polymer of vinyl acetate and quaternary ammonium compound (PMN P-99-0874) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15088, Mar. 28, 2003]

### § 721.8660 Propionic acid methyl ester (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a propionic acid methyl ester (PMN P-97-370) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44581, Aug. 20, 1998]

### § 721.8670 Alkylcyano substituted pyridazo benzoate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkylcyano substituted pyridazo benzoate (PMN P-94-1129) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in

§ 721.8673

40 CFR Ch. I (7-1-10 Edition)

§ 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11044, Mar. 1, 1995]

§ 721.8673 [(Disubstituted phenyl)azo dihydro hydroxy alkyl oxo alkyl-substituted-pyridines (generic name)].

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as [(disubstituted phenyl)azo dihydro hydroxy alkyl oxo alkyl-substituted-pyridines (PMN P-95-510/511) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[61 FR 63739, Dec. 2, 1996]

§ 721.8675 Halogenated pyridines.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated pyridine (PMN P-83-1163) is subject to reporting under this section for the significant new uses described in paragraph (a)(1)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all

cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contain residual amounts of the chemical substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(C) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(D) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 0.2 ppb). Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(2) The chemical substances identified generically as halogenated pyridines (PMN P-85-216, P-85-1184) is subject to reporting under this section for the significant new uses described in paragraph (a)(4)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all

## Environmental Protection Agency

## § 721.8700

cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(C) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(D) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 0.2 ppb). Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(b) [Reserved]

[56 FR 23769, May 23, 1991; 56 FR 29903, July 1, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993; 59 FR 66747, Dec. 28, 1994]

### § 721.8700 Halogenated alkyl pyridine.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated alkyl pyridine (PMN P-83-237) is subject to reporting under this section for the significant

new uses described in paragraph (a)(1)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(C) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(D) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 10 ppb). Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

**§ 721.8750**

**40 CFR Ch. I (7-1-10 Edition)**

(2) The chemical substance identified generically as halogenated alkyl pyridine (PMN P-83-1162) is subject to reporting under this section for the significant new uses described in paragraph (a)(2)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* The general requirements as specified in § 721.63 (a) (1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contain residual amounts of the chemical substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(C) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(D) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 0.2 ppb). Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(b) [Reserved]

[56 FR 23771, May 23, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993; 59 FR 66747, Dec. 28, 1994]

**§ 721.8750 Halogenated substituted pyridine.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated substituted pyridine (PMN P-86-838) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 1 ppb). Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## Environmental Protection Agency

## § 721.8775

this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 23769, May 23, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993; 59 FR 66747, Dec. 28, 1994]

### § 721.8775 Substituted pyridines.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted pyridine (PMN P-84-1219) is subject to reporting under this section for the significant new uses described in paragraph (a)(1)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(C) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(D) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 10 ppb). Where primary, secondary, and tertiary waste treatment will occur, or

treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(2) The chemical substances identified generically as substituted pyridines (PMNs P-85-236 and P-85-706) are subject to reporting under this section for the significant new uses described in paragraph (a)(2)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(C) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(D) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 0.2 ppb).



Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) The chemical substance identified generically as substituted pyridine (PMN P-85-36) is subject to reporting under this section for the significant new uses described in paragraph (a)(3)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contain residual amounts of the chemical substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(C) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(D) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and

(c)(4) (concentration set at 10 ppb). Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(4) The chemical substance identified generically as substituted pyridine (PMN P-85-1184) is subject to reporting under this section for the significant new uses described in paragraph (a)(4)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(B) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(C) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

## Environmental Protection Agency

## § 721.8825

(D) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 1.3 ppb). Where primary, secondary, and tertiary waste treatment will occur or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(ii) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(A) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(B) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(b) [Reserved]

[56 FR 23770, May 23, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993; 59 FR 66747, Dec. 28, 1994]

### § 721.8780 Substituted pyridine azo substituted phenyl.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as substituted pyridine azo substituted phenyl (PMNs P-96-767 and P-96-773) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers and importers of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3435, Jan. 22, 1998]

### § 721.8825 Substituted methylpyridine and substituted 2-phenoxy pyridine.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The following chemical substances, referred to by their PMN numbers and generic chemical names, are subject to reporting under this section for the significant new uses described in paragraphs (a)(2) and (3) of this section: Substituted methylpyridine (P-83-24, P-83-49, and P-83-272) and substituted 2-phenoxy pyridine (P-83-23 and P-83-75).

(2) The significant new uses for P-83-49 and P-83-272 are manufacture or processing without:

(i) Requiring use of the following personal protective equipment for persons involved in any operation where dermal contact and/or inhalation of the substances may occur, and where local exhaust ventilation is present at the site of the operation:

(A) Chemical cartridge respirator, approved by the National Institute for Occupational Safety and Health for protection from organic vapors, and used and fitted according to 29 CFR 1910.134 and 30 CFR part 11.

(B) Chemical worker gloves and aprons or other equivalent personal protective clothing determined to be impervious to the particular substance in its conditions of use. (Equipment may be determined to be impervious either by testing under the conditions of use, including the duration of exposure, or by evaluating the specifications supplied by the supplier of the equipment.)

(ii) Requiring use of the following personal protective equipment for persons involved in and in the immediate area of any operation where dermal contact and/or inhalation of the substance may occur, and where local exhaust ventilation is not present at the site of the operation:

(A) Full facepiece, positive pressure air-supplied respirator, approved by the Bureau of Mines, Department of the Interior or by the National Institute of Occupational Safety and Health fitted according to procedures established at 29 CFR 1910.134.

(B) Chemical worker gloves and aprons, or other equivalent personal protective clothing determined to be impervious to the particular substance in its conditions of use. (Equipment

§ 721.8850

40 CFR Ch. I (7-1-10 Edition)

may be determined to be impervious either by testing under the conditions of use, including the duration of exposure, or by evaluating the specifications supplied by the supplier of the equipment.)

(iii) Notifying in writing, each employee required to use protective equipment that these chemical substances may present a hazard of liver, kidney, and nervous system toxicity unless the specified protective equipment is used.

(3) The significant new uses for P-83-23, P-83-24, and P-83-75 are manufacture or processing without:

(i) Requiring the use of the following personal protective equipment for persons involved in any operation where dermal contact may occur:

(A) Chemical goggles.

(B) Chemical worker gloves and aprons, or other equivalent personal protective clothing determined to be impervious to the particular substance in its conditions of use. (Equipment may be determined to be impervious either by testing under the conditions of use, including the duration of exposure, or by evaluating the specifications supplied by the supplier of the equipment.)

(ii) Notifying in writing, each employee required to use protective equipment that these chemical substances may present a hazard of liver, kidney, and nervous system toxicity unless the specified protective equipment is used.

(b) *Specific requirements.* In addition to the general provisions of subpart A of this part, the following specific requirements apply.

(1) *Recordkeeping.* In addition to the requirements of § 721.17, manufacturers, importers, and processors of the chemical substances identified in paragraph (a) of this section must maintain the following records for five years from the date of their creation:

(i) The names of persons required to wear protective clothing and/or equipment.

(ii) Records of respirator fit tests for each person required to wear a respirator.

(iii) The names and addresses of persons to whom any of these substances are sold or transferred and the date of such sale or transfer.

(2) [Reserved]

[49 FR 50400, Dec. 28, 1984. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

§ 721.8850 **Disubstituted halogenated pyridinol.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as disubstituted halogenated pyridinol (PMN P-88-1274) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 44 ppb). Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## Environmental Protection Agency

## § 721.8900

this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 23771, May 23, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993; 59 FR 66748, Dec. 28, 1994]

### § 721.8875 Substituted halogenated pyridinol.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted halogenated pyridinol (PMN P-88-1273) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2), (c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 44 ppb). Where primary, secondary, and ter-

tiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 23772, May 23, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993; 59 FR 66748, Dec. 28, 1994]

### § 721.8900 Substituted halogenated pyridinol, alkali salt.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as substituted halogenated pyridinols, alkali salts (PMNs P-88-1271 and P-88-1272) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* The general requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xiv), (a)(6)(i), (a)(6)(ii), (a)(6)(iii), (a)(6)(iv), (a)(6)(v), (a)(6)(vi), and (c) apply in all cases except that § 721.63(a)(2)(ii) does not apply for reactor sampling operations where enclosed vented sample boxes are used. In addition § 721.63(a)(2)(iv) applies for processing of any byproduct generated during manufacturing, processing, or use of the chemical substance which contains residual amounts of the chemical substance.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (b)(1), (b)(2),

§ 721.8920

(c)(1), and (c)(2). The following additional disposal methods also apply: Chemical destruction or, where necessary to ensure complete destruction of the substance, chemical destruction and carbon adsorption.

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (concentration set at 44 ppb). Where primary, secondary, and tertiary waste treatment will occur, or treatment in a lined, self-contained solar evaporation pond where UV light will degrade the substance, the number of kilograms per day per site is calculated after wastewater treatment.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: § 721.125 (a) through (h), (j), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[56 FR 23772, May 23, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993; 59 FR 66748, Dec. 28, 1994]

§ 721.8920 **4,6-Disubstituted pyrimidine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 4,6-disubstituted pyrimidine (PMN P-99-1366) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

40 CFR Ch. I (7-1-10 Edition)

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15088, Mar. 28, 2003]

§ 721.8940 **Chromate(3-), bis[3-[[6-amino-1,4-dihydro-2-[[[4-(2-hydroxy-1-naphthalenyl)azo]phenyl]sulfonyl]amino]-4-(oxo-kappa.O)-5-pyrimidinyl]azo-kappa.N1]-4-hydroxy-kappa.O)-5-nitrobenzenesulfonato(3-)-, trisodium.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as chromate(3-), bis[3-[[6-amino-1,4-dihydro-2-[[[4-(2-hydroxy-1-naphthalenyl)azo]phenyl]sulfonyl]amino]-4-(oxo-kappa.O)-5-pyrimidinyl]azo-kappa.N1]-4-hydroxy-kappa.O)-5-nitrobenzenesulfonato(3-)-, trisodium (PMN P-01-459; CAS No. 178452-72-7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70182, Dec. 17, 2003]

§ 721.8950 **Chromate(3-), bis[3-[[6-amino-1,4-dihydro-2-[[[4-(2-hydroxy-1-naphthalenyl)azo]phenyl]sulfonyl]amino]-4-(oxo-kappa.O)-5-pyrimidinyl]azo-kappa.N1]-4-hydroxy-kappa.O)-5-nitrobenzenesulfonato(3-)-, sodium triethanolamine salts.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as chromate(3-), bis[3-[[6-amino-1,4-dihydro-2-[[[4-(2-hydroxy-1-naphthalenyl)azo]phenyl]sulfonyl]amino]-4-(oxo-kappa.O)-5-pyrimidinyl]azo-kappa.N1]

## Environmental Protection Agency

## § 721.9000

-4-hydroxy-.kappa.O)-5-nitrobenzenesulfonato(3-)]-, sodium triethanolamine salts. (PMN P-01-460; CAS No. 327177-98-0) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70182, Dec. 17, 2003]

### § 721.8965 1H-Pyrole-2, 5-dione, 1-(2,4,6-tribromophenyl)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1H-pyrole-2, 5-dione, 1-(2,4,6-tribromophenyl)-, (PMN No. P-90-159) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(iii) for employees likely to have ocular exposure, (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 0.1 percent by weight or volume), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) concentration set at 0.1 percent by weight or volume, (f), (g)(1)(ii), (g)(1)(iii), (g)(1)(iv), (g)(1)(v), (g)(1)(vi), (g)(1)(ix) (corrosion to the eyes), (g)(2)(iii), (g)(2)(iv) (use chemical goggles), (g)(3)(ii), (g)(4)(i), (g)(4)(iii) (except the dewatering step during polymerization of acrylonitrile/butadiene/styrene), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (a), (c), (f), (k) (any use

in a system other than as flame retardant in styrenic, polyolefin elastomer, and thermoset systems), (l), and (q).

(iv) *Disposal.* Requirements as specified in § 721.85 (b)(1) (by industrial incinerator), (b)(2), (c)(1), and (c)(2). Dispose of the PMN substance by industrial incinerator or landfill.

(v) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1). Section 721.90 (c)(1) does not apply to releases of the PMN substance during the dewatering step of the polymerization reactions from use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (d), and (f) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32240, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

### § 721.9000 N-Nitrosopyrrolidine.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance N-nitrosopyrrolidine (CAS No. 930-55-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

§ 721.9005

40 CFR Ch. I (7-1-10 Edition)

§ 721.9005 **2-Pyrrolidinone, 1,1'-(2-methyl-1,5-pentanediy)bis-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-pyrrolidinone, 1,1'-(2-methyl-1,5-pentanediy)bis- (PMN P-93-761; CAS No. 146453-62-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i) (There must be no permeation of the PMN substance greater than 0.08 grams (g)/minutes (min) centimeter (cm<sup>2</sup>) after 8 hours of testing in accordance with the most current version of the American Society for Testing and Materials (ASTM) F739 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases." The results of all glove permeation testing must be reported in accordance with the most current version of (ASTM) F1194 "Guide for Documenting the Results of Chemical Permeation Testing of Protective Clothing Materials." Manufacturers, importers, and processors must submit such glove test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves. The following gloves have been tested in accordance with the ASTM F739 method and found to satisfy the requirements for use by EPA: Ansell Edmond/8-352/ Neoprene rubber, 0.097 cm thick. Gloves may not be used for a time period longer than they are actually tested and must be replaced at the end of each work shift), (a)(2)(ii), (a)(2)(iii), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(iii), (g)(2)(v), and (g)(5). The label and MSDS as required by this paragraph shall also include the following statement: This substance is expected to enhance the absorption of other chemicals into skin or other materials.

(iii) *Industrial, commercial, and consumer activities.* Requirements as speci-

fied in § 721.80 (o), (q), and (k) (use other than as a heat transfer fluid).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 3435, Jan. 22, 1998]

§ 721.9010 **2-pyrrolidone, 1-ethenyl-3-ethylidene-, (E)-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-pyrrolidone, 1-ethenyl-3-ethylidene-, (E)- (PMN P-96-1536; CAS No. 153954-47-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(2)(i) and (a)(3).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (e) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3436, Jan. 22, 1998]

§ 721.9075 **Quaternary ammonium salt of fluorinated alkylaryl amide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as quaternary ammonium salt of fluorinated alkylaryl amide (PMN No. P-92-688) is subject to reporting under this section for the significant new

## Environmental Protection Agency

§ 721.9080

uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[58 FR 32241, June 8, 1993]

### § 721.9078 6-Methoxy-1H-benz[de]isoquinoline-2 [3H]-dione derivative (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 6-methoxy-1H-benz[de]isoquinoline-2 [3H]-dione derivative (PMN P-00-1205) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=30).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70182, Dec. 17, 2003]

### § 721.9079 Dihydro quinacridone derivative (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

chemical substance identified generically as dihydro quinacridone derivative (PMN P-01-397) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (1,000 kg).

(ii) *Release to water.* Requirements as specified § 721.90(a)(4), (b)(4), and (c)(4) (N=2).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70182, Dec. 17, 2003]

### § 721.9080 Nitro methyl quinoline.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as nitro methyl quinoline (PMN P-96-1319) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), and (a)(6)(i).

(ii) *Disposal.* Requirements as specified in § 721.85 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (j) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3436, Jan. 22, 1998]



## § 721.9100

## 40 CFR Ch. I (7–1–10 Edition)

### § 721.9100 Substituted quinoline.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted quinoline (PMN P-93-1183) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(c).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27485, May 27, 1994]

### § 721.9220 Reaction products of secondary alkyl amines with a substituted benzenesulfonic acid and sulfuric acid (generic name).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as reaction products of secondary alkyl amines with a substituted benzenesulfonic acid and sulfuric acid (PMNs P-89-703, P-89-755, and P-89-756) are subject to reporting under this section for significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Uses as specified in § 721.80(q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of these substances: Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 17381, Apr. 24, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9265 Reaction product of dichlorobenzidine and substituted alkylamide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a reaction product of dichlorobenzidine and substituted alkylamide (PMN P-95-1282) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e), (f), and (g)(5). The label and MSDS as required by this paragraph shall also include the following statements: At temperatures above 200 °C, this substance decomposes to produce a suspect human carcinogen, 3,3' dichlorobenzidine. Do not heat above 200 °C or 392 °F.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f) and processing or use of the PMN substance at temperatures above 200 °C.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3436, Jan. 22, 1998]

### § 721.9270 Reaction product of epoxy with anhydride and glycerol and glycol.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as reaction product of epoxy with

## Environmental Protection Agency

## § 721.9285

anhydride and glycerol and glycol (PMN P-96-1233) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), (x)(1) and (y)(2).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3436, Jan. 22, 1998]

### § 721.9280 Reaction product of ethoxylated fatty acid oils and a phenolic pentaerythritol tetraester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a reaction product of ethoxylated fatty acid oils and a phenolic pentaerythritol tetraester (PMN P-92-63) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance

is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who have received, or will receive, this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44072, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9285 Reaction products of formalin (37%) with amine C<sub>12</sub>.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as reaction products of formalin (37%) with amine C<sub>12</sub> (PMN P-95-535) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## § 721.9300

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3436, Jan. 22, 1998]

### **§ 721.9300 Reaction products of substituted hydroxyalkanes and polyalkylpolyisocyanatocarbomonocycle.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as reaction products of substituted hydroxyalkanes and polyalkylpolyisocyanatocarbomonocycle (PMN P-91-75) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive this substance from the employer are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as speci-

## 40 CFR Ch. I (7-1-10 Edition)

fied in § 721.80(p) (volume set at 433,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[57 FR 44073, Sept. 23, 1992, as amended at 58 FR 34204, June 23, 1993]

### **§ 721.9400 Reaction product of phenolic pentaerythritol tetraesters with fatty acid esters and oils, and glyceride triesters.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as Reaction product of phenolic pentaerythritol tetraesters with fatty acid esters and oils, and glyceride triesters (PMNs P-91-1231, -1232, -1233, -1234, and -1235) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

(A) If as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, the employer must incorporate this new information, and any information on methods for protecting against such risk, into an MSDS as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

## Environmental Protection Agency

§ 721.9480

(B) The employer must ensure that persons who will receive this substance, or who have received this substance from the employer within 5 years from the date the employer becomes aware of the new information described in section (a)(2)(i)(A) of this subparagraph, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the employer becomes aware of the new information.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.575(b)(1) apply to this section.

[57 FR 44073, Sept. 23, 1992, as amended by 58 FR 34204, June 23, 1993]

### § 721.9460 Tall oil fatty acids, reaction products with polyamines, alkyl substituted.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as tall oil fatty acids, reaction products with polyamines, alkyl substituted (PMN P-91-225) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q) and any use in a manner that will result in overspray over or into waters of the United States.

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), (c)(1), or use in any manner that will result

in overspray over or into waters of the United States.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a), (b), (c), and (f) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44074, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9470 Reserpine.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance reserpine (CAS No. 50-555) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

### § 721.9480 Resorcinol, formaldehyde substituted carbomonocycle resin (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as resorcinol, formaldehyde substituted carbomonocycle resin (PMN P-89-769) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

**§ 721.9484**

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 39905, Sept. 28, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993; 67 FR 12885, Mar. 20, 2002]

**§ 721.9484 Dimer acid/rosin amidoamine reaction product (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Dimer acid/rosin amidoamine reaction product (PMN P-99-0143) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81403, Dec. 26, 2000]

**§ 721.9485 Dimer acid/polymerized rosin amidoamine reaction product (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Dimer acid/polymerized rosin

**40 CFR Ch. I (7-1-10 Edition)**

amidoamine reaction product (PMN P-99-0144) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81403, Dec. 26, 2000]

**§ 721.9486 Rosin amidoamine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Rosin amidoamine (PMN P-99-0145) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81404, Dec. 26, 2000]

**§ 721.9487 Polymerized rosin amidoamine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Polymerized rosin amidoamine

## Environmental Protection Agency

## § 721.9495

(PMN P-99-0146) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water*. Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[65 FR 81404, Dec. 26, 2000]

### § 721.9488 Substituted resorcinols.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substances identified generically as substituted resorcinols (PMNs P-95-1103, P-95-1104, and P-96-1235) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water*. Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 9).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. The recordkeeping requirements specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[63 FR 3437, Jan. 22, 1998]

### § 721.9490 Coco alkyl dimethyl amine salts (generic).

(a) *Chemical substances and significant new uses subject to reporting*. (1) The chemical substances identified generically as coco alkyl dimethyl amine salts (PMNs P-98-412/414/415/416/417) are

subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water*. Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[63 FR 44582, Aug. 20, 1998]

### § 721.9492 Polymers of styrene, cyclohexyl methacrylate and substituted methacrylate.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substances identified generically as polymers of styrene, cyclohexyl methacrylate and substituted methacrylate (PMNs P-97-143/144) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[63 FR 3437, Jan. 22, 1998]

### § 721.9495 Acrylosilane resins.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substances identified as

**§ 721.9497**

**40 CFR Ch. I (7-1-10 Edition)**

acrylosilane resins (PMNs P-95-1024/1040) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(l).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63740, Dec. 2, 1996]

**§ 721.9497 Trifunctional ketoximino silane.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as trifunctional ketoximino silane (PMNs P-95-605 and P-95-606) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), and (a)(3).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (e) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3437, Jan. 22, 1998]

**§ 721.9499 Modified silicone resin.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a modified silicone resin (PMN

P-96-1649) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 5).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3437, Jan. 22, 1998]

**§ 721.9500 Silane, (1,1-dimethylethoxy) dimethoxy(2-methyl propyl)-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance silane, (1,1-dimethylethoxy) dimethoxy (2-methylpropyl)- (PMN P-89-906) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iv) through (a)(5)(vii), (a)(6)(i) through (a)(6)(vi), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(ii), (g)(2)(ii), (g)(2)(iv), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions

## Environmental Protection Agency

## § 721.9504

of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 46775, Nov. 6, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9501 Silane, triethoxy[3-oxiranylmethoxy]propyl]-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as silane, triethoxy[3-oxiranylmethoxy]propyl]- (PMN P-01-781; CAS No. 2602-34-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) *Release to water.* Requirements as specified § 721.90(a)(4), (b)(4), and (c)(4) (N=10).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70183, Dec. 17, 2003]

### § 721.9502 Siloxanes and silicones, aminoalkyl, fluoroethyl, hydroxy-terminated salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as siloxanes and silicones, aminoalkyl, fluoroethyl, hydroxy-terminated salt (PMN P-00-1132) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (graffiti systems) and (y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 15088, Mar. 28, 2003]

### § 721.9503 Silane, (3,3,4,4,5,5,6,6,7,7,8,8,9,9,10,10,10-heptadecafluorodecyl)trimethoxy-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as silane, (3,3,4,4,5,5,6,6,7,7,8,8,9,9,10,10,10-heptadecafluorodecyl) trimethoxy- (PMN P-97-264; CAS No. 83048-65-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iii), (a)(5)(xii), (a)(5)(xiii), (a)(5)(xv), (a)(6)(ii), and (a)(6)(v).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 10).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3437, Jan. 22, 1998]

### § 721.9504 Silane, triethoxy (3,3,4,4,5,5,6,6,7,7,8,8,8-tridecafluorooctyl)-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as silane, triethoxy (3,3,4,4,5, 5,6,6,7,7,8,8,8-tridecafluorooctyl)- (PMN P-99-1346;



**§ 721.9505**

CAS No. 51851-37-7) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(ii), (a)(5)(xii), and (a)(5)(xiii).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(o).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15088, Mar. 28, 2003]

**§ 721.9505 Silanes substituted macrocycle polyethyl.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as silanes substituted macrocycle polyethyl (PMNs P-93-1423, 1424, 1425, and 1426) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11045, Mar. 1, 1995]

**40 CFR Ch. I (7-1-10 Edition)**

**§ 721.9506 Halogenated arylsilane (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a halogenated arylsilane (PMN P-01-9) is subject to reporting under this section for the significant new use described in paragraph (a)(1) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70183, Dec. 17, 2003]

**§ 721.9507 Polyester silane.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a polyester silane (P-95-1022) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(l).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63740, Dec. 2, 1996]

## Environmental Protection Agency

§ 721.9511

### § 721.9508 Perfluorinatedalkyl polyhydroxysilane (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as perfluorinatedalkyl polyhydroxysilane (PMN P-95-1400) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(viii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(v), (g)(5). The following statement shall appear on each label as specified in § 721.72(b) and the MSDS as specified in § 721.72(c): This substance may cause death if inhaled.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1). Use in any formulation that contains alkylbenzenesulfonate emulsifiers.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (f), (g), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 372, Jan. 5, 2000]

### § 721.9509 Perfluorinatedalkyl polyalkoxysilane (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as perfluorinatedalkyl polyalkoxysilane (PMN P-95-1410) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(viii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(v), (g)(5). The following statement shall appear on each label as

specified in § 721.72(b) and the MSDS as specified in § 721.72(c): This substance may cause death if inhaled.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1). Use in any formulation that contains alkylbenzenesulfonate emulsifiers.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a), (b), (c), (f), (g), (h), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 372, Jan. 5, 2000]

### § 721.9511 Silicic acid (H<sub>6</sub>SiO<sub>2</sub>O<sub>7</sub>), magnesium, strontium salt(1:1:2), dysprosium and europium-doped.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as silicic acid (H<sub>6</sub>SiO<sub>2</sub>O<sub>7</sub>) magnesium, strontium salt(1:1:2), dysprosium and europium-doped. (PMN P-98-848; CAS No.181828-07-9) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (manufacture or import of the chemical substance where greater than 5% of the chemical substance is below the 10 micron (respirable particles) threshold).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70183, Dec. 17, 2003]

## § 721.9513

### § 721.9513 Modified magnesium silicate polymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified magnesium silicate polymer (PMN P-98-604) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 372, Jan. 5, 2000]

### § 721.9514 Ethyl silicate, reaction products with modified alkoxy silane salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as Ethyl silicate, reaction products with modified alkoxy silane salt (PMN P-99-0157) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

## 40 CFR Ch. I (7-1-10 Edition)

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81404, Dec. 26, 2000]

### § 721.9515 Aminofunctional alkoxy alkyl siloxane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an aminofunctional alkoxy alkyl siloxane (PMN P-96-346) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3437, Jan. 22, 1998]

### § 721.9516 Siloxanes and silicones, 3-[(2-aminoethyl) amino]propyl Me, di-Me, reaction products with polyethylene-polypropylene glycol Bu glycidal ether.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as siloxanes and silicones, 3-[(2-aminoethyl) amino]propyl Me, di-Me, reaction products with polyethylene-polypropylene glycol Bu glycidyl ether (PMN P-97-740; CAS No. 189354-73-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## Environmental Protection Agency

§ 721.9520

(1) *Recordkeeping.* Recordkeeping requirements specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 44582, Aug. 20, 1998]

### § 721.9517 Siloxanes and silicones, de-Me, 3-[4-[[[3-(dimethyl amino) propyl] amino]carbonyl]-2-oxo-1-pyrrolidinyl] propyl Me.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as siloxanes and silicones, de-Me, 3-[4-[[[3-(dimethylamino) propyl]amino] carbonyl]-2-oxo-1-pyrrolidinyl]propyl Me (PMN P-97-332) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 44582, Aug. 20, 1998]

### § 721.9518 *Sinorhizobium meliloti* strain RMBPC-2.

(a) *Microorganism and significant new uses subject to reporting.* (1) The microorganism identified as *Sinorhizobium meliloti* strain RMBPC-2 (PMN P-92-403) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Commercial activities before submitting a TSCA section 5(a) notice.* For any manufacturer or importer who has not previously submitted a premanufacture notice or significant new use notice for

this microorganism, the significant new use is any use.

(ii) *Commercial activities after submitting a TSCA section 5(a) notice.* For any manufacturer or importer who has previously submitted a premanufacture notice or a significant new use notice for this microorganism, the significant new use is manufacture, import, or processing greater than a maximum production volume of 500,000 lbs in any consecutive 12-month period.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for §721.5(a)(2). A person who intends to manufacture or import this substance for commercial purposes must have submitted a premanufacture notice or submit a significant new use notice.

(2) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a) and (i) are applicable to manufacturers and importers of this substance.

(3) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[63 FR 29648, June 1, 1998]

### § 721.9520 Methylated-para-rosaniline salt of a trisulfonated triarylmethane dye (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as methylated-para-rosaniline salt of a trisulfonated triarylmethane dye (PMN P-00-0559) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(f).

(ii) *Release to water.* Requirements as specified in §721.90 (a)(4), (b)(4), (c)(4) (N=2 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), (i), and (k) are applicable to

## § 721.9526

## 40 CFR Ch. I (7–1–10 Edition)

manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15088, Mar. 28, 2003]

### § 721.9526 Sodium perthiocarbonate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as sodium perthiocarbonate (PMN P-94-2166) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45084, Aug. 30, 1995]

### § 721.9527 Bis(1,2,2,6,6-pentamethyl-4-piperidin-4-ol) ester of cycloaliphatic spiroketal.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as bis(1,2,2,6,6-pentamethyl-4-piperidin-4-ol) ester of cycloaliphatic spiroketal (PMN No. P-91-1361) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* For manufacturing workers only, requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(6)(i), and (b) (concentration set at 1.0 percent). For processing/use workers only, requirements as specified in § 721.63(a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(vi), (g)(1)(viii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(3)(ii), (g)(4)(iii), and (g)(5). The following additional statements shall appear on each label and MSDS required by this paragraph: This substance may cause systemic effects, eye irritation.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (d), (f) through (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32241, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

### § 721.9530 Bis(2,2,6,6-tetramethylpiperidinyl) ester of cycloalkyl spiroketal.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as bis(2,2,6,6-tetramethyl piperidinyl) ester of cycloalkyl spiroketal (PMN P-88-0083) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* For the manufacturing workers only, requirements as specified in § 721.63 (a)(4), (a)(5)(i), (a)(6)(i), and (b) (concentration set at 1.0 percent). For the processing/use workers only, requirements as specified in § 721.63 (a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1.0 per cent) and (c).

## Environmental Protection Agency

§ 721.9540

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(vi), (g)(1)(viii), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(3)(ii), (g)(4)(iii), and (g)(5). The following additional human health hazard statements shall appear on each label and MSDS required by this paragraph: This substance may cause: systemic effects, eye irritation.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(1).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), (i), and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[56 FR 40215, Aug. 13, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

### § 721.9535 1,4-Dioxo-7,9-dithia-8-stannacycloundecane-5,11-dione, 8,8-dioctyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a 1,4-Dioxo-7,9-dithia-8-stannacycloundecane-5,11-dione, 8,8-dioctyl- (PMN P-99-0093; CAS No. 56875-68-4) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) and (f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 81404, Dec. 26, 2000]

### § 721.9538 Lithium salt of sulfophenyl azo phenyl azo disulfostilbene (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as lithium salt of sulfophenyl azo phenyl azo disulfostilbene (PMN P-00-0698) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(2), (w)(2), (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15088, Mar. 28, 2003]

### § 721.9540 Polysulfide mixture.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polysulfide mixture (PMN P-93-1043) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* A significant new use of this substance is any manner or method of manufacture, import, or processing associated with any use of this substance without providing risk notification as follows:

**§ 721.9545**

**40 CFR Ch. I (7-1-10 Edition)**

(A) If, as a result of the test data required under the section 5(e) consent order for this substance, the employer becomes aware that this substance may present a risk of injury to human health, or the environment, the employer must incorporate this new information, and any information on methods for protecting against such risk, into the applicable Material Safety Data Sheet (MSDS) as described in § 721.72(c) within 90 days from the time the employer becomes aware of the new information. If this substance is not being manufactured, imported, processed, or used in the employer's workplace, the employer must add the new information to an MSDS before the substance is reintroduced into the workplace.

(B) The employer must ensure that persons who will receive, or who have received this substance from the employer within 5 years from the date the employer becomes aware of the new information described in paragraph (a)(2)(i)(A) of this section, are provided an MSDS as described in § 721.72(c) containing the information required under paragraph (a)(2)(i)(A) of this section within 90 days from the time the Company becomes aware of the new information. Requirements as specified in § 721.72 (a), (b), (c), (d), (f), and (g)(4)(iii).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (153,000 kg).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 11045, Mar. 1, 1995]

**§ 721.9545 Substituted phenyl azo substituted sulfocarbopolycycle, sodium salt.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted phenyl azo substituted sulfocarbopolycycle, sodium salt (PMN P-96-1263) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3437, Jan. 22, 1998]

**§ 721.9550 Sulfonamide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as a sulfonamide (PMN P-90-1732) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3), (a)(4), (a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(5)(vii), (a)(6)(i), (b) (concentration set at 1.0 percent) and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), (g)(4)(ii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

## Environmental Protection Agency

## § 721.9573

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 10 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44074, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9570 Halophenyl sulfonamide salt.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halophenyl sulfonamide salt (PMN P-90-1730) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 10 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Recordkeeping requirements as specified at § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 31970, July 20, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9572 Substituted alkyl sulfonamide (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted alkyl sulfonamide (PMN P-00-838) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70183, Dec. 17, 2003]

### § 721.9573 Substituted perfluoroalkyl sulfonamide (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted perfluoroalkyl sulfonamide (PMN P-98-645) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),



§ 721.9575

40 CFR Ch. I (7–1–10 Edition)

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 372, Jan. 5, 2000]

§ 721.9575 Chromate(3-), bis[3-[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-7-[[2-oxo-1-[(phenylamino)carbonyl]propyl]azo]-2-naphthalenesulfonato(3-)-], trisodium (9CI).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as chromate(3-), bis[3-[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-7-[[2-oxo-1-[(phenylamino)carbonyl]propyl]azo]-2-naphthalene sulfonato(3-)-], trisodium (9CI) (PMN P-95-1575; CAS No. 119535-63-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3438, Jan. 22, 1998]

§ 721.9576 Chromate(3-), bis[7-[(aminohydroxyphenyl)azo]-3-[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-2-naphthalene-sulfonato (3-)-], trisodium (9CI).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as chromate(3-), bis[7-

[(aminohydroxyphenyl)azo]-3-[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-2-naphthalene-sulfonato (3-)-], trisodium (9CI) (PMN P-95-1576; CAS No. 118716-62-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3438, Jan. 22, 1998]

§ 721.9577 Chromate(3-), bis[7-[(aminohydroxyphenyl)azo]-3-[[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-2-naphthalene sulfonato (3-)-],-[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-7-[[2-hydroxy-1-[(phenylamino) carbonyl]-1-propenyl]azo]-2-naphthalenesulfonato(3-)-], trisodium (9CI).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as chromate(3-), bis[7-[(aminohydroxyphenyl)azo]-3-[[5-(aminosulfonyl)-2-hydroxy phenyl]azo]-4-hydroxy-2-naphthalenesulfonato (3-)-],-[5-(aminosulfonyl)-2-hydroxyphenyl]azo]-4-hydroxy-7-[[2-hydroxy-1-[(phenylamino) carbonyl]-1-propenyl]azo]-2-naphthalene sulfonato(3-)-], trisodium (9CI) (PMN P-95-1577; CAS No. 118716-61-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

**Environmental Protection Agency**

**§ 721.9582**

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3438, Jan. 22, 1998]

**§ 721.9580 Ethyl methanesulfonate.**

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance ethyl methanesulfonate (CAS No. 62-50-0) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000

pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in §721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63518, Dec. 1, 1993]

**§ 721.9582 Certain perfluoroalkyl sulfonates.**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances listed in Table 1, Table 2, and Table 3 of this section are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

TABLE 1—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER JANUARY 1, 2001

| CAS No./PMN | CAS Ninth Collective Index Name   |
|-------------|---|
| 2250-98-8   | 1-Octanesulfonamide, N,N',N"-[phosphinylidynetris(oxy-2,1-ethanediyl)]tris[N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-   |
| 30381-98-7  | 1-Octanesulfonamide, N,N'-[phosphinicobis(oxy-2,1-ethanediyl)]bis[N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-, ammonium salt   |
| 57589-85-2  | Benzoic acid, 2,3,4,5-tetrachloro-6-[[[3-[[[heptadecafluorooctyl)sulfonyl]oxy]phenyl]amino]carbonyl]-, monopotassium salt   |
| 61660-12-6  | 1-Octanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-[3-(trimethoxysilyl)propyl]-   |
| 67969-69-1  | 1-Octanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-[2-(phosphonoxy)ethyl]-, diammonium salt   |
| 68608-14-0  | Sulfonamides, C4-8-alkane, perfluoro, N-ethyl-N-(hydroxyethyl), reaction products with 1,1'-methylenebis[4-isocyanatobenzene]   |
| 70776-36-2  | 2-Propenoic acid, 2-methyl-, octadecyl ester, polymer with 1,1-dichloroethene, 2-[[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl 2-propenoate, N-(hydroxymethyl)-2-propenamamide, 2-[methyl[(nonafluorobutyl)sulfonyl]amino]ethyl 2-propenoate, 2-[methyl[(pentadecafluoroheptyl)sulfonyl]amino]ethyl 2-propenoate, 2-[methyl[(tridecafluoroheptyl)sulfonyl]amino]ethyl 2-propenoate and 2-[methyl[(undecafluoropentyl)sulfonyl]amino]ethyl 2-propenoate |
| 127133-66-8 | 2-Propenoic acid, 2-methyl-, polymers with Bu methacrylate, lauryl methacrylate and 2-[methyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl methacrylate   |
| 148240-78-2 | Fatty acids, C18-unsatd., trimers, 2-[[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl esters  |
| 148684-79-1 | Sulfonamides, C4-8-alkane, perfluoro, N-(hydroxyethyl)-N-methyl, reaction products with 1,6-diisocyanatohexane homopolymer and ethylene glycol  |
| 178535-22-3 | Sulfonamides, C4-8-alkane, perfluoro, N-ethyl-N-(hydroxyethyl), polymers with 1,1'-methylenebis[4-isocyanatobenzene] and polymethylenepolyphenylene isocyanate, 2-ethylhexyl esters, Me Et ketone oxime-blocked   |
| P-94-2205   | Polymethylenepolyphenylene isocyanate and bis(4-NCO-phenyl)methane reaction products with 2-ethyl-1-hexanol, 2-butanone, oxime, N-ethyl-N-(2-hydroxyethyl)-1-C4-C8 perfluoroalkanesulfonamide   |

TABLE 1—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER JANUARY 1, 2001—Continued

| CAS No./PMN              | CAS Ninth Collective Index Name   |
|--------------------------|---|
| P-96–1645<br>306974–63–0 | Fatty acids, C18-unsatd., dimers, 2-[methyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl esters |

TABLE 2—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER JANUARY 1, 2003

| CAS No./PMN | CAS Ninth Collective Index Name   |
|-------------|---|
| 307–35–7    | 1-Octanesulfonyl fluoride, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-   |
| 307–51–7    | 1-Decanesulfonyl fluoride, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,9,9,10,10,10-heneicosafuoro-   |
| 376–14–7    | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(heptadecafluorooctyl)sulfonyl]amino]ethyl ester  |
| 383–07–3    | 2-Propenoic acid, 2-[butyl[(heptadecafluorooctyl)sulfonyl]amino]ethyl ester   |
| 423–50–7    | 1-Hexanesulfonyl fluoride, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-   |
| 423–82–5    | 2-Propenoic acid, 2-[ethyl[(heptadecafluorooctyl)sulfonyl]amino]ethyl ester   |
| 754–91–6    | 1-Octanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-   |
| 1652–63–7   | 1-Propanaminium, 3-[[heptadecafluorooctyl)sulfonyl]amino]-N,N,N-trimethyl-, iodide  |
| 1691–99–2   | 1-Octanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-(2-hydroxyethyl)-  |
| 1763–23–1   | 1-Octanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-   |
| 2795–39–3   | 1-Octanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-, potassium salt   |
| 2991–51–7   | Glycine, N-ethyl-N-[(heptadecafluorooctyl)sulfonyl]-, potassium salt  |
| 4151–50–2   | 1-Octanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-   |
| 14650–24–9  | 2-Propenoic acid, 2-methyl-, 2-[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl ester  |
| 17202–41–4  | 1-Nonanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,9,9,9-nonadecafluoro-, ammonium salt   |
| 24448–09–7  | 1-Octanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-(2-hydroxyethyl)-N-methyl-   |
| 25268–77–3  | 2-Propenoic acid, 2-[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl ester   |
| 29081–56–9  | 1-Octanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-, ammonium salt  |
| 29117–08–6  | Poly(oxy-1,2-ethanediyl), .alpha.-[2-[ethyl[(heptadecafluorooctyl)sulfonyl]amino]ethyl]-.omega.-hydroxy-  |
| 29457–72–5  | 1-Octanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-, lithium salt   |
| 31506–32–8  | 1-Octanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-methyl-  |
| 38006–74–5  | 1-Propanaminium, 3-[[heptadecafluorooctyl)sulfonyl]amino]-N,N,N-trimethyl-, chloride  |
| 38850–58–7  | 1-Propanaminium, N-(2-hydroxyethyl)-N,N-dimethyl-3-[(3-sulfopropyl)[tridecafluorohexyl)sulfonyl]amino]-, inner salt   |
| 55120–77–9  | 1-Hexanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-, lithium salt   |
| 67584–42–3  | Cyclohexanesulfonic acid, decafluoro(pentafluoroethyl)-, potassium salt   |
| 67906–42–7  | 1-Decanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,9,9,10,10,10-heneicosafuoro-, ammonium salt  |
| 68156–01–4  | Cyclohexanesulfonic acid, nonafluorobis(trifluoromethyl)-, potassium salt   |
| 68298–62–4  | 2-Propenoic acid, 2-[butyl[(heptadecafluorooctyl)sulfonyl]amino]ethyl ester, telomer with 2-[butyl[(pentadecafluoroheptyl)sulfonyl]amino]ethyl 2-propenoate, methyloxirane polymer with oxirane di-2-propenoate, methyloxirane polymer with oxirane mono-2-propenoate and 1-octanethiol |

Environmental Protection Agency

§ 721.9582

TABLE 2—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER JANUARY 1, 2003—Continued

| CAS No./PMN | CAS Ninth Collective Index Name  |
|-------------|--|
| 68329–56–6  | 2-Propenoic acid, eicosyl ester, polymer with 2-[[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl 2-propenoate, hexadecyl 2-propenoate, 2-[methyl((nonafluorobutyl)sulfonyl)amino]ethyl 2-propenoate, 2-[methyl((pentadecafluoroheptyl)sulfonyl)amino]ethyl 2-propenoate, 2-[methyl((tridecafluorohexyl)sulfonyl)amino]ethyl 2-propenoate, and 2-[methyl((undecafluoropentyl)sulfonyl)amino]ethyl 2-propenoate and octadecyl 2-propenoate   |
| 68541–80–0  | 2-Propenoic acid, polymer with 2-[ethyl((heptadecafluorooctyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate and octadecyl 2-propenoate  |
| 68555–90–8  | 2-Propenoic acid, butyl ester, polymer with 2-[[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl 2-propenoate, 2-[methyl((nonafluorobutyl)sulfonyl)amino]ethyl 2-propenoate, 2-[methyl((pentadecafluoroheptyl)sulfonyl)amino]ethyl 2-propenoate, 2-[methyl((tridecafluorohexyl)sulfonyl)amino]ethyl 2-propenoate and 2-[methyl((undecafluoropentyl)sulfonyl)amino]ethyl 2-propenoate   |
| 68555–91–9  | 2-Propenoic acid, 2-methyl-, 2-[ethyl((heptadecafluorooctyl)sulfonyl)amino]ethyl ester, polymer with 2-[ethyl((nonafluorobutyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, 2-[ethyl((pentadecafluoroheptyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, 2-[ethyl((tridecafluorohexyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, and 2-[ethyl((undecafluoropentyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate and octadecyl 2-methyl-2-propenoate  |
| 68555–92–0  | 2-Propenoic acid, 2-methyl-, 2-[[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl ester, polymer with 2-[methyl((nonafluorobutyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, 2-[methyl((pentadecafluoroheptyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, 2-[methyl((tridecafluorohexyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, and 2-[methyl((undecafluoropentyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate and octadecyl 2-methyl-2-propenoate   |
| 68586–14–1  | 2-Propenoic acid, 2-[[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl ester, telomer with 2-[methyl((nonafluorobutyl)sulfonyl)amino]ethyl 2-propenoate, .alpha.-(2-methyl-1-oxo-2-propenyl)-.omega.-hydroxypoly(oxy-1,2-ethanediyl), .alpha.-(2-methyl-1-oxo-2-propenyl)-.omega.-[[2-methyl-1-oxo-2-propenyl]oxy]poly(oxy-1,2-ethanediyl), 2-[methyl((pentadecafluoroheptyl)sulfonyl)amino]ethyl 2-propenoate, 2-[methyl((tridecafluorohexyl)sulfonyl)amino]ethyl 2-propenoate, and 2-[methyl((undecafluoropentyl)sulfonyl)amino]ethyl 2-propenoate and 1-octanethiol |
| 68649–26–3  | 1-Octanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-(2-hydroxyethyl)-, reaction products with N-ethyl-1,1,2,2,3,3,4,4,4-nonafluoro-N-(2-hydroxyethyl)-1-butanedisulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-(2-hydroxyethyl)-1-heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-(2-hydroxyethyl)-1-hexanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,5-undecafluoro-N-(2-hydroxyethyl)-1-pentanesulfonamide, polymethylenepolyphenylene isocyanate and stearyl alc.                            |
| 68867–60–7  | 2-Propenoic acid, 2-[[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl ester, polymer with 2-[methyl((nonafluorobutyl)sulfonyl)amino]ethyl 2-propenoate, 2-[methyl((pentadecafluoroheptyl)sulfonyl)amino]ethyl 2-propenoate, 2-[methyl((tridecafluorohexyl)sulfonyl)amino]ethyl 2-propenoate, and 2-[methyl((undecafluoropentyl)sulfonyl)amino]ethyl 2-propenoate and .alpha.-(1-oxo-2-propenyl)-.omega.-methoxypoly(oxy-1,2-ethanediyl)   |
| 68867–62–9  | 2-Propenoic acid, 2-methyl-, 2-[ethyl((heptadecafluorooctyl)sulfonyl)amino]ethyl ester, telomer with 2-[ethyl((nonafluorobutyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, 2-[ethyl((pentadecafluoroheptyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, 2-[ethyl((tridecafluorohexyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, 2-[ethyl((undecafluoropentyl)sulfonyl)amino]ethyl 2-methyl-2-propenoate, 1-octanethiol and .alpha.-(1-oxo-2-propenyl)-.omega.-methoxypoly(oxy-1,2-ethanediyl)  |
| 68891–96–3  | Chromium, diaquatetrachloro[.mu.-[N-ethyl-N-[[[heptadecafluorooctyl)sulfonyl]glycinato-.kappa.O:.kappa.O]]-.mu.-hydroxybis(2-methylpropano)]di-  |
| 68909–15–9  | 2-Propenoic acid, eicosyl ester, polymers with branched octyl acrylate, 2-[[[heptadecafluorooctyl)sulfonyl]methylamino]ethyl acrylate, 2-[methyl((nonafluorobutyl)sulfonyl)amino]ethyl acrylate, 2-[methyl((pentadecafluoroheptyl)sulfonyl)amino]ethyl acrylate, 2-[methyl((tridecafluorohexyl)sulfonyl)amino]ethyl acrylate, and 2-[methyl((undecafluoropentyl)sulfonyl)amino]ethyl acrylate, polyethylene glycol acrylate Me ether and stearyl acrylate  |

TABLE 2—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER JANUARY 1, 2003—Continued

| CAS No./PMN              | CAS Ninth Collective Index Name  |
|--------------------------|--|
| 68958–61–2               | Poly(oxy-1,2-ethanediyl), .alpha.-[2-ethyl[(heptadecafluorooctyl)sulfonyl]amino]ethyl]-.omega.-methoxy-  |
| 70225–14–8               | 1-Octanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-, compd. with 2,2'-iminobis[ethanol] (1:1)  |
| 71487–20–2               | 2-Propenoic acid, 2-methyl-, methyl ester, polymer with ethenylbenzene, 2-[[[(heptadecafluorooctyl)sulfonyl]methylamino]ethyl 2-propenoate, 2-[methyl[(nonafluorobutyl)sulfonyl]amino]ethyl 2-propenoate, 2-[methyl[(pentadecafluoroheptyl)sulfonyl]amino]ethyl 2-propenoate, 2-[methyl[(tridecafluoroheptyl)sulfonyl]amino]ethyl 2-propenoate, 2-[methyl[(undecafluoropentyl)sulfonyl]amino]ethyl 2-propenoate and 2-propenoic acid |
| 73772–32–4               | 1-Propanesulfonic acid, 3-[[[3-(dimethylamino)propyl]](tridecafluoroheptyl)sulfonyl]amino]-2-hydroxy-, monosodium salt   |
| 81190–38–7               | 1-Propanaminium, N-(2-hydroxyethyl)-3-[[2-(hydroxy-3-sulfo)propyl]](tridecafluoroheptyl)sulfonyl]amino]-N,N-dimethyl-, hydroxide, monosodium salt  |
| 91081–99–1               | Sulfonamides, C4-8-alkane, perfluoro, N-(hydroxyethyl)-N-methyl, reaction products with epichlorohydrin, adipates (esters)   |
| 94133–90–1               | 1-Propanesulfonic acid, 3-[[[3-(dimethylamino)propyl]](heptadecafluorooctyl)sulfonyl]amino]-2-hydroxy-, monosodium salt  |
| 98999–57–6               | Sulfonamides, C7-8-alkane, perfluoro, N-methyl-N-[2-[[1-oxo-2-propenyl]oxy]ethyl], polymers with 2-ethoxyethyl acrylate, glycidyl methacrylate and N,N,N-trimethyl-2-[[2-methyl-1-oxo-2-propenyl]oxy]ethanaminium chloride   |
| 117806–54–9              | 1-Heptanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-, lithium salt   |
| 129813–71–4              | Sulfonamides, C4-8-alkane, perfluoro, N-methyl-N-(oxiranylmethyl)  |
| 148240–80–6              | Fatty acids, C18-unsatd., trimers, 2-[methyl[(tridecafluoroheptyl)sulfonyl]amino]ethyl esters  |
| 148240–82–8              | Fatty acids, C18-unsatd., trimers, 2-[methyl[(pentadecafluoroheptyl)sulfonyl]amino]ethyl esters  |
| 182700–90–9              | 1-Octanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-methyl-, reaction products with benzene-chlorine-sulfur chloride (S2Cl2) reaction products chlorides  |
| L–92–0151                | 2-Propenoic acid, 2-methyl-, butyl ester, polymer with 2-ethyl-2-[[[ethyl[(heptadecafluorooctyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate, 2-ethyl[(nonafluorobutyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate, 2-ethyl[(pentadecafluoroheptyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate, 2-ethyl[(tridecafluoroheptyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate and 2-propenoic acid   |
| P-80–0183<br>192662–29–6 | Sulfonamides, C4-8-alkane, perfluoro, N-[3-(dimethylamino)propyl], reaction products with acrylic acid   |
| P-83–1102<br>306973–46–6 | Fatty acids, linseed-oil, dimers, 2-[[[(heptadecafluorooctyl)sulfonyl]methylamino]ethyl esters   |
| P-84–1163<br>306975–56–4 | Propanoic acid, 3-hydroxy-2-(hydroxymethyl)-2-methyl-, polymer with 2-ethyl-2-(hydroxymethyl)-1,3-propanediol and N,N',2-tris(6-isocyanatohexyl)imidodicarbonic diamide, reaction products with N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-(2-hydroxyethyl)-1-octanesulfonamide and N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-(2-hydroxyethyl)-1-heptanesulfonamide, compds. with triethylamine       |
| P-84–1171<br>306975–57–5 | Propanoic acid, 3-hydroxy-2-(hydroxymethyl)-2-methyl-, polymer with 1,1'-methylenebis[4-isocyanatobenzene] and 1,2,3-propanetriol, reaction products with N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-(2-hydroxyethyl)-1-octanesulfonamide and N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-(2-hydroxyethyl)-1-heptanesulfonamide, compds. with morpholine  |
| P-86–0301<br>306973–47–7 | Sulfonamides, C4-8-alkane, perfluoro, N-(hydroxyethyl)-N-methyl, reaction products with 12-hydroxystearic acid and 2,4-TDI, ammonium salts   |
| P-86–0958<br>306975–62–2 | 2-Propenoic acid, 2-methyl-, dodecyl ester, polymers with 2-[methyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl acrylate and vinylidene chloride  |
| P-89–0799<br>160901–25–7 | Sulfonamides, C4-8-alkane, perfluoro, N-ethyl-N-(hydroxyethyl), reaction products with 2-ethyl-1-hexanol and polymethylenepolyphenylene isocyanate   |

Environmental Protection Agency

§ 721.9582

TABLE 2—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER JANUARY 1, 2003—Continued

| CAS No./PMN              | CAS Ninth Collective Index Name  |
|--------------------------|--|
| P-90-0111<br>306974-19-6 | Sulfonamides, C4-8-alkane, perfluoro, N-methyl-N-[(3-octadecyl-2-oxo-5-oxazolidinyl)methyl]  |
| P-91-1419<br>306975-84-8 | Poly(oxy-1,2-ethanediyl), .alpha.-hydro.-omega.-hydroxy-, polymer with 1,6-diisocyanatohexane, N-(hydroxyethyl)-N-methyl perfluoro C4-8-alkane sulfonamides-blocked  |
| P-93-1444<br>306975-85-9 | 2-Propenoic acid, 2-methyl-, dodecyl ester, polymers with N-(hydroxymethyl)-2-propenamide, 2-[methyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl methacrylate, stearyl methacrylate and vinylidene chloride   |
| P-94-0545<br>306976-25-0 | 1-Hexadecanaminium, N,N-dimethyl-N-2-[(2-methyl-1-oxo-2-propenyl)oxy]ethyl]-, bromide, polymers with Bu acrylate, Bu methacrylate and 2-[methyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl acrylate  |
| P-94-0927<br>306976-55-6 | 2-Propenoic acid, 2-methyl-, 2-methylpropyl ester, polymer with 2,4-diisocyanato-1-methylbenzene, 2-ethyl-2-(hydroxymethyl)-1,3-propanediol and 2-propenoic acid, N-ethyl-N-(hydroxyethyl)perfluoro-C4-8-alkanesulfonamides-blocked                |
| P-94-2206<br>306974-28-7 | Siloxanes and Silicones, di-Me, mono[3-[(2-methyl-1-oxo-2-propenyl)oxy]propyl]group-terminated, polymers with 2-[methyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl acrylate and stearyl methacrylate   |
| P-95-0120<br>306980-27-8 | Sulfonamides, C4-8-alkane, perfluoro, N,N'-[1,6-hexanediy]bis[(2-oxo-3,5-oxazolidinediyl)methylene]]bis[N-methyl-  |
| P-96-1262<br>306974-45-8 | Sulfonic acids, C6-8-alkane, perfluoro, compds. with polyethylene-polypropylene glycol bis(2-aminopropyl) ether  |
| P-96-1424<br>306977-10-6 | 2-Propenoic acid, 2-methyl-, 2-(dimethylamino)ethyl ester, telomer with 2-[ethyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl methacrylate and 1-octanethiol, N-oxides   |
| P-96-1433<br>178094-69-4 | 1-Octanesulfonamide, N-[3-(dimethyloxidoamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-.potassium salt  |
| P-97-0790<br>251099-16-8 | 1-Decanaminium, N-decyl-N,N-dimethyl-, salt with 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-1-octanesulfonic acid (1:1)   |
| P-98-0251<br>306978-04-1 | 2-Propenoic acid, butyl ester, polymers with acrylamide, 2-[methyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl acrylate and vinylidene chloride   |
| P-98-1272<br>306977-58-2 | 2-Propenoic acid, 2-methyl-, 3-(trimethoxysilyl)propyl ester, polymers with acrylic acid, 2-[methyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl acrylate and propylene glycol monoacrylate, hydrolyzed, compds. with 2,2'-(methylimino)bis[ethanol] |
| P-99-0188<br>306978-65-4 | Hexane, 1,6-diisocyanato-, homopolymer, N-(hydroxyethyl)-N-methyl perfluoro-C4-8-alkane sulfonamides- and stearyl alc.-blocked   |
| P-99-0319<br>306979-40-8 | Poly(oxy-1,2-ethanediyl), .alpha.-[2-(methylamino)ethyl]-.omega.-[(1,1,3,3-tetramethylbutyl)phenoxy]-, N-[(perfluoro-C4-8-alkyl)sulfonyl] derivs.  |

TABLE 3—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER NOVEMBER 8, 2007

| CAS No.  | CAS Sixteenth Collective Index Name  |
|----------|--|
| 335-24-0 | Cyclohexanesulfonic acid, 1,2,2,3,3,4,4,5,5,6,6-decafluoro-4-(1,1,2,2,2-pentafluoroethyl)-, potassium salt (1:1) |
| 335-71-7 | 1-Heptanesulfonyl fluoride, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-                                       |
| 335-77-3 | 1-Decanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,9,9,10,10,10-heneicosafuoro-                              |
| 335-97-7 | 1-Pentanesulfonamide, 1,1,2,2,3,3,4,4,5,5,5-undecafluoro-N-2-propen-1-yl-  |
| 355-03-3 | Cyclohexanesulfonyl fluoride, 1,2,2,3,3,4,4,5,5,6,6-undecafluoro-  |
| 355-46-4 | 1-Hexanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-  |
| 375-81-5 | 1-Pentanesulfonyl fluoride, 1,1,2,2,3,3,4,4,5,5,5-undecafluoro-  |
| 375-92-8 | 1-Heptanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-   |

TABLE 3—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER NOVEMBER 8, 2007—  
Continued

| CAS No.    | CAS Sixteenth Collective Index Name   |
|------------|---|
| 423–86–9   | 1-Octanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-2-propen-1-yl-   |
| 1869–77–8  | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]-, ethyl ester   |
| 1893–52–3  | 2-Propenoic acid, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]ethyl ester   |
| 2263–09–4  | 1-Octanesulfonamide, N-butyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-(2-hydroxyethyl)-  |
| 2706–91–4  | 1-Pentanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,5-undecafluoro-   |
| 2965–52–8  | 1-Octanesulfonamide, N,N'-[phosphinicobis(oxy-2,1-ethanediyl)]bis[N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-                            |
| 2991–50–6  | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]-  |
| 2991–52–8  | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]-, ammonium salt (1:1)   |
| 3107–18–4  | Cyclohexanesulfonic acid, 1,2,2,3,3,4,4,5,5,6,6-undecafluoro-, potassium salt (1:1)   |
| 3820–83–5  | 1-Octanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-[2-(phosphonoxy)ethyl]-  |
| 3871–50–9  | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]-, sodium salt (1:1)   |
| 3871–99–6  | 1-Hexanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-, potassium salt (1:1)   |
| 3872–25–1  | 1-Pentanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,5-undecafluoro-, potassium salt (1:1)   |
| 13417–01–1 | 1-Octanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-   |
| 21055–88–9 | Carbamic acid, N,N'-(4-methyl-1,3-phenylene)bis-, C,C'-bis[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]ethyl] ester |
| 24924–36–5 | 1-Octanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-2-propen-1-yl-   |
| 34455–03–3 | 1-Hexanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-(2-hydroxyethyl)-  |
| 37338–48–0 | Poly[oxy(methyl-1,2-ethanediyl)], .alpha.-[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]ethyl]-.omega.-hydroxy-      |
| 38850–52–1 | 1-Propanaminium, 3-[(carboxymethyl)[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]-N,N,N-trimethyl-, inner salt                          |
| 38850–60–1 | 1-Propanesulfonic acid, 3-[[3-(dimethylamino)propyl][(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]-                                     |
| 50598–28–2 | 1-Hexanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-   |
| 50598–29–3 | 1-Octanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-N-(phenylmethyl)-  |
| 51032–47–4 | Benzenesulfonic acid, [[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]methyl]-, sodium salt (1:1)                             |
| 52032–20–9 | Poly(oxy-1,2-ethanediyl), .alpha.-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]methylamino]carbonyl]-.omega.-butoxy-             |
| 52166–82–2 | 1-Propanaminium, N,N,N-trimethyl-3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]-, chloride (1:1)                                    |
| 52550–45–5 | Poly(oxy-1,2-ethanediyl), .alpha.-[2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]propylamino]ethyl]-.omega.-hydroxy-            |
| 55910–10–6 | Glycine, N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]-N-propyl-, potassium salt (1:1)   |
| 56372–23–7 | Poly(oxy-1,2-ethanediyl), .alpha.-[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]ethyl]-.omega.-hydroxy-                        |
| 56773–42–3 | Ethanaminium, N,N,N-triethyl-, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-1-octanesulfonate (1:1)  |

Environmental Protection Agency

§ 721.9582

TABLE 3—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER NOVEMBER 8, 2007—  
Continued

| CAS No.    | CAS Sixteenth Collective Index Name   |
|------------|---|
| 58920–31–3 | 2-Propenoic acid, 4-[[[1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]methylamino]butyl ester  |
| 59071–10–2 | 2-Propenoic acid, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl ester  |
| 60270–55–5 | 1-Heptanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-, potassium salt (1:1)  |
| 61577–14–8 | 2-Propenoic acid, 2-methyl-, 4-[[[1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]methylamino]butyl ester   |
| 66008–68–2 | 2-Propenoic acid, 2-[[[2,2,3,3,4,4,5,5,6,6,7,7,8,8,9,9,10,10,11,11,11-eicosafluoroundecyl)sulfonyl]methylamino]ethyl ester  |
| 66008–69–3 | 2-Propenoic acid, 2-[[[2,2,3,3,4,4,5,5,6,6,7,7,8,8,9,9,9-heptadecafluorononyl)sulfonyl]methylamino]ethyl ester  |
| 66008–70–6 | 2-Propenoic acid, 2-[methyl[(2,2,3,3,4,4,5,5,6,6,7,7,7-tridecafluoroheptyl)sulfonyl]amino]ethyl ester   |
| 67584–48–9 | 1-Hexanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-2-propen-1-yl-   |
| 67584–49–0 | 1-Heptanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-2-propen-1-yl-  |
| 67584–50–3 | 1-Heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-[3-(trichlorosilyl)propyl]-   |
| 67584–52–5 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]-, potassium salt (1:1)  |
| 67584–53–6 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]-, potassium salt (1:1)   |
| 67584–54–7 | 1-Heptanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-  |
| 67584–56–9 | 2-Propenoic acid, 2-[methyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]ethyl ester  |
| 67584–57–0 | 2-Propenoic acid, 2-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]amino]ethyl ester   |
| 67584–58–1 | 1-Propanaminium, N,N,N-trimethyl-3-[[[1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]-, iodide (1:1)  |
| 67584–60–5 | 2-Propenoic acid, 2-methyl-, 2-[methyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]ethyl ester   |
| 67584–61–6 | 2-Propenoic acid, 2-methyl-, 2-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]amino]ethyl ester  |
| 67584–62–7 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]-, potassium salt (1:1)   |
| 67906–38–1 | 2-Propenoic acid, 2-methyl-, 4-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]butyl ester  |
| 67906–40–5 | 2-Propenoic acid, 2-methyl-, 4-[methyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]butyl ester   |
| 67906–41–6 | 1-Heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-2-propen-1-yl-  |
| 67906–70–1 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]amino]ethyl ester   |
| 67906–71–2 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]amino]ethyl ester, polymer with octadecyl 2-propenoate and 2-propenoic acid |
| 67906–73–4 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]ethyl ester  |
| 67906–74–5 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]ethyl ester, polymer with octadecyl 2-propenoate and 2-propenoic acid      |
| 67923–61–9 | 1-Heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-[2-(phosphonoxy)ethyl]-   |
| 67939–36–0 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl ester   |



TABLE 3—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER NOVEMBER 8, 2007—  
Continued

| CAS No.    | CAS Sixteenth Collective Index Name  |
|------------|--|
| 67939–37–1 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl ester, polymer with octadecyl 2-propenoate and 2-propenoic acid  |
| 67939–42–8 | 1-Octanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8-heptadecafluoro-N-[3-(trichlorosilyl)propyl]-   |
| 67939–61–1 | 2-Propenoic acid, 2-methyl-, 4-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]butyl ester  |
| 67939–87–1 | 1-Pentanesulfonamide, N,N'-[phosphinicobis(oxy-2,1-ethanediyl)]bis[N-ethyl-1,1,2,2,3,3,4,4,5,5,5-undecafluoro-   |
| 67939–88–2 | 1-Octanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8-heptadecafluoro-, hydrochloride (1:1)   |
| 67939–90–6 | 1-Pentanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,5-undecafluoro-N-[2-(phosphonoxy)ethyl]-   |
| 67939–92–8 | 1-Hexanesulfonamide, N,N'-[phosphinicobis(oxy-2,1-ethanediyl)]bis[N-ethyl-1,1,2,2,3,3,4,4,5,6,6,6-tridecafluoro-   |
| 67939–93–9 | 1-Heptanesulfonamide, N,N'-[phosphinicobis(oxy-2,1-ethanediyl)]bis[N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-  |
| 67939–94–0 | 1-Heptanesulfonamide, N,N',N'-[phosphinyldynetris(oxy-2,1-ethanediyl)]tris[N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-  |
| 67939–96–2 | 2-Propenoic acid, 2-methyl-, 2-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl ester   |
| 67939–97–3 | 1-Heptanesulfonamide, N,N'-[phosphinicobis(oxy-2,1-ethanediyl)]bis[N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-, ammonium salt (1:1)]  |
| 67939–98–4 | 1-Heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-[2-(phosphonoxy)ethyl]-, ammonium salt (1:2)   |
| 67940–02–7 | 1-Heptanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-, hydrochloride (1:1)  |
| 67969–65–7 | 1-Hexanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-[2-(phosphonoxy)ethyl]-   |
| 68081–83–4 | Carbamic acid, N,N'-(4-methyl-1,3-phenylene)bis-, bis[2-[ethyl[(perfluoro-C4-8-alkyl)sulfonyl]amino]ethyl] ester   |
| 68084–62–8 | 2-Propenoic acid, 2-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl ester  |
| 68156–00–3 | Cyclohexanesulfonyl fluoride, nonafluorobis(trifluoromethyl)-  |
| 68156–06–9 | Cyclohexanesulfonyl fluoride, decafluoro(1,1,2,2,2-pentafluoroethyl)-  |
| 68156–07–0 | Cyclohexanesulfonic acid, decafluoro(trifluoromethyl)-, potassium salt (1:1)   |
| 68227–87–2 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoroocetyl)sulfonyl]amino]ethyl ester, telomer with 2-[ethyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate, 2-[ethyl |
| 68227–94–1 | 2-Propenoic acid, 2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoroocetyl)sulfonyl]methylamino]ethyl ester, polymer with 2-[methyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]ethyl 2-propenoate, .alpha.-(2-methyl-1-oxo-2-propen-1-yl)-.omega.-hydroxypoly(oxy-1,2-ethanediyl), .alpha.-(2-methyl-1-oxo-2-propen-1-yl)-.omega.      |
| 68227–96–3 | 2-Propenoic acid, butyl ester, telomer with 2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoroocetyl)sulfonyl]methylamino]ethyl 2-propenoate, 2-[methyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]ethyl 2-propenoate, .alpha.-(2-methyl-1-oxo-2-propen-1-yl)-.omega.-hydroxypoly(oxy-1,4-butanediyl), .alpha.-(2-methyl               |
| 68227–97–4 | 2-Propenoic acid, 4-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]butyl ester  |

TABLE 3—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER NOVEMBER 8, 2007—  
Continued

| CAS No.    | CAS Sixteenth Collective Index Name   |
|------------|---|
| 68227–98–5 | 2-Propenoic acid, 4-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]butyl ester  |
| 68227–99–6 | 2-Propenoic acid, 4-[methyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]butyl ester  |
| 68228–00–2 | 2-Propenoic acid, ethyl ester, polymer with 4-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptafluorooctyl)sulfonyl]methylamino]butyl 2-propenoate, 4-[methyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]butyl 2-propenoate, .alpha.-(2-methyl-1-oxo-2-propen-1-yl)-.omega.-hydroxypoly(oxy-1,4-butanediyl), .alpha.-(2-methyl |
| 68239–72–5 | 1-Pentanesulfonamide, 1,1,2,2,3,3,4,4,5,5-undecafluoro-N-(4-hydroxybutyl)-N-methyl-   |
| 68239–73–6 | 1-Octanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptafluoro-N-(4-hydroxybutyl)-N-methyl-   |
| 68239–74–7 | 1-Hexanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-(4-hydroxybutyl)-N-methyl-   |
| 68239–75–8 | 1-Heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-[3-(trimethoxysilyl)propyl]-  |
| 68259–06–3 | 1-Nonanesulfonyl fluoride, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,9,9,9-nonafluoro-  |
| 68259–07–4 | 1-Heptanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-, ammonium salt (1:1)   |
| 68259–08–5 | 1-Hexanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-, ammonium salt (1:1)  |
| 68259–09–6 | 1-Pentanesulfonic acid, 1,1,2,2,3,3,4,4,5,5-undecafluoro-, ammonium salt (1:1)  |
| 68259–12–1 | 1-Nonanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,9,9,9-nonafluoro-  |
| 68259–14–3 | 1-Heptanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-methyl-   |
| 68259–15–4 | 1-Hexanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-methyl-  |
| 68259–38–1 | Poly[oxy(methyl-1,2-ethanediyl)], .alpha.-[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]ethyl]-.omega.-hydroxy-  |
| 68259–39–2 | Poly[oxy(methyl-1,2-ethanediyl)], .alpha.-[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl]-.omega.-hydroxy-   |
| 68298–06–6 | 2-Propenoic acid, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]ethyl ester   |
| 68298–08–8 | 1-Pentanesulfonamide, 1,1,2,2,3,3,4,4,5,5-undecafluoro-N-(phenylmethyl)-  |
| 68298–09–9 | 1-Hexanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-(phenylmethyl)-  |
| 68298–10–2 | 1-Heptanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-(phenylmethyl)-   |
| 68298–11–3 | 1-Propanaminium, 3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptafluorooctyl)sulfonyl](3-sulfopropyl)amino]-N-(2-hydroxyethyl)-N,N-dimethyl-, inner salt   |
| 68298–13–5 | 1-Pentanesulfonamide, 1,1,2,2,3,3,4,4,5,5-undecafluoro-N-methyl-  |
| 68298–60–2 | 2-Propenoic acid, 2-[butyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl ester  |
| 68298–78–2 | 2-Propenoic acid, 2-methyl-, 2-[[[[5-[[[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptafluorooctyl)sulfonyl]amino]ethoxy]carbonyl]amino]-2-methylphenyl]amino]carbonyl]oxy]propyl ester, telomer with butyl 2-propenoate, 2-[[[[5-[[[2-[ethyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]ethoxy]carbon                 |
| 68298–80–6 | Poly(oxy-1,2-ethanediyl), .alpha.-[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]ethyl]-.omega.-hydroxy-  |
| 68298–81–7 | Poly(oxy-1,2-ethanediyl), .alpha.-[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl]-.omega.-hydroxy-   |
| 68298–89–5 | 1-Heptanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-(4-hydroxybutyl)-N-methyl-  |
| 68299–20–7 | Benzenesulfonic acid, [[[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]methyl]-, sodium salt (1:1)   |
| 68299–21–8 | Benzenesulfonic acid, [[[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]amino]methyl]-, sodium salt (1:1)   |

TABLE 3—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER NOVEMBER 8, 2007—  
Continued

| CAS No.    | CAS Sixteenth Collective Index Name  |
|------------|--|
| 68299–29–6 | Benzenesulfonic acid, ar-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]methyl]-, sodium salt (1:1)  |
| 68299–39–8 | 2-Propenoic acid, 2-methyl-, 4-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]methylamino]butyl ester, telomer with butyl 2-propenoate, 2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]methylamino]ethyl 2-propenoate, 4-[methyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]butyl 2-methyl-2-propenoate |
| 68310–02–1 | 1-Heptanesulfonamide, N-butyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-(2-hydroxyethyl)-  |
| 68310–17–8 | Poly[oxy(methyl-1,2-ethanediy)], .alpha.-[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]ethyl]-.omega.-hydroxy-  |
| 68310–75–8 | 1-Propanaminium, 3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]-N,N,N-trimethyl-, iodide, ammonium salt (1:1:1)  |
| 68318–34–3 | Cyclohexanesulfonyl fluoride, decafluoro(trifluoromethyl)-   |
| 68318–36–5 | 1-Propanaminium, 3-[(carboxymethyl)[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]-N,N,N-trimethyl-, inner salt   |
| 68391–09–3 | Sulfonic acids, C6-12-alkane, perfluoro, potassium salts   |
| 68541–01–5 | Benzoic acid, 2,3,4,5-tetrachloro-6-[[[3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]oxy]phenyl]amino]carbonyl]-, potassium salt (1:1)  |
| 68541–02–6 | Benzoic acid, 2,3,4,5-tetrachloro-6-[[[3-[[[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]oxy]phenyl]amino]carbonyl]-, potassium salt (1:1)   |
| 68555–69–1 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]-, sodium salt (1:1)  |
| 68555–70–4 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]-, sodium salt (1:1)  |
| 68555–71–5 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]-, sodium salt (1:1)   |
| 68555–72–6 | 1-Pentanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,5-undecafluoro-N-(2-hydroxyethyl)-   |
| 68555–73–7 | 1-Heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-(2-hydroxyethyl)-  |
| 68555–74–8 | 1-Pentanesulfonamide, 1,1,2,2,3,3,4,4,5,5,5-undecafluoro-N-(2-hydroxyethyl)-N-methyl-  |
| 68555–75–9 | 1-Hexanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-(2-hydroxyethyl)-N-methyl-  |
| 68555–76–0 | 1-Heptanesulfonamide, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-N-(2-hydroxyethyl)-N-methyl-   |
| 68555–78–2 | 1-Pentanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,5-undecafluoro-  |
| 68555–79–3 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]-, ethyl ester  |
| 68555–81–7 | 1-Propanaminium, N,N,N-trimethyl-3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]-, chloride (1:1)  |
| 68568–77–4 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]ethyl ester, polymer with 2-chloro-1,3-butadiene, 2-[ethyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl 2-methyl         |
| 68608–13–9 | Sulfonamides, C4-8-alkane, perfluoro, N-ethyl-N-(hydroxyethyl), reaction products with TDI   |
| 68797–76–2 | 2-Propenoic acid, 2-methyl-, 2-ethylhexyl ester, polymer with 2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]methylamino]ethyl 2-propenoate, 2-[methyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]ethyl 2-propenoate, 2-[methyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl 2-propenoate       |
| 68815–72–5 | Benzoic acid, 2,3,4,5-tetrachloro-6-[[[3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluorohexyl)sulfonyl]oxy]phenyl]amino]carbonyl]-, potassium salt (1:1)   |
| 68877–32–7 | 2-Propenoic acid, 2-methyl-, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]ethyl ester, polymer with 2-[ethyl[(1,1,2,2,3,3,4,4,4-nonafluorobutyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl 2-methyl-2-propenoate, 2-[ethyl          |

TABLE 3—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER NOVEMBER 8, 2007—  
Continued

| CAS No.    | CAS Sixteenth Collective Index Name  |
|------------|--|
| 68891-97-4 | Chromium, diaquatetrachloro[.mu.-[N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]glycinato-.kappa.O:.kappa.O']]-.mu.-hydroxybis(2-propanol)-   |
| 68891-98-5 | Chromium, diaquatetrachloro[.mu.-[N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]glycinato-.kappa.O:.kappa.O']]-.mu.-hydroxybis(2-propanol)di-   |
| 68891-99-6 | Chromium, diaquatetrachloro[.mu.-[N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]glycinato-.kappa.O:.kappa.O']]-.mu.-hydroxybis(2-propanol)di-  |
| 68957-31-3 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]-   |
| 68957-32-4 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]-  |
| 68957-53-9 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]-, ethyl ester   |
| 68957-54-0 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]-, ethyl ester   |
| 68957-55-1 | 1-Propanaminium, N,N,N-trimethyl-3-[[[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]-, chloride (1:1)   |
| 68957-57-3 | 1-Propanaminium, N,N,N-trimethyl-3-[[[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]-, iodide (1:1)   |
| 68957-58-4 | 1-Propanaminium, N,N,N-trimethyl-3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]amino]-, iodide (1:1)  |
| 68957-60-8 | 1-Pentanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,5-undecafluoro-, hydrochloride (1:1)   |
| 68957-61-9 | 1-Hexanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-, hydrochloride (1:1)   |
| 68957-62-0 | 1-Heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-   |
| 68957-63-1 | Glycine, N-ethyl-N-[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]-  |
| 68958-60-1 | Poly(oxy-1,2-ethanediyl), .alpha.-[2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]ethyl]-.omega.-methoxy-  |
| 70225-15-9 | 1-Heptanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-, compd. with 2,2'-iminobis[ethanol] (1:1)   |
| 70225-16-0 | 1-Hexanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-, compd. with 2,2'-iminobis[ethanol] (1:1)  |
| 70225-17-1 | 1-Pentanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,5-undecafluoro-, compd. with 2,2'-iminobis[ethanol] (1:1)  |
| 70225-20-6 | 1-Propanaminium, N,N,N-trimethyl-3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]-, sulfate (2:1)   |
| 70225-24-0 | 1-Propanaminium, N,N,N-trimethyl-3-[[[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]-, sulfate (2:1)  |
| 70225-26-2 | 1-Propanaminium, 3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoroocetyl)sulfonyl]amino]-N,N,N-trimethyl-, sulfate (2:1)   |
| 70248-52-1 | 1-Propanaminium, N,N,N-trimethyl-3-[[[(1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoroheptyl)sulfonyl]amino]-, sulfate (2:1)   |
| 70900-40-2 | 2-Propenoic acid, 2-methyl-, 2-[[[5-[[[4-[[[1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoroocetyl)sulfonyl]methylamino]butoxy]carbonyl]amino]-2-methylphenyl]amino]carbonyl]oxy]propyl ester, telomer with butyl 2-propenoate, 2-[[[1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoroocetyl)sulfonyl]methylamino]ethyl 2-propenoate, |
| 71463-74-6 | 1-Octanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoro-, compd. with piperidine (1:1)  |
| 71463-78-0 | Phosphonic acid, P-[3-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluoroocetyl)sulfonyl]amino]propyl]-  |
| 71463-79-1 | Phosphonic acid, P-[3-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]propyl]-  |

TABLE 3—PFAS CHEMICALS SUBJECT TO REPORTING ON OR AFTER NOVEMBER 8, 2007—  
Continued

| CAS No.     | CAS Sixteenth Collective Index Name  |
|-------------|--|
| 71463–80–4  | Phosphonic acid, P-[3-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]propyl]-, diethyl ester  |
| 71463–81–5  | Phosphonic acid, P-[3-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoroheptyl)sulfonyl]amino]propyl]-, diethyl ester   |
| 72785–08–1  | 1-Propanesulfonic acid, 3-[[3-(dimethylamino)propyl][(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]-  |
| 73018–93–6  | 2-Propenoic acid, 2-methyl-, 2-ethylhexyl ester, polymer with 2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]methylamino]ethyl 2-propenoate   |
| 73019–19–9  | Benzamide, 4-[[4-[[[2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]propylamino]ethyl]amino]carbonyl]phenyl]methyl]-N-octadecyl]-  |
| 73019–20–2  | 1,3-Benzenedicarboxamide, N <sup>3</sup> -[2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]methylamino]ethyl]-N <sup>1</sup> -[2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]propylamino]ethyl]-4-methyl]- |
| 73019–28–0  | 2-Propenoic acid, 2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]propylamino]ethyl ester, polymer with .alpha.-(2-methyl-1-oxo-2-propen-1-yl)-.omega.-methoxypoly(oxy-1,2-ethanediyl)   |
| 73038–33–2  | 2-Propenoic acid, 2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]propylamino]ethyl ester, polymer with 2-methyloxirane polymer with oxirane mono(2-methyl-2-propenoate)   |
| 73275–59–9  | 2-Propenoic acid, 2-[[[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]propylamino]ethyl ester, polymer with .alpha.-(2-methyl-1-oxo-2-propen-1-yl)-.omega.-butoxypoly[oxy(methyl-1,2-ethanediyl)]                                      |
| 73772–33–5  | 1-Hexanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-, acetate (1:1)   |
| 73772–34–6  | 1-Hexanesulfonamide, N-[3-(dimethylamino)propyl]-1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-N-[2-[2-(2-hydroxyethoxy)ethoxy]ethyl]-   |
| 95590–48–0  | 2-Propenoic acid, 2-methyl-, 3-(trimethoxysilyl)propyl ester, polymer with ethenylbenzene, 2-[ethyl[(1,1,2,2,3,3,4,4,5,5,6,6,7,7,8,8,8-heptadecafluorooctyl)sulfonyl]amino]ethyl 2-propenoate and 2-hydroxyethyl 2-propenoate                            |
| 148240–81–7 | Fatty acids, C18-unsatd., trimers, 2-[methyl[(1,1,2,2,3,3,4,4,5,5,5-undecafluoropentyl)sulfonyl]amino]ethyl esters   |
| 179005–06–2 | Sulfonamides, C4-8-alkane, perfluoro, N-[3-(dimethylamino)propyl], potassium salts   |

(2) The significant new uses are:

- (i) Any manufacture or import for any use of any chemical substance listed in Table 1 of paragraph (a)(1) of this section.
  - (ii) Any manufacture or import for any use of any chemical substance listed in Table 2 of paragraph (a)(1) of this section, except as noted in paragraph (a)(3) of this section.
  - (iii) Any manufacture or import for any use of any chemical substance listed in Table 3 of paragraph (a)(1) of this section, except as noted in paragraphs (a)(3) through (a)(5) of this section.
- (3) Manufacture or import of any chemical substance listed in Table 2 and Table 3 of paragraph (a)(1) of this section for the following specific uses shall not be considered as a significant

new use subject to reporting under this section:

- (i) Use as an anti-erosion additive in fire-resistant phosphate ester aviation hydraulic fluids.
- (ii) Use as a component of a photoresist substance, including a photo acid generator or surfactant, or as a component of an anti-reflective coating, used in a photomicro lithography process to produce semiconductors or similar components of electronic or other miniaturized devices.
- (iii) Use in coating for surface tension, static discharge, and adhesion control for analog and digital imaging films, papers, and printing plates, or as a surfactant in mixtures used to process imaging films.

## Environmental Protection Agency

## § 721.9620

(iv) Use as an intermediate only to produce other chemical substances to be used solely for the uses listed in paragraph (a)(3)(i), (ii), or (iii) of this section.

(4) Manufacture or import of tetraethylammonium perfluorooctanesulfonate (CAS No. 56773-42-3) for use as a fume/mist suppressant in metal finishing and plating baths shall not be considered as a significant new use subject to reporting under this section. Examples of such metal finishing and plating baths include: Hard chrome plating; decorative chromium plating; chromic acid anodizing; nickel, cadmium, or lead plating; metal plating on plastics; and alkaline zinc plating.

(5) Manufacture or import of: 1-Pentanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,5-undecafluoro-, potassium salt (CAS No. 3872-25-1); Glycine, N-ethyl-N-[(tridecafluorohexyl)sulfonyl]-, potassium salt (CAS No. 67584-53-6); Glycine, N-ethyl-N-[(pentadecafluoroheptyl)sulfonyl]-, potassium salt (CAS No. 67584-62-7); 1-Heptanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro-, ammonium salt (CAS No. 68259-07-4); 1-Heptanesulfonamide, N-ethyl-1,1,2,2,3,3,4,4,5,5,6,6,7,7,7-pentadecafluoro- (CAS No. 68957-62-0); Poly(oxy-1,2-ethanediyl), .alpha.-[2-[ethyl[(pentadecafluoroheptyl)sulfonyl]amino]ethyl]-.omega.-methoxy- (CAS No. 68958-60-1); or 1-Hexanesulfonic acid, 1,1,2,2,3,3,4,4,5,5,6,6,6-tridecafluoro-, compd. with 2,2'-iminobis[ethanol] (1:1) (CAS No. 70225-16-0) for use as a component of an etchant, including a surfactant or fume suppressant, used in the plating process to produce electronic devices shall not be considered a significant new use subject to reporting under this section.

(b) [Reserved]

[67 FR 72863, Dec. 9, 2002, as amended at 72 FR 57229, Oct. 9, 2007]

### § 721.9595 Alkyl benzene sulfonic acids and alkyl sulfates, amine salts (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkyl benzene sulfonic acids and alkyl sulfates, amine salts (PMNs

P-97-296/297/298/299) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44582, Aug. 20, 1998]

### § 721.9597 Salt of a substituted sulfonated aryl azo compound (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as salt of a substituted sulfonated aryl azo compound (PMN P-00-0094) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15089, Mar. 28, 2003]

### § 721.9620 Aromatic sulfonic acid compound with amine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## § 721.9630

chemical substance identified generically as aromatic sulfonic acid compound with amine (PMN P-93-832) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Release to water*. Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 30 ppb).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[58 FR 51709, Oct. 4, 1993]

## § 721.9630 Polyfluorosulfonic acid salt.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as polyfluorosulfonic acid salt (P-90-587) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80(y) (1) and (2).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements*. The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.100 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[56 FR 15793, Apr. 17, 1991. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## 40 CFR Ch. I (7-1-10 Edition)

## § 721.9635 Terpene residue distillates.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as terpene residue distillates (PMN P-96-897) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water*. Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 10).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[63 FR 3438, Jan. 22, 1998]

## § 721.9640 Salt of an acrylic acid - acrylamide terpolymer (generic).

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as salt of an acrylic acid - acrylamide terpolymer (PMN P-99-817) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80(v)(2), (w)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[68 FR 70183, Dec. 17, 2003]

**§ 721.9650 Tetramethylammonium salts of alkylbenzenesulfonic acid.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as tetramethylammonium salts of alkylbenzenesulfonic acid (PMN P-92-1364) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 80 ppb).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51687, Oct. 4, 1993]

**§ 721.9656 Thiaalkanethiol.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a thiaalkanethiol (PMN P-94-1487) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45084, Aug. 30, 1995]

**§ 721.9657 Disubstituted thiadiazole.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a disubstituted thiadiazole (PMN P-97-314) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (a), (b), (c), and (j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3438, Jan. 22, 1998]

**§ 721.9658 Thiadiazole derivative.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a thiadiazole derivative (PMN P-94-1631) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (a), (c), (f), (v)(1), (w)(1), and (x)(1).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where n = 90).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[60 FR 45085, Aug. 30, 1995]



**§ 721.9659 Disubstituted thiadiazosulfone.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a disubstituted thiadiazosulfone (PMN P-97-304) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (a), (b), (c), and (j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3438, Jan. 22, 1998]

**§ 721.9660 Methylthiouracil.**

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance methylthiouracil (CAS No. 56-04-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63517, Dec. 1, 1993]

**§ 721.9661 Diphenol tars (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as diphenol tars (PMN P-97-813) is

subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44582, Aug. 20, 1998]

**§ 721.9662 Thieno[3,4-b]-1,4-dioxin, 2,3-dihydro- (9CI).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as thieno[3,4-b]-1,4-dioxin, 2,3-dihydro-(9CI) (PMN P-95-1825; CAS No. 126213-50-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(2)(i).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3439, Jan. 22, 1998; 63 FR 9441, Feb. 25, 1998]

## Environmental Protection Agency

§ 721.9668

### § 721.9663 Poly(oxy-1,2-ethanediyl), alpha, alpha'-[thiobis (1-oxo-3,1-propanediyl)]bis [omega-hydroxy-bis (C<sub>11-15</sub> and C<sub>11-15-isoalkyl</sub>) ethers.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as poly(oxy-1,2-ethanediyl), alpha, alpha'-[thiobis (1-oxo-3,1-propanediyl)]bis [omega-hydroxy-bis(C<sub>11-15</sub> and C<sub>11-15-isoalkyl</sub>) ethers (PMN P-97-497; CAS No. 174254-18-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44582, Aug. 20, 1998]

### § 721.9664 9H-Thioxanthen-9-one,2,4-diethyl.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 9H-thioxanthen-9-one,2,4-diethyl (PMN P-96-1315; CAS No. 82799-44-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3439, Jan. 22, 1998]

### § 721.9665 Organotin catalysts.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as organotin catalysts (PMNs P-93-853, P-93-854, P-93-855, P-93-856, P-93-857, and P-93-858) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80 (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51709, Oct. 4, 1993]

### § 721.9668 Organotin lithium compound.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as an organotin lithium compound (PMN P-93-1119) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## § 721.9670

(b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 9450, Feb. 25, 1998]

### § 721.9670 Tetraaryltin (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a Tetraaryltin (PMN P-99-0198) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Release to water.* Requirements as specified § 721.90 (a)(4), (b)(4), and (c)(4) (N=1 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81404, Dec. 26, 2000]

### § 721.9671 Triaryltin (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a Triaryltin (PMN P-99-0199) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Release to water.* Requirements as specified § 721.90 (a)(4), (b)(4), and (c)(4) (N=1 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## 40 CFR Ch. I (7-1-10 Edition)

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 81404, Dec. 26, 2000]

### § 721.9672 Amides, tall-oil fatty, N-[2-[2-hydroxyethyl]amino]ethyl], reaction products with sulfur dioxide; fatty acids, tall-oil, reaction products with 1-piperazineethanamine and sulfur dioxide; fatty acids, tall-oil reaction products with sulfur dioxide and triethylenetetramine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as amides, tall-oil fatty, N-[2-[2-hydroxyethyl]amino]ethyl], reaction products with sulfur dioxide; fatty acids, tall-oil, reaction products with 1-piperazineethanamine and sulfur dioxide; fatty acids, tall-oil reaction products with sulfur dioxide and triethylenetetramine (PMN P-98-725; CAS Nos. 202483-48-5, 203809-20-5, and 204401-83-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 373, Jan. 5, 2000]

### § 721.9674 Sulfonated-copper phthalocyanine salt of a triaryl-methane dye (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

§ 721.9685

chemical substance identified generically as sulfonated-copper phthalocyanine salt of a triaryl-methane dye (PMN P-00-1055) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(v)(1), (w)(1), and (x)(1).

(ii) *Release to water.* Requirements as specified in § 721.90(a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70183, Dec. 17, 2003]

### § 721.9675 Titanate [Ti<sub>6</sub>O<sub>13</sub> (2-)], dipotassium.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as titanate [Ti<sub>6</sub>O<sub>13</sub> (2-)], dipotassium (CAS No. 12056-51-8) (PMN P-90-0226) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(ii), (g)(1)(vii), (g)(2)(ii), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (l), and (q). In addition, a significant new use of the substance is importation of the PMN substance if:

(A) Manufactured by other than the method described in premanufacture notice P-90-226.

(B) The bulk density measurements of the PMN substance in the pure form are less than 0.4 g/cm<sup>3</sup> or greater than 0.6 g/cm<sup>3</sup>. The bulk density of each shipment must be verified, by lot, prior to clearing U.S. customs.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance as specified in § 721.125 (a), (b), (c), (f), (g), (h), and (i). In addition, records shall be kept identifying the foreign supplier and documenting, by lot, for each shipment, the method of manufacture and bulk density measurements.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[56 FR 40215, Aug. 13, 1991. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9680 Alkaline titania silica gel (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkaline titania silica gel (PMN P-95-529) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[61 FR 63740, Dec. 2, 1996]

### § 721.9685 Mixed trialkylamines (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

§ 721.9700

40 CFR Ch. I (7-1-10 Edition)

chemical substances identified generically as mixed trialkylamines (PMNs P-97-943/944/945/946/947/948) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44583, Aug. 20, 1998]

§ 721.9700 **Monosubstituted alkoxyaminotrazines (generic name).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance monosubstituted alkoxyaminotrazines (PMN P-86-1043) is subject to reporting under this section for the significant new uses described in paragraph (a)(1)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3), (b) [concentration set at 0.1 percent], and (c).

(B) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) [concentration set at 0.1 percent], (f), and (g)(1)(iv), (g)(1)(vii), and (g)(1)(viii), (g)(2)(i) and (g)(2)(v), (g)(4)(xi), and (g)(5). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on a MSDS does not apply when a MSDS is not required under § 721.72(c).

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(D) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (a)(2) and (b)(1) and (b)(2).

(E) *Release to water.* Requirements as specified in § 721.90 (a)(4) [concern level of 10 ppb], (b)(4) [concern level of 10 ppb], and (c)(4) [concern level of 10 ppb].

(ii) [Reserved]

(2) The chemical substance monosubstituted alkoxyaminotrazines (PMN P-86-1044) is subject to reporting under this section for the significant new uses described in paragraph (a)(2)(i) of this section.

(i) The significant new uses are:

(A) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iii) through (a)(5)(vii), and (a)(6)(i), (b) [concentration set at 0.1 percent], and (c).

(B) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (d), (e) [concentration set at 0.1 percent], (f), and (g)(1)(iv), (g)(1)(vii), and (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v), (g)(4)(xi), and (5). The provisions of § 721.72(d) requiring employees to be provided with information on the location and availability of a written hazard communication program and MSDSs do not apply when the written program and MSDS are not required under § 721.72 (a) and (c), respectively. The provision of § 721.72(g) requiring placement of specific information on a MSDS does not apply when a MSDS is not required under § 721.72(c).

(C) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(D) *Disposal.* Requirements as specified in § 721.85 (a)(1) and (a)(2) and (b)(1) and (b)(2).

(E) *Release to water.* Requirements as specified in § 721.90 (a)(4) [concern level of 1 ppb], (b)(4) [concern level of 1 ppb], and (c)(4) [concern level of 1 ppb].

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable

## Environmental Protection Agency

## § 721.9720

to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26108, June 26, 1990. Redesignated and amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9717 Azo monochloro triazine reactive dye.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an azo monochloro triazine reactive dye (PMN P-96-238) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(2), (w)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3439, Jan. 22, 1998]

### § 721.9719 Tris carbamoyl triazine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as tris carbamoyl triazine (PMN P-95-1098) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 40).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[63 FR 44583, Aug. 20, 1998; 63 FR 62956, Nov. 10, 1998]

### § 721.9720 Disubstituted alkyl triazines (generic name).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as disubstituted alkyl triazines (PMNs P-85-932 and P-85-933) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(iv), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b)(1), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv), and (g)(2)(v). The provision of § 721.72(d) requiring that employees be provided with information on the location and availability of MSDSs does not apply when an MSDS is not required under § 721.72(c). The provision of § 721.72(g) requiring placement of specific information on an MSDS does not apply when an MSDS is not required under § 721.72(c).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(iv) *Release to water.* § 721.90 (a)(1), (b)(1), and (c)(1).

## § 721.9730

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (i) and (k).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[55 FR 26101, June 26, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.9730 1,3,5-Triazin-2-amine, 4-dimethylamino-6-substituted-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances generically identified as 1,3,5-triazin-2-amine, 4-dimethylamino-6-substituted- (PMN Nos. P-92-343 and P-92-344) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(3), (a)(4), (a)(5)(i), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Disposal.* Requirements as specified in § 721.85 as thus amended: It is a significant new use to dispose of the process or use stream associated with any use of the substance or with any manner or method of manufacturing associated with any use of the substance by landfill.

(v) *Release to water.* Requirements as specified in § 721.90(a)(4) (where N = 1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a)

## 40 CFR Ch. I (7-1-10 Edition)

through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[58 FR 32241, June 8, 1993, as amended at 58 FR 29946, May 24, 1993]

## § 721.9740 Brominated triazine derivative.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a brominated triazine derivative (PMN P-91-403) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5)(iv), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(iv), (g)(1)(vi), (g)(1)(vii), (g)(2)(iv), and (g)(5). The hazard communication requirements do not apply when the chemical substance is present in a plastic, elastomer, rubber matrix, or in solution.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in section 721.80(q). Any amount of the PMN substance imported in a plastic, elastomer, rubber matrix, or in a solution, such that inhalation is precluded, shall not be included in the production limit calculations.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (d) and (f) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

## Environmental Protection Agency

§ 721.9790

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44075, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

### § 721.9750 2-Chloro-4,6-bis(substituted)-1,3,5-triazine, dihydrochloride.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 2-chloro-4,6-bis(substituted)-1,3,5-triazine, dihydrochloride (PMN P-91-659) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5). The following additional statements shall appear on each label and MSDS required by this paragraph: This substance may be toxic to terrestrial organisms and plants. Notice to users: Release to water restrictions apply.

(ii) *Disposal.* Requirements as specified in § 721.85. A significant new use of this substance is any release of this substance to land.

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 10 ppb).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (j), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[59 FR 27485, May 27, 1994]

§ 721.9790 **Benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[5-[[4-[bis(2-hydroxypropyl) amino]-6-(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-, disodium salt, compd. with 2,2',2''-nitrolo-tris[ethanol] (1:2); Benzenesulfonic acid, 5-[[4-[bis(2-hydroxyethyl)amino]-6-(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-2-[2-[4-[[4-[bis(2-hydroxypropyl)amino]-6-(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-2-sulfophenyl]ethenyl]-, disodium salt, compd. with 2,2',2''-nitrolo-tris[ethanol] (1:2).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a Benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[5-[[4-[bis(2-hydroxypropyl)amino]-6-(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-, disodium salt, compd. with 2,2',2''-nitrolo-tris[ethanol] (1:2); Benzenesulfonic acid, 5-[[4-[bis(2-hydroxyethyl)amino]-6-(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-2-[2-[4-[[4-[bis(2-hydroxypropyl)amino]-6-(3-sulfophenyl)amino]-1,3,5-triazin-2-yl]amino]-2-sulfophenyl] ethenyl]-, disodium salt, compd. with 2,2',2''-nitrolo-tris[ethanol] (1:2) (PMN P-98-716; CAS Nos. 198716-46-0 and 198716-48-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 373, Jan. 5, 2000]



**§ 721.9795 Benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[(4,6-dichloro-1,3,5-triazin-2-yl) amino]-, disodium salt, substituted with dialkyl amines (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[(4,6-dichloro-1,3,5-triazin-2-yl)amino]-, disodium salt, substituted with dialkyl amines (PMN P-98-774) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 373, Jan. 5, 2000]

**§ 721.9798 Benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[5-[4-substituted-6-substituted-1,3,5-triazin-2-yl]aminol]-, sodium salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a benzenesulfonic acid, 2,2'-(1,2-ethenediyl)bis[5-[4-substituted-6-substituted-1,3,5-triazin-2-yl]amino]-, sodium salt (PMN P-98-1222) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (v)(2), (w)(1), (w)(2), (x)(1), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[65 FR 374, Jan. 5, 2000]

**§ 721.9800 Poly(substituted triazinyl) piperazine (generic name).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance poly(substituted triazinyl) piperazine (PMN P-88-436) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (b)(2), (c), (e) (concentration set at 1.0 percent), (f), (g)(1) (statement-health effects not fully determined), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), and (g)(5). The requirements of this paragraph shall not apply when the PMN substance is encapsulated in a polymeric matrix.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a) through (c), (g), and (h).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 32419, Aug. 9, 1990. Redesignated and amended at 58 FR 29946, 29947, May 24, 1993; 58 FR 34204, June 23, 1993; 63 FR 45956, Aug. 28, 1998]

**§ 721.9820 Substituted triazole.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance generically identified as a substituted triazole (PMN P-90-1731) is subject to reporting under

this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(2)(iv), (a)(3), (a)(4), (a)(5)(i), (a)(5)(ii), (a)(5)(iii), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(iv), (g)(1)(v), (g)(1)(vi), (g)(1)(vii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), (g)(4)(ii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (where N = 12).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44075, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.9825 Phenyl substituted triazolones.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as phenyl substituted triazolones (PMNs P-93-204, P-94-1870, P-94-1871, P-94-1872, P-94-1873, and P-94-1874) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), (a)(5)(iii),

(a)(5)(iv), (a)(5)(v), (a)(5)(vi), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c). The imperviousness of the gloves selected pursuant to (a)(2)(i) of this section must be demonstrated by actual testing under (a)(3)(i) of this section and not by manufacturer specifications. In addition, there must be no permeation of the chemical substance greater than 15 µg/day-cm<sup>2</sup> as a daily cumulative total when tested in accordance with the most current version of the American Society for Testing and Materials (ASTM) F739 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases" or ASTM F1383 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases Under Conditions of Intermittent Contact."

(A) For conditions of exposure which are intermittent, gloves may be tested in accordance with the most current version of ASTM F1383 "Standard Test Method for Resistance of Protective Clothing Materials to Permeation by Liquids or Gases Under Conditions of Intermittent Contact," provided the contact time in testing is greater than or equal to the expected duration of dermal contact, and the purge time used in the testing is less than or equal to the expected duration of non-contact during the intermittent cycle of dermal exposure in the workplace. If ASTM F1383 is used for testing, the company must submit to the Agency a description of worker activities involving the chemical substance which includes daily frequencies and durations of potential worker exposures.

(B) The results of all glove permeation testing must be reported in accordance with the most current version of (ASTM) F1194 "Guide for Documenting the Results of Chemical Permeation Testing of Protective Clothing Materials." The company must submit all test data to the Agency and must receive written Agency approval for each type of glove tested prior to use of such gloves. Gloves must be discarded and replaced with such frequency as to ensure that they will reliably provide an impervious barrier to the chemical substances under normal and expected conditions of exposure within the work area. Gloves that have been damaged

**§ 721.9830**

**40 CFR Ch. I (7–1–10 Edition)**

or are defective shall not be used. For PMNs P-94-1871 through P-94-1874, EPA has approved North Safety Butyl Rubber gloves (32 mils thick). For P-93-204 and P-94-1870, EPA has approved North Safety Butyl Rubber gloves (32 mils thick) only if used in combination with a chemical-resistant glove that has been demonstrated (EPA review not required) impermeable to the solvent, e.g., North Silvershield gloves and North 4H gloves.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iv), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(i), and (g)(5).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 5 for all the chemical substances subject to the provisions of this rule combined). However, contrary to the requirements specified in § 721.91, if the waste stream containing the chemical substances will be treated using activated carbon adsorption, then the amount of chemical substances reasonably likely to be removed from the waste stream by such treatment may be subtracted in calculating the number of kilograms released. No more than the following percent removal efficiencies may be attributed to such treatment for each PMN: P-93-204, 99 percent; P-94-1870, 98 percent; P-94-1871, 97 percent; P-94-1872, 92 percent; P-94-1873, 90 percent; P-94-1874, 73 percent.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3439, Jan. 22, 1998]

**§ 721.9830 1-Tridecyn-3-ol, 3-methyl.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-tridecyn-3-ol, 3-methyl (PMN P-96-236;

CAS No. 100912-15-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Worker protection.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3440, Jan. 22, 1998]

**§ 721.9840 Tungstate (W12(OH)2O386-) hexasodium (9CI).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as tungstate (W12(OH)2O386-) hexasodium (9CI) (PMN P-96-1177; CAS No. 12141-67-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3440, Jan. 22, 1998]

**Environmental Protection Agency**

**§ 721.9900**

**§ 721.9850 2,4,8,10-Tetraoxa-3,9-diphosphaspiro[5.5]undecane, 3,9-bis[2,4,6-tris(1,1-dimethylethyl)phenoxy]-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2,4,8,10-tetraoxa-3,9-diphosphaspiro[5.5]undecane, 3,9-bis[2,4,6-tris(1,1-dimethylethyl)phenoxy]- (PMN P-91-65; CAS number 126505-35-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(5)(ii), (a)(5)(iv), (a)(5)(v), (a)(6)(i), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(vi), (g)(1)(ix), (g)(2)(i) through (v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping requirements.* Requirements as specified in § 721.125 (a) through (h) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[57 FR 44075, Sept. 23, 1992, as amended at 58 FR 29946, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.9892 Alkylated urea.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an alkylated urea (PMN P-93-1649) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (b) (concentration set at 1.0 percent), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(ix), (g)(2)(i), (g)(2)(iii), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (l) and (q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) through (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.575(b)(1) apply to this section.

[60 FR 45085, Aug. 30, 1995]

**§ 721.9900 Urea, condensate with poly[oxy(methyl-1,2-ethanediyl)]- $\alpha$ -(2-aminomethylethyl)- $\mu$ -(2-aminoethylethoxy) (generic name).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance urea, condensate with poly[oxy(methyl-1,2-ethanediyl)]- $\alpha$ -(2-aminomethylethyl)- $\mu$ -(2-aminoethylethoxy) (PMN P-84-482) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance: Recordkeeping requirements specified in § 721.125 (a), (b), (c), and (i).

**§ 721.9920**

**40 CFR Ch. I (7-1-10 Edition)**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[55 FR 26102, June 26, 1990. Redesignated and amended at 58 FR 29947, May 24, 1993; 58 FR 34204, June 23, 1993]

**§ 721.9920 Urea, (hexahydro-6-methyl-2-oxopyrimidinyl)-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance urea, (hexahydro-6-methyl-2-oxopyrimidinyl)- (PMN P-89-303) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(p) (level set at 1,975,000 and 2,200,000 kg).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), (c), and (i).

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this significant new use rule.

[55 FR 26102, June 26, 1990. Redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

**§ 721.9925 Aminoethylethylene urea methacrylamide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an aminoethylethylene urea methacrylamide (PMN P-89-1038) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are: (i) *Industrial, commercial and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[58 FR 51709, Oct. 4, 1993]

**§ 721.9928 Urea, tetraethyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as urea, tetraethyl- (PMN P-94-1017; CAS No. 1187-03-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(r) (445,000 kg) (a dermal developmental toxicity study in mice and rats and either a chromosome aberration assay in mice (40 CFR 798.5385) or a micronucleus assay in mice (40 CFR 798.5395)). A person may not manufacture or import the substance beyond the following aggregate production volume limits, unless that person conducts the following corresponding studies on the substance and submits all final reports and underlying data in accordance with the procedures and criteria specified in paragraphs (a)(2)(i)(A), (a)(2)(i)(B), (a)(2)(i)(C), and (a)(2)(i)(D) of this section.

(A) Each study required to be performed pursuant to this section must be scientifically valid. *Scientific valid* means that the study was conducted according to:

(1) The test guidelines specified in paragraph (a)(2)(i) of this section.

(2) An EPA-approved protocol.

(3) TSCA Good Laboratory Practice Standards at 40 CFR part 792.

(4) Using methodologies generally accepted at the time the study is initiated.

## Environmental Protection Agency

## § 721.9929

(5) Any deviation from these requirements must be approved in writing by EPA.

(B) Before starting to conduct any of the studies in paragraph (a)(2)(i) of this section, the person must obtain approval of test protocols from EPA by submitting written protocols. EPA will respond to the person within 4 weeks of receiving the written protocols. Published test guidelines specified in paragraph (a)(2)(i) of this section (e.g., 40 CFR part 797 or part 798) provide general guidance for development of test protocols, but are not themselves acceptable protocols.

(C) The person shall:

(1) Conduct each study in good faith with due care.

(2) Promptly furnish to EPA the results of any interim phase of each study.

(3) Submit, in triplicate (with an additional sanitized copy, if confidential business information is involved), the final report of each study and all underlying data ("the report and data") to EPA no later than 14 weeks prior to exceeding the applicable production volume limit. The final report shall contain the contents specified in 40 CFR 792.185.

(D)(1) Except as described in paragraph (a)(2)(ii)(D)(2) of this section, if, within 6 weeks of EPA's receipt of a test report and data, the person receives written notice that EPA finds that the data generated by a study are scientifically invalid, the person is prohibited from further manufacture and import of the PMN substance beyond the applicable production volume limit.

(2) The person may continue to manufacture and import the PMN substance beyond the applicable production limit only if so notified, in writing, by EPA in response to the person's compliance with either of the following paragraph (a)(2)(ii)(D)(2)(i) or (a)(2)(ii)(D)(2)(ii) of this section.

(i) The person may reconduct the study. If there is sufficient time to reconduct the study and submit the report and data to EPA at least 14 weeks before exceeding the production limit as required by paragraph (a)(2)(ii)(C)(3) of this section, the person shall comply with paragraph (a)(2)(ii)(C)(3) of this

section. If there is insufficient time for the person to comply with paragraph (a)(2)(ii)(C)(3) of this section, the person may exceed the production limit and shall submit the report and data in triplicate to EPA within a reasonable period of time, all as specified by EPA in the notice described in paragraph (a)(2)(ii)(D)(1) of this section. EPA will respond to the person in writing, within 6 weeks of receiving the person's report and data.

(ii) The person may, within 4 weeks of receiving from EPA the notice described in paragraph (a)(2)(ii)(D)(1) of this section, submit to EPA a written report refuting EPA's finding. EPA will respond to the person in writing, within 4 weeks of receiving the person's report.

(E) The person is not required to conduct a study specified in paragraph (a)(2)(i) of this section if notified in writing by EPA that it is unnecessary to conduct that study.

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 3440, Jan. 22, 1998]

### § 721.9929 Polyurea (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyurea (PMN P-01-716) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90(a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## § 721.9930

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 70184, Dec. 17, 2003]

## § 721.9930 Urethane.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance urethane, CAS Number 51-79-6, is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new use is: Any use.

(b) *Special provisions.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture, import, or process for commercial purposes the substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[51 FR 9453, Mar. 19, 1986. Redesignated at 53 FR 2845, Feb. 2, 1988. Further redesignated at 58 FR 29947, May 24, 1993, as amended at 58 FR 34204, June 23, 1993]

## § 721.9952 Alkoxyated aliphatic diisocyanate allyl ether (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkoxyated aliphatic diisocyanate allyl ether (PMN P-00-0353) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## 40 CFR Ch. I (7-1-10 Edition)

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[68 FR 15089, Mar. 28, 2003]

## § 721.9957 N-Nitroso-N-methylurethane.

(a) *Chemical substance and significant new use subject to reporting.* (1) The chemical substance N-nitroso-N-methylurethane (CAS No. 615-53-2) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is: Manufacture, import, or processing of 10,000 pounds or more per year per facility for any use.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* The following recordkeeping requirements are applicable to manufacturers, importers, and processors of this substance, as specified in § 721.125 (a), (b), and (c).

(2) [Reserved]

[58 FR 63518, Dec. 1, 1993]

## § 721.9959 Polyurethane polymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a polyurethane polymer (PMN P-01-481) is subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125(a),

## Environmental Protection Agency

§ 721.9970

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this chemical substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[68 FR 70184, Dec. 17, 2003]

### § 721.9965 Fatty acids, C<sub>10-13</sub> - branched, vinyl esters.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as fatty acids, C<sub>10-13</sub> - branched, vinyl esters (PMN P-97-482; CAS No. 184785-38-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2), (a)(3), (a)(4), (a)(5)(ii) (if data on Cartridge Service Life Testing has been reviewed and approved in writing by EPA). The following respirators may be used as specified in § 721.63 (a)(5)(xii), (a)(5)(xiii), (a)(6)(i), (a)(6)(ii), (a)(6)(iv), (a)(6)(v), (b) (concentration set at 1.0 percent), and (c). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the NCEL provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 1 ppm.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(iii), (g)(1)(v), (g)(1)(vi), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(4) and (b)(4) (N=6).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), and (k) are applicable to manufacturers, im-

porters, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[65 FR 374, Jan. 5, 2000]

### § 721.9969 3,6-Bis(dialkylamino) -9-[2-alkoxycarbonyl] phenyl]-xanthylium salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 3,6-bis(dialkylamino) -9-[2-alkoxycarbonyl] phenyl]-xanthylium salt (PMN P-97-854) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44583, Aug. 20, 1998]

### § 721.9970 o-Xylene compound (generic name).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as an o-xylene compound (PMN P-95-1030) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to



§ 721.9973

40 CFR Ch. I (7-1-10 Edition)

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[61 FR 63740, Dec. 2, 1996]

§ 721.9973 Zirconium dichlorides (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as zirconium dichlorides (PMNs P-97-179/181/189/769/775/781/782/783) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 20).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[63 FR 44583, Aug. 20, 1998]

§ 721.10000 Certain polybrominated diphenylethers.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as tetrabromodiphenyl ether (CAS No. 40088-47-9; Benzene, 1,1'-oxybis-, tetrabromo deriv.), pentabromodiphenyl ether (CAS No. 32534-81-9; Benzene, 1,1'-oxybis-, pentabromo deriv.), hexabromodiphenyl ether (CAS No. 36483-60-0; Benzene, 1,1'-oxybis-, hexabromo deriv.), heptabromodiphenyl ether (CAS No. 68928-80-3; Benzene, 1,1'-oxybis-, heptabromo deriv.), octabromodiphenyl ether (CAS No. 32536-52-0; Benzene, 1,1'-

oxybis-, octabromo deriv.), and nonabromodiphenyl ether (CAS No. 63936-56-1; Benzene,

pentabromo(tetrabromophenoxy)-), or any combination of these substances resulting from a chemical reaction are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new use is manufacture or import for any use on or after January 1, 2005.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Persons who must report.* Section 721.5 applies to this section except for § 721.5(a)(2). A person who intends to manufacture or import for commercial purposes a substance identified in paragraph (a)(1) of this section and intends to distribute the substance in commerce must submit a significant new use notice.

(2) [Reserved]

[71 FR 34021, June 13, 2006]

§ 721.10001 2-Ethoxyethanol, 2-ethoxyethanol acetate, 2-methoxyethanol, and 2-methoxyethanol acetate.

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified as 2-ethoxyethanol (CAS No. 110-80-5), 2-ethoxyethanol acetate (CAS No. 111-15-9), 2-methoxyethanol (CAS No. 109-86-4), and 2-methoxyethanol acetate (CAS No. 110-49-6) are subject to reporting under this section for the significant new use described in paragraph (a)(2) of this section.

(2) The significant new use is domestic use in a consumer product or the manufacture or import of 2-methoxyethanol acetate at levels greater than 10,000 pounds per year.

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), and (c) apply to the significant new use specified in § 721.10001. In addition, records documenting compliance with the significant new use of domestic use

## Environmental Protection Agency

## § 721.10003

in a consumer product or the manufacture or import of 2-methoxyethanol acetate at levels greater than 10,000 pounds per year must be maintained.

(2) [Reserved]

[70 FR 71406, Nov. 29, 2005]

### § 721.10002 2-Thiazolidinone.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-thiazolidinone (PMN P-97-415; CAS No. 2682-49-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(3), (a)(4), (a)(6)(i), (b), and (c). The following National Institute for Occupational Safety and Health (NIOSH)-approved respirators with an assigned protection factor (APF) of 10–25 meet the minimum requirements for § 721.63(a)(4): Air-purifying, tight-fitting respirator (either half- or full-face) equipped with N100 (if aerosols absent), R100, or P100 filters; powered air-purifying respirator equipped with a loose-fitting hood or helmet and High Efficiency Particulate Air (HEPA) filters; powered air-purifying respirator equipped with a tight-fitting facepiece (either half- or full-face) and HEPA filters; and supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or helmet or tight-fitting facepiece (either half- or full-face). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 0.7 mg/m<sup>3</sup> as an 8-hour time-weighted average. Persons who wish to pursue NCELS as an alternative to the § 721.63 respirator requirements may request to do so under 40 CFR 721.30. Persons whose § 721.30 requests to use the NCELS approach are approved by EPA will receive NCELS provisions comparable to those contained in the corresponding section 5(e) consent order.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a),

(b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(1)(vi), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv) (use respiratory protection or maintain workplace airborne concentrations at or below an 8-hour time-weighted average of 0.7 mg/m<sup>3</sup>), (g)(2)(v), (g)(3)(ii), (g)(4)(i), (g)(4)(ii), (g)(4)(iii), and (g)(5). The following statement shall appear on each label as specified in § 721.72(b) and the Material Safety Data Sheet (MSDS) as specified in § 721.72(c). The substance may cause severe eye irritation. The substance may cause internal organ effects (blood, liver, and kidney). The substance may cause developmental/maternal effects. When handling this substance as a powder, use respiratory protection.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (g), (p) (300,000 kilograms), (v)(1), (w)(1), and (x)(1).

(iv) *Disposal.* Requirements as specified in § 721.85 (a)(1), (a)(2), (a)(3), (b)(1), (b)(2), (b)(3), (c)(1), (c)(2), and (c)(3).

(v) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), (j), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14697, Mar. 29, 2007]

### § 721.10003 Manganese heterocyclic tetraamine complex (generic).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as manganese heterocyclic tetraamine complex (PMNs P-98-625/626/627/628/629 and P-00-614/617) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## § 721.10004

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (10,000 kilograms per chemical substance).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14698, Mar. 29, 2007]

## § 721.10004 2-Butenoic acid, 4,4'-[(dibutylstannylene)bis(oxy)]bis[4-oxo-, (2Z,2'Z)-, di-C<sub>8-10</sub>-isoalkyl esters, C<sub>9</sub>-rich.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-butenic acid, 4,4'-[(dibutylstannylene)bis(oxy)]bis[4-oxo-, (2Z,2'Z)-, di-C<sub>8-10</sub>-isoalkyl esters, C<sub>9</sub>-rich (PMN P-98-1181; CAS No. 247041-56-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(2), (w)(2), (x)(2), and (y)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14698, Mar. 29, 2007]

## 40 CFR Ch. I (7-1-10 Edition)

## § 721.10005 2-Butenoic acid, 4,4'-[(dibutylstannylene)bis(oxy)]bis[4-oxo-, (2Z,2'Z)-, di-C<sub>9-11</sub>-isoalkyl esters, C<sub>10</sub>-rich.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-butenic acid, 4,4'-[(dibutylstannylene)bis(oxy)]bis[4-oxo-, (2Z,2'Z)-, di-C<sub>9-11</sub>-isoalkyl esters, C<sub>10</sub>-rich (PMN P-98-1182) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(2), (w)(2), (x)(2), and (y)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14698, Mar. 29, 2007]

## § 721.10006 Mixed metal oxide (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as mixed metal oxide (PMN P-99-511) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (60,000 kilograms).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## Environmental Protection Agency

## § 721.10009

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14698, Mar. 29, 2007]

### § 721.10007 Alcohols, C<sub>12-14</sub>-secondary, ethoxylated propoxylated.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as alcohols, C<sub>12-14</sub>-secondary, ethoxylated propoxylated (PMN P-00-11; CAS No. 103331-86-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 50).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14698, Mar. 29, 2007]

### § 721.10008 Manganese strontium oxide (MnSrO<sub>3</sub>).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as manganese strontium oxide (MnSrO<sub>3</sub>) (PMN P-00-1121; CAS No. 12163-45-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(vii), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as speci-

fied in § 721.80 (k) (manufacture, processing, or use of the PMN substance if the particle size is less than 10 microns) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14699, Mar. 29, 2007]

### § 721.10009 Manganese yttrium oxide (MnYO<sub>3</sub>).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as manganese yttrium oxide (MnYO<sub>3</sub>) (PMN P-00-1122; CAS No. 12032-75-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(vii), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) (manufacture, processing, or use of the PMN substance if the particle size is less than 10 microns) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## § 721.10010

(b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14699, Mar. 29, 2007]

## § 721.10010 Barium manganese oxide (BaMnO<sub>3</sub>).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as barium manganese oxide (BaMnO<sub>3</sub>) (PMN P-00-1123; CAS No. 12230-80-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(vii), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) (manufacture, processing, or use of the PMN substance if the particle size is less than 10 microns) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14699, Mar. 29, 2007]

## 40 CFR Ch. I (7-1-10 Edition)

## § 721.10011 Barium calcium manganese strontium oxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as barium calcium manganese strontium oxide (PMN P-00-1124; CAS No. 359427-90-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(vii), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) (manufacture, processing, or use of the PMN substance if the particle size is less than 10 microns) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14699, Mar. 29, 2007]

## § 721.10012 Manganate (MnO<sub>2</sub><sup>1-</sup>), calcium (2:1).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as manganate (MnO<sub>2</sub><sup>1-</sup>), calcium (2:1) (PMN P-00-1125; CAS No. 12049-47-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1

## Environmental Protection Agency

## § 721.10015

percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(vii), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) (manufacture, processing, or use of the PMN substance if the particle size is less than 10 microns) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14700, Mar. 29, 2007]

### § 721.10013 Manganese yttrium oxide (Mn<sub>2</sub>YO<sub>5</sub>).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as manganese yttrium oxide (Mn<sub>2</sub>YO<sub>5</sub>) (PMN P-00-1126; CAS No. 12438-71-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(vii), (g)(1)(viii), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), (g)(3)(ii), (g)(4)(i), and (g)(5).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (k) (manufacture, processing, or use of the PMN substance if the particle size is less than 10 microns) and (q).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14700, Mar. 29, 2007]

### § 721.10014 Halogenated naphthalic anhydride (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated naphthalic anhydride (PMN P-01-109) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14700, Mar. 29, 2007]

### § 721.10015 Halogenated benzimidazole (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated benzimidazole (PMN P-01-110) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

**§ 721.10016**

**40 CFR Ch. I (7–1–10 Edition)**

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14700, Mar. 29, 2007]

**§ 721.10016**

**Dibenzimidazothianaphthalene (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dibenzimidazothianaphthalene (PMN P-01-111) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14700, Mar. 29, 2007]

**§ 721.10017 Amine terminated bisphenol A diglycidyl ether polymer (generic).**

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as amine terminated bisphenol A diglycidyl ether polymer (PMNs P-01-257/258/259 and P-01-261) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14700, Mar. 29, 2007]

**§ 721.10018 Calcium hydroxide oxide silicate (Ca<sub>6</sub>(OH)<sub>2</sub>O<sub>2</sub>(Si<sub>2</sub>O<sub>5</sub>)<sub>3</sub>).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as calcium hydroxide oxide silicate (Ca<sub>6</sub>(OH)<sub>2</sub>O<sub>2</sub>(Si<sub>2</sub>O<sub>5</sub>)<sub>3</sub>) (PMN P-01-442; CAS No. 13169-90-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (j) (use other than as filler to reinforce resins, additive for resins, and filter medium), (v)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14701, Mar. 29, 2007]

**§ 721.10019 Benzoic acid, 2-chloro-5-nitro-, 1,1-dimethyl-2-oxo-2-(2-propenyloxy) ethyl ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzoic acid, 2-chloro-5-nitro-, 1,1-dimethyl-2-oxo-2-(2-propenyloxy) ethyl

## Environmental Protection Agency

## § 721.10021

ester (PMN P-01-563; CAS No. 174489-76-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14701, Mar. 29, 2007]

### § 721.10020 Benzoic acid, 5-amino-2-chloro-, 1,1-dimethyl-2-oxo-2-(2-propenyloxy) ethyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzoic acid, 5-amino-2-chloro-, 1,1-dimethyl-2-oxo-2-(2-propenyloxy) ethyl ester (PMN P-01-564; CAS No. 174489-43-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14701, Mar. 29, 2007]

### § 721.10021 Magnesium potassium titanium oxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as mag-

nesium potassium titanium oxide (PMN P-01-764; CAS No. 39290-90-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c). The following National Institute for Occupational Safety and Health (NIOSH)-approved respirators with an assigned protection factor (APF) of 10-25 meet the minimum requirements for § 721.63(a)(4): Air-purifying, tight-fitting respirator equipped with N100 (if aerosols absent), R100, or P100 filters (either half- or full-face); powered air-purifying respirator equipped with a loose-fitting hood or helmet and High Efficiency Particulate Air (HEPA) filters; powered air-purifying respirator equipped with a tight-fitting facepiece (either half- or full-face) and HEPA filters; and supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or helmet or tight-fitting facepiece (either half- or full-face). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 5 mg/m<sup>3</sup> as an 8-hour time-weighted average. Persons who wish to pursue NCELs as an alternative to the § 721.63 respirator requirements may request to do so under 40 CFR 721.30. Persons whose § 721.30 requests to use the NCELs approach are approved by EPA will receive NCELs provisions comparable to those contained in the corresponding section 5(e) consent order.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set 0.1 percent), (f), (g)(1)(ii), (g)(2)(ii), (g)(2)(iv) (use respiratory protection or maintain workplace airborne concentrations at or below an 8-hour time-weighted average of 5 mg/m<sup>3</sup>) and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to



## § 721.10022

## 40 CFR Ch. I (7–1–10 Edition)

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14701, Mar. 29, 2007]

### § 721.10022 Benzenamine, *N*-phenyl-, ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenamine, *N*-phenyl-, ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs (PMN P-01-769; CAS No. 333955-69-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (antioxidant for lubricating oils).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14701, Mar. 29, 2007]

### § 721.10023 Benzenamine, *N*-phenyl-, ar ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenamine, *N*-phenyl-, ar,ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs (PMN P-01-770; CAS No. 333955-70-7) is subject to reporting under this section for the sig-

nificant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (antioxidant for lubricating oils).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14702, Mar. 29, 2007]

### § 721.10024 10H-Phenothiazine, ar-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 10H-phenothiazine, ar-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs (PMN P-01-771; CAS No. 333955-79-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (antioxidant for lubricating oils).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14702, Mar. 29, 2007]

## Environmental Protection Agency

## § 721.10028

### § 721.10025 10H-Phenothiazine, ar, ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified as 10H-phenothiazine, ar, ar'-(C<sub>9</sub>-rich C<sub>8-10</sub>-branched alkyl) derivs (PMN P-01-772; CAS No. 333955-80-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (antioxidant for lubricating oils).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14702, Mar. 29, 2007]

### § 721.10026 Cashew, nutshell liq., ethoxylated.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as cashew, nutshell liq., ethoxylated (PMN P-01-856; CAS No. 350820-95-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (any manufacturing, processing, or use of the PMN substance with less than 55 moles of the ethoxy or with an average molecular weight less than 2,700 daltons).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manu-

facturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14702, Mar. 29, 2007]

### § 721.10027 Ethoxylated alkylsulfate, substituted alkylamine salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as ethoxylated alkylsulfate, substituted alkylamine salt (PMN P-01-862) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14702, Mar. 29, 2007]

### § 721.10028 Disubstituted benzene metal salts (generic).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as disubstituted benzene metal salts (PMNs P-01-901 and P-01-902) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1) and (a)(3).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14703, Mar. 29, 2007]

**§ 721.10029 Isocyanate compound, modified with methoxysilane (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as isocyanate compound, modified with methoxysilane (PMN P-01-918) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(2)(iii), (a)(2)(iv), (a)(3), (a)(4), and (a)(6). The following National Institute for Occupational Safety and Health (NIOSH)-approved respirators meet the minimum requirement for § 721.63(a)(4): Air-purifying, tight-fitting full-face respirator equipped with N100 (if oil aerosols absent), R100, or P100 filters; powered air-purifying respirator equipped with a tight-fitting full facepiece and High Efficiency Particulate Air (HEPA) filters; supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a tight-fitting full facepiece. As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 0.05 mg/m<sup>3</sup> as an 8-hour time-weighted average. Persons who wish to pursue NCELs as an alternative to the § 721.63 respirator requirements may request to do so under 40 CFR 721.30. Persons whose

§ 721.30 requests to use the NCELs approach are approved by EPA will receive NCELs provisions comparable to those contained in the corresponding section 5(e) consent order.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(2)(i), (g)(2)(ii), (g)(2)(iv) (use respiratory protection or maintain workplace airborne concentrations at or below an 8-hour time-weighted average of 0.05 mg/m<sup>3</sup>), (g)(2)(v), and (g)(5). The following statements shall appear on each label as specified in § 721.72(b) and the Material Safety Data Sheet (MSDS) as specified in § 721.72(c): This substance may cause skin irritation and sensitization.

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14703, Mar. 29, 2007]

**§ 721.10030 Pyrimido[5,4-g]pteridine-2,4,6,8-tetramine, 4-methylbenzenesulfonate, base-hydrolyzed.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as pyrimido[5,4-g]pteridine-2,4,6,8-tetramine, 4-methylbenzenesulfonate, base-hydrolyzed (PMN P-01-919; CAS No. 346709-25-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

## Environmental Protection Agency

## § 721.10032

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14703, Mar. 29, 2007]

### § 721.10031 Lithium potassium titanium oxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as lithium potassium titanium oxide (PMN P-02-214; CAS No. 39318-30-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(6)(i), (b) (concentration set at 0.1 percent), and (c). The following National Institute for Occupational Safety and Health (NIOSH)-approved respirators with an APF of 10-25 meet the minimum requirements for § 721.63(a)(4): Air-purifying, tight-fitting respirator (either half- or full-face) equipped with N100 (if aerosols absent), R100, or P100 filters; powered air-purifying, respirator equipped with a loose-fitting hood or helmet or tight-fitting facepiece (either half- or full-face) and High Efficiency Particulate Air (HEPA) filters; and supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or helmet or tight-fitting facepiece (either half- or full-face). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the TSCA section 5(e) consent order for this substance. The NCEL is 5 mg/m<sup>3</sup> as an 8-hour time-weighted average. Persons who wish to pursue NCELs as an alternative to the § 721.63 respirator requirements may request to do so under 40 CFR 721.30. Persons whose § 721.30 requests to use the NCELs ap-

proach are approved by EPA will receive NCELs provisions comparable to those contained in the corresponding section 5(e) consent order.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set 0.1 percent), (f), (g)(1)(ii), (g)(2)(ii), (g)(2)(iv) (use respiratory protection or maintain workplace airborne concentrations at or below an 8-hour time-weighted average of 5 mg/m<sup>3</sup>), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14703, Mar. 29, 2007]

### § 721.10032 Acrylic acid, polymer with substituted acrylamides (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as acrylic acid, polymer with substituted acrylamides (PMN P-02-269) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (any manufacturing, processing, or use of the PMN substance with an aerodynamic diameter less than 10 microns).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a),

## § 721.10033

(b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14704, Mar. 29, 2007]

## § 721.10033 Zinc, [ethanedioato(2)-, kappa. O<sup>1</sup>, . kappa. O<sup>2</sup>]-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as zinc, [ethanedioato(2)-, kappa. O<sup>1</sup>, . kappa. O<sup>2</sup>]- (PMN P-02-322; CAS No. 547-68-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14704, Mar. 29, 2007]

## § 721.10034 Substituted pyridine coupled with diazotized substituted nitrobenzotrile, diazotized substituted benzenamine and substituted pyridinecarbonitrile (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted pyridine coupled with diazotized substituted nitrobenzotrile, diazotized substituted benzenamine and substituted pyridinecarbonitrile (PMN P-02-359) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(ii) [Reserved]

## 40 CFR Ch. I (7-1-10 Edition)

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14704, Mar. 29, 2007]

## § 721.10035 Alkylbenzene sulfonate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylbenzene sulfonate (PMN-02-382) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (manufacture, import, or processing of the chemical without 19 percent or more mineral oil as a diluent).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14704, Mar. 29, 2007]

## § 721.10036 Acetaldehyde based polymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as acetaldehyde based polymer (PMN P-02-406) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## Environmental Protection Agency

## § 721.10039

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14704, Mar. 29, 2007]

### § 721.10037 Complex halogenated salt of tris(ethylatedaminocarbocyclic) methane (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as complex halogenated salt of tris(ethylatedaminocarbocyclic)methane (PMN P-02-423) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (d) and (e).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[705, Mar. 29, 2007]

### § 721.10038 Trimellitic anhydride, polymer with substituted glycol, alkyl phenols and ethoxylated nonylphenol (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

chemical substance identified generically as trimellitic anhydride, polymer with substituted glycol, alkyl phenols and ethoxylated nonylphenol (PMN P-02-434) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14697, Mar. 29, 2007]

### § 721.10039 Diethoxybenzenamine derivative, diazotized, coupled with aminonaphthalenesulfonic acid derivative, ammonium salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a diethoxybenzenamine derivative, diazotized, coupled with aminonaphthalenesulfonic acid derivative, ammonium salt (PMN P-02-514) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14705, Mar. 29, 2007]

§ 721.10040

40 CFR Ch. I (7–1–10 Edition)

§ 721.10040 **Substituted acridine naphtha substituted benzamide (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a substituted acridine naphtha substituted benzamide (PMN P–02–522) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(4), (b)(4), and (c)(4) (N=2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14705, Mar. 29, 2007]

§ 721.10041 **1-Butanone, 2-(dimethylamino)-2-[4-methylphenyl)methyl]-1-[4-(4-morpholinyl)phenyl]-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-butanone, 2-(dimethylamino)-2-[4-methylphenyl)methyl]-1-[4-(4-morpholinyl)phenyl]- (PMN P–02–530; CAS No. 119344–86–4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14705, Mar. 29, 2007]

§ 721.10042 **2-Propanol, 1-[bis(2-hydroxyethyl)amino]-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propanol, 1-[bis(2-hydroxyethyl)amino]- (PMN P–02–585; CAS No. 6712–98–7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14705, Mar. 29, 2007]

§ 721.10043 **Dineopentyl-4-substituted phthalate (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dineopentyl-4-substituted phthalate (PMN P–02–697) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## Environmental Protection Agency

## § 721.10047

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14705, Mar. 29, 2007]

### § 721.10044 Metal oxide, modified with alkyl and vinyl terminated polysiloxanes (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as metal oxide, modified with alkyl and vinyl terminated polysiloxanes (PMN P-02-698) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14706, Mar. 29, 2007]

### § 721.10045 Diazotized substituted heteromonocycle coupled with naphthalene sulfonic acid derivative, nickel complex, alkaline salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a diazotized substituted heteromonocycle coupled with naphthalene sulfonic acid derivative, nickel complex, alkaline salt (PMN P-02-737) is subject to reporting under this section for the significant new uses de-

scribed in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14706, Mar. 29, 2007]

### § 721.10046 Polyaromatic amine phosphate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polyaromatic amine phosphate (PMN P-02-747) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14706, Mar. 29, 2007]

### § 721.10047 Polyphosphoric acids, compds. with piperazine.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a polyphosphoric acids, compds. with piperazine (PMN P-02-766; CAS No. 383905-85-9) is subject to reporting under this section for the significant



**§ 721.10048**

**40 CFR Ch. I (7–1–10 Edition)**

new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14706, Mar. 29, 2007]

**§ 721.10048 Substituted anthraquinone (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted anthraquinone (PMN P-02-869) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (4,500 kilograms).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14706, Mar. 29, 2007]

**§ 721.10049 Phenol, 4,4'-cyclohexylidene bis[2-methyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as a phe-

nol, 4,4'-cyclohexylidene bis[2-methyl- (PMN P-02-912; CAS No. 2362-14-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14706, Mar. 29, 2007]

**§ 721.10050 Disubstituted-N'-hydroxybenzenecarboximidamide (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as disubstituted-N'-hydroxybenzenecarboximidamide (PMN P-02-929) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14707, Mar. 29, 2007]

**§ 721.10051 Spiro naphthoxazine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## Environmental Protection Agency

## § 721.10054

chemical substance identified generically as spiro naphthoxazine (PMN P-02-961) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14707, Mar. 29, 2007]

### § 721.10052 Aminoalkyl substituted alkyphenol (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as aminoalkyl substituted alkyphenol (PMN P-02-1088) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14707, Mar. 29, 2007]

### § 721.10053 Alkyl silane methacrylate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkyl silane methacrylate (PMN P-03-41) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14707, Mar. 29, 2007]

### § 721.10054 Phenol, polymer with formaldehyde, 3-[(2-aminocyclohexyl)amino]-2-hydroxypropyl ethers.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as a phenol, polymer with formaldehyde, 3-[(2-aminocyclohexyl)amino]-2-hydroxypropyl ethers (PMN P-03-43; CAS No. 452082-53-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

**§ 721.10055**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 14707, Mar. 29, 2007]

**§ 721.10055 1-Propanaminium, 3-amino-N-(carboxymethyl)-N,N-dimethyl-, N-soya acyl derivs., inner salts.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-propanaminium, 3-amino-N-(carboxymethyl)-N,N-dimethyl-, N-soya acyl derivs., inner salts (PMN P-03-46; CAS No. 136504-87-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14707, Mar. 29, 2007]

**§ 721.10056 Benzenemethanaminium, N-(3-aminopropyl)-N,N-dimethyl-, N-soya acyl derivs., chlorides.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenemethanaminium, N-(3-aminopropyl)-N,N-dimethyl-, N-soya acyl derivs., chlorides (PMN P-03-47; CAS No. 90194-13-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

**40 CFR Ch. I (7-1-10 Edition)**

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 14708, Mar. 29, 2007]

**§ 721.10057 Dodecanedioic acid, 1, 12-dihydrazide.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as dodecanedioic acid, 1, 12-dihydrazide (PMNs P-01-759 and P-05-555; CAS No. 4080-98-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), (a)(5), (a)(6)(i), (a)(6)(ii), (b), and (c). Respirators must provide a National Institute for Occupational Safety and Health (NIOSH) assigned protection factor (APF) of at least 50. The following NIOSH-approved respirators meet the minimum requirement for § 721.63(a)(4): Air-purifying, tight-fitting full-face respirator equipped with N100 (if oil aerosols absent), R100, or P100 filters; powered air-purifying respirator equipped with a tight-fitting full facepiece and High Efficiency Particulate Air (HEPA) filters; supplied air respirator operated in pressure demand or continuous flow mode and equipped with a tight-fitting full facepiece. Because the substance is a dermal sensitizer and irritates mucous membranes, half-face respirators do not provide adequate protection.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(i), and (g)(2)(i).

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## Environmental Protection Agency

## § 721.10060

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), and (h) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 32465, July 8, 2009]

### § 721.10058 Reaction product of alkylphenol, aromatic cyclicamine, alkyl diglycidyl dibenzene, and formaldehyde (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as reaction product of alkylphenol, aromatic cyclicamine, alkyl diglycidyl dibenzene, and formaldehyde (PMN P-03-546) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53482, Sept. 19, 2007]

### § 721.10059 Reaction product of alkylphenyl glycidyl ether, polyalkylenepolyamine, and alkyl diglycidyl dibenzene (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as reaction product of alkylphenyl glycidyl ether, polyalkylenepolyamine, and alkyl diglycidyl dibenzene (PMN P-03-550) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53482, Sept. 19, 2007]

### § 721.10060 Reaction product of alkylphenyl glycidyl ether, polyalkylenepolyamine, alkyl diglycidyl dibenzene, and polyalkylcyclicdiamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as reaction product of alkylphenyl glycidyl ether, polyalkylenepolyamine, alkyl diglycidyl dibenzene, and polyalkylcyclicdiamine (PMN P-03-551) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53482, Sept. 19, 2007]

**§ 721.10061**

**§ 721.10061 Pentane, 1,1,1,2,2,3,4,5,5,5-decafluoro-3-methoxy-4-(trifluoromethyl)-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as pentane, 1,1,1,2,2,3,4,5,5,5-decafluoro-3-methoxy-4-(trifluoromethyl)- (PMN P-04-341; CAS No. 132182-92-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53482, Sept. 19, 2007]

**§ 721.10062 2,5-Furandione, polymer with oxybis[propanol], benzoate.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2,5-furandione, polymer with oxybis[propanol], benzoate (PMN P-04-627; CAS No. 103458-14-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

**40 CFR Ch. I (7-1-10 Edition)**

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53482, Sept. 19, 2007]

**§ 721.10063 Halo substituted hydroxy nitrophenyl amide (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halo substituted hydroxy nitrophenyl amide (PMN P-04-792) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53482, Sept. 19, 2007]

**§ 721.10064 2-Propenoic acid, 2-[2-(ethenyloxy)ethoxy]ethyl ester.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propenoic acid, 2-[2-(ethenyloxy)ethoxy]ethyl ester (PMN P-04-909; CAS No. 86273-46-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3)(i), (b), and (c). North Butyl Black gloves and T-1 Dailove Ethylene Vinylalcohol Copolymer Laminated Blue gloves have been demonstrated to satisfy (a)(3)(i). Other demonstrated impervious gloves that satisfy (a)(3)(i) are also permissible.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (f), (g)(1)(i), (g)(1)(iv),

## Environmental Protection Agency

## § 721.10068

(g)(1)(vi), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(v), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 53482, Sept. 19, 2007]

### § 721.10065 1-Tetradecanesulfonic acid, (dimethylphenyl)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-tetradecanesulfonic acid, (dimethylphenyl)- (PMN P-04-961; CAS No. 671756-61-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53483, Sept. 19, 2007]

### § 721.10066 1-Hexanesulfonic acid, (dimethylphenyl)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-hexanesulfonic acid, (dimethylphenyl)-

(PMN P-04-962; CAS No. 676143-36-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53483, Sept. 19, 2007]

### § 721.10067 Ether amine phosphonate salt (generic).

(a) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substances identified generically as ether amine phosphonate salt (PMNs P-05-57, P-05-58, P-05-59, P-05-61, P-05-62, P-05-63, P-05-64, and P-05-65) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53483, Sept. 19, 2007]

### § 721.10068 Elemental mercury.

(a) *Definitions.* The definitions in § 721.3 apply to this section. In addition, the following definition applies:

**§ 721.10069**

**40 CFR Ch. I (7-1-10 Edition)**

*Motor vehicle* has the meaning found at 40 CFR 85.1703.

(b) *Chemical substances and significant new uses subject to reporting.* (1) The chemical substance elemental mercury (CAS. No. 7439-97-6) is subject to reporting under this section for the significant new uses described in paragraph (b)(2) of this section.

(2) The significant new uses are:

(i) Manufacture or processing of elemental mercury for use in convenience light switches in new motor vehicles.

(ii) Manufacture or processing of elemental mercury for use in convenience light switches as new aftermarket replacement parts for motor vehicles.

(iii) Manufacture or processing of elemental mercury for use in switches in anti-lock brake systems (ABS) in new motor vehicles.

(iv) Manufacture or processing of elemental mercury for use in switches in ABS as new aftermarket replacement parts for motor vehicles that were manufactured after January 1, 2003.

(v) Manufacture or processing of elemental mercury for use in switches in active ride control systems in new motor vehicles.

(vi) Manufacture or processing of elemental mercury for use in switches in active ride control systems as new aftermarket replacement parts for motor vehicles that were manufactured after January 1, 2003.

(c) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Suspension or revocation of certain notification exemptions.* The provisions of § 721.45(f) do not apply to this section. A person who imports or processes elemental mercury as part of an article is not exempt from submitting a significant new use notice.

(2) [Reserved]

[72 FR 56911, Oct. 5, 2007]

**§ 721.10069 Ether amine phosphonate (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as ether amine phosphonate (PMN P-05-60) is subject to reporting under this section for the significant

new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53483, Sept. 19, 2007]

**§ 721.10070 1,3-Butanediol, 3-methyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,3-butanediol, 3-methyl- (PMN P-05-309; CAS No. 2568-33-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (j)(use as inkjet ink).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53483, Sept. 19, 2007]

**§ 721.10071 9H-Thioxanthenum, 10-[1,1'-biphenyl]-4-yl-2-(1-methylethyl)-9-oxo-, hexafluorophosphate (1-) (1:1).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 9H-thioxanthenum, 10-[1,1'-biphenyl]-4-yl-2-(1-methylethyl)-9-oxo-,

## Environmental Protection Agency

## § 721.10074

hexafluorophosphate (1-) (1:1) (PMN P-05-364; CAS No. 591773-92-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (v)(2), (w)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53483, Sept. 19, 2007]

### § 721.10072 Benzene, 1,1'-methylenebis[4-isocyanato-, polymer with benzenedicarboxylic acid, butyl dialkyl ester, poly[oxy(methyl-1,2-ethanediyl)], .alpha.-hydro.-omega.-hydroxy-, oxirane, alkyl-, polymer with oxirane, ether with propanepolyol and Sartomer's HLBH P-3000 and Lexorez 1180 (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as benzene, 1,1'-methylenebis[4-isocyanato-, polymer with benzenedicarboxylic acid, butyl dialkyl ester, poly[oxy(methyl-1,2-ethanediyl)], .alpha.-hydro.-omega.-hydroxy-, oxirane, alkyl-, polymer with oxirane, ether with propanepolyol and Sartomer's HLBH P-3000 and Lexorez 1180 (PMN P-05-380) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53484, Sept. 19, 2007]

### § 721.10073 Modified alkyl acrylamide (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified alkyl acrylamide (PMN P-05-536) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 53484, Sept. 19, 2007]

### § 721.10074 Acetic acid, 2-chloro-, 1-(3,3-dimethylcyclohexyl)ethyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as acetic acid, 2-chloro-, 1-(3,3-dimethylcyclohexyl)ethyl ester (PMN P-05-568; CAS No. 477218-59-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(h).

(ii) [Reserved]



## § 721.10075

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53484, Sept. 19, 2007]

### § 721.10075 Carbon black, 4-[[2-(Sulfooxy) ethyl]substituted] phenyl-modified, sodium salts (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as carbon black, 4-[[2-(Sulfooxy) ethyl]substituted] phenyl-modified, sodium salts (PMN P-05-722) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 53484, Sept. 19, 2007]

### § 721.10076 Substituted benzenediamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted benzenediamine

## 40 CFR Ch. I (7-1-10 Edition)

(PMN P-05-792) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53484, Sept. 19, 2007]

### § 721.10077 3H-1,2,4-Triazol-3-one, 1,2-dihydro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 3H-1,2,4-triazol-3-one, 1,2-dihydro- (PMNs P-06-1 and P-06-166; CAS No. 930-33-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5), (a)(6), (b), and (c). Respirators must provide a National Institute for Occupational Safety and Health (NIOSH) assigned protection factor of at least 10. The following NIOSH-approved respirators with an assigned protection factor (APF) of 10-25 meet the minimum requirements for § 721.63(a)(4): Air-purifying, tight-fitting respirator equipped with N100 (if aerosols absent), R100, or P100 filters (either half- or full-face); powered air-purifying respirator equipped with a loose-fitting hood or helmet and High Efficiency Particulate Air (HEPA) filters; powered air-purifying respirator equipped with a tight-fitting facepiece (either half- or full-face) and HEPA filters; and supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or

## Environmental Protection Agency

§ 721.10080

helmet or tight-fitting facepiece (either half- or full-face).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (g)(1)(ix), (g)(2)(iv), (g)(3)(ii), and (g)(4)(iii).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53485, Sept. 19, 2007]

### § 721.10078 Butanamide, 2-[(2-methoxy-4-nitrophenyl)azo]-N-(2-methoxyphenyl)-3-oxo-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl)substituted]phenyl derivs., hydrochlorides (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as butanamide, 2-[(2-methoxy-4-nitrophenyl)azo]-N-(2-methoxyphenyl)-3-oxo-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl)substituted]phenyl derivs., hydrochlorides (PMN P-06-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53485, Sept. 19, 2007]

### § 721.10079 Quino[2,3-b]acridine-7, 14-dione, 5,12-dihydro-2,9-dimethyl-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl)substituted]phenyl derivs., hydrochlorides (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as quino[2,3-b]acridine-7, 14-dione, 5,12-dihydro-2,9-dimethyl-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl)substituted]phenyl derivs., hydrochlorides (PMN P-06-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 53485, Sept. 19, 2007]

### § 721.10080 Carbon black, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl) substituted] phenyl-modified, hydrochlorides (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## § 721.10081

chemical substance identified generically as carbon black, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl) substituted] phenyl-modified, hydrochlorides (PMN P-06-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 53485, Sept. 19, 2007]

## § 721.10081 Aromatic urethane acrylate oligomer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as aromatic urethane acrylate oligomer (PMN P-06-26) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manu-

## 40 CFR Ch. I (7-1-10 Edition)

facturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53485, Sept. 19, 2007]

## § 721.10082 Amine modified monomer acrylate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as amine modified monomer acrylate (PMN P-06-29) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53486, Sept. 19, 2007]

## § 721.10083 Copper, [29H, 31H-phthalocyaninato (2-)-N29, N30, N31, N32]-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl) substituted] phenyl derivs., hydrochlorides (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as copper, [29H, 31H-phthalocyaninato (2-)-N29, N30, N31, N32]-, 4-[(17-substituted-3,6,9,12,15-pentaazaheptadec-1-yl) substituted] phenyl derivs., hydrochlorides (PMN P-06-70) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

## Environmental Protection Agency

## § 721.10086

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[72 FR 53486, Sept. 19, 2007]

### § 721.10084 Modified thionocarbamate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified thionocarbamate (PMN P-06-124) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53486, Sept. 19, 2007]

### § 721.10085 Substituted polyaryl sulfonium polyhalide phosphate salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generi-

cally as substituted polyaryl sulfonium polyhalide phosphate salt (PMN P-06-232) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (j) (photo initiator used in photo-curable compositions).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53486, Sept. 19, 2007]

### § 721.10086 Ethane, 2-(difluoromethoxy)-1,1,1-trifluoro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as ethane, 2-(difluoromethoxy)-1,1,1-trifluoro- (PMN P-06-295; CAS No. 1885-48-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e) and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53486, Sept. 19, 2007]

§ 721.10087

40 CFR Ch. I (7–1–10 Edition)

§ 721.10087 **Substituted alkyl phosphine oxide (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted alkyl phosphine oxide (PMN P-06-332) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (100,000 kilograms/year).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[72 FR 53487, Sept. 19, 2007]

§ 721.10088 **Thiophene, 2,5-dibromo-3-hexyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as thiophene, 2,5-dibromo-3-hexyl- (PMN P-07-283; CAS No. 116971-11-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (4,500 kilograms).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 32465, July 8, 2009]

§ 721.10089 **Modified salicylic acid, zirconium complex (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified salicylic acid, zirconium complex (PMN P-00-552) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65758, Nov. 5, 2008]

§ 721.10090 **Tertiary amine salt of glycol succinate (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as tertiary amine salt of glycol succinate (PMN P-01-595) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(A) Restricting the manufacture of the PMN substance with only those feedstocks specified in the PMN submission.

(B) Manufacture, import, or processing of the PMN substance without analyzing representative samples of the chemical substance to determine compliance with the requirements in

## Environmental Protection Agency

## § 721.10092

§ 721.10090(a)(2)(i)(A). To ensure compliance, the PMN substance must be analyzed (1) at the time of initial commencement of non-exempt commercial manufacture of the chemical substance, and (2) at least annually thereafter during every year in which the substance is manufactured.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65758, Nov. 5, 2008]

### § 721.10091 2(1H)-Pyrimidinone, tetrahydro-1,3-dimethyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2(1H)-pyrimidinone, tetrahydro-1,3-dimethyl- (PMN P-02-135; CAS No. 7226-23-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3)(i), (b), and (c). Best's Viton model #890, Best's Butyl model #874, and Best's Butyl #878 have been demonstrated to satisfy § 721.63(a)(3)(i). Other demonstrated impervious gloves that satisfy § 721.63(a)(3)(i) are permissible.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f), (j) (aprotic solvent and catalyst), and (s) (20,000 kg).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65758, Nov. 5, 2008]

### § 721.10092 Poly(oxy-1,2-ethanediyl), .alpha.-sulfo-omega-[[1-[(2-propen-1-yloxy)methyl]undecyl]oxy]-, ammonium salt (1:1); Poly(oxy-1,2-ethanediyl), .alpha.-sulfo-omega-[[1-[(2-propen-1-yloxy)methyl]tridecyl]oxy]-, ammonium salt (1:1).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as poly(oxy-1,2-ethanediyl), .alpha.-sulfo-omega-[[1-[(2-propen-1-yloxy)methyl]undecyl]oxy]-, ammonium salt (1:1); poly(oxy-1,2-ethanediyl), .alpha.-sulfo-omega-[[1-[(2-propen-1-yloxy)methyl]tridecyl]oxy]-, ammonium salt (1:1) (PMN P-02-421; CAS Nos. 352661-91-7 and 224646-44-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (no manufacture or import of the PMN substance unless: (1) The mean number of moles of the ethoxy group is equal to or greater than 8 or (2) the average molecular weight is greater than 721 daltons). Representative samples of the PMN substance must be analyzed and determined to comply with these requirements both at the time of initial commencement and annually thereafter.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65758, Nov. 5, 2008]

**§ 721.10093**

**§ 721.10093 Alkylamides, ethoxylated (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkylamides, ethoxylated (PMNs P-03-12 and P-03-13) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65759, Nov. 5, 2008]

**§ 721.10094 Decene, branched and linear.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as decene, branched and linear (PMN P-03-272; CAS No. 833482-31-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Record keeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65759, Nov. 5, 2008]

**40 CFR Ch. I (7-1-10 Edition)**

**§ 721.10095 Oxetane, 3,3'-[oxybis(methylene)] bis[3-ethyl-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as oxetane, 3,3'-[oxybis(methylene)] bis[3-ethyl- (PMN P-03-471; CAS No. 18934-00-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), and (a)(3) (polyvinyl alcohol gloves with a thickness of no less than 31.3 mils or silvershield/4H sleeves with a thickness of no less than 2.7 mils have satisfied § 721.63(a)(3)(i) for up to 8 hours.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e), (f), (g)(1)(iv), (g)(1)(vi), and (g)(2)(v).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65759, Nov. 5, 2008, as amended at 74 FR 57425, Nov. 6, 2009]

**§ 721.10096 Benzene, 1,4-bis (methoxymethyl)-.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzene, 1,4-bis (methoxymethyl)- (PMN P-03-614; CAS No. 6770-38-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65759, Nov. 5, 2008]

**§ 721.10097 Disubstituted benzenesulfonic acid, alkali metal salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as disubstituted benzenesulfonic acid, alkali metal salt (PMN P-03-642) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65759, Nov. 5, 2008]

**§ 721.10098 Disubstituted benzoic acid, alkali metal salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as disubstituted benzoic acid, alkali metal salt (PMN P-03-643) is sub-

ject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65760, Nov. 5, 2008]

**§ 721.10099 Dialkyl dimethyl ammonium carbonate (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkyl dimethyl ammonium carbonate (1:1) (PMN P-03-715) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 5).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65760, Nov. 5, 2008]

**§ 721.10100 Dialkyl dimethyl ammonium carbonate (2:1) (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The



## § 721.10101

chemical substance identified generically as dialkyl dimethyl ammonium carbonate (2:1) (PMN P-03-716) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 5).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65760, Nov. 5, 2008]

## § 721.10101 Copolymer of alkyl acrylate and ethyleneglycol dimethacrylate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as copolymer of alkyl acrylate and ethyleneglycol dimethacrylate (PMN P-03-755) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5), (a)(6)(i), (a)(6)(ii), (b), and (c). The following National Institute for Occupational Safety and Health (NIOSH)-approved respirators with an assigned protection factor (APF) of 10-25 meet the minimum requirements for § 721.63(a)(4): Air-purifying, tight-fitting respirator equipped with N100 (if oil aerosols absent), R100, or P100 filters (either half- or full-face); powered air-purifying respirator equipped with a loose-fitting hood or helmet and High Efficiency Particulate Air (HEPA) filters; powered air-purifying respirator equipped with a tight-fitting facepiece (either half- or full-face) and HEPA filters; and supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or

## 40 CFR Ch. I (7-1-10 Edition)

helmet, or tight-fitting facepiece (either half- or full-face).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65760, Nov. 5, 2008]

## § 721.10102 Diphosphoric acid, compd. with piperazine (1:1).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as diphosphoric acid, compd. with piperazine (1:1) (PMN P-04-126; CAS No. 66034-17-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (flame retardant).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65760, Nov. 5, 2008]

## § 721.10103 Naphtha (Fischer-Tropsch), C4-11-alkane, branched and linear.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as naphtha (fischer-tropsch), C4-11-alkane, branched and linear (PMN P-04-235;

## Environmental Protection Agency

## § 721.10106

CAS No. 849101-58-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Disposal*. Requirements as specified in § 721.85 (a)(1), (b)(1) and (c)(1).

(ii) *Release to water*. Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (j), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[73 FR 65760, Nov. 5, 2008]

### § 721.10104 Halophosphate metal complex (generic). mixed

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generically as halophosphate mixed metal complex (PMN P-04-254) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water*. Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[73 FR 65761, Nov. 5, 2008]

### § 721.10105 Polyfluoroalkylether (generic).

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified generi-

cally as polyfluoroalkylether (PMN P-04-417) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[73 FR 65761, Nov. 5, 2008]

### § 721.10106 Silica, [(ethenylsilylidyne)tris(oxy)] - modified.

(a) *Chemical substance and significant new uses subject to reporting*. (1) The chemical substance identified as silica, [(ethenylsilylidyne)tris(oxy)] - modified (PMN P-04-419; CAS No. 649574-37-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities*. Requirements as specified in § 721.80 (v)(1), (w)(1), and (x)(1).

(ii) [Reserved]

(b) *Specific requirements*. The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping*. Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements*. The provisions of § 721.185 apply to this section.

[73 FR 65761, Nov. 5, 2008]

**§ 721.10107 Naphthalenedisulfonic acid, [amino-hydroxy-[(substituted)azo-sulfo-naphthaleneyl]azo]-hydroxy-[(methoxy-sulfo-phenyl)azo], metal salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as naphthalenedisulfonic acid, [amino-hydroxy-[(substituted)azo-sulfo-naphthaleneyl]azo]-hydroxy-[(methoxy-sulfo-phenyl)azo], metal salt (PMN P-04-495) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65761, Nov. 5, 2008]

**§ 721.10108 Naphthalenedisulfonic acid, hydroxy-[[[(hydroxyl-disulfonaphthaleneyl)azo]-alkyl(C=1-5)-(sulfoalkoxy)cyclic]azo]-substituted azo-, metal salt (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as naphthalenedisulfonic acid, hydroxy-[[[(hydroxyl-disulfonaphthaleneyl)azo]-alkyl(C=1-5)-(sulfoalkoxy)cyclic]azo]-substituted azo-, metal salt (PMN P-04-498) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65761, Nov. 5, 2008]

**§ 721.10109 Hexanoic acid, 2-ethyl-, mixed triesters with benzoic acid and trimethylolpropane.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hexanoic acid, 2-ethyl-, mixed triesters with benzoic acid and trimethylolpropane (PMN P-04-508; CAS No. 610787-76-3 ) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Record keeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65761, Nov. 5, 2008]

**§ 721.10110 Hexanoic acid, 2-ethyl-, mixed diesters with benzoic acid and neopentyl glycol.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hexanoic acid, 2-ethyl-, mixed diesters with benzoic acid and neopentyl glycol

## Environmental Protection Agency

## § 721.10113

(PMN P-04-509; CAS No. 610787-77-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65762, Nov. 5, 2008]

### § 721.10111 Hexanoic acid, 2-ethyl-, mixed diesters with benzoic acid and diethylene glycol.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as hexanoic acid, 2-ethyl-, mixed diesters with benzoic acid and diethylene glycol (PMN P-04-510; CAS No. 610787-78-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65762, Nov. 5, 2008]

### § 721.10112 Ethanone, 2-chloro-1-(1-chlorocyclopropyl)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as ethanone, 2-chloro-1-(1-chlorocyclopropyl)- (PMN P-04-530; CAS No. 120983-72-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65762, Nov. 5, 2008]

### § 721.10113 Thioether epoxy (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as thioether epoxy (PMN P-04-547) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

## § 721.10114

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65762, Nov. 5, 2008]

### § 721.10114 Polyhydroxyaminoether salts (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as polyhydroxyaminoether salts (PMNs P-04-578, P-04-579, P-04-580, P-04-581, P-04-582, and P-04-583) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of those substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65762, Nov. 5, 2008]

### § 721.10115 1-Hexadecanaminium, N,N-dibutyl-N-(2-hydroxyethyl)-, bromide (1:1).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-hexadecanaminium, N,N-dibutyl-N-(2-hydroxyethyl)-, bromide (1:1) (PMN P-04-625; CAS No. 160653-08-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## 40 CFR Ch. I (7-1-10 Edition)

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65762, Nov. 5, 2008]

### § 721.10116 Blocked polymeric isocyanate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as blocked polymeric isocyanate (PMN P-04-758) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65763, Nov. 5, 2008]

### § 721.10117 Heteromonocyclo-beta-(2,4-dichlorophenyl) -1-propanol (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as heteromonocyclo-beta-(2,4-dichlorophenyl) -1-propanol (PMN P-04-776) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65763, Nov. 5, 2008]

**§ 721.10118 Substituted aryl acetonitrile (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted aryl acetonitrile (PMN P-05-35) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65763, Nov. 5, 2008]

**§ 721.10119 Siloxane modified silica nanoparticles (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as siloxane modified silica nanoparticles (PMN P-05-673) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), (a)(5), (a)(6)(ii), (b) (concentration set at 1 percent), and

(c). The following National Institute for Occupational Safety and Health (NIOSH)-approved respirators with an APF of 10-25 meet the minimum requirements for § 721.63(a)(4): Air-purifying, tight-fitting respirator equipped with N100 (if oil aerosols absent), R100, or P100 filters (either half- or full-face); powered air-purifying respirator equipped with a loose-fitting hood or helmet and High Efficiency Particulate Air (HEPA) filters; powered air-purifying respirator equipped with a tight-fitting facepiece (either half- or full-face) and HEPA filters; supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or helmet, or tight-fitting facepiece (either half- or full-face).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65763, Nov. 5, 2008]

**§ 721.10120 Siloxane modified alumina nanoparticles (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as siloxane modified alumina nanoparticles (PMN P-05-687) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), (a)(5), (a)(6)(ii), (b) (concentration set at 1 percent), and (c). The following National Institute for Occupational Safety and Health (NIOSH)-approved respirators with an

## § 721.10121

APF of 10-25 meet the minimum requirements for § 721.63(a)(4): Air-purifying, tight-fitting respirator equipped with N100 (if oil aerosols absent), R100, or P100 filters (either half- or full-face); powered air-purifying respirator equipped with a loose-fitting hood or helmet and High Efficiency Particulate Air (HEPA) filters; powered air-purifying respirator equipped with a tight-fitting facepiece (either half- or full-face) and HEPA filters; supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or helmet, or tight-fitting facepiece (either half- or full-face).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65763, Nov. 5, 2008]

## § 721.10121 Poly[oxy(methyl-1,2-ethanediyl)], .alpha.-methyl-omega-(4-nonylphenoxy)-, branched.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as poly[oxy(methyl-1,2-ethanediyl)], .alpha.-methyl-omega-(4-nonylphenoxy)-, branched (PMN P-05-766; CAS No. 858944-25-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## 40 CFR Ch. I (7-1-10 Edition)

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65764, Nov. 5, 2008]

## § 721.10122 2-Propenoic acid, 2-methyl-, 1,1'-[2-ethyl-2-[[2-methyl-1-oxo-2-propen-1-yl)oxy]methyl]- 1,3-propanediyl] ester, polymer with 1,3-butadiene, ethenylbenzene and 2-hydroxyethyl 2-methyl-2-propenoate.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propenoic acid, 2-methyl-, 1,1'-[2-ethyl-2-[[2-methyl-1-oxo-2-propen-1-yl)oxy]methyl]- 1,3-propanediyl] ester, polymer with 1,3-butadiene, ethenylbenzene and 2-hydroxyethyl 2-methyl-2-propenoate (PMN P-06-151; CAS No. 849925-18-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (additive in rubber, i.e. as reinforcing agent; additive in plastics, i.e. as polymeric plasticizer; and additive in polyurethane, i.e. to improve low temperature flexibility).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65764, Nov. 5, 2008]

## § 721.10123 [1,2,4-Triazolo[1,5-a]pyrimidin-2-amine, 5,7-dimethoxy-1-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as [1,2,4-

## Environmental Protection Agency

## § 721.10126

triazolo[1,5-a]pyrimidin-2-amine, 5,7-dimethoxy-] (PMN P-06-554; CAS No. 13223-43-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 5).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65764, Nov. 5, 2008]

### § 721.10124 Brominated polyaromatic compound (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as brominated polyaromatic compound (PMN P-06-617) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* ImperVIOUS gloves: Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65764, Nov. 5, 2008]

### § 721.10125 Alkenedioic acid, dialkyl ester, reaction products with polyaminocarbomonocycle and alkenoic acid alkyl ester (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as alkenedioic acid, dialkyl ester, reaction products with polyaminocarbomonocycle and alkenoic acid alkyl ester (PMNs P-06-665, P-06-666, P-06-667, P-06-668, P-06-669, and P-06-670) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65764, Nov. 5, 2008]

### § 721.10126 Alkyl amino substituted triazine amino substituted benzenesulfonic acid reaction product with naphthalenesulfonato azo substituted phenyl azo substituted benzenesulfonic acid copper compound (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkyl amino substituted triazine amino substituted benzenesulfonic acid reaction product with naphthalenesulfonato azo substituted phenyl azo substituted benzenesulfonic acid copper compound (PMN P-06-689) is subject to reporting under this section for the significant



## § 721.10127

new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65764, Nov. 5, 2008]

## § 721.10127 Alkenyl dimethyl betaine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkenyl dimethyl betaine (PMN P-06-693) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65765, Nov. 5, 2008]

## § 721.10128 Modified imidazole (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generi-

## 40 CFR Ch. I (7-1-10 Edition)

cally as modified imidazole (PMN P-06-752) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65765, Nov. 5, 2008]

## § 721.10129 Alkylamine ethoxylated (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylamine ethoxylated (PMN P-07-24) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (emulsifier for oilfield application).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65765, Nov. 5, 2008]

## Environmental Protection Agency

## § 721.10133

### § 721.10130 Quino[2,3-b]acridine-7,14-dione, 5,12-dihydro-ar-[4-[[2-(sulfooxy)ethyl]substituted]phenyl]-, monosodium salt (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as quino[2,3-b]acridine-7,14-dione, 5,12-dihydro-ar-[4-[[2-(sulfooxy)ethyl]substituted]phenyl]-, monosodium salt (PMN P-07-140) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65765, Nov. 5, 2008]

### § 721.10131 Isononanamide, N-(2-ethylhexyl)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as isononanamide, N-(2-ethylhexyl)- (PMN P-07-205; CAS No. 93820-33-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j) (defoamer for cement additives in oilfield applications).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manu-

facturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[73 FR 65765, Nov. 5, 2008]

### § 721.10132 Phosphoramidic acid, carbomonocyclic-, diphenylester (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as phosphoramidic acid, carbomonocyclic-, diphenylester (PMN P-07-269) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j) and (s) (100,000 kilograms).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65765, Nov. 5, 2008]

### § 721.10133 2-Propenoic acid, 2-methyl, 2-hydroxyethyl ester, homopolymer.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-propenoic acid, 2-methyl, 2-hydroxyethyl ester, homopolymer (PMN P-07-401; CAS No. 25249-16-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(4), (a)(5), (a)(6), (b), and (c). Respirators must provide a National Institute for Occupational Safety and Health

## § 721.10134

(NIOSH) assigned protection factor (APF) of at least 1,000. A NIOSH-certified supplied-air respirator operated in pressure demand or other positive pressure mode and equipped with a tight-fitting full facepiece meets the minimum requirements for § 721.63(a)(4).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 0.1 percent), (f), (g)(1)(vii), and (g)(2)(iv).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[73 FR 65766, Nov. 5, 2008]

## § 721.10134 Formaldehyde, polymer with dialkylphenylamine, and dialkylphenol and trimethylhexanediamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as formaldehyde, polymer with dialkylphenylamine, dialkylphenol and trimethylhexanediamine (PMN P-05-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manu-

## 40 CFR Ch. I (7-1-10 Edition)

facturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29994, June 24, 2009]

## § 721.10135 Phosphinic acid, P,P-diethyl-, zinc salt (2:1).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as phosphinic acid, P,P-diethyl-, zinc salt (2:1) (PMN P-05-11; CAS No. 284685-45-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=12).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29994, June 24, 2009]

## § 721.10136 2-Propenoic acid, 2-methyl-, 2-hydroxyethyl ester, reaction products with hexakis(alkoxyalkyl)melamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as 2-propenoic acid, 2-methyl-, 2-hydroxyethyl ester, reaction products with hexakis(alkoxyalkyl)melamine (PMN P-05-177) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

## Environmental Protection Agency

## § 721.10140

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29994, June 24, 2009]

### § 721.10137 Halogenated phenoxy aromatic (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halogenated phenoxy aromatic (PMN P-05-329) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29995, June 24, 2009]

### § 721.10138 3-Isoxazolecarboxylic acid, 4,5-dihydro-5,5-diphenyl-, ethyl ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 3-isoxazolecarboxylic acid, 4,5-dihydro-5,5-diphenyl-, ethyl ester (PMN P-05-336; CAS No. 163520-33-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29995, June 24, 2009]

### § 721.10139 Ethanone, 1-(1-chlorocyclopropyl)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as ethanone, 1-(1-chlorocyclopropyl)- (PMN P-05-776; CAS No. 63141-09-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(g).

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=500).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29995, June 24, 2009]

### § 721.10140 Phosphoric acid, tin (2+) salt (2:3).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as phosphoric acid, tin (2+) salt (2:3) (PMN P-06-33, CAS No. 15578-32-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

## § 721.10141

## 40 CFR Ch. I (7–1–10 Edition)

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29995, June 24, 2009]

### § 721.10141 Oils, ginger, zingiber purpureum.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as oils, ginger, zingiber purpureum (PMN P-06-163; CAS No. 864662-46-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29995, June 24, 2009]

### § 721.10142 Oxabicycloalkane carboxylic acid alkanediyl ester (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as oxabicycloalkane carboxylic acid alkanediyl ester (PMN P-06-199) is subject to reporting under this section

for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29995, June 24, 2009]

### § 721.10143 Amines, bis (C11-14-branched and linear alkyl).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as amines, bis (C11-14-branched and linear alkyl) (PMN P-06-733; CAS No. 900169-60-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29995, June 24, 2009]

### § 721.10144 Modified thiocarbamate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified thiocarbamate (PMN P-06-805) is subject to reporting under

## Environmental Protection Agency

## § 721.10147

this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 29996, June 24, 2009]

### § 721.10145 Modified reaction products of alkyl alcohol, halogenated alkane, substituted epoxide, and amino compound (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified reaction products of alkyl alcohol, halogenated alkane, substituted epoxide, and amino compound (PMN P-06-816) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (analysis and reporting and limitations of maximum impurity levels of certain fluorinated impurities) and (q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29996, June 24, 2009]

### § 721.10146 Partially fluorinated condensation polymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as partially fluorinated condensation polymer (PMN P-07-87) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (analysis and reporting and limitations of maximum impurity levels of certain fluorinated impurities), (l) (maximum percentage of the PMN substance in a non-industrial product or distributed for use as a non-industrial product), (o) (use in a consumer product that could be spray applied), and (q).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29996, June 24, 2009]

### § 721.10147 Acrylate derivative of alkoxysilylalkane ester and mixed metal oxides (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as acrylate derivative of alkoxysilylalkane ester and mixed metal oxides (PMN P-07-198) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

**§ 721.10148**

**40 CFR Ch. I (7–1–10 Edition)**

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29996, June 24, 2009]

**§ 721.10148 Acryloxy alkanolic alkane derivative with mixed metal oxides (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as acryloxy alkanolic alkane derivative with mixed metal oxides (PMN P-07-330) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29996, June 24, 2009]

**§ 721.10149 Carbon black, (3-methylphenyl)-modified, substituted (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as carbon black, (3-methylphenyl)-modified, substituted (PMN P-07-522) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29997, June 24, 2009]

**§ 721.10150 Carbon black, (4-methylphenyl)-modified, substituted (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as carbon black, (4-methylphenyl)-modified, substituted (PMN P-07-523) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1),

## Environmental Protection Agency

## § 721.10153

(a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29997, June 24, 2009]

### § 721.10151 Modified styrene, divinylbenzene polymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified styrene, divinylbenzene polymer (PMN P-07-642) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29997, June 24, 2009]

### § 721.10152 Oxirane, substituted silylmethyl-, hydrolysis products with alkanol zirconium(4+) salt and silica, acetates (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as oxirane, substituted silylmethyl-, hydrolysis products with alkanol zirconium(4+) salt and silica, acetates (PMN P-07-674) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (a), (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29997, June 24, 2009]

### § 721.10153 Modified methyl methacrylate, 2-hydroxyethyl methacrylate polymer (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as modified methyl methacrylate, 2-hydroxyethyl methacrylate polymer (PMN P-08-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:



## § 721.10154

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29997, June 24, 2009]

## § 721.10154 Quaternary ammonium compounds, dicoc alkyldimethyl chlorides, reaction products with silica.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as quaternary ammonium compounds, dicoc alkyldimethyl chlorides, reaction products with silica (PMN P-08-157; CAS No. 956147-76-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (j), (v)(1), (w)(1), and (x)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of these substances.

## 40 CFR Ch. I (7-1-10 Edition)

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 29998, June 24, 2009]

## § 721.10157 Benzeneethanol,halo-,halocycloalkyl-,hydrazinealkyl- (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as benzeneethanol,halo-,halocycloalkyl-,hydrazinealkyl (PMN P-05-775) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(3), (b) (concentration set at 1.0%), and (c).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0%), (f), (g)(1)(i) (eye irritation), (g)(1)(iii), (g)(1)(iv), (g)(1)(viii) (sensitization), (g)(1)(ix), (g)(2)(i), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4) (resulting in receiving stream levels exceeding 0.1 parts per billion (ppb)), and (g)(5).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=0.1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47886, Sept. 18, 2009]

## § 721.10158 2-Pentanone, 3,5-dichloro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 2-pentanone, 3,5-dichloro- (PMN P-06-16;

## Environmental Protection Agency

§ 721.10161

CAS No. 58371-98-5) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(ii), (a)(3), (a)(4), (a)(5), (a)(6), (b) (concentration set at 1.0%), and (c). Respirators must provide a National Institute for Occupational Safety and Health (NIOSH) assigned protection factor (APF) of at least 50. The following NIOSH-approved respirator with an APF of 50 meets the minimum requirements for § 721.63(a)(4): NIOSH-approved air-purifying, tight-fitting full facepiece respirator equipped with combination organic gas/vapor P100 cartridges (organic vapor, acid gas, or substance-specific).

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0%), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iii), (g)(1)(iv), (g)(1)(viii), (g)(1)(ix), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4) (resulting in receiving stream levels exceeding 0.1 parts per billion (ppb)), and (g)(5).

(iii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=0.1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47886, Sept. 18, 2009]

### § 721.10159 1-Docosanamine, N,N-dimethyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-docosanamine, N,N-dimethyl- (PMN P-07-587; CAS No. 21542-96-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47887, Sept. 18, 2009]

### § 721.10160 Poly(oxy-1,2-ethanediyl), .alpha.-[(13Z)-1-oxo-13-docosen-1-yl]-.omega.-[[[(13Z)-1-oxo-13-docosen-1-yl]oxy]-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as poly(oxy-1,2-ethanediyl), .alpha.-[(13Z)-1-oxo-13-docosen-1-yl]-.omega.-[[[(13Z)-1-oxo-13-docosen-1-yl]oxy]- (PMN P-07-629; CAS No. 56565-72-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 47887, Sept. 18, 2009]

### § 721.10161 Substituted silyl methacrylate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The

## § 721.10162

chemical substance identified generically as substituted silyl methacrylate (PMN P-08-3) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47887, Sept. 18, 2009]

## § 721.10162 1,3 Dioxolane-4-butanol, 2-ethenyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,3 dioxolane-4-butanol, 2-ethenyl- (PMN P-08-24; CAS No. 2421-08-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[74 FR 47887, Sept. 18, 2009]

## 40 CFR Ch. I (7-1-10 Edition)

## § 721.10163 Chloro fluoro alkane (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as chloro fluoro alkane (PMN P-08-33) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (f) and (s) (50,000 kilograms).

(ii) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47887, Sept. 18, 2009]

## § 721.10164 Benzenecarboximidamide, N-hydroxy-4-nitro-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as benzenecarboximidamide, N-hydroxy-4-nitro- (PMN P-08-36; CAS No. 1613-86-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

## Environmental Protection Agency

§ 721.10168

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47888, Sept. 18, 2009]

### § 721.10165 Carbonotrithioic acid, bis(phenylmethyl) ester.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as carbonotrithioic acid, bis(phenylmethyl) ester (PMN P-08-138; CAS No. 26504-29-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47888, Sept. 18, 2009]

### § 721.10166 1,3-Cyclohexanedione, 2-[2-chloro-4-(methylsulfonyl)-3-[(2,2,2-trifluoroethoxy)methyl]benzoyl]-, ion(1-), potassium salt (1:1).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,3-cyclohexanedione, 2-[2-chloro-4-(methylsulfonyl)-3-[(2,2,2-trifluoroethoxy)methyl]benzoyl]-, ion(1-), potassium salt (1:1) (PMN P-08-180; CAS No. 1121649-70-4) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N= 0.1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47888, Sept. 18, 2009]

### § 721.10167 Tetrafluoro nitrotoluene (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as tetrafluoro nitrotoluene (PMN P-08-212) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[74 FR 47888, Sept. 18, 2009]

### § 721.10168 Cesium tungsten oxide.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as cesium tungsten oxide (PMN P-08-275; CAS No. 52350-17-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80 (v)(2), (w)(2), and (x)(2).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to

**§721. 10169**

**40 CFR Ch. I (7–1–10 Edition)**

this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[74 FR 47888, Sept. 18, 2009]

**§721. 10169 Cyclopentane, methoxy-**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as cyclopentane, methoxy- (PMN P-03-141; CAS No. 5614-37-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in 721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of §721.1725(b)(1) apply to this section.

[75 FR 4993, Feb. 1, 2010]

**§721.10170 Polyoxyethylene polyalkylarylphenylether ammonium salt (generic) sulfate**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as polyoxyethylene polyalkylarylphenylether sulfate ammonium salt (PMN P-03-197) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(j).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of §721.1725(b)(1) apply to this section.

[75 FR 4993, Feb. 1, 2010]

**§721.10171 1H-benz(e)indolium, 1,1,2,3-tetramethyl-, 4-methylbenzenesulfonic acid (1:1).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1H-benz(e)indolium, 1,1,2,3-tetramethyl-, 4-methylbenzenesulfonic acid (1:1) (PMN P-03-285; CAS No. 141914-99-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in §721.63 (a)(4), (a)(5), (b) (concentration set at 1 percent), and (c). Respirators must provide a National Institute for Occupational Safety and Health (NIOSH) assigned protection factor (APF) of at least 10. The following NIOSH-approved respirators with an APF of 10-25 meet the minimum requirements for §721.63(a)(4): Air-purifying, tight-fitting respirator equipped with N100 (if oil aerosols absent), R100, or P100 filters (either half- or full-face); powered air-purifying respirator equipped with a loose-fitting hood or helmet and High Efficiency Particulate Air (HEPA) filters; powered air-purifying respirator equipped with a tight-fitting facepiece (either half- or full-face) and HEPA filters; supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a hood or helmet, or tight-fitting facepiece (either half- or full-face).

## Environmental Protection Agency

§ 721.10174

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (11,000 kilograms).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4994, Feb. 1, 2010]

### § 721.10172 Alkylamide derivative (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as alkylamide derivative (PMN P-03-633) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N = 1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4994, Feb. 1, 2010]

### § 721.10173 Silanamine,1,1,1-triethoxy-N,N-diethyl-

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as silanamine,1,1,1-triethoxy-N,N-diethyl- (PMN P-03-793; CAS No. 35077-00-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4994, Feb. 1, 2010]

### § 721.10174 1-Propanaminium, 3-amino-N-(carboxymethyl)-N,N-dimethyl-, N-peanut-oil acyl derivs., inner salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-Propanaminium, 3-amino-N-(carboxymethyl)-N,N-dimethyl-, N-peanut-oil acyl derivs., inner salts (PMN P-04-139; CAS No. 691401-28-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (b) (concentration set at 1 percent), and (c).

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[75 FR 4994, Feb. 1, 2010]

§ 721.10175

40 CFR Ch. I (7–1–10 Edition)

**§ 721.10175 1-Propanaminium, N-(3-aminopropyl)-2-hydroxy-N,N-dimethyl-3-sulfo-, N-(C12-18 and C18-unsatd. acyl) derivs., inner salts.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-Propanaminium, N-(3-aminopropyl)-2-hydroxy-N,N-dimethyl-3-sulfo-, N-(C12-18 and C18-unsatd. acyl) derivs., inner salts (PMN P-04-141; CAS No. 691400-36-9) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=6).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4994, Feb. 1, 2010]

**§ 721.10176 Amides, peanut-oil, N-[3-(dimethylamino)propyl].**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as amides, peanut-oil, N-[3-(dimethylamino)propyl] (PMN P-04-144; CAS No. 691400-76-7) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4995, Feb. 1, 2010]

**§ 721.10177 Phosphoric acid, yttrium(3+) salt (1:1).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as phosphoric acid, yttrium(3+) salt (1:1) (PMN P-04-153; CAS No. 13990-54-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(ii) *Release to water.* Requirements as specified in § 721.90 (b)(4) and (c)(4) (N=6).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4995, Feb. 1, 2010]

**§ 721.10178 Distillates (Fischer-Tropsch), hydroisomerized middle, C10-13-branched alkane fraction.**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as distillates (Fischer-Tropsch), hydroisomerized middle, C10-13-branched alkane fraction (PMN P-04-319; CAS No. 642928-30-1) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(3), (a)(4), (a)(5), (b) (concentration set at 0.1 percent), and (c). Respirators must provide a National Institute for Occupational Safety and Health (NIOSH) assigned protection factor (APF) of at least 100. The following NIOSH-approved respirator

## Environmental Protection Agency

## § 721.10181

meets the minimum requirements for § 721.63(a)(4): Supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a tight-fitting full facepiece.

(ii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(f).

(iii) *Release to water.* Requirements as specified in § 721.90 (b)(1) and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4995, Feb. 1, 2010]

### § 721.10179 Copolymers of phenol and aromatic hydrocarbon (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substances identified generically as copolymers of phenol and aromatic hydrocarbon (PMNs P-04-346 and P-04-347) are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k) (no manufacture or import of the PMN substances unless the average molecular weight is greater than 500 daltons). Representative samples of the PMN substances must be analyzed and determined to comply with these requirements both at the time of initial commencement and annually thereafter.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of these substances.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4995, Feb. 1, 2010]

### § 721.10180 Trifunctional acrylic ester (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as trifunctional acrylic ester (PMN P-04-692) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirement as specified in § 721.80(k) (no manufacture or import of the PMN substance unless the mean number of moles of the ethoxy group is greater than or equal to 8). Representative samples of the PMN substance must be analyzed and determined to comply with these requirements both at the time of initial commencement and annually thereafter.

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 4995, Feb. 1, 2010]

### § 721.10181 Halide salt of an alkylamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as halide salt of an alkylamine (PMN P-07-453) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(j).

(ii) [Reserved]



**§721.10184**

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of §721.1725(b)(1) apply to this section.

[75 FR 4995, Feb. 1, 2010]

**§721.10184 Aliphatic triamine (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as aliphatic triamine (PMN P-02-996) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(y)(1).

(ii) *Release to water.* Requirements as specified in §721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[75 FR 35986, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35986, June 24, 2010, §721.10184 was added, effective August 23, 2010.

**40 CFR Ch. I (7-1-10 Edition)**

**§721.10185 1,2-Propanediol, 3-(diethylamino)-, polymers with 5-isocyanato-1-(isocyanatomethyl)-1,3,3-trimethylcyclohexane, propylene glycol and reduced Me esters of reduced polymd. oxidized tetrafluoroethylene, 2-ethyl-1-hexanol-blocked, acetates (salts).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1,2-propanediol, 3-(diethylamino)-, polymers with 5-isocyanato-1-(isocyanatomethyl)-1,3,3-trimethylcyclohexane, propylene glycol and reduced Me esters of reduced polymd. oxidized tetrafluoroethylene, 2-ethyl-1-hexanol-blocked, acetates (salts) (PMN P-03-106; CAS No. 328389-90-8) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in §721.80(y)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in §721.125 (a), (b), (c), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of §721.185 apply to this section.

[75 FR 35986, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35986, June 24, 2010, §721.10185 was added, effective August 23, 2010.

**§721.10186 Ethylhexyl oxetane (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as ethylhexyl oxetane (PMN P-04-132) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this rule do not apply to quantities of the PMN substance after it has been completely reacted (cured).

(2) The significant new uses are:

## Environmental Protection Agency

## § 721.10188

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2)(i), (a)(2)(iii), (a)(3)(i), (b) (concentration set at 1.0 percent), and (c). Polyvinyl Alcohol gloves with a thickness of no less than 31.3 mils or Silvershield/4H sleeves with a thickness of no less than 2.7 mils have been shown to satisfy the requirements of § 721.63(a)(3)(i) for up to 8 hours.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(iii), (g)(1)(iv), (g)(2)(i), (g)(2)(v), (g)(3)(ii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(k).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), and (i) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[75 FR 35986, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35986, June 24, 2010, § 721.10186 was added, effective August 23, 2010.

### § 721.10187 4-Morpholinepropanamine, N-(1,3-dimethylbutylidene)-.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 4-morpholinepropanamine, N-(1,3-dimethylbutylidene)- (PMN P-05-186, Chemical A; CAS No. 1003863-30-6) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10). However, when this chemical substance is released in combination with any of the substances in § 721.10188, § 721.10189, or § 721.10190, then the value of N shall instead be adjusted according to the following formula:

$$[(N1 \times \text{Release1}) + (N2 \times \text{Release2}) + (N3 \times \text{Release3}) + (N4 \times \text{Release4})] / (\text{Release1} + \text{Release2} + \text{Release3} + \text{Release4}) = \text{Adjusted N}$$

Where the “N” variables are the N values for each of the four substances as specified in this section and § 721.10188, § 721.10189, § 721.10190 and the “Release” variables are the number of kilograms released of the respective four substances (in units of kg/site/day) per § 721.91(a).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35986, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35986, June 24, 2010, § 721.10187 was added, effective August 23, 2010.

### § 721.10188 Fatty acids, tall-oil, reaction products with 4-methyl-2-pentanone and aliphatic polyamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as fatty acids, tall-oil, reaction products with 4-methyl-2-pentanone and aliphatic polyamine (PMN P-05-186, Chemical B) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10). However, when this chemical substance is released in combination with any of the substances in § 721.10187, § 721.10189, or § 721.10190, then the value of N shall instead be adjusted according to the following formula:

$$[(N1 \times \text{Release1}) + (N2 \times \text{Release2}) + (N3 \times \text{Release3}) + (N4 \times \text{Release4})] / (\text{Release1} + \text{Release2} + \text{Release3} + \text{Release4}) = \text{Adjusted N}$$

Where the “N” variables are the N values for each of the four substances

**§ 721.10189**

**40 CFR Ch. I (7–1–10 Edition)**

as specified in this section and § 721.10187, § 721.10189, § 721.10190 and the “Release” variables are the number of kilograms released of the respective four substances (in units of kg/site/day) per § 721.91(a).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35987, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35987, June 24, 2010, § 721.10188 was added, effective August 23, 2010.

**§ 721.10189 Fatty acids, tall-oil, reaction products with (butoxymethyl) oxirane formaldehyde-phenol polymer glycidyl ether, morpholinepropanamine, propylene glycol diamine and aliphatic polyamine, N-(1,3-dimethylbutylidene) derivs (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as fatty acids, tall-oil, reaction products with (butoxymethyl) oxirane formaldehyde-phenol polymer glycidyl ether, morpholinepropanamine, propylene glycol diamine and aliphatic polyamine, N-(1,3-dimethylbutylidene) derivs (PMN P-05-186, Chemical C) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10). However, when this chemical substance is released in combination with any of the substances in § 721.10187, § 721.10188, or § 721.10190, then the value of N shall instead be adjusted according to the following formula:

$$[(N1 \times \text{Release1}) + (N2 \times \text{Release2}) + (N3 \times \text{Release3}) + (N4 \times \text{Release4})] / (\text{Release1} + \text{Release2} + \text{Release3} + \text{Release4}) = \text{Adjusted N}$$

Where the “N” variables are the N values for each of the four substances as specified in this section and § 721.10187, § 721.10188, § 721.10190 and the “Release” variables are the number of kilograms released of the respective four substances (in units of kg/site/day) per § 721.91(a).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35987, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35987, June 24, 2010, § 721.10189 was added, effective August 23, 2010.

**§ 721.10190 Formaldehyde, polymer with aliphatic diamine and phenol, reaction products with 4-methyl-2-pentanone (generic).**

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as formaldehyde, polymer with aliphatic diamine and phenol, reaction products with 4-methyl-2-pentanone (PMN P-05-186; Chemical D) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=10). However, when this chemical substance is released in combination with any of the substances in § 721.10187, § 721.10188, or § 721.10189, then the value of N shall instead be adjusted according to the following formula:

$$[(N1 \times \text{Release1}) + (N2 \times \text{Release2}) + (N3 \times \text{Release3}) + (N4 \times \text{Release4})] / (\text{Release1} + \text{Release2} + \text{Release3} + \text{Release4}) = \text{Adjusted N}$$

Where the “N” variables are the N values for each of the four substances as specified in this section and § 721.10187, § 721.10188, § 721.10189 and the “Release” variables are the number of kilograms released of the respective

## Environmental Protection Agency

## § 721.10193

four substances (in units of kg/site/day) per § 721.91(a).

(i) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35987, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35987, June 24, 2010, § 721.10190 was added, effective August 23, 2010.

### § 721.10191 Amides, coco, N-[3-(dibutylamino)propyl].

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as amides, coco, N-[3-(dibutylamino)propyl] (PMN P-06-262; CAS No. 851544-20-2) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35988, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35988, June 24, 2010, § 721.10191 was added, effective August 23, 2010.

### § 721.10192 Amides, coco, N-[3-(dibutylamino)propyl], acrylates.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as amides, coco, N-[3-(dibutylamino)propyl],

acrylates (PMN P-06-263, Chemical A; CAS No. 851545-09-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35988, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35988, June 24, 2010, § 721.10192 was added, effective August 23, 2010.

### § 721.10193 1-Butanaminium, N-(3-aminopropyl)-N-butyl-N-(2-carboxyethyl)-, N-coco acyl derivs., inner salts.

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified as 1-butanaminium, N-(3-aminopropyl)-N-butyl-N-(2-carboxyethyl)-, N-coco acyl derivs., inner salts (PMN P-06-263, Chemical B; CAS No. 851545-17-0) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35988, June 24, 2010]

## § 721.10194

EFFECTIVE DATE NOTE: At 75 FR 35988, June 24, 2010, § 721.10193 was added, effective August 23, 2010.

### § 721.10194 Dialkylcocoamidoalkylpropionate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkylcocoamidoalkylpropionate (PMN P-06-264) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35988, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35988, June 24, 2010, § 721.10194 was added, effective August 23, 2010.

### § 721.10195 Dialkylcornoilamidoalkylamine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkylcornoilamidoalkylamine (PMN P-06-265) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

## 40 CFR Ch. I (7-1-10 Edition)

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35988, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35988, June 24, 2010, § 721.10195 was added, effective August 23, 2010.

### § 721.10196 Dialkylcornoilamidoacrylate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkylcornoilamidoacrylate (PMN P-06-266, Chemical A) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35988, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35988, June 24, 2010, § 721.10196 was added, effective August 23, 2010.

### § 721.10197 Dialkylcornoilamidoalkylbetaine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkylcornoilamidoalkylbetaine (PMN P-06-266, Chemical B) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

## Environmental Protection Agency

## § 721.10199

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35988, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35988, June 24, 2010, § 721.10197 was added, effective August 23, 2010.

### § 721.10198 Dialkylcornoilamidopropionate (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as dialkylcornoilamidopropionate (PMN P-06-267) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(ii) [Reserved]

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35989, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35989, June 24, 2010, § 721.10198 was added, effective August 23, 2010.

### § 721.10199 Substituted aliphatic amine (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as substituted aliphatic amine (PMN P-06-702) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section. The requirements of this rule do not apply to quantities of the PMN substance after it has been completely reacted (cured).

(2) The significant new uses are:

(i) *Protection in the workplace.* Requirements as specified in § 721.63 (a)(1), (a)(2), (a)(3)(i), (a)(4), (a)(5), (a)(6), (b) (concentration set at 1.0 percent), and (c). Ansell NEOX style 9-912 gloves have been shown to satisfy the requirements of § 721.63(a)(3)(i) for up to 110 minutes. Respirators must provide a National Institute for Occupational Safety and Health (NIOSH) assigned protection factor (APF) of at least 50. The following NIOSH-approved respirators meet the requirements for § 721.63(a)(4): Air purifying, tight-fitting full-face respirator equipped with the appropriate combination cartridges, cartridges should be tested and approved for the gas/vapor substance (i.e., organic vapor, acid gas, or substance-specific cartridge) and should include a particulate filter (N100 if oil aerosols are absent, R100, or P100); powered air-purifying respirator equipped with a tight-fitting facepiece (full-face) and the appropriate combination cartridges, cartridges should be tested and approved for the gas/vapor substance (i.e., organic vapor, acid gas, or substance-specific cartridges) and should include High Efficiency Particulate Air (HEPA) filters; supplied-air respirator operated in pressure demand or continuous flow mode and equipped with a tight-fitting face piece (full-face). As an alternative to the respiratory requirements listed here, a manufacturer, importer, or processor may choose to follow the new chemical exposure limit (NCEL) provisions listed in the Toxic Substances Control Act (TSCA) section 5(e) consent order for this substance. The NCEL is 0.14 mg/m<sup>3</sup> as an 8-hour time-weighted average. Persons who wish to pursue NCELs as an alternative to the § 721.63 respirator

## § 721.10200

requirements may request to do so under § 721.30. Persons whose § 721.30 requests to use the NCELS approach are approved by EPA will receive NCELS provisions comparable to those contained in the corresponding section 5(e) consent order.

(ii) *Hazard communication program.* Requirements as specified in § 721.72 (a), (b), (c), (d), (e) (concentration set at 1.0 percent), (f), (g)(1)(i), (g)(1)(ii), (g)(1)(iv), (g)(2)(i), (g)(2)(ii), (g)(2)(iii), (g)(2)(iv), (g)(2)(v), (g)(3)(i), (g)(3)(ii), (g)(4)(iii), and (g)(5).

(iii) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(r).

(iv) *Release to water.* Requirements as specified in § 721.90 (a)(1), (b)(1), and (c)(1).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (d), (e), (f), (g), (h), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

(3) *Determining whether a specific use is subject to this section.* The provisions of § 721.1725(b)(1) apply to this section.

[75 FR 35989, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35989, June 24, 2010, § 721.10199 was added, effective August 23, 2010.

## § 721.10200 Benzenacetonitrile, cyclohexylidene-alkyl substituted (generic).

(a) *Chemical substance and significant new uses subject to reporting.* (1) The chemical substance identified generically as benzenacetonitrile, cyclohexylidene-alkyl substituted (PMN P-09-75) is subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new uses are:

(i) *Industrial, commercial, and consumer activities.* Requirements as specified in § 721.80(s) (10,000 kg).

## 40 CFR Ch. I (7–1–10 Edition)

(ii) *Release to water.* Requirements as specified in § 721.90 (a)(4), (b)(4), and (c)(4) (N=123).

(b) *Specific requirements.* The provisions of subpart A of this part apply to this section except as modified by this paragraph.

(1) *Recordkeeping.* Recordkeeping requirements as specified in § 721.125 (a), (b), (c), (i), and (k) are applicable to manufacturers, importers, and processors of this substance.

(2) *Limitations or revocation of certain notification requirements.* The provisions of § 721.185 apply to this section.

[75 FR 35989, June 24, 2010]

EFFECTIVE DATE NOTE: At 75 FR 35989, June 24, 2010, § 721.10200 was added, effective August 23, 2010.

## PART 723—PREMANUFACTURE NOTIFICATION EXEMPTIONS

### Subpart A [Reserved]

### Subpart B—Specific Exemptions

Sec.

723.50 Chemical substances manufactured in quantities of 10,000 kilograms or less per year, and chemical substances with low environmental releases and human exposures.

723.175 Chemical substances used in or for the manufacture or processing of instant photographic and peel-apart film articles.

723.250 Polymers.

AUTHORITY: 15 U.S.C. 2604.

### Subpart A [Reserved]

### Subpart B—Specific Exemptions

§ 723.50 **Chemical substances manufactured in quantities of 10,000 kilograms or less per year, and chemical substances with low environmental releases and human exposures.**

(a) *Purpose and scope.* (1) This section grants an exemption from the premanufacture notice requirements of section 5(a)(1)(A) of the Toxic Substances Control Act (15 U.S.C. 2604(a)(1)(A)) for the manufacture of:

(i) Chemical substances manufactured in quantities of 10,000 kilograms or less per year.

## Environmental Protection Agency

## § 723.50

(ii) Chemical substances with low environmental releases and human exposures.

(2) To manufacture a new chemical substance under the terms of this exemption a manufacturer must:

(i) Submit a notice of intent to manufacture 30 days before manufacture begins, as required under paragraph (e) of this section.

(ii) Comply with all other provisions of this section.

(3) This section does not apply to microorganisms subject to part 725 of this chapter.

(b) *Definitions.* The following definitions apply to this subpart.

(1) *Act* means the Toxic Substances Control Act (15 U.S.C. 2601 et seq).

(2) *Consumer* means a private individual who uses a chemical substance or any product containing the chemical substance in or around a permanent or temporary household or residence, during recreation, or for any personal use or enjoyment.

(3) *Environment* has the same meaning as in section 3 of the Act (15 U.S.C. 2602).

(4) *Environmental transformation product* means any chemical substance resulting from the action of environmental processes on a parent compound that changes the molecular identity of the parent compound.

(5) *Metabolite* means a chemical entity produced by one or more enzymatic or nonenzymatic reactions as a result of exposure of an organism to a chemical substance.

(6) *Serious acute effects* means human disease processes or other adverse effects that have short latency periods for development, result from short-term exposure, or are a combination of these factors and that are likely to result in death, severe or prolonged incapacitation, disfigurement, or severe or prolonged loss of the ability to use a normal bodily or intellectual function with a consequent impairment of normal activities.

(7) *Serious chronic effects* means human disease processes or other adverse effects that have long latency periods for development, result from long-term exposure, are long-term illnesses, or are a combination of these factors and that are likely to result in

death, severe or prolonged incapacitation, disfigurement, or severe or prolonged loss of the ability to use a normal bodily or intellectual function with a consequent impairment of normal activities.

(8) *Significant environmental effects* means:

(i) Any irreversible damage to biological, commercial, or agricultural resources of importance to society;

(ii) Any reversible damage to biological, commercial, or agricultural resources of importance to society if the damage persists beyond a single generation of the damaged resource or beyond a single year; or

(iii) Any known or reasonably anticipated loss of members of an endangered or threatened species. Endangered or threatened species are those species identified as such by the Secretary of the Interior in accordance with the Endangered Species Act, as amended (16 U.S.C. 1531).

(9) *Site* means a contiguous property unit. Property divided only by a public right-of-way is one site. There may be more than one manufacturing plant on a single site.

(10) The terms *byproduct, EPA, importer, impurity, known to or reasonably ascertainable, manufacture, manufacturer, new chemical substance, person, possession or control, and test data* have the same meanings as in §720.3 of this chapter.

(c) *Exemption categories.* Except as provided in paragraph (d) of this section, this exemption applies to:

(1) Any manufacturer of a new chemical substance manufactured in quantities of 10,000 kilograms or less per year under the terms of this exemption.

(2) Any manufacturer of a new chemical substance satisfying all of the following low environmental release and low human exposure eligibility criteria:

(i) *Consumers and the general population.* For exposure of consumers and the general population to the new chemical substance during all manufacturing, processing, distribution in commerce, use, and disposal of the substance:

(A) No dermal exposure.



(B) No inhalation exposure (except as described in paragraph (c)(2)(iv) of this section).

(C) Exposure in drinking water no greater than a 1 milligram per year (estimated average dosage resulting from drinking water exposure in streams from the maximum allowable concentration level from ambient surface water releases established under paragraph (c)(2)(iii) of this section or a higher concentration authorized by EPA under paragraph (c)(2)(iii) of this section).

(ii) *Workers.* For exposure of workers to the new chemical substance during all manufacturing, processing, distribution in commerce, use and disposal of the substance:

(A) No dermal exposure (this criterion is met if adequate dermal exposure controls are used in accordance with applicable EPA guidance).

(B) No inhalation exposure (this criterion is considered to be met if adequate inhalation exposure controls are used in accordance with applicable EPA guidance).

(iii) *Ambient surface water.* For ambient surface water releases, no releases resulting in surface water concentrations above 1 part per billion, calculated using the methods prescribed in §§ 721.90 and 721.91, unless EPA has approved a higher surface water concentration supported by relevant and scientifically valid data submitted to EPA in a notice under paragraph (e) of this section on the substance or a close structural analogue of the substance which demonstrates that the new substance will not present an unreasonable risk of injury to aquatic species or human health at the higher concentration.

(iv) *Incineration.* For ambient air releases from incineration, no releases of the new chemical substance above 1 microgram per cubic meter maximum annual average concentration, calculated using the formula:

(kg/day of release after treatment) multiplied by (number of release days per year) multiplied by  $(9.68 \times 10^{-6})$  micrograms per cubic meter.

(v) *Land or groundwater.* For releases to land or groundwater, no releases to groundwater, to land, or to a landfill unless the manufacturer has dem-

onstrated to EPA's satisfaction in a notice under paragraph (e) of this section that the new substance has negligible groundwater migration potential.

(d) *Chemical substances that cannot be manufactured under this exemption.* A new chemical substance cannot be manufactured under this section, notwithstanding satisfaction of the criterion of paragraphs (c)(1) or (c)(2) of this section, if EPA determines, in accordance with paragraph (g) of this section, that the substance, any reasonably anticipated metabolites, environmental transformation products, or by-products of the substance, or any reasonably anticipated impurities in the substance may cause, under anticipated conditions of manufacture, processing, distribution in commerce, use, or disposal of the new chemical substance:

(1) Serious acute (lethal or sublethal) effects.

(2) Serious chronic (including carcinogenic and teratogenic) effects.

(3) Significant environmental effects.

(e) *Exemption notice.* (1) A manufacturer applying for an exemption under either paragraph (c)(1) or (c)(2) of this section must submit an exemption notice to the EPA at least 30 days before manufacture of the new chemical substance begins. Unless allowed as described by § 723.50(e)(1)(i), (e)(1)(ii), or (e)(1)(iii), exemption notices and modifications must be submitted to EPA on EPA Form No. 7710-25 via EPA's Central Data Exchange (CDX) using EPA-provided e-PMN reporting software in the manner set forth in this paragraph. Support documents related to these notices must also be submitted to EPA via CDX using e-PMN software in the manner set forth in this paragraph. See 40 CFR 720.40(a)(2)(iv) for information on how to obtain e-PMN software.

(i) *Paper-based submissions—(A)* Such notices, and any support documents related to these notices, submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted

## Environmental Protection Agency

## § 723.50

via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(B) All other notices and related support documents may be submitted on paper on or before April 6, 2011. All paper-based notices must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print EPA Form 7710-25 for submission to EPA. Paper notices must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(ii) *Submissions on optical disc*—(A) Notices may be submitted as electronic files on optical disc on or before April 6, 2012. Notices submitted as electronic files on optical disc must be generated using e-PMN reporting software and be completed through the finalization step of the software. Optical discs containing electronic notices must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(B) Persons submitting on optical disc must still complete and submit on paper the Certification and Submitter Identification sections of EPA Form 7710-25 accompanying the optical disc.

(iii) *Submissions via CDX*—(A) On or after April 6, 2010, notices, and any related support documents, may be submitted electronically to EPA via CDX. Prior to submission to EPA via CDX, notices must be generated and completed on EPA Form 7710-25 using e-PMN reporting software.

(B) On or after April 6, 2012, all notices must be generated and completed on EPA Form 7710-25 using e-PMN reporting software and submitted electronically, along with any support documents related to these notices, to EPA via CDX.

(iv) Support documents for notices that are submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(2) The notice shall contain the information described below, pursuant to the referenced provisions of § 720.45.

(i) Manufacturer identity.

(ii) Chemical identity (§ 720.45(a)).

(iii) Impurities (§ 720.45(b)).

(iv) Known synonyms or trade names (§ 720.45(c)).

(v) Byproducts (§ 720.45(d)).

(vi) Production volume (§ 720.45(e)).

(A) Manufacturers submitting an exemption application under paragraph (c)(1) of this section will be assumed to be manufacturing at an annual production volume of 10,000 kilograms. Manufacturers who intend to manufacture an exempted substance at annual volumes of less than 10,000 kilograms and wish EPA to conduct its risk assessment based upon such lesser annual production level rather than a 10,000-kilograms level, may so specify by writing the lesser annual production volume in the appropriate box on the PMN form and marking the adjacent binding option box. Manufacturers who opt to specify annual production levels below 10,000 kilograms and who mark the production volume binding option box shall not manufacture more than the specific annual amount of the exempted substance unless a new exemption notice for a higher (up to 10,000 kgs) manufacturing volume is submitted and approved pursuant to this section.

(B) Manufacturers submitting an exemption under paragraph (c)(2) of this section shall list the estimated maximum amount to be manufactured during the first year of production and the estimated maximum amount to be manufactured during any 12-month period during the first 3 years of production.

(vii) Description of intended categories of use (§ 720.45(f)).

(viii) For manufacturer-controlled sites, the manufacturer shall supply identity of manufacturing sites, process descriptions, and worker exposure and environmental release information (§ 720.45(g)); for sites not controlled by the manufacturer, processing and use operation descriptions, estimated number of processing and use sites, and worker exposure/environmental release information (§ 720.45(h)). A manufacturer applying for an exemption under paragraph (c)(1) of this section need not provide information on worker exposure and environmental release referenced in paragraphs (e)(2)(viii) of this section if such information is not known or not readily available to the manufacturer. To assist in reporting this information, manufacturers may obtain a copy of EPA's Guidance for Reporting Occupational Exposure and Environmental Release Information under 40 CFR 723.50, available from the Environmental Assistance Division at the address listed in paragraph (e)(1) of this section. Where worker exposure and environmental release information is not supplied by the manufacturer, EPA will generally apply "bounding estimates" (i.e., exposure estimates higher than those incurred by persons in the population with the highest exposure) to account for uncertainties in actual exposure and release scenarios.

(ix) Type and category of notice. The manufacturer must clearly indicate on the first page of the PMN form that the submission is a "TSCA section 5(h)(4) exemption notice," and must indicate whether the notice is being submitted under paragraph (c)(1) or (c)(2) of this section. Manufacturers of chemical substances that qualify for an exemption under both paragraph (c)(1) and (c)(2) of this section may apply for either exemption, but not both.

(x) Test data (§ 720.50).

(xi) Certification. In addition to the certifications required in EPA form 7710-25, the following certifications shall be included in notices under this section. The manufacturer must certify that:

(A) The manufacturer intends to manufacture or import the new chemical substance for commercial pur-

poses, other than in small quantities solely for research and development, under the terms of this section.

(B) The manufacturer is familiar with the terms of this section and will comply with those terms.

(C) The new chemical substance for which the notice is submitted meets all applicable exemption conditions.

(D) For substances manufactured under paragraph (c)(1) of this section, the manufacturer intends to commence manufacture of the exempted substance for commercial purposes within 1 year of the date of the expiration of the 30-day review period.

(xii) Sanitized copy of notice. (A) The manufacturer must make all claims of confidentiality in accordance with paragraph (1) of this section. If any information is claimed confidential, the manufacturer must submit a second copy of the notice, with all information claimed as confidential deleted, in accordance with paragraph (1)(3) of this section.

(B) If the manufacturer does not provide the second copy, the submission will be considered incomplete.

(3) *Incomplete notices.* If EPA receives a submission which does not include all of the information required under this paragraph (e) of this section, the submission will be determined to be incomplete by EPA. When a submission for a new chemical substance has been determined to be incomplete, a manufacturer reapplying for an exemption for the new chemical substance must submit a new exemption notice containing all the information required under this paragraph (e) of this section including a certification page containing an original dated signature; partial submissions sent to EPA to supplement notices declared incomplete will not be accepted. Photocopied pages from previously submitted exemption forms will be accepted provided that the certifications page contains an original dated signature.

(f) *Multiple exemption holders.* (1) A manufacturer who intends to manufacture a substance for which an exemption under this section was previously approved may apply for an exemption under paragraph (c)(1) or (c)(2) of this section; however, EPA will not approve any subsequent exemption application

under paragraph (c)(1) of this section unless it can determine that the potential human exposure to, and environmental release of, the new chemical substance at the higher aggregate production volume will not present an unreasonable risk of injury to human health or the environment.

(2)(i) If EPA proposes to deny an exemption application for a substance for which another manufacturer currently holds an exemption, and that proposed denial is based exclusively on the cumulative human exposure or environmental release of the substance which precludes the EPA from determining that the subsequent applicant's activities will not present an unreasonable risk of injury to human health or the environment, the EPA will notify the first exemption holder that it must, within 21 days of its receipt of EPA's notice, either:

(A) Provide a new certification that it has commenced, or that it will commence, manufacture of the new chemical substance under this section within 1 year of the expiration of its exemption review period; or

(B) Withdraw its exemption for the new chemical substance.

(ii) If the first exemption holder does not respond to the EPA's notice under paragraph (f)(2)(i) of this section within the prescribed time period, EPA shall issue a notice of ineligibility to the first exemption holder under the provisions of paragraph (h)(2) of this section.

(g) *Review period.* (1) EPA will review the notice submitted under paragraph (e) of this section to determine whether manufacture of the new chemical substance is eligible for the exemption. The review period will end 30 days after receipt of the notice by the TSCA Document Control Officer. To provide additional time to address any unresolved issues concerning an exemption application, the exemption applicant may, at any time during the review period, request a suspension of the review period pursuant to the provisions of § 720.75(b) of this chapter.

(2) Upon expiration of the 30-day review period, if EPA has taken no action, the manufacturer may consider its exemption approved and begin to manufacture the new chemical sub-

stance under the terms described in its notice and in this section.

(h) *Notice of ineligibility*—(1) *During the review period.* If the EPA determines during the review period that manufacture of the new chemical substance does not meet the terms of this section or that there are issues concerning toxicity or exposure that require further review which cannot be accomplished within the 30-day review period, EPA will notify the manufacturer by telephone that the substance is not eligible. This telephone notification will subsequently be confirmed by certified letter that identifies the reasons for the ineligibility determination. The manufacturer may not begin manufacture of the new chemical substance without complying with section 5(a)(1) of the Act or submitting a new notice under paragraph (e) of this section that satisfies EPA's concerns.

(2) *After the review period.* (i)(A) If at any time after the review period specified in paragraph (g) of this section the Assistant Administrator for the Office of Prevention, Pesticides, and Toxic Substances ("the Assistant Administrator") makes a preliminary determination that manufacture of the new chemical substance does not meet the terms of this section, the Assistant Administrator will notify the manufacturer by certified letter that EPA believes that the new chemical substance does not meet the terms of the section.

(B) The manufacturer may continue to manufacture, process, distribute in commerce, and use the substance after receiving the notice under paragraph (h)(2)(i)(A) of this section if the manufacturer was manufacturing, processing, distributing in commerce, or using the substance at the time of the notification and if the manufacturer submits objections or an explanation under paragraph (h)(2)(ii) of this section. Manufacturers not manufacturing, processing, distributing in commerce, or using the substance at the time of the notification may not begin manufacture until EPA makes its final determination under paragraph (h)(2)(iii) of this section.

(ii) A manufacturer who has received notice under paragraph (h)(2)(i)(A) of this section may submit, within 15 days of receipt of written notification,

detailed objections to the determination or an explanation of its diligence and good faith efforts in attempting to comply with the terms of this section.

(iii) The Assistant Administrator will consider any objections or explanation submitted under paragraph (h)(2)(ii) of this section and will make a final determination. The Assistant Administrator will notify the manufacturer of the final determination by telephone within 15 days of receipt of the objections or explanation, and subsequently by certified letter.

(iv) If the Assistant Administrator determines that manufacture of the new chemical substance meets the terms of this section, the manufacturer may continue or resume manufacture, processing, distribution in commerce, and use in accordance with the terms of this section.

(v) If the Assistant Administrator determines that manufacture of the new chemical substance does not meet the terms of this section and that the manufacturer did not act with due diligence and in good faith to meet the terms of this section, the manufacturer must cease any continuing manufacture, processing, distribution in commerce, and use of the new chemical substance within 7 days of the written notification under paragraph (h)(2)(iii) of this section. The manufacturer may not resume manufacture, processing, distribution in commerce, and use of the new chemical substance until it submits a notice under section 5(a)(1) of the Act and part 720 of this chapter and the notice review period has ended.

(vi) If the Assistant Administrator determines that manufacture of the new chemical substance does not meet the terms of this section and that the manufacturer acted with due diligence and in good faith to meet the terms of this section, the manufacturer may continue manufacture, processing, distribution in commerce, and use of the new chemical substance if:

(A) It was actually manufacturing, processing, distributing in commerce, or using the chemical substance at the time it received the notification specified in paragraph (h)(2)(i)(A) of this section.

(B) It submits a notice on the new chemical substance under section

5(a)(1) of the Act and part 720 of this chapter within 15 days of receipt of the written notification under paragraph (h)(2)(iii) of this section. Such manufacture, processing, distribution in commerce, and use may continue unless EPA takes action under section 5(e) or 5(f) of the Act.

(3) Action under this paragraph does not preclude action under sections 7, 15, 16, or 17 of the Act.

(i) *Additional information.* If the manufacturer of a new chemical substance under the terms of this exemption obtains test data or other information indicating that the new chemical substance may not qualify under terms of this section, the manufacturer must submit these data or information to EPA within 15 working days of receipt of the information. If, during the notice review period specified in paragraph (g) of this section, the submitter obtains possession, control, or knowledge of new information that materially adds to, changes, or otherwise makes significantly more complete the information included in the notice, the submitter must send that information to the address listed on the notice form within 10 days of receiving the new information, but no later than 5 days before the end of the notice review period. The new submission must clearly identify the submitter and the exemption notice to which the new information is related. If the new information becomes available during the last 5 days of the notice review period, the submitter must immediately inform its EPA contact for that notice by telephone.

(j) *Changes in manufacturing site, use, human exposure and environmental release controls, and certain manufacturing volumes.* (1) Except as provided in paragraph (j)(6) of this section, chemical substances manufactured under this section must be manufactured at the site or sites described, for the uses described, and under the human exposure and environmental release controls described in the exemption notice under paragraph (e) of this section.

(2) Where the manufacturer lists a specific physical form in which the new

chemical substance will be manufactured, processed, and/or used, the manufacturer must continue manufacturing, processing, and/or using the new chemical substance in either the same physical form described in the notice under paragraph (e), or in a physical form which will not increase the human exposure to or environmental release of the new chemical substance over those exposures or releases resulting from the specified physical form (e.g., a manufacturer which specifies that the new chemical substance will be produced in a non-volatile liquid form generally may not change to a respirable powder form).

(3) The annual production volume of chemical substances manufactured under paragraph (c)(1) of this section for which the manufacturer designated a binding annual production volume pursuant to paragraph (e)(2)(vi) of this section must not exceed that designated volume.

(4) Any person who manufactures a new chemical substance under paragraph (c)(1) or (c)(2) of this section must comply with the provisions of this section, including submission of a new notice under paragraph (e) of this section, before:

(i) Manufacturing the new chemical substance at a site that was not approved in a previous exemption notice for the substance, except as provided in paragraph (j)(6) of this section.

(ii) Manufacturing the new chemical substance for a use that was not approved in a previous exemption notice for the substance.

(iii) Manufacturing the new chemical substance without employing the human exposure and environmental release controls approved in a previous exemption notice for the substance.

(iv) Manufacturing the new chemical substance in a physical form different than that physical form approved in a previous exemption notice for the substance and which form may increase the human exposure to, or environmental release of, the new chemical substance over those exposures or releases resulting from the physical form approved in the previous notice.

(v) Manufacturing the chemical substance in annual production volumes above any volume designated by the

manufacturer as binding under paragraph (e)(2)(vi) of this section in a previous exemption notice for the substance.

(5) In an exemption notice informing EPA of a change in site, use, or worker protection, or environmental release controls, the manufacturer is not required to provide all of the same information submitted to EPA in a previous exemption notice for that chemical substance. The new exemption notice, however, must indicate the identity of the new chemical substance; the manufacturer's name; the name and telephone number of a technical contact; and location of the new site, new worker protection or environmental release controls, and new use information. The notice must also include the EPA-designated exemption number assigned to the previous notice and a new certification by the manufacturer, as described in paragraph (e)(2)(xi) of this section.

(6)(i) A manufacturer may, without submitting a new notice, manufacture the new chemical substance at a site not listed in its exemption application under the following conditions:

(A) the magnitude, frequency, and duration of exposure of individual workers to the new chemical substance at the new manufacturing site is equal to, or less than, the magnitude, frequency, and duration of exposure of the individual workers to the new chemical substance at the manufacturing site for which the EPA performed its original risk-assessment pursuant to the original exemption notice; and

(B) Either (1) at the new manufacturing site, the manufacturer does not release to surface waters any of the new chemical substance, or any waste streams containing the new chemical substance; or (2) at the new manufacturing site, the manufacturer maintains surface water concentrations of the chemical substance, resulting from direct or indirect discharges from the manufacturing site, at or below 1 part per billion, or at or below an alternative concentration level approved by the Agency in writing or under the procedures described in paragraph (c)(2)(iii) of this section, using the water concentration calculation method described at §§ 721.90 and 721.91.

(ii) The manufacturer shall notify EPA of any new manufacturing site no later than 30 days after the commencement of manufacture of the new chemical substance under the exemption at the new manufacturing site as follows:

(A) The notification must contain the EPA-designated exemption number to which the notification applies, manufacturer identity, the street address of the new manufacturing site, the date on which manufacture commenced at the new site, the name and telephone number of a technical contact at the new site, any claim of confidentiality, and a statement that the notification is an amendment to the original exemption application under the terms of this section.

(B) The notification may be submitted on EPA form 7710–56 “Notice of Commencement of Manufacture;” however, the manufacturer must add the statement required under paragraph (j)(6)(ii)(A) of this section that the notification is an amendment to the original exemption.

(C) The notification must contain an original signature of an authorized official of the manufacturer.

(k) *Customer notification.* (1) Manufacturers of new chemical substances described in paragraphs (c)(1) and (c)(2) of this section must notify processors and industrial users that the substance can be used only for the uses specified in the exemption notice at paragraph (e) of this section. The manufacturer must also inform processors and industrial users of any controls specified in the exemption notice. The manufacturer may notify processors and industrial users by means of a container labeling system, written notification, or any other method that adequately informs them of use restrictions or controls.

(2) A manufacturer of a new chemical substance described in paragraph (c)(2) of this section may distribute the chemical substance only to other persons who agree in writing to not further distribute the substance until it has been reacted, incorporated into an article, or otherwise rendered into a physical form or state in which environmental releases and human exposures above the eligibility criteria in paragraph (c)(2) of this section are not likely to occur.

(3) If the manufacturer learns that a direct or indirect customer is processing or using the new substance in violation of use restrictions or without imposing prescribed worker protection or environmental release controls, the manufacturer must cease distribution of the substance to the customer or the customer’s supplier immediately unless the manufacturer is able to document each of the following:

(i) That the manufacturer has, within 5 working days, notified the customer in writing that the customer has failed to comply with the conditions specified in this section and the exemption notice under paragraph (e) of this section.

(ii) That, within 15 working days of notifying the customer of the non-compliance, the manufacturer received from the customer, in writing, a statement of assurance that the customer is aware of the terms of this section and the exemption notice and will comply with those terms.

(4) If, after receiving a statement of assurance from a customer under paragraph (k)(3)(ii) of this section, the manufacturer obtains knowledge that the customer has again failed to comply with any of the conditions specified in this section or the exemption notice, the manufacturer shall cease supplying the new chemical substance to that customer and shall report the failure to comply to EPA within 15 days of obtaining this knowledge. Within 30 days of its receipt of the report, EPA will notify the manufacturer whether, and under what conditions, distribution of the chemical substance to the customer may resume.

(1) *Confidentiality.* (1) If the manufacturer submits information to EPA under this section which the manufacturer claims to be confidential business information, the manufacturer must clearly identify the information at the time of submission to EPA by bracketing, circling, or underlining it and stamping it with “CONFIDENTIAL” or some other appropriate designation. Any information so identified will be treated in accordance with the procedures in part 2 of this chapter. Any information not claimed confidential at the time of submission may be made available to the public without further notice.

(2)(i) Any person who asserts a claim of confidentiality for chemical identity under this paragraph (1) must provide a generic chemical name that is only as generic as necessary to protect the confidential chemical identity of the particular chemical substance. The name should reveal the specific chemical identity to the maximum extent possible.

(ii) The generic name provided by the manufacturer will be subject to EPA review and approval in accordance with the procedures specified in § 720.85(b)(6) of this chapter. The generic name provided by the submitter or an alternative selected by EPA under these procedures will be placed on a public list of substances exempt under this section.

(3) If any information is claimed confidential, the manufacturer must submit a second copy of the notice with all information claimed as confidential deleted. EPA will place the second copy in the public file.

(m) *Exemptions granted under superseded regulations.* Manufacturers holding exemptions granted under the superseded requirements of this section (as in effect on May 26, 1995) shall either continue to comply with those requirements (including the production volume limit) or apply for a new exemption pursuant to this section. EPA will not accept requests to amend exemptions granted under the superseded requirements; manufacturers wishing to amend such exemptions must submit a new exemption under paragraph (e) of this section. If a new exemption for a new chemical substance is granted under this exemption to the manufacturer holding an exemption under the superseded requirements, the exemption under the superseded requirements for such substance shall be void.

(n) *Recordkeeping.* (1) A manufacturer of a new chemical substance under paragraph (c) of this section must maintain the records described in this paragraph at the manufacturing site or site of importation for a period of 5 years after their preparation.

(2) The records must include the following to demonstrate compliance with this section:

(i) Records of annual production volume and import volume.

(ii) Records documenting compliance with the applicable requirements and restrictions of paragraphs (c), (e), (f), (h), (i), (j), and (k) of this section.

(3) Any person who manufactures a new chemical substance under the terms of this section must, upon request of a duly designated representative of EPA, permit such person at all reasonable times to have access to and to copy records kept under paragraph (n)(2) of this section.

(4) The manufacturer must submit the records listed in paragraph (n)(2) of this section to EPA upon request. Manufacturers must provide these records within 15 working days of receipt of such request.

(o) *Compliance.* (1) Failure to comply with any provision of this section is a violation of section 15 of the Act (15 U.S.C. 2614).

(2) Submitting materially misleading or false information in connection with the requirements of any provision of this section is a violation of this section and therefore a violation of section 15 of the Act (15 U.S.C. 2614).

(3) Violators may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation.

(4) EPA may seek to enjoin the manufacture or processing of a chemical substance in violation of this section, or act to seize any chemical substance manufactured or processed in violation of this section, or take other action under the authority of section 7 of the Act (15 U.S.C. 2606) or section 17 of the Act (15 U.S.C. 1616).

[60 FR 16346, Mar. 29, 1995, as amended at 60 FR 34465, July 3, 1995; 62 FR 17932, April 11, 1997; 64 FR 31989, June 15, 1999; 71 FR 33642, June 12, 2006; 75 FR 787, Jan. 6, 2010]

**§ 723.175 Chemical substances used in or for the manufacture or processing of instant photographic and peel-apart film articles.**

(a) *Purpose and scope.* (1) This section grants an exemption from the premanufacture notice requirements of section 5(a)(1)(A) of the Toxic Substances Control Act (15 U.S.C. 2604(a)(1)(A)) for the manufacture and processing of new chemical substances used in or for the manufacture or processing of instant photographic and



peel-apart film articles. This section does not apply to microorganisms subject to part 725 of this chapter.

(2) To manufacture a new chemical substance under the terms of this exemption, a manufacturer of instant photographic or peel-apart film articles must:

(i) Submit an exemption notice when manufacture begins under paragraph (i) of this section.

(ii) Comply with certain requirements to limit exposure to the new chemical substance under paragraphs (e), (f), (g), and (h) of this section.

(iii) Comply with all recordkeeping requirements under paragraph (j) of this section.

(b) *Definitions.* (1) *Act* means the Toxic Substances Control Act (15 U.S.C. 2601 *et seq.*).

(2) An *article* is a manufactured item (i) which is formed to a specific shape or design during manufacture, (ii) which has end use function(s) dependent in whole or in part upon its shape or design during end use, and (iii) which has either no change of chemical composition during its end use or only those changes of composition which have no commercial purpose separate from that of the article and that may occur as described in §710.2 of this chapter except that fluids and particles are not considered articles regardless of shape or design.

(3) The terms *byproduct*, *EPA*, *impurities*, *person*, and *site* have the same meanings as in §710.3 of this chapter.

(4) The term *category of chemical substances* has the same meaning as in section 26(c)(2) of the Act (15 U.S.C. 2625).

(5) The terms *chemical substance*, *distribute in commerce*, *distribution in commerce*, *environment*, *manufacture*, *new chemical substance*, and *process* have the same meanings as in section 3 of the Act (15 U.S.C. 2602).

(6) *Director of the Office of Pollution Prevention and Toxics* means the Director of the EPA Office of Pollution Prevention and Toxics or any EPA employee designated by the Office Director to carry out the Office Director's functions under this section.

(7) The term *exemption category* means a category of chemical substances for which a person(s) has applied for or been granted an exemption

under section 5(h)(4) of the Act (15 U.S.C. 2604).

(8) The term *instant photographic film article* means a self-developing photographic film article designed so that all the chemical substances contained in the article, including the chemical substances required to process the film, remain sealed during distribution and use.

(9) *Intermediate* means any chemical substance which is consumed in whole or in part in a chemical reaction(s) used for the intentional manufacture of another chemical substance.

(10) *Known to or reasonably ascertainable* means all information in a person's possession or control, plus all information that a reasonable person similarly situated might be expected to possess, control, or know, or could obtain without unreasonable burden or cost.

(11) The term *peel-apart film article* means a self-developing photographic film article consisting of a positive image receiving sheet, a light sensitive negative sheet, and a sealed reagent pod containing a developer reagent and designed so that all the chemical substances required to develop or process the film will not remain sealed within the article during and after the development of the film.

(12) *Photographic article* means any article which will become a component of an instant photographic or peel-apart film article.

(13) *Special production area* means a demarcated area within which all manufacturing, processing, and use of a new chemical substance takes place, except as provided in paragraph (f) of this section, in accordance with the requirements of paragraph (e) of this section.

(14) *Test data* means:

(i) Data from a formal or informal study, test, experiment, recorded observation, monitoring, or measurement.

(ii) Information concerning the objectives, experimental methods and materials, protocols, results, data analyses (including risk assessments), and conclusions from a study, test, experiment, recorded observation, monitoring, or measurement.

(15) *Used in or for the manufacturing or processing of an instant photographic or peel-apart film article*, when used to describe activities involving a new chemical substance, means the new chemical substance (i) is included in the article, or (ii) is an intermediate to a chemical substance included in the article or is one of a series of intermediates used to manufacture a chemical substance included in the article.

(16) *Wet mixture* means a water or organic solvent-based suspension, solution, dispersion, or emulsion used in the manufacture of an instant photographic or peel-apart film article.

(c) *Exemption category*. The exemption category includes new chemical substances used in or for the manufacture or processing of instant photographic or peel-apart film articles which are manufactured and processed under the terms of this section.

(d) *Applicability*. This exemption applies only to manufacturers of instant photographic or peel-apart film articles who:

(1) Manufacture the new chemical substances used in or for the manufacture or processing of the instant photographic or peel-apart film articles.

(2) Limit manufacture and processing of a new chemical substance to the site(s) listed in the exemption notice for that new chemical substance submitted under paragraph (i) of this section.

(3) Comply with the requirements of paragraphs (e), (f), (g), (h), and (j) of this section.

(4) Do not distribute in commerce or use a peel-apart film article containing a new chemical substance until submission of a premanufacture notice under section 5(a)(1)(A) of the Act (15 U.S.C. 2604) and until the review period for the notice has ended without EPA action to prevent distribution or use.

(e) *Conditions of manufacture and processing in the special production area*. All manufacturing, processing, and use operations involving the new chemical substance must be performed in a special production area under the conditions set forth in this paragraph until the new chemical substance has been incorporated into a wet mixture, photographic article, or instant photographic or peel-apart film article.

(1) *Exposure limits*. In the special production area, the ambient air concentration of the new chemical substance during manufacture, processing, and use cannot exceed an 8-hour time weighted average (TWA) of 10 ppm for gases and vapors and 50 µg/m<sup>3</sup> for particulates, with an allowable TWA excursion of 50 percent above those concentrations for a duration of 30 minutes or less.

(2) *Respiratory protection*—(i) *Respirator requirement*. Except as specified in paragraph (e)(2)(ii) of this section, each person in the special production area must wear an appropriate respiratory protection device to protect against dusts, fumes, vapors, and other airborne contaminants, as described in 29 CFR 1910.134. Selection of an appropriate respirator must be made according to the guidance of American National Standard Practices for Respiratory Protection Z88.2-1969 and the NIOSH Certified Equipment List, U.S. Department of Health and Human Services, NIOSH publication No. 80-144.

(ii) *Waiver of respirator requirement*. Employees are not required to wear respirators if monitoring information collected and analyzed in accordance with paragraph (e)(3) of this section demonstrates that the ambient 8-hour TWA concentration of the new chemical substance in the area is less than 1 ppm for gases and vapors and 5 µg/m<sup>3</sup> for particulates with an allowable TWA excursion of 50 percent above these concentrations for a duration of 30 minutes or less.

(iii) *Quantitative fit test*. Each respirator must be issued to a specific individual for personal use. A quantitative fit test must be performed for each respirator before its first use by that person in a special production area.

(3) *Monitoring*—(i) *When to monitor*. (A) When suitable sampling and analytic methods exist, periodic monitoring in accordance with this paragraph must be done to ensure compliance with the exposure limits of paragraphs (e)(1) and (2)(ii) of this section.

(B) When suitable sampling and analytic methods do not exist, compliance with the exposure limits of paragraph

(e)(1) and the requirements of paragraph (e)(10) of this section must be determined by an evaluation of monitoring data developed for a surrogate chemical substance possessing comparable physical-chemical properties under similar manufacturing and processing conditions.

(ii) *Monitoring methods.* A suitable air sampling method must permit personal or fixed location sampling by conventional collection methods. A suitable analytic method must have adequate sensitivity for the volume of sample available and be specific for the new chemical substance being monitored. If chemical-specific monitoring methods are not available, nonspecific methods may be used if the concentration of the new chemical substance is assumed to be the total concentration of chemical substances monitored.

(iii) *Monitoring frequency.* (A) When suitable air sampling and analytical procedures are available, monitoring must be done in each special production area during the first three 8-hour work shifts involving the manufacture or processing of each new chemical substance. Thereafter, monitoring must be done in each special production area for at least one 8-hour period per month, during a production run in which the new chemical substance is manufactured or processed. Samples must be of such frequency and pattern as to represent with reasonable accuracy the mean level and maximum 30-minute level of employee exposure during an 8-hour work shift. In monitoring for an 8-hour work shift or the equivalent, samples must be collected periodically or continuously for the duration of the 8-hour work shift. Samples must be taken during a period which is likely to represent the maximum employee exposure.

(B) If the manufacturer demonstrates compliance with the exposure limits for 3 consecutive months, further monitoring of the identical process must be performed only every 6 months thereafter, unless there is a significant change in the process, process design, or equipment. If there is such a change, the manufacturer must begin monitoring again according to the schedule in paragraph (e)(3)(iii)(A) of this section.

(iv) *Location of monitoring.* Air samples must be taken so as to ensure that the samples adequately represent the ambient air concentration of a new chemical substance present in each worker's breathing zone.

(4) *Engineering controls and exposure safeguards.* Engineering controls such as, but not limited to, isolation, enclosure, local exhaust ventilation, and dust collection must be used to ensure compliance with the exposure limits prescribed in paragraphs (e)(1) or (e)(2)(ii) of this section.

(5) *Training, hygiene, and work practices—*(i) *Training.* No employee may enter a special production area before the completion of a training program. The training program must be adapted to the individual circumstances of the manufacturer and must address: The known physical-chemical and toxicological properties of the chemical substances handled in the area; procedures for using and maintaining respirators and other personal safeguards; applicable principles of hygiene; special handling procedures designed to limit personal exposure to, and inadvertent release of, chemical substances; and procedures for responding to emergencies or spills.

(ii) *Hygiene.* Appropriate standards of hygiene must be observed by all employees handling a new chemical substance in manufacturing, processing, or transfer operations. The manufacturer must provide appropriate facilities for employee changing and wash-up. Food, beverages, tobacco products, and cosmetics must not be allowed in special production areas.

(iii) *Work practices.* Operating procedures such as those related to chemical weighing and filtering, or the charging, discharging and clean-up of process equipment, must be designed and conducted to ensure compliance with the exposure limits prescribed in paragraph (e)(1) or (e)(2)(ii) of this section. Written procedures and all materials necessary for responding to emergency situations must be immediately accessible to all employees in a special production area. Any spill or unanticipated emission must be controlled by specially trained personnel using the

equipment and protective clothing described in paragraph (e)(6) of this section.

(6) *Personal protection devices.* All workers engaged in the manufacture and processing of a new chemical substance in the special production area must wear suitable protective clothing or equipment, such as chemical-resistant coveralls, protective eyewear, and gloves.

(7) *Caution signs.* Each special production area must be clearly posted with signs identifying the area as a special production area where new chemical substances are manufactured and processed under controlled conditions. Each sign must clearly restrict entry into the special production area to qualified personnel who are properly trained and equipped with appropriate personal exposure safeguards.

(8) *Removal for storage or transportation.* A new chemical substance that is not incorporated into a wet mixture, photographic article, or instant photographic or peel-apart film article may be removed from the special production area for purposes of storage between operational steps or for purposes of transportation to another special production area. Such storage or transportation must be conducted in a manner that limits worker and environmental exposure through the use of engineering controls, training, hygiene, work practices, and personal protective devices appropriate to the chemical substance in question.

(9) *Labeling.* (i) Any new chemical substance removed from a special production area or stored or transported between operational steps must be clearly labeled. The label must show the identity of the new chemical substance or an appropriate identification code, a statement of any known hazards associated with it, a list of special handling instructions, first aid information, spill control directions, and where applicable, the appropriate U.S. Department of Transportation notations.

(ii) No label is required if the new chemical substance has been incorporated into a photographic article, or if it is contained in a sealed reaction vessel or pipeline, or if it has been in-

corporated into an instant photographic or peel-apart film article.

(10) *Areas immediately adjacent to the special production area.* The ambient air concentration of the new chemical substance in areas immediately adjacent to the special production area must not exceed the exposure limit established in paragraph (e)(2)(ii) of this section for waiver of respirator protection within the special production area. Periodic monitoring in accordance with paragraph (e)(3) of this section must be performed in immediately adjacent areas where it is reasonable to expect a risk of inhalation exposure.

(f) *Conditions of processing outside the special production area.* A wet mixture may be incorporated into a photographic article or an instant photographic or peel-apart film article outside the special production area under the conditions listed in this paragraph:

(1) *Engineering controls and exposure safeguards.* Engineering controls must limit the exposure to a new chemical substance contained in a wet mixture.

(2) *Training, hygiene and work practices—(i) Training.* Training of employees involved in the handling of wet mixtures containing a new chemical substance must be adapted to the individual circumstances of the employees' activities and must address: Procedures for using personal exposure safeguards, applicable principles of hygiene, handling procedures designed to limit personal exposure, and procedures for responding to emergencies and spills.

(ii) *Hygiene.* Appropriate standards of hygiene that limit exposure must be observed by all employees handling wet mixtures that contain new chemical substances.

(iii) *Work practices.* Work practices and operating procedures must be designed to limit exposure to any new chemical substance contained in wet mixtures. Any spills or unanticipated releases of a wet mixture must be controlled by trained personnel wearing appropriate protective clothing or equipment such as gloves, eye protection, and, where necessary, respirators or chemically impervious clothing.

(3) *Personal protection devices.* All workers engaged in the processing of a wet mixture containing a new chemical

substance must wear suitable protective clothing or equipment such as coveralls, protective eyewear, respirators, and gloves.

(g) *Incorporation of photographic articles into instant photographic and peel-apart film articles.* A photographic article may be incorporated into the instant photographic or peel-apart film article outside the special production area. The manufacturer must take measures to limit worker and environmental exposure to new chemical substances during these operations using engineering controls, training, hygiene, work practices, and personal protective devices.

(h) *Environmental release and waste treatment—(1) Release to land.* Process waste from manufacturing and processing operations in the special production area that contain a new chemical substance are considered to be hazardous waste and must be handled in accordance with the requirements of parts 262 through 267 and parts 122 and 124 of this chapter.

(2) *Release to water.* All wastewater or discharge which contain the new chemical substance must be appropriately pretreated before release to a Publicly Owned Treatment Works (POTW) or other receiving body of water. In the case of release to a POTW, the pretreatment must prevent structural damage to, obstruction of, or interference with the operation of the POTW. The treatment of direct release to a receiving body of water must be appropriate for the new chemical substance's physical-chemical properties and potential toxicity.

(3) *Release to air.* All process emissions released to the air which contain the new chemical substance must be vented through control devices appropriate for the new chemical substance's physical-chemical properties and potential toxicity.

(i) *Exemption notice.* An exemption notice must be submitted to EPA when manufacture of the new chemical substance begins.

(1) *Contents of exemption notice.* The exemption notice must include the following information:

(i) *Manufacturer and sites.* The notice must identify the manufacturer and the sites and locations where the new

chemical substance and the instant photographic or peel-apart film articles will be manufactured and processed.

(ii) *Chemical identification.* The notice must identify the new chemical substance as follows:

(A) *Class 1 substances.* For chemical substances whose composition can be represented by a definite structural diagram (Class 1 substances), the notice must provide the chemical name (preferably CAS or IUPAC nomenclature), the molecular formula, CAS Registry Number (if available), known synonyms (including trade names), and a structural diagram.

(B) *Class 2 substances.* For chemical substances that cannot be fully represented by a structural diagram, (Class 2 substances), the notice must provide the chemical name, the molecular formula, the CAS Registry Number (if available), and known synonyms (including trade names). The notice must identify the immediate precursors and reactants by name and CAS Registry Number (if available). The notice must include a partial or incomplete structural diagram, if available.

(C) *Polymers.* For a polymer, the notice must identify monomers and other reactants used in the manufacture of the polymer by chemical name and CAS Registry Number. The notice must indicate the amount of each monomer used (by weight percent of total monomer); the maximum residual of each monomer present in the polymer; and a partial or incomplete structural diagram, if available. The notice must indicate the number average molecular weight of the polymer and characterize the anticipated low molecular weight species. The notice must include this information for each typical average molecular weight composition of the polymer to be manufactured.

(iii) *Impurities.* The notice must identify the impurities that can be reasonably anticipated to be present in the new chemical substance when manufactured under the exemption by name and CAS Registry Number, by class of substances, or by process or source. The notice also must estimate the maximum percent (by weight) of each

impurity in the new chemical substance and the percent of unknown impurities present.

(iv) *Physical-chemical properties.* The notice must describe the physical-chemical properties of the new chemical substance. Where specific physical-chemical data are not available, reasonable estimates and the techniques used to develop these estimates must be provided.

(v) *Byproducts.* The notice must identify the name, CAS Registry number (if available), and the volume of each by-product that would be manufactured during manufacture of the new chemical substance.

(vi) *Production volume.* The notice must include an estimate of the anticipated maximum annual production volume.

(vii) *Test data.* The notice must include all information and test data on the new chemical substance's health and environmental effects that are known to or reasonably ascertainable by the manufacturer.

(viii) *Identity of the article.* The notice must identify and describe the instant photographic film article(s) or peel-apart film article(s) that will contain the new chemical substance.

(ix) *Release to water.* The notice must include a description of the methods used to control and treat wastewater or discharge released to a POTW or other receiving body of water. The notice must also identify the POTW or receiving body of water.

(x) *Certification.* The manufacturer must certify in the notice that it is familiar with the terms of the exemption and that the manufacture, processing, distribution, use, and disposal of the new chemical substance will comply with those terms.

(2) *Duplication of information in premanufacture notice.* If a manufacturer who submits an exemption notice under this paragraph has already submitted, or simultaneously submits, a premanufacture notice under section 5(a)(1)(A) of the Act for the new chemical substance, it may, in lieu of submitting the information required by this paragraph, reference the required information to the extent it is included in the premanufacture notice. At a minimum, the exemption notice must

identify the manufacturer and the new chemical substance, and contain the certification required by paragraph (i)(1)(x) of this section.

(3) *Address.* The exemption notice must be addressed to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001.

(j) *Recordkeeping.* (1) Manufacturers of a new chemical substance under this exemption must keep the following records for 30 years from the final date of manufacture.

(i) *Production records.* Each manufacturer must maintain records of the annual production volume of each new chemical substance manufactured under the terms of the exemption. This record must indicate when manufacture of the new chemical substance began.

(ii) *Exposure monitoring records.* Manufacturers must maintain an accurate record of all monitoring required by this section. Monitoring records may be adapted to the individual circumstances of the manufacturer but, at a minimum, must contain the following information: The chemical identity of the new chemical substance, date of the monitoring, the actual monitoring data for each monitoring location and sampling, and a reference to or description of the collection and analytic techniques. If the manufacturer does not monitor, the manufacturer must maintain a record of the reasons for not monitoring and the methods used to determine compliance with the exposure limits of paragraph (e)(1) of this section.

(iii) *Training and exposure records.* For each employee engaged in the manufacture or processing of a new chemical substance, the company must develop and maintain a record of the worker's participation in required training. This record must also demonstrate the regular use of personal exposure safeguards, including the results of any personal exposure monitoring, the results of the quantitative fit test for the worker's personal respirator, and any additional information related to the worker's occupational exposure.

## § 723.250

(iv) *Treatment records.* Manufacturers who release treated wastewater or discharge containing a new chemical substance to a POTW or other receiving body of water must maintain records of the method of treatment.

(2) The manufacturer must make the records listed in paragraph (j)(1) of this section available to EPA upon written request by the Director of the Office of Pollution Prevention and Toxics. The manufacturer must provide these records within 15 working days of receipt of this request.

(k) *Confidentiality.* If the manufacturer submits information under paragraph (i) or (j) of this section which it claims to be confidential business information, the manufacturer must clearly identify the information at the time of submission to the Agency by bracketing, circling, or underlining it and stamping it with "CONFIDENTIAL" or some other appropriate designation. Any information so identified will be treated in accordance with the procedures in part 2 of this chapter. Any information not claimed confidential at the time of submission will be made available to the public without further notice to the submitter.

(1) *Amendment and repeal.* (1) EPA may amend or repeal any term of this exemption if it determines that the manufacture, processing, distribution, use, and disposal of new chemical substances under the terms of the exemption may present an unreasonable risk of injury to health or the environment. EPA also may amend this exemption to enlarge the exemption category or to reduce the restrictions or conditions of the exemption.

(2) As required by section 5(h)(4) of the Act, EPA will amend or repeal the substantive terms of an exemption granted under this part only by the formal rulemaking procedures described in section 6(c)(2) and (3) of the Act (15 U.S.C. 2605(c)).

(m) *Prohibition of use of the exemption.* The Director of the Office of Pollution Prevention and Toxics may prohibit the manufacture, processing, distribution, use, or disposal of any new chemical substance under the terms of this exemption if he or she determines that the manufacture, processing, distribution in commerce, use, or disposal of

## 40 CFR Ch. I (7-1-10 Edition)

the new chemical substance may present an unreasonable risk of injury to health or the environment.

(n) *Enforcement.* (1) A failure to comply with any provision of this part is a violation of section 15 of the Act (15 U.S.C. 2614).

(2) Submitting materially misleading or false information in connection with the requirements of any provision of this part is a violation of this regulation and therefore a violation of section 15 of the Act (15 U.S.C. 2614).

(3) Violators may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation.

(4) EPA may seek to enjoin the manufacture of a new chemical substance in violation of this exemption or act to seize any chemical substances manufactured in violation of the exemption under the authority of section 17 of the Act (15 U.S.C. 2616).

[47 FR 24317, June 4, 1982, as amended at 53 FR 12523, Apr. 15, 1988; 60 FR 34465, July 3, 1995; 62 FR 17932, April 11, 1997; 68 FR 906, Jan. 7, 2003; 71 FR 33642, June 12, 2006]

## § 723.250 Polymers.

(a) *Purpose and scope.* (1) This section grants an exemption from certain of the premanufacture notice requirements of section 5(a)(1)(A) of the Toxic Substances Control Act (15 U.S.C. 2604(a)(1)(A)) for the manufacture of certain polymers. This section does not apply to microorganisms subject to part 725 of this chapter.

(2) To manufacture a new chemical substance under the terms of this section, a manufacturer must:

(i) Determine that the substance meets the definition of polymer in paragraph (b) of this section.

(ii) Determine that the substance is not specifically excluded by paragraph (d) of this section.

(iii) Ensure that the substance meets the exemption criteria of paragraph (e) of this section.

(iv) Submit a report as required under paragraph (f) of this section.

(v) Comply with the recordkeeping requirements of paragraph (j) of this section.

(b) *Definitions.* In addition to the definitions under section 3 of the Act, 15

U.S.C. 2602, the following definitions apply to this part.

*Act* means the Toxic Substances Control Act (15 U.S.C. 2601 et seq.).

*Biopolymer* means a polymer directly produced by living or once-living cells or cellular components.

*Category of chemical substances* has the same meaning as in section 26(c)(2) of the Act (15 U.S.C. 2625).

*Cationic polymer* means a polymer that contains a net positively charged atom(s) or associated groups of atoms covalently linked to its polymer molecule.

*Chemical substance, Director, EPA, importer, impurity, Inventory, known to or reasonably ascertainable, manufacture, manufacturer, mixture, new chemical, person, possession or control, process and test data* have the same meanings as in §720.3 of this chapter.

*Equivalent weight of a functional group* means the ratio of the molecular weight to the number of occurrences of that functional group in the molecule. It is the weight of substance that contains one formula-weight of the functional group.

*Fluorotelomers* means the products of telomerization, which is the reaction of a telogen (such as pentafluoroethyl iodide) with an ethylenic compound (such as tetrafluoroethylene) to form low molecular weight polymeric compounds, which contain an array of saturated carbon atoms covalently bonded to each other (C-C bonds) and to fluorine atoms (C-F bonds). This array is predominantly a straight chain, and depending on the telogen used produces a compound having an even number of carbon atoms. However, the carbon chain length of the fluorotelomer varies widely. The perfluoroalkyl groups formed by this process are usually, but do not have to be, connected to the polymer through a functionalized ethylene group as indicated by the following structural diagram: (Rf-CH<sub>2</sub>CH<sub>2</sub>-Anything).

*Internal monomer unit* means a monomer unit that is covalently bonded to at least two other molecules. Internal monomer units of polymer molecules are chemically derived from monomer molecules that have formed covalent bonds between two or more other monomer molecules or other reactants.

*Monomer* means a chemical substance that is capable of forming covalent bonds with two or more like or unlike molecules under the conditions of the relevant polymer-forming reaction used for the particular process.

*Monomer Unit* means the reacted form of the monomer in a polymer.

*Number-average molecular weight* means the arithmetic average (mean) of the molecular weight of all molecules in a polymer.

*Oligomer* means a polymer molecule consisting of only a few monomer units (dimer, trimer, tetramer)

*Other reactant* means a molecule linked to one or more sequences of monomer units but which, under the relevant reaction conditions used for the particular process, cannot become a repeating unit in the polymer structure.

*Perfluoroalkyl carboxylate (PFAC)* means a group of saturated carbon atoms covalently bonded to each other in a linear, branched, or cyclic array and covalently bonded to a carbonyl moiety and where all carbon-hydrogen (C-H) bonds have been replaced with carbon-fluorine (C-F) bonds. The carbonyl moiety is also covalently bonded to a hetero atom, typically, but not necessarily oxygen (O) or nitrogen (N).

*Perfluoroalkyl sulfonate (PFAS)* means a group of saturated carbon atoms covalently bonded to each other in a linear, branched, or cyclic array and covalently bonded to a sulfonyl moiety and where all carbon - hydrogen (C-H) bonds have been replaced with carbon - fluorine (C-F) bonds. The sulfonyl moiety is also covalently bonded to a hetero atom, typically, but not necessarily oxygen (O) or nitrogen (N).

*Polyester* means a chemical substance that meets the definition of polymer and whose polymer molecules contain at least two carboxylic acid ester linkages, at least one of which links internal monomer units together.

*Polymer* means a chemical substance consisting of molecules characterized by the sequence of one or more types of monomer units and comprising a simple weight majority of molecules containing at least 3 monomer units which are covalently bound to at least one other monomer unit or other reactant



and which consists of less than a simple weight majority of molecules of the same molecular weight. Such molecules must be distributed over a range of molecular weights wherein differences in the molecular weight are primarily attributable to differences in the number of monomer units. In the context of this definition, sequence means that the monomer units under consideration are covalently bound to one another and form a continuous string within the molecule, uninterrupted by units other than monomer units.

*Polymer molecule* means a molecule which contains a sequence of at least 3 monomer units which are covalently bound to at least one other monomer unit or other reactant.

*Reactant* means a chemical substance that is used intentionally in the manufacture of a polymer to become chemically a part of the polymer composition.

*Reactive functional group* means an atom or associated group of atoms in a chemical substance that is intended or can reasonably be anticipated to undergo further chemical reaction.

*Reasonably anticipated* means that a knowledgeable person would expect a given physical or chemical composition or characteristic to occur based on such factors as the nature of the precursors used to manufacture the polymer, the type of reaction, the type of manufacturing process, the products produced in polymerization, the intended uses of the substance, or associated use conditions.

(c) *Applicability.* This section applies to manufacturers of new chemical substances that otherwise must submit a premanufacture notice to EPA under § 720.22 of this chapter. New substances are eligible for exemption under this section if they meet the definition of "polymer" in paragraph (b) of this section, and the criteria in paragraph (e) of this section, and if they are not excluded from the exemption under paragraph (d) of this section.

(d) *Polymers that cannot be manufactured under this section*—(1) *Cationic polymers.* A polymer cannot be manufactured under this section if the polymer is a cationic polymer as defined under paragraph (b) of this section or if

the polymer is reasonably anticipated to become a cationic polymer in a natural aquatic environment (e.g., rivers, lakes) unless:

(i) The polymer is a solid material that is not soluble or dispersible in water and will be used only in the solid phase (e.g., polymers that will be used as ion exchange beads), or

(ii) The combined (total) functional group equivalent weight of cationic groups in the polymer is equal to or greater than 5,000.

(2) *Elemental limitations.* (i) A polymer manufactured under this section must contain as an integral part of its composition at least two of the atomic elements carbon, hydrogen, nitrogen, oxygen, silicon, and sulfur.

(ii) A polymer cannot be manufactured under this section if it contains as an integral part of its composition, except as impurities, any elements other than the following:

(A) The elements listed in paragraph (d)(2)(i) of this section.

(B) Sodium, magnesium, aluminum, potassium, calcium, chlorine, bromine, and iodine as the monatomic counterions  $\text{Na}^+$ ,  $\text{Mg}^{+2}$ ,  $\text{Al}^{+3}$ ,  $\text{K}^+$ ,  $\text{Ca}^{+2}$ ,  $\text{Cl}^-$ ,  $\text{Br}^-$ , or  $\text{I}^-$ .

(C) Fluorine, chlorine, bromine, and iodine covalently bound to carbon.

(D) Less than 0.20 weight percent of any combination of the atomic elements lithium, boron, phosphorus, titanium, manganese, iron, nickel, copper, zinc, tin, and zirconium.

(3) *Polymers which degrade, decompose, or depolymerize.* A polymer cannot be manufactured under this section if the polymer is designed or is reasonably anticipated to substantially degrade, decompose, or depolymerize, including those polymers that could substantially decompose after manufacture and use, even though they are not actually intended to do so. For the purposes of this section, degradation, decomposition, or depolymerization mean those types of chemical change that convert a polymeric substance into simpler, smaller substances, through processes including but not limited to oxidation, hydrolysis, attack by solvents, heat, light, or microbial action.

(4) *Polymers manufactured or imported from monomers and reactants not on the TSCA Chemical Substance Inventory.* A

polymer cannot be manufactured under this section if the polymer being manufactured or imported is prepared from monomers and/or other reactants (that are either charged to the reaction vessel or incorporated in the polymer at levels of greater than 2 weight percent) that are not already included on the TSCA Chemical Substance Inventory or manufactured under an applicable TSCA section 5 exemption.

(5) *Water absorbing polymers with number average molecular weight (MW) 10,000 and greater.* A polymer cannot be manufactured under this section if the polymer being manufactured or imported is a water absorbing polymer and has a number average MW greater than or equal to 10,000 daltons. For purposes of this section, a water-absorbing polymer is a polymeric substance that is capable of absorbing its weight of water.

(6) *Polymers which contain certain perfluoroalkyl moieties consisting of a CF<sub>3</sub>- or longer chain length.* Except as provided in paragraph (d)(6)(i), after February 26, 2010, a polymer cannot be manufactured under this section if the polymer contains as an integral part of its composition, except as impurities, one or more of the following perfluoroalkyl moieties consisting of a CF<sub>3</sub>- or longer chain length: Perfluoroalkyl sulfonates (PFAS), perfluoroalkyl carboxylates (PFAC), fluorotelomers, or perfluoroalkyl moieties that are covalently bound to either a carbon or sulfur atom where the carbon or sulfur atom is an integral part of the polymer molecule.

(i) Any polymer that has been manufactured previously in full compliance with the requirements of this section prior to February 26, 2010 may no longer be manufactured under this section after January 27, 2012.

(ii) [Reserved]

(e) *Exemption criteria.* To be manufactured under this section, the polymer must meet one of the following criteria:

(1) *Polymers with number average MW greater than or equal to 1,000 and less than 10,000 daltons (and oligomer content less than 10 percent below MW 500 and less than 25 percent below MW 1,000).* (i) The polymer must have a number average MW greater than or equal to 1,000

and less than 10,000 daltons and contain less than 10 percent oligomeric material below MW 500 and less than 25 percent oligomeric material below MW 1,000.

(ii) The polymer cannot contain reactive functional groups unless it meets one of the following criteria:

(A) The polymer contains only the following reactive functional groups: carboxylic acid groups, aliphatic hydroxyl groups, unconjugated olefinic groups that are considered "ordinary," (i.e., not specially activated either by being part of a larger functional group, such as a vinyl ether, or by other activating influences, e.g., strongly electron-withdrawing sulfone group with which the olefinic groups interact), butenedioic acid groups, those conjugated olefinic groups contained in naturally-occurring fats, oils, and carboxylic acids, blocked isocyanates (including ketoxime-blocked isocyanates), thiols, unconjugated nitrile groups, and halogens (except that reactive halogen-containing groups such as benzylic or allylhalides cannot be included).

(B) The polymer has a combined (total) reactive group equivalent weight greater than or equal to 1,000 for the following reactive functional groups: acidhalides; acid anhydrides; aldehydes, hemiacetals; methylolamides,- amines or,- ureas; alkoxy silanes with alkoxy greater than C<sub>2</sub>-alkoxy silanes; allyl ethers; conjugated olefins; cyanates; epoxides; imines; or unsubstituted positions *ortho* or *para* to phenolic hydroxyl; or

(C) If any reactive functional groups not included in paragraph (e)(1)(ii)(A) and (B) of this section are present, the combined (total) reactive group equivalent weight, including any groups listed in paragraph (e)(1)(ii)(B), is greater than or equal to 5,000.

(2) *Polymers with number average MW greater than or equal to 10,000 (and oligomer content less than 2 percent below MW 500 and less than 5 percent below MW 1,000).* The polymer must have a number average MW greater than or equal to 10,000 daltons and contain less than 2 percent oligomeric material below MW 500 and less than 5 percent oligomeric material below MW 1000.

(3) *Polyester polymers*. The polymer is solely from one or more of the a polyester as defined in paragraph (b) reactants in the following table 1: of this section and is manufactured

TABLE 1—LIST OF REACTANTS FROM WHICH POLYESTER MAY BE MADE

| Reactant  | CAS No.      |
|---|--------------|
| <b>Monobasic Acids and Natural Oils</b>                           |              |
| Benzoic acid .....  | 65-85-0      |
| Canola oil .....  | 120962-03-0  |
| Coconut oil .....   | 8001-31-8*   |
| Corn oil .....  | 8001-30-7*   |
| Cottonseed oil .....  | 8001-29-4*   |
| Dodecanoic acid .....   | 143-07-7     |
| Fats and glyceridic oils, anchovy .....                           | 128952-11-4* |
| Fats and glyceridic oils, babassu .....                           | 91078-92-1*  |
| Fats and glyceridic oils, herring .....                           | 68153-06-0*  |
| Fats and glyceridic oils, menhaden .....                          | 8002-50-4*   |
| Fats and glyceridic oils, sardine .....                           | 93334-41-9*  |
| Fats and glyceridic oils, oiticica .....                          | 8016-35-1*   |
| Fatty acids, C <sub>16-18</sub> and C <sub>18</sub> -unsatd. .... | 67701-08-0*  |
| Fatty acids, castor-oil .....                                     | 61789-44-4*  |
| Fatty acids, coco .....   | 61788-47-4*  |
| Fatty acids, dehydrated castor-oil .....                          | 61789-45-5*  |
| Fatty acids, linseed oil .....                                    | 68424-45-3*  |
| Fatty acids, safflower oil. ....                                  |              |
| Fatty acids, soya .....   | 68308-53-2*  |
| Fatty acids, sunflower oil .....                                  | 84625-38-7*  |
| Fatty acids, sunflower-oil, conjugated .....                      | 68953-27-5*  |
| Fatty acids, tall-oil .....                                       | 61790-12-3*  |
| Fatty acids, tall-oil, conjugated*. ....                          |              |
| Fatty acids, vegetable oil .....                                  | 61788-66-7*  |
| Glycerides, C <sub>16-18</sub> and C <sub>18</sub> -unsatd. ....  | 67701-30-8*  |
| Heptanoic acid .....  | 111-14-8     |
| Hexanoic acid .....   | 142-62-1     |
| Hexanoic acid, 3,3,5-trimethyl- .....                             | 3302-10-1    |
| Linseed oil .....   | 8001-26-1*   |
| Linseed oil, oxidized .....                                       | 68649-95-6*  |
| Nonanoic acid .....   | 112-05-0     |
| Oils, Cannabis*. ....   |              |
| Oils, palm kernel .....   | 8023-79-8*   |
| Oils, perilla .....   | 68132-21-8*  |
| Oils, walnut .....  | 8024-09-7    |
| Safflower oil .....   | 8001-23-8*   |
| Soybean oil .....   | 8001-22-7*   |
| Sunflower oil .....   | 8001-21-6*   |
| Tung oil .....  | 8001-20-5*   |
| <b>Di and Tri Basic Acids:</b>                                    |              |
| 1,2-Benzenedicarboxylic acid .....                                | 88-99-3      |
| 1,3-Benzenedicarboxylic acid .....                                | 121-91-5     |
| 1,3-Benzenedicarboxylic acid, dimethyl ester .....                | 1459-93-4    |
| 1,4-Benzenedicarboxylic acid .....                                | 100-21-0     |
| 1,4-Benzenedicarboxylic acid, diethyl ester .....                 | 636-09-9     |
| 1,4-Benzenedicarboxylic acid, dimethyl ester .....                | 120-61-6     |
| 1,2,4-Benzenetricarboxylic acid .....                             | 528-44-9     |
| Butanedioic acid .....  | 110-15-6     |
| Butanedioic acid, diethyl ester .....                             | 123-25-1     |
| Butanedioic acid, dimethyl ester .....                            | 106-65-0     |
| 2-Butenedioic acid (E)- .....                                     | 110-17-8     |
| Decanedioic acid .....  | 111-20-6     |
| Decanedioic acid, diethyl ester .....                             | 110-40-7     |
| Decanedioic acid, dimethyl ester .....                            | 106-79-6     |
| Dodecanedioic acid .....  | 693-23-2     |
| Fatty acids, C <sub>18</sub> -unsatd., dimers .....               | 61788-89-4*  |
| Heptanedioic acid .....   | 111-16-0     |
| Heptanedioic acid, dimethyl ester .....                           | 1732-08-7    |
| Hexanedioic acid .....  | 124-04-9     |
| Hexanedioic acid, dimethyl ester .....                            | 627-93-0     |
| Hexanedioic acid, diethyl ester .....                             | 141-28-6     |
| Nonanedioic acid .....  | 123-99-9     |
| Nonanedioic acid, dimethyl ester .....                            | 1732-10-1    |
| Nonanedioic acid, diethyl ester .....                             | 624-17-9     |
| Octanedioic acid .....  | (505-48-6)   |
| Octanedioic acid, dimethyl ester .....                            | 1732-09-8    |

TABLE 1—LIST OF REACTANTS FROM WHICH POLYESTER MAY BE MADE—Continued

| Reactant  | CAS No.      |
|---|--------------|
| Pentanedioic acid .....   | (110-94-1)   |
| Pentanedioic acid, dimethyl ester .....   | 1119-40-0    |
| Pentanedioic acid, diethyl ester .....  | 818-38-2     |
| Undecanedioic acid .....  | 1852-04-6    |
| <b>Polyols</b>  |              |
| 1,3-Butanediol .....  | 107-88-0     |
| 1,4-Butanediol .....  | 110-63-4     |
| 1,4-Cyclohexanedimethanol .....   | 105-08-8     |
| 1,2-Ethandiol .....   | 107-21-1     |
| Ethanol, 2,2'-oxybis- .....   | 111-46-6     |
| 1,6-Hexanediol .....  | 629-11-8     |
| 1,3-Pentanediol, 2,2,4-trimethyl- .....   | 144-19-4     |
| 1,2-Propanediol, .....  | 57-55-6      |
| 1,3-Propanediol, 2,2-bis(hydroxymethyl)- .....  | 115-77-5     |
| 1,3-Propanediol, 2,2-dimethyl- .....  | 126-30-7     |
| 1,3-Propanediol, 2-ethyl-2-(hydroxymethyl)- .....   | 77-99-6      |
| 1,3-Propanediol, 2-(hydroxymethyl)-2-methyl- .....  | 77-85-0      |
| 1,3-propanediol, 2-methyl .....   | 2163-42-0    |
| 1,2,3-Propanetriol .....  | 56-81-5      |
| 1,2,3-Propanetriol, homopolymer .....   | 25618-55-7   |
| 2-Propen-1-ol, polymer with ethenylbenzene .....  | 25119-62-4   |
| <b>Modifiers</b>  |              |
| Acetic acid, 2,2'-oxybis- .....   | 110-99-6     |
| 1-Butanol .....   | 71-36-3**    |
| Cyclohexanol .....  | 108-93-0     |
| Cyclohexanol, 4,4'-(1-methylethylidene)bis- .....   | 80-04-6      |
| Ethanol, 2-(2-butoxyethoxy)- .....  | 112-34-5     |
| 1-Hexanol .....   | 111-27-3     |
| Methanol, hydrolysis products with trichlorohexylsilane and trichlorophenylsilane .....                                     | 72318-84-4*  |
| 1-Phenanthrenemethanol, tetradecahydro-1,4a-dimethyl-7-(1-methylethyl)- .....   | 13393-93-6   |
| Phenol, 4,4'-(1-methylethylidene)bis-, polymer with 2,2'-[(1-methylethylidene)bis(4,1-phenyleneoxymethylene)] bis[oxirane]. | 25036-25-3   |
| Siloxanes and Silicones, di-Me, di-Ph, polymers with Ph silsesquioxanes, methoxy-terminated .....                           | 68440-65-3*  |
| Siloxanes and Silicones, di-Me, methoxy Ph, polymers with Ph silsesquioxanes, methoxy-terminated .....                      | 68957-04-0*  |
| Siloxanes and Silicones, Me Ph, methoxy Ph, polymers with Ph silsesquioxanes, methoxy- and Ph-terminated.                   | 168957-06-2* |
| Silsesquioxanes, Ph Pr .....  | 168037-90-1* |

\* Chemical substance of unknown or variable composition, complex reaction products, and biological materials (UVCB). The CAS Registry Numbers for UVCB substances are not used in CHEMICAL ABSTRACTS and its indexes.

\*\* These substances may not be used in a substance manufactured from fumaric or maleic acid because of potential risks associated with esters, which may be formed by reaction of these reactants.

(f) *Exemption report for polymers manufactured under the terms of this section.* For substances exempt under paragraphs (e)(1), (e)(2), and (e)(3) of this section a report of manufacture or import must be submitted (postmarked) by January 31 of the year subsequent to initial manufacture. The notice must include:

(1) *Manufacturer's name.* This includes the name and address of the manufacturer and the name and telephone number of a technical contact.

(2) *Number of substances manufactured.* Number of substances manufactured. The manufacturer must identify the number of polymers manufactured under terms of the exemption for the first time in the year preceding the notice.

(g) *Chemical identity information.* For substances exempt under paragraph (e) of this section the manufacturer must to the extent known to or reasonably ascertainable by the manufacturer identify the following and maintain the records in accordance with paragraph (j) of this section:

(1) A specific chemical name and CAS Registry Number (or EPA assigned Accession Number) for each "reactant," as that term is defined in paragraph (b) of this section, used at any weight in the manufacture of the polymer. For purposes of determining chemical identity, the manufacturer may determine whether a reactant is used at greater than two weight percent according to either the weight of the reactant charged to the reaction vessel or the

weight of the chemically combined (incorporated) reactant in the polymer. Manufacturers who choose the "incorporated" method must have analytical data, or theoretical calculations (if it can be documented that an analytical determination cannot be made or is not necessary), to demonstrate compliance with this paragraph. Reactants that introduce into the polymer elements, properties, or functional groups that would render the polymer ineligible for the exemption are not allowed at any level.

(2) A representative structural diagram, if possible.

(h) *Certification.* To manufacture a substance under the terms of this section, a manufacturer must as of the date of first manufacture, make the following certification statements and maintain them in accordance with paragraph (j) of this section:

(1) The substance is manufactured or imported for a commercial purpose other than for research and development.

(2) All information in the certification is truthful.

(3) The new chemical substance meets the definition of a polymer, is not specifically excluded from the exemption in paragraph (d) of this section, and meets the conditions of the exemption in paragraph (e) of this section.

(i) *Exemptions granted under superseded regulations.* Manufacturers granted exemptions under the superseded requirements of § 723.250 (as in effect on May 26, 1995) shall either continue to comply with those requirements or follow all procedural and recordkeeping requirements pursuant to this section. If an exemption holder continues to follow the superseded regulations, the Notice of Commencement requirements apply and the exempt polymer will continue to be listed on the Inventory with exclusion criteria and exemption category restrictions on residual monomer/reactant and low molecular weight species content limitations.

(j) *Recordkeeping.* (1) A manufacturer of a new polymer under paragraphs (e) of this section, must retain the records described in this paragraph at the manufacturing site for a period of 5 years

from the date of commencement of manufacture or import.

(2) The records must include the following to demonstrate compliance with the terms of this section:

(i) Chemical identity information as required in paragraph (g) of this section.

(ii) Information to demonstrate that the new polymer is not specifically excluded from the exemption.

(iii) Records of production volume for the first 3 years of manufacture and the date of commencement of manufacture.

(iv) Information to demonstrate that the new polymer meets the exemption criteria in paragraphs (e)(1), (e)(2), or (e)(3) of this section.

(v) Analytical data, or theoretical calculations (if it can be documented that an analytical determination cannot be made or is not necessary), to demonstrate that the polymer meets the number-average MW exemption criteria in paragraphs (e)(1) or (e)(2) of this section. The analytical tests may include gel permeation chromatography (GPC), vapor pressure osmometry (VPO), or other such tests which will demonstrate that the polymer meets the number-average MW criterion.

(vi) Analytical data, or theoretical calculations (if it can be documented that an analytical determination cannot be made or is not necessary), to demonstrate that the polymer meets the criteria in paragraphs (e)(1) or (e)(2) of this section, meets the low MW content criteria in paragraphs (e)(1) or (e)(2) of this section.

(vii) If applicable, analytical data, or theoretical calculations (if it can be documented that an analytical determination cannot be made or is not necessary) required in paragraph (g) of this section for determining monomers or reactants charged to the reaction vessel at greater than 2 weight percent but incorporated at 2 weight percent or less in the manufactured polymer.

(viii) The certification statements as required under paragraph (h) of this section.

(3) The manufacturer must submit the records listed in paragraph (j)(2) of this section to EPA upon written request by EPA. The manufacturer must

provide these records within 15 working days of receipt of this request. In addition, any person who manufactures a new chemical substance under the terms of this section, upon request of EPA, must permit such person at all reasonable times to have access to and to copy these records.

(k) *Submission of information.* Information submitted to EPA under this section must be sent in writing to: TSCA Document Control Officer, (7407), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460.

(1) *Compliance.* (1) A person who manufactures or imports a new chemical substance and fails to comply with any provision of this section is in violation of section 15 of the Act (15 U.S.C. 2614).

(2) Using for commercial purposes a chemical substance or mixture which a person knew or had reason to know was manufactured, processed, or distributed in commerce in violation of section 5 of the Act is a violation of section 15 of the Act (15 U.S.C. 2614).

(3) Failure or refusal to establish and maintain records or to permit access to or copying of records, as required by this section and section 11 of the Act, is a violation of section 15 of the Act (15 U.S.C. 2614).

(4) Failure or refusal to permit entry or inspection as required by section 11 of the Act is a violation of section 15 of the Act (15 U.S.C. 2614).

(5) Violators may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation. Persons who submit materially misleading or false information in connection with the requirements of any provision of this section may be subject to penalties calculated as if they never filed their notices.

(6) EPA may seek to enjoin the manufacture or processing of a chemical substance in violation of this section or act to seize any chemical substance manufactured or processed in violation of this section or take other actions under the authority of section 7 of the Act (15 U.S.C. 2606) or section 17 of the Act (15 U.S.C. 2616).

(m) *Inspections.* EPA will conduct inspections under section 11 of the Act to assure compliance with section 5 and

this section, to verify that information submitted to EPA under this section is true and correct, and to audit data submitted to EPA under this section.

(n) *Confidentiality.* If a manufacturer submits information to EPA under this section which the manufacturer claims to be confidential business information, the manufacturer must clearly identify the information at the time of submission to EPA by bracketing, circling, or underlining it and stamping it with "CONFIDENTIAL" or some other appropriate designation. Any information so identified will be treated in accordance with the procedures in 40 CFR part 2. Any information not claimed confidential at the time of submission may be made available to the public without further notice.

[60 FR 16332, Mar. 29, 1995, as amended at 62 FR 17932, April 11, 1997; 75 FR 4305, Jan. 27, 2010]

## PART 725—REPORTING REQUIREMENTS AND REVIEW PROCESSES FOR MICROORGANISMS

### Subpart A—General Provisions and Applicability

| Sec.   |  |
|--------|--|
| 725.1  | Scope and purpose.   |
| 725.3  | Definitions.   |
| 725.8  | Coverage of this part.   |
| 725.12 | Identification of microorganisms for inventory and other listing purposes.                 |
| 725.15 | Determining applicability when microorganism identity or use is confidential or uncertain. |
| 725.17 | Consultation with EPA.   |

### Subpart B—Administrative Procedures

|        |   |
|--------|---|
| 725.20 | Scope and purpose.  |
| 725.25 | General administrative requirements.                      |
| 725.27 | Submissions.  |
| 725.28 | Notice that submission is not required.                   |
| 725.29 | EPA acknowledgement of receipt of submission.             |
| 725.32 | Errors in the submission.                                 |
| 725.33 | Incomplete submissions.                                   |
| 725.36 | New information.  |
| 725.40 | Notice in the FEDERAL REGISTER.                           |
| 725.50 | EPA review.   |
| 725.54 | Suspension of the review period.                          |
| 725.56 | Extension of the review period.                           |
| 725.60 | Withdrawal of submission by the submitter.                |
| 725.65 | Recordkeeping.  |
| 725.67 | Applications to exempt new microorganisms from this part. |

## § 725.1

- 725.70 Compliance.
- 725.75 Inspections.

### Subpart C—Confidentiality and Public Access to Information

- 725.80 General provisions for confidentiality claims.
- 725.85 Microorganism identity.
- 725.88 Uses of a microorganism.
- 725.92 Data from health and safety studies of microorganisms.
- 725.94 Substantiation requirements.
- 725.95 Public file.

### Subpart D—Microbial Commercial Activities Notification Requirements

- 725.100 Scope and purpose.
- 725.105 Persons who must report.
- 725.110 Persons not subject to this subpart.
- 725.150 Procedural requirements for this subpart.
- 725.155 Information to be included in the MCAN.
- 725.160 Submission of health and environmental effects data.
- 725.170 EPA review of the MCAN.
- 725.190 Notice of commencement of manufacture or import.

### Subpart E—Exemptions for Research and Development Activities

- 725.200 Scope and purpose.
- 725.205 Persons who may report under this subpart.
- 725.232 Activities subject to the jurisdiction of other Federal programs or agencies.
- 725.234 Activities conducted inside a structure.
- 725.235 Conditions of exemption for activities conducted inside a structure.
- 725.238 Activities conducted outside a structure.
- 725.239 Use of specific microorganisms in activities conducted outside a structure.
- 725.250 Procedural requirements for the TERA.
- 725.255 Information to be included in the TERA.
- 725.260 Submission of health and environmental effects data.
- 725.270 EPA review of the TERA.
- 725.288 Revocation or modification of TERA approval.

### Subpart F—Exemptions for Test Marketing

- 725.300 Scope and purpose.
- 725.305 Persons who may apply under this subpart.
- 725.350 Procedural requirements for this subpart.
- 725.355 Information to be included in the TME application.
- 725.370 EPA review of the TME application.

## 40 CFR Ch. I (7–1–10 Edition)

### Subpart G—General Exemptions for New Microorganisms

- 725.400 Scope and purpose.
- 725.420 Recipient microorganisms.
- 725.421 Introduced genetic material.
- 725.422 Physical containment and control technologies.
- 725.424 Requirements for the Tier I exemption.
- 725.426 Applicability of the Tier I exemption.
- 725.428 Requirements for the Tier II exemption.
- 725.450 Procedural requirements for the Tier II exemption.
- 725.455 Information to be included in the Tier II exemption request.
- 725.470 EPA review of the Tier II exemption request.

### Subparts H–K [Reserved]

### Subpart L—Additional Procedures for Reporting on Significant New Uses of Microorganisms

- 725.900 Scope and purpose.
- 725.910 Persons excluded from reporting significant new uses.
- 725.912 Exemptions.
- 725.920 Exports and imports.
- 725.950 Additional recordkeeping requirements.
- 725.975 EPA approval of alternative control measures.
- 725.980 Expedited procedures for issuing significant new use rules for microorganisms subject to section 5(e) orders.
- 725.984 Modification or revocation of certain notification requirements.

### Subpart M—Significant New Uses for Specific Microorganisms

- 725.1000 Scope.
  - 725.1075 Burkholderia cepacia complex.
- AUTHORITY: 15 U.S.C. 2604, 2607, 2613, and 2625.

SOURCE: 62 FR 17932, April 11, 1997, unless otherwise noted.

### Subpart A—General Provisions and Applicability

#### § 725.1 Scope and purpose.

(a) This part establishes all reporting requirements under section 5 of TSCA for manufacturers, importers, and processors of microorganisms subject to TSCA jurisdiction for commercial purposes, including research and development for commercial purposes. New

microorganisms for which manufacturers and importers are required to report under section 5(a)(1)(A) of TSCA are those that are intergeneric. In addition, under section 5(a)(1)(B) of TSCA, manufacturers, importers, and processors may be required to report for any microorganism that EPA determines by rule is being manufactured, imported, or processed for a significant new use.

(b) Any manufacturer, importer, or processor required to report under section 5 of TSCA (see § 725.100 for new microorganisms and § 725.900 for significant new uses) must file a Microbial Commercial Activity Notice (MCAN) with EPA, unless the activity is eligible for a specific exemption as described in this part. The general procedures for filing MCANs are described in subpart D of this part. The exemptions from the requirement to file a MCAN are for certain kinds of contained activities (see §§ 725.424 and 725.428), test marketing activities (see § 725.300), and research and development activities described in paragraph (c) of this section.

(c) Any manufacturer, importer, or processor required to file a MCAN for research and development (R&D) activities may instead file a TSCA Experimental Release Application (TERA) for a specific test (see § 725.250). A TERA is not required for certain R&D activities; however a TERA exemption does not extend beyond the research and development stage, to general commercial use of the microorganism, for which compliance with MCAN requirements is required. The TERA exemptions are for R&D activities subject to other Federal agencies or programs (see § 725.232), certain kinds of contained R&D activities (see § 725.234), and R&D activities using certain listed microorganisms (see § 725.238).

(d) New microorganisms will be added to the Inventory established under section 8 of TSCA once a MCAN has been received, the MCAN review period has expired, and EPA receives a Notice of Commencement (NOC) indicating that manufacture or importation has actually begun. New microorganisms approved for use under a TERA will not be added to the Inventory until a MCAN has been received,

the MCAN review period has expired, and EPA has received an NOC.

### § 725.3 Definitions.

Definitions in section 3 of the Act (15 U.S.C. 2602), as well as definitions contained in §§ 704.3, 720.3, and 721.3 of this chapter, apply to this part unless otherwise specified in this section. In addition, the following definitions apply to this part:

*Consolidated microbial commercial activity notice* or *consolidated MCAN* means any MCAN submitted to EPA that covers more than one microorganism (each being assigned a separate MCAN number by EPA) as a result of a prenotice agreement with EPA.

*Containment and/or inactivation controls* means any combination of engineering, mechanical, procedural, or biological controls designed and operated to restrict environmental release of viable microorganisms from a structure.

*Director* means the Director of the EPA Office of Pollution Prevention and Toxics.

*Exemption request* means any application submitted to EPA under subparts E, F, or G of this part.

*General commercial use* means use for commercial purposes other than research and development.

*Genome* means the sum total of chromosomal and extrachromosomal genetic material of an isolate and any descendants derived under pure culture conditions from that isolate.

*Health and safety study of a microorganism* or *health and safety study* means any study of any effect of a microorganism or microbial mixture on health or the environment or on both, including underlying data and epidemiological studies, studies of occupational exposure to a microorganism or microbial mixture, toxicological, clinical, and ecological, or other studies of a microorganism or microbial mixture, and any test performed under the Act. Microorganism identity is always part of a health and safety study of a microorganism.

(1) It is intended that the term "health and safety study of a microorganism" be interpreted broadly. Not only is information which arises as a



result of a formal, disciplined study included, but other information relating to the effects of a microorganism or microbial mixture on health or the environment is also included. Any data that bear on the effects of a microorganism on health or the environment would be included.

(2) Examples include:

(i) Tests for ecological or other environmental effects on invertebrates, fish, or other animals, and plants, including: Acute toxicity tests, chronic toxicity tests, critical life stage tests, behavioral tests, algal growth tests, seed germination tests, plant growth or damage tests, microbial function tests, bioconcentration or bioaccumulation tests, and model ecosystem (microcosm) studies.

(ii) Long- and short-term tests of mutagenicity, carcinogenicity, or teratogenicity; dermatotoxicity; cumulative, additive, and synergistic effects; and acute, subchronic, and chronic effects.

(iii) Assessments of human and environmental exposure, including workplace exposure, and impacts of a particular microorganism or microbial mixture on the environment, including surveys, tests, and studies of: Survival and transport in air, water, and soil; ability to exchange genetic material with other microorganisms, ability to colonize human or animal guts, and ability to colonize plants.

(iv) Monitoring data, when they have been aggregated and analyzed to measure the exposure of humans or the environment to a microorganism.

(v) Any assessments of risk to health and the environment resulting from the manufacture, processing, distribution in commerce, use, or disposal of the microorganism.

*Inactivation* means that living microorganisms are rendered nonviable.

*Institutional Biosafety Committee* means the committees described in the NIH Guidelines in section IV.B.2.

*Intergeneric microorganism* means a microorganism that is formed by the deliberate combination of genetic material originally isolated from organisms of different taxonomic genera.

(1) The term “intergeneric microorganism” includes a microorganism which contains a mobile genetic ele-

ment which was first identified in a microorganism in a genus different from the recipient microorganism.

(2) The term “intergeneric microorganism” does not include a microorganism which contains introduced genetic material consisting of only well-characterized, non-coding regulatory regions from another genus.

*Introduced genetic material* means genetic material that is added to, and remains as a component of, the genome of the recipient.

*Manufacture, import, or process for commercial purposes* means:

(1) To import, produce, manufacture, or process with the purpose of obtaining an immediate or eventual commercial advantage for the manufacturer, importer, or processor, and includes, among other things, “manufacture” or “processing” of any amount of a microorganism or microbial mixture:

(i) For commercial distribution, including for test marketing.

(ii) For use by the manufacturer, including use for product research and development or as an intermediate.

(2) The term also applies to substances that are produced coincidentally during the manufacture, processing, use, or disposal of another microorganism or microbial mixture, including byproducts that are separated from that other microorganism or microbial mixture and impurities that remain in that microorganism or microbial mixture. Byproducts and impurities without separate commercial value are nonetheless produced for the purpose of obtaining a commercial advantage, since they are part of the manufacture or processing of a microorganism for commercial purposes.

*Microbial commercial activity notice* or *MCAN* means a notice for microorganisms submitted to EPA pursuant to section 5(a)(1) of the Act in accordance with subpart D of this part.

*Microbial mixture* means any combination of microorganisms or microorganisms and other chemical substances, if the combination does not occur in nature and is not an article.

*Microorganism* means an organism classified, using the 5-kingdom classification system of Whittacker, in the kingdoms Monera (or Procaryotae), Protista, Fungi, and the Chlorophyta

## Environmental Protection Agency

## § 725.8

and the Rhodophyta of the Plantae, and a virus or virus-like particle.

*Mobile genetic element* or *MGE* means an element of genetic material that has the ability to move genetic material within and between organisms. "Mobile genetic elements" include all plasmids, viruses, transposons, insertion sequences, and other classes of elements with these general properties.

*New microorganism* means a microorganism not included on the Inventory.

*NIH Guidelines* means the National Institutes of Health (NIH) "Guidelines for Research Involving Recombinant DNA Molecules" (July 5, 1994).

*Non-coding regulatory region* means a segment of introduced genetic material for which:

(1) The regulatory region and any inserted flanking nucleotides do not code for protein, peptide, or functional ribonucleic acid molecules.

(2) The regulatory region solely controls the activity of other regions that code for protein or peptide molecules or act as recognition sites for the initiation of nucleic acid or protein synthesis.

*Small quantities solely for research and development* (or "small quantities solely for purposes of scientific experimentation or analysis or research on, or analysis of, such substance or another substance, including such research or analysis for development of a product") means quantities of a microorganism manufactured, imported, or processed or proposed to be manufactured, imported, or processed solely for research and development that meet the requirements of § 725.234.

*Structure* means a building or vessel which effectively surrounds and encloses the microorganism and includes features designed to restrict the microorganism from leaving.

*Submission* means any MCAN or exemption request submitted to EPA under this part.

*Technically qualified individual* means a person or persons:

(1) Who, because of education, training, or experience, or a combination of these factors, is capable of understanding the health and environmental risks associated with the microorganism

which is used under his or her supervision,

(2) Who is responsible for enforcing appropriate methods of conducting scientific experimentation, analysis, or microbiological research to minimize such risks, and

(3) Who is responsible for the safety assessments and clearances related to the procurement, storage, use, and disposal of the microorganism as may be appropriate or required within the scope of conducting a research and development activity.

*TSCA Experimental Release Application* or *TERA* means an exemption request for a research and development activity, which is not eligible for a full exemption from reporting under § 725.232, 725.234, or 725.238, submitted to EPA in accordance with subpart E of this part.

*Well-characterized* for introduced genetic material means that the following have been determined:

(1) The function of all of the products expressed from the structural gene(s).

(2) The function of sequences that participate in the regulation of expression of the structural gene(s).

(3) The presence or absence of associated nucleotide sequences and their associated functions, where associated nucleotide sequences are those sequences needed to move genetic material including linkers, homopolymers, adaptors, transposons, insertion sequences, and restriction enzyme sites.

### § 725.8 Coverage of this part.

(a) *Microorganisms subject to this part.* Only microorganisms which are manufactured, imported, or processed for commercial purposes, as defined in § 725.3, are subject to the requirements of this part.

(b) *Microorganisms automatically included on the Inventory.* Microorganisms that are not intergeneric are automatically included on the Inventory.

(c) *Microorganisms not subject to this part.* The following microorganisms are not subject to this part, either because they are not subject to jurisdiction under the Act or are not subject to reporting under section 5 of the Act.

(1) Any microorganism which would be excluded from the definition of

## § 725.12

“chemical substance” in section 3 of the Act and § 720.3(e) of this chapter.

(2) Any microbial mixture as defined in § 725.3. This exclusion applies only to a microbial mixture as a whole and not to any microorganisms and other chemical substances which are part of the microbial mixture.

(3) Any microorganism that is manufactured and processed solely for export if the following conditions are met:

(i) The microorganism is labeled in accordance with section 12(a)(1)(B) of the Act, when the microorganism is distributed in commerce.

(ii) The manufacturer and processor can document at the commencement of manufacturing or processing that the person to whom the microorganism will be distributed intends to export it or process it solely for export as defined in § 721.3 of this chapter.

## § 725.12 Identification of microorganisms for Inventory and other listing purposes.

To identify and list microorganisms on the Inventory, both taxonomic designations and supplemental information will be used. The supplemental information required in paragraph (b) of this section will be used to specifically describe an individual microorganism on the Inventory. Submitters must provide the supplemental information required by paragraph (b) of this section to the extent necessary to enable a microorganism to be accurately and unambiguously identified on the Inventory.

(a) *Taxonomic designation.* The taxonomic designation of a microorganism must be provided for the donor organism and the recipient microorganism to the level of strain, as appropriate. These designations must be substantiated by a letter from a culture collection, literature references, or the results of tests conducted for the purpose of taxonomic classification. Upon EPA's request to the submitter, data supporting the taxonomic designation must be provided to EPA. The genetic history of the recipient microorganism should be documented back to the isolate from which it was derived.

(b) *Supplemental information.* The supplemental information described in

## 40 CFR Ch. I (7–1–10 Edition)

paragraphs (b)(1) and (b)(2) of this section is required to the extent that it enables a microorganism to be accurately and unambiguously identified.

(1) *Phenotypic information.* Phenotypic information means pertinent traits that result from the interaction of a microorganism's genotype and the environment in which it is intended to be used and may include intentionally added biochemical and physiological traits.

(2) *Genotypic information.* Genotypic information means the pertinent and distinguishing genotypic characteristics of a microorganism, such as the identity of the introduced genetic material and the methods used to construct the reported microorganism. This also may include information on the vector construct, the cellular location, and the number of copies of the introduced genetic material.

## § 725.15 Determining applicability when microorganism identity or use is confidential or uncertain.

(a) *Consulting EPA.* Persons intending to conduct activities involving microorganisms may determine their obligations under this part by consulting the Inventory or the microorganisms and uses specified in § 725.239 or in subpart M of this part. This section establishes procedures for EPA to assist persons in determining whether the microorganism or the use is listed on the Inventory, in § 725.239 or in subpart M of this part.

(1) *Confidential identity or use.* In some cases it may not be possible to directly determine if a specific microorganism is listed, because portions of that entry may contain generic information to protect confidential business information (CBI). If any portion of the microorganism's identity or use has been claimed as CBI, that portion does not appear on the public version of the Inventory, in § 725.239 or in subpart M of this part. Instead, it is contained in a confidential version held in EPA's Confidential Business Information Center (CBIC). The public versions contain generic information which masks the confidential business information. A person who intends to conduct an activity involving a microorganism or

## Environmental Protection Agency

## § 725.15

use whose entry is described with generic information will need to inquire of EPA whether the unreported microorganism or use is on the confidential version.

(2) Uncertain microorganism identity. The current state of scientific knowledge leads to some imprecision in describing a microorganism. As the state of knowledge increases, EPA will be developing policies to determine whether one microorganism is equivalent to another. Persons intending to conduct activities involving microorganisms may inquire of EPA whether the microorganisms they intend to manufacture, import, or process are equivalent to specific microorganisms described on the Inventory, in § 725.239, or in subpart M of this part.

(b) *Requirement of bona fide intent.* (1) EPA will answer the inquiries described in paragraph (a) of this section only if the Agency determines that the person has a *bona fide* intent to conduct the activity for which reporting is required or for which any exemption may apply.

(2) To establish a *bona fide* intent to manufacture, import, or process a microorganism, the person who intends to manufacture, import, or process the microorganism must submit the following information in writing to the Office of Pollution Prevention and Toxics, Document Control Officer, 7407, 1200 Pennsylvania Ave., NW., Washington, DC 20460, ATTN: BIOTECH *bona fide* submission.

(i) Taxonomic designations and supplemental information required by § 725.12.

(ii) A signed statement certifying that the submitter intends to manufacture, import, or process the microorganism for commercial purposes.

(iii) A description of research and development activities conducted with the microorganism to date, demonstration of the submitter's ability to produce or obtain the microorganism from a foreign manufacturer, and the purpose for which the person will manufacture, import, or process the microorganism.

(iv) An indication of whether a related microorganism was previously reviewed by EPA to the extent known by the submitter.

(v) A specific description of the major intended application or use of the microorganism.

(c) If an importer or processor cannot provide all the information required by paragraph (b) of this section, because it is claimed as confidential business information by its foreign manufacturer or supplier, the foreign manufacturer or supplier may supply the information directly to EPA.

(d) EPA will review the information submitted by the manufacturer, importer, or processor under this paragraph to determine whether that person has shown a *bona fide* intent to manufacture, import, or process the microorganism. If necessary, EPA will compare this information to the information requested for the confidential microorganism under § 725.85(b)(3)(iii).

(e) In order for EPA to make a conclusive determination of the microorganism's status, the proposed manufacturer, importer, or processor must show a *bona fide* intent to manufacture, import, or process the microorganism and must provide sufficient information to establish identity unambiguously. After sufficient information has been provided, EPA will inform the manufacturer, importer, or processor whether the microorganism is subject to this part and if so, which sections of this part apply.

(f) If the microorganism is found on the confidential version of the Inventory, in § 725.239 or in subpart M of this part, EPA will notify the person(s) who originally reported the microorganism that another person (whose identity will remain confidential, if so requested) has demonstrated a *bona fide* intent to manufacture, import, or process the microorganism and therefore was told that the microorganism is on the Inventory, in § 725.239, or in subpart M of this part.

(g) A disclosure to a person with a *bona fide* intent to manufacture, import, or process a particular microorganism that the microorganism is on the Inventory, in § 725.239, or in subpart M of this part will not be considered a public disclosure of confidential business information under section 14 of the Act.

(h) EPA will answer an inquiry on whether a particular microorganism is

## § 725.17

subject to this part within 30 days after receipt of a complete submission under paragraph (b) of this section.

### § 725.17 Consultation with EPA.

Persons may consult with EPA, either in writing or by telephone, about their obligations under this part. Written consultation is preferred. Written inquiries should be sent to the following address: Environmental Assistance Division (7408), Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460, ATTN: Biotechnology Notice Consultation. Persons wishing to consult with EPA by telephone should call (202) 554-1404; hearing impaired TDD (202) 554-0551 or e-mail: *TSCA-Hotline@epamail.epa.gov*.

## Subpart B—Administrative Procedures

### § 725.20 Scope and purpose.

This subpart describes general administrative procedures applicable to all persons who submit MCANs and exemption requests to EPA under section 5 of the Act for microorganisms.

### § 725.25 General administrative requirements.

(a) *General.* (1) Each person who is subject to the notification provisions of this part must complete, sign, and submit a MCAN or exemption request containing the information as required for the appropriate submission under this part. Except as otherwise provided, each submission must include all referenced attachments. All information in the submission (unless certain attachments appear in the open scientific literature) must be in English. All information submitted must be true and correct.

(2) In addition to specific information required, the submitter should submit all information known to or reasonably ascertainable by the submitter that would permit EPA to make a reasoned evaluation of the human health and environmental effects of the microorganism and any microbial mixture or article that may contain the microorganism.

## 40 CFR Ch. I (7–1–10 Edition)

(b) *Certification.* Persons submitting MCANs and exemption requests to EPA under this part, and material related to their reporting obligations under this part, must attach the following statement to any information submitted to EPA. This statement must be signed and dated by an authorized official of the submitter:

I certify that to the best of my knowledge and belief: The company named in this submission intends to manufacture, import, or process for a commercial purpose, other than in small quantities solely for research and development, the microorganism identified in this submission. All information provided in this submission is complete and truthful as of the date of submission. I am including with this submission all test data in my possession or control and a description of all other data known to or reasonably ascertainable by me as required by 40 CFR 725.160 or 725.260.

(c) *Where to submit information under this part.* MCANs and exemption requests, and any support documents related to these submissions, may only be submitted in a manner set forth in this paragraph.

(1) *Paper-based submissions.* MCANs and exemption requests, and any support documents related to these submissions, may be submitted on paper on or before April 6, 2011. All paper-based submissions must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print the biotechnology notice submission to be sent to EPA. Paper notices must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(2) *Submissions on optical disc—*(i) MCANs and exemption requests may be submitted as electronic files on optical disc on or before April 6, 2012. MCANs and exemption requests submitted as electronic files on optical disc must be

## Environmental Protection Agency

## § 725.25

generated using e-PMN reporting software and be completed through the finalization step of the software. Optical discs containing electronic notices must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(ii) Persons submitting on optical disc must still prepare, sign, and submit on paper, the Certification statement in 40 CFR 725.25(b) along with submitter identification and contact information.

(iii) Support documents for MCANs or exemption requests that are submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(3) *Submissions via CDX.* MCANs and exemption requests, and any related support documents, may be submitted electronically to EPA via CDX. Prior to submission to EPA via CDX, notices must be generated and completed on EPA Form 6300-07 using e-PMN reporting software.

(d) *General requirements for submission of data.* (1) Submissions under this part must include the information described in § 725.155, 725.255, 725.355, or 725.455, as appropriate, to the extent such information is known to or reasonably ascertainable by the submitter.

(2) In accordance with § 725.160 or 725.260, as appropriate, the submission must also include any test data in the submitter's possession or control and descriptions of other data which are known to or reasonably ascertainable by the submitter and which concern the health and environmental effects of the microorganism.

(e) *Agency or joint submissions.* (1) A manufacturer or importer may designate an agent to assist in submitting the MCAN. If so, only the manufacturer or importer, and not the agent, signs the certification on the form.

(2) A manufacturer or importer may authorize another person, (e.g., a supplier or a toll manufacturer) to report some of the information required in the MCAN to EPA on its behalf. The manufacturer or importer should indicate in a cover letter accompanying the MCAN which information will be supplied by another person and identify that other person as a joint submitter where indicated in their MCAN. The other person supplying information (i.e., the joint submitter) may submit the information to EPA either in the MCAN or a Letter of Support, except that if the joint submitter is not incorporated, licensed, or doing business in the United States, the joint submitter must submit the information to EPA in a Letter of Support only, rather than the MCAN. The joint submitter must indicate in the MCAN or Letter of Support the identity of the manufacturer or importer. Any person who submits the MCAN or Letter of Support for a joint submission must sign and certify the MCAN or Letter of Support.

(3) If EPA receives a submission which does not include the information required, which the submitter indicates that it has authorized another person to provide, the review period will not begin until EPA receives all of the required information.

(f) *Microorganisms subject to a section 4 test rule.* (1) Except as provided in paragraph (f)(3) of this section, if a person intends to manufacture or import a new microorganism which is subject to the notification requirements of this part, and the microorganism is subject to a test rule promulgated under section 4 of the Act before the notice is submitted, section 5(b)(1) of the Act requires the person to submit the test data required by the testing rule with the notice. The person must submit the data in the form and manner specified in the test rule and in accordance with § 725.160. If the person does not submit the test data, the submission is incomplete and EPA will follow the procedures in § 725.33.

(2) If EPA has granted the submitter an exemption under section 4(c) of the Act from the requirement to conduct tests and submit data, the person may not file a MCAN or TERA until EPA receives the test data.

**§ 725.27**

**40 CFR Ch. I (7-1-10 Edition)**

(3) If EPA has granted the submitter an exemption under section 4(c) of the Act and if another person previously has submitted the test data to EPA, the exempted person may either submit the test data or provide the following information as part of the notice:

(i) The name, title, and address of the person who submitted the test data to EPA.

(ii) The date the test data were submitted to EPA.

(iii) A citation for the test rule.

(iv) A description of the exemption and a reference identifying it.

(g) *Microorganisms subject to a section 5(b)(4) rule.* (1) If a person:

(i) Intends to manufacture or import a microorganism which is subject to the notification requirements of this part and which is subject to a rule issued under section 5(b)(4) of the Act; and

(ii) Is not required by a rule issued under section 4 of the Act to submit test data for the microorganism before the filing of a submission, the person must submit to EPA data described in paragraph (g)(2) of this section at the time the submission is filed.

(2) Data submitted under paragraph (g)(1) of this section must be data which the person submitting the notice believes show that the manufacture, processing, distribution in commerce, use, and disposal of the microorganism, or any combination of such activities, will not present an unreasonable risk of injury to health or the environment.

(h) *Data that need not be submitted.* Specific data requirements are listed in subparts D, E, F, G, and L of this part. The following is a list of data that need not be submitted under this part:

(1) Data previously submitted to EPA. (i) A person need not submit any data previously submitted to EPA with no claims of confidentiality if the new submission includes: the office or person to whom the data were submitted; the date of submission; and, if appropriate, a standard literature citation as specified in § 725.160(a)(3)(ii).

(ii) For data previously submitted to EPA with a claim of confidentiality, the person must resubmit the data with the new submission and any claim of confidentiality, under § 725.80.

(2) Efficacy data. This part does not require submission of any data related solely to product efficacy. However, including efficacy data will improve EPA's ability to assess the benefits of the use of the microorganism. This does not exempt a person from submitting any of the data specified in § 725.160 or 725.260.

(3) Non-U.S. exposure data. This part does not require submission of any data which relates only to exposure of humans or the environment outside the United States. This does not exclude nonexposure data such as data on health effects (including epidemiological studies), ecological effects, physical and chemical properties, or environmental fate characteristics.

[62 FR 17932, April 11, 1997, as amended at 75 FR 788, Jan. 6, 2010]

**§ 725.27 Submissions.**

Each person who is required to submit information under this part must submit the information in the form and manner set forth in the appropriate subpart.

(a) Requirements specific to MCANs are described in §§ 725.150 through 725.160.

(b) Requirements specific to TERAs are described in §§ 725.250 through 725.260.

(c) Requirements specific to test marketing exemptions (TMEs) are described in §§ 725.350 and 725.355.

(d) Requirements specific to Tier I and Tier II exemptions for certain general commercial uses are described in §§ 725.424 through 725.470.

(e) Additional requirements specific to significant new uses for microorganisms are described at § 725.950.

**§ 725.28 Notice that submission is not required.**

When EPA receives a MCAN or exemption request, EPA will review it to determine whether the microorganism is subject to the requirements of this part. If EPA determines that the microorganism is not subject to these requirements, EPA will notify the submitter that section 5 of the Act does not prevent the manufacture, import, or processing of the microorganism and that the submission is not needed.

## Environmental Protection Agency

## § 725.33

### § 725.29 EPA acknowledgement of receipt of submission.

(a) EPA will acknowledge receipt of each submission by sending a letter via CDX or U.S. mail to the submitter that identifies the number assigned to each MCAN or exemption request and the date on which the review period begins. The review period will begin on the date the MCAN or exemption request is received by the Office of Pollution Prevention and Toxics Document Control Officer.

(b) The acknowledgement does not constitute a finding by EPA that the submission is in compliance with this part.

[62 FR 17932, April 11, 1997, as amended at 75 FR 788, Jan. 6, 2010]

### § 725.32 Errors in the submission.

(a) Within 30 days of receipt of the submission, EPA may request that the submitter remedy errors in the submission. The following are examples of such errors:

(1) Failure to date the submission.

(2) Typographical errors that cause data to be misleading or answers to any questions to be unclear.

(3) Contradictory information.

(4) Ambiguous statements or information.

(b) In the request to correct the submission, EPA will explain the action which the submitter must take to correct the submission.

(c) If the submitter fails to correct the submission within 15 days of receipt of the request, EPA may extend the review period.

### § 725.33 Incomplete submissions.

(a) A submission under this part is not complete, and the review period does not begin, if:

(1) The wrong person files the submission.

(2) The submitter does not attach and sign the certification statement as required by § 725.25(b).

(3) Some or all of the information in the submission or any attachments are not in English, except for published scientific literature.

(4) The submitter does not provide information that is required by sections

5(d)(1)(B) and (C) of the Act and § 725.160 or 725.260, as appropriate.

(5) The submitter does not provide information required by § 725.25, 725.155, 725.255, 725.355, or 725.455, as appropriate, or indicate that it is not known to or reasonably ascertainable by the submitter.

(6) The submitter has asserted confidentiality claims and has failed to:

(i) Submit a second copy of the submission with all confidential information deleted for the public file, as required by § 725.80(b)(2).

(ii) Comply with the substantiation requirements as described in § 725.94.

(7) The submitter does not include any information required by section 5(b)(1) of the Act and pursuant to a rule promulgated under section 4 of the Act, as required by § 725.25(f).

(8) The submitter does not submit data which the submitter believes show that the microorganism will not present an unreasonable risk of injury to health or the environment, if EPA has listed the microorganism under section 5(b)(4) of the Act, as required in § 725.25(g).

(9) For MCANs, the submitter does not remit the fees required by § 700.45(b)(1) or (b)(2)(vi) of this chapter.

(10) The submitter does not include an identifying number and a payment identity number as required by § 700.45(e)(3) of this chapter.

(11) The submitter does not submit the notice in the manner set forth in § 725.25(c).

(b)(1) If EPA receives an incomplete submission under this part, the Director, or a designee, will notify the submitter within 30 days of receipt that the submission is incomplete and that the review period will not begin until EPA receives a complete submission.

(2) If EPA obtains additional information during the review period for any submission that indicates the original submission was incomplete, the Director, or a designee, may declare the submission incomplete within 30 days after EPA obtains the additional information and so notify the submitter.

(c) The notification that a submission is incomplete under paragraph (b) of this section will include:



**§ 725.36**

**40 CFR Ch. I (7-1-10 Edition)**

(1) A statement of the basis of EPA's determination that the submission is incomplete.

(2) The requirements for correcting the incomplete submission.

(3) Information on procedures under paragraph (d) of this section for filing objections to the determination or requesting modification of the requirements for completing the submission.

(d) Within 10 days after receipt of notification by EPA that a submission is incomplete, the submitter may file written objections requesting that EPA accept the submission as complete or modify the requirements necessary to complete the submission.

(e)(1) EPA will consider the objections filed by the submitter. The Director, or a designee, will determine whether the submission was complete or incomplete, or whether to modify the requirements for completing the submission. EPA will notify the submitter in writing of EPA's response within 10 days of receiving the objections.

(2) If the Director, or a designee, determines, in response to the objection, that the submission was complete, the review period will be deemed suspended on the date EPA declared the submission incomplete, and will resume on the date that the submission is declared complete. The submitter need not correct the submission as EPA originally requested. If EPA can complete its review within the review period beginning on the date of the submission, the Director, or a designee, may inform the submitter that the running of the review period will resume on the date EPA originally declared it incomplete.

(3) If the Director, or a designee, modifies the requirements for completing the submission or concurs with EPA's original determination, the review period will begin when EPA receives a complete submission.

(f) If EPA discovers at any time that a person submitted materially false or misleading statements in information submitted under this part, EPA may find that the submission was incomplete from the date it was submitted, and take any other appropriate action.

[62 FR 17932, April 11, 1997, as amended at 75 FR 788, Jan. 6, 2010]

**§ 725.36 New information.**

(a) During the review period, if a submitter possesses, controls, or knows of new information that materially adds to, changes, or otherwise makes significantly more complete the information included in the MCAN or exemption request, the submitter must send that information within 10 days of receiving the new information, but no later than 5 days before the end of the review period. The new information must be sent in the same manner the original notice or exemption was sent, as described in § 725.25(c)(1), (c)(2), and (c)(3).

(b) The new submission must clearly identify the submitter, the MCAN or exemption request to which the new information is related, and the number assigned to that submission by EPA, if known to the submitter.

(c) If the new information becomes available during the last 5 days of the review period, the submitter must immediately inform the EPA contact for that submission by telephone of the new information.

[62 FR 17932, April 11, 1997, as amended at 75 FR 789, Jan. 6, 2010]

**§ 725.40 Notice in the Federal Register.**

(a) *Filing of FEDERAL REGISTER notice.* After EPA receives a MCAN or an exemption request under this part, EPA will issue a notice in the FEDERAL REGISTER including the information specified in paragraph (b) of this section.

(b) *Contents of notice.* (1) In the public interest, the specific microorganism identity listed in the submission will be published in the FEDERAL REGISTER unless the submitter has claimed the microorganism identity confidential. If the submitter claims confidentiality, a generic name will be published in accordance with § 725.85.

(2) The categories of use of the microorganism will be published as reported in the submission unless this information is claimed confidential. If confidentiality is claimed, the generic information which is submitted under § 725.88 will be published.

(3) A list of information submitted in accordance with § 725.160(a), 725.255,

## Environmental Protection Agency

## § 725.54

725.260, 725.355, or 725.455, as appropriate, will be published.

(4) The submitter's identity will be published, unless the submitter has claimed it confidential.

(c) *Publication of exemption decisions.* Following the expiration of the appropriate review period for the exemption request, EPA will issue a notice in the FEDERAL REGISTER indicating whether the request has been approved or denied and the reasons for the decision.

### § 725.50 EPA review.

(a) *MCANs.* The review period specified in section 5(a) of the Act for MCANs runs for 90 days from the date the Document Control Officer receives a complete submission, or the date EPA determines the submission is complete under § 725.33, unless the Agency extends the review period under section 5(c) of the Act and § 725.56.

(b) *Exemption requests.* The review period starts on the date the Document Control Officer receives a complete exemption request, or the date EPA determines the request is complete under § 725.33, unless the Agency extends the review period under § 725.56. The review periods for exemption requests run as follows:

(1) *TERAs.* The review period for TERAs is 60 days.

(2) *TMEs.* The review period for TMEs is 45 days.

(3) *Tier II exemption requests.* The review period for Tier II exemption requests is 45 days.

### § 725.54 Suspension of the review period.

(a) A submitter may voluntarily suspend the running of the review period if the Director, or a designee, agrees. If the Director does not agree, the review period will continue to run, and EPA will notify the submitter. A submitter may request a suspension at any time during the review period. The suspension must be for a specified period of time.

(b) A request for suspension may only be submitted in a manner set forth in this paragraph. The request for suspension also may be made orally, including by telephone, to the submitter's EPA contact for that notice, subject to paragraph (c) of this section.

(1) *Older notices.* Requests for suspension for notices submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(2) *Newer notices.* For notices submitted on or after April 6, 2010, EPA will accept requests for suspension only if submitted in accordance with this paragraph:

(i) Requests for suspension may be submitted on paper on or before April 6, 2011. All paper-based requests for suspension must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print the request for suspension for submission to EPA. Paper requests for suspension must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(ii) Requests for suspension may be submitted as electronic files on optical disc on or before April 6, 2012. All requests for suspension submitted as electronic files on optical disc generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print the request for suspension for submission to EPA. Paper requests for suspension must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted

## § 725.56

via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(iii) Requests for suspension may be submitted electronically to EPA via CDX. Such requests must be generated and completed using e-PMN reporting software. See 40 CFR 720.40(a)(2)(iv) for information on how to obtain e-PMN software.

(c) An oral request for suspension may be granted by EPA for a maximum of 15 days only. Requests for longer suspension must only be submitted in the manner set forth in this paragraph.

(d) If the submitter has not made a previous oral request, the running of the notice review period is suspended as of the date of receipt of the written paper request, electronic request on optical disc, or CDX submission by EPA.

[62 FR 17932, April 11, 1997, as amended at 75 FR 789, Jan. 6, 2010]

## § 725.56 Extension of the review period.

(a) At any time during the review period, EPA may unilaterally determine that good cause exists to extend the review period specified for MCANs, or the exemption requests.

(b) If EPA makes such a determination, EPA:

(1) Will notify the submitter that EPA is extending the review period for a specified length of time and state the reasons for the extension.

(2) For MCANs, EPA may issue a notice for publication in the FEDERAL REGISTER which states that EPA is extending the review period and gives the reasons for the extension.

(c) The total period of the extension may be for a period of up to the same length of time as specified for each type of submission in § 725.50. If the initial extension is for less than the total time allowed, EPA may make additional extensions. However, the sum of the extensions may not exceed the total allowed.

(d) The following are examples of situations in which EPA may find that good cause exists for extending the review period:

(1) EPA has reviewed the submission and is seeking additional information.

## 40 CFR Ch. I (7–1–10 Edition)

(2) EPA has received significant additional information during the review period.

(3) The submitter has failed to correct a submission after receiving EPA's request under § 725.32.

(4) EPA has reviewed the submission and determined that there is a significant possibility that the microorganism will be regulated under section 5(e) or section 5(f) of the Act, but EPA is unable to initiate regulatory action within the initial review period.

## § 725.60 Withdrawal of submission by the submitter.

(a) A submitter may withdraw a notice during the notice review period by submitting a statement of withdrawal in a manner set forth in this paragraph. The withdrawal is effective upon receipt of the written paper request, electronic request on optical disc, or CDX submission by EPA.

(1) *Older notices.* Statements of withdrawal for notices submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(2) *Newer notices.* For notices submitted on or after April 6, 2010, EPA will accept statements of withdrawal only if submitted in accordance with this paragraph:

(i) Statements of withdrawal may be submitted on paper on or before April 6, 2011. All paper-based statements of withdrawal must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print the statement of withdrawal for submission to EPA. Paper statements of withdrawal must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted

## Environmental Protection Agency

## § 725.67

via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(ii) Statements of withdrawal be submitted as electronic files on optical disc on or before April 6, 2012. All statements of withdrawal submitted as electronic files on optical disc must be generated using e-PMN reporting software and be completed through the finalization step of the software. Optical discs containing electronic statements of withdrawal must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(iii) Statements of withdrawal may be submitted electronically to EPA via CDX. Prior to submission to EPA via CDX, such statements of withdrawal must be generated and completed using e-PMN reporting software. See 40 CFR 720.40(a)(2)(iv) for information on how to obtain e-PMN software.

(b) If a manufacturer, importer, or processor who withdrew a submission later resubmits a submission for the same microorganism, a new review period begins.

[62 FR 17932, April 11, 1997, as amended at 75 FR 789, Jan. 6, 2010]

### § 725.65 Recordkeeping.

(a) *General provisions.* (1) Any person who submits a notice under this part must retain documentation of information in the submission, including:

(i) Any data in the submitter's possession or control; and

(ii) Records of production volume for the first 3 years of manufacture, import, or processing.

(2) Any person who submits a notice under this part must retain documentation of the date of commencement of testing, manufacture, import, or processing.

(3) Any person who is exempt from some or all of the reporting requirements of this part must retain documentation that supports the exemption.

(4) All information required by this section must be retained for 3 years from the date of commencement of

each activity for which records are required under this part.

(b) *Specific requirements.* In addition to the requirements of paragraph (a) of this section, specific recordkeeping requirements included in certain subparts must also be followed.

(1) Additional recordkeeping requirements for activities conducted inside a structure are set forth in § 725.235(h).

(2) Additional recordkeeping requirements for TERAs are set forth in § 725.250(f).

(3) Additional recordkeeping requirements for TMEs are set forth in § 725.350(c).

(4) Additional recordkeeping requirements for Tier I exemptions under subpart G of this part are set forth in § 725.424(a)(5).

(5) Additional recordkeeping requirements for Tier II exemptions under subpart G of this part are set forth in § 725.450(d).

(6) Additional recordkeeping requirements for significant new uses of microorganisms reported under subpart L of this part are set forth in § 725.850. Recordkeeping requirements may also be included when a microorganism and significant new use are added to subpart M of this part.

### § 725.67 Applications to exempt new microorganisms from this part.

(a) *Submission.* (1) Any manufacturer or importer of a new microorganism may request, under TSCA section 5(h)(4), an exemption, in whole or in part, from this part by sending a Letter of Application in the manner set forth in § 725.25(c).

(2) *General provisions.* The Letter of Application should provide information to show that any activities affected by the requested exemption will not present an unreasonable risk of injury to health or the environment. This information should include data described in the following paragraphs.

(i) The effects of the new microorganism on health and the environment.

(ii) The magnitude of exposure of human beings and the environment to the new microorganism.

(iii) The benefits of the new microorganism for various uses and the availability of substitutes for such uses.

(iv) The reasonably ascertainable economic consequences of granting or denying the exemption, including effects on the national economy, small business, and technological innovation.

(3) *Specific requirements.* In addition to the requirements of paragraph (a)(2) of this section, the specific information requirements of the relevant subpart under which the exemption is sought should be met.

(i) *Exemption from MCAN reporting under subpart D.* Information requirements are set forth in §§ 725.155 and 725.160.

(ii) *Exemption from TERA reporting under subpart E.* Information requirements are set forth in §§ 725.255 and 725.260.

(iii) *Listing a recipient microorganism as eligible for exemption under subpart G.* Information regarding the following criteria should be addressed in an application to list a recipient microorganism under § 725.420:

(A) Identification and classification of the microorganism using available genotypic and phenotypic information;

(B) Information to evaluate the relationship of the microorganism to any other closely related microorganisms which have a potential for adverse effects on health or the environment;

(C) A history of safe commercial use for the microorganism;

(D) Commercial uses indicating that the microorganism products might be subject to TSCA;

(E) Studies which indicate the potential for the microorganism to cause adverse effects to health or the environment; and

(F) Studies which indicate the survival characteristics of the microorganism in the environment.

(b) *Processing of the Letter of Application by EPA—(1) Grant of the Application.* If, after consideration of the Letter of Application and any other relevant information available to EPA, the Assistant Administrator for Prevention, Pesticides and Toxic Substances makes a preliminary determination that the new microorganism will not present an unreasonable risk of injury to health or the environment, the Assistant Administrator will propose a rule to grant the exemption

using the applicable procedures in part 750 of this chapter.

(2) *Denial of the application.* If the Assistant Administrator decides that the preliminary determination described in paragraph (b)(1) of this section cannot be made, the application will be denied by sending the applicant a written statement with the Assistant Administrator's reasons for denial.

(c) *Processing of the exemption—(1) Unreasonable risk standard.* Granting a section 5(h)(4) exemption requires a determination that the activities will not present an unreasonable risk of injury to health or the environment.

(i) An unreasonable risk determination under the Act is an administrative judgment that requires balancing of the harm to health or the environment that a chemical substance may cause and the magnitude and severity of that harm, against the social and economic effects on society of EPA action to reduce that harm.

(ii) A determination of unreasonable risk under section 5(h)(4) of the Act will examine the reasonably ascertainable economic and social consequences of granting or denying the exemption after consideration of the effect on the national economy, small business, technological innovation, the environment, and public health.

(2) *Grant of the exemption.* The exemption will be granted if the Assistant Administrator determines, after consideration of all relevant evidence presented in the rulemaking proceeding described in paragraph (b)(1) of this section, that the new microorganism will not present an unreasonable risk of injury to health or the environment.

(3) *Denial of the exemption.* The exemption will be denied if the Assistant Administrator determines, after consideration of all relevant evidence presented in the rulemaking proceeding described in paragraph (b)(1) of this section, that the determination described in paragraph (c)(2) of this section cannot be made. A final decision terminating the rulemaking proceeding will be published in the FEDERAL REGISTER.

[62 FR 17932, April 11, 1997, as amended at 75 FR 789, Jan. 6, 2010]

**§ 725.70 Compliance.**

(a) Failure to comply with any provision of this part is a violation of section 15 of the Act (15 U.S.C. 2614).

(b) A person who manufactures or imports a microorganism before a MCAN is submitted and the MCAN review period expires is in violation of section 15 of the Act even if that person was not required to submit the MCAN under § 725.105.

(c) Using a microorganism which a person knew or had reason to know was manufactured, processed, or distributed in commerce in violation of section 5 of the Act or this part is a violation of section 15 of the Act (15 U.S.C. 2614).

(d) Failure or refusal to establish and maintain records or to permit access to or copying of records, as required by the Act, is a violation of section 15 of the Act (15 U.S.C. 2614).

(e) Failure or refusal to permit entry or inspection as required by section 11 of the Act is a violation of section 15 of the Act (15 U.S.C. 2614).

(f) Violators may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation. Persons who submit materially misleading or false information in connection with the requirements of any provision of this part may be subject to penalties calculated as if they never filed their submissions.

(g) EPA may seek to enjoin the manufacture or processing of a microorganism in violation of this part or act to seize any microorganism manufactured or processed in violation of this part or take other actions under the authority of section 7 of the Act (15 U.S.C. 2606) or section 17 of the Act (15 U.S.C. 2616).

**§ 725.75 Inspections.**

EPA will conduct inspections under section 11 of the Act to assure compliance with section 5 of the Act and this part, to verify that information required by EPA under this part is true and correct, and to audit data submitted to EPA under this part.

**Subpart C—Confidentiality and Public Access to Information****§ 725.80 General provisions for confidentiality claims.**

(a) A person may assert a claim of confidentiality for any information submitted to EPA under this part. However,

(1) Any person who asserts a claim of confidentiality for portions of the specific microorganism identity must provide the information as described in § 725.85.

(2) Any person who asserts a claim of confidentiality for a use of a microorganism must provide the information as described in § 725.88.

(3) Any person who asserts a claim of confidentiality for information contained in a health and safety study of a microorganism must provide the information described in § 725.92.

(b) Any claim of confidentiality must accompany the information when it is submitted to EPA.

(1) When a person submits any information under this part, including any attachments, for which claims of confidentiality are made, the claim(s) must be asserted by circling the specific information which is claimed and marking the page on which that information appears with an appropriate designation such as “trade secret,” “TSCA CBI,” or “confidential business information.”

(2) If any information is claimed confidential, the person must submit two copies of the document including the claimed information.

(i) One copy of the document must be complete. In that copy, the submitter must mark the information which is claimed as confidential in the manner prescribed in paragraph (b)(1) of this section.

(ii) The second copy must be complete except that all information claimed as confidential in the first copy must be deleted. EPA will place the second copy in the public file.

(iii) If the submitter does not provide the second copy, the submission is incomplete and the review period does not begin to run until EPA receives the second copy, in accordance with § 725.33.

(iv) Any information contained within the copy submitted under paragraph (b)(2)(ii) of this section which has been in the public file for more than 30 days will be presumed to be in the public domain, notwithstanding any assertion of confidentiality made under this section.

(3) A person who submits information to EPA under this part must reassert a claim of confidentiality and substantiate the claim each time the information is submitted to EPA.

(c) Any person asserting a claim of confidentiality under this part must substantiate each claim in accordance with the requirements in § 725.94.

(d) EPA will disclose information that is subject to a claim of confidentiality asserted under this section only to the extent permitted by the Act, this subpart, and part 2 of this title.

(e) If a submitter does not assert a claim of confidentiality for information at the time it is submitted to EPA, EPA may make the information public and place it in the public file without further notice to the submitter.

#### § 725.85 Microorganism identity.

(a) *Claims applicable to the period prior to commencement of manufacture or import for general commercial use*—(1) *When to make a claim.* (i) A person who submits information to EPA under this part may assert a claim of confidentiality for portions of the specific microorganism identity at the time of submission of the information. This claim will apply only to the period prior to the commencement of manufacture or import for general commercial use.

(ii) A person who submits information to EPA under this part must reassert a claim of confidentiality and substantiate the claim each time the information is submitted to EPA. For example, if a person claims certain information confidential in a TERA submission and wishes the same information to remain confidential in a subsequent TERA or MCAN submission, the person must reassert and resubstantiate the claim in the subsequent submission.

(2) *Assertion of claim.* (i) A submitter may assert a claim of confidentiality

only if the submitter believes that public disclosure prior to commencement of manufacture or import for general commercial use of the fact that anyone is initiating research and development activities pertaining to the specific microorganism or intends to manufacture or import the specific microorganism for general commercial use would reveal confidential business information. Claims must be substantiated in accordance with the requirements of § 725.94(a).

(ii) If the submission includes a health and safety study concerning the microorganism and if the claim for confidentiality with respect to the specific identity is denied in accordance with § 725.92(c), EPA will deny a claim asserted under paragraph (a) of this section.

(3) *Development of generic name.* Any person who asserts a claim of confidentiality for portions of the specific microorganism identity under this paragraph must provide one of the following items at the time the submission is filed:

(i) The generic name which was accepted by EPA in the prenotice consultation conducted under paragraph (a)(4) of this section.

(ii) One generic name that is only as generic as necessary to protect the confidential identity of the particular microorganism. The name should reveal the specific identity to the maximum extent possible. The generic name will be subject to EPA review and approval.

(4) *Determination by EPA.* (i) Any person who intends to assert a claim of confidentiality for the specific identity of a new microorganism may seek a determination by EPA of an appropriate generic name for the microorganism before filing a submission. For this purpose, the person should submit to EPA:

(A) The specific identity of the microorganism.

(B) A proposed generic name(s) which is only as generic as necessary to protect the confidential identity of the new microorganism. The name(s) should reveal the specific identity of the microorganism to the maximum extent possible.

(ii) Within 30 days, EPA will inform the submitter either that one of the proposed generic names is adequate or that none is adequate and further consultation is necessary.

(5) *Use of generic name.* If a submitter claims microorganism identity as confidential under paragraph (a) of this section, and if the submitter complies with paragraph (a)(2) of this section, EPA will issue for publication in the FEDERAL REGISTER notice described in § 725.40 the generic name proposed by the submitter or one agreed upon by EPA and the submitter.

(b) *Claims applicable to the period after commencement of manufacture or import for general commercial use—(1) Maintaining claim.* Any claim of confidentiality under paragraph (a) of this section is applicable only until the microorganism is manufactured or imported for general commercial use and becomes eligible for inclusion on the Inventory. To maintain the confidential status of the microorganism identity when the microorganism is added to the Inventory, a submitter must reassert the confidentiality claim and substantiate the claim in the notice of commencement of manufacture required under § 725.190.

(i) A submitter may not claim the microorganism identity confidential for the period after commencement of manufacture or import for general commercial use unless the submitter claimed the microorganism identity confidential under paragraph (a) of this section in the MCAN submitted for the microorganism.

(ii) A submitter may claim the microorganism identity confidential for the period after commencement of manufacture or import for general commercial use if the submitter did not claim the microorganism identity confidential under paragraph (a) of this section in any TERA submitted for the microorganism, but subsequently did claim microorganism identity confidential in the MCAN submitted for the microorganism.

(2) *Assertion of claim.* (i) A person who believes that public disclosure of the fact that anyone manufactures or imports the microorganism for general commercial use would reveal confidential business information may assert a

claim of confidentiality under paragraph (b) of this section.

(ii) If the notice includes a health and safety study concerning the new microorganism, and if the claim for confidentiality with respect to the microorganism identity is denied in accordance with § 725.92(c), EPA will deny a claim asserted under paragraph (b) of this section.

(3) *Requirements for assertion.* Any person who asserts a confidentiality claim for microorganism identity must:

(i) Comply with the requirements of paragraph (a)(3) of this section regarding submission of a generic name.

(ii) Agree that EPA may disclose to a person with a *bona fide* intent to manufacture or import the microorganism the fact that the particular microorganism is included on the confidential Inventory for purposes of notification under section 5(a)(1)(A) of the Act.

(iii) Have available and agree to furnish to EPA upon request the taxonomic designations and supplemental information required by § 725.12.

(iv) Provide a detailed written substantiation of the claim, in accordance with the requirements of § 725.94(b).

(4) *Denial of claim.* If the submitter does not meet the requirements of paragraph (b) of this section, EPA will deny the claim of confidentiality.

(5) *Acceptance of claim.* (i) EPA will publish a generic name on the public Inventory if:

(A) The submitter asserts a claim of confidentiality in accordance with this paragraph.

(B) No claim for confidentiality of the microorganism identity as part of a health and safety study has been denied in accordance with part 2 of this title or § 725.92.

(ii) Publication of a generic name on the public Inventory does not create a category for purposes of the Inventory. Any person who has a *bona fide* intent to manufacture or import a microorganism which is described by a generic name on the public Inventory may submit an inquiry to EPA under § 725.15(b) to determine whether the particular microorganism is included on the confidential Inventory.

(iii) Upon receipt of a request described in § 725.15(b), EPA may require the submitter who originally asserted



**§ 725.88**

**40 CFR Ch. I (7–1–10 Edition)**

confidentiality for a microorganism to submit to EPA the information listed in paragraph (b)(3)(iii) of this section.

(iv) Failure to submit any of the information required under paragraph (b)(3)(iii) of this section within 10 calendar days of receipt of a request by EPA under paragraph (b) of this section will constitute a waiver of the original submitter's confidentiality claim. In this event, EPA may place the specific microorganism identity on the public Inventory without further notice to the original submitter.

(6) *Use of generic name on the public Inventory.* If a submitter asserts a claim of confidentiality under paragraph (b) of this section, EPA will examine the generic microorganism name proposed by the submitter.

(i) If EPA determines that the generic name proposed by the submitter is only as generic as necessary to protect the confidential identity of the particular microorganism, EPA will place that generic name on the public Inventory.

(ii) If EPA determines that the generic name proposed by the submitter is more generic than necessary to protect the confidential identity, EPA will propose in writing, for review by the submitter, an alternative generic name that will reveal the identity of the microorganism to the maximum extent possible.

(iii) If the generic name proposed by EPA is acceptable to the submitter, EPA will place that generic name on the public Inventory.

(iv) If the generic name proposed by EPA is not acceptable to the submitter, the submitter must explain in detail why disclosure of that generic name would reveal confidential business information and propose another generic name which is only as generic as necessary to protect the confidential identity of the microorganism. If EPA does not receive a response from the submitter within 30 days after the submitter receives the proposed name, EPA will place EPA's chosen generic name on the public Inventory. If the submitter does provide the information requested, EPA will review the response. If the submitter's proposed generic name is acceptable, EPA will publish that generic name on the pub-

lic Inventory. If the submitter's proposed generic name is not acceptable, EPA will notify the submitter of EPA's choice of a generic name. Thirty days after this notification, EPA will place the chosen generic name on the public Inventory.

**§ 725.88 Uses of a microorganism.**

(a) *Assertion of claim.* A person who submits information to EPA under this part on the categories or proposed categories of use of a microorganism may assert a claim of confidentiality for this information.

(b) *Requirements for claim.* A submitter that asserts such a claim must:

(1) Report the categories or proposed categories of use of the microorganism.

(2) Provide, in nonconfidential form, a description of the uses that is only as generic as necessary to protect the confidential business information. The generic use description will be included in the FEDERAL REGISTER notice described in § 725.40.

(c) *Generic use description.* The person must submit the information required by paragraph (b) of this section by describing the uses as precisely as possible, without revealing the information which is claimed confidential, to disclose as much as possible how the use may result in human exposure to the microorganism or its release to the environment.

**§ 725.92 Data from health and safety studies of microorganisms.**

(a) *Information other than specific microorganism identity.* Except as provided in paragraph (b) of this section, EPA will deny any claim of confidentiality with respect to information included in a health and safety study of a microorganism, unless the information would disclose confidential business information concerning:

(1) Processes used in the manufacture or processing of a microorganism.

(2) Information which is not in any way related to the effects of a microorganism on health or the environment, such as, the name of the submitting company, cost or other financial data, product development or marketing plans, and advertising plans, for which the person submits a claim of

## Environmental Protection Agency

## § 725.94

confidentiality in accordance with § 725.80.

(b) *Microorganism identity*—(1) *Claims applicable to the period prior to commencement of manufacture or import for general commercial use.* A claim of confidentiality for the period prior to commencement of manufacture or import for general commercial use for the specific identity of a microorganism for which a health and safety study was submitted must be asserted in conjunction with a claim asserted under § 725.85(a). The submitter must substantiate each claim in accordance with the requirements of § 725.94(a).

(2) *Claims applicable to the period after commencement of manufacture or import for general commercial use.* To maintain the confidential status of the specific identity of a microorganism for which a health and safety study was submitted after commencement of manufacture or import for general commercial use, the claim must be reasserted and substantiated in conjunction with a claim under § 725.85(b). The submitter must substantiate each claim in accordance with the requirements of § 725.94(b).

(c) *Denial of confidentiality claim.* EPA will deny a claim of confidentiality for microorganism identity under paragraph (b) of this section, unless:

(1) The information would disclose processes used in the manufacture or processing of a microorganism.

(2) The microorganism identity is not necessary to interpret a health and safety study.

(d) *Use of generic names.* When EPA discloses a health and safety study containing a microorganism identity, which the submitter has claimed confidential, and if the Agency has not denied the claim under paragraph (c) of this section, EPA will identify the microorganism by the generic name selected under § 725.85.

### § 725.94 Substantiation requirements.

(a) *Claims applicable to the period prior to commencement of manufacture or import for general commercial use*—(1) *MCAN, TME, Tier I certification, and Tier II exemption request requirements.* Any person who submits a MCAN, TME, Tier I certification, or Tier II exemption request should strictly limit

confidentiality claims to that information which is confidential and proprietary to the business.

(i) If any information in the submission is claimed as confidential business information, the submitter must substantiate each claim by submitting written answers to the questions in paragraphs (c), (d), and (e) of this section at the time the person submits the information.

(ii) If the submitter does not provide written substantiation as required in paragraph (a)(1)(i) of this section, the submission will be considered incomplete and the review period will not begin in accordance with § 725.33.

(2) *TERA requirements.* Any person who submits a TERA, should strictly limit confidentiality claims to that information which is confidential and proprietary to the business. If any information in such a submission is claimed as confidential business information, the submitter must have available for each of those claims, and agree to furnish to EPA upon request, written answers to the questions in paragraphs (d) and (e) of this section.

(b) *Claims applicable to the period after commencement of manufacture or import for general commercial use.* (1) If a submitter claimed portions of the microorganism identity confidential in the MCAN and wants the identity to be listed on the confidential Inventory, the claim must be reasserted and substantiated at the time the Notice of Commencement (NOC) is submitted under § 725.190. Otherwise, EPA will list the specific microorganism identity on the public Inventory.

(2) The submitter must substantiate the claim for confidentiality of the microorganism identity by answering all of the questions in paragraphs (c), (d), and (e) in this section. In addition, the following questions must be answered:

(i) What harmful effects to the company's or institution's competitive position, if any, would result if EPA publishes on the Inventory the identity of the microorganism? How could a competitor use such information given the fact that the identity of the microorganism otherwise would appear on the TSCA Inventory with no link between the microorganism and the company or

institution? How substantial would the harmful effects of disclosure be? What is the causal relationship between the disclosure and the harmful effects?

(ii) Has the identity of the microorganism been kept confidential to the extent that competitors do not know it is being manufactured or imported for general commercial use by anyone?

(c) *General questions.* The following questions must be answered in detail for each confidentiality claim:

(1) For what period of time is a claim of confidentiality being asserted? If the claim is to extend until a certain event or point in time, indicate that event or time period. Explain why the information should remain confidential until such point.

(2) Briefly describe any physical or procedural restrictions within the company or institution relating to the use and storage of the information claimed as confidential. What other steps, if any, apply to use or further disclosure of the information?

(3) Has the information claimed as confidential been disclosed to individuals outside of the company or institution? Will it be disclosed to such persons in the future? If so, what restrictions, if any, apply to use or further disclosure of the information?

(4) Does the information claimed as confidential appear, or is it referred to, in any of the following questions? If the answer is yes to any of these questions, indicate where the information appears and explain why it should nonetheless be treated as confidential.

(i) Advertising or promotional materials for the microorganism or the resulting end product?

(ii) Material safety data sheets or other similar materials for the microorganism or the resulting end product?

(iii) Professional or trade publications?

(iv) Any other media available to the public or to competitors?

(v) Patents?

(vi) Local, State, or Federal agency public files?

(5) Has EPA, another Federal agency, a Federal court, or a State made any confidentiality determination regarding the information claimed as confidential? If so, provide copies of such determinations.

(6) For each type of information claimed confidential, describe the harm to the company's or institution's competitive position that would result if this information were disclosed. Why would this harm be substantial? How could a competitor use such information? What is the causal connection between the disclosure and harm?

(7) If EPA disclosed to the public the information claimed as confidential, how difficult would it be for the competitor to enter the market for the resulting product? Consider such constraints as capital and marketing cost, specialized technical expertise, or unusual processes.

(d) *Microorganism identity and production method.* If confidentiality claims are asserted for the identity of the microorganism or information on how the microorganism is produced, the following questions must be answered:

(1) Has the microorganism or method of production been patented in the U.S. or elsewhere? If so, why is confidentiality necessary?

(2) Does the microorganism leave the site of production or testing in a form which is accessible to the public or to competitors? What is the cost to a competitor, in time and money, to develop appropriate use conditions? What factors facilitate or impede product analysis?

(3) For each additional type of information claimed as confidential, explain what harm would result from disclosure of each type of information if the identity of the microorganism were to remain confidential.

(e) *Health and safety studies of microorganisms.* If confidentiality claims are asserted for information in a health or safety study of a microorganism, the following questions must be answered:

(1) Would the disclosure of the information claimed confidential reveal: confidential process information, or information unrelated to the effects of the microorganism on health and the environment. Describe the causal connection between the disclosure and harm.

(2) Does the company or institution assert that disclosure of the microorganism identity is not necessary to interpret any health and safety studies

## Environmental Protection Agency

## § 725.105

which have been submitted? If so, explain how a less specific identity would be sufficient to interpret the studies.

### § 725.95 Public file.

All information submitted, including any health and safety study of a microorganism and other supporting documentation, will become part of the public file for that submission, unless such materials are claimed confidential. In addition, EPA may add materials to the public file, unless such materials are claimed confidential. Any of the nonconfidential material described in this subpart will be available for public inspection in the TSCA Public Docket Office, Rm. NE-B607, 401 M St., SW., Washington, DC, between the hours of noon to 4 p.m., Monday through Friday, excluding legal holidays.

## Subpart D—Microbial Commercial Activities Notification Requirements

### § 725.100 Scope and purpose.

(a) This subpart establishes procedures for submission of a notice to EPA under section 5(a) of the Act for persons who manufacture, import, or process microorganisms for commercial purposes. This notice is called a Microbial Commercial Activity Notice (MCAN). It is expected that MCANs will in general only be submitted for microorganisms intended for general commercial use. Persons who manufacture, import, or process a microorganism in small quantities solely for research and development as defined in § 725.3 are not required to submit a notice to EPA. Persons who manufacture, import, or process a microorganism for research and development activities that do not fit the definition of small quantities solely for research and development may nonetheless qualify for more limited reporting requirements in Subpart E, including the TERA which can be used for review of research and development involving environmental release.

(b) Persons subject to MCAN submission are described in § 725.105.

(c) Exclusions and exemptions specific to MCAN submissions are described in § 725.110.

(d) Submission requirements applicable specifically to MCANs are described at § 725.150.

(e) Data requirements for MCANs are set forth in §§ 725.155 and 725.160.

(f) EPA review procedures specific to MCANs are set forth in § 725.170.

(g) Subparts A through C of this part apply to any MCAN submitted under this subpart.

### § 725.105 Persons who must report.

(a) *Manufacturers of new microorganisms.* (1) MCAN submission is required for any person who intends to manufacture for commercial purposes in the United States a new microorganism. Exclusions are described in § 725.110.

(2) If a person contracts with a manufacturer to produce or process a new microorganism and the manufacturer produces or processes the microorganism exclusively for that person, and that person specifies the identity of the microorganism, and controls the total amount produced and the basic technology for the plant process, then that person must submit the MCAN. If it is unclear who must report, EPA should be contacted to determine who must submit the MCAN.

(3) Only manufacturers that are incorporated, licensed, or doing business in the United States may submit a MCAN.

(b) *Importers of new microorganisms.* (1) MCAN submission is required for a person who intends to import into the United States for commercial purposes a new microorganism. Exclusions are described in § 725.110.

(2) When several persons are involved in an import transaction, the MCAN must be submitted by the principal importer. If no one person fits the principal importer definition in a particular transaction, the importer should contact EPA to determine who must submit the MCAN for that transaction.

(3) Except as otherwise provided in paragraph (b)(4) of this section, the provisions of this subpart D apply to each person who submits a MCAN for a new microorganism which such person intends to import for a commercial purpose. In addition, each importer must comply with paragraph (b)(4) of this section.

**§ 725.110**

**40 CFR Ch. I (7-1-10 Edition)**

(4) EPA will hold the principal importer, or the importer that EPA determines must submit the MCAN when there is no principal importer under paragraph (b)(2) of this section, liable for complying with this part, for completing the MCAN, and for the completeness and truthfulness of all information which it submits.

(c) *Manufacturers, importers, or processors of microorganisms for a significant new use.* MCAN submission is required for any person who intends to manufacture, import, or process for commercial purposes a microorganism identified as having one or more significant new uses in subpart M of this part, and who intends either to engage in a designated significant new use of the microorganism or intends to distribute it in commerce. Persons excluded from reporting on significant new uses of microorganisms and additional procedures for reporting are described in subpart L of this part.

**§ 725.110 Persons not subject to this subpart.**

Persons are not subject to the requirements of this subpart for the following activities:

(a) Manufacturing, importing, or processing solely for research and development microorganisms that meet the requirements for an exemption under subpart E of this part.

(b) Manufacturing, importing, or processing microorganisms for test marketing activities which have been granted an exemption under subpart F of this part.

(c) Manufacturing or importing new microorganisms under the conditions of a Tier I or Tier II exemption under subpart G of this part.

**§ 725.150 Procedural requirements for this subpart.**

General requirements for all MCANs under this part are contained in subparts A through C of this part. In addition, the following requirements apply to MCANs submitted under this subpart:

(a) *When to submit a MCAN.* A MCAN must be submitted at least 90 calendar days prior to manufacturing or importing a new microorganism and at least 90 calendar days prior to manufac-

turing, importing, or processing a microorganism for a significant new use.

(b) *Section 5(b) of the Act.* The submitter must comply with any applicable requirement of section 5(b) of the Act for the submission of test data.

(c) *Contents of a MCAN.* Each person who submits a MCAN under this subpart must provide the information and test data described in §§ 725.155 and 725.160.

(d) *Recordkeeping.* Each person who submits a MCAN under this subpart must comply with the recordkeeping requirements of § 725.65.

**§ 725.155 Information to be included in the MCAN.**

(a) Each person who is required by this part to submit a MCAN must include the information specified in paragraphs (c) through (h) of this section, to the extent it is known to or reasonably ascertainable by that person. However, no person is required to include information which relates solely to exposure of humans or ecological populations outside of the United States.

(b) Each person should also submit, in writing, all other information known to or reasonably ascertainable by that person that would permit EPA to make a reasoned evaluation of the health and environmental effects of the microorganism, or any microbial mixture or article, including information on its effects on humans, animals, plants, and other microorganisms, and in the environment. The information to be submitted under this subpart includes the information listed in paragraphs (c) through (h) of this section relating to the manufacture, processing, distribution in commerce, use, and disposal of the new microorganism.

(c) *Submitter identification.* (1) The name and headquarters address of the submitter.

(2) The name, address, and office telephone number (including area code) of the principal technical contact representing the submitter.

(d) *Microorganism identity information.* Persons must submit sufficient information to allow the microorganism to

be accurately and unambiguously identified for listing purposes as required by § 725.12.

(1) *Description of the recipient microorganism and the new microorganism.* (i) Data substantiating the taxonomy of the recipient microorganism and the new microorganism to the level of strain, as appropriate. In lieu of data, EPA will accept a letter from a culture collection substantiating taxonomy, provided EPA, upon request to the submitter, may have access to the data supporting the taxonomic designation.

(ii) Information on the morphological and physiological features of the new microorganism.

(iii) Other specific data by which the new microorganism may be uniquely identified for Inventory purposes.

(2) *Genetic construction of the new microorganism.* (i) Data substantiating the taxonomy of the donor organism(s). In lieu of data, EPA will accept a letter from a culture collection substantiating taxonomy, provided EPA, upon request to the submitter, may have access to the data supporting the taxonomic designation.

(ii) Description of the traits for which the new microorganism has been selected or developed and other traits known to have been added or modified.

(iii) A detailed description of the genetic construction of the new microorganism, including the technique used to modify the microorganism (e.g., fusion of cells, injection of DNA, electroporation or chemical poration, or methods used for induced mutation and selection). The description should include, for example, a description of the introduced genetic material, including any regulatory sequences and structural genes and the products of those genes; how the introduced genetic material is expected to affect behavior of the recipient; expression, alteration, and stability of the introduced genetic material; methods for vector construction and introduction; and a description of the regulatory and structural genes that are components of the introduced genetic material, including genetic maps of the introduced sequences.

(3) *Phenotypic and ecological characteristics.* (i) Habitat, geographical dis-

tribution, and source of the recipient microorganism.

(ii) Survival and dissemination under relevant environmental conditions including a description of methods for detecting the new or recipient microorganism(s) in the environment and the sensitivity limit of detection for these techniques.

(iii) A description of anticipated biological interactions with and effects on target organisms and other organisms such as competitors, prey, hosts, symbionts, parasites, and pathogens; a description of host range; a description of pathogenicity, infectivity, toxicity, virulence, or action as a vector of pathogens; and capacity for genetic transfer under laboratory and relevant environmental conditions.

(iv) A description of anticipated involvement in biogeochemical or biological cycling processes, involvement in rate limiting steps in mineral or nutrient cycling, or involvement in inorganic compounds cycling (such as possible sequestration or transformation of heavy metals).

(e) *Byproducts.* A description of the byproducts resulting from the manufacture, processing, use, and disposal of the new microorganism.

(f) *Total production volume.* The estimated maximum amount of the new microorganism intended to be manufactured or imported during the first year of production and the estimated maximum amount to be manufactured or imported during any consecutive 12-month period during the first 3 years of production. This estimate may be by weight or volume and should include an estimation of viability (i.e., viable cells per unit volume or colony forming units per unit dry weight).

(g) *Use information.* A description of intended categories of use by function and application, the estimated percent of production volume devoted to each category of use, and the percent of the new microorganism in the formulation for each commercial or consumer use.

(h) *Worker exposure and environmental release.* (1) For sites controlled by the submitter:

(i) The identity of sites where the new microorganism will be manufactured, processed, or used. For purposes of this section, the site for a person

who imports a new microorganism is the site of the operating unit within the person's organization which is directly responsible for importing the new microorganism and which controls the import transaction. The import site may in some cases be the organization's headquarters office in the United States.

(ii) A process description of each manufacture, processing, and use operation, which includes a diagram of the major unit operations and conversions, the identity and entry point of all feedstocks, and the identity of any possible points of release of the new microorganism from the process, including a description of all controls, including engineering controls, used to prevent such releases.

(iii) Worker exposure information, including worker activities, physical form of process streams which contain the new microorganism to which workers may be exposed, the number of workers, and the duration of activities.

(iv) Information on release of the new microorganism to the environment, including the quantity and media of release and type of control technology used.

(v) A narrative description of the intended transport of the new microorganism, including the means of transport, containment methods to be used during transport, and emergency containment procedures to be followed in case of accidental release.

(vi) Procedures for disposal of any articles, waste, clothing, or other equipment involved in the activity, including procedures for inactivation of the new microorganism, containment, disinfection, and disposal of contaminated items.

(2) For sites not controlled by the submitter, a description of each type of processing and use operation involving the new microorganism, including identification of the estimated number of processing or use sites, situations in which worker exposure to and/or environmental release of the new microorganism will occur, the number of workers exposed and the duration of exposure; procedures for transport of the new microorganism and for disposal, including procedures for inactivation of the new microorganism; and

control measures which limit worker exposure and environmental release.

**§ 725.160 Submission of health and environmental effects data.**

(a) *Test data on the new microorganism in the possession or control of the submitter.* (1) Except as provided in § 725.25(h), and in addition to the information required by § 725.155(d)(3), each MCAN must contain all test data in the submitter's possession or control which are related to the effects on health or the environment of any manufacture, processing, distribution in commerce, use, or disposal of the new microorganism or any microbial mixture or article containing the new microorganism, or any combination of such activities. This includes test data concerning the new microorganism in a pure culture or formulated form as used or as intended to be used in one of the activities listed above.

(2) A full report or standard literature citation must be submitted for the following types of test data:

- (i) Health effects data.
- (ii) Ecological effects data.
- (iii) Physical and chemical properties data.
- (iv) Environmental fate characteristics.
- (v) Monitoring data and other test data related to human exposure to or environmental release of the new microorganism.

(3)(i) If the data do not appear in the open scientific literature, the submitter must provide a full report. A full report includes the experimental methods and materials, results, discussion and data analysis, conclusions, references, and the name and address of the laboratory that developed the data.

(ii) If the data appear in the open scientific literature, the submitter need only provide a standard literature citation. A standard literature citation includes author, title, periodical name, date of publication, volume, and page numbers.

(4)(i) If a study, report, or test is incomplete when a person submits a MCAN, the submitter must identify the nature and purpose of the study; name and address of the laboratory developing the data; progress to date; types

## Environmental Protection Agency

## § 725.170

of data collected, significant preliminary results; and anticipated completion date.

(ii) If a test or experiment is completed before the MCAN review period ends, the person must submit the study, report, or test, as specified in paragraph (a)(3)(i) of this section, to the address listed in § 725.25(c) within 10 days of receiving it, but no later than 5 days before the end of the review period. If the test or experiment is completed during the last 5 days of the review period, the submitter must immediately inform its EPA contact for that submission by telephone.

(5) For test data in the submitter's possession or control which are not listed in paragraph (a)(2) of this section, a person is not required to submit a complete report. The person must submit a summary of the data. If EPA so requests, the person must submit a full report within 10 days of the request, but no later than 5 days before the end of the review period.

(6) All test data described under paragraph (a) of this section are subject to these requirements, regardless of their age, quality, or results.

(b) *Other data concerning the health and environmental effects of the new microorganism that are known to or reasonably ascertainable by the submitter.* (1) Except as provided in § 725.25(h), and in addition to the information required by § 725.155(c)(3), any person who submits a MCAN must describe the following data, including any data from a health and safety study of a microorganism, if the data are related to effects on health or the environment of any manufacture, processing, distribution in commerce, use, or disposal of the microorganism, of any microbial mixture or article containing the new microorganism, or of any combination of such activities:

(i) Any data, other than test data, in the submitter's possession or control.

(ii) Any data, including test data, which are not in the submitter's possession or control, but which are known to or reasonably ascertainable by the submitter. For the purposes of this section, data are known to or reasonably ascertainable by the submitter if the data are known to any of its employees or other agents who are associ-

ated with the research and development, test marketing, or commercial marketing of the microorganism.

(2) Data that must be described include data concerning the new microorganism in a pure culture or formulated form as used or as intended to be used in one of the activities listed in paragraph (b)(1) of this section.

(3) The description of data reported under paragraph (b) of this section must include:

(i) If the data appear in the open scientific literature, a standard literature citation, which includes the author, title, periodical name, date of publication, volume, and pages.

(ii) If the data are not available in the open scientific literature, a description of the type of data and summary of the results, if available, and the names and addresses of persons the submitter believes may have possession or control of the data.

(4) All data described in paragraph (b) of this section are subject to these requirements, regardless of their age, quality, or results; and regardless of whether they are complete at the time the MCAN is submitted.

### § 725.170 EPA review of the MCAN.

General procedures for review of all submissions under this part are contained in §§ 725.28 through 725.60. In addition, the following procedures apply to EPA review of MCANs submitted under this subpart:

(a) Length of the review period. The MCAN review period specified in section 5(a) of the Act runs for 90 days from the date the Document Control Officer for the Office of Pollution Prevention and Toxics receives a complete MCAN, or the date EPA determines the MCAN is complete under § 725.33, unless the Agency extends the period under section 5(c) of the Act and § 725.56.

(b) Notice of expiration of MCAN review period. (1) EPA will notify the submitter that the MCAN review period has expired or that EPA has completed its review of the MCAN. Expiration of the review period does not constitute EPA approval or certification of the new microorganism, and does not mean that EPA may not take regulatory action against the microorganism in the future.



(2) After expiration of the MCAN review period, in the absence of regulatory action by EPA under section 5(e), 5(f), or 6(a) of the Act, the submitter may manufacture or import the microorganism even if the submitter has not received notice of expiration.

(3) Early notification that EPA has completed its review does not permit commencement of manufacture or import prior to the expiration of the 90-day MCAN review period.

(c) No person submitting a MCAN in response to the requirements of this subpart may manufacture, import, or process a microorganism subject to this subpart until the review period, including all extensions and suspensions, has expired.

**§ 725.190 Notice of commencement of manufacture or import.**

(a) *Applicability.* Any person who commences the manufacture or import of a new microorganism for nonexempt, commercial purposes for which that person previously submitted a section 5(a) notice under this part must submit a notice of commencement (NOC) of manufacture or import.

(b) *When to report.* (1) If manufacture or import for nonexempt, commercial purposes begins on or after May 27, 1997, the submitter must submit the NOC to EPA no later than 30 calendar days after the first day of such manufacture or import.

(2) If manufacture or import for nonexempt, commercial purposes began or will begin before May 27, 1997, the submitter must submit the NOC by May 27, 1997.

(3) Submission of an NOC prior to the commencement of manufacture or import is a violation of section 15 of the Act.

(c) *Information to be reported.* The NOC must contain the following information: Specific microorganism identity, MCAN number, and the date when manufacture or import commences. If the person claimed microorganism identity confidential in the MCAN, and wants the identity to be listed on the confidential Inventory, the claim must be reasserted and resubstantiated in accordance with § 725.85(b). Otherwise, EPA will list the specific microorganism identity on the public Inventory.

(d) *Where to submit.* All notices of commencement must be submitted to EPA in a manner set forth in this paragraph.

(1) *Older notices.* Notices of commencement for a MCAN submitted before April 6, 2010 must be submitted on paper either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(2) *Newer notices.* For MCANs submitted on or after April 6, 2010, EPA will accept notices of commencement only if submitted in accordance with this paragraph:

(i) Notices of commencement may be submitted on paper on or before April 6, 2011. All paper-based notices of commencement must be generated using e-PMN reporting software and be completed through the finalization step of the software, and e-PMN software must be used to print the statement of withdrawal for submission to EPA. Paper notices of commencement must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001 or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(ii) Notices of commencement may be submitted as electronic files on optical disc on or before April 6, 2012. All notices of commencement submitted as electronic files on optical disc must be generated using e-PMN reporting software and be completed through the finalization step of the software. Optical discs containing electronic notices of commencement must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004.

(iii) Notices of commencement may be submitted electronically to EPA via CDX on or after April 6, 2010. After April 6, 2012 all notices of commencement must be submitted electronically to EPA via CDX. Prior to submission to EPA via CDX, such notices of commencement must be generated and completed using e-PMN reporting software. See 40 CFR 720.40(a)(2)(iv) for information on how to obtain e-PMN software.

[62 FR 17932, April 11, 1997, as amended at 75 FR 789, Jan. 6, 2010]

### Subpart E—Exemptions for Research and Development Activities

#### § 725.200 Scope and purpose.

(a) This subpart describes exemptions from the reporting requirements under subpart D of this part for research and development activities involving microorganisms.

(b) In lieu of complying with subpart D of this part, persons described in § 725.205 may submit a TSCA Experimental Release Application (TERA) for research and development activities involving microorganisms or otherwise comply with this subpart.

(c) Exemptions from part 725 are provided at §§ 725.232, 725.234, and 725.238.

(d) Submission requirements specific for TERAs are described at § 725.250.

(e) Data requirements for TERAs are set forth in §§ 725.255 and 725.260.

(f) EPA review procedures specific for TERAs are set forth in §§ 725.270 and 725.288.

(g) Subparts A through C of this part apply to any submission under this subpart.

#### § 725.205 Persons who may report under this subpart.

(a) Commercial research and development activities involving new microorganisms or significant new uses of microorganisms are subject to reporting under this part unless they qualify for an exemption under this part.

(b) Commercial purposes for research and development means that the activities are conducted with the purpose of obtaining an immediate or eventual

commercial advantage for the researcher and would include:

(1) All research and development activities which are funded directly, in whole or in part, by a commercial entity regardless of who is actually conducting the research. Indications that the research and development activities are funded directly, in whole or in part, may include, but are not limited to:

(i) Situations in which a commercial entity contracts directly with a university or researcher; or

(ii) Situations in which a commercial entity gives a conditional grant where the commercial entity holds patent rights, or establishes a joint venture where the commercial entity holds patent or licensing rights; or

(iii) Any other situation in which the commercial entity intends to obtain an immediate or eventual commercial advantage for the commercial entity and/or the researcher.

(2) Research and development activities that are not funded directly by a commercial entity, if the researcher intends to obtain an immediate or eventual commercial advantage. Indications that the researcher intends to obtain an immediate or eventual commercial advantage may include, but are not limited to:

(i) The research is directed toward developing a commercially viable improvement of a product already on the market; or

(ii) The researcher has sought or is seeking commercial funding for the purpose of developing a commercial application; or

(iii) The researcher or university has sought or is seeking a patent to protect a commercial application which the research is developing; or

(iv) Other evidence that the researcher is aware of a commercial application for the research and has directed the research toward developing that application.

(c) Certain research and development activities involving microorganisms subject to jurisdiction under the Act are exempt from reporting under this part. A person conducting research and development activities which meet the conditions for the exemptions described in §§ 725.232, 725.234, or 725.238 is

**§ 725.232**

**40 CFR Ch. I (7-1-10 Edition)**

exempt from TERA reporting under this subpart.

(d) A microorganism is not exempt from reporting under subpart D of this part if any amount of the microorganism, including as part of a mixture, is processed, distributed in commerce, or used, for any commercial purpose other than research and development.

(e) Quantities of the inactivated microorganism, or mixtures or articles containing the inactivated microorganism, remaining after completion of research and development activities may be disposed of as a waste in accordance with applicable Federal, State, and local regulations.

(f) A person who manufactures, imports, or processes a microorganism solely for research and development is not required to comply with the requirements of this section if:

(1) The person is manufacturing a microbial pesticide identified in §172.45(c), or

(2) The person is manufacturing a microbial pesticide for which an Experimental Use Permit is required, pursuant to §172.3; or

(3) The person is manufacturing a microbial pesticide for which a notification or an Experimental Use Permit is not required to be submitted.

**§ 725.232 Activities subject to the jurisdiction of other Federal programs or agencies.**

This part does not apply to any research and development activity that meets all of the following conditions.

(a) The microorganism is manufactured, imported, or processed solely for research and development activities.

(b) There is no intentional testing of a microorganism outside of a structure, as structure is defined in §725.3.

(c)(1) The person receives research funds from another Federal agency, and the funds are awarded on the condition that the research will be conducted in accordance with the relevant portions of the NIH Guidelines, or

(2) A Federal agency or program otherwise imposes the legally binding requirement that the research is to be conducted in accordance with relevant portions of the NIH Guidelines.

**§ 725.234 Activities conducted inside a structure.**

A person who manufactures, imports, or processes a microorganism is not subject to the reporting requirements under subpart D of this part if all of the following conditions are met:

(a) The microorganism is manufactured, imported, or processed solely for research and development activities.

(b) The microorganism is used by, or directly under the supervision of, a technically qualified individual, as defined in §725.3. The technically qualified individual must maintain documentation of the procedures selected to comply with paragraph (d) of this section and must ensure that the procedures are used.

(c) There is no intentional testing of a microorganism outside of a structure, as structure is defined in §725.3.

(d) Containment and/or inactivation controls. (1) Selection and use of containment and/or inactivation controls inside a structure for a particular microorganism shall take into account the following:

(i) Factors relevant to the organism's ability to survive in the environment.

(ii) Potential routes of release in air, solids and liquids; in or on waste materials and equipment; in or on people, including maintenance and custodial personnel; and in or on other organisms, such as insects and rodents.

(iii) Procedures for transfer of materials between facilities.

(2) The technically qualified individual's selection of containment and/or inactivation controls shall be approved and certified by an authorized official (other than the TQI) of the institution that is conducting the test prior to the commencement of the test.

(3) Records shall be developed and maintained describing the selection and use of containment and/or inactivation controls, as specified in §725.235(c). These records, which must be maintained at the location where the research and development activity is being conducted, shall be submitted to EPA upon written request and within the time frame specified in EPA's request.

(4) Subsequent to EPA review of records in accordance with paragraph (d)(3) of this section, changes to the

containment/inactivation controls selected under paragraph (d)(1) of this section must be made upon EPA order. Failure to comply with EPA's order shall result in automatic loss of eligibility for an exemption under this section.

(e) The manufacturer, importer, or processor notifies all persons in its employ or to whom it directly distributes the microorganism, who are engaged in experimentation, research, or analysis on the microorganism, including the manufacture, processing, use, transport, storage, and disposal of the microorganism associated with research and development activities, of any risk to health, identified under § 725.235(a), which may be associated with the microorganism. The notification must be made in accordance with § 725.235(b).

**§ 725.235 Conditions of exemption for activities conducted inside a structure.**

(a) *Determination of risks.* To determine whether notification under § 725.234(e) is required, the manufacturer, importer, or processor must do one of the following:

(1) For research conducted in accordance with the NIH Guidelines, the manufacturer, importer, or processor must meet the conditions laid out at IV-B-4-d of the NIH Guidelines; or

(2) For all other research conducted in accordance with § 725.234, the manufacturer, importer, or processor must review and evaluate the following information to determine whether there is reason to believe there is any risk to health which may be associated with the microorganism:

(i) Information in its possession or control concerning any significant adverse reaction of persons exposed to the microorganism which may reasonably be associated with such exposure.

(ii) Information provided to the manufacturer, importer, or processor by a supplier or any other person concerning a health risk believed to be associated with the microorganism.

(iii) Health and environmental effects data in its possession or control concerning the microorganism.

(iv) Information on health effects which accompanies any EPA rule or

order issued under TSCA section 4, 5, or 6 of the Act that applies to the microorganism and of which the manufacturer, importer, or processor has knowledge.

(b) *Notification to employees and others.* (1) The manufacturer, importer, or processor must notify the persons identified in § 725.234(e) by means of a container labeling system, conspicuous placement of notices in areas where exposure may occur, written notification to each person potentially exposed, or any other method of notification which adequately informs persons of health risks which the manufacturer, importer, or processor has reason to believe may be associated with the microorganism, as determined under paragraph (a) of this section.

(2) If the manufacturer, importer, or processor distributes a microorganism manufactured, imported, or processed under this section to persons not in its employ, the manufacturer, importer, or processor must in written form:

(i) Notify those persons that the microorganism is to be used only for research and development purposes and the requirements of § 725.234 are to be met.

(ii) Provide the notice of health risks specified in paragraph (b)(1) of this section.

(3) The adequacy of any notification under this section is the responsibility of the manufacturer, importer, or processor.

(c) *Recordkeeping.* (1) For research conducted in accordance with the NIH Guidelines, a person who manufactures, imports, or processes a microorganism under this section must retain the following records:

(i) Documentation that the NIH Guidelines have been adhered to. Such documentation shall include:

(A) For experiments subject to Institutional Biosafety Committee review, or notification simultaneous with initiation of the experiment, the information submitted for review or notification, along with standard laboratory records, shall satisfy the recordkeeping requirements specified in § 725.234(d)(3).

(B) For experiments exempt from Institutional Biosafety Committee review or notification simultaneous with

§ 725.238

40 CFR Ch. I (7–1–10 Edition)

initiation of the experiment, documentation of the exemption, along with standard laboratory records, shall satisfy the recordkeeping requirement specified in § 725.234(d)(3).

(ii) Documentation of how the following requirements are satisfied under the NIH Guidelines:

(A) Copies or citations to information reviewed and evaluated to determine the need to make any notification of risk.

(B) Documentation of the nature and method of notification of risk, including copies of any labels or written notices used.

(C) The names and addresses of any persons other than the manufacturer, importer, or processor to whom the substance is distributed, the identity of the microorganism, the amount distributed, and copies of the notifications required.

(2) For all other research conducted in accordance with § 725.234, a person who manufactures, imports, or processes a microorganism under this section, must maintain the following records:

(i) Records describing selection and use of containment and/or inactivation controls required by § 725.234(d)(3) and certification by an authorized official required by § 725.234(d)(2) for each microorganism.

(ii) Copies or citations to information reviewed and evaluated under paragraph (a) of this section to determine the need to make any notification of risk.

(iii) Documentation of the nature and method of notification under paragraph (b)(1) of this section, including copies of any labels or written notices used.

(iv) The names and addresses of any persons other than the manufacturer, importer, or processor to whom the substance is distributed, the identity of the microorganism, the amount distributed, and copies of the notifications required under paragraph (b)(2) of this section.

**§ 725.238 Activities conducted outside a structure.**

(a) *Exemption.* (1) Research and development activities involving intentional testing in the environment of certain microorganisms listed in § 725.239 may

be conducted without prior review by EPA if all of the conditions of this section and § 725.239 are met.

(2) The research and development activity involving a microorganism listed in § 725.239 must be conducted by, or directly under the supervision of, a technically qualified individual, as defined in § 725.3.

(b) *Certification.* To be eligible for the exemption under this section, a manufacturer or importer must submit to EPA prior to initiation of the activity a document signed by an authorized official containing the following information:

(1) Name, address, and telephone number of the manufacturer or importer.

(2) Location, estimated duration, and planned start date of the test.

(3) Certification of the following:

(i) Compliance with the conditions of the exemption specified for the microorganism in § 725.239.

(ii) If state and/or local authorities have been notified of the activity, evidence of notification.

(c) *Recordkeeping.* Persons who conduct research and development activities under this section must comply with the recordkeeping requirements of § 725.65 and retain documentation that supports their compliance with the requirements of this section and the specific requirements for the microorganism listed in § 725.239.

**§ 725.239 Use of specific microorganisms in activities conducted outside a structure.**

(a) *Bradyrhizobium japonicum.* To qualify for an exemption under this section, all of the following conditions must be met for a test involving *Bradyrhizobium japonicum*:

(1) *Characteristics of recipient microorganism.* The recipient microorganism is limited to strains of *Bradyrhizobium japonicum*.

(2) *Modification of traits.* (i) The introduced genetic material must meet the criteria for poorly mobilizable listed in § 725.421(c).

(ii) The introduced genetic material must consist only of the following components:

(A) The structural gene(s) of interest, which have the following limitations:

## Environmental Protection Agency

## § 725.250

(1) For structural genes encoding marker sequences, the gene is limited to the *aadH* gene, which confers resistance to the antibiotics streptomycin and spectinomycin.

(2) For traits other than antibiotic resistance, the structural gene must be limited to the genera *Bradyrhizobium* and *Rhizobium*.

(B) The regulatory sequences permitting the expression of solely the gene(s) of interest.

(C) Associated nucleotide sequences needed to move genetic material, including linkers, homopolymers, adaptors, transposons, insertion sequences, and restriction enzyme sites.

(D) The vector nucleotide sequences needed for vector transfer.

(E) The vector nucleotide sequences needed for vector maintenance.

(3) *Limitations on exposure.* (i) The test site area must be no more than 10 terrestrial acres.

(ii) The technically qualified individual must select appropriate methods to limit the dissemination of modified *Bradyrhizobium japonicum*.

(b) *Rhizobium meliloti.* To qualify for an exemption under this section, all of the following conditions must be met for a test involving *Rhizobium meliloti*:

(1) *Characteristics of recipient microorganism.* The recipient microorganism is limited to strains of *Rhizobium meliloti*.

(2) *Modification of traits.* (i) The introduced genetic material must meet the criteria for poorly mobilizable listed in § 725.421(c) of this part.

(ii) The introduced genetic material must consist only of the following components:

(A) The structural gene(s) of interest, which have the following limitations:

(1) For structural genes encoding marker sequences, the gene is limited to the *aadH* gene, which confers resistance to the antibiotics streptomycin and spectinomycin.

(2) For traits other than antibiotic resistance, the structural gene must be limited to the genera *Bradyrhizobium* and *Rhizobium*.

(B) The regulatory sequences permitting the expression of solely the gene(s) of interest.

(C) Associated nucleotide sequences needed to move genetic material, in-

cluding linkers, homopolymers, adaptors, transposons, insertion sequences, and restriction enzyme sites.

(D) The vector nucleotide sequences needed for vector transfer.

(E) The vector nucleotide sequences needed for vector maintenance.

(3) *Limitations on exposure.* (i) The test site area must be no more than 10 terrestrial acres.

(ii) The technically qualified individual must select appropriate methods to limit the dissemination of modified *Rhizobium meliloti*.

### § 725.250 Procedural requirements for the TERA.

General requirements for all submissions under this part are contained in subparts A through C of this part. In addition, the following requirements apply to TERAs submitted under this subpart:

(a) When to submit the TERA. Each person who is eligible to submit a TERA under this subpart must submit the TERA at least 60 calendar days before the person intends to initiate the proposed research and development activity.

(b) Contents of the TERA. Each person who submits a TERA under this subpart must provide the information and test data described in §§ 725.255 and 725.260. In addition, the submitter must supply sufficient information to enable EPA to evaluate the effects of all activities for which approval is requested.

(c) A person may submit a TERA for one or more microorganisms and one or more research and development activities, including a research program.

(d) EPA will either approve the TERA, with or without conditions, or disapprove it under procedures established in this subpart.

(e) The manufacturer, importer, or processor who receives a TERA approval must comply with all terms of the approval, as well as conditions described in the TERA, and remains liable for compliance with all terms and conditions, regardless of who conducts the research and development activity. Any person conducting the research and development activity approved under the TERA must comply with all

**§ 725.255**

**40 CFR Ch. I (7–1–10 Edition)**

terms of the TERA approval, as well as the conditions described in the TERA.

(f) Recordkeeping. Persons submitting a TERA must comply with the recordkeeping requirements of § 725.65. In addition, the following requirements apply to TERAs:

(1) Each person submitting a TERA under this part must retain documentation of information contained in the TERA for a period of 3 years from the date that the results of the study are submitted to the Agency.

(2) Summaries of all data, conclusions, and reports resulting from the conduct of the research and development activity under the TERA must be submitted to the EPA address identified in § 725.25(c) within 1 year of the termination of the activity.

**§ 725.255 Information to be included in the TERA.**

(a) To review a TERA, EPA must have sufficient information to permit a reasoned evaluation of the health and environmental effects of the planned test in the environment. The person seeking EPA approval must submit all information known to or reasonably ascertainable by the submitter on the microorganism(s) and the research and development activity, including information not listed in paragraphs (c), (d), and (e) of this section that the person believes will be useful for EPA's risk assessment. The TERA must be in writing and must include at least the information described in the following paragraphs.

(b) When specific information is not submitted, an explanation of why such information is not available or not applicable must be included.

(c) Persons applying for a TERA, must include the submitter identification and microorganism identity information required for MCANs in § 725.155(c), (d)(1), and (d)(2).

(d) Persons applying for a TERA must submit phenotypic and ecological characteristics information required in § 725.155(d)(3) as it relates directly to the conditions of the proposed research and development activity.

(e) Persons applying for a TERA must also submit the following information about the proposed research and development activity:

(1) *A detailed description of the proposed research and development activity.*

(i) The objectives and significance of the activity and a rationale for testing the microorganisms in the environment.

(ii) Number of microorganisms released (including viability per volume if applicable) and the method(s) of application or release.

(iii) Characteristics of the test site(s), including location, geographical, physical, chemical, and biological features, proximity to human habitation or activity, and description of site characteristics that would influence dispersal or confinement.

(iv) Target organisms (if the microorganism(s) to be tested has an intended target), including identification of each target organism and anticipated mechanism and result of interaction.

(v) Planned start date and duration of each activity.

(vi) If State and/or local authorities have been notified of the activity, evidence of notification.

(2) *Information on monitoring, confinement, mitigation, and emergency termination procedures.* (i) Confinement procedures for the activity, access and security measures, and procedures for routine termination of the activity.

(ii) Mitigation and emergency procedures.

(iii) Measures to detect and control potential adverse effects.

(iv) Name of principal investigator and chief of site personnel responsible for emergency procedures.

(v) Personal protective equipment, engineering controls, and procedures to be followed to minimize dispersion of the microorganism(s) by people, machinery, or equipment.

(vi) Procedures for disposal of any articles, waste, clothing, machinery, or other equipment involved in the experimental release, including methods for inactivation of the microorganism(s), containment, disinfection, and disposal of contaminated items.

## Environmental Protection Agency

## § 725.288

### § 725.260 Submission of health and environmental effects data.

Each TERA must contain all available data concerning actual or potential effects on health or the environment of the new microorganism that are in the possession or control of the submitter and a description of other data known to or reasonably ascertainable by the submitter that will permit a reasoned evaluation of the planned test in the environment. The data must be reported in the manner described in § 725.160(a)(3) and (b)(3).

### § 725.270 EPA review of the TERA.

General procedures for review of all submissions under this part are contained in §§ 725.28 through 725.60. In addition, the following procedures apply to EPA review of applications submitted under this subpart:

(a) *Length of the review period.* (1) The review period for the TERA will be 60 days from the date the Document Control Officer for the Office of Pollution Prevention and Toxics receives a complete TERA, or the date EPA determines the TERA is complete under § 725.33, unless EPA finds good cause for an extension under § 725.56.

(2) A submitter shall not proceed with the research and development activity described in the TERA unless and until EPA provides written approval of the TERA. A submitter may receive early approval if a review is completed in less than 60 days.

(b) *EPA decision regarding proposed TERA activity.* (1) A decision concerning a TERA under this subpart will be made by the Administrator, or a designee.

(2) If EPA determines that the proposed research and development activity for the microorganism does not present an unreasonable risk of injury to health or the environment, EPA will notify the submitter that the TERA is approved and that the submitter can proceed with the proposed research and development activity described in the TERA.

(3) EPA may include requirements and conditions in its approval of the TERA that would be stated in the TERA approval under paragraph (c) of this section.

(4) If EPA concludes that it cannot determine that the proposed research and development activity described in the TERA will not present an unreasonable risk of injury to health or the environment, EPA will deny the TERA and will provide reasons for the denial in writing.

(c) *TERA approval.* (1) A TERA approval issued by EPA under this section is legally binding on the TERA submitter.

(2) When EPA approves a TERA, the submitter must conduct the research and development activity only as described in the TERA and in accordance with any requirements and conditions prescribed by EPA in its approval of the TERA.

(3) Any person who fails to conduct the research and development activity as described in the TERA and in accordance with any requirements and conditions prescribed by EPA in its approval of the TERA under this section, shall be in violation of sections 5 and 15 of the Act and be subject to civil and criminal penalties under section 16 of the Act.

### § 725.288 Revocation or modification of TERA approval.

(a) *Significant questions about risk.* (1) If, after approval of a TERA under this subpart, EPA receives information which raises significant questions about EPA's determination that the activity does not present an unreasonable risk of injury to health or the environment, EPA will notify the submitter in writing of those questions.

(2) The submitter may, within 10 days of receipt of EPA's notice, provide in writing additional information or arguments concerning the significance of the questions and whether EPA should modify or revoke the approval of the TERA.

(3) After considering any such information and arguments, EPA will decide whether to change its determination regarding approval of the TERA.

(i) If EPA determines that the activity will not present an unreasonable risk of injury to health or the environment, it will notify the submitter in writing. To make this finding, EPA may prescribe additional conditions



## § 725.300

which must be followed by the submitter.

(ii) If EPA determines that it can no longer conclude that the activity will not present an unreasonable risk of injury to health or the environment, it will notify the submitter in writing that EPA is revoking its approval and state its reasons. In that event, the submitter must terminate the research and development activity within 48 hours of receipt of the notice in accordance with directions provided by EPA in the notice.

(b) *Evidence of unreasonable risk.* (1) If, after approval of a TERA under this subpart, EPA determines that the proposed research and development activity will present an unreasonable risk of injury to health or the environment, EPA will notify the submitter in writing and state its reasons.

(2) In the notice, EPA may prescribe additional safeguards to address or reduce the risk, or may instruct the submitter to suspend the research and development activities.

(3) Within 48 hours, the submitter must implement the instructions contained in the notice. The submitter may then submit additional information or arguments concerning the matters raised by EPA and whether EPA should modify or revoke the approval of the TERA in accordance with paragraph (a)(2) of this section.

(4) EPA will consider the information and arguments in accordance with paragraph (a)(3) of this section.

(5) Following consideration of the information and arguments under paragraph (a)(3) of this section, if EPA notifies the submitter that the R&D activity must be suspended or terminated, the submitter may resume the activity only upon written notice from EPA that EPA has approved resumption of the activity. In approving resumption of an activity, EPA may prescribe additional conditions which must be followed by the submitter.

(c) *Modifications.* If, after approval of a TERA under this subpart, the submitter concludes that it is necessary to alter the conduct of the research and development activity in a manner which would result in the activity being different from that described in the TERA agreement and any condi-

## 40 CFR Ch. I (7-1-10 Edition)

tions EPA prescribed in its approval, the submitter must inform the EPA contact for the TERA and may not modify the activity without the approval of EPA.

### Subpart F—Exemptions for Test Marketing

#### § 725.300 Scope and purpose.

(a) This subpart describes exemptions from the reporting requirements under subpart D of this part for test marketing activities involving microorganisms.

(b) In lieu of complying with subpart D of this part, persons described in § 725.305 may submit an application for a test marketing exemption (TME).

(c) Submission requirements specific for TME applications are described at § 725.350.

(d) Data requirements for TME applications are set forth in § 725.355.

(e) EPA review procedures specific for TMEs are set forth in § 725.370.

(f) Subparts A through C of this part apply to any submission under this subpart.

#### § 725.305 Persons who may apply under this subpart.

A person identified in this section may apply for a test marketing exemption. EPA may grant the exemption if the person demonstrates that the microorganism will not present an unreasonable risk of injury to health or the environment as a result of the test marketing. A person may apply under this subpart for the following test marketing activities:

(a) A person who intends to manufacture or import for commercial purposes a new microorganism.

(b) A person who intends to manufacture, import, or process for commercial purposes a microorganism identified in subpart M of this part for a significant new use.

#### § 725.350 Procedural requirements for this subpart.

General requirements for all submissions under this part are contained in subparts A through C of this part. In addition, the following requirements apply to applications submitted under this subpart:

## Environmental Protection Agency

## § 725.400

(a) *Prenotice consultation.* EPA strongly suggests that for a TME, the applicant contact EPA for a prenotice consultation regarding eligibility for a TME.

(b) *When to submit a TME application.* Each person who is eligible to apply for a TME under this subpart must submit the application at least 45 calendar days before the person intends to commence the test marketing activity.

(c) *Recordkeeping.* Each person who is granted a TME must comply with the recordkeeping requirements of § 725.65. In addition, any person who obtains a TME must retain documentation of compliance with any restrictions imposed by EPA when it grants the TME. This information must be retained for 3 years from the final date of manufacture or import under the exemption.

### § 725.355 Information to be included in the TME application.

(a) To review a TME application, EPA must have sufficient information to permit a reasoned evaluation of the health and environmental effects of the planned test marketing activity. The person seeking EPA approval must submit all information known to or reasonably ascertainable by the person on the microorganism and the test marketing activity, including information not listed in paragraphs (c), (d), and (e) of this section that the person believes will demonstrate that the microorganism will not present an unreasonable risk of injury to health or the environment as a result of the test marketing. The TME application must be in writing and must include at least the information described in paragraphs (b), (c), (d), and (e) of this section.

(b) When specific information is not submitted, an explanation of why such information is not available or not applicable must be included.

(c) Persons applying for a TME must submit the submitter identification and microorganism identity information required for MCANs in § 725.155(c), (d)(1), and (d)(2).

(d) Persons applying for a TME must submit phenotypic and ecological characteristics information required in § 725.155(d)(3) as it relates directly to the conditions of the proposed test marketing activity.

(e) Persons applying for a TME must also submit the following information about the proposed test marketing activity:

(1) *Proposed test marketing activity.* (i) The maximum quantity of the microorganism which the applicant will manufacture or import for test marketing.

(ii) The maximum number of persons who may be provided the microorganism during test marketing.

(iii) The maximum number of persons who may be exposed to the microorganism as a result of test marketing, including information regarding duration and route of such exposures.

(iv) A description of the test marketing activity, including its duration and how it can be distinguished from full-scale commercial production and research and development activities.

(2) *Health and environmental effects data.* All existing data regarding health and environmental effects of the microorganism must be reported in accordance with § 725.160.

### § 725.370 EPA review of the TME application.

General procedures for review of all submissions under this part are contained in §§ 725.28 through 725.60. In addition, the following procedures apply to EPA review of TME applications submitted under this subpart:

(a) No later than 45 days after EPA receives a TME, the Agency will either approve or deny the application.

(b) A submitter may only proceed with test marketing activities after receipt of EPA approval.

(c) In approving a TME application, EPA may impose any restrictions necessary to ensure that the microorganism will not present an unreasonable risk of injury to health and the environment as a result of test marketing.

## Subpart G—General Exemptions for New Microorganisms

### § 725.400 Scope and purpose.

(a) This subpart describes exemptions from reporting under subpart D of this part, and from review under this part altogether, for manufacturing and importing of certain new microorganisms for commercial purposes.

## § 725.420

(b) Recipient microorganisms eligible for the tiered exemption from review under this part are listed in § 725.420.

(c) Criteria for the introduced genetic material contained in the new microorganisms are described in § 725.421.

(d) Physical containment and control technologies are described in § 725.422.

(e) The conditions for the Tier I exemption are listed in § 725.424.

(f) In lieu of complying with subpart D of this part, persons using recipient microorganisms eligible for the tiered exemption may submit a Tier II exemption request. The limited reporting requirements for the Tier II exemption, including data requirements, are described in §§ 725.450 and 725.455.

(g) EPA review procedures for the Tier II exemption are set forth in § 725.470.

(h) Subparts A through C of this part apply to any submission under this subpart.

### § 725.420 Recipient microorganisms.

The following recipient microorganisms are eligible for either exemption under this subpart:

- (a) *Acetobacter aceti*.
- (b) *Aspergillus niger*.
- (c) *Aspergillus oryzae*.
- (d) *Bacillus licheniformis*.
- (e) *Bacillus subtilis*.
- (f) *Clostridium acetobutylicum*.
- (g) *Escherichia coli* K-12.
- (h) *Penicillium roqueforti*.
- (i) *Saccharomyces cerevisiae*.
- (j) *Saccharomyces uvarum*.

### § 725.421 Introduced genetic material.

For a new microorganism to qualify for either exemption under this subpart, introduced genetic material must meet all of the criteria listed in this section.

(a) *Limited in size*. The introduced genetic material must consist only of the following:

- (1) The structural gene(s) of interest.
- (2) The regulatory sequences permitting the expression of solely the gene(s) of interest.
- (3) Associated nucleotide sequences needed to move genetic material, including linkers, homopolymers, adaptors, transposons, insertion sequences, and restriction enzyme sites.

## 40 CFR Ch. I (7-1-10 Edition)

(4) The nucleotide sequences needed for vector transfer.

(5) The nucleotide sequences needed for vector maintenance.

(b) *Well-characterized*. For introduced genetic material, well-characterized means that the following have been determined:

(1) The function of all of the products expressed from the structural gene(s).

(2) The function of sequences that participate in the regulation of expression of the structural gene(s).

(3) The presence or absence of associated nucleotide sequences and their associated functions, where associated nucleotide sequences are those sequences needed to move genetic material including linkers, homopolymers, adaptors, transposons, insertion sequences, and restriction enzyme sites.

(c) *Poorly mobilizable*. The ability of the introduced genetic material to be transferred and mobilized is inactivated, with a resulting frequency of transfer of less than  $10^{-8}$  transfer events per recipient.

(d) *Free of certain sequences*. (1) The introduced genetic material must not contain a functional portion of any of the toxin-encoding sequences described in this paragraph (d).

(i) For the purposes of this section, a functional portion of a toxin-encoding sequence means any sequence which codes for a polypeptide that has one of the following effects:

(A) It directly or indirectly contributes to toxic effects in humans. Directly contributes to toxic effects in humans means those sequences encoding polypeptides that have direct toxicity to target cells. An example of a sequence which directly contributes to toxic effects in humans is one which encodes the portion of diphtheria toxin, listed in paragraph (d)(2) of this section, capable of interacting with elongation factor 2, leading to inhibition of protein synthesis in target respiratory, heart, kidney, and nerve tissues. Indirectly contributes to toxic effects in humans means a sequence whose encoded polypeptide is not directly toxic to target cells, yet still adversely affects humans. An example of a sequence which indirectly contributes to toxic effects is the sequence

**Environmental Protection Agency**

**§ 725.421**

which encodes the portion of the botulinum toxin, listed in paragraph (d)(3) of this section, capable of blocking the release of acetylcholine from gangliosides. Botulinum toxin affects neuromuscular junctions by its blockage of acetylcholine release, leading to irreversible relaxation of muscles and respiratory arrest.

(B) It binds a toxin or toxin precursor to target human cells.

(C) It facilitates intracellular transport of a toxin in target human cells.

(ii) While these toxins are listed (with synonyms in parentheses) in paragraphs (d)(2) through (d)(7) of this section according to the source organism, it is use of the nucleotide sequences that encode the toxins that is being restricted and not the use of the source organisms. The source organisms are listed to provide specificity in identification of sequences whose use is restricted. Although similar or identical sequences may be isolated from organisms other than those listed below in paragraphs (d)(2) through (d)(7) of this section, these comparable toxin sequences, regardless of the organism from which they are derived, must not be included in the introduced genetic material.

(2) *Sequences for protein synthesis inhibitor.*

| Sequence Source   | Toxin Name   |
|---|--|
| <i>Corynebacterium diphtheriae</i> & <i>C. ulcerans</i> | Diphtheria toxin   |
| <i>Pseudomonas aeruginosa</i>                           | Exotoxin A   |
| <i>Shigella dysenteriae</i>                             | Shigella toxin (Shiga toxin, Shigella dysenteriae type I toxin, Vero cell toxin) |
| <i>Abrus precatorius</i> , seeds                        | Abrin  |
| <i>Ricinus communis</i> , seeds                         | Ricin  |

(3) *Sequences for neurotoxins.*

| Sequence Source              | Toxin Name  |
|------------------------------|---|
| <i>Clostridium botulinum</i> | Neurotoxins A, B, C1, D, E, F, G (Botulinum toxins, botulinal toxins) |
| <i>Clostridium tetani</i>    | Tetanus toxin (tetanospasmin)   |
| <i>Proteus mirabilis</i>     | Neurotoxin  |
| <i>Staphylococcus aureus</i> | Alpha toxin (alpha lysin)   |
| <i>Yersinia pestis</i>       | Murine toxin  |
| Snake toxins                 |   |
| <i>Bungarus caeruleus</i>    | Caeruleotoxin   |
| <i>Bungarus multicinctus</i> | Beta-bungarotoxin (phospholipase)                                     |
| <i>Crotalus</i> spp.         | Crototoxin (phospholipase)  |
| <i>Dendroaspis viridis</i>   | Neurotoxin  |
| <i>Naja naja</i> varieties   | Neurotoxin  |
| <i>Notechia scutatus</i>     | Notexin (phospholipase)   |
| <i>Oxyuranus scutellatus</i> | Taipoxin  |

| Sequence Source                  | Toxin Name |
|----------------------------------|------------|
| Invertebrate toxins              |            |
| <i>Chironex fleckeri</i>         | Neurotoxin |
| <i>Androctonus australis</i>     | Neurotoxin |
| <i>Centruroides sculpturatus</i> | Neurotoxin |

(4) *Sequences for oxygen labile cytolysins.*

| Sequence Source                 | Toxin Name                   |
|---------------------------------|------------------------------|
| <i>Bacillus alve</i>            | Alveolysin                   |
| <i>Bacillus cereus</i>          | Cereolysin                   |
| <i>Bacillus laterosporus</i>    | Laterosporolysin             |
| <i>Bacillus thuringiensis</i>   | Thuringiolysin               |
| <i>Clostridium bifermentans</i> | Lysin                        |
| <i>Clostridium botulinum</i>    | Lysin                        |
| <i>Clostridium caproicum</i>    | Lysin                        |
| <i>Clostridium chauvoei</i>     | Delta-toxin                  |
| <i>Clostridium histolyticum</i> | Epsilon-toxin                |
| <i>Clostridium novyi</i>        | Gamma-toxin                  |
| <i>Clostridium oedematiens</i>  | Delta-toxin                  |
| <i>Clostridium perfringens</i>  | Theta-toxin (Perfringolysin) |
| <i>Clostridium septicum</i>     | Delta-toxin                  |
| <i>Clostridium sordellii</i>    | Lysin                        |
| <i>Clostridium tetani</i>       | Tetanolysin                  |
| <i>Listeria monocytogenes</i>   | Listeriolysin (A B)          |
| <i>Streptococcus pneumoniae</i> | Pneumolysin                  |
| <i>Streptococcus pyogenes</i>   | Streptolysin O (SLO)         |

(5) *Sequences for toxins affecting membrane function.*

| Sequence Source   | Toxin Name   |
|---|--|
| <i>Bacillus anthracis</i>                               | Edema factor (Factors I II); Lethal factor (Factors II III)  |
| <i>Bacillus cereus</i>                                  | Enterotoxin (diarrheagenic toxin, mouse lethal factor)   |
| <i>Bordetella pertussis</i>                             | Adenylate cyclase (Heat-labile factor); Pertussigen (pertussis toxin, islet activating factor, histamine sensitizing factor, lymphocytosis promoting factor) |
| <i>Clostridium botulinum</i>                            | C2 toxin   |
| <i>Clostridium difficile</i>                            | Enterotoxin (toxin A)  |
| <i>Clostridium perfringens</i>                          | Beta-toxin; Delta-toxin  |
| <i>Escherichia coli</i> & other Enterobacteriaceae spp. | Heat-labile enterotoxins (LT); Heat-stable enterotoxins (STa, ST1 subtypes ST1a ST1b; also STb, STII)  |
| <i>Legionella pneumophila</i>                           | Cytolysin  |
| <i>Vibrio cholerae</i> & <i>Vibrio mimicus</i>          | Cholera toxin (choleraegen)  |

(6) *Sequences that affect membrane integrity.*

| Sequence Source   | Toxin Name   |
|---|--|
| <i>Clostridium bifermentans</i> & other <i>Clostridium</i> spp      | Lecithinase  |
| <i>Clostridium perfringens</i>                                      | Alpha-toxin (phospholipase C, lecithinase); Enterotoxin      |
| <i>Corynebacterium pyogenes</i> & other <i>Corynebacterium</i> spp. | Cytolysin (phospholipase C), Ovis toxin (sphingomyelinase D) |
| <i>Staphylococcus aureus</i>  | Beta-lysin (beta toxin)                                      |

(7) *Sequences that are general cytotoxins.*

**§ 725.422**

**40 CFR Ch. I (7–1–10 Edition)**

| Sequence Source  | Toxin Name  |
|--|---|
| <i>Adenia digitata</i>   | Modeccin  |
| <i>Aeromonas hydrophila</i>                                    | Aerolysin (beta-lysin, cytotoxic lysin)   |
| <i>Clostridium difficile</i>                                   | Cytotoxin (toxin B)   |
| <i>Clostridium perfringens</i>                                 | Beta-toxin; Epsilon-toxin; Kappa-toxin  |
| <i>Escherichia coli</i> & other <i>Enterobacteriaceae</i> spp. | Cytotoxin (Shiga-like toxin, Vero cell toxin)   |
| <i>Pseudomonas aeruginosa</i>                                  | Proteases   |
| <i>Staphylococcus aureus</i>                                   | Gamma lysin (Gamma toxin); Enterotoxins (SEA, SEB, SEC, SED SEE); Pyrogenic exotoxins A B; Toxic shock syndrome toxins (TSST-1) |
| <i>Staphylococcus aureus</i> & <i>Pseudomonas aeruginosa</i>   | Leucocidin (leukocidin, cytotoxin)  |
| <i>Streptococcus pyogenes</i>                                  | Streptolysin S (SLS); Erythrogenic toxins (scarlet fever toxins, pyrogenic exotoxins)   |
| <i>Yersinia enterocolitica</i>                                 | Heat-stable enterotoxins (ST)   |

**§ 725.422 Physical containment and control technologies.**

The manufacturer must meet all of the following criteria for physical containment and control technologies for any facility in which the new microorganism will be used for a Tier I exemption; these criteria also serve as guidance for a Tier II exemption.

- (a) Use a structure that is designed and operated to contain the new microorganism.
- (b) Control access to the structure.
- (c) Provide written, published, and implemented procedures for the safety of personnel and control of hygiene.
- (d) Use inactivation procedures demonstrated and documented to be effective against the new microorganism contained in liquid and solid wastes prior to disposal of the wastes. The inactivation procedures must reduce viable microbial populations by at least 6 logs in liquid and solid wastes.
- (e) Use features known to be effective in minimizing viable microbial populations in aerosols and exhaust gases released from the structure, and document use of such features.
- (f) Use systems for controlling dissemination of the new microorganism through other routes, and document use of such features.
- (g) Have in place emergency clean-up procedures.

**§ 725.424 Requirements for the Tier I exemption.**

(a) *Conditions of exemption.* The manufacture or import of a new microorganism

for commercial purposes is not subject to review under this part if all of the following conditions are met for all activities involving the new microorganism:

- (1) The recipient microorganism is listed in and meets any requirements specified in § 725.420.
- (2) The introduced genetic material meets the criteria under § 725.421.
- (3) The physical containment and control technologies of any facility in which the microorganism will be manufactured, processed, or used meet the criteria under § 725.422.
- (4) The manufacturer or importer submits a certification described in paragraph (b) of this section to EPA at least 10 days before commencing initial manufacture or import of a new microorganism derived from a recipient microorganism listed in § 725.420.

(5) The manufacturer or importer complies with the recordkeeping requirements of § 725.65 and maintains records for the initial and subsequent uses of the new microorganism that verify compliance with the following:

- (i) The certifications made in paragraph (b) of this section.
- (ii) All the eligibility criteria for the Tier I exemption including the criteria for the recipient microorganism, the introduced genetic material, the physical containment and control technologies.

(b) *Certification.* To be eligible for the Tier I exemption under this subpart, the manufacturer or importer must submit to EPA a document signed by a responsible company official containing the information listed in this paragraph.

- (1) Name and address of manufacturer or importer.
- (2) Date when manufacture or import is expected to begin.
- (3) The identification (genus, species) of the recipient microorganism listed in § 725.420 which is being used to create the new microorganism which will be used under the conditions of the Tier I exemption.

(4) Certification of the following:

- (i) Compliance with the introduced genetic material criteria described in § 725.421.

## Environmental Protection Agency

## § 725.455

(ii) Compliance with the containment requirements described in § 725.422, including the provision in paragraph (a)(3) of this section.

(5) The site of waste disposal and the type of permits for disposal, the permit numbers and the institutions issuing the permits.

(6) The certification statement required in § 725.25(b). Certification of submission of test data is not required for the Tier I exemption.

### § 725.426 Applicability of the Tier I exemption.

The Tier I exemption under § 725.424 applies only to a manufacturer or importer of a new microorganism that certifies that the microorganism will be used in all cases in compliance with §§ 725.420, 725.421, and 725.422.

### § 725.428 Requirements for the Tier II exemption.

The manufacturer or importer of a new microorganism for commercial purposes may submit to EPA a Tier II exemption request in lieu of a MCAN under subpart D of this part if all of the following conditions are met:

(a) The recipient microorganism is listed in and meets any requirements specified in § 725.420.

(b) The introduced genetic material meets the criteria under § 725.421.

(c) Adequate physical containment and control technologies are used. The criteria listed under § 725.422 for physical containment and control technologies of facilities should be used as guidance to satisfy the Tier II exemption request data requirements listed at § 725.455(d). EPA will review proposed process and containment procedures as part of the submission for a Tier II exemption under this section.

### § 725.450 Procedural requirements for the Tier II exemption.

General requirements for all submissions under this part are contained in § 725.25. In addition, the following requirements apply to requests submitted under this subpart:

(a) *Prenotice consultation.* EPA strongly suggests that for a Tier II exemption, the submitter contact the Agency for a prenotice consultation regarding eligibility for the exemption.

(b) *When to submit the Tier II exemption request.* Each person who is eligible to submit a Tier II exemption request under this subpart must submit the request at least 45 calendar days before the person intends to commence manufacture or import.

(c) *Contents of the Tier II exemption request.* Each person who submits a request under this subpart must provide the information described in §§ 725.428 and 725.455, as well as information known to or reasonably ascertainable by the person that would permit EPA to determine that use of the microorganism, under the conditions specified in the request, will not present an unreasonable risk of injury to health or the environment.

(d) *Recordkeeping.* Each person who submits a request under this subpart must comply with the recordkeeping requirements of § 725.65. In addition, the submitter should maintain records which contain information that verifies compliance with the following:

(1) The certifications made in the request.

(2) All the eligibility criteria for the Tier II exemption request including the criteria for the recipient microorganism, the introduced genetic material, the physical containment and control technologies.

### § 725.455 Information to be included in the Tier II exemption request.

The submitter must indicate clearly that the submission is a Tier II exemption request for a microorganism instead of the MCAN under subpart D of this part and must submit the following information:

(a) *Submitter identification.* (1) The name and headquarters address of the submitter.

(2) The name, address, and office telephone number (including area code) of the principal technical contact representing the submitter.

(b) *Microorganism identity information.* (1) Identification (genus, species, and strain) of the recipient microorganism. Genus, species designation should be substantiated by a letter from a culture collection or a brief summary of the results of tests conducted for taxonomic identification.

**§ 725.470**

**40 CFR Ch. I (7–1–10 Edition)**

(2) Type of genetic modification and the function of the introduced genetic material.

(3) Site of insertion.

(4) Certification of compliance with the introduced genetic material criteria described in § 725.421.

(c) *Production volume.* Production volume, including total liters per year, and the maximum cell concentration achieved during the production process.

(d) *Process and containment information.* (1) A description of the process including the following:

(i) Identity and location of the manufacturing site(s).

(ii) Process flow diagram illustrating the production process, including downstream separations, and indicating the containment envelope around the appropriate equipment.

(iii) Identities and quantities of feedstocks.

(iv) Sources and quantities of potential releases to both the workplace and environment, and a description of engineering controls, inactivation procedures, and other measures which will reduce worker exposure and environmental releases.

(v) A description of procedures which will be undertaken to prevent fugitive emissions, i.e. leak detection and repair program.

(vi) A description of procedures/safeguards to prevent and mitigate accidental releases to the workplace and the environment.

(2) Certification of those elements of the containment criteria described in § 725.422 with which the manufacturer is in compliance, including stating by number the elements with which the manufacturer is in full compliance.

(e) The site of waste disposal and the type of permits for disposal, the permit numbers and the institutions issuing the permits.

(f) The certification statement required in § 725.25(b). Certification of submission of test data is not required for the Tier II exemption.

**§ 725.470 EPA review of the Tier II exemption request.**

General procedures for review of all submissions under this part are contained in §§ 725.28 through 725.60. In ad-

dition, the following procedures apply to EPA review of Tier II exemption requests submitted under this subpart:

(a) *Length of the review period.* The review period for the request will be 45 days from the date the Document Control Officer for the Office of Pollution Prevention and Toxics receives a complete request, or the date EPA determines the request is complete under § 725.33, unless the Agency extends the review period for good cause under § 725.56.

(b) *Criteria for review.* EPA will review the request to determine that the new microorganism complies with § 725.428 and that its manufacture, processing, use, and disposal as described in the request will not present an unreasonable risk of injury to health or the environment.

(c) *EPA decision regarding the Tier II exemption request.* A decision concerning a request under this subpart will be made by the Administrator, or a designee.

(d) *Determination that the microorganism is ineligible for a Tier II review.* (1) EPA may determine that the manufacturer or importer is not eligible for Tier II review, because the microorganism does not meet the criteria under § 725.428 or the Administrator, or a designee, decides that there is insufficient information to determine that the conditions of manufacture, processing, use, or disposal of the microorganism as described in the request will not present an unreasonable risk to health or the environment.

(2) If the Agency makes this determination, the Administrator, or a designee will notify the manufacturer or importer by telephone, followed by a letter, that the request has been denied. The letter will explain reasons for the denial.

(3) If the request is denied, the manufacturer or importer may submit the information necessary to constitute a MCAN under subpart D of this part.

(e) *Approval or denial of the Tier II exemption request.* (1) No later than 45 days after EPA receives a request, the Agency will either approve or deny the request.

(2) In approving a request, EPA may impose any restrictions necessary to ensure that the microorganism will not

present an unreasonable risk of injury to health and the environment as a result of general commercial use.

(f) EPA may seek to enjoin the manufacture or import of a microorganism in violation of this subpart, or act to seize any microorganism manufactured or imported in violation of this section or take other actions under the authority of sections 7 or 17 of the Act.

(g) A manufacturer or importer may only proceed after receipt of EPA approval.

### Subparts H–K [Reserved]

### Subpart L—Additional Procedures for Reporting on Significant New Uses of Microorganisms

#### § 725.900 Scope and purpose.

(a) This subpart describes additional provisions governing submission of MCANs for microorganisms subject to significant new use rules identified in subpart M of this part.

(b) Manufacturers, importers, and processors described in § 725.105(c) must submit a MCAN under subpart D of this part for significant new uses of microorganisms described in subpart M of this part, unless they are excluded under §§ 725.910 or 725.912.

(c) Section 725.920 discusses exports and imports.

(d) Additional recordkeeping requirements specific to significant new uses of microorganisms are described in § 725.950.

(e) Section 725.975 describes how EPA will approve alternative means of complying with significant new use requirements designated in subpart M of this part.

(f) Expedited procedures for promulgating significant new use requirements under subpart M of this part for microorganisms subject to section 5(e) orders are discussed in §§ 725.980 and 725.984.

(g) This subpart L contains provisions governing submission and review of notices for the microorganisms and significant new uses identified in subpart M of this part. The provisions of this subpart L apply to the microorganisms and significant new uses identified in subpart M of this part, except to

the extent that they are specifically modified or supplanted by specific requirements in subpart M of this part. In the event of a conflict between the provisions of this subpart L and the provisions of subpart M of this part, the provisions of subpart M of this part shall govern.

(h) The provisions of subparts A through F of this part also apply to subparts L and M of this part. For purposes of subparts L and M of this part, wherever the words “microorganism” or “new microorganism” appear in subparts A through F of this part, it shall mean the microorganism subject to subparts L and M of this part. In the event of a conflict between the provisions of subparts A through F and the provisions of subparts L and M of this part, the provisions of subparts L and M of this part shall govern.

#### § 725.910 Persons excluded from reporting significant new uses.

(a) A person who intends to manufacture, import, or process a microorganism identified in subpart M of this part and who intends to distribute it in commerce is not required to submit a MCAN under subpart D of this part, if that person can document one or more of the following as to each recipient of the microorganism from that person:

(1) That the person has notified the recipient, in writing, of the specific section in subpart M of this part which identifies the microorganism and its designated significant new uses, or

(2) That the recipient has knowledge of the specific section in subpart M of this part which identifies the microorganism and its designated significant new uses, or

(3) That the recipient cannot undertake any significant new use described in the specific section in subpart M of this part.

(b) The manufacturer, importer, or processor described in paragraph (a) of this section must submit a MCAN under subpart D of this part, if such person has knowledge at the time of commercial distribution of the microorganism identified in the specific section in subpart M of this part that a recipient intends to engage in a designated significant new use of that



**§ 725.912**

**40 CFR Ch. I (7-1-10 Edition)**

microorganism without submitting a MCAN under this part.

(c) A person who processes a microorganism identified in a specific section in subpart M of this part for a significant new use of that microorganism is not required to submit a MCAN if that person can document each of the following:

(1) That the person does not know the specific microorganism identity of the microorganism being processed, and

(2) That the person is processing the microorganism without knowledge that the microorganism is identified in subpart M of this part.

(d)(1) If at any time after commencing distribution in commerce of a microorganism identified in a specific section in subpart M of this part, a person who manufactures, imports, or processes a microorganism described in subpart M of this part and distributes it in commerce has knowledge that a recipient of the microorganism is engaging in a significant new use of that microorganism designated in that section without submitting a MCAN under this part, the person is required to cease supplying the microorganism to that recipient and to submit a MCAN for that microorganism and significant new use, unless the person is able to document each of the following:

(i) That the person has notified the recipient and EPA enforcement authorities (at the address in paragraph (d)(1)(iii) of this section), in writing within 15 working days of the time the person develops knowledge that the recipient is engaging in a significant new use, that the recipient is engaging in a significant new use without submitting a MCAN.

(ii) That, within 15 working days of notifying the recipient as described in paragraph (d)(1)(i) of this section, the person received from the recipient, in writing, a statement of assurance that the recipient is aware of the terms of the applicable section in subpart M of this part and will not engage in the significant new use.

(iii) That the person has promptly provided EPA enforcement authorities with a copy of the recipient's statement of assurance described in paragraph (d)(1)(ii) of this section. The copy must be sent to the Director, Office of

Compliance (2221A), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460.

(2) If EPA notifies the manufacturer, importer, or processor that the recipient is engaging in a significant new use after providing the statement of assurance described in paragraph (d)(1)(ii) of this section and without submitting a MCAN under this part, the manufacturer, importer, or processor shall immediately cease distribution to that recipient until the manufacturer, importer, or processor or the recipient has submitted a MCAN under this part and the MCAN review period has ended.

(3) If, after receiving a statement of assurance from a recipient under paragraph (d)(1)(ii) of this section, a manufacturer, importer, or processor has knowledge that the recipient is engaging in a significant new use without submitting a MCAN under this part, the manufacturer, importer, or processor must immediately cease distributing the microorganism to that recipient and notify EPA enforcement authorities at the address identified in paragraph (d)(1)(iii) of this section. The manufacturer, importer, or processor may not resume distribution to that recipient until any one of the following has occurred:

(i) The manufacturer, importer, or processor has submitted a MCAN under this part and the MCAN review period has ended.

(ii) The recipient has submitted a MCAN under this part and the MCAN review period has ended.

(iii) The manufacturer, importer, or processor has received notice from EPA enforcement authorities that it may resume distribution to that recipient.

**§ 725.912 Exemptions.**

Persons identified in § 725.105(c) are not required to submit a MCAN under subpart D of this part for a microorganism identified in subpart M of this part, unless otherwise specified in a specific section in subpart M, if:

(a) The person submits a MCAN for the microorganism prior to the promulgation date of the section in subpart M of this part which identifies the microorganism, and the person receives written notification of compliance from EPA prior to the effective

## Environmental Protection Agency

## § 725.975

date of such section. The MCAN submitter must comply with any applicable requirement of section 5(b) of the Act. The MCAN must include the information and test data specified in section 5(d)(1) of the Act. For purposes of this exemption, the specific section in subpart M of this part which identifies the microorganism and §§ 725.3, 725.15, 725.65, 725.70, 725.75, 725.100, and 725.900 apply; after the effective date of the section in subpart M of this part which identifies the microorganism, §§ 725.105 and 725.910 apply and § 725.920 continues to apply. EPA will provide the MCAN submitter with written notification of compliance only if one of the following occurs:

(1) EPA is unable to make the finding that the activities described in the MCAN will or may present an unreasonable risk of injury to health or the environment under reasonably foreseeable circumstances, or

(2) EPA and the person negotiate a consent order under section 5(e) of the Act, such order to take effect on the effective date of the section in subpart M of this part which identifies the microorganism.

(b) The person is operating under the terms of a consent order issued under section 5(e) of the Act applicable to that person. If a provision of such section 5(e) order is inconsistent with a specific significant new use identified in subpart M of this part, abiding by the provision of the section 5(e) order exempts the person from submitting a MCAN for that specific significant new use.

### § 725.920 Exports and imports.

(a) *Exports.* Persons who intend to export a microorganism identified in subpart M of this part, or in any proposed rule which would amend subpart M of this part, are subject to the export notification provisions of section 12(b) of the Act. The regulations that interpret section 12(b) appear at part 707 of this chapter.

(b) *Imports.* Persons who import a substance identified in a specific section in subpart M of this part are subject to the import certification requirements under section 13 of the Act, which are codified at 19 CFR §§ 12.118 through 12.127 and 127.28(i). The EPA

policy in support of the import certification requirements appears at part 707 of this chapter.

### § 725.950 Additional recordkeeping requirements.

Persons submitting a MCAN for a significant new use of a microorganism must comply with the recordkeeping requirements of § 725.65. In addition, the following requirements apply:

(a) At the time EPA adds a microorganism to subpart M of this part, EPA may specify appropriate recordkeeping requirements. Each manufacturer, importer, and processor of the microorganism shall maintain the records for 3 years from the date of their creation.

(b) The records required to be maintained under this section may include the following:

(1) Records documenting the information contained in the MCAN submitted to EPA.

(2) Records documenting the manufacture and importation volume of the microorganism and the corresponding dates of manufacture and import.

(3) Records documenting volumes of the microorganism purchased domestically by processors of the microorganism, names and addresses of suppliers and corresponding dates of purchase.

(4) Records documenting the names and addresses (including shipment destination address, if different) of all persons outside the site of manufacture or import to whom the manufacturer, importer, or processor directly sells or transfers the microorganism, the date of each sale or transfer, and the quantity of the microorganism sold or transferred on such date.

### § 725.975 EPA approval of alternative control measures.

(a) In certain sections of subpart M of this part, significant new uses for the identified microorganisms are described as the failure to establish and implement programs providing for the use of either: specific measures to control worker exposure to or release of microorganisms which are identified in such sections, or alternative measures to control worker exposure or environmental release which EPA has determined provide substantially the same

degree of protection as the specified control measures. Persons who manufacture, import, or process a microorganism identified in such sections and who intend to employ alternative measures to control worker exposure or environmental release must submit a request to EPA for a determination of equivalency before commencing manufacture, import, or processing involving the alternative control measures.

(b) Persons submitting a request for a determination of equivalency to EPA under this part, unless allowed by § 725.25(c) (1), (2), or (3), must submit the request to EPA via EPA's Central Data Exchange (CDX) using EPA-provided e-PMN software in the manner set forth in § 725.25(c). See 40 CFR 720.40(a)(2)(iv) for information on how to obtain e-PMN software. Support documents related to these requests must also be submitted to EPA via CDX using e-PMN software. If submitted on paper, requests must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001; ATTN: SNUR Equivalency Determination or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004; ATTN: SNUR Equivalency Determination. Optical discs containing electronic requests must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004; ATTN: SNUR Equivalency Determination. A request for a determination of equivalency must contain:

- (1) The name of the submitter.
- (2) The specific identity of the microorganism.
- (3) The citation for the specific section in subpart M of this part which pertains to the microorganism for which the request is being submitted.
- (4) A detailed description of the activities involved.
- (5) The specifications of the alternative worker exposure control meas-

ures or environmental release control measures.

(6) A detailed analysis explaining why such alternative control measures provide substantially the same degree of protection as the specific control measures identified in the specific section in subpart M of this part which pertains to the microorganism for which the request is being submitted.

(7) The data and information described in §§ 725.155 and 725.160. If such data and information have already been submitted to EPA's Office of Pollution Prevention and Toxics, the submitter need only document that it was previously submitted, to whom, and the date it was submitted.

(c) Requests for determinations of equivalency will be reviewed by EPA within 45 days. Determinations under this paragraph will be made by the Director, or a designee. Notice of the results of such determinations will be mailed to the submitter.

(d) If EPA notifies the submitter under paragraph (c) of this section that EPA has determined that the alternative control measures provide substantially the same degree of protection as the specified control measures identified in the specific section of subpart M of this part which pertains to the microorganism for which the request is being submitted, the submitter may commence manufacture, import, or processing in accordance with the specifications for alternative worker exposure control measures or environmental release control measures identified in the submitter's request, and may alter any corresponding notification to workers to reflect such alternative controls. Deviations from the activities described in the EPA notification constitute a significant new use and are subject to the requirements of this part.

[62 FR 17932, April 11, 1997, as amended at 75 FR 790, Jan. 6, 2010]

**§ 725.980 Expedited procedures for issuing significant new use rules for microorganisms subject to section 5(e) orders.**

(a) *Selection of microorganisms.* (1) In accordance with the expedited process specified in this section, EPA will issue

significant new use notification requirements for each new microorganism that, after MCAN review under subpart D of this part, becomes subject to a final order issued under section 5(e) of the Act, except for an order that prohibits manufacture and import of the microorganism, unless EPA determines that significant new use notification requirements are not needed for the microorganism.

(2) If EPA determines that significant new use notifications requirements are not needed for a microorganism that is subject to a final order issued under section 5(e) of the Act, EPA will issue a notice in the FEDERAL REGISTER explaining why the significant new use requirements are not needed.

(b) *Designation of requirements.* (1) The significant new use notification and other specific requirements will be based on and be consistent with the provisions included in the final order issued for the microorganism under section 5(e) of the Act. EPA may also designate additional activities as significant new uses which will be subject to notification.

(2) Significant new use requirements and other specific requirements designated under this section will be listed in subpart M of this part. For each microorganism, subpart M of this part will identify:

- (i) The microorganism name.
- (ii) The activities designated as significant new uses.
- (iii) Other specific requirements applicable to the microorganism, including recordkeeping requirements or any other requirements included in the final section 5(e) order.

(c) *Procedures for issuing significant new use rules—(1) Possible processes.* EPA will issue significant new use rules (SNURs) under this section by one of the following three processes: direct final rulemaking, interim final rulemaking, or notice and comment rulemaking. EPA will use the direct final rulemaking process to issue significant new use rules unless it determines that, in a particular case, one of the other processes is more appropriate.

(2) *Notice in the Federal Register.* FEDERAL REGISTER documents issued to

propose or establish significant new uses under this section will contain the following:

(i) The microorganism identity or, if its specific identity is claimed confidential, an appropriate generic microorganism name and an accession number assigned by EPA.

(ii) The MCAN number.

(iii) A summary of EPA's findings under section 5(e)(1)(A) of the Act for the final order issued under section 5(e).

(iv) Designation of the significant new uses subject to, or proposed to be subject to, notification and any other applicable requirements.

(v) Any modification of subpart L of this part applicable to the specific microorganism and significant new uses.

(vi) If the FEDERAL REGISTER document establishes a final rule, or notifies the public that a final rule will not be issued after public comment has been received, the document will describe comments received and EPA's response.

(3) *Direct final rulemaking.* (i) EPA will use direct final rulemaking to issue a significant new use rule, when specific requirements will be based on and be consistent with the provisions included in the final order issued for the microorganism under section 5(e) of the Act. EPA will issue a final rule in the FEDERAL REGISTER following its decision to develop a significant new use rule under this section for a specific new microorganism.

(ii) The FEDERAL REGISTER document will state that, unless written notice is received by EPA within 30 days of publication that someone wishes to submit adverse or critical comments, the rule will be effective 60 days from the date of publication. The written notice of intent to submit adverse or critical comments should state which SNUR(s) will be the subject of the adverse or critical comments, if several SNURs are established through the direct final rule. If notice is received within 30 days that someone wishes to submit adverse or critical comments, the section(s) of the direct final rule containing the SNUR(s) for which a notice of intent to comment was received will

**§ 725.984**

**40 CFR Ch. I (7-1-10 Edition)**

be withdrawn by EPA issuing a document in the final rule section of the FEDERAL REGISTER, and a proposal will be published in the proposed rule section of the FEDERAL REGISTER. The proposal will establish a 30-day comment period.

(iii) If EPA, having considered any timely comments submitted in response to the proposal, decides to establish notification requirements under this section, EPA will issue a final rule adding the microorganism to subpart M of this part and designating the significant new uses subject to notification.

(4) *Interim final rulemaking.* (i) EPA will use the interim final rulemaking procedure to issue a significant new use rule, when specific requirements will be based on and be consistent with the provisions included in the final order issued for the microorganism under section 5(e) of the Act. The Agency will issue an interim final rule in the FEDERAL REGISTER following its decision to develop a significant new use rule for a specific new microorganism. The document will state EPA's reasons for using the interim final rulemaking procedure.

(A) The significant new use rule will take effect on the date of publication.

(B) Persons will be given 30 days from the date of publication to submit comments.

(ii) Interim final rules issued under this section shall cease to be in effect 180 days after publication unless, within the 180-day period, EPA issues a final rule in the FEDERAL REGISTER responding to any written comments received during the 30-day comment period specified in paragraph (c)(4)(i)(B) of this section and promulgating final significant new use notification requirements and other requirements for the microorganism.

(5) *Notice and comment rulemaking.* (i) EPA will use a notice and comment procedure to issue a significant new use rule, when EPA is designating additional activities which are not provisions included in the final order issued for the microorganism under section 5(e) of the Act as significant new uses which will be subject to notification. EPA will issue a proposal in the FEDERAL REGISTER following its decision to

develop a significant new use rule under this section for a specific new microorganism. Persons will be given 30 days to comment on whether EPA should establish notification requirements for the microorganism under this part.

(ii) If EPA, having considered any timely comments, decides to establish notification requirements under this section, EPA will issue a final rule adding the microorganism to subpart M of this part and designating the significant new uses subject to notification.

(d) *Schedule for issuing significant new use rules.* (1) Unless EPA determines that a significant new use rule should not be issued under this section, EPA will issue a proposed rule, a direct final rule, or an interim final rule within 180 days of receipt of a valid notice of commencement under § 725.190.

(2) If EPA receives adverse or critical significant comments following publication of a proposed or interim final rule, EPA will either withdraw the rule or issue a final rule addressing the comments received.

**§ 725.984 Modification or revocation of certain notification requirements.**

(a) *Criteria for modification or revocation.* EPA may at any time modify or revoke significant new use notification requirements for a microorganism which has been added to subpart M of this part using the procedures of § 725.980. Such action may be taken under this section if EPA makes one of the following determinations, unless other information shows that the requirements should be retained:

(1) Test data or other information obtained by EPA provide a reasonable basis for concluding that activities designated as significant new uses of the microorganism will not present an unreasonable risk of injury to health or the environment.

(2) EPA has promulgated a rule under section 4 or 6 of the Act, or EPA or another agency has taken action under another law, for the microorganism that eliminates the need for significant new use notification under section 5(a)(2) of the Act.

(3) EPA has received MCANs for some or all of the activities designated as

## Environmental Protection Agency

§ 725.1075

significant new uses of the microorganism and, after reviewing such MCANs, concluded that there is no need to require additional notice from persons who propose to engage in identical or similar activities.

(4) EPA has examined new information, or has reexamined the test data or other information supporting its finding under section 5(e)(1)(A)(ii)(I) of the Act and has concluded that a rational basis no longer exists for the findings that activities involving the microorganism may present an unreasonable risk of injury to health or the environment required under section 5(e)(1)(A) of the Act.

(5) Certain activities involving the microorganism have been designated as significant new uses pending the completion of testing, and adequate test data developed in accordance with applicable procedures and criteria have been submitted to EPA.

(b) *Procedures for limitation or revocation.* Modification or revocation of significant new use notification requirements for a microorganism that has been added to subpart M of this part using the procedures described in § 725.980 may occur either at EPA's initiative or in response to a written request.

(1) Any affected person may request modification or revocation of significant new use notification requirements for a microorganism that has been added to subpart M of this part using the procedures described in § 725.980 by writing to the Director, or a designee, and stating the basis for such request. The request must be accompanied by information sufficient to support the request. Persons submitting a request to EPA under this part, unless allowed by § 725.25(c)(1), (c)(2), or (c)(3), must submit the request to EPA via EPA's Central Data Exchange (CDX) using EPA-provided e-PMN reporting software in the manner set forth in § 725.25(c). See 40 CFR 720.40(a)(2)(iv) for information on how to obtain the e-PMN software. Support documents related to these requests must also be submitted to EPA via CDX using e-PMN software. Paper requests must be submitted either via U.S. mail to the Document Control Office (DCO) (7407M), Office of Pollution Prevention

and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001; ATTN: Request to Amend SNUR or submitted via courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004; ATTN: Request to Amend SNUR. Optical discs containing electronic requests must be submitted by courier to the Environmental Protection Agency, OPPT Document Control Office (DCO), EPA East Bldg., 1201 Constitution Ave., NW., Rm. 6428, Washington, DC 20004; ATTN: Request to Amend SNUR.

(2) The Director, or a designee, will consider the request, make a determination whether to initiate rulemaking to modify the requirements, and notify the requester of that determination by certified letter. If the request is denied, the letter will explain why EPA has concluded that the significant new use notification requirements for that microorganism should remain in effect.

(3) If EPA concludes that significant new use notification requirements for a microorganism should be limited or revoked, EPA will propose the changes in a notice in the FEDERAL REGISTER, briefly describe the grounds for the action, and provide interested parties an opportunity to comment.

[62 FR 17932, April 11, 1997, as amended at 75 FR 790, Jan. 6, 2010]

### Subpart M—Significant New Uses for Specific Microorganisms

#### § 725.1000 Scope.

This subpart identifies uses of microorganisms which EPA has determined to be significant new uses under the authority of section 5(a)(2) of the Toxic Substances Control Act.

#### § 725.1075 *Burkholderia cepacia* complex.

(a) *Microorganism and significant new uses subject to reporting.* (1) The microorganisms identified as the *Burkholderia cepacia* complex defined as containing the following nine species, *Burkholderia cepacia*, *Burkholderia multivorans*, *Burkholderia stabilis*,

**Pt. 745**

**40 CFR Ch. I (7–1–10 Edition)**

*Burkholderia vietnamiensis*, *Burkholderia ambifaria*, *Burkholderia pyrrocinia*, *Burkholderia cepacia* genomovar VIII (*Burkholderia anthina*), and *Burkholderia cepacia* genomovars III and VI are subject to reporting under this section for the significant new uses described in paragraph (a)(2) of this section.

(2) The significant new use is any use other than research and development in the degradation of chemicals via injection into subsurface groundwater.

(b) [Reserved]

[68 FR 35320, June 13, 2003]

**PART 745—LEAD-BASED PAINT POISONING PREVENTION IN CERTAIN RESIDENTIAL STRUCTURES**

**Subparts A–C [Reserved]**

**Subpart D—Lead-Based Paint Hazards**

- 745.61 Scope and applicability.
- 745.63 Definitions.
- 745.65 Lead-based paint hazards.

**Subpart E—Residential Property Renovation**

- Sec.
- 745.80 Purpose.
  - 745.81 Effective dates.
  - 745.82 Applicability.
  - 745.83 Definitions.
  - 745.84 Information distribution requirements.
  - 745.85 Work practice standards.
  - 745.86 Recordkeeping and reporting requirements.
  - 745.87 Enforcement and inspections.
  - 745.88 Recognized test kits.
  - 745.89 Firm certification.
  - 745.90 Renovator certification and dust sampling technician certification.
  - 745.91 Suspending, revoking, or modifying an individual's or firm's certification.
  - 745.92 Fees for the accreditation of renovation and dust sampling technician training and the certification of renovation firms.

**Subpart F—Disclosure of Known Lead-Based Paint and/or Lead-Based Paint Hazards Upon Sale or Lease of Residential Property**

- 745.100 Purpose.
- 745.101 Scope and applicability.
- 745.102 Effective dates.
- 745.103 Definitions.
- 745.107 Disclosure requirements for sellers and lessors.

- 745.110 Opportunity to conduct an evaluation.
- 745.113 Certification and acknowledgment of disclosure.
- 745.115 Agent responsibilities.
- 745.118 Enforcement.
- 745.119 Impact on State and local requirements.

**Subparts G–K [Reserved]**

**Subpart L—Lead-Based Paint Activities**

- 745.220 Scope and applicability.
- 745.223 Definitions.
- 745.225 Accreditation of training programs: target housing and child-occupied facilities.
- 745.226 Certification of individuals and firms engaged in lead-based paint activities: target housing and child-occupied facilities.
- 745.227 Work practice standards for conducting lead-based paint activities: target housing and child-occupied facilities.
- 745.228 Accreditation of training programs: public and commercial buildings, bridges and superstructures. [Reserved]
- 745.229 Certification of individuals and firms engaged in lead-based paint activities: public and commercial buildings, bridges and superstructures. [Reserved]
- 745.230 Work practice standards for conducting lead-based paint activities: public and commercial buildings, bridges and superstructures. [Reserved]
- 745.233 Lead-based paint activities requirements.
- 745.235 Enforcement.
- 745.237 Inspections.
- 745.238 Fees for accreditation and certification of lead-based paint activities.
- 745.239 Effective dates.

**Subparts M–P [Reserved]**

**Subpart Q—State and Indian Tribal Programs**

- 745.320 Scope and purpose.
- 745.323 Definitions.
- 745.324 Authorization of State or Tribal programs.
- 745.325 Lead-based paint activities: State and Tribal program requirements.
- 745.326 Renovation: State and Tribal program requirements.
- 745.327 State or Indian Tribal lead-based paint compliance and enforcement programs.
- 745.339 Effective date.

AUTHORITY: 15 U.S.C. 2605, 2607, 2681–2692 and 42 U.S.C. 4852d.

SOURCE: 61 FR 9085, Mar. 6, 1996, unless otherwise noted.

## Subparts A–C [Reserved]

## Subpart D—Lead-Based Paint Hazards

SOURCE: 66 FR 1237, Jan. 5, 2001, unless otherwise noted.

**§ 745.61 Scope and applicability.**

(a) This subpart identifies lead-based paint hazards.

(b) The standards for lead-based paint hazards apply to target housing and child-occupied facilities.

(c) Nothing in this subpart requires the owner of property(ies) subject to these standards to evaluate the property(ies) for the presence of lead-based paint hazards or take any action to control these conditions if one or more of them is identified.

**§ 745.63 Definitions.**

The following definitions apply to part 745.

*Arithmetic mean* means the algebraic sum of data values divided by the number of data values (e.g., the sum of the concentration of lead in several soil samples divided by the number of samples).

*Chewable surface* means an interior or exterior surface painted with lead-based paint that a young child can mouth or chew. A chewable surface is the same as an “accessible surface” as defined in 42 U.S.C. 4851b(2)). Hard metal substrates and other materials that cannot be dented by the bite of a young child are not considered chewable.

*Common area group* means a group of common areas that are similar in design, construction, and function. Common area groups include, but are not limited to hallways, stairwells, and laundry rooms.

*Concentration* means the relative content of a specific substance contained within a larger mass, such as the amount of lead (in micrograms per gram or parts per million by weight) in a sample of dust or soil.

*Deteriorated paint* means any interior or exterior paint or other coating that is peeling, chipping, chalking or cracking, or any paint or coating located on an interior or exterior surface or fix-

ture that is otherwise damaged or separated from the substrate.

*Dripline* means the area within 3 feet surrounding the perimeter of a building.

*Friction surface* means an interior or exterior surface that is subject to abrasion or friction, including, but not limited to, certain window, floor, and stair surfaces.

*Impact surface* means an interior or exterior surface that is subject to damage by repeated sudden force such as certain parts of door frames.

*Interior window sill* means the portion of the horizontal window ledge that protrudes into the interior of the room.

*Lead-based paint hazard* means hazardous lead-based paint, dust-lead hazard or soil-lead hazard as identified in § 745.65.

*Loading* means the quantity of a specific substance present per unit of surface area, such as the amount of lead in micrograms contained in the dust collected from a certain surface area divided by the surface area in square feet or square meters.

*Mid-yard* means an area of a residential yard approximately midway between the dripline of a residential building and the nearest property boundary or between the driplines of a residential building and another building on the same property.

*Play area* means an area of frequent soil contact by children of less than 6 years of age as indicated by, but not limited to, such factors including the following: the presence of play equipment (e.g., sandboxes, swing sets, and sliding boards), toys, or other children’s possessions, observations of play patterns, or information provided by parents, residents, care givers, or property owners.

*Residential building* means a building containing one or more residential dwellings.

*Room* means a separate part of the inside of a building, such as a bedroom, living room, dining room, kitchen, bathroom, laundry room, or utility room. To be considered a separate room, the room must be separated from adjoining rooms by built-in walls or archways that extend at least 6 inches from an intersecting wall. Half walls or bookcases count as room separators if



built-in. Movable or collapsible partitions or partitions consisting solely of shelves or cabinets are not considered built-in walls. A screened in porch that is used as a living area is a room.

*Soil sample* means a sample collected in a representative location using ASTM E1727, "Standard Practice for Field Collection of Soil Samples for Lead Determination by Atomic Spectrometry Techniques," or equivalent method.

*Weighted arithmetic mean* means the arithmetic mean of sample results weighted by the number of subsamples in each sample. Its purpose is to give influence to a sample relative to the surface area it represents. A single surface sample is comprised of a single subsample. A composite sample may contain from two to four subsamples of the same area as each other and of each single surface sample in the composite. The weighted arithmetic mean is obtained by summing, for all samples, the product of the sample's result multiplied by the number of subsamples in the sample, and dividing the sum by the total number of subsamples contained in all samples. For example, the weighted arithmetic mean of a single surface sample containing 60 µg/ft<sup>2</sup>, a composite sample (three subsamples) containing 100 µg/ft<sup>2</sup>, and a composite sample (4 subsamples) containing 110 µg/ft<sup>2</sup> is 100 µg/ft<sup>2</sup>. This result is based on the equation  $[60+(3*100)+(4*110)]/(1+3+4)$ .

*Window trough* means, for a typical double-hung window, the portion of the exterior window sill between the interior window sill (or stool) and the frame of the storm window. If there is no storm window, the window trough is the area that receives both the upper and lower window sashes when they are both lowered. The window trough is sometimes referred to as the window "well."

*Wipe sample* means a sample collected by wiping a representative surface of known area, as determined by ASTM E1728, "Standard Practice for Field Collection of Settled Dust Samples Using Wipe Sampling Methods for Lead Determination by Atomic Spectrometry Techniques, or equivalent method, with an acceptable wipe material as defined in ASTM E 1792, "Standard Specifi-

fication for Wipe Sampling Materials for Lead in Surface Dust."

#### § 745.65 Lead-based paint hazards.

(a) *Paint-lead hazard*. A paint-lead hazard is any of the following:

(1) Any lead-based paint on a friction surface that is subject to abrasion and where the lead dust levels on the nearest horizontal surface underneath the friction surface (e.g., the window sill, or floor) are equal to or greater than the dust-lead hazard levels identified in paragraph (b) of this section.

(2) Any damaged or otherwise deteriorated lead-based paint on an impact surface that is caused by impact from a related building component (such as a door knob that knocks into a wall or a door that knocks against its door frame.

(3) Any chewable lead-based painted surface on which there is evidence of teeth marks.

(4) Any other deteriorated lead-based paint in any residential building or child-occupied facility or on the exterior of any residential building or child-occupied facility.

(b) *Dust-lead hazard*. A dust-lead hazard is surface dust in a residential dwelling or child-occupied facility that contains a mass-per-area concentration of lead equal to or exceeding 40 µg/ft<sup>2</sup> on floors or 250 µg/ft<sup>2</sup> on interior window sills based on wipe samples.

(c) *Soil-lead hazard*. A soil-lead hazard is bare soil on residential real property or on the property of a child-occupied facility that contains total lead equal to or exceeding 400 parts per million (µg/g) in a play area or average of 1,200 parts per million of bare soil in the rest of the yard based on soil samples.

(d) *Work practice requirements*. Applicable certification, occupant protection, and clearance requirements and work practice standards are found in regulations issued by EPA at 40 CFR part 745, subpart L and in regulations issued by the Department of Housing and Urban Development (HUD) at 24 CFR part 35, subpart R. The work practice standards in those regulations do not apply when treating paint-lead hazards of less than:

(1) Two square feet of deteriorated lead-based paint per room or equivalent,

## Environmental Protection Agency

## § 745.81

(2) Twenty square feet of deteriorated paint on the exterior building, or

(3) Ten percent of the total surface area of deteriorated paint on an interior or exterior type of component with a small surface area.

### Subpart E—Residential Property Renovation

SOURCE: 63 FR 29919, June 1, 1998, unless otherwise noted.

#### § 745.80 Purpose.

This subpart contains regulations developed under sections 402 and 406 of the Toxic Substances Control Act (15 U.S.C. 2682 and 2686) and applies to all renovations performed for compensation in target housing and child-occupied facilities. The purpose of this subpart is to ensure the following:

(a) Owners and occupants of target housing and child-occupied facilities receive information on lead-based paint hazards before these renovations begin; and

(b) Individuals performing renovations regulated in accordance with § 745.82 are properly trained; renovators and firms performing these renovations are certified; and the work practices in § 745.85 are followed during these renovations.

[73 FR 21758, Apr. 22, 2008]

#### § 745.81 Effective dates.

(a) *Training, certification and accreditation requirements and work practice standards.* The training, certification and accreditation requirements and work practice standards in this subpart are applicable in any State or Indian Tribal area that does not have a renovation program that is authorized under subpart Q of this part. The training, certification and accreditation requirements and work practice standards in this subpart will become effective as follows:

(1) *Training programs.* Effective June 23, 2008, no training program may provide, offer, or claim to provide training or refresher training for EPA certification as a renovator or a dust sampling technician without accreditation from EPA under § 745.225. Training pro-

grams may apply for accreditation under § 745.225 beginning April 22, 2009.

(2) *Firms.* (i) Firms may apply for certification under § 745.89 beginning October 22, 2009.

(ii) On or after April 22, 2010, no firm may perform, offer, or claim to perform renovations without certification from EPA under § 745.89 in target housing or child-occupied facilities, unless the renovation qualifies for one of the exceptions identified in § 745.82(a) or (c).

(3) *Individuals.* On or after April 22, 2010, all renovations must be directed by renovators certified in accordance with § 745.90(a) and performed by certified renovators or individuals trained in accordance with § 745.90(b)(2) in target housing or child-occupied facilities, unless the renovation qualifies for one of the exceptions identified in § 745.82(a) or (c).

(4) *Work practices.* On or after April 22, 2010, all renovations must be performed in accordance with the work practice standards in § 745.85 and the associated recordkeeping requirements in § 745.86(b)(6) and (b)(7) in target housing or child-occupied facilities, unless the renovation qualifies for one of the exceptions identified in § 745.82(a) or (c).

(5) The suspension and revocation provisions in § 745.91 are effective April 22, 2010.

(b) *Renovation-specific pamphlet.* Before December 22, 2008, renovators or firms performing renovations in States and Indian Tribal areas without an authorized program may provide owners and occupants with either of the following EPA pamphlets: *Protect Your Family From Lead in Your Home* or *Renovate Right: Important Lead Hazard Information for Families, Child Care Providers and Schools*. After that date, *Renovate Right: Important Lead Hazard Information for Families, Child Care Providers and Schools* must be used exclusively.

(c) *Pre-Renovation Education Rule.* With the exception of the requirement to use the pamphlet entitled *Renovate Right: Important Lead Hazard Information for Families, Child Care Providers and Schools*, the provisions of the Pre-

**✕745.81, Nt.**

**40 CFR Ch. I (7-1-10 Edition)**

Renovation Education Rule in this subpart have been in effect since June 1999.

[73 FR 21758, Apr. 22, 2008]

EFFECTIVE DATE NOTE: At 75 FR 24818, May 6, 2010, §745.81 was amended by revising paragraph (a)(4), effective July 6, 2010. For the convenience of the user, the revised text is set forth as follows:

**§745.81 Effective dates.**

(a) \* \* \*

(4) *Work practices.* (i) On or after April 22, 2010 and before July 6, 2010 all renovations must be performed in accordance with the work practice standards in § 745.85 and the associated recordkeeping requirements in § 745.86 (b)(6) in target housing or child-occupied facilities, unless the renovation qualifies for one of the exceptions identified in §745.82(a). This does not apply to renovations in target housing for which the firm performing the renovation has obtained a statement signed by the owner that the renovation will occur in the owner's residence, no child under age 6 resides there, the housing is not a child-occupied facility, and the owner acknowledges that the work practices to be used during the renovation will not necessarily include all of the lead-safe work practices contained in EPA's renovation, repair, and painting rule. For the purposes of this section, a child resides in the primary residence of his or her custodial parents, legal guardians, and foster parents. A child also resides in the primary residence of an informal caretaker if the child lives and sleeps most of the time at the caretaker's residence.

(ii) On or after July 6, 2010, all renovations must be performed in accordance with the work practice standards in § 745.85 and the associated recordkeeping requirements in § 745.86(b)(1) and (b)(6) in target housing or child-occupied facilities, unless the renovation qualifies for the exception identified in §745.82(a).

\* \* \* \* \*

**§745.82 Applicability.**

(a) This subpart applies to all renovations performed for compensation in target housing and child-occupied facilities, except for the following:

(1) Renovations in target housing or child-occupied facilities in which a written determination has been made by an inspector or risk assessor (certified pursuant to either Federal regulations at §745.226 or a State or Tribal certification program authorized pursuant to §745.324) that the components

affected by the renovation are free of paint or other surface coatings that contain lead equal to or in excess of 1.0 milligrams per square centimeter (mg/cm<sup>2</sup>) or 0.5% by weight, where the firm performing the renovation has obtained a copy of the determination.

(2) Renovations in target housing or child-occupied facilities in which a certified renovator, using an EPA recognized test kit as defined in §745.83 and following the kit manufacturer's instructions, has tested each component affected by the renovation and determined that the components are free of paint or other surface coatings that contain lead equal to or in excess of 1.0 mg/cm<sup>2</sup> or 0.5% by weight. If the components make up an integrated whole, such as the individual stair treads and risers of a single staircase, the renovator is required to test only one of the individual components, unless the individual components appear to have been repainted or refinished separately.

(b) The information distribution requirements in §745.84 do not apply to emergency renovations, which are renovation activities that were not planned but result from a sudden, unexpected event (such as non-routine failures of equipment) that, if not immediately attended to, presents a safety or public health hazard, or threatens equipment and/or property with significant damage. Interim controls performed in response to an elevated blood lead level in a resident child are also emergency renovations. Emergency renovations other than interim controls are also exempt from the warning sign, containment, waste handling, training, and certification requirements in §§745.85, 745.89, and 745.90 to the extent necessary to respond to the emergency. Emergency renovations are not exempt from the cleaning requirements of §745.85(a)(5), which must be performed by certified renovators or individuals trained in accordance with §745.90(b)(2), the cleaning verification requirements of §745.85(b), which must be performed by certified renovators, and the recordkeeping requirements of §745.86(b)(6) and (b)(7).

(c) The training requirements in §745.90 and the work practice standards for renovation activities in §745.85

apply to all renovations covered by this subpart, except for renovations in target housing for which the firm performing the renovation has obtained a statement signed by the owner that the renovation will occur in the owner's residence, no child under age 6 resides there, no pregnant woman resides there, the housing is not a child-occupied facility, and the owner acknowledges that the renovation firm will not be required to use the work practices contained in EPA's renovation, repair, and painting rule. For the purposes of this section, a child resides in the primary residence of his or her custodial parents, legal guardians, and foster parents. A child also resides in the primary residence of an informal caretaker if the child lives and sleeps most of the time at the caretaker's residence.

[73 FR 21758, Apr. 22, 2008]

EFFECTIVE DATE NOTE: At 75 FR 24818, May 6, 2010, §745.82 was amended by removing paragraph (c), effective July 6, 2010.

#### § 745.83 Definitions.

For purposes of this part, the definitions in §745.103 as well as the following definitions apply:

*Administrator* means the Administrator of the Environmental Protection Agency.

*Child-occupied facility* means a building, or portion of a building, constructed prior to 1978, visited regularly by the same child, under 6 years of age, on at least two different days within any week (Sunday through Saturday period), provided that each day's visit lasts at least 3 hours and the combined weekly visits last at least 6 hours, and the combined annual visits last at least 60 hours. Child-occupied facilities may include, but are not limited to, day care centers, preschools and kindergarten classrooms. Child-occupied facilities may be located in target housing or in public or commercial buildings. With respect to common areas in public or commercial buildings that contain child-occupied facilities, the child-occupied facility encompasses only those common areas that are routinely used by children under age 6, such as restrooms and cafeterias. Common areas that children under age 6 only pass through, such as hallways,

stairways, and garages are not included. In addition, with respect to exteriors of public or commercial buildings that contain child-occupied facilities, the child-occupied facility encompasses only the exterior sides of the building that are immediately adjacent to the child-occupied facility or the common areas routinely used by children under age 6.

*Cleaning verification card* means a card developed and distributed, or otherwise approved, by EPA for the purpose of determining, through comparison of wet and dry disposable cleaning cloths with the card, whether post-renovation cleaning has been properly completed.

*Component or building component* means specific design or structural elements or fixtures of a building or residential dwelling that are distinguished from each other by form, function, and location. These include, but are not limited to, interior components such as: Ceilings, crown molding, walls, chair rails, doors, door trim, floors, fireplaces, radiators and other heating units, shelves, shelf supports, stair treads, stair risers, stair stringers, newel posts, railing caps, balustrades, windows and trim (including sashes, window heads, jambs, sills or stools and troughs), built in cabinets, columns, beams, bathroom vanities, counter tops, and air conditioners; and exterior components such as: Painted roofing, chimneys, flashing, gutters and downspouts, ceilings, soffits, fascias, rake boards, cornerboards, bulkheads, doors and door trim, fences, floors, joists, lattice work, railings and railing caps, siding, handrails, stair risers and treads, stair stringers, columns, balustrades, windowsills or stools and troughs, casings, sashes and wells, and air conditioners.

*Dry disposable cleaning cloth* means a commercially available dry, electrostatically charged, white disposable cloth designed to be used for cleaning hard surfaces such as uncarpeted floors or counter tops.

*Firm* means a company, partnership, corporation, sole proprietorship or individual doing business, association, or other business entity; a Federal, State, Tribal, or local government agency; or a nonprofit organization.

*HEPA vacuum* means a vacuum cleaner which has been designed with a high-efficiency particulate air (HEPA) filter as the last filtration stage. A HEPA filter is a filter that is capable of capturing particles of 0.3 microns with 99.97% efficiency. The vacuum cleaner must be designed so that all the air drawn into the machine is expelled through the HEPA filter with none of the air leaking past it.

*Interim controls* means a set of measures designed to temporarily reduce human exposure or likely exposure to lead-based paint hazards, including specialized cleaning, repairs, maintenance, painting, temporary containment, ongoing monitoring of lead-based paint hazards or potential hazards, and the establishment and operation of management and resident education programs.

*Minor repair and maintenance activities* are activities, including minor heating, ventilation or air conditioning work, electrical work, and plumbing, that disrupt 6 square feet or less of painted surface per room for interior activities or 20 square feet or less of painted surface for exterior activities where none of the work practices prohibited or restricted by § 745.85(a)(3) are used and where the work does not involve window replacement or demolition of painted surface areas. When removing painted components, or portions of painted components, the entire surface area removed is the amount of painted surface disturbed. Jobs, other than emergency renovations, performed in the same room within the same 30 days must be considered the same job for the purpose of determining whether the job is a minor repair and maintenance activity.

*Pamphlet* means the EPA pamphlet titled *Renovate Right: Important Lead Hazard Information for Families, Child Care Providers and Schools* developed under section 406(a) of TSCA for use in complying with section 406(b) of TSCA, or any State or Tribal pamphlet approved by EPA pursuant to 40 CFR 745.326 that is developed for the same purpose. This includes reproductions of the pamphlet when copied in full and without revision or deletion of material from the pamphlet (except for the addition or revision of State or local

sources of information). Before December 22, 2008, the term “pamphlet” also means any pamphlet developed by EPA under section 406(a) of TSCA or any State or Tribal pamphlet approved by EPA pursuant to § 745.326.

*Person* means any natural or judicial person including any individual, corporation, partnership, or association; any Indian Tribe, State, or political subdivision thereof; any interstate body; and any department, agency, or instrumentality of the Federal Government.

*Recognized test kit* means a commercially available kit recognized by EPA under § 745.88 as being capable of allowing a user to determine the presence of lead at levels equal to or in excess of 1.0 milligrams per square centimeter, or more than 0.5% lead by weight, in a paint chip, paint powder, or painted surface.

*Renovation* means the modification of any existing structure, or portion thereof, that results in the disturbance of painted surfaces, unless that activity is performed as part of an abatement as defined by this part (40 CFR 745.223). The term renovation includes (but is not limited to): The removal, modification or repair of painted surfaces or painted components (e.g., modification of painted doors, surface restoration, window repair, surface preparation activity (such as sanding, scraping, or other such activities that may generate paint dust)); the removal of building components (e.g., walls, ceilings, plumbing, windows); weatherization projects (e.g., cutting holes in painted surfaces to install blown-in insulation or to gain access to attics, planing thresholds to install weatherstripping), and interim controls that disturb painted surfaces. A renovation performed for the purpose of converting a building, or part of a building, into target housing or a child-occupied facility is a renovation under this subpart. The term renovation does not include minor repair and maintenance activities.

*Renovator* means an individual who either performs or directs workers who

## Environmental Protection Agency

## § 745.84

perform renovations. A certified renovator is a renovator who has successfully completed a renovator course accredited by EPA or an EPA-authorized State or Tribal program.

*Training hour* means at least 50 minutes of actual learning, including, but not limited to, time devoted to lecture, learning activities, small group activities, demonstrations, evaluations, and hands-on experience.

*Wet disposable cleaning cloth* means a commercially available, pre-moistened white disposable cloth designed to be used for cleaning hard surfaces such as uncarpeted floors or counter tops.

*Wet mopping system* means a device with the following characteristics: A long handle, a mop head designed to be used with disposable absorbent cleaning pads, a reservoir for cleaning solution, and a built-in mechanism for distributing or spraying the cleaning solution onto a floor, or a method of equivalent efficacy.

*Work area* means the area that the certified renovator establishes to contain the dust and debris generated by a renovation.

[63 FR 29919, June 1, 1998, as amended at 73 FR 21758, Apr. 22, 2008]

### § 745.84 Information distribution requirements.

(a) *Renovations in dwelling units.* No more than 60 days before beginning renovation activities in any residential dwelling unit of target housing, the firm performing the renovation must:

(1) Provide the owner of the unit with the pamphlet, and comply with one of the following:

(i) Obtain, from the owner, a written acknowledgment that the owner has received the pamphlet.

(ii) Obtain a certificate of mailing at least 7 days prior to the renovation.

(2) In addition to the requirements in paragraph (a)(1) of this section, if the owner does not occupy the dwelling unit, provide an adult occupant of the unit with the pamphlet, and comply with one of the following:

(i) Obtain, from the adult occupant, a written acknowledgment that the occupant has received the pamphlet; or certify in writing that a pamphlet has been delivered to the dwelling and that the firm performing the renovation has

been unsuccessful in obtaining a written acknowledgment from an adult occupant. Such certification must include the address of the unit undergoing renovation, the date and method of delivery of the pamphlet, names of the persons delivering the pamphlet, reason for lack of acknowledgment (e.g., occupant refuses to sign, no adult occupant available), the signature of a representative of the firm performing the renovation, and the date of signature.

(ii) Obtain a certificate of mailing at least 7 days prior to the renovation.

(b) *Renovations in common areas.* No more than 60 days before beginning renovation activities in common areas of multi-unit target housing, the firm performing the renovation must:

(1) Provide the owner with the pamphlet, and comply with one of the following:

(i) Obtain, from the owner, a written acknowledgment that the owner has received the pamphlet.

(ii) Obtain a certificate of mailing at least 7 days prior to the renovation.

(2) *Comply with one of the following.* (i) Notify in writing, or ensure written notification of, each affected unit and make the pamphlet available upon request prior to the start of renovation. Such notification shall be accomplished by distributing written notice to each affected unit. The notice shall describe the general nature and locations of the planned renovation activities; the expected starting and ending dates; and a statement of how the occupant can obtain the pamphlet, at no charge, from the firm performing the renovation, or

(ii) While the renovation is ongoing, post informational signs describing the general nature and locations of the renovation and the anticipated completion date. These signs must be posted in areas where they are likely to be seen by the occupants of all of the affected units. The signs must be accompanied by a posted copy of the pamphlet or information on how interested occupants can review a copy of the pamphlet or obtain a copy from the renovation firm at no cost to occupants.

(3) Prepare, sign, and date a statement describing the steps performed to

notify all occupants of the intended renovation activities and to provide the pamphlet.

(4) If the scope, locations, or expected starting and ending dates of the planned renovation activities change after the initial notification, and the firm provided written initial notification to each affected unit, the firm performing the renovation must provide further written notification to the owners and occupants providing revised information on the ongoing or planned activities. This subsequent notification must be provided before the firm performing the renovation initiates work beyond that which was described in the original notice.

(c) *Renovations in child-occupied facilities.* No more than 60 days before beginning renovation activities in any child-occupied facility, the firm performing the renovation must:

(1)(i) Provide the owner of the building with the pamphlet, and comply with one of the following:

(A) Obtain, from the owner, a written acknowledgment that the owner has received the pamphlet.

(B) Obtain a certificate of mailing at least 7 days prior to the renovation.

(ii) If the child-occupied facility is not the owner of the building, provide an adult representative of the child-occupied facility with the pamphlet, and comply with one of the following:

(A) Obtain, from the adult representative, a written acknowledgment that the adult representative has received the pamphlet; or certify in writing that a pamphlet has been delivered to the facility and that the firm performing the renovation has been unsuccessful in obtaining a written acknowledgment from an adult representative. Such certification must include the address of the child-occupied facility undergoing renovation, the date and method of delivery of the pamphlet, names of the persons delivering the pamphlet, reason for lack of acknowledgment (e.g., representative refuses to sign), the signature of a representative of the firm performing the renovation, and the date of signature.

(B) Obtain a certificate of mailing at least 7 days prior to the renovation.

(2) Provide the parents and guardians of children using the child-occupied fa-

cility with the pamphlet and information describing the general nature and locations of the renovation and the anticipated completion date by complying with one of the following:

(i) Mail or hand-deliver the pamphlet and the renovation information to each parent or guardian of a child using the child-occupied facility.

(ii) While the renovation is ongoing, post informational signs describing the general nature and locations of the renovation and the anticipated completion date. These signs must be posted in areas where they can be seen by the parents or guardians of the children frequenting the child-occupied facility. The signs must be accompanied by a posted copy of the pamphlet or information on how interested parents or guardians can review a copy of the pamphlet or obtain a copy from the renovation firm at no cost to the parents or guardians.

(3) The renovation firm must prepare, sign, and date a statement describing the steps performed to notify all parents and guardians of the intended renovation activities and to provide the pamphlet.

(d) *Written acknowledgment.* The written acknowledgments required by paragraphs (a)(1)(i), (a)(2)(i), (b)(1)(i), (c)(1)(i)(A), and (c)(1)(ii)(A) of this section must:

(1) Include a statement recording the owner or occupant's name and acknowledging receipt of the pamphlet prior to the start of renovation, the address of the unit undergoing renovation, the signature of the owner or occupant as applicable, and the date of signature.

(2) Be either a separate sheet or part of any written contract or service agreement for the renovation.

(3) Be written in the same language as the text of the contract or agreement for the renovation or, in the case of non-owner occupied target housing, in the same language as the lease or rental agreement or the pamphlet.

[63 FR 29919, June 1, 1998. Redesignated and amended at 73 FR 21760, Apr. 22, 2008]

EFFECTIVE DATE NOTE: At 75 FR 24818, May 6, 2010, §745.84 was amended by revising paragraph (b)(2), the introductory text of paragraph (c)(2), and paragraph (c)(2)(ii), effective

**Environmental Protection Agency**

**§ 745.85**

July 6, 2010. For the convenience of the user, the revised text is set forth as follows:

**§ 745.84 Information distribution requirements.**

\* \* \* \* \*

(b) \* \* \*

(2) *Comply with one of the following.* (i) Notify in writing, or ensure written notification of, each affected unit and make the pamphlet available upon request prior to the start of renovation. Such notification shall be accomplished by distributing written notice to each affected unit. The notice shall describe the general nature and locations of the planned renovation activities; the expected starting and ending dates; and a statement of how the occupant can obtain the pamphlet and a copy of the records required by § 745.86(c) and (d), at no cost to the occupants, or

(ii) While the renovation is ongoing, post informational signs describing the general nature and locations of the renovation and the anticipated completion date. These signs must be posted in areas where they are likely to be seen by the occupants of all of the affected units. The signs must be accompanied by a posted copy of the pamphlet or information on how interested occupants can review a copy of the pamphlet or obtain a copy from the renovation firm at no cost to occupants. The signs must also include information on how interested occupants can review a copy of the records required by § 745.86(c) and (d) or obtain a copy from the renovation firm at no cost to the occupants.

\* \* \* \* \*

(c) \* \* \*

(2) Provide the parents and guardians of children using the child-occupied facility with the pamphlet, information describing the general nature and locations of the renovation and the anticipated completion date, and information on how interested parents or guardians of children frequenting the child-occupied facility can review a copy of the records required by §745.86(c) and (d) or obtain a copy from the renovation firm at no cost to the occupants by complying with one of the following:

\* \* \* \* \*

(ii) While the renovation is ongoing, post informational signs describing the general nature and locations of the renovation and the anticipated completion date. These signs must be posted in areas where they can be seen by the parents or guardians of the children frequenting the child-occupied facility. The signs must be accompanied by a posted copy of the pamphlet or information on how

interested parents or guardians of children frequenting the child-occupied facility can review a copy of the pamphlet or obtain a copy from the renovation firm at no cost to the parents or guardians. The signs must also include information on how interested parents or guardians of children frequenting the child-occupied facility can review a copy of the records required by § 745.86(c) and (d) or obtain a copy from the renovation firm at no cost to the parents or guardians.

\* \* \* \* \*

**§ 745.85 Work practice standards.**

(a) *Standards for renovation activities.*

Renovations must be performed by certified firms using certified renovators as directed in §745.89. The responsibilities of certified firms are set forth in §745.89(d) and the responsibilities of certified renovators are set forth in §745.90(b).

(1) *Occupant protection.* Firms must post signs clearly defining the work area and warning occupants and other persons not involved in renovation activities to remain outside of the work area. To the extent practicable, these signs must be in the primary language of the occupants. These signs must be posted before beginning the renovation and must remain in place and readable until the renovation and the post-renovation cleaning verification have been completed. If warning signs have been posted in accordance with 24 CFR 35.1345(b)(2) or 29 CFR 1926.62(m), additional signs are not required by this section.

(2) *Containing the work area.* Before beginning the renovation, the firm must isolate the work area so that no dust or debris leaves the work area while the renovation is being performed. In addition, the firm must maintain the integrity of the containment by ensuring that any plastic or other impermeable materials are not torn or displaced, and taking any other steps necessary to ensure that no dust or debris leaves the work area while the renovation is being performed. The firm must also ensure that containment is installed in such a manner that it does not interfere with occupant and worker egress in an emergency.

(i) *Interior renovations.* The firm must:



(A) Remove all objects from the work area, including furniture, rugs, and window coverings, or cover them with plastic sheeting or other impermeable material with all seams and edges taped or otherwise sealed.

(B) Close and cover all ducts opening in the work area with taped-down plastic sheeting or other impermeable material.

(C) Close windows and doors in the work area. Doors must be covered with plastic sheeting or other impermeable material. Doors used as an entrance to the work area must be covered with plastic sheeting or other impermeable material in a manner that allows workers to pass through while confining dust and debris to the work area.

(D) Cover the floor surface, including installed carpet, with taped-down plastic sheeting or other impermeable material in the work area 6 feet beyond the perimeter of surfaces undergoing renovation or a sufficient distance to contain the dust, whichever is greater.

(E) Use precautions to ensure that all personnel, tools, and other items, including the exteriors of containers of waste, are free of dust and debris before leaving the work area.

(ii) *Exterior renovations.* The firm must:

(A) Close all doors and windows within 20 feet of the renovation. On multi-story buildings, close all doors and windows within 20 feet of the renovation on the same floor as the renovation, and close all doors and windows on all floors below that are the same horizontal distance from the renovation.

(B) Ensure that doors within the work area that will be used while the job is being performed are covered with plastic sheeting or other impermeable material in a manner that allows workers to pass through while confining dust and debris to the work area.

(C) Cover the ground with plastic sheeting or other disposable impermeable material extending 10 feet beyond the perimeter of surfaces undergoing renovation or a sufficient distance to collect falling paint debris, whichever is greater, unless the property line prevents 10 feet of such ground covering.

(D) In certain situations, the renovation firm must take extra precautions in containing the work area to ensure that dust and debris from the renovation does not contaminate other buildings or other areas of the property or migrate to adjacent properties.

(3) *Prohibited and restricted practices.* The work practices listed below shall be prohibited or restricted during a renovation as follows:

(i) Open-flame burning or torching of lead-based paint is prohibited.

(ii) The use of machines that remove lead-based paint through high speed operation such as sanding, grinding, power planing, needle gun, abrasive blasting, or sandblasting, is prohibited unless such machines are used with HEPA exhaust control.

(iii) Operating a heat gun on lead-based paint is permitted only at temperatures below 1100 degrees Fahrenheit.

(4) *Waste from renovations*—(i) Waste from renovation activities must be contained to prevent releases of dust and debris before the waste is removed from the work area for storage or disposal. If a chute is used to remove waste from the work area, it must be covered.

(ii) At the conclusion of each work day and at the conclusion of the renovation, waste that has been collected from renovation activities must be stored under containment, in an enclosure, or behind a barrier that prevents release of dust and debris out of the work area and prevents access to dust and debris.

(iii) When the firm transports waste from renovation activities, the firm must contain the waste to prevent release of dust and debris.

(5) *Cleaning the work area.* After the renovation has been completed, the firm must clean the work area until no dust, debris or residue remains.

(i) *Interior and exterior renovations.* The firm must:

(A) Collect all paint chips and debris and, without dispersing any of it, seal this material in a heavy-duty bag.

(B) Remove the protective sheeting. Mist the sheeting before folding it, fold the dirty side inward, and either tape shut to seal or seal in heavy-duty bags. Sheeting used to isolate contaminated

## Environmental Protection Agency

## § 745.85

rooms from non-contaminated rooms must remain in place until after the cleaning and removal of other sheeting. Dispose of the sheeting as waste.

(ii) *Additional cleaning for interior renovations.* The firm must clean all objects and surfaces in the work area and within 2 feet of the work area in the following manner, cleaning from higher to lower:

(A) *Walls.* Clean walls starting at the ceiling and working down to the floor by either vacuuming with a HEPA vacuum or wiping with a damp cloth.

(B) *Remaining surfaces.* Thoroughly vacuum all remaining surfaces and objects in the work area, including furniture and fixtures, with a HEPA vacuum. The HEPA vacuum must be equipped with a beater bar when vacuuming carpets and rugs.

(C) Wipe all remaining surfaces and objects in the work area, except for carpeted or upholstered surfaces, with a damp cloth. Mop uncarpeted floors thoroughly, using a mopping method that keeps the wash water separate from the rinse water, such as the 2-bucket mopping method, or using a wet mopping system.

(b) *Standards for post-renovation cleaning verification*—(1) *Interiors.* (i) A certified renovator must perform a visual inspection to determine whether dust, debris or residue is still present. If dust, debris or residue is present, these conditions must be removed by re-cleaning and another visual inspection must be performed.

(ii) After a successful visual inspection, a certified renovator must:

(A) Verify that each windowsill in the work area has been adequately cleaned, using the following procedure.

(1) Wipe the windowsill with a wet disposable cleaning cloth that is damp to the touch. If the cloth matches or is lighter than the cleaning verification card, the windowsill has been adequately cleaned.

(2) If the cloth does not match and is darker than the cleaning verification card, re-clean the windowsill as directed in paragraphs (a)(5)(ii)(B) and (a)(5)(ii)(C) of this section, then either use a new cloth or fold the used cloth in such a way that an unused surface is exposed, and wipe the surface again. If the cloth matches or is lighter than

the cleaning verification card, that windowsill has been adequately cleaned.

(3) If the cloth does not match and is darker than the cleaning verification card, wait for 1 hour or until the surface has dried completely, whichever is longer.

(4) After waiting for the windowsill to dry, wipe the windowsill with a dry disposable cleaning cloth. After this wipe, the windowsill has been adequately cleaned.

(B) Wipe uncarpeted floors and countertops within the work area with a wet disposable cleaning cloth. Floors must be wiped using an application device with a long handle and a head to which the cloth is attached. The cloth must remain damp at all times while it is being used to wipe the surface for post-renovation cleaning verification. If the surface within the work area is greater than 40 square feet, the surface within the work area must be divided into roughly equal sections that are each less than 40 square feet. Wipe each such section separately with a new wet disposable cleaning cloth. If the cloth used to wipe each section of the surface within the work area matches the cleaning verification card, the surface has been adequately cleaned.

(1) If the cloth used to wipe a particular surface section does not match the cleaning verification card, re-clean that section of the surface as directed in paragraphs (a)(5)(ii)(B) and (a)(5)(ii)(C) of this section, then use a new wet disposable cleaning cloth to wipe that section again. If the cloth matches the cleaning verification card, that section of the surface has been adequately cleaned.

(2) If the cloth used to wipe a particular surface section does not match the cleaning verification card after the surface has been re-cleaned, wait for 1 hour or until the entire surface within the work area has dried completely, whichever is longer.

(3) After waiting for the entire surface within the work area to dry, wipe each section of the surface that has not yet achieved post-renovation cleaning verification with a dry disposable cleaning cloth. After this wipe, that section of the surface has been adequately cleaned.

(iii) When the work area passes the post-renovation cleaning verification, remove the warning signs.

(2) *Exteriors.* A certified renovator must perform a visual inspection to determine whether dust, debris or residue is still present on surfaces in and below the work area, including windowsills and the ground. If dust, debris or residue is present, these conditions must be eliminated and another visual inspection must be performed. When the area passes the visual inspection, remove the warning signs.

(c) *Optional dust clearance testing.* Cleaning verification need not be performed if the contract between the renovation firm and the person contracting for the renovation or another Federal, State, Territorial, Tribal, or local law or regulation requires:

(1) The renovation firm to perform dust clearance sampling at the conclusion of a renovation covered by this subpart.

(2) The dust clearance samples are required to be collected by a certified inspector, risk assessor or dust sampling technician.

(3) The renovation firm is required to re-clean the work area until the dust clearance sample results are below the clearance standards in § 745.227(e)(8) or any applicable State, Territorial, Tribal, or local standard.

(d) *Activities conducted after post-renovation cleaning verification.* Activities that do not disturb paint, such as applying paint to walls that have already been prepared, are not regulated by this subpart if they are conducted after post-renovation cleaning verification has been performed.

[73 FR 21761, Apr. 22, 2008]

**§ 745.86 Recordkeeping and reporting requirements.**

(a) Firms performing renovations must retain and, if requested, make available to EPA all records necessary to demonstrate compliance with this subpart for a period of 3 years following completion of the renovation. This 3-year retention requirement does not supersede longer obligations required by other provisions for retaining the same documentation, including any applicable State or Tribal laws or regulations.

(b) Records that must be retained pursuant to paragraph (a) of this section shall include (where applicable):

(1) Reports certifying that a determination had been made by an inspector (certified pursuant to either Federal regulations at § 745.226 or an EPA-authorized State or Tribal certification program) that lead-based paint is not present on the components affected by the renovation, as described in § 745.82(b)(1).

(2) Signed and dated acknowledgments of receipt as described in § 745.84(a)(1)(i), (a)(2)(i), (b)(1)(i), (c)(1)(i)(A), and (c)(1)(ii)(A).

(3) Certifications of attempted delivery as described in § 745.84(a)(2)(i) and (c)(1)(ii)(A).

(4) Certificates of mailing as described in § 745.84(a)(1)(ii), (a)(2)(ii), (b)(1)(ii), (c)(1)(i)(B), and (c)(1)(ii)(B).

(5) Records of notification activities performed regarding common area renovations, as described in § 745.84(b)(3) and (b)(4), and renovations in child-occupied facilities, as described in § 745.84(c)(2).

(6) Any signed and dated statements received from owner-occupants documenting that the requirements of § 745.85 do not apply. These statements must include a declaration that the renovation will occur in the owner's residence, a declaration that no children under age 6 reside there, a declaration that no pregnant woman resides there, a declaration that the housing is not a child-occupied facility, the address of the unit undergoing renovation, the owner's name, an acknowledgment by the owner that the work practices to be used during the renovation will not necessarily include all of the lead-safe work practices contained in EPA's renovation, repair, and painting rule, the signature of the owner, and the date of signature. These statements must be written in the same language as the text of the renovation contract, if any.

(7) Documentation of compliance with the requirements of § 745.85, including documentation that a certified renovator was assigned to the project, that the certified renovator provided on-the-job training for workers used on the project, that the certified renovator performed or directed workers

**Environmental Protection Agency**

**✕745.86, Nt.**

who performed all of the tasks described in §745.85(a), and that the certified renovator performed the post-renovation cleaning verification described in §745.85(b). If the renovation firm was unable to comply with all of the requirements of this rule due to an emergency as defined in §745.82, the firm must document the nature of the emergency and the provisions of the rule that were not followed. This documentation must include a copy of the certified renovator's training certificate, and a certification by the certified renovator assigned to the project that:

(i) Training was provided to workers (topics must be identified for each worker).

(ii) Warning signs were posted at the entrances to the work area.

(iii) If test kits were used, that the specified brand of kits was used at the specified locations and that the results were as specified.

(iv) The work area was contained by:

(A) Removing or covering all objects in the work area (interiors).

(B) Closing and covering all HVAC ducts in the work area (interiors).

(C) Closing all windows in the work area (interiors) or closing all windows in and within 20 feet of the work area (exteriors).

(D) Closing and sealing all doors in the work area (interiors) or closing and sealing all doors in and within 20 feet of the work area (exteriors).

(E) Covering doors in the work area that were being used to allow passage but prevent spread of dust.

(F) Covering the floor surface, including installed carpet, with taped-down plastic sheeting or other impermeable material in the work area 6 feet beyond the perimeter of surfaces undergoing renovation or a sufficient distance to contain the dust, whichever is greater (interiors) or covering the ground with plastic sheeting or other disposable impermeable material anchored to the building extending 10 feet beyond the perimeter of surfaces undergoing renovation or a sufficient distance to collect falling paint debris, whichever is greater, unless the property line prevents 10 feet of such ground covering, weighted down by heavy objects (exteriors).

(G) Installing (if necessary) vertical containment to prevent migration of dust and debris to adjacent property (exteriors).

(v) Waste was contained on-site and while being transported off-site.

(vi) The work area was properly cleaned after the renovation by:

(A) Picking up all chips and debris, misting protective sheeting, folding it dirty side inward, and taping it for removal.

(B) Cleaning the work area surfaces and objects using a HEPA vacuum and/or wet cloths or mops (interiors).

(vii) The certified renovator performed the post-renovation cleaning verification (the results of which must be briefly described, including the number of wet and dry cloths used).

(c) When test kits are used, the renovation firm must, within 30 days of the completion of the renovation, provide identifying information as to the manufacturer and model of the test kits used, a description of the components that were tested including their locations, and the test kit results to the person who contracted for the renovation.

(d) If dust clearance sampling is performed in lieu of cleaning verification as permitted by §745.85(c), the renovation firm must provide, within 30 days of the completion of the renovation, a copy of the dust sampling report to the person who contracted for the renovation.

[73 FR 21761, Apr. 22, 2008]

EFFECTIVE DATE NOTE: At 75 FR 24819, May 6, 2010, §745.86 was amended by removing paragraph (b)(6), redesignating paragraph (b)(7) as (b)(6) and revising paragraphs (b)(1), (c), and (d) effective July 6, 2010. For the convenience of the user, the revised text is set forth as follows:

**§ 745.86 Recordkeeping and reporting requirements.**

\* \* \* \* \*

(b) \* \* \*

(1) Records or reports certifying that a determination had been made that lead-based paint was not present on the components affected by the renovation, as described in §745.82(a). These records or reports include:

(i) Reports prepared by a certified inspector or certified risk assessor (certified pursuant to either Federal regulations at §745.226

**§ 745.87**

**40 CFR Ch. I (7-1-10 Edition)**

or an EPA-authorized State or Tribal certification program).

(i) Records prepared by a certified renovator after using EPA-recognized test kits, including an identification of the manufacturer and model of any test kits used, a description of the components that were tested including their locations, and the result of each test kit used.

\* \* \* \* \*

(c)(1) When the final invoice for the renovation is delivered or within 30 days of the completion of the renovation, whichever is earlier, the renovation firm must provide information pertaining to compliance with this subpart to the following persons:

(i) The owner of the building; and, if different,

(ii) An adult occupant of the residential dwelling, if the renovation took place within a residential dwelling, or an adult representative of the child-occupied facility, if the renovation took place within a child-occupied facility.

(2) When performing renovations in common areas of multi-unit target housing, renovation firms must post the information required by this subpart or instructions on how interested occupants can obtain a copy of this information. This information must be posted in areas where it is likely to be seen by the occupants of all of the affected units.

(3) The information required to be provided by paragraph (c) of this section may be provided by completing the sample form titled "Sample Renovation Recordkeeping Checklist" or a similar form containing the test kit information required by § 745.86(b)(1)(ii) and the training and work practice compliance information required by § 745.86(b)(6).

(d) If dust clearance sampling is performed in lieu of cleaning verification as permitted by § 745.85(c), the renovation firm must provide, when the final invoice for the renovation is delivered or within 30 days of the completion of the renovation, whichever is earlier, a copy of the dust sampling report to:

(1) The owner of the building; and, if different,

(2) An adult occupant of the residential dwelling, if the renovation took place within a residential dwelling, or an adult representative of the child-occupied facility, if the renovation took place within a child-occupied facility.

(3) When performing renovations in common areas of multi-unit target housing, renovation firms must post these dust sampling reports or information on how interested occupants of the housing being renovated can obtain a copy of the report. This information must be posted in areas where they are likely to be seen by the occupants of all of the affected units.

**§ 745.87 Enforcement and inspections.**

(a) Failure or refusal to comply with any provision of this subpart is a violation of TSCA section 409 (15 U.S.C. 2689).

(b) Failure or refusal to establish and maintain records or to make available or permit access to or copying of records, as required by this subpart, is a violation of TSCA sections 15 and 409 (15 U.S.C. 2614 and 2689).

(c) Failure or refusal to permit entry or inspection as required by 40 CFR 745.87 and TSCA section 11 (15 U.S.C. 2610) is a violation of sections 15 and 409 (15 U.S.C. 2614 and 2689).

(d) Violators may be subject to civil and criminal sanctions pursuant to TSCA section 16 (15 U.S.C. 2615) for each violation.

(e) Lead-based paint is assumed to be present at renovations covered by this subpart. EPA may conduct inspections and issue subpoenas pursuant to the provisions of TSCA section 11 (15 U.S.C. 2610) to ensure compliance with this subpart.

[63 FR 29919, June 1, 1998, as amended at 73 FR 21763, Apr. 22, 2008]

**§ 745.88 Recognized test kits.**

(a) Effective June 23, 2008, EPA recognizes the test kits that have been determined by National Institute of Standards and Technology research to meet the negative response criteria described in paragraph (c)(1) of this section. This recognition will last until EPA publicizes its recognition of the first test kit that meets both the negative response and positive response criteria in paragraph (c) of this section.

(b) No other test kits will be recognized until they are tested through EPA's Environmental Technology Verification Program or other equivalent EPA approved testing program.

(1) Effective September 1, 2008, to initiate the testing process, a test kit manufacturer must submit a sufficient number of kits, along with the instructions for using the kits, to EPA. The test kit manufacturer should first visit the following website for information on where to apply: <http://www.epa.gov/etv/howtoapply.html>.

(2) After the kit has been tested through the Environmental Technology Verification Program or other equivalent approved EPA testing program, EPA will review the report to determine whether the required criteria have been met.

(3) Before September 1, 2010, test kits must meet only the negative response criteria in paragraph (c)(1) of this section. The recognition of kits that meet only this criteria will last until EPA publicizes its recognition of the first test kits that meets both of the criteria in paragraph (c) of this section.

(4) After September 1, 2010, test kits must meet both of the criteria in paragraph (c) of this section.

(5) If the report demonstrates that the kit meets the required criteria, EPA will issue a notice of recognition to the kit manufacturer, provide them with the report, and post the information on EPA's website.

(6) If the report demonstrates that the kit does not meet the required criteria, EPA will notify the kit manufacturer and provide them with the report.

(c) *Response criteria*—(1) *Negative response criteria*. For paint containing lead at or above the regulated level, 1.0 mg/cm<sup>2</sup> or 0.5% by weight, a demonstrated probability (with 95% confidence) of a negative response less than or equal to 5% of the time.

(2) *Positive response criteria*. For paint containing lead below the regulated level, 1.0 mg/cm<sup>2</sup> or 0.5% by weight, a demonstrated probability (with 95% confidence) of a positive response less than or equal to 10% of the time.

[73 FR 21763, Apr. 22, 2008]

#### § 745.89 Firm certification.

(a) *Initial certification*. (1) Firms that perform renovations for compensation must apply to EPA for certification to perform renovations or dust sampling. To apply, a firm must submit to EPA a completed "Application for Firms," signed by an authorized agent of the firm, and pay at least the correct amount of fees. If a firm pays more than the correct amount of fees, EPA will reimburse the firm for the excess amount.

(2) After EPA receives a firm's application, EPA will take one of the fol-

lowing actions within 90 days of the date the application is received:

(i) EPA will approve a firm's application if EPA determines that it is complete and that the environmental compliance history of the firm, its principals, or its key employees does not show an unwillingness or inability to maintain compliance with environmental statutes or regulations. An application is complete if it contains all of the information requested on the form and includes at least the correct amount of fees. When EPA approves a firm's application, EPA will issue the firm a certificate with an expiration date not more than 5 years from the date the application is approved. EPA certification allows the firm to perform renovations covered by this section in any State or Indian Tribal area that does not have a renovation program that is authorized under subpart Q of this part.

(ii) EPA will request a firm to supplement its application if EPA determines that the application is incomplete. If EPA requests a firm to supplement its application, the firm must submit the requested information or pay the additional fees within 30 days of the date of the request.

(iii) EPA will not approve a firm's application if the firm does not supplement its application in accordance with paragraph (a)(2)(ii) of this section or if EPA determines that the environmental compliance history of the firm, its principals, or its key employees demonstrates an unwillingness or inability to maintain compliance with environmental statutes or regulations. EPA will send the firm a letter giving the reason for not approving the application. EPA will not refund the application fees. A firm may reapply for certification at any time by filing a new, complete application that includes the correct amount of fees.

(b) *Re-certification*. To maintain its certification, a firm must be re-certified by EPA every 5 years.

(1) *Timely and complete application*. To be re-certified, a firm must submit a complete application for re-certification. A complete application for re-certification includes a completed "Application for Firms" which contains all of the information requested

by the form and is signed by an authorized agent of the firm, noting on the form that it is submitted as a re-certification. A complete application must also include at least the correct amount of fees. If a firm pays more than the correct amount of fees, EPA will reimburse the firm for the excess amount.

(i) An application for re-certification is timely if it is postmarked 90 days or more before the date the firm's current certification expires. If the firm's application is complete and timely, the firm's current certification will remain in effect until its expiration date or until EPA has made a final decision to approve or disapprove the re-certification application, whichever is later.

(ii) If the firm submits a complete re-certification application less than 90 days before its current certification expires, and EPA does not approve the application before the expiration date, the firm's current certification will expire and the firm will not be able to conduct renovations until EPA approves its re-certification application.

(iii) If the firm fails to obtain re-certification before the firm's current certification expires, the firm must not perform renovations or dust sampling until it is certified anew pursuant to paragraph (a) of this section.

(2) *EPA action on an application.* After EPA receives a firm's application for re-certification, EPA will review the application and take one of the following actions within 90 days of receipt:

(i) EPA will approve a firm's application if EPA determines that it is timely and complete and that the environmental compliance history of the firm, its principals, or its key employees does not show an unwillingness or inability to maintain compliance with environmental statutes or regulations. When EPA approves a firm's application for re-certification, EPA will issue the firm a new certificate with an expiration date 5 years from the date that the firm's current certification expires. EPA certification allows the firm to perform renovations or dust sampling covered by this section in any State or Indian Tribal area that does not have a renovation program that is authorized under subpart Q of this part.

(ii) EPA will request a firm to supplement its application if EPA determines that the application is incomplete.

(iii) EPA will not approve a firm's application if it is not received or is not complete as of the date that the firm's current certification expires, or if EPA determines that the environmental compliance history of the firm, its principals, or its key employees demonstrates an unwillingness or inability to maintain compliance with environmental statutes or regulations. EPA will send the firm a letter giving the reason for not approving the application. EPA will not refund the application fees. A firm may reapply for certification at any time by filing a new application and paying the correct amount of fees.

(c) *Amendment of certification.* A firm must amend its certification within 90 days of the date a change occurs to information included in the firm's most recent application. If the firm fails to amend its certification within 90 days of the date the change occurs, the firm may not perform renovations or dust sampling until its certification is amended.

(1) To amend a certification, a firm must submit a completed "Application for Firms," signed by an authorized agent of the firm, noting on the form that it is submitted as an amendment and indicating the information that has changed. The firm must also pay at least the correct amount of fees.

(2) If additional information is needed to process the amendment, or the firm did not pay the correct amount of fees, EPA will request the firm to submit the necessary information or fees. The firm's certification is not amended until the firm complies with the request.

(3) Amending a certification does not affect the certification expiration date.

(d) *Firm responsibilities.* Firms performing renovations must ensure that:

(1) All individuals performing renovation activities on behalf of the firm are either certified renovators or have been trained by a certified renovator in accordance with § 745.90.

(2) A certified renovator is assigned to each renovation performed by the firm and discharges all of the certified

## Environmental Protection Agency

## § 745.90

renovator responsibilities identified in § 745.90.

(3) All renovations performed by the firm are performed in accordance with the work practice standards in § 745.85.

(4) The pre-renovation education requirements of § 745.84 have been performed.

(5) The recordkeeping requirements of § 745.86 are met.

[73 FR 21764, Apr. 22, 2008]

### **§ 745.90 Renovator certification and dust sampling technician certification.**

(a) *Renovator certification and dust sampling technician certification.* (1) To become a certified renovator or certified dust sampling technician, an individual must successfully complete the appropriate course accredited by EPA under § 745.225 or by a State or Tribal program that is authorized under subpart Q of this part. The course completion certificate serves as proof of certification. EPA renovator certification allows the certified individual to perform renovations covered by this section in any State or Indian Tribal area that does not have a renovation program that is authorized under subpart Q of this part. EPA dust sampling technician certification allows the certified individual to perform dust clearance sampling under § 745.85(c) in any State or Indian Tribal area that does not have a renovation program that is authorized under subpart Q of this part.

(2) Individuals who have successfully completed an accredited abatement worker or supervisor course, or individuals who have successfully completed an EPA, HUD, or EPA/HUD model renovation training course may take an accredited refresher renovator training course in lieu of the initial renovator training course to become a certified renovator.

(3) Individuals who have successfully completed an accredited lead-based paint inspector or risk assessor course may take an accredited refresher dust sampling technician course in lieu of the initial training to become a certified dust sampling technician.

(4) To maintain renovator certification or dust sampling technician certification, an individual must complete

a renovator or dust sampling technician refresher course accredited by EPA under § 745.225 or by a State or Tribal program that is authorized under subpart Q of this part within 5 years of the date the individual completed the initial course described in paragraph (a)(1) of this section. If the individual does not complete a refresher course within this time, the individual must re-take the initial course to become certified again.

(b) *Renovator responsibilities.* Certified renovators are responsible for ensuring compliance with § 745.85 at all renovations to which they are assigned. A certified renovator:

(1) Must perform all of the tasks described in § 745.85(b) and must either perform or direct workers who perform all of the tasks described in § 745.85(a).

(2) Must provide training to workers on the work practices they will be using in performing their assigned tasks.

(3) Must be physically present at the work site when the signs required by § 745.85(a)(1) are posted, while the work area containment required by § 745.85(a)(2) is being established, and while the work area cleaning required by § 745.85(a)(5) is performed.

(4) Must regularly direct work being performed by other individuals to ensure that the work practices are being followed, including maintaining the integrity of the containment barriers and ensuring that dust or debris does not spread beyond the work area.

(5) Must be available, either on-site or by telephone, at all times that renovations are being conducted.

(6) When requested by the party contracting for renovation services, must use an acceptable test kit to determine whether components to be affected by the renovation contain lead-based paint.

(7) Must have with them at the work site copies of their initial course completion certificate and their most recent refresher course completion certificate.

(8) Must prepare the records required by § 745.86(b)(7).

(c) *Dust sampling technician responsibilities.* When performing optional dust clearance sampling under



**§ 745.90, Nt.**

**40 CFR Ch. I (7–1–10 Edition)**

§ 745.85(c), a certified dust sampling technician:

(1) Must collect dust samples in accordance with § 745.227(e)(8), must send the collected samples to a laboratory recognized by EPA under TSCA section 405(b), and must compare the results to the clearance levels in accordance with § 745.227(e)(8).

(2) Must have with them at the work site copies of their initial course completion certificate and their most recent refresher course completion certificate.

[73 FR 21765, Apr. 22, 2008]

EFFECTIVE DATE NOTE: At 75 FR 24819, May 6, 2010, § 745.90 was amended by revising paragraphs (a)(4) and (b)(8), effective July 6, 2010. For the convenience of the user, the revised text is set forth as follows:

**§ 745.90 Renovator certification and dust sampling technician certification.**

(a) \* \* \*

(4) To maintain renovator certification or dust sampling technician certification, an individual must complete a renovator or dust sampling technician refresher course accredited by EPA under § 745.225 or by a State or Tribal program that is authorized under subpart Q of this part within 5 years of the date the individual completed the initial course described in paragraph (a)(1) of this section. If the individual does not complete a refresher course within this time, the individual must re-take the initial course to become certified again. Individuals who complete a renovator course accredited by EPA before April 22, 2010, must complete an EPA-accredited renovator refresher course before July 1, 2015, to maintain renovator certification.

(b) \* \* \*

(8) Must prepare the records required by § 745.86(b)(1) and (b)(6).

\* \* \* \* \*

**§ 745.91 Suspending, revoking, or modifying an individual's or firm's certification.**

(a)(1) *Grounds for suspending, revoking, or modifying an individual's certification.* EPA may suspend, revoke, or modify an individual's certification if the individual fails to comply with Federal lead-based paint statutes or regulations. EPA may also suspend, revoke, or modify a certified renovator's certification if the renovator fails to ensure that all assigned renovations comply with § 745.85. In addition to an

administrative or judicial finding of violation, execution of a consent agreement in settlement of an enforcement action constitutes, for purposes of this section, evidence of a failure to comply with relevant statutes or regulations.

(2) *Grounds for suspending, revoking, or modifying a firm's certification.* EPA may suspend, revoke, or modify a firm's certification if the firm:

(i) Submits false or misleading information to EPA in its application for certification or re-certification.

(ii) Fails to maintain or falsifies records required in § 745.86.

(iii) Fails to comply, or an individual performing a renovation on behalf of the firm fails to comply, with Federal lead-based paint statutes or regulations. In addition to an administrative or judicial finding of violation, execution of a consent agreement in settlement of an enforcement action constitutes, for purposes of this section, evidence of a failure to comply with relevant statutes or regulations.

(b) *Process for suspending, revoking, or modifying certification.* (1) Prior to taking action to suspend, revoke, or modify an individual's or firm's certification, EPA will notify the affected entity in writing of the following:

(i) The legal and factual basis for the proposed suspension, revocation, or modification.

(ii) The anticipated commencement date and duration of the suspension, revocation, or modification.

(iii) Actions, if any, which the affected entity may take to avoid suspension, revocation, or modification, or to receive certification in the future.

(iv) The opportunity and method for requesting a hearing prior to final suspension, revocation, or modification.

(2) If an individual or firm requests a hearing, EPA will:

(i) Provide the affected entity an opportunity to offer written statements in response to EPA's assertions of the legal and factual basis for its proposed action.

(ii) Appoint an impartial official of EPA as Presiding Officer to conduct the hearing.

(3) The Presiding Officer will:

(i) Conduct a fair, orderly, and impartial hearing within 90 days of the request for a hearing.

**Environmental Protection Agency**

**§ 745.92**

(ii) Consider all relevant evidence, explanation, comment, and argument submitted.

(iii) Notify the affected entity in writing within 90 days of completion of the hearing of his or her decision and order. Such an order is a final agency action which may be subject to judicial review. The order must contain the commencement date and duration of the suspension, revocation, or modification.

(4) If EPA determines that the public health, interest, or welfare warrants immediate action to suspend the certification of any individual or firm prior to the opportunity for a hearing, it will:

(i) Notify the affected entity in accordance with paragraph (b)(1)(i) through (b)(1)(iii) of this section, explaining why it is necessary to suspend the entity's certification before an opportunity for a hearing.

(ii) Notify the affected entity of its right to request a hearing on the immediate suspension within 15 days of the suspension taking place and the procedures for the conduct of such a hearing.

(5) Any notice, decision, or order issued by EPA under this section, any transcript or other verbatim record of oral testimony, and any documents filed by a certified individual or firm in a hearing under this section will be available to the public, except as otherwise provided by section 14 of TSCA or by part 2 of this title. Any such hearing at which oral testimony is presented will be open to the public, except that the Presiding Officer may exclude the public to the extent necessary to allow presentation of information which may be entitled to confidential treatment under section 14 of TSCA or part 2 of this title.

(6) EPA will maintain a publicly available list of entities whose certification has been suspended, revoked, modified, or reinstated.

(7) Unless the decision and order issued under paragraph (b)(3)(iii) of this section specify otherwise:

(i) An individual whose certification has been suspended must take a refresher training course (renovator or dust sampling technician) in order to make his or her certification current.

(ii) An individual whose certification has been revoked must take an initial renovator or dust sampling technician course in order to become certified again.

(iii) A firm whose certification has been revoked must reapply for certification after the revocation ends in order to become certified again. If the firm's certification has been suspended and the suspension ends less than 5 years after the firm was initially certified or re-certified, the firm does not need to do anything to re-activate its certification.

[73 FR 21765, Apr. 22, 2008]

**§ 745.92 Fees for the accreditation of renovation and dust sampling technician training and the certification of renovation firms.**

(a) *Persons who must pay fees.* Fees in accordance with paragraph (b) of this section must be paid by:

(1) *Training programs*—(i) *Non-exempt training programs.* All non-exempt training programs applying to EPA for the accreditation and re-accreditation of training programs in one or more of the following disciplines: Renovator, dust sampling technician.

(ii) *Exemption.* No fee shall be imposed on any training program operated by a State, federally recognized Indian Tribe, local government, or non-profit organization. This exemption does not apply to the certification of firms or individuals.

(2) *Firms.* All firms applying to EPA for certification and re-certification to conduct renovations.

(b) *Fee amounts*—(1) *Certification and accreditation fees.* Initial and renewal certification and accreditation fees are specified in the following table:

| Training Program                                     | Accreditation | Re-accreditation (every 4 years, see 40 CFR 745.225(f)(1) for details) |
|--|---------------|--|
| Initial Renovator or Dust Sampling Technician Course | \$560         | \$340  |

§ 745.100

40 CFR Ch. I (7–1–10 Edition)

| Training Program  | Accreditation | Re-accreditation (every 4 years, see 40 CFR 745.225(f)(1) for details) |
|---|---------------|--|
| Refresher Renovator or Dust Sampling Technician Course                      | \$400         | \$310  |
| Renovation Firm   | Certification | Re-certification (every 5 years see 40 CFR 745.89(b))                  |
| Firm  | \$300         | \$300  |
| Combined Renovation and Lead-based Paint Activities Firm Application        | \$550         | \$550  |
| Combined Renovation and Lead-based Paint Activities Tribal Firm Application | \$20          | \$20   |
| Tribal Firm   | \$20          | \$20   |

(2) *Lost certificate.* A \$15 fee will be charged for the replacement of a firm certificate.

(c) *Certificate replacement.* Firms seeking certificate replacement must:

(1) Complete the applicable portions of the “Application for Firms” in accordance with the instructions provided.

(2) Submit the application and a payment of \$15 in accordance with the instructions provided with the application package.

(d) *Failure to remit fees.* (1) EPA will not provide certification, re-certification, accreditation, or re-accreditation for any firm or training program that does not remit fees described in paragraph (b) of this section in accordance with the procedures specified in 40 CFR 745.89.

(2) EPA will not replace a certificate for any firm that does not remit the \$15 fee in accordance with the procedures specified in paragraph (c) of this section.

[74 FR 11869, Mar. 20, 2009]

**Subpart F—Disclosure of Known Lead-Based Paint and/or Lead-Based Paint Hazards Upon Sale or Lease of Residential Property**

**§ 745.100 Purpose.**

This subpart implements the provisions of 42 U.S.C. 4852d, which impose certain requirements on the sale or lease of target housing. Under this subpart, a seller or lessor of target housing shall disclose to the purchaser or lessee the presence of any known lead-based paint and/or lead-based paint hazards; provide available records and

reports; provide the purchaser or lessee with a lead hazard information pamphlet; give purchasers a 10-day opportunity to conduct a risk assessment or inspection; and attach specific disclosure and warning language to the sales or leasing contract before the purchaser or lessee is obligated under a contract to purchase or lease target housing.

**§ 745.101 Scope and applicability.**

This subpart applies to all transactions to sell or lease target housing, including subleases, with the exception of the following:

(a) Sales of target housing at foreclosure.

(b) Leases of target housing that have been found to be lead-based paint free by an inspector certified under the Federal certification program or under a federally accredited State or tribal certification program. Until a Federal certification program or federally accredited State certification program is in place within the State, inspectors shall be considered qualified to conduct an inspection for this purpose if they have received certification under any existing State or tribal inspector certification program. The lessor has the option of using the results of additional test(s) by a certified inspector to confirm or refute a prior finding.

(c) Short-term leases of 100 days or less, where no lease renewal or extension can occur.

(d) Renewals of existing leases in target housing in which the lessor has previously disclosed all information required under § 745.107 and where no new information described in § 745.107 has come into the possession of the lessor.

## Environmental Protection Agency

## § 745.103

For the purposes of this paragraph, renewal shall include both renegotiation of existing lease terms and/or ratification of a new lease.

### § 745.102 Effective dates.

The requirements in this subpart take effect in the following manner:

(a) For owners of more than four residential dwellings, the requirements shall take effect on September 6, 1996.

(b) For owners of one to four residential dwellings, the requirements shall take effect on December 6, 1996.

### § 745.103 Definitions.

The following definitions apply to this subpart.

*The Act* means the Residential Lead-Based Paint Hazard Reduction Act of 1992, 42 U.S.C. 4852d.

*Agent* means any party who enters into a contract with a seller or lessor, including any party who enters into a contract with a representative of the seller or lessor, for the purpose of selling or leasing target housing. This term does not apply to purchasers or any purchaser's representative who receives all compensation from the purchaser.

*Available* means in the possession of or reasonably obtainable by the seller or lessor at the time of the disclosure.

*Common area* means a portion of a building generally accessible to all residents/users including, but not limited to, hallways, stairways, laundry and recreational rooms, playgrounds, community centers, and boundary fences.

*Contract for the purchase and sale of residential real property* means any contract or agreement in which one party agrees to purchase an interest in real property on which there is situated one or more residential dwellings used or occupied, or intended to be used or occupied, in whole or in part, as the home or residence of one or more persons.

*EPA* means the Environmental Protection Agency.

*Evaluation* means a risk assessment and/or inspection.

*Foreclosure* means any of the various methods, statutory or otherwise, known in different jurisdictions, of enforcing payment of a debt, by the taking and selling of real property.

*Housing for the elderly* means retirement communities or similar types of housing reserved for households composed of one or more persons 62 years of age or more at the time of initial occupancy.

*HUD* means the U.S. Department of Housing and Urban Development.

*Inspection* means:

(1) A surface-by-surface investigation to determine the presence of lead-based paint as provided in section 302(c) of the Lead-Based Paint Poisoning and Prevention Act [42 U.S.C. 4822], and

(2) The provision of a report explaining the results of the investigation.

*Lead-based paint* means paint or other surface coatings that contain lead equal to or in excess of 1.0 milligram per square centimeter or 0.5 percent by weight.

*Lead-based paint free housing* means target housing that has been found to be free of paint or other surface coatings that contain lead equal to or in excess of 1.0 milligram per square centimeter or 0.5 percent by weight.

*Lead-based paint hazard* means any condition that causes exposure to lead from lead-contaminated dust, lead-contaminated soil, or lead-contaminated paint that is deteriorated or present in accessible surfaces, friction surfaces, or impact surfaces that would result in adverse human health effects as established by the appropriate Federal agency.

*Lessee* means any entity that enters into an agreement to lease, rent, or sublease target housing, including but not limited to individuals, partnerships, corporations, trusts, government agencies, housing agencies, Indian tribes, and nonprofit organizations.

*Lessor* means any entity that offers target housing for lease, rent, or sublease, including but not limited to individuals, partnerships, corporations, trusts, government agencies, housing agencies, Indian tribes, and nonprofit organizations.

*Owner* means any entity that has legal title to target housing, including but not limited to individuals, partnerships, corporations, trusts, government agencies, housing agencies, Indian tribes, and nonprofit organizations, except where a mortgagee holds legal title to property serving as collateral

**§ 745.107**

**40 CFR Ch. I (7-1-10 Edition)**

for a mortgage loan, in which case the owner would be the mortgagor.

*Purchaser* means an entity that enters into an agreement to purchase an interest in target housing, including but not limited to individuals, partnerships, corporations, trusts, government agencies, housing agencies, Indian tribes, and nonprofit organizations.

*Reduction* means measures designed to reduce or eliminate human exposure to lead-based paint hazards through methods including interim controls and abatement.

*Residential dwelling* means:

(1) A single-family dwelling, including attached structures such as porches and stoops; or

(2) A single-family dwelling unit in a structure that contains more than one separate residential dwelling unit, and in which each such unit is used or occupied, or intended to be used or occupied, in whole or in part, as the residence of one or more persons.

*Risk assessment* means an on-site investigation to determine and report the existence, nature, severity, and location of lead-based paint hazards in residential dwellings, including:

(1) Information gathering regarding the age and history of the housing and occupancy by children under age 6;

(2) Visual inspection;

(3) Limited wipe sampling or other environmental sampling techniques;

(4) Other activity as may be appropriate; and

(5) Provision of a report explaining the results of the investigation.

*Secretary* means the Secretary of Housing and Urban Development.

*Seller* means any entity that transfers legal title to target housing, in whole or in part, in return for consideration, including but not limited to individuals, partnerships, corporations, trusts, government agencies, housing agencies, Indian tribes, and nonprofit organizations. The term "seller" also includes:

(1) An entity that transfers shares in a cooperatively owned project, in return for consideration; and

(2) An entity that transfers its interest in a leasehold, in jurisdictions or circumstances where it is legally permissible to separate the fee title from

the title to the improvement, in return for consideration.

*Target housing* means any housing constructed prior to 1978, except housing for the elderly or persons with disabilities (unless any child who is less than 6 years of age resides or is expected to reside in such housing) or any 0-bedroom dwelling.

*TSCA* means the Toxic Substances Control Act, 15 U.S.C. 2601.

*0-bedroom dwelling* means any residential dwelling in which the living area is not separated from the sleeping area. The term includes efficiencies, studio apartments, dormitory housing, military barracks, and rentals of individual rooms in residential dwellings.

**§ 745.107 Disclosure requirements for sellers and lessors.**

(a) The following activities shall be completed before the purchaser or lessee is obligated under any contract to purchase or lease target housing that is not otherwise an exempt transaction pursuant to § 745.101. Nothing in this section implies a positive obligation on the seller or lessor to conduct any evaluation or reduction activities.

(1) The seller or lessor shall provide the purchaser or lessee with an EPA-approved lead hazard information pamphlet. Such pamphlets include the EPA document entitled *Protect Your Family From Lead in Your Home* (EPA #747-K-94-001) or an equivalent pamphlet that has been approved for use in that State by EPA.

(2) The seller or lessor shall disclose to the purchaser or lessee the presence of any known lead-based paint and/or lead-based paint hazards in the target housing being sold or leased. The seller or lessor shall also disclose any additional information available concerning the known lead-based paint and/or lead-based paint hazards, such as the basis for the determination that lead-based paint and/or lead-based paint hazards exist, the location of the lead-based paint and/or lead-based paint hazards, and the condition of the painted surfaces.

(3) The seller or lessor shall disclose to each agent the presence of any known lead-based paint and/or lead-

## Environmental Protection Agency

## § 745.113

based paint hazards in the target housing being sold or leased and the existence of any available records or reports pertaining to lead-based paint and/or lead-based paint hazards. The seller or lessor shall also disclose any additional information available concerning the known lead-based paint and/or lead-based paint hazards, such as the basis for the determination that lead-based paint and/or lead-based paint hazards exist, the location of the lead-based paint and/or lead-based paint hazards, and the condition of the painted surfaces.

(4) The seller or lessor shall provide the purchaser or lessee with any records or reports available to the seller or lessor pertaining to lead-based paint and/or lead-based paint hazards in the target housing being sold or leased. This requirement includes records or reports regarding common areas. This requirement also includes records or reports regarding other residential dwellings in multifamily target housing, provided that such information is part of an evaluation or reduction of lead-based paint and/or lead-based paint hazards in the target housing as a whole.

(b) If any of the disclosure activities identified in paragraph (a) of this section occurs after the purchaser or lessee has provided an offer to purchase or lease the housing, the seller or lessor shall complete the required disclosure activities prior to accepting the purchaser's or lessee's offer and allow the purchaser or lessee an opportunity to review the information and possibly amend the offer.

### **§ 745.110 Opportunity to conduct an evaluation.**

(a) Before a purchaser is obligated under any contract to purchase target housing, the seller shall permit the purchaser a 10-day period (unless the parties mutually agree, in writing, upon a different period of time) to conduct a risk assessment or inspection for the presence of lead-based paint and/or lead-based paint hazards.

(b) Notwithstanding paragraph (a) of this section, a purchaser may waive the opportunity to conduct the risk assessment or inspection by so indicating in writing.

### **§ 745.113 Certification and acknowledgment of disclosure.**

(a) *Seller requirements.* Each contract to sell target housing shall include an attachment containing the following elements, in the language of the contract (e.g., English, Spanish):

(1) A Lead Warning Statement consisting of the following language:

Every purchaser of any interest in residential real property on which a residential dwelling was built prior to 1978 is notified that such property may present exposure to lead from lead-based paint that may place young children at risk of developing lead poisoning. Lead poisoning in young children may produce permanent neurological damage, including learning disabilities, reduced intelligence quotient, behavioral problems, and impaired memory. Lead poisoning also poses a particular risk to pregnant women. The seller of any interest in residential real property is required to provide the buyer with any information on lead-based paint hazards from risk assessments or inspections in the seller's possession and notify the buyer of any known lead-based paint hazards. A risk assessment or inspection for possible lead-based paint hazards is recommended prior to purchase.

(2) A statement by the seller disclosing the presence of known lead-based paint and/or lead-based paint hazards in the target housing being sold or indicating no knowledge of the presence of lead-based paint and/or lead-based paint hazards. The seller shall also provide any additional information available concerning the known lead-based paint and/or lead-based paint hazards, such as the basis for the determination that lead-based paint and/or lead-based paint hazards exist, the location of the lead-based paint and/or lead-based paint hazards, and the condition of the painted surfaces.

(3) A list of any records or reports available to the seller pertaining to lead-based paint and/or lead-based paint hazards in the housing that have been provided to the purchaser. If no such records or reports are available, the seller shall so indicate.

(4) A statement by the purchaser affirming receipt of the information set out in paragraphs (a)(2) and (a)(3) of this section and the lead hazard information pamphlet required under 15 U.S.C. 2696.

(5) A statement by the purchaser that he/she has either:

(i) Received the opportunity to conduct the risk assessment or inspection required by § 745.110(a); or

(ii) Waived the opportunity.

(6) When one or more agents are involved in the transaction to sell target housing on behalf of the seller, a statement that:

(i) The agent has informed the seller of the seller's obligations under 42 U.S.C. 4852d; and

(ii) The agent is aware of his/her duty to ensure compliance with the requirements of this subpart.

(7) The signatures of the sellers, agents, and purchasers certifying to the accuracy of their statements to the best of their knowledge, along with the dates of signature.

(b) *Lessor requirements.* Each contract to lease target housing shall include, as an attachment or within the contract, the following elements, in the language of the contract (e.g., English, Spanish):

(1) A Lead Warning Statement with the following language:

Housing built before 1978 may contain lead-based paint. Lead from paint, paint chips, and dust can pose health hazards if not managed properly. Lead exposure is especially harmful to young children and pregnant women. Before renting pre-1978 housing, lessors must disclose the presence of lead-based paint and/or lead-based paint hazards in the dwelling. Lessees must also receive a federally approved pamphlet on lead poisoning prevention.

(2) A statement by the lessor disclosing the presence of known lead-based paint and/or lead-based paint hazards in the target housing being leased or indicating no knowledge of the presence of lead-based paint and/or lead-based paint hazards. The lessor shall also disclose any additional information available concerning the known lead-based paint and/or lead-based paint hazards, such as the basis for the determination that lead-based paint and/or lead-based paint hazards exist, the location of the lead-based paint and/or lead-based paint hazards, and the condition of the painted surfaces.

(3) A list of any records or reports available to the lessor pertaining to lead-based paint and/or lead-based

paint hazards in the housing that have been provided to the lessee. If no such records or reports are available, the lessor shall so indicate.

(4) A statement by the lessee affirming receipt of the information set out in paragraphs (b)(2) and (b)(3) of this section and the lead hazard information pamphlet required under 15 U.S.C. 2696.

(5) When one or more agents are involved in the transaction to lease target housing on behalf of the lessor, a statement that:

(i) The agent has informed the lessor of the lessor as obligations under 42 U.S.C. 4852d; and

(ii) The agent is aware of his/her duty to ensure compliance with the requirements of this subpart.

(6) The signatures of the lessors, agents, and lessees, certifying to the accuracy of their statements, to the best of their knowledge, along with the dates of signature.

(c) *Retention of Certification and Acknowledgment Information.*

(1) The seller, and any agent, shall retain a copy of the completed attachment required under paragraph (a) of this section for no less than 3 years from the completion date of the sale. The lessor, and any agent, shall retain a copy of the completed attachment or lease contract containing the information required under paragraph (b) of this section for no less than 3 years from the commencement of the leasing period.

(2) This recordkeeping requirement is not intended to place any limitations on civil suits under the Act, or to otherwise affect a lessee's or purchaser's rights under the civil penalty provisions of 42 U.S.C. 4852d(b)(3).

(d) The seller, lessor, or agent shall not be responsible for the failure of a purchaser's or lessee's legal representative (where such representative receives all compensation from the purchaser or lessee) to transmit disclosure materials to the purchaser or lessee, provided that all required parties have completed and signed the necessary certification and acknowledgment language required under paragraphs (a) and (b) of this section.

## Environmental Protection Agency

## § 745.220

### § 745.115 Agent responsibilities.

(a) Each agent shall ensure compliance with all requirements of this subpart. To ensure compliance, the agent shall:

(1) Inform the seller or lessor of his/her obligations under §§ 745.107, 745.110, and 745.113.

(2) Ensure that the seller or lessor has performed all activities required under §§ 745.107, 745.110, and 745.113, or personally ensure compliance with the requirements of §§ 745.107, 745.110, and 745.113.

(b) If the agent has complied with paragraph (a)(1) of this section, the agent shall not be liable for the failure to disclose to a purchaser or lessee the presence of lead-based paint and/or lead-based paint hazards known by a seller or lessor but not disclosed to the agent.

### § 745.118 Enforcement.

(a) Any person who knowingly fails to comply with any provision of this subpart shall be subject to civil monetary penalties in accordance with the provisions of 42 U.S.C. 3545 and 24 CFR part 30.

(b) The Secretary is authorized to take such action as may be necessary to enjoin any violation of this subpart in the appropriate Federal district court.

(c) Any person who knowingly violates the provisions of this subpart shall be jointly and severally liable to the purchaser or lessee in an amount equal to 3 times the amount of damages incurred by such individual.

(d) In any civil action brought for damages pursuant to 42 U.S.C. 4852d(b)(3), the appropriate court may award court costs to the party commencing such action, together with reasonable attorney fees and any expert witness fees, if that party prevails.

(e) Failure or refusal to comply with § 745.107 (disclosure requirements for sellers and lessors), § 745.110 (opportunity to conduct an evaluation), § 745.113 (certification and acknowledgment of disclosure), or § 745.115 (agent responsibilities) is a violation of 42 U.S.C. 4852d(b)(5) and of TSCA section 409 (15 U.S.C. 2689).

(f) Violators may be subject to civil and criminal sanctions pursuant to

TSCA section 16 (15 U.S.C. 2615) for each violation. For purposes of enforcing this subpart, the penalty for each violation applicable under 15 U.S.C. 2615 shall not be more than \$11,000 for all violations occurring after July 28, 1997; all violations occurring on or prior to that date are subject to a penalty not more than \$10,000.

[61 FR 9085, Mar. 6, 1996, as amended at 62 FR 35041, June 27, 1997]

### § 745.119 Impact on State and local requirements.

Nothing in this subpart shall relieve a seller, lessor, or agent from any responsibility for compliance with State or local laws, ordinances, codes, or regulations governing notice or disclosure of known lead-based paint or lead-based paint hazards. Neither HUD nor EPA assumes any responsibility for ensuring compliance with such State or local requirements.

## Subparts G–K [Reserved]

## Subpart L—Lead-Based Paint Activities

SOURCE: 61 FR 45813, Aug. 29, 1996, unless otherwise noted.

### § 745.220 Scope and applicability.

(a) This subpart contains procedures and requirements for the accreditation of training programs for lead-based paint activities and renovations, procedures and requirements for the certification of individuals and firms engaged in lead-based paint activities, and work practice standards for performing such activities. This subpart also requires that, except as discussed below, all lead-based paint activities, as defined in this subpart, be performed by certified individuals and firms.

(b) This subpart applies to all individuals and firms who are engaged in lead-based paint activities as defined in § 745.223, except persons who perform these activities within residential dwellings that they own, unless the residential dwelling is occupied by a person or persons other than the owner or the owner's immediate family while these activities are being performed, or a child residing in the building has



**§ 745.223**

**40 CFR Ch. I (7–1–10 Edition)**

been identified as having an elevated blood lead level. This subpart applies only in those States or Indian Country that do not have an authorized State or Tribal program pursuant to § 745.324 of subpart Q.

(c) Each department, agency, and instrumentality of the executive, legislative, and judicial branches of the Federal Government having jurisdiction over any property or facility, or engaged in any activity resulting, or which may result, in a lead-based paint hazard, and each officer, agent, or employee thereof shall be subject to, and comply with, all Federal, State, interstate, and local requirements, both substantive and procedural, including the requirements of this subpart regarding lead-based paint, lead-based paint activities, and lead-based paint hazards.

(d) While this subpart establishes specific requirements for performing lead-based paint activities should they be undertaken, nothing in this subpart requires that the owner or occupant undertake any particular lead-based paint activity.

[61 FR 45813, Aug. 29, 1996, as amended at 73 FR 21766, Apr. 22, 2008]

**§ 745.223 Definitions.**

The definitions in subpart A apply to this subpart. In addition, the following definitions apply.

*Abatement* means any measure or set of measures designed to permanently eliminate lead-based paint hazards. Abatement includes, but is not limited to:

(1) The removal of paint and dust, the permanent enclosure or encapsulation of lead-based paint, the replacement of painted surfaces or fixtures, or the removal or permanent covering of soil, when lead-based paint hazards are present in such paint, dust or soil; and

(2) All preparation, cleanup, disposal, and post-abatement clearance testing activities associated with such measures.

(3) Specifically, abatement includes, but is not limited to:

(i) Projects for which there is a written contract or other documentation, which provides that an individual or firm will be conducting activities in or

to a residential dwelling or child-occupied facility that:

(A) Shall result in the permanent elimination of lead-based paint hazards; or

(B) Are designed to permanently eliminate lead-based paint hazards and are described in paragraphs (1) and (2) of this definition.

(ii) Projects resulting in the permanent elimination of lead-based paint hazards, conducted by firms or individuals certified in accordance with § 745.226, unless such projects are covered by paragraph (4) of this definition;

(iii) Projects resulting in the permanent elimination of lead-based paint hazards, conducted by firms or individuals who, through their company name or promotional literature, represent, advertise, or hold themselves out to be in the business of performing lead-based paint activities as identified and defined by this section, unless such projects are covered by paragraph (4) of this definition; or

(iv) Projects resulting in the permanent elimination of lead-based paint hazards, that are conducted in response to State or local abatement orders.

(4) Abatement does not include renovation, remodeling, landscaping or other activities, when such activities are not designed to permanently eliminate lead-based paint hazards, but, instead, are designed to repair, restore, or remodel a given structure or dwelling, even though these activities may incidentally result in a reduction or elimination of lead-based paint hazards. Furthermore, abatement does not include interim controls, operations and maintenance activities, or other measures and activities designed to temporarily, but not permanently, reduce lead-based paint hazards.

*Accredited training program* means a training program that has been accredited by EPA pursuant to § 745.225 to provide training for individuals engaged in lead-based paint activities.

*Adequate quality control* means a plan or design which ensures the authenticity, integrity, and accuracy of samples, including dust, soil, and paint chip or paint film samples. Adequate quality control also includes provisions for representative sampling.

## Environmental Protection Agency

## § 745.223

*Business day* means Monday through Friday with the exception of Federal holidays.

*Certified firm* means a company, partnership, corporation, sole proprietorship, association, or other business entity that performs lead-based paint activities to which EPA has issued a certificate of approval pursuant to § 745.226(f).

*Certified inspector* means an individual who has been trained by an accredited training program, as defined by this section, and certified by EPA pursuant to § 745.226 to conduct inspections. A certified inspector also samples for the presence of lead in dust and soil for the purposes of abatement clearance testing.

*Certified abatement worker* means an individual who has been trained by an accredited training program, as defined by this section, and certified by EPA pursuant to § 745.226 to perform abatements.

*Certified project designer* means an individual who has been trained by an accredited training program, as defined by this section, and certified by EPA pursuant to § 745.226 to prepare abatement project designs, occupant protection plans, and abatement reports.

*Certified risk assessor* means an individual who has been trained by an accredited training program, as defined by this section, and certified by EPA pursuant to § 745.226 to conduct risk assessments. A risk assessor also samples for the presence of lead in dust and soil for the purposes of abatement clearance testing.

*Certified supervisor* means an individual who has been trained by an accredited training program, as defined by this section, and certified by EPA pursuant to § 745.226 to supervise and conduct abatements, and to prepare occupant protection plans and abatement reports.

*Child-occupied facility* means a building, or portion of a building, constructed prior to 1978, visited regularly by the same child, 6 years of age or under, on at least two different days within any week (Sunday through Saturday period), provided that each day's visit lasts at least 3 hours and the combined weekly visit lasts at least 6 hours, and the combined annual visits

last at least 60 hours. Child-occupied facilities may include, but are not limited to, day-care centers, preschools and kindergarten classrooms.

*Clearance levels* are values that indicate the maximum amount of lead permitted in dust on a surface following completion of an abatement activity.

*Common area* means a portion of a building that is generally accessible to all occupants. Such an area may include, but is not limited to, hallways, stairways, laundry and recreational rooms, playgrounds, community centers, garages, and boundary fences.

*Component or building component* means specific design or structural elements or fixtures of a building, residential dwelling, or child-occupied facility that are distinguished from each other by form, function, and location. These include, but are not limited to, interior components such as: ceilings, crown molding, walls, chair rails, doors, door trim, floors, fireplaces, radiators and other heating units, shelves, shelf supports, stair treads, stair risers, stair stringers, newel posts, railing caps, balustrades, windows and trim (including sashes, window heads, jambs, sills or stools and troughs), built in cabinets, columns, beams, bathroom vanities, counter tops, and air conditioners; and exterior components such as: painted roofing, chimneys, flashing, gutters and downspouts, ceilings, soffits, fascias, rake boards, cornerboards, bulkheads, doors and door trim, fences, floors, joists, lattice work, railings and railing caps, siding, handrails, stair risers and treads, stair stringers, columns, balustrades, window sills or stools and troughs, casings, sashes and wells, and air conditioners.

*Containment* means a process to protect workers and the environment by controlling exposures to the lead-contaminated dust and debris created during an abatement.

*Course agenda* means an outline of the key topics to be covered during a training course, including the time allotted to teach each topic.

*Course test* means an evaluation of the overall effectiveness of the training which shall test the trainees' knowledge and retention of the topics covered during the course.

*Course test blue print* means written documentation identifying the proportion of course test questions devoted to each major topic in the course curriculum.

*Deteriorated paint* means paint that is cracking, flaking, chipping, peeling, or otherwise separating from the substrate of a building component.

*Discipline* means one of the specific types or categories of lead-based paint activities identified in this subpart for which individuals may receive training from accredited programs and become certified by EPA. For example, “abatement worker” is a discipline.

*Distinct painting history* means the application history, as indicated by its visual appearance or a record of application, over time, of paint or other surface coatings to a component or room.

*Documented methodologies* are methods or protocols used to sample for the presence of lead in paint, dust, and soil.

*Elevated blood lead level (EBL)* means an excessive absorption of lead that is a confirmed concentration of lead in whole blood of 20 µg/dl (micrograms of lead per deciliter of whole blood) for a single venous test or of 15–19 µg/dl in two consecutive tests taken 3 to 4 months apart.

*Encapsulant* means a substance that forms a barrier between lead-based paint and the environment using a liquid-applied coating (with or without reinforcement materials) or an adhesively bonded covering material.

*Encapsulation* means the application of an encapsulant.

*Enclosure* means the use of rigid, durable construction materials that are mechanically fastened to the substrate in order to act as a barrier between lead-based paint and the environment.

*Guest instructor* means an individual designated by the training program manager or principal instructor to provide instruction specific to the lecture, hands-on activities, or work practice components of a course.

*Hands-on skills assessment* means an evaluation which tests the trainees’ ability to satisfactorily perform the work practices and procedures identified in §745.225(d), as well as any other skill taught in a training course.

*Hazardous waste* means any waste as defined in 40 CFR 261.3.

*Inspection* means a surface-by-surface investigation to determine the presence of lead-based paint and the provision of a report explaining the results of the investigation.

*Interim certification* means the status of an individual who has successfully completed the appropriate training course in a discipline from an accredited training program, as defined by this section, but has not yet received formal certification in that discipline from EPA pursuant to §745.226. Interim certifications expire 6 months after the completion of the training course, and is equivalent to a certificate for the 6-month period.

*Interim controls* means a set of measures designed to temporarily reduce human exposure or likely exposure to lead-based paint hazards, including specialized cleaning, repairs, maintenance, painting, temporary containment, ongoing monitoring of lead-based paint hazards or potential hazards, and the establishment and operation of management and resident education programs.

*Lead-based paint* means paint or other surface coatings that contain lead equal to or in excess of 1.0 milligrams per square centimeter or more than 0.5 percent by weight.

*Lead-based paint activities* means, in the case of target housing and child-occupied facilities, inspection, risk assessment, and abatement, as defined in this subpart.

*Lead-based paint activities courses* means initial and refresher training courses (worker, supervisor, inspector, risk assessor, project designer) provided by accredited training programs.

*Lead-based paint hazard* means any condition that causes exposure to lead from lead-contaminated dust, lead-contaminated soil, or lead-contaminated paint that is deteriorated or present in accessible surfaces, friction surfaces, or impact surfaces that would result in adverse human health effects as identified by the Administrator pursuant to TSCA section 403.

*Lead-hazard screen* is a limited risk assessment activity that involves limited paint and dust sampling as described in §745.227(c).

*Living area* means any area of a residential dwelling used by one or more

## Environmental Protection Agency

## § 745.223

children age 6 and under, including, but not limited to, living rooms, kitchen areas, dens, play rooms, and children's bedrooms.

*Local government* means a county, city, town, borough, parish, district, association, or other public body (including an agency comprised of two or more of the foregoing entities) created under State law.

*Multi-family dwelling* means a structure that contains more than one separate residential dwelling unit, which is used or occupied, or intended to be used or occupied, in whole or in part, as the home or residence of one or more persons.

*Nonprofit* means an entity which has demonstrated to any branch of the Federal Government or to a State, municipal, tribal or territorial government, that no part of its net earnings inure to the benefit of any private shareholder or individual.

*Paint in poor condition* means more than 10 square feet of deteriorated paint on exterior components with large surface areas; or more than 2 square feet of deteriorated paint on interior components with large surface areas (e.g., walls, ceilings, floors, doors); or more than 10 percent of the total surface area of the component is deteriorated on interior or exterior components with small surface areas (window sills, baseboards, soffits, trim).

*Permanently covered soil* means soil which has been separated from human contact by the placement of a barrier consisting of solid, relatively impermeable materials, such as pavement or concrete. Grass, mulch, and other landscaping materials are not considered permanent covering.

*Person* means any natural or judicial person including any individual, corporation, partnership, or association; any Indian Tribe, State, or political subdivision thereof; any interstate body; and any department, agency, or instrumentality of the Federal government.

*Principal instructor* means the individual who has the primary responsibility for organizing and teaching a particular course.

*Recognized laboratory* means an environmental laboratory recognized by

EPA pursuant to TSCA section 405(b) as being capable of performing an analysis for lead compounds in paint, soil, and dust.

*Reduction* means measures designed to reduce or eliminate human exposure to lead-based paint hazards through methods including interim controls and abatement.

*Residential dwelling* means (1) a detached single family dwelling unit, including attached structures such as porches and stoops; or (2) a single family dwelling unit in a structure that contains more than one separate residential dwelling unit, which is used or occupied, or intended to be used or occupied, in whole or in part, as the home or residence of one or more persons.

*Risk assessment* means (1) an on-site investigation to determine the existence, nature, severity, and location of lead-based paint hazards, and (2) the provision of a report by the individual or the firm conducting the risk assessment, explaining the results of the investigation and options for reducing lead-based paint hazards.

*Start date* means the first day of any lead-based paint activities training course or lead-based paint abatement activity.

*Start date provided to EPA* means the start date included in the original notification or the most recent start date provided to EPA in an updated notification.

*State* means any State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, the Canal Zone, American Samoa, the Northern Mariana Islands, or any other territory or possession of the United States.

*Target housing* means any housing constructed prior to 1978, except housing for the elderly or persons with disabilities (unless any one or more children age 6 years or under resides or is expected to reside in such housing for the elderly or persons with disabilities) or any 0-bedroom dwelling.

*Training curriculum* means an established set of course topics for instruction in an accredited training program for a particular discipline designed to provide specialized knowledge and skills.

§ 745.225

40 CFR Ch. I (7-1-10 Edition)

*Training hour* means at least 50 minutes of actual learning, including, but not limited to, time devoted to lecture, learning activities, small group activities, demonstrations, evaluations, and/or hands-on experience.

*Training manager* means the individual responsible for administering a training program and monitoring the performance of principal instructors and guest instructors.

*Training provider* means any organization or entity accredited under § 745.225 to offer lead-based paint activities courses.

*Visual inspection for clearance testing* means the visual examination of a residential dwelling or a child-occupied facility following an abatement to determine whether or not the abatement has been successfully completed.

*Visual inspection for risk assessment* means the visual examination of a residential dwelling or a child-occupied facility to determine the existence of deteriorated lead-based paint or other potential sources of lead-based paint hazards.

[61 FR 45813, Aug. 29, 1996, as amended at 64 FR 31097, June 9, 1999; 66 FR 1239, Jan. 5, 2001; 69 FR 18495, Apr. 8, 2004]

**§ 745.225 Accreditation of training programs: target housing and child-occupied facilities.**

(a) *Scope.* (1) A training program may seek accreditation to offer courses in any of the following disciplines: Inspector, risk assessor, supervisor, project designer, abatement worker, renovator, and dust sampling technician. A training program may also seek accreditation to offer refresher courses for each of the above listed disciplines.

(2) Training programs may first apply to EPA for accreditation of their lead-based paint activities courses or refresher courses pursuant to this section on or after August 31, 1998. Training programs may first apply to EPA for accreditation of their renovator or dust sampling technician courses or refresher courses pursuant to this section on or after April 22, 2009.

(3) A training program must not provide, offer, or claim to provide EPA-accredited lead-based paint activities courses without applying for and receiving accreditation from EPA as re-

quired under paragraph (b) of this section on or after March 1, 1999. A training program must not provide, offer, or claim to provide EPA-accredited renovator or dust sampling technician courses without applying for and receiving accreditation from EPA as required under paragraph (b) of this section on or after June 23, 2008.

(b) *Application process.* The following are procedures a training program must follow to receive EPA accreditation to offer lead-based paint activities courses, renovator courses, or dust sampling technician courses:

(1) A training program seeking accreditation shall submit a written application to EPA containing the following information:

(i) The training program's name, address, and telephone number.

(ii) A list of courses for which it is applying for accreditation. For the purposes of this section, courses taught in different languages are considered different courses, and each must independently meet the accreditation requirements.

(iii) A statement signed by the training program manager certifying that the training program meets the requirements established in paragraph (c) of this section. If a training program uses EPA-recommended model training materials, or training materials approved by a State or Indian Tribe that has been authorized by EPA under subpart Q of this part, the training program manager shall include a statement certifying that, as well.

(iv) If a training program does not use EPA-recommended model training materials or training materials approved by an authorized State or Indian Tribe, its application for accreditation shall also include:

(A) A copy of the student and instructor manuals, or other materials to be used for each course.

(B) A copy of the course agenda for each course.

(C) When applying for accreditation of a course in a language other than English, a signed statement from a qualified, independent translator that they had compared the course to the English language version and found the translation to be accurate.

## Environmental Protection Agency

## § 745.225

(v) All training programs shall include in their application for accreditation the following:

(A) A description of the facilities and equipment to be used for lecture and hands-on training.

(B) A copy of the course test blueprint for each course.

(C) A description of the activities and procedures that will be used for conducting the assessment of hands-on skills for each course.

(D) A copy of the quality control plan as described in paragraph (c)(9) of this section.

(2) If a training program meets the requirements in paragraph (c) of this section, then EPA shall approve the application for accreditation no more than 180 days after receiving a complete application from the training program. In the case of approval, a certificate of accreditation shall be sent to the applicant. In the case of disapproval, a letter describing the reasons for disapproval shall be sent to the applicant. Prior to disapproval, EPA may, at its discretion, work with the applicant to address inadequacies in the application for accreditation. EPA may also request additional materials retained by the training program under paragraph (i) of this section. If a training program's application is disapproved, the program may reapply for accreditation at any time.

(3) A training program may apply for accreditation to offer courses or refresher courses in as many disciplines as it chooses. A training program may seek accreditation for additional courses at any time as long as the program can demonstrate that it meets the requirements of this section.

(4) A training program applying for accreditation must submit the appropriate fees in accordance with § 745.238.

(c) *Requirements for the accreditation of training programs.* For a training program to obtain accreditation from EPA to offer lead-based paint activities courses, renovator courses, or dust sampling technician courses, the program must meet the following requirements:

(1) The training program shall employ a training manager who has:

(i) At least 2 years of experience, education, or training in teaching workers or adults; or

(ii) A bachelor's or graduate degree in building construction technology, engineering, industrial hygiene, safety, public health, education, business administration or program management or a related field; or

(iii) Two years of experience in managing a training program specializing in environmental hazards; and

(iv) Demonstrated experience, education, or training in the construction industry including: lead or asbestos abatement, painting, carpentry, renovation, remodeling, occupational safety and health, or industrial hygiene.

(2) The training manager shall designate a qualified principal instructor for each course who has:

(i) Demonstrated experience, education, or training in teaching workers or adults; and

(ii) Successfully completed at least 16 hours of any EPA-accredited or EPA-authorized State or Tribal-accredited lead-specific training; and

(iii) Demonstrated experience, education, or training in lead or asbestos abatement, painting, carpentry, renovation, remodeling, occupational safety and health, or industrial hygiene.

(3) The principal instructor shall be responsible for the organization of the course and oversight of the teaching of all course material. The training manager may designate guest instructors as needed to provide instruction specific to the lecture, hands-on activities, or work practice components of a course.

(4) The following documents shall be recognized by EPA as evidence that training managers and principal instructors have the education, work experience, training requirements or demonstrated experience, specifically listed in paragraphs (c)(1) and (c)(2) of this section. This documentation need not be submitted with the accreditation application, but, if not submitted, shall be retained by the training program as required by the recordkeeping requirements contained in paragraph (i) of this section. Those documents include the following:

(i) Official academic transcripts or diploma as evidence of meeting the education requirements.

(ii) Resumes, letters of reference, or documentation of work experience, as evidence of meeting the work experience requirements.

(iii) Certificates from train-the-trainer courses and lead-specific training courses, as evidence of meeting the training requirements.

(5) The training program shall ensure the availability of, and provide adequate facilities for, the delivery of the lecture, course test, hands-on training, and assessment activities. This includes providing training equipment that reflects current work practices and maintaining or updating the equipment and facilities as needed.

(6) To become accredited in the following disciplines, the training program shall provide training courses that meet the following training hour requirements:

(i) The inspector course shall last a minimum of 24 training hours, with a minimum of 8 hours devoted to hands-on training activities. The minimum curriculum requirements for the inspector course are contained in paragraph (d)(1) of this section.

(ii) The risk assessor course shall last a minimum of 16 training hours, with a minimum of 4 hours devoted to hands-on training activities. The minimum curriculum requirements for the risk assessor course are contained in paragraph (d)(2) of this section.

(iii) The supervisor course shall last a minimum of 32 training hours, with a minimum of 8 hours devoted to hands-on activities. The minimum curriculum requirements for the supervisor course are contained in paragraph (d)(3) of this section.

(iv) The project designer course shall last a minimum of 8 training hours. The minimum curriculum requirements for the project designer course are contained in paragraph (d)(4) of this section.

(v) The abatement worker course shall last a minimum of 16 training hours, with a minimum of 8 hours devoted to hands-on training activities. The minimum curriculum requirements for the abatement worker course

are contained in paragraph (d)(5) of this section.

(vi) The renovator course must last a minimum of 8 training hours, with a minimum of 2 hours devoted to hands-on training activities. The minimum curriculum requirements for the renovator course are contained in paragraph (d)(6) of this section. Hands-on training activities must cover renovation methods that minimize the creation of dust and lead-based paint hazards, interior and exterior containment and cleanup methods, and post-renovation cleaning verification.

(vii) The dust sampling technician course must last a minimum of 8 training hours, with a minimum of 2 hours devoted to hands-on training activities. The minimum curriculum requirements for the dust sampling technician course are contained in paragraph (d)(7) of this section. Hands-on training activities must cover dust sampling methodologies.

(7) For each course offered, the training program shall conduct either a course test at the completion of the course, and if applicable, a hands-on skills assessment, or in the alternative, a proficiency test for that discipline. Each individual must successfully complete the hands-on skills assessment and receive a passing score on the course test to pass any course, or successfully complete a proficiency test.

(i) The training manager is responsible for maintaining the validity and integrity of the hands-on skills assessment or proficiency test to ensure that it accurately evaluates the trainees' performance of the work practices and procedures associated with the course topics contained in paragraph (d) of this section.

(ii) The training manager is responsible for maintaining the validity and integrity of the course test to ensure that it accurately evaluates the trainees' knowledge and retention of the course topics.

(iii) The course test shall be developed in accordance with the test blueprint submitted with the training accreditation application.

(8) The training program shall issue unique course completion certificates to each individual who passes the

## Environmental Protection Agency

## § 745.225

training course. The course completion certificate shall include:

(i) The name, a unique identification number, and address of the individual.

(ii) The name of the particular course that the individual completed.

(iii) Dates of course completion/test passage.

(iv) For initial inspector, risk assessor, project designer, supervisor, or abatement worker course completion certificates, the expiration date of interim certification, which is 6 months from the date of course completion.

(v) The name, address, and telephone number of the training program.

(vi) The language in which the course was taught.

(vii) For renovator and dust sampling technician course completion certificates, a photograph of the individual.

(9) The training manager shall develop and implement a quality control plan. The plan shall be used to maintain and improve the quality of the training program over time. This plan shall contain at least the following elements:

(i) Procedures for periodic revision of training materials and the course test to reflect innovations in the field.

(ii) Procedures for the training manager's annual review of principal instructor competency.

(10) Courses offered by the training program must teach the work practice standards contained in § 745.85 or § 745.227, as applicable, in such a manner that trainees are provided with the knowledge needed to perform the renovations or lead-based paint activities they will be responsible for conducting.

(11) The training manager shall be responsible for ensuring that the training program complies at all times with all of the requirements in this section.

(12) The training manager shall allow EPA to audit the training program to verify the contents of the application for accreditation as described in paragraph (b) of this section.

(13) The training manager must provide notification of renovator, dust sampling technician, or renovator, dust sampling technician, or lead-based paint activities offered.

(i) The training manager must provide EPA with notification of all renovator, dust sampling technician, or

lead-based paint activities courses offered. The original notification must be received by EPA at least 7 business days prior to the start date of any renovator, dust sampling technician, or lead-based paint activities course.

(ii) The training manager must provide EPA updated notification when renovator, dust sampling technician, or lead-based paint activities courses will begin on a date other than the start date specified in the original notification, as follows:

(A) For renovator, dust sampling technician, or lead-based paint activities courses beginning prior to the start date provided to EPA, an updated notification must be received by EPA at least 7 business days before the new start date.

(B) For renovator, dust sampling technician, or lead-based paint activities courses beginning after the start date provided to EPA, an updated notification must be received by EPA at least 2 business days before the start date provided to EPA.

(iii) The training manager must update EPA of any change in location of renovator, dust sampling technician, or lead-based paint activities courses at least 7 business days prior to the start date provided to EPA.

(iv) The training manager must update EPA regarding any course cancellations, or any other change to the original notification. Updated notifications must be received by EPA at least 2 business days prior to the start date provided to EPA.

(v) Each notification, including updates, must include the following:

(A) Notification type (original, update, cancellation).

(B) Training program name, EPA accreditation number, address, and telephone number.

(C) Course discipline, type (initial/ refresher), and the language in which instruction will be given.

(D) Date(s) and time(s) of training.

(E) Training location(s) telephone number, and address.

(F) Principal instructor's name.

(G) Training manager's name and signature.

(vi) Notification must be accomplished using any of the following



methods: Written notification, or electronically using the Agency's Central Data Exchange (CDX). Written notification of renovator, dust sampling technician, or lead-based paint activities course schedules can be accomplished by using either the sample form titled "Lead-Based Paint Activities Training Course Schedule" or a similar form containing the information required in paragraph (c)(13)(v) of this section. All written notifications must be delivered by U.S. Postal Service, fax, commercial delivery service, or hand delivery (persons submitting notification by U.S. Postal Service are reminded that they should allow 3 additional business days for delivery in order to ensure that EPA receives the notification by the required date). Instructions and sample forms can be obtained from the NLIC at 1-800-424-LEAD(5323), or on the Internet at <http://www.epa.gov/lead>.

(vii) Lead-based paint activities courses must not begin on a date, or at a location other than that specified in the original notification unless an updated notification identifying a new start date or location is submitted, in which case the course must begin on the new start date and/or location specified in the updated notification.

(viii) No training program shall provide renovator, dust sampling technician, or lead-based paint activities courses without first notifying EPA of such activities in accordance with the requirements of this paragraph.

(14) The training manager must provide notification following completion of renovator, dust sampling technician, or lead-based paint activities courses.

(i) The training manager must provide EPA notification after the completion of any renovator, dust sampling technician, or lead-based paint activities course. This notice must be received by EPA no later than 10 business days following course completion.

(ii) The notification must include the following:

(A) Training program name, EPA accreditation number, address, and telephone number.

(B) Course discipline and type (initial/refreshers).

(C) Date(s) of training.

(D) The following information for each student who took the course:

(1) Name.

(2) Address.

(3) Date of birth.

(4) Course completion certificate number.

(5) Course test score.

(6) For renovator or dust sampling technician courses only, a digital photograph of the student.

(E) Training manager's name and signature.

(iii) Notification must be accomplished using any of the following methods: Written notification, or electronically using the Agency's Central Data Exchange (CDX). Written notification following training courses can be accomplished by using either the sample form, entitled *Post-Training Notification* or a similar form containing the information required in paragraph (c)(14)(i) of this section. All written notifications must be delivered by U.S. Postal Service, fax, commercial delivery service, or hand delivery (persons submitting notification by U.S. Postal Service are reminded that they should allow 3 additional business days for delivery in order to ensure that EPA receives the notification by the required date). Instructions and sample forms can be obtained from the NLIC at 1-800-424-LEAD (5323), or on the Internet at <http://www.epa.gov/lead>.

(d) *Minimum training curriculum requirements.* To become accredited to offer lead-based paint courses instruction in the specific disciplines listed below, training programs must ensure that their courses of study include, at a minimum, the following course topics. Requirements ending in an asterisk (\*) indicate areas that require hands-on activities as an integral component of the course.

(1) *Inspector.* (i) Role and responsibilities of an inspector.

(ii) Background information on lead and its adverse health effects.

(iii) Background information on Federal, State, and local regulations and guidance that pertains to lead-based paint and lead-based paint activities.

(iv) Lead-based paint inspection methods, including selection of rooms and components for sampling or testing.\*

## Environmental Protection Agency

## § 745.225

(v) Paint, dust, and soil sampling methodologies.\*

(vi) Clearance standards and testing, including random sampling.\*

(vii) Preparation of the final inspection report.\*

(viii) Recordkeeping.

(2) *Risk assessor.* (i) Role and responsibilities of a risk assessor.

(ii) Collection of background information to perform a risk assessment.

(iii) Sources of environmental lead contamination such as paint, surface dust and soil, water, air, packaging, and food.

(iv) Visual inspection for the purposes of identifying potential sources of lead-based paint hazards.\*

(v) Lead hazard screen protocol.

(vi) Sampling for other sources of lead exposure.\*

(vii) Interpretation of lead-based paint and other lead sampling results, including all applicable State or Federal guidance or regulations pertaining to lead-based paint hazards.\*

(viii) Development of hazard control options, the role of interim controls, and operations and maintenance activities to reduce lead-based paint hazards.

(ix) Preparation of a final risk assessment report.

(3) *Supervisor.* (i) Role and responsibilities of a supervisor.

(ii) Background information on lead and its adverse health effects.

(iii) Background information on Federal, State, and local regulations and guidance that pertain to lead-based paint abatement.

(iv) Liability and insurance issues relating to lead-based paint abatement.

(v) Risk assessment and inspection report interpretation.\*

(vi) Development and implementation of an occupant protection plan and abatement report.

(vii) Lead-based paint hazard recognition and control.\*

(viii) Lead-based paint abatement and lead-based paint hazard reduction methods, including restricted practices.\*

(ix) Interior dust abatement/cleanup or lead-based paint hazard control and reduction methods.\*

(x) Soil and exterior dust abatement or lead-based paint hazard control and reduction methods.\*

(xi) Clearance standards and testing.

(xii) Cleanup and waste disposal.

(xiii) Recordkeeping.

(4) *Project designer.* (i) Role and responsibilities of a project designer.

(ii) Development and implementation of an occupant protection plan for large scale abatement projects.

(iii) Lead-based paint abatement and lead-based paint hazard reduction methods, including restricted practices for large-scale abatement projects.

(iv) Interior dust abatement/cleanup or lead hazard control and reduction methods for large-scale abatement projects.

(v) Clearance standards and testing for large scale abatement projects.

(vi) Integration of lead-based paint abatement methods with modernization and rehabilitation projects for large scale abatement projects.

(5) *Abatement worker.* (i) Role and responsibilities of an abatement worker.

(ii) Background information on lead and its adverse health effects.

(iii) Background information on Federal, State and local regulations and guidance that pertain to lead-based paint abatement.

(iv) Lead-based paint hazard recognition and control.\*

(v) Lead-based paint abatement and lead-based paint hazard reduction methods, including restricted practices.\*

(vi) Interior dust abatement methods/cleanup or lead-based paint hazard reduction.\*

(vii) Soil and exterior dust abatement methods or lead-based paint hazard reduction.\*

(6) *Renovator.* (i) Role and responsibility of a renovator.

(ii) Background information on lead and its adverse health effects.

(iii) Background information on EPA, HUD, OSHA, and other Federal, State, and local regulations and guidance that pertains to lead-based paint and renovation activities.

(iv) Procedures for using acceptable test kits to determine whether paint is lead-based paint.

(v) Renovation methods to minimize the creation of dust and lead-based paint hazards.

(vi) Interior and exterior containment and cleanup methods.

(vii) Methods to ensure that the renovation has been properly completed, including cleaning verification, and clearance testing.

(viii) Waste handling and disposal.

(ix) Providing on-the-job training to other workers.

(x) Record preparation.

(7) *Dust sampling technician.* (i) Role and responsibility of a dust sampling technician.

(ii) Background information on lead and its adverse health effects.

(iii) Background information on Federal, State, and local regulations and guidance that pertains to lead-based paint and renovation activities.

(iv) Dust sampling methodologies.

(v) Clearance standards and testing.

(vi) Report preparation.

(e) *Requirements for the accreditation of refresher training programs.* A training program may seek accreditation to offer refresher training courses in any of the following disciplines: Inspector, risk assessor, supervisor, project designer, abatement worker, renovator, and dust sampling technician. To obtain EPA accreditation to offer refresher training, a training program must meet the following minimum requirements:

(1) Each refresher course shall review the curriculum topics of the full-length courses listed under paragraph (d) of this section, as appropriate. In addition, to become accredited to offer refresher training courses, training programs shall ensure that their courses of study include, at a minimum, the following:

(i) An overview of current safety practices relating to lead-based paint in general, as well as specific information pertaining to the appropriate discipline.

(ii) Current laws and regulations relating to lead-based paint in general, as well as specific information pertaining to the appropriate discipline.

(iii) Current technologies relating to lead-based paint in general, as well as specific information pertaining to the appropriate discipline.

(2) Refresher courses for inspector, risk assessor, supervisor, and abatement worker must last a minimum of 8 training hours. Refresher courses for project designer, renovator, and dust

sampling technician must last a minimum of 4 training hours.

(3) For each course offered, the training program shall conduct a hands-on assessment (if applicable), and at the completion of the course, a course test.

(4) A training program may apply for accreditation of a refresher course concurrently with its application for accreditation of the corresponding training course as described in paragraph (b) of this section. If so, EPA shall use the approval procedure described in paragraph (b) of this section. In addition, the minimum requirements contained in paragraphs (c) (except for the requirements in paragraph (c)(6)), and (e)(1), (e)(2) and (e)(3) of this section shall also apply.

(5) A training program seeking accreditation to offer refresher training courses only shall submit a written application to EPA containing the following information:

(i) The refresher training program's name, address, and telephone number.

(ii) A list of courses for which it is applying for accreditation.

(iii) A statement signed by the training program manager certifying that the refresher training program meets the minimum requirements established in paragraph (c) of this section, except for the requirements in paragraph (c)(6) of this section. If a training program uses EPA-developed model training materials, or training materials approved by a State or Indian Tribe that has been authorized by EPA under §745.324 to develop its refresher training course materials, the training manager shall include a statement certifying that, as well.

(iv) If the refresher training course materials are not based on EPA-developed model training materials or training materials approved by an authorized State or Indian Tribe, the training program's application for accreditation shall include:

(A) A copy of the student and instructor manuals to be used for each course.

(B) A copy of the course agenda for each course.

(v) All refresher training programs shall include in their application for accreditation the following:

## Environmental Protection Agency

## § 745.225

(A) A description of the facilities and equipment to be used for lecture and hands-on training.

(B) A copy of the course test blueprint for each course.

(C) A description of the activities and procedures that will be used for conducting the assessment of hands-on skills for each course (if applicable).

(D) A copy of the quality control plan as described in paragraph (c)(9) of this section.

(vi) The requirements in paragraphs (c)(1) through (c)(5), and (c)(7) through (c)(14) of this section apply to refresher training providers.

(vii) If a refresher training program meets the requirements listed in this paragraph, then EPA shall approve the application for accreditation no more than 180 days after receiving a complete application from the refresher training program. In the case of approval, a certificate of accreditation shall be sent to the applicant. In the case of disapproval, a letter describing the reasons for disapproval shall be sent to the applicant. Prior to disapproval, EPA may, at its discretion, work with the applicant to address inadequacies in the application for accreditation. EPA may also request additional materials retained by the refresher training program under paragraph (i) of this section. If a refresher training program's application is disapproved, the program may reapply for accreditation at any time.

(f) *Re-accreditation of training programs.* (1) Unless re-accredited, a training program's accreditation (including refresher training accreditation) shall expire 4 years after the date of issuance. If a training program meets the requirements of this section, the training program shall be re-accredited.

(2) A training program seeking re-accreditation shall submit an application to EPA no later than 180 days before its accreditation expires. If a training program does not submit its application for re-accreditation by that date, EPA cannot guarantee that the program will be re-accredited before the end of the accreditation period.

(3) The training program's application for re-accreditation shall contain:

(i) The training program's name, address, and telephone number.

(ii) A list of courses for which it is applying for re-accreditation.

(iii) A description of any changes to the training facility, equipment or course materials since its last application was approved that adversely affects the students ability to learn.

(iv) A statement signed by the program manager stating:

(A) That the training program complies at all times with all requirements in paragraphs (c) and (e) of this section, as applicable; and

(B) The recordkeeping and reporting requirements of paragraph (i) of this section shall be followed.

(v) A payment of appropriate fees in accordance with § 745.238.

(4) Upon request, the training program shall allow EPA to audit the training program to verify the contents of the application for re-accreditation as described in paragraph (f)(3) of this section.

(g) *Suspension, revocation, and modification of accredited training programs.*

(1) EPA may, after notice and an opportunity for hearing, suspend, revoke, or modify training program accreditation (including refresher training accreditation) if a training program, training manager, or other person with supervisory authority over the training program has:

(i) Misrepresented the contents of a training course to EPA and/or the student population.

(ii) Failed to submit required information or notifications in a timely manner.

(iii) Failed to maintain required records.

(iv) Falsified accreditation records, instructor qualifications, or other accreditation-related information or documentation.

(v) Failed to comply with the training standards and requirements in this section.

(vi) Failed to comply with Federal, State, or local lead-based paint statutes or regulations.

(vii) Made false or misleading statements to EPA in its application for accreditation or re-accreditation which EPA relied upon in approving the application.

(2) In addition to an administrative or judicial finding of violation, execution of a consent agreement in settlement of an enforcement action constitutes, for purposes of this section, evidence of a failure to comply with relevant statutes or regulations.

(h) *Procedures for suspension, revocation or modification of training program accreditation.* (1) Prior to taking action to suspend, revoke, or modify the accreditation of a training program, EPA shall notify the affected entity in writing of the following:

(i) The legal and factual basis for the suspension, revocation, or modification.

(ii) The anticipated commencement date and duration of the suspension, revocation, or modification.

(iii) Actions, if any, which the affected entity may take to avoid suspension, revocation, or modification, or to receive accreditation in the future.

(iv) The opportunity and method for requesting a hearing prior to final EPA action to suspend, revoke or modify accreditation.

(v) Any additional information, as appropriate, which EPA may provide.

(2) If a hearing is requested by the accredited training program, EPA shall:

(i) Provide the affected entity an opportunity to offer written statements in response to EPA's assertions of the legal and factual basis for its proposed action, and any other explanations, comments, and arguments it deems relevant to the proposed action.

(ii) Provide the affected entity such other procedural opportunities as EPA may deem appropriate to ensure a fair and impartial hearing.

(iii) Appoint an official of EPA as Presiding Officer to conduct the hearing. No person shall serve as Presiding Officer if he or she has had any prior connection with the specific matter.

(3) The Presiding Officer appointed pursuant to paragraph (h)(2) of this section shall:

(i) Conduct a fair, orderly, and impartial hearing within 90 days of the request for a hearing.

(ii) Consider all relevant evidence, explanation, comment, and argument submitted.

(iii) Notify the affected entity in writing within 90 days of completion of

the hearing of his or her decision and order. Such an order is a final agency action which may be subject to judicial review.

(4) If EPA determines that the public health, interest, or welfare warrants immediate action to suspend the accreditation of any training program prior to the opportunity for a hearing, it shall:

(i) Notify the affected entity of its intent to immediately suspend training program accreditation for the reasons listed in paragraph (g)(1) of this section. If a suspension, revocation, or modification notice has not previously been issued pursuant to paragraph (g)(1) of this section, it shall be issued at the same time the emergency suspension notice is issued.

(ii) Notify the affected entity in writing of the grounds for the immediate suspension and why it is necessary to suspend the entity's accreditation before an opportunity for a suspension, revocation or modification hearing.

(iii) Notify the affected entity of the anticipated commencement date and duration of the immediate suspension.

(iv) Notify the affected entity of its right to request a hearing on the immediate suspension within 15 days of the suspension taking place and the procedures for the conduct of such a hearing.

(5) Any notice, decision, or order issued by EPA under this section, any transcripts or other verbatim record of oral testimony, and any documents filed by an accredited training program in a hearing under this section shall be available to the public, except as otherwise provided by section 14 of TSCA or by part 2 of this title. Any such hearing at which oral testimony is presented shall be open to the public, except that the Presiding Officer may exclude the public to the extent necessary to allow presentation of information which may be entitled to confidential treatment under section 14 of TSCA or part 2 of this title.

(6) The public shall be notified of the suspension, revocation, modification or reinstatement of a training program's accreditation through appropriate mechanisms.

**Environmental Protection Agency**

**§ 745.226**

(7) EPA shall maintain a list of parties whose accreditation has been suspended, revoked, modified or reinstated.

(i) *Training program recordkeeping requirements.* (1) Accredited training programs shall maintain, and make available to EPA, upon request, the following records:

(i) All documents specified in paragraph (c)(4) of this section that demonstrate the qualifications listed in paragraphs (c)(1) and (c)(2) of this section of the training manager and principal instructors.

(ii) Current curriculum/course materials and documents reflecting any changes made to these materials.

(iii) The course test blueprint.

(iv) Information regarding how the hands-on assessment is conducted including, but not limited to:

- (A) Who conducts the assessment.
- (B) How the skills are graded.
- (C) What facilities are used.
- (D) The pass/fail rate.

(v) The quality control plan as described in paragraph (c)(9) of this section.

(vi) Results of the students' hands-on skills assessments and course tests, and a record of each student's course completion certificate.

(vii) Any other material not listed above in paragraphs (i)(1)(i) through (i)(1)(vi) of this section that was submitted to EPA as part of the program's application for accreditation.

(2) The training program shall retain these records at the address specified on the training program accreditation application (or as modified in accordance with paragraph (i)(3) of this section for a minimum of 3 years and 6 months.

(3) The training program shall notify EPA in writing within 30 days of changing the address specified on its training program accreditation application or transferring the records from that address.

[61 FR 45813, Aug. 29, 1996, as amended at 64 FR 31098, June 9, 1999; 69 FR 18495, Apr. 8, 2004; 73 FR 21766, Apr. 22, 2008; 74 FR 34262, July 15, 2009]

EFFECTIVE DATE NOTE: At 75 FR 24819, May 6, 2010, §745.225 was amended by revising paragraph (c)(2)(ii), effective July 6, 2010. For

the convenience of the user, the revised text is set forth as follows:

**§ 745.225 Accreditation of training programs; target housing and child-occupied facilities.**

\* \* \* \* \*

(c) \* \* \*

(2) \* \* \*

(ii) Successfully completed at least 16 hours of any EPA-accredited or EPA-authorized State or Tribal-accredited lead-specific training for instructors of lead-based paint activities courses or 8 hours of any EPA-accredited or EPA-authorized State or Tribal-accredited lead-specific training for instructors of renovator or dust sampling technician courses; and

\* \* \* \* \*

**§ 745.226 Certification of individuals and firms engaged in lead-based paint activities; target housing and child-occupied facilities.**

(a) *Certification of individuals.* (1) Individuals seeking certification by EPA to engage in lead-based paint activities must either:

(i) Submit to EPA an application demonstrating that they meet the requirements established in paragraphs (b) or (c) of this section for the particular discipline for which certification is sought; or

(ii) Submit to EPA an application with a copy of a valid lead-based paint activities certification (or equivalent) from a State or Tribal program that has been authorized by EPA pursuant to subpart Q of this part.

(2) Individuals may first apply to EPA for certification to engage in lead-based paint activities pursuant to this section on or after March 1, 1999.

(3) Following the submission of an application demonstrating that all the requirements of this section have been met, EPA shall certify an applicant as an inspector, risk assessor, supervisor, project designer, or abatement worker, as appropriate.

(4) Upon receiving EPA certification, individuals conducting lead-based paint activities shall comply with the work practice standards for performing the appropriate lead-based paint activities as established in §745.227.

(5) It shall be a violation of TSCA for an individual to conduct any of the

lead-based paint activities described in § 745.227 after March 1, 2000, if that individual has not been certified by EPA pursuant to this section to do so.

(6) Individuals applying for certification must submit the appropriate fees in accordance with § 745.238.

(b) *Inspector, risk assessor or supervisor.* (1) To become certified by EPA as an inspector, risk assessor, or supervisor, pursuant to paragraph (a)(1)(i) of this section, an individual must:

(i) Successfully complete an accredited course in the appropriate discipline and receive a course completion certificate from an accredited training program.

(ii) Pass the certification exam in the appropriate discipline offered by EPA; and,

(iii) Meet or exceed the following experience and/or education requirements:

(A) Inspectors. (1) No additional experience and/or education requirements.

(2) [Reserved]

(B) Risk assessors. (1) Successful completion of an accredited training course for inspectors; and

(2) Bachelor's degree and 1 year of experience in a related field (e.g., lead, asbestos, environmental remediation work, or construction), or an Associates degree and 2 years experience in a related field (e.g., lead, asbestos, environmental remediation work, or construction); or

(3) Certification as an industrial hygienist, professional engineer, registered architect and/or certification in a related engineering/health/environmental field (e.g., safety professional, environmental scientist); or

(4) A high school diploma (or equivalent), and at least 3 years of experience in a related field (e.g., lead, asbestos, environmental remediation work or construction).

(C) Supervisor: (1) One year of experience as a certified lead-based paint abatement worker; or

(2) At least 2 years of experience in a related field (e.g., lead, asbestos, or environmental remediation work) or in the building trades.

(2) The following documents shall be recognized by EPA as evidence of meeting the requirements listed in (b)(2)(iii) of this paragraph:

(i) Official academic transcripts or diploma, as evidence of meeting the education requirements.

(ii) Resumes, letters of reference, or documentation of work experience, as evidence of meeting the work experience requirements.

(iii) Course completion certificates from lead-specific or other related training courses, issued by accredited training programs, as evidence of meeting the training requirements.

(3) In order to take the certification examination for a particular discipline an individual must:

(i) Successfully complete an accredited course in the appropriate discipline and receive a course completion certificate from an accredited training program.

(ii) Meet or exceed the education and/or experience requirements in paragraph (b)(1)(iii) of this section.

(4) The course completion certificate shall serve as interim certification for an individual until the next available opportunity to take the certification exam. Such interim certification shall expire 6 months after issuance.

(5) After passing the appropriate certification exam and submitting an application demonstrating that he/she meets the appropriate training, education, and/or experience prerequisites described in paragraph (b)(1) of this section, an individual shall be issued a certificate by EPA. To maintain certification, an individual must be recertified as described in paragraph (e) of this section.

(6) An individual may take the certification exam no more than three times within 6 months of receiving a course completion certificate.

(7) If an individual does not pass the certification exam and receive a certificate within 6 months of receiving his/her course completion certificate, the individual must retake the appropriate course from an accredited training program before reapplying for certification from EPA.

(c) *Abatement worker and project designer.* (1) To become certified by EPA as an abatement worker or project designer, pursuant to paragraph (a)(1)(i) of this section, an individual must:

## Environmental Protection Agency

## § 745.226

(i) Successfully complete an accredited course in the appropriate discipline and receive a course completion certificate from an accredited training program.

(ii) Meet or exceed the following additional experience and/or education requirements:

(A) Abatement workers. (1) No additional experience and/or education requirements.

(2) [Reserved]

(B) Project designers. (1) Successful completion of an accredited training course for supervisors.

(2) Bachelor's degree in engineering, architecture, or a related profession, and 1 year of experience in building construction and design or a related field; or

(3) Four years of experience in building construction and design or a related field.

(2) The following documents shall be recognized by EPA as evidence of meeting the requirements listed in this paragraph:

(i) Official academic transcripts or diploma, as evidence of meeting the education requirements.

(ii) Resumes, letters of reference, or documentation of work experience, as evidence of meeting the work experience requirements.

(iii) Course completion certificates from lead-specific or other related training courses, issued by accredited training programs, as evidence of meeting the training requirements.

(3) The course completion certificate shall serve as an interim certification until certification from EPA is received, but shall be valid for no more than 6 months from the date of completion.

(4) After successfully completing the appropriate training courses and meeting any other qualifications described in paragraph (c)(1) of this section, an individual shall be issued a certificate from EPA. To maintain certification, an individual must be re-certified as described in paragraph (e) of this section.

(d) *Certification based on prior training.*

(1) Any individual who received training in a lead-based paint activity between October 1, 1990, and March 1, 1999 shall be eligible for certification by

EPA under the alternative procedures contained in this paragraph. Individuals who have received lead-based paint activities training at an EPA-authorized State or Tribal accredited training program shall also be eligible for certification by EPA under the following alternative procedures:

(i) Applicants for certification as an inspector, risk assessor, or supervisor shall:

(A) Demonstrate that the applicant has successfully completed training or on-the-job training in the conduct of a lead-based paint activity.

(B) Demonstrate that the applicant meets or exceeds the education and/or experience requirements in paragraph (b)(1)(iii) of this section.

(C) Successfully complete an accredited refresher training course for the appropriate discipline.

(D) Pass a certification exam administered by EPA for the appropriate discipline.

(ii) Applicants for certification as an abatement worker or project designer shall:

(A) Demonstrate that the applicant has successfully completed training or on-the-job training in the conduct of a lead-based paint activity.

(B) Demonstrate that the applicant meets the education and/or experience requirements in paragraphs (c)(1) of this section; and

(C) Successfully complete an accredited refresher training course for the appropriate discipline.

(2) Individuals shall have until March 1, 2000, to apply to EPA for certification under the above procedures. After that date, all individuals wishing to obtain certification must do so through the procedures described in paragraph (a), and paragraph (b) or (c) of this section, according to the discipline for which certification is being sought.

(e) *Re-certification.* (1) To maintain certification in a particular discipline, a certified individual shall apply to and be re-certified by EPA in that discipline by EPA either:

(i) Every 3 years if the individual completed a training course with a course test and hands-on assessment; or



§ 745.226

40 CFR Ch. I (7-1-10 Edition)

(ii) Every 5 years if the individual completed a training course with a proficiency test.

(2) An individual shall be re-certified if the individual successfully completes the appropriate accredited refresher training course and submits a valid copy of the appropriate refresher course completion certificate.

(3) Individuals applying for re-certification must submit the appropriate fees in accordance with § 745.238.

(f) *Certification of firms.* (1) All firms which perform or offer to perform any of the lead-based paint activities described in § 745.227 after March 1, 2000, shall be certified by EPA.

(2) A firm seeking certification shall submit to EPA a letter attesting that the firm shall only employ appropriately certified employees to conduct lead-based paint activities, and that the firm and its employees shall follow the work practice standards in § 745.227 for conducting lead-based paint activities.

(3) From the date of receiving the firm's letter requesting certification, EPA shall have 90 days to approve or disapprove the firm's request for certification. Within that time, EPA shall respond with either a certificate of approval or a letter describing the reasons for a disapproval.

(4) The firm shall maintain all records pursuant to the requirements in § 745.227.

(5) Firms may first apply to EPA for certification to engage in lead-based paint activities pursuant to this section on or after March 1, 1999.

(6) Firms applying for certification must submit the appropriate fees in accordance with § 745.238.

(7) To maintain certification a firm shall submit appropriate fees in accordance with § 745.238 every 3 years.

(g) *Suspension, revocation, and modification of certifications of individuals engaged in lead-based paint activities.* (1) EPA may, after notice and opportunity for hearing, suspend, revoke, or modify an individual's certification if an individual has:

(i) Obtained training documentation through fraudulent means.

(ii) Gained admission to and completed an accredited training program

through misrepresentation of admission requirements.

(iii) Obtained certification through misrepresentation of certification requirements or related documents dealing with education, training, professional registration, or experience.

(iv) Performed work requiring certification at a job site without having proof of certification.

(v) Permitted the duplication or use of the individual's own certificate by another.

(vi) Performed work for which certification is required, but for which appropriate certification has not been received.

(vii) Failed to comply with the appropriate work practice standards for lead-based paint activities at § 745.227.

(viii) Failed to comply with Federal, State, or local lead-based paint statutes or regulations.

(2) In addition to an administrative or judicial finding of violation, for purposes of this section only, execution of a consent agreement in settlement of an enforcement action constitutes evidence of a failure to comply with relevant statutes or regulations.

(h) *Suspension, revocation, and modification of certifications of firms engaged in lead-based paint activities.* (1) EPA may, after notice and opportunity for hearing, suspend, revoke, or modify a firm's certification if a firm has:

(i) Performed work requiring certification at a job site with individuals who are not certified.

(ii) Failed to comply with the work practice standards established in § 745.227.

(iii) Misrepresented facts in its letter of application for certification to EPA.

(iv) Failed to maintain required records.

(v) Failed to comply with Federal, State, or local lead-based paint statutes or regulations.

(2) In addition to an administrative or judicial finding of violation, for purposes of this section only, execution of a consent agreement in settlement of an enforcement action constitutes evidence of a failure to comply with relevant statutes or regulations.

(i) *Procedures for suspension, revocation, or modification of the certification of individuals or firms.*

## Environmental Protection Agency

## § 745.227

(1) If EPA decides to suspend, revoke, or modify the certification of any individual or firm, it shall notify the affected entity in writing of the following:

(i) The legal and factual basis for the suspension, revocation, or modification.

(ii) The commencement date and duration of the suspension, revocation, or modification.

(iii) Actions, if any, which the affected entity may take to avoid suspension, revocation, or modification or to receive certification in the future.

(iv) The opportunity and method for requesting a hearing prior to final EPA action to suspend, revoke, or modify certification.

(v) Any additional information, as appropriate, which EPA may provide.

(2) If a hearing is requested by the certified individual or firm, EPA shall:

(i) Provide the affected entity an opportunity to offer written statements in response to EPA's assertion of the legal and factual basis and any other explanations, comments, and arguments it deems relevant to the proposed action.

(ii) Provide the affected entity such other procedural opportunities as EPA may deem appropriate to ensure a fair and impartial hearing.

(iii) Appoint an official of EPA as Presiding Officer to conduct the hearing. No person shall serve as Presiding Officer if he or she has had any prior connection with the specific matter.

(3) The Presiding Officer shall:

(i) Conduct a fair, orderly, and impartial hearing within 90 days of the request for a hearing;

(ii) Consider all relevant evidence, explanation, comment, and argument submitted; and

(iii) Notify the affected entity in writing within 90 days of completion of the hearing of his or her decision and order. Such an order is a final EPA action subject to judicial review.

(4) If EPA determines that the public health, interest, or welfare warrants immediate action to suspend the certification of any individual or firm prior to the opportunity for a hearing, it shall:

(i) Notify the affected entity of its intent to immediately suspend certifi-

cation for the reasons listed in paragraph (h)(1) of this section. If a suspension, revocation, or modification notice has not previously been issued, it shall be issued at the same time the immediate suspension notice is issued.

(ii) Notify the affected entity in writing of the grounds upon which the immediate suspension is based and why it is necessary to suspend the entity's accreditation before an opportunity for a hearing to suspend, revoke, or modify the individual's or firm's certification.

(iii) Notify the affected entity of the commencement date and duration of the immediate suspension.

(iv) Notify the affected entity of its right to request a hearing on the immediate suspension within 15 days of the suspension taking place and the procedures for the conduct of such a hearing.

(5) Any notice, decision, or order issued by EPA under this section, transcript or other verbatim record of oral testimony, and any documents filed by a certified individual or firm in a hearing under this section shall be available to the public, except as otherwise provided by section 14 of TSCA or by part 2 of this title. Any such hearing at which oral testimony is presented shall be open to the public, except that the Presiding Officer may exclude the public to the extent necessary to allow presentation of information which may be entitled to confidential treatment under section 14 of TSCA or part 2 of this title.

[61 FR 45813, Aug. 29, 1996, as amended at 64 FR 31098, June 9, 1999; 64 FR 42851, Aug. 6, 1999]

### **§ 745.227 Work practice standards for conducting lead-based paint activities: target housing and child-occupied facilities.**

(a) *Effective date, applicability, and terms.* (1) Beginning on March 1, 2000, all lead-based paint activities shall be performed pursuant to the work practice standards contained in this section.

(2) When performing any lead-based paint activity described by the certified individual as an inspection, lead-hazard screen, risk assessment or abatement, a certified individual must perform that activity in compliance

with the appropriate requirements below.

(3) Documented methodologies that are appropriate for this section are found in the following: The U.S. Department of Housing and Urban Development (HUD) Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing; the EPA Guidance on Residential Lead-Based Paint, Lead-Contaminated Dust, and Lead-Contaminated Soil; the EPA Residential Sampling for Lead: Protocols for Dust and Soil Sampling (EPA report number 7474-R-95-001); Regulations, guidance, methods or protocols issued by States and Indian Tribes that have been authorized by EPA; and other equivalent methods and guidelines.

(4) Clearance levels are appropriate for the purposes of this section may be found in the EPA Guidance on Residential Lead-Based Paint, Lead-Contaminated Dust, and Lead Contaminated Soil or other equivalent guidelines.

(b) *Inspection.* (1) An inspection shall be conducted only by a person certified by EPA as an inspector or risk assessor and, if conducted, must be conducted according to the procedures in this paragraph.

(2) When conducting an inspection, the following locations shall be selected according to documented methodologies and tested for the presence of lead-based paint:

(i) In a residential dwelling and child-occupied facility, each component with a distinct painting history and each exterior component with a distinct painting history shall be tested for lead-based paint, except those components that the inspector or risk assessor determines to have been replaced after 1978, or to not contain lead-based paint; and

(ii) In a multi-family dwelling or child-occupied facility, each component with a distinct painting history in every common area, except those components that the inspector or risk assessor determines to have been replaced after 1978, or to not contain lead-based paint.

(3) Paint shall be sampled in the following manner: (i) The analysis of paint to determine the presence of lead shall be conducted using documented

methodologies which incorporate adequate quality control procedures; and/or

(ii) All collected paint chip samples shall be analyzed according to paragraph (f) of this section to determine if they contain detectable levels of lead that can be quantified numerically.

(4) The certified inspector or risk assessor shall prepare an inspection report which shall include the following information:

(i) Date of each inspection.

(ii) Address of building.

(iii) Date of construction.

(iv) Apartment numbers (if applicable).

(v) Name, address, and telephone number of the owner or owners of each residential dwelling or child-occupied facility.

(vi) Name, signature, and certification number of each certified inspector and/or risk assessor conducting testing.

(vii) Name, address, and telephone number of the certified firm employing each inspector and/or risk assessor, if applicable.

(viii) Each testing method and device and/or sampling procedure employed for paint analysis, including quality control data and, if used, the serial number of any x-ray fluorescence (XRF) device.

(ix) Specific locations of each painted component tested for the presence of lead-based paint.

(x) The results of the inspection expressed in terms appropriate to the sampling method used.

(c) *Lead hazard screen.* (1) A lead hazard screen shall be conducted only by a person certified by EPA as a risk assessor.

(2) If conducted, a lead hazard screen shall be conducted as follows:

(i) Background information regarding the physical characteristics of the residential dwelling or child-occupied facility and occupant use patterns that may cause lead-based paint exposure to one or more children age 6 years and under shall be collected.

(ii) A visual inspection of the residential dwelling or child-occupied facility shall be conducted to:

(A) Determine if any deteriorated paint is present, and

## Environmental Protection Agency

## § 745.227

(B) Locate at least two dust sampling locations.

(iii) If deteriorated paint is present, each surface with deteriorated paint, which is determined, using documented methodologies, to be in poor condition and to have a distinct painting history, shall be tested for the presence of lead.

(iv) In residential dwellings, two composite dust samples shall be collected, one from the floors and the other from the windows, in rooms, hallways or stairwells where one or more children, age 6 and under, are most likely to come in contact with dust.

(v) In multi-family dwellings and child-occupied facilities, in addition to the floor and window samples required in paragraph (c)(1)(iii) of this section, the risk assessor shall also collect composite dust samples from common areas where one or more children, age 6 and under, are most likely to come into contact with dust.

(3) Dust samples shall be collected and analyzed in the following manner:

(i) All dust samples shall be taken using documented methodologies that incorporate adequate quality control procedures.

(ii) All collected dust samples shall be analyzed according to paragraph (f) of this section to determine if they contain detectable levels of lead that can be quantified numerically.

(4) Paint shall be sampled in the following manner: (i) The analysis of paint to determine the presence of lead shall be conducted using documented methodologies which incorporate adequate quality control procedures; and/or

(ii) All collected paint chip samples shall be analyzed according to paragraph (f) of this section to determine if they contain detectable levels of lead that can be quantified numerically.

(5) The risk assessor shall prepare a lead hazard screen report, which shall include the following information:

(i) The information required in a risk assessment report as specified in paragraph (d) of this section, including paragraphs (d)(11)(i) through (d)(11)(xiv), and excluding paragraphs (d)(11)(xv) through (d)(11)(xviii) of this section. Additionally, any background information collected pursuant to paragraph (c)(2)(i) of this section shall

be included in the risk assessment report; and

(ii) Recommendations, if warranted, for a follow-up risk assessment, and as appropriate, any further actions.

(d) *Risk assessment.* (1) A risk assessment shall be conducted only by a person certified by EPA as a risk assessor and, if conducted, must be conducted according to the procedures in this paragraph.

(2) A visual inspection for risk assessment of the residential dwelling or child-occupied facility shall be undertaken to locate the existence of deteriorated paint, assess the extent and causes of the deterioration, and other potential lead-based paint hazards.

(3) Background information regarding the physical characteristics of the residential dwelling or child-occupied facility and occupant use patterns that may cause lead-based paint exposure to one or more children age 6 years and under shall be collected.

(4) The following surfaces which are determined, using documented methodologies, to have a distinct painting history, shall be tested for the presence of lead:

(i) Each friction surface or impact surface with visibly deteriorated paint; and

(ii) All other surfaces with visibly deteriorated paint.

(5) In residential dwellings, dust samples (either composite or single-surface samples) from the interior window sill(s) and floor shall be collected and analyzed for lead concentration in all living areas where one or more children, age 6 and under, are most likely to come into contact with dust.

(6) For multi-family dwellings and child-occupied facilities, the samples required in paragraph (d)(4) of this section shall be taken. In addition, interior window sill and floor dust samples (either composite or single-surface samples) shall be collected and analyzed for lead concentration in the following locations:

(i) Common areas adjacent to the sampled residential dwelling or child-occupied facility; and

(ii) Other common areas in the building where the risk assessor determines that one or more children, age 6 and

under, are likely to come into contact with dust.

(7) For child-occupied facilities, interior window sill and floor dust samples (either composite or single-surface samples) shall be collected and analyzed for lead concentration in each room, hallway or stairwell utilized by one or more children, age 6 and under, and in other common areas in the child-occupied facility where one or more children, age 6 and under, are likely to come into contact with dust.

(8) Soil samples shall be collected and analyzed for lead concentrations in the following locations:

(i) Exterior play areas where bare soil is present; and

(ii) The rest of the yard (i.e., non-play areas) where bare soil is present.

(iii) Dripline/foundation areas where bare soil is present.

(9) Any paint, dust, or soil sampling or testing shall be conducted using documented methodologies that incorporate adequate quality control procedures.

(10) Any collected paint chip, dust, or soil samples shall be analyzed according to paragraph (f) of this section to determine if they contain detectable levels of lead that can be quantified numerically.

(11) The certified risk assessor shall prepare a risk assessment report which shall include the following information:

(i) Date of assessment.

(ii) Address of each building.

(iii) Date of construction of buildings.

(iv) Apartment number (if applicable).

(v) Name, address, and telephone number of each owner of each building.

(vi) Name, signature, and certification of the certified risk assessor conducting the assessment.

(vii) Name, address, and telephone number of the certified firm employing each certified risk assessor if applicable.

(viii) Name, address, and telephone number of each recognized laboratory conducting analysis of collected samples.

(ix) Results of the visual inspection.

(x) Testing method and sampling procedure for paint analysis employed.

(xi) Specific locations of each painted component tested for the presence of lead.

(xii) All data collected from on-site testing, including quality control data and, if used, the serial number of any XRF device.

(xiii) All results of laboratory analysis on collected paint, soil, and dust samples.

(xiv) Any other sampling results.

(xv) Any background information collected pursuant to paragraph (d)(3) of this section.

(xvi) To the extent that they are used as part of the lead-based paint hazard determination, the results of any previous inspections or analyses for the presence of lead-based paint, or other assessments of lead-based paint-related hazards.

(xvii) A description of the location, type, and severity of identified lead-based paint hazards and any other potential lead hazards.

(xviii) A description of interim controls and/or abatement options for each identified lead-based paint hazard and a suggested prioritization for addressing each hazard. If the use of an encapsulant or enclosure is recommended, the report shall recommend a maintenance and monitoring schedule for the encapsulant or enclosure.

(e) *Abatement.* (1) An abatement shall be conducted only by an individual certified by EPA, and if conducted, shall be conducted according to the procedures in this paragraph.

(2) A certified supervisor is required for each abatement project and shall be onsite during all work site preparation and during the post-abatement cleanup of work areas. At all other times when abatement activities are being conducted, the certified supervisor shall be onsite or available by telephone, pager or answering service, and able to be present at the work site in no more than 2 hours.

(3) The certified supervisor and the certified firm employing that supervisor shall ensure that all abatement activities are conducted according to the requirements of this section and all other Federal, State and local requirements.

## Environmental Protection Agency

## § 745.227

(4) A certified firm must notify EPA of lead-based paint abatement activities as follows:

(i) Except as provided in paragraph (e)(4)(ii) of this section, EPA must be notified prior to conducting lead-based paint abatement activities. The original notification must be received by EPA at least 5 business days before the start date of any lead-based paint abatement activities.

(ii) Notification for lead-based paint abatement activities required in response to an elevated blood lead level (EBL) determination, or Federal, State, Tribal, or local emergency abatement order should be received by EPA as early as possible before, but must be received no later than the start date of the lead-based paint abatement activities. Should the start date and/or location provided to EPA change, an updated notification must be received by EPA on or before the start date provided to EPA. Documentation showing evidence of an EBL determination or a copy of the Federal/State/Tribal/local emergency abatement order must be included in the written notification to take advantage of this abbreviated notification period.

(iii) Except as provided in paragraph (e)(4)(ii) of this section, updated notification must be provided to EPA for lead-based paint abatement activities that will begin on a date other than the start date specified in the original notification, as follows:

(A) For lead-based paint abatement activities beginning prior to the start date provided to EPA an updated notification must be received by EPA at least 5 business days before the new start date included in the notification.

(B) For lead-based paint abatement activities beginning after the start date provided to EPA an updated notification must be received by EPA on or before the start date provided to EPA.

(iv) Except as provided in paragraph (e)(4)(ii) of this section, updated notification must be provided to EPA for any change in location of lead-based paint abatement activities at least 5 business days prior to the start date provided to EPA.

(v) Updated notification must be provided to EPA when lead-based paint abatement activities are canceled, or

when there are other significant changes including, but not limited to, when the square footage or acreage to be abated changes by more than 20%. This updated notification must be received by EPA on or before the start date provided to EPA, or if work has already begun, within 24 hours of the change.

(vi) The following must be included in each notification:

(A) Notification type (original, updated, cancellation).

(B) Date when lead-based paint abatement activities will start.

(C) Date when lead-based paint abatement activities will end (approximation using best professional judgment).

(D) Firm's name, EPA certification number, address, telephone number.

(E) Type of building (e.g., single family dwelling, multi-family dwelling, child-occupied facilities) on/in which abatement work will be performed.

(F) Property name (if applicable).

(G) Property address including apartment or unit number(s) (if applicable) for abatement work.

(H) Documentation showing evidence of an EBL determination or a copy of the Federal/State/Tribal/local emergency abatement order, if using the abbreviated time period as described in paragraph (e)(4)(ii) of this section.

(I) Name and EPA certification number of the project supervisor.

(J) Approximate square footage/acreage to be abated.

(K) Brief description of abatement activities to be performed.

(L) Name, title, and signature of the representative of the certified firm who prepared the notification.

(vii) Notification must be accomplished using any of the following methods: Written notification, or electronically using the Agency's Central Data Exchange (CDX). Written notification can be accomplished using either the sample form titled "Notification of Lead-Based Paint Abatement Activities" or similar form containing the information required in paragraph (e)(4)(vi) of this section. All written notifications must be delivered by U.S. Postal Service, fax, commercial delivery service, or hand delivery (persons submitting notification by U.S. Postal

**§ 745.227**

**40 CFR Ch. I (7-1-10 Edition)**

Service are reminded that they should allow 3 additional business days for delivery in order to ensure that EPA receives the notification by the required date). Instructions and sample forms can be obtained from the NLIC at 1-800-424-LEAD(5323), or on the Internet at <http://www.epa.gov/lead>.

(viii) Lead-based paint abatement activities shall not begin on a date, or at a location other than that specified in either an original or updated notification, in the event of changes to the original notification.

(ix) No firm or individual shall engage in lead-based paint abatement activities, as defined in § 745.223, prior to notifying EPA of such activities according to the requirements of this paragraph.

(5) A written occupant protection plan shall be developed for all abatement projects and shall be prepared according to the following procedures:

(i) The occupant protection plan shall be unique to each residential dwelling or child-occupied facility and be developed prior to the abatement. The occupant protection plan shall describe the measures and management procedures that will be taken during the abatement to protect the building occupants from exposure to any lead-based paint hazards.

(ii) A certified supervisor or project designer shall prepare the occupant protection plan.

(6) The work practices listed below shall be restricted during an abatement as follows:

(i) Open-flame burning or torching of lead-based paint is prohibited;

(ii) Machine sanding or grinding or abrasive blasting or sandblasting of lead-based paint is prohibited unless used with High Efficiency Particulate Air (HEPA) exhaust control which removes particles of 0.3 microns or larger from the air at 99.97 percent or greater efficiency;

(iii) Dry scraping of lead-based paint is permitted only in conjunction with heat guns or around electrical outlets or when treating defective paint spots totaling no more than 2 square feet in any one room, hallway or stairwell or totaling no more than 20 square feet on exterior surfaces; and

(iv) Operating a heat gun on lead-based paint is permitted only at temperatures below 1100 degrees Fahrenheit.

(7) If conducted, soil abatement shall be conducted in one of the following ways:

(i) If the soil is removed:

(A) The soil shall be replaced by soil with a lead concentration as close to local background as practicable, but no greater than 400 ppm.

(B) The soil that is removed shall not be used as top soil at another residential property or child-occupied facility.

(ii) If soil is not removed, the soil shall be permanently covered, as defined in § 745.223.

(8) The following post-abatement clearance procedures shall be performed only by a certified inspector or risk assessor:

(i) Following an abatement, a visual inspection shall be performed to determine if deteriorated painted surfaces and/or visible amounts of dust, debris or residue are still present. If deteriorated painted surfaces or visible amounts of dust, debris or residue are present, these conditions must be eliminated prior to the continuation of the clearance procedures.

(ii) Following the visual inspection and any post-abatement cleanup required by paragraph (e)(8)(i) of this section, clearance sampling for lead in dust shall be conducted. Clearance sampling may be conducted by employing single-surface sampling or composite sampling techniques.

(iii) Dust samples for clearance purposes shall be taken using documented methodologies that incorporate adequate quality control procedures.

(iv) Dust samples for clearance purposes shall be taken a minimum of 1 hour after completion of final post-abatement cleanup activities.

(v) The following post-abatement clearance activities shall be conducted as appropriate based upon the extent or manner of abatement activities conducted in or to the residential dwelling or child-occupied facility:

(A) After conducting an abatement with containment between abated and unabated areas, one dust sample shall be taken from one interior window sill and from one window trough (if

## Environmental Protection Agency

## § 745.227

present) and one dust sample shall be taken from the floors of each of no less than four rooms, hallways or stairwells within the containment area. In addition, one dust sample shall be taken from the floor outside the containment area. If there are less than four rooms, hallways or stairwells within the containment area, then all rooms, hallways or stairwells shall be sampled.

(B) After conducting an abatement with no containment, two dust samples shall be taken from each of no less than four rooms, hallways or stairwells in the residential dwelling or child-occupied facility. One dust sample shall be taken from one interior window sill and window trough (if present) and one dust sample shall be taken from the floor of each room, hallway or stairwell selected. If there are less than four rooms, hallways or stairwells within the residential dwelling or child-occupied facility then all rooms, hallways or stairwells shall be sampled.

(C) Following an exterior paint abatement, a visible inspection shall be conducted. All horizontal surfaces in the outdoor living area closest to the abated surface shall be found to be cleaned of visible dust and debris. In addition, a visual inspection shall be conducted to determine the presence of paint chips on the dripline or next to the foundation below any exterior surface abated. If paint chips are present, they must be removed from the site and properly disposed of, according to all applicable Federal, State and local requirements.

(vi) The rooms, hallways or stairwells selected for sampling shall be selected according to documented methodologies.

(vii) The certified inspector or risk assessor shall compare the residual lead level (as determined by the laboratory analysis) from each single surface dust sample with clearance levels in paragraph (e)(8)(viii) of this section for lead in dust on floors, interior window sills, and window troughs or from each composite dust sample with the applicable clearance levels for lead in dust on floors, interior window sills, and window troughs divided by half the number of subsamples in the composite sample. If the residual lead level in a single surface dust sample equals or ex-

ceeds the applicable clearance level or if the residual lead level in a composite dust sample equals or exceeds the applicable clearance level divided by half the number of subsamples in the composite sample, the components represented by the failed sample shall be recleaned and retested.

(viii) The clearance levels for lead in dust are 40  $\mu\text{g}/\text{ft}^2$  for floors, 250  $\mu\text{g}/\text{ft}^2$  for interior window sills, and 400  $\mu\text{g}/\text{ft}^2$  for window troughs.

(9) In a multi-family dwelling with similarly constructed and maintained residential dwellings, random sampling for the purposes of clearance may be conducted provided:

(i) The certified individuals who abate or clean the residential dwellings do not know which residential dwelling will be selected for the random sample.

(ii) A sufficient number of residential dwellings are selected for dust sampling to provide a 95 percent level of confidence that no more than 5 percent or 50 of the residential dwellings (whichever is smaller) in the randomly sampled population exceed the appropriate clearance levels.

(iii) The randomly selected residential dwellings shall be sampled and evaluated for clearance according to the procedures found in paragraph (e)(8) of this section.

(10) An abatement report shall be prepared by a certified supervisor or project designer. The abatement report shall include the following information:

(i) Start and completion dates of abatement.

(ii) The name and address of each certified firm conducting the abatement and the name of each supervisor assigned to the abatement project.

(iii) The occupant protection plan prepared pursuant to paragraph (e)(5) of this section.

(iv) The name, address, and signature of each certified risk assessor or inspector conducting clearance sampling and the date of clearance testing.

(v) The results of clearance testing and all soil analyses (if applicable) and the name of each recognized laboratory that conducted the analyses.

(vi) A detailed written description of the abatement, including abatement methods used, locations of rooms and/



or components where abatement occurred, reason for selecting particular abatement methods for each component, and any suggested monitoring of encapsulants or enclosures.

(f) *Collection and laboratory analysis of samples.* Any paint chip, dust, or soil samples collected pursuant to the work practice standards contained in this section shall be:

(1) Collected by persons certified by EPA as an inspector or risk assessor; and

(2) Analyzed by a laboratory recognized by EPA pursuant to section 405(b) of TSCA as being capable of performing analyses for lead compounds in paint chip, dust, and soil samples.

(g) *Composite dust sampling.* Composite dust sampling may only be conducted in the situations specified in paragraphs (c) through (e) of this section. If such sampling is conducted, the following conditions shall apply:

(1) Composite dust samples shall consist of at least two subsamples;

(2) Every component that is being tested shall be included in the sampling; and

(3) Composite dust samples shall not consist of subsamples from more than one type of component.

(h) *Determinations.* (1) Lead-based paint is present:

(i) On any surface that is tested and found to contain lead equal to or in excess of 1.0 milligrams per square centimeter or equal to or in excess of 0.5% by weight; and

(ii) On any surface like a surface tested in the same room equivalent that has a similar painting history and that is found to be lead-based paint.

(2) A paint-lead hazard is present:

(i) On any friction surface that is subject to abrasion and where the lead dust levels on the nearest horizontal surface underneath the friction surface (e.g., the window sill or floor) are equal to or greater than the dust hazard levels identified in § 745.227(b);

(ii) On any chewable lead-based paint surface on which there is evidence of teeth marks;

(iii) Where there is any damaged or otherwise deteriorated lead-based paint on an impact surface that is caused by impact from a related building component (such as a door knob that knocks

into a wall or a door that knocks against its door frame; and

(iv) If there is any other deteriorated lead-based paint in any residential building or child-occupied facility or on the exterior of any residential building or child-occupied facility.

(3) A dust-lead hazard is present in a residential dwelling or child occupied facility:

(i) In a residential dwelling on floors and interior window sills when the weighted arithmetic mean lead loading for all single surface or composite samples of floors and interior window sills are equal to or greater than 40 µg/ft<sup>2</sup> for floors and 250 µg/ft<sup>2</sup> for interior window sills, respectively;

(ii) On floors or interior window sills in an unsampled residential dwelling in a multi-family dwelling, if a dust-lead hazard is present on floors or interior window sills, respectively, in at least one sampled residential unit on the property; and

(iii) On floors or interior window sills in an unsampled common area in a multi-family dwelling, if a dust-lead hazard is present on floors or interior window sills, respectively, in at least one sampled common area in the same common area group on the property.

(4) A soil-lead hazard is present:

(i) In a play area when the soil-lead concentration from a composite play area sample of bare soil is equal to or greater than 400 parts per million; or

(ii) In the rest of the yard when the arithmetic mean lead concentration from a composite sample (or arithmetic mean of composite samples) of bare soil from the rest of the yard (i.e., non-play areas) for each residential building on a property is equal to or greater than 1,200 parts per million.

(i) *Recordkeeping.* All reports or plans required in this section shall be maintained by the certified firm or individual who prepared the report for no fewer than 3 years. The certified firm or individual also shall provide copies of these reports to the building owner who contracted for its services.

[61 FR 45813, Aug. 29, 1996, as amended at 64 FR 42852, Aug. 6, 1999; 66 FR 1239, Jan. 5, 2001; 69 FR 18496, Apr. 8, 2004]

## Environmental Protection Agency

## § 745.238

**§ 745.228 Accreditation of training programs: public and commercial buildings, bridges and superstructures. [Reserved]**

**§ 745.229 Certification of individuals and firms engaged in lead-based paint activities: public and commercial buildings, bridges and superstructures. [Reserved]**

**§ 745.230 Work practice standards for conducting lead-based paint activities: public and commercial buildings, bridges and superstructures. [Reserved]**

**§ 745.233 Lead-based paint activities requirements.**

Lead-based paint activities, as defined in this part, shall only be conducted according to the procedures and work practice standards contained in § 745.227 of this subpart. No individual or firm may offer to perform or perform any lead-based paint activity as defined in this part, unless certified to perform that activity according to the procedures in § 745.226.

**§ 745.235 Enforcement.**

(a) Failure or refusal to comply with any requirement of §§ 745.225, 745.226, 745.227, or 745.233 is a prohibited act under sections 15 and 409 of TSCA (15 U.S.C. 2614, 2689).

(b) Failure or refusal to establish, maintain, provide, copy, or permit access to records or reports as required by §§ 745.225, 745.226, or 745.227 is a prohibited act under sections 15 and 409 of TSCA (15 U.S.C. 2614, 2689).

(c) Failure or refusal to permit entry or inspection as required by § 745.237 and section 11 of TSCA (15 U.S.C. 2610) is a prohibited act under sections 15 and 409 of TSCA (15 U.S.C. 2614, 2689).

(d) In addition to the above, any individual or firm that performs any of the following acts shall be deemed to have committed a prohibited act under sections 15 and 409 of TSCA (15 U.S.C. 2614, 2689). These include the following:

(i) Obtaining certification through fraudulent representation;

(ii) Failing to obtain certification from EPA and performing work requiring certification at a job site; or

(iii) Fraudulently obtaining certification and engaging in any lead-based paint activities requiring certification.

(e) Violators are subject to civil and criminal sanctions pursuant to section 16 of TSCA (15 U.S.C. 2615) for each violation.

**§ 745.237 Inspections.**

EPA may conduct reasonable inspections pursuant to the provisions of section 11 of TSCA (15 U.S.C. 2610) to ensure compliance with this subpart.

**§ 745.238 Fees for accreditation and certification of lead-based paint activities.**

(a) *Purpose.* To establish and impose fees for certified individuals and firms engaged in lead-based paint activities and persons operating accredited training programs under section 402(a) of the Toxic Substances Control Act (TSCA).

(b) *Persons who must pay fees.* Fees in accordance with paragraph (c) of this section must be paid by:

(1) *Training programs.* (i) All non-exempt training programs applying to EPA for the accreditation and re-accreditation of training programs in one or more of the following disciplines: inspector, risk assessor, supervisor, project designer, abatement worker.

(ii) *Exemptions.* No fee shall be imposed on any training program operated by a State, federally recognized Indian Tribe, local government, or non-profit organization. This exemption does not apply to the certification of firms or individuals.

(2) *Firms and individuals.* All firms and individuals seeking certification and re-certification from EPA to engage in lead-based paint activities in one or more of the following disciplines: inspector, risk assessor, supervisor, project designer, abatement worker.

(c) *Fee amounts—*(1) *Certification and accreditation fees.* Initial and renewal certification and accreditation fees are specified in the following table:

§ 745.238

40 CFR Ch. I (7–1–10 Edition)

| Training Program  | Accreditation | Re-accreditation (every 4 years, see 40 CFR 745.225(f)(1) for details) |
|---|---------------|--|
| Initial Course  |               |  |
| Inspector   | \$870         | \$620  |
| Risk assessor   | \$870         | \$620  |
| Supervisor  | \$870         | \$620  |
| Worker  | \$870         | \$620  |
| Project Designer  | \$870         | \$620  |
| Refresher Course  |               |  |
| Inspector   | \$690         | \$580  |
| Risk assessor   | \$690         | \$580  |
| Supervisor  | \$690         | \$580  |
| Worker  | \$690         | \$580  |
| Project Designer  | \$690         | \$580  |
| Lead-based Paint Activities—Individual                                      | Certification | Re-certification (every 3 years, see 40 CFR 745.226(e)(1) for details) |
| Inspector   | \$410         | \$410  |
| Risk assessor   | \$410         | \$410  |
| Supervisor  | \$410         | \$410  |
| Worker  | \$310         | \$310  |
| Project designer  | \$410         | \$410  |
| Tribal certification (each discipline)                                      | \$10          | \$10   |
| Lead-based Paint Activities—Firm  | Certification | Re-certification (every 3 years, see 40 CFR 745.226(f)(7) for details) |
| Firm  | \$550         | \$550  |
| Combined Renovation and Lead-based Paint Activities Firm Application        | \$550         | \$550  |
| Combined Renovation and Lead-based Paint Activities Tribal Firm Application | \$20          | \$20   |
| Tribal Firm   | \$20          | \$20   |

(2) *Certification examination fee.* Individuals required to take a certification exam in accordance with § 745.226 will be assessed a fee of \$70 for each exam attempt.

(3) *Multi-jurisdiction registration fee.* An individual, firm, or training program certified or accredited by EPA may wish to provide training or perform lead-based paint activities in additional EPA-administered jurisdictions. A fee of \$35 per discipline will be assessed for each additional EPA-administered jurisdiction in which an individual, firm, or training program applies for certification/re-certification or accreditation/re-accreditation. For purposes of this multi-jurisdiction registration fee, an EPA-administered jurisdiction is either an individual state without an authorized program or all Indian Tribes without authorized programs that are within a given EPA Region.

(4) *Lost identification card or certificate.* A \$15 fee shall be charged for replacement of an identification card or

certificate. (See replacement procedure in paragraph (e) of this section.)

(d) *Application/payment procedure—(1) Certification and re-certification in one or more EPA-administered jurisdiction—(i) Individuals.* Submit a completed application (titled “Application for Individuals to Conduct Lead-based Paint Activities”), the materials described at § 745.226, and the application fee(s) described in paragraph (c) of this section.

(ii) *Firms.* Submit a completed application (titled “Application for Firms”), the materials described at § 745.226, and the application fee(s) described in paragraph (c) of this section.

(2) *Accreditation and re-accreditation in one or more EPA-administered jurisdiction.* Submit a completed application (titled “Accreditation Application for Training Programs”), the materials described at § 745.225, and the application fee described in paragraph (c) of this section.

(3) *Application forms.* Application forms and instructions can be obtained

## Environmental Protection Agency

## § 745.320

from the National Lead Information Center at: 1-800-424-LEAD.

(e) *Identification card replacement and certificate replacement.* (1) Parties seeking identification card or certificate replacement shall complete the applicable portions of the appropriate application in accordance with the instructions provided. The appropriate applications are:

(i) *Individuals.* "Application for Individuals to Conduct Lead-based Paint Activities."

(ii) *Firms.* "Application for Firms."

(iii) *Training programs.* "Accreditation Application for Training Programs."

(2) Submit application and payment in the amount specified in paragraph (c)(4) of this section in accordance with the instructions provided with the application package.

(f) *Adjustment of fees.* (1) EPA will collect fees reflecting the costs associated with the administration and enforcement of subpart L of this part with the exception of costs associated with the accreditation of training programs operated by a State, federally recognized Indian Tribe, local government, and nonprofit organization. In order to do this, EPA will periodically adjust the fees to reflect changed economic conditions.

(2) The fees will be evaluated based on the cost to administer and enforce the program, and the number of applicants. New fee schedules will be published in the FEDERAL REGISTER.

(g) *Failure to remit a fee.* (1) EPA will not provide certification, re-certification, accreditation, or re-accreditation for any individual, firm, or training program which does not remit fees described in paragraph (c) of this section in accordance with the procedures specified in paragraph (d) of this section.

(2) EPA will not replace identification cards or certificates for any individual, firm, or training program which does not remit fees described in paragraph (c) of this section in accordance with the procedures specified in paragraph (e) of this section.

[64 FR 31098, June 9, 1999, as amended at 74 FR 11870, Mar. 20, 2009]

### § 745.239 Effective dates.

This subpart L shall apply in any State or Indian Country that does not have an authorized program under subpart Q, effective August 31, 1998. In such States or Indian Country:

(a) Training programs shall not provide, offer or claim to provide training or refresher training for certification without accreditation from EPA pursuant to § 745.225 on or after March 1, 1999.

(b) No individual or firm shall perform, offer, or claim to perform lead-based paint activities, as defined in this subpart, without certification from EPA to conduct such activities pursuant to § 745.226 on or after March 1, 2000.

(c) All lead-based paint activities shall be performed pursuant to the work practice standards contained in § 745.227 on or after March 1, 2000.

[61 FR 45813, Aug. 29, 1996, as amended at 64 FR 42852, Aug. 6, 1999]

### Subparts M-P [Reserved]

### Subpart Q—State and Indian Tribal Programs

SOURCE: 61 FR 45825, Aug. 29, 1996, unless otherwise noted.

### § 745.320 Scope and purpose.

(a) This subpart establishes the requirements that State or Tribal programs must meet for authorization by the Administrator to administer and enforce the standards, regulations, or other requirements established under TSCA section 402 and/or section 406 and establishes the procedures EPA will follow in approving, revising, and withdrawing approval of State or Tribal programs.

(b) For State or Tribal lead-based paint training and certification programs, a State or Indian Tribe may seek authorization to administer and enforce §§ 745.225, 745.226, and 745.227. The provisions of §§ 745.220, 745.223, 745.233, 745.235, 745.237, and 745.239 shall be applicable for the purposes of such program authorization.

(c) A State or Indian Tribe may seek authorization to administer and enforce all of the provisions of subpart E of this part, just the pre-renovation

### § 745.323

education provisions of subpart E of this part, or just the training, certification, accreditation, and work practice provisions of subpart E of this part. The provisions of §§ 745.324 and 745.326 apply for the purposes of such program authorizations.

(d) A State or Indian Tribe applying for program authorization may seek either interim approval or final approval of the compliance and enforcement portion of the State or Tribal lead-based paint program pursuant to the procedures at § 745.327(a).

(e) State or Tribal submissions for program authorization shall comply with the procedures set out in this subpart.

(f) Any State or Tribal program approved by the Administrator under this subpart shall at all times comply with the requirements of this subpart.

(g) In many cases States will lack authority to regulate activities in Indian Country. This lack of authority does not impair a State's ability to obtain full program authorization in accordance with this subpart. EPA will administer the program in Indian Country if neither the State nor Indian Tribe has been granted program authorization by EPA.

[61 FR 45825, Aug. 29, 1996, as amended at 73 FR 21767, Apr. 22, 2008]

### § 745.323 Definitions.

The definitions in subpart A apply to this subpart. In addition, the definitions in § 745.223 and the following definitions apply:

*Indian Country* means (1) all land within the limits of any American Indian reservation under the jurisdiction of the U.S. government, notwithstanding the issuance of any patent, and including rights-of-way running throughout the reservation; (2) all dependent Indian communities within the borders of the United States whether within the original or subsequently acquired territory thereof, and whether within or outside the limits of a State; and (3) all Indian allotments, the Indian titles which have not been extinguished, including rights-of-way running through the same.

*Indian Tribe* means any Indian Tribe, band, nation, or community recognized by the Secretary of the Interior and ex-

### 40 CFR Ch. I (7-1-10 Edition)

ercising substantial governmental duties and powers.

### § 745.324 Authorization of State or Tribal programs.

(a) *Application content and procedures.*

(1) Any State or Indian Tribe that seeks authorization from EPA to administer and enforce the provisions of subpart E or subpart L of this part must submit an application to the Administrator in accordance with this paragraph.

(2) Before developing an application for authorization, a State or Indian Tribe shall disseminate a public notice of intent to seek such authorization and provide an opportunity for a public hearing.

(3) A State or Tribal application shall include:

(i) A transmittal letter from the State Governor or Tribal Chairperson (or equivalent official) requesting program approval.

(ii) A summary of the State or Tribal program. This summary will be used to provide notice to residents of the State or Tribe.

(iii) A description of the State or Tribal program in accordance with paragraph (b) of this section.

(iv) An Attorney General's or Tribal Counsel's (or equivalent) statement in accordance with paragraph (c) of this section.

(v) Copies of all applicable State or Tribal statutes, regulations, standards, and other materials that provide the State or Indian Tribe with the authority to administer and enforce a lead-based paint program.

(4) After submitting an application, the Agency will publish a FEDERAL REGISTER notice that contains an announcement of the receipt of the State or Tribal application, the summary of the program as provided by the State or Tribe, and a request for public comments to be mailed to the appropriate EPA Regional Office. This comment period shall last for no less than 45 days. EPA will consider these comments during its review of the State or Tribal application.

(5) Within 60 days of submission of a State or Tribal application, EPA will, if requested, conduct a public hearing

## Environmental Protection Agency

## § 745.324

in each State or Indian Country seeking program authorization and will consider all comments submitted at that hearing during the review of the State or Tribal application.

(b) *Program description.* A State or Indian Tribe seeking to administer and enforce a program under this subpart must submit a description of the program. The description of the State or Tribal program must include:

(1)(i) The name of the State or Tribal agency that is or will be responsible for administering and enforcing the program, the name of the official in that agency designated as the point of contact with EPA, and addresses and phone numbers where this official can be contacted.

(ii) Where more than one agency is or will be responsible for administering and enforcing the program, the State or Indian Tribe must designate a primary agency to oversee and coordinate administration and enforcement of the program and serve as the primary contact with EPA.

(iii) In the event that more than one agency is or will be responsible for administering and enforcing the program, the application must also include a description of the functions to be performed by each agency. The description shall explain and how the program will be coordinated by the primary agency to ensure consistency and effective administration of the within the State or Indian Tribe.

(2) To demonstrate that the State or Tribal program is at least as protective as the Federal program, fulfilling the criteria in paragraph (e)(2)(i) of this section, the State or Tribal application must include:

(i) A description of the program that demonstrates that the program contains all of the elements specified in § 745.325, § 745.326, or both; and

(ii) An analysis of the State or Tribal program that compares the program to the Federal program in subpart E or subpart L of this part, or both. This analysis must demonstrate how the program is, in the State's or Indian Tribe's assessment, at least as protective as the elements in the Federal program at subpart E or subpart L of this part, or both. EPA will use this analysis to evaluate the protectiveness of

the State or Tribal program in making its determination pursuant to paragraph (e)(2)(i) of this section.

(3) To demonstrate that the State or Tribal program provides adequate enforcement, fulfilling the criteria in paragraph (e)(2)(ii) of this section, the State or Tribal application must include a description of the State or Tribal lead-based paint compliance and enforcement program that demonstrates that the program contains all of the elements specified at § 745.327. This description shall include copies of all policies, certifications, plans, reports, and other materials that demonstrate that the State or Tribal program contains all of the elements specified at § 745.327.

(4)(i) The program description for an Indian Tribe shall also include a map, legal description, or other information sufficient to identify the geographical extent of the territory over which the Indian Tribe exercises jurisdiction.

(ii) The program description for an Indian Tribe shall also include a demonstration that the Indian Tribe:

(A) Is recognized by the Secretary of the Interior.

(B) has an existing government exercising substantial governmental duties and powers.

(C) has adequate civil regulatory jurisdiction (as shown in the Tribal legal certification in paragraph (c)(2) of this section) over the subject matter and entities regulated.

(D) is reasonably expected to be capable of administering the Federal program for which it is seeking authorization.

(iii) If the Administrator has previously determined that an Indian Tribe has met the prerequisites in paragraphs (b)(4)(ii)(A) and (B) of this section for another EPA program, the Indian Tribe need provide only that information unique to the lead-based paint program required by paragraphs (b)(4)(ii)(C) and (D) of this section.

(c) *Attorney General's statement.* (1) A State or Indian Tribe must submit a written statement signed by the Attorney General or Tribal Counsel (or equivalent) certifying that the laws and regulations of the State or Indian Tribe provide adequate legal authority to administer and enforce the State or

Tribal program. This statement shall include citations to the specific statutes and regulations providing that legal authority.

(2) The Tribal legal certification (the equivalent to the Attorney General's statement) may also be submitted and signed by an independent attorney retained by the Indian Tribe for representation in matters before EPA or the courts pertaining to the Indian Tribe's program. The certification shall include an assertion that the attorney has the authority to represent the Indian Tribe with respect to the Indian Tribe's authorization application.

(3) If a State application seeks approval of its program to operate in Indian Country, the required legal certification shall include an analysis of the applicant's authority to implement its provisions in Indian Country. The applicant shall include a map delineating the area over which it seeks to operate the program.

(d) *Program certification.* (1) At the time of submitting an application, a State may also certify to the Administrator that the State program meets the requirements contained in paragraphs (e)(2)(i) and (e)(2)(ii) of this section.

(2) If this certification is contained in a State's application, the program shall be deemed to be authorized by EPA until such time as the Administrator disapproves the program application or withdraws the program authorization. A program shall not be deemed authorized pursuant to this subpart to the extent that jurisdiction is asserted over Indian Country, including non-member fee lands within an Indian reservation.

(3) If the application does not contain such certification, the State program will be authorized only after the Administrator authorizes the program in accordance with paragraph (e) of this section.

(4) This certification shall take the form of a letter from the Governor or the Attorney General to the Administrator. The certification shall reference the program analysis in paragraph (b)(3) of this section as the basis for concluding that the State program is at least as protective as the Federal

program, and provides adequate enforcement.

(e) *EPA approval.* (1) EPA will fully review and consider all portions of a State or Tribal application.

(2) Within 180 days of receipt of a complete State or Tribal application, the Administrator shall either authorize the program or disapprove the application. The Administrator shall authorize the program, after notice and the opportunity for public comment and a public hearing, only if the Administrator finds that:

(i) The State or Tribal program is at least as protective of human health and the environment as the corresponding Federal program under subpart E or subpart L of this part, or both; and

(ii) The State or Tribal program provides adequate enforcement.

(3) EPA shall notify in writing the State or Indian Tribe of the Administrator's decision to authorize the State or Tribal program or disapprove the State's or Indian Tribe's application.

(4) If the State or Indian Tribe applies for authorization of State or Tribal programs under both subpart E and subpart L, EPA may, as appropriate, authorize one program and disapprove the other.

(f) *EPA administration and enforcement.* (1) If a State or Indian Tribe does not have an authorized program to administer and enforce subpart L of this part in effect by August 31, 1998, the Administrator shall, by such date, establish and enforce the provisions of subpart L of this part as the Federal program for that State or Indian Country.

(2) If a State or Indian Tribe does not have an authorized program to administer and enforce the pre-renovation education requirements of subpart E of this part by August 31, 1998, the Administrator will, by such date, enforce those provisions of subpart E of this part as the Federal program for that State or Indian Country. If a State or Indian Tribe does not have an authorized program to administer and enforce the training, certification and accreditation requirements and work practice standards of subpart E of this part by April 22, 2009, the Administrator will, by such date, enforce those provisions

## Environmental Protection Agency

## § 745.324

of subpart E of this part as the Federal program for that State or Indian Country.

(3) Upon authorization of a State or Tribal program, pursuant to paragraph (d) or (e) of this section, it shall be an unlawful act under sections 15 and 409 of TSCA for any person to fail or refuse to comply with any requirements of such program.

(g) *Oversight.* EPA shall periodically evaluate the adequacy of a State's or Indian Tribe's implementation and enforcement of its authorized programs.

(h) *Reports.* Beginning 12 months after the date of program authorization, the primary agency for each State or Indian Tribe that has an authorized program shall submit a written report to the EPA Regional Administrator for the Region in which the State or Indian Tribe is located. This report shall be submitted at least once every 12 months for the first 3 years after program authorization. If these reports demonstrate successful program implementation, the Agency will automatically extend the reporting interval to every 2 years. If the subsequent reports demonstrate problems with implementation, EPA will require a return to annual reporting until the reports demonstrate successful program implementation, at which time the Agency will extend the reporting interval to every 2 years.

The report shall include the following information:

(1) Any significant changes in the content or administration of the State or Tribal program implemented since the previous reporting period; and

(2) All information regarding the lead-based paint enforcement and compliance activities listed at §745.327(d) "Summary on Progress and Performance."

(i) *Withdrawal of authorization.* (1) If EPA concludes that a State or Indian Tribe is not administering and enforcing an authorized program in compliance with the standards, regulations, and other requirements of sections 401 through 412 of TSCA and this subpart, the Administrator shall notify the primary agency for the State or Indian Tribe in writing and indicate EPA's intent to withdraw authorization of the program.

(2) The Notice of Intent to Withdraw shall:

(i) Identify the program aspects that EPA believes are inadequate and provide a factual basis for such findings.

(ii) Include copies of relevant documents.

(iii) Provide an opportunity for the State or Indian Tribe to respond either in writing or at a meeting with appropriate EPA officials.

(3) EPA may request that an informal conference be held between representatives of the State or Indian Tribe and EPA officials.

(4) Prior to issuance of a withdrawal, a State or Indian Tribe may request that EPA hold a public hearing. At this hearing, EPA, the State or Indian Tribe, and the public may present facts bearing on whether the State's or Indian Tribe's authorization should be withdrawn.

(5) If EPA finds that deficiencies warranting withdrawal did not exist or were corrected by the State or Indian Tribe, EPA may rescind its Notice of Intent to Withdraw authorization.

(6) Where EPA finds that deficiencies in the State or Tribal program exist that warrant withdrawal, an agreement to correct the deficiencies shall be jointly prepared by the State or Indian Tribe and EPA. The agreement shall describe the deficiencies found in the program, specify the steps the State or Indian Tribe has taken or will take to remedy the deficiencies, and establish a schedule, no longer than 180 days, for each remedial action to be initiated.

(7) If the State or Indian Tribe does not respond within 60 days of issuance of the Notice of Intent to Withdraw or an agreement is not reached within 180 days after EPA determines that a State or Indian Tribe is not in compliance with the Federal program, the Agency shall issue an order withdrawing the State's or Indian Tribe's authorization.

(8) By the date of such order, the Administrator will establish and enforce the provisions of subpart E or subpart L of this part, or both, as the Federal program for that State or Indian Country.

[61 FR 45825, Aug. 29, 1996, as amended at 73 FR 21767, Apr. 22, 2008]



**§ 745.325 Lead-based paint activities: State and Tribal program requirements.**

(a) *Program elements.* To receive authorization from EPA, a State or Tribal program must contain at least the following program elements for lead-based paint activities:

- (1) Procedures and requirements for the accreditation of lead-based paint activities training programs.
- (2) Procedures and requirements for the certification of individuals engaged in lead-based paint activities.
- (3) Work practice standards for the conduct of lead-based paint activities.
- (4) Requirements that all lead-based paint activities be conducted by appropriately certified contractors.
- (5) Development of the appropriate infrastructure or government capacity to effectively carry out a State or Tribal program.

(b) *Accreditation of training programs.* The State or Indian Tribe must have either:

- (1) Procedures and requirements for the accreditation of training programs that establish:
  - (i) Requirements for the accreditation of training programs, including but not limited to:
    - (A) Training curriculum requirements.
    - (B) Training hour requirements.
    - (C) Hands-on training requirements.
    - (D) Trainee competency and proficiency requirements.
    - (E) Requirements for training program quality control.
  - (ii) Procedures for the re-accreditation of training programs.
  - (iii) Procedures for the oversight of training programs.
  - (iv) Procedures for the suspension, revocation, or modification of training program accreditations; or
- (2) Procedures or regulations, for the purposes of certification, for the acceptance of training offered by an accredited training provider in a State or Tribe authorized by EPA.

(c) *Certification of individuals.* The State or Indian Tribe must have requirements for the certification of individuals that:

- (1) Ensure that certified individuals:
  - (i) Are trained by an accredited training program; and

- (ii) Possess appropriate education or experience qualifications for certification.

- (2) Establish procedures for re-certification.

- (3) Require the conduct of lead-based paint activities in accordance with work practice standards established by the State or Indian Tribe.

- (4) Establish procedures for the suspension, revocation, or modification of certifications.

- (5) Establish requirements and procedures for the administration of a third-party certification exam.

(d) *Work practice standards for the conduct of lead-based paint activities.* The State or Indian Tribe must have requirements or standards that ensure that lead-based paint activities are conducted reliably, effectively, and safely. At a minimum the State's or Indian Tribe's work practice standards for conducting inspections, risk assessments, and abatements must contain the requirements specified in paragraphs (d)(1), (d)(2), and (d)(3) of this section.

(1) The work practice standards for the inspection for the presence of lead-based paint must require that:

- (i) Inspections are conducted only by individuals certified by the appropriate State or Tribal authority to conduct inspections.

- (ii) Inspections are conducted in a way that identifies the presence of lead-based paint on painted surfaces within the interior or on the exterior of a residential dwelling or child-occupied facility.

- (iii) Inspections are conducted in a way that uses documented methodologies that incorporate adequate quality control procedures.

- (iv) A report is developed that clearly documents the results of the inspection.

- (v) Records are retained by the certified inspector or the firm.

(2) The work practice standards for risk assessment must require that:

- (i) Risk assessments are conducted only by individuals certified by the appropriate State or Tribal authority to conduct risk assessments.

- (ii) Risk assessments are conducted in a way that identifies and reports the presence of lead-based paint hazards.

## Environmental Protection Agency

## § 745.326

(iii) Risk assessments consist of, at least:

(A) An assessment, including a visual inspection, of the physical characteristics of the residential dwelling or child-occupied facility;

(B) Environmental sampling for lead in paint, dust, and soil;

(C) Environmental sampling requirements for lead in paint, dust, and soil that allow for comparison to the standards for lead-based paint hazards established or revised by the State or Indian Tribe pursuant to paragraph (e) of this section; and

(D) A determination of the presence of lead-based paint hazards made by comparing the results of visual inspection and environmental sampling to the standards for lead-based paint hazards established or revised by the State or Indian Tribe pursuant to paragraph (e) of this section.

(iv) The program elements required in paragraph (d)(2)(iii)(C) and (d)(2)(iii)(D) of this section shall be adopted in accordance with the schedule for the demonstration required in paragraph (e) of this section.

(v) The risk assessor develops a report that clearly presents the results of the assessment and recommendations for the control or elimination of all identified hazards.

(vi) The certified risk assessor or the firm retains the appropriate records.

(3) The work practice standards for abatement must require that:

(i) Abatements are conducted only by individuals certified by the appropriate State or Tribal authority to conduct or supervise abatements.

(ii) Abatements permanently eliminate lead-based paint hazards and are conducted in a way that does not increase the hazards of lead-based paint to the occupants of the dwelling or child-occupied facility.

(iii) Abatements include post-abatement lead in dust clearance sampling and conformance with clearance levels established or adopted by the State or Indian Tribe.

(iv) The abatement contractor develops a report that describes areas of the residential dwelling or child-occupied facility abated and the techniques employed.

(v) The certified abatement contractor or the firm retains appropriate records.

(e) The State or Indian Tribe must demonstrate that it has standards for identifying lead-based paint hazards and clearance standards for dust, that are at least as protective as the standards in §745.227 as amended on February 5, 2001. A State or Indian Tribe with such a section 402 program approved before February 5, 2003 shall make this demonstration no later than the first report submitted pursuant to §745.324(h) on or after February 5, 2003. A State or Indian Tribe with such a program submitted but not approved before February 5, 2003 may make this demonstration by amending its application or in its first report submitted pursuant to §745.324(h). A State or Indian Tribe submitting its program on or after February 5, 2003 shall make this demonstration in its application.

[61 FR 45825, Aug. 29, 1996, as amended at 66 FR 1240, Jan. 5, 2001]

### § 745.326 Renovation: State and Tribal program requirements.

(a) *Program elements.* To receive authorization from EPA, a State or Tribal program must contain the following program elements:

(1) For pre-renovation education programs, procedures and requirements for the distribution of lead hazard information to owners and occupants of target housing and child-occupied facilities before renovations for compensation.

(2) For renovation training, certification, accreditation, and work practice standards programs:

(i) Procedures and requirements for the accreditation of renovation and dust sampling technician training programs.

(ii) Procedures and requirements for the certification of renovators and dust sampling technicians.

(iii) Procedures and requirements for the certification of individuals and/or firms.

(iv) Requirements that all renovations be conducted by appropriately certified individuals and/or firms.

(v) Work practice standards for the conduct of renovations.

(3) For all renovation programs, development of the appropriate infrastructure or government capacity to effectively carry out a State or Tribal program.

(b) *Pre-renovation education.* To be considered at least as protective as the Federal program, the State or Tribal program must:

(1) Establish clear standards for identifying renovation activities that trigger the information distribution requirements.

(2) Establish procedures for distributing the lead hazard information to owners and occupants of housing and child-occupied facilities prior to renovation activities.

(3) Require that the information to be distributed include either the pamphlet titled *Renovate Right: Important Lead Hazard Information for Families, Child Care Providers and Schools*, developed by EPA under section 406(a) of TSCA, or an alternate pamphlet or package of lead hazard information that has been submitted by the State or Tribe, reviewed by EPA, and approved by EPA for that State or Tribe. Such information must contain renovation-specific information similar to that in *Renovate Right: Important Lead Hazard Information for Families, Child Care Providers and Schools*, must meet the content requirements prescribed by section 406(a) of TSCA, and must be in a format that is readable to the diverse audience of housing and child-occupied facility owners and occupants in that State or Tribe.

(i) A State or Tribe with a pre-renovation education program approved before June 23, 2008, must demonstrate that it meets the requirements of this section no later than the first report that it submits pursuant to § 745.324(h) on or after April 22, 2009.

(ii) A State or Tribe with an application for approval of a pre-renovation education program submitted but not approved before June 23, 2008, must demonstrate that it meets the requirements of this section either by amending its application or in the first report that it submits pursuant to § 745.324(h) of this part on or after April 22, 2009.

(iii) A State or Indian Tribe submitting its application for approval of a pre-renovation education program on

or after June 23, 2008, must demonstrate in its application that it meets the requirements of this section.

(c) *Accreditation of training programs.* To be considered at least as protective as the Federal program, the State or Tribal program must meet the requirements of either paragraph (c)(1) or (c)(2) of this section:

(1) The State or Tribal program must establish accreditation procedures and requirements, including:

(i) Procedures and requirements for the accreditation of training programs, including, but not limited to:

(A) Training curriculum requirements.

(B) Training hour requirements.

(C) Hands-on training requirements.

(D) Trainee competency and proficiency requirements.

(E) Requirements for training program quality control.

(ii) Procedures and requirements for the re-accreditation of training programs.

(iii) Procedures for the oversight of training programs.

(iv) Procedures and standards for the suspension, revocation, or modification of training program accreditations; or

(2) The State or Tribal program must establish procedures and requirements for the acceptance of renovation training offered by training providers accredited by EPA or a State or Tribal program authorized by EPA under this subpart.

(d) *Certification of renovators.* To be considered at least as protective as the Federal program, the State or Tribal program must:

(1) Establish procedures and requirements for individual certification that ensure that certified renovators are trained by an accredited training program.

(2) Establish procedures and requirements for re-certification.

(3) Establish procedures for the suspension, revocation, or modification of certifications.

(e) *Work practice standards for renovations.* To be considered at least as protective as the Federal program, the State or Tribal program must establish standards that ensure that renovations are conducted reliably, effectively, and safely. At a minimum, the State or

## Environmental Protection Agency

## § 745.327

Tribal program must contain the following requirements:

(1) Renovations must be conducted only by certified contractors.

(2) Renovations are conducted using lead-safe work practices that are at least as protective to occupants as the requirements in § 745.85.

(3) Certified contractors must retain appropriate records.

[73 FR 21768, Apr. 22, 2008]

EFFECTIVE DATE NOTE: At 75 FR 24819, May 6, 2010, § 745.326 was amended by adding paragraph (f), effective July 6, 2010. For the convenience of the user, the added text is set forth as follows:

### § 745.326 Renovation: State and Tribal program requirements.

\* \* \* \* \*

(f) *Revisions to renovation program requirements.* When EPA publishes in the FEDERAL REGISTER revisions to the renovation program requirements contained in subparts E and L of this part:

(1) A State or Tribe with a renovation program approved before the effective date of the revisions to the renovation program requirements in subparts E and L of this part must demonstrate that it meets the requirements of this section no later than the first report that it submits pursuant to § 745.324(h) but no later than 2 years after the effective date of the revisions.

(2) A State or Tribe with an application for approval of a renovation program submitted but not approved before the effective date of the revisions to the renovation program requirements in subparts E and L of this part must demonstrate that it meets the requirements of this section either by amending its application or in the first report that it submits pursuant to § 745.324(h) of this part but no later than 2 years after the effective date of the revisions.

(3) A State or Tribe submitting its application for approval of a renovation program on or after the effective date of the revisions must demonstrate in its application that it meets the requirements of the new renovation program requirements in subparts E and L of this part.

### § 745.327 State or Indian Tribal lead-based paint compliance and enforcement programs.

(a) *Approval of compliance and enforcement programs.* A State or Indian Tribe seeking authorization of a lead-based paint program can apply for and receive either interim or final approval of the compliance and enforcement

program portion of its lead-based paint program. Indian Tribes are not required to exercise criminal enforcement jurisdiction as a condition for program authorization.

(1) *Interim approval.* Interim approval of the compliance and enforcement program portion of the State or Tribal lead-based paint program may be granted by EPA only once, and subject to a specific expiration date.

(i) To be considered adequate for purposes of obtaining interim approval for the compliance and enforcement program portion of a State or Tribal lead-based paint program, a State or Indian Tribe must, in its application described at § 745.324(a):

(A) Demonstrate it has the legal authority and ability to immediately implement the elements in paragraph (b) of this section. This demonstration shall include a statement that the State or Indian Tribe, during the interim approval period, shall carry out a level of compliance monitoring and enforcement necessary to ensure that the State or Indian Tribe addresses any significant risks posed by noncompliance with lead-based paint activity requirements.

(B) Present a plan with time frames identified for implementing in the field each element in paragraph (c) of this section. All elements of paragraph (c) of this section must be fully implemented no later than 3 years from the date of EPA's interim approval of the compliance and enforcement program portion of a State or Tribal lead-based paint program. A statement of resources must be included in the State or Tribal plan which identifies what resources the State or Indian Tribe intends to devote to the administration of its lead-based paint compliance and enforcement program.

(C) Agree to submit to EPA the Summary on Progress and Performance of lead-based paint compliance and enforcement activities as described at paragraph (d) of this section.

(ii) Any interim approval granted by EPA for the compliance and enforcement program portion of a State or Tribal lead-based paint program will expire no later than 3 years from the date of EPA's interim approval. One hundred and eighty days prior to this

expiration date, a State or Indian Tribe shall apply to EPA for final approval of the compliance and enforcement program portion of a State or Tribal lead-based paint program. Final approval shall be given to any State or Indian Tribe which has in place all of the elements of paragraphs (b), (c), and (d) of this section. If a State or Indian Tribe does not receive final approval for the compliance and enforcement program portion of a State or Tribal lead-based paint program by the date 3 years after the date of EPA's interim approval, the Administrator shall, by such date, initiate the process to withdraw the State or Indian Tribe's authorization pursuant to § 745.324(i).

(2) *Final approval.* Final approval of the compliance and enforcement program portion of a State or Tribal lead-based paint program can be granted by EPA either through the application process described at § 745.324(a), or, for States or Indian Tribes which previously received interim approval as described in paragraph (a)(1) of this section, through a separate application addressing only the compliance and enforcement program portion of a State or Tribal lead-based paint program.

(i) For the compliance and enforcement program to be considered adequate for final approval through the application described at § 745.324(a), a State or Indian Tribe must, in its application:

(A) Demonstrate it has the legal authority and ability to immediately implement the elements in paragraphs (b) and (c) of this section.

(B) Submit a statement of resources which identifies what resources the State or Indian Tribe intends to devote to the administration of its lead-based paint compliance and enforcement program.

(C) Agree to submit to EPA the Summary on Progress and Performance of lead-based paint compliance and enforcement activities as described at paragraph (d) of this section.

(ii) For States or Indian Tribes which previously received interim approval as described in paragraph (a)(1) of this section, in order for the State or Tribal compliance and enforcement program to be considered adequate for final approval through a separate application

addressing only the compliance and enforcement program portion of a State or Tribal lead-based paint program, a State or Indian Tribe must, in its application:

(A) Demonstrate that it has the legal authority and ability to immediately implement the elements in paragraphs (b) and (c) of this section.

(B) Submit a statement which identifies the resources the State or Indian Tribe intends to devote to the administration of its lead-based paint compliance and enforcement program.

(C) Agree to submit to EPA the Summary on Progress and Performance of lead-based paint compliance and enforcement activities as described at paragraph (d) of this section.

(D) To the extent not previously submitted through the application described at § 745.324(a), submit copies of all applicable State or Tribal statutes, regulations, standards, and other material that provide the State or Indian Tribe with authority to administer and enforce the lead-based paint compliance and enforcement program, and copies of the policies, certifications, plans, reports, and any other documents that demonstrate that the program meets the requirements established in paragraphs (b) and (c) of this section.

(b) *Standards, regulations, and authority.* The standards, regulations, and authority described in paragraphs (b)(1) through (b)(4) of this section are part of the required elements for the compliance and enforcement portion of a State or Tribal lead-based paint program.

(1) *Lead-based paint activities and requirements.* State or Tribal lead-based paint compliance and enforcement programs will be considered adequate if the State or Indian Tribe demonstrates, in its application at § 745.324(a), that it has established a lead-based paint program containing the following requirements:

(i) Accreditation of training programs as described at § 745.325(b).

(ii) Certification of individuals engaged in lead-based paint activities as described at § 745.325(c).

(iii) Standards for the conduct of lead-based paint activities as described at § 745.325(d); and, as appropriate,

## Environmental Protection Agency

## § 745.327

(iv) Requirements that regulate the conduct of renovation activities as described at § 745.326.

(2) *Authority to enter.* State or Tribal officials must be able to enter, through consent, warrant, or other authority, premises or facilities where lead-based paint activities violations may occur for purposes of conducting inspections.

(i) State or Tribal officials must be able to enter premises or facilities where those engaged in training for lead-based paint activities conduct business.

(ii) For the purposes of enforcing a renovation program, State or Tribal officials must be able to enter a firm's place of business or work site.

(iii) State or Tribal officials must have authority to take samples and review records as part of the lead-based paint activities inspection process.

(3) *Flexible remedies.* A State or Tribal lead-based paint compliance and enforcement program must provide for a diverse and flexible array of enforcement remedies. At a minimum, the remedies that must be reflected in an enforcement response policy must include the following:

(i) Warning letters, Notices of Non-compliance, Notices of Violation, or the equivalent;

(ii) Administrative or civil actions, including penalty authority (e.g., accreditation or certification suspension, revocation, or modification); and

(iii) Authority to apply criminal sanctions or other criminal authority using existing State or Tribal laws, as applicable.

(4) *Adequate resources.* An application must include a statement that identifies the resources that will be devoted by the State or Indian Tribe to the administration of the State or Tribal lead-based paint compliance and enforcement program. This statement must address fiscal and personnel resources that will be devoted to the program.

(c) *Performance elements.* The performance elements described in paragraphs (c)(1) through (c)(7) of this section are part of the required elements for the compliance and enforcement program portion of a State or Tribal lead-based paint program.

(1) *Training.* A State or Tribal lead-based paint compliance and enforcement program must implement a process for training enforcement and inspection personnel and ensure that enforcement personnel and inspectors are well trained. Enforcement personnel must understand case development procedures and the maintenance of proper case files. Inspectors must successfully demonstrate knowledge of the requirements of the particular discipline (e.g., abatement supervisor, and/or abatement worker, and/or lead-based paint inspector, and/or risk assessor, and/or project designer) for which they have compliance monitoring and enforcement responsibilities. Inspectors must also be trained in violation discovery, methods of obtaining consent, evidence gathering, preservation of evidence and chain-of-custody, and sampling procedures. A State or Tribal lead-based paint compliance and enforcement program must also implement a process for the continuing education of enforcement and inspection personnel.

(2) *Compliance assistance.* A State or Tribal lead-based paint compliance and enforcement program must provide compliance assistance to the public and the regulated community to facilitate awareness and understanding of and compliance with State or Tribal requirements governing the conduct of lead-based paint activities. The type and nature of this assistance can be defined by the State or Indian Tribe to achieve this goal.

(3) *Sampling techniques.* A State or Tribal lead-based paint compliance and enforcement program must have the technological capability to ensure compliance with the lead-based paint program requirements. A State or Tribal application for approval of a lead-based paint program must show that the State or Indian Tribe is technologically capable of conducting a lead-based paint compliance and enforcement program. The State or Tribal program must have access to the facilities and equipment necessary to perform sampling and laboratory analysis as needed. This laboratory facility must be a recognized laboratory as defined at § 745.223, or the State or Tribal

program must implement a quality assurance program that ensures appropriate quality of laboratory personnel and protects the integrity of analytical data.

(4) *Tracking tips and complaints.* A State or Tribal lead-based paint compliance and enforcement program must demonstrate the ability to process and react to tips and complaints or other information indicating a violation.

(5) *Targeting inspections.* A State or Tribal lead-based paint compliance and enforcement program must demonstrate the ability to target inspections to ensure compliance with the lead-based paint program requirements. Such targeting must include a method for obtaining and using notifications of commencement of abatement activities.

(6) *Follow up to inspection reports.* A State or Tribal lead-based paint compliance and enforcement program must demonstrate the ability to reasonably, and in a timely manner, process and follow-up on inspection reports and other information generated through enforcement-related activities associated with a lead-based paint program. The State or Tribal program must be in a position to ensure correction of violations and, as appropriate, effectively develop and issue enforcement remedies/responses to follow up on the identification of violations.

(7) *Compliance monitoring and enforcement.* A State or Tribal lead-based paint compliance and enforcement program must demonstrate, in its application for approval, that it is in a position to implement a compliance monitoring and enforcement program. Such a compliance monitoring and enforcement program must ensure correction of violations, and encompass either planned and/or responsive lead-based paint compliance inspections and development/issuance of State or Tribal enforcement responses which are appropriate to the violations.

(d) *Summary on Progress and Performance.* The Summary on Progress and Performance described below is part of the required elements for the compliance and enforcement program portion of a State or Tribal lead-based paint program. A State or Tribal lead-based paint compliance and enforcement pro-

gram must submit to the appropriate EPA Regional Administrator a report which summarizes the results of implementing the State or Tribal lead-based paint compliance and enforcement program, including a summary of the scope of the regulated community within the State or Indian Tribe (which would include the number of individuals and firms certified in lead-based paint activities and the number of training programs accredited), the inspections conducted, enforcement actions taken, compliance assistance provided, and the level of resources committed by the State or Indian Tribe to these activities. The report shall be submitted according to the requirements at § 745.324(h).

(e) *Memorandum of Agreement.* An Indian Tribe that obtains program approval must establish a Memorandum of Agreement with the Regional Administrator. The Memorandum of Agreement shall be executed by the Indian Tribe's counterpart to the State Director (e.g., the Director of Tribal Environmental Office, Program or Agency). The Memorandum of Agreement must include provisions for the timely and appropriate referral to the Regional Administrator for those criminal enforcement matters where that Indian Tribe does not have the authority (e.g., those addressing criminal violations by non-Indians or violations meriting penalties over \$5,000). The Agreement must also identify any enforcement agreements that may exist between the Indian Tribe and any State.

(f) *Electronic reporting under State or Indian Tribe programs.* States and tribes that choose to receive electronic documents under the authorized state or Indian tribe lead-based paint program, must ensure that the requirements of 40 CFR part 3—(Electronic reporting) are satisfied in their lead-based paint program.

[61 FR 45825, Aug. 29, 1996, as amended at 70 FR 59889, Oct. 13, 2005; 73 FR 21769, Apr. 22, 2008]

**§ 745.339 Effective date.**

States and Indian Tribes may seek authorization to administer and enforce subpart L of this part pursuant to this subpart at any time. States and

## Environmental Protection Agency

## § 747.115

Indian Tribes may seek authorization to administer and enforce the pre-renovation education provisions of subpart E of this part pursuant to this subpart at any time. States and Indian Tribes may seek authorization to administer and enforce all of subpart E of this part pursuant to this subpart effective June 23, 2008.

[73 FR 21769, Apr. 22, 2008]

### PART 747—METALWORKING FLUIDS

#### Subpart A [Reserved]

#### Subpart B—Specific Use Requirements for Certain Chemical Substances

Sec.

747.115 Mixed mono and diamides of an organic acid.

747.195 Triethanolamine salt of a substituted organic acid.

747.200 Triethanolamine salt of tricarboxylic acid.

AUTHORITY: 15 U.S.C. 2604 and 2605.

#### Subpart A [Reserved]

#### Subpart B—Specific Use Requirements for Certain Chemical Substances

##### § 747.115 Mixed mono and diamides of an organic acid.

This section identifies activities with respect to a chemical substance which are prohibited and requires that warnings and instructions accompany the substance when distributed in commerce.

(a) *Chemical substance subject to this section.* The following chemical substance, referred to by its premanufacture notice number and generic chemical name, is subject to this section: P-84-529, mixed mono and diamides of an organic acid.

(b) *Definitions.* Definitions in section 3 of the Act, 15 U.S.C. 2602, apply to this section unless otherwise specified in this paragraph. In addition, the following definitions apply:

(1) The terms *Act*, *article*, *chemical substance*, *commerce*, *importer*, *impurity*, *Inventory*, *manufacturer*, *person*, *process*, *processor*, and *small quantities solely for research and development* have the same meaning as in § 720.3 of this chapter.

(2) *Metalworking fluid* means a liquid of any viscosity or color containing intentionally added water used in metal machining operations for the purpose of cooling, lubricating, or rust inhibition.

(3) *Nitrosating agent* means any substance that has the potential to transfer a nitrosyl group (–NO) to a primary, secondary, or tertiary amine to form the corresponding nitrosamine.

(4) *Process or distribute in commerce solely for export* means to process or distribute in commerce solely for export from the United States under the following restrictions on domestic activity:

(i) Processing must be performed at sites under the control of the processor.

(ii) Distribution in commerce is limited to purposes of export.

(iii) The processor or distributor may not use the substance except in small quantities solely for research and development.

(c) *Use limitations.* (1) Any person producing a metalworking fluid, or a product which could be used in or as a metalworking fluid, which includes as one of its components P-84-529, is prohibited from adding any nitrosating agent to the metalworking fluid or product.

(2) Any person using as a metalworking fluid a product containing P-84-529 is prohibited from adding any nitrosating agent to the product.

(d) *Warnings and instructions.* (1) Any person who distributes in commerce P-84-529 in a metalworking fluid, or in any form in which it could be used as a component of a metalworking fluid, must send to each recipient of P-84-529 and confirm receipt in writing prior to the first shipment to that person:

(i) A letter that includes the following statements:

A substance, identified generically as mixed mono and diamides of an organic acid, contained in the product (*insert distributor's other identifier for product containing P-84-529*) has been regulated by the Environmental Protection Agency, at 40 CFR 747.115, as published in the FEDERAL REGISTER of September 20, 1984. A copy of the regulation is enclosed. The regulation prohibits the addition of any nitrosating agent, including nitrites, to the mixed mono and diamides of an organic acid, when the substance is or could be used in metalworking fluids. The



## § 747.115

## 40 CFR Ch. I (7-1-10 Edition)

addition of nitrites or other nitrosating agents to this substance leads to formation of a substance known to cause cancer in laboratory animals. The mixed mono and diamides of an organic acid has been specifically designed to be used without nitrites. Consult the enclosed regulation for further information.

(ii) A copy of this § 747.115.

(2)(i) Any person who distributes in commerce a metalworking fluid containing P-84-529 must affix a label to each container containing the fluid.

(ii) The label shall contain a warning statement which shall consist only of the following language:

**WARNING! Do Not Add Nitrites to This Metalworking Fluid under Penalty of Federal Law.** Addition of nitrites leads to formation of a substance known to cause cancer. This product is designed to be used without nitrites.

(iii) The first word of the warning statement shall be capitalized, and the type size for the first word shall be no smaller than six point type for a label five square inches or less in area, ten point type for a label above five but below ten square inches in area, twelve point type for a label above ten but below fifteen square inches in area, fourteen point type for a label above fifteen but below thirty square inches in area, or eighteen point type for a label over thirty square inches in area. The type size of the remainder of the warning statement shall be no smaller than six point type. All required label text shall be of sufficient prominence, and shall be placed with such conspicuousness relative to other label text and graphic material, to insure that the warning statement is read and understood by the ordinary individual under customary conditions of purchase and use.

(e) *Liability and determining whether a chemical substance is subject to this section.* (1) If a manufacturer or importer of a chemical substance which is described by the generic chemical name in paragraph (a) of this section makes an inquiry under § 710.7(g) of this chapter or § 720.25(b) of this chapter as to whether the specific substance is on the Inventory and EPA informs the manufacturer or importer that the substance is on the Inventory, EPA will also inform the manufacturer or im-

porter whether the substance is subject to this section.

(2) Except for manufacturers and importers of P-84-529, no processor, distributor, or user of P-84-529 will be in violation of this section unless that person has received a letter specified in paragraph (d)(1) of this section or a container with the label specified in paragraph (d)(2) of this section.

(f) *Exemptions.* A person identified in paragraphs (c) and (d) of this section is not subject to the requirements of those paragraphs if:

(1) The person manufactures, imports, processes, distributes in commerce, or uses the substance only in small quantities solely for research and development and in accordance with section 5(h)(3) of the Act.

(2) The person manufactures, imports, processes, distributes in commerce, or uses the substance only as an impurity.

(3) The person imports, processes, distributes in commerce, or uses the substance only as part of an article.

(4) The person processes or distributes the substance in commerce solely for export and, when distributing in commerce, labels the substance in accordance with section 12(a)(1)(B) of the Act.

(g) *Enforcement.* (1) Failure to comply with any provision of this section is a violation of section 15 of the Act [15 U.S.C. 2614].

(2) Failure or refusal to permit access to or copying of records, as required under section 11 of the Act, is a violation of section 15 of the Act [15 U.S.C. 2614].

(3) Failure or refusal to permit entry or inspection, as required under section 11 of the Act, is a violation of section 15 of the Act [15 U.S.C. 2614].

(4) Violators may be subject to the civil and criminal penalties in section 16 of the Act [15 U.S.C. 2615] for each violation.

(5) EPA may seek to enjoin the processing, distribution in commerce, or use of a chemical substance in violation of this section; act to seize any chemical substance processed, distributed in commerce, or used in violation of this section; or take other actions

## Environmental Protection Agency

## § 747.195

under the authority of sections 7 and 17 of the Act [15 U.S.C. 2605 and 2616].

[49 FR 36855, Sept. 20, 1984]

### § 747.195 Triethanolamine salt of a substituted organic acid.

This section identifies activities with respect to a chemical substance which are prohibited and requires that warnings and instructions accompany the substance when distributed in commerce.

(a) *Chemical substance subject to this section.* The following chemical substance, referred to by its premanufacture notice number and generic chemical name, is subject to this section: P-84-310, triethanolamine salt of a substituted organic acid.

(b) *Definitions.* Definitions in section 3 of the Act, 15 U.S.C. 2602, apply to this section unless otherwise specified in this paragraph. In addition, the following definitions apply:

(1) The terms *Act*, *article*, *chemical substance*, *commerce*, *importer*, *impurity*, *Inventory*, *manufacturer*, *person*, *process*, *processor*, and *small quantities solely for research and development*, have the same meaning as in § 720.3 of this chapter.

(2) *Metalworking fluid* means a liquid of any viscosity or color containing intentionally added water used in metal machining operations for the purpose of cooling, lubricating, or rust inhibition.

(3) *Nitrosating agent* means any substance that has the potential to transfer a nitrosyl group (—NO) to a primary, secondary, or tertiary amine to form the corresponding nitrosamine.

(4) *Process or distribute in commerce solely for export* means to process or distribute in commerce solely for export from the United States under the following restrictions on domestic activity:

(i) Processing must be performed at sites under the control of the processor.

(ii) Distribution in commerce is limited to purposes of export.

(iii) The processor or distributor may not use the substance except in small quantities solely for research and development.

(c) *Use limitations.* (1) Any person producing a metalworking fluid, or a product which could be used in or as a met-

alworking fluid, which includes as one of its components P-84-310, is prohibited from adding any nitrosating agent to the metalworking fluid or product.

(2) A person using as a metalworking fluid a product containing P-84-310 is prohibited from adding any nitrosating agent to the product.

(d) *Warnings and instructions.* (1) Any person who distributes in commerce P-84-310 in a metalworking fluid, or in any form in which it could be used as a component of a metalworking fluid, must send to each recipient of P-84-310 and confirm receipt in writing prior to the first shipment to that person:

(i) A letter that includes the following statements: A substance, identified generically as a triethanolamine salt of a substituted organic acid, contained in the product (*insert distributor's trade name or other identifier for product containing P-84-310*) has been regulated by the Environmental Protection Agency, at 40 CFR 747.195, as published in the FEDERAL REGISTER of June 14, 1984. A copy of the regulation is enclosed. The regulation prohibits the addition of any nitrosating agent, including nitrites, to the triethanolamine salt of a substituted organic acid, when the substance is or could be used in metalworking fluids. The addition of nitrites or other nitrosating agents to this substance leads to formation of a substance known to cause cancer in laboratory animals. The triethanolamine salt of a substituted organic acid has been specifically designed to be used without nitrites. Consult the enclosed regulation for further information.

(ii) A copy of this § 747.195.

(2)(i) Any person who distributes in commerce a metalworking fluid containing P-84-310 must affix a label to each container containing the fluid.

(ii) The label shall contain a warning statement which shall consist only of the following language:

WARNING! Do Not Add Nitrites to This Metalworking Fluid under Penalty of Federal Law. Addition of nitrites leads to formation of a substance known to cause cancer. This product is designed to be used without nitrites.

(iii) The first word of the warning statement shall be capitalized, and the type size for the first word shall be no

smaller than six point type for a label five square inches or less in area, ten point type for a label above five but below ten square inches in area, twelve point type for a label above ten but below fifteen square inches in area, fourteen point type for a label above fifteen but below thirty square inches in area, or eighteen point type for a label over thirty square inches in area. The type size of the remainder of the warning statement shall be no smaller than six point type. All required label text shall be of sufficient prominence, and shall be placed with such conspicuousness relative to other label text and graphic material, to insure that the warning statement is read and understood by the ordinary individual under customary conditions of purchase and use.

(e) *Liability and determining whether a chemical substance is subject to this section.* (1) If a manufacturer or importer of a chemical substance which is described by the generic chemical name in paragraph (a) of this section makes an inquiry under § 710.7(g) of this chapter or § 720.25(b) of this chapter as to whether the specific substance is on the Inventory and EPA informs the manufacturer or importer that the substance is on the Inventory, EPA will also inform the manufacturer or importer whether the substance is subject to this section.

(2) Except for manufacturers and importers of P-84-310, no processor, distributor, or user of P-84-310 will be in violation of this section unless that person has received a letter specified in paragraph (d)(1) of this section or a container with the label specified in paragraph (d)(2) of this section.

(f) *Exemptions.* A person identified in paragraphs (c) and (d) of this section is not subject to the requirements of those paragraphs if:

(1) The person manufactures, imports, processes, distributes in commerce, or uses the substance only in small quantities solely for research and development and in accordance with section 5(h)(3) of the Act.

(2) The person manufactures, imports, processes, distributes in commerce, or uses the substance only as an impurity.

(3) The person imports, processes, distributes in commerce, or uses the substance only as part of an article.

(4) The person processes or distributes the substance in commerce solely for export, and when distributing in commerce, labels the substance in accordance with section 12(a)(1)(B) of the Act.

(g) *Enforcement.* (1) Failure to comply with any provision of this section is a violation of section 15 of the Act (15 U.S.C. 2614).

(2) Failure or refusal to permit access to or copying of records, as required under section 11 of the Act, is a violation of section 15 of the Act (15 U.S.C. 2614).

(3) Failure or refusal to permit entry or inspection, as required under section 11 of the Act, is a violation of section 15 of the Act (15 U.S.C. 2614).

[49 FR 24668, June 14, 1984]

#### § 747.200 Triethanolamine salt of tricarboxylic acid.

This section identifies activities with respect to two chemical substances which are prohibited and requires that warnings and instructions accompany the substances when distributed in commerce.

(a) *Chemical substances subject to this section.* The following chemical substances, referred to by their premanufacture notice numbers and generic chemical names, are subject to this section:

P-83-1005, triethanolamine salt of tricarboxylic acid; and  
P-83-1062, tricarboxylic acid.

(b) *Definitions.* Definitions in section 3 of the Act, 15 U.S.C. 2602, apply to this section unless otherwise specified in this paragraph. In addition, the following definitions apply:

(1) The terms *Act*, *article*, *byproducts*, *chemical substance*, *commerce*, *imported*, *impurity*, *Inventory*, *manufacture or import for commercial purposes*, *manufacture solely for export*, *manufacturer*, *new chemical substance*, *person*, *process*, *processor*, and *small quantities solely for research and development* have the same meaning as in § 720.3 of this chapter.

(2) *Metalworking fluid* means a liquid of any viscosity or color containing intentionally added water used in metal

## Environmental Protection Agency

## § 747.200

machining operations for the purpose of cooling or lubricating.

(3) *Nitrosating agent* means any substance that has the potential to transfer a nitrosyl group ( $-\text{NO}$ ) to a secondary or tertiary amine to form the corresponding nitrosamine.

(c) *Use limitations.* (1) Any person producing a metalworking fluid, or a product which could be used in or as a metalworking fluid, which includes as one of its components P-83-1005 is prohibited from adding any nitrosating agent to the metalworking fluid or product.

(2) Any person using as metalworking fluid a product containing P-83-1005 is prohibited from adding any nitrosating agent to the product.

(d) *Warnings and instructions.* (1) Any person who distributes in commerce P-83-1005 in a metalworking fluid, or in any form in which it could be used as a component of a metalworking fluid, must send to each recipient of P-83-1005 and confirm receipt prior to the first shipment to that person:

(i) A letter that includes the following statements:

A substance, identified generically as triethanolamine salt, of tricarboxylic acid, contained in the product (*insert distributor's trade name or other identifier for product containing P-83-1005*) has been regulated by the Environmental Protection Agency, at 40 CFR 747.200, as published in the FEDERAL REGISTER of January 23, 1984. A copy of the regulation is enclosed. The regulation prohibits the addition of any nitrosating agent, including nitrites, to the triethanolamine salt of tricarboxylic acid, when the substance is or could be used in metalworking fluids. The addition of nitrites or other nitrosating agents to this substance leads to formation of a substance known to cause cancer in laboratory animals. The triethanolamine salt of the tricarboxylic acid, has been specifically designed to be used without nitrites. Consult the enclosed regulation for further information.

(ii) A copy of this rule.

(2) Any person who distributes in commerce a metalworking fluid containing P-83-1005 must affix to each container containing the fluid a label that includes, in letters no smaller than ten point type, the following statement:

WARNING! Do Not Add Nitrites to This Metalworking Fluid under Penalty of Federal Law. Addition of nitrite leads to forma-

tion of a substance known to cause cancer. This product is designed to be used without nitrites.

(3) Any person who distributes in commerce P-83-1062 in any form in which it could be combined with water and triethanolamine to produce P-83-1005 must send to each recipient of P-83-1062, and confirm receipt prior to the first shipment to that person:

(i) A letter that includes the following statements:

A substance, identified generically as tricarboxylic acid, contained in the product (*insert distributor's trade name or other identifier for product containing P-83-1062*) has been regulated by the Environmental Protection Agency (40 CFR 747.200 published in the FEDERAL REGISTER of January 23, 1984. A copy of the regulation is enclosed. Combining tricarboxylic acid with water and the triethanolamine produces a substance, identified generically as the triethanolamine salt of the tricarboxylic acid. The regulation prohibits the addition of nitrosating agents, including nitrites, to the triethanolamine salt of tricarboxylic acid, when that substance is or could be used in metalworking fluids. The addition of nitrites or other nitrosating agents to that substance leads to formation of a substance known to cause cancer in laboratory animals. Consult the enclosed regulation for further information.

(ii) A copy of this rule.

(e) *Liability and determining whether a chemical substance is subject to this section.* (1) If a manufacturer or importer of a chemical substance which is described by one of the generic names in paragraph (a) of this section makes an inquiry under § 710.7(g) of this chapter or § 720.25(b) of this chapter as to whether the specific substance is on the Inventory and EPA informs the manufacturer or importer that the substance is on the Inventory, EPA will also inform the manufacturer or importer whether the substance is subject to this section.

(2) Except for manufacturers and importers of P-83-1005 and P-83-1062, no processor, distributor, or user of P-83-1005 or P-83-1062 will be in violation of this section unless that person has received a letter specified in paragraph (d)(1) or (3) of this section or a container with the label specified in paragraph (d)(2) of this section.

(2) Except for manufacturers and importers of P-83-1005 and P-83-1062, no processor, distributor, or user of P-83-1005 or P-83-1062 will be in violation of this section unless that person has received a letter specified in paragraph (d)(1) or (3) of this section or a container with the label specified in paragraph (d)(2) of this section.

(f) *Exemptions and exclusions.* The chemical substances identified in paragraph (a) of this section are not subject to the requirements of paragraphs (c) and (d) of this section, if:

(1) The substance is manufactured, imported, processed, distributed in commerce, and used only in small quantities solely for research and development, and if the substance is manufactured, imported, processed, distributed in commerce, and used in accordance with section 5(h)(3) of the Act.

(2) The substance is manufactured, imported, processed, distributed in commerce, or used only as an impurity.

(3) The substance is imported, processed, distributed in commerce, or used only as part of an article.

(4) The substance is manufactured solely for export.

(g) *Enforcement.* (1) Failure to comply with any provision of this section is a violation of section 15 of the Act (15 U.S.C. 2614).

(2) Failure or refusal to permit access to or copying of records, as required under section 11 of the Act, is a violation of a section 15 of the Act (15 U.S.C. 2614).

(3) Failure or refusal to permit entry or inspection, as required under section 11 of the Act, is a violation of section 15 of the Act (15 U.S.C. 2614).

(4) Violators may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation.

(5) EPA may seek to enjoin the processing, distribution in commerce, or use of a chemical substance in violation of this section, act to seize any chemical substance, processed, distributed in commerce, or used in violation of this section or take other actions under the authority of section 7 or 17 of the Act (15 U.S.C. 2605 or 2616).

[49 FR 2772, Jan. 23, 1984]

## PART 749—WATER TREATMENT CHEMICALS

### Subparts A-C [Reserved]

### Subpart D—Air Conditioning and Cooling Systems

Sec.

749.68 Hexavalent chromium-based water treatment chemicals in cooling systems.

AUTHORITY: 15 U.S.C. 2605 and 2607.

### Subparts A-C [Reserved]

### Subpart D—Air Conditioning and Cooling Systems

#### § 749.68 Hexavalent chromium-based water treatment chemicals in cooling systems.

(a) *Chemicals subject to this section.* Hexavalent chromium-based water treatment chemicals that contain hexavalent chromium, usually in the form of sodium dichromate (CAS No. 10588-01-9), are subject to this section. Other examples of hexavalent chromium compounds that can be used to treat water are: Chromic acid (CAS No. 7738-94-5), chromium trioxide (CAS No. 1333-83-0), dichromic acid (CAS No. 13530-68-2), potassium chromate (CAS No. 7789-00-6), potassium dichromate (CAS No. 7778-50-9), sodium chromate (CAS No. 7775-11-3), zinc chromate (CAS No. 13530-65-9), zinc chromate hydroxide (CAS No. 153936-94-6), zinc dichromate (CAS No. 14018-95-2), and zinc potassium chromate (CAS No. 11103-86-9).

(b) *Purpose.* The purpose of this section is to impose certain requirements on activities involving hexavalent chromium-based water treatment chemicals to prevent unreasonable risks associated with human exposure to air emissions of hexavalent chromium from comfort cooling towers.

(c) *Applicability.* This section is applicable to use of hexavalent chromium-based water treatment chemicals in comfort cooling towers and to distribution in commerce of hexavalent chromium-based water treatment chemicals for use in cooling systems.

(d) *Definitions.* Definitions in section 3 of the Toxic Substances Control Act, 15 U.S.C. 2602, apply to this section unless otherwise specified in this paragraph. In addition, the following definitions apply:

(1) *Act* means the Toxic Substances Control Act, 15 U.S.C. 2601 *et seq.*

## Environmental Protection Agency

§ 749.68

(2) *Chilled water loop* means any closed cooling water system that transfers heat from air handling units or refrigeration equipment to a refrigeration machine, or chiller.

(3) *Closed cooling water system* means any configuration of equipment in which heat is transferred by circulating water that is contained within the equipment and not discharged to the air; chilled water loops are included.

(4) *Comfort cooling towers* means cooling towers that are dedicated exclusively to and are an integral part of heating, ventilation, and air conditioning or refrigeration systems.

(5) *Container* means any bag, barrel, bottle, box, can, cylinder, drum, or the like that holds hexavalent chromium-based water treatment chemicals for use in cooling systems.

(6) *Cooling tower* means an open water recirculating device that uses fans or natural draft to draw or force ambient air through the device to cool warm water by direct contact.

(7) *Cooling system* means any cooling tower or closed cooling water system.

(8) *Distributor* means any person who distributes in commerce water treatment chemicals for use in cooling systems.

(9) *EPA* means the Environmental Protection Agency.

(10) *Hexavalent chromium* means the oxidation state of chromium with an oxidation number of +6; a coordination number of 4 and tetrahedral geometry.

(11) *Hexavalent chromium-based water treatment chemicals* means any chemical containing hexavalent chromium which can be used to treat water, either alone or in combination with other chemicals, where the mixture can be used to treat water.

(12) *Industrial cooling tower* means any cooling tower used to remove heat from industrial processes, chemical reactions, or plants producing electrical power.

(13) *Label* means any written, printed, or graphic material displayed on or affixed to containers of hexavalent chromium-based water treatment chemicals that are to be used in cooling systems.

(14) *Person* means any natural person, firm, company, corporation, joint ven-

ture, partnership, sole proprietorship, association, or any other business entity; any State or political subdivision thereof; any municipality; any interstate body; and any department, agency, or instrumentality of the Federal Government.

(15) *Shipment* means the act or process of shipping goods by any form of conveyance.

(16) *Water treatment chemicals* means any combination of chemical substances used to treat water in cooling systems and can include corrosion inhibitors, antiscalants, dispersants, and any other chemical substances except biocides.

(e) *Prohibition of distribution in commerce and commercial use.* (1) All persons are prohibited from distributing in commerce hexavalent chromium-based water treatment chemicals for use in comfort cooling towers.

(2) All persons are prohibited from commercial use of hexavalent chromium-based water treatment chemicals in comfort cooling towers.

(3) Distribution in commerce of hexavalent chromium-based water treatment chemicals for use in, and commercial use of hexavalent chromium-based water treatment chemicals in, industrial cooling towers and closed cooling water systems are not prohibited.

(f) *Effective dates.* (1) The prohibition described in paragraph (e)(1) of this section against distributing in commerce hexavalent chromium-based water treatment chemicals for use in comfort cooling towers is effective February 20, 1990.

(2) The prohibition described in paragraph (e)(2) of this section against using hexavalent chromium-based water treatment chemicals in comfort cooling towers is effective May 18, 1990.

(g) *Labeling.* (1) Each person who distributes in commerce hexavalent chromium-based water treatment chemicals for use in cooling systems after February 20, 1990, shall affix a label or keep affixed an existing label in accordance with this paragraph, to each container of the chemicals. The label shall consist of the following language:

WARNING: This product contains hexavalent chromium. Inhalation of

hexavalent chromium air emissions increases the risk of lung cancer. Federal Law prohibits use of this substance in comfort cooling towers, which are towers that are open water recirculation devices and that are dedicated exclusively to, and are an integral part of, heating, ventilation, and air conditioning or refrigeration systems.

(2) The first word of the warning statement shall be capitalized, and the type size for the first word shall be no smaller than 10-point type for a label less than or equal to 10 square inches in area, 12-point type for a label above 10 but less than or equal to 15 square inches in area, 14-point type for a label above 15 but less than or equal to 30 square inches in area, or 18-point type for a label above 30 square inches in area. The type size of the remainder of the warning statement shall be no smaller than 6-point type. All required label text shall be in English and of sufficient prominence and shall be placed with such conspicuousness, relative to other label text and graphic material, to ensure that the warning statement is read and understood by the ordinary individual under customary conditions of purchase and use.

(h) *Recordkeeping.* (1) Each person who distributes in commerce any hexavalent chromium-based water treatment chemicals for use in cooling systems after February 20, 1990, shall retain in one location at the headquarters of the distributor documentation showing:

(i) The name, address, contact, and telephone number of the cooling system owners/operators to whom the chemicals were shipped.

(ii) The chemicals included in the shipment, the amount of each chemical shipped, and the location(s) at which the chemicals will be used.

(2) The information described in paragraph (h)(1) of this section shall be retained for 2 years from the date of shipment.

(i) *Reporting.* (1) Each person who distributes in commerce any hexavalent chromium-based water treatment chemicals for use in cooling systems shall report to the Regional Administrator of the EPA Region in which the distributor headquarters is located. The report shall be postmarked not later than February 20, 1990, or 30 days after the person first begins the distribution

in commerce of hexavalent chromium-based water treatment chemicals, whichever is later, and shall include:

(i) For the headquarters, the distributor name, address, telephone number, and the name of a contact.

(ii) For the shipment offices through which hexavalent chromium-based water treatment chemicals are sold for use in cooling systems, the distributor name, address, telephone number, and the name of a contact.

(2) The report identified in paragraph (i)(1) of this section shall be updated as changes occur in the distributor headquarters or shipment office information. The updated report shall be submitted to the Regional Administrator and postmarked no later than 10 calendar days after the change occurs.

(3) A person may assert a claim of confidentiality for any information submitted to EPA in connection with this rule. Any claim of confidentiality must accompany the information when submitted to EPA. Persons claiming information as confidential should do so by circling, bracketing, or underlining it and marking it with "CONFIDENTIAL." EPA will disclose information subject to a claim of confidentiality only to the extent permitted by section 14 of TSCA and 40 CFR part 2, subpart B. If a person does not assert a claim of confidentiality for information at the time it is submitted to EPA, EPA may make the information public without further notice to that person.

(j) *Enforcement.* (1) Failure to comply with any provision of this section is a violation of section 15 of the Act (15 U.S.C. 2614).

(2) Failure or refusal to establish and maintain records or to permit access to or copying of records, as required by the Act, is a violation of section 15 of the Act (15 U.S.C. 2614).

(3) Failure or refusal to permit entry or inspection as required by section 11 of the Act (15 U.S.C. 2610) is a violation of section 15 of the Act (15 U.S.C. 2614).

(4) Violators may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation.

(k) *Inspections.* EPA will conduct inspections under section 11 of the Act

## Environmental Protection Agency

## § 750.2

(15 U.S.C. 2610) to ensure compliance with this section.

[55 FR 240, Jan. 3, 1990, as amended at 59 FR 42773, Aug. 19, 1994]

### **PART 750—PROCEDURES FOR RULE- MAKING UNDER SECTION 6 OF THE TOXIC SUBSTANCES CON- TROL ACT**

#### **Subpart A—Procedures for Rulemaking Under Section 6 of the Toxic Sub- stances Control Act**

Sec.

- 750.1 Applicability.
- 750.2 Notice of proposed rulemaking.
- 750.3 Record.
- 750.4 Public comments.
- 750.5 Subpoenas.
- 750.6 Participation in informal hearing.
- 750.7 Conduct of legislative hearing.
- 750.8 Cross-examination.
- 750.9 Final rule.

APPENDIX A TO SUBPART A

#### **Subpart B—Interim Procedural Rules for Manufacturing Exemptions**

- 750.10 Applicability.
- 750.11 Filing of petitions for exemption.
- 750.12 Consolidation of rulemakings.
- 750.13 Notice of proposed rulemaking.
- 750.14 Record.
- 750.15 Public comments.
- 750.16 Confidentiality.
- 750.17 Subpoenas.
- 750.18 Participation in informal hearing.
- 750.19 Conduct of informal hearing.
- 750.20 Cross-examination.
- 750.21 Final rule.

#### **Subpart C—Interim Procedural Rules for Processing and Distribution in Com- merce Exemptions**

- 750.30 Applicability.
- 750.31 Filing of petitions for exemption.
- 750.32 Consolidation of rulemaking.
- 750.33 Notice of proposed rulemaking.
- 750.34 Record.
- 750.35 Public comments.
- 750.36 Confidentiality.
- 750.37 Subpoenas.
- 750.38 Participation in informal hearing.
- 750.39 Conduct of informal hearing.
- 750.40 Cross-examination.
- 750.41 Final rule.

AUTHORITY: 15 U.S.C. 2605.

#### **Subpart A—Procedures for Rule- making Under Section 6 of the Toxic Substances Control Act**

SOURCE: 42 FR 61259, Dec. 2, 1977, unless otherwise noted.

##### **§ 750.1 Applicability.**

This part applies to all rulemakings under authority of section 6 of the Toxic Substances Control Act (TSCA), 15 U.S.C. 2605.

##### **§ 750.2 Notice of proposed rulemaking.**

(a) Each rulemaking becomes subject to this part with the publication of a Notice of Proposed Rulemaking in the FEDERAL REGISTER. A proceeding under section 6 of the Toxic Substances Control Act may begin, as appropriate, with the publication in the FEDERAL REGISTER of a Notice of Proposed Rulemaking, an Advance Notice of Proposed Rulemaking, or notice of other action, such as a formal regulatory investigation designed to lead to issuance of rules within a reasonable time.

(b) Each such notice shall contain:

(1) A draft finding that there is a reasonable basis to conclude that the manufacture, processing, distribution in commerce, use or disposal of the chemical substance(s) or mixture(s) at issue, or any combination of such activities, presents or will present an unreasonable risk of injury to health or the environment.

(2) A Notice of Proposed Rulemaking stating with particularity the reasons for the proposed rule together with a statement why the proposed rule protects adequately against the risk(s) involved using the least burdensome requirements authorized by TSCA.

(3) Either the draft text of the proposed rule (which may include alternative approaches among which a final choice has not yet been made) or a description of the approaches and provisions being considered for inclusion in the rule, or some combination of the above.

(4) Except for rules published under authority of section 6(e), a draft statement with respect to:

(i) The effects of the substance(s) or mixture(s) at issue on health and the



magnitude of the exposure of human beings to such substance(s) or mixture(s);

(ii) The effects of the substance(s) or mixture(s) at issue on the environment and the magnitude of the exposure of the environment to such substance(s) or mixture(s).

(iii) The benefits of the substance(s) or mixture(s) at issue for various uses and the availability of substitutes for such uses; and

(iv) The reasonably ascertainable economic consequences of the rule, after consideration of the effect on the national economy, small business, technological innovation, the environment, and public health.

(v) Major impacts of alternatives to the proposed rule shall also be analyzed.

(5) In cases where the administrator, in his or her discretion, determines that a risk of injury to health or the environment could be eliminated or reduced to a sufficient extent by actions taken under a Federal law (or laws) other than TSCA administered in whole or in part by the Administrator, a finding that it is in the public interest to proceed against such risk under TSCA. Any such finding shall be accompanied by a brief statement discussing:

(i) All relevant aspects of the risk;

(ii) A comparison of the estimated costs of complying with actions taken under TSCA and under such other law (or laws); and

(iii) The relative efficiency of actions under TSCA and under such other law (or laws) to protect against risk of injury.

Two or more or all of the statements required above may be combined in the same narrative for efficiency of exposition as long as each of the required points is discussed. Any statement required by this paragraph may reference other documents which are not published in the FEDERAL REGISTER. All such referenced documents shall be included in the rulemaking record. Either the statements required by this paragraph or the documents they reference shall contain a discussion of the factual, analytical, policy and legal considerations behind the agency decision to issue the proposed rule in the

form chosen. A brief summary of these considerations shall be included in the preamble in any case. All factual materials and each analytical methodology seriously considered shall be fully disclosed. Significant areas of uncertainty known to the Agency under each heading shall be identified, and the manner in which the Agency intends to deal with them shall be specified.

(c) In addition to the material required under paragraph (b) of this section, each notice of proposed rule-making shall contain:

(1) A statement of the time and place at which the informal hearing required by section 6(c)(2)(C) of TSCA shall begin, or, to the extent these are not specified, a statement that they will be specified later in a separate FEDERAL REGISTER notice *Provided*, That FEDERAL REGISTER notice of the date and city at which any informal hearing shall begin shall be given at least 30 days in advance;

(2) A statement identifying the place at which the official record of the rule-making is located, the hours during which it will be open for public inspection, the documents contained in it as of the date the notice of proposed rule-making was issued, and a statement of the approximate times at which additional materials such as public comments, hearing transcripts, and agency studies in progress will be added to the record. If any material other than public comments or material generated by a hearing is added to the record after publication of the notice required by this section, and notice of its future addition was not given at the time of that initial publication, a separate FEDERAL REGISTER notice announcing its addition to the record and inviting comment shall be published;

(3) The due date for public comments, which shall be at least two weeks prior to the informal hearing for main comments and no more than two weeks after the informal hearing for reply comments;

(4) The name, address and office telephone number of the Record and Hearing Clerk for the rulemaking in question; and

## Environmental Protection Agency

## § 750.5

(5) A nonbinding target date for issuing the final rule.

[42 FR 61259, Dec. 1977, as amended at 54 FR 21623, May 19, 1989]

### § 750.3 Record.

(a) No later than the date of proposal of a rule subject to this part, a rule-making record for that rule shall be established. It shall consist of a separate identified filing space containing:

(1) All documents required by § 750.2(b);

(2) All documents cited in the documents required by § 750.2(b);

(3) All public comments timely received;

(4) All public hearing transcripts;

(5) All material received during an informal hearing and accepted for the record of that hearing; and

(6) Any other information which the Administrator considers to be relevant to such rule and which the Administrator identified, on or before the date of the promulgation of the rule, in a notice published in the FEDERAL REGISTER.

All material in the record shall be appropriately indexed. Each record shall be available for public inspection during normal Agency business hours. Appropriate arrangements allowing members of the public to copy record materials that do not risk the permanent loss of such materials shall be made. All material required to be included in the record shall be added to the record as soon as feasible after its receipt by the Agency.

(b) The Record and Hearing Clerk for each rulemaking shall be responsible for Agency compliance with the requirements of paragraph (a) of this section.

### § 750.4 Public comments.

(a) Main comments shall be post-marked or received no later than the time specified in the Notice of Proposed Rulemaking and shall contain all comments on and criticisms of that Notice by the commenting person, based on information which is or reasonably could have been available to that person at the time.

(b) Reply comments shall be post-marked or received no later than two weeks after the close of all informal

hearings on the proposed rule and shall be restricted to comments on:

(1) Other comments;

(2) Material in the hearing record; and

(3) Material which was not and could not reasonably have been available to the commenting party a sufficient time before main comments were due.

(c) Extensions of the time for filing comments may be granted in writing by the Record and Hearing Clerk. Application for an extension shall be made in writing. Comments submitted after the comment period and all extensions of it have expired need not be added to the rulemaking record and need not be considered in decisions concerning the rule. Unless the Notice of Proposed Rulemaking states otherwise, four copies of all comments shall be submitted.

### § 750.5 Subpoenas.

(a) Where necessary, subpoenas requiring the production of documentary material, the attendance of persons at the hearing, or responses to written questions may be issued. Subpoenas may be issued either upon request as provided in paragraph (b) of this section or by EPA on its own motion.

(b) All subpoena requests shall be in writing. Hearing participants may request the issuance of subpoenas as follows:

(1) Subpoenas for the attendance of persons, and for the production of documents or responses to questions at the legislative hearing may be requested at any time up to the deadline for filing main comments.

(2) Subpoenas for production of documents or answers to questions after the legislative hearing may be requested at any time between the beginning of the legislative hearing and the deadline for submitting reply comments.

(c) EPA will rule on all subpoena requests filed under paragraph (b)(1) of this section no later than the beginning of the legislative hearing. Such requests may be granted, denied, or deferred. EPA will rule on all subpoena requests filed under paragraph (b)(2) of this section and all deferred subpoena requests filed under paragraph (b)(1) of

## § 750.6

this section no later than the promulgation of the final rule. Such requests shall be either granted or denied.

### § 750.6 Participation in informal hearing.

(a) Each person or organization desiring to participate in the informal hearing required by section 6(c)(2)(C) of TSCA shall file a written request to so participate with the Record and Hearing Clerk which shall be postmarked or received no later than three weeks prior to the scheduled start of such hearing. The request shall include:

(1) A brief statement of the interest of the person or organization in the proceeding;

(2) A brief outline of the points to be addressed;

(3) An estimate of the time required; and

(4) If the request comes from an organization, a nonbinding list of the persons to take part in the presentation. Organizations are requested to bring with them, to the extent possible, employees with individual expertise in and responsibility for each of the areas to be addressed. No organization not filing main comments in the rulemaking will be allowed to participate at the hearing, unless a waiver of this requirement is granted in writing by the Record and Hearing Clerk or the organization is appearing at the request of EPA or under subpoena.

(b) No later than one week prior to the start of the hearing, the Record and Hearing Clerk shall make a hearing schedule publicly available and mail or deliver it to each of the persons who requested to appear at the hearing. This schedule shall be subject to change during the course of the hearing at the discretion of those presiding over it.

(c) Opening statements should be brief, and restricted either to points that could not have been made in main comments, or to emphasizing points which are made in main comments, but which the participant believes can be more forcefully urged in the hearing context.

### § 750.7 Conduct of legislative hearing.

(a) A panel of EPA employees shall preside at each hearing conducted

## 40 CFR Ch. I (7-1-10 Edition)

under section 6(c)(2)(C) of TSCA. In appropriate cases other Executive Branch employees may also sit with and assist the panel. The membership of the panel may change as different topics arise during the hearing. In general, the panel membership will consist of agency employees with special responsibility for the final rule or special expertise in the topics under discussion. One member of the panel shall be named to chair the proceedings and shall attend throughout the hearing, unless unavoidably prevented by sickness or similar personal circumstances.

(b) The panel may question any individual or group participating in the hearing on any subject relating to the rulemaking. Cross-examination by others will normally not be permitted at this stage. It may be granted in compelling circumstances at the sole discretion of the hearing panel. However, persons in the hearing audience may submit questions in writing for the hearing panel to ask the participants, and the hearing panel may, at their discretion, ask these questions.

(c) Participants in the hearing may submit additional material for the hearing record and shall submit such additional material as the hearing panel may request. All such submissions shall become part of the record of the hearing. A verbatim transcript of the hearing shall be made.

### § 750.8 Cross-examination.

(a) After the close of the legislative hearing conducted under § 750.7, any participant in that hearing may submit a written request for cross-examination. The request shall be received by EPA within one week after a full transcript of the legislative hearing becomes available and shall specify:

(1) The disputed issue(s) of material fact as to which cross-examination is requested. This shall include an explanation of why the questions at issue are "factual", rather than of an analytical or policy nature, the extent to which they are in "dispute" in the light of the record made thus far, and the extent to which and why they can reasonably be considered "material" to the decision on the final rule; and

(2) The person(s) the participant desires to cross-examine, and an estimate

of the time necessary. This shall include a statement by the cross-examination requested can be expected to result in "full and true disclosure" resolving the issue of material fact involved.

(b) Within one week after receipt of all requests for cross-examination under paragraph (a) of this section the hearing panel shall rule on them. The ruling shall be served by the Record and Hearing Clerk on all participants who have requested cross-examination and shall be inserted in the record. Written notice of the ruling shall be given to all persons requesting cross-examination and all persons to be cross-examined. The ruling shall specify:

(1) The issues as to which cross-examination is granted,

(2) The persons to be cross-examined on each issue,

(3) The persons to be allowed to conduct cross-examination, and

(4) Time limits for the examination of each witness by each cross-examiner.

In issuing this ruling, the panel may determine that one or more participants who have requested cross-examination have the same or similar interests and should be required to choose a single representative for purposes of cross-examination. In such a case the order shall simply assign time for cross-examination by that single representative without identifying the representative further. Subpoenas for witnesses may be issued where necessary.

(c) Within one week after the insertion into the record of the ruling under paragraph (b) of this section, the hearing at which the cross-examination will be conducted shall commence. One or more members of the original panel shall preside for the Agency. The panel shall have authority to conduct cross-examination on behalf of any participant, although as a general rule this right will not be exercised. The panel shall also have authority to modify the governing ruling in any respect and to make new rulings on group representation under section 6(c)(3)(C) of TSCA. A verbatim transcript of the hearing shall be made.

(d)(1) No later than the time set for requesting cross-examination, a hearing participant may request that other alternative methods of clarifying the record (such as informal conferences or the submittal of additional information) be used. Such requests may be submitted either in lieu of cross-examination requests, or in conjunction with them.

(2) The panel in passing on a cross-examination request may as a precondition to ruling on its merits require that alternative means of clarifying the record be used whether or not that has been requested under paragraph (d)(1) of this section. In such a case the results of the use of such alternative means shall be made available to the person requesting cross-examination of a one-week comment period, and the panel shall make a final ruling on cross-examination within one week thereafter.

(e) Waivers or extensions of any deadline in this section applicable to persons other than EPA may be granted on the record of the hearing by the person chairing it or in writing by the Record and Hearing Clerk.

#### § 750.9 Final rule.

(a) As soon as feasible after the deadline for submittal of reply comments, the Agency shall issue a final rule. Final versions of the statements required by paragraph (b) of § 750.2 shall be published in the FEDERAL REGISTER together with the final rule. The Agency shall also publish at that time:

(1) A list of all material added to the record (other than public comments and material from the hearing record) which has not previously been listed in a FEDERAL REGISTER document, and

(2) The effective date of the rule.

(b) [Reserved]

#### APPENDIX A TO SUBPART A OF PART 750

To assist in reading the regulations set forth above, this appendix sets forth the principal stages through which rules promulgated under section 6 of TSCA will pass.

The second column gives the relationship that one date bears to another whenever that relationship is specified in the regulations, and cites the governing provision. The third column contains estimates of the time that a typical rulemaking is likely to require to

**§ 750.10**

**40 CFR Ch. I (7-1-10 Edition)**

reach and complete each stage of these proceedings. In drawing up this third column, we have assumed that 60 days will be allowed for the submission of main comments; that the legislative phase of the informal hearing will take two weeks, and that cross-examination will take four days. Since these are only estimates, in any given rulemaking shorter or longer times may actually be required for each of these stages.

| Stage  | Timing in relation to other stages                              | Estimated total time elapsed (days) |
|--|---|-------------------------------------|
| Proposed regulation                              | Sec. 750.2.   |                                     |
| Requests to participate in informal hearing due. | 3 weeks prior to beginning of hearing (§ 750.2(a)).             | 53                                  |
| Main comments due                                | 2 weeks prior to beginning of hearing (§ 750.2(c)(3)).          | 60                                  |
| Begin informal hearing.                          | .....   | 74                                  |
| End legislative hearing.                         | .....   | 88                                  |
| Requests for cross-examination due.              | 1 week after end of legislative hearing (§ 750.8(a)).           | 95                                  |
| Ruling on cross-examination requests.            | 1 week after requests are due (§ 750.8(b)).                     | 102                                 |
| Cross-examination begins.                        | 1 week after ruling on cross-examination requests (§ 750.8(c)). | 109                                 |
| Cross-examination ends; informal hearing ends.   | .....   | 113                                 |
| Reply comments due                               | 2 weeks after end of informal hearing (§ 750.4(b)).             | 127                                 |

**Subpart B—Interim Procedural Rules for Manufacturing Exemptions**

SOURCE: 43 FR 50905, Nov. 1, 1978, unless otherwise noted.

**§ 750.10 Applicability.**

Sections 750.10–750.21 apply to all rulemakings under authority of section 6(e)(3)(B) of the Toxic Substances Control Act (TSCA), 15 U.S.C. 2605(e)(3)(B) with respect to petitions filed pursuant to § 750.11(a) of this part.

**§ 750.11 Filing of petitions for exemption.**

(a) *Who may file.* Any person seeking an exemption from the PCB manufacturing ban imposed by section 6(e)(3)(A) of TSCA may file a petition for exemption. Petitions must be submitted on an individual basis for each manufacturer or individual affected by the 1979 manufacturing ban.

(b) *Where to file.* All petitions pertaining to:

(1) PCB use, which includes storage for use or reuse, manufacture, processing related to manufacture and use, and distribution in commerce related to use or processing for use, must be submitted to: OPPT Document Control Officer (7407T), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001.

(2) PCB disposal, which includes cleanup, storage for disposal, processing related to disposal, distribution in commerce related to disposal or processing for disposal, and decontamination, must be submitted to: Document Control Officer, Office of Resource Conservation and Recovery (5305P), Environmental Protection Agency, 1200 Pennsylvania, NW., Washington, DC 20460-0001.

(c) *Content of petition.* Each petition shall contain the following:

(1) Name, address and telephone number of petitioner.

(2) Description of PCB ban exemption requested, including items to be manufactured and nature of manufacturing process—such as smelting.

(3) Location(s) of manufacturing sites requiring exemption.

(4) Length of time requested for exemption (maximum length of exemption is 1 year).

(5) Amount of PCB chemical substance or PCB mixture (by pounds and/or volume) to be manufactured or used during requested exemption period and the manner of release of PCB's into the environment associated with such manufacture or use.

(6) The basis for the petitioner's contention that under section 6(e)(3)(B)(i) of TSCA "an unreasonable risk of injury to health or environment would not result" from the granting of his petition for exemption.

(7) The basis for the petitioner's contention that he meets the criterion of section 6(e)(3)(B)(ii) of TSCA concerning substitutes for PCB's.

(8) Quantification of the reasonably ascertainable economic consequences of denial of the petition for exemption from the 1979 manufacturing ban and an explanation of the manner of computation.

## Environmental Protection Agency

## § 750.16

(d) *Request for further information.* The Agency reserves the right to request further information as to each petition prior to or after publication of the notice of proposed rulemaking required by § 750.13.

(e) *Renewal requests.* (1) Any petitioner who has been granted an exemption under section 6(e)(3)(B) of TSCA, on or after May 25, 1994, and who seeks to renew that exemption without changing its terms, must submit a letter by certified mail to EPA requesting that the exemption be granted for the following year.

(i) This letter must contain a certification by the petitioner that the type of activities, the procedures for handling the PCBs, the amount of PCBs handled, and any other aspect of the exemption have not changed from the original exemption petition request.

(ii) This letter must be received by EPA at least 6 months prior to the expiration of the existing exemption.

(iii) If a petitioner fails to make a submission or the submission is not timely under this section, the exemption will expire 1 year from the effective date of granting that exemption.

(iv) EPA will address a timely submission of a renewal request by rulemaking and either grant or deny the request.

(2) Any petitioner who has been granted an exemption on or after May 25, 1994, and who seeks to increase the amount of PCBs handled or to change the type of activities, the procedures for handling the PCBs, and any other aspect of their existing exemption must submit a new exemption petition to EPA. The existing exemption activity may continue until the new submission is addressed by rulemaking, provided the activity conforms to the terms of the current exemption approved by EPA, and the petitioner complies with the conditions of paragraph (e)(1) of this section.

(3) Any petitioner who has been granted a TSCA section 6(e)(3)(B) exemption in a rule prior to May 25, 1994, and who seeks to increase the amount of PCBs handled or to change the type of activities, the procedures for handling the PCBs, and any other aspect of their existing exemption must submit a new exemption petition to EPA. The

existing exemption activity may continue until the new submission is addressed by rulemaking, provided the activity conforms to the terms of the original exemption approved by EPA.

[43 FR 50905, Nov. 1, 1978, as amended at 53 FR 12524, Apr. 15, 1988; 59 FR 16998, Apr. 11, 1994; 72 FR 57238, Oct. 9, 2007; 74 FR 30232, June 25, 2009]

### § 750.12 Consolidation of rulemakings.

All petitions received pursuant to § 750.11(a) will be consolidated into one rulemaking with one informal hearing held on all petitions.

### § 750.13 Notice of proposed rulemaking.

Rulemaking for PCB exemptions filed pursuant to § 750.11(a) shall begin with the publication of a notice of proposed rulemaking in the FEDERAL REGISTER. The notice shall state in summary form the required information described in § 750.11(c). Due to time constraints, the notice need not indicate what action EPA proposes to take on the exemption petitions. The notice shall also be subject to § 750.2(c) with the exceptions (1) that the clause “in addition to the material required under paragraph (b)” is eliminated; and (2) that § 750.2(c)(3) is changed to read:

The due date for public comments, which shall be (1) thirty days after publication of the notice of proposed rulemaking for main comments and (2) one week after the close of the informal hearing for reply comments.

[43 FR 50905, Nov. 1, 1978, as amended at 59 FR 16998, Apr. 11, 1994]

### § 750.14 Record.

Section 750.3 shall be applicable with the exception that the words “§ 750.11(c)” are substituted for “§ 750.2(b)” in § 750.3(a)(1) and (2).

[43 FR 50905, Nov. 1, 1978, as amended at 59 FR 16998, Apr. 11, 1994]

### § 750.15 Public comments.

Section 750.4 shall be applicable with the exception that the time period in § 750.4(b) is shortened to 1 week.

### § 750.16 Confidentiality.

The Agency encourages the submission of nonconfidential information by

## § 750.17

petitioners and commenters. The Agency does not wish to have unnecessary restrictions on access to the rule-making record. However, if a petitioner or commenter believes that he can only state his position through the use of information claimed to be confidential, he may submit it. Such information must be separately submitted for the rulemaking record and marked "confidential" by the submitter. For the information claimed to be confidential, the Agency will list only the date and the name and address of the petitioner or commenter in the public file, noting that the petitioner or commenter has requested confidential treatment. The information claimed to be confidential will be placed in a confidential file. A petitioner must also file a nonconfidential petition with a nonconfidential summary of the confidential information to be placed in the public file. Similarly, a commenter must supply a nonconfidential summary of the information claimed to be confidential to be placed in the public file. Any information not marked as confidential will be placed in the public file. Information marked confidential will be treated in accordance with the procedures in part 2, subpart B of this title.

## § 750.17 Subpoenas.

Section 750.5 shall be applicable.

## § 750.18 Participation in informal hearing.

(a) Each person or organization desiring to participate in the informal hearing required by section 6(c)(2)(C) of TSCA shall file a written request to so participate with the record and hearing clerk which shall be received no later than 7 days prior to the scheduled start of the hearing. The hearing shall begin 7 days after the close of the 30-day comment period or as soon thereafter as practicable.

(b) With the exception of the first sentence in § 750.6(a), § 750.6 shall be applicable with the further exception that the time period in § 750.6(b) is shortened to no later than 3 days prior to the start of the hearing.

## 40 CFR Ch. I (7–1–10 Edition)

## § 750.19 Conduct of informal hearing.

Section 750.7 shall be applicable with the addition of the following sentence at the end of § 750.7(c):

Participants shall be allowed to designate testimony from prior EPA informal rule-making hearings concerning PCB's under TSCA. The hearing panel may reject repetitive testimony previously presented at such hearings.

## § 750.20 Cross-examination.

Section 750.8 shall be applicable.

## § 750.21 Final rule.

(a) As soon as feasible after the deadline for submittal of reply comments, the Agency shall issue a final rule. The Agency shall also publish at that time:

(1) A list of all material added to the record (other than public comments and material from the hearing record) which has not previously been listed in a FEDERAL REGISTER document, and

(2) The effective date of the rule.

(b) EPA will grant or deny petitions under section 6(e)(3)(B) of TSCA submitted pursuant to § 750.11. EPA will act on such petitions subsequent to opportunity for an informal hearing pursuant to this rule.

(c) In determining whether to grant an exemption to the PCB ban, the Agency shall apply the two standards enunciated in section 6(e)(3)(B) of TSCA.

[43 FR 50905, Nov. 1, 1978, as amended at 72 FR 57238, Oct. 9, 2007]

## Subpart C—Interim Procedural Rules for Processing and Distribution in Commerce Exemptions

SOURCE: 44 FR 31560, Mar. 31, 1979, unless otherwise noted.

## § 750.30 Applicability.

Sections 750.30–750.41 apply to all rulemakings under authority of section 6(e)(3)(B) of the Toxic Substances Control Act (TSCA), 15 U.S.C. 2605(e)(3)(B) with respect to petitions for PCB processing and distribution in commerce exemptions filed pursuant to § 750.31(a) of this part.

## Environmental Protection Agency

## § 750.31

### § 750.31 Filing of petitions for exemption.

(a) *Who may file.* Any person seeking an exemption from the PCB processing and distribution in commerce prohibitions imposed by section 6(e)(3)(A)(ii) of TSCA may file a petition for exemption. Petitions must be submitted on an individual basis for each processor, distributor, seller or individual affected by the 1979 processing and distribution in commerce prohibitions, except as described in paragraphs (a) (1) through (9) of this section.

(1) *Processing and distribution in commerce of PCB-contaminated transformer dielectric fluid.* Persons who process or distribute in commerce dielectric fluid containing 50 ppm or greater PCB (but less than 500 ppm PCB) for use in PCB-Contaminated Transformers may submit a single consolidated petition on behalf of any number of petitioners. The name and address of each petitioner must be stated in the petition.

(2) *Contaminated substances and mixtures—processing.* Persons who process the same chemical substance or the same mixture containing 50 ppm or greater PCB as an impurity or contaminant may submit a consolidated petition if the chemical substance or mixture is processed for the same use by each person represented by the petition. For example, persons who process a PCB-contaminated pigment into printing inks may combine their petitions into one petition. The name and address of each petitioner must be stated in the petition.

(3) *Contaminated substances and mixtures—distribution in commerce.* Persons who distribute in commerce the same chemical substance or the same mixture containing 50 ppm or greater PCB as an impurity or contaminant may submit a consolidated petition if the chemical substance or mixture is distributed in commerce for a common use. Such a petition is not required to name each person who distributes in commerce the chemical substance or mixture.

(4) *PCB capacitor distribution for purposes of repair.* Persons who distribute in commerce PCB capacitors for servicing (repair) of PCB Equipment may submit a single consolidated petition on behalf of any number of petitioners

engaged in such distribution in commerce for purposes of repair. The name of each petitioner need not be stated in the petition.

(5) *Small quantities for research and development.* Persons who process or distribute in commerce small quantities of PCBs for research and development may submit a single consolidated petition. The name and address of each petitioner must be stated in the petition.

(6) *Microscopy.* Persons who process or distribute in commerce PCBs for use as a mounting medium in microscopy may submit a single consolidated petition on behalf of any number of petitioners. The name and address of each petitioner must be stated in the petition.

(7) *Processing of PCB Articles into PCB Equipment.* A person who processes (incorporates) PCB Articles (such as small PCB Capacitors) into PCB Equipment may submit a petition on behalf of himself and all persons who further process or distribute in commerce PCB Equipment built by the petitioner. For example, a builder of motors who places small PCB Capacitors in the motors may submit a petition on behalf of all persons who process or incorporate motors built by the petitioner into other pieces of PCB Equipment and all those who sell the equipment. Such a petition is not required to identify the persons who distribute in commerce or further process the PCB Equipment. A separate petition must be filed, however, by each processor of PCB Articles into PCB Equipment.

(8) *Processing of PCB Equipment into other PCB Equipment.* A person who processes (incorporates) PCB Equipment into other PCB Equipment may submit a petition on behalf of himself and all persons who further process or distribute in commerce PCB Equipment built by the petitioner. Such a petition is not required to identify the persons who distribute in commerce or further process the PCB Equipment. If a petition has been filed under paragraph (a)(7) of this section by the builder of the original PCB Equipment, no other petition is required.



(9) *Distribution of PCB Equipment.* Distributors in commerce of PCB Equipment may submit a consolidated petition on behalf of persons who distribute in commerce PCB Equipment of one type (such as air conditioners). The petition is not required to name the persons who distribute in commerce the affected PCB Equipment.

(b) *Where to file.* All petitions pertaining to:

(1) PCB use, which includes storage for use or reuse, manufacture, processing related to manufacture and use, and distribution in commerce related to use or processing for use, must be submitted to: OPPT Document Control Officer (7407T), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001.

(2) PCB disposal, which includes cleanup, storage for disposal, processing related to disposal, distribution in commerce related to disposal or processing for disposal, and decontamination, must be submitted to: Document Control Officer, Office of Resource Conservation and Recovery (5305P), Environmental Protection Agency, 1200 Pennsylvania Avenue, NW., Washington, DC 20460-0001.

(c) *Content of petition.* Each petition must contain the following:

(1) Name, address and telephone number of petitioner. See also paragraphs (a) (1) through (9) of this section for additional identification requirements applicable to certain consolidated petitions.

(2) Description of PCB processing or distribution in commerce exemption requested, including a description of the chemical substances, mixtures or items to be processed or distributed in commerce and, if processing is involved, the nature of the processing.

(3) For processing petitions, location(s) of sites requiring exemption.

(4) Length of time requested for exemption (maximum length of exemption is one year).

(5) Estimated amount of PCBs (by pound and/or volume) to be processed, distributed in commerce, or used during requested exemption period and the manner of release of PCBs into the environment associated with such processing, distribution in commerce, or use. Where the PCB concentration is

less than 500 ppm, both the total liquid volume and the total PCB volume must be provided.

(6) The basis for the petitioner's contention that under section 6(e)(3)(B)(i) of TSCA "an unreasonable risk of injury to health or environment would not result" from the granting of the petition for exemption.

(7) The basis for the petitioner's contention that under section 6(e)(3)(B)(ii) "good faith efforts have been made to develop a chemical substance which does not present an unreasonable risk of injury to health or the environment and which may be substituted for" the PCB.

(8) Quantification of the reasonably ascertainable economic consequences of denying the petition for exemption and an explanation of the manner of computation.

(9) In addition to the information in paragraphs (c)(1) through (c)(8) of this section, certain petitions must contain additional information as follows:

(i) Persons who process or distribute in commerce dielectric fluids containing 50 ppm or greater PCB for use in PCB Transformers, railroad transformers, or PCB electromagnets must also state the expected number of PCB Transformers, railroad transformers, or PCB electromagnets to be serviced under the exemption. In addition, a person must identify all the facilities which he owns or operates where he services PCB transformers, railroad transformers, or PCB electromagnets.

(ii) Persons filing petitions under paragraph (a)(1) of this section (Processing and Distribution in Commerce of PCB-Contaminated Transformer Dielectric Fluid) must also provide the expected number of PCB-Contaminated Transformers to be serviced under the requested exemption and the expected method of disposal of waste dielectric fluid. In addition, a person must identify all the facilities which he owns or operates where he services PCB-Contaminated Transformers. This information, as well as the information required by paragraphs (c)(1), (c)(3), and (c)(5) of this section, must be provided for each person represented by the petition. All other information may be provided on a group basis.

## Environmental Protection Agency

## § 750.31

(iii) Persons filing petitions under paragraphs (a)(2) (Contaminated Substances and Mixtures-Processing) and (a)(3) (Contaminated Substances and Mixtures-Distribution in Commerce) must also provide a justification for the class grouping selected and a description of the uses and the human and environmental exposure associated with each use of the PCB-contaminated chemical substance or mixture for which an exemption is sought. Information may be provided on a group basis, except that the information required by paragraphs (c)(1), (c)(3) and (c)(5) of this section, must be provided for each person represented by a petition under paragraph (a)(2) of this section.

(iv) Persons filing petitions under paragraph (a)(4) of this section (PCB Capacitor Distribution for Purposes of Repair) must also provide an estimate of the expected total number of PCB Capacitors to be distributed in commerce under the requested exemption. All information may be provided on a group basis.

(v) Persons filing petitions under paragraphs (a) (7) and (8) of this section (Processing of PCB Articles into PCB Equipment and Processing of PCB Equipment into Other PCB Equipment) must provide a description of each type of PCB Equipment (including the amount of PCBs by poundage and/or volume in the PCB Equipment) to be processed and/or distributed in commerce under the exemption, the number of each type of equipment expected to be processed and/or distributed in commerce, and the approximate number of distributors or further processors covered by the petition. All information may be provided on a group basis. However, in the case of a petition under paragraph (a)(7) of this section, the processor of PCB Articles into PCB Equipment must be identified in the petition. In the case of a petition under paragraph (a)(8) of this section, the processor of PCB Equipment who files the petition must be identified.

(vi) Persons filing petitions under paragraph (a)(9) of this section (Distribution of PCB Equipment) must provide a description of each type of PCB Equipment (including the amount of PCBs by poundage and/or volume in the

PCB Equipment) to be distributed in commerce under the exemption, the number of each type of equipment to be distributed in commerce, and the approximate number of distributors covered by the petition. All information may be provided on a group basis.

(vii) Persons filing petitions under paragraphs (a) (5) and (6) of this section must provide the information required by paragraphs (c) (1) through (8) of this section for each petitioner named in the petition.

(d) EPA reserves the right to request further information as to each petition where necessary to determine whether the petition meets the statutory tests of section 6(e)(3)(B) of TSCA prior to or after publication of the notice of proposed rulemaking required by § 750.33 of these rules.

(e) *Renewal requests.* (1) Any petitioner who has been granted an exemption under 40 CFR 761.80, except paragraph (g) of 40 CFR 761.80, on or after May 25, 1994, and who seeks to renew that exemption without changing its terms, must submit a letter by certified mail to EPA requesting that the exemption be granted for the following year.

(i) This letter must contain a certification by the petitioner that the type of activities, the procedures for handling the PCBs, the amount of PCBs handled, and any other aspect of the exemption have not changed from the original exemption petition request.

(ii) This letter must be received by EPA at least 6 months prior to the expiration of the existing exemption.

(iii) If a petitioner fails to make a submission or the submission is not timely under this section, the exemption will expire 1 year from the effective date of granting that exemption.

(iv) EPA will address a timely submission of a renewal request by rulemaking and either grant or deny the request.

(2) Any petitioner who has been granted an exemption on or after May 25, 1994, and who seeks to increase the amount of PCBs handled or to change the type of activities, the procedures for handling the PCBs, and any other aspect of their existing exemption must submit a new exemption petition

## § 750.32

## 40 CFR Ch. I (7–1–10 Edition)

to EPA. The existing exemption activity may continue until the new submission is addressed by rulemaking, provided the activity conforms to the terms of the current exemption approved by EPA, and the petitioner complies with the conditions of paragraph (e)(1) of this section.

(3) Any petitioner who has been granted a TSCA section 6(e)(3)(B) exemption in a rule prior to May 25, 1994, and who seeks to increase the amount of PCBs handled or to change the type of activities, the procedures for handling the PCBs, and any other aspect of their existing exemption must submit a new exemption petition to EPA. The existing exemption activity may continue until the new submission is addressed by rulemaking, provided the activity conforms to the terms of the original exemption approved by EPA.

[44 FR 31560, Mar. 31, 1979, as amended at 53 FR 12524, Apr. 15, 1988; 59 FR 16998, Apr. 11, 1994; 63 FR 35436, June 29, 1998; 72 FR 57238, Oct. 9, 2007; 74 FR 30232, June 25, 2009]

### § 750.32 Consolidation of rulemaking.

All petitions received pursuant to § 750.31(a) will be consolidated into one rulemaking with one informal hearing held on all petitions.

### § 750.33 Notice of proposed rulemaking.

Rulemaking for PCB processing and distribution in commerce exemptions filed pursuant to § 750.31(a) will begin with the publication of a Notice of Proposed Rulemaking in the FEDERAL REGISTER. Each notice will contain:

(a) A summary of the information required in § 750.31(d);

(b) A statement of the time and place at which the informal hearing required by section 6(c)(2)(C) of TSCA shall begin, or, to the extent these are not specified, a statement that they will be specified later in a separate FEDERAL REGISTER notice provided that FEDERAL REGISTER notice of the date and city at which any informal hearing shall begin will be given at least 30 days in advance;

(c) A statement identifying the place at which the official record of the rulemaking is located, the hours during which it will be open for public inspection, the documents contained in it as

of the date the Notice of Proposed Rulemaking was issued, and a statement of the approximate times at which additional materials such as public comments, hearing transcripts, and Agency studies in progress will be added to the record. If any material other than public comments or material generated by a hearing is added to the record after publication of the notice required by this action, and notice of its future addition was not given at the time of that initial publication, a separate FEDERAL REGISTER notice announcing its addition to the record and inviting comment will be published;

(d) The due date for public comments, which will be (1) 30 days after publication of the notice of proposed rulemaking for main comments and (2) one week after the informal hearing for reply comments;

(e) The name, address, and office telephone number of the Record Clerk and the Hearing Clerk for the rulemaking in question; and

(f) A nonbinding target date for issuing the final rule.

### § 750.34 Record.

(a) No later than the date of proposal of a rule subject to this subpart, a rulemaking record for that rule will be established. It will consist of a separate identified filing space containing:

(1) All documents required by § 750.31(d);

(2) All public comments timely received;

(3) All public hearing transcripts;

(4) All material received during an informal hearing and accepted for the record of that hearing; and

(5) Any other information that EPA considers to be relevant to such rule and that EPA identified, on or before the date of the promulgation of the rule, in a notice published in the FEDERAL REGISTER.

(b) All material in the record will be appropriately indexed. Each record will be available for public inspection during normal EPA business hours. Appropriate arrangements allowing members of the public to copy record materials that do not risk the permanent loss of such materials will be made. All material required to be included in the record will be added to the record as

## Environmental Protection Agency

## § 750.37

soon as feasible after its receipt by EPA.

(c) The Record Clerk for each rule-making will be responsible for EPA compliance with the requirements of paragraph (a) of this section.

[44 FR 31560, Mar. 31, 1979, as amended at 72 FR 57238, Oct. 9, 2007]

### § 750.35 Public comments.

(a) Main comments must be post-marked or received no later than the time specified in the Notice of Proposed Rulemaking and must contain all comments on and criticisms of that Notice by the commenting person, based on information which is or reasonably could have been available to that person at the time.

(b) Reply comments must be post-marked or received no later than one week after the close of all informal hearings on the proposed rule and must be restricted to comments on:

- (1) Other comments;
- (2) Material in the hearing record; and
- (3) Material which was not and could not reasonably have been available to the commenting party a sufficient time before main comments were due.

(c) Extensions of the time for filing comments may be granted in writing by the Hearing Chairman. Application for an extension must be made in writing. Comments submitted after the comment period and all extensions of it have expired need not be added to the rulemaking record and need not be considered in decisions concerning the rule.

(d) Unless the Notice of Proposed Rulemaking states otherwise, four copies of all comments must be submitted.

### § 750.36 Confidentiality.

EPA encourages the submission of non-confidential information by petitioners and commentors. EPA does not wish to have unnecessary restrictions on access to the rulemaking record. However, if a petitioner or commentor believes that he can only state his position through the use of information claimed to be confidential, he may submit it. Such information must be separately submitted for the rulemaking record and marked "confidential" by the submitter. For the information

claimed to be confidential, EPA will list only the date and the name and address of the petitioner or commentor in the public file, noting that the petitioner or commentor has requested confidential treatment. The information claimed to be confidential will be placed in a confidential file. A petitioner must also file a non-confidential petition with a non-confidential summary of the confidential information to be placed in the public file. Similarly, a commentor must supply a non-confidential summary of the information claimed to be confidential to be placed in the public file. Any information not marked as confidential will be placed in the public file. Information marked confidential will be treated in accordance with the procedures in part 2, subpart B of this title.

### § 750.37 Subpoenas.

(a) Where necessary, subpoenas requiring the production of documentary material, the attendance of persons at the hearing, or responses to written questions may be issued. Subpoenas may be issued either upon request as provided in paragraph (b) of this section or by EPA on its own motion.

(b) All subpoena requests must be in writing. Hearing participants may request the issuance of subpoenas as follows:

(1) Subpoenas for the attendance of persons or for the production of documents or responses to questions at the legislative hearing may be requested at any time up to the deadline for filing main comments.

(2) Subpoenas for production of documents or answers to questions after the legislative hearing may be requested at any time between the beginning of the legislative hearing and the deadline for submitting reply comments.

(c) EPA will rule on all subpoena requests filed under paragraph (b)(1) of this section no later than the beginning of the informal hearing. Such requests may be granted, denied, or deferred. EPA will rule on all subpoena requests filed under paragraph (b)(2) of this section and all deferred subpoena requests filed under paragraph (b)(1) of this section no later than the promulgation of the final rule. Such requests will be either granted or denied.

**§ 750.38 Participation in informal hearing.**

(a) Each person or organization desiring to participate in the informal hearing required by section 6(c)(2)(C) of TSCA must file a written request to participate with the Hearing Clerk. This request must be received no later than seven days prior to the scheduled start of the hearing. The hearing will begin seven days after the close of the thirty day comment period or as soon thereafter as practicable. The request must include:

(1) A brief statement of the interest of the person or organization in the proceeding;

(2) A brief outline of the points to be addressed;

(3) An estimate of the time required; and

(4) If the request comes from an organization, a nonbinding list of the persons to take part in the presentation. Organizations are requested to bring with them, to the extent possible, employees with individual expertise in and responsibility for each of the areas to be addressed. No organization not filing main comments in the rulemaking will be allowed to participate at the hearing, unless a waiver of this requirement is granted in writing by the Hearing Chairman or the organization is appearing at the request of EPA or under subpoena.

(b) No later than three days prior to the start of the hearing, the Hearing Clerk will make a hearing schedule publicly available and mail or deliver it to each of the persons who requested to appear at the hearing. This schedule will be subject to change during the course of the hearing at the discretion of those presiding over it.

(c) Opening statements should be brief, and restricted either to points that could not have been made in main comments or to emphasizing points which are made in main comments, but which the participant believes can be more forcefully urged in the hearing context.

**§ 750.39 Conduct of informal hearing.**

(a) A panel of EPA employees shall preside at each hearing conducted under section 6(c)(2)(C) of TSCA. In appropriate cases, other Executive

Branch employees may also sit with and assist the panel. The membership of the panel may change as different topics arise during the hearing. In general, the panel membership will consist of EPA employees with special responsibility for the final rule or special expertise in the topics under discussion. One member of the panel will be named to chair the proceedings and will attend throughout the hearing, unless unavoidably prevented by sickness or similar personal circumstances.

(b) The panel may question any individual or group participating in the hearing on any subject relating to the rulemaking. Cross-examination by others will normally not be permitted at this stage. It may be granted in compelling circumstances at the sole discretion of the hearing panel. However, persons in the hearing audience may submit questions in writing for the hearing panel to ask the participants, and the hearing panel may, at their discretion, ask these questions.

(c) Participants in the hearing may submit additional material for the hearing record and shall submit such additional material as the hearing panel may request. All such submissions will become part of the record of the hearing. A verbatim transcript of the hearing shall be made. Participants will be allowed to designate testimony from prior EPA informal rulemaking hearings concerning PCBs under TSCA. The hearing panel may reject repetitive testimony previously presented at such hearings.

**§ 750.40 Cross-examination.**

(a) After the close of the informal hearing conducted under § 750.39, any participant in that hearing may submit a written request for cross-examination. The request must be received by EPA within one week after a full transcript of the informal hearing becomes available and must specify:

(1) The disputed issue(s) of material fact as to which cross-examination is requested. This must include an explanation of why the questions at issue are "factual", rather than of an analytical or policy nature, the extent to which they are in "dispute" in the light of the record made thus far, and the extent to which and why they can

## Environmental Protection Agency

## § 750.41

reasonably be considered “material” to the decision on the final rule; and

(2) The person(s) the participant desires to cross-examine, and an estimate of the time necessary. This must include a statement as to how the cross-examination requested can be expected to result in “full and true disclosure” resolving the issue of material fact involved.

(b) Within one week after receipt of all requests for cross-examination under paragraph (a), the hearing panel will rule on them. The ruling will be served by the Hearing Clerk on all participants who have requested cross-examination and will be inserted in the record. Written notice of the ruling will be given to all persons requesting cross-examination and all persons to be cross-examined. The ruling will specify:

(1) The issues as to which cross-examination is granted;

(2) The persons to be cross-examined on each issue;

(3) The persons to be allowed to conduct cross-examination; and

(4) Time limits for the examination of each witness by each cross-examiner.

(c) In issuing this ruling, the panel may determine that one or more participants who have requested cross-examination have the same or similar interests and should be required to choose a single representative for purposes of cross-examination by that single representative without identifying the representative further. Subpoenas for witnesses may be issued where necessary.

(d) Within one week after the insertion into the record of the ruling under paragraph (b) of this section, the hearing at which the cross-examination will be conducted will begin. One or more members of the original panel will preside for EPA. The panel will have authority to conduct cross-examination on behalf of any participant, although as a general rule this right will not be exercised. The panel will also have authority to modify the governing ruling in any respect and to make new rulings on group representation under section 6(c)(3)(C) of TSCA. A verbatim transcript of the hearing will be made.

(e)(1) No later than the time set for requesting cross-examination, a hearing participant may request that other alternative methods of clarifying the record (such as informal conferences or the submittal of additional information) be used. Such requests may be submitted either in lieu of cross-examination requests, or in conjunction with them.

(2) The panel in passing on a cross-examination request may, as a precondition to ruling on its merits, require that alternative means of clarifying the record be used whether or not that has been requested under paragraph (e)(1) of this section. In such a case, the results of the use of such alternative means will be made available to the person requesting cross-examination for a one-week comment period, and the panel will make a final ruling on cross-examination within one week thereafter.

(f) Waivers or extensions of any deadline in this section applicable to persons other than EPA may be granted on the record of the hearing by the person chairing it or in writing by the Hearing Chairman.

### § 750.41 Final rule.

(a) As soon as feasible after the deadline for submittal of reply comments, EPA will issue a final rule. EPA will also publish at that time:

(1) A list of all material added to the record (other than public comments and material from the hearing record) which has not previously been listed in a FEDERAL REGISTER document, and

(2) The effective date of the rule.

(b) EPA will grant or deny petitions under section 6(e)(3)(B) of TSCA submitted pursuant to § 750.31. EPA will act on such petitions subsequent to opportunity for an informal hearing pursuant to this rule.

(c) In determining whether to grant an exemption to the PCB ban, EPA will apply the two standards enunciated in section 6(e)(3)(B) of TSCA.

[44 FR 31560, Mar. 31, 1979, as amended at 72 FR 57238, Oct. 9, 2007]

**PART 761—POLYCHLORINATED BIPHENYLS (PCBs) MANUFACTURING, PROCESSING, DISTRIBUTION IN COMMERCE, AND USE PROHIBITIONS**

**Subpart A—General**

Sec.

- 761.1 Applicability.
- 761.2 PCB concentration assumptions for use.
- 761.3 Definitions.
- 761.19 References.

**Subpart B—Manufacturing, Processing, Distribution in Commerce, and Use of PCBs and PCB Items**

- 761.20 Prohibitions and exceptions.
- 761.30 Authorizations.
- 761.35 Storage for reuse.

**Subpart C—Marking of PCBs and PCB Items**

- 761.40 Marking requirements.
- 761.45 Marking formats.

**Subpart D—Storage and Disposal**

- 761.50 Applicability.
- 761.60 Disposal requirements.
- 761.61 PCB remediation waste.
- 761.62 Disposal of PCB bulk product waste.
- 761.63 PCB household waste storage and disposal.
- 761.64 Disposal of wastes generated as a result of research and development activities authorized under § 761.30(j) and chemical analysis of PCBs.
- 761.65 Storage for disposal.
- 761.70 Incineration.
- 761.71 High efficiency boilers.
- 761.72 Scrap metal recovery ovens and smelters.
- 761.75 Chemical waste landfills.
- 761.77 Coordinated approval.
- 761.79 Decontamination standards and procedures.

**Subpart E—Exemptions**

- 761.80 Manufacturing, processing and distribution in commerce exemptions.

**Subpart F—Transboundary Shipments of PCBs for Disposal**

- 761.91 Applicability.
- 761.93 Import for disposal.
- 761.97 Export for disposal.
- 761.99 Other transboundary shipments.

**Subpart G—PCB Spill Cleanup Policy**

- 761.120 Scope.

- 761.123 Definitions.
- 761.125 Requirements for PCB spill cleanup.
- 761.130 Sampling requirements.
- 761.135 Effect of compliance with this policy and enforcement.

**Subparts H–I [Reserved]**

**Subpart J—General Records and Reports**

- 761.180 Records and monitoring.
- 761.185 Certification program and retention of records by importers and persons generating PCBs in excluded manufacturing processes.
- 761.187 Reporting importers and by persons generating PCBs in excluded manufacturing processes.
- 761.193 Maintenance of monitoring records by persons who import, manufacture, process, distribute in commerce, or use chemicals containing inadvertently generated PCBs.

**Subpart K—PCB Waste Disposal Records and Reports**

- 761.202 EPA identification numbers.
- 761.205 Notification of PCB waste activity (EPA Form 7710-53).
- 761.207 The manifest—general requirements.
- 761.208 Use of the manifest.
- 761.209 Retention of manifest records.
- 761.210 Manifest discrepancies.
- 761.211 Unmanifested waste report.
- 761.215 Exception reporting.
- 761.218 Certificate of disposal.

**Subpart L [Reserved]**

**Subpart M—Determining a PCB Concentration for Purposes of Abandonment or Disposal of Natural Gas Pipeline: Selecting Sample Sites, Collecting Surface Samples, and Analyzing Standard PCB Wipe Samples**

- 761.240 Scope and definitions.
- 761.243 Standard wipe sample method and size.
- 761.247 Sample site selection for pipe segment removal.
- 761.250 Sample site selection for pipeline section abandonment.
- 761.253 Chemical analysis.
- 761.257 Determining the regulatory status of sampled pipe.

**Subpart N—Cleanup Site Characterization Sampling for PCB Remediation Waste in Accordance with § 761.61(a)(2)**

- 761.260 Applicability.
- 761.265 Sampling bulk PCB remediation waste and porous surfaces.
- 761.267 Sampling non-porous surfaces.

## Environmental Protection Agency

Pt. 761

761.269 Sampling liquid PCB remediation waste.

761.272 Chemical extraction and analysis of samples.

761.274 Reporting PCB concentrations in samples.

### **Subpart O—Sampling To Verify Completion of Self-Implementing Cleanup and On-Site Disposal of Bulk PCB Remediation Waste and Porous Surfaces in Accordance with § 761.61(a)(6)**

761.280 Application and scope.

761.283 Determination of the number of samples to collect and sample collection locations.

761.286 Sample size and procedure for collecting a sample.

761.289 Compositing samples.

761.292 Chemical extraction and analysis of individual samples and composite samples.

761.295 Reporting and recordkeeping of the PCB concentrations in samples.

761.298 Decisions based on PCB concentration measurements resulting from sampling.

### **Subpart P—Sampling Non-Porous Surfaces for Measurement-Based Use, Reuse, and On-Site or Off-Site Disposal Under § 761.61(a)(6) and Determination Under § 761.79(b)(3)**

761.300 Applicability.

761.302 Proportion of the total surface area to sample.

761.304 Determining sample location.

761.306 Sampling 1 meter square surfaces by random selection of halves.

761.308 Sample selection by random number generation on any two-dimensional square grid.

761.310 Collecting the sample.

761.312 Compositing of samples.

761.314 Chemical analysis of standard wipe test samples.

761.316 Interpreting PCB concentration measurements resulting from this sampling scheme.

### **Subpart Q—Self-Implementing Alternative Extraction and Chemical Analysis Procedures for Non-liquid PCB Remediation Waste Samples**

761.320 Applicability.

761.323 Sample preparation.

761.326 Conducting the comparison study.

### **Subpart R—Sampling Non-Liquid, Non-Metal PCB Bulk Product Waste for Purposes of Characterization for PCB Disposal in Accordance With § 761.62, and Sampling PCB Remediation Waste Destined for Off-Site Disposal, in Accordance With § 761.61**

761.340 Applicability.

761.345 Form of the waste to be sampled.

761.346 Three levels of sampling.

761.347 First level sampling—waste from existing piles.

761.348 Contemporaneous sampling.

761.350 Subsampling from composite samples.

761.353 Second level of sample selection.

761.355 Third level of sample selection.

761.356 Conducting a leach test.

761.357 Reporting the results of the procedure used to simulate leachate generation.

761.358 Determining the PCB concentration of samples of waste.

761.359 Reporting the PCB concentrations in samples.

### **Subpart S—Double Wash/Rinse Method for Decontaminating Non-Porous Surfaces**

761.360 Background.

761.363 Applicability.

761.366 Cleanup equipment.

761.369 Pre-cleaning the surface.

761.372 Specific requirements for relatively clean surfaces.

761.375 Specific requirements for surfaces coated or covered with dust, dirt, grime, grease, or another absorbent material.

761.378 Decontamination, reuse, and disposal of solvents, cleaners, and equipment.

### **Subpart T—Comparison Study for Validating a New Performance-Based Decontamination Solvent Under § 761.79(d)(4)**

761.380 Background.

761.383 Applicability.

761.386 Required experimental conditions for the validation study and subsequent use during decontamination.

761.389 Testing parameter requirements.

761.392 Preparing validation study samples.

761.395 A validation study.

761.398 Reporting and recordkeeping.

AUTHORITY: 15 U.S.C. 2605, 2607, 2611, 2614, and 2616.



**Subpart A—General****§ 761.1 Applicability.**

(a) This part establishes prohibitions of, and requirements for, the manufacture, processing, distribution in commerce, use, disposal, storage, and marking of PCBs and PCB Items.

(b)(1) This part applies to all persons who manufacture, process, distribute in commerce, use, or dispose of PCBs or PCB Items. Substances that are regulated by this part include, but are not limited to: dielectric fluids; solvents; oils; waste oils; heat transfer fluids; hydraulic fluids; paints or coatings; sludges; slurries; sediments; dredge spoils; soils; materials containing PCBs as a result of spills; and other chemical substances or combinations of substances, including impurities and by-products and any byproduct, intermediate, or impurity manufactured at any point in a process.

(2) Unless otherwise noted, PCB concentrations shall be determined on a weight-per-weight basis (e.g., milligrams per kilogram), or for liquids, on a weight-per-volume basis (e.g., milligrams per liter) if the density of the liquid is also reported. Unless otherwise provided, PCBs are quantified based on the formulation of PCBs present in the material analyzed. For example, measure Aroclor™ 1242 PCBs based on a comparison with Aroclor™ 1242 standards. Measure individual congener PCBs based on a comparison with individual PCB congener standards.

(3) Most provisions in this part apply only if PCBs are present in concentrations above a specified level. Provisions that apply to PCBs at concentrations of < 50 ppm apply also to contaminated surfaces at PCB concentrations of  $\leq 10 \mu\text{g}/100 \text{ cm}^2$ . Provisions that apply to PCBs at concentrations of  $\geq 50$  to < 500 ppm apply also to contaminated surfaces at PCB concentrations of  $> 10/100 \text{ cm}^2$  to  $< 100 \mu\text{g}/100 \text{ cm}^2$ . Provisions that apply to PCBs at concentrations of  $\geq 500$  ppm apply also to contaminated surfaces at PCB concentrations of  $\geq 100 \mu\text{g}/100 \text{ cm}^2$ .

(4) PCBs can be found in liquid, non-liquid and multi-phasic (combinations of liquid and non-liquid) forms. A person should use the following criteria to determine PCB concentrations to de-

termine which provisions of this part apply to such PCBs.

(i) Any person determining PCB concentrations for non-liquid PCBs must do so on a dry weight basis.

(ii) Any person determining PCB concentrations for liquid PCBs must do so on a wet weight basis. Liquid PCBs containing more than 0.5 percent by weight non-dissolved material shall be analyzed as multi-phasic non-liquid/liquid mixtures.

(iii) Any person determining the PCB concentration of samples containing PCBs and non-dissolved non-liquid materials  $\geq 0.5$  percent, must separate the non-dissolved materials into non-liquid PCBs and liquid PCBs. For multi-phasic non-liquid/liquid or liquid/liquid mixtures, the phases shall be separated before chemical analysis. Following phase separation, the PCB concentration in each non-liquid phase shall be determined on a dry weight basis and the PCB concentration in each liquid phase shall be determined separately on a wet weight basis.

(iv) Any person disposing of multi-phasic non-liquid/liquid or liquid/liquid mixtures must use the PCB disposal requirements that apply to the individual phase with the highest PCB concentration except where otherwise noted. Alternatively, phases may be separated and disposed of using the PCB disposal requirements that apply to each separated, single-phase material.

(5) No person may avoid any provision specifying a PCB concentration by diluting the PCBs, unless otherwise specifically provided.

(6) Unless otherwise specified, references to weights or volumes of PCBs in this part apply to the total weight or total volume of the material (oil, soil, debris, etc.) that contains regulated concentrations of PCBs, not the calculated weight or volume of only the PCB molecules contained in the material.

(c) Definitions of the terms used in these regulations are in subpart A. The basic requirements applicable to disposal and marking of PCBs and PCB Items are set forth in subpart D—Disposal of PCBs and PCB Items and in subpart C—Marking of PCBs and PCB Items. Prohibitions applicable to PCB

## Environmental Protection Agency

## §761.2

activities are set forth in subpart B—Manufacture, Processing, Distribution in Commerce, and Use of PCBs and PCB Items. Subpart B also includes authorizations from the prohibitions. Subparts C and D set forth the specific requirements for disposal and marking of PCBs and PCB Items.

(d) Section 15 of the Toxic Substances Control Act (TSCA) states that failure to comply with these regulations is unlawful. Section 16 imposes liability for civil penalties upon any person who violates these regulations, and the Administrator can establish appropriate remedies for any violations subject to any limitations included in section 16 of TSCA. Section 16 also subjects a person to criminal prosecution for a violation which is knowing or willful. In addition, section 17 authorizes Federal district courts to enjoin activities prohibited by these regulations, compel the taking of actions required by these regulations, and issue orders to seize PCBs and PCB Items manufactured, processed or distributed in violation of these regulations.

(e) These regulations do not preempt other more stringent Federal statutes and regulations.

(f) Unless and until superseded by any new more stringent regulations issued under EPA authorities, or any permits or any pretreatment requirements issued by EPA, a state or local government that affect release of PCBs to any particular medium:

(1) Persons who inadvertently manufacture or import PCBs generated as unintentional impurities in excluded manufacturing processes, as defined in §761.3, are exempt from the requirements of subpart B of this part, provided that such persons comply with subpart J of this part, as applicable.

(2) Persons who process, distribute in commerce, or use products containing PCBs generated in excluded manufacturing processes defined in §761.3 are exempt from the requirements of subpart B provided that such persons comply with subpart J of this part, as applicable.

(3) Persons who process, distribute in commerce, or use products containing recycled PCBs defined in §761.3, are exempt from the requirements of subpart B of this part, provided that such per-

sons comply with subpart J of this part, as applicable.

(4) Except as provided in §761.20 (d) and (e), persons who process, distribute in commerce, or use products containing excluded PCB products as defined in §761.3, are exempt from the requirements of subpart B of this part.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[44 FR 31542, May 31, 1979, as amended at 49 FR 28189, July 10, 1984; 53 FR 24220, June 27, 1988; 63 FR 35436, June 29, 1998; 64 FR 33759, June 24, 1999]

### §761.2 PCB concentration assumptions for use.

(a)(1) Any person may assume that transformers with < 3 pounds (1.36 kilograms (kgs)) of fluid, circuit breakers, reclosers, oil-filled cable, and rectifiers whose PCB concentration is not established contain PCBs at < 50 ppm.

(2) Any person must assume that mineral oil-filled electrical equipment that was manufactured before July 2, 1979, and whose PCB concentration is not established is PCB-Contaminated Electrical Equipment (i.e., contains ≥50 ppm PCB, but < 500 ppm PCB). All pole-top and pad-mounted distribution transformers manufactured before July 2, 1979, must be assumed to be mineral-oil filled. Any person may assume that electrical equipment manufactured after July 2, 1979, is non-PCB (i.e., < 50 ppm PCBs). If the date of manufacture of mineral oil-filled electrical equipment is unknown, any person must assume it to be PCB-Contaminated.

(3) Any person must assume that a transformer manufactured prior to July 2, 1979, that contains 1.36 kg (3 pounds) or more of fluid other than mineral oil and whose PCB concentration is not established, is a PCB Transformer (i.e., ≥ 500 ppm). If the date of manufacture and the type of dielectric fluid are unknown, any person must assume the transformer to be a PCB Transformer.

(4) Any person must assume that a capacitor manufactured prior to July 2, 1979, whose PCB concentration is not established contains ≥500 ppm PCBs. Any person may assume that a capacitor manufactured after July 2, 1979, is non-PCB (i.e., < 50 ppm PCBs). If the date of manufacture is unknown, any

### §761.3

### 40 CFR Ch. I (7-1-10 Edition)

person must assume the capacitor contains  $\geq 500$  ppm PCBs. Any person may assume that a capacitor marked at the time of manufacture with the statement "No PCBs" in accordance with §761.40(g) is non-PCB.

(b) PCB concentration may be established by:

(1) Testing the equipment; or

(2)(i) A permanent label, mark, or other documentation from the manufacturer of the equipment indicating its PCB concentration at the time of manufacture; and

(ii) Service records or other documentation indicating the PCB concentration of all fluids used in servicing the equipment since it was first manufactured.

[63 FR 35436, June 29, 1998, as amended at 64 FR 33759, June 24, 1999]

#### §761.3 Definitions.

For the purpose of this part:

*Administrator* means the Administrator of the Environmental Protection Agency, or any employee of the Agency to whom the Administrator may either herein or by order delegate his authority to carry out his functions, or any person who shall by operation of law be authorized to carry out such functions.

*Agency* means the United States Environmental Protection Agency.

*Air compressor system* means air compressors, piping, receiver tanks, volume tanks and bottles, dryers, airlines, and related appurtenances.

*Annual document log* means the detailed information maintained at the facility on the PCB waste handling at the facility.

*Annual report* means the written document submitted each year by each disposer and commercial storer of PCB waste to the appropriate EPA Regional Administrator. The annual report is a brief summary of the information included in the annual document log.

*ASTM* means American Society for Testing and Materials, 100 Barr Harbor Drive, West Conshohocken, PA 19428-2959.

*Byproduct* means a chemical substance produced without separate commercial intent during the manufacturing or processing of another chemical substance(s) or mixture(s).

*Capacitor* means a device for accumulating and holding a charge of electricity and consisting of conducting surfaces separated by a dielectric. Types of capacitors are as follows:

(1) *Small capacitor* means a capacitor which contains less than 1.36 kg (3 lbs.) of dielectric fluid. The following assumptions may be used if the actual weight of the dielectric fluid is unknown. A capacitor whose total volume is less than 1,639 cubic centimeters (100 cubic inches) may be considered to contain less than 1.36 kgs (3 lbs.) of dielectric fluid and a capacitor whose total volume is more than 3,278 cubic centimeters (200 cubic inches) must be considered to contain more than 1.36 kg (3 lbs.) of dielectric fluid. A capacitor whose volume is between 1,639 and 3,278 cubic centimeters may be considered to contain less than 1.36 kg (3 lbs.) of dielectric fluid if the total weight of the capacitor is less than 4.08 kg (9 lbs.).

(2) *Large high voltage capacitor* means a capacitor which contains 1.36 kg (3 lbs.) or more of dielectric fluid and which operates at 2,000 volts (a.c. or d.c.) or above.

(3) *Large low voltage capacitor* means a capacitor which contains 1.36 kg (3 lbs.) or more of dielectric fluid and which operates below 2,000 volts (a.c. or d.c.).

*CERCLA* means the Comprehensive Environmental Response, Compensation, and Liability Act (42 U.S.C. 9601-9657).

*Certification* means a written statement regarding a specific fact or representation that contains the following language:

Under civil and criminal penalties of law for the making or submission of false or fraudulent statements or representations (18 U.S.C. 1001 and 15 U.S.C. 2615), I certify that the information contained in or accompanying this document is true, accurate, and complete. As to the identified section(s) of this document for which I cannot personally verify truth and accuracy, I certify as the company official having supervisory responsibility for the persons who, acting under my direct instructions, made the verification that this information is true, accurate, and complete.

*Chemical substance*, (1) except as provided in paragraph (2) of this definition, means any organic or inorganic substance of a particular molecular identity, including: Any combination

## Environmental Protection Agency

## §761.3

of such substances occurring in whole or part as a result of a chemical reaction or occurring in nature, and any element or uncombined radical.

(2) Such term does not include: Any mixture; any pesticide (as defined in the Federal Insecticide, Fungicide, and Rodenticide Act) when manufactured, processed, or distributed in commerce for use as a pesticide; tobacco or any tobacco product; any source material, special nuclear material, or byproduct material (as such terms are defined in the Atomic Energy Act of 1954 and regulations issued under such Act); any article the sale of which is subject to the tax imposed by section 4181 of the Internal Revenue Code of 1954 (determined without regard to any exemptions from such tax provided by section 4182 or section 4221 or any provisions of such Code); and any food, food additive, drug, cosmetic, or device (as such terms are defined in section 201 of the Federal Food, Drug, and Cosmetic Act) when manufactured, processed, or distributed in commerce for use as a food, food additive, drug, cosmetic, or device.

*Chemical waste landfill* means a landfill at which protection against risk of injury to health or the environment from migration of PCBs to land, water, or the atmosphere is provided from PCBs and PCB Items deposited therein by locating, engineering, and operating the landfill as specified in §761.75.

*Cleanup site* means the areal extent of contamination and all suitable areas in very close proximity to the contamination necessary for implementation of a cleanup of PCB remediation waste, regardless of whether the site was intended for management of waste.

*Commerce* means trade, traffic, transportation, or other commerce:

(1) Between a place in a State and any place outside of such State, or

(2) Which affects trade, traffic, transportation, or commerce described in paragraph (1) of this definition.

*Commercial storer of PCB waste* means the owner or operator of each facility that is subject to the PCB storage unit standards of §761.65(b)(1) or (c)(7) or meets the alternate storage criteria of §761.65(b)(2), and who engages in storage activities involving either PCB waste generated by others or that was

removed while servicing the equipment owned by others and brokered for disposal. The receipt of a fee or any other form of compensation for storage services is not necessary to qualify as a commercial storer of PCB waste. A generator who only stores its own waste is subject to the storage requirements of §761.65, but is not required to obtain approval as a commercial storer. If a facility's storage of PCB waste generated by others at no time exceeds a total of 500 gallons of liquid and/or non-liquid material containing PCBs at regulated levels, the owner or operator is a commercial storer but is not required to seek EPA approval as a commercial storer of PCB waste. Storage of one company's PCB waste by a related company is not considered commercial storage. A "related company" includes, but is not limited to: a parent company and its subsidiaries; sibling companies owned by the same parent company; companies owned by a common holding company; members of electric cooperatives; entities within the same Executive agency as defined at 5 U.S.C. 105; and a company having a joint ownership interest in a facility from which PCB waste is generated (such as a jointly owned electric power generating station) where the PCB waste is stored by one of the co-owners of the facility. A "related company" does not include another voluntary member of the same trade association. Change in ownership or title of a generator's facility, where the generator is storing PCB waste, does not make the new owner of the facility a commercial storer of PCB waste.

*Designated facility* means the off-site disposer or commercial storer of PCB waste designated on the manifest as the facility that will receive a manifested shipment of PCB waste.

*Disposal* means intentionally or accidentally to discard, throw away, or otherwise complete or terminate the useful life of PCBs and PCB Items. Disposal includes spills, leaks, and other uncontrolled discharges of PCBs as well as actions related to containing, transporting, destroying, degrading, decontaminating, or confining PCBs and PCB Items.

*Disposer of PCB waste*, as the term is used in subparts J and K of this part,

means any person who owns or operates a facility approved by EPA for the disposal of PCB waste which is regulated for disposal under the requirements of subpart D of this part.

*Distribute in commerce* and *Distribution in Commerce* when used to describe an action taken with respect to a chemical substance, mixture, or article containing a substance or mixture means to sell, or the sale of, the substance, mixture, or article in commerce; to introduce or deliver for introduction into commerce, or the introduction or delivery for introduction into commerce of the substance, mixture, or article; or to hold or the holding of, the substance, mixture, or article after its introduction into commerce.

*DOT* means the United States Department of Transportation.

*Dry weight* means the weight of the sample, excluding the weight of the water in the sample. Prior to chemical analysis the water may be removed by any reproducible method that is applicable to measuring PCBs in the sample matrix at the concentration of concern, such as air drying at ambient temperature, filtration, decantation, heating at low temperature followed by cooling in the presence of a desiccant, or other processes or combinations of processes which would remove water but not remove PCBs from the sample. Analytical procedures which calculate the dry weight concentration by adjusting for moisture content may also be used.

*EPA identification number* means the 12-digit number assigned to a facility by EPA upon notification of PCB waste activity under §761.205.

*Excluded manufacturing process* means a manufacturing process in which quantities of PCBs, as determined in accordance with the definition of inadvertently generated PCBs, calculated as defined, and from which releases to products, air, and water meet the requirements of paragraphs (1) through (5) of this definition, or the importation of products containing PCBs as unintentional impurities, which products meet the requirements of paragraphs (1) and (2) of this definition.

(1) The concentration of inadvertently generated PCBs in products leaving any manufacturing site or im-

ported into the United States must have an annual average of less than 25 ppm, with a 50 ppm maximum.

(2) The concentration of inadvertently generated PCBs in the components of detergent bars leaving the manufacturing site or imported into the United States must be less than 5 ppm.

(3) The release of inadvertently generated PCBs at the point at which emissions are vented to ambient air must be less than 10 ppm.

(4) The amount of inadvertently generated PCBs added to water discharged from a manufacturing site must be less than 100 micrograms per resolvable gas chromatographic peak per liter of water discharged.

(5) Disposal of any other process wastes above concentrations of 50 ppm PCB must be in accordance with subpart D of this part.

*Excluded PCB products* means PCB materials which appear at concentrations less than 50 ppm, including but not limited to:

(1) Non-Aroclor inadvertently generated PCBs as a byproduct or impurity resulting from a chemical manufacturing process.

(2) Products contaminated with Aroclor or other PCB materials from historic PCB uses (investment casting waxes are one example).

(3) Recycled fluids and/or equipment contaminated during use involving the products described in paragraphs (1) and (2) of this definition (heat transfer and hydraulic fluids and equipment and other electrical equipment components and fluids are examples).

(4) Used oils, provided that in the cases of paragraphs (1) through (4) of this definition:

(i) The products or source of the products containing < 50 ppm concentration PCBs were legally manufactured, processed, distributed in commerce, or used before October 1, 1984.

(ii) The products or source of the products containing < 50 ppm concentrations PCBs were legally manufactured, processed, distributed in commerce, or used, i.e., pursuant to authority granted by EPA regulation, by exemption petition, by settlement agreement, or pursuant to other Agency-approved programs;

(iii) The resulting PCB concentration (i.e. below 50 ppm) is not a result of dilution, or leaks and spills of PCBs in concentrations over 50 ppm.

*Facility* means all contiguous land, and structures, other appurtenances, and improvements on the land, used for the treatment, storage, or disposal of PCB waste. A facility may consist of one or more treatment, storage, or disposal units.

*Fluorescent light ballast* means a device that electrically controls fluorescent light fixtures and that includes a capacitor containing 0.1 kg or less of dielectric.

*Generator of PCB waste* means any person whose act or process produces PCBs that are regulated for disposal under subpart D of this part, or whose act first causes PCBs or PCB Items to become subject to the disposal requirements of subpart D of this part, or who has physical control over the PCBs when a decision is made that the use of the PCBs has been terminated and therefore is subject to the disposal requirements of subpart D of this part. Unless another provision of this part specifically requires a site-specific meaning, "generator of PCB waste" includes all of the sites of PCB waste generation owned or operated by the person who generates PCB waste.

*High occupancy area* means any area where PCB remediation waste has been disposed of on-site and where occupancy for any individual not wearing dermal and respiratory protection for a calendar year is: 840 hours or more (an average of 16.8 hours or more per week) for non-porous surfaces and 335 hours or more (an average of 6.7 hours or more per week) for bulk PCB remediation waste. Examples could include a residence, school, day care center, sleeping quarters, a single or multiple occupancy 40 hours per week work station, a school class room, a cafeteria in an industrial facility, a control room, and a work station at an assembly line.

*Importer* means any person defined as an "importer" at § 720.3(1) of this chapter who imports PCBs or PCB Items and is under the jurisdiction of the United States.

*Impurity* means a chemical substance which is unintentionally present with another chemical substance.

*In or Near Commercial Buildings* means within the interior of, on the roof of, attached to the exterior wall of, in the parking area serving, or within 30 meters of a non-industrial non-substation building. Commercial buildings are typically accessible to both members of the general public and employees, and include: (1) Public assembly properties, (2) educational properties, (3) institutional properties, (4) residential properties, (5) stores, (6) office buildings, and (7) transportation centers (e.g., airport terminal buildings, subway stations, bus stations, or train stations).

*Incinerator* means an engineered device using controlled flame combustion to thermally degrade PCBs and PCB Items. Examples of devices used for incineration include rotary kilns, liquid injection incinerators, cement kilns, and high temperature boilers.

*Industrial building* means a building directly used in manufacturing or technically productive enterprises. Industrial buildings are not generally or typically accessible to other than workers. Industrial buildings include buildings used directly in the production of power, the manufacture of products, the mining of raw materials, and the storage of textiles, petroleum products, wood and paper products, chemicals, plastics, and metals.

*Laboratory* means a facility that analyzes samples for PCBs and is unaffiliated with any entity whose activities involve PCBs.

*Leak or leaking* means any instance in which a PCB Article, PCB Container, or PCB Equipment has any PCBs on any portion of its external surface.

*Liquid PCBs* means a homogenous flowable material containing PCBs and no more than 0.5 percent by weight non-dissolved material.

*Low occupancy area* means any area where PCB remediation waste has been disposed of on-site and where occupancy for any individual not wearing dermal and respiratory protection for a calendar year is: less than 840 hours (an average of 16.8 hours per week) for non-porous surfaces and less than 335 hours (an average of 6.7 hours per week) for bulk PCB remediation waste. Examples could include an electrical substation

or a location in an industrial facility where a worker spends small amounts of time per week (such as an unoccupied area outside a building, an electrical equipment vault, or in the non-office space in a warehouse where occupancy is transitory).

*Manifest* means the shipping document EPA form 8700-22 and any continuation sheet attached to EPA form 8700-22, originated and signed by the generator of PCB waste in accordance with the instructions included with the form and subpart K of this part.

*Manned Control Center* means an electrical power distribution control room where the operating conditions of a PCB Transformer are continuously monitored during the normal hours of operation (of the facility), and, where the duty engineers, electricians, or other trained personnel have the capability to deenergize a PCB Transformer completely within 1 minute of the receipt of a signal indicating abnormal operating conditions such as an over-temperature condition or overpressure condition in a PCB Transformer.

*Manufacture* means to produce, manufacture, or import into the customs territory of the United States.

*Manufacturing process* means all of a series of unit operations operating at a site, resulting in the production of a product.

*Mark* means the descriptive name, instructions, cautions, or other information applied to PCBs and PCB Items, or other objects subject to these regulations.

*Marked* means the marking of PCB Items and PCB storage areas and transport vehicles by means of applying a legible mark by painting, fixation of an adhesive label, or by any other method that meets the requirements of these regulations.

*Market/Marketers* means the processing or distributing in commerce, or the person who processes or distributes in commerce, used oil fuels to burners or other marketers, and may include the generator of the fuel if it markets the fuel directly to the burner.

*Mineral Oil PCB Transformer* means any transformer originally designed to contain mineral oil as the dielectric fluid and which has been tested and

found to contain 500 ppm or greater PCBs.

*Mixture* means any combination of two or more chemical substances if the combination does not occur in nature and is not, in whole or in part, the result of a chemical reaction; except that such term does include any combination which occurs, in whole or in part, as a result of a chemical reaction if none of the chemical substances comprising the combination is a new chemical substance and if the combination could have been manufactured for commercial purposes without a chemical reaction at the time the chemical substances comprising the combination were combined.

*Municipal solid wastes* means garbage, refuse, sludges, wastes, and other discarded materials resulting from residential and non-industrial operations and activities, such as household activities, office functions, and commercial housekeeping wastes.

*Natural gas pipeline system* means natural gas gathering facilities, natural gas pipe, natural gas compressors, natural gas storage facilities, and natural gas pipeline appurtenances (including instrumentation and vessels directly in contact with transported natural gas such as valves, regulators, drips, filter separators, etc., but not including air compressors).

*Non-liquid PCBs* means materials containing PCBs that by visual inspection do not flow at room temperature (25 °C or 77 °F) or from which no liquid passes when a 100 g or 100 ml representative sample is placed in a mesh number 60 ±5 percent paint filter and allowed to drain at room temperature for 5 minutes.

*Non-PCB Transformer* means any transformer that contains less than 50 ppm PCB; except that any transformer that has been converted from a PCB Transformer or a PCB-Contaminated Transformer cannot be classified as a non-PCB Transformer until reclassification has occurred, in accordance with the requirements of §761.30(a)(2)(v).

*Non-porous surface* means a smooth, unpainted solid surface that limits penetration of liquid containing PCBs beyond the immediate surface. Examples are: smooth uncorroded metal; natural

## Environmental Protection Agency

## § 761.3

gas pipe with a thin porous coating originally applied to inhibit corrosion; smooth glass; smooth glazed ceramics; impermeable polished building stone such as marble or granite; and high density plastics, such as polycarbonates and melamines, that do not absorb organic solvents.

*NTIS* means the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

*On site* means within the boundaries of a contiguous property unit.

*Open burning* means the combustion of any PCB regulated for disposal, in a manner not approved or otherwise allowed under subpart D of this part, and without any of the following:

(1) Control of combustion air to maintain adequate temperature for efficient combustion.

(2) Containment of the combustion reaction in an enclosed device to provide sufficient residence time and mixing for complete combustion.

(3) Control of emission of the gaseous combustion products.

*PCB* and *PCBs* means any chemical substance that is limited to the biphenyl molecule that has been chlorinated to varying degrees or any combination of substances which contains such substance. Refer to § 761.1(b) for applicable concentrations of PCBs. PCB and PCBs as contained in PCB items are defined in § 761.3. For any purposes under this part, inadvertently generated non-Aroclor PCBs are defined as the total PCBs calculated following division of the quantity of monochlorinated biphenyls by 50 and dichlorinated biphenyls by 5.

*PCB Article* means any manufactured article, other than a PCB Container, that contains PCBs and whose surface(s) has been in direct contact with PCBs. "PCB Article" includes capacitors, transformers, electric motors, pumps, pipes and any other manufactured item (1) which is formed to a specific shape or design during manufacture, (2) which has end use function(s) dependent in whole or in part upon its shape or design during end use, and (3) which has either no change of chemical composition during its end use or only those changes of composition which

have no commercial purpose separate from that of the PCB Article.

*PCB Article Container* means any package, can, bottle, bag, barrel, drum, tank, or other device used to contain PCB Articles or PCB Equipment, and whose surface(s) has not been in direct contact with PCBs.

*PCB bulk product waste* means waste derived from manufactured products containing PCBs in a non-liquid state, at any concentration where the concentration at the time of designation for disposal was  $\geq 50$  ppm PCBs. PCB bulk product waste does not include PCBs or PCB Items regulated for disposal under § 761.60(a) through (c), § 761.61, § 761.63, or § 761.64. PCB bulk product waste includes, but is not limited to:

(1) Non-liquid bulk wastes or debris from the demolition of buildings and other man-made structures manufactured, coated, or serviced with PCBs. PCB bulk product waste does not include debris from the demolition of buildings or other man-made structures that is contaminated by spills from regulated PCBs which have not been disposed of, decontaminated, or otherwise cleaned up in accordance with subpart D of this part.

(2) PCB-containing wastes from the shredding of automobiles, household appliances, or industrial appliances.

(3) Plastics (such as plastic insulation from wire or cable; radio, television and computer casings; vehicle parts; or furniture laminates); preformed or molded rubber parts and components; applied dried paints, varnishes, waxes or other similar coatings or sealants; caulking; adhesives; paper; Galbestos; sound deadening or other types of insulation; and felt or fabric products such as gaskets.

(4) Fluorescent light ballasts containing PCBs in the potting material.

*PCB Capacitor* means any capacitor that contains  $\geq 500$  ppm PCB. Concentration assumptions applicable to capacitors appear under § 761.2.

*PCB Container* means any package, can, bottle, bag, barrel, drum, tank, or other device that contains PCBs or PCB Articles and whose surface(s) has been in direct contact with PCBs.



*PCB-Contaminated* means a non-liquid material containing PCBs at concentrations  $\geq 50$  ppm but  $< 500$  ppm; a liquid material containing PCBs at concentrations  $\geq 50$  ppm but  $< 500$  ppm or where insufficient liquid material is available for analysis, a non-porous surface having a surface concentration  $> 10$   $\mu\text{g}/100$   $\text{cm}^2$  but  $< 100$   $\mu\text{g}/100$   $\text{cm}^2$ , measured by a standard wipe test as defined in §761.123.

*PCB-Contaminated Electrical Equipment* means any electrical equipment including, but not limited to, transformers (including those used in railway locomotives and self-propelled cars), capacitors, circuit breakers, reclosers, voltage regulators, switches (including sectionalizers and motor starters), electromagnets, and cable, that contains PCBs at concentrations of  $\geq 50$  ppm and  $< 500$  ppm in the contaminating fluid. In the absence of liquids, electrical equipment is PCB-Contaminated if it has PCBs at  $> 10$   $\mu\text{g}/100$   $\text{cm}^2$  and  $< 100$   $\mu\text{g}/100$   $\text{cm}^2$  as measured by a standard wipe test (as defined in §761.123) of a non-porous surface.

*PCB Equipment* means any manufactured item, other than a PCB Container or a PCB Article Container, which contains a PCB Article or other PCB Equipment, and includes microwave ovens, electronic equipment, and fluorescent light ballasts and fixtures.

*PCB field screening test* means a portable analytical device or kit which measures PCBs. PCB field screening tests usually report less than or greater than a specific numerical PCB concentration. These tests normally build in a safety factor which increases the probability of a false positive report and decreases the probability of a false negative report. PCB field screening tests do not usually provide: an identity record generated by an instrument; a quantitative comparison record from calibration standards; any identification of PCBs; and/or any indication or identification of interferences with the measurement of the PCBs. PCB field screening test technologies include, but are not limited to, total chlorine colorimetric tests, total chlorine x-ray fluorescence tests, total chlorine microcoulometric tests, and rapid immunoassay tests.

*PCB household waste* means PCB waste that is generated by residents on the premises of a temporary or permanent residence for individuals (including individually owned or rented units of a multi-unit construction), and that is composed primarily of materials found in wastes generated by consumers in their homes. PCB household waste includes unwanted or discarded non-commercial vehicles (prior to shredding), household items, and appliances or appliance parts and wastes generated on the premises of a residence for individuals as a result of routine household maintenance by or on behalf of the resident. Bulk or commingled liquid PCB wastes at concentrations of  $\geq 50$  ppm, demolition and renovation wastes, and industrial or heavy duty equipment with PCBs are not household wastes.

*PCB Item* means any PCB Article, PCB Article Container, PCB Container, PCB Equipment, or anything that deliberately or unintentionally contains or has as a part of it any PCB or PCBs.

*PCB/radioactive waste* means PCBs regulated for disposal under subpart D of this part that also contain source, special nuclear, or byproduct material subject to regulation under the Atomic Energy Act of 1954, as amended, or naturally-occurring or accelerator-produced radioactive material.

*PCB remediation waste* means waste containing PCBs as a result of a spill, release, or other unauthorized disposal, at the following concentrations: Materials disposed of prior to April 18, 1978, that are currently at concentrations  $\geq 50$  ppm PCBs, regardless of the concentration of the original spill; materials which are currently at any volume or concentration where the original source was  $\geq 500$  ppm PCBs beginning on April 18, 1978, or  $\geq 50$  ppm PCBs beginning on July 2, 1979; and materials which are currently at any concentration if the PCBs are spilled or released from a source not authorized for use under this part. PCB remediation waste means soil, rags, and other debris generated as a result of any PCB spill cleanup, including, but not limited to:

(1) Environmental media containing PCBs, such as soil and gravel; dredged materials, such as sediments, settled

sediment fines, and aqueous decantate from sediment.

(2) Sewage sludge containing < 50 ppm PCBs and not in use according to § 761.20(a)(4); PCB sewage sludge; commercial or industrial sludge contaminated as the result of a spill of PCBs including sludges located in or removed from any pollution control device; aqueous decantate from an industrial sludge.

(3) Buildings and other man-made structures (such as concrete floors, wood floors, or walls contaminated from a leaking PCB or PCB-Contaminated Transformer), porous surfaces, and non-porous surfaces.

*PCB sewage sludge* means sewage sludge as defined in 40 CFR 503.9(w) which contains ≥50 ppm PCBs, as measured on a dry weight basis.

*PCB Transformer* means any transformer that contains ≥500 ppm PCBs. For PCB concentration assumptions applicable to transformers containing 1.36 kilograms (3 lbs.) or more of fluid other than mineral oil, see § 761.2. For provisions permitting reclassification of electrical equipment, including PCB Transformers, containing ≥500 ppm PCBs to PCB-Contaminated Electrical Equipment, see § 761.30(a) and (h).

*PCB waste(s)* means those PCBs and PCB Items that are subject to the disposal requirements of subpart D of this part.

*Performance-based organic decontamination fluid (PODF)* means kerosene, diesel fuel, terpene hydrocarbons, and terpene hydrocarbon/alcohol mixtures.

*Person* means any natural or judicial person including any individual, corporation, partnership, or association; any State or political subdivision thereof; any interstate body; and any department, agency, or instrumentality of the Federal Government.

*Porous surface* means any surface that allows PCBs to penetrate or pass into itself including, but not limited to, paint or coating on metal; corroded metal; fibrous glass or glass wool; unglazed ceramics; ceramics with a porous glaze; porous building stone such as sandstone, travertine, limestone, or coral rock; low-density plastics such as styrofoam and low-density polyethylene; coated (varnished or painted)

or uncoated wood; concrete or cement; plaster; plasterboard; wallboard; rubber; fiberboard; chipboard; asphalt; or tar paper. For purposes of cleaning and disposing of PCB remediation waste, porous surfaces have different requirements than non-porous surfaces.

*Posing an exposure risk to food or feed* means being in any location where human food or animal feed products could be exposed to PCBs released from a PCB Item. A PCB Item poses an exposure risk to food or feed if PCBs released in any way from the PCB Item have a potential pathway to human food or animal feed. EPA considers human food or animal feed to include items regulated by the U.S. Department of Agriculture or the Food and Drug Administration as human food or animal feed; this includes direct additives. Food or feed is excluded from this definition if it is used or stored in private homes.

*Process* means the preparation of a chemical substance or mixture, after its manufacture, for distribution in commerce:

(1) In the same form or physical state as, or in a different form or physical state from, that in which it was received by the person so preparing such substance or mixture, or

(2) As part of an article containing the chemical substance or mixture.

*Qualified incinerator* means one of the following:

(1) An incinerator approved under the provisions of § 761.70. Any level of PCB concentration can be destroyed in an incinerator approved under § 761.70.

(2) A high efficiency boiler which complies with the criteria of § 761.71(a)(1), and for which the operator has given written notice to the appropriate EPA Regional Administrator in accordance with the notification requirements for the burning of mineral oil dielectric fluid under § 761.71(a)(2).

(3) An incinerator approved under section 3005(c) of the Resource Conservation and Recovery Act (42 U.S.C. 6925(c)) (RCRA).

(4) Industrial furnaces and boilers which are identified in 40 CFR 260.10 and 40 CFR 279.61 (a)(1) and (2) when operating at their normal operating temperatures (this prohibits feeding fluids,

above the level of detection, during either startup or shutdown operations).

*Quantifiable Level/Level of Detection* means 2 micrograms per gram from any resolvable gas chromatographic peak, i.e. 2 ppm.

*RCRA* means the Resource Conservation and Recovery Act (40 U.S.C. 6901 *et seq.*).

*Recycled PCBs* means those PCBs which appear in the processing of paper products or asphalt roofing materials from PCB-contaminated raw materials. Processes which recycle PCBs must meet the following requirements:

(1) There are no detectable concentrations of PCBs in asphalt roofing material products leaving the processing site.

(2) The concentration of PCBs in paper products leaving any manufacturing site processing paper products, or in paper products imported into the United States, must have an annual average of less than 25 ppm with a 50 ppm maximum.

(3) The release of PCBs at the point at which emissions are vented to ambient air must be less than 10 ppm.

(4) The amount of Aroclor PCBs added to water discharged from an asphalt roofing processing site must at all times be less than 3 micrograms per liter ( $\mu\text{g/L}$ ) for total Aroclors (roughly 3 parts per billion (3 ppb)). Water discharges from the processing of paper products must at all times be less than 3 micrograms per liter ( $\mu\text{g/L}$ ) for total Aroclors (roughly 3 ppb), or comply with the equivalent mass-based limitation.

(5) Disposal of any other process wastes at concentrations of 50 ppm or greater must be in accordance with subpart D of this part.

*Research and development (R&D) for PCB disposal* means demonstrations for commercial PCB disposal approvals, pre-demonstration tests, tests of major modifications to previously approved PCB disposal technologies, treatability studies for PCB disposal technologies which have not been approved, development of new disposal technologies, and research on chemical transformation processes including, but not limited to, biodegradation.

*Retrofill* means to remove PCB or PCB-contaminated dielectric fluid and

to replace it with either PCB, PCB-contaminated, or non-PCB dielectric fluid.

*Rupture of a PCB Transformer* means a violent or non-violent break in the integrity of a PCB Transformer caused by an overtemperature and/or overpressure condition that results in the release of PCBs.

*Sale for purposes other than resale* means sale of PCBs for purposes of disposal and for purposes of use, except where use involves sale for distribution in commerce. PCB Equipment which is first leased for purposes of use any time before July 1, 1979, will be considered sold for purposes other than resale.

*Sewage sludge* means sewage sludge as defined in §503.9(w) of this chapter that contains < 50 ppm (on a dry weight basis) PCBs.

*Small quantities for research and development* means any quantity of PCBs (1) that is originally packaged in one or more hermetically sealed containers of a volume of no more than five (5.0) milliliters, and (2) that is used only for purposes of scientific experimentation or analysis, or chemical research on, or analysis of, PCBs, but not for research or analysis for the development of a PCB product.

*Soil washing* means the extraction of PCBs from soil using a solvent, recovering the solvent from the soil, separating the PCBs from the recovered solvent for disposal, and then disposal or reuse of the solvent.

*Standard wipe sample* means a sample collected for chemical extraction and analysis using the standard wipe test as defined in §761.123. Except as designated elsewhere in part 761, the minimum surface area to be sampled shall be 100  $\text{cm}^2$ .

*Storage for disposal* means temporary storage of PCBs that have been designated for disposal.

*SW-846* means the document having the title "SW-846, Test Methods for Evaluating Solid Waste," which is available from either the National Technical Information Service (NTIS, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161, telephone: (703) 487-4650 or the U.S. Government Printing Office (U.S. GPO,

## Environmental Protection Agency

## § 761.19

710 North Capitol St., NW., Washington, DC 20401, telephone: (202) 783-3238.

*Totally enclosed manner* means any manner that will ensure no exposure of human beings or the environment to any concentration of PCBs.

*Transfer facility* means any transportation-related facility including loading docks, parking areas, and other similar areas where shipments of PCB waste are held during the normal course of transportation. Transport vehicles are not transfer facilities under this definition, unless they are used for the storage of PCB waste, rather than for actual transport activities. Storage areas for PCB waste at transfer facilities are subject to the storage facility standards of § 761.65, but such storage areas are exempt from the approval requirements of § 761.65(d) and the record-keeping requirements of § 761.180, unless the same PCB waste is stored there for a period of more than 10 consecutive days between destinations.

*Transporter of PCB waste* means, for the purposes of subpart K of this part, any person engaged in the transportation of regulated PCB waste by air, rail, highway, or water for purposes other than consolidation by a generator.

*Transport vehicle* means a motor vehicle or rail car used for the transportation of cargo by any mode. Each cargo-carrying body (e.g., trailer, railroad freight car) is a separate transport vehicle.

*Treatability Study* means a study in which PCB waste is subjected to a treatment process to determine:

- (1) Whether the waste is amenable to the treatment process;
- (2) What pretreatment (if any) is required;
- (3) The optimal process conditions needed to achieve the desired treatment;
- (4) The efficiency of a treatment process for the specific type of waste (i.e., soil, sludge, liquid, etc.); or,
- (5) The characteristics and volumes of residuals from a particular treatment process. A "treatability study" is not a mechanism to commercially treat or dispose of PCB waste. Treatment is a form of disposal under this part.

*TSCA* means the Toxic Substances Control Act (15 U.S.C. 2601 *et seq.*).

*TSCA PCB Coordinated Approval* means the process used to recognize other Federal or State waste management documents governing the storage, cleanup, treatment, and disposal of PCB wastes. It is the mechanism under TSCA for accomplishing review, coordination, and approval of PCB waste management activities which are conducted outside of the TSCA PCB approval process, but require approval under the TSCA PCB regulations at 40 CFR part 761.

*Unit* means a particular building, structure, or cell used to manage PCB waste (including, but not limited to, a building used for PCB waste storage, a landfill, an industrial boiler, or an incinerator).

*U.S. GPO* means the U.S. Government Printing Office, 710 North Capitol St., NW., Washington, DC 20401.

*Waste Oil* means used products primarily derived from petroleum, which include, but are not limited to, fuel oils, motor oils, gear oils, cutting oils, transmission fluids, hydraulic fluids, and dielectric fluids.

*Wet weight* means reporting chemical analysis results by including either the weight, or the volume and density, of all liquids.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605))

[49 FR 25239, June 20, 1984, as amended at 49 FR 28189, July 10, 1984; 49 FR 29066, July 18, 1984; 49 FR 44638, Nov. 8, 1984; 50 FR 29199, July 17, 1985; 50 FR 32176, Aug. 9, 1985; 53 FR 24220, June 27, 1988; 53 FR 27327, July 19, 1988; 54 FR 52745, Dec. 21, 1989; 55 FR 26205, June 27, 1990; 58 FR 32061, June 8, 1993; 61 FR 11106, Mar. 18, 1996; 63 FR 35437, June 29, 1998; 64 FR 33759, June 24, 1999]

### § 761.19 References.

- (a) [Reserved]
- (b) *Incorporation by reference.* The following material is incorporated by reference, and is available for inspection at the National Archives and Records Administration (NARA). For information on the availability of this material at NARA, call 202-741-6030, or go to: [http://www.archives.gov/federal\\_register/code\\_of\\_federal\\_regulations/ibr\\_locations.html](http://www.archives.gov/federal_register/code_of_federal_regulations/ibr_locations.html).

These

**§ 761.20**

incorporations by reference were approved by the Director of the Office of the Federal Register. These materials are incorporated as they exist on the date of approval and a notice of any change in these materials will be published in the FEDERAL REGISTER. Copies of the incorporated material are available for inspection at the EPA Docket Center (EPA/DC), Rm. 3334, EPA West Bldg., 1301 Constitution Ave., NW., Washington, DC 20460-0001. Copies of the incorporated material may be obtained from the American Society for Testing and Materials (ASTM), 100 Barr Harbor Drive, West Conshohocken, PA 19428-2959.

| References   | CFR Citation                               |
|--|--|
| ASTM D 93 – 90 Standard Test Methods for Flash Point by Pensky-Martens Closed Tester.  | § 761.71(b)(2)(vi);<br>§ 761.75(b)(8)(iii) |
| ASTM D 129–64 (Reapproved 1978) Standard Test Method for Sulfur in Petroleum Products (General Bomb Method).                               | § 761.71(b)(2)(vi)                         |
| ASTM D 240–87 Standard Test Method for Heat of Combustion of Liquid Hydrocarbon Fuel by Bomb Calorimeter.                                  | § 761.71(b)(2)(vi)                         |
| ASTM D 482–87 Standard Test Method for Ash from Petroleum Products.  | § 761.71(b)(2)(vi)                         |
| ASTM D 524–88 Standard Test Method for Ramsbottom Carbon Residue of Petroleum Products.  | § 761.71(b)(2)(vi)                         |
| ASTM D 808–87 Standard Test Method for Chlorine in New and Used Petroleum Products (Bomb Method).  | § 761.71(b)(2)(vi)                         |
| ASTM D 923–86 Standard Test Method for Sampling Electrical Insulating Liquids.   | § 761.60(g)(1)(iii);<br>(g)(2)(ii)         |
| ASTM D 923–89 Standard Methods of Sampling Electrical Insulating Liquids.  | § 761.60(g)(1)(iii);<br>(g)(2)(ii)         |
| ASTM D 1266–87 Standard Test Method for Sulfur in Petroleum Products (Lamp Method).  | § 761.71(b)(2)(vi)                         |
| ASTM D 1796–83 (Reapproved 1990) Standard Test Method for Water and Sediment in Fuel Oils by the Centrifuge Method (Laboratory Procedure). | § 761.71(b)(2)(vi)                         |
| ASTM D 2158–89 Standard Test Method for Residues in Liquefied Petroleum (LP) Gases.  | § 761.71(b)(2)(vi)                         |
| ASTM D 2709–88 Standard Test Method for Water and Sediment in Distillate Fuels by Centrifuge.  | § 761.71(b)(2)(vi)                         |
| ASTM D 2784–89 Standard Test Method for Sulfur in Liquefied Petroleum Gases (Oxy-hydrogen Burner or Lamp).                                 | § 761.71(b)(2)(vi)                         |
| ASTM D 3178–84 Standard Test Methods for Carbon and Hydrogen in the Analysis Sample of Coke and Coal.                                      | § 761.71(b)(2)(vi)                         |
| ASTM D 3278–89 Standard Test Methods for Flash Point of Liquids by Setafash Closed-Cup Apparatus.  | § 761.75(b)(8)(iii)                        |

**40 CFR Ch. I (7–1–10 Edition)**

| References  | CFR Citation       |
|---|--------------------|
| ASTM E 258–67 (Reapproved 1987) Standard Test Method for Total Nitrogen Inorganic Material by Modified KJELDAHL Method. | § 761.71(b)(2)(vi) |

[47 FR 22098, May 21, 1982, as amended at 49 FR 29067, July 18, 1984; 49 FR 36648, Sept. 19, 1984; 53 FR 10391, Mar. 31, 1988; 53 FR 12524, Apr. 15, 1988; 53 FR 21641, June 9, 1988; 57 FR 13323, Apr. 16, 1992; 59 FR 33697, June 30, 1994; 60 FR 34465, July 3, 1995; 63 FR 35439, June 29, 1998; 64 FR 33759, June 24, 1999; 69 FR 18803, Apr. 9, 2004; 72 FR 57239, Oct. 9, 2007]

**Subpart B—Manufacturing, Processing, Distribution in Commerce, and Use of PCBs and PCB Items**

**§ 761.20 Prohibitions and exceptions.**

Except as authorized in § 761.30, the activities listed in paragraphs (a) and (d) of this section are prohibited pursuant to section 6(e)(2) of TSCA. The requirements set forth in paragraph (c) of this section and subpart F of this part concerning export and import of PCBs and PCB Items for disposal are established pursuant to section 6(e)(1) of TSCA. Subject to any exemptions granted pursuant to section 6(e)(3)(B) of TSCA, the activities listed in paragraphs (b) and (c) of this section are prohibited pursuant to section 6(e)(3)(A) of TSCA. In addition, the Administrator hereby finds, under the authority of section 12(a)(2) of TSCA, that the manufacture, processing, and distribution in commerce of PCBs at concentrations of 50 ppm or greater and PCB Items with PCB concentrations of 50 ppm or greater present an unreasonable risk of injury to health within the United States. This finding is based upon the well-documented human health and environmental hazard of PCB exposure, the high probability of human and environmental exposure to PCBs and PCB Items from manufacturing, processing, or distribution activities; the potential hazard of PCB exposure posed by the transportation of PCBs or PCB Items within the United States; and the evidence that contamination of the environment by PCBs is spread far beyond the areas where they are used. In addition, the

## Environmental Protection Agency

## § 761.20

Administrator hereby finds, for purposes of section 6(e)(2)(C) of TSCA, that any exposure of human beings or the environment to PCBs, as measured or detected by any scientifically acceptable analytical method, may be significant, depending on such factors as the quantity of PCBs involved in the exposure, the likelihood of exposure to humans and the environment, and the effect of exposure. For purposes of determining which PCB Items are totally enclosed, pursuant to section 6(e)(2)(C) of TSCA, since exposure to such Items may be significant, the Administrator further finds that a totally enclosed manner is a manner which results in no exposure to humans or the environment to PCBs. The following activities are considered totally enclosed: distribution in commerce of intact, non-leaking electrical equipment such as transformers (including transformers used in railway locomotives and self-propelled cars), capacitors, electromagnets, voltage regulators, switches (including sectionalizers and motor starters), circuit breakers, reclosers, and cable that contain PCBs at any concentration and processing and distribution in commerce of PCB Equipment containing an intact, non-leaking PCB Capacitor. See paragraph (c)(1) of this section for provisions allowing the distribution in commerce of PCBs and PCB Items.

(a) No persons may use any PCB, or any PCB Item regardless of concentration, in any manner other than in a totally enclosed manner within the United States unless authorized under § 761.30, except that:

(1) An authorization is not required to use those PCBs or PCB Items which consist of excluded PCB products as defined in § 761.3.

(2) An authorization is not required to use those PCBs or PCB Items resulting from an excluded manufacturing process or recycled PCBs as defined in § 761.3, provided all applicable conditions of § 761.1(f) are met.

(3) An authorization is not required to use those PCB Items which contain or whose surfaces have been in contact with excluded PCB products as defined in § 761.3.

(4) An authorization is not required to use sewage sludge where the uses are

regulated at parts 257, 258, and 503 of this chapter. No person may blend or otherwise dilute PCBs regulated for disposal, including PCB sewage sludge and sewage sludge not used pursuant to parts 257, 258, and 503 of this chapter, for purposes of use or to avoid disposal requirements under this part. Except as explicitly provided in subpart D of this part, no person may dispose of regulated PCB wastes including, but not limited to, PCB remediation waste, PCB bulk product waste, PCBs, and PCB industrial sludges, into treatment works, as defined in § 503.9(aa) of this chapter.

(b) No person may manufacture PCBs for use within the United States or manufacture PCBs for export from the United States without an exemption, except that: an exemption is not required for PCBs manufactured in an excluded manufacturing process as defined in § 761.3, provided all applicable conditions of § 761.1(f) are met.

(c) No persons may process or distribute in commerce any PCB, or any PCB Item regardless of concentration, for use within the United States or for export from the United States without an exemption, except that an exemption is not required to process or distribute in commerce PCBs or PCB Items resulting from an excluded manufacturing process as defined in § 761.3, or to process or distribute in commerce recycled PCBs as defined in § 761.3, or to process or distribute in commerce excluded PCB products as defined in § 761.3, provided that all applicable conditions of § 761.1(f) are met. In addition, the activities described in paragraphs (c) (1) through (5) of this section may also be conducted without an exemption, under the conditions specified therein.

(1) PCBs at concentrations of 50 ppm or greater, or PCB Items with PCB concentrations of 50 ppm or greater, sold before July 1, 1979 for purposes other than resale may be distributed in commerce only in a totally enclosed manner after that date.

(2) Any person may process and distribute in commerce for disposal PCBs at concentrations of  $\geq 50$  ppm, or PCB Items with PCB concentrations of  $\geq 50$  ppm, if they comply with the applicable provisions of this part.

## § 761.20

## 40 CFR Ch. I (7-1-10 Edition)

(i) Processing activities which are primarily associated with and facilitate storage or transportation for disposal do not require a TSCA PCB storage or disposal approval.

(ii) Processing activities which are primarily associated with and facilitate treatment, as defined in § 260.10 of this chapter, or disposal require a TSCA PCB disposal approval unless they are part of an existing approval, are part of a self-implementing activity under § 761.61(a) or § 761.79 (b) or (c), or are otherwise specifically allowed under subpart D of this part.

(iii) With the exception of provisions in § 761.60 (a)(2) and (a)(3), in order to meet the intent of § 761.1(b), processing, diluting, or otherwise blending of waste prior to being introduced into a disposal unit for purposes of meeting a PCB concentration limit shall be done in accordance with a TSCA PCB disposal approval or comply with the requirements of § 761.79.

(iv) Where the rate of delivering liquids or non-liquids into a PCB disposal unit is an operating parameter, this rate shall be a condition of the TSCA PCB disposal approval for the unit when an approval is required.

(3) PCBs and PCB Items may be exported for disposal in accordance with the requirements of subpart F of this part.

(4) PCBs, at concentrations of less than 50 ppm, or PCB Items, with concentrations of less than 50 ppm, may be processed and distributed in commerce for purposes of disposal.

(5) Decontaminated materials. Any person may distribute in commerce equipment, structures, or other liquid or non-liquid materials that were contaminated with PCBs  $\geq 50$  ppm, including those not otherwise authorized for distribution in commerce under this part, provided that one of the following applies:

(i) The materials were decontaminated in accordance with a TSCA PCB disposal approval issued under subpart D of this part, with § 761.79, or with applicable EPA PCB spill cleanup policies in effect at the time of the decontamination.

(ii) If not previously decontaminated, the materials now meet an applicable decontamination standard in § 761.79(b).

(d) The use of waste oil that contains any detectable concentration of PCB as a sealant, coating, or dust control agent is prohibited. Prohibited uses include, but are not limited to, road oiling, general dust control, use as a pesticide or herbicide carrier, and use as a rust preventative on pipes.

(e) In addition to any applicable requirements under 40 CFR part 279, subparts G and H, marketers and burners of used oil who market (process or distribute in commerce) for energy recovery, used oil containing any quantifiable level of PCBs are subject to the following requirements:

(1) *Restrictions on marketing.* Used oil containing any quantifiable level of PCBs (2 ppm) may be marketed only to:

(i) Qualified incinerators as defined in 40 CFR 761.3.

(ii) Marketers who market off-specification used oil for energy recovery only to other marketers who have notified EPA of their used oil management activities, and who have an EPA identification number where an identification number is required by 40 CFR 279.73. This would include persons who market off-specification used oil who are subject to the requirements at 40 CFR part 279 and the notification requirements of 40 CFR 279.73.

(iii) Burners identified in 40 CFR 279.61(a)(1) and (2). Only burners in the automotive industry may burn used oil generated from automotive sources in used oil-fired space heaters provided the provisions of 40 CFR 279.23 are met. The Regional Administrator may grant a variance for a boiler that does not meet the 40 CFR 279.61(a)(1) and (2) criteria after considering the criteria listed in 40 CFR 260.32 (a) through (f). The applicant must address the relevant criteria contained in 40 CFR 260.32 (a) through (f) in an application to the Regional Administrator.

(2) *Testing of used oil fuel.* Used oil to be burned for energy recovery is presumed to contain quantifiable levels (2 ppm) of PCB unless the marketer obtains analyses (testing) or other information that the used oil fuel does not contain quantifiable levels of PCBs.

(i) The person who first claims that a used oil fuel does not contain quantifiable level (2 ppm) PCB must obtain

## Environmental Protection Agency

## § 761.30

analyses or other information to support that claim.

(ii) Testing to determine the PCB concentration in used oil may be conducted on individual samples, or in accordance with the testing procedures described in § 761.60(g)(2). However, for purposes of this part, if any PCBs at a concentration of 50 ppm or greater have been added to the container or equipment, then the total container contents must be considered as having a PCB concentration of 50 ppm or greater for purposes of complying with the disposal requirements of this part.

(iii) Other information documenting that the used oil fuel does not contain quantifiable levels (2 ppm) of PCBs may consist of either personal, special knowledge of the source and composition of the used oil, or a certification from the person generating the used oil claiming that the oil contains no detectable PCBs.

(3) *Restrictions on burning.* (i) Used oil containing any quantifiable levels of PCB may be burned for energy recovery only in the combustion facilities identified in paragraph (e)(1) of this section when such facilities are operating at normal operating temperatures (this prohibits feeding these fuels during either startup or shutdown operations). Owners and operators of such facilities are “burners” of used oil fuels.

(ii) Before a burner accepts from a marketer the first shipment of used oil fuel containing detectable PCBs (2 ppm), the burner must provide the marketer a one-time written and signed notice certifying that:

(A) The burner has complied with any notification requirements applicable to “qualified incinerators” (§ 761.3) or to “burners” regulated under 40 CFR part 279, subpart G.

(B) The burner will burn the used oil only in a combustion facility identified in paragraph (e)(1) of this section and identify the class of burner he qualifies.

(4) *Recordkeeping requirements.* The following recordkeeping requirements are in addition to the recordkeeping requirements for marketers found in 40 CFR 279.72(b), 279.74(a), (b) and (c), and 279.75, and for burners found in 40 CFR 279.65 and 279.66.

(i) *Marketers.* Marketers who first claim that the used oil fuel contains no detectable PCBs must include among the records required by 40 CFR 279.72(b) and 279.74(b) and (c), copies of the analysis or other information documenting his claim, and he must include among the records required by 40 CFR 279.74(a) and (c) and 279.75, a copy of each certification notice received or prepared relating to transactions involving PCB-containing used oil.

(ii) *Burners.* Burners must include among the records required by 40 CFR 279.65 and 279.66, a copy of each certification notice required by paragraph (e)(3)(ii) of this section that he sends to a marketer.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020, (15 U.S.C. 2605)

[44 FR 31542, May 31, 1979. Redesignated at 47 FR 19527, May 6, 1982, and amended at 49 FR 25241, June 20, 1984; 49 FR 28190, July 10, 1984; 49 FR 44638, Nov. 8, 1984; 53 FR 12524, Apr. 15, 1988; 53 FR 24220, June 27, 1988; 58 FR 15435, Mar. 23, 1993; 58 FR 34205, June 23, 1993; 60 FR 34465, July 3, 1995; 61 FR 11106, Mar. 18, 1996; 63 FR 35439, June 29, 1998; 64 FR 33760, June 24, 1999]

### § 761.30 Authorizations.

The following non-totally enclosed PCB activities are authorized pursuant to section 6(e)(2)(B) of TSCA:

(a) *Use in and servicing of transformers (other than railroad transformers).* PCBs at any concentration may be used in transformers (other than in railroad locomotives and self-propelled railroad cars) and may be used for purposes of servicing including rebuilding these transformers for the remainder of their useful lives, subject to the following conditions:

(1) *Use conditions.* (i) As of October 1, 1985, the use and storage for reuse of PCB Transformers that pose an exposure risk to food or feed is prohibited.

(ii) As of October 1, 1990, the use of network PCB Transformers with higher secondary voltages (secondary voltages equal to or greater than 480 volts, including 480/277 volt systems) in or near commercial buildings is prohibited. Network PCB Transformers with higher secondary voltages which are removed from service in accordance with this requirement must either be reclassified to PCB Contaminated or non



PCB status, placed into storage for disposal, or disposed.

(iii) Except as otherwise provided, as of October 1, 1985, the installation of PCB Transformers, which have been placed into storage for reuse or which have been removed from another location, in or near commercial buildings is prohibited.

(A) Retrofilled mineral oil PCB Transformers may be installed for reclassification purposes indefinitely after October 1, 1990.

(B) Once a retrofilled transformer has been installed for reclassification purposes, it must be tested 3 months after installation to ascertain the concentration of PCBs. If the PCB concentration is below 50 ppm, the transformer can be reclassified as a non-PCB Transformer. If the PCB concentration is between 50 and 500 ppm, the transformer can be reclassified as a PCB-Contaminated transformer. If the PCB concentration remains at 500 ppm or greater, the entire process must either be repeated until the transformer has been reclassified to a non-PCB or PCB-Contaminated transformer in accordance with paragraph (a)(2)(v) of this section or the transformer must be removed from service.

(iv) As of October 1, 1990, all higher secondary voltage radial PCB Transformers, in use in or near commercial buildings, and lower secondary voltage network PCB Transformers not located in sidewalk vaults in or near commercial buildings (network transformers with secondary voltages below 480 volts) that have not been removed from service as provided in paragraph (a)(1)(iv)(B) of this section, must be equipped with electrical protection to avoid transformer ruptures caused by high current faults. As of February 25, 1991, all lower secondary voltage radial PCB Transformers, in use in or near commercial buildings, must be equipped with electrical protection to avoid transformer ruptures caused by high current faults.

(A) Current-limiting fuses or other equivalent technology must be used to detect sustained high current faults and provide for the complete deenergization of the transformer (within several hundredths of a second in the case of higher secondary voltage

radial PCB Transformers and within tenths of a second in the case of lower secondary voltage network PCB Transformers), before transformer rupture occurs. Lower secondary voltage radial PCB Transformers must be equipped with electrical protection as provided in paragraph (a)(1)(iv)(E) of this section. The installation, setting, and maintenance of current-limiting fuses or other equivalent technology to avoid PCB Transformer ruptures from sustained high current faults must be completed in accordance with good engineering practices.

(B) All lower secondary voltage network PCB Transformers not located in sidewalk vaults (network transformers with secondary voltages below 480 volts), in use in or near commercial buildings, which have not been protected as specified in paragraph (a)(1)(iv)(A) of this section by October 1, 1990, must be removed from service by October 1, 1993.

(C) As of October 1, 1990, owners of lower secondary voltage network PCB Transformers, in use in or near commercial buildings which have not been protected as specified in paragraph (a)(1)(iv)(A) of this section and which are not located in sidewalk vaults, must register in writing those transformers with the EPA Regional Administrator in the appropriate region. The information required to be provided in writing to the Regional Administrator includes:

(1) The specific location of the PCB Transformer(s).

(2) The address(es) of the building(s) and the physical location of the PCB Transformer(s) on the building site(s).

(3) The identification number(s) of the PCB Transformer(s).

(D) As of October 1, 1993, all lower secondary voltage network PCB Transformers located in sidewalk vaults (network transformers with secondary voltages below 480 volts) in use near commercial buildings must be removed from service.

## Environmental Protection Agency

## § 761.30

(E) As of February 25, 1991, all lower secondary voltage radial PCB Transformers must be equipped with electrical protection, such as current-limiting fuses or other equivalent technology, to detect sustained high current faults and provide for the complete deenergization of the transformer or complete deenergization of the faulted phase of the transformer within several hundredths of a second. The installation, setting, and maintenance of current-limiting fuses or other equivalent technology to avoid PCB Transformer ruptures from sustained high current faults must be completed in accordance with good engineering practices.

(v) As of October 1, 1990, all radial PCB Transformers with higher secondary voltages (480 volts and above, including 480/277 volt systems) in use in or near commercial buildings must, in addition to the requirements of paragraph (a)(1)(iv)(A) of this section, be equipped with protection to avoid transformer ruptures caused by sustained low current faults.

(A) Pressure and temperature sensors (or other equivalent technology which has been demonstrated to be effective in early detection of sustained low current faults) must be used in these transformers to detect sustained low current faults.

(B) Disconnect equipment must be provided to insure complete deenergization of the transformer in the event of a sensed abnormal condition (e.g., an overpressure or over-temperature condition in the transformer), caused by a sustained low current fault. The disconnect equipment must be configured to operate automatically within 30 seconds to 1 minute of the receipt of a signal indicating an abnormal condition from a sustained low current fault, or can be configured to allow for manual deenergization from a manned on-site control center upon the receipt of an audio or visual signal indicating an abnormal condition caused by a sustained low current fault. Manual deenergization from a manned on-site control center must occur within 1 minute of the receipt of the audio or visual signal indicating an abnormal condition caused by a sustained low

current fault. If automatic operation is selected and a circuit breaker is utilized for disconnection, it must also have the capability to be manually opened if necessary.

(C) The enhanced electrical protective system required for the detection of sustained low current faults and the complete and rapid deenergization of transformers must be properly installed, maintained, and set sensitive enough (in accordance with good engineering practices) to detect sustained low current faults and allow for rapid and total deenergization prior to PCB Transformer rupture (either violent or non violent rupture) and release of PCBs.

(vi)(A) No later than December 28, 1998 all owners of PCB Transformers, including those in storage for reuse, must register their transformers with the Environmental Protection Agency, National Program Chemicals Division, Office of Pollution Prevention and Toxics (7404), 1200 Pennsylvania Ave., NW., Washington, DC 20460. This registration requirement is subject to the limitations in paragraph (a)(1) of this section.

(1) A transformer owner who assumes a transformer is a PCB-Contaminated transformer, and discovers after December 28, 1998 that it is a PCB-Transformer, must register the newly-identified PCB Transformer, in writing, with the Environmental Protection Agency no later than 30 days after it is identified as such. This requirement does not apply to transformer owners who have previously registered with the EPA PCB Transformers located at the same address as the transformer that they assumed to be PCB-Contaminated and later determined to be a PCB Transformer.

(2) A person who takes possession of a PCB Transformer after December 28, 1998 is not required to register or re-register the transformer with the EPA.

(B) Any person submitting a registration under this section must include:

(1) Company name and address.

(2) Contact name and telephone number.

(3) Address where these transformers are located. For mobile sources such as ships, provide the name of the ship.

(4) Number of PCB Transformers and the total weight in kilograms of PCBs contained in the transformers.

(5) Whether any transformers at this location contain flammable dielectric fluid (optional).

(6) Signature of the owner, operator, or other authorized representative certifying the accuracy of the information submitted.

(C) A transformer owner must retain a record of each PCB Transformer's registration (e.g., a copy of the registration and the return receipt signed by EPA) with the inspection and maintenance records required for each PCB Transformer under paragraph (a)(1)(xii)(I) of this section.

(D) A transformer owner must comply with all requirements of paragraph (a)(1)(vi)(A) of this section to continue the PCB-Transformer's authorization for use, or storage for reuse, pursuant to this section and TSCA section 6(e)(2)(B).

(vii) As of December 1, 1985, PCB Transformers in use in or near commercial buildings must be registered with building owners. For PCB Transformers located in commercial buildings, PCB Transformer owners must register the transformers with the building owner of record. For PCB Transformers located near commercial buildings, PCB Transformer owners must register the transformers with all owners of buildings located within 30 meters of the PCB Transformer(s). Information required to be provided to building owners by PCB Transformer owners includes but is not limited to:

(A) The specific location of the PCB Transformer(s).

(B) The principal constituent of the dielectric fluid in the transformer(s) (e.g., PCBs, mineral oil, or silicone oil).

(C) The type of transformer installation (e.g., 208/120 volt network, 208/120 volt radial, 208 volt radial, 480 volt network, 480/277 volt network, 480 volt radial, 480/277 volt radial).

(viii) As of December 1, 1985, combustible materials, including, but not limited to paints, solvents, plastics, paper, and sawn wood must not be stored within a PCB Transformer enclosure (i.e., in a transformer vault or in a partitioned area housing a transformer); within 5 meters of a transformer enclosure,

or, if unenclosed (unpartitioned), within 5 meters of a PCB Transformer.

(ix) A visual inspection of each PCB Transformer (as defined in the definition of "PCB Transformer" under §761.3) in use or stored for reuse shall be performed at least once every 3 months. These inspections may take place any time during the 3-month periods: January-March, April-June, July-September, and October-December as long as there is a minimum of 30 days between inspections. The visual inspection must include investigation for any leak of dielectric fluid on or around the transformer. The extent of the visual inspections will depend on the physical constraints of each transformer installation and should not require an electrical shutdown of the transformer being inspected.

(x) If a PCB Transformer is found to have a leak which results in any quantity of PCBs running off or about to run off the external surface of the transformer, then the transformer must be repaired or replaced to eliminate the source of the leak. In all cases any leaking material must be cleaned up and properly disposed of according to disposal requirements of subpart D of this part. Cleanup of the released PCBs must be initiated as soon as possible, but in no case later than 48 hours of its discovery. Until appropriate action is completed, any active leak of PCBs must be contained to prevent exposure of humans or the environment and inspected daily to verify containment of the leak. Trenches, dikes, buckets, and pans are examples of proper containment measures.

(xi) If a PCB Transformer is involved in a fire-related incident, the owner of the transformer must immediately report the incident to the National Response Center (toll-free 1-800-424-8802; in Washington, DC 202-426-2675). A fire-related incident is defined as any incident involving a PCB Transformer which involves the generation of sufficient heat and/or pressure (by any source) to result in the violent or non-violent rupture of a PCB Transformer and the release of PCBs. Information must be provided regarding the type of PCB Transformer installation involved in the fire-related incident (e.g., high or low secondary voltage network

## Environmental Protection Agency

## § 761.30

transformer, high or low secondary voltage simple radial system, expanded radial system, primary selective system, primary loop system, or secondary selective system or other systems) and the readily ascertainable cause of the fire-related incident (e.g., high current fault in the primary or secondary or low current fault in secondary). The owner of the PCB Transformer must also take measures as soon as practically and safely possible to contain and control any potential releases of PCBs and incomplete combustion products into water. These measures include, but are not limited to:

(A) The blocking of all floor drains in the vicinity of the transformer.

(B) The containment of water runoff.

(C) The control and treatment (prior to release) of any water used in subsequent cleanup operations.

(xii) Records of inspection and maintenance history shall be maintained at least 3 years after disposing of the transformer and shall be made available for inspection, upon request by EPA. Such records shall contain the following information for each PCB Transformer:

(A) Its location.

(B) The date of each visual inspection and the date that leak was discovered, if different from the inspection date.

(C) The person performing the inspection.

(D) The location of any leak(s).

(E) An estimate of the amount of dielectric fluid released from any leak.

(F) The date of any cleanup, containment, repair, or replacement.

(G) A description of any cleanup, containment, or repair performed.

(H) The results of any containment and daily inspection required for uncorrected active leaks.

(I) Record of the registration of PCB Transformer(s).

(J) Records of transfer of ownership in compliance with § 761.180(a)(2)(ix).

(xiii) A reduced visual inspection frequency of at least once every 12 months applies to PCB Transformers that utilize either of the following risk reduction measures. These inspections may take place any time during the calendar year as long as there is a minimum of 180 days between inspections.

(A) A PCB Transformer which has impervious, undrained, secondary containment capacity of at least 100 percent of the total dielectric fluid volume of all transformers so contained or

(B) A PCB Transformer which has been tested and found to contain less than 60,000 ppm PCBs (after 3 months of in service use if the transformer has been serviced for purposes of reducing the PCB concentration).

(xiv) An increased visual inspection frequency of at least once every week applies to any PCB Transformer in use or stored for reuse which poses an exposure risk to food or feed. The user of a PCB Transformer posing an exposure risk to food is responsible for the inspection, recordkeeping, and maintenance requirements under this section until the user notifies the owner that the transformer may pose an exposure risk to food or feed. Following such notification, it is the owner's ultimate responsibility to determine whether the PCB Transformer poses an exposure risk to food or feed.

(xv) In the event a mineral oil transformer, assumed to contain less than 500 ppm of PCBs as provided in § 761.2, is tested and found to be contaminated at 500 ppm or greater PCBs, it will be subject to all the requirements of this part 761. In addition, efforts must be initiated immediately to bring the transformer into compliance in accordance with the following schedule:

(A) Report fire-related incidents, effectively immediately after discovery.

(B) Mark the PCB transformer within 7 days after discovery.

(C) Mark the vault door, machinery room door, fence, hallway or other means of access to the PCB Transformer within 7 days after discovery.

(D) Register the PCB Transformer in writing with the building owner within 30 days of discovery.

(E) Install electrical protective equipment on a radial PCB Transformer and a non-sidewalk vault, lower secondary voltage network PCB Transformer in or near a commercial building within 18 months of discovery or by October 1, 1990, whichever is later.

(F) Remove a non-sidewalk vault, lower secondary voltage network PCB Transformer in or near a commercial

**§ 761.30**

**40 CFR Ch. I (7-1-10 Edition)**

building, if electrical protective equipment is not installed, within 18 months of discovery or by October 1, 1993, whichever is later.

(G) Remove a lower secondary voltage network PCB Transformer located in a sidewalk vault in or near a commercial building, within 18 months of discovery or by October 1, 1993, whichever is later.

(H) Retrofill and reclassify a radial PCB Transformer or a lower or higher secondary voltage network PCB Transformer, located in other than a sidewalk vault in or near a commercial building, within 18 months or by October 1, 1990, whichever is later. This is an option in lieu of installing electrical protective equipment on a radial or lower secondary voltage network PCB Transformer located in other than a sidewalk vault or of removing a higher secondary voltage network PCB Transformer or a lower secondary voltage network PCB Transformer, located in a sidewalk vault, from service.

(I) Retrofill and reclassify a lower secondary voltage network PCB Transformer, located in a sidewalk vault, in or near a commercial building within 18 months or by October 1, 1993, whichever is later. This is an option in lieu of installing electrical protective equipment or removing the transformer from service.

(J) Retrofill and reclassify a higher secondary voltage network PCB Transformer, located in a sidewalk vault, in or near a commercial building within 18 months or by October 1, 1990, whichever is later. This is an option in lieu of other requirements.

(2) *Servicing conditions.* (i) Transformers classified as PCB-Contaminated Electrical Equipment (as defined in the definition of "PCB-Contaminated Electrical Equipment" under § 761.3) may be serviced (including rebuilding) only with dielectric fluid containing less than 500 ppm PCB.

(ii) Any servicing (including rebuilding) of PCB Transformers (as defined in the definition of "PCB Transformer" under § 761.3) that requires the removal of the transformer coil from the transformer casing is prohibited. PCB Transformers may be serviced (including topping off) with dielectric fluid at any PCB concentration.

(iii) PCBs removed during any servicing activity must be captured and either reused as dielectric fluid or disposed of in accordance with the requirements of § 761.60. PCBs from PCB Transformers must not be mixed with or added to dielectric fluid from PCB-Contaminated Electrical Equipment.

(iv) Regardless of its PCB concentration, dielectric fluids containing less than 500 ppm PCB that are mixed with fluids that contain 500 ppm or greater PCB must not be used as dielectric fluid in any electrical equipment. The entire mixture of dielectric fluid must be considered to be greater than 500 ppm PCB and must be disposed of in an incinerator that meets the requirements in § 761.70.

(v) You may reclassify a PCB Transformer that has been tested and determined to have a concentration of  $\geq 500$  ppm PCBs to a PCB-Contaminated transformer ( $\geq 50$  but  $< 500$  ppm) or to a non-PCB transformer ( $< 50$  ppm), and you may reclassify a PCB-Contaminated transformer that has been tested and determined to have a concentration of  $\geq 50$  ppm but  $< 500$  ppm to a non-PCB transformer, as follows:

(A) Remove the free-flowing PCB dielectric fluid from the transformer. Flushing is not required. Either test the fluid or assume it contains  $\geq 1,000$  ppm PCBs. Retrofill the transformer with fluid containing known PCB levels according to the following table. Determine the transformer's reclassified status according to the following table (if following this process does not result in the reclassified status you desire, you may repeat the process):

Environmental Protection Agency

§ 761.30

| If test results show the PCB concentration (ppm) in the transformer prior to retrofit is . . . | and you retrofit the transformer with dielectric fluid containing . . . | and you . . .   | and test results show the PCB concentration (ppm) after retrofit is . . . | then the transformer's reclassified status is . . . |
|--|---|---|---|---|
| ≥1,000 (or untested)   | < 50 ppm PCBs   | operate the transformer electrically under loaded conditions for at least 90 continuous days after retrofit, then test the fluid for PCBs | ≥50 but < 500   | PCB-contaminated                                    |
|  | < 50 ppm PCBs   | operate the transformer electrically under loaded conditions for at least 90 continuous days after retrofit, then test the fluid for PCBs | <50   | non-PCB   |
| ≥500 but <1,000  | <50 ppm PCBs  | test the fluid for PCBs at least 90 days after retrofit   | ≥50 but <500  | PCB-contaminated                                    |
|  | <50 ppm PCBs  | test the fluid for PCBs at least 90 days after retrofit   | <50   | non-PCB   |
| ≥50 but <500   | ≥2 but <50 ppm PCBs   | test the fluid for PCBs at least 90 days after retrofit   | <50   | non-PCB   |
|  | <2 ppm PCBs   | (no need to test)   | (not applicable)  | non-PCB   |

(B) If you discover that the PCB concentration of the fluid in a reclassified transformer has changed, causing the reclassified status to change, the transformer is regulated based on the actual concentration of the fluid. For example, a transformer that was reclassified to non-PCB status is regulated as a PCB-contaminated transformer if you discover that the concentration of the fluid has increased to ≥50 but <500 ppm PCBs. If you discover that the PCB concentration of the fluid has risen to ≥500 ppm, the transformer is regulated as a PCB Transformer. Follow paragraphs (a)(1)(xv)(A) through (J) of this section to come into compliance with the regulations applicable to PCB Transformers. You also have the option of repeating the reclassification process.

(C) The Director, National Program Chemicals Division, may, without further rulemaking, grant approval on a case-by-case basis for the use of alternative methods to reclassify transformers. You may request an approval by writing to the Director, National Program Chemicals Division (7404), Environmental Protection Agency, 1200

Pennsylvania Ave., NW., Washington, DC 20460. Describe the equipment you plan to reclassify, the alternative reclassification method you plan to use, and test data or other evidence on the effectiveness of the method.

(D) You must keep records of the reclassification required by § 761.180(g).

(vi) Any dielectric fluid containing 50 ppm or greater PCB used for servicing transformers must be stored in accordance with the storage for disposal requirements of § 761.65.

(vii) Processing and distribution in commerce of PCBs for purposes of servicing transformers is permitted only for persons who are granted an exemption under TSCA 6(e)(3)(B).

(b) *Use in and servicing of railroad transformers.* PCBs may be used in transformers in railroad locomotives or railroad self-propelled cars ("railroad transformers") and may be processed and distributed in commerce for purposes of servicing these transformers in a manner other than a totally enclosed manner subject to the following conditions:

§761.30

40 CFR Ch. I (7-1-10 Edition)

(1) *Use restrictions.* After July 1, 1986, use of railroad transformers that contain dielectric fluids with a PCB concentration >1,000 ppm is prohibited.

(2) *Servicing restrictions.* (i) If the coil is removed from the casing of a railroad transformer (e.g., the transformer is rebuilt), after January 1, 1982, the railroad transformer may not be refilled with dielectric fluid containing a PCB concentration greater than 50 ppm;

(ii) After January 1, 1984, railroad transformers may only be serviced with dielectric fluid containing less than 1000 ppm PCB, except as provided in paragraph (b)(2)(i) of this section;

(iii) Dielectric fluid may be filtered through activated carbon or otherwise industrially processed for the purpose of reducing the PCB concentration in the fluid;

(iv) Any PCB dielectric fluid that is used to service PCB railroad transformers must be stored in accordance with the storage for disposal requirements of §761.65;

(v) After July 1, 1979, processing and distribution in commerce of PCBs for purposes of servicing railroad transformers is permitted only for persons who are granted an exemption under TSCA section 6(e)(3)(B).

(vi) A PCB Transformer may be converted to a PCB-Contaminated Transformer or to a non-PCB Transformer by draining, refilling, and/or otherwise servicing the railroad transformer. In order to reclassify, the railroad transformer's dielectric fluid must contain less than 500 ppm (for conversion to PCB-Contaminated Transformer) or less than 50 ppm PCB (for conversion to a non-PCB Transformer) after a minimum of three months of inservice use subsequent to the last servicing conducted for the purpose of reducing the PCB concentration in the transformer.

(c) *Use in mining equipment.* After January 1, 1982, PCBs may be used in mining equipment only at a concentration level of <50 ppm.

(d) *Use in heat transfer systems.* After July 1, 1984, PCBs may be used in heat transfer systems only at a concentration level of < 50 ppm. Heat transfer systems that were in operation after July 1, 1984, with a concentration level of <50 ppm PCBs may be serviced to

maintain a concentration level of <50 ppm PCBs. Heat transfer systems may only be serviced with fluids containing <50 ppm PCBs.

(e) *Use in hydraulic systems.* After July 1, 1984, PCBs may be used in hydraulic systems only at a concentration level of <50 ppm. Hydraulic systems that were in operation after July 1, 1984, with a concentration level of <50 ppm PCBs may be serviced to maintain a concentration level of <50 ppm PCBs. Hydraulic systems may only be serviced with fluids containing <50 ppm PCBs.

(f) *Use in carbonless copy paper.* Carbonless copy paper containing PCBs may be used in a manner other than a totally enclosed manner indefinitely.

(g) [Reserved]

(h) *Use in and servicing of electromagnets, switches and voltage regulators.* PCBs at any concentration may be used in electromagnets, switches (including sectionalizers and motor starters), and voltage regulators and may be used for purposes of servicing this equipment (including rebuilding) for the remainder of their useful lives, subject to the following conditions:

(1) *Use conditions.* (i) After October 1, 1985, the use and storage for reuse of any electromagnet which poses an exposure risk to food or feed is prohibited if the electromagnet contains greater than 500 ppm PCBs.

(ii) Use and storage for reuse of voltage regulators which contain 1.36 kilograms (3 lbs) or more of dielectric fluid with a PCB concentration of ≥500 ppm are subject to the following provisions:

(A) The owner of the voltage regulator must mark its location in accordance with §761.40.

(B) If a voltage regulator is involved in a fire-related incident, the owner must immediately report the incident to the National Response Center (Toll-free: 1-800-424-8802; in Washington, DC: 202-426-2675). A fire-related incident is defined as any incident that involves the generation of sufficient heat and/or pressure, by any source, to result in the violent or non-violent rupture of the voltage regulator and the release of PCBs.

(C) The owner of the voltage regulator must inspect it in accordance with the requirements of paragraphs

**Environmental Protection Agency**

**§ 761.30**

(a)(1)(ix), (a)(1)(xiii), and (a)(1)(xiv) of this section that apply to PCB Transformers.

(D) The owner of the voltage regulator must comply with the record-keeping and reporting requirements at § 761.180.

(iii) The owner of a voltage regulator that assumes it contains <500 ppm PCBs as provided in § 761.2, and discovers by testing that it is contaminated at ≥500 ppm PCBs, must comply with paragraph (h)(1)(ii)(A) of this section 7 days after the discovery, and paragraphs (h)(1)(ii)(B), (h)(1)(ii)(C), and (h)(1)(ii)(D) of this section immediately upon discovery.

(2) *Servicing conditions.* (i) Servicing (including rebuilding) any electromagnet, switch, or voltage regulator with a PCB concentration of 500 ppm or greater which requires the removal and rework of the internal components is prohibited.

(ii) Electromagnets, switches, and voltage regulators classified as PCB-Contaminated Electrical Equipment (as defined in the definition of “PCB-Contaminated Electrical Equipment” under § 761.3) may be serviced (including rebuilding) only with dielectric fluid containing less than 500 ppm PCB.

(iii) PCBs removed during any servicing activity must be captured and either reused as dielectric fluid or disposed of in accordance with the requirements of § 761.60. PCBs from electromagnets switches, and voltage regulators with a PCB concentration of at least 500 ppm must not be mixed with or added to dielectric fluid from

PCB-Contaminated Electrical Equipment.

(iv) Regardless of its PCB concentration, dielectric fluids containing less than 500 ppm PCB that are mixed with fluids that contain 500 ppm or greater PCB must not be used as dielectric fluid in any electrical equipment. The entire mixture of dielectric fluid must be considered to be greater than 500 ppm PCB and must be disposed of in an incinerator that meets the requirements of § 761.70.

(v) You may reclassify an electromagnet, switch, or voltage regulator that has been tested and determined to have a concentration of ≥500 ppm PCBs to PCB-Contaminated status (≥50 but <500 ppm) or to non-PCB status (<50 ppm), and you may reclassify a PCB-Contaminated electromagnet, switch, or voltage regulator that has been tested and determined to have a concentration of ≥50 ppm but <500 ppm to a non-PCB status, as follows:

(A) Remove the free-flowing PCB dielectric fluid from the electromagnet, switch, or voltage regulator. Flushing is not required. Either test the fluid or assume it contains ≥1,000 ppm PCBs. Refill the electromagnet, switch, or voltage regulator with fluid containing known PCB levels according to the following table. Determine the electromagnet, switch, or voltage regulator’s reclassified status according to the following table (if following this process does not result in the reclassified status you desire, you may repeat the process):

| If test results show the PCB concentration (ppm) in the equipment prior to refill is . . . | and you refill the equipment with dielectric fluid containing . . . | and you . . .   | and test results show the PCB concentration (ppm) after refill is . . . | then the electromagnet, switch, or voltage regulator’s reclassified status is . . . |
|--|---|---|---|---|
| ≥1,000 (or untested)   | <50 ppm PCBs  | operate the equipment electrically under loaded conditions for at least 90-continuous days after refill, then test the fluid for PCBs | ≥50 but <500  | PCB-contaminated  |
|  | <50 ppm PCBs  | operate the equipment electrically under loaded conditions for at least 90-continuous days after refill, then test the fluid for PCBs | <50   | non-PCB   |



| If test results show the PCB concentration (ppm) in the equipment prior to retrofit is . . . | and you retrofit the equipment with dielectric fluid containing . . . | and you . . .   | and test results show the PCB concentration (ppm) after retrofit is . . . | then the electromagnet, switch, or voltage regulator's reclassified status is . . . |
|--|---|---|---|---|
| ≥500 but <1,000  | <50 ppm PCBs  | test the fluid for PCBs at least 90 days after retrofit | ≥50 but <500  | PCB-contaminated  |
|  | <50 ppm PCBs  | test the fluid for PCBs at least 90 days after retrofit | <50   | non-PCB   |
| ≥50 but <500   | ≥2 but <50 ppm PCBs   | test the fluid for PCBs at least 90 days after retrofit | <50   | non-PCB   |
|  | <2 ppm PCBs   | (no need to test)                                       | (not applicable)  | non-PCB   |

(B) If you discover that the PCB concentration of the fluid in a reclassified electromagnet, switch, or voltage regulator has changed, causing the reclassified status to change, the electromagnet, switch, or voltage regulator is regulated based on the actual concentration of the fluid. For example, an electromagnet, switch, or voltage regulator that was reclassified to non-PCB status is regulated as a PCB-Contaminated electromagnet, switch, or voltage regulator if you discover that the concentration of the fluid has increased to ≥50 but <500 ppm PCBs. If you discover that the PCB concentration of the fluid in a voltage regulator has risen to ≥500 ppm, follow paragraph (h)(1)(iii) of this section to come into compliance with the regulations applicable to voltage regulators containing ≥500 ppm PCBs. You also have the option of repeating the reclassification process.

(C) The Director, National Program Chemicals Division may, without further rulemaking, grant approval on a case-by-case basis for the use of alternative methods to reclassify electromagnets, switches or voltage regulators. You may request an approval by writing to the Director, National Program Chemicals Division (7404), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460. Describe the equipment you plan to reclassify, the alternative reclassification method you plan to use, and test data or other evidence on the effectiveness of the method.

(D) You must keep records of the reclassification required by § 761.180(g).

(vi) Any dielectric fluid containing 50 ppm or greater PCB used for servicing electromagnets, switches, or voltage regulators must be stored in accordance with the storage for disposal requirements of § 761.65.

(vii) Processing and distribution in commerce of PCBs for purposes of servicing electromagnets, switches or voltage regulators is permitted only for persons who are granted an exemption under TSCA 6(e)(3)(B).

(i) *Use and reuse of PCBs in natural gas pipeline systems; use and reuse of PCB-Contaminated natural gas pipe and appurtenances.* (1)(i) PCBs are authorized for use in natural gas pipeline systems at concentrations <50 ppm.

(ii) PCBs are authorized for use, at concentrations ≥50 ppm, in natural gas pipeline systems not owned or operated by a seller or distributor of natural gas.

(iii)(A) PCBs are authorized for use, at concentrations ≥50 ppm, in natural gas pipeline systems owned or operated by a seller or distributor of natural gas, if the owner or operator:

(1) Submits to EPA, upon request, a written description of the general nature and location of PCBs ≥50 ppm in their natural gas pipeline system. Each written description shall be submitted to the EPA Regional Administrator having jurisdiction over the segment or component of the system (or the Director, National Program Chemicals Division, Office of Prevention, Pesticides, and Toxic Substances, if the system is contaminated in more than one region).

(2) Within 120 days after discovery of PCBs ≥50 ppm in natural gas pipeline

## Environmental Protection Agency

## § 761.30

systems, or by December 28, 1998, whichever is later, characterizes the extent of PCB contamination by collecting and analyzing samples to identify the upstream and downstream end points of the segment or component where PCBs  $\geq 50$  ppm were discovered.

(3) Within 120 days of characterization of the extent of PCB contamination, or by December 28, 1998, whichever is later, samples and analyzes all potential sources of introduction of PCBs into the natural gas pipeline system for PCBs  $\geq 50$  ppm. Potential sources include natural gas compressors, natural gas scrubbers, natural gas filters, and interconnects where natural gas is received upstream from the most downstream sampling point where PCBs  $\geq 50$  ppm were detected; potential sources exclude valves, drips, or other small liquid condensate collection points.

(4) Within 1 year of characterization of the extent of PCB contamination, reduces all demonstrated sources of PCBs  $\geq 50$  ppm to  $< 50$  ppm, or removes such sources from the natural gas pipeline system; or implements other engineering measures or methods to reduce PCB levels to  $< 50$  ppm and to prevent further introduction of PCBs  $\geq 50$  ppm into the natural gas pipeline system (e.g., pigging, decontamination, in-line filtration).

(5) Repeats sampling and analysis at least annually where PCBs are  $\geq 50$  ppm, until sampling results indicate the natural gas pipeline segment or component is  $< 50$  ppm PCB in two successive samples with a minimum interval between samples of 180 days.

(6) Marks aboveground sources of PCB liquids in natural gas pipeline systems with the M<sub>L</sub> Mark in accordance with § 761.45(a), where such sources have been demonstrated through historical data or recent sampling to contain PCBs  $\geq 50$  ppm.

(B) Owners or operators of natural gas pipeline systems which do not include potential sources of PCB contamination as described in paragraph (i)(1)(iii)(A)(3) of this section containing  $\geq 50$  ppm PCB are not subject to paragraphs (i)(1)(iii)(A)(2), (i)(1)(iii)(A)(3), (i)(1)(iii)(A)(4), or (i)(1)(iii)(A)(6) of this section. Owners or operators of these systems, however,

must comply with the other provisions of this section (e.g., sampling of any collected PCB liquids and record-keeping).

(C) The owner or operator of a natural gas pipeline system must document in writing all data collected and actions taken, or not taken, pursuant to the authorization in paragraph (i)(1)(iii)(A) of this section. They must maintain the information for 3 years after the PCB concentration in the component or segment is reduced to  $< 50$  ppm, and make it available to EPA upon request.

(D) The Director, National Program Chemicals Division, after consulting with the appropriate EPA Region(s) may, based on a finding of no unreasonable risk, modify in writing the requirements of paragraph (i)(1)(iii)(A) of this section, including extending any compliance date, approving alternative formats for documentation, waiving one or more requirements for a segment or component, requiring sampling and analysis, and requiring implementation of engineering measures to reduce PCB concentrations. EPA will make such modifications based on the natural gas pipeline system size, configuration, and current operating conditions; nature, extent or source of contamination; proximity of contamination to end-users; or previous sampling, monitoring, remedial actions or documentation of activities taken regarding compliance with this authorization or other applicable Federal, State, or local laws and regulations. The Director, National Program Chemicals Division, may defer the authority described in this paragraph, upon request, to the appropriate EPA Region.

(E) The owner or operator of a natural gas pipeline system may use historical data to fulfill the requirements of paragraphs (i)(1)(iii)(A)(1), (i)(1)(iii)(A)(2) and (i)(1)(iii)(A)(3) of this section. They may use documented historical actions taken to reduce PCB concentrations in known sources; decontaminate components or segments of natural gas pipeline systems; or otherwise to reduce PCB levels to fulfill the requirements of paragraph (i)(1)(iii)(A)(4) of this section.

(2) Any person may reuse PCB-Contaminated natural gas pipe and appurtenances in a natural gas pipeline system, provided all free-flowing liquids have been removed.

(3) Any person may use PCB-Contaminated natural gas pipe, drained of all free-flowing liquids, in the transport of liquids (e.g., bulk hydrocarbons, chemicals, petroleum products, or coal slurry), as casing to provide secondary containment or protection (e.g., protection for electrical cable), as industrial structural material (e.g., fence posts, sign posts, or bridge supports), as temporary flume at construction sites, as equipment skids, as culverts under transportation systems in intermittent flow situations, for sewage service with written consent of the Publicly Owned Treatment Works (POTW), for steam service, as irrigation systems (<20 inch diameter) of less than 200 miles in length, and in a totally enclosed compressed air system.

(4) Any person characterizing PCB contamination in natural gas pipe or natural gas pipeline systems must do so by analyzing organic liquids collected at existing condensate collection points in the pipe or pipeline system. The level of PCB contamination found at a collection point is assumed to extend to the next collection point downstream. Any person characterizing multi-phasic liquids must do so in accordance with § 761.1(b)(4); if no liquids are present, they must use standard wipe samples in accordance with subpart M of this part.

(5)(i) Any person disposing of liquids containing PCBs  $\geq 50$  ppm removed, spilled, or otherwise released from a natural gas pipeline system must do so in accordance with § 761.61(a)(5)(iv) based on the PCB concentration at the time of removal from the system. Any person disposing of materials contaminated by spills or other releases of PCBs  $\geq 50$  ppm from a natural gas pipeline system, must do so in accordance with §§ 761.61 or 761.79, as applicable.

(ii) Any person who markets or burns for energy recovery liquids containing PCBs at concentrations  $< 50$  ppm PCBs at the time of removal from a natural gas pipeline system must do so in accordance with the provisions pertaining to used oil at § 761.20(e). No

other use of liquid containing PCBs at concentrations above the quantifiable level/level of detection removed from a natural gas pipeline system is authorized.

(j) *Research and development.* For purposes of this section, authorized research and development (R&D) activities include, but are not limited to: the chemical analysis of PCBs, including analyses to determine PCB concentration; determinations of the physical properties of PCBs; studies of environmental transport processes; studies of biochemical transport processes; studies of effects of PCBs on the environment; and studies of the health effects of PCBs, including direct toxicity and toxicity of metabolic products of PCBs. Authorized R&D activities do not include research, development, or analysis for the development of any PCB product. Any person conducting R&D activities under this section is also responsible for determining and complying with all other applicable Federal, State, and local laws and regulations. Although the use of PCBs and PCBs in analytical reference samples derived from waste material is authorized in conjunction with PCB-disposal related activities, R&D for PCB disposal (as defined under § 761.3) is addressed in § 761.60(j). PCBs and PCBs in analytical reference samples derived from waste materials are authorized for use, in a manner other than a totally enclosed manner, provided that:

(1) They obtain the PCBs and PCBs in analytical reference samples derived from waste materials from sources authorized under § 761.80 to manufacture, process, and distribute PCBs in commerce and the PCBs are packaged in compliance with the Hazardous Materials Regulations at 49 CFR parts 171 through 180.

(2) They store all PCB wastes resulting from R&D activities (e.g., spent laboratory samples, residuals, contaminated media such as clothing, etc.) in compliance with § 761.65(b) and dispose of all PCB wastes in compliance with § 761.64.

(3) [Reserved]

(4) No person may manufacture, process, or distribute in commerce PCBs for research and development unless they

## Environmental Protection Agency

## § 761.30

have been granted an exemption to do so under TSCA section 6(e)(3)(B).

(k) *Use in scientific instruments.* PCBs may be used indefinitely in scientific instruments, for example, in oscillatory flow birefringence and viscoelasticity instruments for the study of the physical properties of polymers, as microscopy mounting fluids, as microscopy immersion oil, and as optical liquids in a manner other than a totally enclosed manner. No person may manufacture, process, or distribute in commerce PCBs for use in scientific instruments unless they have been granted an exemption to do so under TSCA section 6(e)(3)(B).

(l) *Use in capacitors.* PCBs at any concentration may be used in capacitors, subject to the following conditions:

(1) *Use conditions.* (i) After October 1, 1988, the use and storage for reuse of PCB Large High Voltage Capacitors and PCB Large Low Voltage Capacitors which pose an exposure risk to food or feed is prohibited.

(ii) After October 1, 1988, the use of PCB Large High Voltage Capacitors and PCB Large Low Voltage Capacitors is prohibited unless the capacitor is used within a restricted-access electrical substation or in a contained and restricted-access indoor installation. A restricted-access electrical substation is an outdoor, fenced or walled-in facility that restricts public access and is used in the transmission or distribution of electric power. A contained and restricted-access indoor installation does not have public access and has an adequate roof, walls, and floor to contain any release of PCBs within the indoor location.

(2) [Reserved]

(m) *Use in and servicing of circuit breakers, reclosers and cable.* PCBs at any concentration may be used in circuit breakers, reclosers, and cable and may be used for purposes of servicing this electrical equipment (including rebuilding) for the remainder of their useful lives, subject to the following conditions:

(1) *Servicing conditions.* (i) Circuit breakers, reclosers, and cable may be serviced (including rebuilding) only with dielectric fluid containing less than 50 ppm PCB.

(ii) Any circuit breaker, recloser or cable found to contain at least 50 ppm PCBs may be serviced only in accordance with the conditions contained in 40 CFR 761.30(h)(2).

(2) [Reserved]

(n)-(o) [Reserved]

(p) *Continued use of porous surfaces contaminated with PCBs regulated for disposal by spills of liquid PCBs.* (1) Any person may use porous surfaces contaminated by spills of liquid PCBs at concentrations  $>10 \mu\text{g}/100 \text{ cm}^2$  for the remainder of the useful life of the surfaces and subsurface material if the following conditions are met:

(i) The source of PCB contamination is removed or contained to prevent further release to porous surfaces.

(ii) If the porous surface is accessible to superficial surface cleaning:

(A) The double wash rinse procedure in subpart S of this part is conducted on the surface to remove surface PCBs.

(B) The treated surface is allowed to dry for 24 hours.

(iii) After accessible surfaces have been cleaned according to paragraph (p)(1)(ii) of this section and for all surfaces inaccessible to cleanup:

(A) The surface is completely covered to prevent release of PCBs with:

(1) Two solvent resistant and water repellent coatings of contrasting colors to allow for a visual indication of wear through or loss of outer coating integrity; or

(2) A solid barrier fastened to the surface and covering the contaminated area or all accessible parts of the contaminated area. Examples of inaccessible areas are underneath a floor-mounted electrical transformer and in an impassible space between an electrical transformer and a vault wall.

(B) The surface is marked with the  $M_L$  Mark in a location easily visible to individuals present in the area; the  $M_L$  Mark shall be placed over the encapsulated area or the barrier to the encapsulated area.

(C)  $M_L$  Marks shall be replaced when worn or illegible.

(2) Removal of a porous surface contaminated with PCBs from its location or current use is prohibited except for removal for disposal in accordance

**§ 761.35**

**40 CFR Ch. I (7-1-10 Edition)**

with §§ 761.61 or 761.79 for surfaces contaminated by spills, or § 761.62 for manufactured porous surfaces.

(q) [Reserved]

(r) *Use in and servicing of rectifiers.* Any person may use PCBs at any concentration in rectifiers for the remainder of the PCBs' useful life, and may use PCBs <50 ppm in servicing (including rebuilding) rectifiers.

(s) *Use of PCBs in air compressor systems.* (1) Any person may use PCBs in air compressor systems at concentrations <50 ppm.

(2) Any person may use PCBs in air compressor systems (or components thereof) at concentrations ≥50 ppm provided that:

(i) All free-flowing liquids containing PCBs ≥50 ppm are removed from the air compressor crankcase and the crankcase is refilled with non-PCB liquid.

(ii) Other air compressor system components contaminated with PCBs ≥50 ppm, are decontaminated in accordance with § 761.79 or disposed of in accordance with subpart D of this part.

(iii) Air compressor piping with a nominal inside diameter of <2 inches is decontaminated by continuous flushing for 4 hours, at no <300 gallons per hour (§ 761.79 contains solvent requirements).

(3) The requirements in paragraph (s)(2) of this section must be completed by August 30, 1999 or within 1 year of the date of discovery of PCBs at ≥50 ppm in the air compressor system, whichever is later. The EPA Regional Administrator for the EPA Region in which an air compressor system is located may, at his/her discretion and in writing, extend this timeframe.

(t) *Use of PCBs in other gas or liquid transmission systems.* (1) PCBs are authorized for use in intact and non-leaking gas or liquid transmission systems at concentrations <50 ppm PCBs.

(2) PCBs are authorized for use at concentrations ≥50 ppm in intact and non-leaking gas or liquid transmission systems not owned or operated by a seller or distributor of the gas or liquid transmitted in the system.

(3) Any person may use PCBs at concentrations ≥50 ppm in intact and non-leaking gas or liquid transmission systems, with the written approval of the Director, National Program Chemicals Division, subject to the requirements

applicable to natural gas pipeline systems at paragraphs (i)(1)(iii)(A), (i)(1)(iii)(C) through (i)(1)(iii)(E), and (i)(2) through (i)(5) of this section.

(u) *Use of decontaminated materials.* (1) Any person may use equipment, structures, other non-liquid or liquid materials that were contaminated with PCBs during manufacture, use, servicing, or because of spills from, or proximity to, PCBs ≥50 ppm, including those not otherwise authorized for use under this part, provided:

(i) The materials were decontaminated in accordance with:

(A) A TSCA PCB disposal approval issued under subpart D of this part;

(B) Section 761.79; or

(C) Applicable EPA PCB spill cleanup policies (e.g., TSCA, RCRA, CERCLA, EPA regional) in effect at the time of the decontamination; or

(ii) If not previously decontaminated, the materials now meet an applicable decontamination standard in § 761.79(b).

(2) No person shall use or reuse materials decontaminated in accordance with paragraph (u)(1)(i) of this section or meeting an applicable decontamination standard in paragraph (u)(1)(ii) of this section, in direct contact with food, feed, or drinking water unless otherwise allowed under this section or this part.

(3) Any person may use water containing PCBs at concentrations ≤0.5µg/L PCBs without restriction.

(4) Any person may use water containing PCBs at concentrations <200 µg/L (i.e., < 200 ppb PCBs) for non-contact use in a closed system where there are no releases (e.g., as a non-contact cooling water).

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020, 2025 (15 U.S.C. 2605))

[44 FR 31542, May 31, 1979. Redesignated at 47 FR 19527, May 6, 1982]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 761.35 see the List of CFR Sections Affected, which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 761.35 Storage for reuse.**

(a) The owner or operator of a PCB Article may store it for reuse in an area which is not designed, constructed, and operated in compliance with § 761.65(b), for no more than 5

years after the date the Article was originally removed from use (e.g., disconnected electrical equipment) or 5 years after August 28, 1998, whichever is later, if the owner or operator complies with the following conditions:

(1) Follows all use requirements at § 761.30 and marking requirements at subpart C of this part that are applicable to the PCB Article.

(2) Maintains records starting at the time the PCB Article is removed from use or August 28, 1998. The records must indicate:

(i) The date the PCB Article was removed from use or August 28, 1998, if the removal date is not known.

(ii) The projected location and the future use of the PCB Article.

(iii) If applicable, the date the PCB Article is scheduled for repair or servicing.

(b) The owner or operator of a PCB Article may store it for reuse in an area that does not comply with § 761.65(b) for a period longer than 5 years, provided that the owner or operator has received written approval from the EPA Regional Administrator for the Region in which the PCB Article is stored. An owner or operator of a PCB Article seeking approval to extend the 5-year period must submit a request for extension to the EPA Regional Administrator at least 6 months before the 5-year storage for reuse period expires and must include an item-by-item justification for the desired extension. The EPA Regional Administrator may include any conditions to such approval deemed necessary to protect health or the environment. The owner or operator of the PCB Article being stored for reuse must comply with the other applicable provisions of this part, including the record retention requirements at § 761.180(a).

(c) Any person may store a PCB Article for reuse indefinitely in:

(1) A unit in compliance with § 761.65(b).

(2) A unit permitted under section 3004 of RCRA to manage hazardous wastes in containers.

(3) A unit permitted by a State authorized under section 3006 of RCRA to manage hazardous waste.

[63 FR 35443, June 29, 1998]

### Subpart C—Marking of PCBs and PCB Items

#### § 761.40 Marking requirements.

(a) Each of the following items in existence on or after July 1, 1978 shall be marked as illustrated in Figure 1 in § 761.45(a): The mark illustrated in Figure 1 is referred to as  $M_L$  throughout this subpart.

(1) PCB Containers;

(2) PCB Transformers at the time of manufacture, at the time of distribution in commerce if not already marked, and at the time of removal from use if not already marked. [Marking of PCB-Contaminated Electrical Equipment is not required];

(3) PCB Large High Voltage Capacitors at the time of manufacture, at the time of distribution in commerce if not already marked, and at the time of removal from use if not already marked;

(4) Equipment containing a PCB Transformer or a PCB Large High Voltage Capacitor at the time of manufacture, at the time of distribution in commerce if not already marked, and at the time of removal of the equipment from use if not already marked;

(5) PCB Large Low Voltage Capacitors at the time of removal from use (see also paragraph (k) of this section).

(6) Electric motors using PCB coolants (See also paragraph (e) of this section).

(7) Hydraulic systems using PCB hydraulic fluid (See also paragraph (e) of this section);

(8) Heat transfer systems (other than PCB Transformers) using PCBs (See also paragraph (e) of this section);

(9) PCB Article Containers containing articles or equipment that must be marked under paragraphs (a) (1) through (8) of this section;

(10) Each storage area used to store PCBs and PCB Items for disposal.

(b) As of October 1, 1978, each transport vehicle loaded with PCB Containers that contain more than 45 kg (99.4 lbs.) of liquid PCBs at concentrations of  $\geq 50$  ppm or with one or more PCB Transformers shall be marked on each end and each side with the  $M_L$  mark as described in § 761.45(a).

(c) As of January 1, 1979, the following PCB Articles shall be marked

**§ 761.40**

**40 CFR Ch. I (7-1-10 Edition)**

with mark  $M_L$  as described in § 761.45(a):

(1) All PCB Transformers not marked under paragraph (a) of this section [marking of PCB-Contaminated Electrical Equipment is not required];

(2) All PCB Large High Voltage Capacitors not marked under paragraph (a) of this section

(i) Will be marked individually with mark  $M_L$ , or

(ii) If one or more PCB Large High Voltage Capacitors are installed in a protected location such as on a power pole, or structure, or behind a fence; the pole, structure, or fence shall be marked with mark  $M_L$ , and a record or procedure identifying the PCB Capacitors shall be maintained by the owner or operator at the protected location.

(d) As of January 1, 1979, all PCB Equipment containing a PCB Small Capacitor shall be marked at the time of manufacture with the statement, "This equipment contains PCB Capacitor(s)". The mark shall be of the same size as the mark  $M_L$ .

(e) As of October 1, 1979, applicable PCB Items in paragraphs (a)(1), (a)(6), (a)(7), and (a)(8) of this section containing PCBs in concentrations of 50 to 500 ppm shall be marked with the  $M_L$  mark as described in § 761.45(a).

(f) Where mark  $M_L$  is specified but the PCB Article or PCB Equipment is too small to accommodate the smallest permissible size of mark  $M_L$ , mark  $M_S$  as described in § 761.45(b), may be used instead of mark  $M_L$ .

(g) Each large low voltage capacitor, each small capacitor normally used in alternating current circuits, and each fluorescent light ballast manufactured ("manufactured", for purposes of this sentence, means built) between July 1, 1978 and July 1, 1998 that do not contain PCBs shall be marked by the manufacturer at the time of manufacture with the statement, "No PCBs". The mark shall be of similar durability and readability as other marking that indicate electrical information, part numbers, or the manufacturer's name. For purposes of this paragraph marking requirement only is applicable to items built domestically or abroad after June 30, 1978.

(h) All marks required by this subpart must be placed in a position on

the exterior of the PCB Items, storage units, or transport vehicles so that the marks can be easily read by any persons inspecting or servicing the marked PCB Items, storage units, or transport vehicles.

(i) Any chemical substance or mixture that is manufactured after the effective date of this rule and that contains less than 500 ppm PCB (0.05% on a dry weight basis), including PCB that is a byproduct or impurity, must be marked in accordance with any requirements contained in the exemption granted by EPA to permit such manufacture and is not subject to any other requirement in this subpart unless so specified in the exemption. This paragraph applies only to containers of chemical substances or mixtures. PCB articles and equipment into which the chemical substances or mixtures are processed, are subject to the marking requirements contained elsewhere in this subpart.

(j) PCB Transformer locations shall be marked as follows:

(1) Except as provided in paragraph (j)(2) of this section, as of December 1, 1985, the vault door, machinery room door, fence, hallway, or means of access, other than grates and manhole covers, to a PCB Transformer must be marked with the mark  $M_L$  as required by paragraph (a) of this section.

(2) A mark other than the  $M_L$  mark may be used provided all of the following conditions are met:

(i) The program using such an alternative mark was initiated prior to August 15, 1985, and can be substantiated with documentation.

(ii) Prior to August 15, 1985, coordination between the transformer owner and the primary fire department occurred, and the primary fire department knows, accepts, and recognizes what the alternative mark means, and that this can be substantiated with documentation.

(iii) The EPA Regional Administrator in the appropriate region is informed in writing of the use of the alternative mark by October 3, 1988 and is provided with documentation that the program began before August 15, 1985, and documentation that demonstrates that prior to that date the

## Environmental Protection Agency

## § 761.45

primary fire department knew, accepted and recognized the meaning of the mark, and included this information in firefighting training.

(iv) The Regional Administrator will either approve or disapprove in writing the use of an alternative mark within 30 days of receipt of the documentation of a program.

(3) Any mark placed in accordance with the requirements of this section must be placed in the locations described in paragraph (j)(1) of this section and in a manner that can be easily read by emergency response personnel fighting a fire involving this equipment.

(k) As of April 26, 1999 the following PCB Items shall be marked with the  $M_L$  mark as described in § 761.45(a):

(1) All PCB Large Low Voltage Capacitors not marked under paragraph (a) of this section shall be marked individually, or if one or more PCB Large Low Voltage Capacitors are installed in a protected location such as on a power pole, or structure, or behind a fence, then the owner or operator shall mark the pole, structure, or fence with the  $M_L$  mark, and maintain a record or procedure identifying the PCB Capacitors at the protected location. PCB Large Low Voltage Capacitors in inaccessible locations inside equipment need not be marked individually, provided the owner or operator marks the equipment in accordance with paragraph (k)(2) of this section, and marks the individual capacitors at the time of removal from use in accordance with paragraph (a) of this section.

(2) All equipment not marked under paragraph (a) of this section containing a PCB Transformer or a PCB Large High or Low Voltage Capacitor.

(1)(1) All voltage regulators which contain 1.36 kilograms (3 lbs.) or more of dielectric fluid with a PCB concentration of  $\geq 500$  ppm must be marked individually with the  $M_L$  mark as described in § 761.45(a).

(2) Locations of voltage regulators which contain 1.36 kilograms (3 lbs.) or more of dielectric fluid with a PCB concentration of  $\geq 500$  ppm shall be marked as follows: The vault door, machinery room door, fence, hallway, or means of access, other than grates or

manhole covers, must be marked with the  $M_L$  mark as described in § 761.45(a).

[44 FR 31542, May 31, 1979. Redesignated at 47 FR 19527, May 6, 1982, and amended at 47 FR 37359, Aug. 25, 1982; 50 FR 29201, July 17, 1985; 50 FR 32176, Aug. 9, 1985; 53 FR 12524, Apr. 15, 1988; 53 FR 27329, July 19, 1988; 63 FR 35443, June 29, 1998; 64 FR 33760, June 24, 1999]

### § 761.45 Marking formats.

The following formats shall be used for marking:

(a) *Large PCB Mark— $M_L$* . Mark  $M_L$  shall be as shown in Figure 1, letters and striping on a white or yellow background and shall be sufficiently durable to equal or exceed the life (including storage for disposal) of the PCB Article, PCB Equipment, or PCB Container. The size of the mark shall be at least 15.25 cm (6 inches) on each side. If the PCB Article or PCB Equipment is too small to accommodate this size, the mark may be reduced in size proportionately down to a minimum of 5 cm (2 inches) on each side.

(b) *Small PCB Mark— $M_s$* . Mark  $M_s$  shall be as shown in Figure 2, letters and striping on a white or yellow background, and shall be sufficiently durable to equal or exceed the life (including storage for disposal) of the PCB Article, PCB Equipment, or PCB Container. The mark shall be a rectangle 2.5 by 5 cm (1 inch by 2 inches). If the PCB Article or PCB Equipment is too small to accommodate this size, the mark may be reduced in size proportionately down to a minimum of 1 by 2 cm (.4 by .8 inches).






Figure 1




Figure 2

[44 FR 31542, May 31, 1979. Redesignated at 47 FR 19527, May 6, 1982]

**Subpart D—Storage and Disposal**

**§ 761.50 Applicability.**

(a) *General PCB disposal requirements.* Any person storing or disposing of PCB waste must do so in accordance with subpart D of this part. The following prohibitions and conditions apply to all PCB waste storage and disposal:

(1) No person may open burn PCBs. Combustion of PCBs approved under § 761.60 (a) or (e), or otherwise allowed under part 761, is not open burning.

(2) No person may process liquid PCBs into non-liquid forms to circumvent the high temperature incineration requirements of § 761.60(a).

(3) No person may discharge water containing PCBs to a treatment works (as defined § 503.9(aa) of this chapter) or to navigable waters unless the PCB concentration is <3 µg/L (approximately 3 ppb), or unless the discharge is in accordance with a PCB discharge limit included in a permit issued under

section 307(b) or 402 of the Clean Water Act.

(4) Spills and other uncontrolled discharges of PCBs at concentrations of ≥50 ppm constitute the disposal of PCBs.

(5) Any person land disposing of non-liquid PCBs may avoid otherwise-applicable sampling requirements by presuming that the PCBs disposed of are ≥500 ppm (or ≥100 µg/100 cm<sup>2</sup> if no free-flowing liquids are present).

(6) Any person storing or disposing of PCBs is also responsible for determining and complying with all other applicable Federal, State, and local laws and regulations.

(b) *PCB waste*—(1) *PCB liquids.* Any person removing PCB liquids from use (i.e., not PCB remediation waste) must dispose of them in accordance with § 761.60(a), or decontaminate them in accordance with § 761.79.

(2) *PCB Items.* Any person removing from use a PCB Item containing an intact and non-leaking PCB Article must dispose of it in accordance with § 761.60(b), or decontaminate it in accordance with § 761.79. PCB Items where the PCB Articles are no longer intact and non-leaking are regulated for disposal as PCB bulk product waste under § 761.62(a) or (c).

(i) Fluorescent light ballasts containing PCBs only in an intact and non-leaking PCB Small Capacitor are regulated for disposal under § 761.60(b)(2)(ii).

(ii) Fluorescent light ballasts containing PCBs in the potting material are regulated for disposal as PCB bulk product waste under § 761.62.

(3) *PCB remediation waste.* PCB remediation waste, including PCB sewage sludge, is regulated for cleanup and disposal in accordance with § 761.61.

(i) Any person responsible for PCB waste at as-found concentrations ≥50 ppm that was either placed in a land disposal facility, spilled, or otherwise released into the environment prior to April 18, 1978, regardless of the concentration of the spill or release; or placed in a land disposal facility, spilled, or otherwise released into the environment on or after April 18, 1978, but prior to July 2, 1979, where the concentration of the spill or release was

## Environmental Protection Agency

## § 761.50

≥50 ppm but < 500 ppm, must dispose of the waste as follows:

(A) Sites containing these wastes are presumed not to present an unreasonable risk of injury to health or the environment from exposure to PCBs at the site. However, the EPA Regional Administrator may inform the owner or operator of the site that there is reason to believe that spills, leaks, or other uncontrolled releases or discharges, such as leaching, from the site constitute ongoing disposal that may present an unreasonable risk of injury to health or the environment from exposure to PCBs at the site, and may require the owner or operator to generate data necessary to characterize the risk. If after reviewing any such data, the EPA Regional Administrator makes a finding, that an unreasonable risk exists, then he or she may direct the owner or operator of the site to dispose of the PCB remediation waste in accordance with §761.61 such that an unreasonable risk of injury no longer exists.

(B) Unless directed by the EPA Regional Administrator to dispose of PCB waste in accordance with paragraph (b)(3)(i)(A) of this section, any person responsible for PCB waste at as-found concentrations ≥50 ppm that was either placed in a land disposal facility, spilled, or otherwise released into the environment prior to April 18, 1978, regardless of the concentration of the spill or release; or placed in a land disposal facility, spilled, or otherwise released into the environment on or after April 18, 1978, but prior to July 2, 1979, where the concentration of the spill or release was ≥50 ppm but < 500 ppm, who unilaterally decides to dispose of that waste (for example, to obtain insurance or to sell the property), is not required to clean up in accordance with §761.61. Disposal of the PCB remediation waste must comply with §761.61. However, cleanup of those wastes that is not in complete compliance with §761.61 will not afford the responsible party with relief from the applicable PCB regulations for that waste.

(ii) Any person responsible for PCB waste at as-found concentrations ≥50 ppm that was either placed in a land disposal facility, spilled, or otherwise released into the environment on or

after April 18, 1978, but prior to July 2, 1979, where the concentration of the spill or release was ≥500 ppm; or placed in a land disposal facility, spilled, or otherwise released into the environment on or after July 2, 1979, where the concentration of the spill or release was ≥50 ppm, must dispose of it in accordance with either of the following:

(A) In accordance with the PCB Spill Cleanup Policy (Policy) at subpart G of this part, for those PCB remediation wastes that meet the criteria of the Policy. Consult the Policy for a description of the spills it covers and its notification and timing requirements.

(B) In accordance with §761.61. Complete compliance with §761.61 does not create a presumption against enforcement action for penalties for any unauthorized PCB disposal.

(iii) The owner or operator of a site containing PCB remediation waste has the burden of proving the date that the waste was placed in a land disposal facility, spilled, or otherwise released into the environment, and the concentration of the original spill.

(4) *PCB bulk product waste*—(i) *General*. Any person disposing of PCB bulk product waste must do so in accordance with §761.62. PCB bulk product waste, as that term is defined in §761.3, is waste that was ≥50 ppm when originally removed from service, even if its current PCB concentration is <50 ppm. PCB bulk product waste is regulated for disposal based on the risk from the waste once disposed of. For waste which is land disposed, the waste is regulated based on how readily the waste is released from disposal to the environment, in particular by leaching out from the land disposal unit.

(ii) *Metal surfaces in contact with PCBs*. Any person disposing of metal surfaces in contact with PCBs (e.g., painted metal) may use thermal decontamination procedures in accordance with §761.79(c)(6) (see §761.62(a)(6)).

(5) *PCB household waste*. Any person storing or disposing of PCB household waste, as that term is defined in §761.3, must do so in accordance with §761.63.

(6) *PCB research and development waste*. Any person disposing of PCB wastes generated during and as a result of research and development for use under §761.30(j), or for disposal under

## § 761.60

## 40 CFR Ch. I (7–1–10 Edition)

§ 761.60(j), must do so in accordance with § 761.64.

(7) *PCB/Radioactive waste.* (i) Any person storing PCB/radioactive waste  $\geq 50$  ppm PCBs must do so taking into account both its PCB concentration and its radioactive properties, except as provided in § 761.65(a)(1), (b)(1)(ii), and (c)(6)(i).

(ii) Any person disposing of PCB/radioactive waste must do so taking into account both its PCB concentration and its radioactive properties. If, taking into account only the properties of the PCBs in the waste (and not the radioactive properties of the waste), the waste meets the requirements for disposal in a facility permitted, licensed, or registered by a State as a municipal or non-municipal non-hazardous waste landfill (e.g., PCB bulk product waste under § 761.62(b)(1)), then the person may dispose of the PCB/radioactive waste, without regard to the PCB component of the waste, on the basis of its radioactive properties in accordance with all applicable requirements for the radioactive component of the waste.

(8) *Porous surfaces.* In most cases a person must dispose of porous surfaces as materials where PCBs have penetrated far beneath the surface, rather than a simple surface contamination. Any person disposing of porous surfaces on which PCBs have been spilled and meeting the definition of PCB remediation waste at § 761.3 must do so in accordance with § 761.61. Any person disposing of porous surfaces which are part of manufactured non-liquid products containing PCBs and meeting the definition of PCB bulk product waste at § 761.3 must do so in accordance with § 761.62. Any person may decontaminate concrete surfaces upon which PCBs have been spilled in accordance with § 761.79(b)(4), if the decontamination procedure is commenced within 72 hours of the initial spill of PCBs to the concrete or portion thereof being decontaminated. Any person may decontaminate porous non-liquid PCBs in contact with non-porous surfaces, such as underground metal fuel tanks coated with fire retardant resin or pitch, for purposes of unrestricted use or disposal in a smelter in accordance with § 761.79(b)(3).

(c) *Storage for disposal.* Any person who holds PCB waste must store it in accordance with § 761.65.

(d) *Performance specifications for disposal technologies—(1) Incinerators.* Any person using an incinerator to dispose of PCBs must use an incinerator that meets the criteria set forth in § 761.70.

(2) *High efficiency boilers.* Any person using a high efficiency boiler to dispose of PCBs must use a boiler that meets the criteria set forth in § 761.71.

(3) *Scrap metal recovery ovens and smelters.* Any person using scrap metal recovery ovens and smelters to dispose of PCBs must use a device that meets the criteria set forth in § 761.72.

(4) *Chemical waste landfills.* Any person using a chemical waste landfill to dispose of PCBs must use a chemical waste landfill that meets the criteria set forth in § 761.75.

(e) *TSCA PCB Coordinated Approval.* Any person seeking a TSCA PCB Coordinated Approval must follow the procedures set forth in § 761.77.

[63 FR 35444, June 29, 1998, as amended at 64 FR 33760, June 24, 1999]

### § 761.60 Disposal requirements.

(a) *PCB liquids.* PCB liquids at concentrations  $\geq 50$  ppm must be disposed of in an incinerator which complies with § 761.70, except that PCB liquids at concentrations  $\geq 50$  ppm and  $< 500$  ppm may be disposed of as follows:

(1) For mineral oil dielectric fluid, in a high efficiency boiler according to § 761.71(a).

(2) For liquids other than mineral oil dielectric fluid, in a high efficiency boiler according to § 761.71(b).

(3) For liquids from incidental sources, such as precipitation, condensation, leachate or load separation and are associated with PCB Articles or non-liquid PCB wastes, in a chemical waste landfill which complies with § 761.75 if:

(i) [Reserved]

(ii) Information is provided to or obtained by the owner or operator of the chemical waste landfill that shows that the liquids do not exceed 500 ppm PCB and are not an ignitable waste as described in § 761.75(b)(8)(iii).

## Environmental Protection Agency

## § 761.60

(b) *PCB Articles*. This paragraph does not authorize disposal that is otherwise prohibited in § 761.20 or elsewhere in this part.

(1) *Transformers*. (i) PCB Transformers shall be disposed of in accordance with either of the following:

(A) In an incinerator that complies with § 761.70; or

(B) In a chemical waste landfill approved under § 761.75; provided that all free-flowing liquid is removed from the transformer, the transformer is filled with a solvent, the transformer is allowed to stand for at least 18 continuous hours, and then the solvent is thoroughly removed. Any person disposing of PCB liquids that are removed from the transformer (including the dielectric fluid and all solvents used as a flush), shall do so in an incinerator that complies with § 761.70 of this part, or shall decontaminate them in accordance with § 761.79. Solvents may include kerosene, xylene, toluene, and other solvents in which PCBs are readily soluble. Any person disposing of these PCB liquids must ensure that the solvent flushing procedure is conducted in accordance with applicable safety and health standards as required by Federal or State regulations.

(ii) [Reserved]

(2) *PCB Capacitors*. (i) The disposal of any capacitor shall comply with all requirements of this subpart unless it is known from label or nameplate information, manufacturer's literature (including documented communications with the manufacturer), or chemical analysis that the capacitor does not contain PCBs.

(ii) Any person may dispose of PCB Small Capacitors as municipal solid waste, unless that person is subject to the requirements of paragraph (b)(2)(iv) of this section.

(iii) Any PCB Large High or Low Voltage Capacitor which contains 500 ppm or greater PCBs, owned by any person, shall be disposed of in accordance with either of the following:

(A) Disposal in an incinerator that complies with § 761.70; or

(B) Until March 1, 1981, disposal in a chemical waste landfill that complies with § 761.75.

(iv) Any person who manufactures or at any time manufactured PCB Capaci-

tors or PCB Equipment, and acquired the PCB Capacitor in the course of such manufacturing, shall place the PCB Small Capacitors in a container meeting the DOT packaging requirements at 49 CFR parts 171 through 180 and dispose of them in accordance with either of the following:

(A) Disposal in an incinerator which complies with § 761.70; or

(B) Until March 1, 1981, disposal in a chemical waste landfill which complies with § 761.75.

(v) Notwithstanding the restrictions imposed by paragraph (b)(2)(iii)(B) or (b)(2)(iv)(B) of this section, PCB capacitors may be disposed of in PCB chemical waste landfills that comply with § 761.75 subsequent to March 1, 1981, if EPA publishes a notice in the FEDERAL REGISTER declaring that those landfills are available for such disposal and explaining the reasons for the extension or reopening. An extension or reopening for disposal of PCB capacitors that is granted under this subsection shall be subject to such terms and conditions as the Assistant Administrator may prescribe and shall be in effect for such period as the Assistant Administrator may prescribe. EPA may permit disposal of PCB capacitors in EPA-approved chemical waste landfills after March 1, 1981, if in its opinion,

(A) Adequate incineration capability for PCB capacitors is not available, or

(B) The incineration of PCB capacitors will significantly interfere with the incineration of liquid PCBs, or

(C) There is other good cause shown.

As part of this evaluation, the Assistant Administrator will consider the impact of his action on the incentives to construct or expand PCB incinerators.

(vi) Any person disposing of large PCB capacitors or small PCB capacitors described in paragraph (b)(2)(iv) of this section in a chemical waste landfill approved under § 761.75, shall first place them in a container meeting the DOT packaging requirements at 49 CFR parts 171 through 180. In all cases, the person must fill the interstitial space in the container with sufficient absorbent material (such as soil) to absorb any liquid PCBs remaining in the capacitors.

(3) *PCB hydraulic machines.* (i) Any person disposing of PCB hydraulic machines containing PCBs at concentrations of  $\geq 50$  ppm, such as die casting machines, shall do so by one of the following methods:

(A) In accordance with §761.79.

(B) In a facility which is permitted, licensed, or registered by a State to manage municipal solid waste subject to part 258 of this chapter or non-municipal non-hazardous waste subject to §§257.5 through 257.30 of this chapter, as applicable (excluding thermal treatment units).

(C) In a scrap metal recovery oven or smelter operating in compliance with §761.72.

(D) In a disposal facility approved under this part.

(ii) All free-flowing liquid must be removed from each machine and the liquid must be disposed of in accordance with the provisions of paragraph (a) of this section. If the PCB liquid contains  $\geq 1,000$  ppm PCB, then the hydraulic machine must be decontaminated in accordance with §761.79 or flushed prior to disposal with a solvent listed at paragraph (b)(1)(i)(B) of this section which contains  $< 50$  ppm PCB. The solvent must be disposed of in accordance with paragraph (a) of this section or §761.79.

(4) *PCB-Contaminated Electrical Equipment.* Any person disposing of PCB-Contaminated Electrical Equipment, except capacitors, shall do so in accordance with paragraph (b)(6)(ii)(A) of this section. Any person disposing of Large Capacitors that contain  $\geq 50$  ppm but  $< 500$  ppm PCBs shall do so in a disposal facility approved under this part.

(5) *Natural gas pipeline systems containing PCBs.* The owner or operator of natural gas pipeline systems containing  $\geq 50$  ppm PCBs, when no longer in use, shall dispose of the system either by abandonment in place of the pipe under paragraph (b)(5)(i) of this section or removal with subsequent action under paragraph (b)(5)(ii) of this section. Any person determining the PCB concentrations in natural gas pipeline systems shall do so in accordance with paragraph (b)(5)(iii) of this section.

(i) *Abandonment.* Natural gas pipe containing  $\geq 50$  ppm PCBs may be aban-

doned in place under one or more of the following provisions:

(A) Natural gas pipe having a nominal inside diameter of  $\leq 4$  inches, and containing PCBs at any concentration but no free-flowing liquids, may be abandoned in the place it was used to transport natural gas if each end is sealed closed and the pipe is either:

(1) Included in a public service notification program, such as a "one-call" system under 49 CFR 192.614(a) and (b).

(2) Filled to 50 percent or more of the volume of the pipe with grout (such as a hardening slurry consisting of cement, bentonite, or clay) or high density polyurethane foam.

(B) PCB-Contaminated natural gas pipe of any diameter, where the PCB concentration was determined after the last transmission of gas through the pipe or at the time of abandonment, that contains no free-flowing liquids may be abandoned in the place it was used to transport natural gas if each end is sealed closed.

(C) Natural gas pipe of any diameter which contains PCBs at any concentration but no free-flowing liquids, may be abandoned in the place it was used to transport natural gas, if each end is sealed closed, and either:

(1) The interior surface is decontaminated with one or more washes of a solvent in accordance with the use and disposal requirements of §761.79(d). This decontamination process must result in a recovery of 95 percent of the solvent volume introduced into the system, and the PCB concentration of the recovered wash must be  $< 50$  ppm (see §761.79(a)(1) for requirements on use and disposal of decontaminating fluids).

(2) The pipe is filled to 50 percent or more of the volume of the pipe with grout (such as a hardening slurry-like cement, bentonite, or clay) or high density polyurethane foam (except that only cement shall be used as grout under rivers or streams) and each end is sealed closed.

(D) Natural gas pipe of any diameter which contains PCBs at any concentration may be abandoned in place after decontamination in accordance with §761.79(c)(3), (c)(4) or (h) or a PCB disposal approval issued under §761.60(e) or §761.61(c).

## Environmental Protection Agency

## § 761.60

(ii) *Removal with subsequent action.* Natural gas pipeline systems may be disposed of under one of the following provisions:

(A) The following classifications of natural gas pipe containing no free-flowing liquids may be disposed of in a facility permitted, licensed, or registered by a State to manage municipal solid waste subject to part 258 of this chapter or non-municipal non-hazardous waste subject to §§ 257.5 through 257.30 of this chapter, as applicable (excluding thermal treatment units); a scrap metal recovery oven or smelter operating in compliance with the requirements of § 761.72; or a disposal facility approved under this part:

(1) PCB-Contaminated natural gas pipe of any diameter where the PCB concentration was determined after the last transmission of gas through the pipe or during removal from the location it was used to transport natural gas.

(2) Natural gas pipe containing PCBs at any concentration and having a nominal inside diameter ≤ 4 inches.

(B) Any component of a natural gas pipeline system may be disposed of under one of the following provisions:

(1) In an incinerator operating in compliance with § 761.70.

(2) In a chemical waste landfill operating in compliance with § 761.75, provided that all free-flowing liquid PCBs have been thoroughly drained.

(3) As a PCB remediation waste in compliance with § 761.61.

(4) In accordance with § 761.79.

(iii) *Characterization of natural gas pipeline systems by PCB concentration in condensate.* (A) Any person disposing of a natural gas pipeline system under paragraphs (b)(5)(i)(B) or (b)(5)(ii)(A)(1) of this section must characterize it for PCB contamination by analyzing organic liquids collected at existing condensate collection points in the natural gas pipeline system. The level of PCB contamination found at a collection point is assumed to extend to the next collection point downstream. If no organic liquids are present, drain free-flowing liquids and collect standard wipe samples according to subpart M of this part. Collect condensate within 72 hours of the final transmission of natural gas through the part of the system

to be abandoned or removed. Collect wipe samples after the last transmission of gas through the pipe or during removal from the location it was used to transport natural gas.

(B) PCB concentration of the organic phase of multi-phasic liquids shall be determined in accordance with § 761.1(b)(4).

(iv) *Disposal of pipeline liquids.* (A) Any person disposing of liquids containing PCBs ≥ 50 ppm removed, spilled, or otherwise released from a natural gas pipeline system must do so in accordance with § 761.61(a)(5)(iv) based on the PCB concentration at the time of removal from the system. Any person disposing of material contaminated by spills or other releases of PCBs ≥ 50 ppm from a natural gas pipeline system, must do so in accordance with § 761.61 or § 761.79, as applicable.

(B) Any person who markets or burns for energy recovery liquid containing PCBs at concentrations < 50 ppm PCBs at the time of removal from a natural gas pipeline system must do so in accordance with the provisions pertaining to used oil at § 761.20(e). No other use of liquid containing PCBs at concentrations above the quantifiable level/level of detection removed from a natural gas pipeline system is authorized.

(6) *Other PCB Articles.* (i) PCB articles with concentrations at 500 ppm or greater must be disposed of:

(A) In an incinerator that complies with § 761.70; or

(B) In a chemical waste landfill that complies with § 761.75, provided that all free-flowing liquid PCBs have been thoroughly drained from any articles before the articles are placed in the chemical waste landfill and that the drained liquids are disposed of in an incinerator that complies with § 761.70.

(ii)(A) Except as specifically provided in paragraphs (b)(1) through (b)(5) of this section, any person disposing of a PCB-Contaminated Article must do so by removing all free-flowing liquid from the article, disposing of the liquid in accordance with paragraph (a) of this section, and disposing of the PCB-Contaminated Article with no free-flowing liquid by one of the following methods:

(1) In accordance with § 761.79.

## § 761.60

## 40 CFR Ch. I (7-1-10 Edition)

(2) In a facility permitted, licensed, or registered by a State to manage municipal solid waste subject to part 258 of this chapter or non-municipal non-hazardous waste subject to §§ 257.5 through 257.30 of this chapter, as applicable (excluding thermal treatment units).

(3) In a scrap metal recovery oven or smelter operating in compliance with § 761.72.

(4) In a disposal facility approved under this part.

(B) Storage for disposal of PCB-Contaminated Articles from which all free-flowing liquids have been removed is not regulated under subpart D of this part.

(C) Requirements in subparts J and K of this part do not apply to PCB-Contaminated Articles from which all free-flowing liquids have been removed.

(iii) Fluorescent light ballasts containing PCBs in their potting material must be disposed of in a TSCA-approved disposal facility, as bulk product waste under § 761.62, as household waste under § 761.63 (where applicable), or in accordance with the decontamination provisions of § 761.79.

(7) *Storage of PCB Articles.* Except for a PCB Article described in paragraph (b)(2)(ii) of this section and hydraulic machines that comply with the municipal solid waste disposal provisions described in paragraph (b)(3) of this section, any PCB Article, with PCB concentrations at 50 ppm or greater, shall be stored in accordance with § 761.65 prior to disposal.

(8) Persons disposing of PCB Articles must wear or use protective clothing or equipment to protect against dermal contact with or inhalation of PCBs or materials containing PCBs.

(c) *PCB Containers.* (1) Unless decontaminated in compliance with § 761.79 or as provided in paragraph (c)(2) of this section, a PCB container with PCB concentrations at 500 ppm or greater shall be disposed of:

(i) In an incinerator which complies with § 761.70, or

(ii) In a chemical waste landfill that complies with § 761.75; provided that if there are PCBs in a liquid state, the PCB Container shall first be drained and the PCB liquid disposed of in ac-

cordance with paragraph (a) of this section.

(2) Any PCB Container used to contain only PCBs at a concentration less than 500 ppm shall be disposed of as municipal solid wastes; provided that if the PCBs are in a liquid state, the PCB Container shall first be drained and the PCB liquid shall be disposed of in accordance with paragraph (a) of this section.

(3) Prior to disposal, a PCB container with PCB concentrations at 50 ppm or greater shall be stored in a unit which complies with § 761.65.

(d) [Reserved]

(e) Any person who is required to incinerate any PCBs and PCB items under this subpart and who can demonstrate that an alternative method of destroying PCBs and PCB items exists and that this alternative method can achieve a level of performance equivalent to an incinerator approved under § 761.70 or a high efficiency boiler operating in compliance with § 761.71, must submit a written request to the Regional Administrator or the Director, Office of Resource Conservation and Recovery, for a waiver from the incineration requirements of § 761.70 or § 761.71. Requests for approval of alternate methods that will be operated in more than one Region must be submitted to the Director, Office of Resource Conservation and Recovery, except for research and development activities involving less than 500 pounds of PCB material (see paragraph (i)(2) of this section). Requests for approval of alternate methods that will be operated in only one Region must be submitted to the appropriate EPA Regional Administrator. The applicant must show that his or her method of destroying PCBs will not present an unreasonable risk of injury to health or the environment. On the basis of such information and any available information, EPA may, in its discretion, approve the use of the alternate method if it finds that the alternate disposal method provides PCB destruction equivalent to disposal in a § 761.60 incinerator or a § 761.61 high efficiency boiler and will not present an unreasonable risk of injury to health or the environment. Any approval must be stated in writing and may include such

## Environmental Protection Agency

## § 761.60

conditions and provisions as EPA deems appropriate. The person to whom such waiver is issued must comply with all limitations contained in such determination. No person may use the alternate method of destroying PCBs or PCB items prior to obtaining permission from the appropriate EPA official.

(f)(1) Each operator of a chemical waste landfill, incinerator, or alternative to incineration approved under paragraph (e) of this section shall give the following written notices to the state and local governments within whose jurisdiction the disposal facility is located:

(i) Notice at least thirty (30) days before a facility is first used for disposal of PCBs required by these regulations; and

(ii) At the request of any state or local government, annual notice of the quantities and general description of PCBs disposed of during the year. This annual notice shall be given no more than thirty (30) days after the end of the year covered.

(iii) The Regional Administrator may reduce the notice period required by paragraph (f)(1)(i) of this section from thirty days to a period of no less than five days in order to expedite interim approval of the chemical waste landfill located in Sedgwick County, Kansas.

(2) [Reserved]

(g) *Testing procedures.* (1) Owners or users of mineral oil dielectric fluid electrical equipment may use the following procedures to determine the concentration of PCBs in the dielectric fluid:

(i) Dielectric fluid removed from mineral oil dielectric fluid electrical equipment may be collected in a common container, provided that no other chemical substances or mixtures are added to the container. This common container option does not permit dilution of the collected oil. Mineral oil that is assumed or known to contain at least 50 ppm PCBs must not be mixed with mineral oil that is known or assumed to contain less than 50 ppm PCBs to reduce the concentration of PCBs in the common container. If dielectric fluid from untested, oil-filled circuit breakers, reclosers, or cable is collected in a common container with

dielectric fluid from other oil-filled electrical equipment, the entire contents of the container must be treated as PCBs at a concentration of at least 50 ppm, unless all of the fluid from the other oil-filled electrical equipment has been tested and shown to contain less than 50 ppm PCBs.

(ii) For purposes of complying with the marking and disposal requirements, representative samples may be taken from either the common containers or the individual electrical equipment to determine the PCB concentration, except that if any PCBs at a concentration of 500 ppm or greater have been added to the container or equipment then the total container contents must be considered as having a PCB concentration of 500 ppm or greater for purposes of complying with the disposal requirements of this subpart. For purposes of this subparagraph, representative samples of mineral oil dielectric fluid are either samples taken in accordance with ASTM D 923-86 or ASTM D 923-89 or samples taken from a container that has been thoroughly mixed in a manner such that any PCBs in the container are uniformly distributed throughout the liquid in the container.

(iii) Unless otherwise specified in this part, any person conducting the chemical analysis of PCBs shall do so using gas chromatography. Any gas chromatographic method that is appropriate for the material being analyzed may be used, including EPA Method 608, "Organochlorine Pesticides and PCBs" at 40 CFR part 136, Appendix A;" EPA Method 8082, "Polychlorinated Biphenyls (PCBs) by Capillary Column Gas Chromatography" of SW-846, "OSW Test Methods for Evaluating Solid Waste," which is available from NTIS; and ASTM Standard D-4059, "Standard Test Method for Analysis of Polychlorinated Biphenyls in Insulating Liquids by Gas Chromatography," which is available from ASTM.

(2) Owners or users of waste oil may use the following procedures to determine the PCB concentration of waste oil:

(i) Waste oil from more than one source may be collected in a common container, provided that no other



chemical substances or mixtures, such as non-waste oils, are added to the container.

(ii) For purposes of complying with the marking and disposal requirements, representative samples may be taken from either the common containers or the individual electrical equipment to determine the PCB concentration. *Except*, That if any PCBs at a concentration of 500 ppm or greater have been added to the container or equipment then the total container contents must be considered as having a PCB concentration of 500 ppm or greater for purposes of complying with the disposal requirements of this subpart. For purposes of this paragraph, representative samples of mineral oil dielectric fluid are either samples taken in accordance with ASTM D 923-86 or ASTM D 923-89 or samples taken from a container that has been thoroughly mixed in a manner such that any PCBs in the container are uniformly distributed throughout the liquid in the container.

(iii) Unless otherwise specified in this part, any person conducting the chemical analysis of PCBs shall do so using gas chromatography. Any gas chromatographic method that is appropriate for the material being analyzed may be used, including those indicated in paragraph (g)(1)(iii) of this section.

(h) Requirements for export and import of PCBs and PCB Items for disposal are found in Subpart F of this part.

(i) *Approval authority for disposal methods.* (1) The officials designated in §§761.60(e) and 761.70 (a) and (b) to receive requests for approval of PCB disposal activities are the primary approval authorities for these activities. Notwithstanding, EPA may, at its discretion, assign the authority to review and approve any aspect of a disposal system to the Office of Solid Waste and Emergency Response or to a Regional Administrator.

(2) Except for activity authorized under paragraph (j) of this section, research and development (R&D) for PCB disposal using a total of <500 pounds of PCB material (regardless of PCB concentration) will be reviewed and approved by the EPA Regional Administrator for the Region where the R&D

will be conducted, and R&D for PCB disposal using 500 pounds or more of PCB material (regardless of PCB concentration) will be reviewed and approved by the EPA.

(j) *Self-implementing requirements for research and development (R&D) for PCB disposal.* (1) Any person may conduct R&D for PCB disposal without prior written approval from EPA if they meet the following conditions:

(i) File a notification and obtain an EPA identification number pursuant to subpart K of this part.

(ii) Notify in writing the EPA Regional Administrator, the State environmental protection agency, and local environmental protection agency, having jurisdiction where the R&D for PCB disposal activity will occur at least 30 days prior to the commencement of any R&D for PCB disposal activity conducted under this section. Each written notification shall include the EPA identification number of the site where the R&D for PCB disposal activities will be conducted, the quantity of PCBs to be treated, the type of R&D technology to be used, the general physical and chemical properties of material being treated, and an estimate of the duration of the PCB activity. The EPA Regional Administrator, the State environmental protection agency, and the local environmental protection agency may waive notification in writing prior to commencement of the research.

(iii) The amount of material containing PCBs treated annually by the facility during R&D for PCB disposal activities does not exceed 500 gallons or 70 cubic feet of liquid or non-liquid PCBs and does not exceed a maximum concentration of 10,000 ppm PCBs.

(iv) No more than 1 kilogram total of pure PCBs per year is disposed of in all R&D for PCB disposal activities at a facility.

(v) Each R&D for PCB disposal activity under this section lasts no more than 1 calendar year.

(vi) Store all PCB wastes (treated and untreated PCB materials, testing samples, spent laboratory samples, residuals, untreated samples, contaminated media or instrumentation, clothing, etc.) in compliance with §761.65(b) and dispose of them according to the

## Environmental Protection Agency

## § 761.61

undiluted PCB concentration prior to treatment. However, PCB materials not treated in the R&D for PCB disposal activity may be returned either to the physical location where the samples were collected or a location where other regulated PCBs from the physical location where the samples were collected are being stored for disposal.

(vii) Use manifests pursuant to subpart K of this part for all R&D PCB wastes being transported from the R&D facility to an approved PCB storage or disposal facility. However, §§ 761.207 through 761.218 do not apply if the residuals or treated samples are returned either to the physical location where the samples were collected or a location where other regulated PCBs from the physical location where the samples were collected are being stored for disposal.

(viii) Package and ship all PCB wastes pursuant to DOT requirements under 49 CFR parts 171 through 180.

(ix) Comply with the recordkeeping requirements of § 761.180.

(2) Do not exceed material limitations set out in paragraphs (j)(1)(iii) and (iv) of this section and the time limitation set out in paragraph (j)(1)(v) of this section without prior written approval from EPA. Requests for approval to exceed the material limitations for PCBs in R&D for PCB disposal activities as specified in this section must be submitted in writing to the EPA Regional Administrator for the Region in which the facility conducting R&D for PCB disposal activities is located. Each request shall specify the quantity or concentration requested or additional time needed for disposal and include a justification for each increase. For extensions to the duration of the R&D for PCB disposal activity, the request shall also include a report on the accomplishments and progress of the previously authorized R&D for PCB disposal activity for which the extension is sought. The EPA Regional Administrator may grant a waiver in writing for an increase in the volume of PCB material, the maximum concentration of PCBs, the total amount of pure PCBs, or the duration of the R&D activity. Approvals will state all requirements applica-

ble to the R&D for PCB disposal activity.

(3) The EPA Regional Administrator for the Region in which an R&D for PCB disposal activity is conducted may determine, at any time, that an R&D PCB disposal approval is required under paragraphs (e) and (i)(2) of this section or § 761.70(d) to ensure that any R&D for PCB disposal activity does not present an unreasonable risk of injury to health or the environment.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[44 FR 31542, May 31, 1979]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 761.60, see the List of CFR Sections Affected, which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 761.61 PCB remediation waste.

This section provides cleanup and disposal options for PCB remediation waste. Any person cleaning up and disposing of PCBs managed under this section shall do so based on the concentration at which the PCBs are found. This section does not prohibit any person from implementing temporary emergency measures to prevent, treat, or contain further releases or mitigate migration to the environment of PCBs or PCB remediation waste.

(a) *Self-implementing on-site cleanup and disposal of PCB remediation waste.* EPA designed the self-implementing procedure for a general, moderately-sized site where there should be low residual environmental impact from remedial activities. The procedure may be less practical for larger or environmentally diverse sites. For these other sites, the self-implementing procedure still applies, but an EPA Regional Administrator may authorize more practical procedures through paragraph (c) of this section. Any person may conduct self-implementing cleanup and disposal of PCB remediation waste in accordance with the following requirements without prior written approval from EPA.

(1) *Applicability.* (i) The self-implementing procedures may not be used to clean up:

(A) Surface or ground waters.

(B) Sediments in marine and freshwater ecosystems.

(C) Sewers or sewage treatment systems.

(D) Any private or public drinking water sources or distribution systems.

(E) Grazing lands.

(F) Vegetable gardens.

(ii) The self-implementing cleanup provisions shall not be binding upon cleanups conducted under other authorities, including but not limited to, actions conducted under section 104 or section 106 of CERCLA, or section 3004(u) and (v) or section 3008(h) of RCRA.

(2) *Site characterization.* Any person conducting self-implementing cleanup of PCB remediation waste must characterize the site adequately to be able to provide the information required by paragraph (a)(3) of this section. Subpart N of this part provides a method for collecting new site characterization data or for assessing the sufficiency of existing site characterization data.

(3) *Notification and certification.* (i) At least 30 days prior to the date that the cleanup of a site begins, the person in charge of the cleanup or the owner of the property where the PCB remediation waste is located shall notify, in writing, the EPA Regional Administrator, the Director of the State or Tribal environmental protection agency, and the Director of the county or local environmental protection agency where the cleanup will be conducted. The notice shall include:

(A) The nature of the contamination, including kinds of materials contaminated.

(B) A summary of the procedures used to sample contaminated and adjacent areas and a table or cleanup site map showing PCB concentrations measured in all pre-cleanup characterization samples. The summary must include sample collection and analysis dates. The EPA Regional Administrator may require more detailed information including, but not limited to, additional characterization sampling or all sample identification numbers from all previous characterization activities at the cleanup site.

(C) The location and extent of the identified contaminated area, including topographic maps with sample collection sites cross referenced to the sample identification numbers in the

data summary from paragraph (a)(3)(i)(B) of this section.

(D) A cleanup plan for the site, including schedule, disposal technology, and approach. This plan should contain options and contingencies to be used if unanticipated higher concentrations or wider distributions of PCB remediation waste are found or other obstacles force changes in the cleanup approach.

(E) A written certification, signed by the owner of the property where the cleanup site is located and the party conducting the cleanup, that all sampling plans, sample collection procedures, sample preparation procedures, extraction procedures, and instrumental/chemical analysis procedures used to assess or characterize the PCB contamination at the cleanup site, are on file at the location designated in the certificate, and are available for EPA inspection. Persons using alternate methods for chemical extraction and chemical analysis for site characterization must include in the certificate a statement that such a method will be used and that a comparison study which meets or exceeds the requirements of subpart Q of this part, and for which records are on file, has been completed prior to verification sampling.

(ii) Within 30 calendar days of receiving the notification, the EPA Regional Administrator will respond in writing approving of the self-implementing cleanup, disapproving of the self-implementing cleanup, or requiring additional information. If the EPA Regional Administrator does not respond within 30 calendar days of receiving the notice, the person submitting the notification may assume that it is complete and acceptable and proceed with the cleanup according to the information the person provided to the EPA Regional Administrator. Once cleanup is underway, the person conducting the cleanup must provide any proposed changes from the notification to the EPA Regional Administrator in writing no less than 14 calendar days prior to the proposed implementation of the change. The EPA Regional Administrator will determine in his or her discretion whether to accept the change, and will respond to the change notification verbally within 7 calendar days

## Environmental Protection Agency

## § 761.61

and in writing within 14 calendar days of receiving it. If the EPA Regional Administrator does not respond verbally within 7 calendar days and in writing within 14 calendar days of receiving the change notice, the person who submitted it may deem it complete and acceptable and proceed with the cleanup according to the information in the change notice provided to the EPA Regional Administrator.

(iii) Any person conducting a cleanup activity may obtain a waiver of the 30-day notification requirement, if they receive a separate waiver, in writing, from each of the agencies they are required to notify under this section. The person must retain the original written waiver as required in paragraph (a)(9) of this section.

(4) *Cleanup levels.* For purposes of cleaning, decontaminating, or removing PCB remediation waste under this section, there are four general waste categories: bulk PCB remediation waste, non-porous surfaces, porous surfaces, and liquids. Cleanup levels are based on the kind of material and the potential exposure to PCBs left after cleanup is completed.

(i) *Bulk PCB remediation waste.* Bulk PCB remediation waste includes, but is not limited to, the following non-liquid PCB remediation waste: soil, sediments, dredged materials, muds, PCB sewage sludge, and industrial sludge.

(A) *High occupancy areas.* The cleanup level for bulk PCB remediation waste in high occupancy areas is  $\leq 1$  ppm without further conditions. High occupancy areas where bulk PCB remediation waste remains at concentrations  $> 1$  ppm and  $\leq 10$  ppm shall be covered with a cap meeting the requirements of paragraphs (a)(7) and (a)(8) of this section.

(B) *Low occupancy areas.* (1) The cleanup level for bulk PCB remediation waste in low occupancy areas is  $\leq 25$  ppm unless otherwise specified in this paragraph.

(2) Bulk PCB remediation wastes may remain at a cleanup site at concentrations  $> 25$  ppm and  $\leq 50$  ppm if the site is secured by a fence and marked with a sign including the  $M_L$  mark.

(3) Bulk PCB remediation wastes may remain at a cleanup site at concentrations  $> 25$  ppm and  $\leq 100$  ppm if

the site is covered with a cap meeting the requirements of paragraphs (a)(7) and (a)(8) of this section.

(ii) *Non-porous surfaces.* In high occupancy areas, the surface PCB cleanup standard is  $\leq 10$   $\mu\text{g}/100$   $\text{cm}^2$  of surface area. In low occupancy areas, the surface cleanup standard is  $< 100$   $\mu\text{g}/100$   $\text{cm}^2$  of surface area. Select sampling locations in accordance with subpart P of this part or a sampling plan approved under paragraph (c) of this section.

(iii) *Porous surfaces.* In both high and low occupancy areas, any person disposing of porous surfaces must do so based on the levels in paragraph (a)(4)(i) of this section. Porous surfaces may be cleaned up for use in accordance with § 761.79(b)(4) or § 761.30(p).

(iv) *Liquids.* In both high and low occupancy areas, cleanup levels are the concentrations specified in § 761.79(b)(1) and (b)(2).

(v) *Change in the land use for a cleanup site.* Where there is an actual or proposed change in use of an area cleaned up to the levels of a low occupancy area, and the exposure of people or animal life in or at that area could reasonably be expected to increase, resulting in a change in status from a low occupancy area to a high occupancy area, the owner of the area shall clean up the area in accordance with the high occupancy area cleanup levels in paragraphs (a)(4)(i) through (a)(4)(iv) of this section.

(vi) The EPA Regional Administrator, as part of his or her response to a notification submitted in accordance with § 761.61(a)(3) of this part, may require cleanup of the site, or portions of it, to more stringent cleanup levels than are otherwise required in this section, based on the proximity to areas such as residential dwellings, hospitals, schools, nursing homes, playgrounds, parks, day care centers, endangered species habitats, estuaries, wetlands, national parks, national wildlife refuges, commercial fisheries, and sport fisheries.

(5) *Site cleanup.* In addition to the options set out in this paragraph, PCB disposal technologies approved under §§ 761.60 and 761.70 are acceptable for

on-site self-implementing PCB remediation waste disposal within the confines of the operating conditions of the respective approvals.

(i) *Bulk PCB remediation waste.* Any person cleaning up bulk PCB remediation waste shall do so to the levels in paragraph (a)(4)(i) of this section.

(A) Any person cleaning up bulk PCB remediation waste on-site using a soil washing process may do so without EPA approval, subject to all of the following:

- (1) A non-chlorinated solvent is used.
- (2) The process occurs at ambient temperature.
- (3) The process is not exothermic.
- (4) The process uses no external heat.
- (5) The process has secondary containment to prevent any solvent from being released to the underlying or surrounding soils or surface waters.

(6) Solvent disposal, recovery, and/or reuse is in accordance with relevant provisions of approvals issued according to paragraphs (b)(1) or (c) of this section or applicable paragraphs of §761.79.

(B) Bulk PCB remediation waste may be sent off-site for decontamination or disposal in accordance with this paragraph, provided the waste is either dewatered on-site or transported off-site in containers meeting the requirements of the DOT Hazardous Materials Regulations (HMR) at 49 CFR parts 171 through 180.

(1) Removed water shall be disposed of according to paragraph (b)(1) of this section.

(2) Any person disposing off-site of dewatered bulk PCB remediation waste shall do so as follows:

(i) Unless sampled and analyzed for disposal according to the procedures set out in §§761.283, 761.286, and 761.292, the bulk PCB remediation waste shall be assumed to contain  $\geq 50$  ppm PCBs.

(ii) Bulk PCB remediation wastes with a PCB concentration of  $< 50$  ppm shall be disposed of in accordance with paragraph (a)(5)(v)(A) of this section.

(iii) Bulk PCB remediation wastes with a PCB concentration  $\geq 50$  ppm shall be disposed of in a hazardous waste landfill permitted by EPA under section 3004 of RCRA, or by a State authorized under section 3006 of RCRA, or

a PCB disposal facility approved under this part.

(iv) The generator must provide written notice, including the quantity to be shipped and highest concentration of PCBs (using extraction EPA Method 3500B/3540C or Method 3500B/3550B followed by chemical analysis using EPA Method 8082 in SW-846 or methods validated under subpart Q of this part) at least 15 days before the first shipment of bulk PCB remediation waste from each cleanup site by the generator, to each off-site facility where the waste is destined for an area not subject to a TSCA PCB Disposal Approval.

(3) Any person may decontaminate bulk PCB remediation waste in accordance with §761.79 and return the waste to the cleanup site for disposal as long as the cleanup standards of paragraph (a)(4) of this section are met.

(ii) *Non-porous surfaces.* PCB remediation waste non-porous surfaces shall be cleaned on-site or off-site for disposal on-site, disposal off-site, or use, as follows:

(A) For on-site disposal, non-porous surfaces shall be cleaned on-site or off-site to the levels in paragraph (a)(4)(ii) of this section using:

(1) Procedures approved under §761.79.

(2) Technologies approved under §761.60(e).

(3) Procedures or technologies approved under paragraph (c) of this section.

(B) For off-site disposal, non-porous surfaces:

(1) Having surface concentrations  $< 100$   $\mu\text{g}/100$   $\text{cm}^2$  shall be disposed of in accordance with paragraph (a)(5)(i)(B)(2)(ii) of this section. Metal surfaces may be thermally decontaminated in accordance with §761.79(c)(6)(i).

(2) Having surface concentrations  $\geq 100$   $\mu\text{g}/100$   $\text{cm}^2$  shall be disposed of in accordance with paragraph (a)(5)(i)(B)(2)(iii) of this section. Metal surfaces may be thermally decontaminated in accordance with §761.79(c)(6)(ii).

(C) For use, non-porous surfaces shall be decontaminated on-site or off-site to the standards specified in §761.79(b)(3) or in accordance with §761.79(c).

## Environmental Protection Agency

## § 761.61

(iii) *Porous surfaces.* Porous surfaces shall be disposed on-site or off-site as bulk PCB remediation waste according to paragraph (a)(5)(i) of this section or decontaminated for use according to § 761.79(b)(4), as applicable.

(iv) *Liquids.* Any person disposing of liquid PCB remediation waste shall either:

(A) Decontaminate the waste to the levels specified in § 761.79(b)(1) or (b)(2).

(B) Dispose of the waste in accordance with paragraph (b) of this section or an approval issued under paragraph (c) of this section.

(v) *Cleanup wastes.* Any person generating the following wastes during and from the cleanup of PCB remediation waste shall dispose of or reuse them using one of the following methods:

(A) Non-liquid cleaning materials and personal protective equipment waste at any concentration, including non-porous surfaces and other non-liquid materials such as rags, gloves, booties, other disposable personal protective equipment, and similar materials resulting from cleanup activities shall be either decontaminated in accordance with § 761.79(b) or (c), or disposed of in one of the following facilities, without regard to the requirements of subparts J and K of this part:

(1) A facility permitted, licensed, or registered by a State to manage municipal solid waste subject to part 258 of this chapter.

(2) A facility permitted, licensed, or registered by a State to manage non-municipal non-hazardous waste subject to §§ 257.5 through 257.30 of this chapter, as applicable.

(3) A hazardous waste landfill permitted by EPA under section 3004 of RCRA, or by a State authorized under section 3006 of RCRA.

(4) A PCB disposal facility approved under this part.

(B) Cleaning solvents, abrasives, and equipment may be reused after decontamination in accordance with § 761.79.

(6) *Cleanup verification*—(i) *Sampling and analysis.* Any person collecting and analyzing samples to verify the cleanup and on-site disposal of bulk PCB remediation wastes and porous surfaces must do so in accordance with subpart O of this part. Any person collecting and analyzing samples from non-porous

surfaces must do so in accordance with subpart P of this part. Any person collecting and analyzing samples from liquids must do so in accordance with § 761.269. Any person conducting interim sampling during PCB remediation waste cleanup to determine when to sample to verify that cleanup is complete, may use PCB field screening tests.

(ii) *Verification.* (A) Where sample analysis results in a measurement of PCBs less than or equal to the levels specified in paragraph (a)(4) of this section, self-implementing cleanup is complete.

(B) Where sample analysis results in a measurement of PCBs greater than the levels specified in paragraph (a)(4) of this section, self-implementing cleanup of the sampled PCB remediation waste is not complete. The owner or operator of the site must either dispose of the sampled PCB remediation waste, or reclean the waste represented by the sample and reinitiate sampling and analysis in accordance with paragraph (a)(6)(i) of this section.

(7) *Cap requirements.* A cap means, when referring to on-site cleanup and disposal of PCB remediation waste, a uniform placement of concrete, asphalt, or similar material of minimum thickness spread over the area where remediation waste was removed or left in place in order to prevent or minimize human exposure, infiltration of water, and erosion. Any person designing and constructing a cap must do so in accordance with § 264.310(a) of this chapter, and ensure that it complies with the permeability, sieve, liquid limit, and plasticity index parameters in § 761.75(b)(1)(ii) through (b)(1)(v). A cap of compacted soil shall have a minimum thickness of 25 cm (10 inches). A concrete or asphalt cap shall have a minimum thickness of 15 cm (6 inches). A cap must be of sufficient strength to maintain its effectiveness and integrity during the use of the cap surface which is exposed to the environment. A cap shall not be contaminated at a level  $\geq 1$  ppm PCB per Aroclor<sup>TM</sup> (or equivalent) or per congener. Repairs shall begin within 72 hours of discovery for any breaches which would impair the integrity of the cap.

## §761.61

## 40 CFR Ch. I (7-1-10 Edition)

(8) *Deed restrictions for caps, fences and low occupancy areas.* When a cleanup activity conducted under this section includes the use of a fence or a cap, the owner of the site must maintain the fence or cap, in perpetuity. In addition, whenever a cap, or the procedures and requirements for a low occupancy area, is used, the owner of the site must meet the following conditions:

(i) Within 60 days of completion of a cleanup activity under this section, the owner of the property shall:

(A) Record, in accordance with State law, a notation on the deed to the property, or on some other instrument which is normally examined during a title search, that will in perpetuity notify any potential purchaser of the property:

(1) That the land has been used for PCB remediation waste disposal and is restricted to use as a low occupancy area as defined in §761.3.

(2) Of the existence of the fence or cap and the requirement to maintain the fence or cap.

(3) The applicable cleanup levels left at the site, inside the fence, and/or under the cap.

(B) Submit a certification, signed by the owner, that he/she has recorded the notation specified in paragraph (a)(8)(i)(A) of this section to the EPA Regional Administrator.

(ii) The owner of a site being cleaned up under this section may remove a fence or cap after conducting additional cleanup activities and achieving cleanup levels, specified in paragraph (a)(4) of this section, which do not require a cap or fence. The owner may remove the notice on the deed no earlier than 30 days after achieving the cleanup levels specified in this section which do not require a fence or cap.

(9) *Recordkeeping.* For paragraphs (a)(3), (a)(4), and (a)(5) of this section, recordkeeping is required in accordance with §761.125(c)(5).

(b) *Performance-based disposal.* (1) Any person disposing of liquid PCB remediation waste shall do so according to §761.60(a) or (e), or decontaminate it in accordance with §761.79.

(2) Any person disposing of non-liquid PCB remediation waste shall do so by one of the following methods:

(i) Dispose of it in a high temperature incinerator approved under §761.70(b), an alternate disposal method approved under §761.60(e), a chemical waste landfill approved under §761.75, or in a facility with a coordinated approval issued under §761.77.

(ii) Decontaminate it in accordance with §761.79.

(3) Any person may manage or dispose of material containing <50 ppm PCBs that has been dredged or excavated from waters of the United States:

(i) In accordance with a permit that has been issued under section 404 of the Clean Water Act, or the equivalent of such a permit as provided for in regulations of the U.S. Army Corps of Engineers at 33 CFR part 320.

(ii) In accordance with a permit issued by the U.S. Army Corps of Engineers under section 103 of the Marine Protection, Research, and Sanctuaries Act, or the equivalent of such a permit as provided for in regulations of the U.S. Army Corps of Engineers at 33 CFR part 320.

(c) *Risk-based disposal approval.* (1) Any person wishing to sample, cleanup, or dispose of PCB remediation waste in a manner other than prescribed in paragraphs (a) or (b) of this section, or store PCB remediation waste in a manner other than prescribed in §761.65, must apply in writing to the Regional Administrator in the Region where the sampling, cleanup, disposal, or storage site is located, for sampling, cleanup, disposal, or storage occurring in a single EPA Region; or to the Director, Office of Resource Conservation and Recovery, for sampling, cleanup, disposal, or storage occurring in more than one EPA Region. Each application must include information described in the notification required by paragraph (a)(3) of this section. EPA may request other information that it believes necessary to evaluate the application. No person may conduct cleanup activities under this paragraph prior to obtaining written approval by EPA.

(2) EPA will issue a written decision on each application for a risk-based method for PCB remediation wastes. EPA will approve such an application if it finds that the method will not pose

## Environmental Protection Agency

## § 761.62

an unreasonable risk of injury to health or the environment.

[63 FR 35448, June 29, 1998, as amended at 64 FR 33761, June 24, 1999; 72 FR 57239, Oct. 9, 2007; 74 FR 30232, June 25, 2009]

### § 761.62 Disposal of PCB bulk product waste.

PCB bulk product waste shall be disposed of in accordance with paragraph (a), (b), or (c) of this section. Under some of these provisions, it may not be necessary to determine the PCB concentration or leaching characteristics of the PCB bulk product waste. When it is necessary to analyze the waste to make either of these determinations, use the applicable procedures in subpart R of this part to sample the waste for analysis, unless EPA approves another sampling plan under paragraph (c) of this section.

(a) *Performance-based disposal.* Any person disposing of PCB bulk product waste may do so as follows:

(1) In an incinerator approved under § 761.70.

(2) In a chemical waste landfill approved under § 761.75.

(3) In a hazardous waste landfill permitted by EPA under section 3004 of RCRA, or by a State authorized under section 3006 of RCRA.

(4) Under an alternate disposal approval under § 761.60(e).

(5) In accordance with the decontamination provisions of § 761.79.

(6) For metal surfaces in contact with PCBs, in accordance with the thermal decontamination provisions of § 761.79(c)(6).

(7) In accordance with a TSCA PCB Coordinated Approval issued under § 761.77.

(b) *Disposal in solid waste landfills.* (1) Any person may dispose of the following PCB bulk product waste in a facility permitted, licensed, or registered by a State as a municipal or non-municipal non-hazardous waste landfill:

(i) Plastics (such as plastic insulation from wire or cable; radio, television and computer casings; vehicle parts; or furniture laminates); preformed or molded rubber parts and components; applied dried paints, varnishes, waxes or other similar coatings or sealants; caulking; Galbestos; non-liquid building demolition debris; or non-liquid

PCB bulk product waste from the shredding of automobiles or household appliances from which PCB small capacitors have been removed (shredder fluff).

(ii) Other PCB bulk product waste, sampled in accordance with the protocols set out in subpart R of this part, that leaches PCBs at <10 µg/L of water measured using a procedure used to simulate leachate generation.

(2) Any person may dispose of PCB bulk product waste other than those materials meeting the conditions of paragraph (b)(1) of this section, (e.g., paper or felt gaskets contaminated by liquid PCBs in a facility that is permitted, licensed, or registered by a State to manage municipal solid waste subject to part 258 of this chapter or non-municipal non-hazardous waste subject to §§ 257.5 through 257.30 of this chapter, as applicable, if:

(i) The PCB bulk product waste is segregated from organic liquids disposed of in the landfill unit.

(ii) Leachate is collected from the landfill unit and monitored for PCBs.

(3) Any release of PCBs (including but not limited to leachate) from the landfill unit shall be cleaned up in accordance with § 761.61.

(4)(i) Any person disposing off-site of PCB bulk product waste regulated under paragraph (b)(1) of this section at a waste management facility not having a commercial PCB storage or disposal approval must provide written notice to the facility a minimum of 15 days in advance of the first shipment from the same disposal waste stream. The notice shall state that the PCB bulk product waste may include components containing PCBs at ≥50 ppm based on analysis of the waste in the shipment or application of a general knowledge of the waste stream (or similar material) which is known to contain PCBs at those levels, and that the PCB bulk product waste is known or presumed to leach <10 µg/L PCBs.

(ii) Any person disposing off-site of PCB bulk product waste regulated under paragraph (b)(2) of this section at a waste management facility not having a commercial PCB storage or disposal approval must provide written notice to the facility a minimum of 15 days in advance of the first shipment



## § 761.63

from the same disposal waste stream and with each shipment thereafter. The notice shall state that the PCB bulk product waste may include components containing PCBs at  $\geq 50$  ppm based on analysis of the waste in the shipment or application of a general knowledge of the waste stream (or similar material) which is known to contain PCBs at those levels, and that the PCB bulk product waste is known or presumed to leach  $\geq 10$   $\mu\text{g/L}$  PCBs.

(5) Any person disposing of PCB bulk product waste must maintain a written record of all sampling and analysis of PCBs or notifications made under this paragraph for 3 years from the date of the waste's generation. The records must be made available to EPA upon request.

(6) Requirements in subparts C, J, and K of this part do not apply to waste disposed of under paragraph (b) of this section.

(c) *Risk-based disposal approval.* (1) Any person wishing to sample or dispose of PCB bulk product waste in a manner other than prescribed in paragraphs (a) or (b) of this section, or store PCB bulk product waste in a manner other than prescribed in § 761.65, must apply in writing to the Regional Administrator in the Region where the sampling, disposal, or storage site is located, for sampling, disposal, or storage occurring in a single EPA Region; or to the Director, Office of Resource Conservation and Recovery, for sampling, disposal, or storage occurring in more than one EPA Region. Each application must contain information indicating that, based on technical, environmental, or waste-specific characteristics or considerations, the proposed sampling, disposal, or storage methods or locations will not pose an unreasonable risk or injury to health or the environment. EPA may request other information that it believes necessary to evaluate the application. No person may conduct sampling, disposal, or storage activities under this paragraph prior to obtaining written approval by EPA.

(2) EPA will issue a written decision on each application for a risk-based sampling, disposal, or storage method for PCB bulk product wastes. EPA will approve such an application if it finds

## 40 CFR Ch. I (7-1-10 Edition)

that the method will not pose an unreasonable risk of injury to health or the environment.

(d) *Disposal as daily landfill cover or roadbed.* Bulk product waste described in paragraph (b)(1) of this section may be disposed of:

(1) As daily landfill cover as long as the daily cover remains in the landfill and is not released or dispersed by wind or other action; or

(2) Under asphalt as part of a road bed.

[63 FR 35451, June 29, 1998, as amended at 64 FR 33761, June 24, 1999; 72 FR 57239, Oct. 9, 2007; 74 FR 30232, June 25, 2009]

### § 761.63 PCB household waste storage and disposal.

PCB household waste, as defined at § 761.3, managed in a facility permitted, licensed, or registered by a State to manage municipal or industrial solid waste, or in a facility with an approval to dispose of PCB bulk product waste under § 761.62(c), is not subject to any other requirements of part 761 of this chapter. PCB household waste stored in a unit regulated for storage of PCB waste must not be commingled with PCB waste.

[63 FR 35452, June 29, 1998]

### § 761.64 Disposal of wastes generated as a result of research and development activities authorized under § 761.30(j) and chemical analysis of PCBs.

This section provides disposal requirements for wastes generated during and as a result of research and development authorized under § 761.30(j). This section also provides disposal requirements for wastes generated during the chemical analysis of samples containing PCBs under part 761, including §§ 761.30, 761.60, 761.61, 761.62, and 761.79. For determining the presence of PCBs in samples, chemical analysis includes: sample preparation, sample extraction, extract cleanup, extract concentration, addition of PCB standards, and instrumental analysis.

(a) Portions of samples of a size designated in a chemical extraction and analysis method for PCBs and extracted for purposes of determining the presence of PCBs or concentration of

## Environmental Protection Agency

## § 761.65

PCBs are unregulated for PCB disposal under this part.

(b) All other wastes generated during these activities are regulated for disposal based on their concentration at the time of disposal as follows:

(1) Liquid wastes, including rinse solvents, must be disposed of according to § 761.61(a)(5)(iv).

(2) Non-liquid wastes must be disposed of in the same manner as non-liquid cleaning materials and personal protective equipment waste according to § 761.61(a)(5)(v)(A).

[63 FR 35452, June 29, 1998]

### § 761.65 Storage for disposal.

This section applies to the storage for disposal of PCBs at concentrations of 50 ppm or greater and PCB Items with PCB concentrations of 50 ppm or greater.

(a)(1) *Storage limitations.* Any PCB waste shall be disposed of as required by subpart D of this part within 1-year from the date it was determined to be PCB waste and the decision was made to dispose of it. This date is the date of removal from service for disposal and the point at which the 1-year time frame for disposal begins. PCB/radioactive waste removed from service for disposal is exempt from the 1-year time limit provided that the provisions at paragraphs (a)(2)(ii) and (a)(2)(iii) of this section are followed and the waste is managed in accordance with all other applicable Federal, State, and local laws and regulations for the management of radioactive material.

(2) *One-year extension.* Any person storing PCB waste that is subject to the 1-year time limit for storage and disposal in paragraph (a)(1) of this section may provide written notification to the EPA Regional Administrator for the Region in which the PCB waste is stored that their continuing attempts to dispose of or secure disposal for their waste within the 1-year time limit have been unsuccessful. Upon receipt of the notice by the EPA Regional Administrator, the time for disposal is automatically extended for 1 additional year (2 years total) if the following conditions are met:

(i) The notification is received by the EPA Regional Administrator at least 30 days before the initial 1-year time

limit expires and the notice identifies the storer, the types, volumes, and locations of the waste and the reasons for failure to meet the initial 1-year time limit.

(ii) A written record documenting all continuing attempts to secure disposal is maintained until the waste is disposed of.

(iii) The written record required by paragraph (a)(2)(ii) of this section is available for inspection or submission if requested by EPA.

(iv) Continuing attempts to secure disposal were initiated within 270 days after the time the waste was first subject to the 1-year time limit requirement, as specified in paragraph (a)(1) of this section. Failure to initiate and continue attempts to secure disposal throughout the total time the waste is in storage shall automatically disqualify the notifier from receiving an automatic extension under this section.

(3) *Additional extensions.* Upon written request, the EPA Regional Administrator for the Region in which the wastes are stored or the appropriate official at EPA Headquarters, may grant additional extensions beyond the 1-year extension authorized in paragraph (a)(2) of this section. At the time of the request, the requestor must supply specific justification for the additional extension and indicate what measures the requestor is taking to secure disposal of the waste or indicate why disposal could not be conducted during the period of the prior extension. The EPA Regional Administrator or the appropriate official at EPA Headquarters may require, as a condition to granting any extension under this section, specific actions including, but not limited to, marking, inspection, recordkeeping, or financial assurance to ensure that the waste does not pose an unreasonable risk of injury to health or the environment.

(4) *Storage at an approved facility.* Increased time for storage may be granted as a condition of any TSCA PCB storage or disposal approval, by the EPA Regional Administrator for the Region in which the PCBs or PCB Items are to be stored or disposed of, or by the appropriate official at EPA Headquarters, if EPA determines that

there is a demonstrated need or justification for additional time, that the owner or operator of the facility is pursuing relevant treatment or disposal options, and that no unreasonable risk of injury to health or the environment will result from the increased storage time. In making this determination, EPA will consider such factors as absence of any approved treatment technology and insufficient time to complete the treatment or destruction process. EPA may require as a condition of the approval that the owner or operator submit periodic progress reports.

(b) Except as provided in paragraphs (b)(2), (c)(1), (c)(7), (c)(9), and (c)(10) of this section, after July 1, 1978, owners or operators of any facilities used for the storage of PCBs and PCB Items designated for disposal shall comply with the following storage unit requirements:

(1) The facilities shall meet the following criteria:

(i) Adequate roof and walls to prevent rain water from reaching the stored PCBs and PCB Items;

(ii) An adequate floor that has continuous curbing with a minimum 6 inch high curb. The floor and curbing must provide a containment volume equal to at least two times the internal volume of the largest PCB Article or PCB Container or 25 percent of the total internal volume of all PCB Articles or PCB Containers stored there, whichever is greater. PCB/radioactive wastes are not required to be stored in an area with a minimum 6 inch high curbing. However, the floor and curbing must still provide a containment volume equal to at least two times the internal volume of the largest PCB Container or 25 percent of the total internal volume of all PCB Containers stored there, whichever is greater.

(iii) No drain valves, floor drains, expansion joints, sewer lines, or other openings that would permit liquids to flow from the curbed area;

(iv) Floors and curbing constructed of Portland cement, concrete, or a continuous, smooth, non-porous surface as defined at § 761.3, which prevents or minimizes penetration of PCBs.

(v) Not located at a site that is below the 100-year flood water elevation.

(2) No person may store PCBs and PCB Items designated for disposal in a storage unit other than one approved pursuant to paragraph (d) of this section or meeting the design requirements of paragraph (b) of this section, unless the unit meets one of the following conditions:

(i) Is permitted by EPA under section 3004 of RCRA to manage hazardous waste in containers, and spills of PCBs are cleaned up in accordance with subpart G of this part.

(ii) Qualifies for interim status under section 3005 of RCRA to manage hazardous waste in containers, meets the requirements for containment at § 264.175 of this chapter, and spills of PCBs are cleaned up in accordance with subpart G of this part.

(iii) Is permitted by a State authorized under section 3006 of RCRA to manage hazardous waste in containers, and spills of PCBs are cleaned up in accordance with subpart G of this part.

(iv) Is approved or otherwise regulated pursuant to a State PCB waste management program no less stringent in protection of health or the environment than the applicable TSCA requirements found in this part.

(v) Is subject to a TSCA Coordinated Approval, which includes provisions for storage of PCBs, issued pursuant to § 761.77.

(vi) Has a TSCA PCB waste management approval, which includes provisions for storage, issued pursuant to § 761.61(c) or § 761.62(c).

(c)(1) The following PCB Items may be stored temporarily in an area that does not comply with the requirements of paragraph (b) of this section for up to thirty days from the date of their removal from service, provided that a notation is attached to the PCB Item or a PCB Container (containing the item) indicating the date the item was removed from service:

(i) Non-leaking PCB Articles and PCB Equipment;

(ii) Leaking PCB Articles and PCB Equipment if the PCB Items are placed in a non-leaking PCB Container that contains sufficient sorbent materials to absorb any liquid PCBs remaining in the PCB Items;

## Environmental Protection Agency

## § 761.65

(iii) PCB Containers containing non-liquid PCBs such as contaminated soil, rags, and debris; and

(iv) PCB containers containing liquid PCBs at concentrations of  $\geq 50$  ppm, provided a Spill Prevention, Control and Countermeasure Plan has been prepared for the temporary storage area in accordance with part 112 of this chapter and the liquid PCB waste is in packaging authorized in the DOT Hazardous Materials Regulations at 49 CFR parts 171 through 180 or stationary bulk storage tanks (including rolling stock such as, but not limited to, tanker trucks, as specified by DOT).

(2) Non-leaking and structurally undamaged PCB Large High Voltage Capacitors and PCB-Contaminated Electrical Equipment that have not been drained of free flowing dielectric fluid may be stored on pallets next to a storage facility that meets the requirements of paragraph (b) of this section. PCB-Contaminated Electrical Equipment that has been drained of free flowing dielectric fluid is not subject to the storage provisions of § 761.65. Storage under this subparagraph will be permitted only when the storage facility has immediately available unfilled storage space equal to 10 percent of the volume of capacitors and equipment stored outside the facility. The capacitors and equipment temporarily stored outside the facility shall be checked for leaks weekly.

(3) Any storage area subject to the requirements of paragraph (b) or paragraph (c)(1) of this section shall be marked as required in subpart C § 761.40(a)(10).

(4) No item of movable equipment that is used for handling PCBs and PCB Items in the storage units and that comes in direct contact with PCBs shall be removed from the storage unit area unless it has been decontaminated as specified in § 761.79.

(5) All PCB Items in storage shall be checked for leaks at least once every 30 days. Any leaking PCB Items and their contents shall be transferred immediately to properly marked non-leaking containers. Any spilled or leaked materials shall be immediately cleaned up and the materials and residues containing PCBs shall be disposed of in accordance with § 761.61. Records of in-

spection, maintenance, cleanup and disposal must be maintained in accordance with § 761.180(a) and (b).

(6) Except as provided in paragraphs (c)(6)(i) and (c)(6)(ii) of this section, any container used for the storage of liquid or non-liquid PCB waste shall be in accordance with the requirements set forth in the DOT Hazardous Materials Regulations (HMR) at 49 CFR parts 171 through 180. PCB waste not subject to the HMR (i.e., PCB wastes at concentrations of  $< 20$  ppm or  $< 1$  pound of PCBs regardless of concentration) must be packaged in accordance with Packaging Group III, unless other hazards associated with the PCB waste cause it to require packaging in accordance with Packaging Groups I or II. For purposes of describing PCB waste not subject to DOT's HMR on a manifest, one may use the term "Non-DOT Regulated PCBs."

(i) Containers other than those meeting HMR performance standards may be used for storage of PCB/radioactive waste provided the following requirements are met:

(A) Containers used for storage of liquid PCB/radioactive wastes must be non-leaking.

(B) Containers used for storage of non-liquid PCB/ radioactive wastes must be designed to prevent the build-up of liquids if such containers are stored in an area meeting the containment requirements of paragraph (b)(1)(ii) of this section, as well as all other applicable State or Federal regulations or requirements for control of radioactive materials.

(C) Containers used to store both liquid and non-liquid PCB/radioactive wastes must meet all regulations and requirements pertaining to nuclear criticality safety. Acceptable container materials currently include polyethylene and stainless steel provided that the container material is chemically compatible with the wastes being stored. Other containers may be used to store both liquid and non-liquid PCB/radioactive wastes if the users are able to demonstrate, to the appropriate Regional Administrator and other appropriate regulatory authorities (i.e., Nuclear Regulatory Commission, Department of Energy or the Department of Transportation), that the use of such

containers is protective of health and the environment as well as public health and safety.

(ii) The following DOT specification containers that conform to the requirements of 49 CFR, chapter I, subchapter C in effect on September 30, 1991, may be used for storage and transportation activities that are not subject to DOT regulation, and may be used on a transitional basis as permitted at 49 CFR 171.14. For liquid PCBs: Specification 5 container without removable head, Specification 5B container without removable head, Specification 6D overpack with Specification 2S or 2SL polyethylene containers, or Specification 17E container. For non-liquid PCBs: Specification 5 container, Specification 5B container, or Specification 17C container.

(7) Stationary storage containers for liquid PCBs can be larger than the containers specified in paragraph (c)(6) of this section provided that:

(i) The containers are designed, constructed, and operated in compliance with Occupational Safety and Health Standards, 29 CFR 1910.106, *Flammable and combustible liquids*. Before using these containers for storing PCBs, the design of the containers must be reviewed to determine the effect on the structural safety of the containers that will result from placing liquids with the specific gravity of PCBs into the containers (see 29 CFR 1910.106(b)(1)(i)(f)).

(ii) The owners or operators of any facility using containers described in paragraph (c)(7)(i) of this section, shall prepare and implement a Spill Prevention Control and Countermeasure (SPCC) Plan as described in part 112 of this title. In complying with 40 CFR part 112, the owner or operator shall read "oil(s)" as "PCB(s)" whenever it appears. The exemptions for storage capacity, 40 CFR 112.1(d)(2), and the amendment of SPCC plans by the Regional Administrator, 40 CFR 112.4, shall not apply unless some fraction of the liquids stored in the container are oils as defined by section 311 of the Clean Water Act.

(8) PCB Items shall be dated on the item when they are removed from service for disposal. The storage shall be managed so that the PCB Items can be

located by this date. Storage containers provided in paragraph (c)(7) of this section, shall have a record that includes for each batch of PCBs the quantity of the batch and date the batch was added to the container. The record shall also include the date, quantity, and disposition of any batch of PCBs removed from the container.

(9) Bulk PCB remediation waste or PCB bulk product waste may be stored at the clean-up site or site of generation for 180 days subject to the following conditions:

(i) The waste is placed in a pile designed and operated to control dispersal of the waste by wind, where necessary, by means other than wetting.

(ii) The waste must not generate leachate through decomposition or other reactions.

(iii) The storage site must have:

(A) A liner that is designed, constructed, and installed to prevent any migration of wastes off or through the liner into the adjacent subsurface soil, ground water or surface water at any time during the active life (including the closure period) of the storage site. The liner may be constructed of materials that may allow waste to migrate into the liner. The liner must be:

(1) Constructed of materials that have appropriate chemical properties and sufficient strength and thickness to prevent failure due to pressure gradients (including static head and external hydrogeologic forces), physical contact with the waste or leachate to which they are exposed, climatic conditions, the stress of installation, and the stress of daily operation.

(2) Placed upon a foundation or base capable of providing support to the liner and resistance to pressure gradients above and below the liner to prevent failure of the liner due to settlement, compression, or uplift.

(3) Installed to cover all surrounding earth likely to be in contact with the waste.

(B) A cover that meets the requirements of paragraph (c)(9)(iii)(A) of this section, is installed to cover all of the stored waste likely to be contacted with precipitation, and is secured so as not to be functionally disabled by winds expected under normal seasonal

## Environmental Protection Agency

## § 761.65

meteorological conditions at the storage site.

(C) A run-on control system designed, constructed, operated, and maintained such that:

(1) It prevents flow onto the stored waste during peak discharge from at least a 25-year storm.

(2) It collects and controls at least the water volume resulting from a 24-hour, 25-year storm. Collection and holding facilities (e.g., tanks or basins) must be emptied or otherwise managed expeditiously after storms to maintain design capacity of the system.

(iv) The provisions of this paragraph may be modified under § 761.61(c).

(10) Owners or operators of storage facilities shall establish and maintain records as provided in § 761.180.

(d) *Approval of commercial storers of PCB waste.* (1) All commercial storers of PCB waste shall have interim approval to operate commercial facilities for the storage of PCB waste until August 2, 1990. Commercial storers of PCB waste are prohibited from storing any PCB waste at their facilities after August 2, 1990 unless they have submitted by August 2, 1990 a complete application for a final storage approval under paragraph (d)(2) of this section. The period of interim approval shall continue until EPA makes a final decision on the storage application at which time such interim approval shall terminate.

(2) The Regional Administrator for the region in which the storage facility is located (or the appropriate official at EPA Headquarters, if the commercial storage area is ancillary to a disposal facility for which an official at EPA Headquarters has approval authority) shall grant written, final approval to engage in the commercial storage of PCB waste upon a determination that the criteria in paragraph (d)(2)(i) through (d)(2)(vii) of this section have been met by the applicant:

(i) The applicant, its principals, and its key employees responsible for the establishment or operation of the commercial storage facility are qualified to engage in the business of commercial storage of PCB waste.

(ii) The facility possesses the capacity to handle the quantity of PCB waste which the owner or operator of the facility has estimated will be the

maximum quantity of PCB waste that will be handled at any one time at the facility.

(iii) The owner or operator of the unit has certified compliance with the storage facility standards in paragraphs (b) and (c)(7) of this section.

(iv) The owner or operator has developed a written closure plan for the facility that is deemed acceptable by the Regional Administrator (or the appropriate official at EPA Headquarters, if the commercial storage area is ancillary to a disposal facility permitted by an official at EPA Headquarters) under the closure plan standards of paragraph (e) of this section.

(v) The owner or operator has included in the application for final approval a demonstration of financial responsibility for closure that meets the financial responsibility standards of paragraph (g) of this section.

(vi) The operation of the storage facility will not pose an unreasonable risk of injury to health or the environment.

(vii) The environmental compliance history of the applicant, its principals, and its key employees may be deemed to constitute a sufficient basis for denial of approval whenever in the judgment of the appropriate EPA official that history of environmental civil violations or criminal convictions evidences a pattern or practice of non-compliance that demonstrates the applicant's unwillingness or inability to achieve and maintain compliance with the regulations.

(3) Applicants for storage approvals shall submit a written application that includes any relevant information bearing upon the qualifications of the facility's principals and key employees to engage in the business of commercial storage of PCB wastes. This information shall include, but is not limited to:

(i) The identification of the owner and the operator of the facility, including all general partners of a partnership, any limited partner of a partnership, any stockholder of a corporation or any participant in any other type of business organization or entity who owns or controls, directly or indirectly,

more than 5 percent of each partnership, corporation, or other business organization and all officials of the facility who have direct management responsibility for the facility.

(ii) The identification of the person responsible for the overall operations of the facility (i.e., a plant manager, superintendent, or a person of similar responsibility) and the supervisory employees who are or will be responsible for the operation of the facility.

(iii) Information concerning the technical qualifications and experience of the persons responsible for the overall operation of the facility and the employees responsible for handling PCB waste or other wastes.

(iv) Information concerning any past State or Federal environmental violations involving the same business or another business with which the principals or supervisory employees were affiliated directly that occurred within 5 years preceding the date of submission and which relate directly to violations that resulted in either a civil penalty (irrespective of whether the matter was disposed of by an adjudication or by a without prejudice settlement) or judgment of conviction whether entered after trial or a plea, either of guilt or nolo contendere or civil injunctive relief and involved storage, disposal, transport, or other waste handling activities.

(v) A list of all companies currently owned or operated in the past by the principals or key employees identified in paragraphs (d)(3)(i) and (d)(3)(ii) of this section that are or were directly or indirectly involved with waste handling activities.

(vi) The owner's or operator's estimate of maximum PCB waste quantity to be handled at the facility.

(vii) A written statement certifying compliance with paragraph (b) or (c) of this section and containing a certification as defined in § 761.3.

(viii) A written closure plan for the facility, as described in paragraph (e) of this section.

(ix) The current closure cost estimate for the facility, as described in paragraph (f) of this section.

(x) A demonstration of financial responsibility to close the facility, as described in paragraph (g) of this section.

(4) The written approval issued by EPA shall include, but not be limited to, the following:

(i) The determination that the applicant has satisfied the requirements set forth in paragraph (d)(2) of this section, and a brief statement setting forth the basis for the determination.

(ii) Incorporation of the closure plan submitted by the facility owner or operator and approved by EPA.

(iii) A condition imposing a maximum PCB storage capacity which the facility shall not exceed during its PCB waste storage operations. The maximum storage capacity imposed under this condition shall not be greater than the estimated maximum inventory of PCB waste included in the owner's or operator's application for final approval.

(iv) Such other conditions as deemed necessary by EPA to ensure that the operations of the PCB storage facility will not pose an unreasonable risk of injury to health or the environment.

(5) Storage areas at transfer facilities are exempt from the requirement to obtain approval as a commercial storer of PCB waste under this paragraph, unless the same PCB waste is stored at these facilities for a period of time greater than 10 consecutive days between destinations.

(6) Storage areas at RCRA-permitted facilities may be exempt from the separate TSCA storage approval requirements in this paragraph (d) upon a showing to the Regional Administrator's satisfaction that the facility's existing RCRA closure plan is substantially equivalent to this rule's closure plan standards, and that such facility's closure cost estimate and financial assurance demonstration account for maximum PCB waste inventories, and the requirements of paragraph (d)(3)(i) through (d)(3)(v) and (d)(3)(vii) of this section are met. A pay-in period of longer than 3 years after approval of the storage facility pursuant to this rule, will be acceptable to EPA if that pay-in period has already been established for a valid RCRA facility or previously approved TSCA facility.

(7) Storage areas ancillary to TSCA-approved disposal facilities may be exempt from a separate facility approval

## Environmental Protection Agency

## § 761.65

provided all of the following conditions are met:

(i) The current disposal approval contains an expiration date.

(ii) The current disposal approval's closure and financial responsibility conditions specifically extend to storage areas ancillary to disposal.

(iii) The current disposal approval's closure and financial responsibility conditions provide for annual adjustments for inflation, and for modification when changes in operation would affect closure costs.

(iv) The current disposal approval contains conditions on closure and financial responsibility that are at least as stringent as those in paragraphs (e) and (g) of this section. However, the provision for a 3-year closure trust pay-in period, as specified in paragraph (g)(1)(i) of this section, would be waived in a case in which an approved TSCA facility or RCRA facility that covers PCB storage has a longer pay-in period for the trust.

(v) The current disposal approval satisfies the requirements of paragraph (d)(3)(i) through (d)(3)(v) of this section.

(8) The approval of any existing TSCA-approved disposal facility ancillary to a commercial storage facility that is deficient in any of the conditions of paragraph (d)(7)(i) through (d)(7)(v) of this section shall be called in by the Regional Administrator (or the appropriated official at EPA Headquarters, if approval was granted by an official at EPA Headquarters). The approval shall be modified to meet the requirements of paragraph (d)(7) of this section within 180 days of the effective date of this final rule, or a separate application for approval of the storage facility may be submitted to the Regional Administrator or the Director, Office of Resource Conservation and Recovery, in the cases where an official at EPA Headquarters issued the approval.

(e) *Closure.* (1) A commercial storer of PCB waste shall have a written closure plan that identifies the steps that the owner or operator of the facility shall take to close the PCB waste storage facility in a manner that eliminates the potential for post-closure releases of PCBs which may present an unreason-

able risk to human health or the environment. An acceptable closure plan must include, at a minimum, all of the following:

(i) A description of how the PCB storage areas of the facility will be closed in a manner that eliminates the potential for post-closure releases of PCBs into the environment.

(ii) An identification of the maximum extent of storage operations that will be open during the active life of the facility, including an identification of the extent of PCB storage operations at the facility relative to other wastes that will be handled at the facility.

(iii) An estimate of the maximum inventory of PCB wastes that could be handled at one time at the facility over its active life, and a detailed description of the methods or arrangements to be used during closure for removing, transporting, storing, or disposing of the facility's inventory of PCB waste, including an identification of any off-site facilities that will be used.

(iv) A detailed description of the steps needed to remove or decontaminate PCB waste residues and contaminated containment system components, equipment, structures, and soils during closure in accordance with the levels specified in the PCB Spills Cleanup Policy in subpart G of this part, including a description of the methods for sampling and testing of surrounding soils, and the criteria for determining the extent of removal or decontamination.

(v) A detailed description of other activities necessary during the closure period to ensure that any post-closure releases of PCBs will not present unreasonable risks to human health or the environment. This includes activities such as ground-water monitoring, run-on and run-off control, and facility security.

(vi) A schedule for closure of each area of the facility where PCB waste is stored or handled, including the total time required to close each area of PCB waste storage or handling, and the time required for any intervening closure activities.

(vii) An estimate of the expected year of closure of the PCB waste storage areas, if a trust fund is opted for as the financial mechanism.



(2) A written closure plan determined to be acceptable by EPA under this section shall become a condition of any approval granted under paragraph (d) of this section.

(3) A separate and new closure plan need not be submitted in cases where a facility is currently covered by a TSCA approval or a RCRA permit, upon a showing to the satisfaction of the Regional Administrator (or the appropriate official at EPA Headquarters, if the commercial storage area is ancillary to a disposal facility for which an official at EPA Headquarters has approval authority) that the existing closure plan is substantially equivalent to closure plans required under paragraphs (d) through (g) of this section, and that the plan adequately accounts for PCB waste inventories.

(4) The commercial storer of PCB waste shall submit a written request to the Regional Administrator (or the Director, Office of Resource Conservation and Recovery, if an official at EPA Headquarters approved the closure plan) for a modification to its storage approval to amend its closure plan, whenever:

(i) Changes in ownership, operating plans, or facility design affect the existing closure plan.

(ii) There is a change in the expected date of closure, if applicable.

(iii) In conducting closure activities, unexpected events require a modification of the approved closure plan.

(5) The Regional Administrator or the Director, appropriate official at EPA Headquarters, if an official at EPA Headquarters approved the closure plan, may modify the existing closure plan under the conditions described in paragraph (e)(4) of this section.

(6) Commercial storers of PCB waste shall comply with the following closure schedule:

(i) The commercial storer shall notify in writing the Regional Administrator or the Director, Office of Resource Conservation and Recovery, if an official at EPA Headquarters approved the closure plan, at least 60 days prior to the date on which final closure of its PCB storage facility is expected to begin.

(ii) The date when a commercial storer of PCB waste "expects to begin closure" shall be no later than 30 days after the date on which the storage facility received its final quantities of PCB waste. For good cause shown, EPA may extend the date for commencement of closure for an additional 30-day period.

(iii) Within 90 days after receiving the final quantity of PCB waste for storage, a commercial storer of PCB waste shall remove all PCB waste in storage at the facility from the facility in accordance with the approved closure plan. For good cause shown, EPA may approve a reasonable extension to the period for removal of the PCB waste.

(iv) A commercial storer of PCB waste shall complete closure activities in accordance with the approved closure plan and within 180 days after receiving the final quantity of PCB waste for storage at the facility. For good cause shown, EPA may approve a reasonable extension to the closure period.

(7) During the closure period, all contaminated system component equipment, structures, and soils shall be disposed of in accordance with the disposal requirements of subpart D of this part, or, if applicable, decontaminated in accordance with the levels specified in the PCB Spills Cleanup Policy at subpart G of this part. When PCB waste is removed from the storage facility during closure, the owner or operator becomes a generator of PCB waste subject to the generator requirements of subpart J of this part.

(8) Within 60 days of completion of closure of each facility for the storage of PCB waste, the commercial storer of PCB waste shall submit to the Regional Administrator (or the Director, Office of Resource Conservation and Recovery, if an official at EPA Headquarters approved the closure plan), by registered mail, a certification that the PCB storage facility has been closed in accordance with the approved closure plan. The certification shall be signed by the owner or operator and by an independent registered professional engineer.

(f) *Closure cost estimate.* (1) A commercial storer of PCB wastes shall have a detailed estimate, in current dollars, of

## Environmental Protection Agency

## § 761.65

the cost of closing the facility in accordance with its approved closure plan. The closure cost estimate shall be in writing, be certified by the person preparing it (using the certification defined in §761.3) and comply with all of the following criteria:

(i) The closure cost estimate shall equal the cost of final closure at the point in the PCB storage facility's active life when the extent and manner of PCB storage operations would make closure the most expensive, as indicated by the facility's closure plan.

(ii) The closure cost estimate shall be based on the costs to the owner or operator of hiring a third party to close the facility, and the third party shall not be either a corporate parent or subsidiary of the owner or operator, or member in joint ownership of the facility.

(iii) The owner or operator shall include in the estimate the current market costs for off-site commercial disposal of the facility's maximum estimated inventory of PCB wastes, except that on-site disposal costs may be used if on-site disposal capacity will exist at the facility at all times over the life of the PCB storage facility.

(iv) The closure cost estimate may not incorporate any salvage value that may be realized with the sale of wastes, facility structures or equipment, land, or other assets associated with the facility at the time of closure.

(2) During the active life of the PCB storage facility, the commercial storer of PCB waste shall adjust annually for inflation the closure cost estimate within 60 days prior to the anniversary date of the establishment of the financial instruments used to demonstrate financial responsibility for closure, except that owners or operators who use the financial test or corporate guarantee shall adjust their closure cost estimates for inflation within 30 days after the close of the storer's fiscal year. The adjustment may be made by recalculating the maximum costs of closure in current dollars, or by using an inflation factor derived from the most recent Implicit Price Deflator for Gross National Product published by the U.S. Department of Commerce in its *Survey of Current Business*. The Implicit Price Deflator for Gross National

Product is included in a monthly publication titled *Economic Indicators*, which is available from the Superintendent of Documents, Government Printing Office, Washington, DC 20402. The inflation factor used in the latter method is the result of dividing the latest published annual Deflator by the Deflator for the previous year. The adjustment to the closure cost estimate is then made by multiplying the most recent closure cost estimate by the latest inflation factor.

(3) Where EPA approves a modification to the facility's closure plan, and that modification increases the cost of closure, the owner or operator shall revise the closure cost estimate no later than 30 days after the modification is approved. Any such revision shall also be adjusted for inflation in accordance with paragraph (f)(2) of this section.

(4) The owner or operator of the facility shall keep at the facility during its operating life the most recent closure cost estimate, including any adjustments resulting from inflation or from modifications to the closure plan.

(g) *Financial assurance for closure.* A commercial storer of PCB waste shall establish financial assurance for closure of each PCB storage facility that he owns or operates. In establishing financial assurance for closure, the commercial storer of PCB waste may choose from the following financial assurance mechanisms or any combination of mechanisms:

(1) The "closure trust fund," as specified in §264.143(a) of this chapter, except for paragraph (a)(3) of §264.143. For purposes of this paragraph, the following provisions also apply:

(i) Payments into the trust fund shall be made annually by the owner or operator over the remaining operating life of the facility as estimated in the closure plan, or over 3 years, whichever period is shorter. This period of time is hereafter referred to as the "pay-in period." For an existing facility, the first payment must be made within 30 calendar days after EPA has notified the facility of its conditional approval. Interim approval to operate is canceled and the application is denied if EPA does not receive verification that the payment was made in that 30-day period.

(ii) For a new facility, the first payment into the closure trust fund shall be made before EPA grants final approval of the application and before the facility may accept the initial shipment of PCB waste for commercial storage. A receipt from the trustee shall be submitted by the owner or operator to the Regional Administrator (or the Director, Office of Resource Conservation and Recovery, if the commercial storage area is ancillary to a disposal facility approved by an official at EPA Headquarters) before this initial delivery of PCB waste. The first payment shall be at least equal to the current closure cost estimate, divided by the number of years in the pay-in period, except as provided in paragraph (g)(7) of this section for multiple mechanisms. Subsequent payments shall be made no later than 30 days after each anniversary date of the first payment. The amount of each subsequent payment shall be determined by subtracting the current value of the trust fund from the current closure cost estimate, and dividing this difference by the number of years remaining in the pay-in period.

(iii) If an owner or operator of a facility existing on the effective date of this paragraph establishes a trust fund to meet the financial assurance requirements of this paragraph, and the value of the trust fund is less than the current closure cost estimate when a final approval is granted for the facility, the amount of the current closure cost estimate still to be paid into the trust fund shall be paid in over the pay-in period as defined in paragraph (g)(1)(i) of this section. Payments shall continue to be made no later than 30 days after each anniversary date of the first payment made into the trust fund. The amount of each payment shall be determined by subtracting the current value of the trust fund from the current closure cost estimate, and dividing this difference by the number of years remaining in the pay-in period.

(iv) The submission of a trust agreement with the wording specified in § 264.151(a)(1) of this chapter, including any reference to hazardous waste management facilities, shall be deemed to be in compliance with the requirement

to submit a trust agreement under this subpart.

(2) The “surety bond guaranteeing payment into a closure trust fund,” as specified in § 264.143(b) of this chapter, including the use of the surety bond instrument specified at § 264.151(b) of this chapter and the standby trust specified at § 264.143(b)(3) of this chapter. The use of the surety bonds, surety bond instruments, and standby trust agreements specified in §§ 264.143(b) and 264.151(b) of this chapter shall be deemed to be in compliance with this subpart.

(3)(i) The “surety bond guaranteeing performance of closure,” as specified at § 264.143(c) of this chapter, except for paragraph (c)(5) of § 264.143 of this chapter. The submission and use of the surety bond instrument specified at § 264.151(c) of this chapter and the standby trust specified at § 264.143(c)(3) of this chapter shall be deemed to be in compliance with the requirements under this subpart relating to the use of surety bonds and standby trust funds.

(ii) For the purposes of this paragraph, and under the terms of the bond, the surety shall become liable on the bond obligation when the owner or operator fails to perform as guaranteed by the bond. Liability is established by a final administrative determination pursuant to section 16 of TSCA that the owner or operator has failed to perform final closure in accordance with the closure plan and other approval or regulatory requirements when required to do so.

(4)(i) The “closure letter of credit” specified in § 264.143(d) of this chapter, except for paragraph (d)(8). The submission and use of the irrevocable letter of credit instrument specified in § 264.151(d) of this chapter and the standby trust specified in § 264.143(d)(3) of this chapter shall be deemed to be in compliance with the requirements of this subpart relating to the use of letters of credit and standby trust funds.

(ii) For the purposes of this paragraph, the Regional Administrator (or the appropriate official at EPA Headquarters, if the commercial storage area is ancillary to a disposal facility for which an official at EPA Headquarters has approval authority) may draw on the letter of credit following a

## Environmental Protection Agency

## § 761.65

final administrative determination pursuant to section 16 of TSCA that the owner or operator has failed to perform final closure in accordance with the closure plan and other approval or regulatory requirements when required to do so.

(5) "Closure insurance," as specified in §264.143(e) of this chapter, utilizing the certificate of insurance for closure specified at §264.151(e) of this chapter. The use of closure insurance as specified in §264.143(e) of this chapter and the submission and use of the certificate of insurance specified in §264.151(e) of this chapter shall be deemed to be in compliance with the requirements of this subpart relating to the use of closure insurance.

(6) The "financial test and corporate guarantee for closure," as described in §264.143(f) of this chapter, including a letter signed by the owner's or operator's chief financial officer as specified at §264.151(f) of this chapter and, if applicable, the written corporate guarantee specified at §264.151(h) of this chapter. The use of the financial test and corporate guarantee specified in §264.143(f) of this chapter, the submission and use of the letter specified in §264.151(f) of this chapter, and the submission and use of the written corporate guarantee specified at §264.151(h) of this chapter shall be deemed to be in compliance with the requirements of this subpart relating to the use of financial tests and corporate guarantees.

(7) The corporate guarantee as specified in §264.143(f)(10) of this chapter.

(8) The use of multiple financial mechanisms, as specified in §264.143(g) of this chapter is permitted.

(9) A modification to a facility storing PCB waste that increases the maximum storage capacity indicated in the permit requires that a new financial assurance mechanism be established or an existing one be amended. When such a modification occurs, the Director of the Federal or State issuing authority must be notified in writing no later than 30 days from the completion of the modification. The new or revised financial assurance mechanism must be established and activated no later than 30 days after the Director of the Federal or State issuing authority is noti-

fied of the completion of the modification, but prior to the use of the modified portion of the facility.

(h) *Release of owner or operator.* Within 60 days after receiving certifications from the owner or operator and an independent registered professional engineer that final closure has been completed in accordance with the approved closure plan, EPA will notify the owner or operator in writing that the owner or operator is no longer required by this section to maintain financial assurance for final closure of the facility, unless EPA has reason to believe that final closure has not been completed in accordance with the approved closure plan. EPA shall provide the owner or operator with a detailed written statement stating the reasons why EPA shall provide the owner or operator with a detailed written statement stating the reasons why he believed closure was not conducted in accordance with the approved closure plan.

(i) *Laboratories and samples.* (1) A laboratory is conditionally exempt from the notification and approval requirements for a commercial storer under §761.65 (d) through (h) when it stores samples held for disposal in a facility that complies with the standards in §761.65 (b)(1)(i) through (b)(1)(iv).

(2) A laboratory sample is exempt from the manifesting requirements in §761.208 when:

(i) The sample is being transported to a laboratory for the purpose of testing.

(ii) The sample is being transported back to the sample collector after testing.

(iii) The sample is being stored by the sample collector before transport to a laboratory for testing.

(iv) The sample is being stored in a laboratory before testing.

(v) The sample is being stored in a laboratory after testing but before it is returned to the sample collector.

(vi) The sample is being stored temporarily in the laboratory after testing for a specific purpose (for example, until conclusion of a court case or enforcement action where further testing of the sample may be necessary).

(3) In order to qualify for the exemption in paragraph (i)(2)(i) and (i)(2)(ii)

## §761.70

## 40 CFR Ch. I (7–1–10 Edition)

of this section, a sample collector shipping samples to a laboratory and a laboratory returning samples to a sample collector must:

(i) Comply with applicable U.S. Department of Transportation (DOT) or U.S. Postal Service (USPS) shipping requirements, found respectively in 49 CFR 173.345 and U.S. Postal Regulations 652.2 and 652.3.

(ii) Assure that the following information accompanies the sample:

(A) The sample collector's name, mailing address, and telephone number.

(B) The laboratory's name, mailing address, and telephone number.

(C) The quantity of the sample.

(D) The date of shipment.

(E) A description of the sample.

(iii) Package the sample so that it does not leak, spill, or vaporize from its packaging.

(4) When the concentration of the PCB sample has been determined, and its use is terminated, the sample must be properly disposed. A laboratory must either manifest the PCB waste to a disposer or commercial storer, as required under §761.208, retain a copy of each manifest, as required under §761.209, and follow up on exception reporting, as required under §761.215 (a) and (b), or return the sample to the sample collector who must then properly dispose of the sample. If the laboratory returns the sample to the sample collector, the laboratory must comply with the shipping requirements set forth in paragraph (i)(3)(i) through (i)(3)(iii) of this section.

(j) *Changes in ownership or operational control of a commercial storage facility.* The date of transfer of interim status or final approval shall be the date the EPA Regional Administrator (or appropriate official at EPA Headquarters) provides written approval of the transfer. EPA will provide a final written decision within 90 days of receipt of the complete new or amended application. The Agency will approve the transfer if the following conditions are met:

(1) The transferee has established financial assurance for closure pursuant to paragraph (g) of this section using a mechanism effective as of the date of final approval so that there will be no

lapse in financial assurance for the transferred facility.

(2) The transferor or transferee has resolved any deficiencies (e.g., technical operations, closure plans, cost estimates, etc.) the Agency has identified in the transferor's application.

(k) *States and the Federal Government.* States and the Federal Government are exempt from the requirements of paragraphs (f) and (g) of this section.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[44 FR 31542, May 31, 1979. Redesignated at 47 FR 19527, May 6, 1982, and amended at 47 FR 37359, Aug. 8, 1982; 49 FR 28191, July 10, 1984; 53 FR 12524, Apr. 15, 1988; 54 FR 52746, Dec. 21, 1989; 55 FR 695, Jan. 8, 1990; 55 FR 26205, June 27, 1990; 58 FR 15809, Mar. 24, 1993; 58 FR 34205, June 23, 1993; 58 FR 59374, Nov. 9, 1993; 63 FR 35439, 35452, June 29, 1998; 72 FR 57239, 57240 Oct. 9, 2007; 74 FR 30232, June 25, 2009]

### §761.70 Incineration.

This section applies to facilities used to incinerate PCBs required to be incinerated by this part.

(a) *Liquid PCBs.* An incinerator used for incinerating PCBs shall be approved by EPA pursuant to paragraph (d) of this section. Requests for approval of incinerators to be used in more than one region must be submitted to the Director, Office of Resource Conservation and Recovery, except for research and development involving less than 500 pounds of PCB material (see §761.60(i)(2)). Requests for approval of incinerators to be used in only one region must be submitted to the appropriate Regional Administrator. The incinerator shall meet all of the requirements specified in paragraphs (a)(1) through (9) of this section, unless a waiver from these requirements is obtained pursuant to paragraph (d)(5) of this section. In addition, the incinerator shall meet any other requirements which may be prescribed pursuant to paragraph (d)(4) of this section.

(1) Combustion criteria shall be either of the following:

(i) Maintenance of the introduced liquids for a 2-second dwell time at 1200 °C (±100 °C) and 3 percent excess oxygen in the stack gas; or

(ii) Maintenance of the introduced liquids for a 1½ second dwell time at

## Environmental Protection Agency

## § 761.70

1600 °C(±100 °C) and 2 percent excess oxygen in the stack gas.

(2) Combustion efficiency shall be at least 99.9 percent computed as follows:

$$\text{Combustion efficiency} = [\text{Cco}_2 / (\text{Cco}_2 + \text{Cco})]100$$

where

Cco<sub>2</sub>=Concentration of carbon dioxide.

Cco=Concentration of carbon monoxide.

(3) The rate and quantity of PCBs which are fed to the combustion system shall be measured and recorded at regular intervals of no longer than 15 minutes.

(4) The temperatures of the incineration process shall be continuously measured and recorded. The combustion temperature of the incineration process shall be based on either direct (pyrometer) or indirect (wall thermocouple-pyrometer correlation) temperature readings.

(5) The flow of PCBs to the incinerator shall stop automatically whenever the combustion temperature drops below the temperatures specified in paragraph (a)(1) of this section.

(6) Monitoring of stack emission products shall be conducted:

(i) When an incinerator is first used for the disposal of PCBs under the provisions of this regulation;

(ii) When an incinerator is first used for the disposal of PCBs after the incinerator has been modified in a manner which may affect the characteristics of the stack emission products; and

(iii) At a minimum such monitoring shall be conducted for the following parameters:

(a) O<sub>2</sub>; (b) CO; (c) CO<sub>2</sub>; (d) Oxides of Nitrogen (NO<sub>x</sub>); (e) Hydrochloric Acid (HCl); (f) Total Chlorinated Organic Content (RCI); (g) PCBs; and (h) Total Particulate Matter.

(7) At a minimum monitoring and recording of combustion products and incineration operations shall be conducted for the following parameters whenever the incinerator is incinerating PCBs:

(i) O<sub>2</sub>; (ii) CO; and (iii) CO<sub>2</sub>. The monitoring for O<sub>2</sub> and CO shall be continuous. The monitoring for CO<sub>2</sub> shall be periodic, at a frequency specified by the Regional Administrator or appropriate official at EPA Headquarters.

(8) The flow of PCBs to the incinerator shall stop automatically when any one or more of the following conditions occur, unless a contingency plan is submitted by the incinerator owner or operator and approved by the Regional Administrator or appropriate official at EPA Headquarters. The contingency plan indicates what alternative measures the incinerator owner or operator would take if any of the following conditions occur:

(i) Failure of monitoring operations specified in paragraph (a)(7) of this section;

(ii) Failure of the PCB rate and quantity measuring and recording equipment specified in paragraph (a)(3) of this section; or

(iii) Excess oxygen falls below the percentage specified in paragraph (a)(1) of this section.

(9) Water scrubbers shall be used for HCl control during PCB incineration and shall meet any performance requirements specified by EPA. Scrubber effluent shall be monitored and shall comply with applicable effluent or pretreatment standards, and any other State and Federal laws and regulations. An alternate method of HCl control may be used if the alternate method has been approved by EPA. (The HCl neutralizing capability of cement kilns is considered to be an alternate method.)

(b) *Nonliquid PCBs*. An incinerator used for incinerating nonliquid PCBs, PCB Articles, PCB Equipment, or PCB Containers shall be approved by EPA pursuant to paragraph (d) of this section. Requests for approval of incinerators to be used in more than one region must be submitted to the Director, Office of Resource Conservation and Recovery except for research and development involving less than 500 pounds of PCB material (see §761.60(i)(2)). Requests for approval of incinerators to be used in only one region must be submitted to the appropriate Regional Administrator. The incinerator shall meet all of the requirements specified in paragraphs (b)(1) and (2) of this section unless a waiver from these requirements is obtained pursuant to paragraph (d)(5) of this section. In addition, the incinerator shall meet any other requirements that may

be prescribed pursuant to paragraph (d)(4) of this section.

(1) The mass air emissions from the incinerator shall be no greater than 0.001g PCB/kg of the PCB introduced into the incinerator.

(2) The incinerator shall comply with the provisions of paragraphs (a)(2), (3), (4), (6), (7), (8)(i) and (ii), and (9) of this section.

(c) *Maintenance of data and records.* All data and records required by this section shall be maintained in accordance with §761.180, Records and monitoring.

(d) *Approval of incinerators.* Prior to the incineration of PCBs and PCB Items the owner or operator of an incinerator shall receive the written approval of the Agency Regional Administrator for the region in which the incinerator is located, or the appropriate official at EPA Headquarters. Approval from the appropriate official at EPA Headquarters may be effective in all ten EPA regions. Such approval shall be obtained in the following manner:

(1) *Application.* The owner or operator shall submit to the Regional Administrator or the Director, Office of Resource Conservation and Recovery an application which contains:

- (i) The location of the incinerator;
- (ii) A detailed description of the incinerator including general site plans and design drawings of the incinerator;
- (iii) Engineering reports or other information on the anticipated performance of the incinerator;
- (iv) Sampling and monitoring equipment and facilities available;
- (v) Waste volumes expected to be incinerated;
- (vi) Any local, State, or Federal permits or approvals; and
- (vii) Schedules and plans for complying with the approval requirements of this regulation.

(2) *Trial burn.* (i) Following receipt of the application described in paragraph (d)(1) of this section, EPA shall determine if a trial burn is required and notify the person who submitted the report whether a trial burn of PCBs and PCB Items must be conducted. EPA may require the submission of any other information that EPA finds to be reasonably necessary to determine the need for a trial burn. Such other infor-

mation shall be restricted to the types of information required in paragraphs (d)(1)(i) through (vii) of this section.

(ii) If EPA determines that a trial burn must be held, the person who submitted the report described in paragraph (d)(1) of this section shall submit to the Regional Administrator or the Director, Office of Resource Conservation and Recovery a detailed plan for conducting and monitoring the trial burn. At a minimum, the plan must include:

- (A) Date trial burn is to be conducted;
- (B) Quantity and type of PCBs and PCB Items to be incinerated;
- (C) Parameters to be monitored and location of sampling points;
- (D) Sampling frequency and methods and schedules for sample analyses; and
- (E) Name, address, and qualifications of persons who will review analytical results and other pertinent data, and who will perform a technical evaluation of the effectiveness of the trial burn.

(iii) Following receipt of the plan described in paragraph (d)(2)(ii) of this section, EPA will approve the plan, require additions or modifications to the plan, or disapprove the plan. If the plan is disapproved, EPA will notify the person who submitted the plan of such disapproval, together with the reasons why it is disapproved. That person may thereafter submit a new plan in accordance with paragraph (d)(2)(ii) of this section. If the plan is approved (with any additions or modifications which EPA may prescribe), EPA will notify the person who submitted the plan of the approval. Thereafter, the trial burn shall take place at a date and time to be agreed upon between EPA and the person who submitted the plan.

(3) *Other information.* In addition to the information contained in the report and plan described in paragraphs (d)(1) and (2) of this section, EPA may require the owner or operator to submit any other information that the EPA finds to be reasonably necessary to determine whether an incinerator shall be approved.

NOTE: The Regional Administrator will have available for review and inspection an Agency manual containing information on sampling methods and analytical procedures

## Environmental Protection Agency

## § 761.71

for the parameters required in § 761.70(a) (3), (4), (6), and (7) plus any other parameters he/she may determine to be appropriate. Owners or operators are encouraged to review this manual prior to submitting any report required in § 761.70.

(4) *Contents of approval.* (i) Except as provided in paragraph (d)(5) of this section, the Regional Administrator or the appropriate official at EPA Headquarters may not approve an incinerator for the disposal of PCBs and PCB Items unless he finds that the incinerator meets all of the requirements of paragraphs (a) and/or (b) of this section.

(ii) In addition to the requirements of paragraphs (a) and/or (b) of this section, EPA may include in an approval any other requirements that EPA finds are necessary to ensure that operation of the incinerator does not present an unreasonable risk of injury to health or the environment from PCBs. Such requirements may include a fixed period of time for which the approval is valid.

(5) *Waivers.* An owner or operator of the incinerator may submit evidence to the Regional Administrator or the Director, Office of Resource Conservation and Recovery that operation of the incinerator will not present an unreasonable risk of injury to health or the environment from PCBs, when one or more of the requirements of paragraphs (a) and/or (b) of this section are not met. On the basis of such evidence and any other available information, EPA may, in its discretion, find that any requirement of paragraphs (a) and (b) of this section is not necessary to protect against such a risk, and may waive the requirements in any approval for that incinerator. Any finding and waiver under this paragraph must be stated in writing and included as part of the approval.

(6) *Persons approved.* An approval will designate the persons who own and who are authorized to operate the incinerator, and will apply only to such persons, except as provided in paragraph (d)(8) of this section.

(7) *Final approval.* Approval of an incinerator will be in writing and signed by the appropriate EPA official. The approval will state all requirements applicable to the approved incinerator.

(8) *Transfer of property.* Any person who owns or operates an approved incinerator must notify EPA at least 30 days before transferring ownership in the incinerator or the property it stands upon, or transferring the right to operate the incinerator. The transferor must also submit to EPA, at least 30 days before such transfer, a notarized affidavit signed by the transferee which states that the transferee will abide by the transferor's EPA incinerator approval. Within 30 days of receiving such notification and affidavit, EPA will issue an amended approval substituting the transferee's name for the transferor's name, or EPA may require the transferee to apply for a new incinerator approval. In the latter case, the transferee must abide by the transferor's EPA approval until EPA issues the new approval to the transferee.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[44 FR 31542, May 31, 1979. Redesignated at 47 FR 19527, May 6, 1982, and amended at 48 FR 13185, Mar. 30, 1983; 49 FR 28191, July 10, 1984; 53 FR 12524, Apr. 15, 1988; 58 FR 15809, Mar. 24, 1993; 63 FR 35439, June 29, 1998; 72 FR 57240, Oct. 9, 2007; 74 FR 30233, June 25, 2009]

### § 761.71 High efficiency boilers.

(a) To burn mineral oil dielectric fluid containing a PCB concentration of  $\geq 50$  ppm, but  $< 500$  ppm:

(1) The boiler shall comply with the following criteria:

(i) The boiler is rated at a minimum of 50 million BTU hours.

(ii) If the boiler uses natural gas or oil as the primary fuel, the carbon monoxide concentration in the stack is  $\leq 50$  ppm and the excess oxygen is at least 3 percent when PCBs are being burned.

(iii) If the boiler uses coal as the primary fuel, the carbon monoxide concentration in the stack is  $\leq 100$  ppm and the excess oxygen is at least 3 percent when PCBs are being burned.

(iv) The mineral oil dielectric fluid does not comprise more than 10 percent (on a volume basis) of the total fuel feed rate.

(v) The mineral oil dielectric fluid is not fed into the boiler unless the boiler is operating at its normal operating temperature (this prohibits feeding



these fluids during either start up or shut down operations).

(vi) The owner or operator of the boiler:

(A) Continuously monitors and records the carbon monoxide concentration and excess oxygen percentage in the stack gas while burning mineral oil dielectric fluid; or

(B) If the boiler will burn <30,000 gallons of mineral oil dielectric fluid per year, measures and records the carbon monoxide concentration and excess oxygen percentage in the stack gas at regular intervals of no longer than 60 minutes while burning mineral oil dielectric fluid.

(vii) The primary fuel feed rates, mineral oil dielectric fluid feed rates, and total quantities of both primary fuel and mineral oil dielectric fluid fed to the boiler are measured and recorded at regular intervals of no longer than 15 minutes while burning mineral oil dielectric fluid.

(viii) The carbon monoxide concentration and the excess oxygen percentage are checked at least once every hour that mineral oil dielectric fluid is burned. If either measurement falls below the levels specified in this section, the flow of mineral oil dielectric fluid to the boiler shall be stopped immediately.

(2) Thirty days before any person burns mineral oil dielectric fluid in the boiler, the person gives written notice to the EPA Regional Administrator for the EPA Region in which the boiler is located and that the notice contains the following information:

(i) The name and address of the owner or operator of the boiler and the address of the boiler.

(ii) The boiler rating in units of BTU/hour.

(iii) The carbon monoxide concentration and the excess oxygen percentage in the stack of the boiler when it is operated in a manner similar to the manner in which it will be operated when mineral oil dielectric fluid is burned.

(iv) The type of equipment, apparatus, and procedures to be used to control the feed of mineral oil dielectric fluid to the boiler and to monitor and record the carbon monoxide concentration and excess oxygen percentage in the stack.

(3) When burning mineral oil dielectric fluid, the boiler must operate at a level of output no less than the output at which the measurements required under paragraph (a)(2)(iii) of this section were taken.

(4) Any person burning mineral oil dielectric fluid in a boiler obtains the following information and retains the information for 5 years at the boiler location:

(i) The data required to be collected under paragraphs (a)(1)(vi) and (vii) of this section.

(ii) The quantity of mineral oil dielectric fluid burned in the boiler each month.

(b) To burn liquids, other than mineral oil dielectric fluid, containing a PCB concentration of  $\geq 50$  ppm, but  $< 500$  ppm:

(1) The boiler shall comply with the following criteria:

(i) The boiler is rated at a minimum of 50 million BTU/hour.

(ii) If the boiler uses natural gas or oil as the primary fuel, the carbon monoxide concentration in the stack is  $\leq 50$  ppm and the excess oxygen is at least 3 percent when PCBs are being burned.

(iii) If the boiler uses coal as the primary fuel, the carbon monoxide concentration in the stack is  $\leq 100$  ppm and the excess oxygen is at least 3 percent when PCBs are being burned.

(iv) The waste does not comprise more than 10 percent (on a volume basis) of the total fuel feed rate.

(v) The waste is not fed into the boiler unless the boiler is operating at its normal operating temperature (this prohibits feeding these fluids during either start up or shut down operations).

(vi) The owner or operator of the boiler must:

(A) Continuously monitor and record the carbon monoxide concentration and excess oxygen percentage in the stack gas while burning waste fluid; or

(B) If the boiler will burn <30,000 gallons of waste fluid per year, measure and record the carbon monoxide concentration and excess oxygen percentage in the stack gas at regular intervals of no longer than 60 minutes while burning waste fluid.

## Environmental Protection Agency

## § 761.72

(vii) The primary fuel feed rate, waste fluid feed rate, and total quantities of both primary fuel and waste fluid fed to the boiler must be measured and recorded at regular intervals of no longer than 15 minutes while burning waste fluid.

(viii) The carbon monoxide concentration and the excess oxygen percentage must be checked at least once every hour that the waste is burned. If either measurement falls below the levels specified in either (a)(1)(ii) or (a)(1)(iii) of this section, the flow of waste to the boiler shall be stopped immediately.

(2) Prior to any person burning these liquids in the boiler, approval must be obtained from the EPA Regional Administrator for the EPA Region in which the boiler is located and any persons seeking such approval must submit to the EPA Regional Administrator a request containing at least the following information:

(i) The name and address of the owner or operator of the boiler and the address of the boiler.

(ii) The boiler rating in units of BTU/hour.

(iii) The carbon monoxide concentration and the excess oxygen percentage in the stack of the boiler when it is operated in a manner similar to the manner in which it will be operated when low concentration PCB liquid is burned.

(iv) The type of equipment, apparatus, and procedures to be used to control the feed of mineral oil dielectric fluid to the boiler and to monitor and record the carbon monoxide concentration and excess oxygen percentage in the stack.

(v) The type of waste to be burned (e.g., hydraulic fluid, contaminated fuel oil, heat transfer fluid, etc.).

(vi) The concentration of PCBs and of any other chlorinated hydrocarbon in the waste and the results of analyses using the American Society of Testing and Materials (ASTM) methods as follows: Carbon and hydrogen content using ASTM D-3178-84, nitrogen content using ASTM E-258-67 (Reapproved 1987), sulfur content using ASTM D-2784-89, ASTM D-1266-87, or ASTM D-129-64, chlorine content using ASTM D-808-87, water and sediment content

using either ASTM D-2709-88 or ASTM D-1796-83 (Reapproved 1990), ash content using ASTM D-482-87, calorific value using ASTM D-240-87, carbon residue using either ASTM D-2158-89 or ASTM D-524-88, and flash point using ASTM D-93-90.

(vii) The quantity of wastes estimated to be burned in a 30-day period.

(viii) An explanation of the procedures to be followed to ensure that burning the waste will not adversely affect the operation of the boiler such that combustion efficiency will decrease.

(3) On the basis of the information in paragraph (b)(2) of this section and any other available information, the Regional Administrator may, at his/her discretion, find that the alternate disposal method will not present an unreasonable risk of injury to health or the environment and approve the use of the boiler.

(4) When burning PCB wastes, the boiler must operate at a level of output no less than the output at which the measurements required under paragraph (b)(2)(iii) of this section were taken.

(5) Any person burning liquids in boilers approved as provided in paragraph (b)(3) of this section, must obtain the following information and retain the information for 5 years at the boiler location:

(i) The data required to be collected in paragraphs (b)(1)(vi) and (b)(1)(vii) of this section.

(ii) The quantity of low concentration PCB liquid burned in the boiler each month.

(iii) The analysis of the waste required by paragraph (b)(2)(vi) of this section taken once a month for each month during which low concentration PCB liquid is burned in the boiler.

[63 FR 35454, June 29, 1998]

### § 761.72 Scrap metal recovery ovens and smelters.

Any person may dispose of residual PCBs associated with PCB-contaminated articles regulated for disposal under § 761.60(b), metal surfaces in PCB remediation waste regulated under § 761.61, or metal surfaces in PCB bulk product waste regulated under §§ 761.62(a)(6) and 761.79(c)(6), from

§761.72

40 CFR Ch. I (7-1-10 Edition)

which all free-flowing liquids have been removed:

(a) In a scrap metal recovery oven:

(1) The oven shall have at least two enclosed (i.e., negative draft, no fugitive emissions) interconnected chambers.

(2) The equipment with all free-flowing liquid removed shall first be placed in the primary chamber at room temperature.

(3) The primary chamber shall operate at a temperature between 537 °C and 650 °C for a minimum of 2½ hours and reach a minimum temperature of 650 °C (1,202 °F) once during each heating cycle or batch treatment of unheated, liquid-free equipment.

(4) Heated gases from the primary chamber must feed directly into the secondary chamber (i.e., afterburner) which must operate at a minimum temperature of 1,200 °C (2,192 °F) with at least a 3 percent excess oxygen and a retention time of 2.0 seconds with a minimum combustion efficiency of 99.9 percent according to the definition in §761.70(a)(2).

(5) Heating of the primary chamber shall not commence until the secondary chamber has reached a temperature of 1,200 ±100 °C (2,192 ° ±180 °F).

(6) Continuous emissions monitors and recorders for carbon dioxide, carbon monoxide, and excess oxygen in the secondary chamber and continuous temperature recorders in the primary and secondary chambers shall be installed and operated while the primary and secondary chambers are in operation to assure that the two chambers are within the operating parameters in paragraphs (a)(3) through (a)(5) of this section.

(7) Emissions from the secondary chamber must be vented through an exhaust gas stack in accordance with either:

(i) State or local air regulations or permits, or

(ii) The standards in paragraph (a)(8) of this section.

(8) Exhaust gas stack emissions shall be for: particulates <0.015 grains/dry standard cubic foot, sulfur dioxide <35 parts per million by volume (ppmv), nitrogen oxide <150 ppmv, carbon monoxide <35 ppmv, and hydrogen chloride <35 ppmv.

(9) A measurement of the temperature in the secondary chamber at the time the primary chamber starts heating must be taken, recorded and retained at the facility for 3 years from the date each charge is introduced into the primary chamber.

(b) By smelting:

(1) The operating temperature of the hearth must be at least 1,000 °C at the time it is charged with any PCB-Contaminated non-porous surface.

(2) Each charge containing a PCB-Contaminated item must be added into molten metal or a hearth at ≥1,000 °C.

(3) Successive charges may not be introduced into the hearth in less than 15-minute intervals.

(4) The smelter must operate in compliance with any applicable emissions standards in part 60 of this chapter.

(5) The smelter must have an operational device which accurately measures directly or indirectly, the temperature in the hearth.

(6) Take, record and retain at the disposal facility for 3 years from the date each charge is introduced, a reading of the temperature in the hearth at the time it is charged with a non-porous surface item.

(c)(1) Scrap metal recovery ovens and smelters must either have a final permit under RCRA (part 266, subpart H of this chapter and §270.66 of this chapter) or be operating under a valid State air emissions permit which includes a standard for PCBs.

(2) Scrap metal recovery ovens and smelters disposing of PCBs must provide notification as disposers of PCBs, are not required to submit annual reports, and shall otherwise comply with all applicable provisions of subparts J and K of this part, as well as other applicable Federal, State, and local laws and regulations.

(3) In lieu of the requirements in paragraph (c)(1) of this section, upon written request by the owner or operator of a scrap metal recovery oven or smelter, the EPA Regional Administrator, for the Region where the oven or smelter is located, may make a finding in writing, based on a site-specific risk assessment, that the oven or smelter does not pose an unreasonable

risk of injury to health or the environment because it is operating in compliance with the parameters and conditions listed in paragraph (a) or (b) of this section even though the oven or smelter does not have a RCRA or State air permit as required by paragraph (c)(1) of this section. The written request shall include a site-specific risk assessment.

(d) PCB liquids, other liquid waste qualifying as waste oils which may be used as provided for at § 761.20(e), or PCB remediation waste, other than PCB-contaminated articles, may not be disposed of in a scrap metal recovery oven or smelter unless approved or otherwise allowed under subpart D of this part.

[63 FR 35455, June 29, 1998, as amended at 64 FR 33761, June 24, 1999]

#### § 761.75 Chemical waste landfills.

This section applies to facilities used to dispose of PCBs in accordance with the part.

(a) *General.* A chemical waste landfill used for the disposal of PCBs and PCB Items shall be approved by the Agency Regional Administrator pursuant to paragraph (c) of this section. The landfill shall meet all of the requirements specified in paragraph (b) of this section, unless a waiver from these requirements is obtained pursuant to paragraph (c)(4) of this section. In addition, the landfill shall meet any other requirements that may be prescribed pursuant to paragraph (c)(3) of this section.

(b) *Technical requirements.* Requirements for chemical waste landfills used for the disposal of PCBs and PCB Items are as follows:

(1) *Soils.* The landfill site shall be located in thick, relatively impermeable formations such as large-area clay pans. Where this is not possible, the soil shall have a high clay and silt content with the following parameters:

(i) In-place soil thickness, 4 feet or compacted soil liner thickness, 3 feet;

(ii) Permeability (cm/sec), equal to or less than  $1 \times 10^{-7}$ ;

(iii) Percent soil passing No. 200 Sieve, >30;

(iv) Liquid Limit, >30; and

(v) Plasticity Index >15.

(2) *Synthetic membrane liners.* Synthetic membrane liners shall be used when, in the judgment of the Regional Administrator, the hydrologic or geologic conditions at the landfill require such a liner in order to provide at least a permeability equivalent to the soils in paragraph (b)(1) of this section. Whenever a synthetic liner is used at a landfill site, special precautions shall be taken to insure that its integrity is maintained and that it is chemically compatible with PCBs. Adequate soil underlining and soil cover shall be provided to prevent excessive stress on the liner and to prevent rupture of the liner. The liner must have a minimum thickness of 30 mils.

(3) *Hydrologic conditions.* The bottom of the landfill shall be above the historical high groundwater table as provided below. Floodplains, shorelands, and groundwater recharge areas shall be avoided. There shall be no hydraulic connection between the site and standing or flowing surface water. The site shall have monitoring wells and leachate collection. The bottom of the landfill liner system or natural in-place soil barrier shall be at least fifty feet from the historical high water table.

(4) *Flood protection.* (i) If the landfill site is below the 100-year floodwater elevation, the operator shall provide surface water diversion dikes around the perimeter of the landfill site with a minimum height equal to two feet above the 100-year floodwater elevation.

(ii) If the landfill site is above the 100-year floodwater elevation, the operators shall provide diversion structures capable of diverting all of the surface water runoff from a 24-hour, 25-year storm.

(5) *Topography.* The landfill site shall be located in an area of low to moderate relief to minimize erosion and to help prevent landslides or slumping.

(6) *Monitoring systems—(i) Water sampling.* (A) For all sites receiving PCBs, the ground and surface water from the disposal site area shall be sampled prior to commencing operations under an approval provided in paragraph (c) of this section for use as baseline data.

(B) Any surface watercourse designated by the Regional Administrator

using the authority provided in paragraph (c)(3)(ii) of this section shall be sampled at least monthly when the landfill is being used for disposal operations.

(C) Any surface watercourse designated by the Regional Administrator using the authority provided in paragraph (c)(3)(ii) of this section shall be sampled for a time period specified by the Regional Administrator on a frequency of no less than once every six months after final closure of the disposal area.

(ii) *Groundwater monitor wells.* (A) If underlying earth materials are homogenous, impermeable, and uniformly sloping in one direction, only three sampling points shall be necessary. These three points shall be equally spaced on a line through the center of the disposal area and extending from the area of highest water table elevation to the area of the lowest water table elevation on the property.

(B) All monitor wells shall be cased and the annular space between the monitor zone (zone of saturation) and the surface shall be completely backfilled with Portland cement or an equivalent material and plugged with Portland cement to effectively prevent percolation of surface water into the well bore. The well opening at the surface shall have a removable cap to provide access and to prevent entrance of rainfall or stormwater runoff. The well shall be pumped to remove the volume of liquid initially contained in the well before obtaining a sample for analysis. The discharge shall be treated to meet applicable State or Federal discharge standards or recycled to the chemical waste landfill.

(iii) *Water analysis.* As a minimum, all samples shall be analyzed for the following parameters, and all data and records of the sampling and analysis shall be maintained as required in §761.180(d)(1). Sampling methods and analytical procedures for these parameters shall comply with those specified in 40 CFR part 136 as amended in 41 FR 52779 on December 1, 1976.

- (A) PCBs.
- (B) pH.
- (C) Specific conductance.
- (D) Chlorinated organics.

(7) *Leachate collection.* A leachate collection monitoring system shall be installed above the chemical waste landfill. Leachate collection systems shall be monitored monthly for quantity and physicochemical characteristics of leachate produced. The leachate should be either treated to acceptable limits for discharge in accordance with a State or Federal permit or disposed of by another State or Federally approved method. Water analysis shall be conducted as provided in paragraph (b)(6)(iii) of this section. Acceptable leachate monitoring/collection systems shall be any of the following designs, unless a waiver is obtained pursuant to paragraph (c)(4) of this section.

(i) *Simple leachate collection.* This system consists of a gravity flow drainfield installed above the waste disposal unit liner. This design is recommended for use when semi-solid or leachable solid wastes are placed in a lined pit excavated into a relatively thick, unsaturated, homogenous layer of low permeability soil.

(ii) *Compound leachate collection.* This system consists of a gravity flow drainfield installed above the waste disposal unit liner and above a secondary installed liner. This design is recommended for use when semi-liquid or leachable solid wastes are placed in a lined pit excavated into relatively permeable soil.

(iii) *Suction lysimeters.* This system consists of a network of porous ceramic cups connected by hoses/tubing to a vacuum pump. The porous ceramic cups or suction lysimeters are installed along the sides and under the bottom of the waste disposal unit liner. This type of system works best when installed in a relatively permeable unsaturated soil immediately adjacent to the bottom and/or sides of the disposal facility.

(8) *Chemical waste landfill operations.*  
 (i) PCBs and PCB Items shall be placed in a landfill in a manner that will prevent damage to containers or articles. Other wastes placed in the landfill that are not chemically compatible with PCBs and PCB Items including organic solvents shall be segregated from the PCBs throughout the waste handling and disposal process.

## Environmental Protection Agency

## § 761.75

(ii) An operation plan shall be developed and submitted to the Regional Administrator for approval as required in paragraph (c) of this section. This plan shall include detailed explanations of the procedures to be used for recordkeeping, surface water handling procedures, excavation and backfilling, waste segregation burial coordinates, vehicle and equipment movement, use of roadways, leachate collection systems, sampling and monitoring procedures, monitoring wells, environmental emergency contingency plans, and security measures to protect against vandalism and unauthorized waste placements. EPA guidelines entitled "Thermal Processing and Land Disposal of Solid Waste" (39 FR 29337, Aug. 14, 1974) are a useful reference in preparation of this plan. If the facility is to be used to dispose of liquid wastes containing between 50 ppm and 500 ppm PCB, the operations plan must include procedures to determine that liquid PCBs to be disposed of at the landfill do not exceed 500 ppm PCB and measures to prevent the migration of PCBs from the landfill. Bulk liquids not exceeding 500 ppm PCBs may be disposed of provided such waste is pretreated and/or stabilized (e.g., chemically fixed, evaporated, mixed with dry inert absorbant) to reduce its liquid content or increase its solid content so that a non-flowing consistency is achieved to eliminate the presence of free liquids prior to final disposal in a landfill. PCB Container of liquid PCBs with a concentration between 50 and 500 ppm PCB may be disposed of if each container is surrounded by an amount of inert sorbant material capable of absorbing all of the liquid contents of the container.

(iii) Ignitable wastes shall not be disposed of in chemical waste landfills. Liquid ignitable wastes are wastes that have a flash point less than 60 degrees C (140 degrees F) as determined by the following method or an equivalent method: Flash point of liquids shall be determined by a Pensky-Martens Closed Cup Tester, using the protocol specified in ASTM D 93-90, or the Setaflash Closed Tester using the protocol specified in ASTM Standard D-3278-89.

(iv) Records shall be maintained for all PCB disposal operations and shall include information on the PCB concentration in liquid wastes and the three dimensional burial coordinates for PCBs and PCB Items. Additional records shall be developed and maintained as required in § 761.180.

(9) *Supporting facilities.* (i) A six foot woven mesh fence, wall, or similar device shall be placed around the site to prevent unauthorized persons and animals from entering.

(ii) Roads shall be maintained to and within the site which are adequate to support the operation and maintenance of the site without causing safety or nuisance problems or hazardous conditions.

(iii) The site shall be operated and maintained in a manner to prevent safety problems or hazardous conditions resulting from spilled liquids and windblown materials.

(c) *Approval of chemical waste landfills.* Prior to the disposal of any PCBs and PCB Items in a chemical waste landfill, the owner or operator of the landfill shall receive written approval of the Agency Regional Administrator for the Region in which the landfill is located. The approval shall be obtained in the following manner:

(1) *Initial report.* The owner or operator shall submit to the Regional Administrator an initial report which contains:

(i) The location of the landfill;

(ii) A detailed description of the landfill including general site plans and design drawings;

(iii) An engineering report describing the manner in which the landfill complies with the requirements for chemical waste landfills specified in paragraph (b) of this section;

(iv) Sampling and monitoring equipment and facilities available;

(v) Expected waste volumes of PCBs;

(vi) General description of waste materials other than PCBs that are expected to be disposed of in the landfill;

(vii) Landfill operations plan as required in paragraph (b) of this section;

(viii) Any local, State, or Federal permits or approvals; and

(ix) Any schedules or plans for complying with the approval requirements of these regulations.

(2) *Other information.* In addition to the information contained in the report described in paragraph (c)(1) of this section, the Regional Administrator may require the owner or operator to submit any other information that the Regional Administrator finds to be reasonably necessary to determine whether a chemical waste landfill should be approved. Such other information shall be restricted to the types of information required in paragraphs (c)(1) (i) through (ix) of this section.

(3) *Contents of approval.* (i) Except as provided in paragraph (c)(4) of this section the Regional Administrator may not approve a chemical waste landfill for the disposal of PCBs and PCB Items, unless he finds that the landfill meets all of the requirements of paragraph (b) of this section.

(ii) In addition to the requirements of paragraph (b) of this section, the Regional Administrator may include in an approval any other requirements or provisions that the Regional Administrator finds are necessary to ensure that operation of the chemical waste landfill does not present an unreasonable risk of injury to health or the environment from PCBs. Such provisions may include a fixed period of time for which the approval is valid.

The approval may also include a stipulation that the operator of the chemical waste landfill report to the Regional Administrator any instance when PCBs are detectable during monitoring activities conducted pursuant to paragraph (b)(6) of this section.

(4) *Waivers.* An owner or operator of a chemical waste landfill may submit evidence to the Regional Administrator that operation of the landfill will not present an unreasonable risk of injury to health or the environment from PCBs when one or more of the requirements of paragraph (b) of this section are not met. On the basis of such evidence and any other available information, the Regional Administrator may in his discretion find that one or more of the requirements of paragraph (b) of this section is not necessary to protect against such a risk and may waive the requirements in any approval for that landfill. Any finding and waiver under this paragraph will

be stated in writing and included as part of the approval.

(5) *Persons approved.* Any approval will designate the persons who own and who are authorized to operate the chemical waste landfill, and will apply only to such persons, except as provided by paragraph (c)(7) of this section.

(6) *Final approval.* Approval of a chemical waste landfill will be in writing and will be signed by the Regional Administrator. The approval will state all requirements applicable to the approved landfill.

(7) *Transfer of property.* Any person who owns or operates an approved chemical waste landfill must notify EPA at least 30 days before transferring ownership in the property or transferring the right to conduct the chemical waste landfill operation. The transferor must also submit to EPA, at least 30 days before such transfer, a notarized affidavit signed by the transferee which states that the transferee will abide by the transferor's EPA chemical waste landfill approval. Within 30 days of receiving such notification and affidavit, EPA will issue an amended approval substituting the transferee's name for the transferor's name, or EPA may require the transferee to apply for a new chemical waste landfill approval. In the latter case, the transferee must abide by the transferor's EPA approval until EPA issues the new approval to the transferee.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[44 FR 31542, May 31, 1979. Redesignated at 47 FR 19527, May 6, 1982, and amended at 48 FR 5730, Feb. 8, 1983; 49 FR 28191, July 10, 1984; 53 FR 12524, Apr. 15, 1988; 53 FR 21641, June 9, 1988; 57 FR 13323, Apr. 16, 1992; 63 FR 35456, June 29, 1998]

#### §761.77 Coordinated approval.

(a) *General requirements.* Notwithstanding any other provision of this part, the EPA Regional Administrator for the Region in which a PCB disposal or PCB commercial storage facility described in paragraphs (b) and (c) of this section is located may issue a TSCA PCB Coordinated Approval to the persons described in those paragraphs if the conditions listed in this section are

## Environmental Protection Agency

## § 761.77

met. A TSCA PCB Coordinated Approval will designate the persons who own and who are authorized to operate the facilities described in paragraphs (b) and (c) of this section and will apply only to such persons. All requirements, conditions, and limitations of any other permit or waste management document cited or described in paragraphs (b) and (c) of this section, as the technical or legal basis on which the TSCA PCB Coordinated Approval is issued, are conditions of the TSCA PCB Coordinated Approval.

(1) Persons seeking a TSCA PCB Coordinated Approval shall submit a request for approval by certified mail, to the EPA Regional Administrator for the Region in which the activity will take place. Persons seeking a TSCA PCB Coordinated Approval for a new PCB activity shall submit the request for approval at the same time they seek a permit, approval, or other action for a PCB waste management activity under any other Federal or State authority.

(i) The request for a TSCA PCB Coordinated Approval shall include a copy of the letter from EPA announcing or confirming the EPA identification number issued to the facility for conducting PCB activities; the name, organization, and telephone number of the person who is the contact point for the non-TSCA Federal or State waste management authority; a copy of the relevant permit or waste management document specified in paragraphs (b) and (c) of this section, including all requirements, conditions, and limitations, if the EPA Regional Administrator does not have a copy of the document, or a description of the waste management activities to be conducted if a permit or other relevant waste management document has not been issued; and a certification that the person who owns or operates the facility is aware of and will adhere to the TSCA PCB reporting and recordkeeping requirements at subparts J and K of this part.

(ii) The EPA Regional Administrator shall review the request for completeness, for compliance with the requirements of paragraphs (b) and (c) of this section, and to ensure that the PCB activity for which approval is requested

will not present an unreasonable risk of injury to health or the environment. The EPA Regional Administrator shall either:

(A) Issue a written notice of deficiency explaining why the request for approval is deficient. If appropriate, the EPA Regional Administrator may either:

(1) Request additional information to cure the deficiency.

(2) Deny the request for a TSCA PCB Coordinated Approval.

(B) Issue a letter granting or denying the TSCA PCB Coordinated Approval. If the EPA Regional Administrator grants the TSCA PCB Coordinated Approval, he or she may acknowledge the non-TSCA approval meets the regulatory requirements under TSCA as written, or require additional conditions the EPA Regional Administrator has determined are necessary to prevent unreasonable risk of injury to health or the environment.

(C) If the EPA Regional Administrator denies a request for a Coordinated Approval under paragraphs (a)(1)(ii)(A) or (a)(1)(ii)(B) of this section, the person who requested the TSCA PCB Coordinated Approval may submit an application for a TSCA Disposal Approval.

(2) The EPA Regional Administrator may issue a notice of deficiency, revoke the TSCA PCB Coordinated Approval, require the person to whom the TSCA PCB Coordinated Approval was issued to submit an application for a TSCA PCB approval, or bring an enforcement action under TSCA if he or she determines that:

(i) Conditions of the approval relating to PCB waste management activities are not met.

(ii) The PCB waste management process is being operated in a manner which may result in an unreasonable risk of injury to health or the environment.

(iii) The non-TSCA approval expires, is revoked, is suspended, or otherwise ceases to be in full effect.

(3) Any person with a TSCA PCB Coordinated Approval must notify the EPA Regional Administrator in writing within 5 calendar days of changes relating to PCB waste requirements in



the non-TSCA waste management document which serves as the basis for a TSCA PCB Coordinated Approval. Changes in the ownership of a commercial storage facility which holds a TSCA PCB Coordinated Approval shall be handled pursuant to §761.65(j).

(b) Any person who owns or operates a facility that he or she intends to use to landfill PCB wastes; incinerate PCB wastes; dispose of PCB wastes using an alternative disposal method that is equivalent to disposal in an incinerator approved under §761.70 or a high efficiency boiler operating in compliance with §761.71; or stores PCB wastes may apply for a TSCA PCB Coordinated Approval. The EPA Regional Administrator may approve the request if the EPA Regional Administrator determines that the activity will not pose an unreasonable risk of injury to health or the environment and the person:

(1)(i) Has a waste management permit or other decision or enforcement document which exercises control over PCB wastes, issued by EPA or an authorized State Director for a State program that has been approved by EPA and is no less stringent in protection of health or the environment than the applicable TSCA requirements found in this part; or

(ii) Has a PCB waste management permit or other decision or enforcement document issued by a State Director pursuant to a State PCB waste management program no less stringent in protection of health or the environment than the applicable TSCA requirements found in this part; or

(iii) Is subject to a waste management permit or other decision or enforcement document which is applicable to the disposal of PCBs and which was issued through the promulgation of a regulation published in Title 40 of the Code of Federal Regulations.

(2) Complies with the terms and conditions of the permit or other decision or enforcement document described in paragraph (b)(1) of this section.

(3) Unless otherwise waived or modified in writing by the EPA Regional Administrator, complies with §761.75(b); §761.70(a)(1) through (a)(9), (b)(1) and (b)(2), and (c); or the PCB

storage requirements at §§761.65(a), (c), and (d)(2), as appropriate.

(4) Complies with the reporting and recordkeeping requirements in subparts J and K of this part.

(c) A person conducting research and development (R&D) into PCB disposal methods (regardless of PCB concentration), or conducting PCB remediation activities may apply for a TSCA PCB Coordinated Approval. The EPA Regional Administrator may approve the request if the EPA Regional Administrator determines that the activity will not pose an unreasonable risk of injury to health or the environment and the person:

(1)(i) Has a permit or other decision and enforcement document issued or otherwise agreed to by EPA, or permit or other decision and enforcement document issued by an authorized State Director for a State program that has been approved by EPA, which exercises control over the management of PCB wastes, and that person is in compliance with all terms and conditions of that document; or

(ii) Has a permit, which exercises control over the management of PCB wastes, issued by a State Director pursuant to a State PCB disposal program no less stringent than the requirements in this part.

(2) Complies with the terms and conditions of that permit or other decision and enforcement document.

(3) Complies with the reporting and recordkeeping requirements in subparts J and K of this part.

[63 FR 35456, June 29, 1998]

#### **§761.79 Decontamination standards and procedures.**

(a) *Applicability.* This section establishes decontamination standards and procedures for removing PCBs, which are regulated for disposal, from water, organic liquids, non-porous surfaces (including scrap metal from disassembled electrical equipment), concrete, and non-porous surfaces covered with a porous surface, such as paint or coating on metal.

(1) Decontamination in accordance with this section does not require a disposal approval under subpart D of this part.

## Environmental Protection Agency

## § 761.79

(2) Materials from which PCBs have been removed by decontamination in accordance with this section may be distributed in commerce in accordance with § 761.20(c)(5).

(3) Materials from which PCBs have been removed by decontamination in accordance with this section may be used or reused in accordance with § 761.30(u).

(4) Materials from which PCBs have been removed by decontamination in accordance with this section, not including decontamination waste and residuals under paragraph (g) of this section, are unregulated for disposal under subpart D of this part.

(5) Any person decontaminating porous surfaces other than concrete under paragraph (b)(4) of this section and non-porous surfaces covered with a porous surface, such as paint or coating on metal, under paragraph (b)(3) or (c)(6) of this section must obtain an alternative decontamination approval in accordance with paragraph (h) of this section.

(6) Any person engaging in decontamination under this section is responsible for determining and complying with all other applicable Federal, State, and local laws and regulations.

(b) *Decontamination standards.* Chopping (including wire chopping), distilling, filtering, oil/water separation, spraying, soaking, wiping, stripping of insulation, scraping, scarification or the use of abrasives or solvents may be used to remove or separate PCBs, to the following standards, from liquids, concrete, or non-porous surfaces.

(1) The decontamination standard for water containing PCBs is:

(i) Less than 200 µg/L (i.e., <200 ppb PCBs) for non-contact use in a closed system where there are no releases;

(ii) For water discharged to a treatment works (as defined in § 503.9(aa) of this chapter) or to navigable waters, <3 µg/L (approximately <3 ppb) or a PCB discharge limit included in a permit issued under section 307(b) or 402 of the Clean Water Act; or

(iii) Less than or equal to 0.5 µg/L (i.e., approximately ≤0.5 ppb PCBs) for unrestricted use.

(2) The decontamination standard for organic liquids and non-aqueous inor-

ganic liquids containing PCBs is <2 milligrams per kilogram (i.e., <2 ppm PCBs).

(3) The decontamination standard for non-porous surfaces in contact with liquid and non-liquid PCBs is:

(i) For unrestricted use:

(A) For non-porous surfaces previously in contact with liquid PCBs at any concentration, where no free-flowing liquids are currently present, ≤10 micrograms PCBs per 100 square centimeters (≤10 µg/100 cm<sup>2</sup>) as measured by a standard wipe test (§ 761.123) at locations selected in accordance with subpart P of this part.

(B) For non-porous surfaces in contact with non-liquid PCBs (including non-porous surfaces covered with a porous surface, such as paint or coating on metal), cleaning to Visual Standard No. 2, Near-White Blast Cleaned Surface Finish, of the National Association of Corrosion Engineers (NACE). A person shall verify compliance with standard No. 2 by visually inspecting all cleaned areas.

(ii) For disposal in a smelter operating in accordance with § 761.72(b):

(A) For non-porous surfaces previously in contact with liquid PCBs at any concentration, where no free-flowing liquids are currently present, <100 µg/100 cm<sup>2</sup> as measured by a standard wipe test (§ 761.123) at locations selected in accordance with subpart P of this part.

(B) For non-porous surfaces in contact with non-liquid PCBs (including non-porous surfaces covered with a porous surface, such as paint or coating on metal), cleaning to Visual Standard No. 3, Commercial Blast Cleaned Surface Finish, of the National Association of Corrosion Engineers (NACE). A person shall verify compliance with standard No. 3 by visually inspecting all cleaned areas.

(4) The decontamination standard for concrete is ≤10 µg/100 cm<sup>2</sup> as measured by a standard wipe test (§ 761.123) if the decontamination procedure is commenced within 72 hours of the initial spill of PCBs to the concrete or portion thereof being decontaminated.

(c) *Self-implementing decontamination procedures.* The following self-implementing decontamination procedures are available as an alternative to the

measurement-based decontamination methods specified in paragraph (b) of this section. Any person performing self-implementing decontamination must comply with one of the following procedures.

(1) Any person decontaminating a PCB Container must do so by flushing the internal surfaces of the container three times with a solvent containing <50 ppm PCBs. Each rinse shall use a volume of the flushing solvent equal to approximately 10 percent of the PCB Container capacity.

(2) Any person decontaminating movable equipment contaminated by PCBs, tools, and sampling equipment may do so by:

(i) Swabbing surfaces that have contacted PCBs with a solvent;

(ii) A double wash/rinse as defined in subpart S of this part; or

(iii) Another applicable decontamination procedure in this section.

(3) Any person decontaminating a non-porous surface in contact with free-flowing mineral oil dielectric fluid (MODEF) at levels  $\leq 10,000$  ppm PCBs must do so as follows:

(i) Drain the free-flowing MODEF and allow the residual surfaces to drain for an additional 15 hours.

(ii) Dispose of drained MODEF according to paragraph (g) of this section.

(iii) Soak the surfaces to be decontaminated in a sufficient amount of clean (containing <2 ppm PCBs) performance-based organic decontamination fluid (PODF) such that there is a minimum of 800 ml of PODF for each 100 cm<sup>2</sup> of contaminated or potentially contaminated surface for at least 15 hours at  $\geq 20$  °C.

(iv) Approved PODFs include:

(A) Kerosene.

(B) Diesel fuel.

(C) Terpene hydrocarbons.

(D) Mixtures of terpene hydrocarbons and terpene alcohols.

(v) Drain the PODF from the surfaces.

(vi) Dispose of the drained PODF in accordance with paragraph (g) of this section.

(4) Any person decontaminating a non-porous surface in contact with free-flowing MODEF containing >10,000 ppm PCB in MODEF or askarel PCB

(up to 70 percent PCB in a mixture of trichlorobenzenes and tetrachlorobenzenes) must do so as follows:

(i) Drain the free-flowing MODEF or askarel and allow the residual surfaces to drain for an additional 15 hours.

(ii) Dispose of drained MODEF or askarel according to paragraph (g) of this section.

(iii) Soak the surfaces to be decontaminated in a sufficient amount of clean PODF (containing <2 ppm PCBs) such that there is a minimum of 800 ml of PODF for each 100 cm<sup>2</sup> of contaminated or potentially contaminated surface for at least 15 hours at  $\geq 20$  °C.

(iv) Approved PODFs include:

(A) Kerosene.

(B) Diesel fuel.

(C) Terpene hydrocarbons.

(D) Mixtures of terpene hydrocarbons and terpene alcohols.

(v) Drain the PODF from the surfaces.

(vi) Dispose of the drained PODF in accordance with paragraph (g) of this section.

(vii) Resoak the surfaces to be decontaminated, pursuant to paragraph (c)(3)(iii) of this section, in a sufficient amount of clean PODF (containing <2 ppm PCBs) such that there is a minimum of 800 ml of PODF for each 100 cm<sup>2</sup> of surface for at least 15 hours at  $\geq 20$  °C.

(viii) Drain the PODF from the surfaces.

(ix) Dispose of the drained PODF in accordance with paragraph (g) of this section.

(5) Any person decontaminating piping and air lines in an air compressor system must do so as follows:

(i) Before decontamination proceeds, disconnect or bypass the air compressors and air dryers from the piping and air lines and decontaminate the air compressors and air dryers separately in accordance with paragraphs (b), (c)(1) through (c)(4), or (c)(6) of this section. Dispose of filter media and desiccant in the air dryers based on their existing PCB concentration.

(ii) Test the connecting line and appurtenances of the system to assure that there is no leakage. Test by introducing air into the closed system at from 90 to 100 pounds per square inch

## Environmental Protection Agency

## § 761.79

(psi). Only if there is a pressure drop of <5 psi in 30 minutes may decontamination take place.

(iii) When there is no leakage, fill the piping and air lines with clean (containing <2 ppm PCBs) solvent. Solvents include PODF, aqueous potassium hydroxide at a pH between 9 and 12, or water containing 5 percent sodium hydroxide by weight.

(iv) Circulate the solvent to achieve turbulent flow through the piping and air lines in the air compressor system until the total volume of solvent circulated equals 10 times the total volume of the particular article being decontaminated, then drain the solvent. Calculate the total volume of solvent circulated by multiplying the pump rate by the time of pumping. Turbulent flow means a Reynolds number range from 20,000 to 43,000. Refill the system with clean solvent and repeat the circulation and drain process.

(6) Any person using thermal processes to decontaminate metal surfaces in contact with PCBs, as required by § 761.62(a)(6), must use one of the following options:

(i) Surfaces in contact with liquid and non-liquid PCBs at concentrations <500 ppm may be decontaminated in a scrap metal recovery oven or smelter for purposes of disposal in accordance with § 761.72.

(ii) Surfaces in contact with liquid or non-liquid PCBs at concentrations ≥500 ppm may be smelted in a smelter operating in accordance with § 761.72(b), but must first be decontaminated in accordance with § 761.72(a) or to a surface concentration of <100 µg/100 cm<sup>2</sup>.

(d) *Decontamination solvents.* (1) Unless otherwise provided in paragraphs (c)(3) through (c)(5) of this section, the solubility of PCBs in any solvent used for purposes of decontamination under this section must be 5 percent or more by weight.

(2) The solvent may be reused for decontamination so long as its PCB concentration is <50 ppm.

(3) Solvent shall be disposed of under paragraph (g) of this section.

(4) Other than as allowed in paragraphs (c)(3) and (c)(4) of this section, solvents may be tested and validated for performance-based decontamination of non-porous surfaces contami-

nated with MODEF or other PCB liquids, in accordance with the self-implementing procedures found in subpart T of this part. Specific conditions for the performance-based testing from this validation are determined in the validation study.

(e) *Limitation of exposure and control of releases.* (1) Any person conducting decontamination activities under this section shall take necessary measures to protect against direct release of PCBs to the environment from the decontamination area.

(2) Persons participating in decontamination activities shall wear or use protective clothing or equipment to protect against dermal contact or inhalation of PCBs or materials containing PCBs.

(f) *Sampling and recordkeeping.* (1) Confirmatory sampling is required under paragraph (b) of this section. For liquids described in paragraphs (b)(1) and (b)(2) of this section, sample in accordance with §§ 761.269 and 761.272. For non-porous surfaces and concrete described in paragraphs (b)(3) and (b)(4) of this section, sample in accordance with subpart P of this part. A written record of such sampling must be established and maintained for 3 years from the date of any decontamination under this section. The record must show sampling locations and analytical results and must be retained at the site of the decontamination or a copy of the record must be made available to EPA in a timely manner, if requested. In addition, recordkeeping is required in accordance with § 761.180(a) for all wastes generated by a decontamination process and regulated for disposal under this subpart.

(2) Confirmatory sampling is not required for self-implementing decontamination procedures under paragraph (c) of this section. Any person using these procedures must retain a written record documenting compliance with the procedures for 3 years after completion of the decontamination procedures (e.g., video recordings, photographs).

(g) *Decontamination waste and residues.* Decontamination waste and residues shall be disposed of at their existing PCB concentration unless otherwise specified.

## §761.79

## 40 CFR Ch. I (7-1-10 Edition)

(1) Distillation bottoms or residues and filter media are regulated for disposal as PCB remediation waste.

(2) PCBs physically separated from regulated waste during decontamination (such as by chopping, shredding, scraping, abrading or oil/water separation, as opposed to solvent rinsing and soaking), other than wastes described in paragraph (g)(1) of this section, are regulated for disposal at their original concentration.

(3) Hydrocarbon solvent used or reused for decontamination under this section that contains <50 ppm PCB must be burned and marketed in accordance with the requirements for used oil in §761.20(e), disposed of in accordance with §761.60(a) or (e), or decontaminated pursuant to this section.

(4) Chlorinated solvent at any PCB concentration used for decontamination under this section shall be disposed of in an incinerator operating in compliance with §761.70, or decontaminated pursuant to this section.

(5) Solvents ≥50 ppm other than those described in paragraphs (g)(3) and (g)(4) of this section shall be disposed of in accordance with §761.60(a) or decontaminated pursuant to this section.

(6) Non-liquid cleaning materials and personal protective equipment waste at any concentration, including non-porous surfaces and other non-liquid materials such as rags, gloves, booties, other disposable personal protective equipment, and similar materials resulting from decontamination shall be disposed of in accordance with §761.61(a)(5)(v).

(h) *Alternative decontamination or sampling approval.* (1) Any person wishing to decontaminate material described in paragraph (a) of this section in a manner other than prescribed in paragraph (b) of this section must apply in writing to the Regional Administrator in the Region where the activity would take place, for decontamination activity occurring in a single EPA Region; or to the Director, Office of Resource Conservation and Recovery, for decontamination activity occurring in more than one EPA Region. Each application must describe the material to be decontaminated and the proposed decontamination method, and must demonstrate that the proposed method is

capable of decontaminating the material to the applicable level set out in paragraphs (b)(1) through (b)(4) of this section.

(2) Any person wishing to decontaminate material described in paragraph (a) of this section using a self-implementing procedure other than prescribed in paragraph (c) of this section must apply in writing to the Regional Administrator in the Region where the activity would take place, for decontamination activity occurring in a single EPA Region; or to the Director, Office of Resource Conservation and Recovery, for decontamination activity occurring in more than one EPA Region. Each application must describe the material to be decontaminated and the proposed self-implementing decontamination method and must include a proposed validation study to confirm performance of the method.

(3) Any person wishing to sample decontaminated material in a manner other than prescribed in paragraph (f) of this section must apply in writing to the Regional Administrator in the Region where the activity would take place, for decontamination activity occurring in a single EPA Region; or to the Director, Office of Resource Conservation and Recovery, for decontamination activity occurring in more than one EPA Region. Each application must contain a description of the material to be decontaminated, the nature and PCB concentration of the contaminating material (if known), the decontamination method, the proposed sampling procedure, and a justification for how the proposed sampling is equivalent to or more comprehensive than the sampling procedure required under paragraph (f) of this section.

(4) EPA may request additional information that it believes necessary to evaluate the application.

(5) EPA will issue a written decision on each application for risk-based decontamination or sampling. No person may conduct decontamination or sampling under this paragraph prior to obtaining written approval from EPA. EPA will approve an application if it finds that the proposed decontamination or sampling method will not pose

an unreasonable risk of injury to health or the environment.

[63 FR 35457, June 29, 1998, as amended at 64 FR 33761, June 24, 1999; 72 FR 57240, Oct. 9, 2007; 74 FR 30233, June 25, 2009]

### Subpart E—Exemptions

#### § 761.80 Manufacturing, processing and distribution in commerce exemptions.

(a) The Administrator grants the following petitioner(s) an exemption for 1 year to process and distribute in commerce PCBs for use as a mounting medium in microscopy:

(1) McCrone Accessories Components, Division of Walter C. McCrone Associates, Inc., 2820 South Michigan Avenue, Chicago, IL. 60616.

(2) [Reserved]

(b) The Administrator grants the following petitioner(s) an exemption for 1 year to process and distribute in commerce PCBs for use as a mounting medium in microscopy, an immersion oil in low fluorescence microscopy and an optical liquid:

(1) R.P. Cargille Laboratories, Inc., 55 Commerce Road, Cedar Grove, N.J. 07009.

(2) [Reserved]

(c) The Administrator grants the following petitioner(s) an exemption for 1 year to export PCBs for use in small quantities for research and development:

(1) Accu-Standard, New Haven, CT. 06503.

(2) ManTech, Research Triangle Park, NC 27709.

(d) The Administrator grants the following petitioner(s) an exemption for 1 year to import (manufacture) into the United States, small quantities of existing PCB fluids from electrical equipment for analysis:

(1) Unison Transformer Services, Inc., Tarrytown, N.Y. 10591, provided each of the following conditions are met:

(i) The samples must be shipped in 5.0 ml or less, hermetically sealed vials.

(ii) The exemption is limited to no more than 250 total samples per year.

(iii) Unison makes quarterly inspections of its laboratories to ensure that proper safety procedures are being followed.

(iv) Unison annually notifies and describes to EPA its attempts to have samples analyzed abroad.

(2) [Reserved]

(e) The Administrator grants a class exemption to all research and development (R&D) facilities for a period of 1 year to manufacture or import PCBs for use solely in the manufacturer or importer's own research for the development of PCB disposal technologies. Each person that wishes to be part of the exemption must meet the following conditions:

(1) A petition for an exemption from the PCB prohibition on manufacturing PCBs must be received by EPA 60 days prior to engaging in these activities.

(2) Requests for renewal must be filed pursuant to § 750.11 of this chapter. EPA will deem any properly filed request for the renewal of the exemption by any member of the class as a renewal request for the entire class.

(3) The quantity of the PCBs manufactured annually must not exceed 500 grams by total weight of pure PCBs. Any person who wishes to manufacture or import more than 500 grams of PCBs in 1 year must receive written approval from the Director, National Program Chemicals Division to exceed the limitations established by this provision. The Director, National Program Chemicals Division may grant approval without further rulemaking. Any increase granted will be in writing and will extend only for a maximum of the time remaining in a specific exemption year.

(4) The owner or operator of the facility must notify the EPA Regional Administrator in writing 30 days prior to the commencement of R&D activities that include the manufacture or import of PCBs under the exemption, unless the facility has obtained a PCB R&D approval from EPA pursuant to § 761.60(e), § 761.60(i)(2), § 761.70(a), or § 761.70(b) and the approval contains a provision allowing the manufacture of PCBs.

(5) Records are maintained of their PCB activities for a period of 3 years after ceasing operations. The records must include the sources and the annual amounts of PCBs received if imported and the type and annual amount of PCBs that were manufactured.

(6) All PCBs and materials containing PCBs, regardless of concentration, remaining from the disposal-related studies must be disposed of according to §761.60(j)(1)(vi), or decontaminated pursuant to §761.79, based on the original PCB concentration.

(f) The Administrator grants the following petitioner(s) an exemption for 1 year to manufacture PCBs for use in small quantities for research and development:

(1) California Bionuclear Corp., Sun Valley, CA 91352 (ME-13).

(2) Foxboro Co., North Haven, CT 06473 (ME-6).

(3) ULTRA-Scientific, Inc., Hope, RI 02831 (ME-99.1).

(4) Midwest Research Institute, Kansas City, MO 64110 (ME-70.1).

(5) Pathfinder Laboratories, St. Louis, MO 63146 (A division of Sigma Aldridge Corporation, St. Louis, MO, 63178 (ME-76).

(6) Radian Corp., Austin, TX 78766 (ME-81.2).

(7) Wellington Sciences USA, College Station, TX 77840 (ME-104.1).

(8) Accu-Standard, 25 Science Park, New Haven, CT. 06503.

(g) The Administrator grants a class exemption to all processors and distributors of PCBs in small quantities for research and development provided that the following conditions are met:

(1) All processors and distributors must maintain records of their PCB activities for a period of 5 years.

(2) Any person or company which expects to process or distribute in commerce 100 grams (.22 lb) or more PCBs in 1 year must report to EPA identifying the sites of PCB activities and the quantity of PCBs to be processed or distributed in commerce.

(h) The Administrator grants the following petitioners an exemption for 1 year to process and distribute in commerce PCBs for analytical reference samples derived from actual waste materials:

(1) R.T. Corporation, Laramie, WY 82070.

(2) [Reserved]

(i) The Administrator grants a class exemption to all persons who manufacture, import, process, distribute in commerce, or export PCBs, or analytical reference samples derived from

PCB waste material, provided the PCBs are manufactured, imported, processed, distributed in commerce, or exported solely for the purpose of R&D and the following conditions are met:

(1) Notification in the form of a petition for an exemption from the PCB prohibitions on manufacture, import, processing, distribution in commerce, or export is received by EPA 60 days prior to engaging in these activities.

(2) Requests for renewal are filed pursuant to §§750.11 and 750.31 of this chapter. EPA will deem any properly filed request for the renewal of the exemption by any member of the class as a renewal request for the entire class.

(3) The PCBs are packaged in one or more hermetically sealed containers of a volume of no more than 5.0 ml each. Analytical reference samples derived from PCB waste material may be packaged in a container larger than 5.0 ml when packaged pursuant to applicable DOT performance standards.

(4) The quantity of PCBs manufactured, imported, processed, distributed in commerce, or exported annually must not exceed 500 grams by total weight of pure PCBs. Any person who expects to manufacture, import, process, distribute in commerce, or export more than 500 grams of PCBs in 1 year or to exceed the 5.0 ml packaging requirement must obtain a written approval from the Director, National Program Chemicals Division and must identify the sites of PCB activities and the quantity of PCBs to be manufactured, imported, processed, distributed in commerce, or exported. Each request must include a justification. The Director, National Program Chemicals Division, may grant approval without further rulemaking. Any increase granted will be in writing and will extend only for a maximum of the time remaining in a specific exemption year.

(5) All treated and untreated PCB regulated material and material coming into contact with regulated material must be stored and disposed of according to subpart D of this part, or decontaminated pursuant to §761.79.

(6) All PCB materials must be distributed in DOT-authorized packaging.

(7) Records are maintained of their PCB activities for a period of 3 years after ceasing operations. The records

## Environmental Protection Agency

## § 761.91

must include the sources and the annual amounts of PCBs received if imported, the annual amount of PCBs that were manufactured, the annual amount of PCBs that were processed and/or distributed in commerce (to include export), and the persons to whom the PCBs were shipped.

(j) The Administrator grants the United States Defense Logistics Agency's July 21, 2005 petition for an exemption for 1 year to import 1,328,482 pounds of PCBs and PCB items stored or in use in Japan as identified in its petition, as amended, for disposal.

(k)-(l) [Reserved]

(m) The Administrator grants the following petitioner(s) an exemption for 1 year to process and export small quantities of PCBs for research and development:

(1) Chem Service, Inc., West Chester, PA 19380 (PDE-41).

(2) Foxboro Co., North Haven, CT 06473 (ME-6).

(3) PolyScience Corp., Niles, IL 60648 (PDE-178).

(4) ULTRA-Scientific, Inc., Hope, RI 02831 (PDE-282.1).

(5) Supelco, Inc., Bellefonte, PA 16823-0048 (PDE-41.2).

(6) Radian Corp., Austin, TX 78766 (PDE-182.1).

(7) Restek Corporation, Bellefonte, PA

(n) The 1-year exemption granted to petitioners in paragraphs (a) through (c)(1), (d), (f), and (m)(1) through (m)(6) of this section shall be renewed automatically as long as there is no increase in the amount of PCBs to be processed and distributed, imported (manufactured), or exported, nor any change in the manner of processing and distributing, importing (manufacturing), or exporting of PCBs. If there is such a change, a new exemption petition must be submitted to EPA and it will be addressed through an exemption rulemaking. In such a case, the activities granted under the existing exemption may continue until the new petition is addressed by rulemaking, but must conform to the terms of the existing exemption approved by EPA. The 1-year exemption granted to petitioners in paragraphs (c)(2), (h) and (m)(7) of this section may be extended pursuant to 40 CFR 750.11(e) or 750.31(e).

(o) The 1-year class exemption granted to all processors and distributors of PCBs in small quantities for research and development in paragraph (g) of this section shall be renewed automatically unless information is submitted affecting EPA's conclusion that the class exemption, or the activities of any individual or company included in the exemption, will not pose an unreasonable risk of injury to health or the environment. EPA will evaluate the information, issue a proposed rule for public comment, and issue a final rule affecting the class exemption or individuals or companies included in the class exemption. Until EPA issues a final rule, individuals and companies included in the class exemption will be allowed to continue processing and distributing PCBs in small quantities for research and development.

[55 FR 38999, Sept. 24, 1990, as amended at 59 FR 16998, Apr. 11, 1994; 63 FR 35460, June 29, 1998; 68 FR 4941, Jan. 31, 2003; 72 FR 53158, Sept. 18, 2007]

### Subpart F—Transboundary Shipments of PCBs for Disposal

SOURCE: 61 FR 11107, Mar. 18, 1996, unless otherwise noted.

#### § 761.91 Applicability.

This subpart establishes requirements under section 6 of TSCA applicable to the transboundary shipments of PCBs and PCB Items into and out of the United States for disposal. Nothing in this subpart is intended to obviate or otherwise alter obligations applicable to imported or exported PCBs and PCB Items under foreign laws, international agreements or arrangements, other United States statutes and regulations, other sections of TSCA (e.g., sections 13 and 14), or laws of the various States of the United States. No provision of this section shall be construed to affect or limit the applicability of any requirement applicable to transporters of PCB waste under regulations issued by the U.S. Department of Transportation (DOT) and set forth at 49 CFR parts 171-180.



## § 761.93

### § 761.93 Import for disposal.

(a) *General provisions.* No person may import PCBs or PCB Items for disposal without an exemption issued under the authority of TSCA section 6(e)(3).

(b) [Reserved]

[63 FR 35460, June 29, 1998]

### § 761.97 Export for disposal.

(a) *General provisions.* No person may export PCBs or PCB Items for disposal without an exemption, except that:

(1) PCBs and PCB Items at concentrations <50 ppm (or <10 µg PCB/100 cm<sup>2</sup> if no free-flowing liquids are present) may be exported for disposal.

(2) For the purposes of this section, PCBs and PCB Items of unknown concentrations shall be treated as if they contain ≥50 ppm.

(b) [Reserved]

[61 FR 11107, Mar. 18, 1996, as amended at 63 FR 35460, June 29, 1998]

### § 761.99 Other transboundary shipments.

For purposes of this subpart, the following transboundary shipments are not considered exports or imports:

(a) PCB waste generated in the United States, transported outside the Customs Territory of the United States (including any residuals resulting from cleanup of spills of such wastes in transit) through another country or its territorial waters, or through international waters, and returned to the United States for disposal.

(b) PCB waste in transit, including any residuals resulting from cleanup of spills during transit, through the United States (e.g., from Mexico to Canada, from Canada to Mexico).

(c) PCB waste transported from any State to any other State for disposal, regardless of whether the waste enters or leaves the customs territory of the United States, provided that the PCB waste or the PCBs from which the waste was derived were present in the United States on January 1, 1979, and have remained within the United States since that date.

[63 FR 35461, June 29, 1998, as amended at 66 FR 17478, Mar. 30, 2001]

## 40 CFR Ch. I (7-1-10 Edition)

### Subpart G—PCB Spill Cleanup Policy

SOURCE: 52 FR 10705, Apr. 2, 1987, unless otherwise noted.

### § 761.120 Scope.

(a) *General.* This policy establishes criteria EPA will use to determine the adequacy of the cleanup of spills resulting from the release of materials containing PCBs at concentrations of 50 ppm or greater. The policy applies to spills which occur after May 4, 1987.

(1) Existing spills (spills which occurred prior to May 4, 1987, are excluded from the scope of this policy for two reasons:

(i) For old spills which have already been discovered, this policy is not intended to require additional cleanup where a party has already cleaned a spill in accordance with requirements imposed by EPA through its regional offices, nor is this policy intended to interfere with ongoing litigation of enforcement actions which bring into issue PCB spills cleanup.

(ii) EPA recognizes that old spills which are discovered after the effective date of this policy will require site-by-site evaluation because of the likelihood that the site involves more pervasive PCB contamination than fresh spills and because old spills are generally more difficult to clean up than fresh spills (particularly on porous surfaces such as concrete). Therefore, spills which occurred before the effective date of this policy are to be decontaminated to requirements established at the discretion of EPA, usually through its regional offices.

(2) EPA expects most PCB spills subject to the TSCA PCB regulations to conform to the typical spill situations considered in developing this policy. This policy does, however, exclude from application of the final numerical cleanup standards certain spill situations from its scope: Spills directly into surface waters, drinking water, sewers, grazing lands, and vegetable gardens. These types of spills are subject to final cleanup standards to be established at the discretion of the regional office. These spills are, however, subject to the immediate notification

requirements and measures to minimize further environmental contamination.

(3) For all other spills, EPA generally expects the decontamination standards of this policy to apply. Occasionally, some small percentage of spills covered by this policy may warrant more stringent cleanup requirements because of additional routes of exposure or significantly greater exposures than those assumed in developing the final cleanup standards of this policy. While the EPA regional offices have the authority to require additional cleanup in these circumstances, the Regional Administrator must first make a finding based on the specific facts of a spill that additional cleanup must occur to prevent unreasonable risk. In addition, before a final decision is made to require additional cleanup, the Regional Administrator must notify the Director, Office of Resource Conservation and Recovery of his/her finding and the basis for the finding.

(4) There may also be exceptional spill situations that requires less stringent cleanup or a different approach to cleanup because of factors associated with the particular spill. These factors may mitigate expected exposures and risks or make cleanup to these requirements impracticable.

(b) *Spills that may require more stringent cleanup levels.* For spills within the scope of this policy, EPA generally retains, under § 761.135, the authority to require additional cleanup upon finding that, despite good faith efforts by the responsible party, the numerical decontamination levels in the policy have not been met. In addition, EPA foresees the possibility of exceptional spill situations in which site-specific risk factors may warrant additional cleanup to more stringent numerical decontamination levels than are required by the policy. In these situations, the Regional Administrator has the authority to require cleanup to levels lower than those included in this policy upon finding that further cleanup must occur to prevent unreasonable risk. The Regional Administrator will consult with the Director, Office of Resource Conservation and Recovery, prior to making such a finding.

(1) For example, site-specific characteristics, such as short depth of ground water, type of soil, or the presence of a shallow well, may pose exceptionally high potential for ground water contamination by PCBs remaining after cleanup to the standards specified in this policy. Spills that pose such a high degree of potential for ground water contamination have not been excluded from the policy under paragraph (d) of this section because the presence of such potential may not be readily apparent. EPA feels that automatically excluding such spills from the scope of the policy could result in the delay of cleanup—a particularly undesirable outcome if potential ground water contamination is, in fact, a significant concern.

(2) In those situations, the Regional Administrator may require cleanup in addition to that required under § 761.125(b) and (c). However, the Regional Administrator must first make a finding, based on the specific facts of a spill, that additional cleanup is necessary to prevent unreasonable risk. In addition, before making a final decision on additional cleanup, the Regional Administrator must notify the Director, Office of Resource Conservation and Recovery of his finding and the basis for the finding.

(c) *Flexibility to allow less stringent or alternative requirements.* EPA retains the flexibility to allow less stringent or alternative decontamination measures based upon site-specific considerations. EPA will exercise this flexibility if the responsible party demonstrates that cleanup to the numerical decontamination levels is clearly unwarranted because of risk-mitigating factors, that compliance with the procedural requirements or numerical standards in the policy is impracticable at a particular site, or that site-specific characteristics make the costs of cleanup prohibitive. The Regional Administrator will notify the Director, Office of Resource Conservation and Recovery of any decision and the basis for the decision to allow less stringent cleanup. The purpose of this notification is to enable the Director, Office of Resource Conservation and Recovery to ensure consistency of spill cleanup standards

under special circumstances across the regions.

(d) *Excluded spills.* (1) Although the spill situations in paragraphs (d)(2) (i) through (vi) of this section are excluded from the automatic application of final decontamination standards under § 761.125 (b) and (c), the general requirements under § 761.125(a) do apply to these spills. In addition, all of these excluded situations require practicable, immediate actions to contain the area of contamination. While these situations may not always require more stringent cleanup measures, the Agency is excluding these scenarios because they will always involve significant factors that may not be adequately addressed by cleanup standards based upon typical spill characteristics.

(2) For the spill situations in paragraphs (d)(2)(i) through (vi) of this section, the responsible party shall decontaminate the spill in accordance with site-specific requirements established by the EPA regional offices.

(i) Spills that result in the direct contamination of surface waters (surface waters include, but are not limited to, “waters of the United States” as defined in part 122 of this chapter, ponds, lagoons, wetlands, and storage reservoirs).

(ii) Spills that result in the direct contamination of sewers or sewage treatment systems.

(iii) Spills that result in the direct contamination of any private or public drinking water sources or distribution systems.

(iv) Spills which migrate to and contaminate surface waters, sewers, or drinking water supplies before cleanup has been completed in accordance with this policy.

(v) Spills that contaminate animal grazing lands.

(vi) Spills that contaminate vegetable gardens.

(e) *Relationship of policy to other statutes.* (1) This policy does not affect cleanup standards or requirements for the reporting of spills imposed, or to be imposed, under other Federal statutory authorities, including but not limited to, the Clean Water Act (CWA), the Resource Conservation and Recovery Act (RCRA), and the Comprehensive Envi-

ronmental Response Compensation and Liability Act of 1980 (CERCLA) as amended by the Superfund Amendments and Reauthorization Act (SARA). Where more than one requirement applies, the stricter standard must be met.

(2) The Agency recognizes that the existence of this policy will inevitably result in attempts to apply the standards to situations within the scope of other statutory authorities. However, other statutes require the Agency to consider different or alternative factors in determining appropriate corrective actions. In addition, the types and magnitudes of exposures associated with sites requiring corrective action under other statutes often involve important differences from those expected of the typical, electrical equipment-type spills considered in developing this policy. Thus, cleanups under other statutes, such as RCRA corrective actions or remedial and response actions under SARA may result in different outcomes.

[52 FR 10705, Apr. 2, 1987, as amended at 72 FR 57241, Oct. 9, 2007; 74 FR 30234, June 25, 2009]

#### § 761.123 Definitions.

For purposes of this policy, certain words and phrases are used to denote specific materials, procedures, or circumstances. The following definitions are provided for purposes of clarity and are not to be taken as exhaustive lists of situations and materials covered by the policy.

*Double wash/rinse* means a minimum requirement to cleanse solid surfaces (both impervious and nonimpervious) two times with an appropriate solvent or other material in which PCBs are at least 5 percent soluble (by weight). A volume of PCB-free fluid sufficient to cover the contaminated surface completely must be used in each wash/rinse. The wash/rinse requirement does not mean the mere spreading of solvent or other fluid over the surface, nor does the requirement mean a once-over wipe with a soaked cloth. Precautions must be taken to contain any runoff resulting from the cleansing and to dispose properly of wastes generated during the cleansing.

*High-concentration PCBs* means PCBs that contain 500 ppm or greater PCBs, or those materials which EPA requires to be assumed to contain 500 ppm or greater PCBs in the absence of testing.

*High-contact industrial surface* means a surface in an industrial setting which is repeatedly touched, often for relatively long periods of time. Manned machinery and control panels are examples of high-contact industrial surfaces. High-contact industrial surfaces are generally of impervious solid material. Examples of low-contact industrial surfaces include ceilings, walls, floors, roofs, roadways and sidewalks in the industrial area, utility poles, unmanned machinery, concrete pads beneath electrical equipment, curbing, exterior structural building components, indoor vaults, and pipes.

*High-contact residential/commercial surface* means a surface in a residential/commercial area which is repeatedly touched, often for relatively long periods of time. Doors, wall areas below 6 feet in height, uncovered flooring, windowsills, fencing, bannisters, stairs, automobiles, and children's play areas such as outdoor patios and sidewalks are examples of high-contact residential/commercial surfaces. Examples of low-contact residential/commercial surfaces include interior ceilings, interior wall areas above 6 feet in height, roofs, asphalt roadways, concrete roadways, wooden utility poles, unmanned machinery, concrete pads beneath electrical equipment, curbing, exterior structural building components (e.g., aluminum/vinyl siding, cinder block, asphalt tiles), and pipes.

*Impervious solid surfaces* means solid surfaces which are nonporous and thus unlikely to absorb spilled PCBs within the short period of time required for cleanup of spills under this policy. Impervious solid surfaces include, but are not limited to, metals, glass, aluminum siding, and enameled or laminated surfaces.

*Low-concentration PCBs* means PCBs that are tested and found to contain less than 500 ppm PCBs, or those PCB-containing materials which EPA requires to be assumed to be at concentrations below 500 ppm (i.e., untested mineral oil dielectric fluid).

*Nonimpervious solid surfaces* means solid surfaces which are porous and are more likely to absorb spilled PCBs prior to completion of the cleanup requirements prescribed in this policy. Nonimpervious solid surfaces include, but are not limited to, wood, concrete, asphalt, and plasterboard.

*Nonrestricted access areas* means any area other than restricted access, outdoor electrical substations, and other restricted access locations, as defined in this section. In addition to residential/commercial areas, these areas include unrestricted access rural areas (areas of low density development and population where access is uncontrolled by either man-made barriers or naturally occurring barriers, such as rough terrain, mountains, or cliffs).

*Other restricted access (nonsubstation) locations* means areas other than electrical substations that are at least 0.1 kilometer (km) from a residential/commercial area and limited by man-made barriers (e.g., fences and walls) to substantially limited by naturally occurring barriers such as mountains, cliffs, or rough terrain. These areas generally include industrial facilities and extremely remote rural locations. (Areas where access is restricted but are less than 0.1 km from a residential/commercial area are considered to be residential/commercial areas.)

*Outdoor electrical substations* means outdoor, fenced-off, and restricted access areas used in the transmission and/or distribution of electrical power. Outdoor electrical substations restrict public access by being fenced or walled off as defined under § 761.30(1)(1)(ii). For purposes of this TSCA policy, outdoor electrical substations are defined as being located at least 0.1 km from a residential/commercial area. Outdoor fenced-off and restricted access areas used in the transmission and/or distribution of electrical power which are located less than 0.1 km from a residential/commercial area are considered to be residential/commercial areas.

*PCBs* means polychlorinated biphenyls as defined under § 761.3. As specified under § 761.1(b), no requirements may be avoided through dilution of the PCB concentration.

*Requirements and standards* means:

(1) “Requirements” as used in this policy refers to both the procedural responses and numerical decontamination levels set forth in this policy as constituting adequate cleanup of PCBs.

(2) “Standards” refers to the numerical decontamination levels set forth in this policy.

*Residential/commercial areas* means those areas where people live or reside, or where people work in other than manufacturing or farming industries. Residential areas include housing and the property on which housing is located, as well as playgrounds, roadways, sidewalks, parks, and other similar areas within a residential community. Commercial areas are typically accessible to both members of the general public and employees and include public assembly properties, institutional properties, stores, office buildings, and transportation centers.

*Responsible party* means the owner of the PCB equipment, facility, or other source of PCBs or his/her designated agent (e.g., a facility manager or foreman).

*Soil* means all vegetation, soils and other ground media, including but not limited to, sand, grass, gravel, and oyster shells. It does not include concrete and asphalt.

*Spill* means both intentional and unintentional spills, leaks, and other uncontrolled discharges where the release results in any quantity of PCBs running off or about to run off the external surface of the equipment or other PCB source, as well as the contamination resulting from those releases. This policy applies to spills of 50 ppm or greater PCBs. The concentration of PCBs spilled is determined by the PCB concentration in the material spilled as opposed to the concentration of PCBs in the material onto which the PCBs were spilled. Where a spill of untested mineral oil occurs, the oil is presumed to contain greater than 50 ppm, but less than 500 ppm PCBs and is subject to the relevant requirements of this policy.

*Spill area* means the area of soil on which visible traces of the spill can be observed plus a buffer zone of 1 foot beyond the visible traces. Any surface or object (e.g., concrete sidewalk or automobile) within the visible traces area

or on which visible traces of the spilled material are observed is included in the spill area. This area represents the minimum area assumed to be contaminated by PCBs in the absence of precleanup sampling data and is thus the minimum area which must be cleaned.

*Spill boundaries* means the actual area of contamination as determined by postcleanup verification sampling or by precleanup sampling to determine actual spill boundaries. EPA can require additional cleanup when necessary to decontaminate all areas within the spill boundaries to the levels required in this policy (e.g., additional cleanup will be required if postcleanup sampling indicates that the area decontaminated by the responsible party, such as the spill area as defined in this section, did not encompass the actual boundaries of PCB contamination).

*Standard wipe test* means, for spills of high-concentration PCBs on solid surfaces, a cleanup to numerical surface standards and sampling by a standard wipe test to verify that the numerical standards have been met. This definition constitutes the minimum requirements for an appropriate wipe testing protocol. A standard-size template (10 centimeters (cm) × 10 cm) will be used to delineate the area of cleanup; the wiping medium will be a gauze pad or glass wool of known size which has been saturated with hexane. It is important that the wipe be performed very quickly after the hexane is exposed to air. EPA strongly recommends that the gauze (or glass wool) be prepared with hexane in the laboratory and that the wiping medium be stored in sealed glass vials until it is used for the wipe test. Further, EPA requires the collection and testing of field blanks and replicates.

[52 FR 10705, Apr. 2, 1987; 52 FR 23397, June 19, 1987]

#### **§761.125 Requirements for PCB spill cleanup.**

(a) *General.* Unless expressly limited, the reporting, disposal, and precleanup sampling requirements in paragraphs (a) (1) through (3) of this section apply to all spills of PCBs at concentrations of 50 ppm or greater which are subject to decontamination requirements

under TSCA, including those spills listed under § 761.120(b) which are excluded from the cleanup standards at paragraphs (b) and (c) of this section.

(1) *Reporting requirements.* The reporting in paragraphs (a)(1) (i) through (iv) of this section is required in addition to applicable reporting requirements under the Clean Water Act (CWA) or the Comprehensive Environmental Response Compensation and Liability Act of 1980 (CERCLA). For example, under the National Contingency Plan all spills involving 1 pound or more by weight of PCBs must currently be reported to the National Response Center (1-800-424-8802). The requirements in paragraphs (a)(1) (i) through (iv) of this section are designed to be consistent with existing reporting requirements to the extent possible so as to minimize reporting burdens on governments as well as the regulated community.

(i) Where a spill directly contaminates surface water, sewers, or drinking water supplies, as discussed under § 761.120(d), the responsible party shall notify the appropriate EPA regional office and obtain guidance for appropriate cleanup measures in the shortest possible time after discovery, but in no case later than 24 hours after discovery.

(ii) Where a spill directly contaminates grazing lands or vegetable gardens, as discussed under § 761.120(d), the responsible party shall notify the appropriate EPA regional office and proceed with the immediate requirements specified under paragraph (b) or (c) of this section, depending on the source of the spill, in the shortest possible time after discovery, but in no case later than 24 hours after discovery.

(iii) Where a spill exceeds 10 pounds of PCBs by weight and is not addressed in paragraph (a)(1) (i) or (ii) of this section, the responsible party will notify the appropriate EPA regional office and proceed to decontaminate the spill area in accordance with this TSCA policy in the shortest possible time after discovery, but in no case later than 24 hours after discovery.

(iv) Spills of 10 pounds or less, which are not addressed in paragraph (a)(1) (i) or (ii) of this section, must be cleaned up in accordance with this policy (in order to avoid EPA enforcement liabil-

ity), but notification of EPA is not required.

(2) *Disposal of cleanup debris and materials.* All concentrated soils, solvents, rags, and other materials resulting from the cleanup of PCBs under this policy shall be properly stored, labeled, and disposed of in accordance with the provisions of subpart D of this part.

(3) *Determination of spill boundaries in the absence of visible traces.* For spills where there are insufficient visible traces yet there is evidence of a leak or spill, the boundaries of the spill are to be determined by using a statistically based sampling scheme.

(b) *Requirements for cleanup of low-concentration spills which involve less than 1 pound of PCBs by weight (less than 270 gallons of untested mineral oil)—*

(1) *Decontamination requirements.* Spills of less than 270 gallons of untested mineral oil, low-concentration PCBs, as defined under § 761.123, which involve less than 1 pound of PCBs by weight (e.g., less than 270 gallons of untested mineral oil containing less than 500 ppm PCBs) shall be cleaned in the following manner:

(i) Solid surfaces must be double washed/rinsed (as defined under § 761.123); except that all indoor, residential surfaces other than vault areas must be cleaned to 10 micrograms per 100 square centimeters (10 µg/100 cm<sup>2</sup>) by standard commercial wipe tests.

(ii) All soil within the spill area (i.e., visible traces of soil and a buffer of 1 lateral foot around the visible traces) must be excavated, and the ground be restored to its original configuration by back-filling with clean soil (i.e., containing less than 1 ppm PCBs).

(iii) Requirements of paragraphs (b)(1) (i) and (ii) of this section must be completed within 48 hours after the responsible party was notified or became aware of the spill.

(2) *Effect of emergency or adverse weather.* Completion of cleanup may be delayed beyond 48 hours in case of circumstances including but not limited to, civil emergency, adverse weather conditions, lack of access to the site, and emergency operating conditions. The occurrence of a spill on a weekend or overtime costs are not acceptable reasons to delay response. Completion of cleanup may be delayed only for the

duration of the adverse conditions. If the adverse weather conditions, or time lapse due to other emergency, has left insufficient visible traces, the responsible party must use a statistically based sampling scheme to determine the spill boundaries as required under paragraph (a)(3) of this section.

(3) *Records and certification.* At the completion of cleanup, the responsible party shall document the cleanup with records and certification of decontamination. The records and certification must be maintained for a period of 5 years. The records and certification shall consist of the following:

(i) Identification of the source of the spill (e.g., type of equipment).

(ii) Estimated or actual date and time of the spill occurrence.

(iii) The date and time cleanup was completed or terminated (if cleanup was delayed by emergency or adverse weather; the nature and duration of the delay).

(iv) A brief description of the spill location.

(v) Precleanup sampling data used to establish the spill boundaries if required because of insufficient visible traces, and a brief description of the sampling methodology used to establish the spill boundaries.

(vi) A brief description of the solid surfaces cleaned and of the double wash/rinse method used.

(vii) Approximate depth of soil excavation and the amount of soil removed.

(viii) A certification statement signed by the responsible party stating that the cleanup requirements have been met and that the information contained in the record is true to the best of his/her knowledge.

(ix) While not required for compliance with this policy, the following information would be useful if maintained in the records:

(A) Additional pre- or post-cleanup sampling.

(B) The estimated cost of the cleanup by man-hours, dollars, or both.

(c) *Requirements for cleanup of high-concentration spills and low-concentration spills involving 1 pound or more PCBs by weight (270 gallons or more of untested mineral oil).* Cleanup of low-concentration spills involving 1 lb or more PCBs by weight and of all spills

of materials other than low-concentration materials shall be considered complete if all of the immediate requirements, cleanup standards, sampling, and recordkeeping requirements of paragraphs (c) (1) through (5) of this section are met.

(1) *Immediate requirements.* The four actions in paragraphs (c)(1) (i) through (iv) of this section must be taken as quickly as possible and within no more than 24 hours (or within 48 hours for PCB Transformers) after the responsible party was notified or became aware of the spill, except that actions described in paragraphs (c)(1) (ii) through (iv) of this section can be delayed beyond 24 hours if circumstances (e.g., civil emergency, hurricane, tornado, or other similar adverse weather conditions, lack of access due to physical impossibility, or emergency operating conditions) so require for the duration of the adverse conditions. The occurrence of a spill on a weekend or overtime costs are not acceptable reasons to delay response. Owners of spilled PCBs who have delayed cleanup because of these types of circumstances must keep records documenting the fact that circumstances precluded rapid response.

(i) The responsible party shall notify the EPA regional office and the NRC as required by §761.125(a)(1) or by other applicable statutes.

(ii) The responsible party shall effectively cordon off or otherwise delineate and restrict an area encompassing any visible traces plus a 3-foot buffer and place clearly visible signs advising persons to avoid the area to minimize the spread of contamination as well as the potential for human exposure.

(iii) The responsible party shall record and document the area of visible contamination, noting the extent of the visible trace areas and the center of the visible trace area. If there are no visible traces, the responsible party shall record this fact and contact the regional office of the EPA for guidance in completing statistical sampling of the spill area to establish spill boundaries.

(iv) The responsible party shall initiate cleanup of all visible traces of the fluid on hard surfaces and initiate removal of all visible traces of the spill

on soil and other media, such as gravel, sand, oyster shells, etc.

(v) If there has been a delay in reaching the site and there are insufficient visible traces of PCBs remaining at the spill site, the responsible party must estimate (based on the amount of material missing from the equipment or container) the area of the spill and immediately cordon off the area of suspected contamination. The responsible party must then utilize a statistically based sampling scheme to identify the boundaries of the spill area as soon as practicable.

(vi) Although this policy requires certain immediate actions, as described in paragraphs (c)(1)(i) through (iv) of this section, EPA is not placing a time limit on completion of the cleanup effort since the time required for completion will vary from case to case. However, EPA expects that decontamination will be achieved promptly in all cases and will consider promptness of completion in determining whether the responsible party made good faith efforts to clean up in accordance with this policy.

(2) *Requirements for decontaminating spills in outdoor electrical substations.* Spills which occur in outdoor electrical substations, as defined under § 761.123, shall be decontaminated in accordance with paragraphs (c)(2) (i) and (ii) of this section. Conformance to the cleanup standards under paragraphs (c)(2) (i) and (ii) of this section shall be verified by post-cleanup sampling as specified under § 761.130. At such times as outdoor electrical substations are converted to another use, the spill site shall be cleaned up to the nonrestricted access requirements under paragraph (c)(4) of this section.

(i) Contaminated solid surfaces (both impervious and non-impervious) shall be cleaned to a PCB concentration of 100 micrograms ( $\mu\text{g}$ )/100 square centimeters ( $\text{cm}^2$ ) (as measured by standard wipe tests).

(ii) At the option of the responsible party, soil contaminated by the spill will be cleaned either to 25 ppm PCBs by weight, or to 50 ppm PCBs by weight provided that a label or notice is visibly placed in the area. Upon demonstration by the responsible party that cleanup to 25 ppm or 50 ppm will

jeopardize the integrity of the electrical equipment at the substation, the EPA regional office may establish an alternative cleanup method or level and place the responsible party on a reasonably timely schedule for completion of cleanup.

(3) *Requirements for decontaminating spills in other restricted access areas.* Spills which occur in restricted access locations other than outdoor electrical substations, as defined under § 761.123, shall be decontaminated in accordance with paragraphs (c)(3) (i) through (v) of this section. Conformance to the cleanup standards in paragraphs (c)(3) (i) through (v) of this section shall be verified by postcleanup sampling as specified under § 761.130. At such times as restricted access areas other than outdoor electrical substations are converted to another use, the spill site shall be cleaned up to the nonrestricted access area requirements of paragraph (c)(4) of this section.

(i) High-contact solid surfaces, as defined under § 761.163 shall be cleaned to  $10 \mu\text{g}/100 \text{ cm}^2$  (as measured by standard wipe tests).

(ii) Low-contact, indoor, impervious solid surfaces will be decontaminated to  $10 \mu\text{g}/100 \text{ cm}^2$ .

(iii) At the option of the responsible party, low-contact, indoor, nonimpervious surfaces will be cleaned either to  $10 \mu\text{g}/100 \text{ cm}^2$  or to  $100 \mu\text{g}/100 \text{ cm}^2$  and encapsulated. The Regional Administrator, however, retains the authority to disallow the encapsulation option for a particular spill situation upon finding that the uncertainties associated with that option pose special concerns at that site. That is, the Regional Administrator would not permit encapsulation if he/she determined that if the encapsulation failed the failure would create an imminent hazard at the site.

(iv) Low-contact, outdoor surfaces (both impervious and nonimpervious) shall be cleaned to  $100 \mu\text{g}/100 \text{ cm}^2$ .

(v) Soil contaminated by the spill will be cleaned to 25 ppm PCBs by weight.

(4) *Requirements for decontaminating spills in nonrestricted access areas.* Spills which occur in nonrestricted access locations, as defined under § 761.123, shall be decontaminated in accordance with



paragraphs (c)(4) (i) through (v) of this section. Conformance to the cleanup standards at paragraphs (c)(4) (i) through (v) of this section shall be verified by postcleanup sampling as specified under § 761.130.

(i) Furnishings, toys, and other easily replaceable household items shall be disposed of in accordance with the provisions of subpart D of this part and replaced by the responsible party.

(ii) Indoor solid surfaces and high-contact outdoor solid surfaces, defined as high contact residential/commercial surfaces under § 761.123, shall be cleaned to 10 µg/100 cm<sup>2</sup> (as measured by standard wipe tests).

(iii) Indoor vault areas and low-contact, outdoor, impervious solid surfaces shall be decontaminated to 10 µg/100 cm<sup>2</sup>.

(iv) At the option of the responsible party, low-contact, outdoor, nonimpermeable solid surfaces shall be either cleaned to 10 µg/100 cm<sup>2</sup> or cleaned to 100 µg/100 cm<sup>2</sup> and encapsulated. The Regional Administrator, however, retains the authority to disallow the encapsulation option for a particular spill situation upon finding that the uncertainties associated with that option pose special concerns at that site. That is, the Regional Administrator would not permit encapsulation if he/she determined that if the encapsulation failed the failure would create an imminent hazard at the site.

(v) Soil contaminated by the spill will be decontaminated to 10 ppm PCBs by weight provided that soil is excavated to a minimum depth of 10 inches. The excavated soil will be replaced with clean soil, i.e., containing less than 1 ppm PCBs, and the spill site will be restored (e.g., replacement of turf).

(5) *Records.* The responsible party shall document the cleanup with records of decontamination. The records must be maintained for a period of 5 years. The records and certification shall consist of the following:

(i) Identification of the source of the spill, e.g., type of equipment.

(ii) Estimated or actual date and time of the spill occurrence.

(iii) The date and time cleanup was completed or terminated (if cleanup was delayed by emergency or adverse

weather: the nature and duration of the delay).

(iv) A brief description of the spill location and the nature of the materials contaminated. This information should include whether the spill occurred in an outdoor electrical substation, other restricted access location, or in a non-restricted access area.

(v) Precleanup sampling data used to establish the spill boundaries if required because of insufficient visible traces and a brief description of the sampling methodology used to establish the spill boundaries.

(vi) A brief description of the solid surfaces cleaned.

(vii) Approximate depth of soil excavation and the amount of soil removed.

(viii) Postcleanup verification sampling data and, if not otherwise apparent from the documentation, a brief description of the sampling methodology and analytical technique used.

(ix) While not required for compliance with this policy, information on the estimated cost of cleanup (by man-hours, dollars, or both) would be useful if maintained in the records.

[52 FR 10705, Apr. 2, 1987, as amended at 53 FR 40384, Oct. 19, 1988; 63 FR 35461, June 29, 1998; 72 FR 57241, Oct. 9, 2007]

#### § 761.130 Sampling requirements.

Postcleanup sampling is required to verify the level of cleanup under § 761.125(c) (2) through (4). The responsible party may use any statistically valid, reproducible, sampling scheme (either random samples or grid samples) provided that the requirements of paragraphs (a) and (b) of this section are satisfied.

(a) The sampling area is the greater of (1) an area equal to the area cleaned plus an additional 1-foot boundary, or (2) an area 20 percent larger than the original area of contamination.

(b) The sampling scheme must ensure 95 percent confidence against false positives.

(c) The number of samples must be sufficient to ensure that areas of contamination of a radius of 2 feet or more within the sampling area will be detected, except that the minimum number of samples is 3 and the maximum number of samples is 40.

(d) The sampling scheme must include calculation for expected variability due to analytical error.

(e) EPA recommends the use of a sampling scheme developed by the Midwest Research Institute (MRI) for use in enforcement inspections: "Verification of PCB Spill Cleanup by Sampling and Analysis." Guidance for the use of this sampling scheme is available in the MRI report "Field Manual for Grid Sampling of PCB Spill Sites to Verify Cleanup." Both the MRI sampling scheme and the guidance document are available on EPA's PCB Web site at <http://www.epa.gov/pcb>, or from the Program Management, Communications, and Analysis Office, Office of Resource Conservation and Recovery (5305P), 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001. The major advantage of this sampling scheme is that it is designed to characterize the degree of contamination within the entire sampling area with a high degree of confidence while using fewer samples than any other grid or random sampling scheme. This sampling scheme also allows some sites to be characterized on the basis of composite samples.

(f) EPA may, at its discretion, take samples from any spill site. If EPA's sampling indicates that the remaining concentration level exceeds the required level, EPA will require further cleanup. For this purpose, the numerical level of cleanup required for spills cleaned in accordance with § 761.125(b) is deemed to be the equivalent of numerical cleanup requirements required for cleanups under § 761.125(c) (2) through (4). Using its best engineering judgment, EPA may sample a statistically valid random or grid sampling technique, or both. When using engineering judgment or random "grab" samples, EPA will take into account that there are limits on the power of a grab sample to dispute statistically based sampling of the type required of the responsible party. EPA headquarters will provide guidance to the EPA regions on the degree of certainty associated with various grab sample results.

[52 FR 10705, Apr. 2, 1987, as amended at 60 FR 34465, July 3, 1995; 72 FR 57241, Oct. 9, 2007; 74 FR 30234, June 25, 2009]

#### § 761.135 Effect of compliance with this policy and enforcement.

(a) Although a spill of material containing 50 ppm or greater PCBs is considered improper PCB disposal, this policy establishes requirements that EPA considers to be adequate cleanup of the spilled PCBs. Cleanup in accordance with this policy means compliance with the procedural as well as the numerical requirements of this policy. Compliance with this policy creates a presumption against both enforcement action for penalties and the need for further cleanup under TSCA. The Agency reserves the right, however, to initiate appropriate action to compel cleanup where, upon review of the records of cleanup or EPA sampling following cleanup, EPA finds that the decontamination levels in the policy have not been achieved. The Agency also reserves the right to seek penalties where the Agency believes that the responsible party has not made a good faith effort to comply with all provisions of this policy, such as prompt notification of EPA of a spill, recordkeeping, etc.

(b) EPA's exercise of enforcement discretion does not preclude enforcement action under other provisions of TSCA or any other Federal statute. This includes, even in cases where the numerical decontamination levels set forth in this policy have been met, civil or criminal action for penalties where EPA believes the spill to have been the result of gross negligence or knowing violation.

#### Subparts H-I [Reserved]

#### Subpart J—General Records and Reports

##### § 761.180 Records and monitoring.

This section contains recordkeeping and reporting requirements that apply to PCBs, PCB Items, and PCB storage and disposal facilities that are subject to the requirements of the part.

(a) *PCBs and PCB Items in service or projected for disposal.* Beginning February 5, 1990, each owner or operator of a facility, other than a commercial storer or a disposer of PCB waste, using or storing at any one time at

least 45 kilograms (99.4 pounds) of PCBs contained in PCB Container(s), or one or more PCB Transformers, or 50 or more PCB Large High or Low Voltage Capacitors shall develop and maintain at the facility, or a central facility provided they are maintained at that facility, all annual records and the written annual document log of the disposition of PCBs and PCB Items. The written annual document log must be prepared for each facility by July 1 covering the previous calendar year (January through December). The annual document log shall be maintained for at least 3 years after the facility ceases using or storing PCBs and PCB Items in the quantities prescribed in this paragraph. Annual records (manifests and certificates of disposal) shall be maintained for the same period. The annual records and the annual document log shall be available for inspection at the facility where they are maintained by authorized representatives of EPA during normal business hours, and each owner or operator of a facility subject to these requirements shall know the location of these records. All records and annual documents required to be prepared and maintained by this section prior to February 5, 1990 shall continue to be maintained at the facility for the same time as the annual records and the annual document log. The annual document required for 1989 shall cover the period from January 1, 1989 to February 5, 1990.

(1) The annual records shall include the following:

(i) All signed manifests generated by the facility during the calendar year.

(ii) All Certificates of Disposal that have been received by the facility during the calendar year.

(iii) Records of inspections and cleanups performed in accordance with §761.65(c)(5).

(2) The written annual document log shall include the following:

(i) The name, address, and EPA identification number of the facility covered by the annual document log and the calendar year covered by the annual document log.

(ii) The unique manifest number of every manifest generated by the facility during the calendar year, and from

each manifest and for unmanifested waste that may be stored at the facility, the following information:

(A) For bulk PCB waste (*e.g.*, in a tanker or truck), its weight in kilograms, the first date it was removed from service for disposal, the date it was placed into transport for off-site storage or disposal, and the date of disposal, if known.

(B) The serial number (if available) or other means of identifying each PCB Article (*e.g.*, transformer or capacitor), the weight in kilograms of the PCB waste in each transformer or capacitor, the date it was removed from service for disposal, the date it was placed in transport for off-site storage or disposal, and the date of disposal, if known.

(C) A unique number identifying each PCB Container, a description of the contents of each PCB Container, such as liquid, soil, cleanup debris, etc., including the total weight of the material in kilograms in each PCB Container, the first date material placed in each PCB Container was removed from service for disposal, and the date each PCB Container was placed in transport for off-site storage or disposal, and the date of disposal (if known).

(D) A unique number identifying each PCB Article Container, a description of the contents of each PCB Article Container, such as pipes, capacitors, electric motors, pumps, etc., including the total weight in kilograms of the content of each PCB Article Container, the first date a PCB Article placed in each PCB Article Container was removed from service for disposal, and the date the PCB Article Container was placed in transport for off-site storage or disposal, and the date of disposal (if known.)

(iii) The total number by specific type of PCB Articles and the total weight in kilograms of PCBs in PCB Articles, the total number of PCB Article Containers and total weight in kilograms of the contents of PCB Article Containers, the total number of PCB Containers and the total weight in kilograms of the contents of PCB Containers, and the total weight in kilograms of bulk PCB waste that was placed into storage for disposal or disposed during the calendar year.

## Environmental Protection Agency

## § 761.180

(iv) The total number of PCB Transformers and total weight in kilograms of PCBs contained in the transformers remaining in service at the end of the calendar year.

(v) The total number of Large High or Low Voltage PCB Capacitors remaining in service at the end of the calendar year.

(vi) The total weight in kilograms of any PCBs and PCB Items in PCB Containers, including the identification of container contents, remaining in service at the facility at the end of the calendar year.

(vii) For any PCBs or PCB item received from or shipped to another facility owned or operated by the same generator, the information required under paragraph (a)(2)(ii)(A) through (a)(2)(ii)(D) of this section.

(viii) A record of each telephone call, or other means of verification agreed upon by both parties, made to each designated commercial storer or designated disposer to confirm receipt of PCB waste transported by an independent transporter, as required by § 761.208.

(ix) Whenever a PCB Item, excluding small capacitors, with a concentration of  $\geq 50$  ppm is distributed in commerce for reuse pursuant to § 761.20(c)(1), the name, address, and telephone number of the person to whom the item was transferred, date of transfer, and the serial number of the item or the internal identification number, if a serial number is not available, must be recorded in the annual document log. The serial number or internal identification number shall be permanently marked on the equipment.

(3) [Reserved]

(4) For purposes of this paragraph, PCB Voltage Regulators shall be recorded as PCB Transformers.

(b) *Disposers and commercial storers of PCB waste.* Beginning February 5, 1990, each owner or operator of a facility (including high efficiency boiler operations) used for the commercial storage or disposal of PCBs and PCB Items shall maintain annual records on the disposition of all PCBs and PCB items at the facility and prepare and maintain a written annual document log that includes the information required by paragraphs (b)(2) of this section for

PCBs and PCB Items that were handled as PCB waste at the facility. The written annual document log shall be prepared by July 1 for the previous calendar year (January through December). The written annual document log shall be maintained at each facility for at least 3 years after the facility is no longer used for the storage or disposal of PCBs and PCB Items except that, in the case of chemical waste landfills, the annual document log shall be maintained at least 20 years after the chemical waste landfill is no longer used for the disposal of PCBs and PCB Items. The annual records shall be maintained for the same period. The annual records and written annual document log shall be available at the facility for inspection by authorized representatives of the EPA. All records and annual documents required to be prepared and maintained by this section prior to February 5, 1990 shall continue to be maintained at the facility for the same time as the annual records and the annual document log. The annual document for 1989 shall cover the period from January 1, 1989 to February 5, 1990. From the written annual document log the owner or operator of a facility must prepare the annual report containing the information required by paragraphs (b)(3)(i) through (b)(3)(vi) of this section for PCBs and PCB Items that were handled as PCB waste at the facility during the previous calendar year (January through December). The annual report must be submitted by July 15 of each year for the preceding calendar year. If the facility ceases commercial PCB storage or disposal operations, the owner or operator of the facility shall provide at least 60 days advance written notice to the Regional Administrator for the region in which the facility is located of the date the facility intends to begin closure. d

(1) The annual records shall include the following:

(i) All signed manifests generated or received at the facility during the calendar year.

(ii) All Certificates of Disposal that have been generated or received by the facility during the calendar year.

(iii) Records of inspections and cleanups performed in accordance with § 761.65(c)(5).

(2) The written annual document log shall include the following:

(i) The name, address, and EPA identification number of the storage or disposal facility covered by the annual document log and the calendar year covered by the annual document log.

(ii) For each manifest generated or received by the facility during the calendar year, the unique manifest number and the name and address of the facility that generated the manifest and the following information:

(A) For bulk PCB waste (*e.g.*, in a tanker or truck), its weight in kilograms, the first date PCB waste placed in the tanker or truck was removed from service for disposal, the date it was received at the facility, the date it was placed in transport for off-site disposal (if applicable), and the date of disposal, (if known).

(B) The serial number or other means of identifying each PCB Article, not in a PCB Container or PCB Article Container, the weight in kilograms of the PCB waste in the PCB Article, the date it was removed from service for disposal, the date it was received at the facility, the date it was placed in transport for off-site disposal (if applicable), and the date of disposal (if known).

(C) The unique number assigned by the generator identifying each PCB Container, a description of the contents of each PCB Container, such as liquid, soil, cleanup debris, etc., including the total weight of the PCB waste in kilograms in each PCB Container, the first date PCB waste placed in each PCB Container was removed from service for disposal, the date it was received at the facility, the date each PCB Container was placed in transport for off-site storage or disposal (as applicable), and the date the PCB Container was disposed of (if known).

(D) The unique number assigned by the generator identifying each PCB Article Container, a description of the contents of each PCB Article Container, such as pipes, capacitors, electric motors, pumps, etc., including the total weight in kilograms of the PCB waste in each PCB Article Container, the first date a PCB Article placed in each PCB Article Container was removed from service for disposal, the

date it was received at the facility, the date each PCB Article Container was placed in transport for off-site storage or disposal (as applicable), and the date the PCB Article Container was disposed of (if known).

(E) Disposers of PCB waste shall include the confirmed date of disposal for items in paragraphs (b)(2)(ii)(A) through (b)(2)(ii)(D) of this section.

(iii) For any PCB waste disposed at a facility that generated the PCB waste or any PCB waste that was not manifested to the facility, the information required under paragraph (b)(2)(ii)(A) through (b)(2)(ii)(E) of this section.

(3) The owner or operator of a PCB disposal facility (including an owner or operator who disposes of his/her own waste and does not receive or generate manifests) or a commercial storage facility shall submit an annual report, which briefly summarizes the records and annual document log required to be maintained and prepared under paragraphs (b)(1) and (b)(2) of this section to the EPA Regional Administrator of the Region in which the facility is located by July 15 of each year, beginning with July 15, 1991. The first annual report submitted on July 15, 1991, shall be for the period starting February 5, 1990, and ending December 31, 1990. The annual report shall contain no confidential business information. The annual report shall consist of the information listed in paragraphs (b)(3)(i) through (b)(3)(vi) of this section.

(i) The name, address, and EPA identification number of the facility covered by the annual report for the calendar year.

(ii) A list of the numbers of all signed manifests of PCB waste initiated or received by the facility during that year.

(iii) The total weight in kilograms of bulk PCB waste, PCB waste in PCB Transformers, PCB waste in PCB Large High or Low Voltage Capacitors, PCB waste in PCB Article Containers, and PCB waste in PCB Containers in storage at the facility at the beginning of the calendar year, received or generated at the facility, transferred to another facility, or disposed of at the facility during the calendar year. The information must be provided for each of these categories, as appropriate.

## Environmental Protection Agency

## § 761.180

(iv) The total number of PCB Transformers, the total number of PCB Large High or Low Voltage Capacitors, the total number of PCB Article Containers, and the total number of PCB Containers in storage at the facility at the beginning of the calendar year, received or generated at the facility, transferred to another facility, or disposed of at the facility during the calendar year. The information must be provided for each of these categories, as appropriate.

(v) The total weight in kilograms of each of the following PCB categories: bulk PCB waste, PCB waste in PCB Transformers, PCB waste in PCB Large High or Low Voltage Capacitors, PCB waste in PCB Article Containers, and PCB waste in PCB Containers remaining in storage for disposal at the facility at the end of the calendar year.

(vi) The total number of PCB Transformers, the total number of PCB Large High or Low Voltage Capacitors, the total number of PCB Article Containers, and the total number of PCB Containers remaining in storage for disposal at the facility at the end of the calendar year.

(vii) The requirement to submit annual reports to the Regional Administrator continues until the submission of the annual report for the calendar year during which the facility ceases PCB storage or disposal operations. Storage operations have not ceased until all PCB waste, including any PCB waste generated during closure, has been removed from the facility.

(4) Whenever a commercial storer of PCB waste accepts PCBs or PCB Items at his storage facility and transfers the PCB waste off-site to another facility for storage or disposal, the commercial storer of PCB waste shall initiate a manifest under subpart K of this part for the transfer of PCBs or PCB Items to the next storage or disposal facility.

NOTE: Any requirements for weights in kilograms of PCBs may be calculated values if the internal volume of PCBs in containers and transformers is known and included in the reports, together with any assumptions on the density of the PCBs contained in the containers or transformers. If the internal volume of PCBs is not known, a best estimate may be used.

(5) For purposes of this paragraph, PCB Voltage Regulators shall be re-

corded and reported as PCB Transformers.

(c) *Incineration facilities.* Each owner or operator of a PCB incinerator facility shall collect and maintain for a period of 5 years from the date of collection the following information, in addition to the information required in paragraph (b) of this section:

(1) When PCBs are being incinerated, the following continuous and short-interval data:

(i) Rate and quantity of PCBs fed to the combustion system as required in § 761.70(a)(3);

(ii) Temperature of the combustion process as required in § 761.70(a)(4); and

(iii) Stack emission product to include O<sub>2</sub>, CO, and CO<sub>2</sub> as required in § 761.70(a)(7).

(2) When PCBs are being incinerated, data and records on the monitoring of stack emissions as required in § 761.70(a)(6).

(3) Total weight in kilograms of any solid residues generated by the incineration of PCBs and PCB Items during the calendar year, the total weight in kilograms of any solid residues disposed of by the facility in chemical waste landfills, and the total weight in kilograms of any solid residues remaining on the facility site.

(4) When PCBs and PCB Items are being incinerated, additional periodic data shall be collected and maintained as specified by the Regional Administrator pursuant to § 761.70(d)(4).

(5) Upon any suspension of the operation of any incinerator pursuant to § 761.70(a)(8), the owner or operator of such an incinerator shall prepare a document. The document shall, at a minimum, include the date and time of the suspension and an explanation of the circumstances causing the suspension of operation. The document shall be sent to the appropriate Regional Administrator within 30 days of any such suspension.

(d) *Chemical waste landfill facilities.* Each owner or operator of a PCB chemical waste landfill facility shall collect and maintain until at least 20 years after the chemical waste landfill is no longer used for the disposal of PCBs the following information in addition to the information required in paragraph (b) of this section:

## §761.185

## 40 CFR Ch. I (7–1–10 Edition)

(1) Any water analysis obtained in compliance with §761.75(b)(6)(iii); and

(2) Any operations records including burial coordinates of wastes obtained in compliance with §761.75(b)(8)(ii).

(e) *High efficiency boiler facilities.* Each owner or operator of a high efficiency boiler used for the disposal of liquids between 50 and 500 ppm PCB shall collect and maintain for a period of 5 years the following information, in addition to the information required in paragraph (b) of this section:

(1) For each month PCBs are burned in the boiler the carbon monoxide and excess oxygen data required in §761.71(a)(1)(viii) and §761.71(b)(1)(viii);

(2) The quantity of PCBs burned each month as required in §761.71(a)(1)(vii) and §761.71(b)(1)(vii); and

(3) For each month PCBs (other than mineral oil dielectric fluid) are burned, chemical analysis data of the waste as required in §761.71(b)(2)(vi).

(f) *Retention of special records by storage and disposal facilities.* In addition to the information required to be maintained under paragraphs (b), (c), (d) and (e) of this section, each owner or operator of a PCB storage or disposal facility (including high efficiency boiler operations) shall collect and maintain for the time period specified in paragraph (b) of this section the following data:

(1) All documents, correspondence, and data that have been provided to the owner or operator of the facility by any State or local government agency and that pertain to the storage or disposal of PCBs and PCB Items at the facility.

(2) All documents, correspondence, and data that have been provided by the owner or operator of the facility to any State or local government agency and that pertain to the storage or disposal of PCBs and PCB Items at the facility.

(3) Any applications and related correspondence sent by the owner or operator of the facility to any local, State, or Federal authorities in regard to waste water discharge permits, solid waste permits, building permits, or other permits or authorizations such as those required by §§761.70(d) and 761.75(c).

(g) *Reclassification records.* If you reclassify electrical equipment using the

procedures in §761.30(a)(2)(v) or §761.30(h)(2)(v), you must keep records showing that you followed the required reclassification procedures. Where these procedures require testing, the records must include copies of pre- and post-reclassification PCB concentration measurements from a laboratory using quality control and quality assurance procedures. You must make these records available promptly to EPA or to any party possessing the equipment through sale, loan, lease, or for servicing. You must retain the records for at least 3 years after you sell or dispose of the equipment.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[44 FR 31542, May 31, 1979. Redesignated at 47 FR 19527, May 6, 1982, and further redesignated at 47 FR 37360, Aug. 25, 1982; 49 FR 28191, July 10, 1984; 53 FR 12524, Apr. 15, 1988; 54 FR 52750, Dec. 21, 1989; 55 FR 26205, June 27, 1990; 58 FR 34205, June 23, 1993; 63 FR 35461, June 29, 1998; 66 FR 17619, Apr. 2, 2001]

### **§761.185 Certification program and retention of records by importers and persons generating PCBs in excluded manufacturing processes.**

(a) In addition to meeting the basic requirements of §761.1(f) and the definition of excluded manufacturing processes at §761.3, manufacturers with processes inadvertently generating PCBs and importers of products containing inadvertently generated PCBs must report to EPA any excluded manufacturing process or imports for which the concentration of PCBs in products leaving the manufacturing site or imported is greater than 2 micrograms per gram (2 µg/g, roughly 2 ppm) for any resolvable gas chromatographic peak. Such reports must be filed by October 1, 1984 or, if no processes or imports require reports at the time, within 90 days of having processes or imports for which such reports are required.

(b) Manufacturers required to report by paragraph (a) of this section must transmit a letter notifying EPA of the number, the type, and the location of excluded manufacturing processes in which PCBs are generated when the PCB level in products leaving any manufacturing site is greater than 2 µg/g for any resolvable gas chromatographic

**Environmental Protection Agency**

**§ 761.185**

peak. Importers required to report by paragraph (a) of this section must transmit a letter notifying EPA of the concentration of PCBs in imported products when the PCB concentration of products being imported is greater than 2 µg/g for any resolvable gas chromatographic peak. Persons must also certify the following:

(1) Their compliance with all applicable requirements of § 761.1(f), including any applicable requirements for air and water releases and process waste disposal.

(2) Whether determinations of compliance are based on actual monitoring of PCB levels or on theoretical assessments.

(3) That such determinations of compliance are being maintained.

(4) If the determination of compliance is based on a theoretical assessment, the letter must also notify EPA of the estimated PCB concentration levels generated and released.

(c) Any person who reports pursuant to paragraph (a) of this section:

(1) Must have performed either a theoretical analysis or actual monitoring of PCB concentrations.

(2) Must maintain for a period of three years after ceasing process operations or importation, or for seven years, whichever is shorter, records containing the following information:

(i) *Theoretical analysis.* Manufacturers records must include: the reaction or reactions believed to be generating PCBs; the levels of PCBs generated; and the levels of PCBs released. Importers records must include: the reaction or reactions believed to be generating PCBs and the levels of PCBs generated; the basis for all estimations of PCB concentrations; and the name and qualifications of the person or persons performing the theoretical analysis; or

(ii) *Actual monitoring.* (A) The method of analysis.

(B) The results of the analysis, including data from the Quality Assurance Plan.

(C) Description of the sample matrix.

(D) The name of the analyst or analysts.

(E) The date and time of the analysis.

(F) Numbers for the lots from which the samples are taken.

(d) The certification required by paragraph (b) of this section must be signed by a responsible corporate officer. This certification must be maintained by each facility or importer for a period of three years after ceasing process operation or importation, or for seven years, whichever is shorter, and must be made available to EPA upon request. For the purpose of this section, a responsible corporate officer means:

(1) A president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation.

(2) The manager of one or more manufacturing, production, or operating facilities employing more than 250 persons or having gross annual sales or expenditures exceeding \$25,000,000 (in second quarter 1980 dollars), if authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

(e) Any person signing a document under paragraph (d) of this section shall also make the following certification:

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate information. Based on my inquiry of the person or persons directly responsible for gathering information, the information is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for falsifying information, including the possibility of fines and imprisonment for knowing violations.

Dated: \_\_\_\_\_

Signature: \_\_\_\_\_

(f) This report must be submitted to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, ATTN: PCB Notification. This report must be submitted by October 1, 1984 or within 90 days of starting up processes or commencing importation of PCBs.

(g) This certification process must be repeated whenever process conditions



## § 761.187

are significantly modified to make the previous certification no longer valid.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[49 FR 28191, July 10, 1984; 49 FR 33019, Aug. 20, 1984, as amended at 53 FR 12524, Apr. 15, 1988; 58 FR 34205, June 23, 1993; 59 FR 33697, June 30, 1994; 60 FR 34465, July 3, 1995; 71 FR 33642, June 12, 2006]

### § 761.187 Reporting importers and by persons generating PCBs in excluded manufacturing processes.

In addition to meeting the basic requirements of § 761.1(f) and the definition of excluded manufacturing process at § 761.3, PCB-generating manufacturing processes or importers of PCB-containing products shall be considered "excluded manufacturing processes" only when the following conditions are met:

(a) Data are reported to the EPA by the owner/operator or importer concerning the total quantity of PCBs in product from excluded manufacturing processes leaving any manufacturing site in any calendar year when such quantity exceeds 0.0025 percent of that site's rated capacity for such manufacturing processes as of October 1, 1984; or the total quantity of PCBs imported in any calendar year when such quantity exceeds 0.0025 percent of the average total quantity of such product containing PCBs imported by such importer during the years 1978, 1979, 1980, 1981 and 1982.

(b) Data are reported to the EPA by the owner/operator concerning the total quantity of inadvertently generated PCBs released to the air from excluded manufacturing processes at any manufacturing site in any calendar year when such quantity exceeds 10 pounds.

(c) Data are reported to the EPA by the owner/operator concerning the total quantity of inadvertently generated PCBs released to water from excluded manufacturing processes from any manufacturing site in any calendar year when such quantity exceeds 10 pounds.

(d) These reports must be submitted to the Document Control Office (DCO) (7407M), Office of Pollution Prevention and Toxics (OPPT), Environmental Protection Agency, 1200 Pennsylvania

## 40 CFR Ch. I (7-1-10 Edition)

Ave., NW., Washington, DC 20460-0001, ATTN: PCB Notification.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[49 FR 28192, July 10, 1984, as amended at 53 FR 12524, Apr. 15, 1988; 58 FR 34205, June 23, 1993; 59 FR 33697, June 30, 1994; 60 FR 34465, July 3, 1995; 71 FR 33642, June 12, 2006]

### § 761.193 Maintenance of monitoring records by persons who import, manufacture, process, distribute in commerce, or use chemicals containing inadvertently generated PCBs.

(a) Persons who import, manufacture, process, distribute in commerce, or use chemicals containing PCBs present as a result of inadvertent generation or recycling who perform any actual monitoring of PCB concentrations must maintain records of any such monitoring for a period of three years after a process ceases operation or importing ceases, or for seven years, whichever is shorter.

(b) Monitoring records maintained pursuant to paragraph (a) of this section must contain:

- (1) The method of analysis.
- (2) The results of the analysis, including data from the Quality Assurance Plan.
- (3) Description of the sample matrix.
- (4) The name of the analyst or analysts.
- (5) The date and time of the analysis.
- (6) Numbers for the lots from which the samples are taken.

(Sec. 6, Pub. L. 94-469, 90 Stat. 2020 (15 U.S.C. 2605)

[49 FR 28193, July 10, 1984, as amended at 58 FR 34205, June 23, 1993]

## Subpart K—PCB Waste Disposal Records and Reports

SOURCE: 54 FR 52752, Dec. 21, 1989, unless otherwise noted.

### § 761.202 EPA identification numbers.

(a) *General.* Any generator, commercial storer, transporter, or disposer of PCB waste who is required to have an EPA identification number under this subpart must notify EPA of his/her PCB waste handling activities, using the notification procedures and form

## Environmental Protection Agency

## § 761.205

described in § 761.205. EPA will confirm the EPA identification number of facilities already assigned one, and will assign an EPA identification number to facilities that do not have one.

(b) *Prohibitions.* After June 4, 1990:

(1) A generator of PCB waste shall not:

(i) Process, store, dispose of, transport, or offer for transportation PCB waste without having received an EPA identification number from the Agency. A generator of PCB waste who is exempted from notification under § 761.205(c)(1) or who notifies EPA in a timely manner under § 761.205(c)(2)(i), but has not yet received a unique identification number, shall be regarded as having received from EPA the identification number “40 CFR PART 761.”

(ii) Offer the PCB waste to transporters, disposers, or commercial storers of PCB waste who have not received an EPA identification number.

(2) A transporter of PCB waste shall not:

(i) Transport PCB waste without having received an EPA identification number from EPA.

(ii) Deliver PCB waste to transporters, disposers, or commercial storers of PCB waste that have not received an EPA identification number.

(3) A commercial storer of PCB waste shall not accept any PCB waste for storage without having received an EPA identification number from EPA.

(4) A disposer of PCB waste shall not accept any PCB waste for disposal without having received an EPA identification number from EPA. A disposer of PCB waste who owns more than one disposal facility or mobile treatment unit shall not accept waste unless the disposer has received an EPA identification number for each facility or mobile unit.

(c) *PCB waste handled prior to effective date of this subpart.* Generators (other than generators exempt from notification under § 761.205(c)(1)), commercial storers, transporters, and disposers of PCB waste who are required to have EPA identification numbers under this subpart, and who were engaged in PCB waste handling activities on or prior to February 5, 1990, are not subject to the prohibitions of paragraph (b) of this section if they have applied for an EPA

identification number in accordance with the applicable notification procedures of § 761.205. Such persons shall use the EPA identification number “40 CFR PART 761,” or a number assigned to the persons by EPA or a State under RCRA, until EPA issues to such persons a specific identification number under § 761.205(a), (b), or (c).

(d) *PCB waste first handled after effective date of this subpart.* Generators (other than generators exempt from notification under § 761.205(c)(1)), commercial storers, transporters, and disposers of PCB waste who are required to have EPA identification numbers under this subpart, and who first engage in PCB waste activities after February 5, 1990, are subject to the prohibitions in paragraph (b) of this section.

### **§ 761.205 Notification of PCB waste activity (EPA Form 7710-53).**

(a)(1) All commercial storers, transporters, and disposers of PCB waste who were engaged in PCB waste handling activities on or prior to February 5, 1990 shall notify EPA of their PCB waste activities by filing EPA Form 7710-53 with EPA by no later than April 4, 1990. Upon receiving the notification form, EPA will assign an EPA identification number to each entity that notifies.

(2) All generators (other than generators exempt from notification under paragraph (c)(1) of this section), commercial storers, transporters, and disposers of PCB waste who first engage in PCB waste handling activities after February 5, 1990, shall notify EPA of their PCB waste activities by filing EPA Form 7710-53 with EPA prior to engaging in PCB waste handling activities.

(3) Any person required to notify EPA under this section shall file with EPA Form 7710-53. Copies of EPA Form 7710-53 are available on EPA’s Web site at <http://www.epa.gov/pcb>, or from the Program Management, Communications, and Analysis Office, Office of Resource Conservation and Recovery (5305P), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001. Descriptive information and instructions for filling in the form are included in paragraphs (a)(4)(i) through (vii) of this section.

**§ 761.205**

**40 CFR Ch. I (7-1-10 Edition)**

(4) All of the following information shall be provided to EPA on Form 7710-53:

(i) The name of the facility, and the name of the owner or operator of the facility.

(ii) EPA identification number, if any, previously issued to the facility.

(iii) The facility's mailing address.

(iv) The location of the facility.

(v) The facility's installation contact and telephone number.

(vi) The type of PCB waste activity engaged in at the facility.

(vii) Signature of the signer of the certification statement, typed or printed name and official title of signer, and date signed.

(viii) EPA has determined that the information in paragraphs (a)(4)(i) through (a)(4)(vii) of this section shall not be treated as confidential business information. This information will be disclosed to the public without further notice to the submitter unless the submitter provides a written justification (submitted with the notification form) which demonstrates extraordinary reasons why the information should be entitled to confidential treatment.

(b) Generators (other than those generators exempt from notification under paragraph (c)(1) of this section), commercial storers, transporters, and disposers of PCB waste who have previously notified EPA or a State of hazardous waste activities under RCRA shall notify EPA of their PCB waste activities under this part by filing EPA Form 7710-53 with EPA by no later than April 4, 1990. The notification shall include the EPA identification number previously issued by EPA or the State and upon receipt of the notification, EPA shall verify and authorize the use of the previously issued identification number for PCB waste activities.

(c)(1) Generators of PCB waste need not notify EPA and receive unique EPA identification numbers under this section, unless their PCB waste activities are described in paragraph (c)(2) of this section. Generators exempted from notifying EPA under this paragraph shall use the generic identification number "40 CFR PART 761" on the manifests, records, and reports which they shall prepare under this subpart,

unless such generators elect to use a unique EPA identification number previously assigned to them under RCRA by EPA or a State.

(2) Generators of PCB waste who use, own, service, or process PCBs or PCB Items shall notify EPA of their PCB waste activities only if they own or operate PCB storage facilities subject to the storage requirements of § 761.65 (b) or (c)(7). Such generators shall notify EPA in the following manner:

(i) Generators storing PCB waste subject to the storage requirements of § 761.65 (b) or (c)(7) shall notify EPA by filing EPA Form 7710-53 with EPA by no later than April 4, 1990.

(ii) Generators who desire to commence storage of PCB waste after February 5, 1990 shall notify EPA and receive an EPA identification number before they may commence storage of PCBs at their facilities established under § 761.65 (b) or (c)(7).

(iii) A separate notification shall be submitted to EPA for each PCB storage facility owned or operated by generators of PCB waste. Upon receiving these notifications, EPA will assign generators unique EPA identification numbers for each storage facility notifying EPA under this section.

(d) Persons required to notify under this section shall file EPA Form 7710-53 with EPA by mailing the form to the following address: Document Control Officer, Office of Resource Conservation and Recovery (5305P), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001.

(e) The requirements under this section to notify EPA and obtain EPA identification numbers shall in no case excuse compliance by any person subject to the 1-year limit on storage prior to disposal under § 761.65(a).

(f) When a facility has previously notified EPA of its PCB waste handling activities using EPA Form 7710-53 and those activities change, the facility must resubmit EPA Form 7710-53 to reflect those changes no later than 30 days from when a change is made. Examples of when a PCB waste handler must renotify the Agency include, but are not limited to the following: the company changes location of the facility; or the company had notified solely

as engaging in a certain type of PCB waste handling activity and now wishes to engage in another PCB waste activity (e.g., previously only commercially stored PCB waste and now wishes to transport PCB waste).

[54 FR 52752, Dec. 21, 1989, as amended at 58 FR 15809, Mar. 24, 1993; 58 FR 34205, June 23, 1993; 59 FR 33697, June 30, 1994; 63 FR 35461, June 29, 1998; 72 FR 57241, Oct. 9, 2007; 74 FR 30234, June 25, 2009]

**§ 761.207 The manifest—general requirements.**

(a) A generator who relinquishes control over PCB wastes by transporting, or offering for transport by his own vehicle or by a vehicle owned by another person, PCB waste for commercial off-site storage or off-site disposal shall prepare a manifest on EPA Form 8700-22, and if necessary, a continuation sheet. The generator shall specify:

(1) For each bulk load of PCBs, the identity of the PCB waste, the earliest date of removal from service for disposal, and the weight in kilograms of the PCB waste.

(2) For each PCB Article Container or PCB Container, the unique identifying number, type of PCB waste (e.g., soil, debris, small capacitors), earliest date of removal from service for disposal, and weight in kilograms of the PCB waste contained.

(3) For each PCB Article not in a PCB Container or PCB Article Container, the serial number if available, or other identification if there is no serial number, the date of removal from service for disposal, and weight in kilograms of the PCB waste in each PCB Article.

(b) EPA does not maintain supplies of printed copies of Form 8700-22 for public use, although printed copies of the manifest may be available from State offices. Camera-ready copies of the form are available for printing purposes from State offices, EPA Regional Offices, and EPA Headquarters.

(c) If the State to which the shipment is manifested (i.e., consignment State) supplies the manifest and requires its use, then the generator must use that manifest.

(d) If the consignment State does not supply the manifest, but the State in which the generator is located (i.e.,

generator State) supplies the manifest and requires its use, then the generator must use that State's manifest.

(e) If both the consignment State and the generator State supply manifests and require their use, the generator must use the consignment State's manifest.

(f) If neither the generator State nor the consignment State supplies the manifest, the generator may obtain the manifest from any source.

(g) A generator shall designate on the manifest one off-site commercial storage or disposal facility approved under this part for the commercial storage or disposal of the PCBs and PCB Items described on the manifest.

(h) If the transporter is unable to deliver the PCB waste to the designated disposer or commercial storer, the transporter must contact the generator of the PCB waste for instructions. The generator shall either designate another approved disposer or commercial storer, or instruct the transporter to return the PCB waste back to the generator.

(i) The manifest which accompanies the PCB waste shall consist of at a minimum the number of copies required to provide the generator, the initial transporter, each subsequent transporter, and the owner or operator of the designated commercial storage or disposal facility with one legible copy each for their records, and one additional copy to be returned to the generator by the owner or operator of the first designated commercial storage or disposal facility.

(j) The requirements of this section apply only to PCB wastes as defined in § 761.3. This includes PCB wastes with PCB concentrations below 50 ppm where the PCB concentration below 50 ppm was the result of dilution; these PCB wastes are required under § 761.1(b) to be managed as if they contained PCB concentrations of 50 ppm and above. An example of such a PCB waste is spill cleanup material containing <50 ppm PCBs when the spill involved material containing PCBs at a concentration of ≥50 ppm. However, there is no manifest requirement for material currently below 50 ppm which derives from pre-April 18, 1978, spills of any concentration, pre-July 2, 1979, spills of <

## § 761.208

## 40 CFR Ch. I (7-1-10 Edition)

500 ppm PCBs, or materials decontaminated in accordance with § 761.79.

[54 FR 52752, Dec. 21, 1989, as amended at 63 FR 35461, June 29, 1998]

### § 761.208 Use of the manifest.

(a)(1) The generator of PCB waste shall:

(i) Sign the manifest certification by hand.

(ii) Obtain the handwritten signature of the initial transporter and date of acceptance on the manifest.

(iii) Retain one copy among its records in accordance with § 761.209(a).

(iv) Give to the transporter the remaining copies of the manifest that will accompany the shipment of PCB waste.

(2) For bulk shipments of PCB waste within the United States transported solely by water, the generator shall send three copies of the manifest dated and signed in accordance with this section directly to the owner or operator of the designated commercial storage or disposal facility. Copies of the manifest are not required for each transporter.

(3) For rail shipments of PCB waste within the United States which originate at the site of generation, the generator shall send at least three copies of the manifest dated and signed in accordance with this section to:

(i) The next non-rail transporter, if any.

(ii) The designated commercial storage or disposal facility if transported solely by rail.

(4) When a generator has employed an independent transporter to transport the PCB waste to a commercial storer or disposer, the generator shall confirm by telephone, or by other means of confirmation agreed to by both parties, that the commercial storer or disposer actually received the manifested waste. The generator shall confirm receipt of the waste by close of business the day after he receives the manifest hand-signed by the commercial storer or disposer, in accordance with paragraph (c)(1)(iv) of this section. If the generator has not received the hand-signed manifest within 35 days after the independent transporter accepted the PCB waste, the generator shall telephone, or communicate with

by some other agreed-upon means, the disposer or commercial storer to determine whether the PCB waste has actually been received. If the PCB waste has not been received, the generator shall contact the independent transporter to determine the disposition of the PCB waste. If the generator has not received a hand-signed manifest from an EPA-approved facility within 10 days from the date of the telephone call or other agreed upon means of communication, to the independent transporter, the generator shall submit an exception report to the EPA Regional Administrator for the Region in which the generator is located, as specified in § 761.215. The generator shall retain a written record of all telephone or other confirmations to be included in the annual document log, in accordance with § 761.180.

(b)(1) A transporter shall not accept PCB waste from a generator unless it is accompanied by a manifest signed by the generator in accordance with paragraph (a)(1) of this section, except that a manifest is not required if any one of the following conditions exists:

(i) The shipment of PCB waste consists solely of PCB wastes with PCB concentrations below 50 ppm, unless the PCB concentration below 50 ppm was the result of dilution, in which case § 761.1(b) requires that the waste be managed as if it contained PCBs at the concentration prior to dilution.

(ii) The PCB waste is accepted by the transporter for transport only to a storage or disposal facility owned or operated by the generator of the PCB waste.

(2) Before transporting the PCB waste, the transporter shall sign and date the manifest acknowledging acceptance of the PCB waste from the generator. The transporter shall return a signed copy to the generator before leaving the generator's facility.

(3) The transporter shall ensure that the manifest accompanies the PCB waste.

(4) A transporter who delivers PCB waste to another transporter, or to the designated commercial storer or disposer of PCB waste, shall:

(i) Obtain the date of delivery and the handwritten signature of the subsequent transporter of PCB waste, or of

## Environmental Protection Agency

## § 761.208

the owner or operator of the designated commercial storage or disposal facility on the manifest.

(ii) Retain one copy of the manifest in accordance with § 761.209(b).

(iii) Give the remaining copies of the manifest to the accepting transporter of PCB waste, or to the designated commercial storage or disposal facility.

(5) The requirements of paragraphs (b) (3) and (4) of this section shall not apply to transporters of bulk shipments by water if all of the following conditions are met:

(i) The PCB waste is delivered by water (bulk shipment) to the designated commercial storage or disposal facility.

(ii) A shipping paper containing all the information required on the manifest (excluding EPA identification number, generator certification, and signatures) accompanies the PCB waste.

(iii) The transporter delivering the PCB waste obtains the date of delivery and handwritten signature of the owner or operator of the designated commercial storage or disposal facility on either the manifest or the shipping paper.

(iv) The person delivering the PCB waste to the initial water (bulk shipment) transporter obtains the date of delivery and signature of the water (bulk shipment) transporter on the manifest and forwards it to the designated facility.

(v) A copy of the shipping paper or manifest is retained by each water (bulk shipment) transporter in accordance with § 761.209(b).

(6) For shipments involving rail transportation, the requirements of paragraphs (b)(3) and (b)(4) of this section shall not apply. Instead, the requirements described at § 263.20(f) of this chapter for the rail transportation of hazardous waste apply to such shipments. The rail transporter shall retain one copy of the manifest or rail shipping paper in accordance with § 761.209(b).

(7) The transporter shall deliver the entire quantity of PCB waste accepted from a generator or transporter to either of the following destinations:

(i) The designated commercial storage or disposal facility listed on the manifest.

(ii) The next designated transporter of PCB waste.

(8) If the PCB waste cannot be delivered in accordance with paragraph (b)(7) of this section, the transporter shall contact the generator for further directions and shall revise the manifest and/or return the PCB waste according to the generator's instructions.

(9) No provision of this section shall be construed to affect or limit the applicability of any requirement applicable to transporters of PCB waste under regulations issued by the Department of Transportation (DOT) and set forth at 49 CFR part 171.

(c)(1) If a commercial storage or disposal facility receives an off-site shipment of PCB waste accompanied by a manifest, the owner or operator, or his agent, shall:

(i) Sign and date each copy of the manifest to certify that the PCB waste covered by the manifest was received.

(ii) Note any significant discrepancies in the manifest (as defined in § 761.210(a)(1)) on each copy of the manifest.

(iii) Immediately give the transporter at least one copy of the signed manifest.

(iv) Within 30 days after the delivery, send a copy of the manifest to the generator.

(v) Retain a copy of each manifest among the facility's records in accordance with § 761.209(d).

(2) If a commercial storage or disposal facility receives PCB waste from a rail or water (bulk shipment) transporter accompanied by a shipping paper containing all the information required on the manifest except the EPA identification numbers, generator's certification, and signatures, the owner or operator, or his agent, shall:

(i) Sign and date each copy of the manifest or shipping paper to certify that the PCB waste covered by the manifest or shipping paper was received.

(ii) Note any significant discrepancies in the manifest or shipping paper on each copy of the manifest or shipping paper.

## § 761.209

## 40 CFR Ch. I (7-1-10 Edition)

(iii) Immediately give the rail or water transporter at least one copy of the manifest or shipping paper, if applicable.

(iv) Within 30 days after the delivery, send a copy of the signed and dated manifest to the generator; however, if the manifest has not been received within 30 days after delivery, the owner or operator shall send a copy of the shipping paper signed and dated to the generator.

(v) Retain at the commercial storage or disposal facility a copy of the manifest and shipping paper, if signed in lieu of the manifest, in accordance with § 761.209(d).

(3) Whenever an off-site shipment of PCB waste is initiated from a commercial storage or disposal facility, the owner or operator of the commercial storage or disposal facility shall comply with the manifest requirements that apply to generators of PCB waste.

### § 761.209 Retention of manifest records.

(a) A generator of PCB waste shall keep a copy of each manifest signed in accordance with § 761.208(a)(1) until the generator receives a signed copy from the designated commercial storage or disposal facility which received the PCB waste. The copy signed by the commercial storer or disposer shall be retained for at least 3 years from the date the PCB waste was accepted by the initial transporter. A generator subject to annual document requirements under § 761.180 shall retain copies of each manifest for the period required by § 761.180(a).

(b)(1) A transporter of PCB waste shall keep a copy of the manifest signed by the generator, transporter, and the next designated transporter, if applicable, or the owner or operator of the designated commercial storage or disposal facility. This copy shall be retained for a period of at least 3 years from the date the PCB waste was accepted by the initial transporter.

(2) For shipments of PCB waste delivered to the designated commercial storage or disposal facility by water (bulk shipment), each water (bulk shipment) transporter shall retain a copy of the shipping paper described in § 761.208(b)(5)(ii) for a period of at least

3 years from the date the PCB waste was accepted by the initial transporter.

(3) For shipments of PCB waste by rail within the United States:

(i) The initial rail transporter shall keep a copy of the manifest and the shipping paper required to accompany the PCB waste for a period of at least 3 years from the date the PCB waste was accepted by the initial transporter.

(ii) The final rail transporter shall keep a copy of the signed manifest, or the required shipping paper if signed by the designated facility in lieu of the manifest, for a period of at least 3 years from the date the PCB waste was accepted by the initial transporter.

(c) The owner or operator of a PCB commercial storage or disposal facility that receives off-site shipments of PCB waste shall retain at the facility for at least 3 years a copy of each manifest or shipping paper that the owner or operator signs in accordance with § 761.208(c)(1) or (c)(3).

(d) The periods of record retention required by this section shall be extended automatically during the course of any outstanding enforcement action regarding the regulated activity.

[54 FR 52752, Dec. 21, 1989, as amended at 58 FR 34205, June 23, 1993]

### § 761.210 Manifest discrepancies.

(a) Manifest discrepancies are differences between the quantity or type of PCB waste designated on the manifest or shipping paper and the quantity or type of PCB waste actually delivered to and received by a designated facility.

(1) Significant discrepancies in quantity are:

(i) Variations greater than 10 percent in weight of PCB waste in containers.

(ii) Any variation in piece count, such as a discrepancy of one PCB Transformer or PCB Container or PCB Article Container in a truckload.

(2) Significant discrepancies in type of PCB waste are obvious differences which may be discovered by inspection or waste analysis, such as the substitution of solids for liquids or the substitution of high concentration PCBs (above 500 ppm) with lower concentration materials.

(b) Upon discovering a significant discrepancy, the owner or operator of

## Environmental Protection Agency

## § 761.215

the designated commercial storage or disposal facility shall attempt to reconcile the discrepancy with the waste generator or transporter. If the discrepancy is not resolved within 15 days after receiving the PCB waste, such owner or operator shall immediately submit to the Regional Administrator for the Region in which the designated facility is located a letter describing the discrepancy and attempts to reconcile it, and a copy of the manifest or shipping paper at issue.

[54 FR 52752, Dec. 21, 1989, as amended at 58 FR 34205, June 23, 1993]

### § 761.211 Unmanifested waste report.

(a) After April 4, 1990, if a PCB commercial storage or disposal facility receives any shipment of PCB waste from an off-site source without an accompanying manifest or shipping paper (where required in place of a manifest), and any part of the shipment consists of any PCB waste regulated for disposal, then the owner or operator of the commercial storage or disposal facility shall attempt to contact the generator, using information supplied by the transporter, to obtain a manifest or to return the PCB waste.

(b) If the owner or operator of the commercial storage or disposal facility cannot contact the generator of the PCB waste, he shall notify the Regional Administrator of the EPA region in which his facility is located of the unmanifested PCB waste so that the Regional Administrator can determine whether further actions are required before the owner or operator may store or dispose of the unmanifested PCB waste.

(c) Within 15 days after receiving the unmanifested PCB waste, the owner or operator shall prepare and submit a report to the Regional Administrator for the Region in which the commercial storage or disposal facility is located and to the Regional Administrator for the Region in which the PCB waste originated, if known. The report may be submitted on EPA Form 8700-13B, or by a written letter designated "Unmanifested Waste Report." The report shall include the following information:

(1) The EPA identification number, name, and address of the PCB commercial storage or disposal facility.

(2) The date the commercial storage or disposal facility received the unmanifested PCB waste.

(3) The EPA identification number, name, and address of the generator and transporter, if available.

(4) A description of the type and quantity of the unmanifested PCB waste received at the facility.

(5) A brief explanation of why the waste was unmanifested, if known.

(6) The disposition made of the unmanifested waste by the commercial storage or disposal facility, including:

(i) If the waste was stored or disposed by that facility, was the generator identified and was a manifest subsequently supplied.

(ii) If the waste was sent back to the generator, why and when.

[54 FR 52752, Dec. 21, 1989, as amended at 58 FR 34205, June 23, 1993]

### § 761.215 Exception reporting.

(a) A generator of PCB waste, who does not receive a copy of the manifest with the handwritten signature of the owner or operator of the designated PCB commercial storage or disposal facility within 35 days of the date the waste was accepted by the initial transporter, shall immediately contact the transporter and/or the owner or operator of the designated facility to determine the status of the PCB waste.

(b) A generator of PCB waste subject to the manifesting requirements shall submit an Exception Report to the EPA Regional Administrator for the Region in which the generator is located if the generator has not received a copy of the manifest with the handwritten signature of the owner or operator of the designated facility within 45 days of the date the waste was accepted by the initial transporter. The exception report shall be submitted to EPA no later than 45 days from the date on which the generator should have received the manifest. The Exception Report shall include the following:

(1) A legible copy of the manifest for which the generator does not have confirmation of delivery.

(2) A cover letter signed by the generator or his authorized representative



**§761.218**

**40 CFR Ch. I (7-1-10 Edition)**

explaining the efforts taken to locate the PCB waste and the results of those efforts.

(c) A disposer of PCB waste shall submit a One-year Exception Report to the EPA Regional Administrator for the Region in which the disposal facility is located no later than 45 days from the end of the 1-year storage for disposal date when the following occurs:

(1) The disposal facility receives PCBs or PCB Items on a date more than 9 months from the date the PCBs or PCB Items were removed from service for disposal, as indicated on the manifest or continuation sheet; and

(2) Because of contractual commitments or other factors affecting the facility's disposal capacity, the disposer of PCB waste could not dispose of the affected PCBs or PCB Items within 1 year of the date of removal from service for disposal.

(d) A generator or commercial storer of PCB waste who manifests PCBs or PCB Items to a disposer of PCB waste shall submit a One-year Exception Report to the EPA Regional Administrator for the Region in which the generator or commercial storer is located no later than 45 days from the date the following occurs:

(1) The generator or commercial storer transferred the PCBs or PCB Items to the disposer of PCB waste on a date within 9 months from the date of removal from service for disposal of the affected PCBs or PCB Items, as indicated on the manifest or continuation sheet; and

(2) The generator or commercial storer either has not received within 13 months from the date of removal from service for disposal a Certificate of Disposal confirming the disposal of the affected PCBs or PCB Items, or the generator or commercial storer receives a Certificate of Disposal confirming disposal of the affected PCBs or PCB Items on a date more than 1 year after the date of removal from service.

(e) The One-year Exception Report shall include:

(1) A legible copy of any manifest or other written communication relevant to the transfer and disposal of the affected PCBs or PCB Items.

(2) A cover letter signed by the submitter or an authorized representative explaining:

(i) The date(s) when the PCBs or PCB Items were removed from service for disposal.

(ii) The date(s) when the PCBs or PCB Items were received by the submitter of the report, if applicable.

(iii) The date(s) when the affected PCBs or PCB Items were transferred to a designated disposal facility.

(iv) The identity of the transporters, commercial storers, or disposers known to be involved with the transaction.

(v) The reason, if known, for the delay in bringing about the disposal of the affected PCBs or PCB Items within 1 year from the date of removal from service for disposal.

(f) PCB/radioactive waste that is exempt from the 1-year storage for disposal time limit pursuant to §761.65(a)(1) is also exempt from the exception reporting requirements of paragraphs (c), (d), and (e) of this section.

[54 FR 52752, Dec. 21, 1989, as amended at 55 FR 26205, June 27, 1990; 58 FR 34205, June 23, 1993; 63 FR 35461, June 29, 1998]

**§761.218 Certificate of disposal.**

(a) For each shipment of manifested PCB waste that the owner or operator of a disposal facility accepts by signing the manifest, the owner or operator of the disposal facility shall prepare a Certificate of Disposal for the PCBs and PCB Items disposed of at the facility, which shall include:

(1) The identity of the disposal facility, by name, address, and EPA identification number.

(2) The identity of the PCB waste affected by the Certificate of Disposal including reference to the manifest number for the shipment.

(3) A statement certifying the fact of disposal of the identified PCB waste, including the date(s) of disposal, and identifying the disposal process used.

(4) A certification as defined in §761.3.

(b) The owner or operator of the disposal facility shall send the Certificate of Disposal to the generator identified on the manifest which accompanied the shipment of PCB waste within 30 days of the date that disposal of each item

## Environmental Protection Agency

## § 761.247

of PCB waste identified on the manifest was completed unless the generator and the disposer contractually agree to another time frame.

(c) The disposal facility shall keep a copy of each Certificate of Disposal among the records that it retains under § 761.180(b).

(d)(1) Generators of PCB waste shall keep a copy of each Certificate of Disposal that they receive from disposers of PCB waste among the records they retain under § 761.180(a).

(2) Commercial storers of PCB waste shall keep a copy of each Certificate of Disposal that they receive from disposers of PCB waste among the records they retain under § 761.180(b).

[54 FR 52752, Dec. 21, 1984, as amended at 63 FR 35462, June 29, 1998]

### Subpart L [Reserved]

### Subpart M—Determining a PCB Concentration for Purposes of Abandonment or Disposal of Natural Gas Pipeline: Selecting Sample Sites, Collecting Surface Samples, and Analyzing Standard PCB Wipe Samples

SOURCE: 63 FR 35462, June 29, 1998, unless otherwise noted.

#### § 761.240 Scope and definitions.

(a) Use these procedures to select surface sampling sites for natural gas pipe to determine its PCB surface concentration for abandonment-in-place or removal and disposal off-site in accordance with § 761.60(b)(5).

(b) “Pipe segment” means a length of natural gas pipe that has been removed from the pipeline system to be disposed of or reused, and that is usually approximately 12.2 meters (40 feet) or shorter in length. Pipe segments are usually linear.

(c) “Pipeline section” means a length of natural gas pipe that has been cut or otherwise separated from the active pipeline, usually for purposes of abandonment, and that is usually longer than 12.2 meters in length. Pipeline sections may be branched.

#### § 761.243 Standard wipe sample method and size.

(a) Collect a surface sample from a natural gas pipe segment or pipeline section using a standard wipe test as defined in § 761.123. Detailed guidance for the entire wipe sampling process appears in the document entitled, “Wipe Sampling and Double Wash/Rinse Cleanup as Recommended by the Environmental Protection Agency PCB Spill Cleanup Policy,” dated June 23, 1987 and revised on April 18, 1991. This document is available on EPA’s Web site at <http://www.epa.gov/pcb>, or from the Program Management, Communications, and Analysis Office, Office of Resource Conservation and Recovery (5305P), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001.

(b) Collect a surface sample from a minimum surface area of 100 cm<sup>2</sup> at each sampling site selected. The EPA Regional Administrator may approve, in writing, requests to collect a sample from smaller surface areas, when <100 cm<sup>2</sup> of surface eligible for sampling is present; e.g., when sampling a small diameter pipe, a small valve, or a small regulator. When smaller surfaces are sampled, convert the measurement to the equivalent measurement for 100 cm<sup>2</sup> for purposes of comparison to standards based on 100 cm<sup>2</sup>.

[63 FR 35462, June 29, 1998, as amended at 72 FR 57241, Oct. 9, 2007; 74 FR 30235, June 25, 2009]

#### § 761.247 Sample site selection for pipe segment removal.

(a) *General.* (1) Select the pipe segments to be sampled by following the directions in paragraph (b) of this section.

(2) Locate the proper position along the length of the pipe segment that you have selected for sampling, by following the directions in paragraph (c) of this section.

(3) Select the proper sampling position around the circumference of the pipe segment that you have selected for sampling, by following the directions in paragraph (d) of this section.

(4) Prior to removing pipe from the ground or lifting the pipe from its location during former operations, mark the top side of the pipe.

(5) Do not sample if there are free-flowing liquids in the pipe segment. Free-flowing liquids must be removed prior to sampling.

(b) *Selecting pipe segments to sample.* Select the pipe segment(s) that you will sample from a length of pipe or group of pipe segments, as follows:

(1) Do not sample a pipe segment that is longer than 12.2 meters (40 feet). If a segment is longer than 12.2 meters in length, cut the segment so that all resulting segments are 12.2 meters or less in length.

(2) Determine which pipe segments to sample as follows:

(i) When a length of pipe having seven or fewer segments is removed for purposes of disposal, sample each pipe segment.

(ii) When removing a length of pipe having multiple contiguous segments less than 3 miles in total length, take samples from a total of seven segments.

(A) Sample the first and last segments removed.

(B) Select the five additional segments according to one of the two following procedures:

(1) Assign all segments a unique sequential number. Then select five numbers using a random number table or random number generator. If the random number generator or random number table produces either the first pipe segment, the last pipe segment, or any previously selected segment, select another random number until there are seven different numbers, each corresponding to a different pipe segment.

(2) Divide the total number of segments by six. Round the resulting quotient off to the nearest whole number. The resulting number is the interval between the segments you will sample. For example, cut a 2.9 mile length of pipeline into 383 segments of approximately 40 feet each. Sample the first (number 1) and last (number 383) segments. To determine which additional five segments to sample, divide the total number of segments, 383, by 6. Round up the resulting number in this example, 63.8, to the next whole number, 64. Add 64 to the number of each preceding pipe segment five separate times to select five additional pipe segments for sampling. In this example,

the first pipe segment has the number 1, add 64 to 1 to select segment 65. Next, add 64 to 65 to select segment 129. Continue in this fashion to select all seven segments: 1, 65, 129, 193, 257, 321, and 383.

(iii) When removing a length of pipe having multiple contiguous segments more than 3 miles in total length for purposes of disposal, take samples of each segment that is  $\frac{1}{2}$  mile distant from the segment previously sampled. Sample a minimum of seven segments.

(c) *Selecting the sampling position—length.* Select the sampling position along the length of the pipe segment, as follows:

(1) Take samples at the end upstream of the former gas flow of each segment removed.

(2) If the pipe segment is cut with a torch or other high temperature heat source, take the sample at least 15 cm (6 inches) inside the cut end of the pipe segment.

(3) If the pipe segment is cut with a saw or other mechanical device, take the sample at least 2 cm (1 inch) inside the end of the pipe segment.

(4) If the sample site location selected in the procedure at paragraph (c)(2) or (c)(3) of this section is a porous surface (for example, there is significant corrosion so that the wipe material will be shredded), then move the sample site further inside the pipe segment (away from the end of the pipe or pipe segment) until there is no such porous surface. For purposes of this subpart, natural gas pipe with a thin porous corrosion preventive coating is a non-porous surface.

(5) If there is not a non-porous surface accessible by paragraphs (c)(2) and (c)(3) of this section, use one of the following three options:

(i) Sample the downstream end of the pipe segment using the same sample site location procedure as for the upstream end.

(ii) Select another pipe segment using the random selection procedure described in paragraph (b) of this section.

(iii) If there is no other pipe segment in the population to be sampled and both ends of a pipe segment have porous surfaces at all possible sample collection sites, then assume that the pipe

## Environmental Protection Agency

## § 761.257

segment contains  $\geq 50$  ppm PCB but  $< 500$  ppm PCB.

(d) *Selecting the sample position—circumference.* Based on the mark on the top of the pipe segment made prior to removing pipe from the ground or lifting the pipe from its location during former operations, sample the inside center of the bottom of the pipe being sampled. Make sure the sample is centered on the bottom of the pipe segment; that is, sample an equal area on both sides of the middle of the bottom of the pipe segment for the entire length of the sample.

[63 FR 35462, June 29, 1998, as amended at 64 FR 33762, June 24, 1999]

### § 761.250 Sample site selection for pipeline section abandonment.

This procedure is for the sample site selection for a pipeline section to be abandoned, in accordance with § 761.60(b)(5)(i)(B).

(a) *General.* (1) Select sample collection sites in the pipeline section(s) by following the directions in paragraph (b) of this section.

(2) Select the proper sampling position along the pipe by following the directions in § 761.247 (c) and (d).

(3) Assure, by visual inspection, the absence of free-flowing liquids in the pipe by affirming no liquids at all liquid collection points and all ends of the pipeline section to be abandoned.

(b) *Selection sample collection sites.* At a minimum, sample all ends of all pipeline sections to be abandoned in place.

(1) If the pipeline section to be abandoned is between the pressure side of one compressor station and the suction side of the next compressor station downstream of the former gas flow, at a minimum, sample all ends of the abandoned pipe.

(2) If the pipeline section to be abandoned is longer than the distance between the pressure side of one compressor station and the suction side of the next compressor station downstream of the former gas flow, divide the pipeline section, for purposes of sampling, into smaller pipeline sections no longer than the distance from the pressure side of one compressor station to the suction side of the next compressor station downstream of the former gas flow. Consider each of the

smaller sections to be a separate abandonment and sample each one, at a minimum, at all ends.

(3) Use the following procedure to locate representative sample collection sites in pipeline sections at points other than the suction and pressure side of compressor stations, or the ends of the pipeline section to be abandoned.

(i) First, assign a unique identifying sequential number to each kilometer or fraction of a kilometer length of pipe within the entire pipeline section.

(ii) Use a random number table or a random number generator to select each representative sample collection site from a complete list of the sequential identification numbers.

(iii) Samples may be collected by removing any covering soil, cutting the pipe to gain access to the sampling location, and collecting the surface sample with the pipe in place, rather than completely removing the pipeline sections to collect the surface sample.

[63 FR 35462, June 29, 1998, as amended at 64 FR 33762, June 24, 1999]

### § 761.253 Chemical analysis.

(a) Extract PCBs from the standard wipe sample collection medium and clean-up the extracted PCBs in accordance with either Method 3500B/3540C or Method 3500B/3550B from EPA's SW-846, Test Methods for Evaluating Solid Waste, or a method validated under subpart Q of this part. Use Method 8082 from SW-846, or a method validated under subpart Q of this part, to analyze these extracts for PCBs.

(b) Report all PCB sample concentrations in  $\mu\text{g}/100\text{ cm}^2$  (16 square inches) of surface sampled. If sampling an area smaller than  $100\text{ cm}^2$ , report converted sample concentrations in accordance with § 761.243(b).

### § 761.257 Determining the regulatory status of sampled pipe.

(a) For purposes of removal for disposal of a pipe segment that has been sampled, the sample results for that segment determines its PCB surface concentration. Determine the PCB surface concentration of a segment which was not sampled as follows:

(1) If the unsampled pipe segment is between two pipe segments which have been sampled, assume that the

## § 761.260

## 40 CFR Ch. I (7–1–10 Edition)

unsampled segment has the same PCB surface concentration as the nearest sampled pipe segment.

(2) If an unsampled pipe segment is equidistant between two pipe segments which have been sampled, assume the PCB surface concentration of the unsampled segment to be the arithmetic mean of the PCB surface concentrations measured in the two equidistant, sampled, pipe segments.

(b) For purposes of abandonment of a pipeline section, assume that the PCB surface concentration for an entire pipeline section is the arithmetic mean of the PCB surface concentrations measured at the ends of the pipeline section. If additional representative samples were taken in a pipeline section, assume that the PCB surface concentration for the entire pipeline section is the arithmetic mean of the concentrations measured in all representative samples taken.

(c) For purposes of removal for disposal under § 761.60(b)(5)(ii)(A)(I) or abandonment under § 761.60(b)(5)(i)(B), if the surface PCB concentration of a pipe segment, determined by direct measurement or in accordance with paragraph (a) of this section, or of a pipeline section as determined in accordance with paragraph (b) of this section, is  $>10 \mu\text{g}/100 \text{ cm}^2$ , but  $<100 \mu\text{g}/100 \text{ cm}^2$ , then that segment or section is PCB-Contaminated.

### Subpart N—Cleanup Site Characterization Sampling for PCB Remediation Waste in Accordance with § 761.61(a)(2)

SOURCE: 63 FR 35464, June 29, 1998, unless otherwise noted.

#### § 761.260 Applicability.

This subpart provides a method for collecting new data for characterizing a PCB remediation waste cleanup site or for assessing the sufficiency of existing site characterization data, as required by § 761.61(a)(2).

#### § 761.265 Sampling bulk PCB remediation waste and porous surfaces.

(a) Use a grid interval of 3 meters and the procedures in §§ 761.283 and 761.286 to sample bulk PCB remediation waste

that is not in a container and porous surfaces.

(b) Use the following procedures to sample bulk PCB remediation waste that is in a single container.

(1) Use a core sampler to collect a minimum of one core sample for the entire depth of the waste at the center of the container. Collect a minimum of  $50 \text{ cm}^3$  of waste for analysis.

(2) If more than one core sample is taken, thoroughly mix all samples into a composite sample. Take a subsample of a minimum of  $50 \text{ cm}^3$  from the mixed composite for analysis.

(c) Use the following procedures to sample bulk PCB remediation waste that is in more than one container.

(1) Segregate the containers by type (for example, a 55-gallon drum and a roll-off container are types of containers).

(2) For fewer than three containers of the same type, sample all containers.

(3) For more than three containers of the same type, list the containers and assign each container a unique sequential number. Use a random number generator or table to select a minimum of 10 percent of the containers from the list, or select three containers, whichever is the larger.

(4) Sample the selected container(s) according to paragraph (b) of this section.

#### § 761.267 Sampling non-porous surfaces.

(a) Sample large, nearly flat, non-porous surfaces by dividing the surface into roughly square portions approximately 2 meters on each side. Follow the procedures in § 761.302(a).

(b) It is not necessary to sample small or irregularly shaped surfaces.

#### § 761.269 Sampling liquid PCB remediation waste.

(a) If the liquid is single phase, collect and analyze one sample. There are no required procedures for collecting a sample.

(b) If the liquid is multi-phasic, separate the phases, and collect and analyze a sample from each liquid phase. There are no required procedures for collecting a sample from each single phase liquid.

## Environmental Protection Agency

## § 761.283

(c) If the liquid has a non-liquid phase which is >0.5 percent by total weight of the waste, separate the non-liquid phase from the liquid phase and sample it separately as a non-liquid in accordance with § 761.265.

### § 761.272 Chemical extraction and analysis of samples.

Use either Method 3500B/3540C or Method 3500B/3550B from EPA's SW-846, Test Methods for Evaluating Solid Waste, or a method validated under subpart Q of this part, for chemical extraction of PCBs from individual and composite samples of PCB remediation waste. Use Method 8082 from SW-846, or a method validated under subpart Q of this part, to analyze these extracts for PCBs.

### § 761.274 Reporting PCB concentrations in samples.

(a) Report all sample concentrations for non-liquid PCBs on a dry weight basis as micrograms of PCBs per gram of sample (ppm by weight). Report surface sampling results as  $\mu\text{g}/100\text{ cm}^2$ . Divide  $100\text{ cm}^2$  by the surface area and multiply this quotient by the total number of micrograms of PCBs on the surface to obtain the equivalent measurement of micrograms per  $100\text{ cm}^2$ .

(b) Report all sample concentrations for liquid PCBs on a wet weight basis as micrograms of PCBs per gram of sample (ppm by weight).

### Subpart O—Sampling To Verify Completion of Self-Implementing Cleanup and On-Site Disposal of Bulk PCB Remediation Waste and Porous Surfaces in Accordance With § 761.61(a)(6)

SOURCE: 63 FR 35465, June 29, 1998, unless otherwise noted.

### § 761.280 Application and scope.

Follow the procedures in this subpart when sampling to verify completion of the cleanup for self-implementing, on-site disposal of bulk PCB remediation waste and porous surfaces consistent with the levels of § 761.61(a)(4)(i) and (iii). The objective of this subpart is not to search for new contamination.

Confirmation of compliance with the cleanup levels in § 761.61(a)(4) is only verifiable for the area sampled in accordance with this subpart. Do not make conclusions or extrapolations about PCB concentrations outside of the area which has been cleaned up and verified based on the results of this verification sampling.

### § 761.283 Determination of the number of samples to collect and sample collection locations.

This section addresses how to determine the number of samples to collect and sample collection locations for bulk PCB remediation waste and porous surfaces destined to remain at a cleanup site after cleanup.

(a) *Minimum number of samples.* (1) At each separate cleanup site at a PCB remediation waste location, take a minimum of three samples for each type of bulk PCB remediation waste or porous surface at the cleanup site, regardless of the amount of each type of waste that is present. There is no upper limit to the number of samples required or allowed.

(2) This is an example of how to calculate the minimum number of required samples at a PCB remediation waste location. There are three distinct cleanup sites at this example location: a loading dock, a transformer storage lot, and a disposal pit. The minimum number of samples to take appears in parentheses after each type of waste for each cleanup site. The PCB remediation wastes present at the loading dock are concrete (three samples) and clay soil (three samples). The non-liquid PCB remediation wastes present at the transformer storage lot are oily soil (three samples), clay soil (three samples) and gravel (three samples). The PCB remediation wastes present at the disposal pit are sandy soil (three samples), clay soil (three samples), oily soil (three samples), industrial sludge (three samples), and gravel (three samples).

(b) *Selection of sample locations—general.* (1)(i) Use a square-based grid system to overlay the entire area to be sampled. Orient the grid axes on a magnetic north-south line centered in

the area and an east-west axis perpendicular to the magnetic north-south axis also centered in the area.

(ii) If the site is recleaned based on the results of cleanup verification conducted in accordance with §761.61(a)(6), follow the procedures in paragraph (b) of this section for locating sampling points after the recleaning, but reorient the grid axes established in paragraph (b)(1)(i) of this section by moving the origin one meter in the direction of magnetic north and one meter in the direction east of magnetic north.

(2) Mark out a series of sampling points 1.5 meters apart oriented to the grid axes. The sampling points shall proceed in every direction to the extent sufficient to result in a two-dimensional grid completely overlaying the sampling area.

(3) Collect a sample at each point if the grid falls in the cleanup area. Analyze all samples either individually or according to the compositing schemes provided in the procedures at §761.289. So long as every sample collected at a grid point is analyzed as either an individual sample or as part of a composite sample, there are no other restrictions on how many samples are analyzed.

(c) *Selection of sample locations—small cleanup sites.* When a cleanup site is sufficiently small or irregularly shaped that a square grid with a grid interval of 1.5 meters will not result in a minimum of three sampling points for each type of bulk PCB remediation waste or porous surface at the cleanup site, there are two options.

(1) Use a smaller square grid interval and the procedures in paragraph (b) of this section.

(2) Use the following coordinate-based random sampling scheme. If the site is recleaned based on the results of cleanup verification conducted in accordance with §761.61(a)(6), follow the procedures in this section for locating sampling points after the recleaning, but select three new pairs of sampling coordinates.

(i) Beginning in the southwest corner (lower left when facing magnetic north) of the area to be sampled, measure in centimeters (or inches) the maximum magnetic north-south dimension of the area to be sampled. Next, beginning in the southwest corner, measure

in centimeters (or inches) the maximum magnetic east-west dimension of the area to be sampled. Designate the north-south and east-west dimensions (describing the west and south boundaries, respectively, of the area to be sampled), as the reference axes of a square-based grid system.

(ii) Use a random number table or random number generator to select a pair of coordinates that will locate the sample within the area to be sampled. The first coordinate in the pair is the measurement on the north-south axis. The second coordinate in the pair is the measurement on the east-west axis. Collect the sample at the intersection of an east-west line drawn through the measured spot on the north-south axis, and a north-south line drawn through the measured spot on the east-west axis. If the cleanup site is irregularly shaped and this intersection falls outside the cleanup site, select a new pair of sampling coordinates. Continue to select pairs of sampling coordinates until three are selected for each type of bulk PCB remediation waste or porous surface at the cleanup site.

(d) *Area of inference.* Analytical results for an individual sample point apply to the sample point and to an area of inference extending to four imaginary lines parallel to the grid axes and one half grid interval distant from the sample point in four different directions. The area of inference forms a square around the sample point. The sides of the square are parallel to the grid axes and one grid interval in length. The sample point is in the center of the square area of inference. The area of inference from a composite sample is the total of the areas of the individual samples included in the composite.

**§761.286 Sample size and procedure for collecting a sample.**

At each selected sampling location for bulk PCB remediation waste or porous surfaces, collect at least 20 milliliters of waste, or a portion of sufficient weight for the chemical analyst to measure the concentration of PCBs and still have sufficient analytical detection sensitivity to reproducibly measure PCBs at the levels designated

in § 761.61(a)(4). Use a core sampler having a diameter  $\geq 2$  cm and  $\leq 3$  cm. Collect waste to a maximum depth of 7.5 cms.

**§ 761.289 Compositing samples.**

Compositing is a method of combining several samples of a specific type of bulk PCB remediation waste or porous surface from nearby locations for a single chemical analysis. There are two procedures for compositing bulk PCB remediation waste samples. These procedures are based on the method for selecting sampling site locations in § 761.283(b) and (c). The single chemical analysis of a composite sample results in an averaging of the concentrations of its component samples. The area of inference of a composite is determined by the area of inference of each of its component samples as described in § 761.283(d). Compositing is not mandatory. However, if compositing is used, it must be performed in accordance with the following procedures.

(a) *Compositing in the field or in a laboratory.* Compositing may occur either in the field or in a laboratory. Prepare composite samples using equal volumes of each constituent or component sample. Compositing samples must be from the same type of bulk PCB remediation waste or porous surface (see the example at § 761.283(a)(2)). Mix composite samples thoroughly. From each well-mixed composite sample, take a portion of sufficient weight for the chemical analyst to measure the concentration of PCBs and still have sufficient analytical detection sensitivity to reproducibly measure PCBs at the levels designated in § 761.61(a)(4).

(b)(1) *Compositing from samples collected at grid points in accordance with § 761.283(b).* There are two kinds of composite sampling procedures depending on the original source of contamination of the site.

(i) The first procedure is for sites with multiple point sources of contamination (such as an old electrical equipment storage area, a scrap yard, or repair shop) or for unknown sources of contamination. Under this compositing scheme, composite a maximum of nine samples for each type of bulk PCB remediation waste or porous surface at the cleanup site. The maximum

dimensions of the area enclosing a nine grid point composite is two grid intervals bounded by three collinear grid points (3.0 meters or approximately 10 feet long). Take all samples in the composite at the same depth. Assure that composite sample areas and individually analyzed samples completely overlay the cleanup site.

(ii) The second procedure is for a single point source of contamination, such as discharge into a large containment area (e.g., pit, waste lagoon, or evaporation pond), or a leak onto soil from a single drum or tank. Single point source contamination may be from a one-time or continuous contamination. Composites come from two stages: an initial compositing area centered in the area to be sampled, and subsequent compositing areas forming concentric square zones around the initial compositing area. The center of the initial compositing area and each of the subsequent compositing areas is the origin of the grid axes.

(A) *Definition of the initial compositing area.* The initial compositing area is based on a square that contains nine grid points, is centered on the grid origin, and has sides two grid intervals long. The initial compositing area has the same center as this square and sides one half a grid interval more distant from the center than the square. The initial compositing area has sides three grid intervals long.

(B) *Definition of subsequent compositing areas.* Subsequent composite sampling areas are in concentric square zones one grid interval wide around the initial compositing area and around each successive subsequent compositing area. The inner boundary of the first subsequent compositing area is the outer boundary of the initial compositing area. The outer boundary of the first subsequent compositing area is centered on the grid origin, has sides one grid interval more distant from the grid origin than the inner boundary, and is two grid intervals longer on a side than the inner boundary. The inner boundary of each further subsequent compositing area is the outer boundary of the previous subsequent compositing area. The outer boundary of each further subsequent compositing area is centered on the



**§ 761.292**

grid origin, has sides one grid interval more distant from the grid origin than the inner boundary, and is two grid intervals longer on a side than the inner boundary.

(C) *Taking composite samples from the initial and subsequent compositing areas.*

(1) Select composite sampling areas from the initial compositing area and subsequent compositing areas such that all grid points in the initial compositing area and subsequent compositing areas are part of a composite or individual sample.

(2) A person may include in a single composite sample a maximum of all nine grid points in the initial compositing area. The maximum number of grid points in a composite sample taken from a subsequent compositing area is eight. These eight grid points must be adjacent to one another in the subsequent compositing area, but need not be collinear.

(2) *Compositing from samples taken at grid points or pairs of coordinates in accordance with § 761.283(c).* Samples collected at small sites are based on selecting pairs of coordinates or using the sample site selection procedure for grid sampling with a smaller grid interval.

(i) *Samples collected from a grid having a smaller grid interval.* Use the procedure in paragraph (b)(1)(i) of this section to composite samples and determine the area of inference for composite samples.

(ii) *Samples collected from pairs of coordinates.* All three samples must be composited. The area of inference for the composite is the entire area sampled.

**§ 761.292 Chemical extraction and analysis of individual samples and composite samples.**

Use either Method 3500B/3540C or Method 3500B/3550B from EPA's SW-846, Test Methods for Evaluating Solid Waste, or a method validated under subpart Q of this part, for chemical extraction of PCBs from individual and composite samples of PCB remediation waste. Use Method 8082 from SW-846, or a method validated under subpart Q of this part, to analyze these extracts for PCBs.

**40 CFR Ch. I (7-1-10 Edition)**

**§ 761.295 Reporting and recordkeeping of the PCB concentrations in samples.**

(a) Report all sample concentrations for bulk PCB remediation waste and porous surfaces on a dry weight basis and as micrograms of PCBs per gram of sample (ppm by weight).

(b) Record and keep on file for 3 years the PCB concentration for each sample or composite sample.

**§ 761.298 Decisions based on PCB concentration measurements resulting from sampling.**

(a) For grid samples which are chemically analyzed individually, the PCB concentration applies to the area of inference as described in § 761.283(d).

(b) For grid samples analyzed as part of a composite sample, the PCB concentration applies to the area of inference of the composite sample as described in § 761.283(d) (i.e., the area of inference is the total of the areas of the individual samples included in the composite).

(c) For coordinate pair samples analyzed as part of a composite sample, in accordance with §§ 761.283(c)(2) and 761.289(b)(2)(ii), the PCB concentration applies to the entire cleanup site.

**Subpart P—Sampling Non-Porous Surfaces for Measurement-Based Use, Reuse, and On-Site or Off-Site Disposal Under § 761.61(a)(6) and Decontamination Under § 761.79(b)(3)**

SOURCE: 63 FR 35467, June 29, 1998, unless otherwise noted.

**§ 761.300 Applicability.**

This subpart provides sample site selection procedures for large, nearly flat non-porous surfaces, and for small or irregularly shaped non-porous surfaces. This subpart also provides procedures for analyzing the samples and interpreting the results of the sampling. Any person verifying completion of self-implementing cleanup and on-site disposal of non-porous surfaces under § 761.61(a)(6), or verifying that decontamination standards under

## Environmental Protection Agency

## § 761.306

§ 761.79(b)(3) are met, must use these procedures.

### § 761.302 Proportion of the total surface area to sample.

(a) *Large nearly flat surfaces.* Divide the entire surface into approximately 1 meter square portions and mark the portions so that they are clearly identified. Determine the sample location in each portion as directed in § 761.304.

(1) For large nearly flat surfaces contaminated by a single source of PCBs with a uniform concentration, assign each 1 meter square surface a unique sequential number.

(i) For three or fewer 1 meter square areas, sample all of the areas.

(ii) For four or more 1 meter square areas, use a random number generator or table to select a minimum of 10 percent of the areas from the list, or to select three areas, whichever is more.

(2) For other large nearly flat surfaces, sample all of the one meter square areas.

(b) *Small or irregularly shaped surfaces.* For small surfaces having irregular contours, such as hand tools, natural gas pipeline valves, and most exterior surfaces of machine tools, sample the entire surface. Any person may select sampling locations for small, nearly flat surfaces in accordance with § 761.308 with the exception that the maximum area in § 761.308(a) is <1 meter square.

(c) *Preparation of surfaces.* Drain all free-flowing liquids from surfaces and brush off dust or loose grit.

### § 761.304 Determining sample location.

(a) For 1 square meter non-porous surface areas having the same size and shape, it is permissible to sample the same 10 cm by 10 cm location or position in each identical 1 square meter area. This location or position is determined in accordance with § 761.306 or § 761.308.

(b) If some 1 square meter surfaces for a larger non-porous surface area have different sizes and shapes, separately select the 10 cm by 10 cm sampling position for each different 1 square meter surface in accordance with § 761.308.

(c) If non-porous surfaces have been cleaned and the cleaned surfaces do not

meet the applicable standards or levels, surfaces may be recleaned and resampled. When resampling surfaces previously sampled to verify cleanup levels, use the sampling procedures in §§ 761.306 through 761.316 to resample the surfaces. If any sample site selected coincides with a previous sampling site, restart the sample selection process until all resampling sites are different from any previous sampling sites.

### § 761.306 Sampling 1 meter square surfaces by random selection of halves.

(a) Divide each 1 meter square portion where it is necessary to collect a surface wipe test sample into two equal (or as nearly equal as possible) halves. For example, divide the area into top and bottom halves or left and right halves. Choose the top/bottom or left/right division that produces halves having as close to the shape of a circle as possible. For example, a square is closer to the shape of a circle than is a rectangle and a rectangle having a length to width ratio of 2:1 is closer to the shape of a circle than a rectangle having a length to width ratio of 3:1.

(b) Assign a unique identifier to each half and then select one of the halves for further sampling with a random number generator or other device (i.e., by flipping a coin).

(c) Continue selecting progressively smaller halves by dividing the previously selected half, in accordance with paragraphs (a) and (b) of this section, until the final selected half is larger than or equal to 100 cm<sup>2</sup> and smaller than 200 cm<sup>2</sup>.

(d) Perform a standard PCB wipe test on the final selected halves from each 1 meter square portion.

(e) The following is an example of applying sampling by halves. Assume that the area to sample is a 1 meter square surface area (a square that has sides 1 meter long). Assign each half to one face of a coin. After flipping the coin, the half assigned to the face of the coin that is showing is the half selected.

(1) Selecting the first half:

(i) For a square shape the top/bottom halves have the same shape as the left/right halves when compared to a circle,

§ 761.308

40 CFR Ch. I (7-1-10 Edition)

i.e., regardless of which way the surface is divided, each half is 1 half meter wide by 1 meter long. Therefore, divide the area either top/bottom or left/right. For selecting the first half, this example will select from left/right halves.

(ii) A coin flip selects the left half. The dimensions of this selected surface area are 1 meter high and  $\frac{1}{2}$  meter wide.

(2) Selecting the second half:

(i) If the next selection of halves was left/right, the halves would be rectangles four times as long as they are wide ( $\frac{1}{4}$  meter wide and 1 meter high). Halves selected from top/bottom would be square ( $\frac{1}{2}$  meter on a side). Therefore, select the next halves top/bottom, because the shape of the top/bottom halves (square) is closer to the shape of a circle than the shape of the left/right halves (long narrow rectangles).

(ii) A coin flip selects the top half. The dimensions of this selected surface area are  $\frac{1}{2}$  meter high and  $\frac{1}{2}$  meter wide.

(3) Selecting the third half:

(i) Just as for the selection of the first half, which divided the original square area, both the left/right and the top/bottom halves have the same shape when compared to a circle (both are rectangles having the same dimensions). Therefore, choose either left/right or top/bottom halves. This example will select from left/right halves.

(ii) A coin flip selects the right half. The dimensions of this selected surface area are  $\frac{1}{4}$  meter by  $\frac{1}{2}$  meter.

(4) Selecting the fourth half:

(i) If the next selection of halves was left/right, the halves would be rectangles four times as long as they are wide ( $\frac{1}{8}$  meter wide and  $\frac{1}{2}$  meter high). Halves selected from top/bottom would be square ( $\frac{1}{4}$  meter on a side). Therefore, select the next halves top/bottom, because the shape of the top/bottom halves (square) are closer to the shape of a circle than the shape of the left/right halves (long narrow rectangles).

(ii) A coin flip selects the bottom half. The dimensions of this selected surface area are  $\frac{1}{4}$  meter high and  $\frac{1}{4}$  meter wide.

(5) Selecting the fifth half:

(i) Just as for the selection of the first and third halves, both the left/right and the top/bottom halves have

the same shape when compared to a circle (both are rectangles having the same dimensions). Therefore, choose either left/right or top/bottom halves. This example will select from left/right halves.

(ii) A coin flip selects the right half. The dimensions of the selected surface are  $\frac{1}{8}$  meter by  $\frac{1}{4}$  meter.

(6) Selecting the sixth half:

(i) If the next selection of halves was left/right, the halves would be rectangles four times as long as they are wide ( $\frac{1}{16}$  meter wide and  $\frac{1}{4}$  meter high). Halves selected from top/bottom would be square ( $\frac{1}{8}$  meter on a side). Therefore, select the next halves top/bottom, because the shape of the top/bottom halves (square) are closer to the shape of a circle than the shape of the left/right halves (long narrow rectangles).

(ii) A coin flip selects the top half. The dimensions of this selected surface are  $\frac{1}{8}$  meter high and  $\frac{1}{8}$  meter wide or 12.5 cm by 12.5 cm.

(7) Collect a standard wipe test sample in the sixth half. Since the dimensions of half of the sixth half would be 12.5 cm by 6.25 cm, the area (approximately 78 cm<sup>2</sup>) would be less than the required 100 cm<sup>2</sup> minimum area for the standard wipe test. Therefore, no further sampling by halves is necessary. Take the standard wipe test samples of the entire selected sixth half.

**§ 761.308 Sample selection by random number generation on any two-dimensional square grid.**

(a) Divide the surface area of the non-porous surface into rectangular or square areas having a maximum area of 1 square meter and a minimum dimension of 10 centimeters.

(b) Measure the length and width, in centimeters, of each area created in paragraph (a) of this section. Round off the number of centimeters in the length and the width measurements to the nearest centimeter.

(c) For each 1 square meter area created in accordance with paragraph (a) of this section, select two random numbers: one each for the length and width borders measured in paragraph (b) of this section. An eligible random number can be from zero up to the total width, minus 10 centimeters.

## Environmental Protection Agency

## §761.316

(d) Locate the 10 centimeter by 10 centimeter sample.

(1) Orient the 1 square meter surface area so that, when you are facing the area, the length is left to right and the width is top to bottom. The origin, or reference point for measuring selected random numbers of centimeters to the sampling area, is on the lower left corner when facing the surface.

(2) Mark the random number selected for the length distance, in centimeters, from the origin to the right (at the bottom of the area away from the origin).

(3) From the marked length distance on the bottom of the area, move perpendicularly up from the bottom of the area into the area for the distance randomly selected for the width.

(4) Use the point determined in paragraph (d)(3) of this section as the lower left corner of the 10 centimeter by 10 centimeter sample.

### §761.310 Collecting the sample.

Use the standard wipe test as defined in §761.123 to sample one 10 centimeter by 10 centimeter square (100 cm<sup>2</sup>) area to represent surface area PCB concentrations of each square meter or fraction of a square meter of a nearly flat, non-porous surface. For small surfaces, use the same procedure as for the standard wipe test, only sample the entire area, rather than 10 centimeter by 10 centimeter squares.

### §761.312 Compositing of samples.

For a surface originally contaminated by a single source of PCBs with a uniform concentration, it is permissible to composite surface wipe test samples and to use the composite measurement to represent the PCB concentration of the entire surface. Composite samples consist of more than one sample gauze extracted and chemically analyzed together resulting in a single measurement. The composite measurement represents an arithmetic mean of the composited samples.

(a) *Compositing samples from surfaces to be used or reused.* For small or irregularly shaped surfaces or large nearly flat surfaces, if the surfaces are contaminated by a single source of PCBs with a uniform concentration, com-

posite a maximum of three adjacent samples.

(b) *Compositing samples from surfaces to be disposed of off-site or on-site.* (1) For small or irregularly shaped surfaces, composite a maximum of three adjacent samples.

(2) For large nearly flat surfaces, composite a maximum of 10 adjacent samples.

### §761.314 Chemical analysis of standard wipe test samples.

Perform the chemical analysis of standard wipe test samples in accordance with §761.272. Report sample results in micrograms per 100 cm<sup>2</sup>.

### §761.316 Interpreting PCB concentration measurements resulting from this sampling scheme.

(a) For an individual sample taken from an approximately 1 meter square portion of the entire surface area and not composited with other samples, the status of the portion is based on the surface concentration measured in that sample. If the sample surface concentration is not equal to or lower than the cleanup level, by inference the entire 1 meter area, and not just the immediate area where the sample was taken, is not equal to or lower than the cleanup level.

(b) For areas represented by the measurement results from compositing more than one 10 centimeter by 10 centimeter sample, the measurement for the composite is the measurement for the entire area. For example, when there is a composite of 10 standard wipe test samples representing 9.5 square meters of surface area and the result of the analysis of the composite is 20 µg/100 cm<sup>2</sup>, then the entire 9.5 square meters has a PCB surface concentration of 20 µg/100 cm<sup>2</sup>, not just the area in the 10 cm by 10 cm sampled areas.

(c) For small surfaces having irregular contours, where the entire surface was sampled, measure the surface area. Divide 100 cm<sup>2</sup> by the surface area and multiply this quotient by the total number of micrograms of PCBs on the surface to obtain the equivalent measurement of micrograms per 100 cm<sup>2</sup>.

**Subpart Q—Self-Implementing Alternative Extraction and Chemical Analysis Procedures for Non-liquid PCB Remediation Waste Samples**

SOURCE: 63 FR 35468, June 29, 1998, unless otherwise noted.

**§ 761.320 Applicability.**

This subpart describes self-implementing comparison testing requirements for chemical extraction and chemical analysis methods used as an alternative to the methods required in §§ 761.272 or 761.292. Any person conducting comparison testing under this subpart must comply with the requirements of § 761.80(i), including notification. Use alternative methods only after successful completion of these comparison testing requirements and after documentation of the results of the testing.

**§ 761.323 Sample preparation.**

(a) The comparison study requires analysis of a minimum of 10 samples weighing at least 300 grams each. Samples of PCB remediation waste used in the comparison study must meet the following three requirements.

(1) The samples must either be taken from the PCB remediation waste at the cleanup site, or must be the same kind of material as that waste. For example, if the waste at the cleanup site is sandy soil, you must use the same kind of sandy soil in the comparison study. Do not use unrelated materials such as clay soil or dredged sediments in place of sandy soil.

(2) PCB remediation waste may contain interferences which confound or hamper sample extraction and chemical analysis. These interferences may be from chemicals or other attributes preexisting in the waste material, resulting from the PCB contamination source, or resulting from treatment to remove or destroy PCBs. Comparison study samples must also contain these interfering materials to demonstrate successful analysis in their presence. For example, a PCB remediation waste may have been co-disposed with chlorobenzene solvents or chlorinated pesticides. These chlorinated compounds

would have to be present in the comparison study compounds at the same levels found, or at the highest levels expected to be found, in the PCB remediation waste. As another example, for PCB remediation waste which had been solvent washed with liquid amines to remove PCBs, comparison study samples would have to contain concentrations of these amines at the same levels found, or at the highest levels expected to be found, in the PCB remediation waste.

(b) Prior to initiating the comparison study, confirm the following PCB concentrations in the comparison study samples using the methods specified in § 761.292. All samples of non-liquid PCB remediation waste must have PCB concentrations between 0.1 and 150 ppm.

(1) A minimum of three comparison study samples must have PCB concentrations above the cleanup level specified for the site in § 761.61(a)(4) and a minimum of three comparison study samples must have PCB concentrations below the specified cleanup level.

(2) At least one comparison study sample must have a PCB concentration  $\geq 90$  percent and  $\leq 100$  percent of the cleanup level.

(3) At least one comparison study sample must have a PCB concentration  $\geq 100$  percent and  $\leq 110$  percent of the cleanup level.

(c) If the comparison study samples do not have the concentrations or concentration ranges required by paragraph (b) of this section, for purposes of use in this chemical extraction and chemical analysis comparison study, a person may adjust PCB concentrations by dilution. Any excess material resulting from the preparation of these samples, which is not used as an analytical sample, is regulated as the PCB concentration in the component having the highest PCB concentration of the component materials in the sample.

**§ 761.326 Conducting the comparison study.**

Extract or analyze the comparison study samples using the alternative method. For an alternative extraction method or alternative analytical method to be comparable to the methods required in § 761.292, all of the following conditions must be met.

(a) All samples having PCB concentrations greater than or equal to the level of concern, as measured by the methods required in § 761.292, are found to be greater than or equal to the level of concern as measured by the alternative method (no false negatives).

(b) Only one sample which contains PCBs at a level less than the level of concern, as measured by the methods required in § 761.292, is found to have a PCB concentration greater than the level of concern as measured by the alternative method (false positive); and all other samples which contain PCBs at levels less than the level of concern, as measured by the methods required in § 761.292, are found by the alternative method to have PCBs less than the level of concern (there are no additional false positives).

**Subpart R—Sampling Non-Liquid, Non-Metal PCB Bulk Product Waste for Purposes of Characterization for PCB Disposal in Accordance With § 761.62, and Sampling PCB Remediation Waste Destined for Off-Site Disposal, in Accordance With § 761.61**

SOURCE: 63 FR 35469, June 29, 1998, unless otherwise noted.

**§ 761.340 Applicability.**

Use the procedures specified in this subpart to sample the following types of waste when it is necessary to analyze the waste to determine PCB concentration or leaching characteristics for storage or disposal.

(a) Existing accumulations of non-liquid, non-metal PCB bulk product waste.

(b) Non-liquid, non-metal PCB bulk product waste from processes that continuously generate new waste.

(c) Non-liquid PCB remediation waste from processes that continuously generate new waste, that will be sent off-site for disposal.

**§ 761.345 Form of the waste to be sampled.**

PCB bulk product waste and PCB remediation waste destined for off-site

disposal must be in the form of either flattened or roughly conical piles. This subpart also contains a procedure for contemporaneous sampling of waste as it is being generated.

**§ 761.346 Three levels of sampling.**

To select a sample of the waste and prepare it for chemical extraction and analysis, there are three required levels of random sampling.

(a) First, select a single 19-liter (5 gallon) portion from a composite accumulated either contemporaneously with the generation of the waste or by sampling an existing pile of waste. Collection procedures for the first level of sampling from existing piles of waste are in § 761.347. Collection procedures for the first level of sampling from a contemporaneous generation of waste are in § 761.348. Compositing requirements and requirements for the subsampling of composite samples to result in a single 19-liter sample are in § 761.350. Send the 19-liter sample to the laboratory for the second and third levels of sampling, including particle size reduction for leach testing and drying as required by § 761.1(b)(4).

(b) Second, at the laboratory, select one quarter of the 19-liter sample. Procedures the laboratory must use for this second level of sample selection appear in § 761.353.

(c) Third, select a 100 gram subsample from the second level subsample. Procedures the laboratory must use for this third level of sample selection appear in § 761.355.

**§ 761.347 First level sampling—waste from existing piles.**

(a) *General.* Sample piles that are either specifically configured for sampling (see paragraph (b) of this section) or that are of conical shape (see paragraph (c) of this section). If sampling from either of these shapes is not possible, conduct contemporaneous sampling, in accordance with the procedures in § 761.348, or obtain the approval of the Regional Administrator for an alternate sampling plan in accordance with § 761.62(c).

(b) *Specifically configured piles.* A specifically configured pile is a single flattened pile in the shape of a square or rectangle having no restrictions on

length or width but restricted to 30 cm (1 foot) in depth. A square shaped pile facilitates sampling site selection for the first level sample. Select eight 19-liter samples from the pile and composite them into one 19-liter sample as follows:

- (1) Divide the pile into quarters.
- (2) Divide each of the quarter sections into quarters (i.e., into sixteenths of the original pile).
- (3) Select two sixteenths from each of the four quarters, according to one of the two following options:
  - (i) Randomly select the two sixteenths from one quarter and sample the sixteenths occupying the same positions in each of the other three quarters.
  - (ii) Randomly select two sixteenths from each of the four quarters (i.e., perform a random selection four different times).
- (4) At this point the eight selected sixteenths undergo further division and sample selection. Divide each of the eight selected sixteenths into four equal parts. Using a random number generator or random number table, select one of the four equal parts from each of the eight equal areas. If each of the four equal parts has a volume >76 liters when projected downwards 30 cm, continue to divide each selected area into four equal parts, and select one of the parts, until each selected area has a volume of <76 liters but ≥19 liters. When projected to a depth of 30 cm, a square having a 25 cm side or a circle having a diameter of approximately 28.5 cm equals a volume of approximately 19 liters. The volume of 76 liters is equal to the volume enclosed by a square having a side of 50 cm (or other shape having an area of 250 cm<sup>2</sup>) projected to a depth of 30 cm.
- (5) Take one sample of approximately 19 unsorted liters of waste from each of the eight selected areas. Place each sample into a separate 19-liter container, allowing only sufficient space at the top of the container to secure the lid.
- (6) Composite the eight 19-liter samples in accordance with §761.350.
- (c) *Conical-shaped piles.* If it is necessary to sample a pile which is too large to be spread on the site to a uniform thickness of 1 foot or 30 cm, or if

there are too many piles to spread out in the space available, use the following procedure to sample the piles. This procedure assumes that the shape of the piles is analogous to a cone; that is, having a circular base with PCB bulk product waste or PCB remediation waste destined for off-site disposal stacked up uniformly to a peak that is a point centered above the center of the circular base. Collect eight 19-liter samples as follows:

- (1) *Collecting samples from more than one pile.* If the PCB bulk product waste or PCB remediation waste consists of more than one pile or container, assign each pile or container an integer number and then generate seven random integer numbers to select the piles from which you will collect samples. It is possible that this random selection procedure will result in selecting the same pile number more than once, even if seven or more piles are present. If so, sample the pile once and restart the sampling collection process to collect additional samples. Do not collect multiple samples from the same location in the pile.
- (2) *Collecting samples from a single pile.* If only one pile or container is present, collect all eight samples from the same pile.
- (3) *Setting up the sample site selection system from a pile.* Locate a sample in a pile by the use of three parameters: a particular radial direction, "r," from the peak at the center of the pile to the outer edge at the base of the pile; a point, "s," along that radial direction between the peak of the pile and the outer edge of the base of the pile; and a depth, "t," beneath point "s." The top of the sample material will be below depth *t*, at point *s*, on radius *r*. Use a rod, dowel, stake, or broom handle as a marker. Nail or otherwise fasten to the top of the marker two pieces of string or cord of sufficient length and strength to reach from the top of the marker at the top of the pile to the farthest peripheral edge at the bottom of the pile, when the marker is positioned at the top or apex of the pile. Pound or push the marker into the top center (apex) of the pile, downward toward the center of the base. Insert the marker for at least 30 cm or one foot until the marker is rigidly standing on

its own, even when the cord is pulled tight to the bottom peripheral edge of the pile. Ensure that the marker protrudes from the top of the pile sufficiently to allow the strings to move easily around the pile when they are pulled tight. Select the three parameters and the sampling location as follows:

(i) Determine the radial component ( $r$ ) of the location for each sample.

(A) Tie to a stake or otherwise fasten one of the strings at "b," the bottom of the pile, as a reference point for finding  $r$ .

(B) Measure the circumference "c," the distance around the bottom of the pile. Determine  $r$  from  $b$  in one of two ways:

(1) Multiply  $c$  by a randomly generated fraction or percentage of one.

(2) Select a random number between one and the total number of centimeters in  $c$ .

(C) Locate  $r$  by starting at  $b$ , the place where the fixed string meets the base of the pile, and travel clockwise around the edge of the pile at the base for the distance you selected in paragraph (c)(3)(i)(B) of this section.

(D) Fasten the second string at the selected distance. The second string marks the first parameter  $r$ .

(ii) Determine the second parameter  $s$  of the location for each sample.

(A) Measure the distance,  $l$ , along the string, positioned in paragraph (c)(3)(i)(D) of this section, from the top to the bottom of the pile at the selected radial distance  $r$ . Determine the distance  $s$  from  $l$  in one of two ways:

(1) Multiply  $l$  by a randomly generated fraction or percentage of one.

(2) Select a random number between one and the total number of centimeters in  $l$ .

(B) Mark, for example by placing a piece of tape on the string positioned according to paragraph (c)(3)(i)(D) of this section, the distance  $s$ , up from the bottom of the pile on the string at  $r$ .

(iii) Determine the third and final parameter  $t$  of the location for each sample.

(A) Mark and number 1 cm intervals from one end of a rigid device, for example a rod, dowel, stake, or broom handle, for measuring the distance from the top of the pile to the bottom

at the point  $s$  selected in paragraph (c)(3)(ii)(B) of this section. The marked and numbered device shall be of sufficient strength to be forced down through the maximum depth of the pile and sufficient length to measure the depth of the waste in the pile at any point.

(B) Take the measuring device, constructed according to paragraph (c)(3)(iii)(A) of this section, and at position  $s$ , push the end of the device marked with zero straight down into the pile until it reaches the bottom of the pile or ground level. The vertical distance "v" is the number of centimeters from the surface of the pile at point  $s$  on the string to the bottom of the pile or ground level. Read the distance  $v$  on the measuring device at the surface of the pile. From the distance  $v$ , determine  $t$ , in one of two ways:

(1) Randomly generate a fraction of one and multiply the fraction times  $v$ .

(2) Select a random number between zero and the total number of centimeters of the vertical distance  $v$ .

(iv) Dig a hole straight down into the pile for  $t$  centimeters (inches) from the surface of the pile at  $s$ .

(v) At depth  $t$ , directly under the  $s$  mark on the string, outline the top of the sample container and collect (shovel) all waste under the outline in the following order of preference in paragraphs (c)(3)(v)(A) through (c)(3)(v)(C) of this section. It is possible that some of the eight sampling locations will not provide 19 liters of sample.

(A) For a depth of 30 cm.

(B) Until the container is full.

(C) Until the ground level is reached.

(d) *Compositing the samples.* Composite the eight 19-liter samples and subsample in accordance with § 761.350. Send the subsample to a laboratory for further sampling as described in §§ 761.353 and 761.355 and for chemical extraction and analysis. If there is insufficient sample for a 19-liter sample from the composite sample composed of the eight iterations of sample site selection, according to the procedures in paragraphs (c)(3)(i) through (c)(3)(v) of this section, select additional sample sites, collect additional samples and composite the additional waste in



## § 761.348

## 40 CFR Ch. I (7-1-10 Edition)

the samples until a minimum of 19 liters is in the composite.

[63 FR 35469, June 29, 1998, as amended at 64 FR 33762, June 24, 1999]

### § 761.348 Contemporaneous sampling.

Contemporaneous sampling is possible when there is active generation of waste and it is possible to sample the waste stream as it is generated. Collect eight 19-liter samples as follows.

(a) Collect each sample by filling a 19-liter (5 gallon) container at a location where the PCB bulk product waste is released from the waste generator onto a pile or into a receptacle container before the waste reaches the pile or receptacle container.

(b) Determine a sample collection start time using a random number generator or a random number table to select a number between 1 and 60. Collect the first sample at the randomly selected time in minutes after start up of the waste output, or if the waste is currently being generated, after the random time is selected. For example, if the randomly selected time is 35, begin collection 35 minutes after the start up of waste generation. Similarly, if waste output is ongoing and the random start determination occurred at 8:35 a.m., collect the first sample at 9:10 a.m. (35 minutes after the random start determination).

(c) Collect seven more samples, one every 60 minutes after the initial sample is collected. If the waste output process stops, stop the 60-minute interval time clock. When the process restarts, restart the 60-minute interval time clock and complete the incomplete 60-minute interval.

(d) Composite the eight 19-liter samples and subsample in accordance with § 761.350.

### § 761.350 Subsampling from composite samples.

(a) *Preparing the composite.* Composite the samples (eight from a flattened pile; eight or more from a conical pile; eight from waste that is continuously generated) and select a 19-liter subsample for shipment to the chemical extraction and analysis laboratory for further subsampling. There are two options for the preparation of the composite:

(1) *Option one.* Place all of the contents of all 19-liter samples that you collected into a 209 liter (55 gallon) drum or similar sized, cylinder-shaped container. Completely close the container, and roll it 10 or more complete revolutions to mix the contents.

(2) *Option two.* Add the 19-liter samples one at a time to a 209 liter (55 gallon) drum. Between the addition of each 19-liter sample, stir the composite using a broom handle or similar long, narrow, sturdy rod that reaches the bottom of the container. Stir the mixture for a minimum of 10 complete revolutions of the stirring instrument around the container at a distance approximately half way between the outside and center of the container.

(b) *Selecting a 19-liter subsample from the composite.* Once the composite is mixed, pour the mixture of waste out on a plastic sheet and either divide it into 19-liter size piles or make one large pile.

(1) From 19-liter sized piles, use a random number generator or random number table to select one of the piles.

(2) From one large pile, flatten the pile to a depth of 30 cm and divide it into 4 quarters of equal size. Use a random number generator or random number table to select one quarter of the pile. Further divide the selected quarter pile into 19-liter portions and use a random number generator or random number table to select one 19-liter portion. A square having a 25 cm side or a circle having a diameter of approximately 28.5 cm when projected downwards 30 cm equals approximately 19 liters.

(c) *Transferring the sample to the analytical laboratory.* Place the selected 19-liter subsample in a container, approved for shipment of the sample, to the chemical extraction and analysis laboratory, for the next step in sample selection in accordance with § 761.353.

### § 761.353 Second level of sample selection.

The second level of sample selection reduces the size of the 19-liter subsample that was collected according to either § 761.347 or § 761.348 and subsampled according to § 761.350. The purpose of the sample size reduction is to limit

the amount of time required to manually cut up larger particles of the waste to pass through a 9.5 millimeter (mm) screen.

(a) *Selecting a portion of the subsample for particle size reduction.* At the chemical extraction and analysis laboratory, pour the 19-liter subsample onto a plastic sheet or into a pan and divide the subsample into quarters. Use a random number generator or random number table to select one of these quarters.

(b) *Reduction of the particle size by the use of a 9.5 mm screen.* Collect the contents of the selected quarter of waste resulting from conducting the procedures in paragraph (a) of this section and shake the waste in a 9.5 mm screen. Separate the waste material which passes through the screen from the waste material which does not pass through the screen. Manually cut or otherwise reduce the size of all parts of the waste portion which did not pass through the 9.5 mm screen, such that each part of the waste shall pass through the 9.5 mm screen by shaking.

(c) *Drying the reduced particle size waste.* Dry all of the waste portion resulting from conducting the procedures in paragraph (b) of this section, from 10 to 15 hours in a drying oven at 100 °C. Allow the dried waste to cool to room temperature.

(d) *Mixing the dried waste.* Place all of the waste resulting from conducting the procedures in paragraph (c) of this section in a 19-liter pail or similarly sized, cylinder-shaped container. Mix the dried material according to one of the two following options:

(1) *First mixing option.* Completely close the container and roll the container a minimum of 10 complete revolutions to mix the contents.

(2) *Second mixing option.* Use a sturdy stirring rod, such as a broom handle or other device that reaches the bottom of the container, to stir the waste for a minimum of 10 complete revolutions around the container at a distance approximately half way between the outside and the center of the container.

#### § 761.355 Third level of sample selection.

The third level of sample selection further reduces the size of the sub-

sample to 100 grams which is suitable for the chemical extraction and analysis procedure.

(a) Divide the subsample resulting from conducting the procedures in § 761.353 of this part into 100 gram portions.

(b) Use a random number generator or random number table to select one 100 gram size portion as a sample for a procedure used to simulate leachate generation.

(c) Dry the 100 gram sample, selected after conducting the procedure in paragraph (b) of this section, for 10 to 15 hours in a drying oven at 100 °C and cool it to the analytical laboratory room temperature before analysis using a procedure used to simulate leachate generation. This sample was dried previously in the larger quantity sample at the second level of sampling (§ 761.353(c)) and is dried a second time here (in the third level of sample selection). This dried and cooled sample must weigh at least 50 grams.

(d) If the dried and cooled sample weighs <50 grams, select additional 100 gram portions of sample one at a time by repeating the directions in paragraph (b) and (c) of this section, and add each additional 100 gram portion of sample to the first 100 gram portion until at least 50 grams of dried material is in the sample to be analyzed using a procedure used to simulate leachate generation.

#### § 761.356 Conducting a leach test.

No method is specified as a procedure used to simulate leachate generation.

#### § 761.357 Reporting the results of the procedure used to simulate leachate generation.

Report the results of the procedure used to simulate leachate generation as micrograms PCBs per liter of extract from a 100 gram sample of dry bulk product waste. Divide 100 grams by the grams in the sample and multiply this quotient by the number of micrograms PCBs per liter of extract to obtain the equivalent measurement from a 100 gram sample.

**§ 761.358**

**40 CFR Ch. I (7-1-10 Edition)**

**§ 761.358 Determining the PCB concentration of samples of waste.**

Use either Method 3500B/3540C or Method 3500B/3550B from EPA's SW-846, Test Methods for Evaluating Solid Waste, or a method validated under subpart Q of this part, for chemical extraction of PCBs from individual and composite samples of PCB bulk product waste. Use Method 8082 from SW-846, or a method validated under subpart Q of this part, to analyze these extracts for PCBs.

**§ 761.359 Reporting the PCB concentrations in samples.**

Report all sample concentrations as ppm by weight on a dry weight basis.

**Subpart S—Double Wash/Rinse Method for Decontaminating Non-Porous Surfaces**

SOURCE: 63 FR 35472, June 29, 1998, unless otherwise noted.

**§ 761.360 Background.**

The double wash/rinse procedure is used to quickly and effectively remove PCBs on surfaces. It is important to select and use the proper cleanup equipment, to conduct the procedure correctly so as not to redistribute PCBs, and to comply with disposal requirements for all cleanup materials.

**§ 761.363 Applicability.**

The double wash/rinse procedure includes two washing steps and two rinsing steps. The two washing and rinsing steps are slightly different depending on whether a contaminated surface was relatively clean before the spill (see § 761.372), or whether the surface was coated or covered with dust, dirt, grime, grease or another absorbent material (see § 761.375).

**§ 761.366 Cleanup equipment.**

(a) Use scrubbers and absorbent pads that are not dissolved by the solvents or cleaners used, and that do not shred, crumble, or leave visible fragments on the surface. Scrubbers and absorbent pads used to wash contaminated surfaces must not be reused. Scrubbers and absorbent pads for rinsing must not contain  $\geq 2$  ppm PCBs. Scrubbers

and absorbent pads used in the second rinse of contaminated surfaces may be reused to wash contaminated surfaces.

(b) Capture and contain all solvents and cleaners for reuse, decontamination, or disposal. Clean organic solvents contain  $< 2$  ppm PCBs. Clean water contains  $< 3$  ppb PCBs.

**§ 761.369 Pre-cleaning the surface.**

If visible PCB-containing liquid is present on the surface to be cleaned, thoroughly wipe or mop the entire surface with absorbent paper or cloth until no liquid is visible on the surface.

**§ 761.372 Specific requirements for relatively clean surfaces.**

For surfaces that do not appear dusty or grimy before a spill, such as glass, automobile surfaces, newly-poured concrete, and desk tops, use the double wash/rinse procedures in this section.

(a) *First wash.* Cover the entire surface with organic solvent in which PCBs are soluble to at least 5 percent by weight. Contain and collect any runoff solvent for disposal. Scrub rough surfaces with a scrub brush or disposable scrubbing pad and solvent such that each 900 cm<sup>2</sup> (1 square foot) of the surface is always very wet for 1 minute. Wipe smooth surfaces with a solvent-soaked, disposable absorbent pad such that each 900 cm<sup>2</sup> (1 square foot) is wiped for 1 minute. Any surface  $< 1$  square foot shall also be wiped for 1 minute. Wipe, mop, and/or sorb the solvent onto absorbent material until no visible traces of the solvent remain.

(b) *First rinse.* Wet the surface with clean rinse solvent such that the entire surface is very wet for 1 minute. Drain and contain the solvent from the surface. Wipe the residual solvent off the drained surface using a clean, disposable absorbent pad until no liquid is visible on the surface.

(c) *Second wash.* Repeat the procedures in paragraph (a) of this section. The rinse solvent from the first rinse (paragraph (b) of this section) may be used.

(d) *Second rinse.* Repeat the procedures in paragraph (b) of this section.

**§ 761.375 Specific requirements for surfaces coated or covered with dust, dirt, grime, grease, or another absorbent material.**

(a) *First wash.* Cover the entire surface with concentrated or industrial strength detergent or non-ionic surfactant solution. Contain and collect all cleaning solutions for proper disposal. Scrub rough surfaces with a scrub brush or scrubbing pad, adding cleaning solution such that the surface is always very wet, such that each 900 cm<sup>2</sup> (1 square foot) is washed for 1 minute. Wipe smooth surfaces with a cleaning solution-soaked disposable absorbent pad such that each 900 cm<sup>2</sup> (1 square foot) is wiped for 1 minute. Wash any surface <1 square foot for 1 minute. Mop up or absorb the residual cleaner solution and suds with a clean, disposable, absorbent pad until the surface appears dry. This cleaning should remove any residual dirt, dust, grime, or other absorbent materials left on the surface during the first wash.

(b) *First rinse.* Rinse off the wash solution with 1 gallon of clean water per square foot and capture the rinse water. Mop up the wet surface with a clean, disposable, absorbent pad until the surface appears dry.

(c) *Second wash.* Follow the procedure in § 761.372(a).

(d) *Second rinse.* Follow the procedure in § 761.372(b).

**§ 761.378 Decontamination, reuse, and disposal of solvents, cleaners, and equipment.**

(a) *Decontamination.* Decontaminate solvents and non-porous surfaces on equipment in accordance with the standards and procedures in § 761.79(b) and (c).

(b) *Reuse.* A solvent may be reused so long as its PCB concentration is <50 ppm. Decontaminated equipment may be reused in accordance with § 761.30(u). Store solvents and equipment for reuse in accordance with § 761.35.

(c) *Disposal.* Dispose of all solvents, cleaners, and absorbent materials in accordance with § 761.79(g). Dispose of equipment in accordance with § 761.61(a)(5)(v)(A), or decontaminate in accordance with § 761.79(b) or (c). Store for disposal equipment, solvents, clean-

ers, and absorbent materials in accordance with § 761.65.

**Subpart T—Comparison Study for Validating a New Performance-Based Decontamination Solvent Under § 761.79(d)(4)**

SOURCE: 63 FR 35473, June 29, 1998, unless otherwise noted.

**§ 761.380 Background.**

This subpart provides self-implementing criteria for validating the conditions for use in performance-based decontamination of solvents other than those listed in § 761.79(c)(3) and (c)(4). Any person may use this subpart for validating either a chemical formulation or a product with a trade name whether or not the constituents of the product are proprietary.

**§ 761.383 Applicability.**

Use the self-implementing decontamination procedure only on smooth, non-porous surfaces that were once in contact with liquid PCBs. Decontamination procedures under this subpart shall exactly parallel § 761.79(c)(3) and (c)(4), except that the procedures described in § 761.79(c)(3)(iii) and (c)(3)(iv) and (c)(4)(iii), (c)(4)(iv) and (c)(4)(vii) may be revised to contain parameters validated in accordance with this subpart.

**§ 761.386 Required experimental conditions for the validation study and subsequent use during decontamination.**

The following experimental conditions apply for any solvent:

(a) *Temperature and pressure.* Conduct the validation study and perform decontamination at room temperature (from ≥15 °C to ≤30 °C) and at atmospheric pressure.

(b) *Agitation.* Limit the movement in the solvent to the short-term movement from placing the contaminated surface into the soak solvent and from removing the surface from the soak solvent.

(c) *Time of soak.* Soak the surface for a minimum of 1 hour.

(d) *Surface conditions for the validation study.* Prior to beginning the validation

study, ensure that there are no free-flowing liquids on surfaces and that surfaces are dry (i.e., there are no liquids visible without magnification). Also ensure that surfaces are virtually free from non-liquid residues, corrosion, and other defects which would prevent the solvent from freely circulating over the surface.

(e) *Confirmatory sampling for the validation study.* Select surface sample locations using representative sampling or a census. Sample a minimum area of 100 cm<sup>2</sup> on each individual surface in the validation study. Measure surface concentrations using the standard wipe test, as defined in § 761.123, from which a standard wipe sample is generated for chemical analysis. Guidance for wipe sampling appears in the document entitled “Wipe Sampling and Double Wash/Rinse Cleanup as Recommended by the Environmental Protection Agency PCB Spill Cleanup Policy,” available on EPA’s Web site at <http://www.epa.gov/pcb>, or from the Program Management, Communications, and Analysis Office, Office of Resource Conservation and Recovery (5305P), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460–0001.

(f) *Concentration of PCBs.* The method validated may be used only to decontaminate surfaces containing PCBs at concentrations on which the validation study was performed and lower concentrations.

[63 FR 35473, June 29, 1998, as amended at 72 FR 57241, Oct. 9, 2007; 74 FR 30235, June 25, 2009]

**§ 761.389 Testing parameter requirements.**

There are no restrictions on the variable testing parameters described in this section which may be used in the validation study. The conditions demonstrated in the validation study for these variables shall become the required conditions for decontamination using the solvent being validated and shall replace the comparable conditions in § 761.79(b)(3) through (b)(6). There are limited potential options for varying a single requirement in this section. If you change one of these variable requirements, change it only in the way listed in this section and do not change any other validated condi-

tions. If you desire to change more than one of the requirements in this section, you must conduct a new study to validate the decontamination under the desired conditions.

(a) The study apparatus is not standardized. Critical components of the study are the PCB material (for example MODEF or some other spiking solution), the volume of the soaking solvent, and the area of the contaminated surface. The EPA study used beakers and shallow dishes as the experimental vessels to contain the surface and solvent during the soaking process. In order to minimize surface-to-volume ratios, it is convenient to utilize flat contaminated surfaces and shallow solvent containers. During the validation study, use the same ratio of contaminated surface area to soak solvent volume as would be used during actual decontamination. It is also permissible to use a smaller surface area to soaking solvent volume than used in the validation study, so long as all other required parameters are used as validated in the confirmation required in § 761.386 (a) through (f), and paragraphs (a) through (c) of this section. Do not use a larger surface-area-to-solvent-volumes ratio or different kind of solvent based on the results of the validation study.

(b) Except for the minimum soak time of 1 hour (as required in § 761.386(c)), the length of soak time is not otherwise restricted in the validation study. The soak time used in the validation study, however, is a use requirement for subsequent decontamination using the solvent being validated. It is permissible to use longer soak times for decontamination than the soak time used in the validation study, if all other parameters required in § 761.386, and paragraphs (a) and (c) of this section are used.

(c) There is no restriction on the kind of material containing PCBs to use to create the surface contamination for the validation study. There is also no restriction on the level of starting PCB surface concentration. It is permissible to use lower concentrations of PCB than the concentration used in the validation study, if all other parameters required in § 761.386 (a) through (f), and paragraphs (a) through (c) of this section are used.

**§ 761.392 Preparing validation study samples.**

(a)(1) To validate a procedure to decontaminate a surface contaminated with a spill from liquid of a known concentration, contaminate (spike) the surface to be used in the validation study as follows:

(i) Use a spiking solution made of PCBs mixed with a solvent to contaminate clean surfaces. Clean surfaces are surfaces having PCB surface concentrations  $<1 \mu\text{g}/100 \text{ cm}^2$  before intentionally contaminating the surface.

(ii) Prior to contaminating a surface for the validation study, mark the surface sampling area to assure that it is completely covered with the spiking solution.

(iii) Deliver the spiking solution onto the surface, covering all of the sampling area. Contain any liquids which spill or flow off the surface. Allow the spiking solution to drip drain off into a container and then evaporate the spiking solution off the contaminated surface prior to beginning the validation study. Contaminate a minimum of eight surfaces for a complete validation study.

(iv) As a quality control step, test at least one contaminated surface to determine the PCB concentration to verify that there are measurable surface levels of PCBs resulting from the contamination before soaking the surface in the decontamination solvent. The surface levels of PCBs on the contaminated surfaces must be  $\geq 20 \mu\text{g}/100 \text{ cm}^2$ .

(2) To validate a procedure to decontaminate a specified surface concentrations of PCBs as measured by a standard wipe sample, contaminate a minimum of 10 surfaces. Contaminate all the surfaces identically following the procedures in paragraph (a)(1) of this section and measure the PCB surface concentrations of at least three of the surfaces using a standard wipe test to establish a surface concentration to be included in the standard operating procedure. The surface levels of PCBs on the contaminated surfaces must be  $\geq 20 \mu\text{g}/100 \text{ cm}^2$ .

(b) [Reserved]

**§ 761.395 A validation study.**

(a) Decontaminate the following prepared sample surfaces using the selected testing parameters and experimental conditions. Take a standard wipe sample of the decontaminated surface.

(1) At least one uncontaminated surface. The surface levels of PCBs on the uncontaminated surface must be  $<1 \mu\text{g}/100 \text{ cm}^2$ .

(2) At least seven contaminated surfaces.

(b)(1) Use SW-846, Test Methods for Evaluating Solid Waste methods for sample extraction and chemical analysis as follows: Use Method 3500B/3540C or Method 3500B/3550B for the extraction and cleanup of the extract and Method 8082 for the chemical analysis, or methods validated under subpart Q of this part.

(2) Report all validation study surface sample concentrations on the basis of micrograms of PCBs per  $100 \text{ cm}^2$  of surface sampled.

(c) Following completion of the validation study, measurements from the contaminated surfaces must have an arithmetic mean of  $\leq 10 \mu\text{g}/100 \text{ cm}^2$ . If the arithmetic mean is  $>10 \mu\text{g}/100 \text{ cm}^2$ , then the validation study failed and the solvent may not be used for decontamination under § 761.79(d)(4) according to the parameters tested.

**§ 761.398 Reporting and record-keeping.**

(a) Submit validation study results to the Director, Office of Resource Conservation and Recovery (5301P), Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460-0001, prior to the first use of a new solvent for alternate decontamination under § 761.79(d)(4). The use of a new solvent is not TSCA Confidential Business Information (CBI). From time to time, EPA will confirm the use of validated new decontamination solvents and publish the new solvents and validated decontamination procedures in the FEDERAL REGISTER.

(b) Any person may begin to use solvent validated in accordance with this subpart at the time results are submitted to EPA.

(c) Record all testing parameters and experimental conditions from the successful validation study into a standard operating procedure (SOP) for reference whenever the decontamination procedure is used. Include in the SOP the identity of the soaking solvent, the length of time of the soak, and the ratio of the soak solvent to contaminated surface area during the soaking process. Also include in the SOP the maximum concentration of PCBs in the spilled material and the identity of the spilled material, and/or the measured maximum surface concentration of the contaminated surface used in the validation study. Record and keep the results of the validation study as an appendix to the SOP. Include in this appendix, the solvent used to make the spiking solution, the PCB concentration of the spiking solution used to contaminate the surfaces in the validation study, and all of the validation study testing parameters and experimental conditions.

[63 FR 35473, June 29, 1998, as amended at 72 FR 57241, Oct. 9, 2007; 74 FR 30235, June 25, 2009]

## PART 763—ASBESTOS

### Subparts A–D [Reserved]

#### Subpart E—Asbestos-Containing Materials in Schools

- Sec.  
 763.80 Scope and purpose.  
 763.83 Definitions.  
 763.84 General local education agency responsibilities.  
 763.85 Inspection and reinspections.  
 763.86 Sampling.  
 763.87 Analysis.  
 763.88 Assessment.  
 763.90 Response actions.  
 763.91 Operations and maintenance.  
 763.92 Training and periodic surveillance.  
 763.93 Management plans.  
 763.94 Recordkeeping.  
 763.95 Warning labels.  
 763.97 Compliance and enforcement.  
 763.98 Waiver; delegation to State.  
 763.99 Exclusions.

APPENDIX A TO SUBPART E—INTERIM TRANSMISSION ELECTRON MICROSCOPY ANALYTICAL METHODS—MANDATORY AND NON-MANDATORY—AND MANDATORY SECTION TO DETERMINE COMPLETION OF RESPONSE ACTIONS

APPENDIX B TO SUBPART E [RESERVED]

APPENDIX C TO SUBPART E—ASBESTOS MODEL ACCREDITATION PLAN  
 APPENDIX D TO SUBPART E—TRANSPORT AND DISPOSAL OF ASBESTOS WASTE  
 APPENDIX E TO SUBPART E—INTERIM METHOD OF THE DETERMINATION OF ASBESTOS IN BULK INSULATION SAMPLES

### Subpart F [Reserved]

#### Subpart G—Asbestos Worker Protection

- 763.120 What is the purpose of this subpart?  
 763.121 Does this subpart apply to me?  
 763.122 What does this subpart require me to do?  
 763.123 May a State implement its own asbestos worker protection plan?

### Subpart H [Reserved]

#### Subpart I—Prohibition of the Manufacture, Importation, Processing, and Distribution in Commerce of Certain Asbestos-Containing Products; Labeling Requirements

- 763.160 Scope.  
 763.163 Definitions.  
 763.165 Manufacture and importation prohibitions.  
 763.167 Processing prohibitions.  
 763.169 Distribution in commerce prohibitions.  
 763.171 Labeling requirements.  
 763.173 Exemptions.  
 763.175 Enforcement.  
 763.176 Inspections.  
 763.178 Recordkeeping.  
 763.179 Confidential business information claims.

AUTHORITY: 15 U.S.C. 2605, 2607(c), 2643, and 2646.

### Subparts A–D [Reserved]

#### Subpart E—Asbestos-Containing Materials in Schools

SOURCE: 52 FR 41846, Oct. 30, 1987, unless otherwise noted.

##### § 763.80 Scope and purpose.

(a) This rule requires local education agencies to identify friable and nonfriable asbestos-containing material (ACM) in public and private elementary and secondary schools by visually inspecting school buildings for such materials, sampling such materials if they are not assumed to be ACM, and having samples analyzed by appropriate techniques referred to in this rule. The rule requires local education

agencies to submit management plans to the Governor of their State by October 12, 1988, begin to implement the plans by July 9, 1989, and complete implementation of the plans in a timely fashion. In addition, local education agencies are required to use persons who have been accredited to conduct inspections, reinspections, develop management plans, or perform response actions. The rule also includes recordkeeping requirements. Local education agencies may contractually delegate their duties under this rule, but they remain responsible for the proper performance of those duties. Local education agencies are encouraged to consult with EPA Regional Asbestos Coordinators, or if applicable, a State's lead agency designated by the State Governor, for assistance in complying with this rule.

(b) Local education agencies must provide for the transportation and disposal of asbestos in accordance with EPA's "Asbestos Waste Management Guidance." For convenience, applicable sections of this guidance are reprinted as Appendix D of this subpart. There are regulations in place, however, that affect transportation and disposal of asbestos waste generated by this rule. The transportation of asbestos waste is covered by the Department of Transportation (49 CFR part 173, subpart J) and disposal is covered by the National Emissions Standards for Hazardous Air Pollutants (NESHAP) (40 CFR part 61, subpart M).

#### § 763.83 Definitions.

For purposes of this subpart:

*Act* means the Toxic Substances Control Act (TSCA), 15 U.S.C. 2601, *et seq.*

*Accessible* when referring to ACM means that the material is subject to disturbance by school building occupants or custodial or maintenance personnel in the course of their normal activities.

*Accredited or accreditation* when referring to a person or laboratory means that such person or laboratory is accredited in accordance with section 206 of Title II of the Act.

*Air erosion* means the passage of air over friable ACM which may result in the release of asbestos fibers.

*Asbestos* means the asbestiform varieties of: Chrysotile (serpentine); crocidolite (riebeckite); amosite (cummingtonitegrunerite); anthophyllite; tremolite; and actinolite.

*Asbestos-containing material (ACM)* when referring to school buildings means any material or product which contains more than 1 percent asbestos.

*Asbestos-containing building material (ACBM)* means surfacing ACM, thermal system insulation ACM, or miscellaneous ACM that is found in or on interior structural members or other parts of a school building.

*Asbestos debris* means pieces of ACBM that can be identified by color, texture, or composition, or means dust, if the dust is determined by an accredited inspector to be ACM.

*Damaged friable miscellaneous ACM* means friable miscellaneous ACM which has deteriorated or sustained physical injury such that the internal structure (cohesion) of the material is inadequate or, if applicable, which has delaminated such that its bond to the substrate (adhesion) is inadequate or which for any other reason lacks fiber cohesion or adhesion qualities. Such damage or deterioration may be illustrated by the separation of ACM into layers; separation of ACM from the substrate; flaking, blistering, or crumbling of the ACM surface; water damage; significant or repeated water stains, scrapes, gouges, mars or other signs of physical injury on the ACM. Asbestos debris originating from the ACBM in question may also indicate damage.

*Damaged friable surfacing ACM* means friable surfacing ACM which has deteriorated or sustained physical injury such that the internal structure (cohesion) of the material is inadequate or which has delaminated such that its bond to the substrate (adhesion) is inadequate, or which, for any other reason, lacks fiber cohesion or adhesion qualities. Such damage or deterioration may be illustrated by the separation of ACM into layers; separation of ACM from the substrate; flaking, blistering, or crumbling of the ACM surface; water damage; significant or repeated water stains, scrapes, gouges, mars or other signs of physical injury



on the ACM. Asbestos debris originating from the ACBM in question may also indicate damage.

*Damaged or significantly damaged thermal system insulation ACM* means thermal system insulation ACM on pipes, boilers, tanks, ducts, and other thermal system insulation equipment where the insulation has lost its structural integrity, or its covering, in whole or in part, is crushed, water-stained, gouged, punctured, missing, or not intact such that it is not able to contain fibers. Damage may be further illustrated by occasional punctures, gouges or other signs of physical injury to ACM; occasional water damage on the protective coverings/jackets; or exposed ACM ends or joints. Asbestos debris originating from the ACBM in question may also indicate damage.

*Encapsulation* means the treatment of ACBM with a material that surrounds or embeds asbestos fibers in an adhesive matrix to prevent the release of fibers, as the encapsulant creates a membrane over the surface (bridging encapsulant) or penetrates the material and binds its components together (penetrating encapsulant).

*Enclosure* means an airtight, impermeable, permanent barrier around ACBM to prevent the release of asbestos fibers into the air.

*Fiber release episode* means any uncontrolled or unintentional disturbance of ACBM resulting in visible emission.

*Friable* when referring to material in a school building means that the material, when dry, may be crumbled, pulverized, or reduced to powder by hand pressure, and includes previously nonfriable material after such previously nonfriable material becomes damaged to the extent that when dry it may be crumbled, pulverized, or reduced to powder by hand pressure.

*Functional space* means a room, group of rooms, or homogeneous area (including crawl spaces or the space between a dropped ceiling and the floor or roof deck above), such as classroom(s), a cafeteria, gymnasium, hallway(s), designated by a person accredited to prepare management plans, design abatement projects, or conduct response actions.

*High-efficiency particulate air (HEPA)* refers to a filtering system capable of trapping and retaining at least 99.97 percent of all monodispersed particles 0.3  $\mu\text{m}$  in diameter or larger.

*Homogeneous area* means an area of surfacing material, thermal system insulation material, or miscellaneous material that is uniform in color and texture.

*Local education agency* means:

(1) Any local educational agency as defined in section 198 of the Elementary and Secondary Education Act of 1965 (20 U.S.C. 3381).

(2) The owner of any nonpublic, non-profit elementary, or secondary school building.

(3) The governing authority of any school operated under the defense dependent's education system provided for under the Defense Dependents' Education Act of 1978 (20 U.S.C. 921, et seq.).

*Miscellaneous ACM* means miscellaneous material that is ACM in a school building.

*Miscellaneous material* means interior building material on structural components, structural members or fixtures, such as floor and ceiling tiles, and does not include surfacing material or thermal system insulation.

*Nonfriable* means material in a school building which when dry may not be crumbled, pulverized, or reduced to powder by hand pressure.

*Operations and maintenance program* means a program of work practices to maintain friable ACBM in good condition, ensure clean up of asbestos fibers previously released, and prevent further release by minimizing and controlling friable ACBM disturbance or damage.

*Potential damage* means circumstances in which:

(1) Friable ACBM is in an area regularly used by building occupants, including maintenance personnel, in the course of their normal activities.

(2) There are indications that there is a reasonable likelihood that the material or its covering will become damaged, deteriorated, or delaminated due to factors such as changes in building use, changes in operations and maintenance practices, changes in occupancy, or recurrent damage.

## Environmental Protection Agency

## § 763.84

*Potential significant damage* means circumstances in which:

(1) Friable ACBM is in an area regularly used by building occupants, including maintenance personnel, in the course of their normal activities.

(2) There are indications that there is a reasonable likelihood that the material or its covering will become significantly damaged, deteriorated, or delaminated due to factors such as changes in building use, changes in operations and maintenance practices, changes in occupancy, or recurrent damage.

(3) The material is subject to major or continuing disturbance, due to factors including, but not limited to, accessibility or, under certain circumstances, vibration or air erosion.

*Preventive measures* means actions taken to reduce disturbance of ACBM or otherwise eliminate the reasonable likelihood of the material's becoming damaged or significantly damaged.

*Removal* means the taking out or the stripping of substantially all ACBM from a damaged area, a functional space, or a homogeneous area in a school building.

*Repair* means returning damaged ACBM to an undamaged condition or to an intact state so as to prevent fiber release.

*Response action* means a method, including removal, encapsulation, enclosure, repair, operations and maintenance, that protects human health and the environment from friable ACBM.

*Routine maintenance area* means an area, such as a boiler room or mechanical room, that is not normally frequented by students and in which maintenance employees or contract workers regularly conduct maintenance activities.

*School* means any elementary or secondary school as defined in section 198 of the Elementary and Secondary Education Act of 1965 (20 U.S.C. 2854).

*School building* means:

(1) Any structure suitable for use as a classroom, including a school facility such as a laboratory, library, school eating facility, or facility used for the preparation of food.

(2) Any gymnasium or other facility which is specially designed for athletic

or recreational activities for an academic course in physical education.

(3) Any other facility used for the instruction or housing of students or for the administration of educational or research programs.

(4) Any maintenance, storage, or utility facility, including any hallway, essential to the operation of any facility described in this definition of "school building" under paragraphs (1), (2), or (3).

(5) Any portico or covered exterior hallway or walkway.

(6) Any exterior portion of a mechanical system used to condition interior space.

*Significantly damaged friable miscellaneous ACM* means damaged friable miscellaneous ACM where the damage is extensive and severe.

*Significantly damaged friable surfacing ACM* means damaged friable surfacing ACM in a functional space where the damage is extensive and severe.

*State* means a State, the District of Columbia, the Commonwealth of Puerto Rico, Guam, American Samoa, the Northern Marianas, the Trust Territory of the Pacific Islands, and the Virgin Islands.

*Surfacing ACM* means surfacing material that is ACM.

*Surfacing material* means material in a school building that is sprayed-on, troweled-on, or otherwise applied to surfaces, such as acoustical plaster on ceilings and fireproofing materials on structural members, or other materials on surfaces for acoustical, fireproofing, or other purposes.

*Thermal system insulation* means material in a school building applied to pipes, fittings, boilers, breeching, tanks, ducts, or other interior structural components to prevent heat loss or gain, or water condensation, or for other purposes.

*Thermal system insulation ACM* means thermal system insulation that is ACM.

*Vibration* means the periodic motion of friable ACBM which may result in the release of asbestos fibers.

### § 763.84 General local education agency responsibilities.

Each local education agency shall:

(a) Ensure that the activities of any persons who perform inspections, re-inspections, and periodic surveillance, develop and update management plans, and develop and implement response actions, including operations and maintenance, are carried out in accordance with subpart E of this part.

(b) Ensure that all custodial and maintenance employees are properly trained as required by this subpart E and other applicable Federal and/or State regulations (e.g., the Occupational Safety and Health Administration asbestos standard for construction, the EPA worker protection rule, or applicable State regulations).

(c) Ensure that workers and building occupants, or their legal guardians, are informed at least once each school year about inspections, response actions, and post-response action activities, including periodic reinspection and surveillance activities that are planned or in progress.

(d) Ensure that short-term workers (e.g., telephone repair workers, utility workers, or exterminators) who may come in contact with asbestos in a school are provided information regarding the locations of ACBM and suspected ACBM assumed to be ACM.

(e) Ensure that warning labels are posted in accordance with § 763.95.

(f) Ensure that management plans are available for inspection and notification of such availability has been provided as specified in the management plan under § 763.93(g).

(g)(1) Designate a person to ensure that requirements under this section are properly implemented.

(2) Ensure that the designated person receives adequate training to perform duties assigned under this section. Such training shall provide, as necessary, basic knowledge of:

(i) Health effects of asbestos.

(ii) Detection, identification, and assessment of ACM.

(iii) Options for controlling ACBM.

(iv) Asbestos management programs.

(v) Relevant Federal and State regulations concerning asbestos, including those in this subpart E and those of the Occupational Safety and Health Administration, U.S. Department of Labor, the U.S. Department of Trans-

portation and the U.S. Environmental Protection Agency.

(h) Consider whether any conflict of interest may arise from the interrelationship among accredited personnel and whether that should influence the selection of accredited personnel to perform activities under this subpart.

#### § 763.85 Inspection and reinspections.

(a) *Inspection.* (1) Except as provided in paragraph (a)(2) of this section, before October 12, 1988, local education agencies shall inspect each school building that they lease, own, or otherwise use as a school building to identify all locations of friable and nonfriable ACBM.

(2) Any building leased or acquired on or after October 12, 1988, that is to be used as a school building shall be inspected as described under paragraphs (a) (3) and (4) of this section prior to use as a school building. In the event that emergency use of an uninspected building as a school building is necessitated, such buildings shall be inspected within 30 days after commencement of such use.

(3) Each inspection shall be made by an accredited inspector.

(4) For each area of a school building, except as excluded under § 763.99, each person performing an inspection shall:

(i) Visually inspect the area to identify the locations of all suspected ACBM.

(ii) Touch all suspected ACBM to determine whether they are friable.

(iii) Identify all homogeneous areas of friable suspected ACBM and all homogeneous areas of nonfriable suspected ACBM.

(iv) Assume that some or all of the homogeneous areas are ACM, and, for each homogeneous area that is not assumed to be ACM, collect and submit for analysis bulk samples under §§ 763.86 and 763.87.

(v) Assess, under § 763.88, friable material in areas where samples are collected, friable material in areas that are assumed to be ACBM, and friable ACBM identified during a previous inspection.

(vi) Record the following and submit to the person designated under § 763.84 a copy of such record for inclusion in

## Environmental Protection Agency

## § 763.86

the management plan within 30 days of the inspection:

(A) An inspection report with the date of the inspection signed by each accredited person making the inspection, State of accreditation, and if applicable, his or her accreditation number.

(B) An inventory of the locations of the homogeneous areas where samples are collected, exact location where each bulk sample is collected, dates that samples are collected, homogeneous areas where friable suspected ACBM is assumed to be ACM, and homogeneous areas where nonfriable suspected ACBM is assumed to be ACM.

(C) A description of the manner used to determine sampling locations, the name and signature of each accredited inspector who collected the samples, State of accreditation, and, if applicable, his or her accreditation number.

(D) A list of whether the homogeneous areas identified under paragraph (a)(4)(vi)(B) of this section, are surfacing material, thermal system insulation, or miscellaneous material.

(E) Assessments made of friable material, the name and signature of each accredited inspector making the assessment, State of accreditation, and if applicable, his or her accreditation number.

(b) *Reinspection.* (1) At least once every 3 years after a management plan is in effect, each local education agency shall conduct a reinspection of all friable and nonfriable known or assumed ACBM in each school building that they lease, own, or otherwise use as a school building.

(2) Each inspection shall be made by an accredited inspector.

(3) For each area of a school building, each person performing a reinspection shall:

(i) Visually reinspect, and reassess, under § 763.88, the condition of all friable known or assumed ACBM.

(ii) Visually inspect material that was previously considered nonfriable ACBM and touch the material to determine whether it has become friable since the last inspection or reinspection.

(iii) Identify any homogeneous areas with material that has become friable

since the last inspection or reinspection.

(iv) For each homogeneous area of newly friable material that is already assumed to be ACBM, bulk samples may be collected and submitted for analysis in accordance with §§ 763.86 and 763.87.

(v) Assess, under § 763.88, the condition of the newly friable material in areas where samples are collected, and newly friable materials in areas that are assumed to be ACBM.

(vi) Reassess, under § 763.88, the condition of friable known or assumed ACBM previously identified.

(vii) Record the following and submit to the person designated under § 763.84 a copy of such record for inclusion in the management plan within 30 days of the reinspection:

(A) The date of the reinspection, the name and signature of the person making the reinspection, State of accreditation, and if applicable, his or her accreditation number, and any changes in the condition of known or assumed ACBM.

(B) The exact locations where samples are collected during the reinspection, a description of the manner used to determine sampling locations, the name and signature of each accredited inspector who collected the samples, State of accreditation, and, if applicable, his or her accreditation number.

(C) Any assessments or reassessments made of friable material, the name and signature of the accredited inspector making the assessments, State of accreditation, and if applicable, his or her accreditation number.

(c) *General.* Thermal system insulation that has retained its structural integrity and that has an undamaged protective jacket or wrap that prevents fiber release shall be treated as nonfriable and therefore is subject only to periodic surveillance and preventive measures as necessary.

### § 763.86 Sampling.

(a) *Surfacing material.* An accredited inspector shall collect, in a statistically random manner that is representative of the homogeneous area, bulk samples from each homogeneous area of friable surfacing material that

## § 763.87

is not assumed to be ACM, and shall collect the samples as follows:

(1) At least three bulk samples shall be collected from each homogeneous area that is 1,000 ft<sup>2</sup> or less, except as provided in § 763.87(c)(2).

(2) At least five bulk samples shall be collected from each homogeneous area that is greater than 1,000 ft<sup>2</sup> but less than or equal to 5,000 ft<sup>2</sup>, except as provided in § 763.87(c)(2).

(3) At least seven bulk samples shall be collected from each homogeneous area that is greater than 5,000 ft<sup>2</sup>, except as provided in § 763.87(c)(2).

(b) *Thermal system insulation.* (1) Except as provided in paragraphs (b) (2) through (4) of this section and § 763.87(c), an accredited inspector shall collect, in a randomly distributed manner, at least three bulk samples from each homogeneous area of thermal system insulation that is not assumed to be ACM.

(2) Collect at least one bulk sample from each homogeneous area of patched thermal system insulation that is not assumed to be ACM if the patched section is less than 6 linear or square feet.

(3) In a manner sufficient to determine whether the material is ACM or not ACM, collect bulk samples from each insulated mechanical system that is not assumed to be ACM where cement or plaster is used on fittings such as tees, elbows, or valves, except as provided under § 763.87(c)(2).

(4) Bulk samples are not required to be collected from any homogeneous area where the accredited inspector has determined that the thermal system insulation is fiberglass, foam glass, rubber, or other non-ACBM.

(c) *Miscellaneous material.* In a manner sufficient to determine whether material is ACM or not ACM, an accredited inspector shall collect bulk samples from each homogeneous area of friable miscellaneous material that is not assumed to be ACM.

(d) *Nonfriable suspected ACBM.* If any homogeneous area of nonfriable suspected ACBM is not assumed to be ACM, then an accredited inspector shall collect, in a manner sufficient to determine whether the material is ACM or not ACM, bulk samples from the homogeneous area of nonfriable

## 40 CFR Ch. I (7–1–10 Edition)

suspected ACBM that is not assumed to be ACM.

### § 763.87 Analysis.

(a) Local education agencies shall have bulk samples, collected under § 763.86 and submitted for analysis, analyzed for asbestos using laboratories accredited by the National Bureau of Standards (NBS). Local education agencies shall use laboratories which have received interim accreditation for polarized light microscopy (PLM) analysis under the EPA Interim Asbestos Bulk Sample Analysis Quality Assurance Program until the NBS PLM laboratory accreditation program for PLM is operational.

(b) Bulk samples shall not be composited for analysis and shall be analyzed for asbestos content by PLM, using the “Interim Method for the Determination of Asbestos in Bulk Insulation Samples” found at appendix E to subpart E of this part.

(c)(1) A homogeneous area is considered not to contain ACM only if the results of all samples required to be collected from the area show asbestos in amounts of 1 percent or less.

(2) A homogeneous area shall be determined to contain ACM based on a finding that the results of at least one sample collected from that area shows that asbestos is present in an amount greater than 1 percent.

(d) The name and address of each laboratory performing an analysis, the date of analysis, and the name and signature of the person performing the analysis shall be submitted to the person designated under § 763.84 for inclusion into the management plan within 30 days of the analysis.

[52 FR 41846, Oct. 30, 1987, as amended at 60 FR 31922, June 19, 1995]

### § 763.88 Assessment.

(a)(1) For each inspection and reinspection conducted under § 763.85 (a) and (c) and previous inspections specified under § 763.99, the local education agency shall have an accredited inspector provide a written assessment of all friable known or assumed ACBM in the school building.

(2) Each accredited inspector providing a written assessment shall sign and date the assessment, provide his or

## Environmental Protection Agency

## § 763.90

her State of accreditation, and if applicable, accreditation number, and submit a copy of the assessment to the person designated under §763.84 for inclusion in the management plan within 30 days of the assessment.

(b) The inspector shall classify and give reasons in the written assessment for classifying the ACBM and suspected ACBM assumed to be ACM in the school building into one of the following categories:

- (1) Damaged or significantly damaged thermal system insulation ACM.
- (2) Damaged friable surfacing ACM.
- (3) Significantly damaged friable surfacing ACM.
- (4) Damaged or significantly damaged friable miscellaneous ACM.
- (5) ACBM with potential for damage.
- (6) ACBM with potential for significant damage.
- (7) Any remaining friable ACBM or friable suspected ACBM.

(c) Assessment may include the following considerations:

- (1) Location and the amount of the material, both in total quantity and as a percentage of the functional space.
- (2) Condition of the material, specifying:
  - (i) Type of damage or significant damage (e.g., flaking, blistering, water damage, or other signs of physical damage).
  - (ii) Severity of damage (e.g., major flaking, severely torn jackets, as opposed to occasional flaking, minor tears to jackets).
  - (iii) Extent or spread of damage over large areas or large percentages of the homogeneous area.
- (3) Whether the material is accessible.
- (4) The material's potential for disturbance.
- (5) Known or suspected causes of damage or significant damage (e.g., air erosion, vandalism, vibration, water).
- (6) Preventive measures which might eliminate the reasonable likelihood of undamaged ACM from becoming significantly damaged.
- (d) The local education agency shall select a person accredited to develop management plans to review the results of each inspection, reinspection, and assessment for the school building and to conduct any other necessary ac-

tivities in order to recommend in writing to the local education agency appropriate response actions. The accredited person shall sign and date the recommendation, provide his or her State of accreditation, and, if applicable, provide his or her accreditation number, and submit a copy of the recommendation to the person designated under §763.84 for inclusion in the management plan.

### § 763.90 Response actions.

(a) The local education agency shall select and implement in a timely manner the appropriate response actions in this section consistent with the assessment conducted in §763.88. The response actions selected shall be sufficient to protect human health and the environment. The local education agency may then select, from the response actions which protect human health and the environment, that action which is the least burdensome method. Nothing in this section shall be construed to prohibit removal of ACBM from a school building at any time, should removal be the preferred response action of the local education agency.

(b) If damaged or significantly damaged thermal system insulation ACM is present in a building, the local education agency shall:

- (1) At least repair the damaged area.
- (2) Remove the damaged material if it is not feasible, due to technological factors, to repair the damage.
- (3) Maintain all thermal system insulation ACM and its covering in an intact state and undamaged condition.

(c)(1) If damaged friable surfacing ACM or damaged friable miscellaneous ACM is present in a building, the local education agency shall select from among the following response actions: encapsulation, enclosure, removal, or repair of the damaged material.

(2) In selecting the response action from among those which meet the definitional standards in §763.83, the local education agency shall determine which of these response actions protects human health and the environment. For purposes of determining which of these response actions are the least burdensome, the local education

**§ 763.90**

**40 CFR Ch. I (7-1-10 Edition)**

agency may then consider local circumstances, including occupancy and use patterns within the school building, and its economic concerns, including short- and long-term costs.

(d) If significantly damaged friable surfacing ACM or significantly damaged friable miscellaneous ACM is present in a building the local education agency shall:

(1) Immediately isolate the functional space and restrict access, unless isolation is not necessary to protect human health and the environment.

(2) Remove the material in the functional space or, depending upon whether enclosure or encapsulation would be sufficient to protect human health and the environment, enclose or encapsulate.

(e) If any friable surfacing ACM, thermal system insulation ACM, or friable miscellaneous ACM that has potential for damage is present in a building, the local education agency shall at least implement an operations and maintenance (O&M) program, as described under § 763.91.

(f) If any friable surfacing ACM, thermal system insulation ACM, or friable miscellaneous ACM that has potential for significant damage is present in a building, the local education agency shall:

(1) Implement an O&M program, as described under § 763.91.

(2) Institute preventive measures appropriate to eliminate the reasonable likelihood that the ACM or its covering will become significantly damaged, deteriorated, or delaminated.

(3) Remove the material as soon as possible if appropriate preventive measures cannot be effectively implemented, or unless other response actions are determined to protect human health and the environment. Immediately isolate the area and restrict access if necessary to avoid an imminent and substantial endangerment to human health or the environment.

(g) Response actions including removal, encapsulation, enclosure, or repair, other than small-scale, short-duration repairs, shall be designed and conducted by persons accredited to design and conduct response actions.

(h) The requirements of this subpart E in no way supersede the worker pro-

tection and work practice requirements under 29 CFR 1926.58 (Occupational Safety and Health Administration (OSHA) asbestos worker protection standards for construction), 40 CFR part 763, subpart G (EPA asbestos worker protection standards for public employees), and 40 CFR part 61, subpart M (National Emission Standards for Hazardous Air Pollutants—Asbestos).

(i) Completion of response actions. (1) At the conclusion of any action to remove, encapsulate, or enclose ACBM, a person designated by the local education agency shall visually inspect each functional space where such action was conducted to determine whether the action has been properly completed.

(2)(i) A person designated by the local education agency shall collect air samples using aggressive sampling as described in appendix A to this subpart E to monitor air for clearance after each removal, encapsulation, and enclosure project involving ACBM, except for projects that are of small-scale, short-duration.

(ii) Local education agencies shall have air samples collected under this section analyzed for asbestos using laboratories accredited by the National Bureau of Standards to conduct such analysis using transmission electron microscopy (TEM) or, under circumstances permitted in this section, laboratories enrolled in the American Industrial Hygiene Association Proficiency Analytical Testing Program for phase contrast microscopy (PCM).

(iii) Until the National Bureau of Standards TEM laboratory accreditation program is operational, local educational agencies shall use laboratories that use the protocol described in appendix A to subpart E of this part.

(3) Except as provided in paragraphs (i)(4), and (i)(5), of this section, an action to remove, encapsulate, or enclose ACBM shall be considered complete when the average concentration of asbestos of five air samples collected within the affected functional space and analyzed by the TEM method in appendix A of this subpart E, is not statistically significantly different, as determined by the Z-test calculation found in appendix A of this subpart E,

## Environmental Protection Agency

## § 763.91

from the average asbestos concentration of five air samples collected at the same time outside the affected functional space and analyzed in the same manner, and the average asbestos concentration of the three field blanks described in appendix A of this subpart E is below the filter background level, as defined in appendix A of this subpart E, of 70 structures per square millimeter (70 s/mm<sup>2</sup>).

(4) An action may also be considered complete if the volume of air drawn for each of the five samples collected within the affected functional space is equal to or greater than 1,199 L of air for a 25 mm filter or equal to or greater than 2,799 L of air for a 37 mm filter, and the average concentration of asbestos as analyzed by the TEM method in appendix A of this subpart E, for the five air samples does not exceed the filter background level, as defined in appendix A, of 70 structures per square millimeter (70 s/mm<sup>2</sup>). If the average concentration of asbestos of the five air samples within the affected functional space exceeds 70 s/mm<sup>2</sup>, or if the volume of air in each of the samples is less than 1,199 L of air for a 25 mm filter or less than 2,799 L of air for a 37 mm filter, the action shall be considered complete only when the requirements of paragraph (i)(3) or (i)(5), of this section are met.

(5) At any time, a local education agency may analyze air monitoring samples collected for clearance purposes by phase contrast microscopy (PCM) to confirm completion of removal, encapsulation, or enclosure of ACBM that is greater than small-scale, short-duration and less than or equal to 160 square feet or 260 linear feet. The action shall be considered complete when the results of samples collected in the affected functional space and analyzed by phase contrast microscopy using the National Institute for Occupational Safety and Health (NIOSH) Method 7400 entitled "Fibers" published in the NIOSH Manual of Analytical Methods, 3rd Edition, Second Supplement, August 1987, show that the concentration of fibers for each of the five samples is less than or equal to a limit of quantitation for PCM (0.01 fibers per cubic centimeter (0.01 f/cm<sup>3</sup>) of air). The method is available for public

inspection at the Non-Confidential Information Center (NCIC) (7407), Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, Room B-607 NEM, 401 M St., SW., Washington, DC 20460, between the hours of 12 p.m. and 4 p.m. weekdays excluding legal holidays or at the National Archives and Records Administration (NARA). For information on the availability of this material at NARA, call 202-741-6030, or go to: [http://www.archives.gov/federal\\_register/code\\_of\\_federal\\_regulations/ibr\\_locations.html](http://www.archives.gov/federal_register/code_of_federal_regulations/ibr_locations.html). This incorporation by reference was approved by the Director of the Federal Register in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. The method is incorporated as it exists on the effective date of this rule, and a notice of any change to the method will be published in the FEDERAL REGISTER.

(6) To determine the amount of ACBM affected under paragraph (i)(5) of this section, the local education agency shall add the total square or linear footage of ACBM within the containment barriers used to isolate the functional space for the action to remove, encapsulate, or enclose the ACBM. Contiguous portions of material subject to such action conducted concurrently or at approximately the same time within the same school building shall not be separated to qualify under paragraph (i)(5), of this section.

[52 FR 41846, Oct. 30, 1987, as amended at 53 FR 12525, Apr. 15, 1988; 60 FR 31922, June 19, 1995; 60 FR 34465, July 3, 1995; 69 FR 18803, Apr. 9, 2004]

### § 763.91 Operations and maintenance.

(a) *Applicability.* The local education agency shall implement an operations, maintenance, and repair (O&M) program under this section whenever any friable ACBM is present or assumed to be present in a building that it leases, owns, or otherwise uses as a school building. Any material identified as nonfriable ACBM or nonfriable assumed ACBM must be treated as friable ACBM for purposes of this section when the material is about to become friable as a result of activities performed in the school building.



(b) *Worker protection.* Local education agencies must comply with either the OSHA Asbestos Construction Standard at 29 CFR 1926.1101, or the Asbestos Worker Protection Rule at 40 CFR 763.120, whichever is applicable.

(c) *Cleaning*—(1) *Initial cleaning.* Unless the building has been cleaned using equivalent methods within the previous 6 months, all areas of a school building where friable ACBM, damaged or significantly damaged thermal system insulation ACM, or friable suspected ACBM assumed to be ACM are present shall be cleaned at least once after the completion of the inspection required by §763.85(a) and before the initiation of any response action, other than O&M activities or repair, according to the following procedures:

(i) HEPA-vacuum or steam-clean all carpets.

(ii) HEPA-vacuum or wet-clean all other floors and all other horizontal surfaces.

(iii) Dispose of all debris, filters, mopheads, and cloths in sealed, leak-tight containers.

(2) *Additional cleaning.* The accredited management planner shall make a written recommendation to the local education agency whether additional cleaning is needed, and if so, the methods and frequency of such cleaning.

(d) *Operations and maintenance activities.* The local education agency shall ensure that the procedures described below to protect building occupants shall be followed for any operations and maintenance activities disturbing friable ACBM:

(1) Restrict entry into the area by persons other than those necessary to perform the maintenance project, either by physically isolating the area or by scheduling.

(2) Post signs to prevent entry by unauthorized persons.

(3) Shut off or temporarily modify the air-handling system and restrict other sources of air movement.

(4) Use work practices or other controls, such as, wet methods, protective clothing, HEPA-vacuums, mini-enclosures, glove bags, as necessary to inhibit the spread of any released fibers.

(5) Clean all fixtures or other components in the immediate work area.

(6) Place the asbestos debris and other cleaning materials in a sealed, leak-tight container.

(e) *Maintenance activities other than small-scale, short-duration.* The response action for any maintenance activities disturbing friable ACBM, other than small-scale, short-duration maintenance activities, shall be designed by persons accredited to design response actions and conducted by persons accredited to conduct response actions.

(f) *Fiber release episodes*—(1) *Minor fiber release episode.* The local education agency shall ensure that the procedures described below are followed in the event of a minor fiber release episode (i.e., the falling or dislodging of 3 square or linear feet or less of friable ACBM): 5

(i) Thoroughly saturate the debris using wet methods.

(ii) Clean the area, as described in paragraph (e) of this section.

(iii) Place the asbestos debris in a sealed, leak-tight container.

(iv) Repair the area of damaged ACM with materials such as asbestos-free spackling, plaster, cement, or insulation, or seal with latex paint or an encapsulant, or immediately have the appropriate response action implemented as required by §763.90.

(2) *Major fiber release episode.* The local education agency shall ensure that the procedures described below are followed in the event of a major fiber release episode (i.e., the falling or dislodging of more than 3 square or linear feet of friable ACBM):

(i) Restrict entry into the area and post signs to prevent entry into the area by persons other than those necessary to perform the response action.

(ii) Shut off or temporarily modify the air-handling system to prevent the distribution of fibers to other areas in the building.

(iii) The response action for any major fiber release episode must be designed by persons accredited to design response actions and conducted by persons accredited to conduct response actions.

[52 FR 41846, Oct. 30, 1987, as amended at 65 FR 69216, Nov. 15, 2000]

## Environmental Protection Agency

## § 763.93

### § 763.92 Training and periodic surveillance.

(a) *Training.* (1) The local education agency shall ensure, prior to the implementation of the O&M provisions of the management plan, that all members of its maintenance and custodial staff (custodians, electricians, heating/air conditioning engineers, plumbers, etc.) who may work in a building that contains ACBM receive awareness training of at least 2 hours, whether or not they are required to work with ACBM. New custodial and maintenance employees shall be trained within 60 days after commencement of employment. Training shall include, but not be limited to:

(i) Information regarding asbestos and its various uses and forms.

(ii) Information on the health effects associated with asbestos exposure.

(iii) Locations of ACBM identified throughout each school building in which they work.

(iv) Recognition of damage, deterioration, and delamination of ACBM.

(v) Name and telephone number of the person designated to carry out general local education agency responsibilities under § 763.84 and the availability and location of the management plan.

(2) The local education agency shall ensure that all members of its maintenance and custodial staff who conduct any activities that will result in the disturbance of ACBM shall receive training described in paragraph (a)(1) of this section and 14 hours of additional training. Additional training shall include, but not be limited to:

(i) Descriptions of the proper methods of handling ACBM.

(ii) Information on the use of respiratory protection as contained in the EPA/NIOSH *Guide to Respiratory Protection for the Asbestos Abatement Industry*, September 1986 (EPA 560/OPPTS-86-001), available from the Director, Environmental Assistance Division (7408), Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, Room E-543B, 1200 Pennsylvania Ave., NW., Washington, DC 20460, Telephone: (202) 554-1404, TDD: (202) 544-0551 and other personal protection measures.

(iii) The provisions of this section and § 763.91, Appendices A, C, and D of this subpart E of this part, EPA regulations contained in 40 CFR part 763, subpart G, and in 40 CFR part 61, subpart M, and OSHA regulations contained in 29 CFR 1926.58.

(iv) Hands-on training in the use of respiratory protection, other personal protection measures, and good work practices.

(3) Local education agency maintenance and custodial staff who have attended EPA-approved asbestos training or received equivalent training for O&M and periodic surveillance activities involving asbestos shall be considered trained for the purposes of this section.

(b) *Periodic surveillance.* (1) At least once every 6 months after a management plan is in effect, each local education agency shall conduct periodic surveillance in each building that it leases, owns, or otherwise uses as a school building that contains ACBM or is assumed to contain ACBM.

(2) Each person performing periodic surveillance shall:

(i) Visually inspect all areas that are identified in the management plan as ACBM or assumed ACBM.

(ii) Record the date of the surveillance, his or her name, and any changes in the condition of the materials.

(iii) Submit to the person designated to carry out general local education agency responsibilities under § 763.84 a copy of such record for inclusion in the management plan.

[52 FR 41846, Oct. 30, 1987, as amended at 60 FR 34465, July 3, 1995; 65 FR 69216, Nov. 15, 2000]

### § 763.93 Management plans.

(a)(1) On or before October 12, 1988, each local education agency shall develop an asbestos management plan for each school, including all buildings that they lease, own, or otherwise use as school buildings, and submit the plan to an Agency designated by the Governor of the State in which the local education agency is located. The plan may be submitted in stages that cover a portion of the school buildings under the authority of the local education agency.

(2) If a building to be used as part of a school is leased or otherwise acquired after October 12, 1988, the local education agency shall include the new building in the management plan for the school prior to its use as a school building. The revised portions of the management plan shall be submitted to the Agency designated by the Governor.

(3) If a local education agency begins to use a building as a school after October 12, 1988, the local education agency shall submit a management plan for the school to the Agency designated by the Governor prior to its use as a school.

(b) On or before October 17, 1987, the Governor of each State shall notify local education agencies in the State regarding where to submit their management plans. States may establish administrative procedures for reviewing management plans. If the Governor does not disapprove a management plan within 90 days after receipt of the plan, the local education agency shall implement the plan.

(c) Each local education agency must begin implementation of its management plan on or before July 9, 1989, and complete implementation in a timely fashion.

(d) Each local education agency shall maintain and update its management plan to keep it current with ongoing operations and maintenance, periodic surveillance, inspection, reinspection, and response action activities. All provisions required to be included in the management plan under this section shall be retained as part of the management plan, as well as any information that has been revised to bring the plan up-to-date.

(e) The management plan shall be developed by an accredited management planner and shall include:

(1) A list of the name and address of each school building and whether the school building contains friable ACM, nonfriable ACM, and friable and nonfriable suspected ACM assumed to be ACM.

(2) For each inspection conducted before the December 14, 1987:

(i) The date of the inspection.

(ii) A blueprint, diagram, or written description of each school building that

identifies clearly each location and approximate square or linear footage of any homogeneous or sampling area where material was sampled for ACM, and, if possible, the exact locations where bulk samples were collected, and the dates of collection.

(iii) A copy of the analyses of any bulk samples, dates of analyses, and a copy of any other laboratory reports pertaining to the analyses.

(iv) A description of any response actions or preventive measures taken to reduce asbestos exposure, including if possible, the names and addresses of all contractors involved, start and completion dates of the work, and results of any air samples analyzed during and upon completion of the work.

(v) A description of assessments, required to be made under § 763.88, of material that was identified before December 14, 1987, as friable ACM or friable suspected ACM assumed to be ACM, and the name and signature, State of accreditation, and if applicable, accreditation number of each accredited person making the assessments.

(3) For each inspection and reinspection conducted under § 763.85:

(i) The date of the inspection or reinspection and the name and signature, State of accreditation and, if applicable, the accreditation number of each accredited inspector performing the inspection or reinspection.

(ii) A blueprint, diagram, or written description of each school building that identifies clearly each location and approximate square or linear footage of homogeneous areas where material was sampled for ACM, the exact location where each bulk sample was collected, date of collection, homogeneous areas where friable suspected ACM is assumed to be ACM, and where nonfriable suspected ACM is assumed to be ACM.

(iii) A description of the manner used to determine sampling locations, and the name and signature of each accredited inspector collecting samples, the State of accreditation, and if applicable, his or her accreditation number.

(iv) A copy of the analyses of any bulk samples collected and analyzed, the name and address of any laboratory

## Environmental Protection Agency

## § 763.93

that analyzed bulk samples, a statement that the laboratory meets the applicable requirements of § 763.87(a) the date of analysis, and the name and signature of the person performing the analysis.

(v) A description of assessments, required to be made under § 763.88, of all ACBM and suspected ACBM assumed to be ACM, and the name, signature, State of accreditation, and if applicable, accreditation number of each accredited person making the assessments.

(4) The name, address, and telephone number of the person designated under § 763.84 to ensure that the duties of the local education agency are carried out, and the course name, and dates and hours of training taken by that person to carry out the duties.

(5) The recommendations made to the local education agency regarding response actions, under § 763.88(d), the name, signature, State of accreditation of each person making the recommendations, and if applicable, his or her accreditation number.

(6) A detailed description of preventive measures and response actions to be taken, including methods to be used, for any friable ACBM, the locations where such measures and action will be taken, reasons for selecting the response action or preventive measure, and a schedule for beginning and completing each preventive measure and response action.

(7) With respect to the person or persons who inspected for ACBM and who will design or carry out response actions, except for operations and maintenance, with respect to the ACBM, one of the following statements:

(i) If the State has adopted a contractor accreditation program under section 206(b) of Title II of the Act, a statement that the person(s) is accredited under such plan.

(ii) A statement that the local education agency used (or will use) persons who have been accredited by another State which has adopted a contractor accreditation plan under section 206(b) of Title II of the Act or is accredited by an EPA-approved course under section 206(c) of Title II of the Act.

(8) A detailed description in the form of a blueprint, diagram, or in writing of

any ACBM or suspected ACBM assumed to be ACM which remains in the school once response actions are undertaken pursuant to § 763.90. This description shall be updated as response actions are completed.

(9) A plan for reinspection under § 763.85, a plan for operations and maintenance activities under § 763.91, and a plan for periodic surveillance under § 763.92, a description of the recommendation made by the management planner regarding additional cleaning under § 763.91(c)(2) as part of an operations and maintenance program, and the response of the local education agency to that recommendation.

(10) A description of steps taken to inform workers and building occupants, or their legal guardians, about inspections, reinspections, response actions, and post-response action activities, including periodic reinspection and surveillance activities that are planned or in progress.

(11) An evaluation of the resources needed to complete response actions successfully and carry out reinspection, operations and maintenance activities, periodic surveillance and training.

(12) With respect to each consultant who contributed to the management plan, the name of the consultant and one of the following statements:

(i) If the State has adopted a contractor accreditation plan under section 206(b) of Title II of the Act, a statement that the consultant is accredited under such plan.

(ii) A statement that the contractor is accredited by another State which has adopted a contractor accreditation plan under section 206(b) of Title II of the Act, or is accredited by an EPA-approved course developed under section 206(c) of Title II of the Act.

(f) A local education agency may require each management plan to contain a statement signed by an accredited management plan developer that such person has prepared or assisted in the preparation of such plan or has reviewed such plan, and that such plan is in compliance with this subpart E. Such statement may not be signed by a person who, in addition to preparing or assisting in preparing the management

**§ 763.94**

**40 CFR Ch. I (7-1-10 Edition)**

plan, also implements (or will implement) the management plan.

(g)(1) Upon submission of a management plan to the Governor for review, a local education agency shall keep a copy of the plan in its administrative office. The management plans shall be available, without cost or restriction, for inspection by representatives of EPA and the State, the public, including teachers, other school personnel and their representatives, and parents. The local education agency may charge a reasonable cost to make copies of management plans.

(2) Each local education agency shall maintain in its administrative office a complete, updated copy of a management plan for each school under its administrative control or direction. The management plans shall be available, during normal business hours, without cost or restriction, for inspection by representatives of EPA and the State, the public, including teachers, other school personnel and their representatives, and parents. The local education agency may charge a reasonable cost to make copies of management plans.

(3) Each school shall maintain in its administrative office a complete, updated copy of the management plan for that school. Management plans shall be available for inspection, without cost or restriction, to workers before work begins in any area of a school building. The school shall make management plans available for inspection to representatives of EPA and the State, the public, including parents, teachers, and other school personnel and their representatives within 5 working days after receiving a request for inspection. The school may charge a reasonable cost to make copies of the management plan.

(4) Upon submission of its management plan to the Governor and at least once each school year, the local education agency shall notify in writing parent, teacher, and employee organizations of the availability of management plans and shall include in the management plan a description of the steps taken to notify such organizations, and a dated copy of the notification. In the absence of any such organizations for parents, teachers, or employees, the local education agency

shall provide written notice to that relevant group of the availability of management plans and shall include in the management plan a description of the steps taken to notify such groups, and a dated copy of the notification.

(h) Records required under § 763.94 shall be made by local education agencies and maintained as part of the management plan.

(i) Each management plan must contain a true and correct statement, signed by the individual designated by the local education agency under § 763.84, which certifies that the general, local education agency responsibilities, as stipulated by § 763.84, have been met or will be met.

**§ 763.94 Recordkeeping.**

(a) Records required under this section shall be maintained in a centralized location in the administrative office of both the school and the local education agency as part of the management plan. For each homogeneous area where all ACBM has been removed, the local education agency shall ensure that such records are retained for 3 years after the next reinspection required under § 763.85(b)(1), or for an equivalent period.

(b) For each preventive measure and response action taken for friable and nonfriable ACBM and friable and nonfriable suspected ACBM assumed to be ACM, the local education agency shall provide:

(1) A detailed written description of the measure or action, including methods used, the location where the measure or action was taken, reasons for selecting the measure or action, start and completion dates of the work, names and addresses of all contractors involved, and if applicable, their State of accreditation, and accreditation numbers, and if ACBM is removed, the name and location of storage or disposal site of the ACM.

(2) The name and signature of any person collecting any air sample required to be collected at the completion of certain response actions specified by § 763.90(i), the locations where samples were collected, date of collection, the name and address of the laboratory analyzing the samples, the date of analysis, the results of the

## Environmental Protection Agency

## § 763.97

analysis, the method of analysis, the name and signature of the person performing the analysis, and a statement that the laboratory meets the applicable requirements of § 763.90(i)(2)(ii).

(c) For each person required to be trained under § 763.92(a) (1) and (2), the local education agency shall provide the person's name and job title, the date that training was completed by that person, the location of the training, and the number of hours completed in such training.

(d) For each time that periodic surveillance under § 763.92(b) is performed, the local education agency shall record the name of each person performing the surveillance, the date of the surveillance, and any changes in the conditions of the materials.

(e) For each time that cleaning under § 763.91(c) is performed, the local education agency shall record the name of each person performing the cleaning, the date of such cleaning, the locations cleaned, and the methods used to perform such cleaning.

(f) For each time that operations and maintenance activities under § 763.91(d) are performed, the local education agency shall record the name of each person performing the activity, the start and completion dates of the activity, the locations where such activity occurred, a description of the activity including preventive measures used, and if ACBM is removed, the name and location of storage or disposal site of the ACM.

(g) For each time that major asbestos activity under § 763.91(e) is performed, the local education agency shall provide the name and signature, State of accreditation, and if applicable, the accreditation number of each person performing the activity, the start and completion dates of the activity, the locations where such activity occurred, a description of the activity including preventive measures used, and if ACBM is removed, the name and location of storage or disposal site of the ACM.

(h) For each fiber release episode under § 763.91(f), the local education agency shall provide the date and location of the episode, the method of repair, preventive measures or response action taken, the name of each person performing the work, and if ACBM is

removed, the name and location of storage or disposal site of the ACM.

(Approved by the Office of Management and Budget under control number 2070-0091)

### § 763.95 Warning labels.

(a) The local education agency shall attach a warning label immediately adjacent to any friable and nonfriable ACBM and suspected ACBM assumed to be ACM located in routine maintenance areas (such as boiler rooms) at each school building. This shall include:

(1) Friable ACBM that was responded to by a means other than removal.

(2) ACBM for which no response action was carried out.

(b) All labels shall be prominently displayed in readily visible locations and shall remain posted until the ACBM that is labeled is removed.

(c) The warning label shall read, in print which is readily visible because of large size or bright color, as follows: CAUTION: ASBESTOS. HAZARDOUS. DO NOT DISTURB WITHOUT PROPER TRAINING AND EQUIPMENT.

### § 763.97 Compliance and enforcement.

(a) *Compliance with Title II of the Act.*  
(1) Section 207(a) of Title II of the Act (15 U.S.C. 2647) makes it unlawful for any local education agency to:

(i) Fail to conduct inspections pursuant to section 203(b) of Title II of the Act, including failure to follow procedures and failure to use accredited personnel and laboratories.

(ii) Knowingly submit false information to the Governor regarding any inspection pursuant to regulations under section 203(i) of Title II of the Act.

(iii) Fail to develop a management plan pursuant to regulations under section 203(i) of Title II of the Act.

(2) Section 207(a) of Title II of the Act (15 U.S.C. 2647) also provides that any local education agency which violates any provision of section 207 shall be liable for a civil penalty of not more than \$5,000 for each day during which the violation continues. For the purposes of this subpart, a "violation" means a failure to comply with respect to a single school building.

(b) *Compliance with Title I of the Act.*  
(1) Section 15(1)(D) of Title I of the Act (15 U.S.C. 2614) makes it unlawful for

any person to fail or refuse to comply with any requirement of Title II or any rule promulgated or order issued under Title II. Therefore, any person who violates any requirement of this subpart is in violation of section 15 of Title I of the Act.

(2) Section 15(3) of Title I of the Act (15 U.S.C. 2614) makes it unlawful for any person to fail or refuse to establish or maintain records, submit reports, notices or other information, or permit access to or copying of records, as required by this Act or a rule thereunder.

(3) Section 15(4) (15 U.S.C. 2614) of Title I of the Act makes it unlawful for any person to fail or refuse to permit entry or inspection as required by section 11 of Title I of the Act.

(4) Section 16(a) of Title I of the Act (15 U.S.C. 2615) provides that any person who violates any provision of section 15 of Title I of the Act shall be liable to the United States for a civil penalty in an amount not to exceed \$25,000 for each such violation. Each day such a violation continues shall, for purposes of this paragraph, constitute a separate violation of section 15. A local education agency is not liable for any civil penalty under Title I of the Act for failing or refusing to comply with any rule promulgated or order issued under Title II of the Act.

(c) *Criminal penalties.* If any violation committed by any person (including a local education agency) is knowing or willful, criminal penalties may be assessed under section 16(b) of Title I of the Act.

(d) *Injunctive relief.* The Agency may obtain injunctive relief under section 208(b) of Title II of the Act to respond to a hazard which poses an imminent and substantial endangerment to human health or the environment or section 17 (15 U.S.C. 2616) of Title I of the Act to restrain any violation of section 15 of Title I of the Act or to compel the taking of any action required by or under Title I of the Act.

(e) *Citizen complaints.* Any citizen who wishes to file a complaint pursuant to section 207(d) of Title II of the Act should direct the complaint to the Governor of the State or the EPA Asbestos Ombudsman, 1200 Pennsylvania Ave., NW., Washington, DC 20460. The citizen complaint should be in writing and

identified as a citizen complaint pursuant to section 207(d) of Title II of TSCA. The EPA Asbestos Ombudsman or the Governor shall investigate and respond to the complaint within a reasonable period of time if the allegations provide a reasonable basis to believe that a violation of the Act has occurred.

(f) *Inspections.* EPA may conduct inspections and review management plans under section 11 of Title I of the Act (15 U.S.C. 2610) to ensure compliance.

#### § 763.98 Waiver; delegation to State.

(a) *General.* (1) Upon request from a state Governor and after notice and comment and an opportunity for a public hearing in accordance with paragraphs (b) and (c) of this section, EPA may waive some or all of the requirements of this subpart E if the state has established and is implementing or intends to implement a program of asbestos inspection and management that contains requirements that are at least as stringent as the requirements of this subpart. In addition, if the state chooses to receive electronic documents, the state program must include, at a minimum, the requirements of 40 CFR part 3—(Electronic reporting).

(2) A waiver from any requirement of this subpart E shall apply only to the specific provision for which a waiver has been granted under this section. All requirements of this subpart E shall apply until a waiver is granted under this section.

(b) *Request.* Each request by a Governor to waive any requirement of this subpart E shall be sent with three complete copies of the request to the Regional Administrator for the EPA Region in which the State is located and shall include:

(1) A copy of the State provisions or proposed provisions relating to its program of asbestos inspection and management in schools for which the request is made.

(2)(i) The name of the State agency that is or will be responsible for administering and enforcing the requirements for which a waiver is requested, the names and job titles of responsible officials in that agency, and phone

## Environmental Protection Agency

## § 763.98

numbers where the officials can be contacted.

(ii) In the event that more than one agency is or will be responsible for administering and enforcing the requirements for which a waiver is requested, a description of the functions to be performed by each agency, how the program will be coordinated by the lead agency to ensure consistency and effective administration in the asbestos inspection and management program within the State, the names and job titles of responsible officials in the agencies, and phone numbers where the officials can be contacted. The lead agency will serve as the central contact point for the EPA.

(3) Detailed reasons, supporting papers, and the rationale for concluding that the state's asbestos inspection and management program provisions for which the request is made are at least as stringent as the requirements of Subpart E of this part, and that, if the state chooses to receive electronic documents, the state program includes, at a minimum, the requirements of 40 CFR part 3—(Electronic reporting).

(4) A discussion of any special situations, problems, and needs pertaining to the waiver request accompanied by an explanation of how the State intends to handle them.

(5) A statement of the resources that the State intends to devote to the administration and enforcement of the provisions relating to the waiver request.

(6) Copies of any specific or enabling State laws (enacted and pending enactment) and regulations (promulgated and pending promulgation) relating to the request, including provisions for assessing criminal and/or civil penalties.

(7) Assurance from the Governor, the Attorney General, or the legal counsel of the lead agency that the lead agency or other cooperating agencies have the legal authority necessary to carry out the requirements relating to the request.

(c) *General notice—hearing.* (1) Within 30 days after receipt of a request for a waiver, EPA will determine the completeness of the request. If EPA does not request further information within

the 30-day period, the request will be deemed complete.

(2) Within 30 days after EPA determines that a request is complete, EPA will issue for publication in the FEDERAL REGISTER a notice that announces receipt of the request, describes the information submitted under paragraph (b) of this section, and solicits written comment from interested members of the public. Comments must be submitted within 60 days.

(3) If, during the comment period, EPA receives a written objection to a Governor's request and a request for a public hearing detailing specific objections to the granting of a waiver, EPA will schedule a public hearing to be held in the affected State after the close of the comment period and will announce the public hearing date in the FEDERAL REGISTER before the date of the hearing. Each comment shall include the name and address of the person submitting the comment.

(d) *Criteria.* EPA may waive some or all of the requirements of subpart E of this part if:

(1) The State's lead agency and other cooperating agencies have the legal authority necessary to carry out the provisions of asbestos inspection and management in schools relating to the waiver request.

(2) The State's program of asbestos inspection and management in schools relating to the waiver request and implementation of the program are or will be at least as stringent as the requirements of this subpart E.

(3) The state has an enforcement mechanism to allow it to implement the program described in the waiver request and any electronic reporting requirements are at least as stringent as 40 CFR part 3—(Electronic reporting).

(4) The lead agency and any cooperating agencies have or will have qualified personnel to carry out the provisions relating to the waiver request.

(5) The State will devote adequate resources to the administration and enforcement of the asbestos inspection and management provisions relating to the waiver request.

(6) When specified by EPA, the State gives satisfactory assurances that necessary steps, including specific actions it proposes to take and a time schedule



for their accomplishment, will be taken within a reasonable time to conform with applicable criteria under paragraphs (d) (2) through (4) of this section.

(e) *Decision.* EPA will issue for publication in the FEDERAL REGISTER a notice announcing its decision to grant or deny, in whole or in part, a Governor's request for a waiver from some or all of the requirements of this subpart E within 30 days after the close of the comment period or within 30 days following a public hearing, whichever is applicable. The notice will include the Agency's reasons and rationale for granting or denying the Governor's request. The 30-day period may be extended if mutually agreed upon by EPA and the State.

(f) *Modifications.* When any substantial change is made in the administration or enforcement of a State program for which a waiver was granted under this section, a responsible official in the lead agency shall submit such changes to EPA.

(g) *Reports.* The lead agency in each State that has been granted a waiver by EPA from any requirement of subpart E of this part shall submit a report to the Regional Administrator for the Region in which the State is located at least once every 12 months to include the following information:

(1) A summary of the State's implementation and enforcement activities during the last reporting period relating to provisions waived under this section, including enforcement actions taken.

(2) Any changes in the administration or enforcement of the State program implemented during the last reporting period.

(3) Other reports as may be required by EPA to carry out effective oversight of any requirement of this subpart E that was waived under this section.

(h) *Oversight.* EPA may periodically evaluate the adequacy of a State's implementation and enforcement of and resources devoted to carrying out requirements relating to the waiver. This evaluation may include, but is not limited to, site visits to local education agencies without prior notice to the State.

(i) *Informal conference.* (1) EPA may request that an informal conference be held between appropriate State and EPA officials when EPA has reason to believe that a State has failed to:

(i) Substantially comply with the terms of any provision that was waived under this section.

(ii) Meet the criteria under paragraph (d) of this section, including the failure to carry out enforcement activities or act on violations of the State program.

(2) EPA will:

(i) Specify to the State those aspects of the State's program believed to be inadequate.

(ii) Specify to the State the facts that underlie the belief of inadequacy.

(3) If EPA finds, on the basis of information submitted by the State at the conference, that deficiencies did not exist or were corrected by the State, no further action is required.

(4) Where EPA finds that deficiencies in the State program exist, a plan to correct the deficiencies shall be negotiated between the State and EPA. The plan shall detail the deficiencies found in the State program, specify the steps the State has taken or will take to remedy the deficiencies, and establish a schedule for each remedial action to be initiated.

(j) *Rescission.* (1) If the State fails to meet with EPA or fails to correct deficiencies raised at the informal conference, EPA will deliver to the Governor of the State and a responsible official in the lead agency a written notice of its intent to rescind, in whole or part, the waiver.

(2) EPA will issue for publication in the FEDERAL REGISTER a notice that announces the rescission of the waiver, describes those aspects of the State's program determined to be inadequate, and specifies the facts that underlie the findings of inadequacy.

[52 FR 41846, Oct. 30, 1987, as amended at 70 FR 59889, Oct. 13, 2005]

**§ 763.99 Exclusions.**

(a) A local education agency shall not be required to perform an inspection under § 763.85(a) in any sampling area as defined in 40 CFR 763.103 or homogeneous area of a school building where:

## Environmental Protection Agency

## § 763.99

(1) An accredited inspector has determined that, based on sampling records, friable ACBM was identified in that homogeneous or sampling area during an inspection conducted before December 14, 1987. The inspector shall sign and date a statement to that effect with his or her State of accreditation and if applicable, accreditation number and, within 30 days after such determination, submit a copy of the statement to the person designated under § 763.84 for inclusion in the management plan. However, an accredited inspector shall assess the friable ACBM under § 763.88.

(2) An accredited inspector has determined that, based on sampling records, nonfriable ACBM was identified in that homogeneous or sampling area during an inspection conducted before December 14, 1987. The inspector shall sign and date a statement to that effect with his or her State of accreditation and if applicable, accreditation number and, within 30 days after such determination, submit a copy of the statement to the person designated under § 763.84 for inclusion in the management plan. However, an accredited inspector shall identify whether material that was nonfriable has become friable since that previous inspection and shall assess the newly-friable ACBM under § 763.88.

(3) Based on sampling records and inspection records, an accredited inspector has determined that no ACBM is present in the homogeneous or sampling area and the records show that the area was sampled, before December 14, 1987 in substantial compliance with § 763.85(a), which for purposes of this section means in a random manner and with a sufficient number of samples to reasonably ensure that the area is not ACBM.

(i) The accredited inspector shall sign and date a statement, with his or her State of accreditation and if applicable, accreditation number that the homogeneous or sampling area determined not to be ACBM was sampled in substantial compliance with § 763.85(a).

(ii) Within 30 days after the inspector's determination, the local education agency shall submit a copy of the inspector's statement to the EPA Regional Office and shall include the

statement in the management plan for that school.

(4) The lead agency responsible for asbestos inspection in a State that has been granted a waiver from § 763.85(a) has determined that, based on sampling records and inspection records, no ACBM is present in the homogeneous or sampling area and the records show that the area was sampled before December 14, 1987, in substantial compliance with § 763.85(a). Such determination shall be included in the management plan for that school.

(5) An accredited inspector has determined that, based on records of an inspection conducted before December 14, 1987, suspected ACBM identified in that homogeneous or sampling area is assumed to be ACM. The inspector shall sign and date a statement to that effect, with his or her State of accreditation and if applicable, accreditation number and, within 30 days of such determination, submit a copy of the statement to the person designated under § 763.84 for inclusion in the management plan. However, an accredited inspector shall identify whether material that was nonfriable suspected ACBM assumed to be ACM has become friable since the previous inspection and shall assess the newly friable material and previously identified friable suspected ACBM assumed to be ACM under § 763.88.

(6) Based on inspection records and contractor and clearance records, an accredited inspector has determined that no ACBM is present in the homogeneous or sampling area where asbestos removal operations have been conducted before December 14, 1987, and shall sign and date a statement to that effect and include his or her State of accreditation and, if applicable, accreditation number. The local education agency shall submit a copy of the statement to the EPA Regional Office and shall include the statement in the management plan for that school.

(7) An architect or project engineer responsible for the construction of a new school building built after October 12, 1988, or an accredited inspector signs a statement that no ACBM was specified as a building material in any

construction document for the building, or, to the best of his or her knowledge, no ACBM was used as a building material in the building. The local education agency shall submit a copy of the signed statement of the architect, project engineer, or accredited inspector to the EPA Regional Office and shall include the statement in the management plan for that school.

(b) The exclusion, under paragraphs (a) (1) through (4) of this section, from conducting the inspection under §763.85(a) shall apply only to homogeneous or sampling areas of a school building that were inspected and sampled before October 17, 1987. The local education agency shall conduct an inspection under §763.85(a) of all areas inspected before October 17, 1987, that were not sampled or were not assumed to be ACM.

(c) If ACBM is subsequently found in a homogeneous or sampling area of a local education agency that had been identified as receiving an exclusion by an accredited inspector under paragraphs (a) (3), (4), (5) of this section, or an architect, project engineer or accredited inspector under paragraph (a)(7) of this section, the local education agency shall have 180 days following the date of identification of ACBM to comply with this subpart E.

APPENDIX A TO SUBPART E OF PART 763—INTERIM TRANSMISSION ELECTRON MICROSCOPY ANALYTICAL METHODS—MANDATORY AND NON-MANDATORY—AND MANDATORY SECTION TO DETERMINE COMPLETION OF RESPONSE ACTIONS

*I. Introduction*

The following appendix contains three units. The first unit is the mandatory transmission electron microscopy (TEM) method which all laboratories must follow; it is the minimum requirement for analysis of air samples for asbestos by TEM. The mandatory method contains the essential elements of the TEM method. The second unit contains the complete non-mandatory method. The non-mandatory method supplements the mandatory method by including additional steps to improve the analysis. EPA recommends that the non-mandatory method be employed for analyzing air filters; however, the laboratory may choose to employ the mandatory method. The non-mandatory method contains the same minimum require-

ments as are outlined in the mandatory method. Hence, laboratories may choose either of the two methods for analyzing air samples by TEM.

The final unit of this Appendix A to subpart E defines the steps which must be taken to determine completion of response actions. This unit is mandatory.

*II. Mandatory Transmission Electron Microscopy Method*

A. Definitions of Terms

1. *Analytical sensitivity*—Airborne asbestos concentration represented by each fiber counted under the electron microscope. It is determined by the air volume collected and the proportion of the filter examined. This method requires that the analytical sensitivity be no greater than 0.005 structures/cm<sup>3</sup>.

2. *Asbestiform*—A specific type of mineral fibrosity in which the fibers and fibrils possess high tensile strength and flexibility.

3. *Aspect ratio*—A ratio of the length to the width of a particle. Minimum aspect ratio as defined by this method is equal to or greater than 5:1.

4. *Bundle*—A structure composed of three or more fibers in a parallel arrangement with each fiber closer than one fiber diameter.

5. *Clean area*—A controlled environment which is maintained and monitored to assure a low probability of asbestos contamination to materials in that space. Clean areas used in this method have HEPA filtered air under positive pressure and are capable of sustained operation with an open laboratory blank which on subsequent analysis has an average of less than 18 structures/mm<sup>2</sup> in an area of 0.057 mm<sup>2</sup> (nominally 10 200-mesh grid openings) and a maximum of 53 structures/mm<sup>2</sup> for any single preparation for that same area.

6. *Cluster*—A structure with fibers in a random arrangement such that all fibers are intermixed and no single fiber is isolated from the group. Groupings must have more than two intersections.

7. *ED*—Electron diffraction.

8. *EDXA*—Energy dispersive X-ray analysis.

9. *Fiber*—A structure greater than or equal to 0.5 μm in length with an aspect ratio (length to width) of 5:1 or greater and having substantially parallel sides.

10. *Grid*—An open structure for mounting on the sample to aid in its examination in the TEM. The term is used here to denote a 200-mesh copper lattice approximately 3 mm in diameter.

11. *Intersection*—Nonparallel touching or crossing of fibers, with the projection having an aspect ratio of 5:1 or greater.

12. *Laboratory sample coordinator*—That person responsible for the conduct of sample

## Environmental Protection Agency

## Pt. 763, Subpt. E, App. A

handling and the certification of the testing procedures.

13. *Filter background level*—The concentration of structures per square millimeter of filter that is considered indistinguishable from the concentration measured on a blank (filters through which no air has been drawn). For this method the filter background level is defined as 70 structures/mm<sup>2</sup>.

14. *Matrix*—Fiber or fibers with one end free and the other end embedded in or hidden by a particulate. The exposed fiber must meet the fiber definition.

15. *NSD*—No structure detected.

16. *Operator*—A person responsible for the TEM instrumental analysis of the sample.

17. *PCM*—Phase contrast microscopy.

18. *SAED*—Selected area electron diffraction.

19. *SEM*—Scanning electron microscope.

20. *STEM*—Scanning transmission electron microscope.

21. *Structure*—a microscopic bundle, cluster, fiber, or matrix which may contain asbestos.

22. *S/cm<sup>3</sup>*—Structures per cubic centimeter.

23. *S/mm<sup>2</sup>*—Structures per square millimeter.

24. *TEM*—Transmission electron microscope.

### B. Sampling

1. The sampling agency must have written quality control procedures and documents which verify compliance.

2. Sampling operations must be performed by qualified individuals completely independent of the abatement contractor to avoid possible conflict of interest (References 1, 2, 3, and 5 of Unit II.J.).


3. Sampling for airborne asbestos following an abatement action must use commercially available cassettes.

4. Prescreen the loaded cassette collection filters to assure that they do not contain concentrations of asbestos which may interfere with the analysis of the sample. A filter blank average of less than 18 s/mm<sup>2</sup> in an area of 0.057 mm<sup>2</sup> (nominally 10 200-mesh grid openings) and a single preparation with a maximum of 53 s/mm<sup>2</sup> for that same area is acceptable for this method.

5. Use sample collection filters which are either polycarbonate having a pore size less than or equal to 0.4 μm or mixed cellulose ester having a pore size less than or equal to 0.45 μm.

6. Place these filters in series with a 5.0 μm backup filter (to serve as a diffuser) and a support pad. See the following Figure 1:

FIGURE I--SAMPLING CASSETTE CONFIGURATION



7. Reloading of used cassettes is not permitted.

8. Orient the cassette downward at approximately 45 degrees from the horizontal.

9. Maintain a log of all pertinent sampling information.

**Environmental Protection Agency**

**Pt. 763, Subpt. E, App. A**

10. Calibrate sampling pumps and their flow indicators over the range of their intended use with a recognized standard. Assemble the sampling system with a representative filter (not the filter which will be used in sampling) before and after the sampling operation.

11. Record all calibration information.

12. Ensure that the mechanical vibrations from the pump will be minimized to prevent transferral of vibration to the cassette.

13. Ensure that a continuous smooth flow of negative pressure is delivered by the pump by damping out any pump action fluctuations if necessary.

14. The final plastic barrier around the abatement area remains in place for the sampling period.

15. After the area has passed a thorough visual inspection, use aggressive sampling conditions to dislodge any remaining dust. (See suggested protocol in Unit III.B.7.d.)

16. Select an appropriate flow rate equal to or greater than 1 liter per minute (L/min) or less than 10 L/min for 25 mm cassettes. Larger filters may be operated at proportionally higher flow rates.

17. A minimum of 13 samples are to be collected for each testing site consisting of the following:

a. A minimum of five samples per abatement area.

b. A minimum of five samples per ambient area positioned at locations representative of the air entering the abatement site.

c. Two field blanks are to be taken by removing the cap for not more than 30 seconds and replacing it at the time of sampling before sampling is initiated at the following places:

i. Near the entrance to each abatement area.

ii. At one of the ambient sites. (DO NOT leave the field blanks open during the sampling period.)

d. A sealed blank is to be carried with each sample set. This representative cassette is not to be opened in the field.

18. Perform a leak check of the sampling system at each indoor and outdoor sampling site by activating the pump with the closed sampling cassette in line. Any flow indicates a leak which must be eliminated before initiating the sampling operation.

19. The following Table I specifies volume ranges to be used:

TABLE 1--NUMBER OF 200 MESH EM GRID OPENINGS (0.0057 MM<sup>2</sup>) THAT NEED TO BE ANALYZED TO MAINTAIN SENSITIVITY OF 0.005 STRUCTURES/CC BASED ON VOLUME AND EFFECTIVE FILTER AREA

| Effective Filter Area<br>385 sq mm |                    | Effective Filter Area<br>855 sq mm |                    |
|------------------------------------|--------------------|------------------------------------|--------------------|
| Volume (liters)                    | # of grid openings | Volume (liters)                    | # of grid openings |
| 560                                | 24                 | 1,250                              | 24                 |
| 600                                | 23                 | 1,300                              | 23                 |
| 700                                | 19                 | 1,400                              | 21                 |
| 800                                | 17                 | 1,600                              | 19                 |
| 900                                | 15                 | 1,800                              | 17                 |
| 1,000                              | 14                 | 2,000                              | 15                 |
| 1,100                              | 12                 | 2,200                              | 14                 |
| 1,200                              | 11                 | 2,400                              | 13                 |
| 1,300                              | 10                 | 2,600                              | 12                 |
| 1,400                              | 10                 | 2,800                              | 11                 |
| 1,500                              | 9                  | 3,000                              | 10                 |
| 1,600                              | 8                  | 3,200                              | 9                  |
| 1,700                              | 8                  | 3,400                              | 9                  |
| 1,800                              | 8                  | 3,600                              | 8                  |
| 1,900                              | 7                  | 3,800                              | 8                  |
| 2,000                              | 7                  | 4,000                              | 8                  |
| 2,100                              | 6                  | 4,200                              | 7                  |
| 2,200                              | 6                  | 4,400                              | 7                  |
| 2,300                              | 6                  | 4,600                              | 7                  |
| 2,400                              | 6                  | 4,800                              | 6                  |
| 2,500                              | 5                  | 5,000                              | 6                  |
| 2,600                              | 5                  | 5,200                              | 6                  |
| 2,700                              | 5                  | 5,400                              | 6                  |
| 2,800                              | 5                  | 5,600                              | 5                  |
| 2,900                              | 5                  | 5,800                              | 5                  |
| 3,000                              | 5                  | 6,000                              | 5                  |
| 3,100                              | 4                  | 6,200                              | 5                  |
| 3,200                              | 4                  | 6,400                              | 5                  |
| 3,300                              | 4                  | 6,600                              | 5                  |
| 3,400                              | 4                  | 6,800                              | 4                  |
| 3,500                              | 4                  | 7,000                              | 4                  |
| 3,600                              | 4                  | 7,200                              | 4                  |
| 3,700                              | 4                  | 7,400                              | 4                  |
| 3,800                              | 4                  | 7,600                              | 4                  |

Note minimum volumes required:  
 25 mm : 560 liters  
 37 mm : 1250 liters

Filter diameter of 25 mm = effective area of 385 sq mm  
 Filter diameter of 37 mm = effective area of 855 sq mm

- 20. Ensure that the sampler is turned up-right before interrupting the pump flow.
- 21. Check that all samples are clearly labeled and that all pertinent information has been enclosed before transfer of the samples to the laboratory.

- 22. Ensure that the samples are stored in a secure and representative location.
- 23. Do not change containers if portions of these filters are taken for other purposes.
- 24. A summary of Sample Data Quality Objectives is shown in the following Table II:

TABLE II--SUMMARY OF SAMPLING AGENCY DATA QUALITY OBJECTIVES

This table summarizes the data quality objectives from the performance of this method in terms of precision, accuracy, completeness, representativeness, and comparability. These objectives are assured by the periodic control checks and reference checks listed here and described in the text of the method.

| Unit Operation     | QC Check                          | Frequency                          | Conformance Expectation |
|--------------------|-----------------------------------|------------------------------------|-------------------------|
| Sampling materials | Sealed blank                      | 1 per I/O site                     | 95%                     |
| Sample procedures  | Field blanks                      | 2 per I/O site                     | 95%                     |
|                    | Pump calibration                  | Before and after each field series | 90%                     |
| Sample custody     | Review of chain-of-custody record | Each sample                        | 95% complete            |
| Sample shipment    | Review of sending report          | Each sample                        | 95% complete            |

#### C. Sample Shipment

Ship bulk samples to the analytical laboratory in a separate container from air samples.

#### D. Sample Receiving

1. Designate one individual as sample coordinator at the laboratory. While that individual will normally be available to receive samples, the coordinator may train and supervise others in receiving procedures for those times when he/she is not available.

2. Bulk samples and air samples delivered to the analytical laboratory in the same container shall be rejected.

#### E. Sample Preparation

1. All sample preparation and analysis shall be performed by a laboratory independent of the abatement contractor.

2. Wet-wipe the exterior of the cassettes to minimize contamination possibilities before taking them into the clean room facility.

3. Perform sample preparation in a well-equipped clean facility.

NOTE: The clean area is required to have the following minimum characteristics. The area or hood must be capable of maintaining a positive pressure with make-up air being HEPA-filtered. The cumulative analytical blank concentration must average less than 18 s/mm<sup>2</sup> in an area of 0.057 mm<sup>2</sup> (nominally 10 200-mesh grid openings) and a single preparation with a maximum of 53 s/mm<sup>2</sup> for that same area.

4. Preparation areas for air samples must not only be separated from preparation areas for bulk samples, but they must be prepared in separate rooms.

5. Direct preparation techniques are required. The object is to produce an intact film containing the particulates of the filter surface which is sufficiently clear for TEM analysis.

a. TEM Grid Opening Area measurement must be done as follows:

i. The filter portion being used for sample preparation must have the surface collapsed using an acetone vapor technique.

ii. Measure 20 grid openings on each of 20 random 200-mesh copper grids by placing a grid on a glass and examining it under the PCM. Use a calibrated graticule to measure the average field diameters. From the data, calculate the field area for an average grid opening.

iii. Measurements can also be made on the TEM at a properly calibrated low magnification or on an optical microscope at a magnification of approximately 400X by using an eyepiece fitted with a scale that has been calibrated against a stage micrometer. Optical microscopy utilizing manual or automated procedures may be used providing instrument calibration can be verified.

b. TEM specimen preparation from polycarbonate (PC) filters. Procedures as described in Unit III.G. or other equivalent methods may be used.

c. TEM specimen preparation from mixed cellulose ester (MCE) filters.

i. Filter portion being used for sample preparation must have the surface collapsed using an acetone vapor technique or the Burdette procedure (Ref. 7 of Unit II.J.)

ii. Plasma etching of the collapsed filter is required. The microscope slide to which the collapsed filter pieces are attached is placed in a plasma asher. Because plasma ashers vary greatly in their performance, both from unit to unit and between different positions in the asher chamber, it is difficult to specify the conditions that should be used. Insufficient etching will result in a failure to expose embedded filters, and too much etching may result in loss of particulate from the surface. As an interim measure, it is recommended that the time for ashing of a



known weight of a collapsed filter be established and that the etching rate be calculated in terms of micrometers per second. The actual etching time used for the particulate ash and operating conditions will then be set such that a 1-2  $\mu\text{m}$  (10 percent) layer of collapsed surface will be removed.

iii. Procedures as described in Unit III, or other equivalent methods may be used to prepare samples.

#### F. TEM Method

1. An 80-120 kV TEM capable of performing electron diffraction with a fluorescent screen inscribed with calibrated gradations is required. If the TEM is equipped with EDXA it must either have a STEM attachment or be capable of producing a spot less than 250 nm in diameter at crossover. The microscope shall be calibrated routinely for magnification and camera constant.

2. *Determination of Camera Constant and ED Pattern Analysis.* The camera length of the TEM in ED operating mode must be calibrated before ED patterns on unknown samples are observed. This can be achieved by using a carbon-coated grid on which a thin film of gold has been sputtered or evaporated. A thin film of gold is evaporated on the specimen TEM grid to obtain zone-axis ED patterns superimposed with a ring pattern from the polycrystalline gold film. In practice, it is desirable to optimize the thickness of the gold film so that only one or two sharp rings are obtained on the superimposed ED pattern. Thicker gold film would normally give multiple gold rings, but it will tend to mask weaker diffraction spots from the unknown fibrous particulate. Since the unknown d-spacings of most interest in asbestos analysis are those which lie closest to the transmitted beam, multiple gold rings are unnecessary on zone-axis ED patterns. An average camera constant using multiple gold rings can be determined. The camera constant is one-half the diameter of the rings times the interplanar spacing of the ring being measured.

3. *Magnification Calibration.* The magnification calibration must be done at the fluorescent screen. The TEM must be calibrated at the grid opening magnification (if used) and also at the magnification used for fiber counting. This is performed with a cross grating replica (e.g., one containing 2,160 lines/mm). Define a field of view on the fluorescent screen either by markings or physical boundaries. The field of view must be measurable or previously inscribed with a scale or concentric circles (all scales should

be metric). A logbook must be maintained, and the dates of calibration and the values obtained must be recorded. The frequency of calibration depends on the past history of the particular microscope. After any maintenance of the microscope that involved adjustment of the power supplied to the lenses or the high-voltage system or the mechanical disassembly of the electron optical column apart from filament exchange, the magnification must be recalibrated. Before the TEM calibration is performed, the analyst must ensure that the cross grating replica is placed at the same distance from the objective lens as the specimens are. For instruments that incorporate a eucentric tilting specimen stage, all specimens and the cross grating replica must be placed at the eucentric position.

4. While not required on every microscope in the laboratory, the laboratory must have either one microscope equipped with energy dispersive X-ray analysis or access to an equivalent system on a TEM in another laboratory.

5. Microscope settings: 80-120 kV, grid assessment 250-1,000X, then 15,000-20,000X screen magnification for analysis.

6. Approximately one-half (0.5) of the predetermined sample area to be analyzed shall be performed on one sample grid preparation and the remaining half on a second sample grid preparation.

7. Individual grid openings with greater than 5 percent openings (holes) or covered with greater than 25 percent particulate matter or obviously having nonuniform loading must not be analyzed.

8. Reject the grid if:

a. Less than 50 percent of the grid openings covered by the replica are intact.

b. The replica is doubled or folded.


c. The replica is too dark because of incomplete dissolution of the filter.

9. *Recording Rules.*

a. Any continuous grouping of particles in which an asbestos fiber with an aspect ratio greater than or equal to 5:1 and a length greater than or equal to 0.5  $\mu\text{m}$  is detected shall be recorded on the count sheet. These will be designated asbestos structures and will be classified as fibers, bundles, clusters, or matrices. Record as individual fibers any contiguous grouping having 0, 1, or 2 definable intersections. Groupings having more than 2 intersections are to be described as cluster or matrix. An intersection is a non-parallel touching or crossing of fibers, with the projection having an aspect ratio of 5:1 or greater. See the following Figure 2:

FIGURE 2--COUNTING GUIDELINES USED IN DETERMINING ASBESTOS STRUCTURES


Count as 1 fiber; 1 Structure; no intersections.



Count as 2 fibers if space between fibers is greater than width of 1 fiber diameter or number of intersections is equal to or less than 1.




Count as 3 structures if space between fibers is greater than width of 1 fiber diameter or if the number of intersections is equal to or less than 2.




Count bundles as 1 structure; 3 or more parallel fibrils less than 1 fiber diameter separation.



Count clusters as 1 structure; fibers having greater than or equal to 3 intersections.



Count matrix as 1 structure.



DO NOT COUNT AS STRUCTURES:



Fiber protrusion  
<5:1 Aspect Ratio



No fiber protrusion



Fiber protrusion  
<0.5 micrometer

— <0.5 micrometer in length  
— <5:1 Aspect Ratio

i. *Fiber*. A structure having a minimum length greater than or equal to 0.5  $\mu\text{m}$  and an aspect ratio (length to width) of 5:1 or greater and substantially parallel sides. Note the appearance of the end of the fiber, i.e., whether it is flat, rounded or dovetailed.

ii. *Bundle*. A structure composed of three or more fibers in a parallel arrangement with each fiber closer than one fiber diameter.

iii. *Cluster*. A structure with fibers in a random arrangement such that all fibers are intermixed and no single fiber is isolated

from the group. Groupings must have more than two intersections.

iv. *Matrix*. Fiber or fibers with one end free and the other end embedded in or hidden by a particulate. The exposed fiber must meet the fiber definition.

b. Separate categories will be maintained for fibers less than 5  $\mu\text{m}$  and for fibers equal to or greater than 5  $\mu\text{m}$  in length.

c. Record NSD when no structures are detected in the field.

d. Visual identification of electron diffraction (ED) patterns is required for each asbestos structure counted which would cause the

analysis to exceed the 70 s/mm<sup>2</sup> concentration. (Generally this means the first four fibers identified as asbestos must exhibit an identifiable diffraction pattern for chrysotile or amphibole.)

e. The micrograph number of the recorded diffraction patterns must be reported to the client and maintained in the laboratory's quality assurance records. In the event that examination of the pattern by a qualified individual indicates that the pattern has been misidentified visually, the client shall be contacted.

f. Energy Dispersive X-ray Analysis (EDXA) is required of all amphiboles which would cause the analysis results to exceed the 70 s/mm<sup>2</sup> concentration. (Generally speaking, the first 4 amphiboles would require EDXA.)

g. If the number of fibers in the non-asbestos class would cause the analysis to exceed the 70 s/mm<sup>2</sup> concentration, the fact that they are not asbestos must be confirmed by EDXA or measurement of a zone axis diffraction pattern.

h. Fibers classified as chrysotile must be identified by diffraction or X-ray analysis and recorded on a count sheet. X-ray analysis alone can be used only after 70 s/mm<sup>2</sup> have been exceeded for a particular sample.

i. Fibers classified as amphiboles must be identified by X-ray analysis and electron diffraction and recorded on the count sheet. (X-ray analysis alone can be used only after 70 s/mm<sup>2</sup> have been exceeded for a particular sample.)

j. If a diffraction pattern was recorded on film, record the micrograph number on the count sheet.

k. If an electron diffraction was attempted but no pattern was observed, record N on the count sheet.

l. If an EDXA spectrum was attempted but not observed, record N on the count sheet.

m. If an X-ray analysis spectrum is stored, record the file and disk number on the count sheet.

#### 10. Classification Rules.

a. *Fiber*. A structure having a minimum length greater than or equal to 0.5 μm and an aspect ratio (length to width) of 5:1 or greater and substantially parallel sides. Note the appearance of the end of the fiber, i.e., whether it is flat, rounded or dovetailed.

b. *Bundle*. A structure composed of three or more fibers in a parallel arrangement with each fiber closer than one fiber diameter.

c. *Cluster*. A structure with fibers in a random arrangement such that all fibers are intermixed and no single fiber is isolated from the group. Groupings must have more than two intersections.

d. *Matrix*. Fiber or fibers with one end free and the other end embedded in or hidden by a particulate. The exposed fiber must meet the fiber definition.

11. After finishing with a grid, remove it from the microscope, and replace it in the appropriate grid holder. Sample grids must be stored for a minimum of 1 year from the date of the analysis; the sample cassette must be retained for a minimum of 30 days by the laboratory or returned at the client's request.

#### G. Sample Analytical Sequence

1. Under the present sampling requirements a minimum of 13 samples is to be collected for the clearance testing of an abatement site. These include five abatement area samples, five ambient samples, two field blanks, and one sealed blank.

2. Carry out visual inspection of work site prior to air monitoring.

3. Collect a minimum of 5 air samples inside the work site and 5 samples outside the work site. The indoor and outdoor samples shall be taken during the same time period.

4. Remaining steps in the analytical sequence are contained in Unit IV of this Appendix.

#### H. Reporting

1. The following information must be reported to the client for each sample analyzed:

a. Concentration in structures per square millimeter and structures per cubic centimeter.

b. Analytical sensitivity used for the analysis.

c. Number of asbestos structures.

d. Area analyzed.

e. Volume of air sampled (which must be initially supplied to lab by client).

f. Copy of the count sheet must be included with the report.

g. Signature of laboratory official to indicate that the laboratory met specifications of the method.

h. Report form must contain official laboratory identification (e.g., letterhead).

i. Type of asbestos.

#### I. Quality Control/Quality Assurance Procedures (Data Quality Indicators)

Monitoring the environment for airborne asbestos requires the use of sensitive sampling and analysis procedures. Because the test is sensitive, it may be influenced by a variety of factors. These include the supplies used in the sampling operation, the performance of the sampling, the preparation of the grid from the filter and the actual examination of this grid in the microscope. Each of these unit operations must produce a product of defined quality if the analytical result is to be a reliable and meaningful test result. Accordingly, a series of control checks and reference standards are to be performed along with the sample analysis as indicators that the materials used are adequate and the

operations are within acceptable limits. In this way, the quality of the data is defined and the results are of known value. These checks and tests also provide timely and specific warning of any problems which might

develop within the sampling and analysis operations. A description of these quality control/quality assurance procedures is summarized in the following Table III:

TABLE III--SUMMARY OF LABORATORY DATA QUALITY OBJECTIVES

| Unit Operation                  | QC Check  | Frequency  | Conformance Expectation                 |
|---------------------------------|---|--|---|
| Sample receiving                | Review of receiving report  | Each sample  | 95% complete                            |
| Sample custody                  | Review of chain-of-custody record   | Each sample  | 95% complete                            |
| Sample preparation              | Supplies and reagents   | On receipt   | Meet specs. or reject                   |
|                                 | Grid opening size   | 20 openings/20 grids/lot of 1000 or 1 opening/sample | 100%                                    |
|                                 | Special clean area monitoring   | After cleaning or service                            | Meet specs or reclean                   |
|                                 | Laboratory blank  | 1 per prep series or 10%                             | Meet specs. or reanalyze series         |
|                                 | Plasma etch blank   | 1 per 20 samples                                     | 75%                                     |
| Sample analysis                 | Multiple preps (3 per sample)   | Each sample  | One with cover of 15 complete grid sqs. |
|                                 | System check  | Each day   | Each day                                |
|                                 | Alignment check   | Each day   | Each day                                |
|                                 | Magnification calibration with low and high standards   | Each month or after service                          | 95%                                     |
|                                 | ED calibration by gold standard   | Weekly   | 95%                                     |
|                                 | EDS calibration by copper line  | Daily  | 95%                                     |
| Performance check               | Laboratory blank (measure of cleanliness)   | Prep 1 per series or 10% read 1 per 25 samples       | Meet specs or reanalyze series          |
|                                 | Replicate counting (measure of precision)   | 1 per 100 samples                                    | 1.5 x Poisson Std. Dev.                 |
|                                 | Duplicate analysis (measure of reproducibility)   | 1 per 100 samples                                    | 2 x Poisson Std. Dev.                   |
|                                 | Known samples of typical materials (working standards)  | Training and for comparison with unknowns            | 100%                                    |
|                                 | Analysis of NBS SRM 1876 and/or RM 8410 (measure of accuracy and comparability)                             | 1 per analyst per year                               | 1.5 x Poisson Std. Dev.                 |
|                                 | Data entry review (data validation and measure of completeness)   | Each sample  | 95%                                     |
|                                 | Record and verify ID electron diffraction pattern of structure  | 1 per 5 samples                                      | 80% accuracy                            |
| Calculations and data reduction | Hand calculation of automated data reduction procedure or independent recalculation of hand-calculated data | 1 per 100 samples                                    | 85%                                     |

1. When the samples arrive at the laboratory, check the samples and documentation for completeness and requirements before initiating the analysis.

2. Check all laboratory reagents and supplies for acceptable asbestos background levels.

3. Conduct all sample preparation in a clean room environment monitored by laboratory blanks. Testing with blanks must also be done after cleaning or servicing the room.

4. Prepare multiple grids of each sample.

5. Provide laboratory blanks with each sample batch. Maintain a cumulative average of these results. If there are more than 53 fibers/mm<sup>2</sup> per 10 200-mesh grid openings, the system must be checked for possible sources of contamination.

6. Perform a system check on the transmission electron microscope daily.

7. Make periodic performance checks of magnification, electron diffraction and energy dispersive X-ray systems as set forth in Table III under Unit II.I.

8. Ensure qualified operator performance by evaluation of replicate analysis and standard sample comparisons as set forth in Table III under Unit II.I.

9. Validate all data entries.

10. Recalculate a percentage of all computations and automatic data reduction steps as specified in Table III under Unit II.I.

11. Record an electron diffraction pattern of one asbestos structure from every five samples that contain asbestos. Verify the identification of the pattern by measurement or comparison of the pattern with patterns collected from standards under the same conditions. The records must also demonstrate that the identification of the pattern has been verified by a qualified individual and that the operator who made the identification is maintaining at least an 80 percent correct visual identification based on his measured patterns.

12. Appropriate logs or records must be maintained by the analytical laboratory verifying that it is in compliance with the mandatory quality assurance procedures.

#### J. References

For additional background information on this method, the following references should be consulted.

1. "Guidance for Controlling Asbestos-Containing Materials in Buildings," EPA 560/5-85-024, June 1985.

2. "Measuring Airborne Asbestos Following an Abatement Action," USEPA, Office of Pollution Prevention and Toxics, EPA 600/4-85-049, 1985.

3. Small, John and E. Steel. Asbestos Standards: Materials and Analytical Methods. N.B.S. Special Publication 619, 1982.

4. Campbell, W.J., R.L. Blake, L.L. Brown, E.E. Cather, and J.J. Sjoberg. Selected Silicate Minerals and Their Asbestiform Varieties. Information Circular 8751, U.S. Bureau of Mines, 1977.

5. Quality Assurance Handbook for Air Pollution Measurement System. Ambient Air Methods, EPA 600/4-77-027a, USEPA, Office of Research and Development, 1977.

6. Method 2A: Direct Measurement of Gas Volume through Pipes and Small Ducts. 40 CFR Part 60 Appendix A.

7. Burdette, G.J., Health & Safety Exec. Research & Lab. Services Div., London,

"Proposed Analytical Method for Determination of Asbestos in Air."

8. Chatfield, E.J., Chatfield Tech. Cons., Ltd., Clark, T., PEI Assoc., "Standard Operating Procedure for Determination of Airborne Asbestos Fibers by Transmission Electron Microscopy Using Polycarbonate Membrane Filters," WERL SOP 87-1, March 5, 1987.

9. NIOSH Method 7402 for Asbestos Fibers, 12-11-86 Draft.

10. Yamate, G., Agarwall, S.C., Gibbons, R.D., IIT Research Institute, "Methodology for the Measurement of Airborne Asbestos by Electron Microscopy," Draft report, USEPA Contract 68-02-3266, July 1984.

11. "Guidance to the Preparation of Quality Assurance Project Plans," USEPA, Office of Pollution Prevention and Toxics, 1984.

#### III. Nonmandatory Transmission Electron Microscopy Method

##### A. Definitions of Terms

1. *Analytical sensitivity*—Airborne asbestos concentration represented by each fiber counted under the electron microscope. It is determined by the air volume collected and the proportion of the filter examined. This method requires that the analytical sensitivity be no greater than 0.005 s/cm<sup>3</sup>.

2. *Asbestiform*—A specific type of mineral fibrosity in which the fibers and fibrils possess high tensile strength and flexibility.

3. *Aspect ratio*—A ratio of the length to the width of a particle. Minimum aspect ratio as defined by this method is equal to or greater than 5:1.

4. *Bundle*—A structure composed of three or more fibers in a parallel arrangement with each fiber closer than one fiber diameter.

5. *Clean area*—A controlled environment which is maintained and monitored to assure a low probability of asbestos contamination to materials in that space. Clean areas used in this method have HEPA filtered air under positive pressure and are capable of sustained operation with an open laboratory blank which on subsequent analysis has an average of less than 18 structures/mm<sup>2</sup> in an area of 0.057 mm<sup>2</sup> (nominally 10 200 mesh grid openings) and a maximum of 53 structures/mm<sup>2</sup> for no more than one single preparation for that same area.

6. *Cluster*—A structure with fibers in a random arrangement such that all fibers are intermixed and no single fiber is isolated from the group. Groupings must have more than two intersections.

7. *ED*—Electron diffraction.

8. *EDXA*—Energy dispersive X-ray analysis.

9. *Fiber*—A structure greater than or equal to 0.5 μm in length with an aspect ratio (length to width) of 5:1 or greater and having substantially parallel sides.

10. *Grid*—An open structure for mounting on the sample to aid in its examination in the TEM. The term is used here to denote a 200-mesh copper lattice approximately 3 mm in diameter.

11. *Intersection*—Nonparallel touching or crossing of fibers, with the projection having an aspect ratio of 5:1 or greater.

12. *Laboratory sample coordinator*—That person responsible for the conduct of sample handling and the certification of the testing procedures.

13. *Filter background level*—The concentration of structures per square millimeter of filter that is considered indistinguishable from the concentration measured on blanks (filters through which no air has been drawn). For this method the filter background level is defined as 70 structures/mm<sup>2</sup>.

14. *Matrix*—Fiber or fibers with one end free and the other end embedded in or hidden by a particulate. The exposed fiber must meet the fiber definition.

15. *NSD*—No structure detected.

16. *Operator*—A person responsible for the TEM instrumental analysis of the sample.

17. *PCM*—Phase contrast microscopy.

18. *SAED*—Selected area electron diffraction.

19. *SEM*—Scanning electron microscope.

20. *STEM*—Scanning transmission electron microscope.

21. *Structure*—a microscopic bundle, cluster, fiber, or matrix which may contain asbestos.

22. *S/cm<sup>3</sup>*—Structures per cubic centimeter.

23. *S/mm<sup>2</sup>*—Structures per square millimeter.

24. *TEM*—Transmission electron microscope.

#### B. Sampling

1. Sampling operations must be performed by qualified individuals completely independent of the abatement contractor to avoid possible conflict of interest (See References 1, 2, and 5 of Unit III.L.) Special precautions should be taken to avoid contamination of the sample. For example, materials that have not been prescreened for their asbestos background content should not be used; also, sample handling procedures which

do not take cross contamination possibilities into account should not be used.

2. Material and supply checks for asbestos contamination should be made on all critical supplies, reagents, and procedures before their use in a monitoring study.

3. Quality control and quality assurance steps are needed to identify problem areas and isolate the cause of the contamination (see Reference 5 of Unit III.L.). Control checks shall be permanently recorded to document the quality of the information produced. The sampling firm must have written quality control procedures and documents which verify compliance. Independent audits by a qualified consultant or firm should be performed once a year. All documentation of compliance should be retained indefinitely to provide a guarantee of quality. A summary of Sample Data Quality Objectives is shown in Table II of Unit II.B.

4. Sampling materials.

a. Sample for airborne asbestos following an abatement action using commercially available cassettes.

b. Use either a cowl or a filter-retaining middle piece. Conductive material may reduce the potential for particulates to adhere to the walls of the cowl.

c. Cassettes must be verified as “clean” prior to use in the field. If packaged filters are used for loading or preloaded cassettes are purchased from the manufacturer or a distributor, the manufacturer’s name and lot number should be entered on all field data sheets provided to the laboratory, and are required to be listed on all reports from the laboratory.


d. Assemble the cassettes in a clean facility (See definition of clean area under Unit III.A.).

e. Reloading of used cassettes is not permitted.

f. Use sample collection filters which are either polycarbonate having a pore size of less than or equal to 0.4 μm or mixed cellulose ester having a pore size of less than or equal to 0.45 μm.

g. Place these filters in series with a backup filter with a pore size of 5.0 μm (to serve as a diffuser) and a support pad. See the following Figure 1:

FIGURE I--SAMPLING CASSETTE CONFIGURATION



h. When polycarbonate filters are used, position the highly reflective face such that the incoming particulate is received on this surface.

i. Seal the cassettes to prevent leakage around the filter edges or between cassette part joints. A mechanical press may be useful to achieve a reproducible leak-free seal.



**Pt. 763, Subpt. E, App. A**

**40 CFR Ch. I (7–1–10 Edition)**

Shrink fit gel-bands may be used for this purpose and are available from filter manufacturers and their authorized distributors.

j. Use wrinkle-free loaded cassettes in the sampling operation.

**5. Pump setup.**

a. Calibrate the sampling pump over the range of flow rates and loads anticipated for the monitoring period with this flow measuring device in series. Perform this calibration using guidance from EPA Method 2A each time the unit is sent to the field (See Reference 6 of Unit III.L.).

b. Configure the sampling system to preclude pump vibrations from being transmitted to the cassette by using a sampling stand separate from the pump station and making connections with flexible tubing.

c. Maintain continuous smooth flow conditions by damping out any pump action fluctuations if necessary.

d. Check the sampling system for leaks with the end cap still in place and the pump operating before initiating sample collection. Trace and stop the source of any flow indicated by the flowmeter under these conditions.

e. Select an appropriate flow rate equal to or greater than 1 L/min or less than 10 L/min for 25 mm cassettes. Larger filters may be operated at proportionally higher flow rates.

f. Orient the cassette downward at approximately 45 degrees from the horizontal.

g. Maintain a log of all pertinent sampling information, such as pump identification number, calibration data, sample location, date, sample identification number, flow rates at the beginning, middle, and end, start and stop times, and other useful information or comments. Use of a sampling log form is recommended. See the following Figure 2:



TABLE 1--NUMBER OF 200 MESH EM GRID OPENINGS (0.0057 MM<sup>2</sup>) THAT NEED TO BE ANALYZED TO MAINTAIN SENSITIVITY OF 0.005 STRUCTURES/CC BASED ON VOLUME AND EFFECTIVE FILTER AREA

| Effective Filter Area<br>385 sq mm |                    | Effective Filter Area<br>855 sq mm |                    |
|------------------------------------|--------------------|------------------------------------|--------------------|
| Volume (liters)                    | # of grid openings | Volume (liters)                    | # of grid openings |
| 560                                | 24                 | 1,250                              | 24                 |
| 600                                | 23                 | 1,300                              | 23                 |
| 700                                | 19                 | 1,400                              | 21                 |
| 800                                | 17                 | 1,600                              | 19                 |
| 900                                | 15                 | 1,800                              | 17                 |
| 1,000                              | 14                 | 2,000                              | 15                 |
| 1,100                              | 12                 | 2,200                              | 14                 |
| 1,200                              | 11                 | 2,400                              | 13                 |
| 1,300                              | 10                 | 2,600                              | 12                 |
| 1,400                              | 10                 | 2,800                              | 11                 |
| 1,500                              | 9                  | 3,000                              | 10                 |
| 1,600                              | 8                  | 3,200                              | 9                  |
| 1,700                              | 8                  | 3,400                              | 9                  |
| 1,800                              | 8                  | 3,600                              | 8                  |
| 1,900                              | 7                  | 3,800                              | 8                  |
| 2,000                              | 7                  | 4,000                              | 8                  |
| 2,100                              | 6                  | 4,200                              | 7                  |
| 2,200                              | 6                  | 4,400                              | 7                  |
| 2,300                              | 6                  | 4,600                              | 7                  |
| 2,400                              | 6                  | 4,800                              | 6                  |
| 2,500                              | 5                  | 5,000                              | 6                  |
| 2,600                              | 5                  | 5,200                              | 6                  |
| 2,700                              | 5                  | 5,400                              | 6                  |
| 2,800                              | 5                  | 5,600                              | 5                  |
| 2,900                              | 5                  | 5,800                              | 5                  |
| 3,000                              | 5                  | 6,000                              | 5                  |
| 3,100                              | 4                  | 6,200                              | 5                  |
| 3,200                              | 4                  | 6,400                              | 5                  |
| 3,300                              | 4                  | 6,600                              | 5                  |
| 3,400                              | 4                  | 6,800                              | 4                  |
| 3,500                              | 4                  | 7,000                              | 4                  |
| 3,600                              | 4                  | 7,200                              | 4                  |
| 3,700                              | 4                  | 7,400                              | 4                  |
| 3,800                              | 4                  | 7,600                              | 4                  |

Note minimum volumes required:  
 25 mm : 560 liters  
 37 mm : 1250 liters

Filter diameter of 25 mm = effective area of 385 sq mm  
 Filter diameter of 37 mm = effective area of 855 sq mm

k. At the conclusion of sampling, turn the cassette upward before stopping the flow to minimize possible particle loss. If the sampling is resumed, restart the flow before re-orienting the cassette downward. Note the condition of the filter at the conclusion of sampling.

l. Double check to see that all information has been recorded on the data collection forms and that the cassette is securely

closed and appropriately identified using a waterproof label. Protect cassettes in individual clean resealed polyethylene bags. Bags are to be used for storing cassette caps when they are removed for sampling purposes. Caps and plugs should only be removed or replaced using clean hands or clean disposable plastic gloves.

m. Do not change containers if portions of these filters are taken for other purposes.

6. Minimum sample number per site. A minimum of 13 samples are to be collected for each testing consisting of the following:

- a. A minimum of five samples per abatement area.
- b. A minimum of five samples per ambient area positioned at locations representative of the air entering the abatement site.
- c. Two field blanks are to be taken by removing the cap for not more than 30 sec and replacing it at the time of sampling before sampling is initiated at the following places:
  - i. Near the entrance to each ambient area.
  - ii. At one of the ambient sites.

(NOTE: Do not leave the blank open during the sampling period.)

d. A sealed blank is to be carried with each sample set. This representative cassette is not to be opened in the field.

7. Abatement area sampling.

a. Conduct final clearance sampling only after the primary containment barriers have been removed; the abatement area has been thoroughly dried; and, it has passed visual inspection tests by qualified personnel. (See Reference 1 of Unit III.L.)

b. Containment barriers over windows, doors, and air passageways must remain in place until the TEM clearance sampling and analysis is completed and results meet clearance test criteria. The final plastic barrier remains in place for the sampling period.

c. Select sampling sites in the abatement area on a random basis to provide unbiased and representative samples.

d. After the area has passed a thorough visual inspection, use aggressive sampling conditions to dislodge any remaining dust.

i. Equipment used in aggressive sampling such as a leaf blower and/or fan should be properly cleaned and decontaminated before use.

ii. Air filtration units shall remain on during the air monitoring period.

iii. Prior to air monitoring, floors, ceiling and walls shall be swept with the exhaust of a minimum one (1) horsepower leaf blower.

iv. Stationary fans are placed in locations which will not interfere with air monitoring equipment. Fan air is directed toward the ceiling. One fan shall be used for each 10,000 ft<sup>3</sup> of worksite.

v. Monitoring of an abatement work area with high-volume pumps and the use of circulating fans will require electrical power. Electrical outlets in the abatement area may be used if available. If no such outlets are available, the equipment must be supplied with electricity by the use of extension cords and strip plug units. All electrical power supply equipment of this type must be approved Underwriter Laboratory equipment that has not been modified. All wiring must be grounded. Ground fault interrupters should be used. Extreme care must be taken to clean up any residual water and ensure

that electrical equipment does not become wet while operational.

vi. Low volume pumps may be carefully wrapped in 6-mil polyethylene to insulate the pump from the air. High volume pumps cannot be sealed in this manner since the heat of the motor may melt the plastic. The pump exhausts should be kept free.

vii. If recleaning is necessary, removal of this equipment from the work area must be handled with care. It is not possible to completely decontaminate the pump motor and parts since these areas cannot be wetted. To minimize any problems in this area, all equipment such as fans and pumps should be carefully wet wiped prior to removal from the abatement area. Wrapping and sealing low volume pumps in 6-mil polyethylene will provide easier decontamination of this equipment. Use of clean water and disposable wipes should be available for this purpose.

e. Pump flow rate equal to or greater than 1 L/min or less than 10 L/min may be used for 25 mm cassettes. The larger cassette diameters may have comparably increased flow.

f. Sample a volume of air sufficient to ensure the minimum quantitation limits. (See Table I of Unit III.B.5.j.)

8. Ambient sampling.

a. Position ambient samplers at locations representative of the air entering the abatement site. If makeup air entering the abatement site is drawn from another area of the building which is outside of the abatement area, place the pumps in the building, pumps should be placed out of doors located near the building and away from any obstructions that may influence wind patterns. If construction is in progress immediately outside the enclosure, it may be necessary to select another ambient site. Samples should be representative of any air entering the work site.

b. Locate the ambient samplers at least 3 ft apart and protect them from adverse weather conditions.

c. Sample same volume of air as samples taken inside the abatement site.

C. Sample Shipment

1. Ship bulk samples in a separate container from air samples. Bulk samples and air samples delivered to the analytical laboratory in the same container shall be rejected.

2. Select a rigid shipping container and pack the cassettes upright in a noncontaminating nonfibrous medium such as a bubble pack. The use of resealable polyethylene bags may help to prevent jostling of individual cassettes.

3. Avoid using expanded polystyrene because of its static charge potential. Also avoid using particle-based packaging materials because of possible contamination.

4. Include a shipping bill and a detailed listing of samples shipped, their descriptions

and all identifying numbers or marks, sampling data, shipper's name, and contact information. For each sample set, designate which are the ambient samples, which are the abatement area samples, which are the field blanks, and which is the sealed blank if sequential analysis is to be performed.

5. Hand-carry samples to the laboratory in an upright position if possible; otherwise choose that mode of transportation least likely to jar the samples in transit.

6. Address the package to the laboratory sample coordinator by name when known and alert him or her of the package description, shipment mode, and anticipated arrival as part of the chain of custody and sample tracking procedures. This will also help the laboratory schedule timely analysis for the samples when they are received.

#### D. Quality Control/Quality Assurance Procedures (Data Quality Indicators)

Monitoring the environment for airborne asbestos requires the use of sensitive sampling and analysis procedures. Because the test is sensitive, it may be influenced by a variety of factors. These include the supplies used in the sampling operation, the performance of the sampling, the preparation of the grid from the filter and the actual examination of this grid in the microscope. Each of these unit operations must produce a product of defined quality if the analytical result is to be a reliable and meaningful test result. Accordingly, a series of control checks and reference standards is performed along with the sample analysis as indicators that the materials used are adequate and the operations are within acceptable limits. In this way, the quality of the data is defined, and the results are of known value. These checks and tests also provide timely and specific warning of any problems which might develop within the sampling and analysis operations. A description of these quality control/quality assurance procedures is summarized in the text below.

1. Prescreen the loaded cassette collection filters to assure that they do not contain concentrations of asbestos which may interfere with the analysis of the sample. A filter blank average of less than 18 s/mm<sup>2</sup> in an area of 0.057 mm<sup>2</sup> (nominally 10 200-mesh grid openings) and a maximum of 53 s/mm<sup>2</sup> for that same area for any single preparation is acceptable for this method.

2. Calibrate sampling pumps and their flow indicators over the range of their intended use with a recognized standard. Assemble the sampling system with a representative filter—not the filter which will be used in sampling—before and after the sampling operation.

3. Record all calibration information with the data to be used on a standard sampling form.

4. Ensure that the samples are stored in a secure and representative location.

5. Ensure that mechanical calibrations from the pump will be minimized to prevent transferral of vibration to the cassette.

6. Ensure that a continuous smooth flow of negative pressure is delivered by the pump by installing a damping chamber if necessary.

7. Open a loaded cassette momentarily at one of the indoor sampling sites when sampling is initiated. This sample will serve as an indoor field blank.

8. Open a loaded cassette momentarily at one of the outdoor sampling sites when sampling is initiated. This sample will serve as an outdoor field blank.

9. Carry a sealed blank into the field with each sample series. Do not open this cassette in the field.

10. Perform a leak check of the sampling system at each indoor and outdoor sampling site by activating the pump with the closed sampling cassette in line. Any flow indicates a leak which must be eliminated before initiating the sampling operation.

11. Ensure that the sampler is turned upright before interrupting the pump flow.

12. Check that all samples are clearly labeled and that all pertinent information has been enclosed before transfer of the samples to the laboratory.

#### E. Sample Receiving

1. Designate one individual as sample coordinator at the laboratory. While that individual will normally be available to receive samples, the coordinator may train and supervise others in receiving procedures for those times when he/she is not available.

2. Adhere to the following procedures to ensure both the continued chain-of-custody and the accountability of all samples passing through the laboratory:

a. Note the condition of the shipping package and data written on it upon receipt.

b. Retain all bills of lading or shipping slips to document the shipper and delivery time.

c. Examine the chain-of-custody seal, if any, and the package for its integrity.

d. If there has been a break in the seal or substantive damage to the package, the sample coordinator shall immediately notify the shipper and a responsible laboratory manager before any action is taken to unpack the shipment.

e. Packages with significant damage shall be accepted only by the responsible laboratory manager after discussions with the client.

3. Unwrap the shipment in a clean, uncluttered facility. The sample coordinator or his or her designee will record the contents, including a description of each item and all identifying numbers or marks. A

**Environmental Protection Agency**

**Pt. 763, Subpt. E, App. A**

Sample Receiving Form to document this information is attached for use when necessary. (See the following Figure 3.)

FIGURE 3--SAMPLE RECEIVING FORM

Date of package delivery \_\_\_\_\_ Package shipped from \_\_\_\_\_  
 Carrier \_\_\_\_\_ Shipping bill retained \_\_\_\_\_  
 \*Condition of package on receipt \_\_\_\_\_  
 \*Condition of custody seal \_\_\_\_\_  
 Number of samples received \_\_\_\_\_ Shipping manifest attached \_\_\_\_\_  
 Purchase Order No. \_\_\_\_\_ Project I.D. \_\_\_\_\_  
 Comments \_\_\_\_\_

| No. | Description | Sampling Medium |     | Sampled Volume<br>Liters | Receiving ID # | Assigned # |
|-----|-------------|-----------------|-----|--------------------------|----------------|------------|
|     |             | PC              | MCE |                          |                |            |
| 1   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 2   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 3   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 4   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 5   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 6   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 7   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 8   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 9   | _____       | ___             | ___ | ___                      | ___            | ___        |
| 10  | _____       | ___             | ___ | ___                      | ___            | ___        |
| 11  | _____       | ___             | ___ | ___                      | ___            | ___        |
| 12  | _____       | ___             | ___ | ___                      | ___            | ___        |
| 13  | _____       | ___             | ___ | ___                      | ___            | ___        |

(Use as many additional sheets as needed.)

Comments \_\_\_\_\_  
 Date of acceptance into sample bank \_\_\_\_\_  
 Signature of chain-of-custody recipient \_\_\_\_\_  
 Disposition of samples \_\_\_\_\_

\*Note: If the package has sustained substantial damage or the custody seal is broken, stop and contact the project manager and the shipper.

NOTE: The person breaking the chain-of-custody seal and itemizing the contents assumes responsibility for the shipment and signs documents accordingly.

4. Assign a laboratory number and schedule an analysis sequence.

5. Manage all chain-of-custody samples within the laboratory such that their integrity can be ensured and documented.

#### F. Sample Preparation

1. Personnel not affiliated with the Abatement Contractor shall be used to prepare samples and conduct TEM analysis. Wet-wipe the exterior of the cassettes to minimize contamination possibilities before taking them to the clean sample preparation facility.

2. Perform sample preparation in a well-equipped clean facility.

NOTE: The clean area is required to have the following minimum characteristics. The area or hood must be capable of maintaining a positive pressure with make-up air being HEPA filtered. The cumulative analytical blank concentration must average less than 18 s/mm<sup>2</sup> in an area of 0.057 s/mm<sup>2</sup> (nominally 10 200-mesh grid openings) with no more than one single preparation to exceed 53 s/mm<sup>2</sup> for that same area.

3. Preparation areas for air samples must be separated from preparation areas for bulk samples. Personnel must not prepare air samples if they have previously been preparing bulk samples without performing appropriate personal hygiene procedures, i.e., clothing change, showering, etc.

4. *Preparation.* Direct preparation techniques are required. The objective is to produce an intact carbon film containing the particulates from the filter surface which is sufficiently clear for TEM analysis. Currently recommended direct preparation procedures for polycarbonate (PC) and mixed cellulose ester (MCE) filters are described in Unit III.F.7. and 8. Sample preparation is a subject requiring additional research. Variation on those steps which do not substantively change the procedure, which improve filter clearing or which reduce contamination problems in a laboratory are permitted.

a. Use only TEM grids that have had grid opening areas measured according to directions in Unit III.J.

b. Remove the inlet and outlet plugs prior to opening the cassette to minimize any pressure differential that may be present.

c. Examples of techniques used to prepare polycarbonate filters are described in Unit III.F.7.

d. Examples of techniques used to prepare mixed cellulose ester filters are described in Unit III.F.8.

e. Prepare multiple grids for each sample.

f. Store the three grids to be measured in appropriately labeled grid holders or polyethylene capsules.

5. Equipment.

a. Clean area.

b. Tweezers. Fine-point tweezers for handling of filters and TEM grids.

c. Scalpel Holder and Curved No. 10 Surgical Blades.

d. Microscope slides.

e. Double-coated adhesive tape.

f. Gummed page reinforcements.

g. Micro-pipet with disposal tips 10 to 100  $\mu$ L variable volume.

h. Vacuum coating unit with facilities for evaporation of carbon. Use of a liquid nitrogen cold trap above the diffusion pump will minimize the possibility of contamination of the filter surface by oil from the pumping system. The vacuum-coating unit can also be used for deposition of a thin film of gold.

i. *Carbon rod electrodes.* Spectrochemically pure carbon rods are required for use in the vacuum evaporator for carbon coating of filters.

j. *Carbon rod sharpener.* This is used to sharpen carbon rods to a neck. The use of necked carbon rods (or equivalent) allows the carbon to be applied to the filters with a minimum of heating.

k. *Low-temperature plasma asher.* This is used to etch the surface of collapsed mixed cellulose ester (MCE) filters. The asher should be supplied with oxygen, and should be modified as necessary to provide a throttle or bleed valve to control the speed of the vacuum to minimize disturbance of the filter. Some early models of ashers admit air too rapidly, which may disturb particulates on the surface of the filter during the etching step.

l. *Glass petri dishes, 10 cm in diameter, 1 cm high.* For prevention of excessive evaporation of solvent when these are in use, a good seal must be provided between the base and the lid. The seal can be improved by grinding the base and lid together with an abrasive grinding material.

m. Stainless steel mesh.

n. Lens tissue.

o. Copper 200-mesh TEM grids, 3 mm in diameter, or equivalent.

p. Gold 200-mesh TEM grids, 3 mm in diameter, or equivalent.

q. Condensation washer.

r. Carbon-coated, 200-mesh TEM grids, or equivalent.

s. Analytical balance, 0.1 mg sensitivity.

t. Filter paper, 9 cm in diameter.

u. Oven or slide warmer. Must be capable of maintaining a temperature of 65-70 °C.

v. Polyurethane foam, 6 mm thickness.

w. Gold wire for evaporation.

6. Reagents.

a. *General.* A supply of ultra-clean, fiber-free water must be available for washing of all components used in the analysis. Water

that has been distilled in glass or filtered or deionized water is satisfactory for this purpose. Reagents must be fiber-free.

b. Polycarbonate preparation method—chloroform.

c. Mixed Cellulose Ester (MCE) preparation method—acetone or the Burdette procedure (Ref. 7 of Unit III.L.).

7. TEM specimen preparation from polycarbonate filters.

a. *Specimen preparation laboratory.* It is most important to ensure that contamination of TEM specimens by extraneous asbestos fibers is minimized during preparation.

b. Cleaning of sample cassettes. Upon receipt at the analytical laboratory and before they are taken into the clean facility or laminar flow hood, the sample cassettes must be cleaned of any contamination adhering to the outside surfaces.

c. Preparation of the carbon evaporator. If the polycarbonate filter has already been carbon-coated prior to receipt, the carbon coating step will be omitted, unless the analyst believes the carbon film is too thin. If there is a need to apply more carbon, the filter will be treated in the same way as an uncoated filter. Carbon coating must be performed with a high-vacuum coating unit. Units that are based on evaporation of carbon filaments in a vacuum generated only by an oil rotary pump have not been evaluated for this application, and must not be used. The carbon rods should be sharpened by a carbon rod sharpener to necks of about 4 mm long and 1 mm in diameter. The rods are installed in the evaporator in such a manner that the points are approximately 10 to 12 cm from the surface of a microscope slide held in the rotating and tilting device.

d. Selection of filter area for carbon coating. Before preparation of the filters, a 75 mm×50 mm microscope slide is washed and dried. This slide is used to support strips of filter during the carbon evaporation. Two parallel strips of double-sided adhesive tape are applied along the length of the slide. Polycarbonate filters are easily stretched during handling, and cutting of areas for further preparation must be performed with great care. The filter and the MCE backing filter are removed together from the cassette and placed on a cleaned glass microscope slide. The filter can be cut with a curved scalpel blade by rocking the blade from the point placed in contact with the filter. The process can be repeated to cut a strip approximately 3 mm wide across the diameter of the filter. The strip of polycarbonate filter is separated from the corresponding strip of backing filter and carefully placed so that it bridges the gap between the adhesive tape strips on the microscope slide. The filter strip can be held with fine-point tweezers and supported underneath by the scalpel blade during placement on the microscope slide. The analyst can place several such

strips on the same microscope slide, taking care to rinse and wet-wipe the scalpel blade and tweezers before handling a new sample. The filter strips should be identified by etching the glass slide or marking the slide using a marker insoluble in water and solvents. After the filter strip has been cut from each filter, the residual parts of the filter must be returned to the cassette and held in position by reassembly of the cassette. The cassette will then be archived for a period of 30 days or returned to the client upon request.

e. Carbon coating of filter strips. The glass slide holding the filter strips is placed on the rotation-tilting device, and the evaporator chamber is evacuated. The evaporation must be performed in very short bursts, separated by some seconds to allow the electrodes to cool. If evaporation is too rapid, the strips of polycarbonate filter will begin to curl, which will lead to cross-linking of the surface material and make it relatively insoluble in chloroform. An experienced analyst can judge the thickness of carbon film to be applied, and some test should be made first on unused filters. If the film is too thin, large particles will be lost from the TEM specimen, and there will be few complete and undamaged grid openings on the specimen. If the coating is too thick, the filter will tend to curl when exposed to chloroform vapor and the carbon film may not adhere to the support mesh. Too thick a carbon film will also lead to a TEM image that is lacking in contrast, and the ability to obtain ED patterns will be compromised. The carbon film should be as thin as possible and remain intact on most of the grid openings of the TEM specimen intact.

f. Preparation of the Jaffe washer. The precise design of the Jaffe washer is not considered important, so any one of the published designs may be used. A washer consisting of a simple stainless steel bridge is recommended. Several pieces of lens tissue approximately 1.0 cm×0.5 cm are placed on the stainless steel bridge, and the washer is filled with chloroform to a level where the meniscus contacts the underside of the mesh, which results in saturation of the lens tissue. See References 8 and 10 of Unit III.L.

g. Placing of specimens into the Jaffe washer. The TEM grids are first placed on a piece of lens tissue so that individual grids can be picked up with tweezers. Using a curved scalpel blade, the analyst excises three 3 mm square pieces of the carbon-coated polycarbonate filter from the filter strip. The three squares are selected from the center of the strip and from two points between the outer periphery of the active surface and the center. The piece of filter is placed on a TEM specimen grid with the shiny side of the TEM grid facing upwards, and the whole assembly is placed boldly onto the saturated lens tissue in the Jaffe washer. If carbon-coated grids are used, the filter should be



placed carbon-coated side down. The three excised squares of filters are placed on the same piece of lens tissue. Any number of separate pieces of lens tissue may be placed in the same Jaffe washer. The lid is then placed on the Jaffe washer, and the system is allowed to stand for several hours, preferably overnight.

h. *Condensation washing.* It has been found that many polycarbonate filters will not dissolve completely in the Jaffe washer, even after being exposed to chloroform for as long as 3 days. This problem becomes more serious if the surface of the filter was overheated during the carbon evaporation. The presence of undissolved filter medium on the TEM preparation leads to partial or complete obscuration of areas of the sample, and fibers that may be present in these areas of the specimen will be overlooked; this will lead to a low result. Undissolved filter medium also compromises the ability to obtain ED patterns. Before they are counted, TEM grids must be examined critically to determine whether they are adequately cleared of residual filter medium. It has been found that condensation washing of the grids after the initial Jaffe washer treatment, with chloroform as the solvent, clears all residual filter medium in a period of approximately 1 hour. In practice, the piece of lens tissue supporting the specimen grids is transferred to the cold finger of the condensation washer, and the washer is operated for about 1 hour. If the specimens are cleared satisfactorily by the Jaffe washer alone, the condensation washer step may be unnecessary.

8. TEM specimen preparation from MCE filters.

a. This method of preparing TEM specimens from MCE filters is similar to that specified in NIOSH Method 7402. See References 7, 8, and 9 of Unit III.L.

b. Upon receipt at the analytical laboratory, the sample cassettes must be cleaned of any contamination adhering to the outside surfaces before entering the clean sample preparation area.

c. Remove a section from any quadrant of the sample and blank filters.

d. Place the section on a clean microscope slide. Affix the filter section to the slide with a gummed paged reinforcement or other suitable means. Label the slide with a water and solvent-proof marking pen.

e. Place the slide in a petri dish which contains several paper filters soaked with 2 to 3 mL acetone. Cover the dish. Wait 2 to 4 minutes for the sample filter to fuse and clear.

f. Plasma etching of the collapsed filter is required.

i. The microscope slide to which the collapsed filter pieces are attached is placed in a plasma asher. Because plasma ashers vary greatly in their performance, both from unit to unit and between different positions in the asher chamber, it is difficult to specify

the conditions that should be used. This is one area of the method that requires further evaluation. Insufficient etching will result in a failure to expose embedded filters, and too much etching may result in loss of particulate from the surface. As an interim measure, it is recommended that the time for ashing of a known weight of a collapsed filter be established and that the etching rate be calculated in terms of micrometers per second. The actual etching time used for a particular asher and operating conditions will then be set such that a 1-2  $\mu\text{m}$  (10 percent) layer of collapsed surface will be removed.

ii. Place the slide containing the collapsed filters into a low-temperature plasma asher, and etch the filter.

g. Transfer the slide to a rotating stage inside the bell jar of a vacuum evaporator. Evaporate a 1 mm $\times$ 5 mm section of graphite rod onto the cleared filter. Remove the slide to a clean, dry, covered petri dish.

h. Prepare a second petri dish as a Jaffe washer with the wicking substrate prepared from filter or lens paper placed on top of a 6 mm thick disk of clean spongy polyurethane foam. Cut a V-notch on the edge of the foam and filter paper. Use the V-notch as a reservoir for adding solvent. The wicking substrate should be thin enough to fit into the petri dish without touching the lid.

i. Place carbon-coated TEM grids face up on the filter or lens paper. Label the grids by marking with a pencil on the filter paper or by putting registration marks on the petri dish lid and marking with a waterproof marker on the dish lid. In a fume hood, fill the dish with acetone until the wicking substrate is saturated. The level of acetone should be just high enough to saturate the filter paper without creating puddles.

j. Remove about a quarter section of the carbon-coated filter samples from the glass slides using a surgical knife and tweezers. Carefully place the section of the filter, carbon side down, on the appropriately labeled grid in the acetone-saturated petri dish. When all filter sections have been transferred, slowly add more solvent to the wedge-shaped trough to bring the acetone level up to the highest possible level without disturbing the sample preparations. Cover the petri dish. Elevate one side of the petri dish by placing a slide under it. This allows drops of condensed solvent vapors to form near the edge rather than in the center where they would drip onto the grid preparation.

#### G. TEM Method

##### 1. Instrumentation.

a. Use an 80-120 kV TEM capable of performing electron diffraction with a fluorescent screen inscribed with calibrated gradations. If the TEM is equipped with EDXA it must either have a STEM attachment or be capable of producing a spot less than 250 nm

**Environmental Protection Agency**

**Pt. 763, Subpt. E, App. A**

in diameter at crossover. The microscope shall be calibrated routinely (see Unit III.J.) for magnification and camera constant.

b. While not required on every microscope in the laboratory, the laboratory must have either one microscope equipped with energy dispersive X-ray analysis or access to an equivalent system on a TEM in another laboratory. This must be an Energy Dispersive X-ray Detector mounted on TEM column and associated hardware/software to collect, save, and read out spectral information. Calibration of Multi-Channel Analyzer shall be checked regularly for Al at 1.48 KeV and Cu at 8.04 KeV, as well as the manufacturer's procedures.

i. Standard replica grating may be used to determine magnification (e.g., 2160 lines/mm).

ii. Gold standard may be used to determine camera constant.

c. Use a specimen holder with single tilt and/or double tilt capabilities.

2. Procedure.

a. Start a new Count Sheet for each sample to be analyzed. Record on count sheet: analyst's initials and date; lab sample number; client sample number microscope identification; magnification for analysis; number of predetermined grid openings to be analyzed; and grid identification. See the following Figure 4:



## Environmental Protection Agency

## Pt. 763, Subpt. E, App. A

i. Individual grid openings with greater than 5 percent openings (holes) or covered with greater than 25 percent particulate matter or obviously having nonuniform loading shall not be analyzed.

ii. Examine the grid at low magnification (<1000X) to determine its suitability for detailed study at higher magnifications.

iii. Reject the grid if:

(1) Less than 50 percent of the grid openings covered by the replica are intact.

(2) It is doubled or folded.

(3) It is too dark because of incomplete dissolution of the filter.

iv. If the grid is rejected, load the next sample grid.

v. If the grid is acceptable, continue on to Step 6 if mapping is to be used; otherwise proceed to Step 7.

f. Grid Map (Optional).

i. Set the TEM to the low magnification mode.

ii. Use flat edge or finder grids for mapping.

iii. Index the grid openings (fields) to be counted by marking the acceptable fields for one-half (0.5) of the area needed for analysis on each of the two grids to be analyzed. These may be marked just before examining each grid opening (field), if desired.

iv. Draw in any details which will allow the grid to be properly oriented if it is re-

loaded into the microscope and a particular field is to be reliably identified.

g. Scan the grid.

i. Select a field to start the examination.

ii. Choose the appropriate magnification (15,000 to 20,000X screen magnification).

iii. Scan the grid as follows.

(1) At the selected magnification, make a series of parallel traverses across the field. On reaching the end of one traverse, move the image one window and reverse the traverse.

NOTE: A slight overlap should be used so as not to miss any part of the grid opening (field).


(2) Make parallel traverses until the entire grid opening (field) has been scanned.

h. Identify each structure for appearance and size.


i. Appearance and size: Any continuous grouping of particles in which an asbestos fiber within aspect ratio greater than or equal to 5:1 and a length greater than or equal to 0.5  $\mu\text{m}$  is detected shall be recorded on the count sheet. These will be designated asbestos structures and will be classified as fibers, bundles, clusters, or matrices. Record as individual fibers any contiguous grouping having 0, 1, or 2 definable intersections. Groupings having more than 2 intersections are to be described as cluster or matrix. See the following Figure 5:

FIGURE 5--COUNTING GUIDELINES USED IN DETERMINING ASBESTOS STRUCTURES


Count as 1 fiber; 1 Structure; no intersections.



Count as 2 fibers if space between fibers is greater than width of 1 fiber diameter or number of intersections is equal to or less than 1.




Count as 3 structures if space between fibers is greater than width of 1 fiber diameter or if the number of intersections is equal to or less than 2.




Count bundles as 1 structure; 3 or more parallel fibrils less than 1 fiber diameter separation.



Count clusters as 1 structure; fibers having greater than or equal to 3 intersections.



Count matrix as 1 structure.




DO NOT COUNT AS STRUCTURES:



Fiber protrusion  
<5:1 Aspect Ratio



No fiber protrusion



Fiber protrusion  
<0.5 micrometer

— <0.5 micrometer in length  
— <5:1 Aspect Ratio

An intersection is a non-parallel touching or crossing of fibers, with the projection having an aspect ratio of 5:1 or greater. Combinations such as a matrix and cluster, matrix and bundle, or bundle and cluster are categorized by the dominant fiber quality—cluster, bundle, and matrix, respectively. Separate categories will be maintained for fibers less than 5  $\mu\text{m}$  and for fibers greater than or equal to 5  $\mu\text{m}$  in length. Not required, but useful, may be to record the fiber length in 1  $\mu\text{m}$  intervals. (Identify each structure morphologically and analyze it as it enters the "window".)

(1) *Fiber*. A structure having a minimum length greater than 0.5  $\mu\text{m}$  and an aspect ratio (length to width) of 5:1 or greater and substantially parallel sides. Note the appearance of the end of the fiber, i.e., whether it is flat, rounded or dovetailed, no intersections.

(2) *Bundle*. A structure composed of 3 or more fibers in a parallel arrangement with each fiber closer than one fiber diameter.

(3) *Cluster*. A structure with fibers in a random arrangement such that all fibers are intermixed and no single fiber is isolated from the group; groupings must have more than 2 intersections.

(4) *Matrix*. Fiber or fibers with one end free and the other end embedded in or hidden by a particulate. The exposed fiber must meet the fiber definition.

(5) *NSD*. Record NSD when no structures are detected in the field.

(6) *Intersection*. Non-parallel touching or crossing of fibers, with the projection having an aspect ratio 5:1 or greater.

ii. Structure Measurement.

(1) Recognize the structure that is to be sized.

(2) Memorize its location in the "window" relative to the sides, inscribed square and to other particulates in the field so this exact location can be found again when scanning is resumed.

(3) Measure the structure using the scale on the screen.

(4) Record the length category and structure type classification on the count sheet after the field number and fiber number.

(5) Return the fiber to its original location in the window and scan the rest of the field for other fibers; if the direction of travel is not remembered, return to the right side of the field and begin the traverse again.

i. Visual identification of Electron Diffraction (ED) patterns is required for each asbestos structure counted which would cause the analysis to exceed the 70 s/mm<sup>2</sup> concentration. (Generally this means the first four fibers identified as asbestos must exhibit an identifiable diffraction pattern for chrysotile or amphibole.)

i. Center the structure, focus, and obtain an ED pattern. (See Microscope Instruction Manual for more detailed instructions.)

ii. From a visual examination of the ED pattern, obtained with a short camera length, classify the observed structure as belonging to one of the following classifications: chrysotile, amphibole, or nonasbestos.

(1) Chrysotile: The chrysotile asbestos pattern has characteristic streaks on the layer lines other than the central line and some streaking also on the central line. There will be spots of normal sharpness on the central layer line and on alternate lines (2nd, 4th, etc.). The repeat distance between layer lines is 0.53 nm and the center doublet is at 0.73 nm. The pattern should display (002), (110), (130) diffraction maxima; distances and geometry should match a chrysotile pattern and be measured semiquantitatively.

(2) Amphibole Group [includes grunerite (amosite), crocidolite, anthophyllite, tremolite, and actinolite]: Amphibole asbestos fiber patterns show layer lines formed by very closely spaced dots, and the repeat distance between layer lines is also about 0.53 nm. Streaking in layer lines is occasionally present due to crystal structure defects.

(3) Nonasbestos: Incomplete or unobtainable ED patterns, a nonasbestos EDXA, or a nonasbestos morphology.

iii. The micrograph number of the recorded diffraction patterns must be reported to the client and maintained in the laboratory's quality assurance records. The records must also demonstrate that the identification of the pattern has been verified by a qualified individual and that the operator who made the identification is maintaining at least an 80 percent correct visual identification based on his measured patterns. In the event that examination of the pattern by the qualified individual indicates that the pattern had been misidentified visually, the client shall be contacted. If the pattern is a suspected chrysotile, take a photograph of the diffraction pattern at 0 degrees tilt. If the structure is suspected to be amphibole, the sample may have to be tilted to obtain a simple geometric array of spots.

j. Energy Dispersive X-Ray Analysis (EDXA).

i. Required of all amphiboles which would cause the analysis results to exceed the 70 s/mm<sup>2</sup> concentration. (Generally speaking, the first 4 amphiboles would require EDXA.)

ii. Can be used alone to confirm chrysotile after the 70 s/mm<sup>2</sup> concentration has been exceeded.

iii. Can be used alone to confirm all non-asbestos.

iv. Compare spectrum profiles with profiles obtained from asbestos standards. The closest match identifies and categorizes the structure.

v. If the EDXA is used for confirmation, record the properly labeled spectrum on a computer disk, or if a hard copy, file with analysis data.

vi. If the number of fibers in the non-asbestos class would cause the analysis to exceed the 70 s/mm<sup>2</sup> concentration, their identities must be confirmed by EDXA or measurement of a zone axis diffraction pattern to establish that the particles are non-asbestos.

k. Stopping Rules.

i. If more than 50 asbestiform structures are counted in a particular grid opening, the analysis may be terminated.

ii. After having counted 50 asbestiform structures in a minimum of 4 grid openings, the analysis may be terminated. The grid opening in which the 50th fiber was counted must be completed.

iii. For blank samples, the analysis is always continued until 10 grid openings have been analyzed.

iv. In all other samples the analysis shall be continued until an analytical sensitivity of 0.005 s/cm<sup>3</sup> is reached.

l. Recording Rules. The count sheet should contain the following information:

i. Field (grid opening): List field number.

ii. Record "NSD" if no structures are detected.

iii. Structure information.

(1) If fibers, bundles, clusters, and/or matrices are found, list them in consecutive numerical order, starting over with each field.

(2) Length. Record length category of asbestos fibers examined. Indicate if less than 5  $\mu\text{m}$  or greater than or equal to 5  $\mu\text{m}$ .

(3) Structure Type. Positive identification of asbestos fibers is required by the method. At least one diffraction pattern of each fiber type from every five samples must be recorded and compared with a standard diffraction pattern. For each asbestos fiber reported, both a morphological descriptor and an identification descriptor shall be specified on the count sheet.

(4) Fibers classified as chrysotile must be identified by diffraction and/or X-ray analysis and recorded on the count sheet. X-ray analysis alone can be used as sole identification only after 70s/mm<sup>2</sup> have been exceeded for a particular sample.

(5) Fibers classified as amphiboles must be identified by X-ray analysis and electron diffraction and recorded on the count sheet. (X-ray analysis alone can be used as sole identification only after 70s/mm<sup>2</sup> have been exceeded for a particular sample.)

(6) If a diffraction pattern was recorded on film, the micrograph number must be indicated on the count sheet.

(7) If an electron diffraction was attempted and an appropriate spectra is not observed, N should be recorded on the count sheet.

(8) If an X-ray analysis is attempted but not observed, N should be recorded on the count sheet.

(9) If an X-ray analysis spectrum is stored, the file and disk number must be recorded on the count sheet.

m. Classification Rules.

i. *Fiber*. A structure having a minimum length greater than or equal to 0.5  $\mu\text{m}$  and an aspect ratio (length to width) of 5:1 or greater and substantially parallel sides. Note the appearance of the end of the fiber, i.e., whether it is flat, rounded or dovetailed.

ii. *Bundle*. A structure composed of three or more fibers in a parallel arrangement with each fiber closer than one fiber diameter.

iii. *Cluster*. A structure with fibers in a random arrangement such that all fibers are intermixed and no single fiber is isolated

from the group. Groupings must have more than two intersections.

iv. *Matrix*. Fiber or fibers with one end free and the other end embedded in or hidden by a particulate. The exposed fiber must meet the fiber definition.

v. *NSD*. Record NSD when no structures are detected in the field.

n. After all necessary analyses of a particle structure have been completed, return the goniometer stage to 0 degrees, and return the structure to its original location by recall of the original location.

o. Continue scanning until all the structures are identified, classified and sized in the field.

p. Select additional fields (grid openings) at low magnification; scan at a chosen magnification (15,000 to 20,000X screen magnification); and analyze until the stopping rule becomes applicable.

q. Carefully record all data as they are being collected, and check for accuracy.

r. After finishing with a grid, remove it from the microscope, and replace it in the appropriate grid hold. Sample grids must be stored for a minimum of 1 year from the date of the analysis; the sample cassette must be retained for a minimum of 30 days by the laboratory or returned at the client's request.

H. Sample Analytical Sequence

1. Carry out visual inspection of work site prior to air monitoring.

2. Collect a minimum of five air samples inside the work site and five samples outside the work site. The indoor and outdoor samples shall be taken during the same time period.

3. Analyze the abatement area samples according to this protocol. The analysis must meet the 0.005 s/cm<sup>3</sup> analytical sensitivity.

4. Remaining steps in the analytical sequence are contained in Unit IV. of this Appendix.

I. Reporting

The following information must be reported to the client. See the following Table II:





9. Signature of laboratory official to indicate that the laboratory met specifications of the AHERA method.

10. Report form must contain official laboratory identification (e.g., letterhead).

11. Type of asbestos.

#### J. Calibration Methodology

NOTE: Appropriate implementation of the method requires a person knowledgeable in electron diffraction and mineral identification by ED and EDXA. Those inexperienced laboratories wishing to develop capabilities may acquire necessary knowledge through analysis of appropriate standards and by following detailed methods as described in References 8 and 10 of Unit III.L.

1. *Equipment Calibration.* In this method, calibration is required for the air-sampling equipment and the transmission electron microscope (TEM).

a. *TEM Magnification.* The magnification at the fluorescent screen of the TEM must be calibrated at the grid opening magnification (if used) and also at the magnification used for fiber counting. This is performed with a cross grating replica. A logbook must be maintained, and the dates of calibration depend on the past history of the particular microscope; no frequency is specified. After any maintenance of the microscope that involved adjustment of the power supplied to the lenses or the high-voltage system or the mechanical disassembly of the electron optical column apart from filament exchange, the magnification must be recalibrated. Before the TEM calibration is performed, the analyst must ensure that the cross grating replica is placed at the same distance from the objective lens as the specimens are. For instruments that incorporate an eucentric tilting specimen stage, all specimens and the cross grating replica must be placed at the eucentric position.

b. Determination of the TEM magnification on the fluorescent screen.

i. Define a field of view on the fluorescent screen either by markings or physical boundaries. The field of view must be measurable or previously inscribed with a scale or concentric circles (all scales should be metric).

ii. Insert a diffraction grating replica (for example a grating containing 2,160 lines/mm) into the specimen holder and place into the microscope. Orient the replica so that the grating lines fall perpendicular to the scale on the TEM fluorescent screen. Ensure that the goniometer stage tilt is 0 degrees.

iii. Adjust microscope magnification to 10,000X or 20,000X. Measure the distance (mm) between two widely separated lines on the grating replica. Note the number of spaces between the lines. Take care to measure between the same relative positions on the lines (e.g., between left edges of lines).

NOTE: The more spaces included in the measurement, the more accurate the final

calculation. On most microscopes, however, the magnification is substantially constant only within the central 8-10 cm diameter region of the fluorescent screen.

iv. Calculate the true magnification (M) on the fluorescent screen:

$$M = XG/Y$$

where:

X = total distance (mm) between the designated grating lines;

G = calibration constant of the grating replica (lines/mm);

Y = number of grating replica spaces counted along X.

c. *Calibration of the EDXA System.* Initially, the EDXA system must be calibrated by using two reference elements to calibrate the energy scale of the instrument. When this has been completed in accordance with the manufacturer's instructions, calibration in terms of the different types of asbestos can proceed. The EDXA detectors vary in both solid angle of detection and in window thickness. Therefore, at a particular accelerating voltage in use on the TEM, the count rate obtained from specific dimensions of fiber will vary both in absolute X-ray count rate and in the relative X-ray peak heights for different elements. Only a few minerals are relevant for asbestos abatement work, and in this procedure the calibration is specified in terms of a "fingerprint" technique. The EDXA spectra must be recorded from individual fibers of the relevant minerals, and identifications are made on the basis of semiquantitative comparisons with these reference spectra.

d. *Calibration of Grid Openings.*

i. Measure 20 grid openings on each of 20 random 200-mesh copper grids by placing a grid on a glass slide and examining it under the PCM. Use a calibrated graticule to measure the average field diameter and use this number to calculate the field area for an average grid opening. Grids are to be randomly selected from batches up to 1,000.

NOTE: A grid opening is considered as one field.

ii. The mean grid opening area must be measured for the type of specimen grids in use. This can be accomplished on the TEM at a properly calibrated low magnification or on an optical microscope at a magnification of approximately 400X by using an eyepiece fitted with a scale that has been calibrated against a stage micrometer. Optical microscopy utilizing manual or automated procedures may be used providing instrument calibration can be verified.

e. *Determination of Camera Constant and ED Pattern Analysis.*

i. The camera length of the TEM in ED operating mode must be calibrated before ED patterns on unknown samples are observed. This can be achieved by using a carbon-coated grid on which a thin film of gold has been

sputtered or evaporated. A thin film of gold is evaporated on the specimen TEM grid to obtain zone-axis ED patterns superimposed with a ring pattern from the polycrystalline gold film.

ii. In practice, it is desirable to optimize the thickness of the gold film so that only one or two sharp rings are obtained on the superimposed ED pattern. Thicker gold film would normally give multiple gold rings, but it will tend to mask weaker diffraction spots from the unknown fibrous particulates. Since the unknown d-spacings of most interest in asbestos analysis are those which lie closest to the transmitted beam, multiple gold rings are unnecessary on zone-axis ED patterns. An average camera constant using multiple gold rings can be determined. The camera constant is one-half the diameter,  $D$ , of the rings times the interplanar spacing,  $d$ , of the ring being measured.

K. Quality Control/Quality Assurance Procedures (Data Quality Indicators)

Monitoring the environment for airborne asbestos requires the use of sensitive sam-

pling and analysis procedures. Because the test is sensitive, it may be influenced by a variety of factors. These include the supplies used in the sampling operation, the performance of the sampling, the preparation of the grid from the filter and the actual examination of this grid in the microscope. Each of these unit operations must produce a product of defined quality if the analytical result is to be a reliable and meaningful test result. Accordingly, a series of control checks and reference standards is performed along with the sample analysis as indicators that the materials used are adequate and the operations are within acceptable limits. In this way, the quality of the data is defined and the results are of known value. These checks and tests also provide timely and specific warning of any problems which might develop within the sampling and analysis operations. A description of these quality control/quality assurance procedures is summarized in the following Table III:

TABLE III--SUMMARY OF LABORATORY  
DATA QUALITY OBJECTIVES

| Unit Operation  | QC Check  | Frequency  | Conformance Expectation                 |
|---|---|--|---|
| Sample receiving                                      | Review of receiving report  | Each sample  | 95% complete                            |
| Sample custody  | Review of chain-of-custody record   | Each sample  | 95% complete                            |
| Sample preparation                                    | Supplies and reagents   | On receipt   | Meet specs. or reject                   |
|   | Grid opening size   | 20 openings/20 grids/lot of 1000 or 1 opening/sample | 100%                                    |
|   | Special clean area monitoring   | After cleaning or service                            | Meet specs or reclean                   |
|   | Laboratory blank  | 1 per prep series or 10%                             | Meet specs. or reanalyze series         |
|   | Plasma etch blank   | 1 per 20 samples                                     | 75%                                     |
|   | Multiple preps (3 per sample)   | Each sample  | One with cover of 15 complete grid sqs. |
|   | Sample analysis   | System check   | Each day                                |
| Alignment check                                       |   | Each day   | Each day                                |
| Magnification calibration with low and high standards |   | Each month or after service                          | 95%                                     |
| ED calibration by gold standard                       |   | Weekly   | 95%                                     |
| EDS calibration by copper line                        |   | Daily  | 95%                                     |
| Performance check                                     | Laboratory blank (measure of cleanliness)   | Prep 1 per series or 10% read 1 per 25 samples       | Meet specs or reanalyze series          |
|   | Replicate counting (measure of precision)   | 1 per 100 samples                                    | 1.5 x Poisson Std. Dev.                 |
|   | Duplicate analysis (measure of reproducibility)   | 1 per 100 samples                                    | 2 x Poisson Std. Dev.                   |
|   | Known samples of typical materials (working standards)  | Training and for comparison with unknowns            | 100%                                    |
|   | Analysis of NBS SRM 1876 and/or RM 8410 (measure of accuracy and comparability)                             | 1 per analyst per year                               | 1.5 x Poisson Std. Dev.                 |
|   | Data entry review (data validation and measure of completeness)   | Each sample  | 95%                                     |
|   | Record and verify ID electron diffraction pattern of structure  | 1 per 5 samples                                      | 80% accuracy                            |
| Calculations and data reduction                       | Hand calculation of automated data reduction procedure or independent recalculation of hand-calculated data | 1 per 100 samples                                    | 85%                                     |

1. When the samples arrive at the laboratory, check the samples and documentation for completeness and requirements before initiating the analysis.

2. Check all laboratory reagents and supplies for acceptable asbestos background levels.

3. Conduct all sample preparation in a clean room environment monitored by laboratory blanks and special testing after cleaning or servicing the room.

4. Prepare multiple grids of each sample.

5. Provide laboratory blanks with each sample batch. Maintain a cumulative average of these results. If this average is greater than 53 f/mm<sup>2</sup> per 10 200-mesh grid openings, check the system for possible sources of contamination.

6. Check for recovery of asbestos from cellulose ester filters submitted to plasma asher.

7. Check for asbestos carryover in the plasma asher by including a blank alongside the positive control sample.

8. Perform a systems check on the transmission electron microscope daily.

9. Make periodic performance checks of magnification, electron diffraction and energy dispersive X-ray systems as set forth in Table III of Unit III.K.

10. Ensure qualified operator performance by evaluation of replicate counting, duplicate analysis, and standard sample comparisons as set forth in Table III of Unit III.K.

11. Validate all data entries.

12. Recalculate a percentage of all computations and automatic data reduction steps as specified in Table III.

13. Record an electron diffraction pattern of one asbestos structure from every five samples that contain asbestos. Verify the identification of the pattern by measurement or comparison of the pattern with patterns collected from standards under the same conditions.

The outline of quality control procedures presented above is viewed as the minimum required to assure that quality data is produced for clearance testing of an asbestos abated area. Additional information may be gained by other control tests. Specifics on those control procedures and options available for environmental testing can be obtained by consulting References 6, 7, and 11 of Unit III.L.

#### L. References

For additional background information on this method the following references should be consulted.

1. "Guidelines for Controlling Asbestos-Containing Materials in Buildings," EPA 560/5-85-024, June 1985.
2. "Measuring Airborne Asbestos Following an Abatement Action," USEP/Office of Pollution Prevention and Toxics, EPA 600/4-85-049, 1985.
3. Small, John and E. Steel. Asbestos Standards: Materials and Analytical Methods. N.B.S. Special Publication 619, 1982.
4. Campbell, W.J., R.L. Blake, L.L. Brown, E.E. Cather, and J.J. Sjoberg. Selected Silicate Minerals and Their Asbestiform Varieties. Information Circular 8751, U.S. Bureau of Mines, 1977.
5. Quality Assurance Handbook for Air Pollution Measurement System. Ambient Air Methods, EPA 600/4-77-027a, USEPA, Office of Research and Development, 1977.
6. Method 2A: Direct Measurement of Gas Volume Through Pipes and Small Ducts. 40 CFR Part 60 Appendix A.
7. Burdette, G.J. Health & Safety Exec., Research & Lab. Services Div., London, "Proposed Analytical Method for Determination of Asbestos in Air."
8. Chatfield, E.J., Chatfield Tech. Cons., Ltd., Clark, T., PEI Assoc. "Standard Operating Procedure for Determination of Airborne Asbestos Fibers by Transmission Elec-

tron Microscopy Using Polycarbonate Membrane Filters." WERL SOP 87-1, March 5, 1987.

9. NIOSH. Method 7402 for Asbestos Fibers, December 11, 1986 Draft.

10. Yamate, G., S.C. Agarwall, R.D. Gibbons, IIT Research Institute, "Methodology for the Measurement of Airborne Asbestos by Electron Microscopy." Draft report, USEPA Contract 68-02-3266, July 1984.

11. Guidance to the Preparation of Quality Assurance Project Plans. USEPA, Office of Pollution Prevention and Toxics, 1984.

#### IV. Mandatory Interpretation of Transmission Electron Microscopy Results To Determine Completion of Response Actions

##### A. Introduction

A response action is determined to be completed by TEM when the abatement area has been cleaned and the airborne asbestos concentration inside the abatement area is no higher than concentrations at locations outside the abatement area. "Outside" means outside the abatement area, but not necessarily outside the building. EPA reasons that an asbestos removal contractor cannot be expected to clean an abatement area to an airborne asbestos concentration that is lower than the concentration of air entering the abatement area from outdoors or from other parts of the building. After the abatement area has passed a thorough visual inspection, and before the outer containment barrier is removed, a minimum of five air samples inside the abatement area and a minimum of five air samples outside the abatement area must be collected. Hence, the response action is determined to be completed when the average airborne asbestos concentration measured inside the abatement area is not statistically different from the average airborne asbestos concentration measured outside the abatement area.

The inside and outside concentrations are compared by the Z-test, a statistical test that takes into account the variability in the measurement process. A minimum of five samples inside the abatement area and five samples outside the abatement area are required to control the false negative error rate, i.e., the probability of declaring the removal complete when, in fact, the air concentration inside the abatement area is significantly higher than outside the abatement area. Additional quality control is provided by requiring three blanks (filters through which no air has been drawn) to be analyzed to check for unusually high filter contamination that would distort the test results.

When volumes greater than or equal to 1,199 L for a 25 mm filter and 2,799 L for a 37 mm filter have been collected and the average number of asbestos structures on samples inside the abatement area is no greater than 70 s/mm<sup>2</sup> of filter, the response action

may be considered complete without comparing the inside samples to the outside samples. EPA is permitting this initial screening test to save analysis costs in situations where the airborne asbestos concentration is sufficiently low so that it cannot be distinguished from the filter contamination/background level (fibers deposited on the filter that are unrelated to the air being sampled). The screening test cannot be used when volumes of less than 1,199 L for 25 mm filter or 2,799 L for a 37 mm filter are collected because the ability to distinguish levels significantly different from filter background is reduced at low volumes.

The initial screening test is expressed in structures per square millimeter of filter because filter background levels come from sources other than the air being sampled and cannot be meaningfully expressed as a concentration per cubic centimeter of air. The value of 70 s/mm<sup>2</sup> is based on the experience of the panel of microscopists who consider one structure in 10 grid openings (each grid opening with an area of 0.0057 mm<sup>2</sup>) to be comparable with contamination/background levels of blank filters. The decision is based, in part, on Poisson statistics which indicate that four structures must be counted on a filter before the fiber count is statistically distinguishable from the count for one structure. As more information on the performance of the method is collected, this criterion may be modified. Since different combinations of the number and size of grid openings are permitted under the TEM protocol, the criterion is expressed in structures per square millimeter of filter to be consistent across all combinations. Four structures per 10 grid openings corresponds to approximately 70 s/mm<sup>2</sup>.

#### B. Sample Collection and Analysis

1. A minimum of 13 samples is required: five samples collected inside the abatement area, five samples collected outside the abatement area, two field blanks, and one sealed blank.

2. Sampling and TEM analysis must be done according to either the mandatory or nonmandatory protocols in Appendix A. At least 0.057 mm<sup>2</sup> of filter must be examined on blank filters.

#### C. Interpretation of Results

1. The response action shall be considered complete if either:

a. Each sample collected inside the abatement area consists of at least 1,199 L of air for a 25 mm filter, or 2,799 L of air for a 37 mm filter, and the arithmetic mean of their asbestos structure concentrations per square millimeter of filter is less than or equal to 70 s/mm<sup>2</sup>; or

b. The three blank samples have an arithmetic mean of the asbestos structure con-

centration on the blank filters that is less than or equal to 70 s/mm<sup>2</sup> and the average airborne asbestos concentration measured inside the abatement area is not statistically higher than the average airborne asbestos concentration measured outside the abatement area as determined by the Z-test. The Z-test is carried out by calculating

$$Z = \frac{\bar{Y}_1 - \bar{Y}_0}{0.8(1/n_1 + 1/n_0)^{1/2}}$$

where  $\bar{Y}_1$  is the average of the natural logarithms of the inside samples and  $\bar{Y}_0$  is the average of the natural logarithms of the outside samples,  $n_1$  is the number of inside samples and  $n_0$  is the number of outside samples. The response action is considered complete if Z is less than or equal to 1.65.

NOTE: When no fibers are counted, the calculated detection limit for that analysis is inserted for the concentration.

2. If the abatement site does not satisfy either (1) or (2) of this Section C, the site must be recleaned and a new set of samples collected.

#### D. Sequence for Analyzing Samples

It is possible to determine completion of the response action without analyzing all samples. Also, at any point in the process, a decision may be made to terminate the analysis of existing samples, reclean the abatement site, and collect a new set of samples. The following sequence is outlined to minimize the number of analyses needed to reach a decision.

1. Analyze the inside samples.

2. If at least 1,199 L of air for a 25 mm filter or 2,799 L of air for a 37 mm filter is collected for each inside sample and the arithmetic mean concentration of structures per square millimeter of filter is less than or equal to 70 s/mm<sup>2</sup>, the response action is complete and no further analysis is needed.

3. If less than 1,199 L of air for a 25 mm filter or 2,799 L of air for a 37 mm filter is collected for any of the inside samples, or the arithmetic mean concentration of structures per square millimeter of filter is greater than 70 s/mm<sup>2</sup>, analyze the three blanks.

4. If the arithmetic mean concentration of structures per square millimeter on the blank filters is greater than 70 s/mm<sup>2</sup>, terminate the analysis, identify and correct the source of blank contamination, and collect a new set of samples.

5. If the arithmetic mean concentration of structures per square millimeter on the blank filters is less than or equal to 70 s/mm<sup>2</sup>, analyze the outside samples and perform the Z-test.

6. If the Z-statistic is less than or equal to 1.65, the response action is complete. If the Z-statistic is greater than 1.65, reclean the abatement site and collect a new set of samples.

[52 FR 41857, Oct. 30, 1987]

APPENDIX B TO SUBPART E OF PART 763  
[RESERVED]

APPENDIX C TO SUBPART E OF PART  
763—ASBESTOS MODEL ACCREDITA-  
TION PLAN

*1. Asbestos Model Accreditation Plan for States*

The Asbestos Model Accreditation Plan (MAP) for States has eight components:

- (A) Definitions
- (B) Initial Training
- (C) Examinations
- (D) Continuing Education
- (E) Qualifications
- (F) Recordkeeping Requirements for Training Providers
- (G) Deaccreditation
- (H) Reciprocity
- (I) Electronic reporting

A. Definitions

For purposes of Appendix C:

1. “Friable asbestos-containing material (ACM)” means any material containing more than one percent asbestos which has been applied on ceilings, walls, structural members, piping, duct work, or any other part of a building, which when dry, may be crumbled, pulverized, or reduced to powder by hand pressure. The term includes non-friable asbestos-containing material after such previously non-friable material becomes damaged to the extent that when dry it may be crumbled, pulverized, or reduced to powder by hand pressure.

2. “Friable asbestos-containing building material (ACBM)” means any friable ACM that is in or on interior structural members or other parts of a school or public and commercial building.

3. “Inspection” means an activity undertaken in a school building, or a public and commercial building, to determine the presence or location, or to assess the condition of, friable or non-friable asbestos-containing building material (ACBM) or suspected ACBM, whether by visual or physical examination, or by collecting samples of such material. This term includes reinspections of friable and non-friable known or assumed ACBM which has been previously identified. The term does not include the following:

- a. Periodic surveillance of the type described in 40 CFR 763.92(b) solely for the purpose of recording or reporting a change in the condition of known or assumed ACBM;
- b. Inspections performed by employees or agents of Federal, State, or local government solely for the purpose of determining

compliance with applicable statutes or regulations; or

c. visual inspections of the type described in 40 CFR 763.90(i) solely for the purpose of determining completion of response actions.

4. “Major fiber release episode” means any uncontrolled or unintentional disturbance of ACBM, resulting in a visible emission, which involves the falling or dislodging of more than 3 square or linear feet of friable ACBM.

5. “Minor fiber release episode” means any uncontrolled or unintentional disturbance of ACBM, resulting in a visible emission, which involves the falling or dislodging of 3 square or linear feet or less of friable ACBM.

6. “Public and commercial building” means the interior space of any building which is not a school building, except that the term does not include any residential apartment building of fewer than 10 units or detached single-family homes. The term includes, but is not limited to: industrial and office buildings, residential apartment buildings and condominiums of 10 or more dwelling units, government-owned buildings, colleges, museums, airports, hospitals, churches, preschools, stores, warehouses and factories. Interior space includes exterior hallways connecting buildings, porticos, and mechanical systems used to condition interior space.

7. “Response action” means a method, including removal, encapsulation, enclosure, repair, and operation and maintenance, that protects human health and the environment from friable ACBM.

8. “Small-scale, short-duration activities (SSSD)” are tasks such as, but not limited to:

- a. Removal of asbestos-containing insulation on pipes.
- b. Removal of small quantities of asbestos-containing insulation on beams or above ceilings.
- c. Replacement of an asbestos-containing gasket on a valve.
- d. Installation or removal of a small section of drywall.
- e. Installation of electrical conduits through or proximate to asbestos-containing materials.

SSSD can be further defined by the following considerations:

- f. Removal of small quantities of ACM only if required in the performance of another maintenance activity not intended as asbestos abatement.
- g. Removal of asbestos-containing thermal system insulation not to exceed amounts greater than those which can be contained in a single glove bag.
- h. Minor repairs to damaged thermal system insulation which do not require removal.
- i. Repairs to a piece of asbestos-containing wallboard.

j. Repairs, involving encapsulation, enclosure, or removal, to small amounts of friable ACM only if required in the performance of emergency or routine maintenance activity and not intended solely as asbestos abatement. Such work may not exceed amounts greater than those which can be contained in a single prefabricated mini-enclosure. Such an enclosure shall conform spatially and geometrically to the localized work area, in order to perform its intended containment function.

#### B. Initial Training

Training requirements for purposes of accreditation are specified both in terms of required subjects of instruction and in terms of length of training. Each initial training course has a prescribed curriculum and number of days of training. One day of training equals 8 hours, including breaks and lunch. Course instruction must be provided by EPA or State-approved instructors. EPA or State instructor approval shall be based upon a review of the instructor's academic credentials and/or field experience in asbestos abatement.

Beyond the initial training requirements, individual States may wish to consider requiring additional days of training for purposes of supplementing hands-on activities or for reviewing relevant state regulations. States also may wish to consider the relative merits of a worker apprenticeship program. Further, they might consider more stringent minimum qualification standards for the approval of training instructors. EPA recommends that the enrollment in any given course be limited to 25 students so that adequate opportunities exist for individual hands-on experience.

States have the option to provide initial training directly or approve other entities to offer training. The following requirements are for the initial training of persons required to have accreditation under TSCA Title II.

Training requirements for each of the five accredited disciplines are outlined below. Persons in each discipline perform a different job function and distinct role. Inspectors identify and assess the condition of ACBM, or suspect ACBM. Management planners use data gathered by inspectors to assess the degree of hazard posed by ACBM in schools to determine the scope and timing of appropriate response actions needed for schools. Project designers determine how asbestos abatement work should be conducted. Lastly, workers and contractor/supervisors carry out and oversee abatement work. In addition, a recommended training curriculum is also presented for a sixth discipline, which is not federally-accredited, that of "Project Monitor." Each accredited discipline and training curriculum is separate and distinct from the others. A person

seeking accreditation in any of the five accredited MAP disciplines cannot attend two or more courses concurrently, but may attend such courses sequentially.

In several instances, initial training courses for a specific discipline (e.g., workers, inspectors) require hands-on training. For asbestos abatement contractor/supervisors and workers, hands-on training should include working with asbestos-substitute materials, fitting and using respirators, use of glovebags, donning protective clothing, and constructing a decontamination unit as well as other abatement work activities.

#### 1. WORKERS

A person must be accredited as a worker to carry out any of the following activities with respect to friable ACBM in a school or public and commercial building: (1) A response action other than a SSSD activity, (2) a maintenance activity that disturbs friable ACBM other than a SSSD activity, or (3) a response action for a major fiber release episode. All persons seeking accreditation as asbestos abatement workers shall complete at least a 4-day training course as outlined below. The 4-day worker training course shall include lectures, demonstrations, at least 14 hours of hands-on training, individual respirator fit testing, course review, and an examination. Hands-on training must permit workers to have actual experience performing tasks associated with asbestos abatement. A person who is otherwise accredited as a contractor/supervisor may perform in the role of a worker without possessing separate accreditation as a worker.

Because of cultural diversity associated with the asbestos workforce, EPA recommends that States adopt specific standards for the approval of foreign language courses for abatement workers. EPA further recommends the use of audio-visual materials to complement lectures, where appropriate.

The training course shall adequately address the following topics:

(a) *Physical characteristics of asbestos.* Identification of asbestos, aerodynamic characteristics, typical uses, and physical appearance, and a summary of abatement control options.

(b) *Potential health effects related to asbestos exposure.* The nature of asbestos-related diseases; routes of exposure; dose-response relationships and the lack of a safe exposure level; the synergistic effect between cigarette smoking and asbestos exposure; the latency periods for asbestos-related diseases; a discussion of the relationship of asbestos exposure to asbestosis, lung cancer, mesothelioma, and cancers of other organs.

(c) *Employee personal protective equipment.* Classes and characteristics of respirator



types; limitations of respirators; proper selection, inspection; donning, use, maintenance, and storage procedures for respirators; methods for field testing of the facepiece-to-face seal (positive and negative-pressure fit checks); qualitative and quantitative fit testing procedures; variability between field and laboratory protection factors that alter respiratory fit (e.g., facial hair); the components of a proper respiratory protection program; selection and use of personal protective clothing; use, storage, and handling of non-disposable clothing; and regulations covering personal protective equipment.

(d) *State-of-the-art work practices.* Proper work practices for asbestos abatement activities, including descriptions of proper construction; maintenance of barriers and decontamination enclosure systems; positioning of warning signs; lock-out of electrical and ventilation systems; proper working techniques for minimizing fiber release; use of wet methods; use of negative pressure exhaust ventilation equipment; use of high-efficiency particulate air (HEPA) vacuums; proper clean-up and disposal procedures; work practices for removal, encapsulation, enclosure, and repair of ACM; emergency procedures for sudden releases; potential exposure situations; transport and disposal procedures; and recommended and prohibited work practices.

(e) *Personal hygiene.* Entry and exit procedures for the work area; use of showers; avoidance of eating, drinking, smoking, and chewing (gum or tobacco) in the work area; and potential exposures, such as family exposure.

(f) *Additional safety hazards.* Hazards encountered during abatement activities and how to deal with them, including electrical hazards, heat stress, air contaminants other than asbestos, fire and explosion hazards, scaffold and ladder hazards, slips, trips, and falls, and confined spaces.

(g) *Medical monitoring.* OSHA and EPA Worker Protection Rule requirements for physical examinations, including a pulmonary function test, chest X-rays, and a medical history for each employee.

(h) *Air monitoring.* Procedures to determine airborne concentrations of asbestos fibers, focusing on how personal air sampling is performed and the reasons for it.

(i) *Relevant Federal, State, and local regulatory requirements, procedures, and standards.* With particular attention directed at relevant EPA, OSHA, and State regulations concerning asbestos abatement workers.

(j) *Establishment of respiratory protection programs.*

(k) *Course review.* A review of key aspects of the training course.

## 2. CONTRACTOR/SUPERVISORS

A person must be accredited as a contractor/supervisor to supervise any of the following activities with respect to friable ACBM in a school or public and commercial building: (1) A response action other than a SSSD activity, (2) a maintenance activity that disturbs friable ACBM other than a SSSD activity, or (3) a response action for a major fiber release episode. All persons seeking accreditation as asbestos abatement contractor/supervisors shall complete at least a 5-day training course as outlined below. The training course must include lectures, demonstrations, at least 14 hours of hands-on training, individual respirator fit testing, course review, and a written examination. Hands-on training must permit supervisors to have actual experience performing tasks associated with asbestos abatement.

EPA recommends the use of audiovisual materials to complement lectures, where appropriate.

Asbestos abatement supervisors include those persons who provide supervision and direction to workers performing response actions. Supervisors may include those individuals with the position title of foreman, working foreman, or leadman pursuant to collective bargaining agreements. At least one supervisor is required to be at the work-site at all times while response actions are being conducted. Asbestos workers must have access to accredited supervisors throughout the duration of the project.

The contractor/supervisor training course shall adequately address the following topics:

(a) *The physical characteristics of asbestos and asbestos-containing materials.* Identification of asbestos, aerodynamic characteristics, typical uses, physical appearance, a review of hazard assessment considerations, and a summary of abatement control options.

(b) *Potential health effects related to asbestos exposure.* The nature of asbestos-related diseases; routes of exposure; dose-response relationships and the lack of a safe exposure level; synergism between cigarette smoking and asbestos exposure; and latency period for diseases.

(c) *Employee personal protective equipment.* Classes and characteristics of respirator types; limitations of respirators; proper selection, inspection, donning, use, maintenance, and storage procedures for respirators; methods for field testing of the facepiece-to-face seal (positive and negative-pressure fit checks); qualitative and quantitative fit testing procedures; variability between field and laboratory protection factors that alter respiratory fit (e.g., facial hair); the components of a proper respiratory protection program; selection and use of personal protective clothing; and use, storage,

and handling of non-disposable clothing; and regulations covering personal protective equipment.

(d) *State-of-the-art work practices.* Proper work practices for asbestos abatement activities, including descriptions of proper construction and maintenance of barriers and decontamination enclosure systems; positioning of warning signs; lock-out of electrical and ventilation systems; proper working techniques for minimizing fiber release; use of wet methods; use of negative pressure exhaust ventilation equipment; use of HEPA vacuums; and proper clean-up and disposal procedures. Work practices for removal, encapsulation, enclosure, and repair of ACM; emergency procedures for unplanned releases; potential exposure situations; transport and disposal procedures; and recommended and prohibited work practices. New abatement-related techniques and methodologies may be discussed.

(e) *Personal hygiene.* Entry and exit procedures for the work area; use of showers; and avoidance of eating, drinking, smoking, and chewing (gum or tobacco) in the work area. Potential exposures, such as family exposure, shall also be included.

(f) *Additional safety hazards.* Hazards encountered during abatement activities and how to deal with them, including electrical hazards, heat stress, air contaminants other than asbestos, fire and explosion hazards, scaffold and ladder hazards, slips, trips, and falls, and confined spaces.

(g) *Medical monitoring.* OSHA and EPA Worker Protection Rule requirements for physical examinations, including a pulmonary function test, chest X-rays and a medical history for each employee.

(h) *Air monitoring.* Procedures to determine airborne concentrations of asbestos fibers, including descriptions of aggressive air sampling, sampling equipment and methods, reasons for air monitoring, types of samples and interpretation of results.

EPA recommends that transmission electron microscopy (TEM) be used for analysis of final air clearance samples, and that sample analyses be performed by laboratories accredited by the National Institute of Standards and Technology's (NIST) National Voluntary Laboratory Accreditation Program (NVLAP).

(i) *Relevant Federal, State, and local regulatory requirements, procedures, and standards, including:*

(i) Requirements of TSCA Title II.

(ii) National Emission Standards for Hazardous Air Pollutants (40 CFR part 61), Subparts A (General Provisions) and M (National Emission Standard for Asbestos).

(iii) OSHA standards for permissible exposure to airborne concentrations of asbestos fibers and respiratory protection (29 CFR 1910.134).

(iv) OSHA Asbestos Construction Standard (29 CFR 1926.58). (v) EPA Worker Protection Rule, (40 CFR part 763, Subpart G).

(j) *Respiratory Protection Programs and Medical Monitoring Programs.*

(k) *Insurance and liability issues.* Contractor issues; worker's compensation coverage and exclusions; third-party liabilities and defenses; insurance coverage and exclusions.

(l) *Recordkeeping for asbestos abatement projects.* Records required by Federal, State, and local regulations; records recommended for legal and insurance purposes.

(m) *Supervisory techniques for asbestos abatement activities.* Supervisory practices to enforce and reinforce the required work practices and discourage unsafe work practices.

(n) *Contract specifications.* Discussions of key elements that are included in contract specifications.

(o) *Course review.* A review of key aspects of the training course.

### 3. INSPECTOR

All persons who inspect for ACBM in schools or public and commercial buildings must be accredited. All persons seeking accreditation as an inspector shall complete at least a 3-day training course as outlined below. The course shall include lectures, demonstrations, 4 hours of hands-on training, individual respirator fit-testing, course review, and a written examination.

EPA recommends the use of audiovisual materials to complement lectures, where appropriate. Hands-on training should include conducting a simulated building walk-through inspection and respirator fit testing. The inspector training course shall adequately address the following topics:

(a) *Background information on asbestos.* Identification of asbestos, and examples and discussion of the uses and locations of asbestos in buildings; physical appearance of asbestos.

(b) *Potential health effects related to asbestos exposure.* The nature of asbestos-related diseases; routes of exposure; dose-response relationships and the lack of a safe exposure level; the synergistic effect between cigarette smoking and asbestos exposure; the latency periods for asbestos-related diseases; a discussion of the relationship of asbestos exposure to asbestosis, lung cancer, mesothelioma, and cancers of other organs.

(c) *Functions/qualifications and role of inspectors.* Discussions of prior experience and qualifications for inspectors and management planners; discussions of the functions of an accredited inspector as compared to those of an accredited management planner; discussion of inspection process including inventory of ACM and physical assessment.

(d) *Legal liabilities and defenses.* Responsibilities of the inspector and management

planner; a discussion of comprehensive general liability policies, claims-made, and occurrence policies, environmental and pollution liability policy clauses; state liability insurance requirements; bonding and the relationship of insurance availability to bond availability.

(e) *Understanding building systems.* The interrelationship between building systems, including: an overview of common building physical plan layout; heat, ventilation, and air conditioning (HVAC) system types, physical organization, and where asbestos is found on HVAC components; building mechanical systems, their types and organization, and where to look for asbestos on such systems; inspecting electrical systems, including appropriate safety precautions; reading blueprints and as-built drawings.

(f) *Public/employee/building occupant relations.* Notifying employee organizations about the inspection; signs to warn building occupants; tact in dealing with occupants and the press; scheduling of inspections to minimize disruptions; and education of building occupants about actions being taken.

(g) *Pre-inspection planning and review of previous inspection records.* Scheduling the inspection and obtaining access; building record review; identification of probable homogeneous areas from blueprints or as-built drawings; consultation with maintenance or building personnel; review of previous inspection, sampling, and abatement records of a building; the role of the inspector in exclusions for previously performed inspections.

(h) *Inspecting for friable and non-friable ACM and assessing the condition of friable ACM.* Procedures to follow in conducting visual inspections for friable and non-friable ACM; types of building materials that may contain asbestos; touching materials to determine friability; open return air plenums and their importance in HVAC systems; assessing damage, significant damage, potential damage, and potential significant damage; amount of suspected ACM, both in total quantity and as a percentage of the total area; type of damage; accessibility; material's potential for disturbance; known or suspected causes of damage or significant damage; and deterioration as assessment factors.

(i) *Bulk sampling/documentation of asbestos.* Detailed discussion of the "Simplified Sampling Scheme for Friable Surfacing Materials (EPA 560/5-85-030a October 1985)"; techniques to ensure sampling in a randomly distributed manner for other than friable surfacing materials; sampling of non-friable materials; techniques for bulk sampling; inspector's sampling and repair equipment; patching or repair of damage from sampling; discussion of polarized light microscopy; choosing an accredited laboratory to analyze bulk samples; quality control and quality as-

urance procedures. EPA's recommendation that all bulk samples collected from school or public and commercial buildings be analyzed by a laboratory accredited under the NVLAP administered by NIST.

(j) *Inspector respiratory protection and personal protective equipment.* Classes and characteristics of respirator types; limitations of respirators; proper selection, inspection; donning, use, maintenance, and storage procedures for respirators; methods for field testing of the facepiece-to-face seal (positive and negative-pressure fit checks); qualitative and quantitative fit testing procedures; variability between field and laboratory protection factors that alter respiratory fit (e.g., facial hair); the components of a proper respiratory protection program; selection and use of personal protective clothing; use, storage, and handling of non-disposable clothing.

(k) *Recordkeeping and writing the inspection report.* Labeling of samples and keying sample identification to sampling location; recommendations on sample labeling; detailing of ACM inventory; photographs of selected sampling areas and examples of ACM condition; information required for inclusion in the management plan required for school buildings under TSCA Title II, section 203 (i)(1). EPA recommends that States develop and require the use of standardized forms for recording the results of inspections in schools or public or commercial buildings, and that the use of these forms be incorporated into the curriculum of training conducted for accreditation.

(l) *Regulatory review.* The following topics should be covered: National Emission Standards for Hazardous Air Pollutants (NESHAP; 40 CFR part 61, Subparts A and M); EPA Worker Protection Rule (40 CFR part 763, Subpart G); OSHA Asbestos Construction Standard (29 CFR 1926.58); OSHA respirator requirements (29 CFR 1910.134); the Asbestos-Containing Materials in School Rule (40 CFR part 763, Subpart E; applicable State and local regulations, and differences between Federal and State requirements where they apply, and the effects, if any, on public and nonpublic schools or commercial or public buildings.

(m) *Field trip.* This includes a field exercise, including a walk-through inspection; on-site discussion about information gathering and the determination of sampling locations; on-site practice in physical assessment; classroom discussion of field exercise.

(n) *Course review.* A review of key aspects of the training course.

#### 4. MANAGEMENT PLANNER

All persons who prepare management plans for schools must be accredited. All persons seeking accreditation as management planners shall complete a 3-day inspector training course as outlined above and a 2-day

management planner training course. Possession of current and valid inspector accreditation shall be a prerequisite for admission to the management planner training course. The management planner course shall include lectures, demonstrations, course review, and a written examination.

EPA recommends the use of audiovisual materials to complement lectures, where appropriate.

TSCA Title II does not require accreditation for persons performing the management planner role in public and commercial buildings. Nevertheless, such persons may find this training and accreditation helpful in preparing them to design or administer asbestos operations and maintenance programs for public and commercial buildings.

The management planner training course shall adequately address the following topics:

(a) *Course overview.* The role and responsibilities of the management planner; operations and maintenance programs; setting work priorities; protection of building occupants.

(b) *Evaluation/interpretation of survey results.* Review of TSCA Title II requirements for inspection and management plans for school buildings as given in section 203(i)(1) of TSCA Title II; interpretation of field data and laboratory results; comparison of field inspector's data sheet with laboratory results and site survey.

(c) *Hazard assessment.* Amplification of the difference between physical assessment and hazard assessment; the role of the management planner in hazard assessment; explanation of significant damage, damage, potential damage, and potential significant damage; use of a description (or decision tree) code for assessment of ACM; assessment of friable ACM; relationship of accessibility, vibration sources, use of adjoining space, and air plenums and other factors to hazard assessment.

(d) *Legal implications.* Liability; insurance issues specific to planners; liabilities associated with interim control measures, in-house maintenance, repair, and removal; use of results from previously performed inspections.

(e) *Evaluation and selection of control options.* Overview of encapsulation, enclosure, interim operations and maintenance, and removal; advantages and disadvantages of each method; response actions described via a decision tree or other appropriate method; work practices for each response action; staging and prioritizing of work in both vacant and occupied buildings; the need for containment barriers and decontamination in response actions.

(f) *Role of other professionals.* Use of industrial hygienists, engineers, and architects in developing technical specifications for response actions; any requirements that may exist for architect sign-off of plans; team ap-

proach to design of high-quality job specifications.

(g) *Developing an operations and maintenance (O&M) plan.* Purpose of the plan; discussion of applicable EPA guidance documents; what actions should be taken by custodial staff; proper cleaning procedures; steam cleaning and HEPA vacuuming; reducing disturbance of ACM; scheduling O&M for off-hours; rescheduling or canceling renovation in areas with ACM; boiler room maintenance; disposal of ACM; in-house procedures for ACM—bridging and penetrating encapsulants; pipe fittings; metal sleeves; polyvinyl chloride (PVC), canvas, and wet wraps; muslin with straps, fiber mesh cloth; mineral wool, and insulating cement; discussion of employee protection programs and staff training; case study in developing an O&M plan (development, implementation process, and problems that have been experienced).

(h) *Regulatory review.* Focusing on the OSHA Asbestos Construction Standard found at 29 CFR 1926.58; the National Emission Standard for Hazardous Air Pollutants (NESHAP) found at 40 CFR part 61, Subparts A (General Provisions) and M (National Emission Standard for Asbestos); EPA Worker Protection Rule found at 40 CFR part 763, Subpart G; TSCA Title II; applicable State regulations.

(i) *Recordkeeping for the management planner.* Use of field inspector's data sheet along with laboratory results; on-going recordkeeping as a means to track asbestos disturbance; procedures for recordkeeping. EPA recommends that States require the use of standardized forms for purposes of management plans and incorporate the use of such forms into the initial training course for management planners.

(j) *Assembling and submitting the management plan.* Plan requirements for schools in TSCA Title II section 203(i)(1); the management plan as a planning tool.

(k) *Financing abatement actions.* Economic analysis and cost estimates; development of cost estimates; present costs of abatement versus future operation and maintenance costs; Asbestos School Hazard Abatement Act grants and loans.

(l) *Course review.* A review of key aspects of the training course.

##### 5. PROJECT DESIGNER

A person must be accredited as a project designer to design any of the following activities with respect to friable ACM in a school or public and commercial building: (1) A response action other than a SSSD maintenance activity, (2) a maintenance activity that disturbs friable ACM other than a SSSD maintenance activity, or (3) a response action for a major fiber release episode. All persons seeking accreditation as a project designer shall complete at least a minimum

3-day training course as outlined below. The project designer course shall include lectures, demonstrations, a field trip, course review and a written examination.

EPA recommends the use of audiovisual materials to complement lectures, where appropriate.

The abatement project designer training course shall adequately address the following topics:

(a) *Background information on asbestos.* Identification of asbestos; examples and discussion of the uses and locations of asbestos in buildings; physical appearance of asbestos.

(b) *Potential health effects related to asbestos exposure.* Nature of asbestos-related diseases; routes of exposure; dose-response relationships and the lack of a safe exposure level; the synergistic effect between cigarette smoking and asbestos exposure; the latency period of asbestos-related diseases; a discussion of the relationship between asbestos exposure and asbestosis, lung cancer, mesothelioma, and cancers of other organs.

(c) *Overview of abatement construction projects.* Abatement as a portion of a renovation project; OSHA requirements for notification of other contractors on a multi-employer site (29 CFR 1926.58).

(d) *Safety system design specifications.* Design, construction, and maintenance of containment barriers and decontamination enclosure systems; positioning of warning signs; electrical and ventilation system lock-out; proper working techniques for minimizing fiber release; entry and exit procedures for the work area; use of wet methods; proper techniques for initial cleaning; use of negative-pressure exhaust ventilation equipment; use of HEPA vacuums; proper clean-up and disposal of asbestos; work practices as they apply to encapsulation, enclosure, and repair; use of glove bags and a demonstration of glove bag use.

(e) *Field trip.* A visit to an abatement site or other suitable building site, including on-site discussions of abatement design and building walk-through inspection. Include discussion of rationale for the concept of functional spaces during the walk-through.

(f) *Employee personal protective equipment.* Classes and characteristics of respirator types; limitations of respirators; proper selection, inspection; donning, use, maintenance, and storage procedures for respirators; methods for field testing of the facepiece-to-face seal (positive and negative-pressure fit checks); qualitative and quantitative fit testing procedures; variability between field and laboratory protection factors that alter respiratory fit (e.g., facial hair); the components of a proper respiratory protection program; selection and use of personal protective clothing; use, storage, and handling of non-disposable clothing.

(g) *Additional safety hazards.* Hazards encountered during abatement activities and

how to deal with them, including electrical hazards, heat stress, air contaminants other than asbestos, fire, and explosion hazards.

(h) *Fiber aerodynamics and control.* Aerodynamic characteristics of asbestos fibers; importance of proper containment barriers; settling time for asbestos fibers; wet methods in abatement; aggressive air monitoring following abatement; aggressive air movement and negative-pressure exhaust ventilation as a clean-up method.

(i) *Designing abatement solutions.* Discussions of removal, enclosure, and encapsulation methods; asbestos waste disposal.

(j) *Final clearance process.* Discussion of the need for a written sampling rationale for aggressive final air clearance; requirements of a complete visual inspection; and the relationship of the visual inspection to final air clearance.

EPA recommends the use of TEM for analysis of final air clearance samples. These samples should be analyzed by laboratories accredited under the NIST NVLAP.

(k) *Budgeting/cost estimating.* Development of cost estimates; present costs of abatement versus future operation and maintenance costs; setting priorities for abatement jobs to reduce costs.

(l) *Writing abatement specifications.* Preparation of and need for a written project design; means and methods specifications versus performance specifications; design of abatement in occupied buildings; modification of guide specifications for a particular building; worker and building occupant health/medical considerations; replacement of ACM with non-asbestos substitutes.

(m) *Preparing abatement drawings.* Significance and need for drawings, use of as-built drawings as base drawings; use of inspection photographs and on-site reports; methods of preparing abatement drawings; diagramming containment barriers; relationship of drawings to design specifications; particular problems related to abatement drawings.

(n) *Contract preparation and administration.*

(o) *Legal/liabilities/defenses.* Insurance considerations; bonding; hold-harmless clauses; use of abatement contractor's liability insurance; claims made versus occurrence policies.

(p) *Replacement.* Replacement of asbestos with asbestos-free substitutes.

(q) *Role of other consultants.* Development of technical specification sections by industrial hygienists or engineers; the multi-disciplinary team approach to abatement design.

(r) *Occupied buildings.* Special design procedures required in occupied buildings; education of occupants; extra monitoring recommendations; staging of work to minimize occupant exposure; scheduling of renovation to minimize exposure.

(s) *Relevant Federal, State, and local regulatory requirements, procedures and standards, including, but not limited to:*

- (i) Requirements of TSCA Title II.
- (ii) National Emission Standards for Hazardous Air Pollutants, (40 CFR part 61) subparts A (General Provisions) and M (National Emission Standard for Asbestos).
- (iii) OSHA Respirator Standard found at 29 CFR 1910.134.
- (iv) EPA Worker Protection Rule found at 40 CFR part 763, subpart G.
- (v) OSHA Asbestos Construction Standard found at 29 CFR 1926.58.
- (vi) OSHA Hazard Communication Standard found at 29 CFR 1926.59.
- (t) *Course review.* A review of key aspects of the training course.

#### 6. PROJECT MONITOR

EPA recommends that States adopt training and accreditation requirements for persons seeking to perform work as project monitors. Project monitors observe abatement activities performed by contractors and generally serve as a building owner's representative to ensure that abatement work is completed according to specification and in compliance with all relevant statutes and regulations. They may also perform the vital role of air monitoring for purposes of determining final clearance. EPA recommends that a State seeking to accredit individuals as project monitors consider adopting a minimum 5-day training course covering the topics outlined below. The course outlined below consists of lectures and demonstrations, at least 6 hours of hands-on training, course review, and a written examination. The hands-on training component might be satisfied by having the student simulate participation in or performance of any of the relevant job functions or activities (or by incorporation of the workshop component described in item "n" below of this unit).

EPA recommends that the project monitor training course adequately address the following topics:

- (a) *Roles and responsibilities of the project monitor.* Definition and responsibilities of the project monitor, including regulatory/specification compliance monitoring, air monitoring, conducting visual inspections, and final clearance monitoring.
- (b) *Characteristics of asbestos and asbestos-containing materials.* Typical uses of asbestos; physical appearance of asbestos; review of asbestos abatement and control techniques; presentation of the health effects of asbestos exposure, including routes of exposure, dose-response relationships, and latency periods for asbestos-related diseases.
- (c) *Federal asbestos regulations.* Overview of pertinent EPA regulations, including: NESHAP, 40 CFR part 61, subparts A and M; AHERA, 40 CFR part 763, subpart E; and the

EPA Worker Protection Rule, 40 CFR part 763, subpart G. Overview of pertinent OSHA regulations, including: Construction Industry Standard for Asbestos, 29 CFR 1926.58; Respirator Standard, 29 CFR 1910.134; and the Hazard Communication Standard, 29 CFR 1926.59. Applicable State and local asbestos regulations; regulatory interrelationships.

(d) *Understanding building construction and building systems.* Building construction basics, building physical plan layout; understanding building systems (HVAC, electrical, etc.); layout and organization, where asbestos is likely to be found on building systems; renovations and the effect of asbestos abatement on building systems.

(e) *Asbestos abatement contracts, specifications, and drawings.* Basic provisions of the contract; relationships between principle parties, establishing chain of command; types of specifications, including means and methods, performance, and proprietary and nonproprietary; reading and interpreting records and abatement drawings; discussion of change orders; common enforcement responsibilities and authority of project monitor.

(f) *Response actions and abatement practices.* Pre-work inspections; pre-work considerations, precleaning of the work area, removal of furniture, fixtures, and equipment; shutdown/modification of building systems; construction and maintenance of containment barriers, proper demarcation of work areas; work area entry/exit, hygiene practices; determining the effectiveness of air filtration equipment; techniques for minimizing fiber release, wet methods, continuous cleaning; abatement methods other than removal; abatement area clean-up procedures; waste transport and disposal procedures; contingency planning for emergency response.

(g) *Asbestos abatement equipment.* Typical equipment found on an abatement project; air filtration devices, vacuum systems, negative pressure differential monitoring; HEPA filtration units, theory of filtration, design/construction of HEPA filtration units, qualitative and quantitative performance of HEPA filtration units, sizing the ventilation requirements, location of HEPA filtration units, qualitative and quantitative tests of containment barrier integrity; best available technology.

(h) *Personal protective equipment.* Proper selection of respiratory protection; classes and characteristics of respirator types, limitations of respirators; proper use of other safety equipment, protective clothing selection, use, and proper handling, hard/bump hats, safety shoes; breathing air systems, high pressure v. low pressure, testing for Grade D air, determining proper backup air volumes.

(i) *Air monitoring strategies.* Sampling equipment, sampling pumps (low v. high volume), flow regulating devices (critical and

limiting orifices), use of fibrous aerosol monitors on abatement projects; sampling media, types of filters, types of cassettes, filter orientation, storage and shipment of filters; calibration techniques, primary calibration standards, secondary calibration standards, temperature/pressure effects, frequency of calibration, recordkeeping and field work documentation, calculations; air sample analysis, techniques available and limitations of AHERA on their use, transmission electron microscopy (background to sample preparation and analysis, air sample conditions which prohibit analysis, EPA's recommended technique for analysis of final air clearance samples), phase contrast microscopy (background to sample preparation, and AHERA's limits on the use of phase contrast microscopy), what each technique measures; analytical methodologies, AHERA TEM protocol, NIOSH 7400, OSHA reference method (non clearance), EPA recommendation for clearance (TEM); sampling strategies for clearance monitoring, types of air samples (personal breathing zone v. fixed-station area) sampling location and objectives (pre-abatement, during abatement, and clearance monitoring), number of samples to be collected, minimum and maximum air volumes, clearance monitoring (post-visual-inspection) (number of samples required, selection of sampling locations, period of sampling, aggressive sampling, interpretations of sampling results, calculations), quality assurance; special sampling problems, crawl spaces, acceptable samples for laboratory analysis, sampling in occupied buildings (barrier monitoring).

(j) *Safety and health issues other than asbestos.* Confined-space entry, electrical hazards, fire and explosion concerns, ladders and scaffolding, heat stress, air contaminants other than asbestos, fall hazards, hazardous materials on abatement projects.

(k) *Conducting visual inspections.* Inspections during abatement, visual inspections using the ASTM E1368 document; conducting inspections for completeness of removal; discussion of "how clean is clean?"

(l) *Legal responsibilities and liabilities of project monitors.* Specification enforcement capabilities; regulatory enforcement; licensing; powers delegated to project monitors through contract documents.

(m) *Recordkeeping and report writing.* Developing project logs/daily logs (what should be included, who sees them); final report preparation; recordkeeping under Federal regulations.

(n) *Workshops (6 hours spread over 3 days).* Contracts, specifications, and drawings: This workshop could consist of each participant being issued a set of contracts, specifications, and drawings and then being asked to answer questions and make recommendations to a project architect, engineer or to

the building owner based on given conditions and these documents.

*Air monitoring strategies/asbestos abatement equipment:* This workshop could consist of simulated abatement sites for which sampling strategies would have to be developed (i.e., occupied buildings, industrial situations). Through demonstrations and exhibition, the project monitor may also be able to gain a better understanding of the function of various pieces of equipment used on abatement projects (air filtration units, water filtration units, negative pressure monitoring devices, sampling pump calibration devices, etc.).

*Conducting visual inspections:* This workshop could consist, ideally, of an interactive video in which a participant is "taken through" a work area and asked to make notes of what is seen. A series of questions will be asked which are designed to stimulate a person's recall of the area. This workshop could consist of a series of two or three videos with different site conditions and different degrees of cleanliness.

#### C. Examinations

1. Each State shall administer a closed book examination or designate other entities such as State-approved providers of training courses to administer the closed-book examination to persons seeking accreditation who have completed an initial training course. Demonstration testing may also be included as part of the examination. A person seeking initial accreditation in a specific discipline must pass the examination for that discipline in order to receive accreditation. For example, a person seeking accreditation as an abatement project designer must pass the State's examination for abatement project designer.

States may develop their own examinations, have providers of training courses develop examinations, or use standardized examinations developed for purposes of accreditation under TSCA Title II. In addition, States may supplement standardized examinations with questions about State regulations. States may obtain commercially developed standardized examinations, develop standardized examinations independently, or do so in cooperation with other States, or with commercial or non-profit providers on a regional or national basis. EPA recommends the use of standardized, scientifically-validated testing instruments, which may be beneficial in terms of both promoting competency and in fostering accreditation reciprocity between States.

Each examination shall adequately cover the topics included in the training course for that discipline. Each person who completes a

## Environmental Protection Agency

## Pt. 763, Subpt. E, App. C

training course, passes the required examination, and fulfills whatever other requirements the State imposes must receive an accreditation certificate in a specific discipline. Whether a State directly issues accreditation certificates, or authorizes training providers to issue accreditation certificates, each certificate issued to an accredited person must contain the following minimum information:

- a. A unique certificate number
- b. Name of accredited person
- c. Discipline of the training course completed.
- d. Dates of the training course.
- e. Date of the examination.
- f. An expiration date of 1 year after the date upon which the person successfully completed the course and examination.
- g. The name, address, and telephone number of the training provider that issued the certificate.
- h. A statement that the person receiving the certificate has completed the requisite training for asbestos accreditation under TSCA Title II.

States or training providers who reaccredit persons based upon completion of required refresher training must also provide accreditation certificates with all of the above information, except the examination date may be omitted if a State does not require a refresher examination for reaccreditation.

Where a State licenses accredited persons but has authorized training providers to issue accreditation certificates, the State may issue licenses in the form of photo-identification cards. Where this applies, EPA recommends that the State licenses should include all of the same information required for the accreditation certificates. A State may also choose to issue photo-identification cards in addition to the required accreditation certificates.

Accredited persons must have their initial and current accreditation certificates at the location where they are conducting work.

2. The following are the requirements for examination in each discipline:

- a. Worker:
  - i. 50 multiple-choice questions
  - ii. Passing score: 70 percent correct
- b. Contractor/Supervisor:
  - i. 100 multiple-choice questions
  - ii. Passing score: 70 percent correct
- c. Inspector:
  - i. 50 Multiple-choice questions
  - ii. Passing score: 70 percent correct
- d. Management Planner:
  - i. 50 Multiple-choice questions
  - ii. Passing score: 70 percent correct
- e. Project Designer:
  - i. 100 multiple-choice questions
  - ii. Passing score: 70 percent correct

### D. Continuing Education

For all disciplines, a State's accreditation program shall include annual refresher training as a requirement for reaccreditation as indicated below:

1. Workers: One full day of refresher training.
2. Contractor/Supervisors: One full day of refresher training.
3. Inspectors: One half-day of refresher training.
4. Management Planners: One half-day of inspector refresher training and one half-day of refresher training for management planners.
5. Project Designers: One full day of refresher training.

The refresher courses shall be specific to each discipline. Refresher courses shall be conducted as separate and distinct courses and not combined with any other training during the period of the refresher course. For each discipline, the refresher course shall review and discuss changes in Federal, State, and local regulations, developments in state-of-the-art procedures, and a review of key aspects of the initial training course as determined by the State. After completing the annual refresher course, persons shall have their accreditation extended for an additional year from the date of the refresher course. A State may consider requiring persons to pass reaccreditation examinations at specific intervals (for example, every 3 years).

EPA recommends that States formally establish a 12-month grace period to enable formerly accredited persons with expired certificates to complete refresher training and have their accreditation status reinstated without having to re-take the initial training course.

### E. Qualifications

In addition to requiring training and an examination, a State may require candidates for accreditation to meet other qualification and/or experience standards that the State considers appropriate for some or all disciplines. States may choose to consider requiring qualifications similar to the examples outlined below for inspectors, management planners and project designers. States may modify these examples as appropriate. In addition, States may want to include some requirements based on experience in performing a task directly as a part of a job or in an apprenticeship role. They may also wish to consider additional criteria for the approval of training course instructors beyond those prescribed by EPA.

1. Inspectors: Qualifications - possess a high school diploma. States may want to require an Associate's Degree in specific fields (e.g., environmental or physical sciences).



2. Management Planners: Qualifications - Registered architect, engineer, or certified industrial hygienist or related scientific field.

3. Project Designers: Qualifications - registered architect, engineer, or certified industrial hygienist.

4. Asbestos Training Course Instructor: Qualifications - academic credentials and/or field experience in asbestos abatement.

EPA recommends that States prescribe minimum qualification standards for training instructors employed by training providers.

#### F. Recordkeeping Requirements for Training Providers

All approved providers of accredited asbestos training courses must comply with the following minimum recordkeeping requirements.

1. Training course materials. A training provider must retain copies of all instructional materials used in the delivery of the classroom training such as student manuals, instructor notebooks and handouts.

2. Instructor qualifications. A training provider must retain copies of all instructors' resumes, and the documents approving each instructor issued by either EPA or a State. Instructors must be approved by either EPA or a State before teaching courses for accreditation purposes. A training provider must notify EPA or the State, as appropriate, in advance whenever it changes course instructors. Records must accurately identify the instructors that taught each particular course for each date that a course is offered.

3. Examinations. A training provider must document that each person who receives an accreditation certificate for an initial training course has achieved a passing score on the examination. These records must clearly indicate the date upon which the exam was administered, the training course and discipline for which the exam was given, the name of the person who proctored the exam, a copy of the exam, and the name and test score of each person taking the exam. The topic and dates of the training course must correspond to those listed on that person's accreditation certificate. States may choose to apply these same requirements to examinations for refresher training courses.

4. Accreditation certificates. The training providers or States, whichever issues the accreditation certificate, shall maintain records that document the names of all persons who have been awarded certificates, their certificate numbers, the disciplines for which accreditation was conferred, training and expiration dates, and the training location. The training provider or State shall maintain the records in a manner that allows verification by telephone of the required information.

5. Verification of certificate information. EPA recommends that training providers of refresher training courses confirm that their students possess valid accreditation before granting course admission. EPA further recommends that training providers offering the initial management planner training course verify that students have met the prerequisite of possessing valid inspector accreditation at the time of course admission.

6. Records retention and access. (a) The training provider shall maintain all required records for a minimum of 3 years. The training provider, however, may find it advantageous to retain these records for a longer period of time.

(b) The training provider must allow reasonable access to all of the records required by the MAP, and to any other records which may be required by States for the approval of asbestos training providers or the accreditation of asbestos training courses, to both EPA and to State Agencies, on request. EPA encourages training providers to make this information equally accessible to the general public.

(c) If a training provider ceases to conduct training, the training provider shall notify the approving government body (EPA or the State) and give it the opportunity to take possession of that providers asbestos training records.

#### G. Deaccreditation

1. States must establish criteria and procedures for deaccrediting persons accredited as workers, contractor/supervisors, inspectors, management planners, and project designers. States must follow their own administrative procedures in pursuing deaccreditation actions. At a minimum, the criteria shall include:

(a) Performing work requiring accreditation at a job site without being in physical possession of initial and current accreditation certificates;

(b) Permitting the duplication or use of one's own accreditation certificate by another;

(c) Performing work for which accreditation has not been received; or

(d) Obtaining accreditation from a training provider that does not have approval to offer training for the particular discipline from either EPA or from a State that has a contractor accreditation plan at least as stringent as the EPA MAP.

EPA may directly pursue deaccreditation actions without reliance on State deaccreditation or enforcement authority or actions. In addition to the above-listed situations, the Administrator may suspend or revoke the accreditation of persons who have been subject to a final order imposing a civil penalty or convicted under section 16 of TSCA, 15 U.S.C. 2615 or 2647, for violations of 40 CFR part 763, or section 113 of the Clean

## Environmental Protection Agency

## Pt. 763, Subpt. E, App. C

Air Act, 42 U.S.C. 7413, for violations of 40 CFR part 61, subpart M.

2. Any person who performs asbestos work requiring accreditation under section 206(a) of TSCA, 15 U.S.C. 2646(a), without such accreditation is in violation of TSCA. The following persons are not accredited for purposes of section 206(a) of TSCA:

(a) Any person who obtains accreditation through fraudulent representation of training or examination documents;

(b) Any person who obtains training documentation through fraudulent means;

(c) Any person who gains admission to and completes refresher training through fraudulent representation of initial or previous refresher training documentation; or

(d) Any person who obtains accreditation through fraudulent representation of accreditation requirements such as education, training, professional registration, or experience.

### H. Reciprocity

EPA recommends that each State establish reciprocal arrangements with other States that have established accreditation programs that meet or exceed the requirements of the MAP. Such arrangements might address cooperation in licensing determinations, the review and approval of training programs and/or instructors, candidate testing and exam administration, curriculum development, policy formulation, compliance monitoring, and the exchange of information and data. The benefits to be derived from these arrangements include a potential cost-savings from the reduction of duplicative activity and the attainment of a more professional accredited workforce as States are able to refine and improve the effectiveness of their programs based upon the experience and methods of other States.

### I. Electronic Reporting

States that choose to receive electronic documents must include, at a minimum, the requirements of 40 CFR Part 3—(Electronic reporting) in their programs.

### II. EPA Approval Process for State Accreditation Programs

A. States may seek approval for a single discipline or all disciplines as specified in the MAP. For example, a State that currently only requires worker accreditation may receive EPA approval for that discipline alone. EPA encourages States that currently do not have accreditation requirements for all disciplines required under section 206(b)(2) of TSCA, 15 U.S.C. 2646(b)(2), to seek EPA approval for those disciplines the State does accredit. As States establish accreditation requirements for the remaining disciplines, the requested information outlined below should be submitted to EPA as soon as

possible. Any State that had an accreditation program approved by EPA under an earlier version of the MAP may follow the same procedures to obtain EPA approval of their accreditation program under this MAP.

B. Partial approval of a State Program for the accreditation of one or more disciplines does not mean that the State is in full compliance with TSCA where the deadline for that State to have adopted a State Plan no less stringent than the MAP has already passed. State Programs which are at least as stringent as the MAP for one or more of the accredited disciplines may, however, accredit persons in those disciplines only.

C. States seeking EPA approval or re-approval of accreditation programs shall submit the following information to the Regional Asbestos Coordinator at their EPA Regional office:

1. A copy of the legislation establishing or upgrading the State's accreditation program (if applicable).

2. A copy of the State's accreditation regulations or revised regulations.

3. A letter to the Regional Asbestos Coordinator that clearly indicates how the State meets the program requirements of this MAP. Addresses for each of the Regional Asbestos Coordinators are shown below:

EPA, Region I, (ATC-111) Asbestos Coordinator, JFK Federal Bldg., Boston, MA 02203-2211, (617) 565-3836.

EPA, Region II, (MS-500), Asbestos Coordinator, 2890 Woodbridge Ave., Edison, NJ 08837-3679, (908) 321-6671.

EPA, Region III, (3AT-33), Asbestos Coordinator, 841 Chestnut Bldg., Philadelphia, PA 19107, (215) 597-3160.

EPA, Region IV, Asbestos Coordinator, 345 Courtland St., N.E., Atlanta, GA 30365, (404) 347-5014.

EPA, Region V, (SP-14J), Asbestos Coordinator, 77 W. Jackson Blvd., Chicago, IL 60604-3590, (312) 886-6003.

EPA, Region VI, (6T-PT), Asbestos Coordinator, 1445 Ross Ave. Dallas, TX 75202-2744, (214) 655-7244.

EPA, Region VII, (ARTX/ASBS), Asbestos Coordinator, 726 Minnesota Ave., Kansas City, KS 66101, (913) 551-7020.

EPA, Region VIII, (8AT-TS), Asbestos Coordinator, 1 Denver Place, Suite 500 999 - 18th St., Denver, CO 80202-2405, (303) 293-1442.

EPA, Region IX, (A-4-4), Asbestos Coordinator, 75 Hawthorne St., San Francisco, CA 94105, (415) 744-1128.

EPA, Region X, (AT-083), Asbestos Coordinator, 1200 Sixth Ave., Seattle, WA 98101, (206) 553-4762.

EPA maintains a listing of all those States that have applied for and received EPA approval for having accreditation requirements that are at least as stringent as the MAP for one or more disciplines. Any training courses

approved by an EPA-approved State Program are considered to be EPA-approved for purposes of accreditation.

### III. Approval of Training Courses

Individuals or groups wishing to sponsor training courses for disciplines required to be accredited under section 206(b)(1)(A) of TSCA, 15 U.S.C. 2646(b)(1)(A), may apply for approval from States that have accreditation program requirements that are at least as stringent as this MAP. For a course to receive approval, it must meet the requirements for the course as outlined in this MAP, and any other requirements imposed by the State from which approval is being sought. Courses that have been approved by a State with an accreditation program at least as stringent as this MAP are approved under section 206(a) of TSCA, 15 U.S.C. 2646(a), for that particular State, and also for any other State that does not have an accreditation program as stringent as this MAP.

#### A. Initial Training Course Approval

A training provider must submit the following minimum information to a State as part of its application for the approval of each training course:

1. The course provider's name, address, and telephone number.
2. A list of any other States that currently approve the training course.
3. The course curriculum.
4. A letter from the provider of the training course that clearly indicates how the course meets the MAP requirements for:
  - a. Length of training in days.
  - b. Amount and type of hands-on training.
  - c. Examination (length, format, and passing score).
  - d. Topics covered in the course.
5. A copy of all course materials (student manuals, instructor notebooks, handouts, etc.).
6. A detailed statement about the development of the examination used in the course.
7. Names and qualifications of all course instructors. Instructors must have academic and/or field experience in asbestos abatement.
8. A description of and an example of the numbered certificates issued to students who attend the course and pass the examination.

#### B. Refresher Training Course Approval

The following minimum information is required for approval of refresher training courses by States:

1. The length of training in half-days or days.
2. The topics covered in the course.
3. A copy of all course materials (student manuals, instructor notebooks, handouts, etc.).

4. The names and qualifications of all course instructors. Instructors must have academic and/or field experience in asbestos abatement.

5. A description of and an example of the numbered certificates issued to students who complete the refresher course and pass the examination, if required.

#### C. Withdrawal of Training Course Approval

States must establish criteria and procedures for suspending or withdrawing approval from accredited training programs. States should follow their own administrative procedures in pursuing actions for suspension or withdrawal of approval of training programs. At a minimum, the criteria shall include:

- (1) Misrepresentation of the extent of a training course's approval by a State or EPA;
- (2) Failure to submit required information or notifications in a timely manner;
- (3) Failure to maintain requisite records;
- (4) Falsification of accreditation records, instructor qualifications, or other accreditation information; or
- (5) Failure to adhere to the training standards and requirements of the EPA MAP or State Accreditation Program, as appropriate.

In addition to the criteria listed above, EPA may also suspend or withdraw a training course's approval where an approved training course instructor, or other person with supervisory authority over the delivery of training has been found in violation of other asbestos regulations administered by EPA. An administrative or judicial finding of violation, or execution of a consent agreement and order under 40 CFR 22.18, constitutes evidence of a failure to comply with relevant statutes or regulations. States may wish to adopt this criterion modified to include their own asbestos statutes or regulations. EPA may also suspend or withdraw approval of training programs where a training provider has submitted false information as a part of the self-certification required under Unit V.B. of the revised MAP.

Training course providers shall permit representatives of EPA or the State which approved their training courses to attend, evaluate, and monitor any training course without charge. EPA or State compliance inspection staff are not required to give advance notice of their inspections. EPA may suspend or withdraw State or EPA approval of a training course based upon the criteria specified in this Unit III.C.

#### IV. EPA Procedures for Suspension or Revocation of Accreditation or Training Course Approval.

A. If the Administrator decides to suspend or revoke the accreditation of any person or

## Environmental Protection Agency

## Pt. 763, Subpt. E, App. C

suspend or withdraw the approval of a training course, the Administrator will notify the affected entity of the following:

1. The grounds upon which the suspension, revocation, or withdrawal is based.

2. The time period during which the suspension, revocation, or withdrawal is effective, whether permanent or otherwise.

3. The conditions, if any, under which the affected entity may receive accreditation or approval in the future.

4. Any additional conditions which the Administrator may impose.

5. The opportunity to request a hearing prior to final Agency action to suspend or revoke accreditation or suspend or withdraw approval.

B. If a hearing is requested by the accredited person or training course provider pursuant to the preceding paragraph, the Administrator will:

1. Notify the affected entity of those assertions of law and fact upon which the action to suspend, revoke, or withdraw is based.

2. Provide the affected entity an opportunity to offer written statements of facts, explanations, comments, and arguments relevant to the proposed action.

3. Provide the affected entity such other procedural opportunities as the Administrator may deem appropriate to ensure a fair and impartial hearing.

4. Appoint an EPA attorney as Presiding Officer to conduct the hearing. No person shall serve as Presiding Officer if he or she has had any prior connection with the specific case.

C. The Presiding Officer appointed pursuant to the preceding paragraph shall:

1. Conduct a fair, orderly, and impartial hearing, without unnecessary delay.

2. Consider all relevant evidence, explanation, comment, and argument submitted pursuant to the preceding paragraph.

3. Promptly notify the affected entity of his or her decision and order. Such an order is a final Agency action.

D. If the Administrator determines that the public health, interest, or welfare warrants immediate action to suspend the accreditation of any person or the approval of any training course provider, the Administrator will:

1. Notify the affected entity of the grounds upon which the emergency suspension is based;

2. Notify the affected entity of the time period during which the emergency suspension is effective.

3. Notify the affected entity of the Administrator's intent to suspend or revoke accreditation or suspend or withdraw training course approval, as appropriate, in accordance with Unit IV.A. above. If such suspension, revocation, or withdrawal notice has not previously been issued, it will be issued

at the same time the emergency suspension notice is issued.

E. Any notice, decision, or order issued by the Administrator under this section, and any documents filed by an accredited person or approved training course provider in a hearing under this section, shall be available to the public except as otherwise provided by section 14 of TSCA or by 40 CFR part 2. Any such hearing at which oral testimony is presented shall be open to the public, except that the Presiding Officer may exclude the public to the extent necessary to allow presentation of information which may be entitled to confidential treatment under section 14 of TSCA or 40 CFR part 2.

### V. Implementation Schedule

The various requirements of this MAP become effective in accordance with the following schedules:

#### A. Requirements applicable to State Programs

1. Each State shall adopt an accreditation plan that is at least as stringent as this MAP within 180 days after the commencement of the first regular session of the legislature of the State that is convened on or after April 4, 1994.

2. If a State has adopted an accreditation plan at least as stringent as this MAP as of April 4, 1994, the State may continue to:

a. Conduct TSCA training pursuant to this MAP.

b. Approve training course providers to conduct training and to issue accreditation that satisfies the requirements for TSCA accreditation under this MAP.

c. Issue accreditation that satisfies the requirements for TSCA accreditation under this MAP.

3. A State that had complied with an earlier version of the MAP, but has not adopted an accreditation plan at least as stringent as this MAP by April 4, 1994, may:

a. Conduct TSCA training which remains in compliance with the requirements of Unit V.B. of this MAP. After such training has been self-certified in accordance with Unit V.B. of this MAP, the State may issue accreditation that satisfies the requirement for TSCA accreditation under this MAP.

b. Sustain its approval for any training course providers to conduct training and issue TSCA accreditation that the State had approved before April 4, 1994, and that remain in compliance with Unit V.B. of this MAP.

c. Issue accreditation pursuant to an earlier version of the MAP that provisionally satisfies the requirement for TSCA accreditation until October 4, 1994.

Such a State may not approve new TSCA training course providers to conduct training or to issue TSCA accreditation that satisfies

the requirements of this MAP until the State adopts an accreditation plan that is at least as stringent as this MAP.

4. A State that had complied with an earlier version of the MAP, but fails to adopt a plan as stringent as this MAP by the deadline established in Unit V.A.1., is subject to the following after that deadline date:

a. The State loses any status it may have held as an EPA-approved State for accreditation purposes under section 206 of TSCA, 15 U.S.C. 2646.

b. All training course providers approved by the State lose State approval to conduct training and issue accreditation that satisfies the requirements for TSCA accreditation under this MAP.

c. The State may not:

i. Conduct training for accreditation purposes under section 206 of TSCA, 15 U.S.C. 2646.

ii. Approve training course providers to conduct training or issue accreditation that satisfies the requirements for TSCA accreditation; or

iii. Issue accreditation that satisfies the requirement for TSCA accreditation.

EPA will extend EPA-approval to any training course provider that loses State approval because the State does not comply with the deadline, so long as the provider is in compliance with Unit V.B. of this MAP, and the provider is approved by a State that had complied with an earlier version of the MAP as of the day before the State loses its EPA approval.

5. A State that does not have an accreditation program that satisfies the requirements for TSCA accreditation under either an earlier version of the MAP or this MAP, may not:

a. Conduct training for accreditation purposes under section 206 of TSCA, 15 U.S.C. 2646;

b. Approve training course providers to conduct training or issue accreditation that satisfies the requirements for TSCA accreditation; or

c. Issue accreditation that satisfies the requirement for TSCA accreditation.

#### B. Requirements applicable to Training Courses and Providers

As of October 4, 1994, an approved training provider must certify to EPA and to any State that has approved the provider for TSCA accreditation, that each of the provider's training courses complies with the requirements of this MAP. The written submission must document in specific detail the changes made to each training course in order to comply with the requirements of this MAP and clearly state that the provider is also in compliance with all other requirements of this MAP, including the new recordkeeping and certificate provisions. Each submission must include the following state-

ment signed by an authorized representative of the training provider: "Under civil and criminal penalties of law for the making or submission of false or fraudulent statements or representations (18 U.S.C. 1001 and 15 U.S.C. 2615), I certify that the training described in this submission complies with all applicable requirements of Title II of TSCA, 40 CFR part 763, Appendix C to Subpart E, as revised, and any other applicable Federal, state, or local requirements." A consolidated self-certification submission from each training provider that addresses all of its approved training courses is permissible and encouraged.

The self-certification must be sent via registered mail, to EPA Headquarters at the following address: Attn. Self-Certification Program, Field Programs Branch, Chemical Management Division (7404), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460. A duplicate copy of the complete submission must also be sent to any States from which approval had been obtained.

The timely receipt of a complete self-certification by EPA and all approving States shall have the effect of extending approval under this MAP to the training courses offered by the submitting provider. If a self-certification is not received by the approving government bodies on or before the due date, the affected training course is not approved under this MAP. Such training providers must then reapply for approval of these training courses pursuant to the procedures outlined in Unit III.

#### C. Requirements applicable to Accredited Persons.

Persons accredited by a State with an accreditation program no less stringent than an earlier version of the MAP or by an EPA-approved training provider as of April 3, 1994, are accredited in accordance with the requirements of this MAP, and are not required to retake initial training. They must continue to comply with the requirements for annual refresher training in Unit I.D. of the revised MAP.

#### D. Requirements applicable to Non-Accredited Persons.

In order to perform work requiring accreditation under TSCA Title II, persons who are not accredited by a State with an accreditation program no less stringent than an earlier version of the MAP or by an EPA-approved training provider as of April 3, 1994, must comply with the upgraded training requirements of this MAP by no later than October 4, 1994. Non-accredited persons may obtain initial accreditation on a provisional basis by successfully completing any of the training programs approved under an earlier

## Environmental Protection Agency

## Pt. 763, Subpt. E, App. D

version of the MAP, and thereby perform work during the first 6 months after this MAP takes effect. However, by October 4, 1994, these persons must have successfully completed an upgraded training program that fully complies with the requirements of this MAP in order to continue to perform work requiring accreditation under section 206 of TSCA, 15 U.S.C. 2646.

[59 FR 5251, Feb. 3, 1994, as amended at 60 FR 31922, June 19, 1995; 70 FR 59889, Oct. 13, 2005]

### APPENDIX D TO SUBPART E OF PART 763—TRANSPORT AND DISPOSAL OF ASBESTOS WASTE

For the purposes of this appendix, transport is defined as all activities from receipt of the containerized asbestos waste at the generation site until it has been unloaded at the disposal site. Current EPA regulations state that there must be no visible emissions to the outside air during waste transport. However, recognizing the potential hazards and subsequent liabilities associated with exposure, the following additional precautions are recommended.

**Recordkeeping.** Before accepting wastes, a transporter should determine if the waste is properly wetted and containerized. The transporter should then require a chain-of-custody form signed by the generator. A chain-of-custody form may include the name and address of the generator, the name and address of the pickup site, the estimated quantity of asbestos waste, types of containers used, and the destination of the waste. The chain-of-custody form should then be signed over to a disposal site operator to transfer responsibility for the asbestos waste. A copy of the form signed by the disposal site operator should be maintained by the transporter as evidence of receipt at the disposal site.

**Waste handling.** A transporter should ensure that the asbestos waste is properly contained in leak-tight containers with appropriate labels, and that the outside surfaces of the containers are not contaminated with asbestos debris adhering to the containers. If there is reason to believe that the condition of the asbestos waste may allow significant fiber release, the transporter should not accept the waste. Improper containerization of wastes is a violation of the NESHAPs regulation and should be reported to the appropriate EPA Regional Asbestos NESHAPs contact below:

#### *Region I*

Asbestos NESHAPs Contact, Air Management Division, USEPA, Region I, JFK Federal Building, Boston, MA 02203, (617) 223-3266.

#### *Region II*

Asbestos NESHAPs Contact, Air & Waste Management Division, USEPA, Region II, 26 Federal Plaza, New York, NY 10007, (212) 264-6770.

#### *Region III*

Asbestos NESHAPs Contact, Air Management Division, USEPA, Region III, 841 Chestnut Street, Philadelphia, PA 19107, (215) 597-9325.

#### *Region IV*

Asbestos NESHAPs Contact, Air, Pesticide & Toxic Management, USEPA, Region IV, 345 Courtland Street, NE., Atlanta, GA 30365, (404) 347-4298.

#### *Region V*

Asbestos NESHAPs Contact, Air Management Division, USEPA, Region V, 77 West Jackson Boulevard, Chicago, IL 60604, (312) 353-6793.

#### *Region VI*

Asbestos NESHAPs Contact, Air & Waste Management Division, USEPA, Region VI, 1445 Ross Avenue, Dallas, TX 75202, (214) 655-7229.

#### *Region VII*

Asbestos NESHAPs Contact, Air & Waste Management Division, USEPA, Region VII, 726 Minnesota Avenue, Kansas City, KS 66101, (913) 236-2896.

#### *Region VIII*

Asbestos NESHAPs Contact, Air & Waste Management Division, USEPA, Region VIII, 999 18th Street, Suite 500, Denver, CO 80202, (303) 293-1814.

#### *Region IX*

Asbestos NESHAPs Contact, Air Management Division, USEPA, Region IX, 215 Fremont Street, San Francisco, CA 94105, (415) 974-7633.

#### *Region X*

Asbestos NESHAPs Contact, Air & Toxics Management Division, USEPA, Region X, 1200 Sixth Avenue, Seattle, WA 98101, (206) 442-2724.

Once the transporter is satisfied with the condition of the asbestos waste and agrees to handle it, the containers should be loaded into the transport vehicle in a careful manner to prevent breaking of the containers. Similarly, at the disposal site, the asbestos waste containers should be transferred carefully to avoid fiber release.

**Waste transport.** Although there are no regulatory specifications regarding the transport vehicle, it is recommended that vehicles

used for transport of containerized asbestos waste have an enclosed carrying compartment or utilize a canvas covering sufficient to contain the transported waste, prevent damage to containers, and prevent fiber release. Transport of large quantities of asbestos waste is commonly conducted in a 20-cubic-yard "roll off" box, which should also be covered. Vehicles that use compactors to reduce waste volume should not be used because these will cause the waste containers to rupture. Vacuum trucks used to transport waste slurry must be inspected to ensure that water is not leaking from the truck.

Disposal involves the isolation of asbestos waste material in order to prevent fiber release to air or water. Landfilling is recommended as an environmentally sound isolation method because asbestos fibers are virtually immobile in soil. Other disposal techniques such as incineration or chemical treatment are not feasible due to the unique properties of asbestos. EPA has established asbestos disposal requirements for active and inactive disposal sites under NESHAPs (40 CFR Part 61, subpart M) and specifies general requirements for solid waste disposal under RCRA (40 CFR Part 257). Advance EPA notification of the intended disposal site is required by NESHAPs.

*Selecting a disposal facility.* An acceptable disposal facility for asbestos wastes must adhere to EPA's requirements of no visible emissions to the air during disposal, or minimizing emissions by covering the waste within 24 hours. The minimum required cover is 6 inches of nonasbestos material, normally soil, or a dust-suppressing chemical. In addition to these Federal requirements, many state or local government agencies require more stringent handling procedures. These agencies usually supply a list of "approved" or licensed asbestos disposal sites upon request. Solid waste control agencies are listed in local telephone directories under state, county, or city headings. A list of state solid waste agencies may be obtained by calling the RCRA hotline: 1-800-424-9346 (382-3000 in Washington, DC). Some landfill owners or operators place special requirements on asbestos waste, such as placing all bagged waste into 55-gallon metal drums. Therefore, asbestos removal contractors should contact the intended landfill before arriving with the waste.

*Receiving asbestos waste.* A landfill approved for receipt of asbestos waste should require notification by the waste hauler that the load contains asbestos. The landfill operator should inspect the loads to verify that asbestos waste is properly contained in leak-tight containers and labeled appropriately. The appropriate EPA Regional Asbestos NESHAPs Contact should be notified if the landfill operator believes that the asbestos waste is in a condition that may cause significant fiber release during disposal. In situ-

ations when the wastes are not properly containerized, the landfill operator should thoroughly soak the asbestos with a water spray prior to unloading, rinse out the truck, and immediately cover the wastes with non-asbestos material prior to compacting the waste in the landfill.

*Waste deposition and covering.* Recognizing the health dangers associated with asbestos exposure, the following procedures are recommended to augment current federal requirements:

- Designate a separate area for asbestos waste disposal. Provide a record for future landowners that asbestos waste has been buried there and that it would be hazardous to attempt to excavate that area. (Future regulations may require property deeds to identify the location of any asbestos wastes and warn against excavation.)

- Prepare a separate trench to receive asbestos wastes. The size of the trench will depend upon the quantity and frequency of asbestos waste delivered to the disposal site. The trenching technique allows application of soil cover without disturbing the asbestos waste containers. The trench should be ramped to allow the transport vehicle to back into it, and the trench should be as narrow as possible to reduce the amount of cover required. If possible, the trench should be aligned perpendicular to prevailing winds.

- Place the asbestos waste containers into the trench carefully to avoid breaking them. Be particularly careful with plastic bags because when they break under pressure asbestos particles can be emitted.

- Completely cover the containerized waste within 24 hours with a minimum of 6 inches of nonasbestos material. Improperly containerized waste is a violation of the NESHAPs and EPA should be notified.

However, if improperly containerized waste is received at the disposal site, it should be covered immediately after unloading. Only after the wastes, including properly containerized wastes, are completely covered, can the wastes be compacted or other heavy equipment run over it. During compacting, avoid exposing wastes to the air or tracking asbestos material away from the trench.

- For final closure of an area containing asbestos waste, cover with at least an additional 30 inches of compacted nonasbestos material to provide a 36-inch final cover. To control erosion of the final cover, it should be properly graded and vegetated. In areas of the United States where excessive soil erosion may occur or the frost line exceeds 3 feet, additional final cover is recommended. In desert areas where vegetation would be difficult to maintain, 3-6 inches of well graded crushed rock is recommended for placement on top of the final cover.

*Controlling public access.* Under the current NESHAPs regulation, EPA does not require

that a landfill used for asbestos disposal use warning signs or fencing if it meets the requirement to cover asbestos wastes. However, under RCRA, EPA requires that access be controlled to prevent exposure of the public to potential health and safety hazards at the disposal site. Therefore, for liability protection of operators of landfills that handle asbestos, fencing and warning signs are recommended to control public access when natural barriers do not exist. Access to a landfill should be limited to one or two entrances with gates that can be locked when left unattended. Fencing should be installed around the perimeter of the disposal site in a manner adequate to deter access by the general public. Chain-link fencing, 6-ft high and topped with a barbed wire guard, should be used. More specific fencing requirements may be specified by local regulations. Warning signs should be displayed at all entrances and at intervals of 330 feet or less along the property line of the landfill or perimeter of the sections where asbestos waste is deposited. The sign should read as follows:

ASBESTOS WASTE DISPOSAL SITE  
BREATHING ASBESTOS DUST MAY  
CAUSE LUNG DISEASE AND CANCER

*Recordkeeping.* For protection from liability, and considering possible future requirements for notification on disposal site deeds, a landfill owner should maintain documentation of the specific location and quantity of the buried asbestos wastes. In addition, the estimated depth of the waste below the surface should be recorded whenever a landfill section is closed. As mentioned previously, such information should be recorded in the land deed or other record along with a notice warning against excavation of the area.

[52 FR 41897, Oct. 30, 1987, as amended at 62 FR 1834, Jan. 14, 1997]

## APPENDIX E TO SUBPART E OF PART 763—INTERIM METHOD OF THE DETERMINATION OF ASBESTOS IN BULK INSULATION SAMPLES

### SECTION 1. POLARIZED LIGHT MICROSCOPY

#### 1.1 Principle and Applicability

Bulk samples of building materials taken for asbestos identification are first examined for homogeneity and preliminary fiber identification at low magnification. Positive identification of suspect fibers is made by analysis of subsamples with the polarized light microscope.

The principles of optical mineralogy are well established.<sup>1,2</sup> A light microscope equipped with two polarizing filters is used to observe specific optical characteristics of a sample. The use of plane polarized light allows the determination of refractive indices along specific crystallographic axes. Mor-

phology and color are also observed. A retardation plate is placed in the polarized light path for determination of the sign of elongation using orthoscopic illumination. Orientation of the two filters such that their vibration planes are perpendicular (crossed polars) allows observation of the birefringence and extinction characteristics of anisotropic particles.

Quantitative analysis involves the use of point counting. Point counting is a standard technique in petrography for determining the relative areas occupied by separate minerals in thin sections of rock. Background information on the use of point counting<sup>2</sup> and the interpretation of point count data<sup>3</sup> is available.

This method is applicable to all bulk samples of friable insulation materials submitted for identification and quantitation of asbestos components.

#### 1.2 Range

The point counting method may be used for analysis of samples containing from 0 to 100 percent asbestos. The upper detection limit is 100 percent. The lower detection limit is less than 1 percent.

#### 1.3 Interferences

Fibrous organic and inorganic constituents of bulk samples may interfere with the identification and quantitation of the asbestos mineral content. Spray-on binder materials may coat fibers and affect color or obscure optical characteristics to the extent of masking fiber identity. Fine particles of other materials may also adhere to fibers to an extent sufficient to cause confusion in identification. Procedures that may be used for the removal of interferences are presented in Section 1.7.2.2.

#### 1.4 Precision and Accuracy

Adequate data for measuring the accuracy and precision of the method for samples with various matrices are not currently available. Data obtained for samples containing a single asbestos type in a simple matrix are available in the EPA report *Bulk Sample Analysis for Asbestos Content: Evaluation of the Tentative Method*.<sup>4</sup>

#### 1.5 Apparatus

##### 1.5.1 Sample Analysis

A low-power binocular microscope, preferably stereoscopic, is used to examine the bulk insulation sample as received.

- *Microscope:* binocular, 10–45X (approximate).
- *Light Source:* incandescent or fluorescent.
- *Forceps, Dissecting Needles, and Probes*
- *Glassine Paper or Clean Glass Plate*



Compound microscope requirements: A polarized light microscope complete with polarizer, analyzer, port for wave retardation plate, 360° graduated rotating stage, substage condenser, lamp, and lamp iris.

- *Polarized Light Microscope*: described above.
- *Objective Lenses*: 10X, 20X, and 40X or near equivalent.
- *Dispersion Staining Objective Lens* (optional)
- *Ocular Lens*: 10X minimum.
- *Eyeiece Reticle*: cross hair or 25 point Chalkley Point Array.
- *Compensator Plate*: 550 millimicron retardation.

#### 1.5.2 Sample Preparation

Sample preparation apparatus requirements will depend upon the type of insulation sample under consideration. Various physical and/or chemical means may be employed for an adequate sample assessment.

- *Ventilated Hood* or negative pressure glove box.
- *Microscope Slides*
- *Coverslips*
- *Mortar and Pestle*: agate or porcelain. (optional)
- *Wylie Mill* (optional)
- *Beakers and Assorted Glassware* (optional)
- *Centrifuge* (optional)
- *Filtration apparatus* (optional)
- *Low temperature asher* (optional)

#### 1.6 Reagents

##### 1.6.1 Sample Preparation

- *Distilled Water* (optional)
- *Dilute CH<sub>3</sub>COOH*: ACS reagent grade (optional)
- *Dilute HCl*: ACS reagent grade (optional)
- *Sodium metaphosphate* (NaPO<sub>3</sub>)<sub>6</sub> (optional)

##### 1.6.2 Analytical Reagents

*Refractive Index Liquids*: 1.490–1.570, 1.590–1.720 in increments of 0.002 or 0.004.

- *Refractive Index Liquids for Dispersion Staining*: high-dispersion series, 1.550, 1.605, 1.630 (optional).
- *UICC Asbestos Reference Sample Set*: Available from: UICC MRC Pneumoconiosis Unit, Llandough Hospital, Penarth, Glamorgan CF6 1XW, UK, and commercial distributors.
- *Tremolite-asbestos* (source to be determined)
- *Actinolite-asbestos* (source to be determined)

#### 1.7 Procedures

NOTE: Exposure to airborne asbestos fibers is a health hazard. Bulk samples submitted for analysis are usually friable and may release fibers during handling or matrix reduction steps. All sample and slide preparations should be carried out in a ventilated hood or glove box with continuous airflow (negative pressure). Handling of samples without these precautions may result in exposure of the

analyst and contamination of samples by airborne fibers.

#### 1.7.1 Sampling

Samples for analysis of asbestos content shall be taken in the manner prescribed in Reference 5 and information on design of sampling and analysis programs may be found in Reference 6. If there are any questions about the representative nature of the sample, another sample should be requested before proceeding with the analysis.

#### 1.7.2 Analysis

##### 1.7.2.1 Gross Examination

Bulk samples of building materials taken for the identification and quantitation of asbestos are first examined for homogeneity at low magnification with the aid of a stereomicroscope. The core sample may be examined in its container or carefully removed from the container onto a glassine transfer paper or clean glass plate. If possible, note is made of the top and bottom orientation. When discrete strata are identified, each is treated as a separate material so that fibers are first identified and quantified in that layer only, and then the results for each layer are combined to yield an estimate of asbestos content for the whole sample.

##### 1.7.2.2 Sample Preparation

Bulk materials submitted for asbestos analysis involve a wide variety of matrix materials. Representative subsamples may not be readily obtainable by simple means in heterogeneous materials, and various steps may be required to alleviate the difficulties encountered. In most cases, however, the best preparation is made by using forceps to sample at several places from the bulk material. Forcep samples are immersed in a refractive index liquid on a microscope slide, teased apart, covered with a cover glass, and observed with the polarized light microscope.

Alternatively, attempts may be made to homogenize the sample or eliminate interferences before further characterization. The selection of appropriate procedures is dependent upon the samples encountered and personal preference. The following are presented as possible sample preparation steps.

A mortar and pestle can sometimes be used in the size reduction of soft or loosely bound materials though this may cause matting of some samples. Such samples may be reduced in a Wylie mill. Apparatus should be clean and extreme care exercised to avoid cross-contamination of samples. Periodic checks of the particle sizes should be made during the grinding operation so as to preserve any fiber bundles present in an identifiable form. These procedures are not recommended for samples that contain amphibole minerals or

vermiculite. Grinding of amphiboles may result in the separation of fiber bundles or the production of cleavage fragments with aspect ratios greater than 3:1. Grinding of vermiculite may also produce fragments with aspect ratios greater than 3:1.

Acid treatment may occasionally be required to eliminate interferences. Calcium carbonate, gypsum, and bassanite (plaster) are frequently present in sprayed or trowelled insulations. These materials may be removed by treatment with warm dilute acetic acid. Warm dilute hydrochloric acid may also be used to remove the above materials. If acid treatment is required, wash the sample at least twice with distilled water, being careful not to lose the particulates during decanting steps. Centrifugation or filtration of the suspension will prevent significant fiber loss. The pore size of the filter should be 0.45 micron or less. Caution: prolonged acid contact with the sample may alter the optical characteristics of chrysotile fibers and should be avoided.

Coatings and binding materials adhering to fiber surfaces may also be removed by treatment with sodium metaphosphate.<sup>7</sup> Add 10 mL of 10g/L sodium metaphosphate solution to a small (0.1 to 0.5 mL) sample of bulk material in a 15-mL glass centrifuge tube. For approximately 15 seconds each, stir the mixture on a vortex mixer, place in an ultrasonic bath and then shake by hand. Repeat the series. Collect the dispersed solids by centrifugation at 1000 rpm for 5 minutes. Wash the sample three times by suspending in 10 mL distilled water and recentrifuging. After washing, resuspend the pellet in 5 mL distilled water, place a drop of the suspension on a microscope slide, and dry the slide at 110 °C.

In samples with a large portion of cellulose or other organic fibers, it may be useful to ash part of the sample and view the residue. Ashing should be performed in a low temperature ashers. Ashing may also be performed in a muffle furnace at temperatures

of 500 °C or lower. Temperatures of 550 °C or higher will cause dehydroxylation of the asbestos minerals, resulting in changes of the refractive index and other key parameters. If a muffle furnace is to be used, the furnace thermostat should be checked and calibrated to ensure that samples will not be heated at temperatures greater than 550 °C.

Ashing and acid treatment of samples should not be used as standard procedures. In order to monitor possible changes in fiber characteristics, the material should be viewed microscopically before and after any sample preparation procedure. Use of these procedures on samples to be used for quantitation requires a correction for percent weight loss.

1.7.2.3 Fiber Identification

Positive identification of asbestos requires the determination of the following optical properties.

- Morphology
- Color and pleochroism
- Refractive indices
- Birefringence
- Extinction characteristics
- Sign of elongation

Table 1-1 lists the above properties for commercial asbestos fibers. Figure 1-1 presents a flow diagram of the examination procedure. Natural variations in the conditions under which deposits of asbestiform minerals are formed will occasionally produce exceptions to the published values and differences from the UICC standards. The sign of elongation is determined by use of the compensator plate and crossed polars. Refractive indices may be determined by the Becke line test. Alternatively, dispersion staining may be used. Inexperienced operators may find that the dispersion staining technique is more easily learned, and should consult Reference 9 for guidance. Central stop dispersion staining colors are presented in Table 1-2. Available high-dispersion (HD) liquids should be used.

TABLE 1-1—OPTICAL PROPERTIES OF ASBESTOC FIBERS

| Mineral                              | Morphology, color <sup>a</sup>  | Refractive indices <sup>b</sup> |  | Birefringence | Extinction       | Sign of elongation |
|--------------------------------------|---|---------------------------------|--|---------------|------------------|--------------------|
|                                      |   | α                               | γ  |               |                  |                    |
| Chrysotile (asbestiform serpentine). | Wavy fibers. Fiber bundles have splayed ends and "kinks". Aspect ratio typically >10:1. Colorless <sup>3</sup> , nonpleochroic.         | 1.493-1.560                     | 1.517-1.562 <sup>f</sup> (normally 1.556).       | .008          | to fiber length. | + (length slow)    |
| Amosite (asbestiform grunerite).     | Straight, rigid fibers. Aspect ratio typically >10:1. Colorless to brown, nonpleochroic or weakly so. Opaque inclusions may be present. | 1.635-1.696                     | 1.655-1.729 <sup>f</sup> (normally 1.696-1.710). | .020-.033     | to fiber length. | + (length slow)    |

TABLE 1–1—OPTICAL PROPERTIES OF ASBESTOC FIBERS—Continued

| Mineral                                     | Morphology, color <sup>a</sup>  | Refrac- tive indices <sup>b</sup> |  | Birefring-<br>ence | Extinction  | Sign of<br>elongation |
|---|---|-----------------------------------|--|--------------------|---|-----------------------|
|   |   | $\alpha$                          | $\gamma$   |                    |   |                       |
| Crocidolite<br>(asbestiform<br>Riebeckite). | Straight, rigid fibers. Thick fibers and bundles common, blue to purple-blue in color. Pleochroic. Birefringence is generally masked by blue color.             | 1.654–1.701                       | 1.668–<br>1.717 <sup>3e</sup><br>(nor-<br>mally<br>close to<br>1.700). | .014–.016          | to fiber<br>length.   | –<br>(length fast)    |
| Anthophyllite-<br>asbestos.                 | Straight fibers and acicular cleavage fragments. <sup>d</sup> Some composite fibers. Aspect ratio <10:1. Colorless to light brown.                              | 1.596–1.652                       | 1.615–<br>1.676 <sup>f</sup> .   | .019–.024          | to fiber<br>length.   | +<br>(length<br>slow) |
| Tremolite-actin-<br>olite-asbes-<br>tos.    | Normally present as acicular or pris-<br>matic cleavage fragments. <sup>d</sup> Single<br>crystals predominate, aspect ratio<br><10:1. Colorless to pale green. | 1.599–1.668                       | 1.622–<br>1.688 <sup>f</sup> .   | .023–.020          | Oblique<br>extinc-<br>tion, 10–<br>20° for<br>frag-<br>ments.<br>Com-<br>posite fi-<br>bers<br>show  <br>extinc-<br>tion. | +<br>(length<br>slow) |

<sup>a</sup>From reference 5; colors cited are seen by observation with plane polarized light.

<sup>b</sup>From references 5 and 8.

<sup>c</sup>Fibers subjected to heating may be brownish.

<sup>d</sup>Fibers defined as having aspect ratio >3:1.

<sup>e</sup>to fiber length.

<sup>f</sup>To fiber length.

Polarized light microscopy analysis: For each type of material identified by examination of sample at low magnification. Mount spacially dispersed sample in 1.550 RI liquid. (If using dispersion staining, mount in 1.550 HD.) View at 100X with both plane polarized light and crossed polars. More than one fiber type may be present.




Figure 1-1. Flow chart for analysis of bulk samples by polarized light microscopy.

TABLE 1-2—CENTRAL STOP DISPERSION STAINING COLORS<sup>A</sup>

| Mineral                     | RI Liquid             | $\eta$                     | $\eta $              |
|-----------------------------|-----------------------|----------------------------|----------------------|
| Chrysotile .....            | 1.550 <sup>HD</sup>   | Blue .....                 | Blue-magenta         |
| Amosite .....               | 1.680                 | Blue-magenta to pale blue. | Golden-yellow        |
|                             | 1.550 <sup>HD</sup>   | Yellow to white.           | Yellow to white      |
| Crocidolite <sup>b</sup> .. | 1.700                 | Red magenta                | Blue-magenta         |
|                             | 1.550 <sup>HD</sup>   | Yellow to white.           | Yellow to white      |
| Anthophyllite               | 1.605 <sup>HD</sup>   | Blue .....                 | Gold to gold-magenta |
| Tremolite .....             | 1.605 <sup>HD c</sup> | Pale blue .....            | Gold                 |
| Actinolite .....            | 1.605 <sup>HD</sup>   | Gold-magenta to blue.      | Gold                 |
|                             | 1.630 <sup>HD c</sup> | Magenta .....              | Golden-yellow        |

<sup>a</sup> From reference 9.

<sup>b</sup> Blue absorption color.

<sup>c</sup> Oblique extinction view.

#### 1.7.2.4 Quantitation of Asbestos Content

Asbestos quantitation is performed by a point-counting procedure or an equivalent estimation method. An ocular reticle (cross-hair or point array) is used to visually superimpose a point or points on the microscope field of view. Record the number of points positioned directly above each kind of particle or fiber of interest. Score only points directly over asbestos fibers or nonasbestos matrix material. Do not score empty points for the closest particle. If an asbestos fiber and a matrix particle overlap so that a point is superimposed on their visual intersection, a point is scored for both categories. Point counting provides a determination of the area percent asbestos. Reliable conversion of area percent to percent of dry weight is not currently feasible unless the specific gravities and relative volumes of the materials are known.

For the purpose of this method, "asbestos fibers" are defined as having an aspect ratio greater than 3:1 and being positively identified as one of the minerals in Table 1-1.

A total of 400 points superimposed on either asbestos fibers or nonasbestos matrix material must be counted over at least eight different preparations of representative subsamples. Take eight forcep samples and mount each separately with the appropriate refractive index liquid. The preparation should not be heavily loaded. The sample should be uniformly dispersed to avoid overlapping particles and allow 25-50 percent empty area within the fields of view. Count 50 nonempty points on each preparation, using either

- A cross-hair reticle and mechanical stage; or

- A reticle with 25 points (Chalkley Point Array) and counting at least 2 randomly selected fields.

For samples with mixtures of isotropic and anisotropic materials present, viewing the sample with slightly uncrossed polars or the addition of the compensator plate to the polarized light path will allow simultaneous discrimination of both particle types. Quantitation should be performed at 100X or at the lowest magnification of the polarized light microscope that can effectively distinguish the sample components. Confirmation of the quantitation result by a second analyst on some percentage of analyzed samples should be used as standard quality control procedure.

The percent asbestos is calculated as follows:

$$\% \text{ asbestos} = (a/n) 100\%$$

where

a=number of asbestos counts,

n=number of nonempty points counted (400).

If a=0, report "No asbestos detected." If 0 < a ≤ 3, report "<1% asbestos".

The value reported should be rounded to the nearest percent.

#### 1.8 References

1. Paul F. Kerr, *Optical Mineralogy*, 4th ed., New York, McGraw-Hill, 1977.
2. E. M. Chamot and C. W. Mason, *Handbook of Chemical Microscopy, Volume One*, 3rd ed., New York: John Wiley & Sons, 1958.
3. F. Chayes, *Petrographic Modal Analysis: An Elementary Statistical Appraisal*, New York: John Wiley & Sons, 1956.
4. E. P. Brantly, Jr., K. W. Gold, L. E. Myers, and D. E. Lentzen, *Bulk Sample Analysis for Asbestos Content: Evaluation of the Tentative Method*, U.S. Environmental Protection Agency, October 1981.
5. U.S. Environmental Protection Agency, *Asbestos-Containing Materials in School Buildings: A Guidance Document, Parts 1 and 2*, EPA/OPPT No. C00090, March 1979.
6. D. Lucas, T. Hartwell, and A. V. Rao, *Asbestos-Containing Materials in School Buildings: Guidance for Asbestos Analytical Programs*, EPA 560/13-80-017A, U.S. Environmental Protection Agency, December 1980, 96 pp.
7. D. H. Taylor and J. S. Bloom, Hexametaphosphate pretreatment of insulation samples for identification of fibrous constituents, *Microscope*, 28, 1980.
8. W. J. Campbell, R. L. Blake, L. L. Brown, E. E. Cather, and J. J. Sjoberg. *Selected Silicate Minerals and Their Asbestiform Varieties: Mineralogical Definitions and Identification-Characterization*, U.S. Bureau of Mines Information Circular 8751, 1977.
9. Walter C. McCrone, *Asbestos Particle Atlas*, Ann Arbor: Ann Arbor Science Publishers, June 1980.

SECTION 2. X-RAY POWDER DIFFRACTION

2.1 Principle and Applicability

The principle of X-ray powder diffraction (XRD) analysis is well established.<sup>1,2</sup> Any solid, crystalline material will diffract an impinging beam of parallel, monochromatic X-rays whenever Bragg's Law,

$$\lambda = 2d \sin \theta,$$

is satisfied for a particular set of planes in the crystal lattice, where

$\lambda$  = the X-ray wavelength, Å;

$d$  = the interplanar spacing of the set of reflecting lattice planes, Å; and

$\theta$  = the angle of incidence between the X-ray beam and the reflecting lattice planes.

By appropriate orientation of a sample relative to the incident X-ray beam, a diffraction pattern can be generated that, in most cases, will be uniquely characteristic of both the chemical composition and structure of the crystalline phases present.

Unlike optical methods of analysis, however, XRD cannot determine crystal morphology. Therefore, in asbestos analysis, XRD does not distinguish between fibrous and nonfibrous forms of the serpentine and amphibole minerals (Table 2-1). However, when used in conjunction with optical methods such as polarized light microscopy (PLM), XRD techniques can provide a reliable analytical method for the identification and characterization of asbestiform minerals in bulk materials.

For *qualitative analysis* by XRD methods, samples are initially scanned over limited diagnostic peak regions for the serpentine (~7.4 Å) and amphibole (8.2-8.5 Å) minerals (Table 2-2). Standard slow-scanning methods for bulk sample analysis may be used for materials shown by PLM to contain significant amounts of asbestos (>5-10 percent). Detection of minor or trace amounts of asbestos may require special sample preparation and step-scanning analysis. All samples that exhibit diffraction peaks in the diagnostic regions for asbestiform minerals are submitted to a full (5°-60° 2 $\theta$ ; 1° 2 $\theta$ /min) qualitative XRD scan, and their diffraction patterns are compared with standard reference powder diffraction patterns<sup>3</sup> to verify initial peak assignments and to identify possible matrix interferences when subsequent quantitative analysis will be performed.

TABLE 2-1—THE ASBESTOS MINERALS AND THEIR NONASBESTIFORM ANALOGS

| Asbestiform                                  | Nonasbestiform          |
|--|-------------------------|
| SERPENTINE                                   |                         |
| Chrysotile                                   | Antigorite, lizardite   |
| AMPHIBOLE                                    |                         |
| Anthophyllite asbestos                       | Anthophyllite           |
| Cummingtonite-grunerite asbestos ("Amosite") | Cummingtonite-grunerite |
| Crocidolite                                  | Riebeckite              |
| Tremolite asbestos                           | Tremolite               |
| Actinolite asbestos                          | Actinolite              |

TABLE 2-2—PRINCIPAL LATTICE SPACINGS OF ASBESTIFORM MINERALS<sup>A</sup>

| Minerals            | Principal d-spacings (Å) and relative intensities |                     |                     | JCPDS Powder diffraction file <sup>3</sup> number |
|---------------------|---|---------------------|---------------------|---|
|                     |   |                     |                     |   |
| Chrysotile .....    | 7.37 <sub>100</sub>                               | 3.65 <sub>70</sub>  | 4.57 <sub>50</sub>  | 21-543 <sup>b</sup>                               |
|                     | 7.36 <sub>100</sub> ..                            | 3.66 <sub>80</sub>  | 2.45 <sub>65</sub>  | 25-645  |
|                     | 7.10 <sub>100</sub> ..                            | 2.33 <sub>80</sub>  | 3.55 <sub>70</sub>  | 22-1162 (theoretical)                             |
| "Amosite" .....     | 8.33 <sub>100</sub>                               | 3.06 <sub>70</sub>  | 2.756 <sub>70</sub> | 17-745 (nonfibrous)                               |
|                     | 8.22 <sub>100</sub> ..                            | 3.060 <sub>85</sub> | 3.25 <sub>70</sub>  | 27-1170 (UICC)                                    |
| Anthophyllite ..... | 3.05 <sub>100</sub>                               | 3.24 <sub>60</sub>  | 8.26 <sub>55</sub>  | 9-455   |
|                     | 3.06 <sub>100</sub> ..                            | 8.33 <sub>70</sub>  | 3.23 <sub>50</sub>  | 16-401 (synthetic)                                |
| Anthophyllite ..... | 2.72 <sub>100</sub>                               | 2.54 <sub>100</sub> | 3.480 <sub>80</sub> | 25-157  |
| Crocidolite .....   | 8.35 <sub>100</sub>                               | 3.10 <sub>85</sub>  | 2.720 <sub>85</sub> | 27-1415 (UICC)                                    |
| Tremolite .....     | 8.38 <sub>100</sub>                               | 3.12 <sub>100</sub> | 2.705 <sub>90</sub> | 13-437 <sup>b</sup>                               |
|                     | 2.706 <sub>100</sub>                              | 3.14 <sub>95</sub>  | 8.43 <sub>40</sub>  | 20-1310 <sup>b</sup> (synthetic)                  |
|                     | 3.13 <sub>100</sub> ..                            | 2.706 <sub>60</sub> | 8.44 <sub>40</sub>  | 23-666 (synthetic mixture with richterite)        |

<sup>a</sup>This information is intended as a guide, only. Complete powder diffraction data, including mineral type and source, should be referred to, to ensure comparability of sample and reference materials where possible. Additional precision XRD data on amosite, crocidolite, tremolite, and chrysotile are available from the U.S. Bureaus of Mines.<sup>4</sup>

<sup>b</sup>Fibrosity questionable.

Accurate *quantitative analysis* of asbestos in bulk samples by XRD is critically dependent on particle size distribution, crystallite size, preferred orientation and matrix absorption effects, and comparability of standard reference and sample materials. The most intense diffraction peak that has been shown to be free from interference by prior

qualitative XRD analysis is selected for quantitation of each asbestiform mineral. A "thin-layer" method of analysis<sup>5,6</sup> is recommended in which, subsequent to comminution of the bulk material to ~10  $\mu$ m by suitable cryogenic milling techniques, an accurately known amount of the sample is deposited on a silver membrane filter. The

mass of asbestiform material is determined by measuring the integrated area of the selected diffraction peak using a step-scanning mode, correcting for matrix absorption effects, and comparing with suitable calibration standards. Alternative “thick-layer” or bulk methods,<sup>7,8</sup> may be used for *semi-quantitative analysis*.

This XRD method is applicable as a confirmatory method for identification and quantitation of asbestos in bulk material samples that have undergone prior analysis by PLM or other optical methods.

### 2.2 Range and Sensitivity

The range of the method has not been determined.

The sensitivity of the method has not been determined. It will be variable and dependent upon many factors, including matrix effects (absorption and interferences), diagnostic reflections selected, and their relative intensities.

### 2.3 Limitations

#### 2.3.1 Interferences

Since the fibrous and nonfibrous forms of the serpentine and amphibole minerals (Table 2-1) are indistinguishable by XRD techniques unless special sample preparation techniques and instrumentation are used,<sup>9</sup> the presence of nonasbestiform serpentines and amphiboles in a sample will pose severe interference problems in the identification and quantitative analysis of their asbestiform analogs.

The use of XRD for identification and quantitation of asbestiform minerals in bulk samples may also be limited by the presence of other interfering materials in the sample. For naturally occurring materials the commonly associated asbestos-related mineral interferences can usually be anticipated. However, for fabricated materials the nature of the interferences may vary greatly (Table 2-3) and present more serious problems in identification and quantitation.<sup>10</sup> Potential interferences are summarized in Table 2-4 and include the following:

- *Chlorite* has major peaks at 7.19 Å and 3.58 Å that interfere with both the primary (7.36 Å) and secondary (3.66 Å) peaks for chrysotile. Resolution of the primary peak to give good quantitative results may be possible when a step-scanning mode of operation is employed.
- *Halloysite* has a peak at 3.63 Å that interferes with the secondary (3.66 Å) peak for chrysotile.
- *Kaolinite* has a major peak at 7.15 Å that may interfere with the primary peak of chrysotile at 7.36 Å when present at concentrations of >10 percent. However, the secondary chrysotile peak at 3.66 Å may be used for quantitation.

- *Gypsum* has a major peak at 7.5 Å that overlaps the 7.36 Å peak of chrysotile when present as a major sample constituent. This may be removed by careful washing with distilled water, or by heating to 300 °C to convert gypsum to plaster of paris.
- *Cellulose* has a broad peak that partially overlaps the secondary (3.66 Å) chrysotile peak.<sup>8</sup>
- Overlap of major diagnostic peaks of the amphibole asbestos minerals, amosite, anthophyllite, crocidolite, and tremolite, at approximately 8.3 Å and 3.1 Å causes mutual interference when these minerals occur in the presence of one another. In some instances, adequate resolution may be attained by using step-scanning methods and/or by decreasing the collimator slit width at the X-ray port.

TABLE 2-3—COMMON CONSTITUENTS IN INSULATION AND WALL MATERIALS

#### A. Insulation materials

Chrysotile  
 “Amosite”  
 Crocidolite  
 \*Rock wool  
 \*Slag wool  
 \*Fiber glass  
 Gypsum (CaSO<sub>4</sub> · 2H<sub>2</sub>O)  
 Vermiculite (micas)  
 \*Perlite  
 Clays (kaolin)  
 \*Wood pulp  
 \*Paper fibers (talc, clay, carbonate fillers)  
 Calcium silicates (synthetic)  
 Opaques (chromite, magnetite inclusions in serpentine)  
 Hematite (inclusions in “amosite”)  
 Magnesite  
 \*Diatomaceous earth

#### B. Spray finishes or paints

Bassanite  
 Carbonate minerals (calcite, dolomite, vaterite)  
 Talc  
 Tremolite  
 Anthophyllite  
 Serpentine (including chrysotile)  
 Amosite  
 Crocidolite  
 \*Mineral wool  
 \*Rock wool  
 \*Slag wool  
 \*Fiber glass  
 Clays (kaolin)  
 Micas  
 Chlorite  
 Gypsum (CaSO<sub>4</sub> · 2H<sub>2</sub>O)  
 Quartz  
 \*Organic binders and thickeners  
 Hydromagnesite  
 Wollastonite  
 Opaques (chromite, magnetite inclusions in serpentine)  
 Hematite (inclusions in “amosite”)

\*Amorphous materials contribute only to overall scattered radiation and increased background radiation.

orthorhombic anthophyllite separated by less than 0.2 Å.<sup>12</sup>

TABLE 2-4—INTERFERENCES IN XRD ANALYSIS ASBESTIFORM MINERALS

| Asbestiform mineral   | Primary diagnostic peaks (approximate d-spacings, in Å) | Interference  |
|---|---|---|
| Serpentine<br>Chrysotile  | 7.4   | Nonasbestiform serpentines (antigorite, lizardite)<br>Chlorite<br>Kaolinite   |
|   | 3.7   | Gypsum<br>Chlorite<br>Halloysite<br>Cellulose   |
| Amphibole<br>"Amosite"<br>Anthophyllite<br>Crocidolite<br>Tremolite | 3.1   | Nonasbestiform amphiboles (cummingtonite-grunerite, anthophyllite, riebeckite, tremolite)<br>Mutual interferences<br>Carbonates |
|   | 8.3   | Talc<br>Mutual interferences  |

- Carbonates may also interfere with quantitative analysis of the amphibole asbestos minerals, amosite, anthophyllite, crocidolite, and tremolite. Calcium carbonate (CaCO<sub>3</sub>) has a peak at 3.035 Å that overlaps major amphibole peaks at approximately 3.1 Å when present in concentrations of >5 percent. Removal of carbonates with a dilute acid wash is possible; however, if present, chrysotile may be partially dissolved by this treatment.<sup>11</sup>
- A major talc peak at 3.12 Å interferes with the primary tremolite peak at this same position and with secondary peaks of crocidolite (3.10 Å), amosite (3.06 Å), and anthophyllite (3.05 Å). In the presence of talc, the major diagnostic peak at approximately 8.3 Å should be used for quantitation of these asbestiform minerals.

The problem of intraspecies and matrix interferences is further aggravated by the variability of the silicate mineral powder diffraction patterns themselves, which often makes definitive identification of the asbestos minerals by comparison with standard reference diffraction patterns difficult. This variability results from alterations in the crystal lattice associated with differences in isomorphous substitution and degree of crystallinity. This is especially true for the amphiboles. These minerals exhibit a wide variety of very similar chemical compositions, with the result being that their diffraction patterns are characterized by having major (110) reflections of the monoclinic amphiboles and (210) reflections of the

2.3.2 Matrix Effects

If a copper X-ray source is used, the presence of iron at high concentrations in a sample will result in significant X-ray fluorescence, leading to loss of peak intensity along with increased background intensity and an overall decrease in sensitivity. This situation may be corrected by choosing an X-ray source other than copper; however, this is often accompanied both by loss of intensity and by decreased resolution of closely spaced reflections. Alternatively, use of a diffracted beam monochromator will reduce background fluorescent radiation, enabling weaker diffraction peaks to be detected.

X-ray absorption by the sample matrix will result in overall attenuation of the diffracted beam and may seriously interfere with quantitative analysis. Absorption effects may be minimized by using sufficiently "thin" samples for analysis.<sup>5,13,14</sup> However, unless absorption effects are known to be the same for both samples and standards, appropriate corrections should be made by referencing diagnostic peak areas to an internal standard<sup>7,8</sup> or filter substrate (Ag) peak.<sup>5,6</sup>

2.3.3 Particle Size Dependence

Because the intensity of diffracted X-radiation is particle-size dependent, it is essential for accurate quantitative analysis that both sample and standard reference materials have similar particle size distributions. The optimum particle size range for quantitative analysis of asbestos by XRD has been reported to be 1 to 10 µm.<sup>15</sup> Comparability of sample and standard reference material particle size distributions should be verified by optical microscopy (or another suitable method) prior to analysis.

2.3.4 Preferred Orientation Effects

Preferred orientation of asbestiform minerals during sample preparation often poses a serious problem in quantitative analysis by XRD. A number of techniques have been developed for reducing preferred orientation effects in "thick layer" samples.<sup>7,8,15</sup> However, for "thin" samples on membrane filters, the preferred orientation effects seem to be both reproducible and favorable to enhancement of the principal diagnostic reflections of asbestos minerals, actually increasing the overall sensitivity of the method.<sup>12,14</sup> (Further investigation into preferred orientation effects in both thin layer and bulk samples is required.)

2.3.5 Lack of Suitably Characterized Standard Materials

The problem of obtaining and characterizing suitable reference materials for asbestos analysis is clearly recognized. NIOSH has



recently directed a major research effort toward the preparation and characterization of analytical reference materials, including asbestos standards;<sup>16,17</sup> however, these are not available in large quantities for routine analysis.

In addition, the problem of ensuring the comparability of standard reference and sample materials, particularly regarding crystallite size, particle size distribution, and degree of crystallinity, has yet to be adequately addressed. For example, Langer et al.<sup>18</sup> have observed that in insulating matrices, chrysotile tends to break open into bundles more frequently than amphiboles. This results in a line-broadening effect with a resultant decrease in sensitivity. Unless this effect is the same for both standard and sample materials, the amount of chrysotile in the sample will be underestimated by XRD analysis. To minimize this problem, it is recommended that standardized matrix reduction procedures be used for both sample and standard materials.

#### 2.4 Precision and Accuracy

Precision of the method has not been determined.

Accuracy of the method has not been determined.

#### 2.5 Apparatus

##### 2.5.1 Sample Preparation

Sample preparation apparatus requirements will depend upon the sample type under consideration and the kind of XRD analysis to be performed.

- *Mortar and Pestle*: Agate or porcelain.
- *Razor Blades*
- *Sample Mill*: SPEX, Inc., freezer mill or equivalent.
- *Bulk Sample Holders*
- *Silver Membrane Filters*: 25-mm diameter, 0.45- $\mu$ m pore size. Selas Corp. of America, Flotronics Div., 1957 Pioneer Road, Huntingdon Valley, PA 19006.
- *Microscope Slides*
- *Vacuum Filtration Apparatus*: Gelman No. 1107 or equivalent, and side-arm vacuum flask.
- *Microbalance*
- *Ultrasonic Bath or Probe*: Model W140, Ultrasonics, Inc., operated at a power density of approximately 0.1 W/mL, or equivalent.
- *Volumetric Flasks*: 1-L volume.
- *Assorted Pipettes*
- *Pipette Bulb*
- *Nonserrated Forceps*
- *Polyethylene Wash Bottle*
- *Pyrex Beakers*: 50-mL volume.
- *Desiccator*
- *Filter Storage Cassettes*
- *Magnetic Stirring Plate and Bars*
- *Porcelain Crucibles*
- *Muffle Furnace or Low Temperature Asher*

##### 2.5.2 Sample Analysis

Sample analysis requirements include an X-ray diffraction unit, equipped with:

- *Constant Potential Generator; Voltage and mA Stabilizers*
- *Automated Diffractometer with Step-Scanning Mode*
- *Copper Target X-Ray Tube*: High intensity, fine focus, preferably.
- *X-Ray Pulse Height Selector*
- *X-Ray Detector* (with high voltage power supply): Scintillation or proportional counter.
- *Focusing Graphite Crystal Monochromator*; or *Nickel Filter* (if copper source is used, and iron fluorescence is not a serious problem).
- *Data Output Accessories*:
  - *Strip Chart Recorder*
  - *Decade Scaler/Timer*
  - *Digital Printer*
- *Sample Spinner* (optional).
- *Instrument Calibration Reference Specimen*:  $\alpha$ -quartz reference crystal (Arkansas quartz standard, #180-147-00, Philips Electronics Instruments, Inc., 85 McKee Drive, Mahwah, NJ 07430) or equivalent.

#### 2.6 Reagents

##### 2.6.1 Standard Reference Materials

The reference materials listed below are intended to serve as a guide. Every attempt should be made to acquire pure reference materials that are comparable to sample materials being analyzed.

- *Chrysotile*: UICC Canadian, or NIEHS Plastibest. (UICC reference materials available from: UICC, MRC Pneumoconiosis Unit, Llandough Hospital, Penarth, Glamorgan, CF61XW, UK).
- *Crocidolite*: UICC
- *Amosite*: UICC
- *Anthophyllite*: UICC
- *Tremolite Asbestos*: Wards Natural Science Establishment, Rochester, N.Y.; Cyprus Research Standard, Cyprus Research, 2435 Military Ave., Los Angeles, CA 90064 (washed with dilute HCl to remove small amount of calcite impurity); India tremolite, Rajasthan State, India.
- *Actinolite Asbestos*

##### 2.6.2 Adhesive

Tape, petroleum jelly, etc. (for attaching silver membrane filters to sample holders).

##### 2.6.3 Surfactant

1 percent aerosol OT aqueous solution or equivalent.

##### 2.6.4 Isopropanol

ACS Reagent Grade.

## 2.7 Procedure

### 2.7.1 Sampling

Samples for analysis of asbestos content shall be collected as specified in EPA Guidance Document #C0090, *Asbestos-Containing Materials in School Buildings*.<sup>10</sup>

### 2.7.2 Analysis

All samples must be analyzed initially for asbestos content by PLM. XRD should be used as an auxiliary method when a second, independent analysis is requested.

NOTE: Asbestos is a toxic substance. All handling of dry materials should be performed in an operating fume hood.

#### 2.7.2.1 Sample Preparation

The method of sample preparation required for XRD analysis will depend on: (1) The condition of the sample received (sample size, homogeneity, particle size distribution, and overall composition as determined by PLM); and (2) the type of XRD analysis to be performed (qualitative, quantitative, thin layer or bulk).

Bulk materials are usually received as inhomogeneous mixtures of complex composition with very wide particle size distributions. Preparation of a homogeneous, representative sample from asbestos-containing materials is particularly difficult because the fibrous nature of the asbestos minerals inhibits mechanical mixing and stirring, and because milling procedures may cause adverse lattice alterations.

A discussion of specific matrix reduction procedures is given below. Complete methods of sample preparation are detailed in Sections 2.7.2.2 and 2.7.2.3.

NOTE: All samples should be examined microscopically before and after each matrix reduction step to monitor changes in sample particle size, composition, and crystallinity, and to ensure sample representativeness and homogeneity for analysis.

**2.7.2.1.1 Milling**—Mechanical milling of asbestos materials has been shown to decrease fiber crystallinity, with a resultant decrease in diffraction intensity of the specimen; the degree of lattice alteration is related to the duration and type of milling process.<sup>19,22</sup> Therefore, all milling times should be kept to a minimum.

For *qualitative analysis*, particle size is not usually of critical importance and initial characterization of the material with a minimum of matrix reduction is often desirable to document the composition of the sample as received. Bulk samples of very large particle size (>2–3 mm) should be comminuted to ~100  $\mu\text{m}$ . A mortar and pestle can sometimes be used in size reduction of soft or loosely bound materials though this may cause matting of some samples. Such sam-

ples may be reduced by cutting with a razor blade in a mortar, or by grinding in a suitable mill (e.g., a microhammer mill or equivalent). When using a mortar for grinding or cutting, the sample should be moistened with ethanol, or some other suitable wetting agent, to minimize exposures.

For accurate, reproducible *quantitative analysis*, the particle size of both sample and standard materials should be reduced to ~10  $\mu\text{m}$  (see Section 2.3.3). Dry ball milling at liquid nitrogen temperatures (e.g., Spex Freezer Mill, or equivalent) for a maximum time of 10 min. is recommended to obtain satisfactory particle size distributions while protecting the integrity of the crystal lattice.<sup>5</sup> Bulk samples of very large particle size may require grinding in two stages for full matrix reduction to <10  $\mu\text{m}$ .<sup>8,16</sup>

Final particle size distributions should always be verified by optical microscopy or another suitable method.

**2.7.2.1.2 Low temperature ashing**—For materials shown by PLM to contain large amounts of gypsum, cellulosic, or other organic materials, it may be desirable to ash the samples prior to analysis to reduce background radiation or matrix interference. Since chrysotile undergoes dehydroxylation at temperatures between 550 °C and 650 °C, with subsequent transformation to forsterite,<sup>23,24</sup> ashing temperatures should be kept below 500 °C. Use of a low temperature ashing is recommended. In all cases, calibration of the oven is essential to ensure that a maximum ashing temperature of 500 °C is not exceeded.

**2.7.2.1.3 Acid leaching**—Because of the interference caused by gypsum and some carbonates in the detection of asbestiform minerals by XRD (see Section 2.3.1), it may be necessary to remove these interferents by a simple acid leaching procedure prior to analysis (see Section 1.7.2.2).

#### 2.7.2.2 Qualitative Analysis

**2.7.2.2.1 Initial screening of bulk material**—Qualitative analysis should be performed on a representative, homogeneous portion of the sample with a minimum of sample treatment.

1. Grind and mix the sample with a mortar and pestle (or equivalent method, see Section 2.7.2.1.1.) to a final particle size sufficiently small (~100  $\mu\text{m}$ ) to allow adequate packing into the sample holder.

2. Pack the sample into a standard bulk sample holder. Care should be taken to ensure that a representative portion of the milled sample is selected for analysis. Particular care should be taken to avoid possible size segregation of the sample. (Note: Use of a back-packing method<sup>25</sup> of bulk sample preparation may reduce preferred orientation effects.)

3. Mount the sample on the diffractometer and scan over the diagnostic peak regions for

the serpentine (~67.4 Å) and amphibole (8.2-8.5 Å) minerals (see Table 2-2). The X-ray diffraction equipment should be optimized for intensity. A slow scanning speed of 1° 2θ/min is recommended for adequate resolution. Use of a sample spinner is recommended.

4. Submit all samples that exhibit diffraction peaks in the diagnostic regions for asbestiform minerals to a full qualitative XRD scan (5°-60° 2θ; 1°2θ/min) to verify initial peak assignments and to identify potential matrix interferences when subsequent quantitative analysis is to be performed.

5. Compare the sample XRD pattern with standard reference powder diffraction patterns (i.e., JCPDS powder diffraction data<sup>3</sup> or those of other well-characterized reference materials). Principal lattice spacings of asbestiform minerals are given in Table 2-2; common constituents of bulk insulation and wall materials are listed in Table 2-3.

2.7.2.2.2 *Detection of minor or trace constituents*—Routine screening of bulk materials by XRD may fail to detect small concentrations (<5 percent) of asbestos. The limits of detection will, in general, be improved if matrix absorption effects are minimized, and if the sample particle size is reduced to the optimal 1 to 10 μm range, provided that the crystal lattice is not degraded in the milling process. Therefore, in those instances where confirmation of the presence of an asbestiform mineral at very low levels is required, or where a negative result from initial screening of the bulk material by XRD (see Section 2.7.2.2.1) is in conflict with previous PLM results, it may be desirable to prepare the sample as described for quantitative analysis (see Section 2.7.2.3) and step-scan over appropriate 2θ ranges of selected diagnostic peaks (Table 2-2). Accurate transfer of the sample to the silver membrane filter is not necessary unless subsequent quantitative analysis is to be performed.

#### 2.7.2.3 Quantitative Analysis

The proposed method for quantitation of asbestos in bulk samples is a modification of the NIOSH-recommended thin-layer method for chrysotile in air.<sup>5</sup> A thick-layer or bulk method involving pelletizing the sample may be used for semiquantitative analysis;<sup>7,8</sup> however, this method requires the addition of an internal standard, use of a specially fabricated sample press, and relatively large amounts of standard reference materials. Additional research is required to evaluate the comparability of thin- and thick-layer methods for quantitative asbestos analysis.

For quantitative analysis by thin-layer methods, the following procedure is recommended:

1. Mill and size all or a substantial representative portion of the sample as outlined in Section 2.7.2.1.1.

2. Dry at 100 °C for 2 hr; cool in a desiccator.

3. Weigh accurately to the nearest 0.01 mg.

4. Samples shown by PLM to contain large amounts of cellulosic or other organic materials, gypsum, or carbonates, should be submitted to appropriate matrix reduction procedures described in Sections 2.7.2.1.2 and 2.7.2.1.3. After ashing and/or acid treatment, repeat the drying and weighing procedures described above, and determine the percent weight loss; L.

5. Quantitatively transfer an accurately weighed amount (50-100 mg) of the sample to a 1-L volumetric flask with approximately 200 mL isopropanol to which 3 to 4 drops of surfactant have been added.

6. Ultrasonicate for 10 min at a power density of approximately 0.1 W/mL, to disperse the sample material.

7. Dilute to volume with isopropanol.

8. Place flask on a magnetic stirring plate. Stir.

9. Place a silver membrane filter on the filtration apparatus, apply a vacuum, and attach the reservoir. Release the vacuum and add several milliliters of isopropanol to the reservoir. Vigorously hand shake the asbestos suspension and immediately withdraw an aliquot from the center of the suspension so that total sample weight,  $W_T$ , on the filter will be approximately 1 mg. Do not adjust the volume in the pipet by expelling part of the suspension; if more than the desired aliquot is withdrawn, discard the aliquot and resume the procedure with a clean pipet. Transfer the aliquot to the reservoir. Filter rapidly under vacuum. Do not wash the reservoir walls. Leave the filter apparatus under vacuum until dry. Remove the reservoir, release the vacuum, and remove the filter with forceps. (Note: Water-soluble matrix interferences such as gypsum may be removed at this time by careful washing of the filtrate with distilled water. Extreme care should be taken not to disturb the sample.)

10. Attach the filter to a flat holder with a suitable adhesive and place on the diffractometer. Use of a sample spinner is recommended.

11. For each asbestos mineral to be quantitated select a reflection (or reflections) that has been shown to be free from interferences by prior PLM or qualitative XRD analysis and that can be used unambiguously as an index of the amount of material present in the sample (see Table 2-2).

12. Analyze the selected diagnostic reflection(s) by step scanning in increments of 0.02° 2θ for an appropriate fixed time and integrating the counts. (A fixed count scan may be used alternatively; however, the method chosen should be used consistently for all samples and standards.) An appropriate scanning interval should be selected for each peak, and background corrections made. For a fixed time scan, measure the

background on each side of the peak for one-half the peak-scanning time. The net intensity,  $I_n$ , is the difference between the peak integrated count and the total background count.

13. Determine the net count,  $I_{Ag}$ , of the filter 2.36 Å silver peak following the procedure in step 12. Remove the filter from the holder, reverse it, and reattach it to the holder. Determine the net count for the unattenuated silver peak,  $I_{Ag}^o$ . Scan times may be less for measurement of silver peaks than for sample peaks; however, they should be constant throughout the analysis.

14. Normalize all raw, net intensities (to correct for instrument instabilities) by referencing them to an external standard (e.g., the 3.34 Å peak of an  $\alpha$ -quartz reference crystal). After each unknown is scanned, determine the net count,  $I_r$ , of the reference specimen following the procedure in step 12. Determine the normalized intensities by dividing the peak intensities by  $I_r$ :

$$\hat{I}_a = \frac{I_a}{I_r^o}, \quad \hat{I}_{Ag} = \frac{I_{Ag}}{I_r^o}, \quad \text{and} \quad \hat{I}_{Ag}^o = \frac{I_{Ag}^o}{I_r^o}$$

### 2.8 Calibration

#### 2.8.1 Preparation of Calibration Standards

1. Mill and size standard asbestos materials according to the procedure outlined in Section 2.7.2.1.1. *Equivalent, standardized matrix reduction and sizing techniques should be used for both standard and sample materials.*

2. Dry at 100 °C for 2 hr; cool in a desiccator.

3. Prepare two suspensions of each standard in isopropanol by weighing approximately 10 and 50 mg of the dry material to the nearest 0.01 mg. Quantitatively transfer each to a 1-L volumetric flask with approximately 200 mL isopropanol to which a few drops of surfactant have been added.

4. Ultrasonicate for 10 min at a power density of approximately 0.1 W/mL, to disperse the asbestos material.

5. Dilute to volume with isopropanol.

6. Place the flask on a magnetic stirring plate. Stir.

7. Prepare, in triplicate, a series of at least five standard filters to cover the desired analytical range, using appropriate aliquots of the 10 and 50 mg/L suspensions and the following procedure.

Mount a silver membrane filter on the filtration apparatus. Place a few milliliters of isopropanol in the reservoir. Vigorously hand shake the asbestos suspension and immediately withdraw an aliquot from the center of the suspension. Do not adjust the volume in the pipet by expelling part of the suspension; if more than the desired aliquot is withdrawn, discard the aliquot and resume the procedure with a clean pipet. Transfer

the aliquot to the reservoir. Keep the tip of the pipet near the surface of the isopropanol. Filter rapidly under vacuum. Do not wash the sides of the reservoir. Leave the vacuum on for a time sufficient to dry the filter. Release the vacuum and remove the filter with forceps.

#### 2.8.2 Analysis of Calibration Standards

1. Mount each filter on a flat holder. Perform step scans on selected diagnostic reflections of the standards and reference specimens using the procedure outlined in Section 2.7.2.3, step 12, and the same conditions as those used for the samples.

2. Determine the normalized intensity for each peak measured,  $\hat{I}_{std}$ , as outlined in Section 2.7.2.3, step 14.

### 2.9 Calculations

For each asbestos reference material, calculate the exact weight deposited on each standard filter from the concentrations of the standard suspensions and aliquot volumes. Record the weight,  $w$ , of each standard. Prepare a calibration curve by regressing  $\hat{I}_{std}$  on  $w$ . Poor reproducibility ( $\pm 15$  percent RSD) at any given level indicates problems in the sample preparation technique, and a need for new standards. The data should fit a straight line equation.

Determine the slope,  $m$ , of the calibration curve in counts/microgram. The intercept,  $b$ , of the line with the  $\hat{I}_{std}$  axis should be approximately zero. A large negative intercept indicates an error in determining the background. This may arise from incorrectly measuring the baseline or from interference by another phase at the angle of background measurement. A large positive intercept indicates an error in determining the baseline or that an impurity is included in the measured peak.

Using the normalized intensity,  $\hat{I}_{Ag}$ , for the attenuated silver peak of a sample, and the corresponding normalized intensity from the unattenuated silver peak,  $\hat{I}_{Ag}^o$ , of the sample filter, calculate the transmittance,  $T$ , for each sample as follows:<sup>26,27</sup>

$$T = \frac{\hat{I}_{Ag}}{\hat{I}_{Ag}^o}$$

Determine the correction factor,  $f(T)$ , for each sample according to the formula:

$$f(T) = \frac{-R(\ln T)}{1-T^R}$$

where

$$R = \frac{\sin \theta_{Ag}}{\sin \theta_a}$$

$\theta_{Ag}$ =angular position of the measured silver peak (from Bragg's Law), and

$\theta_a$ =angular position of the diagnostic asbestos peak.

Calculate the weight,  $W_a$ , in micrograms, of the asbestos material analyzed for in each sample, using the appropriate calibration data and absorption corrections:

$$W_a = \frac{\hat{I}_a f(t) - b}{m}$$

Calculate the percent composition,  $P_a$ , of each asbestos mineral analyzed for in the parent material, from the total sample weight,  $W_T$ , on the filter:

$$P_a = \frac{W_a(1-0.1L)}{W_T} \times 100$$

where

$P_a$ =percent asbestos mineral in parent material;

$W_a$ =mass of asbestos mineral on filter, in  $\mu\text{g}$ ;

$W_T$ =total sample weight on filter, in  $\mu\text{g}$ ;

$L$ =percent weight loss of parent material on ashing and/or acid treatment (see Section 2.7.2.3).

#### 2.10 References

- H. P. Klug and L. E. Alexander, *X-ray Diffraction Procedures for Polycrystalline and Amorphous Materials*, 2nd ed., New York: John Wiley and Sons, 1979.
- L. V. Azaroff and M. J. Buerger, *The Powder Method of X-ray Crystallography*, New York: McGraw-Hill, 1958.
- JCPDS-International Center for Diffraction Data Powder Diffraction File, U.S. Department of Commerce, National Bureau of Standards, and Joint Committee on Powder Diffraction Studies, Swarthmore, PA.
- W. J. Campbell, C. W. Huggins, and A. G. Wylie, *Chemical and Physical Characterization of Amosite, Chrysotile, Crocidolite, and Non-fibrous Tremolite for National Institute of Environmental Health Sciences Oral Ingestion Studies*, U.S. Bureau of Mines Report of Investigation RI8452, 1980.
- B. A. Lange and J. C. Haartz, Determination of microgram quantities of asbestos by X-ray diffraction: Chrysotile in thin dust layers of matrix material, *Anal. Chem.*, 51(4):520-525, 1979.
- NIOSH Manual of Analytical Methods, Volume 5, U.S. Dept. HEW, August 1979, pp. 309-1 to 309-9.
- H. Dunn and J. H. Stewart, Jr., Quantitative determination of chrysotile in building materials, *The Microscope*, 29(1), 1981.
- M. Taylor, Methods for the quantitative determination of asbestos and quartz in bulk samples using X-ray diffraction, *The Analyst*, 103(1231):1009-1020, 1978.
- L. Birks, M. Fatemi, J. V. Gilfrich, and E. T. Johnson, *Quantitative Analysis of Airborne Asbestos by X-ray Diffraction*, Naval Research Laboratory Report 7879, Naval Research Laboratory, Washington, DC, 1975.
- U.S. Environmental Protection Agency, *Asbestos-Containing Materials in School Buildings: A Guidance Document*, Parts 1 and 2, EPA/OPPT No. C00090, March 1979.
- J. B. Krause and W. H. Ashton, Misidentification of asbestos in talc, pp. 339-353, in: *Proceedings of Workshop on Asbestos: Definitions and Measurement Methods* (NBS Special Publication 506), C. C. Gravatt, P. D. LaFleur, and K. F. Heinrich (eds.), Washington, DC: National Measurement Laboratory, National Bureau of Standards, 1977 (issued 1978).
- H. D. Stanley, The detection and identification of asbestos and asbestiform minerals in talc, pp. 325-337, in *Proceedings of Workshop on Asbestos: Definitions and Measurement Methods* (NBS Special Publication 506), C. C. Gravatt, P. D. LaFleur, and K. F. Heinrich (eds.), Washington, DC, National Measurement Laboratory, National Bureau of Standards, 1977 (issued 1978).
- A. L. Rickards, Estimation of trace amounts of chrysotile asbestos by X-ray diffraction, *Anal. Chem.*, 44(11):1872-3, 1972.
- P. M. Cook, P. L. Smith, and D. G. Wilson, Amphibole fiber concentration and determination for a series of community air samples: use of X-ray diffraction to supplement electron microscope analysis, in: *Electron Microscopy and X-ray Applications to Environmental and Occupation Health Analysis*, P. A. Russell and A. E. Hutchings (eds.), Ann Arbor: Ann Arbor Science Publications, 1977.
- A. N. Rohl and A. M. Langer, Identification and quantitation of asbestos in talc, *Environ. Health Perspectives*, 9:95-109, 1974.
- J. L. Graf, P. K. Ase, and R. G. Draftz, *Preparation and Characterization of Analytical Reference Minerals*, DHEW (NIOSH) Publication No. 79-139, June 1979.
- J. C. Haartz, B. A. Lange, R. G. Draftz, and R. F. Scholl, Selection and characterization of fibrous and nonfibrous amphiboles for analytical methods development, pp. 295-312, in: *Proceedings of Workshop on Asbestos: Definitions and Measurement Methods* (NBS Special Publication 506), C. C. Gravatt, P. D. LaFleur, and K. F. Heinrich (eds.), Washington, DC: National Measurement Laboratory, National Bureau of Standards, 1977 (issued 1978).
- Personal communication, A. M. Langer, Environmental Sciences Laboratory, Mount

## Environmental Protection Agency

## § 763.123

Sinai School of Medicine of the City University of New York, New York, New York.

19. A. M. Langer, M. S. Wolff, A. N. Rohl, and I. J. Selikoff, Variation of properties of chrysotile asbestos subjected to milling, *J. Toxicol. and Environ. Health*, 4:173-188, 1978.

20. A. M. Langer, A. D. Mackler, and F. D. Pooley, Electron microscopical investigation of asbestos fibers, *Environ. Health Perspect.*, 9:63-80, 1974.

21. E. Occella and G. Maddalon, X-ray diffraction characteristics of some types of asbestos in relation to different techniques of comminution, *Med. Lavoro*, 54(10):628-636, 1963.

22. K. R. Spurny, W. Stöber, H. Opiela, and G. Weiss, On the problem of milling and ultrasonic treatment of asbestos and glass fibers in biological and analytical applications, *Am. Ind. Hyg. Assoc. J.*, 41:198-203, 1980.

23. L. G. Berry and B. Mason, *Mineralogy*, San Francisco: W. H. Greeman & Co., 1959.

24. J. P. Schelz, The detection of chrysotile asbestos at low levels in talc by differential thermal analysis, *Thermochimica Acta*, 8:197-204, 1974.

25. Reference 1, pp. 372-374.

26. J. Leroux, *Staub-Reinhalt Luft*, 29:26 (English), 1969.

27. J. A. Leroux, B. C. Davey, and A. Paillard, *Am. Ind. Hyg. Assoc. J.*, 34:409, 1973.

[47 FR 23369, May 27, 1982; 47 FR 38535, Sept. 1, 1982; Redesignated at 60 FR 31922, June 19, 1995]

### Subpart F [Reserved]

### Subpart G—Asbestos Worker Protection

SOURCE: 65 FR 69216, Nov. 15, 2000, unless otherwise noted.

#### § 763.120 What is the purpose of this subpart?

This subpart protects certain State and local government employees who are not protected by the Asbestos Standards of the Occupational Safety and Health Administration (OSHA). This subpart applies the OSHA Asbestos Standards in 29 CFR 1910.1001 and 29 CFR 1926.1101 to these employees.

#### § 763.121 Does this subpart apply to me?

If you are a State or local government employer and you are not subject to a State asbestos standard that OSHA has approved under section 18 of the Occupational Safety and Health Act or a State asbestos plan that EPA

has exempted from the requirements of this subpart under § 763.123, you must follow the requirements of this subpart to protect your employees from occupational exposure to asbestos.

#### § 763.122 What does this subpart require me to do?

If you are a State or local government employer whose employees perform:

(a) Construction activities identified in 29 CFR 1926.1101(a), you must:

(1) Comply with the OSHA standards in 29 CFR 1926.1101.

(2) Submit notifications required for alternative control methods to the Director, National Program Chemicals Division (7404), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460.

(b) Custodial activities not associated with the construction activities identified in 29 CFR 1926.1101(a), you must comply with the OSHA standards in 29 CFR 1910.1001.

(c) Repair, cleaning, or replacement of asbestos-containing clutch plates and brake pads, shoes, and linings, or removal of asbestos-containing residue from brake drums or clutch housings, you must comply with the OSHA standards in 29 CFR 1910.1001.

#### § 763.123 May a State implement its own asbestos worker protection plan?

This section describes the process under which a State may be exempted from the requirements of this subpart.

(a) *States seeking an exemption.* If your State wishes to implement its own asbestos worker protection plan, rather than complying with the requirements of this subpart, your State must apply for and receive an exemption from EPA.

(1) *What must my State do to apply for an exemption?* To apply for an exemption from the requirements of this subpart, your State must send to the Director of EPA's Office of Pollution Prevention and Toxics (OPPT) a copy of its asbestos worker protection regulations and a detailed explanation of how your State's asbestos worker protection plan meets the requirements of TSCA section 18 (15 U.S.C. 2617).

(2) *What action will EPA take on my State's application for an exemption?* EPA will review your State's application and make a preliminary determination whether your State's asbestos worker protection plan meets the requirements of TSCA section 18.

(i) If EPA's preliminary determination is that your State's plan does meet the requirements of TSCA section 18, EPA will initiate a rulemaking, including an opportunity for public comment, to exempt your State from the requirements of this subpart. After considering any comments, EPA will issue a final rule granting or denying the exemption.

(ii) If EPA's preliminary determination is that the State plan does not meet the requirements of TSCA section 18, EPA will notify your State in writing and will give your State a reasonable opportunity to respond to that determination.

(iii) If EPA does not grant your State an exemption, then the State and local government employers in your State are subject to the requirements of this subpart.

(b) *States that have been granted an exemption.* If EPA has exempted your State from the requirements of this subpart, your State must update its asbestos worker protection regulations as necessary to implement changes to meet the requirements of this subpart, and must apply to EPA for an amendment to its exemption.

(1) *What must my State do to apply for an amendment to its exemption?* To apply for an amendment to its exemption, your State must send to the Director of OPPT a copy of its updated asbestos worker protection regulations and a detailed explanation of how your State's updated asbestos worker protection plan meets the requirements of TSCA section 18. Your State must submit its application for an amendment within 6 months of the effective date of any changes to the requirements of this subpart, or within a reasonable time agreed upon by your State and OPPT.

(2) *What action will EPA take on my State's application for an amendment?* EPA will review your State's application for an amendment and make a preliminary determination whether your

State's updated asbestos worker protection plan meets the requirements of TSCA section 18.

(i) If EPA determines that the updated State plan does meet the requirements of TSCA section 18, EPA will issue your State an amended exemption.

(ii) If EPA determines that the updated State plan does not meet the requirements of TSCA section 18, EPA will notify your State in writing and will give your State a reasonable opportunity to respond to that determination.

(iii) If EPA does not grant your State an amended exemption, or if your State does not submit a timely request for amended exemption, then the State and local government employers in your State are subject to the requirements of this subpart.

#### Subpart H [Reserved]

### Subpart I—Prohibition of the Manufacture, Importation, Processing, and Distribution in Commerce of Certain Asbestos-Containing Products; Labeling Requirements

SOURCE: 54 FR 29507, July 12, 1989, unless otherwise noted.

#### § 763.160 Scope.

This subpart prohibits the manufacture, importation, processing, and distribution in commerce of the asbestos-containing products identified and at the dates indicated in §§ 763.165, 763.167, and 763.169. This subpart requires that products subject to this rule's bans, but not yet subject to a ban on distribution in commerce, be labeled. This subpart also includes general exemptions and procedures for requesting exemptions from the provisions of this subpart.

#### § 763.163 Definitions.

For purposes of this subpart:

*Act* means the Toxic Substances Control Act, 15 U.S.C. 2601 *et seq.*

*Agency* means the United States Environmental Protection Agency.

*Asbestos* means the asbestiform varieties of: chrysotile (serpentine); crocidolite (riebeckite); amosite (cummingtonite-grunerite); tremolite; anthophyllite; and actinolite.

*Asbestos-containing product* means any product to which asbestos is deliberately added in any concentration or which contains more than 1.0 percent asbestos by weight or area.

*Chemical substance*, has the same meaning as in section 3 of the Act.

*Commerce* has the same meaning as in section 3 of the Act.

*Commercial paper* means an asbestos-containing product which is made of paper intended for use as general insulation paper or muffler paper. Major applications of commercial papers are insulation against fire, heat transfer, and corrosion in circumstances that require a thin, but durable, barrier.

*Corrugated paper* means an asbestos-containing product made of corrugated paper, which is often cemented to a flat backing, may be laminated with foils or other materials, and has a corrugated surface. Major applications of asbestos corrugated paper include: thermal insulation for pipe coverings; block insulation; panel insulation in elevators; insulation in appliances; and insulation in low-pressure steam, hot water, and process lines.

*Customs territory of the United States* means the 50 States, Puerto Rico, and the District of Columbia.

*Distribute in commerce* has the same meaning as in section 3 of the Act, but the term does not include actions taken with respect to an asbestos-containing product (to sell, resale, deliver, or hold) in connection with the end use of the product by persons who are users (persons who use the product for its intended purpose after it is manufactured or processed). The term also does not include distribution by manufacturers, importers, and processors, and other persons solely for purposes of disposal of an asbestos-containing product.

*Flooring felt* means an asbestos-containing product which is made of paper felt intended for use as an underlayer for floor coverings, or to be bonded to the underside of vinyl sheet flooring.

*Import* means to bring into the customs territory of the United States, except for: (1) Shipment through the cus-

tom territory of the United States for export without any use, processing, or disposal within the customs territory of the United States; or (2) entering the customs territory of the United States as a component of a product during normal personal or business activities involving use of the product.

*Importer* means anyone who imports a chemical substance, including a chemical substance as part of a mixture or article, into the customs territory of the United States. *Importer* includes the person primarily liable for the payment of any duties on the merchandise or an authorized agent acting on his or her behalf. The term includes as appropriate:

(1) The consignee.

(2) The importer of record.

(3) The actual owner if an actual owner's declaration and superseding bond has been filed in accordance with 19 CFR 141.20.

(4) The transferee, if the right to withdraw merchandise in a bonded warehouse has been transferred in accordance with subpart C of 19 CFR part 144.

*Manufacture* means to produce or manufacture in the United States.

*Manufacturer* means a person who produces or manufactures in the United States.

*New uses of asbestos* means commercial uses of asbestos not identified in § 763.165 the manufacture, importation or processing of which would be initiated for the first time after August 25, 1989.

*Person* means any natural person, firm, company, corporation, joint-venture, partnership, sole proprietorship, association, or any other business entity; any State or political subdivision thereof, or any municipality; any interstate body and any department, agency, or instrumentality of the Federal Government.

*Process* has the same meaning as in section 3 of the Act.

*Processor* has the same meaning as in section 3 of the Act.

*Rollboard* means an asbestos-containing product made of paper that is produced in a continuous sheet, is flexible, and is rolled to achieve a desired thickness. Asbestos rollboard consists of two sheets of asbestos paper



## § 763.165

laminated together. Major applications of this product include: office partitioning; garage paneling; linings for stoves and electric switch boxes; and fire-proofing agent for security boxes, safes, and files.

*Specialty paper* means an asbestos-containing product that is made of paper intended for use as filters for beverages or other fluids or as paper fill for cooling towers. Cooling tower fill consists of asbestos paper that is used as a cooling agent for liquids from industrial processes and air conditioning systems.

*State* has the same meaning as in section 3 of the Act.

*Stock-on-hand* means the products which are in the possession, direction, or control of a person and are intended for distribution in commerce.

*United States* has the same meaning as in section 3 of the Act.

[59 FR 33208, June 28, 1994]

## § 763.165 Manufacture and importation prohibitions.

(a) After August 27, 1990, no person shall manufacture or import the following asbestos-containing products, either for use in the United States or for export: flooring felt and new uses of asbestos.

(b) After August 26, 1996, no person shall manufacture or import the following asbestos-containing products, either for use in the United States or for export: commercial paper, corrugated paper, rollboard, and specialty paper.

(c) The import prohibitions of this subpart do not prohibit:

(1) The import into the customs territory of the United States of products imported solely for shipment outside the customs territory of the United States, unless further repackaging or processing of the product is performed in the United States; or

(2) Activities involving purchases or acquisitions of small quantities of products made outside the customs territory of the United States for personal use in the United States.

[59 FR 33209, June 28, 1994]

## 40 CFR Ch. I (7-1-10 Edition)

### § 763.167 Processing prohibitions.

(a) After August 27, 1990, no person shall process for any use, either in the United States or for export, any of the asbestos-containing products listed at § 763.165(a).

(b) After August 26, 1996, no person shall process for any use, either in the United States or for export, any of the asbestos-containing products listed at § 763.165(b).

[59 FR 33209, June 28, 1994]

### § 763.169 Distribution in commerce prohibitions.

(a) After August 25, 1992, no person shall distribute in commerce, either for use in the United States or for export, any of the asbestos-containing products listed at § 763.165(a).

(b) After August 25, 1997, no person shall distribute in commerce, either for use in the United States or for export, any of the asbestos-containing products listed at § 763.165(b).

(c) A manufacturer, importer, processor, or any other person who is subject to a ban on distribution in commerce in paragraph (a) or (b) of this section must, within 6 months of the effective date of the ban of a specific asbestos-containing product from distribution in commerce, dispose of all their remaining stock-on-hand of that product, by means that are in compliance with applicable local, State, and Federal restrictions which are current at that time.

[59 FR 33209, June 28, 1994]

### § 763.171 Labeling requirements.

(a) After August 27, 1990, manufacturers, importers, and processors of all asbestos-containing products that are identified in § 763.165(a) shall label the products as specified in this subpart at the time of manufacture, import, or processing. This requirement includes labeling all manufacturers', importers', and processors' stock-on-hand as of August 27, 1990.

(b) After August 25, 1995, manufacturers, importers, and processors of all asbestos-containing products that are identified in § 763.165(b), shall label the products as specified in this subpart at the time of manufacture, import, or processing. This requirement includes

## Environmental Protection Agency

## § 763.173

labeling all manufacturers', importers', and processors' stock-on-hand as of August 25, 1995.

(c) The label shall be placed directly on the visible exterior of the wrappings and packaging in which the product is placed for sale, shipment, or storage. If the product has more than one layer of external wrapping or packaging, the label must be attached to the innermost layer adjacent to the product. If the innermost layer of product wrapping or packaging does not have a visible exterior surface larger than 5 square inches, either a tag meeting the requirements of paragraph (d) of this section must be securely attached to the product's innermost layer of product wrapping or packaging, or a label must be attached to the next outer layer of product packaging or wrapping. Any products that are distributed in commerce to someone other than the end user, shipped, or stored without packaging or wrapping must be labeled or tagged directly on a visible exterior surface of the product as described in paragraph (d) of this section.

(d)(1) Labels must be either printed directly on product packaging or in the form of a sticker or tag made of plastic, paper, metal, or other durable substances. Labels must be attached in such a manner that they cannot be removed without defacing or destroying them. Product labels shall appear as in paragraph (d)(2) of this section and consist of block letters and numerals of color that contrasts with the background of the label or tag. Labels shall be sufficiently durable to equal or exceed the life, including storage and disposal, of the product packaging or wrapping. The size of the label or tag must be at least 15.25 cm (6 inches) on each side. If the product packaging is too small to accommodate a label of this size, the label may be reduced in size proportionately to the size of the product packaging or wrapping down to a minimum 2.5 cm (1 inch) on each side if the product wrapping or packaging has a visible exterior surface larger than 5 square inches.

(2) Products subject to this subpart shall be labeled in English as follows:

### NOTICE

This product contains *ASBESTOS*. The U.S. Environmental Protection Agency has banned the distribution in U.S. commerce of this product under section 6 of the Toxic Substances Control Act (15 U.S.C. 2605) as of (insert effective date of ban on distribution in commerce). Distribution of this product in commerce after this date and intentionally removing or tampering with this label are *violations of Federal law*.

(e) No one may intentionally remove, deface, cover, or otherwise obscure or tamper with a label or sticker that has been applied in compliance with this section, except when the product is used or disposed of.

[59 FR 33209, June 28, 1994]

### § 763.173 Exemptions.

(a) Persons who are subject to the prohibitions imposed by § 763.165, § 763.167, or § 763.169 may file an application for an exemption. Persons whose exemption applications are approved by the Agency may manufacture, import, process, or distribute in commerce the banned product as specified in the Agency's approval of the application. No applicant for an exemption may continue the banned activity that is the subject of an exemption application after the effective date of the ban unless the Agency has granted the exemption or the applicant receives an extension under paragraph (b)(4) or (5) of this section.

(b) Application filing dates. (1) Applications for products affected by the prohibitions under §§ 763.165(a) and 763.167(a) may be submitted at any time and will be either granted or denied by EPA as soon as is feasible.

(2) Applications for products affected by the ban under § 763.169(a) may be submitted at any time and will be either granted or denied by EPA as soon as is feasible.

(3) Applications for products affected by the ban under §§ 763.165(b) and 763.167(b) may not be submitted prior to February 27, 1995. Complete applications received after that date, but before August 25, 1995, will be either granted or denied by the Agency prior to the effective date of the ban for the product. Applications received after August 25, 1995, will be either granted or denied by EPA as soon as is feasible.

(4) Applications for products affected by the ban under §763.169(b) may not be submitted prior to February 26, 1996. Complete applications received after that date, but before August 26, 1996, will be either granted or denied by the Agency prior to the effective date of the ban for the product. Applications received after August 26, 1996, will be either granted or denied by EPA as soon as is feasible.

(5) The Agency will consider an application for an exemption from a ban under §763.169 for a product at the same time the applicant submits an application for an exemption from a ban under §763.165 or §763.167 for that product. EPA will grant an exemption at that time from a ban under §763.169 if the Agency determines it appropriate to do so.

(6) If the Agency denies an application less than 30 days before the effective date of a ban for a product, the applicant can continue the activity for 30 days after receipt of the denial from the Agency.

(7) If the Agency fails to meet the deadlines stated in paragraphs (b)(3) and (b)(4) of this section for granting or denying a complete application in instances in which the deadline is before the effective date of the ban to which the application applies, the applicant will be granted an extension of 1 year from the Agency's deadline date. During this extension period the applicant may continue the activity that is the subject of the exemption application. The Agency will either grant or deny the application during the extension period. The extension period will terminate either on the date the Agency grants the application or 30 days after the applicant receives the Agency's denial of the application. However, no extension will be granted if the Agency is scheduled to grant or deny an application at some date after the effective date of the ban, pursuant to the deadlines stated in paragraphs (b)(3) and (b)(4) of this section.

(c) Where to file. All applications must be submitted to the following location: TSCA Docket Receipts Office (7407), Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, Rm E-G99, 1200 Pennsylvania Ave., NW., Washington, DC

20460, ATTENTION: Asbestos Exemption. For information regarding the submission of exemptions containing information claimed as confidential business information (CBI), see §763.179.

(d) Content of application and criteria for decisionmaking.

(1) Content of application. Each application must contain the following:

(i) Name, address, and telephone number of the applicant.

(ii) Description of the manufacturing, import, processing, and/or distribution in commerce activity for which an exemption is requested, including a description of the asbestos-containing product to be manufactured, imported, processed, or distributed in commerce.

(iii) Identification of locations at which the exempted activity would take place.

(iv) Length of time requested for exemption (maximum length of an exemption is 4 years).

(v) Estimated amount of asbestos to be used in the activity that is the subject of the exemption application.

(vi) Data demonstrating the exposure level over the life cycle of the product that is the subject of the application.

(vii) Data concerning:

(A) The extent to which non-asbestos substitutes for the product that is the subject of the application fall significantly short in performance under necessary product standards or requirements, including laws or ordinances mandating product safety standards.

(B) The costs of non-asbestos substitutes relative to the costs of the asbestos-containing product and, in the case in which the product is a component of another product, the effect on the cost of the end use product of using the substitute component.

(C) The extent to which the product or use serves a high-valued use.

(viii) Evidence of demonstrable good faith attempts by the applicant to develop and use a non-asbestos substance or product which may be substituted for the asbestos-containing product or the asbestos in the product or use that is the subject to the application.

(ix) Evidence, in addition to that provided in the other information required with the application, showing that the continued manufacture, importation,

## Environmental Protection Agency

## § 763.175

processing, distribution in commerce, and use, as applicable, of the product will not present an unreasonable risk of injury to human health.

(2) Criteria for decision (existing products). After considering all the information provided by an applicant under paragraphs (d)(1) and (e) of this section, and any other information available to EPA, EPA will grant an exemption from the prohibitions in §§ 763.165, 763.167, or 763.169 for an applicant's asbestos-containing product only if EPA determines both of the following:

(i) The applicant has made good faith attempts to develop and use a non-asbestos substance or product which may be substituted for the asbestos-containing product or the asbestos in the product or use, and those attempts have failed to produce a substitute or a substitute that results in a product that can be economically produced.

(ii) Continued manufacturing, processing, distribution in commerce, and use, as applicable, of the product will not present an unreasonable risk of injury to human health.

(3) Criteria for decision (new products). Requests to develop and use an asbestos substance or product will be treated as a petition pursuant to section 21 of TSCA.

(e) The Agency reserves the right to request further information from an exemption applicant if necessary to complete the Agency's evaluation of an application.

(f) Upon receipt of a complete application, the Agency will issue a notice in the FEDERAL REGISTER announcing its receipt and invite public comments on the merits of the application.

(g) If the application does not include all of the information required in paragraph (d) of this section, the Agency will return it to the applicant as incomplete and any resubmission of the application will be considered a new application for purposes of the availability of any extension period. If the application is substantially inadequate to allow the Agency to make a reasoned judgment on any of the information required in paragraph (d) of this section and the Agency chooses to request additional information from the applicant, the Agency may also deter-

mine that an extension period provided for in paragraph (b)(5) of this section is unavailable to the applicant.

(h) When denying an application, the Agency will notify the applicant by registered mail of its decision and rationale. Whenever possible, the Agency will send this letter prior to the appropriate ban. This letter will be considered a final Agency action for purposes of judicial review. A notice announcing the Agency's denial of the application will be published in the FEDERAL REGISTER.

(i) If the Agency proposes to approve an exemption, it will issue a notice in the FEDERAL REGISTER announcing this intent and invite public comments. If, after considering any timely comments received, the Agency approves an exemption, its decision will be published in the FEDERAL REGISTER. This notice will be considered a final Agency action for purposes of judicial review.

(j) The length of an exemption period will be specified by the agency when it approves the exemption. To extend an exemption period beyond the period stipulated by EPA, applicants must submit a new application to the Agency, following the application procedures described in this section. Applications may not be submitted prior to 15 months before the expiration of the exemption period, unless stated otherwise in the notice granting the exemption. Applications received between 15 months and 1 year before the end of the exemption period will be either granted or denied by the Agency before the end of the exemption period. Applications received after the date 1 year prior to the end of the exemption period will be either granted or denied by the Agency as soon as is feasible. Applicants may not continue the activity that is the subject of the renewal application after the date of the end of the exemption period.

[54 FR 29507, July 12, 1989; 54 FR 37531, Sept. 11, 1989, as amended at 54 FR 46898, Nov. 8, 1989; 59 FR 33210, June 28, 1994]

### § 763.175 Enforcement.

(a) Failure to comply with any provision of this subpart is a violation of section 15 of the Act (15 U.S.C. 2614).

(b) Failure or refusal to establish and maintain records, or to permit access

## § 763.176

## 40 CFR Ch. I (7–1–10 Edition)

to or copying of records as required by section 11 of the Act (15 U.S.C. 2610) is a violation of section 15 of the Act (15 U.S.C. 2614).

(c) Failure or refusal to permit entry or inspection as required by section 11 of the Act (15 U.S.C. 2610) is a violation of section 15 of the Act (15 U.S.C. 2614).

(d) Violators may be subject to the civil and criminal penalties in section 16 of the Act (15 U.S.C. 2615) for each violation.

(e) The Agency may seek to enjoin the manufacture, import, processing, or distribution in commerce of asbestos-containing products in violation of this subpart, or act to seize any asbestos-containing products manufactured, imported, processed, or distributed in commerce in violation of this subpart, or take any other actions under the authority of section 7 or 17 of the Act (15 U.S.C. 2606 or 2616) that are appropriate.

### § 763.176 Inspections.

The Agency will conduct inspections under section 11 of the Act (15 U.S.C. 2610) to ensure compliance with this subpart.

### § 763.178 Recordkeeping.

(a) *Inventory.* (1) Each person who is subject to the prohibitions imposed by §§ 763.165 and 763.167 must perform an inventory of the stock-on-hand of each banned product as of the effective date of the ban for that product for the applicable activity.

(2) The inventory shall be in writing and shall include the type of product, the number of product units currently in the stock-on-hand of the person performing the inventory, and the location of the stock.

(3) Results of the inventory for a banned product must be maintained by the person for 3 years after the effective date of the § 763.165 or § 763.167 ban on the product.

(b) *Records.* (1) Each person whose activities are subject to the bans imposed by §§ 763.165, 763.167, and 763.169 for a product must, between the effective date of the § 763.165 or § 763.167 ban on the product and the § 763.169 ban on the product, keep records of all commercial transactions regarding the product, including the dates of purchases

and sales and the quantities purchased or sold. These records must be maintained for 3 years after the effective date of the § 763.169 ban for the product.

(2) Each person who is subject to the requirements of § 763.171 must, for each product required to be labeled, maintain a copy of the label used in compliance with § 763.171. These records must be maintained for 3 years after the effective date of the ban on distribution in commerce for the product for which the § 763.171 requirements apply.

[54 FR 29507, July 12, 1989, as amended by 54 FR 46898, Nov. 8, 1989; 58 FR 34205, June 23, 1993]

### § 763.179 Confidential business information claims.

(a) Applicants for exemptions under § 763.173 may assert a Confidential Business Information (CBI) claim for information in an exemption application or supplement submitted to the Agency under this subpart only if the claim is asserted in accordance with this section, and release of the information would reveal trade secrets or confidential commercial or financial information, as provided in section 14(a) of the Act. Information covered by a CBI claim will be treated in accordance with the procedures set forth in 40 CFR part 2, subpart B. The Agency will place all information not claimed as CBI in the manner described in this section in a public file without further notice to the applicant.

(b) Applicants may assert CBI claims only at the time they submit a completed exemption application and only in the specified manner. If no such claim accompanies the information when it is received by the Agency, the information may be made available to the public without further notice to the applicant. Submitters that claim information as business confidential must do so by writing the word “Confidential” at the top of the page on which the information appears and by underlining, circling, or placing brackets ([ ]) around the information claimed CBI.

(c) Applicants who assert a CBI claim for submitted information must provide the Agency with two copies of their exemption application. The first copy must be complete and contain all

information being claimed as CBI. The second copy must contain only information not claimed as CBI. The Agency will place the second copy of the submission in a public file. Failure to furnish a second copy of the submission when information is claimed as CBI in the first copy will be considered a presumptive waiver of the claim of confidentiality. The Agency will notify the applicant by certified mail that a finding of a presumptive waiver of the claim of confidentiality has been made. The applicant has 30 days from the date of receipt of notification to submit the required second copy. Failure to submit the second copy will cause the Agency to place the first copy in a public file.

(d) Applicants must substantiate all claims of CBI at the time the applicant asserts the claim, i.e., when the exemption application or supplement is submitted, by responding to the questions in paragraph (e) of this section. Failure to provide substantiation of a claim at the time the applicant submits the application will result in a waiver of the CBI claim, and the information may be disclosed to the public without further notice to the applicant.

(e) Applicants who assert any CBI claims must substantiate all claims by providing detailed responses to the following:

(1) Is this information subject to a patent or patent application in the United States or elsewhere? If so, why is confidentiality necessary?

(2) For what period do you assert a claim of confidentiality? If the claim is to extend until a certain event or point in time, please indicate that event or time period. Explain why such information should remain confidential until such point.

(3) Has the information that you are claiming as confidential been disclosed to persons outside of your company? Will it be disclosed to such persons in the future? If so, what restrictions, if any, apply to use or further disclosure of the information?

(4) Briefly describe measures taken by your company to guard against undesired disclosure of the information you are claiming as confidential to others.

(5) Does the information claimed as confidential appear or is it referred to in advertising or promotional materials for the product or the resulting end product, safety data sheets or other similar materials for the product or the resulting end product, professional or trade publications, or any other media available to the public or to your competitors? If you answered yes, indicate where the information appears.

(6) If the Agency disclosed the information you are claiming as confidential to the public, how difficult would it be for the competitor to enter the market for your product? Consider in your answer such constraints as capital and marketing cost, specialized technical expertise, or unusual processes.

(7) Has the Agency, another Federal agency, or a Federal court made any confidentiality determination regarding this information? If so, provide copies of such determinations.

(8) How would your company's competitive position be harmed if the Agency disclosed this information? Why should such harm be considered substantial? Describe the causal relationship between the disclosure and harm.

(9) In light of section 14(b) of TSCA, if you have claimed information from a health and safety study as confidential, do you assert that disclosure of this information would disclose a process used in the manufacturing or processing of a product or information unrelated to the effects of asbestos on human health and the environment? If your answer is yes, explain.

## PART 766—DIBENZO-PARADIOXINS/DIBENZOFURANS

### Subpart A—General Provisions

#### Sec.

- 766.1 Scope and purpose.
- 766.2 Applicability and duration of this part.
- 766.3 Definitions.
- 766.5 Compliance.
- 766.7 Submission of information.
- 766.10 Test standards.
- 766.12 Testing guidelines.
- 766.14 Contents of protocols.
- 766.16 Developing the analytical test method.

## § 766.1

## 40 CFR Ch. I (7–1–10 Edition)

766.18 Method sensitivity.

### Subpart B—Specific Chemical Testing/ Reporting Requirements

766.20 Who must test.  
766.25 Chemical substances for testing.  
766.27 Congeners and LOQs for which quantitation is required.  
766.28 Expert review of protocols.  
766.32 Exclusions and waivers.  
766.35 Reporting requirements.  
766.38 Reporting on precursor chemical substances.

AUTHORITY: 15 U.S.C. 2603 and 2607.

SOURCE: 52 FR 21437, June 5, 1987, unless otherwise noted.

### Subpart A—General Provisions

#### § 766.1 Scope and purpose.

(a) This part identifies requirements for testing under section 4 of the Toxic Substances Control Act (TSCA), 15 U.S.C. 2603, to ascertain whether certain specified chemical substances may be contaminated with halogenated dibenzodioxins (HDDs)/dibenzofurans (HDFs) as defined in § 766.3, and requirements for reporting under section 8 of TSCA, 15 U.S.C. 2607.

(b) Section 766.35(b) requires manufacturers and processors of chemical substances identified in § 766.25 to submit to EPA:

(1) Any existing test data showing analysis of the chemical substances for concentrations of HDDs/HDFs, applicable protocols, and the results of the analysis for HDDs/HDFs, (2) allegations of significant adverse reactions to HDDs/HDFs, compiled in accordance with part 717 of this chapter, and (3) health and safety studies on the HDDs/HDFs, in accordance with applicable provisions of part 716 of this chapter.

(c) Section 766.35(a) requires manufacturers and, under certain circumstances, processors of chemical substances identified in § 766.25 to submit letters of intent to test and protocols for the analysis of the chemical substances for the presence of HDDs/HDFs. Section 766.20 requires these manufacturers and processors to test their chemical substances for the presence of HDDs/HDFs. Any submissions must be in accordance with the EPA Procedures Governing Testing Consent Agreements and Test Rules contained

in part 790 of this chapter and any modifications to such procedures contained in this part.

(d) Section 766.32 specifies conditions under which persons required to test may request an exclusion or waiver from testing.

(e) Deadlines for submission to EPA of protocols, reports, studies, and test results are specified in part 790, subpart C and § 766.35.

(f) Sections 766.10, 766.12, 766.14, 766.16, and 766.18 prescribe analytical methods required; § 766.27 prescribes target levels of quantitation (LOQ) for each congener for which quantitation is required.

(g) If results of existing tests or tests performed under this part indicate the presence of HDDs/HDFs in the identified chemical substance above the LOQ specified in § 766.27, § 766.35(c) requires the following additional reporting on the specified chemicals: production, process, use, exposure and disposal data under section 8(a) of TSCA; health and safety studies under section 8(d) of TSCA; and reports of allegations of significant adverse reactions under section 8(c) of TSCA. In some cases, additional reporting may be required of manufacturers reporting no contamination of the identified chemical substances under § 766.35(c)(2).

(h) Section 766.38 requires manufacturers of chemical substances produced from chemical substances identified as possible precursors to HDD/HDF formation, to report on chemical substances produced from such precursors.

#### § 766.2 Applicability and duration of this part.

(a) *Chemical substances subject to testing.* (1) This part is applicable to each person who, at any time during the duration of this part, manufactures (and/or imports), or processes, a chemical substance identified under § 766.25.

(2) The duration of this part for any testing requirement for any chemical substance is the period commencing with the effective date of this part to the end of the reimbursement period, as defined in § 766.3, for each chemical substance. All reporting requirements for any chemical substance listed under § 766.25 shall be in effect for the

## Environmental Protection Agency

## § 766.3

same period as the testing requirement.

(b) *Precursor chemical substances.* (1) This part is applicable to each person who manufactures (and/or imports) a chemical substance from any precursor chemical substance identified in § 766.38.

(2) The requirement for precursor reporting under § 766.38 shall be in effect until three years after the effective date of this part.

(3) Small manufacturers are exempt from reporting process and reaction condition data on chemical substances made from precursor chemical substances listed under § 766.38.

### § 766.3 Definitions.

The definitions in section 3 of TSCA and the definitions of §§ 704.3, 716.3, 717.3, and 790.3 of this chapter also apply to this part.

*Congener* means any one particular member of a class of chemical substances. A specific congener is denoted by unique chemical structure, for example 2,3,7,8-tetrachlorodibenzofuran.

*Dibenzofuran* means any of a family of compounds which has as a nucleus a triple-ring structure consisting of two benzene rings connected through a pair of bridges between the benzene rings. The bridges are a carbon-carbon bridge and a carbon-oxygen-carbon bridge at both substitution positions.

*Dibenzo-p-dioxin* or *dioxin* means any of a family of compounds which has as a nucleus a triple-ring structure consisting of two benzene rings connected through a pair of oxygen atoms.

*Guidelines* means the Midwest Research Institute (MRI) publication *Guidelines for the Determination of Polyhalogenated Dioxins and Dibenzofurans in Commercial Products*, EPA contract No. 68-02-3938; MRI Project No. 8201-A(41), 1985.

*HDD* or *2,3,7,8-HDD* means any of the dibenzo-p-dioxins totally chlorinated or totally brominated at the following positions on the molecular structure: 2,3,7,8; 1,2,3,7,8; 1,2,3,4,7,8; 1,2,3,6,7,8; 1,2,3,7,8,9; and 1,2,3,4,7,8,9.

*HDF* or *2,3,7,8-HDF* means any of the dibenzofurans totally chlorinated or totally brominated at the following positions on the molecular structure: 2,3,7,8; 1,2,3,7,8; 2,3,4,7,8; 1,2,3,4,7,8;

1,2,3,6,7,8; 1,2,3,7,8,9; 2,3,4,6,7,8; 1,2,3,4,6,7,8; and 1,2,3,4,7,8,9.

*Homolog* means a group of isomers that have the same degree of halogenation. For example, the homologous class of tetrachlorodibenzo-p-dioxins consists of all dibenzo-p-dioxins containing four chlorine atoms. When the homologous classes discussed in this part are referred to, the following abbreviations for the prefix denoting the number of halogens are used:

tetra-, T (4 atoms)  
penta-, Pe (5 atoms)  
hexa-, Hx (6 atoms)  
hepta-, Hp (7 atoms)

*HRGC* means high resolution gas chromatography.

*HRMS* means high resolution mass spectrometry.

*Level of quantitation* or *LOQ* means the lowest concentration at which HDDs/HDFs can be reproducibly measured in a specific chemical substance within specified confidence limits, as described in this part.

*Polybrominated dibenzofurans* refers to any member of a class of dibenzofurans with two to eight bromine substituents.

*Polybrominated dibenzo-p-dioxin* or *PBDD* means to any member of a class of dibenzo-p-dioxins with two to eight bromine substituents.

*Polychlorinated dibenzofuran* means any member of a class of dibenzofurans with two to eight chlorine substituents.

*Polychlorinated dibenzo-p-dioxin* or *PCDD* means any member of a class of dibenzo-p-dioxins with two to eight chlorine substituents.

*Polyhalogenated dibenzofuran* or *PHDF* means any member of a class of dibenzofurans containing two to eight chlorine, bromine, or a combination of chlorine and bromine substituents.

*Polyhalogenated dibenzo-p-dioxin* or *PHDD* means any member of a class of dibenzo-p-dioxins containing two to eight chlorine substituents or two to eight bromine substituents.

*Positive test result* means: (1) Any resolvable gas chromatographic peak for any 2,3,7,8-HDD or HDF which exceeds the LOQ listed under § 766.27 for that congener, or (2) exceeds LOQs approved by EPA under § 766.28.



## §766.5

*Precursor* means a chemical substance which is not contaminated due to the process conditions under which it is manufactured, but because of its molecular structure, and under favorable process conditions, it may cause or aid the formation of HDDs/HDFs in other chemicals in which it is used as a feedstock or intermediate.

*QA* means quality assurance.

*QC* means quality control.

*Reimbursement period* means the period that begins when the data from the last test to be completed under this part for a specific chemical substance listed in §766.25 is submitted to EPA, and ends after an amount of time equal to that which had been required to develop that data or 5 years, whichever is later.

*TSCA* means the Toxic Substances Control Act, 15 U.S.C. 2601 *et seq.*

## §766.5 Compliance.

Any person who fails or refuses to comply with any aspect of this part is in violation of section 15 of TSCA. Section 15(1) makes it unlawful for any person to fail or refuse to comply with any rule or order issued under section 4. Section 15(3) makes it unlawful for any person to fail or refuse to submit information required under this part. Section 16 provides that a violation of section 15 renders a person liable to the United States for a civil penalty and possible criminal prosecution. Under section 17 of TSCA, the district courts of the United States have jurisdiction to restrain any violation of section 15.

## §766.7 Submission of information.

All information (including letters of intent, protocols, data, forms, studies, and allegations) submitted to EPA under this part must bear the applicable Code of Federal Regulations (CFR) section number (e.g., §766.20) and must be addressed to: Document Control Office, (7407), Information Management Division, Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460, ATTN: Dioxin/Furan Report.

[52 FR 21437, June 5, 1987, as amended at 60 FR 31922, June 19, 1995]

## 40 CFR Ch. I (7-1-10 Edition)

## §766.10 Test standards.

Testing required under subpart B of this part must be performed using the protocols submitted to and reviewed by the EPA expert panel established under §766.28. All new data, documentation, records, protocols, specimens, and reports generated as a result of testing under subpart B of this part must be fully developed and retained in accordance with part 792 of this chapter. These items must be made available during an inspection or submitted to EPA upon request by EPA or its authorized representative. Laboratories conducting testing for submission to EPA in response to a test rule promulgated under section 4 of TSCA must adhere to the TSCA Good Laboratory Practices (GLPs) published in part 792 of this chapter. Sponsors must notify the laboratory that the testing is being conducted pursuant to TSCA section 4. Sponsors are also responsible for ensuring that laboratories conducting the testing abide by the TSCA GLP standards. At the time test data are submitted, manufacturers must submit a certification to EPA that the laboratory performing the testing adhered to the TSCA GLPs.

## §766.12 Testing guidelines.

Analytical test methods must be developed using methods equivalent to those described or reviewed in *Guidelines for the Determination of Polyhalogenated Dibenzo-p-dioxins and Dibenzofurans in Commercial Products*. Copies are available from the Director, Environmental Assistance Division (7408), Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, Room E-543B, 1200 Pennsylvania Ave., NW., Washington, DC 20460, Telephone: (202) 554-1404, TDD: (202) 544-0551. Copies are also located in the public docket for this part (Docket No. OPPTS-83002) and are available for inspection in the Non-Confidential Information Center (NCIC) (7407), Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency, Room B-607 NEM, 401 M St., SW., Washington, DC 20460, between the hours of 12 p.m. and 4 p.m. weekdays excluding legal holidays.

[60 FR 34466, July 3, 1995]

## Environmental Protection Agency

## § 766.18

### § 766.14 Contents of protocols.

Protocols should include all parts of the *Quality Assurance Plan for Measurement of Brominated or Chlorinated Dibenzofurans and Dibenzodioxins*, as stated in the Guidelines. For each chemical substance and each process, the manufacturer must submit a statement of how many grades of the chemical substance it produces, a justification for selection of the specific grade of chemical substance for testing, specific plans for collection of samples from the process stream, naming the point of collection, the method of collecting the sample, and an estimate of how well the samples will represent the material to be characterized; a description of how control samples (blanks) and HDD/HDF-reinforced control samples, or isotopically labeled compounds (standards) and duplicate samples will be handled; a description of the chemical extraction and clean up procedures to be used; how extraction efficiency and measurement efficiency will be established; and a description of instrument hardware and operating conditions, including type and source of columns, carrier gas and flow rate, operating temperature range, and ion source temperature.

### § 766.16 Developing the analytical test method.

Because of the matrix differences of the chemicals listed for testing, no one method for sample selection, preparation, extraction and clean up is prescribed. For analysis, High Resolution Gas Chromatography (HRGC) with High Resolution Mass Spectrometry (HRMS) is the method of choice, but other methods may be used if they can be demonstrated to reach the target LOQs as well as HRGC/HRMS.

(a) *Sample selection.* The chemical product to be tested should be sampled so that the specimens collected for analysis are representative of the whole. Additional guidance for sample selection is provided under § 766.12.

(b) *Sample preparation.* The sample must be mechanically homogenized and subsampled as necessary. Subsamples must be spiked or reinforced with surrogate compounds or with standard stock solutions, and the surrogates or standards must be thoroughly incor-

porated by mechanical agitation. Additional guidance is provided under § 766.12.

(c) *Sample extraction and cleanup.* The spiked samples must be treated to separate the HDDs/HDFs from the sample matrix. Methods are reviewed in the Guidelines under § 766.12, but the final method or methods are left to the discretion of the analyst, provided the instrumental response of the surrogates meets the criteria listed in the *Quality Assurance Plan for Measurement of Brominated or Chlorinated Dibenzofurans and Dibenzodioxins*, Appendixes B and C of the Guidelines. Cleanup techniques are described in the Guidelines. These are chosen at the discretion of the analyst to meet the requirements of the chemical matrix.

(d) *Analysis.* The method of choice is High Resolution Gas Chromatographic/High Resolution Mass Spectrometric Determination, (HRGC/HRMS) but alternate methods may be used if the manufacturer can demonstrate that the method will reach the target LOQs as well as HRGC/HRMS. Specific operating requirements are found in the Guidelines.

### § 766.18 Method sensitivity.

The target level of quantitation required under § 766.27 for each HDD/HDF congener is the level which must be attempted for each resolved HRGC peak for that congener. For at least one product sample, at least two analyses of the same isotopically labeled HDD/HDF internal calibration standards spiked to a final product concentration equal to the LOQ for that congener must be reproducibly extracted, cleaned up, and quantified to within  $\pm 20$  percent of each other. For each spiked product sample, the signal to noise ratio for the calibration standard peaks after complete extraction and cleanup must be 10:1 or greater. The recovery of the internal calibration standards in the extracted and cleaned up product samples must be within 50 to 150 percent of the amount spiked, and the results must be corrected for recovery.

**Subpart B—Specific Chemical Testing/Reporting Requirements**

**§ 766.20 Who must test.**

(a) Any person who manufactures, imports, or processes a chemical substance listed in § 766.25 must test that chemical substance and must submit appropriate information to EPA according to the schedules described in § 766.35. Chemical substances manufactured, imported or processed between January 1, 1984 and the date of promulgation of this part are subject to testing upon the effective date of this part. All other chemical substances are subject to testing immediately upon manufacture, import or processing. EPA expects that only manufacturers and importers will perform testing, and that the cost of testing will be passed on to processors through the pricing mechanism, thereby enabling them to share in the cost of testing. However, processors will be called upon to sponsor testing should manufacturers and importers fail to do so. A processor may apply for an exemption from testing upon certification to EPA that a manufacturer or importer is testing the chemical substance which that person processes.

(b) If no manufacturer or importer described in § 766.20 submits a letter of intent to perform testing within the period described under § 766.35(a), or an exemption application under § 790.45(a), or a request for an exclusion or waiver under § 766.32, EPA will issue a notice in the FEDERAL REGISTER to notify all processors of that chemical substance. The notice will state that EPA has not received any of the documents described in the previous sentence, and that current processors will have 30 days to submit either a letter of intent to perform the test or submit an exemption application.

(c) If no manufacturer, importer or processor submits a letter of intent to perform testing of a specific chemical substance produced by a specific process, EPA will notify all manufacturers, importers, and processors, either by notice in the FEDERAL REGISTER or by letter, that all exemption applications will be denied and that within 30 days all manufacturers, importers, and processors will be in violation of this part

until a proposed study plan is submitted for required testing.

(d) Manufacturers, importers, and processors who are subject to this part must comply with the test rule development and exemption procedures in part 790 of this chapter, except as modified in this part.

**§ 766.25 Chemical substances for testing.**

(a) *Listing of chemical substances.* Chemical substances required to be tested for HDDs/HDFs under this rule are listed in this section. The listing is by Chemical Abstracts Service (CAS) Number and common name.

NOTE: For purposes of guidance only, EPA lists the chemical substances subject to testing under this part in two classes—those known to be manufactured or imported between January 1, 1984, and promulgation of this part, and those not known to be manufactured or imported at the time of promulgation of this part.

(1) *Chemicals substances known to be manufactured between January 1, 1984 and date of promulgation of this part.*

| CAS No.    | Chemical name                                      |
|------------|--|
| 79-94-7    | Tetrabromobisphenol-A.                             |
| 118-75-2   | 2,3,5,6-Tetrachloro-2,5-cyclohexadiene-1,4-dione.  |
| 118-79-6   | 2,4,6-Tribromophenol.                              |
| 120-83-2   | 2,4-Dichlorophenol.                                |
| 1163-19-5  | Decabromodiphenyloxide.                            |
| 4162-45-2  | Tetrabromobisphenol-A-bisethoxylate.               |
| 21850-44-2 | Tetrabromobisphenol-A-bis-2,3-dibromopropyl ether. |
| 25327-89-3 | Allyl ether of tetrabromobisphenol-A.              |
| 32534-81-9 | Pentabromodiphenyloxide.                           |
| 32536-52-0 | Octabromodiphenyloxide.                            |
| 37853-59-1 | 1,2-Bis(tribromophenoxy)-ethane.                   |
| 55205-38-4 | Tetrabromobisphenol-A diacrylate.                  |

(2) *Chemicals not known to be manufactured between January 1, 1984 and the date of promulgation of this part.*

| CAS No.   | Chemical name                            |
|-----------|--|
| 79-95-8   | Tetrachlorobisphenol-A.                  |
| 87-10-5   | 3,4',5-Tribromosalicylanilide.           |
| 87-65-0   | 2,6-Dichlorophenol.                      |
| 95-77-2   | 3,4-Dichlorophenol.                      |
| 95-95-4   | 2,4,5-Trichlorophenol.                   |
| 99-28-5   | 2,6-Dibromo-4-nitrophenol.               |
| 120-36-5  | 2[2,4-(Dichlorophenoxy)]-propionic acid. |
| 320-72-9  | 3,5-Dichlorosalicylic acid.              |
| 488-47-1  | Tetrabromocatechol.                      |
| 576-24-9  | 2,3-Dichlorophenol.                      |
| 583-78-8  | 2,5-Dichlorophenol.                      |
| 608-71-9  | Pentabromophenol.                        |
| 615-58-7  | 2,4-Dibromophenol.                       |
| 933-75-5  | 2,3,6-Trichlorophenol.                   |
| 1940-42-7 | 4-Bromo-2,5-dichlorophenol.              |
| 2577-72-2 | 3,5-Dibromosalicylanilide.               |

**Environmental Protection Agency**

**§ 766.32**

| CAS No.    | Chemical name  |
|------------|--|
| 3772-94-9  | Pentachlorophenyl laurate.   |
| 37853-61-5 | Bismethylether of tetrabromobisphenol-A.<br>Alkylamine tetrachlorophenate.<br>Tetrabromobisphenol-B. |

(b) *Grade to be tested.* If the same process is used to manufacture all grades of the same chemical substance, only one grade need be tested. The grade to be tested must be the grade subject to the most intense heat and alkalinity for the longest duration of time, manufactured under each different process. If the heat, alkalinity and duration of reaction do not differ for various grades, the test substance must be the grade of chemical substance with the highest volume of sales.

**§ 766.27 Congeners and LOQs for which quantitation is required.**

Quantitation at the target LOQ shown for each of the following HDDs/HDFs which may be present in the chemical substances is required for the chemical substances listed under § 766.25. Analysis must take place for either chlorinated or brominated dibenzodioxins or dibenzofurans, whichever is predominantly expected to occur in the chemical substance to be tested. Only chlorinated and brominated congeners need be quantified; for chemical substances containing predominantly chlorine atoms, only congeners totally chlorinated at the numbered positions need be quantified; for chemical substances containing predominantly bromine atoms, only congeners totally brominated at the numbered positions need be quantified.

| Chlorinated dioxins     | Brominated dioxins      | LOQ      |
|-------------------------|-------------------------|----------|
| 2,3,7,8-TCDD .....      | 2,3,7,8-TBDD .....      | 0.1 ppb. |
| 1,2,3,7,8-PeCDD .....   | 1,2,3,7,8-PeBDD .....   | 0.5 ppb. |
| 1,2,3,4,7,8-HxCDD ..... | 1,2,3,4,7,8-HxBDD ..... | 2.5 ppb. |
| 1,2,3,6,7,8-HxCDD ..... | 1,2,3,6,7,8-HxBDD ..... | 2.5 ppb. |
| 1,2,3,7,8,9-HxCDD ..... | 1,2,3,7,8,9-HxBDD ..... | 2.5 ppb. |
| 1,2,3,4,6,7,8-HpCDD ... | 1,2,3,4,6,7,8-HpBDD ... | 100 ppb. |
| 2,3,7,8-TCDF .....      | 2,3,7,8-TBDF .....      | 1 ppb.   |
| 1,2,3,7,8-PeCDF .....   | 1,2,3,7,8-PeBDF .....   | 5 ppb.   |
| 2,3,4,7,8-PeCDF .....   | 2,3,4,7,8-PeBDF .....   | 5 ppb.   |
| 1,2,3,4,7,8-HxCDF ..... | 1,2,3,4,7,8-HxBDF ..... | 25 ppb.  |
| 1,2,3,6,7,8-HxCDF ..... | 1,2,3,6,7,8-HxBDF ..... | 25 ppb.  |
| 1,2,3,7,8,9-HxCDF ..... | 1,2,3,7,8,9-HxBDF ..... | 25 ppb.  |
| 2,3,4,6,7,8-HxCDF ..... | 2,3,4,6,7,8-HxBDF ..... | 25 ppb.  |
| 1,2,3,4,6,7,8-HpCDF ... | 1,2,3,4,6,7,8-HpBDF ... | 1 ppm.   |
| 1,2,3,4,7,8,9-HpCDF ... | 1,2,3,4,7,8,9-HpBDF ... | 1 ppm.   |

**§ 766.28 Expert review of protocols.**

EPA will gather a panel of experts in analysis of chemical matrices for HDDs/HDFs to review the protocols for testing submitted to EPA. The panel members will be employees of EPA and/or of other U.S. Government agencies who have had experience in analysis of chemical matrices and/or chemical wastes for HDDs/HDFs. The panel will recommend to the Director, EPA Office of Pollution Prevention and Toxics, whether the protocol submitted is likely to allow analysis down to the target LOQs, or if not, whether the protocol represents a good faith effort on the part of the tester to achieve the lowest possible LOQs. The final determination to accept or reject the protocol will be made by the Director, Office of Pollution Prevention and Toxics. EPA will review the submitted protocols as rapidly as possible and will complete the review within 90 days after receipt. EPA may require submission of revised protocols. Comments and recommendations will be transmitted to the submitter, and if revisions are required, a final protocol must be submitted to EPA within 90 days after EPA transmits such recommendations.

**§ 766.32 Exclusions and waivers.**

(a) *Reasons for exclusions and waivers.* Any person subject to the testing requirements of this part may request an exclusion or waiver from testing for any one of the following reasons:

(1) *Exclusions may be granted if.* (i) Testing of the appropriate grade of the chemical substance has already been carried out, either analytical testing at the lowest LOQ possible, with appropriate QA/QC, or a well-designed bioassay with appropriate QA/QC or;

(ii) Process and reaction conditions of the chemical substance such that no HDDs/HDFs could be produced under those conditions;

(2) *Waivers may be granted if.* (i) A responsible company official certifies that the chemical substance is produced only in quantities of 100 kilograms or less per year, only for research and development purposes; or

(ii) In the judgement of EPA, the cost of testing would drive the chemical substance off the market, or prevent

resumption of manufacture or import of the chemical substance, if it is not currently manufactured, and the chemical substance will be produced so that no unreasonable risk will occur due to its manufacture, import, processing, distribution, use, or disposal. (In this case, the manufacturer must submit to EPA all data supporting the determination.)

(iii) Waivers may be appropriately conditioned with respect to such factors as time and conditions of manufacture or use. The grade of decabromodiphenyl oxide produced by Dow Chemical Company (Dow) for the National Toxicology Program (NTP) bioassay on that chemical is excluded from the testing requirement under this part. Provided, however, that this exclusion will not apply if Dow fails to supply to EPA within 60 days of the effective date of this section evidence showing which grade was used for the NTP bioassay.

(b) *Timing.* Exclusion or waiver requests and detailed supporting data must be submitted to EPA within 60 days from the effective date of this part for persons manufacturing, importing or processing a chemical substance as of the date of promulgation, or 60 days prior to the date of resumption of manufacture or import for a chemical substance produced by a specific process if the chemical substance is not manufactured, imported or processed as of the date of promulgation.

(c) *Publication.* Within 10 days of receipt of any exclusion or waiver request, EPA will issue in the FEDERAL REGISTER a notice of such receipt. EPA will also issue a notice of its decision on each exclusion or waiver request within 60 days of receipt.

(d) *Decision.* The EPA Director of the Office of Pollution Prevention and Toxics will make the decision to grant or deny waivers or exclusions.

#### § 766.35 Reporting requirements.

(a) *Letters of intent, exemption applications, and protocols*—(1) *Letters of Intent.* (i) Persons who have manufactured or imported chemical substances listed under § 766.25 between January 1, 1984, and the effective date of this part are required to submit under § 790.45 of this chapter a letter of intent to test or an

exemption application. These letters must be submitted no later than September 3, 1987.

(ii) Persons who commence manufacture, import or processing of a chemical substance listed under § 766.25 that has not been manufactured, imported or processed between January 1, 1984 and the effective date of this part must submit under § 790.45 of this chapter, within 60 days after the commencement of manufacture, import, or processing of the chemical substance, a letter of intent to test or an exemption application.

(iii) Persons who commence manufacture, import or processing of a chemical substance listed under § 766.25 between the effective date of this part and the end of the reimbursement period for that particular chemical substance produced by a specific process must submit under § 790.45 of this chapter, within 60 days after the commencement of manufacture, import or processing of the chemical substance, a letter of intent to test or an exemption application.

(2) *Protocols.* (i) Each person who is manufacturing or processing a chemical substance listed in § 766.25 as of the effective date of this part who submits a notice of intent to test under § 766.35(a)(1) must submit a protocol for the test as follows:

(A) The protocols for each chlorinated chemical substance produced by each process to be tested must be submitted to EPA no later than 12 months after the effective date of this part.

(B) The protocol for each brominated chemical substance produced by each process to be tested must be submitted to EPA no later than 24 months after the effective date of this part except for the following chemicals.

(1) The deadline for submitting the protocols for tetrabromobisphenol-A (CAS No. 79-94-7); 2,4,6 tribromophenol (CAS No. 118-79-6); decabromodiphenyloxide (CAS No. 1163-19-5); and 1,2-bis(tribromophenoxy)-ethane (CAS No. 37853-59-1) is January 31, 1991.

(2) The deadline for submitting protocols for octabromodiphenyloxide (CAS No. 32536-52-0) and allyl ether of

**Environmental Protection Agency**

**§ 766.35**

tetrabromobisphenol-A (CAS No. 25327-89-3) is January 31, 1991.

(3) The deadline for submitting protocols for pentabromodiphenyloxide (CAS No. 32534-81-9) is February 6, 1995. The deadline for submitting tetrabromobisphenol-A-bisethoxylate (CAS No. 4126-45-2) is January 31, 1991.

(4) The deadline for submitting protocols for 3,4',5-tribromosalicylanilide (CAS No. 87-10-5) is September 5, 1990.

(ii) For chemical substances produced by a specific process not manu-

factured or processed as of the effective date of this part, a person who begins manufacture and submits a notice of intent to test must submit protocols for the test as follows:

(A) Except as noted for the submitter and substance specified in the following table, protocols for testing must be submitted 12 months after manufacture or importation begins for chlorinated chemical substances.

| CAS No.  | Submitter           | Chemical   | Due date      |
|----------|---------------------|--|---------------|
| 118-75-2 | Rhone-Poulenc ..... | 2,3,5,6-tetrachloro-2,5-cyclohexaniene-1,4-dione ..... | March 4, 1994 |

(B) Protocols for testing must be submitted 24 months after manufacture begins for brominated chemical substances.

(iii) For persons who have been granted exemptions, waivers or exclusions from testing, protocols must be submitted 12 months after expiration of the exemption, waiver or exclusion for chlorinated chemical substances, and 24 months after expiration of the exemption, waiver or exclusion for brominated chemical substances.

(b) *Information that must be submitted to EPA.* (1) Persons who manufacture or import a chemical substance listed under § 766.25 must report no later than October 5, 1987 or 90 days after the person first manufactures or imports the chemical substance, whichever is later, the results of all existing test data which show that chemical substance has been tested for the presence of HDDs/HDFs.

(2) Any manufacturer or importer of a chemical substance listed in § 766.25 in possession of unpublished health and safety studies on HDDs/HDFs is re-

quired to submit copies of such studies to EPA no later than October 5, 1987 or 90 days after the person first manufactures or imports the chemical substance, whichever is later. The following provisions of part 716 of this chapter apply to submission of these studies: §§ 716.3, 716.10(a) (1) and (4); 716.20(a) (1), (2), (3), (4), (7), (8) and (10); 716.25; 716.30; 716.35(a) (1), (2), and (4) [if applicable]; 716.35 (b) and (c); 716.40 (a) and (b); 716.50; 716.55; and 716.60(a)(2).

(3) No later than October 5, 1987 or 90 days after the person first manufactures or imports the substance listed in § 766.25, any manufacturer or importer of a chemical substance listed in § 766.25 must submit records required to be held under part 717 of this chapter on any HDDs/HDFs.

(4) *Test results.* (i) Test results must be submitted to EPA not later than 270 days after EPA's transmission of comments or 180 days after a final protocol is submitted to EPA, whichever is shorter, except as noted for the submitters and substances specified in the following table:

| CAS No.   | Submitter          | Chemical   | Due Date                        | Effective Date     |
|-----------|--------------------|--|---------------------------------|--------------------|
| 79-94-7   | Great Lakes        | Tetrabromobisphenol-A                            | May 26, 1992                    | May 28, 1993       |
| 79-94-7   | Ethyl              | Tetrabromobisphenol-A                            | August 10, 1992                 | May 28, 1993       |
| 79-94-7   | Ameribrom          | Tetrabromobisphenol-A                            | April 15, 1994                  | September 29, 1995 |
| 87-10-5   | Pfister            | 3,4',5-tribromosalicylanilide                    | 45 days after protocol approval | May 28, 1993       |
| 118-75-2  | Rhone-Poulenc Inc. | 2,3,5,6-tetrachloro-2,5-cyclohexadiene-1,4-dione | July 5, 1996                    | June 30, 1997      |
| 118-79-6  | Great Lakes        | 2,4,6-Tribromophenol                             | May 26, 1992                    | May 28, 1993       |
| 1163-19-5 | Ameribrom          | Decabromodiphenyloxide                           | April 15, 1994                  | September 29, 1995 |
| 1163-19-5 | Ethyl              | Decabromodiphenyloxide                           | May 26, 1992                    | May 28, 1993       |

| CAS No.    | Submitter           | Chemical                             | Due Date         | Effective Date     |
|------------|---------------------|--------------------------------------|------------------|--------------------|
| 1163-19-5  | Great Lakes         | Decabromodiphenyloxiide              | May 26, 1992     | May 28, 1993       |
| 4162-45-2  | Great Lakes         | Tetrabromobisphenol-A-bisethoxyate   | June 2, 1993     | September 8, 1994  |
| 25327-89-3 | Great Lakes         | Allyl Ether of Tetrabromobisphenol-A | August 10, 1992  | May 28, 1993       |
| 32534-81-9 | Great Lakes         | Pentabromodiphenyloxiide             | March 22, 1993   | September 8, 1994  |
| 32534-81-9 | Akzo Chemicals Inc. | Pentabromodiphenyloxiide             | February 6, 1995 | September 29, 1995 |
| 32534-81-9 | Ameribrom           | Pentabromodiphenyloxiide             | March 22, 1993   | September 8, 1994  |
| 32536-52-0 | Ameribrom           | Octabromodiphenyloxiide              | January 8, 1993  | September 29, 1995 |
| 32536-52-0 | Ethyl               | Octabromodiphenyloxiide              | May 15, 1994     | May 28, 1993       |
| 32536-52-0 | Great Lakes         | Octabromodiphenyloxiide              | May 26, 1992     | May 28, 1993       |
| 37853-59-1 | Great Lakes         | 1,2-bis(tribromophenoxy)ethane       | January 24, 1995 | September 29, 1995 |

(ii) For purposes of reporting test results to EPA, and for further reporting triggered by a positive test result under § 766.35(c), a positive test result is defined at § 766.3.

(iii) Reporting of test results must follow procedures set out in part 790 of this chapter, except as modified in this part.

(c) *Information required to be submitted to EPA after submission of a positive test result.* (1) Any person who submits a positive test result for a specific chemical substance listed under § 766.25 must submit to EPA no later than 90 days after the date of submission of the positive test result the following:

(i) A completed form (EPA 7710-51) for that chemical substance. The form and instructions are available from the Environmental Assistance Division (7408), Office of Pollution Prevention and Toxics, Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460. One form must be submitted for each chemical substance for which a positive test result has been submitted.

(ii) Health and safety studies for the chemical substance for which a positive test result has been reported. The following provisions of part 716 of this chapter apply to submission of these studies: §§ 716.3; 716.10 (a) (1), (2), (3) and (4); 716.20; 716.25; 716.30; 716.35(a) (1), (2), and (4), [if applicable]; 716.35 (b) and (c); 716.40 (a) and (b); 716.50; 716.55; 716.60(a)(2).

(iii) Copies of records on the chemical substances required to be held under part 717 of this chapter.

(2) If a positive test result on a chemical substance is received from one per-

son but not from others, EPA may issue a notice in the FEDERAL REGISTER listing that chemical substance and requiring any person manufacturing, importing or processing that chemical substance who has not submitted a positive test result to submit the information required in Part II of EPA Form 7710-51. Such a notice will be published only if EPA needs additional process data to make a determination of unreasonable risk.

(d)-(e) [Reserved]

(f) *Effective date.* (1) The effective date of this final rule is July 6, 1987, except for paragraphs (a)(2)(i)(B) introductory text, (a)(2)(i)(B)(1), (a)(2)(i)(B)(2), (a)(2)(i)(B)(3), (a)(2)(i)(B)(4), the table in paragraph (a)(2)(ii)(A), and the table in paragraph (b)(4)(i) of this section.

(2) The effective date for paragraph (a)(2)(i)(B) introductory text, (a)(2)(i)(B)(1), (a)(2)(i)(B)(2), and (a)(2)(i)(B)(4), is May 21, 1991. The effective date of paragraphs (a)(2)(i)(B)(3), and the table in paragraph (a)(2)(ii)(A) is September 29, 1995. The effective date of paragraph (b)(4)(i) introductory text is May 28, 1993, and the effective date of the entries in the table in paragraph (b)(4)(i) is shown in the effective dates column of the table.

**Environmental Protection Agency**

**§ 766.38**

(3) The guidelines and other test methods cited in this rule are referenced as they exist on the effective date of the final rule.

[52 FR 21437, June 5, 1987, as amended at 56 FR 23229, May 21, 1991; 57 FR 24960, June 12, 1992; 58 FR 30991, May 28, 1993, 58 FR 34205, June 23, 1993; 59 FR 46356, Sept. 8, 1994; 60 FR 31922, June 19, 1995; 60 FR 50433, Sept. 29, 1995; 60 FR 56955, Nov. 13, 1995; 62 FR 35105, June 30, 1997]

**§ 766.38 Reporting on precursor chemical substances.**

(a) *Identification of precursor chemical substances.* Precursor chemical substances are produced under conditions that will not yield HDDs and HDFs, but their molecular structure is conducive to HDD/HDF formation under favorable reaction conditions when they are used to produce other chemicals or products. The following precursor chemical substances are identified by Chemical Abstract Service (CAS) number and name.

| CAS No.     | Chemical name                              |
|-------------|--|
| 85-22-3 ... | Pentabromoethylbenzene.                    |
| 87-61-6 ... | 1,2,3-Trichlorobenzene.                    |
| 87-84-3 ... | 1,2,3,4,5-Pentabromo-6-chloro-cyclohexane. |
| 89-61-2 ... | 1,4-Dichloro-2-nitrobenzene.               |
| 89-64-5 ... | 4-Chloro-2-nitrophenol.                    |
| 89-69-0 ... | 2,4,5-Trichloronitrobenzene.               |
| 92-04-6 ... | 2-Chloro-4-phenylphenol.                   |
| 94-74-6 ... | 4-Chloro-o-toloxo acetic acid.             |
| 94-81-5 ... | 4-(2-Methyl-4-chlorophenoxy) butyric acid. |
| 95-50-1 ... | o-Dichlorobenzene.                         |
| 95-56-7 ... | o-Bromophenol.                             |
| 95-57-8 ... | o-Chlorophenol.                            |
| 95-88-5 ... | 4-Chlororesorcinol.                        |
| 95-94-3 ... | 1,2,4,5-Tetrachlorobenzene.                |
| 97-50-7 ... | 5-Chloro-2,4-dimethoxyaniline.             |
| 99-30-9 ... | 2,6-Dichloro-4-nitroaniline.               |
| 99-54-7 ... | 1,2-Dichloro-4-nitrobenzene.               |
| 106-46-7    | p-Dichlorobenzene.                         |

| CAS No.  | Chemical name                       |
|----------|-------------------------------------|
| 108-70-3 | 1,3,5-Trichlorobenzene.             |
| 108-86-1 | Bromobenzene.                       |
| 108-90-7 | Chlorobenzene.                      |
| 117-18-0 | 1,2,4,5-Tetrachloro-3-nitrobenzene. |
| 120-82-1 | 1,2,4-Trichlorobenzene.             |
| 348-51-6 | o-Chlorofluorobenzene.              |
| 350-30-1 | 3-Chloro-4-fluoronitrobenzene.      |
| 615-67-8 | Chlorohydroquinone.                 |
| 626-39-1 | 1,3,5-Tribromobenzene.              |
| 827-94-1 | 2,6-Dibromo-4-nitroaniline.         |

(b) *Persons required to report.* All persons who manufacture or import a chemical product produced using any of the chemical substances listed in paragraph (a) of this section as feedstocks or intermediates must report no later than September 29, 1987. Small manufacturers and those manufacturers and importers who produce the precursor chemical substances in quantities of 100 kilograms or less per year only for research and development purposes are not required to report under this section.

(c) *Data to be reported.* Manufacturers and importers of chemical products made from precursor chemical substances identified in paragraph (a) of this section must report process and reaction condition data on Part II of EPA Form 7710-51 for each chemical product. A separate EPA Form 7710-51 must be submitted for each chemical product reported, and the precursor chemical substance used must be identified. All forms must be submitted to EPA no later than September 29, 1987.

[52 FR 21437, June 5, 1987, as amended at 60 FR 31922, June 19, 1995]

**PARTS 767-789 [RESERVED]**





## FINDING AIDS

---

A list of CFR titles, subtitles, chapters, subchapters and parts and an alphabetical list of agencies publishing in the CFR are included in the CFR Index and Finding Aids volume to the Code of Federal Regulations which is published separately and revised annually.

Table of CFR Titles and Chapters  
Alphabetical List of Agencies Appearing in the CFR  
List of CFR Sections Affected



## Table of CFR Titles and Chapters

(Revised as of July 1, 2010)

### Title 1—General Provisions

- I Administrative Committee of the Federal Register (Parts 1—49)
- II Office of the Federal Register (Parts 50—299)
- IV Miscellaneous Agencies (Parts 400—500)

### Title 2—Grants and Agreements

#### SUBTITLE A—OFFICE OF MANAGEMENT AND BUDGET GUIDANCE FOR GRANTS AND AGREEMENTS

- I Office of Management and Budget Governmentwide Guidance for Grants and Agreements (Parts 100—199)
- II Office of Management and Budget Circulars and Guidance (200—299)

#### SUBTITLE B—FEDERAL AGENCY REGULATIONS FOR GRANTS AND AGREEMENTS

- III Department of Health and Human Services (Parts 300—399)
- IV Department of Agriculture (Parts 400—499)
- VI Department of State (Parts 600—699)
- VIII Department of Veterans Affairs (Parts 800—899)
- IX Department of Energy (Parts 900—999)
- XI Department of Defense (Parts 1100—1199)
- XII Department of Transportation (Parts 1200—1299)
- XIII Department of Commerce (Parts 1300—1399)
- XIV Department of the Interior (Parts 1400—1499)
- XV Environmental Protection Agency (Parts 1500—1599)
- XXVIII National Aeronautics and Space Administration (Parts 1880—1899)
- XXII Corporation for National and Community Service (Parts 2200—2299)
- XXIII Social Security Administration (Parts 2300—2399)
- XXIV Housing and Urban Development (Parts 2400—2499)
- XXV National Science Foundation (Parts 2500—2599)
- XXVI National Archives and Records Administration (Parts 2600—2699)
- XXVII Small Business Administration (Parts 2700—2799)
- XXVIII Department of Justice (Parts 2800—2899)
- XXX Department of Homeland Security (Parts 3000—3099)
- XXXI Institute of Museum and Library Services (Parts 3100—3199)
- XXXII National Endowment for the Arts (Parts 3200—3299)

## **Title 2—Grants and Agreements—Continued**

| Chap.  |   |
|--------|---|
| XXXIII | National Endowment for the Humanities (Parts 3300—3399)   |
| XXXV   | Export-Import Bank of the United States (Parts 3500—3599) |
| XXXVII | Peace Corps (Parts 3700—3799)                             |

## **Title 3—The President**

|   |   |
|---|---|
| I | Executive Office of the President (Parts 100—199) |
|---|---|

## **Title 4—Accounts**

|    |  |
|----|--|
| I  | Government Accountability Office (Parts 1—99)                  |
| II | Recovery Accountability and Transparency Board (Parts 200—299) |

## **Title 5—Administrative Personnel**

|        |  |
|--------|--|
| I      | Office of Personnel Management (Parts 1—1199)  |
| II     | Merit Systems Protection Board (Parts 1200—1299)   |
| III    | Office of Management and Budget (Parts 1300—1399)  |
| V      | The International Organizations Employees Loyalty Board (Parts 1500—1599)  |
| VI     | Federal Retirement Thrift Investment Board (Parts 1600—1699)   |
| VIII   | Office of Special Counsel (Parts 1800—1899)  |
| IX     | Appalachian Regional Commission (Parts 1900—1999)  |
| XI     | Armed Forces Retirement Home (Parts 2100—2199)   |
| XIV    | Federal Labor Relations Authority, General Counsel of the Federal Labor Relations Authority and Federal Service Impasses Panel (Parts 2400—2499) |
| XV     | Office of Administration, Executive Office of the President (Parts 2500—2599)  |
| XVI    | Office of Government Ethics (Parts 2600—2699)  |
| XXI    | Department of the Treasury (Parts 3100—3199)   |
| XXII   | Federal Deposit Insurance Corporation (Parts 3200—3299)  |
| XXIII  | Department of Energy (Parts 3300—3399)   |
| XXIV   | Federal Energy Regulatory Commission (Parts 3400—3499)   |
| XXV    | Department of the Interior (Parts 3500—3599)   |
| XXVI   | Department of Defense (Parts 3600—3699)  |
| XXVIII | Department of Justice (Parts 3800—3899)  |
| XXIX   | Federal Communications Commission (Parts 3900—3999)  |
| XXX    | Farm Credit System Insurance Corporation (Parts 4000—4099)   |
| XXXI   | Farm Credit Administration (Parts 4100—4199)   |
| XXXIII | Overseas Private Investment Corporation (Parts 4300—4399)  |
| XXXV   | Office of Personnel Management (Parts 4500—4599)   |
| XL     | Interstate Commerce Commission (Parts 5000—5099)   |
| XLI    | Commodity Futures Trading Commission (Parts 5100—5199)   |
| XLII   | Department of Labor (Parts 5200—5299)  |

## **Title 5—Administrative Personnel—Continued**

| Chap.  |   |
|--------|---|
| XLIII  | National Science Foundation (Parts 5300—5399)   |
| XLV    | Department of Health and Human Services (Parts 5500—5599)   |
| XLVI   | Postal Rate Commission (Parts 5600—5699)  |
| XLVII  | Federal Trade Commission (Parts 5700—5799)  |
| XLVIII | Nuclear Regulatory Commission (Parts 5800—5899)   |
| L      | Department of Transportation (Parts 6000—6099)  |
| LII    | Export-Import Bank of the United States (Parts 6200—6299)   |
| LIII   | Department of Education (Parts 6300—6399)   |
| LIV    | Environmental Protection Agency (Parts 6400—6499)   |
| LV     | National Endowment for the Arts (Parts 6500—6599)   |
| LVI    | National Endowment for the Humanities (Parts 6600—6699)   |
| LVII   | General Services Administration (Parts 6700—6799)   |
| LVIII  | Board of Governors of the Federal Reserve System (Parts 6800—6899)  |
| LIX    | National Aeronautics and Space Administration (Parts 6900—6999)   |
| LX     | United States Postal Service (Parts 7000—7099)  |
| LXI    | National Labor Relations Board (Parts 7100—7199)  |
| LXII   | Equal Employment Opportunity Commission (Parts 7200—7299)   |
| LXIII  | Inter-American Foundation (Parts 7300—7399)   |
| LXIV   | Merit Systems Protection Board (Parts 7400—7499)  |
| LXV    | Department of Housing and Urban Development (Parts 7500—7599)   |
| LXVI   | National Archives and Records Administration (Parts 7600—7699)  |
| LXVII  | Institute of Museum and Library Services (Parts 7700—7799)  |
| LXVIII | Commission on Civil Rights (Parts 7800—7899)  |
| LXIX   | Tennessee Valley Authority (Parts 7900—7999)  |
| LXXI   | Consumer Product Safety Commission (Parts 8100—8199)  |
| LXXII  | Special Inspector General for Iraq Reconstruction (Parts 8200—8299)   |
| LXXIII | Department of Agriculture (Parts 8300—8399)   |
| LXXIV  | Federal Mine Safety and Health Review Commission (Parts 8400—8499)  |
| LXXVI  | Federal Retirement Thrift Investment Board (Parts 8600—8699)  |
| LXXVII | Office of Management and Budget (Parts 8700—8799)   |
| XCVII  | Department of Homeland Security Human Resources Management System (Department of Homeland Security—Office of Personnel Management) (Parts 9700—9799)  |
| XCIX   | Department of Defense Human Resources Management and Labor Relations Systems (Department of Defense—Office of Personnel Management) (Parts 9900—9999) |

## **Title 6—Domestic Security**

|   |   |
|---|---|
| I | Department of Homeland Security, Office of the Secretary (Parts 0—99) |
|---|---|

## Title 7—Agriculture

| Chap.  |  |
|--------|--|
|        | SUBTITLE A—OFFICE OF THE SECRETARY OF AGRICULTURE (PARTS 0—26)   |
|        | SUBTITLE B—REGULATIONS OF THE DEPARTMENT OF AGRICULTURE  |
| I      | Agricultural Marketing Service (Standards, Inspections, Marketing Practices), Department of Agriculture (Parts 27—209)                                   |
| II     | Food and Nutrition Service, Department of Agriculture (Parts 210—299)  |
| III    | Animal and Plant Health Inspection Service, Department of Agriculture (Parts 300—399)  |
| IV     | Federal Crop Insurance Corporation, Department of Agriculture (Parts 400—499)  |
| V      | Agricultural Research Service, Department of Agriculture (Parts 500—599)   |
| VI     | Natural Resources Conservation Service, Department of Agriculture (Parts 600—699)  |
| VII    | Farm Service Agency, Department of Agriculture (Parts 700—799)   |
| VIII   | Grain Inspection, Packers and Stockyards Administration (Federal Grain Inspection Service), Department of Agriculture (Parts 800—899)                    |
| IX     | Agricultural Marketing Service (Marketing Agreements and Orders; Fruits, Vegetables, Nuts), Department of Agriculture (Parts 900—999)                    |
| X      | Agricultural Marketing Service (Marketing Agreements and Orders; Milk), Department of Agriculture (Parts 1000—1199)                                      |
| XI     | Agricultural Marketing Service (Marketing Agreements and Orders; Miscellaneous Commodities), Department of Agriculture (Parts 1200—1299)                 |
| XIV    | Commodity Credit Corporation, Department of Agriculture (Parts 1400—1499)  |
| XV     | Foreign Agricultural Service, Department of Agriculture (Parts 1500—1599)  |
| XVI    | Rural Telephone Bank, Department of Agriculture (Parts 1600—1699)  |
| XVII   | Rural Utilities Service, Department of Agriculture (Parts 1700—1799)   |
| XVIII  | Rural Housing Service, Rural Business-Cooperative Service, Rural Utilities Service, and Farm Service Agency, Department of Agriculture (Parts 1800—2099) |
| XX     | Local Television Loan Guarantee Board (Parts 2200—2299)  |
| XXVI   | Office of Inspector General, Department of Agriculture (Parts 2600—2699)   |
| XXVII  | Office of Information Resources Management, Department of Agriculture (Parts 2700—2799)  |
| XXVIII | Office of Operations, Department of Agriculture (Parts 2800—2899)  |
| XXIX   | Office of Energy Policy and New Uses, Department of Agriculture (Parts 2900—2999)  |
| XXX    | Office of the Chief Financial Officer, Department of Agriculture (Parts 3000—3099)   |

## **Title 7—Agriculture—Continued**

| Chap.   |   |
|---------|---|
| XXXI    | Office of Environmental Quality, Department of Agriculture (Parts 3100—3199)  |
| XXXII   | Office of Procurement and Property Management, Department of Agriculture (Parts 3200—3299)  |
| XXXIII  | Office of Transportation, Department of Agriculture (Parts 3300—3399)   |
| XXXIV   | National Institute of Food and Agriculture (Parts 3400—3499)  |
| XXXV    | Rural Housing Service, Department of Agriculture (Parts 3500—3599)  |
| XXXVI   | National Agricultural Statistics Service, Department of Agriculture (Parts 3600—3699)   |
| XXXVII  | Economic Research Service, Department of Agriculture (Parts 3700—3799)  |
| XXXVIII | World Agricultural Outlook Board, Department of Agriculture (Parts 3800—3899)   |
| XLI     | [Reserved]  |
| XLII    | Rural Business-Cooperative Service and Rural Utilities Service, Department of Agriculture (Parts 4200—4299)                         |
| L       | Rural Business-Cooperative Service, Rural Housing Service, and Rural Utilities Service, Department of Agriculture (Parts 5000—5099) |

## **Title 8—Aliens and Nationality**

|   |  |
|---|--|
| I | Department of Homeland Security (Immigration and Naturalization) (Parts 1—499)   |
| V | Executive Office for Immigration Review, Department of Justice (Parts 1000—1399) |

## **Title 9—Animals and Animal Products**

|     |  |
|-----|--|
| I   | Animal and Plant Health Inspection Service, Department of Agriculture (Parts 1—199)  |
| II  | Grain Inspection, Packers and Stockyards Administration (Packers and Stockyards Programs), Department of Agriculture (Parts 200—299) |
| III | Food Safety and Inspection Service, Department of Agriculture (Parts 300—599)  |

## **Title 10—Energy**

|       |   |
|-------|---|
| I     | Nuclear Regulatory Commission (Parts 0—199)                                   |
| II    | Department of Energy (Parts 200—699)  |
| III   | Department of Energy (Parts 700—999)  |
| X     | Department of Energy (General Provisions) (Parts 1000—1099)                   |
| XIII  | Nuclear Waste Technical Review Board (Parts 1303—1399)                        |
| XVII  | Defense Nuclear Facilities Safety Board (Parts 1700—1799)                     |
| XVIII | Northeast Interstate Low-Level Radioactive Waste Commission (Parts 1800—1899) |



## **Title 11—Federal Elections**

Chap.

- I Federal Election Commission (Parts 1—9099)
- II Election Assistance Commission (Parts 9400—9499)

## **Title 12—Banks and Banking**

- I Comptroller of the Currency, Department of the Treasury (Parts 1—199)
- II Federal Reserve System (Parts 200—299)
- III Federal Deposit Insurance Corporation (Parts 300—399)
- IV Export-Import Bank of the United States (Parts 400—499)
- V Office of Thrift Supervision, Department of the Treasury (Parts 500—599)
- VI Farm Credit Administration (Parts 600—699)
- VII National Credit Union Administration (Parts 700—799)
- VIII Federal Financing Bank (Parts 800—899)
- IX Federal Housing Finance Board (Parts 900—999)
- XI Federal Financial Institutions Examination Council (Parts 1100—1199)
- XII Federal Housing Finance Agency (Parts 1200—1299)
- XIV Farm Credit System Insurance Corporation (Parts 1400—1499)
- XV Department of the Treasury (Parts 1500—1599)
- XVII Office of Federal Housing Enterprise Oversight, Department of Housing and Urban Development (Parts 1700—1799)
- XVIII Community Development Financial Institutions Fund, Department of the Treasury (Parts 1800—1899)

## **Title 13—Business Credit and Assistance**

- I Small Business Administration (Parts 1—199)
- III Economic Development Administration, Department of Commerce (Parts 300—399)
- IV Emergency Steel Guarantee Loan Board (Parts 400—499)
- V Emergency Oil and Gas Guaranteed Loan Board (Parts 500—599)

## **Title 14—Aeronautics and Space**

- I Federal Aviation Administration, Department of Transportation (Parts 1—199)
- II Office of the Secretary, Department of Transportation (Aviation Proceedings) (Parts 200—399)
- III Commercial Space Transportation, Federal Aviation Administration, Department of Transportation (Parts 400—499)
- V National Aeronautics and Space Administration (Parts 1200—1299)
- VI Air Transportation System Stabilization (Parts 1300—1399)

- Chap.      **Title 15—Commerce and Foreign Trade**
- SUBTITLE A—OFFICE OF THE SECRETARY OF COMMERCE (PARTS 0—29)
- SUBTITLE B—REGULATIONS RELATING TO COMMERCE AND FOREIGN TRADE
- I    Bureau of the Census, Department of Commerce (Parts 30—199)
- II   National Institute of Standards and Technology, Department of Commerce (Parts 200—299)
- III   International Trade Administration, Department of Commerce (Parts 300—399)
- IV   Foreign-Trade Zones Board, Department of Commerce (Parts 400—499)
- VII   Bureau of Industry and Security, Department of Commerce (Parts 700—799)
- VIII   Bureau of Economic Analysis, Department of Commerce (Parts 800—899)
- IX   National Oceanic and Atmospheric Administration, Department of Commerce (Parts 900—999)
- XI   Technology Administration, Department of Commerce (Parts 1100—1199)
- XIII   East-West Foreign Trade Board (Parts 1300—1399)
- XIV   Minority Business Development Agency (Parts 1400—1499)
- SUBTITLE C—REGULATIONS RELATING TO FOREIGN TRADE AGREEMENTS
- XX   Office of the United States Trade Representative (Parts 2000—2099)
- SUBTITLE D—REGULATIONS RELATING TO TELECOMMUNICATIONS AND INFORMATION
- XXIII   National Telecommunications and Information Administration, Department of Commerce (Parts 2300—2399)

**Title 16—Commercial Practices**

- I    Federal Trade Commission (Parts 0—999)
- II   Consumer Product Safety Commission (Parts 1000—1799)

**Title 17—Commodity and Securities Exchanges**

- I    Commodity Futures Trading Commission (Parts 1—199)
- II   Securities and Exchange Commission (Parts 200—399)
- IV   Department of the Treasury (Parts 400—499)

**Title 18—Conservation of Power and Water Resources**

- I    Federal Energy Regulatory Commission, Department of Energy (Parts 1—399)
- III   Delaware River Basin Commission (Parts 400—499)
- VI   Water Resources Council (Parts 700—799)

## **Title 18—Conservation of Power and Water Resources—Continued**

Chap.

- VIII Susquehanna River Basin Commission (Parts 800—899)
- XIII Tennessee Valley Authority (Parts 1300—1399)

## **Title 19—Customs Duties**

- I U.S. Customs and Border Protection, Department of Homeland Security; Department of the Treasury (Parts 0—199)
- II United States International Trade Commission (Parts 200—299)
- III International Trade Administration, Department of Commerce (Parts 300—399)
- IV U.S. Immigration and Customs Enforcement, Department of Homeland Security (Parts 400—599)

## **Title 20—Employees' Benefits**

- I Office of Workers' Compensation Programs, Department of Labor (Parts 1—199)
- II Railroad Retirement Board (Parts 200—399)
- III Social Security Administration (Parts 400—499)
- IV Employees Compensation Appeals Board, Department of Labor (Parts 500—599)
- V Employment and Training Administration, Department of Labor (Parts 600—699)
- VI Employment Standards Administration, Department of Labor (Parts 700—799)
- VII Benefits Review Board, Department of Labor (Parts 800—899)
- VIII Joint Board for the Enrollment of Actuaries (Parts 900—999)
- IX Office of the Assistant Secretary for Veterans' Employment and Training Service, Department of Labor (Parts 1000—1099)

## **Title 21—Food and Drugs**

- I Food and Drug Administration, Department of Health and Human Services (Parts 1—1299)
- II Drug Enforcement Administration, Department of Justice (Parts 1300—1399)
- III Office of National Drug Control Policy (Parts 1400—1499)

## **Title 22—Foreign Relations**

- I Department of State (Parts 1—199)
- II Agency for International Development (Parts 200—299)
- III Peace Corps (Parts 300—399)
- IV International Joint Commission, United States and Canada (Parts 400—499)
- V Broadcasting Board of Governors (Parts 500—599)
- VII Overseas Private Investment Corporation (Parts 700—799)
- IX Foreign Service Grievance Board (Parts 900—999)

## **Title 22—Foreign Relations—Continued**

Chap.

- X Inter-American Foundation (Parts 1000—1099)
- XI International Boundary and Water Commission, United States and Mexico, United States Section (Parts 1100—1199)
- XII United States International Development Cooperation Agency (Parts 1200—1299)
- XIII Millenium Challenge Corporation (Parts 1300—1399)
- XIV Foreign Service Labor Relations Board; Federal Labor Relations Authority; General Counsel of the Federal Labor Relations Authority; and the Foreign Service Impasse Disputes Panel (Parts 1400—1499)
- XV African Development Foundation (Parts 1500—1599)
- XVI Japan-United States Friendship Commission (Parts 1600—1699)
- XVII United States Institute of Peace (Parts 1700—1799)

## **Title 23—Highways**

- I Federal Highway Administration, Department of Transportation (Parts 1—999)
- II National Highway Traffic Safety Administration and Federal Highway Administration, Department of Transportation (Parts 1200—1299)
- III National Highway Traffic Safety Administration, Department of Transportation (Parts 1300—1399)

## **Title 24—Housing and Urban Development**

SUBTITLE A—OFFICE OF THE SECRETARY, DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (PARTS 0—99)

SUBTITLE B—REGULATIONS RELATING TO HOUSING AND URBAN DEVELOPMENT

- I Office of Assistant Secretary for Equal Opportunity, Department of Housing and Urban Development (Parts 100—199)
- II Office of Assistant Secretary for Housing-Federal Housing Commissioner, Department of Housing and Urban Development (Parts 200—299)
- III Government National Mortgage Association, Department of Housing and Urban Development (Parts 300—399)
- IV Office of Housing and Office of Multifamily Housing Assistance Restructuring, Department of Housing and Urban Development (Parts 400—499)
- V Office of Assistant Secretary for Community Planning and Development, Department of Housing and Urban Development (Parts 500—599)
- VI Office of Assistant Secretary for Community Planning and Development, Department of Housing and Urban Development (Parts 600—699) [Reserved]
- VII Office of the Secretary, Department of Housing and Urban Development (Housing Assistance Programs and Public and Indian Housing Programs) (Parts 700—799)

## **Title 24—Housing and Urban Development—Continued**

Chap.

- VIII Office of the Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Section 8 Housing Assistance Programs, Section 202 Direct Loan Program, Section 202 Supportive Housing for the Elderly Program and Section 811 Supportive Housing for Persons With Disabilities Program) (Parts 800—899)
- IX Office of Assistant Secretary for Public and Indian Housing, Department of Housing and Urban Development (Parts 900—1699)
- X Office of Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Interstate Land Sales Registration Program) (Parts 1700—1799)
- XII Office of Inspector General, Department of Housing and Urban Development (Parts 2000—2099)
- XX Office of Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Parts 3200—3899)
- XXIV Board of Directors of the HOPE for Homeowners Program (Parts 4000—4099)
- XXV Neighborhood Reinvestment Corporation (Parts 4100—4199)

## **Title 25—Indians**

- I Bureau of Indian Affairs, Department of the Interior (Parts 1—299)
- II Indian Arts and Crafts Board, Department of the Interior (Parts 300—399)
- III National Indian Gaming Commission, Department of the Interior (Parts 500—599)
- IV Office of Navajo and Hopi Indian Relocation (Parts 700—799)
- V Bureau of Indian Affairs, Department of the Interior, and Indian Health Service, Department of Health and Human Services (Part 900)
- VI Office of the Assistant Secretary-Indian Affairs, Department of the Interior (Parts 1000—1199)
- VII Office of the Special Trustee for American Indians, Department of the Interior (Parts 1200—1299)

## **Title 26—Internal Revenue**

- I Internal Revenue Service, Department of the Treasury (Parts 1—899)

## **Title 27—Alcohol, Tobacco Products and Firearms**

- I Alcohol and Tobacco Tax and Trade Bureau, Department of the Treasury (Parts 1—399)
- II Bureau of Alcohol, Tobacco, Firearms, and Explosives, Department of Justice (Parts 400—699)

## **Title 28—Judicial Administration**

Chap.

- I Department of Justice (Parts 0—299)
- III Federal Prison Industries, Inc., Department of Justice (Parts 300—399)
- V Bureau of Prisons, Department of Justice (Parts 500—599)
- VI Offices of Independent Counsel, Department of Justice (Parts 600—699)
- VII Office of Independent Counsel (Parts 700—799)
- VIII Court Services and Offender Supervision Agency for the District of Columbia (Parts 800—899)
- IX National Crime Prevention and Privacy Compact Council (Parts 900—999)
- XI Department of Justice and Department of State (Parts 1100—1199)

## **Title 29—Labor**

SUBTITLE A—OFFICE OF THE SECRETARY OF LABOR (PARTS 0—99)

SUBTITLE B—REGULATIONS RELATING TO LABOR

- I National Labor Relations Board (Parts 100—199)
- II Office of Labor-Management Standards, Department of Labor (Parts 200—299)
- III National Railroad Adjustment Board (Parts 300—399)
- IV Office of Labor-Management Standards, Department of Labor (Parts 400—499)
- V Wage and Hour Division, Department of Labor (Parts 500—899)
- IX Construction Industry Collective Bargaining Commission (Parts 900—999)
- X National Mediation Board (Parts 1200—1299)
- XII Federal Mediation and Conciliation Service (Parts 1400—1499)
- XIV Equal Employment Opportunity Commission (Parts 1600—1699)
- XVII Occupational Safety and Health Administration, Department of Labor (Parts 1900—1999)
- XX Occupational Safety and Health Review Commission (Parts 2200—2499)
- XXV Employee Benefits Security Administration, Department of Labor (Parts 2500—2599)
- XXVII Federal Mine Safety and Health Review Commission (Parts 2700—2799)
- XL Pension Benefit Guaranty Corporation (Parts 4000—4999)

## **Title 30—Mineral Resources**

- I Mine Safety and Health Administration, Department of Labor (Parts 1—199)
- II Minerals Management Service, Department of the Interior (Parts 200—299)
- III Board of Surface Mining and Reclamation Appeals, Department of the Interior (Parts 300—399)

## **Title 30—Mineral Resources—Continued**

Chap.

- IV Geological Survey, Department of the Interior (Parts 400—499)
- VII Office of Surface Mining Reclamation and Enforcement, Department of the Interior (Parts 700—999)

## **Title 31—Money and Finance: Treasury**

SUBTITLE A—OFFICE OF THE SECRETARY OF THE TREASURY (PARTS 0—50)

SUBTITLE B—REGULATIONS RELATING TO MONEY AND FINANCE

- I Monetary Offices, Department of the Treasury (Parts 51—199)
- II Fiscal Service, Department of the Treasury (Parts 200—399)
- IV Secret Service, Department of the Treasury (Parts 400—499)
- V Office of Foreign Assets Control, Department of the Treasury (Parts 500—599)
- VI Bureau of Engraving and Printing, Department of the Treasury (Parts 600—699)
- VII Federal Law Enforcement Training Center, Department of the Treasury (Parts 700—799)
- VIII Office of International Investment, Department of the Treasury (Parts 800—899)
- IX Federal Claims Collection Standards (Department of the Treasury—Department of Justice) (Parts 900—999)

## **Title 32—National Defense**

SUBTITLE A—DEPARTMENT OF DEFENSE

- I Office of the Secretary of Defense (Parts 1—399)
  - V Department of the Army (Parts 400—699)
  - VI Department of the Navy (Parts 700—799)
  - VII Department of the Air Force (Parts 800—1099)
- SUBTITLE B—OTHER REGULATIONS RELATING TO NATIONAL DEFENSE
- XII Defense Logistics Agency (Parts 1200—1299)
  - XVI Selective Service System (Parts 1600—1699)
  - XVII Office of the Director of National Intelligence (Parts 1700—1799)
  - XXVIII National Counterintelligence Center (Parts 1800—1899)
  - XIX Central Intelligence Agency (Parts 1900—1999)
  - XX Information Security Oversight Office, National Archives and Records Administration (Parts 2000—2099)
  - XXI National Security Council (Parts 2100—2199)
  - XXIV Office of Science and Technology Policy (Parts 2400—2499)
  - XXVII Office for Micronesia Status Negotiations (Parts 2700—2799)
  - XXVIII Office of the Vice President of the United States (Parts 2800—2899)

## **Title 33—Navigation and Navigable Waters**

- I Coast Guard, Department of Homeland Security (Parts 1—199)

## **Title 33—Navigation and Navigable Waters—Continued**

Chap.

- II Corps of Engineers, Department of the Army (Parts 200—399)
- IV Saint Lawrence Seaway Development Corporation, Department of Transportation (Parts 400—499)

## **Title 34—Education**

SUBTITLE A—OFFICE OF THE SECRETARY, DEPARTMENT OF EDUCATION (PARTS 1—99)

SUBTITLE B—REGULATIONS OF THE OFFICES OF THE DEPARTMENT OF EDUCATION

- I Office for Civil Rights, Department of Education (Parts 100—199)
  - II Office of Elementary and Secondary Education, Department of Education (Parts 200—299)
  - III Office of Special Education and Rehabilitative Services, Department of Education (Parts 300—399)
  - IV Office of Vocational and Adult Education, Department of Education (Parts 400—499)
  - V Office of Bilingual Education and Minority Languages Affairs, Department of Education (Parts 500—599)
  - VI Office of Postsecondary Education, Department of Education (Parts 600—699)
  - VII Office of Educational Research and Improvement, Department of Education [Reserved]
  - XI National Institute for Literacy (Parts 1100—1199)
- SUBTITLE C—REGULATIONS RELATING TO EDUCATION
- XII National Council on Disability (Parts 1200—1299)

## **Title 35 [Reserved]**

## **Title 36—Parks, Forests, and Public Property**

- I National Park Service, Department of the Interior (Parts 1—199)
- II Forest Service, Department of Agriculture (Parts 200—299)
- III Corps of Engineers, Department of the Army (Parts 300—399)
- IV American Battle Monuments Commission (Parts 400—499)
- V Smithsonian Institution (Parts 500—599)
- VI [Reserved]
- VII Library of Congress (Parts 700—799)
- VIII Advisory Council on Historic Preservation (Parts 800—899)
- IX Pennsylvania Avenue Development Corporation (Parts 900—999)
- X Presidio Trust (Parts 1000—1099)
- XI Architectural and Transportation Barriers Compliance Board (Parts 1100—1199)
- XII National Archives and Records Administration (Parts 1200—1299)
- XV Oklahoma City National Memorial Trust (Parts 1500—1599)
- XVI Morris K. Udall Scholarship and Excellence in National Environmental Policy Foundation (Parts 1600—1699)



## **Title 37—Patents, Trademarks, and Copyrights**

Chap.

- I United States Patent and Trademark Office, Department of Commerce (Parts 1—199)
- II Copyright Office, Library of Congress (Parts 200—299)
- III Copyright Royalty Board, Library of Congress (Parts 301—399)
- IV Assistant Secretary for Technology Policy, Department of Commerce (Parts 400—499)
- V Under Secretary for Technology, Department of Commerce (Parts 500—599)

## **Title 38—Pensions, Bonuses, and Veterans' Relief**

- I Department of Veterans Affairs (Parts 0—99)
- II Armed Forces Retirement Home

## **Title 39—Postal Service**

- I United States Postal Service (Parts 1—999)
- III Postal Regulatory Commission (Parts 3000—3099)

## **Title 40—Protection of Environment**

- I Environmental Protection Agency (Parts 1—1099)
- IV Environmental Protection Agency and Department of Justice (Parts 1400—1499)
- V Council on Environmental Quality (Parts 1500—1599)
- VI Chemical Safety and Hazard Investigation Board (Parts 1600—1699)
- VII Environmental Protection Agency and Department of Defense; Uniform National Discharge Standards for Vessels of the Armed Forces (Parts 1700—1799)

## **Title 41—Public Contracts and Property Management**

### SUBTITLE B—OTHER PROVISIONS RELATING TO PUBLIC CONTRACTS

- 50 Public Contracts, Department of Labor (Parts 50-1—50-999)
  - 51 Committee for Purchase From People Who Are Blind or Severely Disabled (Parts 51-1—51-99)
  - 60 Office of Federal Contract Compliance Programs, Equal Employment Opportunity, Department of Labor (Parts 60-1—60-999)
  - 61 Office of the Assistant Secretary for Veterans' Employment and Training Service, Department of Labor (Parts 61-1—61-999)
- Chapters 62—100 [Reserved]

### SUBTITLE C—FEDERAL PROPERTY MANAGEMENT REGULATIONS SYSTEM

- 101 Federal Property Management Regulations (Parts 101-1—101-99)
  - 102 Federal Management Regulation (Parts 102-1—102-299)
- Chapters 103—104 [Reserved]
- 105 General Services Administration (Parts 105-1—105-999)

## **Title 41—Public Contracts and Property Management—Continued**

Chap.

- 109 Department of Energy Property Management Regulations (Parts 109-1—109-99)
- 114 Department of the Interior (Parts 114-1—114-99)
- 115 Environmental Protection Agency (Parts 115-1—115-99)
- 128 Department of Justice (Parts 128-1—128-99)
- Chapters 129—200 [Reserved]
- SUBTITLE D—OTHER PROVISIONS RELATING TO PROPERTY MANAGEMENT [RESERVED]
- SUBTITLE E—FEDERAL INFORMATION RESOURCES MANAGEMENT REGULATIONS SYSTEM [RESERVED]
- SUBTITLE F—FEDERAL TRAVEL REGULATION SYSTEM
- 300 General (Parts 300-1—300-99)
- 301 Temporary Duty (TDY) Travel Allowances (Parts 301-1—301-99)
- 302 Relocation Allowances (Parts 302-1—302-99)
- 303 Payment of Expenses Connected with the Death of Certain Employees (Part 303-1—303-99)
- 304 Payment of Travel Expenses from a Non-Federal Source (Parts 304-1—304-99)

## **Title 42—Public Health**

- I Public Health Service, Department of Health and Human Services (Parts 1—199)
- IV Centers for Medicare & Medicaid Services, Department of Health and Human Services (Parts 400—499)
- V Office of Inspector General-Health Care, Department of Health and Human Services (Parts 1000—1999)

## **Title 43—Public Lands: Interior**

- SUBTITLE A—OFFICE OF THE SECRETARY OF THE INTERIOR (PARTS 1—199)
- SUBTITLE B—REGULATIONS RELATING TO PUBLIC LANDS
- I Bureau of Reclamation, Department of the Interior (Parts 200—499)
- II Bureau of Land Management, Department of the Interior (Parts 1000—9999)
- III Utah Reclamation Mitigation and Conservation Commission (Parts 10000—10010)

## **Title 44—Emergency Management and Assistance**

- I Federal Emergency Management Agency, Department of Homeland Security (Parts 0—399)
- IV Department of Commerce and Department of Transportation (Parts 400—499)

## **Title 45—Public Welfare**

Chap.

SUBTITLE A—DEPARTMENT OF HEALTH AND HUMAN SERVICES  
(PARTS 1—199)

SUBTITLE B—REGULATIONS RELATING TO PUBLIC WELFARE

- II Office of Family Assistance (Assistance Programs), Administration for Children and Families, Department of Health and Human Services (Parts 200—299)
- III Office of Child Support Enforcement (Child Support Enforcement Program), Administration for Children and Families, Department of Health and Human Services (Parts 300—399)
- IV Office of Refugee Resettlement, Administration for Children and Families, Department of Health and Human Services (Parts 400—499)
- V Foreign Claims Settlement Commission of the United States, Department of Justice (Parts 500—599)
- VI National Science Foundation (Parts 600—699)
- VII Commission on Civil Rights (Parts 700—799)
- VIII Office of Personnel Management (Parts 800—899) [Reserved]
- X Office of Community Services, Administration for Children and Families, Department of Health and Human Services (Parts 1000—1099)
- XI National Foundation on the Arts and the Humanities (Parts 1100—1199)
- XII Corporation for National and Community Service (Parts 1200—1299)
- XIII Office of Human Development Services, Department of Health and Human Services (Parts 1300—1399)
- XVI Legal Services Corporation (Parts 1600—1699)
- XVII National Commission on Libraries and Information Science (Parts 1700—1799)
- XVIII Harry S. Truman Scholarship Foundation (Parts 1800—1899)
- XXI Commission on Fine Arts (Parts 2100—2199)
- XXIII Arctic Research Commission (Part 2301)
- XXIV James Madison Memorial Fellowship Foundation (Parts 2400—2499)
- XXV Corporation for National and Community Service (Parts 2500—2599)

## **Title 46—Shipping**

- I Coast Guard, Department of Homeland Security (Parts 1—199)
- II Maritime Administration, Department of Transportation (Parts 200—399)
- III Coast Guard (Great Lakes Pilotage), Department of Homeland Security (Parts 400—499)
- IV Federal Maritime Commission (Parts 500—599)

## **Title 47—Telecommunication**

- I Federal Communications Commission (Parts 0—199)

## **Title 47—Telecommunication—Continued**

Chap.

- II Office of Science and Technology Policy and National Security Council (Parts 200—299)
- III National Telecommunications and Information Administration, Department of Commerce (Parts 300—399)
- IV National Telecommunications and Information Administration, Department of Commerce, and National Highway Traffic Safety Administration, Department of Transportation (Parts 400—499)

## **Title 48—Federal Acquisition Regulations System**

- 1 Federal Acquisition Regulation (Parts 1—99)
- 2 Defense Acquisition Regulations System, Department of Defense (Parts 200—299)
- 3 Health and Human Services (Parts 300—399)
- 4 Department of Agriculture (Parts 400—499)
- 5 General Services Administration (Parts 500—599)
- 6 Department of State (Parts 600—699)
- 7 Agency for International Development (Parts 700—799)
- 8 Department of Veterans Affairs (Parts 800—899)
- 9 Department of Energy (Parts 900—999)
- 10 Department of the Treasury (Parts 1000—1099)
- 12 Department of Transportation (Parts 1200—1299)
- 13 Department of Commerce (Parts 1300—1399)
- 14 Department of the Interior (Parts 1400—1499)
- 15 Environmental Protection Agency (Parts 1500—1599)
- 16 Office of Personnel Management, Federal Employees Health Benefits Acquisition Regulation (Parts 1600—1699)
- 17 Office of Personnel Management (Parts 1700—1799)
- 18 National Aeronautics and Space Administration (Parts 1800—1899)
- 19 Broadcasting Board of Governors (Parts 1900—1999)
- 20 Nuclear Regulatory Commission (Parts 2000—2099)
- 21 Office of Personnel Management, Federal Employees Group Life Insurance Federal Acquisition Regulation (Parts 2100—2199)
- 23 Social Security Administration (Parts 2300—2399)
- 24 Department of Housing and Urban Development (Parts 2400—2499)
- 25 National Science Foundation (Parts 2500—2599)
- 28 Department of Justice (Parts 2800—2899)
- 29 Department of Labor (Parts 2900—2999)
- 30 Department of Homeland Security, Homeland Security Acquisition Regulation (HSAR) (Parts 3000—3099)
- 34 Department of Education Acquisition Regulation (Parts 3400—3499)
- 51 Department of the Army Acquisition Regulations (Parts 5100—5199)

## **Title 48—Federal Acquisition Regulations System—Continued**

Chap.

- 52 Department of the Navy Acquisition Regulations (Parts 5200—5299)
- 53 Department of the Air Force Federal Acquisition Regulation Supplement [Reserved]
- 54 Defense Logistics Agency, Department of Defense (Parts 5400—5499)
- 57 African Development Foundation (Parts 5700—5799)
- 61 Civilian Board of Contract Appeals, General Services Administration (Parts 6100—6199)
- 63 Department of Transportation Board of Contract Appeals (Parts 6300—6399)
- 99 Cost Accounting Standards Board, Office of Federal Procurement Policy, Office of Management and Budget (Parts 9900—9999)

## **Title 49—Transportation**

SUBTITLE A—OFFICE OF THE SECRETARY OF TRANSPORTATION  
(PARTS 1—99)

SUBTITLE B—OTHER REGULATIONS RELATING TO TRANSPORTATION

- I Pipeline and Hazardous Materials Safety Administration, Department of Transportation (Parts 100—199)
- II Federal Railroad Administration, Department of Transportation (Parts 200—299)
- III Federal Motor Carrier Safety Administration, Department of Transportation (Parts 300—399)
- IV Coast Guard, Department of Homeland Security (Parts 400—499)
- V National Highway Traffic Safety Administration, Department of Transportation (Parts 500—599)
- VI Federal Transit Administration, Department of Transportation (Parts 600—699)
- VII National Railroad Passenger Corporation (AMTRAK) (Parts 700—799)
- VIII National Transportation Safety Board (Parts 800—999)
- X Surface Transportation Board, Department of Transportation (Parts 1000—1399)
- XI Research and Innovative Technology Administration, Department of Transportation [Reserved]
- XII Transportation Security Administration, Department of Homeland Security (Parts 1500—1699)

## **Title 50—Wildlife and Fisheries**

- I United States Fish and Wildlife Service, Department of the Interior (Parts 1—199)
- II National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce (Parts 200—299)
- III International Fishing and Related Activities (Parts 300—399)

## **Title 50—Wildlife and Fisheries—Continued**

Chap.

- IV Joint Regulations (United States Fish and Wildlife Service, Department of the Interior and National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce); Endangered Species Committee Regulations (Parts 400—499)
- V Marine Mammal Commission (Parts 500—599)
- VI Fishery Conservation and Management, National Oceanic and Atmospheric Administration, Department of Commerce (Parts 600—699)

### **CFR Index and Finding Aids**

Subject/Agency Index

List of Agency Prepared Indexes

Parallel Tables of Statutory Authorities and Rules

List of CFR Titles, Chapters, Subchapters, and Parts

Alphabetical List of Agencies Appearing in the CFR



**Alphabetical List of Agencies Appearing in the CFR**  
(Revised as of July 1, 2010)

| Agency   | CFR Title, Subtitle or<br>Chapter |
|--|-----------------------------------|
| Administrative Committee of the Federal Register           | 1, I                              |
| Advanced Research Projects Agency                          | 32, I                             |
| Advisory Council on Historic Preservation                  | 36, VIII                          |
| African Development Foundation                             | 22, XV                            |
| Federal Acquisition Regulation                             | 48, 57                            |
| Agency for International Development                       | 22, II                            |
| Federal Acquisition Regulation                             | 48, 7                             |
| Agricultural Marketing Service                             | 7, I, IX, X, XI                   |
| Agricultural Research Service                              | 7, V                              |
| Agriculture Department                                     | 5, LXXXIII                        |
| Agricultural Marketing Service                             | 7, I, IX, X, XI                   |
| Agricultural Research Service                              | 7, V                              |
| Animal and Plant Health Inspection Service                 | 7, III; 9, I                      |
| Chief Financial Officer, Office of                         | 7, XXX                            |
| Commodity Credit Corporation                               | 7, XIV                            |
| Economic Research Service                                  | 7, XXXVII                         |
| Energy Policy and New Uses, Office of                      | 2, IX; 7, XXIX                    |
| Environmental Quality, Office of                           | 7, XXXI                           |
| Farm Service Agency  | 7, VII, XVIII                     |
| Federal Acquisition Regulation                             | 48, 4                             |
| Federal Crop Insurance Corporation                         | 7, IV                             |
| Food and Nutrition Service                                 | 7, II                             |
| Food Safety and Inspection Service                         | 9, III                            |
| Foreign Agricultural Service                               | 7, XV                             |
| Forest Service   | 36, II                            |
| Grain Inspection, Packers and Stockyards Administration    | 7, VIII; 9, II                    |
| Information Resources Management, Office of                | 7, XXVII                          |
| Inspector General, Office of                               | 7, XXVI                           |
| National Agricultural Library                              | 7, XLI                            |
| National Agricultural Statistics Service                   | 7, XXXVI                          |
| National Institute of Food and Agriculture.                | 7, XXXIV                          |
| Natural Resources Conservation Service                     | 7, VI                             |
| Operations, Office of                                      | 7, XXVIII                         |
| Procurement and Property Management, Office of             | 7, XXXII                          |
| Rural Business-Cooperative Service                         | 7, XVIII, XLII, L                 |
| Rural Development Administration                           | 7, XLII                           |
| Rural Housing Service                                      | 7, XVIII, XXXV, L                 |
| Rural Telephone Bank                                       | 7, XVI                            |
| Rural Utilities Service                                    | 7, XVII, XVIII, XLII, L           |
| Secretary of Agriculture, Office of                        | 7, Subtitle A                     |
| Transportation, Office of                                  | 7, XXXIII                         |
| World Agricultural Outlook Board                           | 7, XXXVIII                        |
| Air Force Department                                       | 32, VII                           |
| Federal Acquisition Regulation Supplement                  | 48, 53                            |
| Air Transportation Stabilization Board                     | 14, VI                            |
| Alcohol and Tobacco Tax and Trade Bureau                   | 27, I                             |
| Alcohol, Tobacco, Firearms, and Explosives, Bureau of      | 27, II                            |
| AMTRAK   | 49, VII                           |
| American Battle Monuments Commission                       | 36, IV                            |
| American Indians, Office of the Special Trustee            | 25, VII                           |
| Animal and Plant Health Inspection Service                 | 7, III; 9, I                      |
| Appalachian Regional Commission                            | 5, IX                             |
| Architectural and Transportation Barriers Compliance Board | 36, XI                            |



| Agency   | CFR Title, Subtitle or<br>Chapter |
|--|-----------------------------------|
| Arctic Research Commission   | 45, XXIII                         |
| Armed Forces Retirement Home   | 5, XI                             |
| Army Department  | 32, V                             |
| Engineers, Corps of  | 33, II; 36, III                   |
| Federal Acquisition Regulation   | 48, 51                            |
| Benefits Review Board  | 20, VII                           |
| Bilingual Education and Minority Languages Affairs, Office of                  | 34, V                             |
| Blind or Severely Disabled, Committee for Purchase From<br>People Who Are      | 41, 51                            |
| Broadcasting Board of Governors  | 22, V                             |
| Federal Acquisition Regulation   | 48, 19                            |
| Census Bureau  | 15, I                             |
| Centers for Medicare & Medicaid Services                                       | 42, IV                            |
| Central Intelligence Agency  | 32, XIX                           |
| Chief Financial Officer, Office of   | 7, XXX                            |
| Child Support Enforcement, Office of   | 45, III                           |
| Children and Families, Administration for                                      | 45, II, III, IV, X                |
| Civil Rights, Commission on  | 5, LXVIII; 45, VII                |
| Civil Rights, Office for   | 34, I                             |
| Coast Guard  | 33, I; 46, I; 49, IV              |
| Coast Guard (Great Lakes Pilotage)   | 46, III                           |
| Commerce Department  | 44, IV                            |
| Census Bureau  | 15, I                             |
| Economic Affairs, Under Secretary  | 37, V                             |
| Economic Analysis, Bureau of   | 15, VIII                          |
| Economic Development Administration  | 13, III                           |
| Emergency Management and Assistance  | 44, IV                            |
| Federal Acquisition Regulation   | 48, 13                            |
| Fishery Conservation and Management  | 50, VI                            |
| Foreign-Trade Zones Board  | 15, IV                            |
| Industry and Security, Bureau of   | 15, VII                           |
| International Trade Administration   | 15, III; 19, III                  |
| National Institute of Standards and Technology                                 | 15, II                            |
| National Marine Fisheries Service  | 50, II, IV, VI                    |
| National Oceanic and Atmospheric Administration                                | 15, IX; 50, II, III, IV, VI       |
| National Telecommunications and Information<br>Administration                  | 15, XXIII; 47, III, IV            |
| National Weather Service   | 15, IX                            |
| Patent and Trademark Office, United States                                     | 37, I                             |
| Productivity, Technology and Innovation, Assistant<br>Secretary for            | 37, IV                            |
| Secretary of Commerce, Office of   | 15, Subtitle A                    |
| Technology, Under Secretary for  | 37, V                             |
| Technology Administration  | 15, XI                            |
| Technology Policy, Assistant Secretary for                                     | 37, IV                            |
| Commercial Space Transportation  | 14, III                           |
| Commodity Credit Corporation   | 7, XIV                            |
| Commodity Futures Trading Commission   | 5, XLI; 17, I                     |
| Community Planning and Development, Office of Assistant<br>Secretary for       | 24, V, VI                         |
| Community Services, Office of  | 45, X                             |
| Comptroller of the Currency  | 12, I                             |
| Construction Industry Collective Bargaining Commission                         | 29, IX                            |
| Consumer Product Safety Commission   | 5, LXXI; 16, II                   |
| Copyright Office   | 37, II                            |
| Copyright Royalty Board  | 37, III                           |
| Corporation for National and Community Service                                 | 2, XXII; 45, XII, XXV             |
| Cost Accounting Standards Board  | 48, 99                            |
| Council on Environmental Quality   | 40, V                             |
| Court Services and Offender Supervision Agency for the<br>District of Columbia | 28, VIII                          |
| Customs and Border Protection Bureau   | 19, I                             |
| Defense Contract Audit Agency  | 32, I                             |
| Defense Department   | 5, XXVI; 32, Subtitle A;          |
|  | 40, VII                           |
| Advanced Research Projects Agency  | 32, I                             |
| Air Force Department   | 32, VII                           |

| Agency  | CFR Title, Subtitle or<br>Chapter |
|---|-----------------------------------|
| Army Department   | 32, V; 33, II; 36, III, 48,<br>51 |
| Defense Acquisition Regulations System  | 48, 2                             |
| Defense Intelligence Agency   | 32, I                             |
| Defense Logistics Agency  | 32, I, XII; 48, 54                |
| Engineers, Corps of   | 33, II; 36, III                   |
| Human Resources Management and Labor Relations<br>Systems                       | 5, XCIX                           |
| National Imagery and Mapping Agency   | 32, I                             |
| Navy Department   | 32, VI; 48, 52                    |
| Secretary of Defense, Office of   | 2, XI; 32, I                      |
| Defense Contract Audit Agency   | 32, I                             |
| Defense Intelligence Agency   | 32, I                             |
| Defense Logistics Agency  | 32, XII; 48, 54                   |
| Defense Nuclear Facilities Safety Board   | 10, XVII                          |
| Delaware River Basin Commission   | 18, III                           |
| District of Columbia, Court Services and Offender Supervision<br>Agency for the | 28, VIII                          |
| Drug Enforcement Administration   | 21, II                            |
| East-West Foreign Trade Board   | 15, XIII                          |
| Economic Affairs, Under Secretary   | 37, V                             |
| Economic Analysis, Bureau of  | 15, VIII                          |
| Economic Development Administration   | 13, III                           |
| Economic Research Service   | 7, XXXVII                         |
| Education, Department of  | 5, LIII                           |
| Bilingual Education and Minority Languages Affairs, Office<br>of                | 34, V                             |
| Civil Rights, Office for  | 34, I                             |
| Educational Research and Improvement, Office of                                 | 34, VII                           |
| Elementary and Secondary Education, Office of                                   | 34, II                            |
| Federal Acquisition Regulation  | 48, 34                            |
| Postsecondary Education, Office of  | 34, VI                            |
| Secretary of Education, Office of   | 34, Subtitle A                    |
| Special Education and Rehabilitative Services, Office of                        | 34, III                           |
| Vocational and Adult Education, Office of                                       | 34, IV                            |
| Educational Research and Improvement, Office of                                 | 34, VII                           |
| Election Assistance Commission  | 11, II                            |
| Elementary and Secondary Education, Office of                                   | 34, II                            |
| Emergency Oil and Gas Guaranteed Loan Board                                     | 13, V                             |
| Emergency Steel Guarantee Loan Board  | 13, IV                            |
| Employee Benefits Security Administration                                       | 29, XXV                           |
| Employees' Compensation Appeals Board   | 20, IV                            |
| Employees Loyalty Board   | 5, V                              |
| Employment and Training Administration  | 20, V                             |
| Employment Standards Administration   | 20, VI                            |
| Endangered Species Committee  | 50, IV                            |
| Energy, Department of   | 5, XXXIII; 10, II, III, X         |
| Federal Acquisition Regulation  | 48, 9                             |
| Federal Energy Regulatory Commission  | 5, XXIV; 18, I                    |
| Property Management Regulations   | 41, 109                           |
| Energy, Office of   | 7, XXIX                           |
| Engineers, Corps of   | 33, II; 36, III                   |
| Engraving and Printing, Bureau of   | 31, VI                            |
| Environmental Protection Agency   | 2, XV; 5, LIV; 40, I, IV,<br>VII  |
| Federal Acquisition Regulation  | 48, 15                            |
| Property Management Regulations   | 41, 115                           |
| Environmental Quality, Office of  | 7, XXXI                           |
| Equal Employment Opportunity Commission   | 5, LXII; 29, XIV                  |
| Equal Opportunity, Office of Assistant Secretary for                            | 24, I                             |
| Executive Office of the President   | 3, I                              |
| Administration, Office of   | 5, XV                             |
| Environmental Quality, Council on   | 40, V                             |
| Management and Budget, Office of  | 5, III, LXXVII; 14, VI;<br>48, 99 |
| National Drug Control Policy, Office of   | 21, III                           |
| National Security Council   | 32, XXI; 47, 2                    |

| Agency   | CFR Title, Subtitle or<br>Chapter |
|--|-----------------------------------|
| Presidential Documents   | 3                                 |
| Science and Technology Policy, Office of   | 32, XXIV; 47, II                  |
| Trade Representative, Office of the United States  | 15, XX                            |
| Export-Import Bank of the United States  | 2, XXXV; 5, LII; 12, IV           |
| Family Assistance, Office of   | 45, II                            |
| Farm Credit Administration   | 5, XXXI; 12, VI                   |
| Farm Credit System Insurance Corporation   | 5, XXX; 12, XIV                   |
| Farm Service Agency  | 7, VII, XVIII                     |
| Federal Acquisition Regulation   | 48, 1                             |
| Federal Aviation Administration  | 14, I                             |
| Commercial Space Transportation  | 14, III                           |
| Federal Claims Collection Standards  | 31, IX                            |
| Federal Communications Commission  | 5, XXIX; 47, I                    |
| Federal Contract Compliance Programs, Office of  | 41, 60                            |
| Federal Crop Insurance Corporation   | 7, IV                             |
| Federal Deposit Insurance Corporation  | 5, XXII; 12, III                  |
| Federal Election Commission  | 11, I                             |
| Federal Emergency Management Agency  | 44, I                             |
| Federal Employees Group Life Insurance Federal Acquisition<br>Regulation                           | 48, 21                            |
| Federal Employees Health Benefits Acquisition Regulation   | 48, 16                            |
| Federal Energy Regulatory Commission   | 5, XXIV; 18, I                    |
| Federal Financial Institutions Examination Council   | 12, XI                            |
| Federal Financing Bank   | 12, VIII                          |
| Federal Highway Administration   | 23, I, II                         |
| Federal Home Loan Mortgage Corporation   | 1, IV                             |
| Federal Housing Enterprise Oversight Office  | 12, XVII                          |
| Federal Housing Finance Agency   | 12, XII                           |
| Federal Housing Finance Board  | 12, IX                            |
| Federal Labor Relations Authority, and General Counsel of<br>the Federal Labor Relations Authority | 5, XIV; 22, XIV                   |
| Federal Law Enforcement Training Center  | 31, VII                           |
| Federal Management Regulation  | 41, 102                           |
| Federal Maritime Commission  | 46, IV                            |
| Federal Mediation and Conciliation Service   | 29, XII                           |
| Federal Mine Safety and Health Review Commission   | 5, LXXIV; 29, XXVII               |
| Federal Motor Carrier Safety Administration  | 49, III                           |
| Federal Prison Industries, Inc.  | 28, III                           |
| Federal Procurement Policy Office  | 48, 99                            |
| Federal Property Management Regulations  | 41, 101                           |
| Federal Railroad Administration  | 49, II                            |
| Federal Register, Administrative Committee of  | 1, I                              |
| Federal Register, Office of  | 1, II                             |
| Federal Reserve System   | 12, II                            |
| Board of Governors   | 5, LVIII                          |
| Federal Retirement Thrift Investment Board   | 5, VI, LXXVI                      |
| Federal Service Impasses Panel   | 5, XIV                            |
| Federal Trade Commission   | 5, XLVII; 16, I                   |
| Federal Transit Administration   | 49, VI                            |
| Federal Travel Regulation System   | 41, Subtitle F                    |
| Fine Arts, Commission on   | 45, XXI                           |
| Fiscal Service   | 31, II                            |
| Fish and Wildlife Service, United States   | 50, I, IV                         |
| Fishery Conservation and Management  | 50, VI                            |
| Food and Drug Administration   | 21, I                             |
| Food and Nutrition Service   | 7, II                             |
| Food Safety and Inspection Service   | 9, III                            |
| Foreign Agricultural Service   | 7, XV                             |
| Foreign Assets Control, Office of  | 31, V                             |
| Foreign Claims Settlement Commission of the United States  | 45, V                             |
| Foreign Service Grievance Board  | 22, IX                            |
| Foreign Service Impasse Disputes Panel   | 22, XIV                           |
| Foreign Service Labor Relations Board  | 22, XIV                           |
| Foreign-Trade Zones Board  | 15, IV                            |
| Forest Service   | 36, II                            |
| General Services Administration  | 5, LVII; 41, 105                  |
| Contract Appeals, Board of   | 48, 61                            |

| Agency   | CFR Title, Subtitle or<br>Chapter  |
|--|------------------------------------|
| Federal Acquisition Regulation   | 48, 5                              |
| Federal Management Regulation  | 41, 102                            |
| Federal Property Management Regulations                                    | 41, 101                            |
| Federal Travel Regulation System   | 41, Subtitle F                     |
| General  | 41, 300                            |
| Payment From a Non-Federal Source for Travel Expenses                      | 41, 304                            |
| Payment of Expenses Connected With the Death of Certain<br>Employees       | 41, 303                            |
| Relocation Allowances  | 41, 302                            |
| Temporary Duty (TDY) Travel Allowances                                     | 41, 301                            |
| Geological Survey  | 30, IV                             |
| Government Accountability Office   | 4, I                               |
| Government Ethics, Office of   | 5, XVI                             |
| Government National Mortgage Association                                   | 24, III                            |
| Grain Inspection, Packers and Stockyards Administration                    | 7, VIII; 9, II                     |
| Harry S. Truman Scholarship Foundation                                     | 45, XVIII                          |
| Health and Human Services, Department of                                   | 2, III; 5, XLV; 45,<br>Subtitle A, |
| Centers for Medicare & Medicaid Services                                   | 42, IV                             |
| Child Support Enforcement, Office of                                       | 45, III                            |
| Children and Families, Administration for                                  | 45, II, III, IV, X                 |
| Community Services, Office of  | 45, X                              |
| Family Assistance, Office of   | 45, II                             |
| Federal Acquisition Regulation   | 48, 3                              |
| Food and Drug Administration   | 21, I                              |
| Human Development Services, Office of                                      | 45, XIII                           |
| Indian Health Service  | 25, V                              |
| Inspector General (Health Care), Office of                                 | 42, V                              |
| Public Health Service  | 42, I                              |
| Refugee Resettlement, Office of  | 45, IV                             |
| Homeland Security, Department of   | 2, XXX; 6, I                       |
| Coast Guard  | 33, I; 46, I; 49, IV               |
| Coast Guard (Great Lakes Pilotage)   | 46, III                            |
| Customs and Border Protection Bureau                                       | 19, I                              |
| Federal Emergency Management Agency  | 44, I                              |
| Human Resources Management and Labor Relations<br>Systems                  | 5, XCVII                           |
| Immigration and Customs Enforcement Bureau                                 | 19, IV                             |
| Immigration and Naturalization   | 8, I                               |
| Transportation Security Administration                                     | 49, XII                            |
| HOPE for Homeowners Program, Board of Directors of                         | 24, XXIV                           |
| Housing and Urban Development, Department of                               | 2, XXIV; 5, LXV; 24,<br>Subtitle B |
| Community Planning and Development, Office of Assistant<br>Secretary for   | 24, V, VI                          |
| Equal Opportunity, Office of Assistant Secretary for                       | 24, I                              |
| Federal Acquisition Regulation   | 48, 24                             |
| Federal Housing Enterprise Oversight, Office of                            | 12, XVII                           |
| Government National Mortgage Association                                   | 24, III                            |
| Housing—Federal Housing Commissioner, Office of<br>Assistant Secretary for | 24, II, VIII, X, XX                |
| Housing, Office of, and Multifamily Housing Assistance                     | 24, IV                             |
| Restructuring, Office of   |                                    |
| Inspector General, Office of   | 24, XII                            |
| Public and Indian Housing, Office of Assistant Secretary for               | 24, IX                             |
| Secretary, Office of   | 24, Subtitle A, VII                |
| Housing—Federal Housing Commissioner, Office of Assistant<br>Secretary for | 24, II, VIII, X, XX                |
| Housing, Office of, and Multifamily Housing Assistance                     | 24, IV                             |
| Restructuring, Office of   |                                    |
| Human Development Services, Office of                                      | 45, XIII                           |
| Immigration and Customs Enforcement Bureau                                 | 19, IV                             |
| Immigration and Naturalization   | 8, I                               |
| Immigration Review, Executive Office for                                   | 8, V                               |
| Independent Counsel, Office of   | 28, VII                            |
| Indian Affairs, Bureau of  | 25, I, V                           |
| Indian Affairs, Office of the Assistant Secretary                          | 25, VI                             |

| Agency  | CFR Title, Subtitle or<br>Chapter         |
|---|---|
| Indian Arts and Crafts Board  | 25, II                                    |
| Indian Health Service   | 25, V                                     |
| Industry and Security, Bureau of  | 15, VII                                   |
| Information Resources Management, Office of   | 7, XXVII                                  |
| Information Security Oversight Office, National Archives and<br>Records Administration          | 32, XX                                    |
| Inspector General   |   |
| Agriculture Department  | 7, XXVI                                   |
| Health and Human Services Department  | 42, V                                     |
| Housing and Urban Development Department  | 24, XII                                   |
| Institute of Peace, United States   | 22, XVII                                  |
| Inter-American Foundation   | 5, LXIII; 22, X                           |
| Interior Department   |   |
| American Indians, Office of the Special Trustee   | 25, VII                                   |
| Endangered Species Committee  | 50, IV                                    |
| Federal Acquisition Regulation  | 48, 14                                    |
| Federal Property Management Regulations System  | 41, 114                                   |
| Fish and Wildlife Service, United States  | 50, I, IV                                 |
| Geological Survey   | 30, IV                                    |
| Indian Affairs, Bureau of   | 25, I, V                                  |
| Indian Affairs, Office of the Assistant Secretary   | 25, VI                                    |
| Indian Arts and Crafts Board  | 25, II                                    |
| Land Management, Bureau of  | 43, II                                    |
| Minerals Management Service   | 30, II                                    |
| National Indian Gaming Commission   | 25, III                                   |
| National Park Service   | 36, I                                     |
| Reclamation, Bureau of  | 43, I                                     |
| Secretary of the Interior, Office of  | 2, XIV; 43, Subtitle A                    |
| Surface Mining and Reclamation Appeals, Board of  | 30, III                                   |
| Surface Mining Reclamation and Enforcement, Office of   | 30, VII                                   |
| Internal Revenue Service  | 26, I                                     |
| International Boundary and Water Commission, United States<br>and Mexico, United States Section | 22, XI                                    |
| International Development, United States Agency for<br>Federal Acquisition Regulation           | 22, II<br>48, 7                           |
| International Development Cooperation Agency, United<br>States                                  | 22, XII                                   |
| International Fishing and Related Activities  | 50, III                                   |
| International Joint Commission, United States and Canada  | 22, IV                                    |
| International Organizations Employees Loyalty Board   | 5, V                                      |
| International Trade Administration  | 15, III; 19, III                          |
| International Trade Commission, United States   | 19, II                                    |
| Interstate Commerce Commission  | 5, XL                                     |
| Investment Security, Office of  | 31, VIII                                  |
| James Madison Memorial Fellowship Foundation  | 45, XXIV                                  |
| Japan–United States Friendship Commission   | 22, XVI                                   |
| Joint Board for the Enrollment of Actuaries   | 20, VIII                                  |
| Justice Department  | 2, XXVII; 5, XXVIII; 28,<br>I, XI; 40, IV |
| Alcohol, Tobacco, Firearms, and Explosives, Bureau of   | 27, II                                    |
| Drug Enforcement Administration   | 21, II                                    |
| Federal Acquisition Regulation  | 48, 28                                    |
| Federal Claims Collection Standards   | 31, IX                                    |
| Federal Prison Industries, Inc.   | 28, III                                   |
| Foreign Claims Settlement Commission of the United<br>States                                    | 45, V                                     |
| Immigration Review, Executive Office for  | 8, V                                      |
| Offices of Independent Counsel  | 28, VI                                    |
| Prisons, Bureau of  | 28, V                                     |
| Property Management Regulations   | 41, 128                                   |
| Labor Department  | 5, XLII                                   |
| Benefits Review Board   | 20, VII                                   |
| Employee Benefits Security Administration   | 29, XXV                                   |
| Employees' Compensation Appeals Board   | 20, IV                                    |
| Employment and Training Administration  | 20, V                                     |
| Employment Standards Administration   | 20, VI                                    |
| Federal Acquisition Regulation  | 48, 29                                    |

| Agency  | CFR Title, Subtitle or<br>Chapter  |
|---|------------------------------------|
| Federal Contract Compliance Programs, Office of   | 41, 60                             |
| Federal Procurement Regulations System  | 41, 50                             |
| Labor-Management Standards, Office of   | 29, II, IV                         |
| Mine Safety and Health Administration   | 30, I                              |
| Occupational Safety and Health Administration   | 29, XVII                           |
| Public Contracts  | 41, 50                             |
| Secretary of Labor, Office of   | 29, Subtitle A                     |
| Veterans' Employment and Training Service, Office of the<br>Assistant Secretary for       | 41, 61; 20, IX                     |
| Wage and Hour Division  | 29, V                              |
| Workers' Compensation Programs, Office of   | 20, I                              |
| Labor-Management Standards, Office of   | 29, II, IV                         |
| Land Management, Bureau of  | 43, II                             |
| Legal Services Corporation  | 45, XVI                            |
| Library of Congress   | 36, VII                            |
| Copyright Office  | 37, II                             |
| Copyright Royalty Board   | 37, III                            |
| Local Television Loan Guarantee Board   | 7, XX                              |
| Management and Budget, Office of  | 5, III, LXXXVII; 14, VI;<br>48, 99 |
| Marine Mammal Commission  | 50, V                              |
| Maritime Administration   | 46, II                             |
| Merit Systems Protection Board  | 5, II, LXIV                        |
| Micronesian Status Negotiations, Office for   | 32, XXXVII                         |
| Millennium Challenge Corporation  | 22, XIII                           |
| Mine Safety and Health Administration   | 30, I                              |
| Minerals Management Service   | 30, II                             |
| Minority Business Development Agency  | 15, XIV                            |
| Miscellaneous Agencies  | 1, IV                              |
| Monetary Offices  | 31, I                              |
| Morris K. Udall Scholarship and Excellence in National<br>Environmental Policy Foundation | 36, XVI                            |
| Museum and Library Services, Institute of   | 2, XXXI                            |
| National Aeronautics and Space Administration   | 2, XVIII; 5, LIX; 14, V            |
| Federal Acquisition Regulation  | 48, 18                             |
| National Agricultural Library   | 7, XLI                             |
| National Agricultural Statistics Service  | 7, XXXVI                           |
| National and Community Service, Corporation for   | 45, XII, XXV                       |
| National Archives and Records Administration  | 2, XXVI; 5, LXVI; 36,<br>XII       |
| Information Security Oversight Office   | 32, XX                             |
| National Capital Planning Commission  | 1, IV                              |
| National Commission for Employment Policy   | 1, IV                              |
| National Commission on Libraries and Information Science                                  | 45, XVII                           |
| National Council on Disability  | 34, XII                            |
| National Counterintelligence Center   | 32, XVIII                          |
| National Credit Union Administration  | 12, VII                            |
| National Crime Prevention and Privacy Compact Council                                     | 28, IX                             |
| National Drug Control Policy, Office of   | 21, III                            |
| National Endowment for the Arts   | 2, XXXII                           |
| National Endowment for the Humanities   | 2, XXXIII                          |
| National Foundation on the Arts and the Humanities  | 45, XI                             |
| National Highway Traffic Safety Administration  | 23, II, III; 47, VI; 49, V         |
| National Imagery and Mapping Agency   | 32, I                              |
| National Indian Gaming Commission   | 25, III                            |
| National Institute for Literacy   | 34, XI                             |
| National Institute of Food and Agriculture.   | 7, XXXIV                           |
| National Institute of Standards and Technology  | 15, II                             |
| National Intelligence, Office of Director of  | 32, XVII                           |
| National Labor Relations Board  | 5, LXI; 29, I                      |
| National Marine Fisheries Service   | 50, II, IV, VI                     |
| National Mediation Board  | 29, X                              |
| National Oceanic and Atmospheric Administration   | 15, IX; 50, II, III, IV, VI        |
| National Park Service   | 36, I                              |
| National Railroad Adjustment Board  | 29, III                            |
| National Railroad Passenger Corporation (AMTRAK)  | 49, VII                            |
| National Science Foundation   | 2, XXV; 5, XLIII; 45, VI           |

| Agency   | CFR Title, Subtitle or<br>Chapter |
|--|-----------------------------------|
| Federal Acquisition Regulation   | 48, 25                            |
| National Security Council  | 32, XXI                           |
| National Security Council and Office of Science and<br>Technology Policy                   | 47, II                            |
| National Telecommunications and Information<br>Administration                              | 15, XXIII; 47, III, IV            |
| National Transportation Safety Board   | 49, VIII                          |
| Natural Resources Conservation Service   | 7, VI                             |
| Navajo and Hopi Indian Relocation, Office of   | 25, IV                            |
| Navy Department  | 32, VI                            |
| Federal Acquisition Regulation   | 48, 52                            |
| Neighborhood Reinvestment Corporation  | 24, XXV                           |
| Northeast Interstate Low-Level Radioactive Waste<br>Commission                             | 10, XVIII                         |
| Nuclear Regulatory Commission  | 5, XLVIII; 10, I                  |
| Federal Acquisition Regulation   | 48, 20                            |
| Occupational Safety and Health Administration  | 29, XVII                          |
| Occupational Safety and Health Review Commission   | 29, XX                            |
| Offices of Independent Counsel   | 28, VI                            |
| Oklahoma City National Memorial Trust  | 36, XV                            |
| Operations Office  | 7, XXVIII                         |
| Overseas Private Investment Corporation  | 5, XXXIII; 22, VII                |
| Patent and Trademark Office, United States   | 37, I                             |
| Payment From a Non-Federal Source for Travel Expenses                                      | 41, 304                           |
| Payment of Expenses Connected With the Death of Certain<br>Employees                       | 41, 303                           |
| Peace Corps  | 22, III                           |
| Pennsylvania Avenue Development Corporation  | 36, IX                            |
| Pension Benefit Guaranty Corporation   | 29, XL                            |
| Personnel Management, Office of  | 5, I, XXXV; 45, VIII              |
| Human Resources Management and Labor Relations<br>Systems, Department of Defense           | 5, XCIX                           |
| Human Resources Management and Labor Relations<br>Systems, Department of Homeland Security | 5, XCVII                          |
| Federal Acquisition Regulation   | 48, 17                            |
| Federal Employees Group Life Insurance Federal<br>Acquisition Regulation                   | 48, 21                            |
| Federal Employees Health Benefits Acquisition Regulation                                   | 48, 16                            |
| Pipeline and Hazardous Materials Safety Administration                                     | 49, I                             |
| Postal Regulatory Commission   | 5, XLVI; 39, III                  |
| Postal Service, United States  | 5, LX; 39, I                      |
| Postsecondary Education, Office of   | 34, VI                            |
| President's Commission on White House Fellowships  | 1, IV                             |
| Presidential Documents   | 3                                 |
| Presidio Trust   | 36, X                             |
| Prisons, Bureau of   | 28, V                             |
| Procurement and Property Management, Office of   | 7, XXXII                          |
| Productivity, Technology and Innovation, Assistant<br>Secretary                            | 37, IV                            |
| Public Contracts, Department of Labor  | 41, 50                            |
| Public and Indian Housing, Office of Assistant Secretary for                               | 24, IX                            |
| Public Health Service  | 42, I                             |
| Railroad Retirement Board  | 20, II                            |
| Reclamation, Bureau of   | 43, I                             |
| Recovery Accountability and Transparency Board   | 4, II                             |
| Refugee Resettlement, Office of  | 45, IV                            |
| Relocation Allowances  | 41, 302                           |
| Research and Innovative Technology Administration  | 49, XI                            |
| Rural Business-Cooperative Service   | 7, XVIII, XLII, L                 |
| Rural Development Administration   | 7, XLII                           |
| Rural Housing Service  | 7, XVIII, XXXV, L                 |
| Rural Telephone Bank   | 7, XVI                            |
| Rural Utilities Service  | 7, XVII, XVIII, XLII, L           |
| Saint Lawrence Seaway Development Corporation  | 33, IV                            |
| Science and Technology Policy, Office of   | 32, XXIV                          |
| Science and Technology Policy, Office of, and National<br>Security Council                 | 47, II                            |

| Agency   | CFR Title, Subtitle or Chapter |
|--|--------------------------------|
| Secret Service   | 31, IV                         |
| Securities and Exchange Commission   | 17, II                         |
| Selective Service System   | 32, XVI                        |
| Small Business Administration  | 2, XXVII; 13, I                |
| Smithsonian Institution  | 36, V                          |
| Social Security Administration   | 2, XXIII; 20, III; 48, 23      |
| Soldiers' and Airmen's Home, United States   | 5, XI                          |
| Special Counsel, Office of   | 5, VIII                        |
| Special Education and Rehabilitative Services, Office of                                     | 34, III                        |
| State Department   | 2, VI; 22, I; 28, XI           |
| Federal Acquisition Regulation   | 48, 6                          |
| Surface Mining and Reclamation Appeals, Board of   | 30, III                        |
| Surface Mining Reclamation and Enforcement, Office of  | 30, VII                        |
| Surface Transportation Board   | 49, X                          |
| Susquehanna River Basin Commission   | 18, VIII                       |
| Technology Administration  | 15, XI                         |
| Technology Policy, Assistant Secretary for   | 37, IV                         |
| Technology, Under Secretary for  | 37, V                          |
| Tennessee Valley Authority   | 5, LXIX; 18, XIII              |
| Thrift Supervision Office, Department of the Treasury  | 12, V                          |
| Trade Representative, United States, Office of   | 15, XX                         |
| Transportation, Department of  | 2, XII; 5, L                   |
| Commercial Space Transportation  | 14, III                        |
| Contract Appeals, Board of   | 48, 63                         |
| Emergency Management and Assistance  | 44, IV                         |
| Federal Acquisition Regulation   | 48, 12                         |
| Federal Aviation Administration  | 14, I                          |
| Federal Highway Administration   | 23, I, II                      |
| Federal Motor Carrier Safety Administration  | 49, III                        |
| Federal Railroad Administration  | 49, II                         |
| Federal Transit Administration   | 49, VI                         |
| Maritime Administration  | 46, II                         |
| National Highway Traffic Safety Administration   | 23, II, III; 47, IV; 49, V     |
| Pipeline and Hazardous Materials Safety Administration                                       | 49, I                          |
| Saint Lawrence Seaway Development Corporation  | 33, IV                         |
| Secretary of Transportation, Office of   | 14, II; 49, Subtitle A         |
| Surface Transportation Board   | 49, X                          |
| Transportation Statistics Bureau   | 49, XI                         |
| Transportation, Office of  | 7, XXXIII                      |
| Transportation Security Administration   | 49, XII                        |
| Transportation Statistics Bureau   | 49, XI                         |
| Travel Allowances, Temporary Duty (TDY)  | 41, 301                        |
| Treasury Department  | 5, XXI; 12, XV; 17, IV; 31, IX |
| Alcohol and Tobacco Tax and Trade Bureau   | 27, I                          |
| Community Development Financial Institutions Fund  | 12, XVIII                      |
| Comptroller of the Currency  | 12, I                          |
| Customs and Border Protection Bureau   | 19, I                          |
| Engraving and Printing, Bureau of  | 31, VI                         |
| Federal Acquisition Regulation   | 48, 10                         |
| Federal Claims Collection Standards  | 31, IX                         |
| Federal Law Enforcement Training Center  | 31, VII                        |
| Fiscal Service   | 31, II                         |
| Foreign Assets Control, Office of  | 31, V                          |
| Internal Revenue Service   | 26, I                          |
| Investment Security, Office of   | 31, VIII                       |
| Monetary Offices   | 31, I                          |
| Secret Service   | 31, IV                         |
| Secretary of the Treasury, Office of   | 31, Subtitle A                 |
| Thrift Supervision, Office of  | 12, V                          |
| Truman, Harry S. Scholarship Foundation  | 45, XVIII                      |
| United States and Canada, International Joint Commission                                     | 22, IV                         |
| United States and Mexico, International Boundary and Water Commission, United States Section | 22, XI                         |
| Utah Reclamation Mitigation and Conservation Commission                                      | 43, III                        |
| Veterans Affairs Department  | 2, VIII; 38, I                 |
| Federal Acquisition Regulation   | 48, 8                          |



| Agency  | CFR Title, Subtitle or<br>Chapter |
|---|-----------------------------------|
| Veterans' Employment and Training Service, Office of the<br>Assistant Secretary for | 41, 61; 20, IX                    |
| Vice President of the United States, Office of                                      | 32, XXVIII                        |
| Vocational and Adult Education, Office of   | 34, IV                            |
| Wage and Hour Division  | 29, V                             |
| Water Resources Council   | 18, VI                            |
| Workers' Compensation Programs, Office of   | 20, I                             |
| World Agricultural Outlook Board  | 7, XXXVIII                        |

## List of CFR Sections Affected

All changes in this volume of the Code of Federal Regulations that were made by documents published in the FEDERAL REGISTER since January 1, 2001, are enumerated in the following list. Entries indicate the nature of the changes effected. Page numbers refer to FEDERAL REGISTER pages. The user should consult the entries for chapters and parts as well as sections for revisions.

Title 40 was established at 36 FR 12213, June 29, 1971. For the period before January 1, 2001, see the “List of CFR Sections Affected, 1964–1972, 1973–1985, and 1986–2000” published in ten separate volumes.

| <b>40 CFR</b>   | <b>2001</b> | <b>66 FR</b><br>Page | <b>40 CFR—Continued</b>                                       | <b>66 FR</b><br>Page |
|---|-------------|----------------------|---|----------------------|
| Chapter I   |             |                      | Chapter I—Continued   |                      |
| 712.30 (d) table and (e) table amended.....                   |             | 38959                | 721.4461 Regulation at 65 FR 81400<br>eff. date delayed ..... | 9211                 |
| 721.303 Regulation at 65 FR 81398<br>eff. date delayed .....  |             | 9211                 | 721.4565 Regulation at 65 FR 81401<br>eff. date delayed ..... | 9211                 |
| 721.333 Regulation at 65 FR 81398<br>eff. date delayed .....  |             | 9211                 | 721.4610 Regulation at 65 FR 81401<br>eff. date delayed ..... | 9211                 |
| 721.480 Regulation at 65 FR 81398<br>eff. date delayed .....  |             | 9211                 | 721.5284 Regulation at 65 FR 81401<br>eff. date delayed ..... | 9211                 |
| 721.545 Regulation at 65 FR 81398<br>eff. date delayed .....  |             | 9211                 | 721.5378 Regulation at 65 FR 81401<br>eff. date delayed ..... | 9211                 |
| 721.632 Regulation at 65 FR 81398<br>eff. date delayed .....  |             | 9211                 | 721.5585 Regulation at 65 FR 81401<br>eff. date delayed ..... | 9211                 |
| 721.633 Regulation at 65 FR 81399<br>eff. date delayed .....  |             | 9211                 | 721.5912 Regulation at 65 FR 81402<br>eff. date delayed ..... | 9211                 |
| 721.1085 Regulation at 65 FR 81399<br>eff. date delayed ..... |             | 9211                 | 721.5914 Regulation at 65 FR 81402<br>eff. date delayed ..... | 9211                 |
| 721.2121 Regulation at 65 FR 81399<br>eff. date delayed ..... |             | 9211                 | 721.5985 Regulation at 65 FR 81402<br>eff. date delayed ..... | 9211                 |
| 721.2265 Regulation at 65 FR 81399<br>eff. date delayed ..... |             | 9211                 | 721.6180 Regulation at 65 FR 81402<br>eff. date delayed ..... | 9211                 |
| 721.3460 Removed.....   |             | 63942                | 721.6196 Regulation at 65 FR 81402<br>eff. date delayed ..... | 9211                 |
| 721.3710 Regulation at 65 FR 81399<br>eff. date delayed ..... |             | 9211                 | 721.6479 Regulation at 65 FR 81402<br>eff. date delayed ..... | 9211                 |
| 721.3810 Regulation at 65 FR 81400<br>eff. date delayed ..... |             | 9211                 | 721.6493 Regulation at 65 FR 81403<br>eff. date delayed ..... | 9211                 |
| 721.3820 Regulation at 65 FR 81400<br>eff. date delayed ..... |             | 9211                 | 721.6515 Regulation at 65 FR 81403<br>eff. date delayed ..... | 9211                 |
| 721.3821 Regulation at 65 FR 81400<br>eff. date delayed ..... |             | 9211                 | 721.6820 Removed.....   | 63942                |
| 721.3830 Regulation at 65 FR 81400<br>eff. date delayed ..... |             | 9211                 | 721.8657 Regulation at 65 FR 81403<br>eff. date delayed ..... | 9211                 |
| 721.3850 Regulation at 65 FR 81400<br>eff. date delayed ..... |             | 9211                 | 721.9484 Regulation at 65 FR 81403<br>eff. date delayed ..... | 9211                 |
| 721.4365 Regulation at 65 FR 81400<br>eff. date delayed ..... |             | 9211                 | 721.9485 Regulation at 65 FR 81403<br>eff. date delayed ..... | 9211                 |
|   |             |                      | 721.9486 Regulation at 65 FR 81404<br>eff. date delayed ..... | 9211                 |

**40 CFR (7-1-10 Edition)**

**40 CFR—Continued**

|   | 66 FR<br>Page |
|---|---------------|
| Chapter I—Continued   |               |
| 721.9487 Regulation at 65 FR 81404<br>eff. date delayed .....   | 9211          |
| 721.9514 Regulation at 65 FR 81404<br>eff. date delayed .....   | 9211          |
| 721.9535 Regulation at 65 FR 81404<br>eff. date delayed .....   | 9211          |
| 721.9670 Regulation at 65 FR 81404<br>eff. date delayed .....   | 9211          |
| 721.9671 Regulation at 65 FR 81404<br>eff. date delayed .....   | 9211          |
| 745.61—745.65 (Subpart D)<br>Added .....  | 1237          |
| 745.223 Amended.....  | 1239          |
| 745.227 (d)(4), (5), (6) introductory<br>text, (7) introductory text, (i),<br>(ii), (e)(8)(ii), (v)(A), (B) and<br>(vii) revised; (d)(8)(ii) and (h)<br>redesignated as (d)(8)(iii) and<br>(i); new (d)(8)(ii), (e)(8)(viii) and<br>(h) added ..... | 1239          |
| 745.325 (d)(2)(iii)(A) and (B) re-<br>vised; (d)(2)(iv) and (v) redesign-<br>ated as (d)(2)(v) and (vi);<br>(d)(2)(iii)(C), (D), new (iv) and<br>(e) added.....   | 1240          |
| 745.330 Removed.....  | 1748          |
| Regulation at 66 FR 1748 eff. date<br>delayed .....   | 9202          |
| 761.30 (a)(2)(v) and (h)(2)(v) re-<br>vised.....  | 17617         |
| 761.99 (c) added.....   | 17478         |
| 761.180 (g) added.....  | 17619         |
| 761.205 (a)(3) amended .....  | 34376         |

**2002**

**40 CFR**

|  | 67 FR<br>Page |
|--|---------------|
| Chapter I  |               |
| 721.1230 Added .....   | 17647         |
| 721.1240 Added .....   | 17648         |
| 721.1925 Section heading, (a)(1)<br>and (2)(iii) revised; (b)(3) re-<br>moved .....                                      | 12885         |
| 721.3628 Removed.....  | 60993         |
| 721.3780 Added .....   | 17649         |
| 721.4589 Section heading, (a)(1),<br>(2)(i) and (b)(1) revised;<br>(a)(2)(ii), (iii), (iv) and (b)(3) re-<br>moved ..... | 12882         |
| 721.5300 Removed.....  | 60993         |
| 721.6175 Section heading, (a)(1),<br>(2)(i) and (b)(1) revised;<br>(a)(2)(ii), (iii) and (b)(3)<br>added.....            | 12882         |

**40 CFR—Continued**

|   | 67 FR<br>Page |
|---|---------------|
| Chapter I—Continued   |               |
| 721.6176 Section heading, (a)(1),<br>(2)(i) and (b)(1) revised;<br>(a)(2)(ii), (iii) and (b)(3)<br>added.....         | 12882         |
| 721.8170 Removed.....   | 60993         |
| 721.8175 Added .....  | 17649         |
| 721.9480 Section heading, (a)(1),<br>(2)(i) and (b)(1) revised;<br>(a)(2)(ii) through (v) and (b)(3)<br>removed ..... | 12885         |
| 721.9582 Added .....  | 11012         |
| Revised.....  | 72863         |
| 745.227 (i) correctly added; CFR<br>correction .....  | 15489         |

**2003**

**40 CFR**

|   | 68 FR<br>Page |
|---|---------------|
| Chapter I   |               |
| 710 Heading revised .....   | 887           |
| 710.1—710.4 (Subpart A) Subpart<br>designation and heading<br>added.....                  | 887           |
| 710.1 Revised .....   | 887           |
| 710.2 Removed.....  | 888           |
| 710.3 Added.....  | 888           |
| 710.4 (a), (b)(2), (c)(1), (2), (3), (d)(2)<br>note, (5) and (8) note amend-<br>ed.....   | 889           |
| 710.23 Added .....  | 889           |
| 710.25—710.39 (Subpart B) Sub-<br>part designation and heading<br>added.....              | 889           |
| 710.39 Heading revised; (a), (c) in-<br>troductory text, (1), (3) and (d)<br>amended..... | 890           |
| 710.43—710.59 (Subpart C)<br>Added .....  | 890           |
| 712.30 (d) table and (e) table<br>amended; eff. 7-11-03.....                              | 34837         |
| 721.304 Added .....   | 70173         |
| 721.321 Added .....   | 15079         |
| 721.330 Added .....   | 70174         |
| 721.338 Added .....   | 15079         |
| 721.463 Added .....   | 15079         |
| 721.465 Added .....   | 15079         |
| 721.522 Added .....   | 15080         |
| 721.525 Added .....   | 15080         |
| 721.532 Added .....   | 15080         |
| 721.533 Added .....   | 15080         |
| 721.535 Added .....   | 70174         |
| 721.638 Added .....   | 15080         |
| 721.647 Added .....   | 70174         |
| 721.648 Added .....   | 15080         |
| 721.843 Added .....   | 15081         |
| 721.910 Added .....   | 15081         |

**List of CFR Sections Affected**

**40 CFR—Continued**

68 FR  
Page

| Chapter I—Continued |             |       |
|---------------------|-------------|-------|
| 721.983             | Added ..... | 70174 |
| 721.984             | Added ..... | 15081 |
| 721.990             | Added ..... | 15081 |
| 721.1070            | Added ..... | 70174 |
| 721.1620            | Added ..... | 70174 |
| 721.1648            | Added ..... | 70175 |
| 721.1680            | Added ..... | 70175 |
| 721.1747            | Added ..... | 70175 |
| 721.1767            | Added ..... | 15081 |
| 721.1852            | Added ..... | 15081 |
| 721.1878            | Added ..... | 15082 |
| 721.1880            | Added ..... | 15082 |
| 721.2060            | Added ..... | 70175 |
| 721.2076            | Added ..... | 70175 |
| 721.2093            | Added ..... | 15082 |
| 721.2098            | Added ..... | 70176 |
| 721.2155            | Added ..... | 15082 |
| 721.2465            | Added ..... | 15082 |
| 721.2577            | Added ..... | 15082 |
| 721.2582            | Added ..... | 15083 |
| 721.2584            | Added ..... | 15083 |
| 721.2673            | Added ..... | 15083 |
| 721.2685            | Added ..... | 70176 |
| 721.2752            | Added ..... | 70176 |
| 721.3062            | Added ..... | 70176 |
| 721.3110            | Added ..... | 70176 |
| 721.3130            | Added ..... | 70176 |
| 721.3135            | Added ..... | 70176 |
| 721.3438            | Added ..... | 70177 |
| 721.3805            | Added ..... | 15084 |
| 721.3807            | Added ..... | 15084 |
| 721.3812            | Added ..... | 15084 |
| 721.3818            | Added ..... | 15084 |
| 721.3835            | Added ..... | 70177 |
| 721.3848            | Added ..... | 15084 |
| 721.4096            | Added ..... | 70177 |
| 721.4136            | Added ..... | 15084 |
| 721.4258            | Added ..... | 70177 |
| 721.4486            | Added ..... | 15084 |
| 721.4575            | Added ..... | 15085 |
| 721.4792            | Added ..... | 15085 |
| 721.5252            | Added ..... | 70177 |
| 721.5253            | Added ..... | 70177 |
| 721.5260            | Added ..... | 15085 |
| 721.5262            | Added ..... | 15085 |
| 721.5283            | Added ..... | 15085 |
| 721.5286            | Added ..... | 15086 |
| 721.5288            | Added ..... | 70178 |
| 721.5293            | Added ..... | 70178 |
| 721.5315            | Added ..... | 70178 |
| 721.5340            | Added ..... | 70178 |
| 721.5358            | Added ..... | 70178 |
| 721.5452            | Added ..... | 15086 |
| 721.5454            | Added ..... | 15086 |
| 721.5546            | Added ..... | 70178 |
| 721.5560            | Added ..... | 70179 |

**40 CFR—Continued**

68 FR  
Page

| Chapter I—Continued |  |       |
|---------------------|--|-------|
| 721.5590            | Added .....                                | 15086 |
| 721.5713            | Added .....                                | 70179 |
| 721.5718            | Added .....                                | 70179 |
| 721.5762            | Added .....                                | 70179 |
| 721.5905            | Added .....                                | 70179 |
| 721.5908            | Added .....                                | 70180 |
| 721.5917            | Added .....                                | 70180 |
| 721.5925            | Added .....                                | 15086 |
| 721.5935            | Added .....                                | 70180 |
| 721.6005            | Added .....                                | 15086 |
| 721.6167            | Added .....                                | 70180 |
| 721.6178            | Added .....                                | 15087 |
| 721.6181            | Added .....                                | 15087 |
| 721.6183            | Added .....                                | 15087 |
| 721.6205            | Added .....                                | 15087 |
| 721.7250            | Added .....                                | 70180 |
| 721.7255            | Added .....                                | 70180 |
| 721.7270            | Added .....                                | 70181 |
| 721.7290            | Added .....                                | 70181 |
| 721.8085            | Added .....                                | 15088 |
| 721.8130            | Added .....                                | 70181 |
| 721.8140            | Added .....                                | 70181 |
| 721.8145            | Added .....                                | 70181 |
| 721.8340            | Added .....                                | 70181 |
| 721.8485            | Added .....                                | 70182 |
| 721.8658            | Added .....                                | 15088 |
| 721.8920            | Added .....                                | 15088 |
| 721.8940            | Added .....                                | 70182 |
| 721.8950            | Added .....                                | 70182 |
| 721.9078            | Added .....                                | 70182 |
| 721.9079            | Added .....                                | 70182 |
| 721.9501            | Added .....                                | 70183 |
| 721.9502            | Added .....                                | 15088 |
| 721.9504            | Added .....                                | 15088 |
| 721.9506            | Added .....                                | 70183 |
| 721.9511            | Added .....                                | 70183 |
| 721.9520            | Added .....                                | 15088 |
| 721.9538            | Added .....                                | 15088 |
| 721.9572            | Added .....                                | 70183 |
| 721.9597            | Added .....                                | 15089 |
| 721.9640            | Added .....                                | 70183 |
| 721.9674            | Added .....                                | 70183 |
| 721.9929            | Added .....                                | 70184 |
| 721.9952            | Added .....                                | 15089 |
| 721.9959            | Added .....                                | 70184 |
| 723.175             | (b)(e) revised.....                        | 890   |
| 725.1075            | Added; eff. 8-12-03.....                   | 35320 |
| 761.30              | (p)(1) introductory text re-<br>vised..... | 36929 |
| 761.80              | (j) added; eff. through 4-17-<br>04 .....  | 4941  |

**2004**

**40 CFR**

69 FR  
Page

|                                    |       |
|------------------------------------|-------|
| Title 40 Nomenclature change ..... | 18803 |
|------------------------------------|-------|

**40 CFR (7-1-10 Edition)**

**40 CFR—Continued**      69 FR  
Page

Chapter I

710.3 (d) amended .....40791

710.43 Amended..... 40791

710.46 (b)(2)(iv) table amended..... 40791

710.52 (c)(3)(ix), (4) heading and (i) heading amended; (c)(4)(i)(E) table revised.....40791

710.58 (b) heading, (c) heading and (d) amended ..... 40791

710.59 (c) introductory text revised..... 40791

712.30 (e) table amended ..... 70556

716.21 Added ..... 24522

716.120 (a) table and (d) table amended..... 24523

721.1710 Removed ..... 1926

721.4200 Removed ..... 1926

721.4240 Removed ..... 1926

721.4466 Removed ..... 1926

745.223 Amended ..... 18495

745.225 (c)(13) and (14) added; (e)(5)(vi) revised..... 18495

745.227 (e)(4) revised ..... 18496

761 Policy statement ..... 54025

**2005**

**40 CFR**      70 FR  
Page

710.43 Amended..... 75068

710.46 (b)(2)(iv) table amended..... 60221, 74700

Heading corrected.....71789

(a)(1)(i), (ii), (b)(1) table, (2)(iii)(A) and (C) amended; (b)(2)(ii)(F) revised.....75068

710.48 (a) amended..... 75069

710.52 (c)(3)(iv) and (4)(ii)(A) table revised; (c)(3)(v) removed; (c)(3)(vi) through (ix) redesignated as (c)(3)(v) through (viii); introductory text, (c)(2) introductory text, (3) introductory text, new (viii) and (4) introductory text amended ..... 75069

710.53 Revised ..... 75069

710.57 Revised ..... 75070

721.10001 Added ..... 71406

745.327 (f) added..... 59889

763.98 (a)(1), (b)(3) and (d)(3) revised..... 59889

763.80—763.99 (Subpart E) Appendix C amended..... 59889

**2006**

**40 CFR**      71 FR  
Page

704.9 Amended ..... 33641

704.25 (g) amended..... 33641

704.104 (g) amended ..... 33641

707.60 (c), (d) and (e) redesignated as (d), (e) and (f) and revised; new (c) added ..... 66244

(c)(2) introductory text correctly amended ..... 68751

707.65 (c) revised ..... 33641

(a) introductory text, (2) and (c) revised ..... 66244

707.67 (a) and (e) amended ..... 66245

707.70 (a) revised ..... 66245

710 Policy statement ..... 53335

710.46 (b)(2)(iv) table amended ..... 8470

710.52 (c)(2)(i), (4)(1)(F) and (ii)(D) amended..... 52498

710.53 Amended..... 76206

710.57 Heading revised ..... 52498

710.59 Revised ..... 52498

712.28 (c) correctly revised ..... 47126

712.30 (c) correctly amended and designated as (c)(1); (c)(2) correctly added; (e) table amended ..... 47126

(e) table correctly amended ..... 54437

(e) table amended ..... 57446

716.21 (a)(7) added..... 47135

716.30 (c) correctly revised ..... 47135

716.35 (c) correctly revised ..... 47135

716.60 (c) correctly amended; (d) correctly added ..... 47135

716.105 (c) correctly amended; (d) correctly added ..... 47135

716.120 (d) table amended ..... 47136, 57446

(d) table correctly amended..... 54437

717.17 (c) amended..... 33641

720.75 (b)(2) and (e)(1) amended ..... 33641

720.102 (d) amended ..... 33641

721.11 (b) introductory text amended..... 33641

721.30 (b) introductory text amended..... 33641

721.185 (b)(1) amended ..... 33641

721.10000 Added; eff. 8-14-06 ..... 34021

723.50 (e)(1) amended..... 33642

723.175 (i)(3) amended..... 33642

761 Policy statement ..... 16703

761.185 (f) amended..... 33642

761.187 (d) amended ..... 33642

**2007**

**40 CFR**      72 FR  
Page

712.30 (e) table amended ..... 21123

**List of CFR Sections Affected**

**40 CFR—Continued**

|  | 72 FR<br>Page |
|--|---------------|
| 716.120 (d) table amended .....  | 21123         |
| 721.9582 (a)(1) introductory text,<br>(2) and (3) revised; (a)(1) Table<br>3, (4) and (5) added..... | 57229         |
| 721.10002 Added .....  | 14697         |
| 721.10003 Added .....  | 14698         |
| 721.10004 Added .....  | 14698         |
| 721.10005 Added .....  | 14698         |
| 721.10006 Added .....  | 14698         |
| 721.10007 Added .....  | 14698         |
| 721.10008 Added .....  | 14699         |
| 721.10009 Added .....  | 14699         |
| 721.10010 Added .....  | 14699         |
| 721.10011 Added .....  | 14699         |
| 721.10012 Added .....  | 14700         |
| 721.10013 Added .....  | 14700         |
| 721.10014 Added .....  | 14700         |
| 721.10015 Added .....  | 14700         |
| 721.10016 Added .....  | 14700         |
| 721.10017 Added .....  | 14700         |
| 721.10018 Added .....  | 14701         |
| 721.10019 Added .....  | 14701         |
| 721.10020 Added .....  | 14701         |
| 721.10021 Added .....  | 14701         |
| 721.10022 Added .....  | 14701         |
| 721.10023 Added .....  | 14702         |
| 721.10024 Added .....  | 14702         |
| 721.10025 Added .....  | 14702         |
| 721.10026 Added .....  | 14702         |
| 721.10027 Added .....  | 14702         |
| 721.10028 Added .....  | 14703         |
| 721.10029 Added .....  | 14703         |
| 721.10030 Added .....  | 14703         |
| 721.10031 Added .....  | 14703         |
| 721.10032 Added .....  | 14704         |
| 721.10033 Added .....  | 14704         |
| 721.10034 Added .....  | 14704         |
| 721.10035 Added .....  | 14704         |
| 721.10036 Added .....  | 14704         |
| 721.10037 Added .....  | 14704         |
| 721.10038 Added .....  | 14705         |
| 721.10039 Added .....  | 14705         |
| 721.10040 Added .....  | 14705         |
| 721.10041 Added .....  | 14705         |
| 721.10042 Added .....  | 14705         |
| 721.10043 Added .....  | 14705         |
| 721.10043 Added .....  | 14705         |
| 721.10044 Added .....  | 14706         |
| 721.10045 Added .....  | 14706         |
| 721.10046 Added .....  | 14706         |
| 721.10047 Added .....  | 14706         |
| 721.10048 Added .....  | 14706         |
| 721.10049 Added .....  | 14706         |
| 721.10050 Added .....  | 14707         |
| 721.10051 Added .....  | 14707         |
| 721.10052 Added .....  | 14707         |
| 721.10053 Added .....  | 14707         |

**40 CFR—Continued**

|  | 72 FR<br>Page |
|--|---------------|
| 721.10054 Added .....  | 14707         |
| 721.10055 Added .....  | 14707         |
| 721.10056 Added .....  | 14708         |
| 721.10057 Added .....  | 53481         |
| Removed.....   | 64951         |
| 721.10058 Added .....  | 53482         |
| 721.10059 Added .....  | 53482         |
| 721.10060 Added .....  | 53482         |
| 721.10061 Added .....  | 53482         |
| 721.10062 Added .....  | 53482         |
| 721.10063 Added .....  | 53482         |
| 721.10064 Added .....  | 53482         |
| 721.10065 Added .....  | 53483         |
| 721.10066 Added .....  | 53483         |
| 721.10067 Added .....  | 53483         |
| 721.10068 Added .....  | 56911         |
| 721.10069 Added .....  | 53483         |
| 721.10070 Added .....  | 53483         |
| 721.10071 Added .....  | 53483         |
| 721.10072 Added .....  | 53484         |
| 721.10073 Added .....  | 53484         |
| 721.10074 Added .....  | 53484         |
| 721.10075 Added .....  | 53484         |
| 721.10076 Added .....  | 53484         |
| 721.10077 Added .....  | 53485         |
| 721.10078 Added .....  | 53485         |
| 721.10079 Added .....  | 53485         |
| 721.10080 Added .....  | 53485         |
| 721.10081 Added .....  | 53485         |
| 721.10082 Added .....  | 53486         |
| 721.10083 Added .....  | 53486         |
| 721.10084 Added .....  | 53486         |
| 721.10085 Added .....  | 53486         |
| 721.10086 Added .....  | 53486         |
| 721.10087 Added .....  | 53486         |
| 721.10088 Added .....  | 53487         |
| Removed.....   | 64951         |
| 750.11 (b) revised .....   | 75238         |
| 750.21 (b) revised .....   | 57238         |
| 750.31 (b) revised .....   | 57238         |
| 750.34 (a)(5) revised .....  | 57238         |
| 750.41 (b) revised .....   | 57238         |
| 761.19 (b) introductory text<br>amended.....   | 57239         |
| 761.60 (b)(2)(v) introductory text,<br>(e), (i)(1) and (2) amended.....  | 57239         |
| 761.61 (c)(1) amended.....   | 57239         |
| 761.62 (c)(1) amended.....   | 57239         |
| 761.65 (a)(3), (4), (d)(1), (2) intro-<br>ductory text, (iv), (vii), (4) in-<br>troductory text, (ii), (iv), (8),<br>(e)(2), (3), (4) introductory text,<br>(5), (6)(i), (ii), (iii), (iv), (8),<br>(f)(3), (g)(1)(ii), (4)(ii), (h) and (j)<br>introductory text amended..... | 57239         |

**40 CFR (7-1-10 Edition)**

**40 CFR—Continued**

|   | 72 FR<br>Page |
|---|---------------|
| 761.70 (a) introductory text, (7), (8), (9), (b) introductory text, (d) introductory text, (1) introductory text, (2)(i), (ii) introductory text, (iii), (3), (4)(i), (ii) (5) and (7) amended..... | 57240         |
| 761.79 (h)(1), (2) and (3) amended.....   | 57240         |
| 761.80 (j) added.....   | 53158         |
| 761.120 (a)(3), (b) introductory text, (2) and (c) amended.....   | 57241         |
| 761.125 (a)(1)(i), (ii) and (iii) amended.....  | 57241         |
| 761.130 (e) amended.....  | 57241         |
| 761.187 (d) amended.....  | 33642         |
| 761.205 (a)(3) and (d) amended.....   | 57241         |
| 761.243 (a) amended.....  | 57241         |
| 761.386 (e) amended.....  | 57241         |
| 761.398 (a) amended.....  | 57241         |

**2008**

**40 CFR**

|                                | 73 FR<br>Page |
|--------------------------------|---------------|
| 716.21 (a)(8) added.....       | 5115          |
| 716.120 (c) table amended..... | 5115          |
| 721.3850 Removed.....          | 21251         |
| 721.5718 Removed.....          | 21251         |
| 721.9785 Removed.....          | 21251         |
| 721.9810 Removed.....          | 21251         |
| 721.10089 Added.....           | 65758         |
| 721.10090 Added.....           | 65758         |
| 721.10091 Added.....           | 65758         |
| 721.10092 Added.....           | 65758         |
| 721.10093 Added.....           | 65759         |
| 721.10094 Added.....           | 65759         |
| 721.10095 Added.....           | 65759         |
| 721.10096 Added.....           | 65759         |
| 721.10097 Added.....           | 65759         |
| 721.10098 Added.....           | 65760         |
| 721.10099 Added.....           | 65760         |
| 721.10100 Added.....           | 65760         |
| 721.10101 Added.....           | 65760         |
| 721.10102 Added.....           | 65760         |
| 721.10103 Added.....           | 65760         |
| 721.10104 Added.....           | 65761         |
| 721.10105 Added.....           | 65761         |
| 721.10106 Added.....           | 65761         |
| 721.10107 Added.....           | 65761         |
| 721.10108 Added.....           | 65761         |
| 721.10109 Added.....           | 65761         |
| 721.10110 Added.....           | 65762         |
| 721.10111 Added.....           | 65762         |
| 721.10112 Added.....           | 65762         |
| 721.10113 Added.....           | 65762         |
| 721.10114 Added.....           | 65762         |
| 721.10115 Added.....           | 65762         |
| 721.10116 Added.....           | 65763         |

**40 CFR—Continued**

|   | 73 FR<br>Page |
|---|---------------|
| 721.10117 Added.....  | 65763         |
| 721.10118 Added.....  | 65763         |
| 721.10119 Added.....  | 65763         |
| 721.10120 Added.....  | 65763         |
| 721.10121 Added.....  | 65764         |
| 721.10122 Added.....  | 65764         |
| 721.10123 Added.....  | 65764         |
| 721.10124 Added.....  | 65764         |
| 721.10125 Added.....  | 65764         |
| 721.10126 Added.....  | 65764         |
| 721.10127 Added.....  | 65765         |
| 721.10128 Added.....  | 65765         |
| 721.10129 Added.....  | 65765         |
| 721.10130 Added.....  | 65765         |
| 721.10131 Added.....  | 65765         |
| 721.10132 Added.....  | 65765         |
| 721.10133 Added.....  | 65766         |
| 745 Policy statement.....   | 21769, 36281  |
| 745.80 Revised.....   | 21758         |
| 745.81 Revised.....   | 21758         |
| 745.82 Revised.....   | 21759         |
| 745.83 Amended.....   | 21759         |
| 745.84 Removed; new 745.84 redesignated from 745.85; (c) redesignated as (d); new (c) added; (a) introductory text, (2)(i), (b) introductory text, (2), (4) and new (d) introductory text revised.....  | 21760         |
| 745.85 Redesignated as 745.84.....  | 21760         |
| Added.....  | 21761         |
| 745.86 Revised.....   | 21763         |
| 745.87 (e) revised.....   | 21763         |
| 745.88 Revised.....   | 21764         |
| 745.89 Added.....   | 21764         |
| 745.90 Added.....   | 21765         |
| 745.91 Added.....   | 21765         |
| 745.220 (a) revised.....  | 21766         |
| 745.225 (a), (b) introductory text, (1)(ii), (c) introductory text, (8)(iv), (10), (e) introductory text and (2) revised; (b)(1)(iv)(C), (c)(6)(vi), (vii), (8)(vi), (vii), (14)(ii)(D)(6), (d)(6) and (7) added; (c)(13) and (e)(1) amended..... | 21766         |
| 745.320 (c) revised.....  | 21767         |
| 745.324 (a)(1), (b)(2)(ii), (e)(2)(i), (4), (f)(2) and (i)(8) revised; (b)(1)(iii) amended.....   | 21767         |
| 745.326 Revised.....  | 21768         |
| 745.327 (b)(1)(iv) and (2)(ii) revised.....   | 21769         |
| 745.339 Revised.....  | 21769         |

**List of CFR Sections Affected**

**2009**

**40 CFR**

|  | 74 FR<br>Page |
|--|---------------|
| 707.60 (c)(2) introductory text corrected; CFR correction .....  | 16327         |
| 721.8950 Heading correctly reinstated; CFR correction .....  | 29998         |
| 721.10057 Added .....  | 32465         |
| 721.10095 (a)(2)(ii) revised .....   | 57425         |
| 721.10134 Added; eff. 8-24-09 .....  | 29994         |
| 721.10135 Added; eff. 8-24-09 .....  | 29994         |
| 721.10136 Added; eff. 8-24-09 .....  | 29994         |
| 721.10137 Added; eff. 8-24-09 .....  | 29995         |
| 721.10138 Added; eff. 8-24-09 .....  | 29995         |
| 721.10139 Added; eff. 8-24-09 .....  | 29995         |
| 721.10140 Added; eff. 8-24-09 .....  | 29995         |
| 721.10141 Added; eff. 8-24-09 .....  | 29995         |
| 721.10142 Added; eff. 8-24-09 .....  | 29995         |
| 721.10143 Added; eff. 8-24-09 .....  | 29995         |
| 721.10144 Added; eff. 8-24-09 .....  | 29996         |
| 721.10145 Added; eff. 8-24-09 .....  | 29996         |
| 721.10146 Added; eff. 8-24-09 .....  | 29996         |
| 721.10147 Added; eff. 8-24-09 .....  | 29996         |
| 721.10148 Added; eff. 8-24-09 .....  | 29996         |
| 721.10149 Added; eff. 8-24-09 .....  | 29997         |
| 721.10150 Added; eff. 8-24-09 .....  | 29997         |
| 721.10151 Added; eff. 8-24-09 .....  | 29997         |
| 721.10152 Added; eff. 8-24-09 .....  | 29997         |
| 721.10153 Added; eff. 8-24-09 .....  | 29997         |
| 721.10154 Added; eff. 8-24-09 .....  | 29998         |
| 721.10155 Added; eff. 8-24-09 .....  | 29998         |
| Removed .....  | 42178         |
| 721.10156 Added; eff. 8-24-09 .....  | 29998         |
| Removed .....  | 42178         |
| 721.10157 Added .....  | 47886         |
| 721.10158 Added .....  | 47886         |
| 721.10159 Added .....  | 47887         |
| 721.10160 Added .....  | 47887         |
| 721.10161 Added .....  | 47887         |
| 721.10162 Added .....  | 47887         |
| 721.10163 Added .....  | 47887         |
| 721.10164 Added .....  | 47888         |
| 721.10165 Added .....  | 47888         |
| 721.10166 Added .....  | 47888         |
| 721.10167 Added .....  | 47888         |
| 721.10168 Added .....  | 47888         |
| 745.92 Added .....   | 11869         |
| 745.225 (c)(13)(i), (ii) introductory text, (A), (B), (iii), (vi) and (viii) corrected; CFR correction ..... | 21554         |
| (c)(14) introductory text, (i), (ii)(D)(6) and (iii) revised .....   | 34262         |
| 745.238 (c)(1) table revised; (d)(1)(ii) and (e)(1)(ii) amended .....  | 11870         |
| 750.11 (b)(2) revised .....  | 30232         |
| 750.31 (b)(2) revised .....  | 30232         |
| 761.60 (e) revised .....   | 30232         |
| 761.61 (c)(1) revised .....  | 30232         |

**40 CFR—Continued**

|  | 74 FR<br>Page |
|--|---------------|
| 761.62 (c)(1) revised .....  | 30232         |
| 761.65 (d)(8), (e)(4) introductory text, (6)(i), (e)(8) and (g)(1)(ii) revised .....   | 30232         |
| 761.70 (a) introductory text, (b) introductory text, (d)(1) introductory text, (2)(ii) introductory text and (5) revised ..... | 30233         |
| 761.79 (h)(1), (2) and (3) revised .....   | 30233         |
| 761.120 (a)(3), (b) introductory text, (2) and (c) revised .....   | 30234         |
| 761.130 (e) revised .....  | 30234         |
| 761.205 (a)(3) and (d) revised .....   | 30234         |
| 761.243 (a) revised .....  | 30235         |
| 761.386 (e) revised .....  | 30235         |
| 761.398 (a) revised .....  | 30235         |

**2010**

(Regulations published from January 1, 2010, through July 1, 2010)

**40 CFR**

|  | 75 FR<br>Page |
|--|---------------|
| 700—799 (Subchapter R) Clarification .....   | 8266          |
| 700 Authority citation revised .....   | 784           |
| 700.45 (e)(1), (2), (3), (4)(i), (ii), (iv), (5)(i), (ii) and (iv) revised .....   | 784           |
| 716.20 (a) introductory text table corrected; part of (a) introductory text table correctly moved to (c); CFR correction ..... | 37310         |
| 720.3 (ii) through (ll) added .....  | 784           |
| 720.40 (a)(2), (c), (d)(2) and (e) revised .....   | 784           |
| 720.65 Heading, (a) and (c)(1)(iv) revised; (c)(x) added .....   | 785           |
| 720.75 (b)(2) and (e)(1) revised; (b)(3) and (4) added .....   | 786           |
| 720.80 (b)(2)(i) revised .....   | 786           |
| 720.102 (c)(1) introductory text and (d) revised .....   | 786           |
| 721.25 (c) revised .....   | 787           |
| 721.30 (b) introductory text revised .....   | 787           |
| 721.5995 Removed; eff. 7-26-10 .....   | 29431         |
| 721.10169 Added .....  | 4993          |
| 721.10170 Added .....  | 4993          |
| 721.10171 Added .....  | 4994          |
| 721.10172 Added .....  | 4994          |
| 721.10173 Added .....  | 4994          |
| 721.10174 Added .....  | 4994          |
| 721.10175 Added .....  | 4994          |
| 721.10176 Added .....  | 4995          |
| 721.10177 Added .....  | 4995          |
| 721.10178 Added .....  | 4995          |



**40 CFR (7-1-10 Edition)**

**40 CFR—Continued**

|  | 75 FR<br>Page |
|--|---------------|
| 721.10179 Added .....                      | 4995          |
| 721.10180 Added .....                      | 4995          |
| 721.10181 Added .....                      | 4995          |
| 721.10182 Added .....                      | 4996          |
| Removed.....                               | 16671         |
| 721.10184 Added; eff. 8-23-10 .....        | 35986         |
| 721.10185 Added; eff. 8-23-10 .....        | 35986         |
| 721.10186 Added; eff. 8-23-10 .....        | 35986         |
| 721.10187 Added; eff. 8-23-10 .....        | 35986         |
| 721.10188 Added; eff. 8-23-10 .....        | 35987         |
| 721.10189 Added; eff. 8-23-10 .....        | 35987         |
| 721.10190 Added; eff. 8-23-10 .....        | 35987         |
| 721.10191 Added; eff. 8-23-10 .....        | 35988         |
| 721.10192 Added; eff. 8-23-10 .....        | 35988         |
| 721.10193 Added; eff. 8-23-10 .....        | 35988         |
| 721.10194 Added; eff. 8-23-10 .....        | 35988         |
| 721.10195 Added; eff. 8-23-10 .....        | 35988         |
| 721.10196 Added; eff. 8-23-10 .....        | 35988         |
| 721.10197 Added; eff. 8-23-10 .....        | 35988         |
| 721.10198 Added; eff. 8-23-10 .....        | 35989         |
| 721.10199 Added; eff. 8-23-10 .....        | 35989         |
| 721.10200 Added; eff. 8-23-10 .....        | 35989         |
| 723.50 (e)(1) revised .....                | 787           |
| 723.250 (b) amended; (d)(6)<br>added ..... | 4305          |
| 725.25 (c), (e)(1) and (2) revised .....   | 788           |

**40 CFR—Continued**

|   | 75 FR<br>Page |
|---|---------------|
| 725.29 (a) revised .....  | 788           |
| 725.33 (a)(10) and (11) revised.....  | 788           |
| 725.36 (a) revised .....  | 789           |
| 725.54 (b) revised; (c) and (d)<br>added.....   | 789           |
| 725.60 (a) revised .....  | 789           |
| 725.67 (a)(1) revised .....   | 789           |
| 725.190 (d) revised.....  | 790           |
| 725.975 (b) introductory text re-<br>vised.....   | 790           |
| 725.984 (b)(1) revised.....   | 790           |
| 745.81 (a)(4) revised; eff. 7-6-10 .....  | 24818         |
| 745.82 (c) removed; eff. 7-6-10 .....   | 24818         |
| 745.84 (b)(2), (c)(2) introductory<br>text and (ii) revised; eff. 7-6-<br>10.....                                   | 24818         |
| 745.86 (b)(1), (c) and (d) revised;<br>(b)(6) removed; (b)(7) redesi-<br>gnated as new (b)(6); eff. 7-6-<br>10..... | 24819         |
| 745.90 (a)(4) and (b)(8) revised; eff.<br>7-6-10.....   | 24819         |
| 745.225 (c)(2)(ii) revised; eff. 7-6-<br>10.....  | 24819         |
| 745.326 (f) added; eff. 7-6-10 .....  | 24819         |

