Part II begins on page 13571

Pages 13531–13735

MULTNOMAH LAW LIBRARY
THE NATIONAL ARCHIVES
LITERAE SCRIPTA MANET

FEDERAL REGISTER

PART I

VOLUME 28 NUMBER 242

Washington, Saturday, December 14, 1963

Contents

THE PRESIDENT

Executive Order

Establishing the Interagency Committee on Export Expansion ... 13533

EXECUTIVE AGENCIES

Agricultural Marketing Service

RULES AND REGULATIONS:
Handling limitations:
Lemons ... 13542
Navel oranges (2 documents) ... 13540, 13541
Potatoes, Irish grown in certain counties in California and Oregon; approval of expenses and rate of assessment ... 13543
Prunes, fresh, grown in designated counties in Idaho and Malhevr County, Oreg.; determination relative to changing fiscal period ... 13543
Raisins produced from grapes grown in California; miscellaneous amendments ... 13544
Shipment limitations:
Grapefruit (2 documents) ... 13538, 13541
Tangelos ... 13540
Tangerines ... 13539
Oranges ... 13539
Potatoes, Irish ... 13543

Agricultural Research Service

PROPOSED RULE MAKING:
Scabies in sheep; addition of certain counties in West Virginia to list of areas designated eradication areas ... 13549

RULES AND REGULATIONS:
Scabies in sheep; interstate movement ... 13544

Agricultural Stabilization and Conservation Service

RULES AND REGULATIONS:
Cotton county reserve, 1964:
Extra long staple ... 13538
Upland ... 13535

Agriculture Department

See Agricultural Marketing Service; Agricultural Research Service; Agricultural Stabilization and Conservation Service; Commodity Credit Corporation.

Civil Service Commission

RULES AND REGULATIONS:
Excepted service:
Agriculture Department ... 13535
Commission on Civil Rights (2 documents) ... 13535
U.S. Arms Control and Disarmament Agency ... 13535

Commerce Department

See International Commerce Bureau; Maritime Administration.

Commodity Credit Corporation

NOTICES:
Jute bagging and bale ties; proposed specifications ... 13551

Comptroller of the Currency

NOTICES:
Decisions granting applications to merge or consolidate:
Birmingham Trust National Bank and Bank for Savings and Trusts ... 13550
Lancaster County National Bank and Farmers Bank and Trust Company of Lancaster ... 13550
Virginia National Bank and Merchants Bank of Staunton ... 13550
Virginia National Bank and Tidewater Bank and Trust Co ... 13550

Customs Bureau

NOTICES:
Commissioner of Customs; order of succession ... 13550

PROPOSED RULE MAKING:
Port of Niagara Falls, N.Y.; proposed change in area ... 13548

RULES AND REGULATIONS:
Customs regulations; amended to conform to Tariff Schedules of United States ... 13546

Education Office

NOTICES:
Applications for Federal financial assistance in construction of noncommercial educational television broadcast facilities; notice of acceptance for filing ... 13553

Federal Aviation Agency

NOTICES:
Determination of no hazard to air navigation:
Bi-States Co ... 13554
WLOX Broadcasting Co., Inc ... 13554

PROPOSED RULE MAKING:
Airborne VOR receiving equipment; extension of time for filing comments ... 13549

Federal Communications Commission

RULES AND REGULATIONS:
Reorganization and revision of chapter ... 13572

Federal Home Loan Bank Board

PROPOSED RULE MAKING:
Members of banks; minimum stock subscription ... 13549

Federal Maritime Commission

NOTICES:
Alaska Steamship Co.; increased rates on tobacco products ... 13555
Castelazo and Associates et al.; agreements filed for approval ... 13555
Kesler, William Gordon, and H. C. Richards Co.; independent ocean freight forwarder applications ... 13555

(Continued on next page)

Federal Power Commission

NOTICES:

Hearings, etc.:

Area rate proceeding et al. 13557
Associated Oil & Gas Co. et al. .. 13556
Northwest Paper Co. 13558

RULES AND REGULATIONS:

General policy statement; area price levels for sales of natural gas by producers 13547

General Services Administration

See also Utilization and Disposal Service.

RULES AND REGULATIONS:

Transportation, communications, and public utilities management; utilization by executive agencies within United States and its insular possessions; correction 13547

Health, Education, and Welfare Department

See Education Office.

Indian Affairs Bureau

PROPOSED RULE MAKING:

Education and social welfare; aid and grants to Indians 13548

Interior Department

See Indian Affairs Bureau; National Park Service.

International Commerce Bureau

NOTICES:

Cremer, Josef; order temporarily denying export privileges 13551
Omnia K. G. Kraus, Weiss and Co., and Friederich Ziffer; order extending temporary denial of export privileges 13552

Interstate Commerce Commission

NOTICES:

Fourth section applications for relief 13561
Motor carrier transfer proceedings 13560

Labor Department

See Wage and Hour Division.

Maritime Administration

NOTICES:

Applications submitted:

Delta Steamship Lines, Inc. 13553
Moore-McCormack Lines, Inc. .. 13553
Waterman Steamship Corp. 13553

National Park Service

NOTICES:

Superintendents et al.; approval of plans and drawings 13550

Securities and Exchange Commission

NOTICES:

General Development Utilities, Inc., and General Development Corp.; application for order or exemption 13559

Small Business Administration

RULES AND REGULATIONS:

Joint set-asides 13545

State Department

NOTICES:

Certification of certain trademarks vested during World War II; correction 13550

Treasury Department

See Comptroller of the Currency; Customs Bureau.

Utilization and Disposal Service

NOTICES:

Delaware River-Killcohook Spoil Disposal Area; transfer of portion to Department of the Interior 13556

Wage and Hour Division

NOTICES:

Certificates authorizing employment of learners at special minimum rates 13559

Codification Guide

The following numerical guide is a list of the parts of each title of the Code of Federal Regulations affected by documents published in today's issue. A cumulative list of parts affected, covering the current month to date, appears at the end of each issue beginning with the second issue of the month.

Monthly, quarterly, and annual cumulative guides, published separately from the daily issues, include the section numbers as well as the part numbers affected.

3 CFR

EXECUTIVE ORDERS:

11132 13533

5 CFR

213 (4 documents) 13535

7 CFR

722 (2 documents) 13535, 13538
905 (4 documents) 13538–13540
907 (2 documents) 13540, 13541
909 13541
910 13542
925 13543
945 13543
947 13543
989 13544

9 CFR

74 13544

PROPOSED RULES:

74 13549

12 CFR

PROPOSED RULES:

523 13549

13 CFR

127 13545

14 CFR

PROPOSED RULES:

514 13549

18 CFR

2 13547

19 CFR

6 13546
8 13546
10 13546

PROPOSED RULES:

1 13548

25 CFR

PROPOSED RULES:

21 13548
22 13548
31 13548
32 13548

44 CFR

184 13547

47 CFR

3 13572
4 13572
73 13572
74 13572

FEDERAL REGISTER

Telephone WOrth 3-3261

Published daily, except Sundays, Mondays, and days following official Federal holidays, by the Office of the Federal Register, National Archives and Records Service, General Services Administration, pursuant to the authority contained in the Federal Register Act, approved July 26, 1935 (49 Stat. 500, as amended; 44 U.S.C., ch. 8B), under regulations prescribed by the Administrative Committee of the Federal Register, approved by the President. Distribution is made only by the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402.

The FEDERAL REGISTER will be furnished by mail to subscribers, free of postage, for $1.50 per month or $15.00 per year, payable in advance. The charge for individual copies (minimum 15 cents) varies in proportion to the size of the issue. Remit check or money order, made payable to the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402.

The regulatory material appearing herein is keyed to the CODE OF FEDERAL REGULATIONS, which is published, under 50 titles, pursuant to section 11 of the Federal Register Act, as amended August 5, 1953. The CODE OF FEDERAL REGULATIONS is sold by the Superintendent of Documents. Prices of books and pocket supplements vary.

There are no restrictions on the republication of material appearing in the FEDERAL REGISTER, or the CODE OF FEDERAL REGULATIONS.

Presidential Documents

Title 3—THE PRESIDENT

Executive Order 11132

ESTABLISHING THE INTERAGENCY COMMITTEE ON EXPORT EXPANSION

WHEREAS foreign trade is an essential and continuing element in the economic strength of the United States, and expansion of exports by and through private enterprise is of increasing importance and necessity to the economic welfare of this nation; and

WHEREAS there is a need for a continuing and systematic coordination of Government programs and policies designed to promote and expand United States exports:

NOW, THEREFORE, by virtue of the authority vested in me as President of the United States, it is ordered as follows:

SECTION 1. *Interagency Committee on Export Expansion.* (a) There is hereby established the Interagency Committee on Export Expansion (hereinafter referred to as the "Committee"), to serve in an advisory capacity to the Secretary of Commerce with respect to export expansion policies and programs, which shall consist of the following members: The Secretary of Commerce, who shall be Chairman; the Secretary of the Treasury; the Secretary of Agriculture; the Secretary of State; the Secretary of Defense; the President of the Export-Import Bank of Washington; the Administrator of the Small Business Administration; and the Administrator of the Agency for International Development. The Chairman shall from time to time invite other heads of Federal agencies to participate in Committee meetings when matters affecting their interests are to be considered by the Committee.

(b) Each member of the Committee shall designate an officer to sit on the Committee as an alternate member whenever the designating member is absent or otherwise unable to participate in a meeting of the Committee. Alternate members from executive departments shall be of rank not less than that of Assistant Secretary and other alternate members shall be of rank as nearly comparable to that of an Assistant Secretary as may be practicable.

SEC. 2. *The Secretary of Commerce.* The Secretary of Commerce shall be responsible for developing methods for improving coordination among Federal agencies in the development and carrying out of export promotion programs.

SEC. 3. *Functions of the Committee.* The Committee shall advise the Secretary of Commerce with regard to (1) means for developing and stimulating more effective export expansion programs; (2) changes in existing policies and programs of the Federal agencies which relate to improving export promotion and expansion; and (3) related areas upon which the Chairman may request advice.

SEC. 4. *Consultation.* In the performance of its functions hereunder the Committee, as may be appropriate, shall seek the advice and support of the National Export Expansion Council and shall consult and closely coordinate with the Cabinet Committee on Balance of Payments.

SEC. 5. *Administrative arrangements.* (a) As may be necessary for effectuating the purposes of this order, the Federal agencies represented on the Committee under the provisions of Section 1 hereof shall furnish assistance to the Committee in consonance with Section 214 of the Act of May 3, 1945 (59 Stat. 134; 31 U.S.C. 691). Such assistance may include the detailing of employees to the Committee to perform such functions consistent with the purposes of this order as the Committee may assign to them and may also include the assignment by the Secretary of Commerce of an official in the Department of Commerce to serve as the executive director of the Committee.

(b) With respect to functions of the Committee under this order and insofar as practicable, Federal agencies shall upon request of the Committee furnish it information, data, and reports and shall otherwise cooperate with the Committee.

SEC. 6. *Construction.* (a) Nothing in this order shall be construed to abrogate, modify, or restrict any function vested by law in, or assigned pursuant to law to, any Federal agency or any officer thereof, or any Federal interagency council or committee.

(b) As used herein the term "Federal agencies" includes executive departments and other executive agencies.

LYNDON B. JOHNSON

THE WHITE HOUSE,
December 12, 1963.

[F.R. Doc. 63-13026; Filed, Dec. 12, 1963; 3:02 p.m.]

Rules and Regulations

Title 5—ADMINISTRATIVE PERSONNEL

Chapter I—Civil Service Commission

PART 213—EXCEPTED SERVICE

Department of Agriculture

In Federal Register Document 63–12081 appearing in the issue for November 19, 1963, at page 12247, the headnote for paragraph (i) of § 213.3113 should read "International Agricultural Development Service."

(R.S. 1753, sec. 2, 22 Stat. 403, as amended; 5 U.S.C. 631, 633; B.O. 10577, 19 F.R. 7521, 3 CFR 1954–1958 Comp., p. 218)

UNITED STATES CIVIL SERVICE COMMISSION,
[SEAL] MARY V. WENZEL,
Executive Assistant to the Commissioners.

[F.R. Doc. 63–12962; Filed, Dec. 13, 1963; 8:45 a.m.]

PART 213—EXCEPTED SERVICE

Commission on Civil Rights

Effective upon publication in the FEDERAL REGISTER, paragraph (b) of § 213.3356 is amended as set out below.

§ 213.3356 **Commission on Civil Rights.**

* * * * *

(b) Director, State Advisory Committees Division.

* * * * *

(R.S. 1753, sec. 2, 22 Stat. 403, as amended; 5 U.S.C. 631, 633; E.O. 10577, 19 F.R. 7521, 3 CFR, 1954–1958 Comp., p. 218)

UNITED STATES CIVIL SERVICE COMMISSION,
[SEAL] MARY V. WENZEL,
Executive Assistant to the Commissioners.

[F.R. Doc. 63–12982; Filed, Dec. 13, 1963; 8:47 a.m.]

PART 213—EXCEPTED SERVICE

Commission on Civil Rights

Effective upon publication in the FEDERAL REGISTER, paragraph (d) is added to § 213.3356 as set out below.

§ 213.3356 **Commission on Civil Rights.**

* * * * *

(d) One Program Assistant (Special Assistant to the Staff Director).

* * * * *

(R.S. 1753, sec. 2, 22 Stat. 403, as amended; 5 U.S.C. 631, 633; E.O. 10577, 19 F.R. 7521, 3 CFR, 1954–1958 Comp., p. 218)

UNITED STATES CIVIL SERVICE COMMISSION,
[SEAL] MARY V. WENZEL,
Executive Assistant to the Commissioners.

[F.R. Doc. 63–12981; Filed, Dec. 13, 1963; 8:46 a.m.]

PART 213—EXCEPTED SERVICE

U.S. Arms Control and Disarmament Agency

Effective upon publication in the FEDERAL REGISTER, paragraph (a) of § 213.3164 is amended as set out below.

§ 213.3164 **U.S. Arms Control and Disarmament Agency.**

(a) Until April 30, 1965, 7 project officers above GS–13 in the Weapons Evaluation and Control Bureau and 10 physical science administration officers above GS–12.

* * * * *

(R.S. 1753, sec. 2, 22 Stat. 403, as amended; 5 U.S.C. 631, 633; E.O. 10577, 19 F.R. 7521; 3 CFR, 1954–1958 Comp., p. 218)

UNITED STATES CIVIL SERVICE COMMISSION,
[SEAL] MARY V. WENZEL,
Executive Assistant to the Commissioners.

[F.R. Doc. 63–13024; Filed, Dec. 13, 1963; 8:49 a.m.]

Title 7—AGRICULTURE

Chapter VII—Agricultural Stabilization and Conservation Service (Agricultural Adjustment), Department of Agriculture

PART 722—COTTON

Subpart—National Marketing Quota, National Allotment, and Apportionment to the States and Counties for the 1964 Crop of Upland Cotton

COUNTY RESERVE

(a) Section 722.246 is issued pursuant to the Agricultural Adjustment Act of 1938, as amended (52 Stat. 31, as amended, 7 U.S.C. 1281 et seq.). This section establishes the county reserve for the 1964 crop of upland cotton.

(b) Notice that the Secretary was preparing to establish State and county allotments was published in the FEDERAL REGISTER on September 14, 1963 (28 F.R. 10002) in accordance with section 4 of the Administrative Procedure Act (60 Stat. 238; 5 U.S.C. 1003). The data, views and recommendations received in response to such notice have been duly considered.

(c) Since the establishment of county reserves under this section requires immediate action by the Agricultural Stabilization and Conservation State and county committees, it is essential that § 722.246 be made effective as soon as possible. Accordingly it is hereby determined and found that compliance with the 30-day effective date requirement of section 4 of the Administrative Procedure Act is impracticable and contrary to the public interest and § 722.246 shall be effective upon filing this document with the Director, Office of the Federal Register.

§ 722.246 **County reserve.**

The county reserve is established for the 1964 crop of upland cotton in accordance with § 722.209 of the Acreage Allotment Regulations for the 1964 and Succeeding Crops of Upland Cotton (28 F.R. 11041). The following table sets forth the county reserve:

ALABAMA

County	County reserve (acres)	County	County reserve (acres)
Augusta	33.7	Jackson	32.5
Baldwin	9.7	Jefferson	45.3
Barbour	80.7	Lamar	60.6
Bibb	6.0	Lauderdale	114.1
Blount	138.4	Lawrence	40.0
Bullock	135.0	Lee	58.4
Butler	230.6	Limestone	97.2
Calhoun	419.2	Lowndes	32.6
Chambers	85.1	Macon	53.9
Cherokee	64.9	Madison	170.4
Chilton	318.1	Marengo	33.3
Choctaw	359.8	Marion	57.5
Clarke	273.5	Marshall	126.6
Clay	20.3	Mobile	15.4
Cleburne	49.9	Monroe	31.3
Coffee	240.4	Montgomery	244.2
Colbert	82.8	Morgan	45.4
Conecuh	476.3	Perry	33.0
Coosa	36.5	Pickens	68.8
Covington	45.8	Pike	297.7
Crenshaw	108.2	Randolph	139.2
Cullman	47.9	Russell	39.9
Dale	137.1	St. Clair	423.7
Dallas	32.6	Shelby	24.0
DeKalb	19.0	Sumter	336.2
Elmore	290.3	Talladega	15.1
Escambia	122.2	Tallapoosa	223.9
Etowah	30.9	Tuscaloosa	32.8
Fayette	150.9	Walker	138.8
Franklin	66.0	Washington	148.7
Geneva	152.4	Wilcox	336.8
Greene	56.6	Winston	48.4
Hale	21.1		
Henry	143.5	State total	8,202.1
Houston	151.0		

ARIZONA

Cochise	16.1	Pinal	35.0
Gila	0.0	Santa Cruz	5.2
Graham	8.4	Yavapai	0.0
Greenlee	1.2	Yuma	21.9
Maricopa	87.4		
Mohave	2.1	State total	193.2
Pima	15.9		

ARKANSAS

Arkansas	6.9	Drew	12.8
Ashley	21.3	Faulkner	31.1
Baxter	1.9	Franklin	3.2
Benton	0.0	Fulton	14.8
Boone	0.0	Garland	0.0
Bradley	104.3	Grant	14.6
Calhoun	39.4	Greene	4.8
Chicot	37.4	Hempstead	16.3
Clark	14.7	Hot Spring	20.6
Clay	21.8	Howard	3.7
Cleburne	15.6	Independence	1.4
Cleveland	6.9	Izard	4.4
Columbia	21.8	Jackson	7.5
Conway	74.5	Jefferson	13.7
Craighead	27.5	Johnson	5.4
Crawford	4.9	Lafayette	174.6
Crittenden	31.4	Lawrence	7.0
Cross	3.4	Lee	86.2
Dallas	6.2	Lincoln	23.0
Desha	33.1		

ARKANSAS—Continued

County	County reserve (acres)	County	County reserve (acres)
Little River	56.8	Pulaski	11.4
Logan	3.8	Randolph	1.9
Lonoke	101.0	St. Francis	0.3
Marion	3.2	Saline	3.0
Miller	14.4	Scott	2.0
Mississippi	23.4	Searcy	5.1
Monroe	5.3	Sebastian	1.9
Montgomery	0.0	Sevier	5.2
Nevada	3.9	Sharp	146.4
Newton	3.9	Stone	4.8
Ouachita	10.9	Union	6.6
Perry	1.6	Van Buren	10.7
Phillips	30.5	Washington	0.0
Pike	6.0	White	12.0
Poinsett	2.8	Woodruff	10.0
Polk	2.9	Yell	3.9
Pope	15.7		
Prairie	62.7	State total	1,492.1

CALIFORNIA

Fresno	196.6	San Benito	0.0
Imperial	22.7	San Bernardino	10.1
Kern	210.4	San Diego	2.1
Kings	77.0	Stanislaus	10.2
Los Angeles	2.0	Tulare	154.4
Madera	184.4		
Merced	6.6		
Riverside	16.4	State total	892.9

FLORIDA

Alachua	0.0	Leon	110.8
Baker	0.0	Levy	0.0
Bay	2.7	Liberty	0.0
Calhoun	100.8	Madison	141.6
Clay	0.0	Nassau	0.0
Columbia	40.4	Okaloosa	206.5
Dixie	0.0	Putnam	0.0
Duval	0.0	Santa Rosa	244.9
Escambia	209.2	Suwannee	91.5
Gadsden	28.1	Taylor	2.0
Gilchrist	0.0	Union	2.3
Hamilton	48.4	Walton	49.3
Holmes	237.1	Washington	123.4
Jackson	368.3		
Jefferson	45.5	State total	2,063.6
Lafayette	10.8		

GEORGIA

Appling	222.3	Crawford	25.0
Atkinson	33.8	Crisp	68.7
Bacon	49.8	Dade	18.3
Baker	35.0	Dawson	7.9
Baldwin	14.5	Decatur	150.8
Banks	326.0	DeKalb	25.1
Barrow	395.9	Dodge	107.8
Bartow	53.1	Dooly	31.8
Ben Hill	78.7	Dougherty	16.4
Berrien	20.6	Douglas	26.8
Bibb	30.1	Early	31.2
Bleckley	47.5	Echols	1.0
Brantley	3.9	Effingham	71.1
Brooks	60.9	Elbert	189.6
Bryan	13.1	Emanuel	301.9
Bulloch	318.5	Evans	24.2
Burke	3,157.5	Fannin	0.0
Butts	98.3	Fayette	76.4
Calhoun	19.6	Floyd	638.0
Camden	0.1	Forsyth	47.6
Candler	192.8	Franklin	547.5
Carroll	166.0	Fulton	64.0
Catoosa	111.9	Gilmer	0.6
Charlton	1.0	Glascock	109.4
Chatham	0.6	Glynn	0.0
Chattahoochee	2.2	Gordon	144.5
Chattooga	232.9	Grady	49.2
Cherokee	18.7	Greene	75.4
Clarke	100.8	Gwinnett	52.8
Clay	108.9	Habersham	1.5
Clayton	49.7	Hall	125.3
Clinch	5.5	Hancock	226.0
Cobb	43.3	Haralson	30.4
Coffee	103.9	Harris	23.1
Colquitt	277.9	Hart	162.6
Columbia	70.5	Heard	46.0
Cook	42.3	Henry	295.3
Coweta	108.6	Houston	58.0

GEORGIA—Continued

County	County reserve (acres)	County	County reserve (acres)
Irwin	191.0	Randolph	28.6
Jackson	480.7	Richmond	43.2
Jasper	195.9	Rockdale	51.4
Jeff Davis	94.9	Schley	67.9
Jefferson	1,036.9	Screven	97.9
Jenkins	61.0	Seminole	61.8
Johnson	1,132.6	Spalding	65.8
Jones	15.0	Stephens	103.0
Lamar	71.2	Stewart	198.9
Lanier	13.4	Sumter	222.8
Laurens	167.1	Talbot	58.5
Lee	42.9	Taliaferro	40.1
Liberty	9.8	Tattnall	85.4
Lincoln	156.1	Taylor	21.0
Long	22.6	Telfair	35.2
Lowndes	40.0	Terrell	256.5
Lumpkin	4.8	Thomas	79.3
McDuffie	159.3	Tift	19.8
McIntosh	0.4	Toombs	43.6
Macon	261.6	Towns	0.0
Madison	854.1	Treutlen	70.0
Marion	67.0	Troup	48.6
Meriwether	85.0	Turner	113.1
Miller	100.6	Twiggs	203.8
Mitchell	177.7	Union	0.0
Monroe	50.1	Upson	54.0
Montgomery	45.2	Walker	54.2
Morgan	149.9	Walton	500.7
Murray	429.1	Ware	23.5
Muscogee	3.7	Warren	295.0
Newton	135.8	Washington	134.1
Oconee	151.5	Wayne	194.1
Oglethorpe	139.5	Webster	16.5
Paulding	58.5	Wheeler	138.1
Peach	24.5	White	50.9
Pickens	35.3	Whitfield	253.1
Pierce	92.5	Wilcox	174.9
Pike	39.2	Wilkes	100.1
Polk	254.8	Wilkinson	164.2
Pulaski	47.8	Worth	77.5
Putnam	34.9		
Quitman	73.5	State total	21,942.4
Rabun	0.0		

ILLINOIS

Alexander	98.8
Massac	0.0
Pulaski	42.2
State total	141.0

KANSAS

Cowley	0.0
Montgomery	0.0
State total	0.0

KENTUCKY

Ballard	1.9	Hickman	99.5
Calloway	9.4	McCracken	0.6
Carlisle	7.6	Marshall	5.7
Fulton	7.9		
Graves	10.4	State total	143.0

LOUISIANA

Parish	Parish reserve (acres)	Parish	Parish reserve (acres)
Acadia	1,306.4	East Carroll	130.9
Allen	88.2	East Feliciana	391.5
Ascension	66.3	Evangeline	466.8
Assumption	0.0	Franklin	583.6
Avoyelles	2,683.3	Grant	347.2
Beauregard	12.8	Iberia	212.2
Bienville	540.2	Iberville	54.9
Bossier	1,797.8	Jackson	126.1
Caddo	3,499.9	Jefferson	0.0
Calcasieu	22.6	Jefferson Davis	30.1
Caldwell	172.0	Lafayette	1,525.7
Cameron	0.0	La Salle	33.1
Catahoula	724.3	Lincoln	325.5
Claiborne	912.7	Livingston	19.4
Concordia	842.9	Madison	50.4
De Soto	301.4	Morehouse	3,058.6
East Baton Rouge	51.6	Natchitoches	2,164.3
		Orleans	0.0

LOUISIANA—Continued

Parish	Parish reserve (acres)	Parish	Parish reserve (acres)
Ouachita	571.5	Tangipahoa	187.6
Pointe Coupee	1,093.5	Tensas	74.5
Rapides	1,192.8	Union	390.1
Red River	994.5	Vermilion	601.3
Richland	96.5	Vernon	145.0
Sabine	162.5	Washington	613.8
St. Helena	262.9	Webster	632.4
St. James	0.0	West Baton Rouge	132.5
St. John	0.0	West Carroll	247.6
St. Landry	263.7	West Feliciana	188.4
St. Martin	809.0	Winn	103.5
St. Mary	0.0		
St. Tammany	41.8	State total	31,348.1

MARYLAND

County	County reserve (acres)
Caroline	0.0
State total	0.0

MISSISSIPPI

Adams	82.7	Lincoln	514.5
Alcorn	964.3	Lowndes	349.5
Amite	720.6	Madison	996.1
Attala	776.5	Marion	490.3
Benton	399.0	Marshall	494.1
Bolivar	33.7	Monroe	966.8
Calhoun	1,272.5	Montgomery	668.0
Carroll	512.6	Neshoba	911.8
Chickasaw	409.8	Newton	1,138.5
Choctaw	86.7	Noxubee	1,480.5
Claiborne	221.2	Oktibbeha	117.9
Clarke	633.7	Panola	505.0
Clay	479.3	Pearl River	22.5
Coahoma	8.3	Perry	154.5
Copiah	219.1	Pike	627.5
Covington	643.7	Pontotoc	945.3
DeSoto	18.9	Prentiss	1,003.3
Forrest	127.5	Quitman	5.3
Franklin	49.9	Rankin	319.5
George	150.0	Scott	781.9
Greene	109.0	Sharkey	6.4
Grenada	318.4	Simpson	728.9
Hancock	3.7	Smith	581.9
Harrison	1.5	Stone	14.0
Hinds	2,852.0	Sunflower	22.1
Holmes	51.5	Tallahatchie	24.7
Humphreys	18.1	Tate	274.3
Issaquena	7.0	Tippah	1,123.4
Itawamba	1,093.3	Tishomingo	809.0
Jackson	41.4	Tunica	4.5
Jasper	677.8	Union	958.3
Jefferson	425.6	Walthall	778.4
Jefferson Davis	484.7	Warren	238.8
Jones	1,084.1	Washington	27.9
Kemper	472.3	Wayne	298.9
Lafayette	722.3	Webster	361.8
Lamar	230.6	Wilkinson	366.9
Lauderdale	607.2	Winston	191.0
Lawrence	434.0	Yalobusha	119.1
Leake	708.9	Yazoo	22.4
Lee	903.0	State total	38,509.2
Leflore	7.3		

MISSOURI

Bollinger	0.0	Ozark	3.9
Butler	68.8	Pemiscot	11.0
Cape Girardeau	0.0	Ripley	9.5
Carter	0.5	Scott	48.0
Dunklin	1.5	Stoddard	35.9
Howell	1.0	Vernon	0.0
Jefferson	0.0	Wayne	0.0
Mississippi	18.0		
New Madrid	50.0	State total	251.2
Oregon	3.1		

NEVADA

County	County reserve (acres)
Clark	0.0
Nye	0.0
State total	0.0

New Mexico

County	County reserve (acres)	County	County reserve (acres)
Bernalillo	0.0	Luna	8.2
Chaves	1,431.1	Otero	0.7
Curry	0.0	Quay	12.2
De Baca	1.2	Roosevelt	21.2
Dona Ana	57.0	Sierra	172.1
Eddy	44.5	Socorro	6.8
Grant	1.7	Valencia	4.0
Guadalupe	0.0		
Hidalgo	4.6	State total	1,833.0
Lea	67.7		

North Carolina

Alamance	9.0	Lee	18.6
Alexander	104.7	Lenoir	145.2
Anson	552.9	Lincoln	360.6
Beaufort	173.3	Martin	182.2
Bertie	782.5	Mecklenburg	500.7
Bladen	330.1	Montgomery	95.5
Brunswick	28.8	Moore	141.7
Burke	6.8	Nash	1,600.7
Cabarrus	244.2	New Hanover	1.6
Caldwell	3.7	Northampton	254.0
Camden	11.7	Onslow	15.1
Carteret	8.4	Orange	11.7
Catawba	342.1	Pamlico	8.2
Chatham	21.5	Pasquotank	21.9
Chowan	170.2	Pender	32.2
Cleveland	2,656.7	Perquimans	121.6
Columbus	384.2	Person	0.0
Craven	27.5	Pitt	1,112.7
Cumberland	32.6	Polk	87.2
Currituck	11.0	Randolph	6.3
Davidson	84.8	Richmond	293.4
Davie	131.0	Robeson	1,452.9
Duplin	398.3	Rockingham	1.0
Durham	18.4	Rowan	387.6
Edgecombe	185.4	Rutherford	552.4
Forsyth	18.0	Sampson	1,807.6
Franklin	1,266.5	Scotland	1,807.6
Gaston	349.7	Stanly	261.0
Gates	16.0	Tyrrell	22.3
Granville	3.0	Union	879.6
Greene	236.5	Vance	10.0
Guilford	4.3	Wake	300.9
Halifax	426.1	Warren	26.8
Harnett	375.3	Washington	51.8
Hertford	212.5	Wayne	245.6
Hoke	1,345.2	Wilkes	8.4
Hyde	13.0	Wilson	1,326.4
Iredell	370.5	Yadkin	6.0
Johnston	2,727.8		
Jones	6.4	State total	28,249.6

Oklahoma

Adair	9.0	Kingfisher	16.8
Atoka	173.3	Kiowa	77.7
Beaver	6.3	Latimer	19.9
Beckham	14.1	Leflore	368.2
Blaine	4.3	Lincoln	168.4
Bryan	2,006.7	Logan	86.1
Caddo	891.6	Love	680.6
Canadian	209.0	McClain	180.4
Carter	115.6	McCurtain	722.4
Cherokee	8.4	McIntosh	1,019.2
Choctaw	449.2	Major	274.2
Cleveland	131.9	Marshall	301.7
Coal	249.3	Mayes	85.1
Comanche	638.3	Murray	48.1
Cotton	1,464.8	Muskogee	806.4
Craig	9.8	Noble	101.0
Creek	66.0	Nowata	94.4
Custer	1,333.1	Okfuskee	379.2
Dewey	179.6	Oklahoma	30.1
Ellis	33.7	Okmulgee	402.5
Garfield	3.3	Osage	338.9
Garvin	25.0	Pawnee	112.5
Grady	285.8	Payne	176.7
Grant	0.0	Pittsburg	603.2
Greer	21.5	Pontotoc	125.1
Harmon	34.2	Pottawatomie	96.1
Harper	0.0	Pushmataha	65.7
Haskell	69.1	Roger Mills	50.8
Hughes	305.1	Rogers	107.4
Jackson	178.6	Seminole	171.8
Jefferson	1,454.2	Sequoyah	94.2
Johnston	77.1	Stephens	186.7
Kay	29.9	Texas	0.0

Oklahoma—Continued

County	County reserve (acres)	County	County reserve (acres)
Tillman	14.2	Washita	6,942.2
Tulsa	196.4	Woodward	62.6
Wagoner	703.0		
Washington	1.9	State total	26,389.6

South Carolina

Abbeville	585.4	Hampton	127.4
Aiken	858.9	Horry	301.3
Allendale	553.4	Jasper	158.4
Anderson	2,052.8	Kershaw	169.6
Bamberg	198.8	Lancaster	645.2
Barnwell	156.2	Laurens	227.3
Beaufort	84.1	Lee	86.8
Berkeley	434.8	Lexington	210.5
Calhoun	249.7	McCormick	188.8
Charleston	151.8	Marion	305.7
Cherokee	809.0	Marlboro	338.5
Chester	172.2	Newberry	529.9
Chesterfield	491.6	Oconee	491.4
Clarendon	391.5	Orangeburg	679.4
Colleton	257.4	Pickens	623.7
Darlington	427.6	Richland	64.4
Dillon	284.6	Saluda	567.1
Dorchester	407.1	Spartanburg	2,457.7
Edgefield	746.7	Sumter	540.2
Fairfield	198.5	Union	154.4
Florence	634.6	Williamsburg	340.7
Georgetown	65.5	York	174.8
Greenville	1,266.5		
Greenwood	336.4	State total	21,198.3

Tennessee

Bedford	178.5	Lincoln	51.3
Benton	14.8	Loudon	0.0
Bradley	30.7	McMinn	19.5
Cannon	2.1	McNairy	37.9
Carroll	77.8	Madison	66.6
Chester	18.0	Marion	33.4
Coffee	181.5	Marshall	41.3
Crockett	109.6	Maury	22.1
Cumberland	0.0	Meigs	15.0
Davidson	0.0	Monroe	3.5
Decatur	112.4	Moore	10.0
DeKalb	3.2	Obion	43.3
Dyer	56.4	Perry	9.0
Fayette	36.2	Polk	25.0
Franklin	118.2	Rhea	2.5
Gibson	59.0	Roane	0.0
Giles	180.3	Robertson	0.0
Grundy	11.5	Rutherford	28.2
Hamilton	10.7	Shelby	31.3
Hardeman	37.3	Tipton	61.6
Hardin	35.1	Van Buren	1.1
Haywood	71.4	Warren	5.0
Henderson	58.2	Wayne	8.1
Henry	20.8	Weakley	133.4
Hickman	0.4	White	2.2
Humphreys	0.9	Williamson	1.1
Lake	34.7	Wilson	0.0
Lauderdale	11.7		
Lawrence	78.2	State total	2,234.1
Lewis	32.1		

Texas

Anderson	11.8	Brooks	9.7
Andrews	4.1	Brown	97.8
Angelina	46.1	Burleson	3,145.8
Aransas	0.2	Burnet	58.2
Archer	32.2	Caldwell	7.4
Armstrong	16.6	Calhoun	27.8
Atascosa	38.4	Callahan	9.0
Austin	1,075.7	Cameron	35.9
Bailey	12.7	Camp	19.5
Bandera	0.4	Carson	54.7
Bastrop	195.2	Cass	466.2
Baylor	8.2	Castro	27.4
Bee	21.2	Chambers	2.0
Bell	176.2	Cherokee	250.9
Bexar	59.3	Childress	36.4
Blanco	5.0	Clay	64.9
Borden	2.3	Cochran	3.3
Bosque	919.3	Coke	574.0
Bowie	77.8	Coleman	61.0
Brazoria	17.9	Collin	1,749.6
Brazos	62.4	Collingsworth	9.1
Brewster	0.0	Colorado	14.9
Briscoe	2.6	Comal	15.4

Texas—Continued

County	County reserve (acres)	County	County reserve (acres)
Comanche	277.9	Knox	20.9
Concho	315.7	Lamar	24.4
Cooke	377.6	Lamb	1.8
Coryell	31.5	Lampasas	32.7
Cottle	10.9	LaSalle	29.4
Crockett	0.0	Lavaca	66.8
Crosby	2.0	Lee	39.7
Culberson	9.8	Leon	33.7
Dallam	5.0	Liberty	27.8
Dallas	1,393.3	Limestone	4,220.0
Dawson	7.9	Live Oak	24.7
Deaf Smith	6.0	Llano	25.1
Delta	56.4	Loving	0.1
Denton	599.3	Lubbock	6.5
DeWitt	28.0	Lynn	19.4
Dickens	30.2	McCulloch	38.9
Dimmit	17.2	McLennan	124.9
Donley	4.8	McMullen	34.6
Duval	13.2	Madison	47.1
Eastland	578.9	Marion	10.6
Ector	0.0	Martin	1.7
Ellis	3,354.8	Mason	21.2
El Paso	194.4	Matagorda	4.2
Erath	88.1	Maverick	23.2
Falls	1,873.2	Medina	69.0
Fannin	1,657.1	Menard	13.4
Fayette	983.1	Midland	12.5
Fisher	2.2	Milam	114.4
Floyd	13.4	Mills	316.3
Foard	4.2	Mitchell	35.6
Fort Bend	8.8	Montague	49.4
Franklin	32.4	Montgomery	13.8
Freestone	54.2	Moore	43.6
Frio	6.6	Morris	24.1
Gaines	5.0	Motley	5.8
Galveston	4.0	Nacogdoches	53.7
Garza	14.7	Navarro	110.1
Gillespie	74.9	Newton	85.5
Glasscock	1.5	Nolan	5.3
Goliad	34.1	Nueces	26.7
Gonzales	28.4	Ochiltree	1.0
Gray	0.1	Oldham	0.1
Grayson	1,175.4	Palo Pinto	40.1
Gregg	17.4	Panola	45.1
Grimes	54.8	Parker	195.4
Guadalupe	43.3	Parmer	16.3
Hale	22.7	Pecos	1.3
Hall	50.7	Polk	31.0
Hamilton	99.5	Potter	0.9
Hansford	15.1	Presidio	1.3
Hardeman	18.8	Rains	19.7
Hardin	6.6	Randall	20.8
Harris	20.5	Reagan	0.2
Harrison	67.7	Real	2.7
Hartley	5.1	Red River	223.0
Haskell	99.5	Reeves	17.0
Hays	39.4	Refugio	3.3
Hemphill	2.0	Roberts	2.4
Henderson	48.8	Robertson	59.3
Hidalgo	173.7	Rockwall	349.0
Hill	127.2	Runnels	89.6
Hockley	12.5	Rusk	130.2
Hood	262.1	Sabine	129.4
Hopkins	0.8	San Augustine	91.9
Houston	635.8	San Jacinto	36.2
Howard	16.8	San Patricio	54.9
Hudspeth	9.1	San Saba	75.7
Hunt	6,517.8	Schleicher	1.3
Irion	1.8	Scurry	13.6
Jack	30.2	Shackelford	29.7
Jackson	20.2	Shelby	9.1
Jasper	75.4	Smith	120.1
Jeff Davis	0.6	Somervell	18.6
Jefferson	3.3	Starr	57.9
Jim Hogg	4.8	Stephens	50.6
Jim Wells	37.1	Sterling	3.7
Johnson	299.8	Stonewall	1.9
Jones	41.7	Sutton	0.0
Karnes	56.4	Swisher	3.3
Kaufman	4,190.2	Tarrant	961.0
Kendall	2.0	Taylor	26.1
Kent	5.9	Terrell	1.6
Kerr	9.3	Terry	12.1
Kimble	23.0	Throckmorton	21.8
King	5.3	Titus	102.5
Kinney	61.0	Tom Green	183.9
Kleberg	35.7	Travis	54.5

TEXAS—Continued

County	County reserve (acres)	County	County reserve (acres)
Trinity	45.9	Wichita	35.9
Tyler	4.8	Wilbarger	54.4
Upshur	123.7	Willacy	25.1
Upton	0.3	Williamson	42.1
Uvalde	5.2	Wilson	303.9
Val Verde	3.0	Winkler	0.0
Van Zandt	66.8	Wise	291.5
Victoria	11.4	Wood	66.6
Walker	28.6	Yoakum	9.9
Waller	23.3	Young	161.1
Ward	0.5	Zapata	154.5
Washington	110.0	Zavala	9.3
Webb	225.2		
Wharton	32.2	State total	47,212.4
Wheeler	33.4		

VIRGINIA

Accomack	0.0	Lunenburg	19.0
Appomattox	89.1	Mecklenburg	5.1
Brunswick	89.1	Nansemond	90.5
Charlotte	1.2	Patrick	0.0
Chesapeake	0.0	Prince Edward	0.0
Chesterfield	0.0	Prince George	1.2
Cumberland	0.1	Southampton	144.2
Dinwiddie	20.8	Surry	1.2
Franklin	0.0	Sussex	100.0
Greensville	88.2	Virginia Beach	0.0
Halifax	0.0		
Henrico	0.0		
Isle of Wight	29.2	State total	589.8

(Secs. 344, 375, 63 Stat. 670, as amended; 52 Stat. 66, as amended; 7 U.S.C. 1344, 1375)

Effective date. Date of filing this document with the Director, Office of the Federal Register.

Signed at Washington, D.C., on December 9, 1963.

E. A. JAENKE,
Acting Administrator, Agricultural Stabilization and Conservation Service.

[F.R. Doc. 63-12915; Filed, Dec. 10, 1963; 1:00 p.m.]

PART 722—COTTON

Subpart—National Marketing Quota, National Allotment, and Apportionment to the States and Counties for the 1964 Crop of Extra Long Staple Cotton

COUNTY RESERVE

(a) Section 722.345 is issued pursuant to the Agricultural Adjustment Act of 1938, as amended (52 Stat. 31, as amended, 7 U.S.C. 1281 et seq.). This section establishes the county reserve for the 1964 crop of extra long staple cotton.

(b) Notice that the Secretary was preparing to establish State and county allotments was published in the FEDERAL REGISTER on September 14, 1963 (28 F.R. 10001) in accordance with section 4 of the Administrative Procedure Act (60 Stat. 238; 5 U.S.C. 1003). The data, views and recommendations received in response to such notice have been duly considered.

(c) Since the establishment of county reserves under this section requires immediate action by the Agricultural Stabilization and Conservation State and county committees, it is essential that § 722.345 be made effective as soon as possible. Accordingly, it is hereby determined and found that compliance with the 30-day effective date requirement of section 4 of the Administrative Procedure Act is impracticable and contrary to the public interest and § 722.345 shall be effective upon filing this document with the Director, Office of the Federal Register.

§ 722.345 County reserve.

The county reserve is established for the 1964 crop of extra long staple cotton in accordance with § 722.309 of the Acreage Allotment Regulations for the 1964 and Succeeding Crops of Extra Long Staple Cotton (28 F.R. 11034). The following table sets forth the county reserve:

County	County reserve (acres)
ARIZONA	
Cochise	3.1
Gila	0.0
Graham	9.9
Maricopa	151.2
Pima	4.7
Pinal	28.5
Santa Cruz	0.0
Yuma	4.8
State total	202.2
CALIFORNIA	
Imperial	3.2
Riverside	9.9
State total	13.1
FLORIDA	
Alachua	0.1
Bradford	1.6
Hamilton	0.0
Jefferson	0.0
Lake	8.8
Madison	0.0
Marion	0.0
Putnam	0.0
Sumter	0.0
Suwannee	0.0
Union	0.0
Volusia	1.5
State total	12.0
GEORGIA	
Berrien	18.5
Cook	0.1
Lanier	0.1
State total	18.7
NEW MEXICO	
Chaves	0.0
Dona Ana	3.4
Eddy	10.9
Hidalgo	0.0
Luna	0.0
Otero	3.7
Sierra	23.9
State total	41.9
TEXAS	
Brewster	0.0
Culberson	4.9
El Paso	40.5
Hudspeth	6.5
Loving	0.0
Pecos	1.4
Presidio	0.1
Reeves	5.1
Ward	0.0
State total	58.5
PUERTO RICO	
North	147.8
South	27.2
Total	175.0

(Secs. 344, 347, 375, 63 Stat. 670, as amended, 63 Stat. 675, as amended, 52 Stat. 66, as amended; 7 U.S.C. 1344, 1347, 1375)

Effective date: Date of filing this document with the Director, Office of the Federal Register.

Signed at Washington, D.C. on December 9, 1963.

E. A. JAENKE,
Acting Administrator, Agricultural Stabilization and Conservation Service.

[F.R. Doc. 63-12914; Filed, Dec. 10, 1963; 1:00 p.m.]

Chapter IX—Agricultural Marketing Service (Marketing Agreements and Orders; Fruits, Vegetables, Tree Nuts), Department of Agriculture

[Grapefruit Reg. 32]

PART 905—ORANGES, GRAPEFRUIT, TANGERINES, AND TANGELOS GROWN IN FLORIDA

Limitation of Shipments

§ 905.400 Grapefruit regulation 32.

(a) *Findings.* (1) Pursuant to the marketing agreement, as amended, and Order No. 905, as amended (7 CFR Part 905), regulating the handling of oranges, grapefruit, tangerines, and tangelos grown in Florida, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601-674), and upon the basis of the recommendations of the committees established under the aforesaid amended marketing agreement and order, and upon other available information, it is hereby found that the limitation of shipments of grapefruit, as hereinafter provided, will tend to effectuate the declared policy of the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rule-making procedure, and postpone the effective date of this section until 30 days after publication thereof in the FEDERAL REGISTER (5 U.S.C. 1001-1011) because the time intervening between the date when information upon which this section is based became available and the time when this section must become effective in order to effectuate the declared policy of the act is insufficient; a reasonable time is permitted, under the circumstances, for preparation for such effective time; and good cause exists for making the provisions hereof effective as hereinafter set forth. Shipments of all grapefruit, grown in the production area, are presently subject to regulation by grades and sizes, pursuant to the amended marketing agreement and order; the recommendation and supporting information for regulation during the period specified herein were promptly submitted to the Department after an open meeting of the Growers Administrative Committee on December 10, 1963, such meeting was held to consider recommendations for regulation, after giving due notice of such meeting, and interested persons were afforded an opportunity to submit their views at this meeting; the provisions of this section, including the effective time hereof, are identical with the aforesaid recommendation of the committee, and information concerning such provisions and

effective time has been disseminated among handlers of such grapefruit; it is necessary, in order to effectuate the declared policy of the act, to make this section effective during the period hereinafter set forth so as to provide for the continued regulation of the handling of grapefruit, and compliance with this section will not require any special preparation on the part of the persons subject thereto which cannot be completed by the effective time hereof.

(b) *Order.* (1) Terms used in the amended marketing agreement and order shall, when used herein, have the same meaning as is given to the respective term in said amended marketing agreement and order; and terms relating to grade, diameter, standard pack, and standard box, as used herein, shall have the same meaning as is given to the respective term in the United States Standards for Florida Grapefruit (§§ 51.750–51.783 of this title).

(2) During the period beginning at 12:01 a.m., e.s.t., December 16, 1963, and ending at 12:01 a.m., e.s.t., January 13, 1964, no handler shall ship between the production area and any point outside thereof in the continental United States, Canada, or Mexico:

(i) Any grapefruit, grown in the production area, which do not grade at least U.S. No. 1 Russet;

(ii) Any seeded grapefruit, grown in the production area, which are smaller than $3\frac{15}{16}$ inches in diameter, except that a tolerance of 10 percent, by count, of seeded grapefruit smaller than such minimum size shall be permitted, which tolerance shall be applied in accordance with the provisions for the application of tolerances, specified in said United States Standards for Florida Grapefruit; or

(iii) Any seedless grapefruit, grown in the production area, which are smaller than $3\frac{9}{16}$ inches in diameter, except that a tolerance of 10 percent, by count, of seedless grapefruit smaller than such minimum size shall be permitted, which tolerance shall be applied in accordance with the provisions for the application of tolerances, specified in said United States Standards for Florida Grapefruit.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 11, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–12988; Filed, Dec. 13, 1963; 8:47 a.m.]

[Orange Reg. 32]

PART 905—ORANGES, GRAPEFRUIT, TANGERINES, AND TANGELOS GROWN IN FLORIDA

Limitation of Shipments

§ 905.399 Orange regulation 32.

(a) *Findings.* (1) Pursuant to the marketing agreement, as amended, and Order No. 905, as amended (7 CFR Part 905), regulating the handling of oranges, grapefruit, tangerines, and tangelos grown in Florida, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601–674), and upon the basis of the recommendations of the committees established under the aforesaid amended marketing agreement and order, and upon other available information, it is hereby found that the limitation of shipments of oranges, as hereinafter provided, will establish and maintain such minimum standards of quality and maturity and such grading and inspection requirements as will tend to effectuate such orderly marketing of Florida oranges as will be in the public interest; will tend to effectuate the declared policy of the act; and is not for the purpose of maintaining prices to farmers above the level which it is declared to be the policy of Congress to establish under the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rule-making procedure, and postpone the effective date of this section until 30 days after publication thereof in the FEDERAL REGISTER (5 U.S.C. 1001–1011) because the time intervening between the date when information upon which this section is based became available and the time when this section must become effective in order to effectuate the declared policy of the act is insufficient; a reasonable time is permitted, under the circumstances, for preparation for such effective time; and good cause exists for making the provisions hereof effective as hereinafter set forth. Shipments of oranges, including Temple oranges, grown in the production area, are presently subject to regulation by grades and sizes, pursuant to the amended marketing agreement and order; the recommendation and supporting information for regulation during the period specified herein were promptly submitted to the Department after an open meeting of the Growers Administrative Committee on December 10, 1963; such meeting was held to consider recommendations for regulation, after giving due notice of such meeting, and interested persons were afforded an opportunity to submit their views at this meeting; the provisions of this section, including the effective time hereof, are identical with the aforesaid recommendation of the committee, and information concerning such provisions and effective time has been disseminated among handlers of such oranges; the provisions of the act require that the minimum standards of quality and maturity, as set forth herein, be made effective when the seasonal average price to growers for such oranges will exceed the parity level specified in section 2(1) of the act; it is necessary, in order to effectuate the declared policy of the act, to make this section effective during the period hereinafter set forth, and at the commencement thereof, so as not to permit the unrestricted shipment thereafter of Florida oranges as such unrestricted shipment would not be conducive to the orderly marketing of such oranges as will be in the public interest and would not tend to effectuate the declared policy of the act; and compliance with this section will not require any special preparation on the part of the persons subject thereto which cannot be completed by the effective time hereof.

(b) *Order.* (1) Terms used in the amended marketing agreement and order shall, when used herein, have the same meaning as is given to the respective term in said amended marketing agreement and order; and terms relating to grade, diameter, standard pack, and standard box, as used herein, shall have the same meaning as is given to the respective term in the United States Standards for Florida Oranges and Tangelos (§§ 51.1140–51.1178 of this title).

(2) During the period beginning at 12:01 a.m., e.s.t., December 16, 1963, and ending at 12:01 a.m., e.s.t., January 13, 1964, no handler shall ship between the production area and any point outside thereof in the continental United States, Canada, or Mexico:

(i) Any oranges, including Temple oranges, grown in the production area, which do not grade at least U.S. No. 2 Russet;

(ii) Any oranges, except Temple oranges, grown in the production area, which are of a size smaller than $2\frac{1}{16}$ inches in diameter, except that a tolerance of 10 percent, by count, of oranges smaller than such minimum diameter shall be permitted, which tolerance shall be applied in accordance with the provisions for the application of tolerances specified in said United States Standards for Florida Oranges and Tangelos: *Provided,* That in determining the percentage of oranges in any lot which are smaller than $2\frac{1}{16}$ inches in diameter, such percentage shall be based only on those oranges in such lot which are of a size $2\frac{10}{16}$ inches in diameter or smaller; or

(iii) Any Temple oranges, grown in the production area, which are of a size smaller than $2\frac{5}{16}$ inches in diameter, except that a tolerance of 10 percent, by count, of Temple oranges smaller than such minimum diameter shall be permitted, which tolerance shall be applied in accordance with the provisions for the application of tolerances specified in the aforesaid United States Standards for Florida Oranges and Tangelos.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 11, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–12989; Filed, Dec. 13, 1963; 8:47 a.m.]

[Tangerine Reg. 17]

PART 905—ORANGES, GRAPEFRUIT, TANGERINES, AND TANGELOS GROWN IN FLORIDA

Limitation of Shipments

§ 905.401 Tangerine regulation 17.

(a) *Findings.* (1) Pursuant to the marketing agreement, as amended, and Order No. 905, as amended (7 CFR Part 905), regulating the handling of oranges, grapefruit, tangerines, and tangelos

grown in Florida, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601–674), and upon the basis of the recommendations of the committees established under the aforesaid amended marketing agreement and order, and upon other available information, it is hereby found that the limitation of shipments of tangerines, as hereinafter provided, will tend to effectuate the declared policy of the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rule-making procedure, and postpone the effective date of this section until 30 days after publication thereof in the FEDERAL REGISTER (5 U.S.C. 1001–1011) because the time intervening between the date when information upon which this section is based became available and the time when this section must become effective in order to effectuate the declared policy of the act is insufficient; a reasonable time is permitted, under the circumstances, for preparation for such effective time; and good cause exists for making the provisions hereof effective as hereinafter set forth. Shipments of tangerines, grown in the production area, are presently subject to regulation by grades and sizes, pursuant to the amended marketing agreement and order; the recommendation and supporting information for regulation during the period specified herein were promptly submitted to the Department after an open meeting of the Growers Administrative Committee on December 10, 1963, such meeting was held to consider recommendations for regulation, after giving due notice of such meeting, and interested persons were afforded an opportunity to submit their views at this meeting; the provisions of this section, including the effective time hereof, are identical with the aforesaid recommendation of the committee, and information concerning such provisions and effective time has been disseminated among handlers of such tangerines; it is necessary, in order to effectuate the declared policy of the act, to make this section effective during the period hereinafter set forth so as to provide for the continued regulation of the handling of tangerines, and compliance with this section will not require any special preparation on the part of the persons subject thereto which cannot be completed by the effective time hereof.

(b) *Order.* (1) Terms used in the amended marketing agreement and order shall, when used herein, have the same meaning as is given to the respective term in said amended marketing agreement and order; and terms relating to grade, diameter, and standard pack, as used herein, shall have the same meaning as is given to the respective term in the United States Standards for Florida Tangerines (§§ 51.1810–51.1834 of this title).

(2) During the period beginning at 12:01 a.m., e.s.t., December 16, 1963, and ending at 12:01 a.m., e.s.t., January 13, 1964, no handler shall ship between the production area and any point outside thereof in the continental United States, Canada, or Mexico:

(i) Any tangerines, grown in the production area, which do not grade at least U.S. No. 1 Russet; or

(ii) Any tangerines, grown in the production area, which are of a size smaller than 2$\frac{4}{16}$ inches in diameter, except that a tolerance of 10 percent, by count, of tangerines smaller than such minimum diameter shall be permitted, which tolerance shall be applied in accordance with the provisions for the application of tolerances specified in said United States Standards for Florida Tangerines.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 11, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–13016; Filed, Dec. 13, 1963; 8:49 a.m.]

[Tangelo Reg. 17]

PART 905—ORANGES, GRAPEFRUIT, TANGERINES, AND TANGELOS GROWN IN FLORIDA

Limitation of Shipments

§ 905.402 Tangelo regulation 17.

(a) *Findings.* (1) Pursuant to the marketing agreement, as amended, and Order No. 905, as amended (7 CFR Part 905), regulating the handling of oranges, grapefruit, tangerines, and tangelos grown in Florida, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601–674), and upon the basis of the recommendations of the committees established under the aforesaid amended marketing agreement and order, and upon other available information, it is hereby found that the limitation of shipments of tangelos, as hereinafter provided, will tend to effectuate the declared policy of the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rule-making procedure, and postpone the effective date of this section until 30 days after publication thereof in the FEDERAL REGISTER (5 U.S.C. 1001–1011) because the time intervening between the date when information upon which this section is based became available and the time when this section must become effective in order to effectuate the declared policy of the act is insufficient; a reasonable time is permitted, under the circumstances, for preparation for such effective time; and good cause exists for making the provisions hereof effective as hereinafter set forth. Shipments of tangelos, grown in the production area, are presently subject to regulation by grades and sizes, pursuant to the amended marketing agreement and order; the recommendation and supporting information for regulation during the period specified herein were promptly submitted to the Department after an open meeting of the Growers Administrative Committee on December 10, 1963, such meeting was held to consider recommendations for regulation, after giving due notice of such meeting, and interested persons were afforded an opportunity to submit their views at this meeting; the provisions of this section, including the effective time hereof, are identical with the aforesaid recommendation of the committee, and information concerning such provisions and effective time has been disseminated among handlers of such tangelos; it is necessary, in order to effectuate the declared policy of the act, to make this section effective during the period hereinafter set forth so as to provide for the continued regulation of the handling of tangelos, and compliance with this section will not require any special preparation on the part of the persons subject thereto which cannot be completed by the effective time hereof.

(b) *Order.* (1) Terms used in the amended marketing agreement and order shall, when used herein, have the same meaning as is given to the respective term in said amended marketing agreement and order; and terms relating to grade, diameter, standard pack, and standard box, as used herein, shall have the same meaning as is given to the respective term in the United States Standards for Florida Oranges and Tangelos (§§ 51.1140–51.1178 of this title).

(2) During the period beginning at 12:01 a.m., e.s.t., December 16, 1963, and ending at 12:01 a.m., e.s.t., January 13, 1964, no handler shall ship between the production area and any point outside thereof in the continental United States, Canada, or Mexico:

(i) Any tangelos, grown in the production area, which do not grade at least U.S. No. 2 Russet; or

(ii) Any tangelos, grown in the production area, which are of a size smaller than 2$\frac{5}{16}$ inches in diameter, except that a tolerance of 10 percent, by count, of tangelos smaller than such minimum diameter shall be permitted, which tolerance shall be applied in accordance with the provisions for the application of tolerances specified in said United States Standards for Florida Oranges and Tangelos.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 11, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–13015; Filed, Dec. 13, 1963; 8:49 a.m.]

[Navel Orange Reg. 41]

PART 907—NAVEL ORANGES GROWN IN ARIZONA AND DESIGNATED PART OF CALIFORNIA

Limitation of Handling

§ 907.341 Navel orange regulation.

(a) *Findings.* (1) Pursuant to the marketing agreement, as amended, and Order No. 907, as amended (7 CFR Part 907; 27 F.R. 10087), regulating the han-

dling of navel oranges grown in Arizona and designated part of California, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601–674), and upon the basis of the recommendations and information submitted by the Navel Orange Administrative Committee, established under the said amended marketing agreement and order, and upon other available information, it is hereby found that the limitation of handling of such navel oranges as hereinafter provided will tend to effectuate the declared policy of the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rule-making procedure, and postpone the effective date of this section until 30 days after publication hereof in the FEDERAL REGISTER (5 U.S.C. 1001–1011) because the time intervening between the date when information upon which this section is based became available and the time when this section must become effective in order to effectuate the declared policy of the act is insufficient, and a reasonable time is permitted, under the circumstances, for preparation for such effective time; and good cause exists for making the provisions hereof effective as hereinafter set forth. The committee held an open meeting last week, after giving due notice thereof, to consider supply and market conditions for navel oranges and the need for regulation; interested persons were afforded an opportunity to submit information and views at this meeting; the recommendation and supporting information for regulation during the period specified herein were promptly submitted to the Department after such meeting was held; the provisions of this section, including its effective time, are identical with the aforesaid recommendation of the committee, and information concerning such provisions and effective time has been disseminated among handlers of such navel oranges; it is necessary, in order to effectuate the declared policy of the act, to make this section effective during the period herein specified; and compliance with this section will not require any special preparation on the part of persons subject hereto which cannot be completed on or before the effective date hereof. Such committee meeting was held on December 5, 1963.

(b) Order (1) Navel Orange Regulation 36 (§ 907.336; 28 F.R. 12198) is hereby terminated at 12:01 a.m., P.s.t., December 15, 1963.

(2) During the period beginning at 12:01 a.m., P.s.t., December 15, 1963, and ending at 12:01 a.m., P.s.t., November 1, 1964, no handler shall handle any navel oranges grown in District 1, District 2, District 3, or District 4 which are a size smaller than 2.32 inches in diameter, which shall be the largest measurement at a right angle to a straight line running from the stem to the blossom end of the fruit, except, that not to exceed 5 percent, by count, of the oranges in any type of container may measure smaller than 2.32 inches in diameter: *Provided*, That in addition to such tolerance each handler may, during each calendar week of the aforesaid period handle a quantity of such oranges, which are smaller than 2.32 inches in diameter but not smaller than 2.20 inches in diameter, except not to exceed 5 percent, by count, of oranges smaller than 2.20 inches in diameter shall be permitted in any container of oranges which are smaller than 2.32 inches in diameter, equal to, but not in excess of, ten (10) percent of (a) the weekly allotment issued to such handler when volume regulation is in effect, or (b) ten (10) percent of the weekly volume handled by such handler when volume regulation is not in effect.

(3) As used in this section, "handle," "handler," "District 1," "District 2," "District 3," and "District 4" shall have the same meaning as when used in said amended marketing agreement and order.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 11, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–12965; Filed, Dec. 13, 1963; 8:45 a.m.]

[Navel Orange Reg. 42]

PART 907—NAVEL ORANGES GROWN IN ARIZONA AND DESIGNATED PART OF CALIFORNIA

Limitation of Handling

§ 907.342 Navel orange regulation 42.

(a) *Findings.* (1) Pursuant to the marketing agreement, as amended, and Order No. 907, as amended (7 CFR Part 907; 27 F.R. 10087), regulating the handling of navel oranges grown in Arizona and designated part of California, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601–674), and upon the basis of the recommendations and information submitted by the Navel Orange Administrative Committee, established under the said amended marketing agreement and order, and upon other available information, it is hereby found that the limitation of handling of such navel oranges as hereinafter provided will tend to effectuate the declared policy of the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rulemaking procedure, and postpone the effective date of this section until 30 days after publication hereof in the FEDERAL REGISTER (5 U.S.C. 1001–1011) because the time intervening between the date when information upon which this section is based became available and the time when this section must become effective in order to effectuate the declared policy of the act is insufficient, and a reasonable time is permitted, under the circumstances, for preparation for such effective time; and good cause exists for making the provisions hereof effective as hereinafter set forth. The committee held an open meeting during the current week, after giving due notice thereof, to consider supply and market conditions for navel oranges and the need for regulation; interested persons were afforded an opportunity to submit information and views at this meeting; the recommendation and supporting information for regulation during the period specified herein were promptly submitted to the Department after such meeting was held; the provisions of this section, including its effective time, are identical with the aforesaid recommendation of the committee, and information concerning such provisions and effective time has been disseminated among handlers of such navel oranges; it is necessary, in order to effectuate the declared policy of the act, to make this section effective during the period herein specified; and compliance with this section will not require any special preparation on the part of persons subject hereto which cannot be completed on or before the effective date hereof. Such committee meeting was held on December 12, 1963.

(b) *Order.* (1) The respective quantities of navel oranges grown in Arizona and designated part of California which may be handled during the period beginning at 12:01 a.m., P.s.t., December 15, 1963, and ending at 12:01 a.m., P.s.t., December 22, 1963, are hereby fixed as follows:

(i) District 1: 800,000 cartons;
(ii) District 2: 122,155 cartons;
(iii) District 3: 125,000 cartons;
(iv) District 4: Unlimited movement.

(2) As used in this section, "handled," "District 1," "District 2," "District 3," "District 4," and "carton" have the same meaning as when used in said amended marketing agreement and order.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 13, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–13063; Filed, Dec. 13, 1963; 11:25 a.m.]

[Grapefruit Reg. 13]

PART 909—GRAPEFRUIT GROWN IN ARIZONA; IN IMPERIAL COUNTY, CALIF.; AND IN THAT PART OF RIVERSIDE COUNTY, CALIF., SITUATED SOUTH AND EAST OF WHITE WATER, CALIF.

Limitation of Shipments

§ 909.313 Grapefruit regulation 13.

(a) *Findings.* (1) Pursuant to the marketing agreement, as amended, and Order No. 909, as amended (7 CFR Part 909), regulating the handling of grapefruit grown in the State of Arizona; in Imperial County, California; and in that part of Riverside County, California, situated south and east of White Water, California, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601 et seq.), and upon the basis of the recommendations of the

Administrative Committee (established under the aforesaid amended marketing agreement and order), and upon other available information, it is hereby found that the limitation of shipments of grapefruit, as hereinafter provided, will tend to effectuate the declared policy of the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rule-making procedure, and postpone the effective date of this section until 30 days after publication thereof in the FEDERAL REGISTER (5 U.S.C. 1001–1011), because the time intervening between the date when information upon which this section is based became available and the time when this section must become effective in order to effectuate the declared policy of the act is insufficient, and a reasonable time is permitted, under the circumstances, for preparation for such effective date. The Administrative Committee held an open meeting on December 5, 1963, to consider recommendations for a regulation, after giving due notice of such meeting, and interested persons were afforded an opportunity to submit their views at this meeting; the recommendation and supporting information for regulation during the period specified herein were promptly submitted to the Department after such open meeting; necessary supplemental economic and statistical information upon which this recommended section is based were received by the Fruit Branch on December 9, 1963; information regarding the provisions of the section recommended by the committee has been disseminated to shippers of grapefruit, grown as aforesaid, and this section, including the effective time thereof, is identical with the recommendation of the committee; it is necessary, in order to effectuate the declared policy of the act, to make this section effective on the date hereinafter set forth; and compliance with this section will not require any special preparation on the part of persons subject thereto which cannot be completed on or before the effective date hereof.

(b) *Order.* (1) During the period beginning at 12:01 a.m., P.s.t., December 15, 1963, and ending at 12:01 a.m., P.s.t., January 19, 1964, no handler shall handle:

(i) From the State of California or the State of Arizona to any point outside thereof any grapefruit of any variety grown in the State of Arizona; in Imperial County, California; or in that part of Riverside County, California, situated south and east of White Water, California, unless such grapefruit are well colored and grade at least U.S. No. 2: *Provided,* That included in the tolerances for defects permitted by such grade not more than 5 percent, by count, shall be allowed for grapefruit having peel more than one inch in thickness at the stem end, measured from the flesh to the highest point of the peel; or

(ii) From the State of California or the State of Arizona to any point in Zone 1 or Zone 2, any grapefruit, grown as aforesaid, which measure less than $3\frac{11}{16}$ inches in diameter, except that a tolerance of 5 percent, by count, of grapefruit smaller than the foregoing minimum size shall be permitted which tolerance shall be applied in accordance with the provisions for the application of tolerances, specified in the revised United States Standards for Grapefruit (California and Arizona), §§ 51.925–51.955 of this title: *Provided,* That, in determining the percentage of grapefruit in any lot which are smaller than $3\frac{11}{16}$ inches in diameter, such percentage shall be based only on the grapefruit in such lot which are of a size $4\frac{7}{16}$ inches in diameter and smaller.

(iii) From the State of California or the State of Arizona to any point in Zone 3 any grapefruit, grown as aforesaid, which measure less than $3\frac{9}{16}$ inches in diameter, except that a tolerance of 5 percent, by count, of grapefruit smaller than the foregoing minimum size shall be permitted which tolerance shall be applied in accordance with the provisions for the application of tolerances, specified in the revised United States Standards for Grapefruit (California and Arizona), §§ 51.925–51.955 of this title: *Provided,* That, in determining the percentage of grapefruit in such lot which are smaller than $3\frac{9}{16}$ inches in diameter, such percentage shall be based only on the grapefruit in such lot which are of a size $3\frac{13}{16}$ inches in diameter and smaller.

(2) As used herein, "handler," "variety," "grapefruit," "handle," "Zone 1," "Zone 2," and "Zone 3" shall have the same meaning as when used in said amended marketing agreement and order; the terms "U.S. No. 2" and "well colored" shall have the same meaning as when used in the aforesaid revised United States Standards for Grapefruit; and "diameter" shall mean the greatest dimension measured at right angles to a line from the stem to blossom end of the fruit.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 11, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–12990; Filed, Dec. 13, 1963; 8:47 a.m.]

[Lemon Reg. 87]

PART 910—LEMONS GROWN IN CALIFORNIA AND ARIZONA

Limitation of Handling

§ 910.387 Lemon regulation 87.

(a) *Findings.* (1) Pursuant to the marketing agreement, as amended, and Order No. 910, as amended (7 CFR Part 910; 27 F.R. 8346), regulating the handling of lemons grown in California and Arizona, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601–674), and upon the basis of the recommendation and information submitted by the Lemon Administrative Committee, established under the said amended marketing agreement and order, and upon other available information, it is hereby found that the limitation of handling of such lemons as hereinafter provided will tend to effectuate the declared policy of the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rule-making procedure, and postpone the effective date of this section until 30 days after publication hereof in the FEDERAL REGISTER (5 U.S.C. 1001–1011) because the time intervening between the date when information upon which this section is based became available and the time when this section must become effective in order to effectuate the declared policy of the act is insufficient, and a reasonable time is permitted, under the circumstances, for preparation for such effective time; and good cause exists for making the provisions hereof effective as hereinafter set forth. The committee held an open meeting during the current week, after giving due notice thereof, to consider supply and market conditions for lemons and the need for regulation; interested persons were afforded an opportunity to submit information and views at this meeting; the recommendation and supporting information for regulation during the period specified herein were promptly submitted to the Department after such meeting was held; the provisions of this section, including its effective time, are identical with the aforesaid recommendation of the committee, and information concerning such provisions and effective time has been disseminated among handlers of such lemons; it is necessary, in order to effectuate the declared policy of the act, to make this section effective during the period herein specified; and compliance with this section will not require any special preparation on the part of persons subject hereto which cannot be completed on or before the effective date hereof. Such committee meeting was held on December 10, 1963.

(b) *Order.* (1) The respective quantities of lemons grown in California and Arizona which may be handled during the period beginning at 12:01 a.m., P.s.t., December 15, 1963, and ending at 12:01 a.m., P.s.t., December 22, 1963, are hereby fixed as follows:

(i) District 1: 27,900 cartons;

(ii) District 2: 116,250 cartons;

(iii) District 3: 69,750 cartons.

(2) As used in this section, "handled," "District 1," "District 2," "District 3," and "carton" have the same meaning as when used in the said amended marketing agreement and order.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 12, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–13014; Filed, Dec. 13, 1963; 8:49 a.m.]

PART 925—FRESH PRUNES GROWN IN DESIGNATED COUNTIES IN IDAHO AND IN MALHEUR COUNTY, OREGON

Determination Relative to Changing Fiscal Period

Notice was published in the November 15, 1963 issue of the FEDERAL REGISTER (28 F.R. 12167) that consideration is being given to the proposal regarding the changing of the fiscal period (July 1 through June 30) under the marketing agreement and Order No. 925 (7 CFR Part 925), regulating the handling of fresh prunes grown in designated counties in Idaho and in Malheur County, Oregon, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601, et seq.).

After consideration of all relevent matters presented, including the proposal set forth in the aforesaid notice which was presented by the Oregon Fresh Prune Mar'.eting Committee (established pursuant to the said marketing agreement and order), it is hereby found that the changing of the fiscal period, as hereinafter set forth, is in accordance with the provisions of the said marketing agreement and order and will tend to effectuate the declared policies of the Agricultural Marketing Agreement Act of 1937, as amended. Such change of the fiscal period is hereby approved; and said change is as follows:

§ 925.107 Change in fiscal period.

The fiscal period which began June 1, 1963, shall end June 30, 1964. Thereafter the fiscal period shall begin July 1 of each year and end June 30 of the following year.

It is hereby further found that good cause exists for not postponing the effective date of § 925.107 beyond the date of publication in the FEDERAL REGISTER in that: (1) No advance preparation for such effective date will be required of handlers for compliance therewith; (2) the changed fiscal period will tend to effectuate the declared policy of the act; and (3) no useful purpose would be served by postponing such effective date.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 11, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Agricultural Marketing Service.

[F.R. Doc. 63–12993; Filed, Dec. 13, 1963; 8:48 a.m.]

[945.322, Amdt. 1]

PART 945—IRISH POTATOES GROWN IN CERTAIN DESIGNATED COUNTIES IN IDAHO AND MALHEUR COUNTY, OREGON

Limitation of Shipments

Findings. (a) Pursuant to Marketing Agreement No. 98, and Order No. 945 (7 CFR Part 945), regulating the handling of Irish potatoes grown in the production area defined therein, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601 et seq.), and upon the basis of recommendations and information submitted by the Idaho-Eastern Oregon Potato Committee, established pursuant to the said marketing agreement and order, and other available information, it is hereby found that the amendment to the limitation of shipments regulations hereinafter established, limiting the grade and size of such potatoes will maintain orderly marketing conditions tending to increase returns to potato growers in the production area.

(b) It is hereby found that it is impracticable and contrary to the public interest to give preliminary notice, and engage in public rule making procedure, and that good cause exists for not postponing the effective date of this amendment until 30 days after publication in the FEDERAL REGISTER (5 U.S.C. 1003) in that (1) the time intervening between the date when information upon which this amendment is based became available and the time when this amendment must become effective in order to effectuate the declared policy of the act is insufficient; (2) more orderly marketing in the public interest, than would otherwise prevail, will be promoted by regulating the handling of potatoes, in the manner set forth below, (3) regulations have been issued under the order since 1948 and have been in effect this season since July 17, 1963, so compliance with this amendment will not require any special preparation on the part of handlers, and (4) information regarding the committee's recommendation has been disseminated to producers and handlers in the production area.

Order, as amended. Amend paragraph (a) of § 945.322 (28 F.R. 7212), to read:

§ 945.322 Limitation of shipments.

(a) Minimum quality requirements.—(1) *Grade:*

(i) *Round varieties.* U.S. No. 1, or better grade.

(ii) *Long varieties.* U.S. No. 2, or better grade.

(2) *Size*—(i) *Round varieties.* 2 inches minimum diameter.

(ii) *Long varieties.* 6 ounces minimum weight except that potatoes of U.S. No. 1, or better grade, may be shipped if they are 2 inches minimum diameter or 4 ounces minimum weight.

(3) *Cleanliness*—(i) *Kennebec variety.* Not more than "slightly dirty."

(ii) *All other varieties.* At least "generally fairly clean."

* * * * *

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601 et seq.)

Dated December 11, 1963, to become effective December 16, 1963.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division.

[F.R. Doc. 63–12991; Filed, Dec. 13, 1963; 8:47 a.m.]

PART 947—IRISH POTATOES GROWN IN MODOC AND SISKIYOU COUNTIES IN CALIFORNIA AND IN ALL COUNTIES IN OREGON EXCEPT MALHEUR COUNTY

Approval of Expenses and Rate of Assessment

Notice of rule making regarding proposed expenses and a proposed rate of assessment, to be effective under Marketing Agreement No. 114, and Order No. 947, both as amended (7 CFR Part 947), regulating the handling of Irish potatoes grown in Modoc and Siskiyou Counties in California and in all counties in Oregon except Malheur was published in the FEDERAL REGISTER October 31, 1963 (28 F.R. 11637). This regulatory program is effective under the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601–674). The notice afforded interested persons an opportunity to submit written data, views, or arguments pertaining thereto not later than 10 days following publication in the FEDERAL REGISTER. None was filed.

After consideration of all relevant matters presented, including the proposals set forth in the aforesaid notice which were recommended by the Oregon-California Potato Committee, established pursuant to said amended marketing agreement and order, it is hereby found and determined that:

§ 947.216 Expenses and rate of assessment.

(a) The reasonable expenses that are likely to be incurred by the Oregon-California Potato Committee, established pursuant to Marketing Agreement No. 114, and Order No. 947, both as amended, to enable such Committee to perform its functions under provisions of the amended marketing agreement and order during the fiscal period beginning July 1, 1963 and ending June 30, 1964, will amount to $21,800.00.

(b) The rate of assessment to be paid by each handler pursuant to Marketing Agreement No. 114 and Order No. 947, both as amended, shall be $0.003 per hundredweight of potatoes handled by him as the first handler thereof during said fiscal period.

(c) Terms used in this section have the same meaning as when used in the said amended marketing agreement and order.

It is hereby found that good cause exists for not postponing the effective time of this section until 30 days after publication in the FEDERAL REGISTER (5 U.S.C. 1003) in that: (1) The relevant provisions of said marketing agreement and this part require that rates of assessment fixed for a particular fiscal period shall be applicable to all assessable potatoes from the beginning of such period, and (2) the current fiscal period began on July 1, 1963, and the rate of assessment herein fixed will apply to all assessable potatoes beginning with such date.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 11, 1963.

PAUL A. NICHOLSON,
Deputy Director,
Fruit and Vegetable Division.

[F.R. Doc. 63–12992; Filed, Dec. 13, 1963; 8:47 a.m.]

PART 989—RAISINS PRODUCED FROM GRAPES GROWN IN CALIFORNIA

Subpart—Administrative Rules and Regulations

MISCELLANEOUS AMENDMENTS

The Raisin Administrative Committee has unanimously recommended an amendment of § 989.158(a) of the administrative rules and regulations, as amended (Subpart—Administrative Rules and Regulations; 7 CFR 989.101 to 989.176). The amendment would permit persons (mainly producers) tendering natural condition raisins to handlers to remove, during the inspection and certification process, certain defects from the raisins. The Committee is established under, and its recommendation is made pursuant to, the marketing agreement, as amended, and Order No. 989, as amended (7 CFR Part 989), regulating the handling of raisins produced from grapes grown in California. This marketing program is effective under the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601–674).

Subparagraph (3) of § 989.158(a) provides that natural condition raisins received by a handler shall, prior to acceptance, be inspected at the handler's inspection point during the unloading process. Handlers occasionally receive from tenderers some lots (as defined in § 989.104(a)(1)) of such raisins which contain a few wet boxes, or boxes with wet or high moisture content raisins in some areas of the individual boxes, especially along the edges or in the corners. Also, a few boxes may contain foreign material which can readily be removed, such as sandburs, puncture vine seed, Eucalyptus pods or leaves, rocks, and sticks. Under § 989.104(a)(4), all such raisins would, if the defects were not removed, become a separate lot or lots and certified as off-grade raisins. However, individual boxes of raisins off grade only due to such defects could, at times, be made to meet the minimum grade and condition standards by removing the wet bunches or foreign material, spreading the wet or high moisture content raisins among the other raisins in the same box so the moisture will equalize, dumping the raisins in a wet box into a dry box, or by a combination of such methods. Such actions can be, and often are, taken by the tenderers prior to delivery of the raisins to the handler. But occasionally boxes of raisins requiring such corrective action are not discovered by the producers prior to delivery and are detected by the inspector at the inspection point. If limited to a small number of boxes of a size which can be easily handled (e.g., not more than 10 or such lesser number of boxes that does not exceed five percent of the lot, and boxes which are not larger than sweat boxes), such action can be taken at the inspection point promptly, and quickly completed, during the inspection and certification process without causing undue delay. Allowing a tenderer to take this action at the handler's inspection point during such process should, of course, be with the handler's permission. It would afford producers an opportunity to eliminate the cost that would otherwise be incurred in removing the raisins from the inspection point, returning them thereto after reworking the raisins at the farm or elsewhere outside of the inspection point, and subjecting them to another inspection and certification as a new lot or lots.

Based on the recommendation of the Committee, the information submitted therewith, other available information, and the foregoing, it is hereby found that the amendment of § 989.158(a) to permit (to the extent hereinafter set forth in the amendment) persons tendering natural condition raisins to handlers to remove, during the inspection and certification process, certain specified defects from the raisins will tend to reduce costs to producers, and other tenderers, thereby increasing producers' overall return, and thus tend to effectuate the declared policy of the act.

Therefore, § 989.158(a) of Subpart—Administrative Rules and Regulations (7 CFR 989.101–989.176) is amended by the addition thereto of subparagraph (9) reading as follows:

§ 989.158 Natural condition raisins.

(a) * * *

(9) With respect to any lot (as defined in § 989.104(a)(1)) of natural condition raisins being received and inspected at a handler's inspection point pursuant to subparagraph (3) of this paragraph and notwithstanding separation of the meeting portion of the original lot from the failing portions thereof for the purposes of § 989.104 and subparagraph (4) of this paragraph, any tenderer may, when permitted by the handler and when notified by the inspector of defects during the inspection and certification process, and in accordance with the provisions of this subparagraph, perform any one or more of the following on an individual box basis: (i) Mix raisins within boxes containing raisins that are wet, or of high moisture content, in some areas of the box; (ii) dump raisins from wet boxes into dry boxes; (iii) remove wet raisins; or (iv) remove foreign material such as sandburs, puncture vine seed, Eucalyptus pods or leaves, rocks, and sticks. This authorization to the tenderer shall not extend to raisins in containers larger than sweat boxes; and the number of boxes in the original lot on which the aforesaid actions may be performed during such process shall not exceed ten, or five percent of the total number of containers in the lot, whichever is less. Where the percentage computation results in a fraction of a box and is less than ten boxes, it shall be rounded upward to the next number. The entire lot of raisins shall remain under surveillance of the inspector during such process. The actions of the tenderer shall be done without delay, take place at the unloading dock in the inspection point, or in the immediate area thereof, and be under observation of the inspector.

* * * * *

It is hereby found that it is impracticable, unnecessary, or contrary to the public interest to give preliminary notice and engage in public rule making procedure, and that good cause exists for making this amendment effective at the time hereinafter set forth and for not postponing the effective time until 30 days after publication in the FEDERAL REGISTER (5 U.S.C. 1003) in that: (1) This action relaxes restrictions on the inspection of raisins; (2) raisins of the 1963 production are now being received and inspected; and (3) this amendment should become effective promptly so that it will be applicable to as much of the 1963 production as practicable and thus tend to maximize the benefits derivable therefrom.

(Secs. 1–19, 48 Stat. 31, as amended; 7 U.S.C. 601–674)

Dated: December 10, 1963, to become effective upon publication in the FEDERAL REGISTER.

FLOYD F. HEDLUND,
Director,
Fruit and Vegetable Division.

[F.R. Doc. 63–12966; Filed, Dec. 13, 1963; 8:46 a.m.]

Title 9—ANIMALS AND ANIMAL PRODUCTS

Chapter I—Agricultural Research Service, Department of Agriculture

SUBCHAPTER C—INTERSTATE TRANSPORTATION OF ANIMALS AND POULTRY

PART 74—SCABIES IN SHEEP

Designation of Free, Infected and Eradication Areas

Pursuant to the provisions of sections 1 through 4 of the Act of March 3, 1905, as amended, sections 1 and 2 of the Act of February 2, 1903, as amended, and sections 4 through 7 of the Act of May 29, 1884, as amended (21 U.S.C. 111–113, 115, 117, 120, 121, 123–126), §§ 74.2 and 74.3 of Part 74, Subchapter C, Chapter I, Title 9, Code of Federal Regulations, as amended, are hereby amended to read, respectively, as follows:

§ 74.2 Designation of free and infected areas.

(a) Notice is hereby given that sheep in the following States, Territories, and District, or parts thereof as specified, are not known to be infected with scabies, and such States, Territories, District, and parts thereof, are hereby designated as free areas:

(1) Alabama, Alaska, Arizona, Arkansas, California, Colorado, Connecticut, Delaware, District of Columbia, Florida, Georgia, Hawaii, Idaho, Kansas, Louisiana, Maine, Maryland, Massachu-

setts, Michigan, Minnesota, Mississippi, Montana, Nevada, New Hampshire, New Jersey, New York, North Carolina, North Dakota, Oklahoma, Oregon, Pennsylvania, Puerto Rico, Rhode Island, South Carolina, South Dakota, Texas, Utah, Vermont, Virgin Islands of the United States, Virginia, Washington, Wisconsin, and Wyoming;

(2) The following counties in Nebraska: Arthur, Banner, Blaine, Brown, Chase, Cherry, Cheyenne, Deuel, Dundy, Garden, Grant, Hooker, Keith, Keya Paha, Kimball, Loup, Merrill, Perkins, Rock, Sheridan, Scotts Bluff, and Thomas;

(3) The following counties in Missouri: Jackson, Lafayette, Saline, Cooper, Moniteau, Cole, Osage, Gasconade, Franklin, St. Louis; and all counties in the State of Missouri lying south thereof;

(4) The following counties in Illinois: Madison, Bond, Clinton, Marion, Clay, Richland, and Lawrence; and all Counties in the State of Illinois lying south thereof:

(5) All counties in New Mexico except those portions of Lincoln County and Socorro County lying within the area bounded by a line beginning at a point on U.S. Highway No. 54 where said highway crosses the Lincoln-Torrance County line at the town of Corona, New Mexico; and thence, running in a westerly direction along the Lincoln-Torrance County line and the Socorro-Torrance County line to New Mexico State Highway No. 10; thence, running in a southerly and southeasterly direction along New Mexico Highway No. 10 to its intersection with U.S. Highway No. 54; thence, running in a southerly direction along U.S. Highway No. 54 to its intersection with U.S. Highway No. 380 at the town of Carrizozo, New Mexico; thence, running in a southeasterly direction along U.S. Highway No. 380 to its intersection with New Mexico State Highway No. 48 at the town of Capitan, New Mexico; thence, running in an easterly direction along New Mexico State Highway No. 48 to its intersection with the Lincoln-Chaves County line; thence, running northward along the Lincoln-Chaves County line and the Lincoln-De Baca County line to the northeastern corner of Lincoln County; thence, running westerly along the Lincoln-Guadalupe County line to its intersection with the Lincoln-Torrance County line; thence, running southerly along the Lincoln-Torrance County line to the southeast corner of Torrance County; thence, running westerly along the Lincoln-Torrance County line to the point of beginning at the town of Corona, New Mexico.

(b) Notice is hereby given also that sheep scabies exists in all States and Territories and parts of States not designated as free areas in paragraph (a) of this section, and they are hereby designated as infected areas.

§ 74.3 Designation of eradication areas.

(a) Notice is hereby given that sheep in the following States, or parts thereof as specified, are being handled systematically to eradicate scabies in sheep, and such States, and parts thereof, are hereby designated as eradication areas:

(1) Kentucky and Tennessee;

(2) All counties in Nebraska except Arthur, Banner, Blaine, Brown, Chase, Cherry, Cheyenne, Deuel, Dundy, Garden, Grant, Hooker, Keith, Keya Paha, Kimball, Loup, Morrill, Perkins, Rock, Sheridan, Scotts Bluff, and Thomas;

(3) The following counties in West Virginia: Berkeley, Fayette, Grant, Greenbrier, Hampshire, Hardy, Jefferson, Mercer, Mineral, Monroe, Morgan, Nicholas, Pendleton, Pocahontas, Raleigh, Randolph, Summers, Tucker, Upshur, and Webster;

(4) All counties in Missouri except Jackson, Lafayette, Saline, Cooper, Moniteau, Cole, Osage, Gasconade, Franklin, St. Louis; and all counties in the State of Missouri lying south thereof;

(5) All counties in Illinois except Madison, Bond, Clinton, Marion, Clay, Richland, and Lawrence; and all counties in the State of Illinois lying south thereof;

(6) The designated parts of the following counties in New Mexico: Those portions of Lincoln County and Socorro County lying within the area bounded by a line beginning at a point on U.S. Highway No. 54 where said highway crosses the Lincoln-Torrance County line at the town of Corona, New Mexico; and thence, running in a westerly direction along the Lincoln-Torrance County line and the Socorro-Torrance County line to New Mexico State Highway No. 10; thence, running in a southerly and southeasterly direction along New Mexico Highway No. 10 to its intersection with U.S. Highway No. 54; thence, running in a southerly direction along U.S. Highway No. 54 to its intersection with U.S. Highway No. 380 at the town of Carrizozo, New Mexico; thence, running in a southeasterly direction along U.S. Highway No. 380 to its intersection with New Mexico State Highway No. 48 at the town of Capitan, New Mexico; thence, running in an easterly direction along New Mexico State Highway No. 48 to its intersection with the Lincoln-Chaves County line; thence, running northward along the Lincoln-Chaves County line and the Lincoln-De Baca County line to the northeastern corner of Lincoln County; thence, running westerly along the Lincoln-Guadalupe County line to its intersection with the Lincoln-Torrance County line; thence, running southerly along the Lincoln-Torrance County line to the scutheast corner of Torrance County; thence, running westerly along the Lincoln-Torrance County line to the point of beginning at the town of Corona, New Mexico.

(Secs. 4–7, 23 Stat. 32, as amended, secs. 1, 2, 32 Stat. 791–792, as amended, secs. 1–4, 33 Stat. 1264, as amended, 1265, as amended; 21 U.S.C. 111–113, 115, 117, 120, 121, 123–126; 19 F.R. 74, as amended)

Effective date. The foregoing amendments shall become effective upon issuance.

The amendments add Hawaii County in the State of Hawaii to the list of free areas and delete such State from the list of infected and eradication areas as sheep scabies is no longer known to exist therein. The entire State of Hawaii has now been designated as a free area. Hereafter, the restrictions pertaining to the interstate movement of sheep from or into infected and eradication areas as contained in 9 CFR Part 74, as amended, will not apply to such State. However, the restrictions in said Part 74 pertaining to the interstate movement of sheep from or into free areas will apply thereto.

The amendments relieve certain restrictions presently imposed and must be made effective immediately to be of maximum benefit to persons subject to the restrictions which are relieved. Accordingly, under section 4 of the Administrative Procedure Act (5 U.S.C. 1003), it is found upon good cause that notice and other public procedure with respect to the amendments are impracticable and contrary to the public interest, and the amendments may be made effective less than 30 days after publication in the FEDERAL REGISTER.

Done at Washington, D.C., this 11th day of December 1963.

M. R. CLARKSON,
Acting Administrator,
Agricultural Research Service.

[F.R. Doc. 63–12995; Filed, Dec. 13, 1963; 8:48 a.m.]

Title 13—BUSINESS CREDIT AND ASSISTANCE

Chapter I—Small Business Administration

[Rev. 1]

PART 127—JOINT SET-ASIDES

Part 127 of Chapter I of Title 13 of the Code of Federal Regulations is revised to read as follows:

Sec.
127.15 Statutory provisions.
127.15–1 General.
127.15–2 Procedures for the set-aside of Government purchases.
127.15–3 Procedures for the set-aside of Government sales.
127.15–4 Participation of small business concerns in Government procurement and disposal program.

AUTHORITY: Section 15 of the Small Business Act, 72 Stat. 385.

§ 127.15 Statutory provisions.

SEC. 15. To effectuate the purposes of this Act, small business concerns within the meaning of this Act shall receive any award or contract or any part thereof, and be awarded any contract for the sale of Government property, as to which it is determined by the Administration and the contracting procurement or disposal agency (1) to be in the interest of maintaining or mobilizing the Nation's full productive capacity, (2) to be in the interest of war or national defense programs, (3) to be in the interest of assuring that a fair proportion of the total purchases and contracts for property and services for the Government are placed with small business concerns, or (4) to be in the interest of assuring that a fair proportion of the total sales of Government property be made to small business concerns; but nothing contained in this Act shall be construed to change any preferences or priorities established by law with respect to the sale of electrical power or other property by the

Government or any agency thereof. These determinations may be made for individual awards or contracts or for classes of awards or contracts. Whenever the Administration and the contracting procurement agency fail to agree, the matter shall be submitted for determination to the Secretary or the Head of the appropriate department or agency by the Administrator.

§ 127.15–1 General.

Set-asides are made by the Government for the purchase of property and services including, but not limited to, contracts for maintenance, repair, construction, research and development, and for the disposal of real and personal property, including timber, minerals and strategic materials.

§ 127.15–2 Procedures for the set-aside of Government purchases.

(a) *Government procurement set-asides.* (1) Under agreements with Federal agencies, representatives of SBA are assigned to the major Federal procurement installations to screen purchase requirements for possible small business set-asides. Set-asides are made in accordance with provisions set forth in the Armed Services Procurement Regulation (for Military agencies), and in the Federal Procurement Regulations (for civilian agencies of the Government). Pursuant to such regulations, the set-aside program operates as follows at installations to which SBA representatives are assigned:

(2) When a procurement or a class of procurements meets one or more of the statutory criteria and there are sufficient numbers of small business concerns considered capable of furnishing the property or services at fair and reasonable prices, SBA representatives recommend small business set-asides. Set-asides may be for entire procurements (called total set-asides) or for portions thereof (called partial set-asides). If the procurement officer does not agree to the set-asides, the SBA representative may carry the disagreement to the Head of the local installation. Where the SBA representative and the Head of the procurement installation disagree, the matter may be submitted by the Administrator of SBA to the Secretary or Head of the procuring department or agency for final determination.

(3) In a total set-aside, the entire procurement is restricted to small business concerns and bids or quotations by large firms are rejected as nonresponsive. It is SBA policy to request total set-asides when there is reasonable expectation that bids or proposals will be obtained from a sufficient number of responsible small business concerns so that awards will be made at reasonable prices.

(4) In a partial set-aside, only a portion of the procurement is restricted to small business concerns. It is SBA policy to request partial set-asides when (i) the procurement is not appropriate for total set-aside, (ii) the procurement is severable into two or more economic production runs or reasonable lots, and (iii) two or more small business concerns are expected to have the technical competency and productive capacity to furnish a severable portion of the item being purchased by the Government at a reasonable price. Where appropriate, partial set-asides will be requested when only one small concern is expected to have the technical competency and productive capacity to furnish a severable portion of the procurement and conditions in subdivisions (i) and (ii) of this subparagraph, are present. Insofar as practicable, the set-aside portion requested shall be such as to make the maximum use of small business capacity.

(b) *Withdrawal of set-asides.* If prior to award, the contracting officer considers that a jointly made set-aside would be detrimental to the public interest (e.g., because of unreasonable price), the contracting officer initiates a request to the SBA representatives for withdrawal of the joint set-aside. If the SBA representative does not agree to the proposed withdrawal, the representative may carry the disagreement to the Head of the procuring activity. If the SBA representative and the Head of the activity disagree, the matter may be appealed by the Administrator of SBA to the Secretary or Head of the department or agency whose decision is final.

(c) *Awards on procurements partially set aside.* (1) In partial set-asides involving Government procurement, negotiations for award of the set-aside portion are conducted by the purchasing officer with responsible small firms who submit responsive bids or proposals on the unreserved portion within 120 percent of the highest unit price awarded on the unreserved portion. Such negotiations are conducted with small business concerns in the following order of priority:

Group 1. Small business concerns which are also persistent surplus area concerns;

Group 2. Small business concerns which are also substantial labor surplus area concerns;

Group 3. Small business concerns which are not labor surplus area concerns. Within each of the groups, negotiations are in the order of the bids on the non-set-aside portion, beginning with the lowest responsive bid.

§ 127.15–3 Procedures for the set-aside of Government sales.

(a) *Property sales or disposal set-asides.* Under agreements with Federal agencies, SBA assigns representatives to cover major property sales and disposal installations in the regions to screen inventory or proposed sales of real, personal, and mixed property, including timber, minerals and strategic materials for possible set-asides.

(1) SBA representatives review includes cost factors and proposed sales methods for the purpose of assuring that a fair proportion of the property for sale or disposal is made available for purchase by small business firms, taking into consideration statutory or regulatory preferences and priorities. When SBA representatives determine that there is a sufficient number of small business firms capable of competing for the purchase of such property at fair and reasonable prices, the SBA representatives recommend small business set-asides. If the disposal officer does not agree to the set-asides, the SBA representative may avail himself of an appeal procedure similar to that described in § 127.15–2 (a)(2). Further, if the disposal officer initiates a request for withdrawal of the set-aside (e.g., because of unreasonable price or other reasons), the SBA representative shall use the appeal procedure referenced above if he does not agree after the matter has been discussed with the disposal officer's supervisor.

(2) Bids or quotations on any set-aside property by firms not qualifying as small business concerns, are rejected as nonresponsive.

§ 127.15–4 Participation by small business concerns in Government procurement or disposal programs.

Small business concerns desiring to avail themselves of the set-aside program should (a) determine which Government purchasing or disposal offices are most likely to buy items which they can supply or which disposal offices dispose of property which they desire to purchase, (b) request placement on the bidders lists maintained by such offices, and (c) bid competitively on these procurements and disposals. Information concerning counsel and guidance in connection with contracting with the Government, furnished by SBA, is set forth under § 124.8–4.

Dated: December 4, 1963.

EUGENE P. FOLEY,
Administrator.

[F.R. Doc. 63–12973; Filed, Dec. 13, 1963; 8:46 a.m.]

Title 19—CUSTOMS DUTIES

Chapter I—Bureau of Customs, Department of the Treasury

[T.D. 56066]

PART 6—AIR COMMERCE REGULATIONS

PART 8—LIABILITY FOR DUTIES; ENTRY OF IMPORTED MERCHANDISE

PART 10—ARTICLES CONDITIONALLY FREE, SUBJECT TO A REDUCED RATE, ETC.

Miscellaneous Amendments

The following technical changes in the Customs Regulations are required by the substitution of the Tariff Schedules of the United States for titles I and II of the Tariff Act of 1930, as amended, pursuant to the Tariff Classification Act of 1962 (76 Stat. 72).

§ 6.7 [Amended]

Section 6.7(g) is amended by substituting "item 812.25, Tariff Schedules

of the United States" for "paragraph 1798(b)(2) of such act" in the last sentence.

(R.S. 251, sec. 624, 46 Stat. 759, sec. 101, 76 Stat. 72; 19 U.S.C. 66, 1624; Gen. Hdnote. 11, Tariff Schedules of the United States)

§ 8.8 [Amended]

The fourth sentence of § 8.8(a) is amended to read: "The description of the merchandise shall be in terms of the Tariff Schedules of the United States Annotated, or in more specific terms which indicate clearly the tariff classification claimed by the importer.[10]".

Section 8.21(b) is amended to read:

§ 8.21 Estimation of duties; classification.

* * * * *

(b) The rates of duty at which the entry is passed and the appropriate item numbers of the Tariff Schedules of the United States shall be noted by the importer with black ink in the left-hand margin of the invoice. (Sec. 484, 46 Stat. 722, as amended; 19 U.S.C. 1484.)

(R.S. 251, sec. 624, 46 Stat. 759, sec. 101, 76 Stat. 72; 19 U.S.C. 66, 1624; Gen. Hdnote. 11, Tariff Schedules of the United States)

The section heading and paragraph (a) of § 10.17a are amended, and the citation of authority for § 10.17a is deleted.

§ 10.17a Temporary regulations applicable during the effective period of item 915.30, Tariff Schedules of the United States.

(a) *Reduced exemptions.* During the effective period of item 915.30, the $200 exemption permitted by item 813.31, Tariff Schedules of the United States is reduced to $100 with the exception of the exemption permitted to residents returning from the Virgin Islands (see paragraph (e) of this section). The additional $300 exemption permitted by item 813.32 of the said schedules is suspended during the effective period of item 915.30.

* * * * *

§ 10.31 [Amended]

Section 10.31(e) is amended by substituting "schedule 8, part 5C, Tariff Schedules of the United States" for "section 308" in the second sentence.

Section 10.31(f) is amended by substituting "item of schedule 8, part 5C, Tariff Schedules of the United States" for "subdivision of section 308" in the last sentence.

§ 10.53 [Amended]

Section 10.53(d) is amended by deleting "or enhancing its artistic quality" in the second sentence and by substituting "of a feature" for "of an artistic or other feature" in the fourth sentence.

The following citation of authority is added for § 10.53: (Sec. 481, 46 Stat. 719; 19 U.S.C. 1481).

(R.S. 251, sec. 624, 46 Stat. 759, sec. 101, 76 Stat. 72; 19 U.S.C. 66, 1624; Gen. Hdnote. 11, Tariff Schedules of the United States.)

[SEAL] PHILIP NICHOLS, Jr.,
Commissioner of Customs.

Approved: December 9, 1963.

JAMES A. REED,
Assistant Secretary of the Treasury.

[F.R. Doc. 63-12980; Filed, Dec. 13, 1963; 8:46 a.m.]

Title 18—CONSERVATION OF POWER

Chapter I—Federal Power Commission

[Docket No. R-252; Order No. 275]

PART 2—GENERAL POLICY AND INTERPRETATION

Area Price Levels for Sales of Natural Gas by Producers

DECEMBER 9, 1963.

The Commission's Statement of General Policy No. 61-1 issued September 28, 1960, announced a price level of 18 cents per Mcf for initial sales in Texas District No. 2 (at 14.65 psia). The Statement of Policy specified that the price levels announced therein were to be "adjusted from time to time as such facts as may come before us compel such adjustments." The price level previously announced for District No. 4 was in fact adjusted by the Fifth Amendment to the Statement of General Policy on August 30, 1962, 28 FPC 441 (27 F.R. 8918), and the price level for District No. 3 was adjusted by the Sixth Amendment dated March 27, 1963, 29 FPC 590 (28 F.R. 3203, 18 CFR 2.56).

The Commission in its Opinion No. 412 in the Hunt case issued this date has had occasion to re-examine the question of the in-line price in Texas District No. 2 immediately prior to September 28, 1960, in light of the subsequent court decisions dealing with the initial pricing question in producer certificate cases.

We have also reviewed the sales in District No. 2 subsequent to September 28, 1960. We have carefully re-examined the appropriate level of initial ceilings in this District in light of present conditions in the area giving due consideration to the applicable court decisions and the factors set forth in our original statement of policy.

Just as was the case in our revision of the ceiling prices in Texas Districts No. 3 and 4, our guiding purpose here is to arrive at a revised price which will enable the Commission to hold the line on new sales in this area at a level consistent with the public interest and, at the same time, to enable producers to obtain authorizations which provide them a reasonable basis for proceeding with their operations and furnishing needed supplies of gas. We conclude that, effective this date, the ceiling price level for initial sales in Texas District No. 2, inclusive of state taxes, shall be 16 cents per Mcf (at 14.65 psia). Accordingly—

The Commission finds:

(1) No notice or hearing is necessary under section 4(a) of the Administrative Procedure Act.

(2) In view of the purpose, intent and effect of the amendment herein ordered, good cause exists for making it effective forthwith.

The Commission, acting pursuant to authority granted by the Natural Gas Act, as amended, particularly sections 4, 5, and 16 thereof (52 Stat. 822, 823, 830, 15 U.S.C. 717c, 717d, 717o), orders:

(A) Effective upon the issuance of this order, the table in the note at the end of § 2.56, Part 2, Statements of General Policy and Interpretations, Chapter I of Title 18, Code of Federal Regulations, is amended by deleting the figure "18.0", the initial service rate for Texas District No. 2, and inserting "16.0" in lieu thereof.

(Secs. 4, 5, 16, 52 Stat. 822, 823, 830; 15 U.S.C. 717c, 717d, 717o)

(B) The Secretary shall cause prompt publication of this order to be made in the FEDERAL REGISTER.

By the Commission.[1]

[SEAL] GORDON M. GRANT,
Acting Secretary.

[F.R. Doc. 63-12958; Filed, Dec. 13, 1963; 8:45 a.m.]

Title 44—PUBLIC PROPERTY AND WORKS

Chapter I—General Services Administration

SUBCHAPTER F—TRANSPORTATION, COMMUNICATIONS, AND PUBLIC UTILITIES MANAGEMENT

[GSA Reg. 2-IX-101.01—401.05]

PART 184—TELECOMMUNICATIONS SERVICES

Utilization by Executive Agencies Within the United States and Its Insular Possessions

Correction

In F.R. Doc. 63-12964, appearing at page 13451 of the issue for Thursday, December 12, 1963, the following corrections are made:

1. In § 184.7, the phrase "least circuit facilities" should read "leased circuit facilities".

2. In § 184.22(a)(8), the phrase "Centerex telephone service" should read "Centrex telephone service".

[1] Concurring statement of Commissioner Ross and dissenting statements of Commissioners O'Connor and Woodward filed as part or original document.

Proposed Rule Making

DEPARTMENT OF THE INTERIOR

Bureau of Indian Affairs

[25 CFR Parts 21, 22, 31, 32]

EDUCATION AND SOCIAL WELFARE

Aid and Grants to Indians

Basis and purpose. Notice is hereby given that pursuant to the authority vested in the Secretary of the Interior by the Acts of February 14, 1920 (41 Stat. 410; 25 U.S.C. 282); June 18, 1934 (48 Stat. 986; 25 U.S.C. 471); April 16, 1934 (48 Stat. 596, as amended; 25 U.S.C. 454); and by section 161 of the Revised Statutes (5 U.S.C. 22), it is proposed to amend 25 CFR Parts 21, 22, 31, and 32 as set forth below. The purpose of this amendment is to define further eligibility for social welfare and for educational services.

It is the policy of the Department of the Interior, whenever practicable, to afford the public an opportunity to participate in the rule making process. Accordingly, interested persons may submit written comments, suggestions, or objections with respect to the proposed amendment to the Bureau of Indian Affairs, Washington 25, D.C., within thirty days of the date of publication of this notice in the FEDERAL REGISTER.

1. Section 21.1 is amended to read as follows:

§ 21.1 Commissioner to negotiate contracts.

The Commissioner of Indian Affairs may negotiate with State, territory, county or other Federal welfare agencies for such agencies to provide welfare services as contemplated by the Act of June 4, 1936 (49 Stat. 1458; 25 U.S.C. 452), for Indians residing within a particular State within the exterior boundaries of Indian reservations under the jurisdiction of the Bureau of Indian Affairs or on trust or restricted lands under the jurisdiction of the Bureau of Indian Affairs.

2. Section 22.3 is amended to read as follows:

§ 22.3 Contracts dependent on need and desire of Indians.

Contracts will be considered only in behalf of children from localities where there are a sufficient number of Indian children requiring this kind of service who reside within the exterior boundaries of Indian reservations under the jurisdiction of the Bureau of Indian Affairs or on trust or restricted lands under the jurisdiction of the Bureau of Indian Affairs, and the Commissioner of Indian Affairs reserves the right to investigate the need and take into consideration the desires of the Indian parents of such children as formally expressed by them.

3. Section 31.1 is amended to read as follows:

§ 31.1 Enrollment in Federal schools.

(a) Enrollment in Bureau-operated boarding schools is available to children of one-fourth or more degree of Indian blood who reside within the exterior boundaries of Indian reservations under the jurisdiction of the Bureau of Indian Affairs or on trust or restricted lands under the jurisdiction of the Bureau of Indian Affairs when there are no other appropriate school facilities available to them or when they are from broken or unsuitable homes. Enrollment may be available also to children of one-fourth or more degree of Indian blood who reside near the reservation when a denial of such enrollment would have a direct effect upon Bureau programs within the reservation.

(b) Enrollment in Bureau operated day schools is available to children of one-fourth or more degree of Indian blood who reside within the exterior boundaries of Indian reservations under the jurisdiction of the Bureau of Indian Affairs or on trust or restricted lands under the jurisdiction of the Bureau.

4. Section 31.3 is amended to read as follows:

§ 31.3 Non-Indian pupils in Indian schools.

Indian and non-Indian children who are not eligible for enrollment in Bureau operated schools under § 31.1 may be enrolled in such schools under the following conditions:

(a) In boarding schools upon payment of tuition fees, which shall not exceed the per capita cost of maintenance in the school attended, when their presence will not exclude Indian pupils eligible under § 31.1 (35 Stat. 783; 25 U.S.C. 289.)

(b) In day schools in areas where there are no other adequate free school facilities available, tuition fees may be charged for such enrollment at the discretion of the superintendent or other officer in charge provided such fees shall not exceed the tuition fees allowed or charged by the State or county in which such school is located for the children admitted in the public schools of such State or county. (34 Stat. 1018; 40 Stat. 564, 25 U.S.C. 288, 297.)

5. Section 32.1 is amended to read as follows:

§ 32.1 Appropriations for loans or grants.

Funds appropriated by Congress for the education of Indians may be used for making educational loans and grants to aid students of one-fourth or more degree of Indian blood seeking higher education or special training who reside within the exterior boundaries of Indian reservations under the jurisdiction of the Bureau of Indian Affairs or on trust or restricted lands under the jurisdiction of the Bureau of Indian Affairs. Educational loans and grants may be made also to children of one-fourth or more degree of Indian blood who reside near the reservation when a denial of such loans or grants would have a direct effect upon Bureau programs within the reservation. Funds appropriated for nonreimbursable grants may not be used to aid students attending sectarian schools (Act of March 2, 1917; 39 Stat. 988).

JOHN A. CARVER, JR.,
Assistant Secretary of the Interior.

DECEMBER 10, 1963.

[F.R. Doc. 63-12959; Filed, Dec. 13, 1963; 8:45 a.m.]

DEPARTMENT OF THE TREASURY

Bureau of Customs

[19 CFR Part 1]

CUSTOMS DISTRICTS, PORTS, AND STATIONS

Proposed Change in Area of Port of Niagara Falls, New York

DECEMBER 7, 1963.

Recently, a regular and recurring need for customs service has developed at several transportation facilities which, although near the port of Niagara Falls, New York, are nevertheless outside the existing port boundaries. The conduct of customs business can be more expeditiously and efficiently performed by extending the existing port boundaries to include these transportation facilities.

Accordingly, notice is hereby given pursuant to section 4 of the Administrative Procedure Act (5 U.S.C. 1003) that under the authority vested in the President by section 1 of the Act of August 1, 1914, 38 Stat. 623 (19 U.S.C. 2), which was delegated to the Secretary of the Treasury by the President by Executive Order No. 10289, September 17, 1951 (3 CFR Ch. II), and pursuant to authorization given to me by Treasury Department Order No. 190, Rev. 2 (28 F.R. 11570), it is proposed that the limits of the customs port of entry of Niagara Falls, New York, in Customs Collection District No. 9 (Buffalo), comprising the territory within the corporate limits of Niagara Falls and Lewiston, New York (T.D. 43982), be extended to include the customs inspection station located on interstate Route 190 where this highway crosses the Niagara River over the Lewiston Bridge in Lewiston township, all the territory within the boundaries of Niagara township, and that part of Wheatfield township which lies within the boundaries of the Niagara Falls Municipal Airport. All of the aforementioned townships are located within Niagara County, New York. It is further

proposed to amend § 1.1(c) of the Customs Regulations to reflect this change.

Data, views, or arguments regarding this proposed change may be addressed in writing to the Commissioner of Customs, Washington, D.C., 20226. To assure consideration of such communications, they must be received by the Commissioner of Customs not later than 30 days from the date of publication of this notice in the FEDERAL REGISTER. No hearings will be held (FM 192–9.1 S).

[SEAL] JAMES A. REED,
Assistant Secretary of the Treasury.

[F.R. Doc. 63–12978; Filed, Dec. 13, 1963; 8:46 a.m.]

DEPARTMENT OF AGRICULTURE

Agricultural Research Service

[9 CFR Part 74]

SCABIES IN SHEEP

Notice of Proposed Amendment

Notice is hereby given in accordance with section 4 of the Administrative Procedure Act (5 U.S.C. 1003) that, pursuant to the provisions of the Act of May 29, 1884, as amended, the Act of February 2, 1903, as amended, and the Act of March 3, 1905, as amended (21 U.S.C. 111–113, 115, 117, 120, 121, 123–126), it is proposed to amend § 74.3(a) of Part 74, Subchapter C, Chapter I, Title 9, Code of Federal Regulations, by adding the counties of Barbour, Boone, Braxton, Brooke, Cabell, Calhoun, Clay, Doddridge, Gilmer, Hancock, Harrison, Jackson, Kanawha, Lewis, Lincoln, Logan, Marion, Marshall, Mason, McDowell, Mingo, Monongalia, Ohio, Pleasants, Preston, Putnam, Ritchie, Roane, Taylor, Tyler, Wayne, Wetzel, Wirt, Wood, and Wyoming, in West Virginia, to the list of areas therein designated as eradication areas since the cooperative sheep scabies eradication program is now being conducted in such counties. The entire State of West Virginia is presently included in the infected areas as sheep scabies is known to exist in such State.

Any person who wishes to submit written data, views, or arguments concerning the proposed amendment may do so by filing them with the Director, Animal Disease Eradication Division, Agricultural Research Service, United States Department of Agriculture, Washington 25, D.C., within 30 days after publication of this notice in the FEDERAL REGISTER.

Done at Washington, D.C., this 11th day of December 1963.

M. R. CLARKSON,
Acting Administrator,
Agricultural Research Service.

[F.R. Doc. 63–12994; Filed, Dec. 13, 1963; 8:48 a.m.]

FEDERAL AVIATION AGENCY

[14 CFR Part 514]

[Reg. Docket No. 1943; Notice No. 63–36A]

AIRBORNE VOR RECEIVING EQUIPMENT (FOR AIR CARRIER AIRCRAFT)—TSO–C40b

Extension of Time for Filing of Comments

In the notice of proposed rule making on TSO–C40b airborne VOR receiving equipment (for air carrier aircraft), Notice No. 63–36, published in the FEDERAL REGISTER on September 13, 1963 (28 F.R. 9957), it was stated that consideration would be given to all relevant comments received on or before December 30, 1963.

It has subsequently been determined that the proposed standard for TSO–C40b was not readily available on the date that the proposal was published in the FEDERAL REGISTER. For this reason, the specified comment date of December 30, 1963, may not afford interested persons sufficient time within which to submit their comments.

Therefore, pursuant to the authority delegated to me by the Administrator (14 CFR 11.45), the time within which comments on proposed TSO–C40b (Notice 63–36) will be received is extended to January 31, 1964.

Communications should be submitted in duplicate to the Docket Section of the Federal Aviation Agency, Office of the General Counsel: Attention Rules Docket, 800 Independence Avenue SW., Washington D.C., 20553. All comments submitted will be available, both during and after the comment period, in the Docket Section for examination by interested persons.

Issued in Washington, D.C., on December 6, 1963.

G. S. MOORE,
Director,
Flight Standards Service.

[F.R. Doc. 63–12954; Filed, Dec. 13, 1963; 8:45 a.m.]

FEDERAL HOME LOAN BANK BOARD

[12 CFR Part 523]

[No. 17,586]

MEMBERS OF BANKS

Stock Subscription

DECEMBER 10, 1963.

Resolved that, pursuant to Part 508 of the General Regulations of the Federal Home Loan Bank Board (12 CFR Part 508), it is hereby proposed that § 523.5 of the regulations for the Federal Home Loan Bank System be amended by an amendment the substance of which is as follows:

Section 523.5 is hereby amended to read as follows:

§ 523.5 Minimum stock subscription.

As of the close of each calendar year, the Bank shall ascertain from the report required by § 523.15, or by such other means as may be appropriate, if an additional subscription to capital stock is required of any member, in order to comply with the act, and the Bank shall notify the member of any additional requirement.

(Sec. 17, 47 Stat. 736, as amended; 12 U.S.C. 1437. Reorg. Plan No. 3 of 1947, 12 F.R. 4981, 3 CFR, 1947 Supp.)

Resolved further that all interested persons are hereby given the opportunity to submit written data, views, or arguments on the following subjects and issues: (1) Whether said proposed amendment should be adopted as proposed; (2) whether said proposed amendment should be modified and adopted as modified; (3) whether said proposed amendment should be rejected. All such written data, views, or arguments must be received through the mail or otherwise at the office of the Secretary, Federal Home Loan Bank Board, Federal Home Loan Bank Board Building, 101 Indiana Avenue NW., Washington, D.C., 20552, not later than January 14, 1964, to be entitled to be considered, but any received later may be considered in the discretion of the Federal Home Loan Bank Board.

By the Federal Home Loan Bank Board.

[SEAL] HARRY W. CAULSEN,
Secretary.

[F.R. Doc. 63–12968; Filed, Dec. 13, 1963; 8:46 a.m.]

Notices

DEPARTMENT OF STATE

[Public Notice 221]

CERTIFICATION OF CERTAIN TRADEMARKS VESTED DURING WORLD WAR II

Correction

In F.R. Doc. 63–8550, appearing in the issue for Friday, August 9, 1963, at page 8219, the following material was inadvertently omitted from the list of trademarks:

314,070	Zeiss-Ikon AG, Stuttgart
316,882	Fabrik fur Metallpuliver-Werkstoffe Vogt & Co. Mbh, Erlau ub. Passau
323,118	Zeiss-Ikon AG, Stuttgart
323,929	Zeiss-Ikon AG, Stuttgart
330,379	Firma Carl Zeiss, Heidenheim/Brenz
330,380	Firma Carl Zeiss, Heidenheim/Brenz
330,381	Firma Carl Zeiss, Heidenheim/Brenz
333,696	Chem. Fabrik Grunau GmbH, Illertissen/Bayern
336,280	Firma Carl Zeiss, Heidenheim/Brenz
340,754	Firma Carl Zeiss Heidenheim/Brenz
343,030	Firma Carl Zeiss, Heidenheim/Brenz
343,122	Firma Carl Zeiss, Heidenheim/Brenz
343,763	Firma Carl Zeiss, Heidenheim/Brenz
345,398	Firma Carl Zeiss, Heidenheim/Brenz
346,260	Firma Carl Zeiss, Heidenheim/Brenz
352,143	Firma Carl Zeiss, Heidenheim/Brenz
352,708	Firma Carl Zeiss, Heidenheim/Brenz
362,050	Firma Carl Zeiss, Heidenheim/Brenz
392,746	Firma Carl Zeiss, Heidenheim/Brenz
350,114	Firma Carl Zeiss, Heidenheim/Brenz
392,716	Firma Carl Zeiss, Heidenheim/Brenz

DEPARTMENT OF THE TREASURY

Bureau of Customs

[Customs Delegation Order No: 19 [Amdt. 1]]

COMMISSIONER OF CUSTOMS

Order of Succession

[T.D. 56067]

DECEMBER 10, 1963.

Under the authority conferred upon me by Treasury Department Order No. 129, Revision No. 2, dated April 22, 1955, it is hereby ordered that the following officers of Customs, in the order of succession enumerated, shall act as Commissioner of Customs during the absence or disability of the Commissioner of Customs, or when there is a vacancy in such office:

1. The Assistant Commissioner of Customs;
2. The Deputy Commissioner of Customs for Investigations and Enforcement;
3. The Deputy Commissioner of Customs for Management and Controls;
4. The Deputy Commissioner of Customs for Appraisement Administration;
5. The Deputy Commissioner of Customs, Division of Classification and Drawbacks;
6. The Deputy Commissioner of Customs, Division of Entry, Value, and Penalties;
7. The Deputy Commissioner of Customs, Division of Marine Administration;
8. The Collector of Customs, Wilmington, North Carolina;
9. The Assistant Collector of Customs, Wilmington, North Carolina.

It is hereby further ordered that the Deputy Commissioner for Investigations and Enforcement shall act as Assistant Commissioner of Customs during the absence of the Assistant Commissioner of Customs or when there is a vacancy in such office.

[SEAL] PHILIP NICHOLS, JR.,
Commissioner of Customs.

[F.R. Doc. 63–12979; Filed, Dec. 13, 1963; 8:46 a.m.]

Comptroller of the Currency

BIRMINGHAM TRUST NATIONAL BANK AND BANK FOR SAVINGS AND TRUSTS

Decision Granting Application to Consolidate

On August 6, 1963, Birmingham Trust National Bank, Birmingham, Alabama, and the Bank for Savings and Trusts, Birmingham, Alabama, applied to the Comptroller of the Currency for permission to consolidate under the charter and with the title of the former.

On December 5, 1963, the Comptroller of the Currency granted this application.

Copies of this decision are available on request to the Comptroller of the Currency, Washington 25, D.C.

Dated: December 10, 1963.

[SEAL] A. J. FAULSTICH,
Administrative Assistant to the Comptroller of the Currency.

[F.R. Doc. 63–12974; Filed, Dec. 13, 1963; 8:46 a.m.]

LANCASTER COUNTY NATIONAL BANK AND FARMERS BANK AND TRUST COMPANY OF LANCASTER

Decision Granting Application to Consolidate

On September 19, 1963, the Lancaster County National Bank, Lancaster, Pennsylvania, and Farmers Bank and Trust Company of Lancaster, Lancaster, Pennsylvania, applied to the Comptroller of the Currency for permission to consolidate under the charter of the former and with the title "Lancaster County Farmers National Bank".

On December 6, 1963, the Comptroller of the Currency granted this application.

Copies of this decision are available on request to the Comptroller of the Currency, Washington 25, D.C.

Dated: December 10, 1963.

[SEAL] A. J. FAULSTICH,
Administrative Assistant to the Comptroller of the Currency.

[F.R. Doc. 63–12975; Filed, Dec. 13, 1963; 8:46 a.m.]

VIRGINIA NATIONAL BANK AND MERCHANTS BANK OF STAUNTON

Decision Granting Application To Merge

On September 19, 1963, the $366 million Virginia National Bank, Norfolk, Virginia, and the $5 million Farmers and Merchants Bank of Staunton, Staunton, Virginia, applied to the Comptroller of the Currency for permission to merge under the charter and with the title of the former.

On December 4, 1963, the Comptroller of the Currency granted this application.

Copies of this decision are available on request to the Comptroller of the Currency, Washington 25, D.C.

Dated: December 10, 1963.

[SEAL] A. J. FAULSTICH,
Administrative Assistant to the Comptroller of the Currency.

[F.R. Doc. 63–12976; Filed, Dec. 13, 1963; 8:46 a.m.]

VIRGINIA NATIONAL BANK AND TIDEWATER BANK AND TRUST CO.

Decision Granting Application to Merge

On September 19, 1963, the $366 million Virginia National Bank, Norfolk, Virginia, and the $17 million Tidewater Bank and Trust Company, Franklin, Virginia, applied to the Comptroller of the Currency for permission to merge under the charter and with the title of the former.

On December 4, 1963, the Comptroller of the Currency granted this application.

Copies of this decision are available on request to the Comptroller of the Currency, Washington 25, D.C.

Dated: December 10, 1963.

[SEAL] A. J. FAULSTICH,
Administrative Assistant to the Comptroller of the Currency.

[F.R. Doc. 63–12977; Filed, Dec. 13, 1963; 8:46 a.m.]

DEPARTMENT OF THE INTERIOR

National Park Service

[Order No. 3, Amdt. 11]

SUPERINTENDENTS ET AL.

Amendment of Delegation of Authority Regarding Approval of Plans and Drawings

1. Paragraph (f) of section 1 of Order No. 3, issued February 17, 1956 (21 F.R. 1494) is amended to read as follows:

(f) Approval of preliminary construction plans and working drawings not preceded by a preliminary drawing, not requiring approval by the Director, and

preliminary and final concessioners' drawings.

2. Paragraph (g) of section 2 of Order No. 3 is amended to read as follows:

(g) Approval of preliminary construction plans and working drawings not preceded by a preliminary drawing, not requiring approval by the Director, and preliminary and final concessioners' drawings.

3. Paragraph (m) of section 3 of Order No. 3 is amended to read as follows:

(m) Approval of preliminary construction plans and working drawings not preceded by a preliminary drawing, not requiring approval by the Director, and preliminary and final concessioners' drawings.

(National Park Service Order No. 14 (19 F.R. 8824), as amended; 39 Stat. 535; 16 U.S.C., sec. 2; Midwest Region Order No. 3 (21 F.R. 1494))

Dated: November 18, 1963.

HOWARD W. BAKER,
Regional Director,
Midwest Region.

[F.R. Doc. 63-12963; Filed, Dec. 13, 1963; 8:45 a.m.]

DEPARTMENT OF AGRICULTURE

Commodity Credit Corporation

JUTE BAGGING AND BALE TIES USED IN WRAPPING COTTON

Proposed Specifications

Notice is hereby given that the Secretary of Agriculture is considering the establishment of minimum specifications for jute bagging and bale ties used in wrapping cotton tendered to Commodity Credit Corporation under the cotton price support program. It is proposed that the specifications for such bagging and ties first become effective with respect to cotton of the 1965 crop.

STATEMENT OF CONSIDERATIONS LEADING TO THE PROPOSED ESTABLISHMENT OF SPECIFICATIONS

The present methods of packaging and handling American cotton result in sizeable economic losses each year and are subject to adverse criticism in the markets of the world. The packaging of American cotton has never been entirely satisfactory from the standpoint of the protection afforded the cotton against loss and damage, and American bales have long been criticized in both domestic and export markets for their unsightly appearance. The increasing competition that American cotton must now meet in the export trade has greatly increased the need for improving the packaging and appearance of American cotton, particularly since many other cotton-producing countries do a much better and neater job of packaging their cotton than the United States. Since larger quantities and a greater range of types and qualities of man-made fibers have become available, an improved cotton bale package has become increasingly important.

In recent years, there has been general agreement that positive steps should be taken to improve the American bale package. In addition to the bagging and ties in which the bale is wrapped, there are other factors, such as sampling and handling practices, which affect the bale package. However, improved bale covering material and a certain degree of uniformity in the wrapping material used are necessary to provide a base from which other improvements can be made.

CCC now has large quantities of cotton in its inventories, and much of the cotton tendered for price support may remain in storage for extended periods. Thus, it is extremely important that this cotton be wrapped in bagging which will fully protect the cotton in order to minimize losses to CCC on disposition of the cotton.

The proposed specifications will result in the use of close-woven bale covering materials which will better protect the cotton.

PROPOSED SPECIFICATIONS FOR JUTE BAGGING AND BALE TIES

When cotton tendered to Commodity Credit Corporation for price support is wrapped in jute bagging, the bagging must be new material manufactured specifically for cotton bale covering and must meet the following specifications:

PHYSICAL REQUIREMENTS FOR JUTE BAGGING

Length: 108 inches minimum for flat bales. 96 inches minimum for gin standard density bales. 112 inches maximum for flat or gin standard density bales.

Weight: 32 ounces per running yard of bagging (plus or minus 1½ ounces) at 13.75% moisture content. Bagging which is not more than 4 ounces per running yard heavier than this prescribed weight may be used for gin standard density bales if the bagging is 96 inches but not to exceed 100 inches in length.

Width: 48 inches minimum, 50 inches maximum.

Weft (filling) Yarns: Minimum size of 40 pounds per spyndle (14,400 yards).

Warp Yarns: Equal to or larger than weft yarns but not less than 75 pounds per spyndle.

Number of Warp Yarns: Minimum of 41 per 12 inches.

Number of Weft (filling) Yarns: Minimum of 25 per 12 inches.

Cotton wrapped in second-hand or used jute bagging or in salvage burlap sack material will not be eligible for tender to Commodity Credit Corporation.

BALE TIES AND BUCKLES

The total weight of bale ties and buckles shall be 9 pounds per bale plus or minus one-half pound.

SUBMISSION OF VIEWS

Prior to making any determination regarding specifications for jute bagging and bale ties, consideration will be given to any data, views, and recommendations which are submitted in writing to the Director, Policy and Program Appraisal Division, Agricultural Stabilization and Conservation Service, U.S. Department of Agriculture, Washington, D.C., 20250, by January 3, 1964.

Signed at Washington, D.C., on December 10, 1963.

H. D. GODFREY,
Executive Vice President,
Commodity Credit Corporation.

[F.R. Doc. 63-12996; Filed, Dec. 13, 1963; 8:48 a.m.]

DEPARTMENT OF COMMERCE

Bureau of International Commerce

[File No. 23-930]

JOSEF CREMER

Order Temporarily Denying Export Privileges

In the matter of Josef Cremer trading as J. Cremer Export-Import, Prinz Eugen Strasse 4, Vienna IV, Austria, File No. 23-930; respondent.

The Export Control Investigations Division, Bureau of International Commerce, United States Department of Commerce, pursuant to the provisions of § 382.11 of the Export Regulations (Title 15, Chapter III, Sub-chapter B, Code of Federal Regulations), has applied to the Compliance Commissioner for an order temporarily denying all export privileges to the above named respondent. It was requested that the order remain in effect pending continued investigation into the facts and transactions giving rise to the application and the commencement of such proceedings, as may be deemed proper under the law, against said respondent.

The Compliance Commissioner has reviewed the application and the evidence presented in support thereof and has submitted his report, together with his recommendation that the application be granted and that a temporary denial order be issued for ninety days.

The evidence and recommendation of the Compliance Commissioner have been considered. The evidence presented shows that Josef Cremer, trading as J. Cremer Export-Import, is in the export-import business and has a place of business in Vienna, Austria. There is substantial basis to believe: that the respondent has been engaged in obtaining commodities of U.S. origin, some of strategic nature, and diverting, transshipping and reexporting such commodities to destinations in contravention of the U.S. Export Control Act and regulations thereunder; that he has caused, aided, induced and procured the doing of acts prohibited by said Act and regulations; that he has acted in concert with others to bring about violations of said Act and regulations; and that he will continue such conduct in contravention of said Act and regulations unless U.S. export privileges are temporarily denied. I find that an order temporarily denying export privileges to the respondent is reasonably necessary for the protection of the public interest and national security.

Accordingly, it is hereby ordered:

I. All outstanding validated export licenses in which respondent appears or

participates in any manner or capacity are hereby revoked and shall be returned forthwith to the Bureau of International Commerce for cancellation.

II. The respondent, his successors or assigns, partners, representatives, agents, and employees hereby are denied all privileges of participating, directly or indirectly, in any manner or capacity, in any transaction involving commodities or technical data exported from the United States in whole or in part, or to be exported, or which are otherwise subject to the Export Regulations. Without limitation of generality of the foregoing, participation prohibited in any such transaction, either in the U.S. or abroad, shall include participation, directly or indirectly, in any manner or capacity, (a) as a party or as a representative of a party to any validated export license application, (b) in the preparation or filing of any export license application or reexportation authorization, or any document to be submitted therewith, (c) in the obtaining or using of any validated or general export license or other export control document, (d) in the carrying on of negotiations with respect to, or in the receiving, ordering, buying, selling, delivering, storing, using, or disposing of any commodities or technical data in whole or in part exported or to be exported from the United States, and (e) in the financing, forwarding, transporting, or other servicing of such commodities or technical data.

III. Such denial of export privileges shall extend not only to the respondent, but also to his agents and employees and to any successor and to any person, firm, corporation, or business organization with which they now or hereafter may be related by affiliation, ownership, control, position of responsibility, or other connection in the conduct of trade or services connected therewith.

IV. This order shall take effect forthwith and shall remain in effect for a period of ninety days from the date hereof, unless it is hereafter extended, amended, modified, or vacated in accordance with the provisions of the United States Export Control Regulations.

V. No person, firm, corporation, partnership or other business organization, whether in the United States or elsewhere, without prior disclosure to and specific authorization from the Bureau of International Commerce, shall do any of the following acts, directly or indirectly, or carry on negotiations with respect thereto, in any manner or capacity, on behalf of or in any association with the respondent or any related party, or whereby the respondent or related party may obtain any benefit therefrom or have any interest or participation therein, directly or indirectly: (a) Apply for, obtain, transfer, or use any license, shipper's export declaration, bill of lading, or other export control document relating to any exportation, reexportation, transshipment, or diversion of any commodity or technical data exported or to be exported from the United States, by, to, or for any such respondent or related party denied export privileges; or (b) order, buy, receive, use, sell, deliver, store, dispose of, forward, transport, finance, or otherwise service or participate in any exportation, reexportation, transshipment, or diversion of any commodity or technical data exported or to be exported from the United States.

VI. A copy of this order shall be served upon the respondent.

VII. In accordance with the provisions of § 382.11(c) of the Export Regulations, the respondent may move at any time to vacate or modify this temporary denial order by filing an appropriate motion therefor, supported by evidence, with the Compliance Commissioner and may request an oral hearing thereon which, if requested, shall be held before the Compliance Commissioner in Washington, D.C., at the earliest convenient date.

Dated: December 10, 1963.

FORREST D. HOCKERSMITH,
Director, Office of Export Control.

[F.R. Doc. 63-12971; Filed, Dec. 13, 1963; 8:46 a.m.]

[File No. 23-917]

OMNIA K. G. KRAUS ET AL.

Order Extending Temporary Denial of Export Privileges

In the matter of Omnia K. G. Kraus, Weiss and Company and Friederich Ziffer, 30a Hanauer Strasse, Munich 54, Federal Republic of Germany, File No. 23-917; respondents.

An order temporarily denying export privileges for a period of sixty days was issued in the above matter on October 8, 1963 (28 F.R. 10927). Said order was issued in connection with an investigation instituted by the Export Control Investigations Division, Bureau of International Commerce, into activities of respondents in obtaining commodities of U.S. origin, and diverting and transshipping said commodities to destinations in contravention of the United States Export Control Act and regulations thereunder.

The Director of said Investigations Division has applied under § 382.11 of the Export Regulations for an extension of the temporary order and has represented that a charging letter is to be issued against said respondents in the near future.

The matter has been considered by the Compliance Commissioner, and he has reported his recommendation to me that the present temporary order be extended until the completion of administrative compliance proceedings to be instituted against said respondents, and that such extension will be in the public interest and is necessary for the effective enforcement of the law. I do so find.

Accordingly, it is hereby ordered:

I. The provisions and restrictions of the temporary denial order issued against the above respondents on October 8, 1963 (28 F.R. 10927) are hereby continued in full force and effect.

II. The respondents, their successors or assigns, officers, partners, representatives, agents, and employees hereby are denied all privileges of participating, directly or indirectly, in any manner or capacity, in any transaction involving commodities or technical data exported from the United States in whole or in part, or to be exported, or which are otherwise subject to the Export Regulations. Without limitation of generality of the foregoing, participation prohibited in any such transaction, either in the U.S. or abroad shall include participation, directly or indirectly, in any manner or capacity, (a) as parties or as representatives of a party to any validated export license application, (b) in the preparation or filing of any export license application or reexportation authorization, or any document to be submitted therewith, (c) in the obtaining or using of any validated or general export license or other export control document, (d) in the carrying on of negotiations with respect to, or in the receiving, ordering, buying, selling, delivering, storing, using, or disposing of any commodities or technical data in whole or in part exported or to be exported from the United States, and (e) in the financing, forwarding, transporting, or other servicing of such commodities or technical data.

III. Such denial of export privileges shall extend not only to the respondents, but also to their agents and employees and to any successor and to any person, firm, corporation, or business organization with which they now or hereafter may be related by affiliation, ownership, control, position of responsibility, or other connection in the conduct of trade or services connected therewith.

IV. This order supersedes the temporary denial order of October 8, 1963 and shall take effect forthwith and shall remain in effect until the completion of administrative compliance proceedings, unless amended, modified or vacated in accordance with the provisions of the U.S. Export Regulations.

V. No person, firm, corporation, partnership or other business organization, whether in the United States or elsewhere, without prior disclosure to and specific authorization from the Bureau of International Commerce, shall do any of the following acts, directly or indirectly, or carry on negotiations with respect thereto, in any manner or capacity, on behalf of or in any association with any such respondents or related party, or whereby any such respondent or related party may obtain any benefit therefrom or have any interest or participation therein, directly or indirectly: (a) Apply for, obtain, transfer, or use any license, shipper's export declaration, bill of lading, or other export control document relating to any exportation, reexportation, transshipment, or diversion of any commodity or technical data exported or to be exported from the United States, by, to, or for any such respondent or related party denied export privileges; or (b) order, buy, receive, use, sell, deliver, store, dispose of, forward, transport, finance, or otherwise service or participate in any exportation, reexportation, transshipment, or diversion of any commodity or technical data exported or to be exported from the United States.

VI. A copy of this order shall be served upon the respondents.

VII. In accordance with the provisions of § 382.11(c) of the Export Regulations, the respondents may move at any time to vacate or modify this temporary denial order by filing an appropriate motion therefor, supported by evidence, with the Compliance Commissioner and may request an oral hearing thereon which, if requested, shall be held before the Compliance Commissioner in Washington, D.C., at the earliest convenient date.

Dated: December 6, 1963.

FORREST D. HOCKERSMITH,
Director, Office of Export Control.

[F.R. Doc. 63-12972; Filed, Dec. 13, 1963; 8:46 a.m.]

Maritime Administration

DELTA STEAMSHIP LINES, INC.

Notice of Application

Notice is hereby given that Delta Steamship Lines, Inc. has applied for an amendment to its Operating-Differential Subsidy Agreement, Contract No. FMB-63 for the privilege of carrying cargo between United States ports on the Gulf of Mexico and ports on the East Coast of Mexico with its freight ships operating on Essential Trade Route No. 20 (U.S. Gulf ports-East Coast South America).

Any person, firm or corporation having any interest in such application and desiring a hearing under section 605(c) of the Merchant Marine Act, 1936, as amended, 46 U.S.C. 1175 should, by the close of business on December 30, 1963, notify the Secretary, Maritime Subsidy Board in writing in triplicate, and file petition for leave to intervene in accordance with the rules of practice and procedure of the Maritime Subsidy Board.

In the event a hearing is ordered to be held on the application under section 605(c), the purpose thereof will be to receive evidence relevant to (1) whether the application is one with respect to a vessel to be operated on a service, route or line served by citizens of the United States which would be in addition to the existing service, or services, and, if so, whether the service already provided by vessels of United States registry in such service, route or line is inadequate, and (2) whether in accomplishment of the purposes and policy of the Act additional vessels should be operated thereon.

If no request for hearing and petition for leave to intervene is received within the specified time, or if the Maritime Subsidy Board determines that petitions for leave to intervene filed within the specified time do not demonstrate sufficient interest to warrant a hearing, the Maritime Subsidy Board will take such action as may be deemed appropriate.

Dated: December 11, 1963.

JAMES S. DAWSON, Jr.,
Secretary.

[F.R. Doc. 63-12999; Filed, Dec. 13, 1963; 8:48 a.m.]

MOORE-McCORMACK LINES, INC.

Notice of Application for Change in Cruise Schedules

Notice is hereby given that Moore-McCormack Lines, Inc. has requested certain changes in its schedule of cruises for calendar year 1964 as previously published in the FEDERAL REGISTER of May 15, 1963 (28 F.R. 4860) and approved by the Maritime Subsidy Board on July 25, 1963. The cruises which differ from those previously approved are as follows:

Ship	Commences	Terminates	Itinerary
	1964	*1964*	
Brasil	Apr. 13	Apr. 17	Savannah, Bermuda, Savannah.
Do	Apr. 18	Apr. 23	Savannah, Bermuda, Savannah, New York.
Argentina	May 1	May 6	Baltimore, Bermuda, Baltimore.
Do	May 7	May 13	Baltimore, Bermuda, Baltimore.
Do	May 14	May 20	Baltimore, Bermuda, Baltimore, New York.
Brasil	Sept. 16	Sept. 25	New York, San Juan, St. Thomas, New York.
Do	Sept. 26	Sept. 30	New York, Bermuda, New York.
Do	Oct. 1	Oct. 9	New York, San Juan, St. Thomas, New York.
Do	Oct. 10	Oct. 14	New York, Bermuda, New York.
Do	Oct. 15	Oct. 22	New York, Bermuda, Nassau, New York.
Do	Oct. 23	Oct. 27	New York, Bermuda, New York.
Do	Oct. 28	Nov. 2	New York, Bermuda, New York.
Do	Nov. 3	Nov. 12	New York, St. Thomas, San Juan, New York.
Do	Nov. 13	Nov. 17	New York, Bermuda, New York.
		1965	
Do	Dec. 22	Jan. 4	Cancelled.

Any person, firm or corporation having any interest, within the meaning of Public Law 87-45, in the foregoing who desires to offer data, views, or arguments should submit the same in writing, in triplicate, to the Secretary, Maritime Subsidy Board, Washington 25, D.C., by close of business on December 30, 1963. In the event an opportunity to present oral argument is also desired, specific reason for such request should also be included. The Maritime Subsidy Board will consider these comments and views and take such action with respect thereto as in its discretion it deems warranted.

Dated: December 11, 1963.

JAMES S. DAWSON, Jr.,
Secretary.

[F.R. Doc. 63-13000; Filed, Dec. 13, 1963; 8:48 a.m.]

WATERMAN STEAMSHIP CORP.

Notice of Application

Notice is hereby given that Waterman Steamship Corporation has applied for Operating-Differential Subsidy under Title VI of the Merchant Marine Act, 1936, as amended, covering the freight service described as follows:

Trade Route No. 12; U.S. Atlantic/Far East; outbound only; A minimum of 18 and a maximum of 30 sailings per year in service from U.S. Atlantic ports (Maine/Atlantic Coast Florida to but not including Key West) and ports in the Far East (Japan, Formosa, Philippine Islands, and the Continent of Asia from the Union of Soviet Socialist Republics to Thailand, inclusive).

Any person, firm or corporation having any interest in such application and desiring a hearing under section 605(c) of the Merchant Marine Act, 1936, as amended, 46 U.S.C. 1175, should, by the close of business on December 30, 1963, notify the Secretary, Maritime Subsidy Board, in writing, in triplicate, and file petition for leave to intervene in accordance with the rules of practice and procedure of the Maritime Subsidy Board.

In the event that a hearing is ordered to be held on the application under section 605(c), the purpose thereof will be to receive evidence relevant to the following: (1) Whether the application is one with respect to vessels to be operated on a service, route or line, served by citizens of the United States which would be in addition to the existing service or services, and, if so, whether the service already provided by vessels of United States registry in such service, route or line is inadequate, and (2) whether in the accomplishment of the purposes and policy of the Act additional vessels should be operated thereon.

If no request for hearing and petition for leave to intervene is received within the specified time, or if the Maritime Subsidy Board determines that petitions for leave to intervene filed within the specified time do not demonstrate sufficient interest to warrant a hearing, the Maritime Subsidy Board will take such action as may otherwise be deemed appropriate.

Dated: December 11, 1963.

By order of the Maritime Subsidy Board.

JAMES S. DAWSON, JR.,
Secretary.

[F.R. Doc. 63-13001; Filed, Dec. 13, 1963; 8:48 a.m.]

DEPARTMENT OF HEALTH, EDUCATION, AND WELFARE

Office of Education

FEDERAL FINANCIAL ASSISTANCE IN CONSTRUCTION OF NONCOMMERCIAL EDUCATIONAL TELEVISION BROADCAST FACILITIES

Notice of Acceptance for Filing of Applications

Notice is hereby given that effective with this publication the following described applications for Federal finan-

cial assistance in the construction of noncommercial educational television broadcast facilities are accepted for filing in accordance with 45 CFR, § 60.7:

The Board of Public Instruction of Dade County, Florida, 1410 NE. Second Avenue, Miami 32, Florida, File No. 41 to expand the facilities of the noncommercial educational television broadcasting stations WTHS–TV, Channel 2, and WSED–TV, Channel 17 in Dade County, Florida.

Regents of Eastern New Mexico University, Portales, New Mexico, File No. 42 for the establishment of a new noncommercial educational television broadcasting station on Channel 3, Portales, New Mexico.

Any interested person may, pursuant to 45 CFR § 60.8, within 30 calendar days from the date of this publication, file comments regarding the above applications with the Director, Educational Television Facilities Program, U.S. Office of Education, Washington, D.C., 20202.

(76 Stat. 64, 47 U.S.C. 390)

RAYMOND J. STANLEY,
Director, Educational Television Facilities Program, U.S. Office of Education.

[F.R. Doc. 63–12983; Filed, Dec. 13, 1963; 8:47 a.m.]

FEDERAL AVIATION AGENCY

[OE Docket No. 63–CE–10]

BI-STATES CO.

Determination of No Hazard to Air Navigation

The Federal Aviation Agency has circularized the following proposal for aeronautical comment and has conducted a study (3–OE–3099) to determine its effect upon the safe and efficient utilization of navigable airspace.

The Bi-States Company, Holdrege, Nebraska, proposes to construct a guyed television antenna structure near Albion, Nebraska, at latitude 41°40'54" N., longitude 97°52'38" W. The overall height of the structure would be 3033.4 feet above mean sea level (1133.4 feet above ground).

The proposed structure would be located approximately 5.5 miles east of Albion, Nebraska, and approximately 7.25 miles northwest of the centerline of an approved off-airway route between the Norfolk, Nebraska, VOR and the Grand Island, Nebraska, VOR. At this location the structure would exceed the standards for determining hazards to air navigation as defined in § 77.23(a)(5) as applied to the above route and would require an increase from 3000 feet to 3500 feet in the minimum en route altitude.

The aeronautical study disclosed that the above route is an alternate route authorized for North Central Airlines and is not used on a scheduled basis. In addition, the Agency's IFR peak day traffic count for fiscal years 1962 and 1963 revealed no record of any operations between Norfolk and Grand Island. Therefore, the increase in minimum en route altitude would have no substantial adverse effect upon instrument flight rule operations.

The aeronautical study further disclosed that the proposed structure would have no substantial adverse effect upon VFR operations since it would not be located in proximity to any airport or specific route generally used by VFR flights.

No other aeronautical operations, procedures or minimum flight altitudes would be affected by the proposed structure.

Therefore, pursuant to the authority delegated to me by the Administrator (§ 77.37 [New]), it is found that the proposed structure would have no substantial adverse effect upon the safe and efficient utilization of navigable airspace and it is hereby determined that the proposed structure would not be a hazard to air navigation provided that it is obstruction marked and lighted in accordance with applicable Federal Communications Commission rules.

This determination is effective and will become final 30 days after the date of issuance unless an appeal is filed under § 77.39 [New] (27 F.R. 10352). If the appeal is denied, the determination will then become final as of the date of the denial or 30 days after the issuance of the determination, whichever is later. Unless otherwise revised or terminated, a final determination hereunder will expire 18 months after its effective date or upon earlier abandonment of the construction proposal (§ 77.41 [New]).

Issued in Washington, D.C., on December 9, 1963.

GEORGE R. BORSARI,
Chief, Obstruction Evaluation Branch.

[F.R. Doc. 63–12952; Filed, Dec. 13, 1963; 8:45 a.m.]

[OE Docket No. 63–SO–17]

WLOX BROADCASTING CO., INC.

Determination of No Hazard to Air Navigation

The Federal Aviation Agency has circularized the following proposal for aeronautical comment and has conducted a study (SO–OE–2691) to determine its effect upon the safe and efficient utilization of navigable airspace.

The WLOX Broadcasting Company, Inc., Biloxi, Mississippi, proposes to construct a television antenna structure at latitude 30°43'25" N., longitude 89°05'-29" W., approximately three miles northeast of McHenry, Mississippi, at an overall height of 1549 feet above mean sea level (1299 feet above ground).

The original circularization of this proposal specified a site at latitude 30°-42'44" N., longitude 89°07'13.5" W. Subsequent to the forwarding of this study to the Washington office, the proponent amended the location to that stated in the above proposal.

The structure would be located approximately 0.5 mile east of the centerline of an approved off-airway route between Gulfport, Mississippi, and Laurel, Mississippi, three miles east of the centerline of an approved off-airway route between Gulfport and Hattiesburg, Mississippi, 5.7 miles south of the centerline of VOR Federal airway No. 70 and 5.6 miles north of the centerline of Victor 20N. It would exceed the standards for determining hazards to air navigation as defined in § 77.23(a)(3) of the Federal Aviation Regulations by 1099 feet since it would be more than 200 feet above ground at the site of construction.

The aeronautical study disclosed that the structure would require the following increases in instrument flight rules minimum altitudes: from 1600 feet to 2000 feet in the minimum obstruction clearance altitude on Victor 70 between Picayune VOR and Citro Intersection, from 1500 feet to 2000 feet in the MOCA on Victor 20N between Caeser and School Intersections, from 2000 feet to 2500 feet in the minimum en route altitude on the approved off-airway routes between Gulfport and Laurel and between Gulfport and Hattiesburg, and from 1800 feet to 2500 feet in the MEA on the approved terminal off-airway route between Wiggins and Mouse Intersections.

The study also disclosed that the increase in MOCA on Victor 20N and Victor 70 would not adversely affect aeronautical operations since the 2000-foot MEA on Victor 20N and the 3500-foot MEA on Victor 70 would remain unchanged. In addition, it has been determined that the approved off-airway routes could be realigned to accommodate the structure without causing a substantial adverse effect upon aeronautical operations on these routes. There were no objections by aeronautical interests to the increase of MEA on the terminal route between Wiggins and Mouse.

The study further disclosed that the structure would not be located on a known visual flight rule route generally used by light aircraft. It would be more than two miles east of a main north-south highway which could be used as a visual navigational aid by flights transitting between Gulfport and Hattiesburg or other points in a north/northwesterly direction. In addition, Agency records indicate no significant volume of VFR flight activity in proximity to the proposed site, there being recorded less than one flight per day that passed within a three-mile radius of the site.

Based on the aeronautical study, it is the finding of the Agency that the proposed structure would have no substantial adverse effect upon aeronautical operations, procedures on minimum flight altitudes either IFR or VFR.

Therefore, pursuant to the authority delegated to me by the Administrator (§ 77.37 [New]), it is found that the proposed structure would have no substantial adverse effect upon the safe and efficient utilization of navigable airspace and it is hereby determined that the proposed structure would not be a hazard to air navigation provided that it is obstruction marked and lighted in accordance with applicable Federal Communications Commission rules.

This determination is effective and will become final 30 days after the date of issuance unless an appeal is filed under

§ 77.39 [New] (27 F.R. 10352). If the appeal is denied the determination will then become final as of the date of the denial or 30 days after the issuance of the determination, whichever is later. Unless otherwise revised or terminated, a final determination hereunder will expire 18 months after its effective date or upon earlier abandonment of the construction proposal (§ 77.41 [New]).

Issued in Washington, D.C., on December 9, 1963.

GEORGE R. BORSARI,
Chief, Obstruction Evaluation Branch.

[F.R. Doc. 63-12953; Filed, Dec. 13, 1963; 8:45 a.m.]

FEDERAL MARITIME COMMISSION

WILLIAM GORDON KESLER AND H. C. RICHARDS CO.

Independent Ocean Freight Forwarder Applications

Notice is hereby given that the following applicants have filed with the Federal Maritime Commission, applications for licenses as independent ocean freight forwarders, pursuant to section 44(a) of the Shipping Act, 1916 (75 Stat. 522 and 46 U.S.C. 841(b)).

Persons knowing of any reason why any applicant should not receive a license are requested to communicate with the Director, Bureau of Domestic Regulation, Federal Maritime Commission, Washington, D.C., 20573. Protests received within 60 days from the date of publication of this notice in the FEDERAL REGISTER will be considered.

NON-GRANDFATHER APPLICANTS

NAME AND ADDRESS

William Gordon Kesler, 321 St. Charles Street, New Orleans, Louisiana. William Gordon Kesler, Owner.

H. C. Richards Company (Helen Currie Richards, d.b.a.), 125B 26th Street, Newport News, Virginia, 23607. Individual.

Dated: December 10, 1963.

THOMAS LISI,
Secretary.

[F.R. Doc. 63-12986; Filed, Dec. 13, 1963; 8:47 a.m.]

CASTELAZO AND ASSOCIATES ET AL.

Notice of Agreements Filed for Approval

Notice is hereby given that the following agreements have been filed with the Federal Maritime Commission for approval pursuant to section 15 of the Shipping Act, 1916, (75 Stat. 763 and 46 U.S.C. 814). All parties involved are eligible to operate as independent ocean freight forwarders pursuant to section 44 of the Shipping Act, 1916.

Unless otherwise indicated, these agreements are non-exclusive, cooperative working arrangements under which the parties may perform freight forwarding services for each other, dividing forwarding and service fees as agreed on each transaction. Ocean freight compensation is to be divided between the parties as agreed.

Castelazo and Associates, Los Angeles, Calif., is party to the following agreements, the terms of which are identical. The other parties are:

Thornley & Pitt, Inc., San Francisco, Calif. ---------- FF-1261
Exporters Forwarding Co., Inc., New York, N.Y. ---------- FF-1262
Triangle Forwarding Corp., New York, N.Y. ---------- FF-1263
W. R. Zanes & Co. of La., Inc., New Orleans, La. ---------- FF-1264

John H. Faunce, Philadelphia, Inc., Philadelphia, Pa., is party to the following agreements, the terms of which are identical.

The other parties are:

Barr Shipping Co., Inc., New York, N.Y. ---------- FF-1271
Barr Shipping Co., Inc., Miami, Fla. FF-1272
Samuel Shapiro & Co., Inc., Baltimore, Md. and Washington, D.C. FF-1273
The F. H. Shallus Co., Baltimore, Md. ---------- FF-1274
W. R. Zanes & Co., Inc., Galveston, Dallas, Tex. ---------- FF-1275
W. R. Zanes & Co., Houston, Tex. FF-1276
John H. Faunce New York, Inc., New York, N.Y. ---------- FF-1277

The following agreements have similar terms:

Transoceanic Shipping Co., New Orleans, La., and Chas. Kurz Co., Philadelphia, Pa. ---------- FF-1260
Lep Transport, Inc., New York, N.Y., and Admiral Shipping Corp., Houston, Tex. ---------- FF-1265
Haras & Co., Inc., Jersey City, N.J., and Poseidon Freight Forwarders, San Francisco, Calif. ---------- FF-1268
Frederic Henjes Jr., Inc., New York, N.Y., and Dolliff & Co., Inc., Boston, Mass. ---------- FF-1279
W. J. Byrnes & Co. of L.A., Inc., Los Angeles, Calif., and A. L. Rankin, Corpus Christi, Tex. ---------- FF-1281
Geo. S. Bush & Co., Inc., Portland, Oreg., and W. D. Wall Traffic Service, San Jose, Calif. ---------- FF-1282
Frank P. Dow Co., Inc., Seattle, Wash.; Frank P. Dow Co., Inc., San Francisco, Calif.; Frank P. Dow Co., Inc. of L.A., Los Angeles, Calif.; Frank P. Dow Co., Inc., Portland, Oreg. and Premier Shipping Co., Inc., New York, N.Y. FF-1269
Stone Forwarding Co., Inc., with offices in Galveston, Houston, Corpus Christi, Texas, and Premier Shipping Co., Inc., New York, N.Y. ---------- FF-1278

Agreement FF-1215 between Alonso Shipping Co., New Orleans, La., and Acosta Shipping Corp., New York, N.Y., provides that forwarding and service fees are $5.00 per shipment with special services remaining subject to agreement. Ocean freight compensation is to be divided equally.

Agreement FF-1280 between Madison Shipping Co., Inc., New York, N.Y., and Alonso Shipping Co., New Orleans, La., provides that forwarding and service fees are $5.00 per shipment with special services remaining subject to agreement. Ocean freight compensation is to be divided equally.

Agreement FF-1257 between Alonso Shipping Co., New Orleans, La., and M. G. Otero Co., Los Angeles, Calif., provides that forwarding and service fees are $3.75 to Puerto Rico and $7.50 to other countries with special services remaining subject to agreement. Ocean freight compensation will be retained by the originating party.

Cobal International, New York, N.Y., is party to the following agreements, whose terms provide for the division of forwarding and service fees and ocean freight compensation on a 50/50 basis.

Win Mar Incorporated, New Orleans, La. ---------- FF-1266
International Shipping Services, Houston, Tex. ---------- FF-1267

Agreement FF-1259 between Star Forwarders, Inc., Omaha, Nebr., party (a), and R. N. Forwarding Co., Inc., New York, N.Y., party (b), provides that forwarding and service fees are $7.00 per bill of lading. Ocean freight compensation is divided 40 percent for party (a) and 60 percent for party (b).

Agreement FF-1270 between Oceanic Shipping Co., Mobile, Ala., party (a), and Major Forwarding Co., Inc., New York, N.Y., party (b), is an arrangement under which on shipments of paper, paper products or wood pulp, party (a) receives one-third (no less than $5.00) and party (b) receives two-thirds of ocean freight compensation. For shipment of all other commodities, party (b) agrees to pay party (a) a minimum charge of $5.00 forwarding fee, plus $0.50 for passing Export Declaration, plus one-third of the steamship brokerage.

Interested persons may inspect these agreements and obtain copies thereof at the Bureau of Domestic Regulation, Federal Maritime Commission, Washington, D.C., or at the Commission's field offices at:

45 Broadway, New York, N.Y.

180 New Montgomery Street, San Francisco, Calif.

Room 333 Federal Office Building South, 600 South Street, New Orleans, La., Mail address: Post Office Box 30550, Lafayette Station, New Orleans, La.

They may submit to the Secretary, Federal Maritime Commission, Washington, D.C., within twenty days after publication of this notice in the FEDERAL REGISTER, written statements with reference to the agreement and their approval, disapproval, or modification, together with request for hearing should such hearing be desired.

Dated: December 11, 1963.

By the Federal Maritime Commission.

THOMAS LISI,
Secretary.

[F.R. Doc. 63-12985; Filed, Dec. 13, 1963; 8:47 a.m.]

[Docket No. 1132; FMC-F No. 114]

ALASKA STEAMSHIP CO.

Investigation Concerning Certain Increased Rates

Whereas, by the First Supplemental Order in Docket No. 1132 served September 12, 1963, the Commission instituted an investigation into and concerning the reasonableness and lawfulness of certain increased rates on "Cigars, Cigarettes, Tobacco and Snuff" stated in Alaska Steamship Company Freight Tar-

iff No. 832, FMC–F No. 114 applying between Seattle and Tacoma, Washington and ports in Southeastern Alaska, and suspended said tariff provisions to and including January 4, 1964;

Whereas, the said order provides in part that "no change shall be made in the matter hereby suspended nor the matter which is continued in effect as a result of such suspension until the period of suspension or any extension thereof has expired, or until this investigation and suspension proceeding has been disposed of, whichever first occurs, unless otherwise authorized by the Commission;"

Whereas, on November 18, 1963, the Alaska Steamship Company filed special permission application seeking authority to amend the suspended matter currently under investigation herein on full statutory notice. The suspended rates are as follows:

1st Revised Page No. 41
Item 335
Cigars, cigarettes, tobacco, and snuff
Between Seattle and Tacoma, Wash., and Alaska ports, viz:

[In cents per 100 pounds]

Ketchikan	Wrangell and Petersburg	Juneau	Haines, Skagway, and Sitka
765	810	863	915

Whereas, the Commission having found good cause therefor has on November 27, 1963, granted Alaska Steamship Company special permission authority to publish the following changes on not less than thirty days' notice under Special Permission No. 4181; said special permission to be without prejudice to the right of the Commission to suspend such schedule within the notice period, either upon receipt of protest thereto or upon its own motion:

2nd Revised Page No. 41
Item 335
Cigars, cigarettes, tobacco, and snuff
Between Seattle and Tacoma, Wash., and Alaska ports, viz:

[In cents per 100 pounds]

Ketchikan	Wrangell and Petersburg	Juneau	Haines, Skagway, and Sitka
430	480	533	579

Now therefore it is ordered, That First Supplemental Order herein is modified to the extent necessary to permit the publication and filing of the changes covered by Special Permission No. 4181;

It is further ordered, That any rates, charges, classifications, rules, regulations, and practices set forth in the schedules filed pursuant to such special permission shall be subject to the investigation and hearing herein to the same extent as the rates, charges, classifications, rules, regulations, tariffs or practices under schedules cancelled thereby, and that the special permission granted hereby shall be without prejudice to the Commission's determination as to the lawfulness of the rates established pursuant hereto;

It is further ordered, That copies of this order shall be filed with said tariff schedule in the Bureau of Domestic Regulation of the Federal Maritime Commission;

It is further ordered, That a copy of this order shall be forthwith served upon the respondent and all protestants and intervenors herein; and that this order shall be published in the FEDERAL REGISTER.

By the Commission, November 27, 1963.

[SEAL] THOMAS LISI,
Secretary.

[F.R. Doc. 63–12984; Filed, Dec. 13, 1963; 8:47 a.m.]

GENERAL SERVICES ADMINISTRATION

Utilization and Disposal Service

[Wildlife Order 70]

DELAWARE RIVER-KILLCOHOOK SPOIL DISPOSAL AREA

Transfer of Property

Pursuant to section 2 of Public Law 537, Eightieth Congress, approved May 19, 1948 (16 U.S.C. 667c), notice is hereby given that:

1. By letter from the U.S. Army Engineer District, New York, Corps of Engineers, dated November 4, 1963, the property comprising a 9.60-acre portion of the Delaware River-Killcohook Spoil Disposal Area, located in Salem County, New Jersey, and more particularly described in the letter of request dated October 18, 1963, from the Department of the Interior, has been transferred, effective November 12, 1963, to the Department of the Interior.

2. The above-described property was transferred to the Department of the Interior for the national migratory bird management program in accordance with the provisions of section 1 of said Public Law 537 (16 U.S.C. 667b).

Dated: December 6, 1963.

WALTER C. MORELAND,
Assistant Commissioner for Real Property, Utilization and Disposal Service.

[F.R. Doc. 63–12987; Filed, Dec. 13, 1963; 8:47 a.m.]

FEDERAL POWER COMMISSION

[Docket No. G–3999 etc.]

ASSOCIATED OIL & GAS CO., ET AL.

Notice of Applications for Certificates, Abandonment of Service and Petitions To Amend Certificates [1]

DECEMBER 10, 1963.

Associated Oil & Gas Co. (Successor to The Nueces Company), Docket No. G–3999; Pan American Petroleum Corporation, Docket No. G–7532; Jabara Lease Committee (Successor to Ashton Oil Company, Inc.), Docket No. G–9302; R. W. Lange (Successor to Colorado Oil & Gas Corporation), Docket No. G–17011; Graridge Corporation (Operator), et al. (formerly Arthur I. Ginsberg, Trustee (Operator), et al.), Docket No. CI60–467; Falcon Seaboard Drilling Company (Operator), et al., Docket No. CI60–586; Don Cohen (Successor to Compadre Oil Corporation (Operator), et al.), Docket No. CI61–280; Petroleum Inc. (Operator), et al., Docket No. CI62–372, (G–12112); Graham-Michaelis Drilling Company (Operator), et al., Docket No. CI62–555; James C. Sherrill, *et al.*, Docket No. CI62–660; Ainslee Perrault (Operator), et al. (formerly Wilshire Oil Company of Texas (Operator), et al.); Docket No. CI62–988; Socony Mobil Oil Company, Inc., Docket No. CI62–1521; Reaves and Myers (Operator), et al., Docket No. CI63–124; Paul Fleming, Agent for Fleming Oil & Gas Company, Docket No. CI64–627; Sam Sklar, et al., Docket No. CI64–628; Bennett's Valley Development Company, Docket No. CI64–629; Star Gas Company, Docket No. CI64–630; Seneca Oil Company, Docket No. CI64–631; Thomas N. Berry & Company, Docket No. CI64–632; J. C. Trahan, Drilling Contractor, Inc., Docket No. CI64–633; Humble Oil & Refining Company, Docket No. CI64–634; Tommy Ward Drilling Company, Docket No. CI64–635; Howard W. Sharpley, et al., Docket No. CI64–636; Thomas Jordan, Inc., Docket No. CI64–637; Ashland Oil & Refining Company, Docket No. CI64–638; Sunray DX Oil Company, Docket No. CI64–639; Mountain States Natural Gas Corporation, Docket No. CI64–640; Jake L. Hamon, Docket No. CI64–641; Anadarko Production Company, Docket No. CI64–642; Texaco Inc., Docket No. CI64–643; Ashland Oil & Refining Company, Docket No. CI64–644; Theodore Lockhard Well #1, Docket No. CI64–645; Cimarron Exploration, Inc., Docket No. CI64–646; Oil States Sales Company, Docket No. CI64–647; Sun Oil Company (Mid-Continent Division), Docket No. CI64–648; Ashland Oil & Refining Company, Docket No. CI64–649; F. A. Gillespie and Sons Company, Docket No. CI64–650; Boyd Oil and Gas Company, Docket No. CI64–651; Shell Oil Company, Docket No. CI64–652; Amax Petroleum Corporation, Docket No. CI64–653; Union Texas Petroleum, a Division of Allied Chemical Corporation, et al., Docket No. CI64–654.

Take notice that each of the above Applicants has filed an application or petition pursuant to section 7 of the Natural Gas Act for authorization to sell natural gas in interstate commerce or to abandon service heretofore authorized as described herein, all as more fully described in the respective applications and amendments which are on file with the Commission and open to public inspection.

[1] This notice does not provide for consolidation for hearing of the several matters covered herein, nor should it be so construed.

Docket No. and date filed	Purchaser	Field and location	Price per Mcf	Pressure base
G-3999 E 11-26-63	Tennessee Gas Transmission Co.	Acreage in Nueces County, Tex.	14.85	14.65
G-7532 D 11-26-63	El Paso Natural Gas Co.	Acreage in Lea County, N. Mex.	(1)	
G-9302 E 11-21-63	Cities Service Gas Co.	Acreage in Cowley County, Kans.	8.0	14.65
G-17011 E 11-27-63	Northern Natural Gas Co.	Crist Gas Unit, Finney County, Kans.	12.0	14.65
CI60-467 11-18-63 [2]	Tennessee Gas Transmission Co.	Southeast Tomball Field, Harris County, Tex.	14.5	14.65
CI60-586 A 5-9-60 4-26-62 [3] D 6-4-63 [4] D 11-8-63 [5]	Transwestern Pipeline Co.	Acreage in Lipscomb County, Tex.	17.0	14.65
CI61-280 D&E 11-26-63 [6]	Lone Star Gas Co.	Minervia Tillerson Lease and Tillerson "A" Lease, Nellie Field, Stevens County, Okla.	14.0	14.65
CI62-372 [7] A 10-9-61	Cities Service Gas Co.	Hugoton Field, Finney County, Kans.	[8] 10.7195	14.65
CI62-555 C 11-29-63	Northern Natural Gas Co.	Sitka Field, Clark County, Kans.	16.0	14.65
CI62-660 C 11-27-63	Colorado Interstate Gas Co.	Acreage in Potter County, Tex.	12.0	14.65
CI62-988 [9] 11-18-63	El Paso Natural Gas Co.	Acreage in San Juan County, N. Mex.	12.0	15.025
CI62-1521 C 11-6-63	do	San Juan Basin Field, San Juan County, N. Mex.	13.0	15.025
CI63-124 A7-26-62	Texas Eastern Transmission Corp.	Goebel Field, Live Oak County, Tex.	13.8733	14.65
CI64-627 A 11-26-63	Cabot Corp.	Washington District, Calhoun County, W. Va.	15.2	14.7
CI64-628 B 11-26-63	United Gas Pipe Line Co.	Sibley Field, Webster Parish, La.	Depleted	
CI64-629 B 11-26-63	New York State Natural Gas Corp.	Bennezette Township, Elk County, Pa.	Depleted	
CI64-630 A 11-26-63	Cabot Corp.	Sherman District, Calhoun County, W. Va.	13.824	15.325
CI64-631 A 11-26-63	Northern Natural Gas Co.	Southeast Dower Field, Beaver County, Okla.	16.5	14.65
CI64-632 A 11-26-63	Cities Service Gas Co.	East Goodnight Area, Lincoln County, Okla.	12.0	14.65
CI64-633 A 11-27-63	Southern Natural Gas Co.	Eloi Bay Field, St. Bernard Parish, La.	23.675	15.025
CI64-634 B 11-29-63	Northern Natural Gas Co.	Dude Wilson Field, Ochiltree County, Tex.	[10]	
CI64-635 A 11-29-63	do	Como Area, Beaver County, Okla.	17.0	14.65
CI64-636 A 11-29-63	Hope Natural Gas Co.	Glenville District, Gilmer County, W. Va.	25.0	15.325
CI64-637 A 11-29-63	Texas Eastern Transmission Corp.	Reeves Field, Allen Parish, La.	13.75	15.025
CI64-638 A 11-29-63	Warren Petroleum Corp.	Acreage in Wheeler County, Tex.	6.25	14.65
CI64-639 A 11-29-63	Texas Gas Transmission Corp.	Egan Field, Acadia Parish, La.	12.7964	15.025
CI64-640 A 11-29-63	El Paso Natural Gas Co.	Basin Dakota Field, La Plata County, Colo.	11.0	15.025
CI64-641 A 11-29-63	Northern Natural Gas Co.	Acreage in Beaver County, Okla.	17.0	14.65
CI64-642 A 12-2-63	Colorado Interstate Gas Co.	Carthage-Reiss Field, Texas County, Okla.	16.0	14.65
CI64-643 B 12-2-63	Tennessee Gas Transmission Co.	Riverside Field, Nueces County, Tex.	Depleted	
CI64-644 A 12-2-63	Natural Gas Pipeline Co. of America.	Quinlan Area, Woodward County, Okla.	17.0	14.65
CI64-645 A 12-2-63	Hope Natural Gas Co.	Troy District, Gilmer County, W. Va.	25.0	15.325
CI64-646 A 12-2-63	Panhandle Eastern Pipe Line Co.	Acreage in Meade County, Kans.	15.0	14.65
CI64-647 A 12-3-63	Equitable Gas Co.	Union District, Ritchie County, W. Va.	25.0	15.325
CI64-648 A 12-2-63	Arkansas Louisiana Gas Co.	Arkoma Area, Latimer County, Okla.	15.0	14.65
CI64-649 B 11-29-63	Lone Star Gas Co.	East Panhandle Field, Wheeler County, Tex.	[11]	
CI64-650 A 11-1-63	Warren Petroleum Corp.	do	6.25	14.65
CI64-651 A 12-2-63	United Fuel Gas Co.	Acreage in Mingo County, W. Va.	20.0	15.325
CI64-652 A 12-4-63	Arkansas Louisana Gas Co.	West Enid Area, Garfield County, Okla.	13.5	14.65
CI64-653 A 12-4-63	Northern Natural Gas Co.	Acreage in Beaver County, Okla.	17.0	14.65
CI64-654 A 12-4-63	Arkansas Louisiana Gas Co.	North East Ames Field, Major County, Okla.	15.0	14.65

Filing code: A—Initial service.
B—Abandonment.
C—Amendment to add acreage.
D—Amendment to delete acreage.
E—Succession.

[1] Amendment to delete acreage by agreement between parties dated Aug. 21, 1963.
[2] Amendment filed to reflect change in operator and redesignate rate schedule to read Graridge Corp. (Operator), et al. in lieu of Arthur I. Ginsberg, Trustee (Operator), et al.
[3] Amendment filed to include interest of coowners and redesignate rate schedule to read (Operator), et al.
[4] Amendment filed to delete acreage per Letter Agreement between parties dated Apr. 23, 1963.
[5] Amendment filed to delete acreage per Letter Agreement between parties dated Sept. 5, 1963.
[6] Amendment provides for deletion of acreage insofar as the Tillerson "A" Lease, which has failed to produce.
[7] Petition was originally assigned Docket No. CI62-372, however said docket will be canceled and petition processed as an amendment to certificate in Docket No. G-12112 to add acreage.
[8] Under suspension in Docket No. RI63-391.
[9] Applicant filed notice to reflect change in operator and redesignate rate schedule to read Ainslee Perrault (Operator), et al. in lieu of Wilshire Oil Co. of Texas (Operator), et al.
[10] By Letter Agreement between parties dated Oct. 8, 1963.
[11] Existing gas purchase contract has been assigned to Warren Petroleum Corp.

Protests or petitions to intervene may be filed with the Federal Power Commission, Washington, D.C., 20426, in accordance with the rules of practice and procedure (18 CFR 1.8 or 1.10) on or before January 6, 1964.

Take further notice that, pursuant to the authority contained in and subject to the jurisdiction conferred upon the Federal Power Commission by sections 7 and 15 of the Natural Gas Act, and the Commission's rules of practice and procedure, a hearing will be held without further notice before the Commission on all applications in which no protest or petition to intervene is filed within the time required herein, if the Commission on its own review of the matter believes that a grant of the certificates is required by the public convenience and necessity. Where a protest or petition for leave to intervene is timely filed, or where the Commission on its own motion believes that a formal hearing is required, further notice of such hearing will be duly given.

Under the procedure herein provided for, unless otherwise advised, it will be unnecessary for Applicants to appear or be represented at the hearing.

GORDON M. GRANT,
Acting Secretary.

[F.R. Doc. 63-12956; Filed, Dec. 13, 1963; 8:45 a.m.]

[Docket No. AR 61-2 etc.]

AREA RATE PROCEEDING ET AL.

Miscellaneous Amendments

OCTOBER 28, and DECEMBER 5, 1963.

Area Rate Proceeding, Docket No. AR 61-2; Amerada Petroleum Company, et al., Docket No. RI62-505, et al.

In the Order Redesignating Proceedings, Severing Certain Rate Suspension and Certificate Proceedings, Adding and Deleting Respondents, and Consolidating Proceedings, issued August 30, 1963 and published in the FEDERAL REGISTER September 6, 1963 (F.R. Doc. 63-9528; F.R. 9796-9799), make the following changes:

In the ninth line of second paragraph from bottom of page 9796 delete "and" and add "RI62-85".

In the seventh line of finding paragraph (2) and fourth line of ordering paragraph (D) add "RI62-120, RI62-202 and RI62-203", after "RI61-170".

In paragraph (C) of the ordering clause add "G-18344" after "G-17448".

Revised Appendix "A"

Change "Bell Oil Corp." to "Bel Oil Corporation".

Change "British American Oil Producing Co." to "The British American Oil Production Co.".

Change "Callery, F. A. Inc." to "Callery, F. A., Inc.".

Change "Chicago Stockyards Research" to "Chicago Stockyards Research Company".

Change "Christie Mitchell & Mitchell" to "Christie, Mitchell & Mitchell Company".

Add "Eason Oil Co." after "Drew Petroleum Inc.".

Change "General American Oil Co. of Texas" to "General American Oil Company of Texas".

Change "Geological Geophysical Associates, Inc." to "Geological, Geophysical Associate, Inc.".

Change "Gulf Interstate Co." to "Gulf Interstate Oil Co.".

Change "Humble Gas Transmission Corporation" to "Humble Gas Transmission Company".

Change "Grardige Corp." to "Graridge Corporation".

Change "Hurley Oil & Gas Co." to "Hurley Oil & Gas Company".

Change "Kerr-McGee Oil Industries" to "Kerr-McGee Oil Industries, Inc.".

Change "Magna Oil Company" to "Magna Oil Corporation".

Change "Mayronne, R. W., Jr." to "Mayronne, R. W., Jr. d/b/a Riverside Oil Company".

Change "Owens Production Company" to "Owen Production Company".

Change "Sunray Mid-Continent Oil" to "Sunray DX Oil Company".

Delete "Riverside Oil Company".

Add "Texas Eastern Transmission Corporation" after "Texas Crude Oil Co.".

Add "United Gas Pipe Line Company" after "Union Texas Petrolum, a Div. of Allied Chemical Corp.".

Insert a "." after ".F." in "W. W. F. Oil Corp.".

Change "Walker, W. E. & Meeker, Jr." to "Walker, W. E. & Meeker, J. R.".

Add "W. E. Walker & Freedom Minerals, Inc." after "Walker, W. E. & Meeker, J. R."

Revised Appendix "C" (Producer and Docket Nos.)

Delete "G–19536" and "RI61–128" after Atlantic Refining Company.

Delete "RI63–143**" after Austril Oil Co., Inc. (Oper.), Agent for Oil Participations Inc.

Add "RI62–79" after "RI61–238" following Columbian Fuel Corporation.

Delete "G–19874" after "General American Oil Co. of Texas".

Delete "RI62–169" after "Goff, J. R. Trustee".

Add "Graridge Corporation (Operator), et al., RI62–169" after "Goff, J. R. Trustee".

Change "Hudson, E. J., et al." to "Hudson Gas & Oil Corporation (Operator), et al., and San Jacinto Oil and Gas Company (Operator), et al.".

Change "G–12128" to "G–12158" after "McDermott, J. Ray & Co., Inc.".

Delete "Owen, J. P. (Oper.), et al. and General American Oil Co. of Texas, G–20555, RI61–220" and insert in lieu thereof:

J. P. Owen (Operator), et al. and General American Oil Company of Texas (Operator), et al., G–20555.

Owen Production Company (Operator), et al. and J. P. Owen (Operator), et al. and General American Oil Company of Texas (Operator), et al., RI61–220.

Change "Shoreline Exploration Company" to "Shoreline Exploration, Inc.".

After "Sunray DX Oil Company, Docket No. RI63–91* add a second footnote "**".

Delete "G–19875 and G–19924" after "U.S. Oil of Louisiana, Inc.". (12–6–63).

Add "RI61–131 and RI62–77", following "G–19922 and RI61–335" respectively after "Atlantic Refining Company".

GORDON M. GRANT,
Acting Secretary.

[F.R. Doc. 63–12955; Filed, Dec. 13, 1963; 8:45 a.m.]

[Docket No. E–7092]

NORTHWEST PAPER CO.

Petition for Declaratory Order

DECEMBER 9, 1963.

On April 25, 1963, The Northwest Paper Company (Petitioner), a Minnesota corporation with principal offices at Cloquet, Minnesota, filed a petition, including a statement of facts, pursuant to § 1.7(c) of the Commission's rules of practice and procedure, for a declaratory order to remove any uncertainty as to Petitioner's need under the Federal Power Act for a license to continue the maintenance and operation of its Brainerd hydroelectric project on the Mississippi River in Crow Wing County, at Brainerd, Minnesota.

Petitioner owns and operates the Brainerd project as a power source for its paper mill located beside the dam. Normally, the paper mill consumes all of the Brainerd project's energy and also larger amounts supplied by the Minnesota Power and Light Company, but when the paper mill is closed, Petitioner may dump its excess energy to the power company.

Congress in 1886 authorized the Mississippi Water-Power and Boom Company to build a dam and other project works for water power and other purposes, across the Mississippi River at Brainerd subject to certain conditions, including conditions in the interests of navigation (24 Stat. 12). The authorized work was completed by 1889 at the site of Petitioner's existing project. The property in 1890 passed after foreclosure sale to Andrew L. Fenessy, who, in the same year conveyed it by quitclaim deed to the Brainerd Water-Power Company, the owner for the next three years. After another foreclosure sale, it was conveyed to Harry J. Jacquith, et al., and then through mesne conveyances to the Northern Water Power Company (Northern Power), which was acquired by Petitioner in 1910; the subsidiary in 1936 conveyed the property to Petitioner.

When Petitioner erected a new paper mill near the dam site in 1916 and 1917, Northern Power rebuilt the dam and powerhouse and installed new generators. No other major work on the project works was performed until 1950, when a flood severely undercut part of the dam and virtually destroyed the gate sections. Petitioner submitted reconstruction plans to the Army Corps of Engineers and to the Division of Waters of the State of Minnesota Department of Conservation, both of which gave their approval. The reconstruction of the project, performed in 1950 and 1951, consisted principally of the following: (1) The west abutment, consisting of a 20-foot-wide tainter gate log sluiceway, was rebuilt by consolidating the rock-filled crib wall and crest structure with intruded concrete; (2) the wooden tainter gate was replaced without changing the dimension or elevation; (3) the top of east-west control spillway structure, consisting of thirteen twelve-foot-wide tainter gates, was replaced by two 85-foot-long by seven-foot-high S. Morgan Smith Company Bascule gates; (4) the crest of the dam was set at an elevation of 1176 feet, and under the crest a six-foot-thick concrete cap was installed, and Prepakt concrete grout was pressure pumped to fill voids in the original rock-filled crib and pile caps; (5) a four-foot-thick concrete face and apron cap to an elevation of 1160 feet were installed, and Prepakt concrete was pressure pumped to consolidate the rock-filled crib and piling; (6) the top of the north-south spill structure was removed, and a four-foot-thick concrete crest cap (with top elevation of 1178 feet), dam face, and apron (with top elevation of 1160 feet) were rebuilt, and the existing rock-filled crib and pile structure were consolidated by pressure-pumped concrete to fill voids; and (7) five thirteen-foot, seven-inch stop log gates were constructed to maintain the reservoir at an elevation of 1182.2 feet.

The powerhouse and generating equipment were not changed in 1950 and 1951. Since then, however, two wood grinders driven by synchronous motors during low water periods have been removed and the motors converted to generators.

Under section 23(b) of the Federal Power Act, it is unlawful for the Petitioner, as a nonlicensee, to maintain and operate hydroelectric project works upon a navigable water of the United States, unless it received a Federal permit for such works prior to passage of the Federal Power Act on June 10, 1920. Petitioner maintains and operates hydroelectric project works upon a navigable water of the United States. It submits, however, that it does not need a license from the Commission because of the special act of Congress approved April 15, 1886 (24 Stat. 12), which authorized the Mississippi Water-Power and Boom Company to build a dam at Brainerd, Minnesota.

The project works authorized and constructed under the special act of 1886 (24 Stat. 12) no longer substantially exist. The project twice has been extensively rebuilt and modified. There are only a few vestiges of the original project works, notably certain oak pilings upon which some of the present structures rest. In our view, it may not be presumed that Congress by the special act of 1886 intended to authorize Mississippi Water-Power and Boom Company or Petitioner to replace the project works with new project works, or to increase or reduce the project's capacity, or otherwise replace or modify the authorized project works.

The first major reconstruction and modification was undertaken in 1916 or 1917 to bring the project's capacity up to the demands of Petitioner's new paper plant near the dam site. Apparently, Petitioner does not claim that Northern Power obtained the consent of Congress for this work, as required by sections 9

and 10 of the Rivers and Harbors Act of 1899 (33 U.S.C. 401, 403). In any event, when Petitioner commenced its construction of project works in 1950, and the installation of new facilities, without having obtained a license pursuant to the provisions of the Federal Power Act, it clearly acted in violation of section 23(b) of that Act.

Upon consideration of the facts presented by Petitioner, we conclude that it will be necessary for Petitioner to file application and obtain a license, pursuant to the provisions of the Federal Power Act and the Commission's rules and regulations thereunder, for the continued maintenance and operation of its project works in and along the Mississippi River at Brainerd, Minnesota.

The Commission orders: The Northwest Paper Company shall, within ninety (90) days from the date of issuance of this order, file application for license, pursuant to the provisions of the Federal Power Act and the Commission's rules and regulations thereunder, for the continued maintenance and operation of its project works in and along the Mississippi River at Brainerd, Minnesota.

By the Commission.

[SEAL] GORDON M. GRANT, *Acting Secretary.*

[F.R. Doc. 63-12957; Filed, Dec. 13, 1963; 8:45 a.m.]

SECURITIES AND EXCHANGE COMMISSION

[File No. 31-669]

GENERAL DEVELOPMENT UTILITIES, INC., AND GENERAL DEVELOPMENT CORP.

Notice of Filing of Application for Order or for Exemption

DECEMBER 10, 1963.

Notice is hereby given that General Development Corporation ("General") and General Development Utilities, Inc. ("Utilities"), 2828 Coral Way, Miami, Florida, a subsidiary company thereof, have filed with this Commission a joint application and amendments thereto requesting an order, pursuant to section 2(a)(4) of the Public Utility Holding Company Act of 1935 ("Act"), declaring Utilities not to be a "gas utility company"; or, in the alternative, an order pursuant to section 3(a)(3) of the Act exempting General and its subsidiary companies from the provisions of the Act on the ground that General is only incidentally a holding company, being primarily engaged or interested in one or more businesses other than the business of a public-utility company.

All interested persons are referred to the application and amendments thereto on file at the office of the Commission for a statement of the facts in support thereof which are summarized as follows:

General, a Delaware corporation, directly and through its subsidiary companies, is engaged in the development of communities and real estate subdivisions in the State of Florida, the principal developments being at Port Charlotte, Port St. Lucie, Port Malabar and Port St. John. General has 22 subsidiary companies, of which Utilities is the sole public-utility company. The subsidiary companies, other than Utilities, conduct various activities related to said real estate developments. At December 31, 1962, the consolidated assets of General and its subsidiary companies aggregated $193,784,929. For the year then ended the consolidated sales totaled $54,245,895; after all expenses and taxes a consolidated net loss of $515,892 was reported.

Utilities, a Florida corporation, furnishes water, sewerage, and gas service to the residents of General's communities and real estate subdivisions and, to a minor extent, to other customers. The gas service consists of the distribution of liquefied petroleum gas through pipes. At December 31, 1962, the assets of Utilities less depreciation reserves totaled $5,958,426; its total plant and property less depreciation reserves amounted to $5,336,263, of which the plant devoted to the distribution of gas amounted to $114,625. For the year 1962, the total revenues of Utilities were $1,103,329, of which $234,562 were gas revenues. All of the outstanding common stock of Utilities is owned by General.

Notice is further given that any interested person may, not later than December 31, 1963, request in writing that a hearing be held in respect of such matter, stating the nature of his interest, the reasons for such request, and the issues of fact or law which he desires to controvert; or he may request that he be notified should the Commission order a hearing in respect thereof. Any such request should be addressed: Secretary, Securities and Exchange Commission, Washington, D.C., 20549. A copy of such request should be served personally or by mail (air mail if the person being served is located more than 500 miles from the point of mailing) upon the applicants at the above-stated address, and proof of service (by affidavit or, in case of an attorney at law, by certificate) should be filed contemporaneously with the request. At any time after said date the application, as amended, or as it may be further amended, may be granted; or the Commission may take such other action as it may deem appropriate.

For the Commission (pursuant to delegated authority).

[SEAL] ORVAL L. DUBOIS, *Secretary.*

[F.R. Doc. 63-12961; Filed, Dec. 13, 1963; 8:45 a.m.]

DEPARTMENT OF LABOR

Wage and Hour Division

CERTIFICATES AUTHORIZING EMPLOYMENT OF LEARNERS AT SPECIAL MINIMUM RATES

Notice is hereby given that pursuant to section 14 of the Fair Labor Standards Act of 1938 (52 Stat. 1060, as amended, 29 U.S.C. 201 et seq.), and Administrative Order No. 579 (28 F.R. 11524) the firms listed in this notice have been issued special certificates authorizing the employment of learners at hourly wage rates lower than the minimum wage rates otherwise applicable under section 6 of the act. The effective and expiration dates, occupations, wage rates, number or proportion of learners and learning periods, for certificates issued under general learner regulations (29 CFR 522.1 to 522.9), and the principal product manufactured by the employer are as indicated below. Conditions provided in certificates issued under the supplemental industry regulations cited in the captions below are as established in those regulations.

Apparel Industry Learner Regulations (29 CFR 522.1 to 522.9, as amended, and 29 CFR 522.20 to 522.25, as amended).

The following learner certificates were issued authorizing the employment of 10 percent of the total number of factory production workers for normal labor turnover purposes. The effective and expiration dates are indicated.

Alabama Textile Products Corp., Andalusia, Ala.; effective 12-1-63 to 11-30-64 (men's dress and sport shirts and work pants).

Alabama Textile Products Corp., Troy, Ala.; effective 12-1-63 to 11-30-64 (men's dress shirts).

The Andala Co., Andalusia, Ala.; effective 12-1-63 to 11-30-64 (men's work shirts and pants).

Anthracite Shirt Co., 1 South Franklin Street, Shamokin, Pa.; effective 12-1-63 to 11-30-64 (men's and boys' dress and sport shirts).

Bannon Mills, Inc., Seventh and Union Streets, Lebanon, Pa.; effective 11-27-63 to 11-26-64 (infants' and children's outerwear—pants, shirts, and creepers).

Adam H. Bartel Co., Richmond, Ind.; effective 11-20-63 to 11-19-64 (men's, women's, and children's dungarees, and men's overalls).

Bayly Manufacturing Co., 2000 Arapahoe Street, Denver, Colo.; effective 11-30-63 to 11-29-64 (men's denim overalls and work jackets).

Bestform Foundations of Windber, Inc., Stockholm Avenue, Windber, Pa.; effective 12-9-63 to 12-8-64 (women's brassieres and girdles).

Blue Bell, Inc., Luray, Va.; effective 12-1-63 to 11-30-64 (ladies', girls', men's and boys' dungarees).

Byrds Manufacturing Corp., Byrdstown, Tenn.; effective 11-29-63 to 11-28-64 (ladies', men's, and boys' shirts).

Corman & Wasserman, Inc., 1220 Curtain Avenue, Baltimore, Md.; effective 12-3-63 to 12-2-64 (men's trousers).

Cowden Manufacturing Co., 112 Hamilton Avenue, Lancaster, Ky.; effective 11-28-63 to 11-27-64 (men's overalls, dungarees, and outerwear jackets).

Duti-Duds, Inc., 300 Monticello Avenue, Lynchburg, Va.; effective 12-2-63 to 12-1-64 (women's cotton nylon and dacron uniforms for maids and nurses).

Florence Manufacturing Co., Inc., 1104 Chase Avenue, Florence, S.C.; effective 11-29-63 to 11-28-64 (ladies' dresses).

Gattman Sportswear, Inc., Gattman, Miss.; effective 11-27-63 to 11-26-64 (men's dress slacks).

Hartsville Manufacturing Co., Inc., Hartsville, S.C.; effective 11-26-63 to 11-25-64 (ladies' dresses).

Henson Garment Co., 450 East Hancock Avenue, Athens, Ga.; effective 11-19-63 to

11–18–64 (men's work jackets and pants, and shirts).

The Hercules Trouser Co., Manchester, Ohio; effective 12–1–63 to 11–30–64 (men's and boys' single pants).

Kenrose Manufacturing Co., Inc., Radford, Va.; effective 12–12–63 to 12–11–64 (women's dresses).

The Manhattan Shirt Co., 461 West Cherry Street, Jesup, Ga.; effective 11–25–63 to 11–24–64 (men's sport shirts).

The Manhattan Shirt Co., Poplar Hill Avenue and Calvert Street, 416 East Main Street, Salisbury, Md.; effective 12–1–63 to 11–30–64 (men's dress shirts and ladies' shirts).

The Manhattan Shirt Co., U.S. Bypass No. 29 and No. 70, Lexington, N.C.; effective 12–1–63 to 11–30–64 (ladies' shirts and men's sport shirts).

Mammoth Cave Garment Co., 237 Broadway, Cave City, Ky.; effective 12–11–63 to 12–10–64 (men's and boys' dungarees).

Nevada Manufacturing Co., Pine Bluff, Ark.; effective 11–25–63 to 11–24–64 (men's work clothing and washable service apparel).

Pittston Apparel Co., East and Tompkins Streets, Pittston, Pa.; effective 12–8–63 to 12–7–64 (women's girdles and brassieres).

Pool Manufacturing Co., 1601 South Montgomery Street, Sherman, Tex.; effective 12–2–63 to 12–1–64 (men's work shirts and pants).

Publix Tenn. Corp., Huntingdon, Tenn.; effective 12–1–63 to 11–30–64 (men's and boys' sport shirts).

I. Schneierson & Sons, Inc., 460 Globe Street, Fall River, Mass.; effective 12–1–63 to 11–30–64. Ten percent of the total number of factory production workers engaged in the production of women's and children's woven nightwear and underwear for normal labor turnover purposes (women's and children's woven underwear, slips and sleepwear).

H. W. Sherman Corp., C. A. Neuburger Co. Div., 913 South Main Street, Oshkosh, Wis.; effective 11–25–63 to 11–24–64. Learners may not be employed at special minimum wage rates in the production of suits, skirts and coat-type tailored jackets (misses' and ladies' pants and blouses).

Spartans Industries, Inc., Dunlap, Tenn.; effective 11–21–63 to 11–20–64 (ladies' blouses).

States Nitewear Manufacturing Co., Inc., Healy and Bates Streets, New Bedford, Mass.; effective 12–1–63 to 11–30–64 (ladies' sleepwear).

Troy Textiles, Inc., Troy, Ala.; effective 11–24–63 to 11–23–64 (men's sport shirts).

The following learner certificates were issued for normal labor turnover purposes. The effective and expiration dates and the number of learners authorized are indicated.

Armored Garments, Inc., 223 Cabin Road, Spruce Pine, N.C.; effective 12–1–63 to 11–30–64; 10 learners (boys' dungarees).

Blue Bell, Inc., Elkton, Va.; effective 11–29–63 to 11–28–64; 10 learners (men's and boys' dungarees).

Blue Bell, Inc., Mount Jackson, Va.; effective 12–1–63 to 11–30–64; 10 learners (misses', boys', and ladies' dungarees).

Blue Bell, Inc., Shenandoah, Va.; effective 11–29–63 to 11–28–64; 10 learners (men's, boys', ladies' and girls' dungarees).

Checotah Manufacturing Co., Post Office Box 326, Checotah, Okla.; effective 11–27–63 to 11–26–64; 10 learners (children's pedalpushers and shorts and women's pedalpushers).

Dushore Lingerie Co., Inc., Box 231, Cherry Street, Dushore, Pa.; effective 11–25–63 to 11–24–64; 10 learners (women's sleepwear).

Gloucester Pants Co., Inc., 377 Main Street, Gloucester, Mass.; effective 12–1–63 to 11–30–64; 10 learners (ladies', men's, and boys' slacks).

Morristown Manufacturing Co., Inc., 1730 West First North Street, Morristown, Tenn.; effective 11–23–63 to 11–22–64; 10 learners (ladies' dresses).

Paul Bruce Manufacturing Co., Inc., Scotland Neck, N.C.; effective 11–27–63 to 11–26–64; 10 learners (women's sleepwear).

Prairie Manufacturing Co., East Prairie, Mo.; effective 12–5–63 to 12–4–64; 10 learners (men's and boys' semidress pants).

Sorbeau Juvenile Manufacturing Co., 821 Central Avenue, Dubuque, Iowa; effective 12–1–63 to 11–30–64; 10 learners (infants' pajamas and playwear).

The following learner certificates were issued for plant expansion purposes. The effective and expiration dates and the number of learners authorized are indicated.

Aalfs Manufacturing Co., Spencer, Iowa; effective 11–18–63 to 5–17–64; 10 learners (boys' denim jeans).

The Dantan Co., Inc., Rankin Street, Dumas, Ark.; effective 12–2–63 to 6–1–64; 35 learners (ladies' pedalpushers, bermudas, and slim jims).

Kingstree Industries, Inc., 204 Hampton Avenue, Kingstree, S.C.; effective 12–1–63 to 5–31–64; 30 learners (ladies' slacks, pedalpushers, capris, and shorts).

Loris Manufacturing Co., Loris, S.C.; effective 11–28–63 to 5–27–64; 60 learners (ladies' blouses).

Punxy Sportswear Co., Inc., Walnut Street, Punxsutawney, Pa.; effective 11–25–63 to 5–24–64; 40 learners (ladies' pants and blouses).

Roanoke Manufacturing Co., Anniston, Ala.; effective 11–25–63 to 5–24–64; 50 learners (men's sport shirts).

Glove Industry Learner Regulations (29 CFR 522.1 to 522.9, as amended, and 29 CFR 522.60 to 522.65, as amended).

Warren Industries, Inc., 9 Broad Street, Glens Falls, N.Y.; effective 11–29–63 to 11–28–64; 10 learners for normal labor turnover purposes (ladies' double woven nylon cotton gloves).

Hosiery Industry Learner Regulations (29 CFR 522.1 to 522.9, as amended, and 29 CFR 522.40 to 522.43, as amended).

Auburn Dyeing and Finishing Co., Auburn, Ky.; effective 11–29–63 to 11–28–64; 5 learners for normal labor turnover purposes (full-fashioned).

Francis-Louise Full Fashion Mills, Inc., Valdese, N.C.; effective 11–28–63 to 11–27–64; 5 percent of the total number of factory production workers for normal labor turnover purposes (full-fashioned and seamless).

Magnet Mills, Inc., Cullom Street, Clinton, Tenn.; effective 11–29–63 to 11–28–64; 5 percent of the total number of factory production workers for normal labor turnover purposes (seamless).

Wigwam Mills, Inc., Sheboygan, Wis.; effective 12–5–63 to 12–4–64; 5 percent of the total number of factory production workers for normal labor turnover purposes (seamless).

Knitted Wear Industry Learner Regulations (29 CFR 522.1 to 522.9, as amended, and 29 CFR 522.30 to 522.35, as amended).

I. Schneierson & Sons, Inc., 460 Globe Street, Fall River, Mass.; effective 12–1–63 to 11–30–64; 5 percent of the total number of factory production workers engaged in the production of women's and children's knitted underwear and sleepwear for normal labor turnover purposes (women's and children's underwear, slips, and sleepwear).

Slumber Sue, Inc., 34 Green Street, Woodbridge, N.J.; effective 12–2–63 to 12–1–64; five learners for normal labor turnover purposes (women's pajamas and nightgowns).

Each learner certificate has been issued upon the representations of the employer which, among other things, were that employment of learners at special minimum rates is necessary in order to prevent curtailment of opportunities for employment, and that experienced workers for the learner occupations are not available. Any person aggrieved by the issuance of any of these certificates may seek a review or reconsideration thereof within fifteen days after publication of this notice in the FEDERAL REGISTER pursuant to the provisions of 29 CFR 522.9. The certificates may be annulled or withdrawn, as indicated therein, in the manner provided in 29 CFR Part 528.

Signed at Washington, D.C., this 6th day of December 1963.

ROBERT G. GRONEWALD,
Authorized Representative of the Administrator.

[F.R. Doc. 63–12960; Filed, Dec. 13, 1963; 8:45 a.m.]

INTERSTATE COMMERCE COMMISSION

[Notice No. 911]

MOTOR CARRIER TRANSFER PROCEEDINGS

DECEMBER 11, 1963.

Synopses of orders entered pursuant to section 212(b) of the Interstate Commerce Act, and rules and regulations prescribed thereunder (49 CFR Part 179), appear below:

As provided in the Commission's special rules of practice any interested person may file a petition seeking reconsideration of the following numbered proceedings within 20 days from the date of publication of this notice. Pursuant to section 17(8) of the Interstate Commerce Act, the filing of such a petition will postpone the effective date of the order in that proceeding pending its disposition. The matters relied upon by petitioners must be specified in their petitions with particularity.

No. MC–FC 66484. By order of December 10, 1963, the Transfer Board approved the transfer and substitution of Lionel A. Lajoie, Jr., doing business as L. A. Lajoie Transportation Co., Old Turnpike Road, Oakham, Mass., as applicant in the "claimed grandfather rights" proceeding seeking the issuance of a Certificate of Registration, in No. MC 99167 (Sub-No. 1) filed February 12, 1963, covering the transportation of general commodities within Massachusetts, conducted under the former second proviso by Lorenzo F. Blackmer, doing business as Blackmer Brothers Express, North Street, Hardwick, Mass., under No. MC 99167.

[SEAL] HAROLD D. MCCOY,
Secretary.

[F.R. Doc. 63–12970; Filed, Dec. 13, 1963; 8:46 a.m.]

FOURTH SECTION APPLICATIONS FOR RELIEF

DECEMBER 11, 1963.

Protests to the granting of an application must be prepared in accordance with Rule 1.40 of the general rules of practice (49 CFR 1.40) and filed within 15 days from the date of publication of this notice in the FEDERAL REGISTER.

LONG-AND-SHORT HAUL

FSA 38696: *Aluminum ingots from Rooseveltown, N.Y.* Filed by Traffic Executive Association-Eastern Railroads, agent (E.R. 2694), for interested rail carriers. Rates on aluminum ingots and kindred articles, in carloads, from Rooseveltown, N.Y., to Chicago, Ill.

Grounds for relief: Truck-water-truck competition.

Tariff: Supplement 285 to Traffic Executive Association-Eastern Railroads, agent, tariff I.C.C. A–1116.

FSA 38697: *Bagging or cloth from North Atlantic ports.* Filed by Traffic Executive Association-Eastern Railroads, agent (E.R. 2693), for interested rail carriers. Rates on bagging or cloth, burlap, gunny, ixtle (istle), jute or sisal, noibn, in carloads, from North Atlantic ports to Ordill, Ill.

Grounds for relief: market competition.

Tariffs: Supplement 47 to Traffic Executive Association-Eastern Railroads, agent, tariff I.C.C. C–236 and other schedules named in the application.

FSA 38698: *Common salt from and to official territory points.* Filed by Traffic Executive Association-Eastern Railroads, agent (E.R. No. 2691), for interested rail carriers. Rates on common salt (sodium chloride), as described in the application, from points in official territory, also Ojibway and Sarnia, Ont., Canada, to points in Illinois Freight Association territory, also northern Illinois, southern Wisconsin and extended zone "C".

Grounds for relief: carrier competition.

Tariffs: Supplements 15 and 56 to Traffic Executive Association-Eastern Railroads, agent, tariffs I.C.C. C–390 and C–301, respectively.

FSA 38699: *Potassium (potash) caustic from Calvert, Ky.* Filed by O. W. South, Jr., agent (A4415), for and on behalf of Illinois Central Railroad Co., Louisville and Nashville Railroad Company and the New York Central Railroad Company. Rates on potassium (potash) caustic, in tank-car loads, from Calvert, Ky., to Cleveland, Ohio.

Grounds for relief: market competition.

Tariff: Supplement 35 to Southern Freight Association, agent, tariff I.C.C. S–263.

FSA 38700: *Lumber from southwestern territory.* Filed by Southwestern Freight Bureau, agent (No. B–8483), for interested rail carriers. Rates on lumber and related articles, in carloads, from points in southwestern territory to points in Illinois on the Illinois Central Railroad.

Grounds for relief: carrier competition.

Tariff: Supplement 68 to Southwestern Freight Bureau, agent, tariff I.C.C. 4506.

By the Commission.

[SEAL] HAROLD D. McCOY, *Secretary.*

[F.R. Doc. 63–12969; Filed, Dec. 13, 1963; 8:46 a.m.]

CUMULATIVE CODIFICATION GUIDE—DECEMBER

The following numerical guide is a list of the parts of each title of the Code of Federal Regulations affected by documents published to date during December.

1 CFR — Page

CFR CHECKLIST ... 12791

3 CFR

PROCLAMATIONS:
2761A ... 13247
3019 ... 12785
3460 ... 12785
3548 ... 12785
3562 ... 12785
3563 ... 12895
3564 ... 13247

EXECUTIVE ORDERS:
Feb. 25, 1919 ... 13307
6964 ... 13306
7951 ... 13306
11129 ... 12787
11130 ... 12789
11131 ... 13485
11132 ... 13533

4 CFR
33 ... 12923
34 ... 12924

5 CFR
213 ... 12901, 13277, 13437, 13535
550 ... 13437

6 CFR
321 ... 13335
322 ... 13343
323 ... 13343
327 ... 13335
341 ... 13355
392 ... 13335

7 CFR
29 ... 13277
33 ... 12901
215 ... 12791
301 ... 12792
318 ... 13280, 13281, 13391
717 ... 13249
722 ... 13282, 13291, 13535, 13538
730 ... 12792, 13254
817 ... 13356
847 ... 13292
905 ... 13538–13540
907 ... 13292, 13540, 13541
909 ... 13541
910 ... 13293, 13487, 13542
925 ... 13543
945 ... 13543
947 ... 13543
958 ... 12851
971 ... 13487
989 ... 13544
1002 ... 12902
1003 ... 13357
1004 ... 12922
1005 ... 12922
1015 ... 12922
1016 ... 13357
1096 ... 12793
1106 ... 12851
1132 ... 13448
1400 ... 13293
1421 ... 13293, 13294, 13391
1427 ... 12794
1434 ... 13297
1464 ... 13391
1482 ... 12923

PROPOSED RULES:
29 ... 13315
811 ... 13363
984 ... 13505
993 ... 12870, 13505
999 ... 12827, 13267
1193 ... 13460

9 CFR
74 ... 13544

PROPOSED RULES:
74 ... 13549

12 CFR
218 ... 13437
PROPOSED RULES:
523 ... 13549

13 CFR
127 ... 13545

PROPOSED RULES:
107 ... 13267
121 ... 13320

14 CFR
Ch. I ... 12924
1 ... 12924, 13394
9 ... 13394
9a ... 13395
71 [New] ... 12925, 13297, 13357–13359, 13396, 13438
73 [New] ... 13297
95 [New] ... 13438
97 [New] ... 12853, 13397, 13442
297 ... 12864
301 ... 13298
507 ... 12926

PROPOSED RULES:
14 ... 13460
35 [New] ... 13460
71 [New] ... 12938, 12940–12944, 13319, 13366, 13368, 13462, 13463, 13465.
75 [New] ... 12944, 13319
77 [New] ... 12828
288 ... 13460
298 ... 13311
507 ... 12945
514 ... 13549

16 CFR
13 ... 12795, 12926, 12927, 13392, 13449

17 CFR

PROPOSED RULES:
240 ... 12829

18 CFR
2 ... 12865, 12866, 13547

18 CFR—Continued

Page

11 ... 12795
157 ... 12866
PROPOSED RULES:
2 ... 12945, 13505
10 ... 13506
16 ... 13505

19 CFR

4 ... 13359
6 ... 13546
8 ... 13546
10 ... 13546
Appendix A ... 13393
PROPOSED RULES:
1 ... 13548
4 ... 13311
12 ... 12870
24 ... 12870

20 CFR

345 ... 13360
614 ... 12928

21 CFR

8 ... 13488
20 ... 13448
120 ... 12867
121 ... 12928, 13360, 13488
141d ... 13360
146a ... 12868
146d ... 13449
146d ... 13360
PROPOSED RULES:
120 ... 12938
146 ... 13505

24 CFR

207 ... 13304
213 ... 13305
220 ... 13305
221 ... 13305
231 ... 13305
232 ... 13306
803 ... 13306

25 CFR

PROPOSED RULES:
21 ... 13548
22 ... 13548
31 ... 13548
32 ... 13548

26 CFR

1 ... 12796, 12817, 13450
48 ... 12928
49 ... 12928
250 ... 12930
PROPOSED RULES:
1 ... 12824

29 CFR

526 ... 13489
PROPOSED RULES:
526 ... 12938
545 ... 13312
681 ... 13312

30 CFR

Page

501 ... 12868

32 CFR

252 ... 12868
561 ... 12937, 13361
563 ... 13400
887 ... 13263

33 CFR

82 ... 13503

38 CFR

2 ... 13489
3 ... 13362, 13489
36 ... 13489

39 CFR

31 ... 12936

41 CFR

9–5 ... 13490
9–7 ... 13264
50–202 ... 12867

42 CFR

51 ... 12937

43 CFR

101 ... 12852, 13362
PROPOSED RULES:
1 ... 13504
PUBLIC LAND ORDERS:
797 ... 13507
800 ... 13508
913 ... 13508
1459 ... 12821
2203 ... 13307
3257 ... 13307
3263 ... 13265
3275 ... 12821
3276 ... 12936
3277 ... 13306
3278 ... 13306
3279 ... 13306
3280 ... 13307
3281 ... 13307
3282 ... 13307
3283 ... 13307
3284 ... 13307
3285 ... 13308
3286 ... 13308
3287 ... 13308
3288 ... 13309
3289 ... 13309
3290 ... 13309

44 CFR

184 ... 13451, 13547

45 CFR

500 ... 13495
501 ... 13496
531 ... 13498
540 ... 13499

45 CFR—Continued

Page

541 ... 13499
542 ... 13500
543 ... 13500
560 ... 13501
580 ... 13501

46 CFR

10 ... 13502
38 ... 13502
40 ... 13502
146 ... 12820
309 ... 12897
402 ... 12852
PROPOSED RULES:
523 ... 13369
527 ... 12870

47 CFR

0 ... 12821
3 ... 13572
4 ... 13572
6 ... 13002
21—66 ... 13002
73 ... 13572
74 ... 13572
PROPOSED RULES:
3 ... 13267
7 ... 13370
8 ... 13370

49 CFR

1 ... 12821
77 ... 13265
91 ... 13400
120 ... 13310

50 CFR

32 ... 12852, 13266
33 ... 13454–13459

Announcing: **Volume 76A**

UNITED STATES STATUTES AT LARGE

Containing

THE CANAL ZONE CODE

Enacted as Public Law 87–845 during the Second Session of the Eighty-seventh Congress (1962)

Price: $5.75

Published by Office of the Federal Register, National Archives and Records Service, General Services Administration

Order from Superintendent of Documents, Government Printing Office, Washington, D.C., 20402

Pages 13571–13735

PART II

THE NATIONAL ARCHIVES
LITTERA SCRIPTA MANET
OF THE UNITED STATES
1934

FEDERAL REGISTER

VOLUME 28 NUMBER 242

Washington, Saturday, December 14, 1963

FEDERAL COMMUNICATIONS COMMISSION

Reorganization and Revision of Chapter

Subchapter C—Broadcast Radio Services

Title 47—TELECOMMUNICATION

Chapter I—Federal Communications Commission

REORGANIZATION AND REVISION OF CHAPTER

Subchapter C

The Commission having under consideration the need for editorial revision of its rules and regulations, and the opportunity for such revision afforded by the reprinting of Title 47 of the Code of Federal Regulations; and

It appearing, that the needs of the public and of the Commission will be served by editorial revision of the Commission's rules and regulations; and

It further appearing, that Subchapter A was published November 22, 1963, 28 F.R. 12386, and Subchapter B on December 5, 1963, 28 F.R. 13001, that Subchapter C is ready for publication now, and that Subchapter D will be published at a later date; and

It further appearing that numerous provisions of the rules and regulations have been rearranged and renumbered and that cross-reference tables for the entire chapter were published November 22, 1963, 28 F.R. 12386; and

It further appearing, that the changes effected by revision of the rules are editorial in nature, and hence that compliance with the notice, procedural, and effective date provisions of section 4 of the Administrative Procedure Act is unnecessary; and

It further appearing, that authority for revision of the rules and regulations is set forth in sections 4(i), 5(d), and 303(r) of the Communications Act of 1934, as amended, and in § 0.261(a) of the Commission's rules;

It is ordered, This 13th day of December 1963, effective December 21, 1963, that Parts 3 and 4 of the rules and regulations of the Federal Communications Commission are redesignated Parts 73 and 74, and editorially revised to read as set forth below; and

It is further ordered, That this order shall not be construed as advancing the effective date of any rule change previously adopted by the Commission.

Released: December 16, 1963.

FEDERAL COMMUNICATIONS COMMISSION,
[SEAL] BEN F. WAPLE,
Secretary.

SUBCHAPTER C—BROADCAST RADIO SERVICES

PART 73—RADIO BROADCAST SERVICES

Subpart A—Standard Broadcast Stations

DEFINITIONS

Sec.
73.1 Standard broadcast station.
73.2 Standard broadcast band.
73.3 Standard broadcast channel.
73.4 Dominant station.
73.5 Secondary station.
73.6 Daytime.
73.7 Nighttime.
73.8 Sunrise and sunset.
73.9 Broadcast day.
73.10 Experimental period.
73.11 Service areas.
73.12 Portable transmitter.
73.13 Auxiliary transmitter.
73.14 Technical definitions.
73.15 NARBA and the U.S./Mexican Agreement.

ADMINISTRATIVE PROCEDURE

73.17 Cross reference.
73.18 Notification of filing of applications.

ALLOCATION OF FACILITIES; AUTHORIZATIONS

73.21 Classes of standard broadcast channels and station.
73.22 Assignment of Class II–A stations.
73.23 Time of operation of the several classes of stations.
73.24 Broadcast facilities; showing required.
73.25 Clear channels; Classes I and II stations.
73.26 Regional channels: Classes III–A and III–B stations.
73.27 Local channels: Class IV stations.
73.28 Assignment of stations to channels.
73.29 Class IV stations on regional channels.
73.30 Station location and program origination.
73.31 Authority to move main studio.
73.32 Special experimental authorizations.
73.33 Antenna systems; showing required.
73.34 Normal license period.
73.35 Multiple ownership.
73.36 Special field test authorization.
73.37 Minimum separation between stations.
73.38 Limited time operation.

EQUIPMENT

73.39 Indicating instruments — specifications.
73.40 Transmitter; design, construction, and safety of life requirements.
73.41 Maximum rated carrier power; tolerances.
73.42 Maximum rated carrier power; how determined.
73.43 Changes in equipment; authority for.
73.44 Other changes in equipment.
73.45 Radiating system.
73.46 Transmitter.
73.47 Equipment performance measurements.
73.48 Acceptability of broadcast transmitters for licensing.
73.49 Requirements for approval of frequency monitors.
73.50 Requirements for approval of modulation monitors.

TECHNICAL OPERATION

73.51 Operating power; how determined.
73.52 Operating power; indirect measurement.
73.54 Operating power; direct measurement.
73.55 Modulation.
73.56 Modulation monitors.
73.57 Operating power; maintenance of.
73.58 Indicating instruments.
73.59 Frequency tolerance.
73.60 Frequency monitor.
73.61 New equipment; restrictions.
73.62 Automatic frequency control equipment; authorization required.
73.63 Auxiliary transmitter.
73.64 Alternate main transmitters.
73.65 Antenna structure, marking and lighting.

REMOTE CONTROL

73.66 Remote control authorization.
73.67 Remote control operation.
73.68 Remote control renewal application.

OPERATION

73.71 Minimum operating schedule.
73.72 Operation during experimental period.
73.73 Specified hours.
73.74 Sharing time.
73.75 Sharing time; equivalence of day and night hours.
73.76 Sharing time; experimental period.
73.77 Sharing time; departure from regular schedule.
73.78 Sharing time stations; notification to Commission.
73.79 License to specify sunrise and sunset hours.
73.80 Secondary station; filing of operating schedule.
73.81 Secondary station; failure to reach agreement.
73.82 Departure from schedule; material violation.
73.83 Local standard time.
73.84 Daylight saving time.
73.85 Changes in time; agreement between licensees.
73.86 Local standard time; license provisions.
73.87 Program transmissions prior to local sunrise.
73.88 Blanketing interference.
73.89 Use of frequency and modulation monitors at auxiliary transmitters.
73.90 Emergency weather warnings.
73.91 Discontinuance of operation.
73.92 Station and operator licenses; posting of.
73.93 Operator requirements.
73.95 Equipment tests.
73.96 Program tests.
73.97 Station inspection.
73.98 Operation during emergency.

OTHER OPERATING REQUIREMENTS

73.111 General requirements relating to logs.
73.112 Program log.
73.113 Operating log.
73.114 Maintenance log.
73.115 Retention of logs.
73.116 Availability of logs and records.
73.117 Station identification.
73.118 Mechanical reproductions.
73.119 Sponsored programs; announcement of.
73.120 Broadcasts by candidates for public office.
73.121 Rebroadcast.
73.122 Lotteries.

LICENSING POLICIES

73.131 Exclusive affiliation of station.
73.132 Territorial exclusivity.
73.133 Term of affiliation.
73.134 Option time.
73.135 Right to reject programs.
73.136 Network ownership of stations.
73.137 Dual network operation.
73.138 Control by networks of station rates.
73.139 Special rules relating to contracts providing for reservation of time upon sale of a station.

DATA AND MEASUREMENTS

73.150 Data required with applications for directional antenna systems.
73.151 Field intensity measurements to establish performance of directional antennas.
73.152 Field intensity measurements in support of applications or evidence at hearings.

STANDARD BROADCAST TECHNICAL STANDARDS

73.181 Introduction.
73.182 Engineering standards of allocation.
73.183 Groundwave signals.
73.184 Groundwave field intensity charts.
73.185 Computation of interfering signal from a directional antenna.
73.186 Field intensity measurements in allocation; establishment of effective field at one mile.
73.187 Limitation on daytime radiation.
73.188 Location of transmitters.

Sec.
73.189 Minimum antenna heights or field intensity requirements.
73.190 Engineering charts.

Subpart B—FM Broadcast Stations

CLASSIFICATION OF FM BROADCAST STATIONS AND ALLOCATION OF FREQUENCIES

73.201 Numerical designation of FM broadcast channels.
73.202 Table of Assignments.
73.203 Availability of channels.
73.204 International agreements and other restrictions on use of channels.
73.205 Zones.
73.206 Classes of commercial channels, and stations operating thereon.
73.207 Minimum mileage separations between co-channel and adjacent-channel stations on commercial channels.
73.208 Reference points and distance computations.
73.209 Protection from interference.
73.210 Station location and program origination.
73.211 Power and antenna height requirement.
73.212 Administrative changes in authorization.

ADMINISTRATIVE PROCEDURE

73.214 Cross reference.
73.215 Notification of filing of applications.
73.216 Equipment tests.
73.217 Program tests.
73.218 Normal license period.

LICENSING POLICIES

73.231 Exclusive affiliation of station.
73.232 Territorial exclusivity.
73.233 Term of affiliation.
73.234 Option time.
73.235 Right to reject programs.
73.236 Network ownership of stations.
73.237 Dual network operation.
73.238 Control by networks of station rates.
73.239 Use of common antenna site.
73.240 Multiple ownership.
73.241 Special rules relating to contracts providing for reservation of time upon sale of a station.

EQUIPMENT

73.250 Acceptability of broadcast transmitters for licensing.
73.252 Frequency monitor.
73.253 Modulation monitor.
73.254 Required transmitter performance.
73.255 Auxiliary transmitter.
73.256 Alternate main transmitters.
73.257 Changes in equipment and antenna system.
73.258 Indicating instruments.

TECHNICAL OPERATION AND OPERATORS

73.261 Time of operation.
73.262 Experimental operation.
73.263 Station inspection.
73.264 Station and operator licenses; posting of.
73.265 Operator requirements.
73.266 Facsimile broadcasting and multiplex transmission.
73.267 Operating power; determination and maintenance of.
73.268 Modulation.
73.269 Frequency tolerance.
73.270 Antenna structure, marking and lighting.
73.271 Discontinuance of operation.
73.273 Emergency antenna.
73.274 Remote control authorization.
73.275 Remote control operation.

OTHER OPERATING REQUIREMENTS

73.281 General requirements relating to logs.
73.282 Program log.
73.283 Operating log.
73.284 Maintenance log.
73.285 Retention of logs.
73.286 Availability of logs and records.
73.287 Station identification.
73.288 Mechanical reproductions.
73.289 Sponsored programs; announcement of.
73.290 Broadcasts by candidates for public office.
73.291 Rebroadcast.
73.292 Lotteries.
73.293 Subsidiary Communications Authorization.
73.294 Nature of the SCA.
73.295 Operation under the SCA.
73.296 Emergency weather warnings.
73.297 Stereophonic broadcasting.
73.298 Operation during emergency.

FM TECHNICAL STANDARDS

73.310 Definitions.
73.311 Field strength contours.
73.312 Topographic data.
73.313 Prediction of coverage.
73.315 Transmitter location.
73.316 Antenna systems.
73.317 Transmitters and associated equipment.
73.318 Facsimile: engineering standards.
73.319 Subsidiary communications multiplex operations: engineering standards.
73.320 Indicating instruments—specifications.
73.321 Auxiliary transmitters.
73.322 Stereophonic transmission standards.
73.330 Frequency and modulation monitors at auxiliary transmitters.
73.331 Requirements for type approval of frequency monitors.
73.332 Requirements for type approval of modulation monitors.
73.333 Engineering charts.

Subpart C—Noncommercial Educational FM Broadcast Stations

CLASSIFICATION OF STATIONS AND ALLOCATION OF FREQUENCIES

73.501 Channels available for assignment.
73.502 State-wide plans.
73.503 Licensing requirements and service.
73.504 Zones, classes of stations, use of channels, facilities, and minimum mileage separation between stations.
73.505 Standards of good engineering practice.

ADMINISTRATIVE PROCEDURE

73.514 Cross reference.
73.515 Notification of filing of applications.
73.516 Equipment tests.
73.517 Program tests.
73.518 Normal license period.

EQUIPMENT

73.550 Acceptability of broadcast transmitters for licensing.
73.552 Frequency monitor.
73.553 Modulation monitor.
73.554 Transmitter performance.
73.555 Auxiliary transmitter.
73.556 Alternate main transmitters.
73.557 Changes in equipment and antenna system.
73.558 Indicating instruments.

TECHNICAL OPERATION AND OPERATORS

73.561 Operating schedule.
73.562 Experimental operation.
73.563 Station inspection.
73.564 Station and operator licenses; posting of.
73.565 Operator requirements.
73.566 Facsimile broadcasting and multiplex transmission.
73.567 Operating power; determination and maintenance of.
73.568 Modulation.
73.569 Frequency tolerance.
73.570 Antenna structure, marking and lighting.
73.571 Discontinuance of operation.
73.572 Remote control authorization.
73.573 Remote control operation.

OTHER OPERATING REQUIREMENTS

73.581 General requirements relating to logs.
73.582 Program log.
73.583 Operating log.
73.584 Maintenance log.
73.585 Retention of logs.
73.586 Availability of logs and records.
73.587 Station identification.
73.588 Mechanical reproductions.
73.590 Broadcasts by candidates for public office.
73.591 Rebroadcast.
73.593 Subsidiary Communications Authorizations.
73.594 Nature of the SCA.
73.595 Operation under the SCA.
73.596 Stereophonic broadcasting.
73.597 Operation during emergency.

Subpart D—[Reserved]

Subpart E—Television Broadcast Stations

GENERAL

73.601 Scope of subpart.
73.602 Other pertinent rules.
73.603 Numerical designation of television channels.

CHANNEL UTILIZATION

73.606 Table of Assignments.
73.607 Availability of channels.
73.608 International agreements.
73.609 Zones.
73.610 Separations.
73.611 Reference points and distance computations.
73.612 Protection from interference.
73.613 Main studio location.
73.614 Power and antenna height requirements.
73.615 Administrative changes in authorizations.

APPLICATIONS AND AUTHORIZATIONS

73.620 Cross reference.
73.621 Noncommercial educational stations.
73.622 Applications for sharing of television channels.
73.623 Notification of filing of applications.
73.628 Equipment tests.
73.629 Program tests.
73.630 Normal license period.
73.632 Emergency weather warnings.
73.635 Use of common antenna site.
73.636 Multiple ownership.
73.637 Alternate main transmitters.
73.638 Auxiliary transmitter.
73.639 Changes in equipment and antenna system.
73.640 Acceptability of broadcast transmitters for licensing.

GENERAL OPERATING REQUIREMENTS

73.651 Time of operation.
73.652 Station identification.
73.653 Mechanical reproductions.
73.654 Sponsored programs, announcement of.
73.655 Rebroadcast.
73.656 Lotteries.
73.657 Broadcasts by candidates for public office.
73.658 Affiliation agreements.
73.659 Special rules relating to contracts providing for reservation of time upon sale of a station.
73.660 Station license, posting of.
73.661 Operator requirements.
73.662 Antenna structure, marking and lighting.
73.665 Station inspection.
73.666 Experimental operation.
73.667 Discontinuance of operation.

Sec.
73.668 Frequency tolerance.
73.669 General requirements relating to logs.
73.670 Program log.
73.671 Operating log.
73.672 Maintenance log.
73.673 Retention of logs.
73.674 Availability of logs and records.
73.675 Operation during emergency.
73.676 Remote control operation.

TV TECHNICAL STANDARDS

73.681 Definitions.
73.682 Transmission standards and changes.
73.683 Field intensity contours.
73.684 Prediction of coverage.
73.685 Transmitter location and antenna system.
73.686 Measurements for rule making purposes and upon request of the Commission.
73.687 Transmitters and associated equipment.
73.688 Indicating instruments.
73.689 Operating power.

MONITORING EQUIPMENT

73.690 Frequency monitors.
73.691 Modulation monitors.
73.692 General requirements for type approval of frequency and modulation monitors.
73.693 Requirements for type approval of frequency monitors.
73.694 Requirements for type approval of aural modulation monitors.
73.698 Tables.
73.699 Engineering charts.

Subpart F—International Broadcast Stations

DEFINITIONS AND ALLOCATION OF FACILITIES

73.701 Definitions.
73.702 Assignment and use of frequencies.
73.703 Latitude and longitude of areas used for field intensity calculations.
73.704 Daily frequency hour availability table.

ADMINISTRATIVE PROCEDURE

73.710 Cross reference.
73.711 Application for international broadcast stations.
73.712 Notification of filing of applications.
73.716 Equipment tests.
73.718 Normal license period.

LICENSING POLICIES

73.731 Licensing requirements; necessary showing.

EQUIPMENT

73.751 Power requirement.
73.752 Frequency control.
73.753 Antenna.
73.754 Frequency monitors.
73.755 Modulation monitors.
73.756 Required transmitter performance.
73.757 Auxiliary transmitters.
73.758 Alternate main transmitters.
73.759 Changes in equipment and antenna system.

TECHNICAL OPERATION AND OPERATOR

73.761 Time of operation.
73.762 Station inspection.
73.763 Station license, posting of.
73.764 Operator requirements.
73.765 Operating power; how determined.
73.766 Modulation.
73.767 Frequency tolerance.
73.768 Antenna structure, marking and lighting.
73.769 Discontinuance of operation.

OTHER OPERATING REQUIREMENTS

73.781 Logs.
73.782 Retention of logs.
73.783 Logs; by whom kept.
73.784 Log form.
73.785 Correction of logs.
73.786 Rough logs.
73.787 Station identification.
73.788 Service; commercial or sponsored programs.
73.789 Sponsored programs; announcement of.
73.790 Rebroadcast.
73.791 Supplemental report with renewal application.
73.792 Engineering chart.

Subpart G—Emergency Broadcast System

SCOPE AND OBJECTIVE

73.901 Scope of subpart.
73.902 Object of subpart.

DEFINITIONS

73.911 Emergency Broadcast System (EBS).
73.912 National Defense Emergency Authorization (NDEA).
73.913 Emergency Action Notification.
73.914 Emergency Action Termination.
73.915 Emergency Action Condition.
73.916 Emergency Broadcast System Plan.

EMERGENCY ACTIONS

73.921 Emergency Action Notification.
73.922 Reception of an Emergency Action Notification.
73.923 Operation during an Emergency Action Condition.

EMERGENCY ACTION CONDITION TERMINATION

73.931 Notification of termination of Emergency Action Condition.
73.932 Termination message.

SYSTEM OPERATION

73.941 Procedure.
73.942 Participation.

TESTS

73.951 Emergency Action Notification System Tests.

WEATHER WARNINGS

73.961 Emergency Weather Warnings.

NETWORK CONNECTION

73.971 Participation by telephone companies.

AUTHORITY: §§ 73.1 to 73.971 issued under sec. 4 and 303, 48 Stat. 1066, as amended, 1082, as amended; 47 U.S.C. 154, 303. Interpret or apply secs. 301, 303, 307, 48 Stat. 1081, 1082, as amended, 1083, as amended, 47 U.S.C. 301, 303, 307. Other statutory and executive order provisions authorizing or interpreted or applied by specific sections are cited to text.

Subpart A—Standard Broadcast Stations

DEFINITIONS

§ 73.1 Standard broadcast station.

The term "standard broadcast station" means a broadcasting station licensed for the transmission of radiotelephone emissions primarily intended to be received by the general public and operated on a channel in the band 535–1605 kilocycles.

§ 73.2 Standard broadcast band.

The term "standard broadcast band" means the band of frequencies extending from 535 to 1605 kilocycles.

§ 73.3 Standard broadcast channel.

The term "standard broadcast channel" means the band of frequencies occupied by the carrier and two side bands of a broadcast signal with the carrier frequency at the center. Channels shall be designated by their assigned carrier frequencies. The 107 carrier frequencies assigned to standard broadcast stations shall begin at 540 kilocycles and be in successive steps of 10 kilocycles.

§ 73.4 Dominant station.

The term "dominant station" means a Class I station, as defined in § 73.21, operating on a clear channel.

§ 73.5 Secondary station.

The term "secondary station" means any station except a Class I station operating on a clear channel.

§ 73.6 Daytime.

The term "daytime" means that period of time between local sunrise and local sunset.

§ 73.7 Nighttime.

The term "nighttime" means that period of time between local sunset and 12 midnight local standard time.

§ 73.8 Sunrise and sunset.

The terms "sunrise and sunset" mean, for each particular location and during any particular month, the time of sunrise and sunset as specified in the instrument of authorization.

§ 73.9 Broadcast day.

The term "broadcast day" means that period of time between local sunrise and 12 midnight local standard time.

§ 73.10 Experimental period.

The term "experimental period" means that time between 12 midnight and local sunrise. This period may be used for experimental purposes in testing and maintaining apparatus by the licensee of any standard broadcast station on its assigned frequency and with its authorized power, provided no interference is caused to other stations maintaining a regular operating schedule within such period. No station licensed for "daytime" or "specified hours" of operation may broadcast any regular or scheduled program during this period.

§ 73.11 Service areas.

(a) The term "primary service area" of a broadcast station means the area in which the groundwave is not subject to objectionable interference or objectionable fading.

(b) The term "secondary service area" of a broadcast station means the area served by the skywave and not subject to objectionable interference. The signal is subject to intermittent variations in intensity.

(c) The term "intermittent service area" of a broadcast station means the area receiving service from the groundwave but beyond the primary service area and subject to some interference and fading.

§ 73.12 Portable transmitter.

The term "portable transmitter" means a transmitter so constructed that it may be moved about conveniently from place to place, and is in fact so moved about from time to time, but not ordinarily used while in motion. In the standard broadcast band, such a trans-

mitter is used in making field intensity measurements for locating a transmitter site for a standard broadcast station. A portable broadcast station will not be licensed in the standard broadcast band for regular transmission of programs intended to be received by the public.

§ 73.13 Auxiliary transmitter.

The term "auxiliary transmitter" means a transmitter maintained only for transmitting the regular programs of a station in case of failure of the main transmitter.

§ 73.14 Technical definitions.

(a) *Combined audio harmonics.* The term "combined audio harmonics" means the arithmetical sum of the amplitudes of all the separate harmonic components. Root sum square harmonic readings may be accepted under conditions prescribed by the Commission.

(b) *Effective field.* The term "effective field" or "effective field intensity" is the root-mean-square (RMS) value of the inverse distance fields at a distance of 1 mile from the antenna in all directions in the horizontal plane.

(c) *Operating power.* "Operating power" is the power that is actually supplied to the radio station antenna.

(d) *Maximum rated carrier power.* "Maximum rated carrier power" is the maximum power at which the transmitter can be operated satisfactorily and is determined by the design of the transmitter and the type and number of vacuum tubes used in the last radio stage.

(e) *Plate input power.* "Plate input power" means the product of the direct plate voltage applied to the tubes in the last radio stage and the total direct current flowing to the plates of these tubes, measured without modulation.

(f) *Antenna power.* "Antenna input power" or "antenna power" means the product of the square of the antenna current and the antenna resistance at the point where the current is measured.

(g) *Antenna current.* "Antenna current" means the radio-frequency current in the antenna with no modulation.

(h) *Antenna resistance.* "Antenna resistance" means the total resistance of the transmitting antenna system at the operating frequency and at the point at which the antenna current is measured.

(i) *Modulator stage.* "Modulator stage" means the last amplifier stage of the modulating wave which modulates a radio-frequency stage.

(j) *Modulated stage* "Modulated stage" means the radio-frequency stage to which the modulator is coupled and in which the continuous wave (carrier wave) is modulated in accordance with the system of modulation and the characteristics of the modulating wave.

(k) *Last radio stage.* "Last radio stage" means the oscillator or radio-frequency-power amplifier stage which supplies power to the antenna.

(l) *Percentage modulation (amplitude).* "Percentage modulation" with respect to an amplitude modulated wave means the ratio of half the difference between the maximum and minimum amplitudes of the amplitude modulated wave to the average amplitude expressed in percentage.

(m) *Maximum percentage of modulation.* "Maximum percentage of modulation" means the greatest percentage of modulation that may be obtained by a transmitter without producing in its output harmonics of the modulating frequency in excess of those permitted by these regulations.

(n) *High level modulation.* "High level modulation" is modulation produced in the plate circuit of the last radio stage of the system.

(o) *Low level modulation.* "Low level modulation" is modulation produced in an earlier stage than the final.

(p) *Plate modulation.* "Plate modulation" is modulation produced by introduction of the modulating wave into the plate circuit of any tube in which the carrier frequency wave is present.

(q) *Grid modulation.* "Grid modulation" is modulation produced by introduction of the modulating wave into any of the grid circuits of any tube in which the carrier frequency wave is present.

(r) *Blanketing.* Blanketing is that form of interference which is caused by the presence of a broadcast signal of 1 v/m or greater intensity in the area adjacent to the antenna of the transmitting station. The 1 v/m contour is referred to as the blanket contour and the area within this contour is referred to as the blanket area.

§ 73.15 NARBA and the U.S./Mexican Agreement.

The term "NARBA" where used in this part means the North American Regional Broadcasting Agreement, signed at Washington, D.C., November 15, 1950, which entered into force April 19, 1960, and to which the signatory countries are The Bahama Islands and Jamaica, Canada, Cuba, the Dominican Republic, and the United States of America. The term "U.S./Mexican Agreement" where used in this part means the Agreement between the United States of America and the United Mexican States concerning Radio Broadcasting in the Standard Broadcast Band, signed at Mexico, D.F., January 29, 1957, which entered into force June 9, 1961.

ADMINISTRATIVE PROCEDURE

§ 73.17 Cross reference.

See Subpart D of Part 1 of this chapter for general requirements as to applications, filing of applications and description of application forms, other forms and information to be filed with the Commission, the manner in which applications are processed, and provisions applying to action on applications. See § 1.1111 of Subpart G of that part for the fees to be paid in connection with applications for facilities in the service covered in this subpart.

§ 73.18 Notification of filing of applications.

In order to minimize harmful interference at the National Radio Astronomy Observatory site located at Green Bank, Pocahontas County, West Virginia, and at the Naval Radio Research Observatory at Sugar Grove, Pendleton County, West Virginia, an applicant for authority to construct a new standard broadcast station or for authority to make changes in the frequency, power, antenna height, or antenna directivity of an existing station within the area bounded by 39°15′ N. on the north, 78°30′ W. on the east, 37°30′ N. on the south, and 80°30′ W. on the west shall, at the time of filing such application with the Commission, simultaneously notify the Director, National Radio Astronomy Observatory, P.O. Box No. 2, Green Bank, West Virginia, 24944, in writing, of the technical particulars of the proposed station. Such notification shall include the geographical coordinates of the antenna, antenna height; antenna directivity if any, proposed frequency, type of emission, and power. In addition, the applicant shall indicate in his application to the Commission the date notification was made to the observatory. After receipt of such applications, the Commission will allow a period of twenty (20) days for comments or objections in response to the notifications indicated. If an objection to the proposed operation is received during the twenty-day period from the National Radio Astronomy Observatory for itself or on behalf of the Naval Radio Research Observatory, the Commission will consider all aspects of the problem and take whatever action is deemed appropriate.

ALLOCATION OF FACILITIES; AUTHORIZATIONS

§ 73.21 Classes of standard broadcast channels and stations.

(a) *Clear channel.* A clear channel is one on which the dominant station or stations render service over wide areas, and which are cleared of objectionable interference within their primary service areas and over all or a substantial portion of their secondary service areas. Stations operating on these channels are classified as follows:

(1) *Class I station.* A class I station is a dominant station operating on a clear channel and designed to render primary and secondary service over an extended area and at relatively long distances. Its primary service area is free from objectionable interference from other stations on the same and adjacent channels, and its secondary service area free from interference except from stations on adjacent channels, and from stations on the same channel in accordance with the channel designation in § 73.25 or §73. 182. The operating power shall not be less than 10 kilowatts nor more than 50 kilowatts. (Also see § 73.25 (a) for further power limitation.)

(2) *Class II station.* A Class II station is a secondary station which operates on a clear channel (see § 73.25) and is designed to render service over a primary service area which is limited by and subject to such interference as may be received from Class I stations. Whenever necessary a Class II station shall use a directional antenna or other means to avoid interference with Class I stations and with other Class II stations, in accordance with § 73.182 (and § 73.22 in the case of Class II–A stations). Class II stations are divided into three groups:

(i) *Class II–A station.* A Class II–A station is an unlimited time Class II sta-

tion operating on one of the clear channels listed in § 73.22 and assigned to a community within a state specified in the Table contained in that section. A Class II–A station shall operate with power of not less than 10 kilowatts nighttime nor more than 50 kilowatts at any time.

(ii) *Class II–B station.* A Class II–B station is an unlimited time Class II station other than those included in Class II–A. A Class II–B station shall operate with power not less than 0.25 kilowatts nor more than 50 kilowatts.

NOTE: The Class II station operating unlimited time on 760 kc/s at San Diego, Calif., shall be limited to a power of 5 kw and the Class II station operating unlimited time on 750 kc/s at Anchorage, Alaska, shall be limited to a power of 10 kw. Both stations shall protect the I–A station on the same frequency to its 0.5 mv/m 50 percent skywave contour.

(iii) *Class II–D station.* A Class II–D station is a Class II station operating daytime or limited time. A Class II–D station shall operate with power not less than 0.25 kilowatts nor more than 50 kilowatts.

(b) *Regional channel.* A regional channel is one on which several stations may operate with powers not in excess of 5 kilowatts. The primary service area of a station operating on any such channel may be limited to a given field intensity contour as a consequence of interference.

(1) *Class III station.* A Class III station is a station which operates on a regional channel and is designed to render service primarily to a principal center of population and the rural area contiguous thereto. Class III stations are subdivided into two classes.

(i) *Class III–A station.* A Class III–A station is a Class III station which operates with power not less than 1 kilowatt nor more than 5 kilowatts and the service area of which is subject to interference in accordance with § 73.182.

(ii) *Class III–B station.* A Class III–B station is a Class III station which operates with power not less than 0.5 kilowatt, nor more than 1 kilowatt night and 5 kilowatts daytime, and the service area of which is subject to interference in accordance with § 73.182.

(c) *Local channel.* A local channel is one on which several stations operate with powers no greater than provided in this paragraph. The primary service area of a station operating on any such channel may be limited to a given field intensity contour as a consequence of interference. Such stations operate with power no greater than 250 watts nighttime, and power daytime no greater than 1 kilowatt (or no greater than 250 watts if the station is located 100 kilometers (62 miles) or closer to the Mexican border, or in the area of the state of Florida south of 28 degrees north latitude and between 80 and 82 degrees west longitude).

(1) *Class IV station.* A Class IV station is a station operating on a local channel and designed to render service primarily to a city or town and the suburban and rural areas contiguous thereto. The power of a station of this class shall not be less than 0.1 kilowatt, and not more than 0.25 kilowatt nighttime and 1 kilowatt daytime, and its service area is subject to interference in accordance with § 73.182.

NOTE 1: Under NARBA, the power ceiling for Class IV stations is 250 watts daytime as well as nighttime. The US-Mexican Agreement permits such stations to operate with up to 1 kilowatt power daytime if they are located further than 100 kilometers (62 miles) from the Mexican border. Pursuant to the US-Mexican Agreement and informal coordination with the other NARBA signatories, the Commission will consider applications for Class IV stations on local channels with daytime powers more than 250 watts, up to 1 kilowatt, if such station is to be located outside of the areas specified in paragraph (c) of this section, and if no objectionable interference would be caused (under the standards set forth in the pertinent international agreement) to a duly notified station in Mexico, Haiti, or any foreign country signatory to NARBA.

NOTE 2: All authorizations of new or changed Class I–B, Class II–B, Class II–D, Class III or Class IV facilities after October 30, 1961, are subject to whatever interference may be received from, or whatever overlap of 2.0 mv/m and 25 mv/m groundwave contours or overlap of 25 mv/m groundwave contours may be involved with, previously or subsequently authorized Class II–A facilities.

§ 73.22 Assignment of Class II–A stations.

(a) *Table of assignments.* One Class II–A station may be assigned on each channel listed in the following table within the designated State or States:

Channel (kc/s)	Location of existing Class I station	State(s) in which Class II–A assignment may be applied for
670	Chicago, Ill.	Idaho.
720	Chicago, Ill.	Nevada or Idaho.
780	Chicago, Ill.	Nevada.
880	New York, N.Y.	North Dakota, South Dakota, or Nebraska.
890	Chicago, Ill.	Utah.
1020	Pittsburgh, Pa.	New Mexico.
1030	Boston, Mass.	Wyoming.
1100	Cleveland, Ohio	Colorado.
1120	St. Louis, Mo.	California or Oregon.
1180	Rochester, N.Y.	Montana.
1210	Philadelphia, Pa.	Kansas, Nebraska, or Oklahoma.

(b) *Minimum service to "white" areas.* No Class II–A station shall be assigned unless at least 25 percent of its nighttime interference-free service area or at least 25 percent of the population residing therein receives no other interference-free nighttime primary service.

(c) *Power.* Class II–A stations shall operate with not less than 10 kw power nighttime.

(d) *Protection.* (1) *Protection by Class II–A stations to other stations.* The co-channel Class I–A station shall be protected by the Class II–A station to its 0.1 mv/m contour daytime and its 0.5 mv/m 50 percent skywave contour nighttime. All other stations of any class authorized on or before October 30, 1961, shall normally receive protection from objectionable interference from Class II–A stations as provided in § 73.182.

(2) *Protection to Class II–A stations.* A Class II–A station shall normally receive daytime protection to its 0.5 mv/m groundwave contour and nighttime protection to the contour to which it is limited by the co-channel Class I–A station.

(e) *Applications not complying with this section.* Applications for Class II–A stations which do not meet the requirements of paragraphs (b) and (c) of this section will be returned without further consideration.

§ 73.23 Time of operation of the several classes of stations.

The several classes of standard broadcast stations may be licensed to operate in accordance with the following:

(a) Unlimited time permits operation without a maximum limit as to time.

(b) Limited time is applicable to Class II (secondary) stations operating on a clear channel with facilities authorized before November 30, 1959. It permits operation of the secondary station during daytime, and until local sunset if located west of the dominant station on the channel, or if located east thereof, until sunset at the dominant station, and in addition during night hours, if any, not used by the dominant station or stations on the channel.

(c) Daytime permits operation during the hours between average monthly local sunrise and average monthly local sunset. Daytime stations operating on local channels with a power of 0.1 kw or 0.25 kw may, upon notification to the Commission and to the Engineer in Charge of the radio district in which they are located, operate at hours beyond those specified in their license.

(d) Sharing time permits operation during hours which are so restricted by the station license as to require a division of time with one or more other stations using the same channel.

(e) Specified hours means that the exact operating hours are specified in the license. (The minimum hours that any station shall operate are specified in § 73.71.) Specified hours stations operating on local channels with a power of 0.1 kw or 0.25 kw, except those sharing time with other stations may, upon notification to the Commission and the Engineer in Charge of the radio district in which they are located, operate at hours beyond those specified in their license.

§ 73.24 Broadcast facilities; showing required.

An authorization for a new standard broadcast station or increase in facilities of an existing station will be issued only after a satisfactory showing has been made in regard to the following, among others:

(a) That the proposed assignment will tend to effect a fair, efficient, and equitable distribution of radio service among the several states and communities.

(b) That objectionable interference will not be caused to existing stations or that, if interference will be caused, the need for the proposed service outweighs the need for the service which will be lost by reason of such interference. (For special provisions concerning interference from Class II–A stations to stations of other classes authorized after October 30, 1961, see Note 2 to § 73.21 and § 73.22(d).) That the proposed station will not suffer interference to such an extent that its service would be reduced to an unsatisfactory

degree. (For determining objectionable interference, see §§ 73.182 and 73.186.)

(c) That the applicant is financially qualified to construct and operate the proposed station.

(d) That the applicant is legally qualified. That the applicant (or the person or persons in control of an applicant corporation or other organization) is of good character and possesses other qualifications sufficient to provide a satisfactory public service.

(e) That the technical equipment proposed, the location of the transmitter, and other technical phases of operation comply with the regulations governing the same, and the requirements of good engineering practice. (See technical regulations of this subpart and § 73.188.)

(f) That the facilities sought are subject to assignment as requested under existing international agreements and the rules and regulations of the Commission.

(g) That the population within the 1 v/m contour does not exceed 1.0 percent of the population within the 25 mv/m contour: *Provided, however,* That where the number of persons within the 1 v/m contour is 300 or less the provisions of this subparagraph are not applicable.

(h) That, in the case of an application for a Class II station, the proposed station would radiate, during two hours following local sunrise and two hours preceding local sunset, in any direction toward the 0.1 mv/m groundwave contour of a co-channel United States Class I station, no more than the maximum radiation values permitted under the provisions of § 73.187.

(i) That, in the case of an application for a Class II–A station (see § 73.22), 25 percent or more of the area or population within the nighttime interference-free service contour of the proposed station receives no nighttime interference-free primary service from another station.

(j) That the public interest, convenience and necessity will be served through the operation under the proposed assignment.

§ 73.25 Clear channels; Classes I and II stations.

The frequencies in the following tabulations are designated as clear channels and assigned for use by the Classes of stations given:

(a) On each of the following channels, one Class I station will be assigned, operating with power of 50 kw: 640, 650, 660, 670, 700, 720, 750, 760, 780, 820, 830, 840, 870, 880, 890, 1020, 1030, 1040, 1100, 1120, 1160, 1180, 1200, and 1210 kc/s. In addition, on the channels listed in this paragraph, Class II stations may be assigned as follows:

(1) On 670, 720, 780, 880, 890, 1020, 1030, 1100, 1120, 1180, and 1210 kc/s, one Class II–A unlimited time station, assigned and located pursuant to the provisions of § 73.22.

(2) On the channel 750 kc/s, an unlimited time Class II station located at Anchorage, Alaska.

(3) On the channel 760 kc/s, an unlimited time Class II station located at San Diego, California.

(4) On any of the channels listed in this paragraph (to the extent consistent with the assignments provided in subparagraphs (1), (2), and (3) of this paragraph), unlimited time Class II stations located in Alaska, Hawaii, Virgin Islands, or Puerto Rico, which will not deliver more than 5 microvolts per meter groundwave day or night or 25 microvolts per meter 10 percent time skywave at night at any point within the continental limits of the United States excluding Alaska.

(5) On any of the channels listed in this paragraph (to the extent consistent with the Class I, Class II–A, and Anchorage and San Diego Class II assignments provided in this paragraph, and, in the case of limited time stations, subject to the restrictions contained in § 73.38), limited time and daytime only stations, as follows:

(i) In Alaska, Hawaii, Puerto Rico, and Virgin Islands.

(ii) Within the continental United States excluding Alaska, where the station would operate with facilities authorized as of October 30, 1961.

NOTE 1: In view of special circumstances arising from the provision of pre-sunrise broadcast service on 640 kc/s at Ames, Iowa, applications will be accepted for broadcast operations on 640 kc/s between 6:00 a.m. central standard time and local sunrise at Ames, Iowa, with not to exceed 1 kw power: *Provided,* That such applications will be acted upon only after and in light of the decision reached in Docket No. 11290.

NOTE 2: In view of special circumstances arising from the provision of a service during some nighttime hours by a Class II station operating on 830 kc/s at New York, N.Y. (i.e., from 6:00 a.m. to local sunrise and from sunset at Minneapolis to 10:00 p.m. e.s.t.), applications will be accepted for such operation: *Provided,* That they will be acted upon only after and in light of the decision reached in Docket No. 11227.

NOTE 3: On the frequency 770 kc/s, two Class I stations may be assigned.

NOTE 4: See NARBA concerning priority for Canadian Class I–B and Cuban Class I–C assignments on 640 kc/s.

NOTE 5: *See* NARBA concerning Cuban Class II–E assignments on 660, 670, 760, 780, 830, 1020, 1030, and 1120 kc/s.

NOTE 6: See the U.S.-Mexican Agreement concerning Mexican use of 660, 760, and 830 kc/s.

(b) To each of the following channels there may be assigned Class I and Class II stations: 680, 710, 810, 850, 940, 1000, 1060, 1070, 1080, 1090, 1110, 1130, 1140, 1170, 1190, 1500, 1510, 1520, 1530, 1540, 1550, and 1560 kc/s.

NOTE 1: See NARBA and the U.S.-Mexican Agreement concerning a Cuban Class II–E assignment on, and Mexican use of, 1030 kc/s.

NOTE 2: Class I and Class II stations on 1540 kc/s shall deliver not over 5 microvolts per meter groundwave or 25 microvolts per meter 10 percent time skywave at any point of land in the Bahama Islands, and such stations operating nighttime (i.e., sunset to sunrise at the location of the Class II station) shall be located not less than 650 miles from the nearest point of land in the Bahama Islands.

(c) For Class II stations which will not deliver over 5 microvolts per meter groundwave or 25 microvolts per meter 10 percent time skywave at any point on the Canadian border, and provided that such stations operating nighttime (i.e., sunset to sunrise at the location of the Class II station) are located not less than 650 miles from the nearest point on the Canadian border, 690, 740, 860, 990, 1010, and 1580 kc/s.

NOTE: See NARBA concerning priority for Cuban Class I–B assignment on 1010 kc/s, Class I–C assignments on 690 and 860 kc/s, and Class I–D assignment on 740 kc/s.

(d) The frequencies 730, 800, 900, 1050, 1220, and 1570 kc/s, for Class II stations which operate daytime only, which will not deliver at any point on the Mexican border over 5 microvolts per meter groundwave, and which operate with no more than the following powers:

(1) If not located within the areas specified in subparagraph (2) of this paragraph, 5 kilowatts.

(2) If operating on any of the following frequencies within the following specified areas, no more than one kilowatt:

(i) 800 kc/s: less than 1319 kilometers (820 miles) from Ciudad Juarez, Chihuahua.

(ii) 1050 kc/s: less than 998 kilometers (620 miles) from Monterrey, Nuevo Leon.

(iii) 1570 kc/s: less than 998 kilometers (620 miles) from Ciudad Acuna, Coahuila.

NOTE: See the U.S./Mexican Agreement concerning specific U.S. unlimited time Class II assignments on each of the following channels: 730, 800, 900, 1050, and 1220 kc/s.

(e) The frequency 540 kc/s, for Class II stations which will not deliver a signal of more than 5 microvolts per meter groundwave or 25 microvolts per meter 10 percent skywave at any point on the Canadian border, nor more than 10 microvolts per meter daytime or 50 microvolts per meter nighttime at any point on the Mexican border: *Provided,* That stations operating at night shall be located:

(1) Within the continental United States including Alaska; and

(2) Not less than 650 miles from the nearest point on the Canadian border; and

(3) North of the parallel 35° N. if west of the meridian 93° W., or north of the parallel 30° N. if east of said meridian.

NOTE: See § 2.106 of this chapter with respect to use of 540 kc/s.

§ 73.26 Regional channels: Classes III–A and III–B stations.

The following frequencies are designated as regional channels and are assigned for use by Class III–A and III–B stations: 550, 560, 570, 580, 590, 600, 610, 620, 630, 790, 910, 920, 930, 950, 960, 970, 980, 1150, 1250, 1260, 1270, 1280, 1290, 1300, 1310, 1320, 1330, 1350, 1360, 1370, 1380, 1390, 1410, 1420, 1430, 1440, 1460, 1470, 1480, 1590, and 1600 kc/s.

NOTE: See NARBA concerning Cuban Class I–C assignment on 550 kc/s, Class I–D assignments on 570, 590, 630, 920, 950 and 980 kc/s, and Class III–E assignments on 790, 910, and 1150 kc/s.

§ 73.27 Local channels: Class IV stations.

The following frequencies are designated as local channels and are assigned for use by Class IV stations: 1230, 1240, 1340, 1400, 1450, and 1490 kc/s.

NOTE: See NARBA concerning Cuban Class IV–E assignments on 1240 and 1340 kc/s.

§ 73.28 Assignment of stations to channels.

(a) The individual assignments of stations to channels which may cause interference to other United States stations only, shall be made in accordance with the provisions of this part for the respective classes of stations involved. (For determining objectionable interference, see §§ 73.22, and 73.182 through 73.186.)

(b) Except as provided in § 73.21(c) concerning Class IV stations, no assignment of a standard broadcast station will be made which would be inconsistent with the provisions of NARBA or the U.S./Mexican Agreement. Similarly, as long as protection for U.S. assignments from Haitian assignments continues, no U.S. assignment of a standard broadcast station will be made which would cause objectionable interference (under the standards set forth in NARBA) to a duly notified Haitian station. (The Haitian stations considered to be duly notified are those notified and accepted in accordance with past agreements, and those subsequently notified in accordance with the procedures and understandings which have pertained thus far.) In all cases where an individual assignment may cause interference with, or may involve a channel assigned for priority of use by, a station in another North American country, the classifications, allocation requirements, and engineering standards set forth in NARBA and the U.S./Mexican Agreement shall be observed.

NOTE: (a) In general, an application for a standard broadcast station assignment, the grant of which would be consistent with the provisions of NARBA and the U.S./Mexican Agreement and would not cause objectionable interference to a duly notified station in Haiti, will be considered and acted upon by the Commission in accordance with its rules and established procedure for action upon such applications. However, in particular cases such applications may also present considerations of an international nature which require that a different procedure be followed. In such cases the procedure to be followed will be determined by the Commission in the light of the special considerations involved.

(b) With respect to applications for facilities which would involve conflict with NARBA only as to a country which has signed but not completed formal ratification of that agreement, and facilities which would cause objectionable interference to a duly notified Haitian station, special provisions of a procedural nature are contained in § 1.570 of this chapter.

(c) Engineering standards now in force domestically differ in some respects from those specified for international purposes. The engineering standards specified for international purposes (in NARBA and the U.S./Mexican Agreement) will be used to determine: (1) The extent to which interference might be caused by a proposed station in the United States to a station in another country of the North American Region; and (2) whether the United States should register an objection to any new or changed assignment notified by another country of the North American Region. The domestic standards in effect in the United States will be used to determine the extent to which interference exists or would exist from a foreign station where the value of such interference enters into a calculation of: (1) The service to be rendered by a proposed operation in the United States; or (2) the permissible interfering signal from one station in the United States to another United States station.

(d) Upon showing that a need exists, a Class II, III, or IV station may be assigned to a channel available for such class, even though interference will be received within its normally protected contour; *Provided:* (1) no objectionable interference will be caused by the proposed station to existing stations or that if interference will be caused, the need for the proposed service outweighs the need for the service which will be lost by reason of such interference; and (2) primary service will be provided to the community in which the proposed station is to be located; and (3) the interference received does not affect more than 10 percent of the population in the proposed station's normally protected primary service area; however, in the event that the nighttime interference received by a proposed Class II or III station would exceed this amount, then an assignment may be made if the proposed station would provide either a standard broadcast nighttime facility to a community not having such a facility or if 25 percent or more of the nighttime primary service area of the proposed station is without primary nighttime service. Further, proviso (3) of this paragraph shall not apply to existing Class IV stations on local channels applying for an increase in power above 250 watts, nor to new Class IV stations proposing power in excess of 250 watts with respect to population in the primary service area outside the equivalent 250 watt, 0.5 mv/m contour.

§ 73.29 Class IV stations on regional channels.

No license will be granted for the operation of a Class IV station on a regional channel: *Provided, however,* That Class IV stations presently authorized to operate on regional channels will not be required to change frequency, or power but will not be protected against interference from Class III stations.

§ 73.30 Station location and program origination.

(a) Except as provided in paragraph (b) of this section, each standard broadcast station will be licensed to serve primarily a particular city, town, political subdivision, or community which will be specified in the station license and the station will be considered to be located in such place. Unless licensed as a synchronous amplifier transmitter, each station shall maintain a studio, which will be known as the main studio, in the place where the station is located provided that the main studio may be located at the transmitter site whether or not the transmitter site is in the place where the station is located. A majority (computed on the basis of duration and not number) of a station's programs or in the case of a station affiliated with a network ⅔ of such station's non-network programs, whichever is smaller, shall originate from the main studio or from the other studios or remote points situated in the place where the station is located.

(b) Stations will be licensed to serve more than one city, town, political subdivision, or community only where a satisfactory showing is made that each such place meets all the requirements of the rules and regulations of this subpart with respect to the location of main studios; that the station can and will originate a substantial number of local live programs from each such place; and that the requirements as to origination of programs contained in paragraph (a) of this section would place an unreasonable burden on the station if it were licensed to serve only one city, town, political subdivision, or community. A station licensed to serve more than one place shall be considered to be located in and shall maintain main studios in each such place. With respect to such station the requirements as to origination of programs contained in paragraph (a) of this section shall be satisfied by the origination of programs from any or all of the main studios or from other studios and remote points situated in any or all of the places in which the main studios are located.

(c) The transmitter of each standard broadcast station shall be so located that primary service is delivered to the borough or city in which the main studio is located in accordance with the rules and regulations of this subpart.

§ 73.31 Authority to move main studio.

The licensee of a station shall not move its main studio outside the borders of the borough or city, state, district, territory, or possession in which it is located, unless such move is to the location of the station's transmitter, without first securing a modification of construction permit or license. The licensee shall promptly notify the Commission of any other change in location of the main studio.

§ 73.32 Special experimental authorizations.

(a) Special experimental authorization may be issued to the licensee of a standard broadcast station in addition to the regular license upon informal application therefor and upon a satisfactory showing in regard to the following, among others:

(1) That the applicant has a program of research and experimentation which indicates reasonable promise of contribution to the development and practical application of broadcasting, and will be in addition to and advancement of the work that can be accomplished under its regular license.

(2) That the experimental operation and experimentation will be under the direct supervision of a qualified engineer

with an adequate staff of engineers qualified to carry on the program of research and experimentation.

(3) That the public interest, convenience, and necessity will be served by granting the authorization requested.

(b) In case a special experimental authorization permits additional hours of operation, no licensee shall transmit any commercial or sponsored program or make any commercial announcement during such time of operation. In case of other additional facilities, no additional charge shall be made by reason of transmission with such facilities.

(c) A special experimental authorization will not be extended after the actual experimentation is concluded.

(d) The program of research and experimentation as outlined in the application for a special experimental authorization shall be adhered to in the main unless the licensee is authorized to do otherwise by the Commission.

(e) The Commission may require from time to time a broadcast station holding such experimental authorization to conduct experiments that are deemed desirable and reasonable.

(f) A supplemental report shall be filed with and made a part of each application for an extension of a special experimental authorization and shall include statements of the following:

(1) Comprehensive summary of all research and experimentation conducted.

(2) Conclusions and outline of proposed program for further research and development.

(3) Comprehensive summary and conclusions as to the social and economic effects of its use.

§ 73.33 Antenna systems; showing required.

(a) An application for authority to install a broadcast antenna shall specify a definite site and include full details of the antenna design and expected performance. (Site-to-be-determined applications which were on file prior to October 28, 1953, may be granted conditioned upon the filing within 60 days of such grant of an application for modification of permit specifying a site conforming to Commission's rules and standards.)

(b) All data necessary to show compliance with the terms and conditions of the construction permit must be filed with the license application. If the station is using a directional antenna, a proof of performance must also be filed.

§ 73.34 Normal license period.

(a) Licenses for standard broadcast stations ordinarily will be issued for a period of three years and, when regularly renewed, at three year intervals thereafter: *Provided, however,* That, if the Commission finds that the public interest, convenience, and necessity will be served thereby, it may issue either an initial license or a renewal thereof for a lesser term. When regularly issued or renewed, licenses will be issued to expire at the hour of 3:00 a.m., eastern standard time, in accordance with the following schedule, and at three year intervals thereafter.

(1) For stations located in Florida, Puerto Rico and Virgin Islands, February 1, 1964.

(2) For stations located in Alabama and Georgia, April 1, 1964.

(3) For stations located in Arkansas, Louisiana and Mississippi, June 1, 1964.

(4) For stations located in Tennessee, Kentucky and Indiana, August 1, 1964.

(5) For stations located in Ohio and Michigan, October 1, 1964.

(6) For stations located in Illinois and Wisconsin, December 1, 1964.

(7) For stations located in Iowa and Missouri, February 1, 1965.

(8) For stations located in Minnesota, North Dakota, South Dakota, Montana and Colorado, April 1, 1965.

(9) For stations located in Kansas, Oklahoma, Nebraska, June 1, 1965.

(10) For stations located in Texas, August 1, 1965.

(11) For stations located in Wyoming, Nevada, Arizona, Utah, New Mexico and Idaho, October 1, 1965.

(12) For stations located in California, December 1, 1965.

(13) For stations located in Washington, Oregon, Alaska, Guam and Hawaii, February 1, 1966.

(14) For stations located in Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island and Vermont, April 1, 1966.

(15) For stations located in New Jersey and New York, June 1, 1966.

(16) For stations located in Delaware and Pennsylvania, August 1, 1966.

(17) For stations located in Maryland, District of Columbia, Virginia, West Virginia, October 1, 1966.

(18) For stations located in North Carolina, South Carolina, December 1, 1966.

§ 73.35 Multiple ownership.

No license for a standard broadcast station shall be granted to any party (including all parties under common control) if:

(a) Such party directly or indirectly owns, operates or controls another standard broadcast station, a substantial portion of whose primary service area would receive primary service from the station in question, except upon a showing that public interest, convenience and necessity will be served through such multiple ownership situation; or

(b) Such party, or any stockholder, officer or director of such party, directly or indirectly owns, operates, controls, or has any interest in, or is an officer or director of any other standard broadcast station if the grant of such license would result in a concentration of control of standard broadcasting in a manner inconsistent with public interest, convenience, or necessity. In determining whether there is such a concentration of control, consideration will be given to the facts of each case with particular reference to such factors as the size, extent and location of areas served, the number of people served, classes of stations involved and the extent of other competitive service to the areas in question. The Commission, however, will in any event consider that there would be such a concentration of control contrary to the public interest, convenience or necessity for any party or any of its stockholders, officers or directors to have a direct or indirect interest in, or be stockholders, officers, or directors of, more than seven standard broadcast stations.

NOTE: 1. The word "control" as used herein is not limited to majority stock ownership, but includes actual working control in whatever manner exercised.

2. In applying the foregoing provisions to the stockholders of a corporation which has more than 50 voting stockholders, only those stockholders need be considered who are officers or directors or who directly or indirectly own 1 percent or more of the outstanding voting stock.

§ 73.36 Special field test authorization.

(a) Upon a showing that a need exists, a special test authorization to operate a portable or regularly authorized transmitter may be issued to persons desiring to make field intensity surveys to determine values of soil conductivity, or other factors influencing radio wave propagation, in particular areas or paths for the period necessary to conduct the survey. Such authorizations may be granted upon the following conditions:

(1) No objectionable interference will result to the operation of other authorized radio services; in this connection, the power requested shall not exceed that necessary for the purposes of the test.

(2) The carrier will be unmodulated except for half-hourly voice identification.

(3) The plate power ($E_p \times I_p$) of the final stage of the transmitter shall not exceed authorized test power and the antenna current shall be maintained at a constant value for each phase of the test.

(4) The test equipment shall not be permanently installed, unless such installation has been separately authorized. Mobile units shall not be deemed permanent installations.

(5) The equipment must be operated by or under the personal direction of either a licensed radiotelephone first-class or second-class operator.

(6) A report, under oath, containing the measurements, their analysis and other results of the survey shall be filed with the Commission within sixty (60) days from the termination of the test authorization. The measurements taken shall be sufficiently complete, in accordance with § 73.186, so as to permit a determination of the inverse distance field at 1 mile in pertinent directions.

(7) The plate voltage (E_p) and plate current (I_p) of the final stage of the transmitter shall be logged at half-hour intervals and at any time that such power is changed. Certified copies of such log notations shall be submitted to the Commission with the required report.

(8) Operation shall conform to the requirements of Subpart G of this part.

(b) The test equipment, installation and operation thereof need not comply with the requirements of Commission rules and standards except as specified in this section: *Provided however,* That the equipment, installation and operation shall be consistent with good engineering principles and practices.

(c) No authorization shall be issued unless the applicant for such authorization is determined to be legally qualified. Requests for authorizations to operate a transmitter under this section shall be made in writing, signed by the applicant under oath or affirmation (with no special form provided, how-

ever), and shall set forth the following information:

(1) Purpose, duration and need for the survey.

(2) Frequency, plate power and time of operation.

(3) A brief description of the test antenna system and its estimated effective field and its proposed location.

(4) In the case of a directional test antenna, an estimate of the maximum fields expected to be radiated in the direction of pertinent broadcast stations.

(5) In the case of a person who is not a licensee or permittee of this Commission the information required by section II of FCC Form 301.

(d) The authorization may be modified or terminated by notification from the Commission if in its judgment such action will promote the public interest, convenience or necessity.

§ 73.37 Minimum separation between stations.

A license will not be granted for a station on a frequency of ±30 kc/s from that of another station if the area enclosed by the 25 mv/m groundwave contours of the two stations overlap, nor will a license be granted for the operation of a station on a frequency ±20 kc/s or ±10 kc/s from the frequency of another station if the area enclosed by the 25 mv/m groundwave contour of either one overlaps the area enclosed by the 2 mv/m groundwave contour of the other.

§ 73.38 Limited time operation.

(a) Starting November 30, 1959, no authorization will be granted for:

(1) A new limited time station;

(2) A limited time station operating on a changed frequency;

(3) A limited time station with a new transmitter site materially closer to the 0.1 mv/m contour of a co-channel U.S. Class I station; or

(4) Modification of the operating facilities of a limited time station resulting in increased radiation toward any point on the 0.1 mv/m contour of a co-channel U.S. Class I station, during the hours after local sunset in which the limited time station is permitted to operate by reason of location east of the Class I station.

EQUIPMENT

§ 73.39 Indicating instruments—specifications.

(a) Instruments indicating the plate current or plate voltage of the last radio stage (linear scale instruments) shall meet the following specifications:

(1) Length of scale shall be not less than $2\frac{3}{16}$ inches.

(2) Accuracy shall be at least 2 percent of the full scale reading.

(3) The maximum rating of the meter shall be such that it does not read off scale during modulation.

(4) Scale shall have at least 40 divisions.

(5) Full scale reading shall not be greater than five times the minimum normal indication.

(b) Instruments indicating antenna current, common point current, and base currents shall meet the following specifications:

(1) Instruments having logarithmic or square law scales.

(i) Shall meet same requirements as paragraph (a) (1), (2) and (3) of this section for linear scale instruments.

(ii) Full scale reading shall not be greater than three times the minimum normal indication.

(iii) No scale division above one-third full scale reading (in amperes) shall be greater than one-thirtieth of the full scale reading. (Example: An ammeter meeting requirement (i) having full scale reading of 6 amperes is acceptable for reading currents from 2 to 6 amperes, provided no scale division between 2 and 6 amperes is greater than one-thirtieth of 6 amperes, 0.2 ampere.)

(2) Radio frequency instruments having expanded scales.

(i) These instruments shall meet same requirements as paragraph (a) (1), (2), and (3) of this section for linear scale instruments.

(ii) Full scale reading shall not be greater than five times the minimum normal indication.

(iii) No scale division above one-fifth full scale reading (in amperes) shall be greater than one-fiftieth of the full scale reading. (Example: An ammeter meeting the requirement (i) is acceptable for indicating currents from 1 to 5 amperes, provided no division between 1 and 5 amperes is greater than one-fiftieth of 5 amperes, 0.1 ampere.)

(iv) Manufacturers of instruments of the expanded scale type must submit data to the Commission showing that these instruments have acceptable expanded scales, and the type number of these instruments must include suitable designation.

(c) A thermocouple type ammeter meeting the requirements of paragraph (b) of this section shall be permanently installed in the antenna circuit or a suitable jack and plug arrangement may be made to permit removal of the meter from the antenna circuit so as to protect it from damage by lightning. Where a jack and plug arrangement is used, contacts shall be made of silver and capable of operating without arcing or heating, and shall be protected against corrosion. Insertion and removal of the meter shall not interrupt the transmissions of the station. When removed from the antenna circuit, the meter shall be stored in a suitable housing at the base of the tower in which it is used. Care shall be exercised in handling the meter to prevent damage which would impair its accuracy. Where the meter is permanently connected in the antenna circuit, provision may be made to short or open the meter circuit when it is not being used to measure antenna current. Such switching shall be accomplished without interrupting the transmissions of the station.

(d) Remote reading antenna ammeter(s) may be employed and the indications logged as the antenna current, or in the case of directional antenna, the common point current and base currents, in accordance with the following:

(1) Remote reading antenna, common point or base ammeters may be provided by:

(i) Inserting second thermocouple directly in the antenna circuit with remote leads to the indicating instrument.

(ii) Inductive coupling to thermocouple or other device for providing direct current to indicating instrument.

(iii) Capacity coupling to thermocouple or other device for providing direct current to indicating instrument.

(iv) Current transformer connected to second thermocouple or other device for providing direct current to indicating instrument.

(v) Using transmission line current meter at transmitter as remote reading ammeter. See subparagraph (7) of this paragraph.

(vi) Using indications of phase monitor for determining the antenna base currents or their ratio in the case of directional antennas, provided that the base current readings are read and logged in accordance with the provision of the station license, and provided further that the indicating instruments in the unit are connected directly in the current sampling circuits with no other shunt circuits of any nature. The meters in the phase monitor may utilize arbitrary scale divisions provided a calibration curve showing the relationship between the arbitrary scale and the scale of the base meters is maintained at the transmitter location.

(vii) Using indications of remote control equipment provided that the indicating instruments are capable of being connected directly into the antenna circuit at the same point as, but below (transmitter side), the antenna ammeter. The meter(s) in the remote control equipment may utilize an arbitrary scale division provided a calibration curve showing the relationship between the arbitrary scale and the scale of the antenna ammeter is maintained at the remote control point. The meter(s) in the remote control equipment must be calibrated once a week against the regular meter and the results thereof entered in the operating log.

(2) Remote ammeters shall be connected into the antenna circuit at the same point as, but below (transmitter side), the antenna ammeter(s), and shall be calibrated to indicate within 2 percent of the regular meter over the entire range above one-third or one-fifth full scale. See paragraphs (b) (1) (i), (iii) and (b) (2) (i), (iii) of this section.

(3) The regular antenna ammeter, common point ammeter, or base current ammeters shall be above (antenna side) the coupling to the remote meters in the antenna circuit so they do not read the current to ground through the remote meter(s).

(4) All remote meters shall meet the same requirements as the regular antenna ammeter with respect to scale accuracy, etc.

(5) Calibration shall be checked against the regular meter at least once a week.

(6) All remote meters shall be provided with shielding or filters as necessary to prevent any feed-back from the antenna to the transmitter.

(7) In the case of shunt excited antennas, the transmission line current

meter at the transmitter may be considered as the remote antenna ammeter provided the transmission line is terminated directly into the excitation circuit feed line, which shall employ series tuning only (no shunt circuits of any type shall be employed) and insofar as practicable, the type and scale of the transmission line meter should be the same as those of the excitation circuit feed line meter (meter in slant wire feed line or equivalent).

(8) Remote reading antenna ammeters employing vacuum tube rectifiers or semi-conductor devices are acceptable, provided:

(i) The indicating instruments shall meet all the above requirements for linear scale instruments.

(ii) Data are submitted under oath showing the unit has an over-all accuracy of at least 2 percent of the full scale reading.

(iii) The installation, calibration, and checking are in accordance with the requirements of this paragraph.

(9) In the event there is any question as to the method of providing, or the accuracy of the remote meter, the burden of proof of statisfactory performance shall be upon the licensee and the manufacturer of the equipment.

(e) Stations determining power by the indirect method may log the transmission line current in lieu of the antenna current provided the instrument meets the above requirements for antenna ammeters, and further provided that the ratio between the transmission line current and the antenna current is entered each time in the log. In case the station is authorized for the same operating power for both day and nighttime operation, this ratio shall be checked at least once daily. Stations which are authorized to operate with nighttime power different from the daytime power shall check the ratio for each power at least once daily.

(f) No instrument, the seal of which has been broken, or the accuracy of which is questionable, shall be employed. Any instrument which was not originally sealed by the manufacturer that has been opened shall not be used until it has been recalibrated and sealed in accordance with the following: Repairs and recalibration of instruments shall be made by the manufacturer, by an authorized instrument repair service of the manufacturer or by some other properly qualified and equipped instrument repair service. In either case the instrument must be resealed with the symbol or trade-mark of the repair service and a certificate of calibration supplied therewith.

(g) Since it is usually impractical to measure the actual antenna current of a shunt excited antenna system, the current measured at the input of the excitation circuit feed line is accepted as the antenna current.

(h) [Reserved]

(i) The function of each instrument shall be clearly and permanently shown on the instrument itself or on the panel immediately adjacent thereto.

§ 73.40 Transmitter; design, construction, and safety of life requirements.

(a) *Design.* The general design of standard broadcast transmitting equipment [main studio microphone (including telephone lines, if used, as to performance only) to antenna output] shall be in accordance with the following specifications. (In cases where telephone lines are not available to give the performance as required in these specifications a relay transmitter may be authorized to supersede the lines.) For the points not specifically covered in this paragraph, the principles set out shall be followed. The equipment shall be so designed that:

(1) The maximum rated carrier power (determined by § 73.42) is in accordance with the requirements of § 73.41.

(2) The equipment is capable of satisfactory operation at the authorized operating power or the proposed operating power with modulation of at least 85 to 95 percent with no more distortion than given in subparagraph (3) of this paragraph.

(3) The total audio frequency distortion from microphone terminals, including microphone amplifier, to antenna output does not exceed 5 percent harmonics (voltage measurements of arithmetical sum or r. s. s.) when modulated from 0 to 84 percent, and not over 7.5 percent harmonics (voltage measurements of arithmetical sum or r. s. s.) when modulating 85 percent to 95 percent (distortion shall be measured with modulating frequencies of 50, 100, 400, 1000, 5000 and 7500 cycles up to tenth harmonic or 16000 cycles, or any intermediate frequency that readings on these frequencies indicate is desirable).

(4) The audio frequency transmitting characteristics of the equipment from the microphone terminals (including microphone amplifier unless microphone frequency correction is included in which event proper allowance shall be made accordingly) to the antenna output does not depart more than 2 decibels from that at 1000 cycles between 100 and 5000 cycles.

(5) The carrier shift (current) at any percentage of modulation does not exceed 5 percent.

(6) The carrier hum and extraneous noise (exclusive of microphone and studio noises) level (unweighted r.s.s.) is at least 45 decibels below 100 percent modulation for the frequency band of 30 to 20,000 cycles.

(7) The transmitter shall be equipped with suitable indicating instruments in accordance with the requirements of § 73.58 and any other instruments necessary for the proper adjustment and operation of the equipment.

(8) Adequate provision is made for varying the transmitter power output between sufficient limits to compensate for excessive variations in line voltage, or other factors which may affect the power output.

(9) The transmitter is equipped with automatic frequency control equipment capable of maintaining the operating frequency within the limit specified by § 73.59.

(i) The maximum temperature variation at the crystal from the normal operating temperature shall not be greater than,

Plus or minus 0.1° C. when an *X* or *Y* cut crystal is employed, or

Plus or minus 1.0° C. when low temperature coefficient crystal is employed.

(ii) Unless otherwise authorized, a thermometer shall be installed in such manner that the temperature at the crystal can be accurately measured within 0.05° C. for *X* or *Y* cut crystal or 0.5° for low temperature coefficient crystal.

(iii) It is preferable that the tank circuit of the oscillator tube be installed in the temperature controlled chamber.

NOTE: Explanations of excessive frequency deviations will not be accepted when temperature variations are in excess of the values specified.

(10) Means are provided for connection and continuous operation of approved modulation monitor and approved frequency monitor. The radio frequency energy for operation of the approved frequency monitor shall be obtained from a radio-frequency stage prior to the modulated stage unless the monitor is of such design as to permit satisfactory operation when otherwise connected and the monitor circuits shall be such that the carrier is not heterodyned thereby.

(11) Adequate margin is provided in all component parts to avoid overheating at the maximum rated power output.

(12) Any emission appearing on a frequency removed from the carrier by between 15 kc/s and 30 kc/s, inclusive, shall be attenuated at least 25 db below the level of the unmodulated carrier. Compliance with the specification will be deemed to show the occupied bandwidth to be 30 kc/s or less.

(13) Any emission appearing on a frequency removed from the carrier by more than 30 kc/s and up to and including 75 kc/s, inclusive, shall be attenuated at least 35 db below the level of the unmodulated carrier.

(14) Any emission appearing on a frequency removed from the carrier by more than 75 kc/s shall be attenuated at least $43+10\ \mathrm{Log}_{10}$ (Power, in watts) decibels below the level of the unmodulated carrier, or 80 decibels, whichever is the lesser attenuation.

(b) *Construction.* In general, the transmitter shall be constructed either on racks and panels or in totally enclosed frames protected as required by article 810 of the National Electrical Code (section 8192 (a), (b), and (c)), and as set forth in this paragraph and paragraph (c) of this section.

NOTE: The final stages of high power transmitters may be assembled in open frames provided the equipment is enclosed by a protective fence.

(1) Means shall be provided for making all tuning adjustments, requiring voltages in excess of 350 volts to be applied to the circuit, from the front of the panels with all access doors closed.

(2) Proper bleeder resistors or other automatic means shall be installed across all the condenser banks to remove

any charge which may remain after the high voltage circuit is opened (in certain instances the plate circuit of the tubes may provide such protection; however, individual approval of such shall be obtained by the manufacturer in case of standard equipment, and the licensee in case of composite equipment).

(3) All plate supply and other high voltage equipment, including transformers, filters, rectifiers and motor generators, shall be protected so as to prevent injury to operating personnel.

(i) Commutator guards shall be provided on all high voltage rotating machinery (coupling guards on motor generators, although desirable, are not required).

(ii) Power equipment and control panels of the transmitter shall meet the above requirements (exposed 220 volt AC switching equipment on the front of the power control panels is not recommended; however, it is not prohibited).

(iii) Power equipment located at a broadcast station but not directly associated with the transmitter (not purchased as part of same), such as power distribution panels, control equipment on indoor or outdoor stations and the substations associated therewith, are not under the jurisdiction of the Commission; therefore, § 73.46 does not apply.

(iv) It is not necessary to protect the equipment in the antenna tuning house and the base of the antenna with screens and interlocks, provided the doors to the tuning house and antenna base are fenced and locked at all times, with the keys in the possession of the operator on duty at the transmitter. Ungrounded fencing or wires should be effectively grounded, either directly or through proper static leaks. Lighting protection for the antenna system is not specifically required but should be installed.

(v) The antenna, antenna lead-in, counterpoise (if used), etc., shall be installed so as not to present a hazard. The antenna may be located close by or at a distance from the transmitter building. A properly designed and terminated transmission line should be used between the transmitter and the antenna when located at a distance.

(4) Metering equipment. (In addition to the following requirements, instruments shall meet the requirements of §§ 73.39 and 73.58.)

(i) All instruments having more than 1,000 volts potential to ground on the movement shall be protected by a cage or cover in addition to the regular case. (Some instruments are designed by the manufacturer to operate safely with voltages in excess of 1,000 volts on the movement. If it can be shown by the manufacturer's rating that the instrument will operate safely at the applied potential, additional protection is not necessary.)

(ii) In case the plate voltmeter is located on the low potential side of the multiplier resistor with one terminal of the instrument at or less than 1,000 volts above ground, no protective case is required. However, it is good practice to protect voltmeters subject to more than 5,000 volts with suitable over-voltage protective devices across the instrument terminals in case the winding opens.

(iii) The antenna ammeters (both regular and remote) and any other radio frequency instrument which it is necessary for the operator to read shall be so installed as to be easily and accurately read without the operator having to risk contact with circuits carrying high potential radio frequency energy.

(c) *Wiring and shielding.* (1) The transmitter panels or units shall be wired in accordance with standard switchboard practice, either with insulated leads properly cabled and supported or with rigid bus bar properly insulated and protected.

(2) Wiring between units of the transmitter, with the exception of circuits carrying radio frequency energy, shall be installed in conduits or approved fiber or metal raceways to protect it from mechanical injury.

(3) Circuits carrying low level radio frequency energy between units shall be either concentric tube, two wire balanced lines, or properly shielded to prevent the pickup of modulated radio frequency energy from the output circuits.

(4) Each stage (including the oscillator) preceding the modulated stage shall be properly shielded and filtered to prevent unintentional feedback from any circuit following the modulated stage (an exception to this requirement may be made in the case of high level modulated transmitters of approved manufacture which have been properly engineered to prevent reaction).

(5) The crystal chamber, together with the conductor or conductors to the oscillator circuit shall be totally shielded.

(6) The monitors and the radio frequency lines to the transmitter shall be thoroughly shielded.

(d) *Installation.* (1) The installation shall be made in suitable quarters.

(2) Since an operator must be on duty at the transmitter control point during operation, suitable facilities for his welfare and comfort shall be provided at the control point.

(e) [Reserved]

(f) *Studio equipment.* (1) The studio equipment shall be subject to all the above requirements where applicable except as follows:

(i) If it is properly covered by an underwriter's certificate, it will be considered as satisfying the safety requirements.

(ii) Section 8192 of article 810 of the National Electrical Code shall apply for voltages only when in excess of 500 volts.

(2) No specific requirements are made relative to the design and acoustical treatment. However, the studios and particularly the main studio should be in accordance with the standard practice for the class of station concerned, keeping the noise level as low as reasonably possible.

§ 73.41 Maximum rated carrier power; tolerances.

The maximum rated carrier power of a transmitter shall be an even power step as recognized by the Commission's plan of allocation (100 watts, 250 watts, 500 watts, 1 kw., 5 kw., 10 kw., 25 kw., 50 kw.) and shall not be less than the authorized power nor shall it be greater than the value specified in the following table:

Class of station	Maximum power authorized to station	Maximum rated carrier power permitted to be installed
		Watts
Class IV	100 watts	250
	250, 500, or 1,000 watts	1,000
Class III	500 or 1,000 watts	1,000
	5,000 watts	5,000
Class II	250, 500, or 1,000 watts	1,000
	5,000 or 10,000 watts	10,000
	25,000 or 50,000 watts	50,000
Class I	10,000 watts	10,000
	25,000 or 50,000 watts	50,000

§ 73.42 Maximum rated carrier power; how determined.

The maximum rated carrier power of a standard broadcast transmitter shall be determined as the sum of the applicable power ratings of the vacuum tubes employed in the last radio stage.

§ 73.43 Changes in equipment; authority for.

No licensee or permittee shall change, in the last radio stage, the number of vacuum tubes, nor change to vacuum tubes of different power rating or class of operation, nor shall it change the system of modulation, without authority of the Commission.

§ 73.44 Other changes in equipment.

Other changes except as provided for in this subpart which do not affect the maximum power rating or operating power of the transmitter or the operation or precision of the frequency control equipment may be made at any time without authority of the Commission, but in the next succeeding application for renewal of license such changes which affect the information already on file shall be shown in full.

§ 73.45 Radiating system.

(a) All applicants for new, additional, or different broadcast facilities and all licensees requesting authority to change the transmitter site of an existing station shall specify a radiating system the efficiency of which complies with the requirements of good engineering practice for the class and power of the station. (See §§ 73.186 and 73.189.)

(b) No broadcast station licensee or permittee shall change the physical height of the transmitting antenna, or supporting structures, or make any changes in the radiating system which will measurably alter the radiation patterns, except upon application to and authority from the Commission.

(c) Should any changes occur which would alter the resistance of the antenna system, the licensee shall immediately make a new determination of the antenna resistance (see § 73.54) and shall submit application for authority to determine power by the direct method on the basis of the new measurements. In this connection, see §§ 73.316(g) and 73.685(h).

(d) The antenna and/or supporting structure shall be painted and illumi-

nated in accordance with the specifications supplied by the Commission pursuant to section 303(q) of the Communications Act of 1934 as amended. (See Part 17 of this chapter, Construction, Marking, and Lighting of Antenna Structures.)

(e) The simultaneous use of a common antenna or antenna structure by more than one standard broadcast station, or by one or more standard broadcast stations and one or more stations of any other class or service may be authorized provided:

(1) Complete verified engineering data are submitted showing that satisfactory operation of each station will be obtained without adversely affecting the operation of the other station.

(2) The minimum antenna height or field intensity for each standard broadcast station concerned complies with paragraph (a) of this section.

(3) Complete responsibility for maintaining the installation and for painting and illuminating the structure in accordance with the pertinent provisions of Part 17 of this chapter is assumed by one of the licensees.

§ 73.46 Transmitter.

(a) The transmitter proper and associated transmitting equipment of each broadcast station shall be designed, constructed, and operated in accordance with good engineering practice in all phases not otherwise specifically included in the regulations in this subpart.

(b) The transmitter shall be wired and shielded in accordance with good engineering practice and shall be provided with safety features in accordance with the specifications of article 810 of the current National Electrical Code as approved by the American Standard Association.

(c) The station equipment shall be so operated, tuned, and adjusted that emissions outside of the authorized channel do not cause harmful interference to the reception of other radio stations. Standard broadcast stations employing radio transmitters type accepted after January 1, 1960, shall maintain the bandwidth occupied by their emissions in accordance with the specifications set forth in § 73.40(a). Stations employing transmitters installed or type accepted prior to January 1, 1960, shall achieve the highest degree of compliance practicable with their existing equipment. In either case, should harmful interference to the reception of other radio stations occur, the licensee may be required to take such further steps as may be necessary to eliminate the interference.

(d) The audio distortion, audio frequency response, carrier hum, noise level, and other essential phases of the operation which control the external effects shall at all times conform to the requirements of good engineering practice.

§ 73.47 Equipment performance measurements.

(a) The licensee of each standard broadcast station shall make the following equipment performance measurements at yearly intervals. One such set shall be made during the four-month period preceding the date of filing application for renewal of station license:

(1) Data and curves showing over-all audio frequency response from 30 to 7500 CPS for approximately 25, 50, 85, and 100 (if obtainable) percent modulation. Family of curves should be plotted (one for each percentage above) with DB above and below a reference frequency of 1000 CPS as ordinate and audio frequency as abscissa.

(2) Data and curves showing audio frequency harmonic content for 25, 50, 85, and 100 percent modulation for fundamental frequencies of 50, 100, 400, 1000, 5000, and 7500 CPS (either arithmetical or root sum square values up to the tenth harmonic or 16000 CPS). Plot family of curves (one for each percentage above) with percent distortion as ordinate and audio frequency as abscissa.

(3) Data showing percentage carrier shift for 25, 50, 85, and 100 percent modulation with 400 CPS tone.

(4) Carrier hum and extraneous noise generated within the equipment and measured as the level below 100 percent modulation throughout the audio spectrum or by bands.

(5) Measurements or evidence showing that spurious radiations including radio frequency harmonics are suppressed or are not present to a degree capable of causing objectionable interference to other radio services. Field intensity measurements are preferred but observations made with a communications type receiver may be accepted. However, in particular cases involving interference or controversy, the Commission may require actual measurements. Measurements shall be made with the equipment adjusted for normal program operation and shall include all circuits between main studio amplifier input and antenna output including equalizer or correction circuits normally employed, but without compression if such amplifier is employed.

(b) The data required by paragraph (a) of this section together with a description of instruments and procedure, signed by the engineer making the measurements, shall be kept on file at the transmitter and retained for a period of two years and on request shall be made available during that time to any duly authorized representative of the Federal Communications Commission.

§ 73.48 Acceptability of broadcast transmitters for licensing.

(a) In order to facilitate the filing of and action on applications for station authorizations, transmitters will be accepted for licensing by the Commission under one of the following conditions:

(1) A transmitter may be type-accepted upon the request of any manufacturer of transmitters built in quantity by following the type acceptance procedure set forth in Part 2 of this chapter, provided that the data and information submitted indicate that the transmitter meets the requirements of § 73.40. If accepted, such transmitter will be included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment". Applicants specifying transmitters included on such a list need not submit detailed descriptions and diagrams where the correct type number is specified, provided that the equipment proposed is identical with that accepted. Copies of this list are available for inspection at the Commission's office in Washington, D.C., and at each of its field offices.

(2) An application specifying a transmitter not included on the Radio Equipment List, Part B, may be accepted upon the request of a prospective licensee submitting with the application for construction permit a complete description of the transmitter, including the circuit diagram, listing of all tubes used, function of each, multiplication in each stage, plate current and voltage applied to each tube, a description of the oscillator circuit together with any devices installed for the purpose of frequency stabilization and the means of varying output power to compensate for power supply voltage variations. However, if this data has been filed with the Commission by a manufacturer in connection with a request for type acceptance, it need not be submitted with the application for construction permit but may be referred to as "on file". Measurement data for type acceptance made in accordance with subparagraph (1) of this paragraph shall be submitted with the license application.

(3) A transmitter shown on an instrument of authorization by manufacturer and type number, or as a composite, and which was in use prior to June 30, 1955, may continue to be used by the licensee, his successors or assignees, provided such transmitter continues to comply with the rules and regulations.

(4) A permittee may, without further authority, install a transmitter other than that specifically authorized in its construction permit if such transmitter is listed in the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment" as accepted for the power authorized.

(5) A licensee may, without further authority, install and utilize a transmitter other than that specifically authorized in its station license if the transmitter so installed and utilized is listed in the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment" as accepted for the power authorized if the Commission and the Engineer in Charge of the radio district in which the station is located are notified within three days after the date of installation of the transmitter. Such notice shall include the make and type number of the transmitter and a certification by the licensee that the transmitter as installed complies with the appropriate technical provisions of this subpart.

(b) Additional rules with respect to withdrawal of type-acceptance, modification of type-accepted equipment and limitations on the findings upon which type acceptance is based are set forth in Part 2 of this chapter.

§ 73.49 Requirements for approval of frequency monitors.

(a) *General requirements.* (1) Any manufacturer desiring to submit a monitor for type approval shall supply the Commission with full specification de-

tails (two sworn copies) as well as the test data specified in paragraph (c) of this section. If this information appears to meet the requirements of the rules, shipping instructions will be issued to the manufacturer. The shipping charges to and from the Laboratory at Laurel, Maryland, shall be paid for by the manufacturer. Approval of a monitor will only be given on the basis of the data obtained from the sample monitor submitted to the Commission for test.

(2) In approving a monitor upon the basis of the tests conducted by the Laboratory, the Commission merely recognizes that the type of monitor has the inherent capability of functioning in compliance with the rules, if properly constructed, maintained, and operated. The Commission realizes that the frequency monitor may have limited range over which the visual indicator will determine deviations. Accordingly, it may be necessary that adjunct equipment be used to determine major deviations.

NOTE: In addition to the visual indicator, the range of which may be limited in order to obtain the required accuracy, an aural indicator should also be employed to indicate frequency deviations beyond the range of the visual indicator, particularly where the visual indicator is so designed that the indication becomes zero when the deviations become considerably greater than the range of the instrument.

(3) Additional rules with respect to withdrawal of type approval, modification of type approval equipment and limitations on the findings upon which type approval is based are set forth in Part 2, Subpart F, of this chapter.

(b) *General specifications.* The general specifications that frequency monitors shall meet before they will be approved by the Commission are as follows:

(1) The unit shall have an accuracy of at least five parts per million under ordinary conditions (temperature, humidity, power supply, and other conditions which may affect its accuracy) encountered in standard broadcast stations throughout the United States.

(2) The range of the indicating device shall be at least from 20 cycles below to 20 cycles above the assigned frequency.

(3) The scale of the indicating device shall be so calibrated as to be accurately read within at least 1 cycle.

(4) The unit shall be equipped with an automatic temperature control chamber (preferably enclosing the tank circuits of the oscillator) such that the maximum temperature variation at the crystal from the normal operating temperature shall not be greater than,

Plus or minus 0.05° C. when *X* or *Y* cut crystal is employed, or

Plus or minus 0.5° C. when low temperature coefficient crystal is employed.

(5) Unless otherwise specifically authorized, the instrument shall be equipped with a thermometer such that the temperature can be accurately measured within 0.025° C. for *X* or *Y* cut crystal or 0.25° C. for low temperature coefficient crystal.

(6) The monitor circuit shall be such that it may be continuously operated and the emitted carrier of the station is not heterodyned thereby.

(7) Means shall be provided for adjustment of the temperature or other means for correction of the indications of the monitor to agree with the external standard.

(c) *Tests to be made by the Laboratory Division of the F. C. C.* The tests to be made at the Laboratory will include the determination of the following:

(1) *Accuracy.* (i) Oscillator frequency, as received.

(ii) Constancy of oscillator frequency, as measured several times in 1 month.

(iii) Accuracy of readings of frequency-difference instrument.

(iv) Functioning of frequency adjustment device.

(v) Effects on frequency of changing tubes and of voltage variations.

(2) *Temperature control stability.* Effect on frequency of variation of room temperature through a range not to exceed 10° to 35° C.

(3) *Sensitivity.* Response of indicating instrument to small changes of frequency.

(4) *General construction.* (i) Inspection to determine ability to stand shipment and service.

(ii) Special tests to determine quality of construction, such as effect of tilting or tipping on frequency.

(5) *Miscellaneous performance.* Various, depending on character of apparatus (e. g., changes after stopping and starting, effect of varying coupling with transmitter, etc.).

(d) *Test operation of equipment.* The equipment will be operated in a test in the same way and the same conditions under which it will be used in service as specified by the manufacturer. The manufacturer shall supply to the Laboratory Division all instructions or services which will be supplied to the purchaser of the equipment. The equipment, as submitted, shall be adjusted for operation in connection with broadcast stations operating on 1600 kilocycles.

§ 73.50 Requirements for approval of modulation monitors.

(a) Any manufacturer desiring to submit a monitor for type approval shall supply the Commission with full specification details (two sworn copies) specified in paragraph (b) of this section. If this information appears to meet the requirements of the rules, shipping instructions will be issued to the manufacturer. The shipping charges to and from the Laboratory at Laurel, Maryland, shall be paid for by the manufacturer. Approval of a monitor will only be given on the basis of the data obtained from the sample monitor submitted to the Commission for test.

(1) In approving a monitor upon the basis of the tests conducted by the Laboratory, the Commission merely recognizes that the type of monitor has the inherent capability of functioning in compliance with the rules, if properly constructed, maintained, and operated.

(2) Additional rules with respect to withdrawal of type approval, modification of type approval equipment and limitations on the findings upon which type approval is based are set forth in Part 2, Subpart F, of this chapter.

(b) The specifications that the modulation monitor shall meet before it will be approved by the Commission are as follows:

(1) A DC meter for setting the average rectified carrier at a specific value and to indicate changes in carrier intensity during modulation.

(2) A peak indicating light or similar device that can be set at any predetermined value from 50 to 120 percent modulation to indicate on positive peaks, and/or from 50 to 100 percent negative modulation.

(3) A semi-peak indicator with a meter having the characteristics given below shall be used with a circuit such that peaks of modulation of duration between 40 and 90 milliseconds are indicated to 90 percent of full value and the discharge rate adjusted so that the pointer returns from full reading to 10 percent of zero within 500 to 800 milliseconds. A switch shall be provided so that this meter will read either positive or negative modulation and, if desired, in the center position it may read both in a full-wave circuit. The characteristics of the indicating meter are as follows:

(i) The damping factor shall be between 16 and 200. The useful scale length shall be at least 2.3 inches. The meter shall be calibrated for modulation from 0 to 110 percent and in decibels below 100 percent with 100 percent being 0 db.

(ii) The accuracy of the reading on percentage of modulation shall be ±2 percent for 100 percent modulation, and ±4 percent of full scale reading at any other percentage of modulation.

(4) The frequency characteristics curve shall not depart from a straight line more than ±½ db from 30 to 10000 cycles. The amplitude distortion or generation of audio harmonics shall be kept to a minimum.

(5) The modulation meter shall be equipped with appropriate terminals so that an external peak counter can be readily connected.

(6) Modulation will be tested at 115 volts ±5 percent and 60 cycles, and the above accuracies shall be applicable under these conditions.

(7) All specifications not already covered above, and the general design, construction, and operation of these units must be in accordance with good engineering practice.

(c) The modulation monitor may be a part of the frequency monitor.

TECHNICAL OPERATION

§ 73.51 Operating power; how determined.

(a) Except as provided in paragraph (b) of this section, the operating power shall be determined by the direct method (the square of the antenna current times the antenna resistance at the point where the current is measured and at the operating frequency).

(b) Operating power shall be determined on a temporary basis by the indirect method: (1) In case of an emergency where the licensed antenna system has been damaged by causes beyond the control of the licensee (see § 73.45), or (2) Pending completion of authorized changes in the antenna system, or (3) If any change is made in the antenna sys-

tem or any other change is made which may affect the antenna system. (See § 73.45.)

§ 73.52 Operating power; indirect measurement.

(a) The operating power determined by indirect measurement from the plate input power of the last radio stage is the product of the plate voltage (Ep), the total plate current of the last radio stage (Ip), and the proper factor (F) given in paragraph (b) of this section: That is

$$\text{Operating power} = Ep \times Ip \times F$$

(b) Factor to be used.

Factor (F)	Method of modulation	Maximum rated carrier power	Class of amplifier
0.70	Plate	0.1-1.0 kw	
.80	Plate	5 kw and over	
.35	Low Level	0.1 kw and over	B
.65	Low Level	0.1 kw and over	BC [1]
.35	Grid	0.1 kw and over	

[1] All linear amplifier operation where efficiency approaches that of Class C operation.

(c) In computing operating power by the indirect method, the factor in paragraph (b) of this section shall apply in all cases, and no distinction will be recognized due to the operating power being less than the maximum rated carrier power.

§ 73.54 Operating power; direct measurement.

(a) Applications to determine the operating power by the direct method shall be made on FCC Form 302.

(b) The resistance variation method, substitution method and bridge method are acceptable methods of measuring the total antenna resistance.

(c) A determination of the resistance of an omni-directional antenna shall be made by taking a series of measurements at 5, 10, 15, and 20 kc/s on each side of the operating frequency. The values measured should be plotted with frequency as abscissa and resistance in ohms as ordinate and a smooth curve drawn. The point on the ordinate where this curve intersects the operating frequency gives the value of the antenna resistance.

(d) Antenna resistance for a directional antenna system shall be measured at the point of common radio frequency input to the directional antenna system. The following conditions shall obtain:

(1) The antenna shall be finally adjusted for the required pattern.

(2) The reactance at the operating frequency and at the point of measurement shall be adjusted to zero or as near thereto as practical.

(3) Suitable radio-frequency bridge or other method shall be employed to determine the resistance and reactance at the point of common radio frequency input.

(4) Resistance and reactance measurements at approximately 5, 10, 15, and 20 kc/s on each side of the operating frequency shall be made. The values measured shall be plotted and the resistance at the operating frequency determined in the same manner as set forth in paragraph (c) of this section.

(5) A permanently installed antenna ammeter shall be placed in each element of the system as well as at the point of measurement of resistance.

(e) The license for a station of power of 5 kw or under which employs a directional antenna will specify the antenna resistance as 92.5 percent of that determined at the point of common input. The resistance specified for stations of a power over 5 kw will be 95 percent of that determined at the point of common input.

§ 73.55 Modulation.

The percentage of modulation shall be maintained as high as possible consistent with good quality of transmission and in no case less than 85 percent on peaks nor more than 100 percent on negative peaks of frequent recurrence during any selection which is transmitted at the highest level of the program under consideration.

§ 73.56 Modulation monitors.

(a) Each station shall have in operation, either at the transmitter or at the place the transmitter is controlled, a modulation monitor of a type approved by the Commission.

NOTE: Approved modulation monitors are included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment". Copies of this list are available for inspection at the Commission's office in Washington, D. C. and at each of its field offices.

(b) In the event that the modulation monitor becomes defective the station may be operated without the monitor pending its repair or replacement for a period not in excess of 60 days without further authority of the Commission: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the monitor was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the monitor is found to be defective and immediately after the repaired or replacement monitor has been installed and is functioning properly.

(3) The degree of modulation of the station shall be monitored with a cathode ray oscilloscope or other acceptable means.

(c) If conditions beyond the control of the licensee prevent the restoration of the monitor to service within the above allowed period, informal request in accordance with § 1.549 of this chapter may be filed with the Engineer in Charge of the radio district in which the station is operating for such additional time as may be required to complete repairs of the defective instrument.

(d) Each station operated by remote control shall continuously, except when other readings are being taken, monitor percent of modulation or shall be equipped with an automatic device to limit percent of modulation on negative peaks to 100.

§ 73.57 Operating power; maintenance of.

(a) The operating power of each station shall be maintained as near as practicable to the licensed power and shall not exceed the limits of 5 percent above and 10 percent below the licensed power, except that in an emergency when due to causes beyond control of the licensee it becomes impossible to operate with full licensed power, the station may be operated with reduced power for a period not to exceed 10 days, provided the Commission and the Engineer in Charge of the radio district in which the station is located shall be notified immediately after the emergency develops and also upon the resumption of licensed power.

(b) In addition to maintaining the operating power within the above limitations, stations employing directional antenna systems shall maintain the ratio of the antenna currents in the elements of the system within 5 percent of that specified by the terms of the license or other instrument of authorization.

§ 73.58 Indicating instruments.

(a) Each standard broadcast station shall be equipped with indicating instruments which conform with the specifications set forth in § 73.39 for measuring the DC plate circuit current and voltage of the last radio frequency amplified stage; the radio frequency base current of each antenna element; and, for stations employing directional antenna systems, the radio frequency current at the point of common input to the directional antenna.

(b) In the event that any one of these indicating instruments becomes defective when no substitute which conforms with the required specifications is available, the station may be operated without the defective instrument pending its repair or replacement for a period not in excess of 60 days without further authority of the Commission: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the meter was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the instrument is found to be defective and immediately after the repaired or replacement instrument has been installed and is functioning properly.

(3) If the defective instrument is the antenna current meter of a nondirectional station which does not employ a remote antenna ammeter, or if the defective instrument is the common point meter of a station which employs a directional antenna, and does not employ a remote common point meter, the operating power shall be determined by the indirect method in accordance with § 73.52 during the entire time the station is operated without the antenna current meter or common point meter. However, if a remote antenna ammeter or a remote common point meter is employed and the antenna current meter or com-

mon point meter becomes defective, the remote meter may be used in determining operating power by the direct method pending the return to service of the regular meter, provided other meters are maintained at same value previously employed.

(c) If conditions beyond the control of the licensee prevent the restoration of the meter to service within the above allowed period, informal request in accordance with § 1.549 of this chapter may be filed with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

(d) Remote antenna ammeters and remote common point meters are not required; therefore, authority to operate without them is not necessary. However, if a remote antenna ammeter or common point meter is employed and becomes defective, the antenna base currents may be read and logged once daily for each mode of operation, pending the return to service of the regular remote meter.

§ 73.59 Frequency tolerance.

The operating frequency of each station shall be maintained within 20 cycles of the assigned frequency.

§ 73.60 Frequency monitor.

(a) The licensee of each station shall have in operation, either at the transmitter or at the place where the transmitter is controlled, a frequency monitor of a type approved by the Commission which shall be independent of the frequency control of the transmitter.

NOTE: Approved frequency monitors are included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment". Copies of this list are available for inspection at the Commission's office in Washington, D. C. and at each of its field offices.

(b) In the event that the frequency monitor becomes defective the station may be operated without the monitor pending its repair or replacement for a period not in excess of 60 days without further authority of the Commission: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the monitor was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the monitor is found to be defective and immediately after the repaired or replacement monitor has been installed and is functioning properly.

(3) The frequency of the station shall be measured by an external source at least once each seven days and the results entered in the station log.

(c) If conditions beyond the control of the licensee prevent the restoration of the monitor to service within the above allowed period, informal request in accordance with § 1.549 of this chapter may be filed with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

§ 73.61 New equipment; restrictions.

The Commission will authorize the installation of new transmitting equipment in a broadcast station or changes in the frequency control of an existing transmitter only if such equipment is so designed that there is reasonable assurance that the transmitter is capable of maintaining automatically the assigned frequency within the limits specified in § 73.59.

§ 73.62 Automatic frequency control equipment; authorization required.

New automatic frequency control equipment and changes in existing automatic frequency control equipment that may affect the precision of frequency control or the operation of the transmitter shall be installed only upon authorization from the Commission.

§ 73.63 Auxiliary transmitter.

Upon showing that a need exists for the use of an auxiliary transmitter in addition to the regular transmitter of a broadcast station, a license therefor may be issued: *Provided,* That:

(a) An auxiliary transmitter may be installed either at the same location as the main transmitter or at another location.

(b) A licensed operator shall be in control whenever an auxiliary transmitter is placed in operation.

(c) The auxiliary transmitter shall be maintained so that it may be placed in operation at any time for any one of the following purposes:

(1) The transmission of the regular programs upon the failure of the main transmitter.

(2) The transmission of the regular programs during maintenance or modification work on the main transmitter necessitating discontinuance of its operation.

(3) Emergency Broadcast System operation, provided the auxiliary transmitter is used in connection with a National Defense Emergency Authorization.

(4) Upon request of a duly authorized representative of the Commission.

(d) The auxiliary transmitter shall be tested at least once each week to determine that it is in proper operating condition and that it is adjusted to the licensed frequency: *Provided, however,* That the test in any week may be omitted if the auxiliary transmitter has been operated during the week pursuant to paragraph (c) of this section and such operation was satisfactory. Tests on the licensed frequency shall be conducted only between 12 midnight and 9 a.m., local standard time. A record shall be kept of the time and result of each test. Such records shall be retained for a period of 2 years.

(e) The auxiliary transmitter shall be equipped with satisfactory control equipment which will enable the maintenance of the frequency emitted by the station within the limits prescribed by the regulations in this part.

(f) An auxiliary transmitter which is licensed at a geographical location different from that of the main transmitter shall be equipped with a frequency control which will automatically hold the frequency within the limits prescribed by the regulations in this part without any manual adjustment during operation or when it is being put into operation.

(g) The operating power of an auxiliary transmitter may be less than the authorized power, but in no event shall it be greater than such power.

(h) All regulations as to safety requirements and spurious emissions applying to broadcast transmitting equipment shall apply also to an auxiliary transmitter.

§ 73.64 Alternate main transmitters.

The licensee of a standard broadcast station may be licensed for alternate main transmitters provided that a technical need for such alternate transmitters is shown, such as licensees maintaining 24-hour schedule and needing alternate operations for maintenance, or where developmental work requires alternate operation, and that the following conditions are met:

(a) Both transmitters are located at the same place.

(b) The transmitters have the same power rating except at stations operating with different daytime and nighttime power, when it shall be permissible to employ transmitters of power ratings appropriate to either the licensed daytime or nighttime power.

(c) The external effects from both transmitters are substantially the same as to frequency stability, reliability of operation, radio harmonics and other spurious emissions, audio frequency range and audio harmonic generation in the transmitter.

§ 73.65 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of that part.

REMOTE CONTROL

AUTHORITY: §§ 3.66 to 3.68 issued under sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318.

§ 73.66 Remote control authorization.

(a) Application to operate a station by remote control may be made as a part of the application for construction permit for a new station, provided that the proposal is for non-directional operation with a power of 10 kw or less.

(b) Application to operate an authorized station by remote control shall be made on FCC Form 301-A.

(c) An authorization for remote control will be issued only after a satisfactory showing has been made in regard to the following, among others:

(1) The location of the remote control point(s);

(2) The directional antenna system, if such is authorized, is in proper adjustment and is stable;

(3) The transmitter, if the power rating is in excess of 10 kw, is reliable and capable of being operated by remote control.

§ 73.67 Remote control operation.

(a) Operation by remote control shall be subject to the following conditions:

(1) The equipment at the operating and transmitting positions shall be so installed and protected that it is not accessible to or capable of operation by persons other than those duly authorized by the licensee.

(2) The control circuits from the operating positions to the transmitter shall provide positive on and off control and shall be such that open circuits, short circuits, grounds or other line faults will not actuate the transmitter and any fault causing loss of such control will automatically place the transmitter in an inoperative position.

(3) A malfunction of any part of the remote control equipment and associated line circuits resulting in improper control or inaccurate meter readings shall be cause for the immediate cessation of operation by remote control.

(4) Control and monitoring equipment shall be installed so as to allow the licensed operator at the remote control point to perform all the functions in a manner required by the Commission's rules.

(5) The indications at the remote control point of the antenna current meter or, for directional antennas, the common point current meter and remote base current meters, shall be read and entered in the operating log each half hour.

(6) The indications at the transmitter, if a directional antenna station, of the common point current, base currents, phase monitor sample loop currents and phase indications shall be read and entered in the operating log once each day for each pattern. These readings must be made within two hours after the commencement of operation for each pattern.

(b) All stations, whether operating by remote control or direct control, shall be equipped so as to be able to follow the prescribed procedure set forth in § 73.921(b).

§ 73.68 Remote control renewal application.

(a) An application for renewal of a remote control authorization may be made on the application for renewal of station license.

(b) Stations employing directional antenna and operated by remote control shall make a skeleton proof of performance each year, consisting of three or four measurements on each radial used in the original application and must submit the results of these measurements, plus the monitoring point readings, with the renewal application.

OPERATION

§ 73.71 Minimum operation schedule.

(a) All standard broadcast stations are required to maintain an operating schedule of not less than two-thirds of the total hours they are authorized to operate between 6 a.m. and 6 p.m., local standard time, and two-thirds of the total hours they are authorized to operate between 6 p.m. and midnight, local standard time, on each day of the week except Sunday: *Provided, however,* That stations authorized for daytime operation only need comply only with the minimum requirement for operation between 6 a.m. and 6 p.m

(b) In the event that causes beyond a licensee's control make it impossible to adhere to the operating schedule in paragraph (a) of this section or to continue operating, the station may limit or discontinue operation for a period of not more than 10 days, without further authority of the Commission. However, the Commission and the Engineer in Charge of the radio district in which the station is located shall be immediately notified in writing if the station is unable to maintain the minimum operating schedule and shall be subsequently notified when the station resumes regular operation.

§ 73.72 Operation during experimental period.

The licensee of each standard broadcast station shall operate or refrain from operating its station during the experimental period as directed by the Commission in order to facilitate frequency measurement or for the determination of interference.

§ 73.73 Specified hours.

If the license of a station specifies the hours of operation, the schedule so specified shall be adhered to except as provided in §§ 73.71 and 73.72.

§ 73.74 Sharing time.

If the licenses of stations authorized to share time do not specify hours of operation, the licensees shall endeavor to reach an agreement for a definite schedule of periods of time to be used by each. Such agreement shall be in writing and each licensee shall file the same in triplicate original with each application to the Commission for renewal of license. If and when such written agreements are properly filed in conformity with this section the file mark of the Commission will be affixed thereto, one copy will be retained by the Commission, one copy forwarded to the Engineer in Charge of the radio district in which the station is located, and one copy returned to the licensee to be posted with the station license and considered as a part thereof. If the license specifies a proportionate time division, the agreement shall maintain this proportion. If no proportionate time division is specified in the license, the licensees shall agree upon a division of time. Such division of time shall not include simultaneous operation of the stations unless specifically authorized by the terms of the license.

§ 73.75 Sharing time; equivalence of day and night hours.

For the purpose of determining the proportionate division of time of the broadcast day for sharing time stations 1 night hour shall be considered the equivalent of 2 day hours.

§ 73.76 Sharing time; experimental period.

If the license of a station authorized to share time does not specify the hours of operation, the station may be operated for the transmission of regular programs during the experimental period provided an agreement thereto is reached with the other stations with which the broadcast day is shared and further provided such operation is not in conflict with § 73.72. Time-sharing agreements for operation during the experimental period need not be submitted to the Commission.

§ 73.77 Sharing time; departure from regular schedule.

A departure from the regular operating schedule set forth in a time-sharing agreement will be permitted only in cases where an agreement to that effect is reduced to writing, is signed by the licensees of the stations affected thereby and filed in triplicate by each licensee with the Commission prior to the time of the proposed change. If time is of the essence, the actual departure in operating schedule may precede the actual filing of written agreement, provided appropriate notice is sent to the Commission and the Engineer in Charge of the radio district in which the station is located.

§ 73.78 Sharing time stations; notification to Commission.

If the licensees of stations authorized to share time are unable to agree on a division of time, the Commission shall be so notified by statement to that effect filed with the applications for renewals of licenses. Upon receipt of such statement the Commission will designate the applications for a hearing and, pending such hearing, the operating schedule previously adhered to shall remain in full force and effect.

§ 73.79 License to specify sunrise and sunset hours.

If the licensee of a broadcast station is required to commence or cease operation, or to change the mode of operation of the station at the times of sunrise and sunset at any particular location, the controlling times for each month of the year are set forth in the station's instrument of authorization. Uniform sunrise and sunset times are specified for all of the days of each month, based upon the actual times of sunrise and sunset for the fifteenth day of that month adjusted to the nearest quarter hour. In accordance with a standardized procedure described therein, actual sunrise and sunset times are derived by interpolation in the tables of the 1946 American Nautical Almanac, issued by the Nautical Almanac Office of the United States Naval Observatory.

§ 73.80 Secondary station; filing of operating schedule.

The licensee of a secondary station which is authorized to operate limited time and which may resume operation at the time the dominant station (or stations) on the same channel ceases operation shall, with each application for renewal of license, file in triplicate a copy

of its regular operating schedule, bearing a signed notation by the licensee of the dominant station of its objection or lack of objection thereto. Upon approval of such operating schedule, the Commission will affix its file mark and return one copy to the licensee authorized to operate limited time, which shall be posted with the station license and considered as a part thereof. Departure from said operating schedule will be permitted only in accordance with the procedure set forth in § 73.77.

§ 73.81 Secondary station; failure to reach agreement.

If the licensee of a secondary station authorized to operate limited time and a dominant station on a channel are unable to agree upon a definite time for resumption of operation by the station authorized limited time, the Commission shall be so notified by the licensee of the station authorized limited time. After receipt of such statement the Commission will designate for hearing the applications of both stations for renewal of license, and pending the hearing the schedule previously adhered to shall remain in full force and effect.

§ 73.82 Departure from schedule; material violation.

In all cases where a station licensee is required to prepare and file an operating schedule, any deviation or departure from such schedule, except as herein authorized, shall be considered as a violation of a material term of the license.

§ 73.83 Local standard time.

All references in this part to standard time or local standard time refer to local standard time as determined and fixed by the Interstate Commerce Commission.

§ 73.84 Daylight saving time.

If local time is changed from standard time to daylight saving time at the location of all stations sharing time on the same channel, the hours of operation of all such stations on that channel shall be understood to refer to daylight saving time, and not standard time, as long as daylight saving time is observed at such locations. This provision shall govern when the time is changed by provision of law or general observance of daylight saving time by the various communities, and when the time of operation of such stations is specified in the license or is mutually agreed upon by the licensees: *Provided, however,* That when the license specifies average time of sunrise and sunset, local standard time shall be observed. In no event shall a station licensed for daytime only operate on regular schedule prior to local sunrise, or shall a station licensed for greater daytime power than nighttime power or for a different radiation pattern for daytime operation than for nighttime operation operate with the daytime power or radiation pattern prior to local sunrise.

§ 73.85 Changes in time; agreement between licensees.

Where the local time is not changed from standard time to daylight saving time at the location of all stations sharing time on the same channel, the hours of operation of such stations shall be understood to have reference to standard time, and not daylight saving time, unless said licensees mutually agree upon a new schedule which shall be effective only while daylight saving time is observed at the location of some of these stations.

§ 73.86 Local standard time; license provisions.

The time of operation of any broadcast station which does not share time with other stations on the same channel shall be understood to have reference to local standard time unless modification of such license with respect to hours of operation is authorized by the Commission.

§ 73.87 Program transmissions prior to local sunrise.

(a) The provisions of §§ 73.6, 73.8, 73.9, 73.10, 73.23, 73.79, and 73.84 shall not prevent the transmission of programs between 4 o'clock a.m., local standard time, and local sunrise, of standard broadcast stations with their authorized daytime facilities: *Provided,* That the provisions of this section shall not extend to:

(1) Stations regularly sharing time during daytime hours either under licenses pursuant to which time-sharing agreements have been entered into or licenses specifying hours of operation, unless time-sharing agreements have been reached covering such operation prior to local sunrise. Sections 73.74, 73.77, and 73.78 shall be applicable to such agreements.

(2) Any Class II station which by use of its daytime facilities causes objectionable interference, as determined by the standard broadcast Technical Standards of this subpart or by the engineering standards of NARBA or the U.S./Mexican Agreement (whichever is controlling) within the 0.5 mv/m 50 percent time skywave contour of any Class I station of the United States, Mexico, or any country party to NARBA, except (i) where the Class I station is located east of the Class II station, in which case operation may begin at local sunrise at the Class I station; (ii) where an agreement has been reached with the United States Class I station affected to begin operation prior to local sunrise.

(3) Operation by use of its daytime facilities of any Class II station on any Class I–A channel not assigned to the United States under the North American Regional Broadcasting Agreement or under the U.S./Mexican Agreement.

(4) Class IV stations authorized for operation with daytime power in excess of 250 watts.

(b) Any station operating during such hours receiving notice from the Commission that undue interference is caused shall refrain from such operation during such hours pending further notice from the Commission.

(c) Nothing contained in outstanding instruments of authorization for such stations shall prohibit such operation except as herein provided.

(d) The period 4 a. m. to 6 a. m., local standard time, shall not be included in determining compliance with § 73.71.

(e) Restrictions imposed by § 73.187 on daytime operations shall apply to presunrise operation under this section.

§ 73.88 Blanketing interference.

The licensee of each broadcast station is required to satisfy all reasonable complaints of blanketing interference within the 1 v/m contour.

§ 73.89 Use of frequency and modulation monitors at auxiliary transmitters.

(a) The following shall govern the installation of approved frequency and modulation monitors at auxiliary transmitters:

(1) In case the auxiliary transmitter location is at a site different from that of the main transmitter, an approved frequency monitor shall be installed at the auxiliary transmitter, except when the frequency of the auxiliary transmitter can be monitored by means of the frequency monitor at the main transmitter.

(2) The provision that the frequency monitor may be located at the site of the main transmitter shall not relieve the obligation that the frequency deviation of the auxiliary transmitter shall be maintained within 20 cycles.

(3) Installation of an approved modulation monitor at the location of the auxiliary transmitter, when different from that of the main transmitter, is optional with the licensee. However, when it is necessary to operate the auxiliary transmitter beyond 2 calendar days, a modulation monitor shall be installed and operated at the auxiliary transmitter. The monitor (if taken from the main transmitter) shall be reinstalled at the main transmitter immediately upon resumption of operation of the main transmitter.

(4) In all cases where the auxiliary transmitter and the main transmitter have the same location, the same frequency and modulation monitor may be used for monitoring both transmitters, provided they are so arranged as to be switched readily from one transmitter to the other.

§ 73.90 Emergency Weather Warnings.

Upon receipt of notification from the United States Weather Bureau of an Emergency Weather Warning of a condition of immediate danger to life and property, all standard broadcast stations may, at their option, during authorized hours of operation only, broadcast the Emergency Action Notification Signal (two 5-second carrier breaks and 15 seconds of 1,000 CPS tone) followed by the Emergency Weather Warning. Nothing in this section shall be construed as authorizing a daytime only or limited time station to operate during unauthorized hours.

(Sec. 606, 48 Stat. 1104, as amended; 47 U.S.C. 606, E.O. 11092, 28 F.R. 1847)

§ 73.91 Discontinuance of operation.

The licensee of each station shall notify the Commission in Washington, D.C., and the Engineer in Charge of the radio district where such station is located of permanent discontinuance of operation at least two days before opera-

tion is discontinued. The licensee, shall, in addition, immediately forward the station license and other instruments of authorization to the Washington, D.C., office of the Commission for cancellation.

§ 73.92 Station and operator licenses; posting of.

(a) The station license and any other instrument of station authorization shall be posted in a conspicuous place and in such manner that all terms are visible, at the place the licensee considers to be the principal control point of the transmitter. At all other control points listed on the station authorization, a photocopy of the station license and other instruments of station authorization shall be posted.

(b) The original operator license, or FCC Form 759, of each station operator shall be posted at the place where he is on duty as an operator.

§ 73.93 Operator requirements.

(a) One or more radio operators holding a valid radiotelephone first-class operator license, except as provided in paragraph (b) of this section, shall be in actual charge of the transmitting apparatus and shall be on duty either at the transmitter location or remote control point.

(b) In cases where a station is authorized for non-directional operation with power not in excess of 10 kilowatts, the routine operation of the transmitter may be performed by an operator holding a valid first-class or second-class radiotelephone or radiotelegraph operator license or a radiotelephone third-class operator permit which has been endorsed for broadcast station operation. The operator shall be on duty at the transmitter or authorized remote control point and in actual charge thereof. Until April 19, 1964, routine operation of transmitters of such stations may be performed by persons holding valid radiotelephone operator third-class permits which are not endorsed for broadcast station operation, or valid restricted radiotelephone operator permits. Except at times when the operation of the station is under the immediate supervision of an operator holding a valid radiotelephone first-class operator license, adjustments of the transmitting equipment shall be limited to the following:

(1) Those necessary to turn the transmitter on and off.

(2) Adjustments of external controls as may be required to compensate for voltage fluctuations in the power supply.

(3) Adjustments of external controls to maintain modulation of the transmitter within the prescribed limits.

(4) Adjustments of external controls necessary to effect routine changes in operating power which are required by the station's instrument of authorization.

(5) Adjustments of external controls necessary to effect operation in accordance with a National Defense Emergency Authorization during an Emergency Action Condition.

It shall be the responsibility of the may be required to perform these tasks as well as to perform other duties (such as reading meters and making log entries), is properly instructed so as to be capable of performing the duties required of him at times when not under the immediate supervision of a radiotelephone first-class operator. Where necessary, printed step-by-step instructions shall be posted for those transmitter adjustments which the lesser grade operator is authorized to make. Should the transmitting apparatus be observed to be operating in any manner inconsistent with this subpart or the current instrument of authorization for the station at any time when an operator holding a valid radiotelephone first-class operator license is not immediately available, and none of the above adjustments is effective in correcting the condition of improper operation, the emissions of the station shall be immediately terminated.

(c) If the routine operation of the transmitting apparatus at a standard broadcast station with power of 10 kw or less and non-directional antenna is performed by an operator other than a radiotelephone first-class operator pursuant to the provisions of paragraph (b) of this section, the licensee shall either employ one or more operators holding a valid radiotelephone first-class operator license as a full-time member of the station staff or, in the alternative, contract in writing for the services on a part-time basis of one or more such operators. The radiotelephone first-class operator or operators shall perform transmitter maintenance and shall be promptly available at all times to correct conditions of improper operation beyond the scope of authority of the lesser grade operator on duty. If such services are on a contract part-time basis, a signed copy of the agreement shall be kept in the files of the station and at the transmitter or control point and shall be made available for inspection upon request by any authorized representative of the Commission. A signed copy of the agreement shall also be forwarded to the Commission and to the Engineer in Charge of the radio district in which the station is located within 3 days after the agreement is signed.

NOTE: During the period prior to April 19, 1964, the alternative of contracting in writing for the services of radiotelephone first-class operators on a part-time basis may not be followed unless the routine transmitter operation under the provisions of paragraph (b) of this section is performed by operators holding at least valid radiotelephone third-class operator permits which have been endorsed for broadcast station operation. Information concerning examinations for such operator permits will be available to all applicants through the Commission's field offices after January 1, 1964.

(d) The licensed operator on duty and in charge of a standard broadcast transmitter may, at the discretion of the licensee, be employed for other duties or for the operation of another radio station or stations in accordance with the class of operator's license which he holds and the rules and regulations governing such other stations: *Provided, however,* That such duties shall in nowise interfere with the proper operation of the standard broadcast transmitter.

(e) At all standard broadcast stations, a complete inspection of all transmitting equipment in use shall be made by an operator holding a valid radiotelephone first-class operator license at least once each day, 5 days each week, with an interval of no less than 12 hours between successive inspections. This inspection shall include such tests, adjustments, and repairs as may be necessary to insure operation in conformance with the provisions of this subpart and the current instrument of authorization for the station.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 73.95 Equipment tests.

(a) During the process of construction of a standard broadcast station the permittee, after notifying the Commission and Engineer in Charge of the radio district in which the station is located, may without further authority of the Commission, conduct equipment tests during the experimental period for the purpose of such adjustments and measurements as may be necessary to assure compliance with the terms of the construction permit, the technical provisions of the application therefor, the rules and regulations, and the applicable engineering standards. In addition, the Commission may authorize equipment tests other than during the experimental period if such operation is shown to be desirable to the proper completion of construction and adjustment of the transmitting equipment and antenna system. An informal application for such authority, giving full details regarding the need for such tests, shall be filed with the Commission at least two (2) days (not including Sundays and Saturdays and legal holidays when the offices of the Commission are not open) prior to the date on which it is desired to begin such operation.

(b) The Commission may notify the permittee to conduct no tests or may cancel, suspend, or change the date for the beginning of equipment tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Equipment tests may be continued so long as the construction permit shall remain valid and shall be conducted only during the experimental period (12 midnight to local sunrise) unless otherwise specifically authorized.

(d) Inspection of a station will ordinarily be required during the equipment test period and before the commencement of program tests. After construction and after adjustments and measurements have been completed to show compliance with the terms of the construction permit, the technical provisions of the application therefor, the rules and regulations and the applicable engineering standards, the permittee should notify the Engineer in Charge of the radio district in which the station is located that it is ready for inspection.

(e) The authorization for tests embodied in this section shall not be con-

strued as constituting a license to operate but as a necessary part of construction.

§ 73.96 Program tests.

(a) Upon completion of construction of a standard broadcast station in accordance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations and applicable engineering standards and when an application for station license has been filed showing the station to be in satisfactory operating condition, the permittee may request authority to conduct program tests: *Provided,* That such request shall be filed with the Commission at least ten (10) days prior to the date on which it is desired to begin such operation and that the Engineer in Charge of the radio district in which the station is located is notified. All data necessary to show compliance with the terms and conditions of the construction permit must be filed with the license application. If the station is using a directional antenna, a proof of performance must also be filed as required by § 73.33(b).

(b) Program tests shall not commence until specific Commission authority is received. The Commission reserves the right to change the date of the beginning of such tests or to suspend or revoke the authority for program tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Unless sooner suspended or revoked program test authority continues valid during Commission consideration of the application for license and during this period further extension of the construction permit is not required. Program test authority shall be automatically terminated by final determination upon the application for station license.

(d) All operation on program test authority shall be in strict compliance with the rules governing standard broadcast stations and in strict accordance with representations made in the application for license pursuant to which the tests were authorized.

(e) The granting of program test authority shall not be construed as approval by the Commission of the application for station license.

§ 73.97 Station inspection.

The licensee of any radio station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 73.98 Operation during emergency.

(a) The licensee of a standard broadcast station or permittee of such a station operating under program test authority is authorized only to disseminate radio communications intended to be received by the public. However, during a period of emergency or imminent emergency in the area in which the station is located such a licensee or permittee may also (during the hours, at the frequency, and with the facilities specified in its instrument of authorization) utilize such station for transmitting communications directly related to the emergency which are intended to be received by specific individuals for the purpose of dispatching aid, assisting in rescue operations, or otherwise promoting the safety of life and property or alleviating hardship. In the course of such operation or any other operation permitted under the provisions of this section a station may communicate with stations of other classes and in other services. For the purposes of this section, an emergency shall mean a situation that would generally and seriously endanger life and property or cause substantial hardship as a result of events such as hurricane or other severe weather conditions, flood, earthquake or wide-area forest fire. The term shall not include situations resulting from frosts, or localized fires which are not a source of general danger.

(b) During periods of emergency or imminent emergency, the licensee of an unlimited-time standard broadcast station, or the permittee of such a station operating under program test authority may, if authorized different powers or antenna patterns for daytime and nighttime service, utilize daytime facilities during nighttime hours to disseminate communications directly related to the emergency which are intended to be received by the public or by specific individuals for the purposes specified in paragraph (a) of this section, if: (1) There are no other standard broadcast stations in the area authorized to operate and actually operating during the hours involved; or (2) such other stations are for any reason not presenting material concerning the emergency during the hours involved; or (3) such licensee or permittee is prepared to make a showing on request that all or part of the area which was affected by the emergency and which it planned to serve was not covered with an adequate signal by such other stations presenting emergency material during the hours involved: *Provided, however,* That if such nighttime emergency operation is not continuous but is interspersed with operations not related to the emergency, the latter operations shall be with normally authorized nighttime facilities: *Provided further,* That such nighttime emergency operation may contain music, but it shall not contain other program material of any kind not related to the emergency, spot announcements (including promotional announcements for a commercial program), or commercial continuity.

(c) During periods of emergency or imminent emergency, a licensee of a standard broadcast station (other than an unlimited-time station), or a permittee of such a station operating under program test authority, may operate at times other than those specified in its instrument of authorization or sharing-time agreement to disseminate communications directly related to the emergency which are intended to be received by the public or by specific individuals for the purposes specified in paragraph (a) of this section, if: (1) There is no standard broadcast station authorized to operate unlimited time in the area; or (2) if no standard broadcast station authorized to operate unlimited-time in the area is engaged in transmitting material concerning the emergency; or (3) such licensee or permittee is prepared to make a showing on request that all or part of the area which was affected by the emergency and which it planned to serve was not covered with an adequate signal by the unlimited-time stations at the time that the extra-hours operation occurred. (Stations sharing time must reach agreement with respect to the division of time for operation under the terms of this paragraph.) Announcements warning of emergencies such as blizzards, hurricanes or tornadoes many hours in advance of the time when they might possibly be expected, and announcements concerning school closings or changes in school bus schedules, road conditions or other matters necessitated by severe weather conditions shall not be made at times other than those specified in instruments of authorization or sharing-time agreements if adequate advance warning can be given during normal hours of operation. Operation under the provisions of this paragraph may contain music, but it shall not contain other program material of any kind not related to the emergency, spot announcements (including promotional announcements for a commercial program), or commercial continuity.

(d) A licensee or permittee operating under the provisions of this section shall (1) as soon as possible after the beginning of such emergency use, send notice to the Commission at Washington, D.C., and to the Engineer in Charge of the district in which the station is located stating the nature of the emergency and the use to which the station is being put; (2) discontinue such emergency operation as soon as the conditions requiring such operation are no longer present or the public has had an opportunity to be adequately informed; and (3) immediately upon cessation of such emergency operation notify the Commission in Washington, D.C., and the Engineer in Charge of the district in which the station is located, and shall in such notice justify the operation by stating the nature of the emergency, the exact times of operation, the type of emergency information transmitted, the total amount of time devoted to transmission of emergency information, the total amount of time (if any) devoted to music when not engaged in transmitting emergency information, the power, frequency, and antenna pattern used during the emergency operation, and other pertinent details. The notice shall also be accompanied by the program and operating logs of the station covering the periods involved, and, in the case of a station operating under the provisions of paragraph (b) or (c) of this section, a statement that there has been compliance with the prohibition against spot announcements, commercial continuity, or program material of any kind (except music) not related to the emergency.

(e) The decision to operate under the provisions of this section lies solely with the licensee or permittee of the station, requests by governmental or other officials not being controlling. However, such emergency operation shall terminate upon order of the Commission.

(f) Operation under the provisions of this section shall in no event occur on

frequencies other than those specified in the instruments of authorization or as otherwise expressly provided by the Commission or by law. When operating under the provisions of this section, power shall not exceed and antenna pattern shall not differ from that specified in the instrument of authorization or as otherwise provided by the Commission or by law, the only permissible deviations with regard to power and antenna pattern being those set forth in paragraph (b) of this section.

(g) No operation under this section shall be permitted if an Emergency Action Condition, under the provisions of Subchapter G of this part, is in effect. If a station is operating under this section and an Emergency Action Condition is declared, compliance with the Emergency Action Notification shall take precedence.

OTHER OPERATING REQUIREMENTS

§ 73.111 General requirements relating to logs.

(a) The licensee or permittee of each standard broadcast station shall maintain program, operating, and maintenance logs as set forth in §§ 73.112, 73.113, and 73.114. Each log shall be kept by the person or persons competent to do so, having actual knowledge of the facts required, who shall sign the appropriate log when starting duty and again when going off duty.

(b) The logs shall be kept in an orderly and legible manner, in suitable form, and in such detail that the data required for the particular class of station concerned is readily available. Key letters or abbreviations may be used if proper meaning or explanation is contained elsewhere in the log. Each sheet shall be numbered and dated. Time entries shall be either in local standard or daylight saving time and shall be indicated accordingly.

(c) No log or portion thereof shall be erased, obliterated, or willfully destroyed within the period of retention provided by the provisions of this part. Any necessary correction may be made only by the person originating the entry who shall strike out the erroneous portion, initial the correction made, and indicate the date of correction.

(d) Original data may be recorded in rough form and later transcribed into the log, but in such case all portions of the original memoranda shall be preserved as a part of the complete log.

§ 73.112 Program log.

(a) The following entries shall be made in the program log:

(1) An entry of the time each station identification announcement (call letters and location) is made.

(2) An entry briefly describing each program broadcast, such as "music," "drama," "speech," etc., together with the name or title thereof, and the sponsor's name, with the time of the beginning and ending of the complete program. If a mechanical record is used, the entry shall show the exact nature thereof, such as "record," "transcription," etc., and the time it is announced as a mechanical record. If a speech is made by a political candidate, the name and political affiliations of such speaker shall be entered.

(3) An entry showing that each sponsored program broadcast has been announced as sponsored, paid for, or furnished by the sponsor.

(4) An entry showing for each program of network origin, the name of the network originating the program.

(b) No provision of this section shall be construed as prohibiting the recording or other automatic maintenance of data required for program logs. However, where such automatic logging is used, the licensee must comply with the following requirements:

(1) The licensee, whether employing manual or automatic logging or a combination thereof, must be able accurately to furnish the Commission with all information required to be logged;

(2) Each recording, tape, or other means employed shall be accompanied by a certificate of the operator or other responsible person on duty at the time or other duly authorized agent of the licensee, to the effect that it accurately reflects what was actually broadcast. Any information required to be logged which cannot be incorporated in the automatic process shall be maintained in a separate record which shall be similarly authenticated;

(3) The licensee shall extract any required information from the recording for the days specified by the Commission or its duly authorized representative and submit it in written log form, together with the underlying recording, tape or other means employed.

§ 73.113 Operating log.

(a) The following entries shall be made in the operating log:

(1) An entry of the time the station begins to supply power to the antenna and the time it stops.

(2) An entry of each interruption of the carrier wave, where restoration is not automatic, its cause and duration followed by the signature of the person restoring operation (if licensed operator other than the licensed operator on duty).

(3) An entry, at the beginning of operation and at intervals not exceeding one-half hour, of the following (actual readings observed prior to making any adjustments to the equipment) and, when appropriate, an indication of corrections made to restore parameters to normal operating values:

(i) Operating constants of last radio stage (total plate voltage and plate current).

(ii) Antenna current or common point current (if directional) without modulation, or with modulation if the meter reading is not affected by modulation.

(iii) Frequency monitor reading.

(4) An entry each day of the following where applicable:

(i) Antenna base current(s) without modulation, or with modulation if the meter reading is not affected by modulation, for each mode of operation:

(*a*) Where remote antenna meters or a remote common point meter are normally employed but are defective.

(*b*) Where required by the station license for directional antenna operation.

(ii) Where there is remote control operation of a directional antenna station, readings for each pattern taken at the transmitter (within 2 hours of commencement of operation with each pattern) of:

(*a*) Common point current without modulation, or with modulation if the meter reading is not affected by modulation.

(*b*) Base current(s) without modulation, or with modulation if the meter reading is not affected by modulation.

(*c*) Phase monitor sample loop current(s) without modulation or with modulation if the meter reading is not affected by modulation.

(*d*) Phase indications.

(5) Any other entries required by the instrument of authorization or the provisions of this part.

(b) Automatic devices accurately calibrated and with appropriate time, date and circuit functions may be utilized to record the entries in the operating log: *Provided*, That:

(1) They do not affect the operation of circuits or accuracy of indicating instruments of the equipment being recorded;

(2) The recording devices have an accuracy equivalent to the accuracy of the indicating instruments;

(3) The calibration is checked against the original indicators at least once a week and the results noted in the maintenance log;

(4) Provision is made to actuate automatically an aural alarm circuit located near the operator on duty if any of the automatic log readings are not within the tolerances or other requirements specified in the rules or instrument of authorization;

(5) Unless the alarm circuit operates continuously, devices which record each parameter in sequence must read each parameter at least once during each 10-minute period and clearly indicate the parameter being recorded;

(6) The automatic logging equipment is located at the remote control point if the transmitter is remotely controlled, or at the transmitter location if the transmitter is manually controlled;

(7) The automatic logging equipment is located in the near vicinity of the operator on duty and is inspected by him periodically during the broadcast day; and

(8) The indicating equipment conforms with the requirements of § 73.39 except that the scales need not exceed 2 inches in length and arbitrary scales may not be used.

§ 73.114 Maintenance log.

The following entries shall be made in the maintenance log:

(a) An entry, each week, of the following where applicable:

(1) A notation indicating the readings of the tower base current ammeter(s) and the associated remote antenna ammeter(s) (actual readings observed prior to remote antenna ammeter recalibration) and indicating calibration of the remote ammeter(s) against the tower base ammeter(s).

(2) Time and result of test of auxiliary transmitter.

(3) A notation of all frequency checks and measurements made independently of the frequency monitor and of the correlation of these measurements with frequency monitor indications.

(4) A notation of the calibration check of automatic recording devices as required by § 73.113(b)(3).

(b) An entry of the date and time of removal from and restoration to service of any of the following equipment in the event it becomes defective:

(1) Modulation monitor.
(2) Frequency monitor.
(3) Final stage plate voltmeter.
(4) Final stage plate ammeter.
(5) Base current ammeter(s).
(6) Common point ammeter.

(c) Record of tower light inspections where required by § 17.38 of this chapter (Part 17—Construction, Marking, and Lighting of Antenna Structures).

(d) Entries made so as to describe fully any experimental operation during the experimental period.

(e) Upon completion of the inspection required by § 73.93(e), the inspecting operator shall enter a signed statement that the required inspection has been made, noting in detail the tests, adjustments, and repairs which were accomplished in order to insure operation in accordance with the provisions of this subpart and the current instrument of authorization of the station. The statement shall also specify the amount of time, exclusive of travel time to and from the transmitter, which was devoted to such inspection duties. If complete repair could not be effected, the statement shall set forth in detail the items of equipment concerned, the manner and degree in which they are defective, and the reasons for failure to make satisfactory repairs.

(f) Any other entries required by the current instrument of authorization of the station and the provisions of this subpart.

§ 73.115 Retention of logs.

Logs of standard broadcast stations shall be retained by the licensee or permittee for a period of 2 years: *Provided, however,* That logs involving communications incident to a disaster or which include communications incident to or involved in an investigation by the Commission and concerning which the licensee or permittee has been notified, shall be retained by the licensee or permittee until he is specifically authorized in writing by the Commission to destroy them: *Provided, further,* That logs incident to or involved in any claim or complaint of which the licensee or permittee has notice shall be retained by the licensee or permittee until such claim or complaint has been fully satisfied or until the same has been barred by statute limiting the time for the filing of suits upon such claims.

NOTE: Application forms for licenses and other authorizations require that certain operating and program data be supplied. It is suggested that these application forms be kept in mind in connection with maintenance of station program and operating records.

§ 73.116 Availability of logs and records.

The following shall be made available upon request by an authorized representative of the Commission:

(a) Program, operating and maintenance logs.

(b) Equipment performance measurements required by § 73.47.

(c) Copy of most recent antenna resistance or common-point impedance measurements submitted to the Commission.

(d) Copy of most recent field intensity measurements to establish performance of directional antennas required by § 73.151.

§ 73.117 Station identification.

(a) A licensee of a standard broadcast station shall make station identification announcement (call letters and location) at the beginning and ending of each time of operation and during operation (1) on the hour and (2) either on the half hour or at the quarter hour following the hour and at the quarter hour preceding the next hour: *Provided,*

(b) Such identification announcement need not be made on the hour when to make such announcement would interrupt a single consecutive speech, play, religious service, symphony concert, or operatic production of longer duration than 30 minutes. In such cases the identification announcement shall be made at the beginning of the program, at the first interruption of the entertainment continuity, and at the conclusion of the program.

(c) Such identification announcement need not be made on the half hour or quarter hours when to make such announcement would interrupt a single consecutive speech, play, religious service, symphony concert, or operatic production. In such cases an identification announcement shall be made at the first interruption of the entertainment continuity and at the conclusion of the program: *Provided,* That an announcement within 5 minutes of the times specified in paragraph (a)(2) of this section will satisfy the requirements of identification announcements.

(d) In the case of variety show programs, baseball game broadcasts, or similar programs of longer duration than 30 minutes, the identification announcement shall be made within 5 minutes of the hour and of the times specified in paragraph (a)(2) of this section.

(e) In the case of all other programs the identification announcement shall be made within 2 minutes of the hour and of the times specified in paragraph (a)(2) of this section.

(f) In making the identification announcement the call letters shall be given only on the channel of the station identified thereby, except as otherwise provided in § 73.287 of the Commission's rules governing FM broadcast stations.

§ 73.118 Mechanical reproductions.

(a) No mechanically reproduced program consisting of a speech, news event, news commentator, forum, panel discussion, or special event in which the element of time is of special significance, or any other program in which the element of time is of special significance and presentation of which would create, either intentionally or otherwise, the impression or belief on the part of the listening audience that the event or program being broadcast is in fact occurring simultaneously with the broadcast, shall be broadcast without an appropriate announcement being made either at the beginning or end of such reproduction or at the beginning or end of the program in which such reproduction is used that it is a mechanical reproduction or a mechanically reproduced program: *Provided, however,* That each such program of one minute or less need not be announced as such.

(b) The exact form of identifying announcement is not prescribed, but the language shall be clear and in terms commonly used and understood. Any other program mechanically reproduced or series of mechanical reproductions, including a mechanical reproduction used for background music, sound effects, station identification, program identification (theme music of short duration) or identification of sponsorship of the program proper, need not be announced as provided in paragraph (a) of this section, but the licensee shall not attempt affirmatively to create the impression that any program being broadcast by mechanical reproduction consists of live talent.

(c) The requirements of paragraph (a) of this section are waived with respect to network programs, transcribed and rebroadcast at a later hour because of the time zone differentials between the place where the program originates and where it is rebroadcast, this waiver being applicable whether the off-the-line recording is made by the network itself at one of its key stations or by an individual station, but only when the off-the-line recording is for broadcast at an hour not exceeding the time zone differential between the place where the program originates and where it is rebroadcast. Each station which broadcasts network programs at a later hour in accordance with this waiver shall make an appropriate announcement at least once each day between the hours of 10:00 a. m. and 10:00 p. m., stating that some or all of the network programs which are broadcast by that station are delayed broadcasts by means of transcription. This waiver provision also applies during the annual periods in which daylight saving time will be effective with respect to network programs transcribed and rebroadcast one hour later because of the time differential resulting from the adoption of daylight saving time in some areas.

§ 73.119 Sponsored programs, announcement of.

(a) When a standard broadcast station transmits any matter for which money, services, or other valuable consideration is either directly or indirectly paid or promised to, or charged or received by, such station, the station shall broadcast an announcement that such matter is sponsored, paid for, or furnished, either in whole or in part, and by whom or on whose behalf such consider-

ation was supplied: *Provided, however,* That "service or other valuable consideration" shall not include any service or property furnished without charge or at a nominal charge for use on, or in connection with, a broadcast unless it is so furnished in consideration for an identification in a broadcast of any person, product, service, trademark, or brand name beyond an identification which is reasonably related to the use of such service or property on the broadcast.

(b) The licensee of each standard broadcast station shall exercise reasonable diligence to obtain from its employees, and from other persons with whom it deals directly in connection with any program matter for broadcast, information to enable such licensee to make the announcement required by this section.

(c) In any case where a report (concerning the providing or accepting of valuable consideration by any person for inclusion of any matter in a program intended for broadcasting) has been made to a standard broadcast station, as required by section 508 of the Communications Act of 1934, as amended, of circumstances which would have required an announcement under this section had the consideration been received by such standard broadcast station, an appropriate announcement shall be made by such station.

(d) In the case of any political program or any program involving the discussion of public controversial issues for which any records, transcriptions, talent, scripts, or other material or services of any kind are furnished, either directly or indirectly, to a station as an inducement to the broadcasting of such program, an announcement shall be made both at the beginning and conclusion of such program on which such material or services are used that such records, transcriptions, talent, scripts, or other material or services have been furnished to such station in connection with the broadcasting of such program: *Provided, however,* That only one such announcement need be made in the case of any such program of 5 minutes' duration or less, which announcement may be made either at the beginning or conclusion of the program.

(e) The announcement required by this section shall fully and fairly disclose the true identity of the person or persons by whom or in whose behalf such payment is made or promised, or from whom or in whose behalf such services or other valuable consideration is received, or by whom the material or services referred to in paragraph (d) of this section are furnished. Where an agent or other person contracts or otherwise makes arrangements with a station on behalf of another, and such fact is known to the station, the announcement shall disclose the identity of the person or persons in whose behalf such agent is acting instead of the name of such agent.

(f) In the case of any program, other than a program advertising commercial products or services, which is sponsored, paid for, or furnished, either in whole or in part, or for which material or services referred to in paragraph (d) of this section are furnished, by a corporation, committee, association, or other unincorporated group, the announcement required by this section shall disclose the name of such corporation, committee, association, or other unincorporated group. In each such case the station shall require that a list of the chief executive officers or members of the executive committee or of the board of directors of the corporation, committee, association or other unincorporated group shall be made available for public inspection at the studios or general offices of one of the standard broadcast stations carrying the program in each community in which the program is broadcast.

(g) In the case of broadcast matter advertising commercial products or services, an announcement stating the sponsor's corporate or trade name, or the name of the sponsor's product, when it is clear that the mention of the name of the product constitutes a sponsorship identification, shall be deemed sufficient for the purposes of this section and only one such announcement need be made at any time during the course of the program.

(h) Commission interpretations in connection with the foregoing rules may be found in the Commission's Public Notice entitled "Applicability of Sponsorship Identification Rules" (FCC 63–409; 28 F.R. 4732, May 10, 1963) and such supplements thereto as are issued from time to time.

(Sec. 317, 48 Stat. 1089, as amended; 47 U.S.C. 317)

§ 73.120 Broadcasts by candidates for public office.

(a) *Definitions.* A "legally qualified candidate" means any person who has publicly announced that he is a candidate for nomination by a convention of a political party or for nomination or election in a primary, special, or general election, municipal, county, State or national, and who meets the qualifications prescribed by the applicable laws to hold the office for which he is a candidate, so that he may be voted for by the electorate directly or by means of delegates or electors, and who:

(1) Has qualified for a place on the ballot or

(2) Is eligible under the applicable law to be voted for by sticker, by writing in his name on the ballot, or other method, and (i) has been duly nominated by a political party which is commonly known and regarded as such, or (ii) makes a substantial showing that he is a bona fide candidate for nomination or office, as the case may be.

(b) *General requirements.* No station licensee is required to permit the use of its facilities by any legally qualified candidate for public office, but if any licensee shall permit any such candidate to use its facilities, it shall afford equal opportunities to all other such candidates for that office to use such facilities: *Provided,* That such licensee shall have no power of censorship over the material broadcast by any such candidate.

(c) *Rates and practices.* (1) The rates, if any, charged all such candidates for the same office shall be uniform and shall not be rebated by any means direct or indirect. A candidate shall, in each case, be charged no more than the rate the station would charge if the candidate were a commercial advertiser whose advertising was directed to promoting its business within the same area as that encompassed by the particular office for which such person is a candidate. All discount privileges otherwise offered by a station to commercial advertisers shall be available upon equal terms to all candidates for public office.

(2) In making time available to candidates for public office no licensee shall make any discrimination between candidates in charges, practices, regulations, facilities, or services for or in connection with the service rendered pursuant to this part, or make or give any preference to any candidate for public office or subject any such candidate to any prejudice or disadvantage; nor shall any licensee make any contract or other agreement which shall have the effect of permitting any legally qualified candidate for any public office to broadcast to the exclusion of other legally qualified candidates for the same public office.

(d) *Records; inspection.* Every licensee shall keep and permit public inspection of a complete record of all requests for broadcast time made by or on behalf of candidates for public office, together with an appropriate notation showing the disposition made by the licensee of such requests, and the charges made, if any, if request is granted. Such records shall be retained for a period of two years.

(e) *Time of request.* A request for equal opportunities must be submitted to the licensee within one week of the day on which the prior use occurred.

(f) *Burden of proof.* A candidate requesting such equal opportunities of the licensee, or complaining of non-compliance to the Commission shall have the burden of proving that he and his opponent are legally qualified candidates for the same public office.

(Sec. 315, 48 Stat. 1088, as amended, 47 U.S.C. 315)

§ 73.121 Rebroadcast.

(a) The term "rebroadcast" means reception by a radio station, and the simultaneous or subsequent retransmission of such a program by a broadcast station.

NOTE 1: As used in § 73.121, "program" includes any complete program or part thereof, or any signals if other than A3 emission.

NOTE 2: In case a program is transmitted from its point of origin to a broadcast station entirely by telephone facilities in which a section of such transmission is by radio, the broadcasting of this program is not considered a rebroadcast.

(b) The licensee of a standard broadcast station may, without further authority of the Commission, rebroadcast the program of a United States standard or FM broadcast station, provided the Commission is notified of the call letters of each station rebroadcast and the licensee certifies that express authority has been received from the licensee of the station originating the program. The foregoing requirements concerning notification of call letters and

certification of authority shall not apply to a station when rebroadcasting Defense Network (FM) programs. (Blanket authorizations for the rebroadcast of such programs have been filed with the Commission by all Defense Network (FM) stations.)

NOTE: The notice and certification of consent shall be given within 3 days of any single rebroadcast, but in case of the regular practice of rebroadcasting certain programs of a standard broadcast station several times during a license period, notice and certification of consent shall be given for the ensuing license period with the application for renewal of license, or at the beginning of such rebroadcast practice if begun during a license period.

(c) (1) The licensee of the standard broadcast station located within a state or the District of Columbia, may, without further authority of the Commission rebroadcast on a noncommercial basis a noncommercial program of a United States international broadcast station.

(2) The licensee of a standard broadcast station located in any territory or insular possession of the United States may, without further authority of the Commission, rebroadcast any program of a United States international broadcast station.

(3) In the case of any rebroadcast under the provisions of this paragraph, the Commission shall be notified of the call letters of each station whose programs are rebroadcast and the licensee shall certify that express authority has been received from the licensee of the station originating the program.

(d) No licensee of a standard broadcast station shall rebroadcast the program of any other class of United States radio station without written authority having first been obtained from the Commission upon application accompanied by written consent or certification of consent of the licensee of the station originating the program.

NOTE 1: The broadcasting of a program relayed by a remote pick-up broadcast station (§ 74.401 of this chapter) is not considered a rebroadcast.

NOTE 2: Informal application may be employed.

NOTE 3: By Order No. 82, dated and effective June 24, 1941, until further order of the Commission, § 73.121(d) is suspended only insofar as it requires prior written authority of the Commission for the rebroadcasting of programs originated for that express purpose by United States Government radio stations.

(e) In case of a program rebroadcast by several standard broadcast stations, such as a chain rebroadcast, the person legally responsible for distributing the program or the network facilities may obtain the necessary authorization for the entire rebroadcast both from the Commission and from the person or licensee of the station originating the program.

(f) Attention is directed to section 325 (b) of the Communications Act of 1934, which reads as follows (see also § 1.545 of this chapter):

No person shall be permitted to locate, use, or maintain a radio broadcast studio or other place or apparatus from which or whereby sound waves are converted into electrical energy, or mechanical or physical reproduction of sound waves produced, and caused to be transmitted or delivered to a radio station in a foreign country for the purpose of being broadcast from any radio station there, having a power output of sufficient intensity, and/or being so located geographically that its emissions may be received consistently in the United States, without first obtaining a permit from the Commission upon proper application therefor.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

§ 73.122 Lotteries.

(a) An application for construction permit, license, renewal of license, or any other authorization for the operation of a broadcast station, will not be granted where the applicant proposes to follow or continue to follow a policy or practice of broadcasting or permitting "the broadcasting of, any advertisement of or information concerning any lottery, gift enterprise, or similar scheme, offering prizes dependent in whole or in part upon lot or chance, or any list of the prizes drawn or awarded by means of any such lottery, gift enterprise, or scheme, whether said list contains any part or all of such prizes." (See 18 U.S.C. 1304.)

(b) The determination whether a particular program comes within the provisions of paragraph (a) of this section depends on the facts of each case. However, the Commission will in any event consider that a program comes within the provisions of paragraph (a) of this section if in connection with such program a prize consisting of money or thing of value is awarded to any person whose selection is dependent in whole or in part upon lot or chance, if as a condition of winning or competing for such prize, such winner or winners are required to furnish any money or thing of value or are required to have in their possession any product sold, manufactured, furnished or distributed by a sponsor of a program broadcast on the station in question.

(Sec. 1304, 62 Stat. 763, 18 U.S.C. 1304)

LICENSING POLICIES

§ 73.131 Exclusive affiliation of station.

No license shall be granted to a standard broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization under which the station is prevented or hindered from, or penalized for, broadcasting the programs of any other network organization. (The term "network organization" as used herein includes national and regional network organizations. See ch. VII, J, of Report on Chain Broadcasting.)

§ 73.132 Territorial exclusivity.

No license shall be granted to a standard broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which prevents or hinders another station serving substantially the same area from broadcasting the network's programs not taken by the former station, or which prevents or hinders another station serving a substantially different area from broadcasting any program of the network organization. This section shall not be construed to prohibit any contract, arrangement, or understanding between a station and a network organization pursuant to which the station is granted the first call in its primary service area upon the programs of the network organization.

§ 73.133 Term of affiliation.

No license shall be granted to a standard broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which provides, by original term, provisions for renewal, or otherwise for the affiliation of the station with the network organization for a period longer than 2 years: *Provided,* That a contract, arrangement, or understanding for a period up to 2 years, may be entered into within six months prior to the commencement of such period.

§ 73.134 Option time.

No license shall be granted to a standard broadcast station which options for network programs any time subject to call on less than 56 days' notice, or more time than a total of 3 hours within each of four segments of the broadcast day, as herein described. The broadcast day is divided into four segments, as follows: 8 a.m. to 1 p.m.; 1 p.m. to 6 p.m.; 6 p.m. to 11 p.m.; 11 p.m. to 8 a.m. (These segments are to be determined for each station in terms of local time at the location of the station but may remain constant throughout the year regardless of shifts from standard to daylight saving time or vice versa.) Such option may not be exclusive as against other network organizations and may not prevent or hinder the station from optioning or selling any or all of the time covered by the option, or other time, to other network organizations.

NOTE 1: As used in this section, an option is any contract, arrangement, or understanding, express or implied, between a station and a network organization which prevents or hinders the station from scheduling programs before the network agrees to utilize the time during which such programs are scheduled, or which requires the station to clear time already scheduled when the network organization seeks to utilize the time.

NOTE 2: All time options permitted under this section must be for specified clock hours, expressed in terms of any time system set forth in the contract agreed upon by the station and network organization. Shifts from daylight saving to standard time or vice versa may or may not shift the specified hours correspondingly as agreed by the station and network organization.

§ 73.135 Right to reject programs.

No license shall be granted to a standard broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which (a) with respect to programs offered pursuant to an affiliation contract, prevents or hinders the station from rejecting or refusing network programs which the station reasonably believes to be unsatisfactory or unsuitable; or which (b) with respect to network programs so offered or already contracted for, prevents the station from rejecting or refusing any program which, in its opinion, is contrary to the public interest, or from substituting a program of outstanding local or national importance.

§ 73.136 Network ownership of stations.

No license shall be granted to a network organization, or to any person directly or indirectly controlled by or under common control with a network organization, for more than one standard broadcast station where one of the stations covers substantially the service area of the other station, or for any standard broadcast station in any locality where the existing standard broadcast stations are so few or of such unequal desirability (in terms of coverage, power, frequency, or other related matters) that competition would be substantially restrained by such licensing. (The word "control" as used herein is not limited to full control but includes such a measure of control as would substantially affect the availability of the station to other networks.)

NOTE: Effective date of this section with respect to any station may be extended from time to time in order to permit the orderly disposition of properties; and it shall be suspended indefinitely with respect to regional network organizations.

§ 73.137 Dual network operation.

No license shall be issued to a standard broadcast station affiliated with a network organization which maintains more than one network: *Provided*, That this section shall not be applicable if such networks are not operated simultaneously, or if there is no substantial overlap in the territory served by the group of stations comprising each such network.

§ 73.138 Control by networks of station rates.

No license shall be granted to a standard broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization under which the station is prevented or hindered from, or penalized for, fixing or altering its rates for the sale of broadcast time for other than the network's programs.

§ 73.139 Special rules relating to contracts providing for reservation of time upon sale of a station.

No license, renewal of license, assignment of license, or transfer of control of a corporate licensee shall be granted or authorized to a standard broadcast station which has a contract, arrangement or understanding, express or implied, pursuant to which, as consideration or partial consideration for the assignment of license or transfer of control, the assignor of a station license or the transferor of stock, where transfer of a corporate licensee is involved or the nominee of such assignor or transferor retains any right of reversion of the license or any right to the reassignment of the license in the future, or reserves the right to use the facilities of the station for any period whatsoever.

DATA AND MEASUREMENTS

§ 73.150 Data required with applications for directional antenna systems.

(a) The following engineering data shall be submitted with the application for authority to install a directional antenna:

(1) Complete description of the proposed system showing:

(i) Number of elements,

(ii) Type of each element (i. e., guyed or self-supporting, uniform cross section or tapered (specifying base width), grounded or insulated, etc.),

(iii) Complete engineering details of top loading or sectionalizing, if any,

(iv) Height of vertical lead of each element in feet (height above base insulator or base, if grounded),

(v) Overall height in feet of each element above ground,

(vi) Details including sketches of ground system for each element (length and number of radials, dimensions of ground screen, if used, and depth buried) and outlines of property,

(vii) Ratio of fields from elements (identifying elements).

(2) Calculated horizontal (ground) plane field intensity patterns for each mode of operation plotted to the largest scale possible on standard letter-size polar coordinate paper (main engraving approximately 7" x 10") using only scale divisions and subdivisions having values of 1, 2, 2.5, or 5 times 10^{nth} and showing:

(i) Inverse field intensity at 1 mile and effective field intensity (RMS).

(ii) Direction true north shall be shown at zero azimuth.

(iii) Direction and distance to each existing station with which interference may be involved. (All directions shall be determined by accurate calculation or from Lambert Conformal Conic Projection Map such as United States Coast and Geodetic Survey Map, No. 3060a, or map of equal accuracy, and all distances shall be determined by accurate calculation or from United States Albers Equal Area Projection Map scale 1/2,500,000 or map of equal accuracy. These may be obtained from United States Geological Survey, Department of the Interior, Washington, D.C., 20240, and the United States Coast and Geodetic Survey, Department of Commerce, Washington, D.C., 20235.

(iv) Orientation of array with respect to true north and time phasing of fields from elements (specifying degrees leading [+] or lagging [−]) and space phasing of elements (identifying elements). (Space phasing should be given in feet as well as in degrees.)

(v) The location of all the minima in the pattern.

(3) Calculated field intensity vs. azimuth patterns for every 5 degrees of elevation through 60 degrees in those instances where radiation at angles above the horizontal plane is a pertinent factor in station allocation. These patterns may be plotted in polar or rectangular coordinates but shall be submitted one to a page. Minor lobe and null detail occurring between the 5 degree intervals need not be submitted.

(4) Data used in computing the patterns in subparagraphs (2) and (3) of this paragraph including:

(i) Formula used for calculating the horizontal patterns, sample calculations. (Derivation of formula if other than standard is used.)

(ii) All assumptions made and basis therefor, including electrical height, current distribution and efficiency of each element, and ground conductivity.

(iii) Complete tabulation of final calculated data used in plotting patterns, including data for determination of RMS value of pattern.

(5) Values of field intensity less than 10 percent of the effective field intensity of the patterns in subparagraphs (2) and (3) of this paragraph shown on an enlarged scale.

(6) In the event actual inverse distance field intensities expected to be determined in practice (that is, the values determined from actual measurements, particularly in sharp nulls) are different from the calculated values in subparagraphs (2) and (3) of this paragraph, the maximum expected operating values (MEOV) as well as the calculated values shall be shown on both the full patterns and the enlarged sections.

(7) Any additional information required by the application form.

§ 73.151 Field intensity measurements to establish performance of directional antennas.

(a) In addition to the information required by the license application form, the following showing must be submitted to indicate that the pattern obtained for each mode of directional operation is essentially the same as that predicted by the application and required by terms of the authorization and that any specific requirements set out are fully met:

(1) Horizontal field intensity pattern(s) showing the inverse field intensity at 1 mile and effective field intensity (RMS) as determined from field intensity measurements taken and analyzed in accordance with § 73.186 in at least the following directions:

(i) Those specified in the instrument of authorization.

(ii) In major lobes. Generally at least three radials are necessary to establish a major lobe; however, additional radials may be required.

(iii) Along sufficient number of other radials to establish the effective field. In the case of a relatively simple directional antenna pattern, approximately five radials in addition to those in subdivisions (i) and (ii) of this subparagraph are sufficient. However, when more complicated patterns are involved, that is, patterns having several or sharp lobes or nulls, measurements shall be taken along as many radials as may be necessary, to definitely establish the pattern(s).

(2) Pattern(s) plotted with direction true north as zero azimuth and showing the orientation of array with respect to true north, time and space phasing of elements, and both calculated and measured parameters. (Specify degrees leading [+] or lagging [−] and space phasing in feet as well as in degrees.)

(3) Pattern(s) plotted to the largest scale possible on standard letter-size polar coordinate paper (main engraving approximately 7" x 10") using divisions and subdivisions having values of 1, 2, 2.5, or 5 times 10^{nth} (no other values shall be used). All values of field intensity less than 10 percent of the RMS field intensity of the pattern shown on an enlarged scale.

(4) Complete tabulation of all data used in plotting the above pattern(s).

(5) The 25 and 5 mv/m field intensity contours and the nighttime interference-free contour, when the pattern is for nighttime operation, as well as any other contours specified by the instrument of authorization, plotted on a map which has the largest practical scale. These contours need not be shown for distances greater than 20 miles from the antenna except that the field intensity contours on the far side of the business and residential areas of the city in which the main studio is located shall be shown. When the station is limited by interference within the 5 mv/m contour the latter contour need not be shown. In the event the 5 mv/m contour includes and extends beyond the city and beyond 20 miles, the highest signal intensity contour that entirely includes the city may be plotted in lieu of the 5 mv/m contour; in the event that the 5 mv/m contour does not include the city, the contour of highest signal intensity encompassing the city shall be plotted in addition to the 5 mv/m contour.

(6) The actual field intensity measured at each monitoring point established in the various directions for which a limiting field was specified in the instrument of authorization together with accurate and detailed description of each monitoring point together with ordinary snapshots, clear and sharp, taken with the field intensity meter in its measuring position and with the camera so located that its field of view takes in as many pertinent landmarks as possible. In addition, the directions for proceeding to each monitoring point together with a rough sketch or map upon which has been indicated the most accessible approaches to the monitoring points should be submitted.

§ 73.152 Field intensity measurements in support of applications or evidence at hearings.

In the determination of interference, groundwave field intensity measurements will take precedence over theoretical values, provided such measurements are properly taken and presented. When measurements of groundwave signal intensity are presented, they shall be sufficiently complete in accordance with § 73.186 to determine the field intensity at 1 mile in the pertinent directions for that station.

NOTE: The antenna resistance measurements required by § 73.186 need not be taken or submitted.

STANDARD BROADCAST TECHNICAL STANDARDS

§ 73.181 Introduction.

(a) There are presented in this subpart the Technical Standards giving interpretations and further considerations concerning the rules and regulations of the Federal Communications Commission governing standard broadcast stations. While rules and regulations form the basis of good engineering practice, these standards may go beyond the rules and regulations and set up engineering principles for consideration of various allocation problems. These standards have been approved by the Commission and thus are considered as reflecting the opinion of the Commission in all matters involved.

NOTE: See also § 73.28.

(b) The Technical Standards set forth in this subpart are those deemed necessary for the construction and operation of standard broadcast stations to meet the requirements of technical regulations and for operation in the public interest along technical lines not specifically enunciated in the regulations. These standards are based on the best engineering data available from evidence supplied in formal and informal hearings and extensive surveys conducted in the field by the Commission's personnel. Numerous informal conferences have been held with radio engineers, manufacturers of radio equipment and others for the guidance of the Commission in the formulation of these standards.

(c) These standards are complete in themselves and supersede any previous announcements or policies which may have been enunciated by the Commission on engineering matters concerning standard broadcast stations.

(d) While these standards provide for flexibility and set forth the conditions under which they are applicable, it is not expected that material deviation therefrom as to fundamental principles will be recognized unless full information is submitted as to the reasonableness of such departure and the need therefor.

(e) These standards will necessarily change as progress is made in the art, and accordingly it will be necessary to make revisions from time to time. The Commission will accumulate and analyze engineering data available as to the progress of the art so that its standards may be kept current with the developments.

§ 73.182 Engineering standards of allocation.

(a) Sections 73.21 to 73.34, inclusive, govern allocation of facilities in the standard broadcast band of 535 to 1605 kc/s. Section 73.21 establishes three classes of channels in this band, namely, clear channels for the use of high-powered stations, regional channels for the use of medium-powered stations, and local channels for the use of low-powered stations. The classes and power of standard broadcast stations which will be assigned to the various channels are set forth in § 73.21. The classification of the standard broadcast stations are as follows:

(1) Class I stations are dominant stations operating on clear channels with powers of not less than 10 or more than 50 kw. These stations are designed to render primary and secondary service over an extended area and at relatively long distances, hence have their primary service areas free from objectionable interference from other stations on the same and adjacent channels and secondary service areas free from objectionable interference from stations on the same channels. (The secondary service area of a Class I station is not protected from adjacent channel interference. However, if it is desired to make a determination of the area in which adjacent channel groundwave interference (10 kc/s removed) to skywave service exists, it may be considered as the area where the ratio of the desired 50% skywave of the Class I station to the undesired groundwave of a station 10 kc/s removed is 1 to 4.) From an engineering point of view, Class I stations may be divided into two groups and, hereafter, for the purpose of convenience, the two groups of Class I stations will be termed Class I–A or I–B in accordance with the assignment to channels allocated by § 73.25 (a) or (b).

(i) The Class I stations in Group I–A are those assigned to the channels allocated by § 73.25(a), on which, except to the extent provided by that section and by § 73.22, duplicate nighttime operation is not permitted. The power of these stations shall not be less than 50 kilowatts. The Class I stations in this group are afforded protection as follows:

Daytime: To the 0.1 mv/m groundwave contour from stations on the same channel, and to the 0.5 mv/m groundwave contour from stations on adjacent channels.

Nighttime: To the 0.5 mv/m, 50 percent skywave contour from stations on the same channel, and to the 0.5 mv/m groundwave contour from stations on adjacent channels.

(ii) The Class I stations in group I-B are those assigned to the channels allocated by § 73.25(b), on which duplicate operation is permitted, that is, other Class I or Class II stations operating unlimited time may be assigned to such channels. During nighttime hours of operation a Class I station of this group is protected to the 500 uv/m 50 percent sky wave contour and during daytime hours of operation to the 100 uv/m ground wave contour from stations on the same channel. Protection is given to the 500 uv/m groundwave contour from stations on adjacent channels for both day and nighttime operation. The operating powers of Class I stations on these frequencies shall be not less than 10 kw nor more than 50 kw.

(2) Class II stations are secondary stations which operate on clear channels with powers not less than 0.25 kw nor more than 50 kw, except that Class II–A stations shall not operate nighttime with less than 10 kw. Class II stations are required to use a directional antenna or other means to avoid causing interference within the normally protected service areas of Class I stations or other Class II stations (for special rules and standards concerning Class II–A stations, see § 73.22). These stations normally render primary service only, the area of which depends on the geographical location, power, and frequency. This may be relatively large but is limited by and subject to such interference as may be received from Class I stations. However, it is recommended that Class II stations be so located that the interference received from other stations will not limit the service area to greater than the 2.5 mv/m groundwave contour nighttime and 0.5 mv/m groundwave contour daytime, which are the values for the mutual protection of this class of stations with other stations of the same class (except that Class II–A stations are normally protected to their 0.5 mv/m groundwave contour daytime, and nighttime to the

limit imposed by the co-channel Class I-A station).

(3) Class III stations operate on regional channels and normally render primary service to the larger cities and the rural area contiguous thereto, and are subdivided into two classes:

(i) Class III–A stations which operate with powers not less than 1 kw or more than 5 kw are normally protected to the 2500 uv/m groundwave contour nighttime and the 500 uv/m groundwave contour daytime.

(ii) Class III–B stations which operate with powers not less than 0.5 kw, or more than 1 kw nighttime and 5 kw daytime are normally protected to the 4000 uv/m groundwave contour nighttime and 500 uv/m groundwave contour daytime.

NOTE: In NARBA and the U.S./Mexican Agreement, no distinction is made between Class III–A and Class III–B stations.

(4) Class IV stations operate on local channels, normally rendering primary service only to a city or town and the suburban or rural areas contiguous thereto, with powers not less than 100 watts, nor more than 250 watts nighttime and 1 kilowatt daytime (for restrictions on daytime power of local stations located near the Mexican border or in an area within the state of Florida, see § 73.21(c)). Such stations are normally protected to the 0.5 mv/m contour daytime. On local channels the separation required for the daytime protection shall also determine the nighttime separation. Where directional antennas are employed daytime by Class IV stations operating with more than 250 watts power, the separations required shall in no case be less than those necessary to afford protection, assuming nondirectional operation with 100 watts or 250 watts, whichever is the nighttime power of the station. In no case will 250 watts nighttime operation be authorized to a station unable to operate nondirectionally at 250 watts in the daytime. The actual nighttime limitation will be calculated.

NOTE: The following approximate method may be used. It is based on the assumption of 0.25 wavelength antenna height and 88 mv/m at one mile effective field for 250 watts power, using the 10% skywave field intensity curve of Figure 2 of § 73.190. Zones defined by circles of various radii specified below are drawn about the desired station and the interfering 10% skywave signal from each station in a given zone is considered to be the value tabulated below. The effective interfering 10% skywave signal is taken to be the RSS value of all signals originating within these zones. (Stations beyond 500 miles are not considered.)

Zone	Inner radius	Outer radius	10 percent skywave signal (mv/m)
A		60	0.10
B	60	80	.12
C	80	100	.14
D	100	250	.16
E	250	350	.14
F	350	450	.12
G	450	500	.10

Where the power of the interfering station is not 250 watts, the 10% skywave signal should be adjusted by the square root of the ratio of the power to 250 watts.

(b) The class of any station is determined by the channel assignment, the power, and the field intensity contour to which it renders service free of interference from other stations as determined by these standards. No station will be permitted to change to a class normally protected to a contour of less intensity than the contour to which the station actually renders interference-free service. Any station of a class normally protected to a contour of less intensity than that to which the station actually renders interference-free service, will be automatically reclassified according to the class normally protected, the minimum consistent with its power and channel assignment. Likewise, any station to which the interference is reduced so that service is rendered to a contour normally protected for a higher class will be automatically changed to that class if consistent with its power and channel assignment.

(c) [Reserved]

(d) When a station is already limited by interference from other stations to a contour of higher value than that normally protected for its class, this contour shall be the established standard for such station with respect to interference from all other stations.

(e) The several classes of broadcast stations have in general three service areas; namely, primary, secondary, and intermittent service areas. (See § 73.11 for the definitions of primary, secondary, and intermittent service areas.) Class I stations render service to all three service areas. Class II stations render service to a primary area but the secondary and intermittent service areas may be materially limited or destroyed due to interference from other stations depending on the station assignments involved. Class III and IV stations usually have only primary service areas as interference from other stations generally prevents any secondary service and may limit the intermittent service area. However, complete intermittent service may be obtained in many cases depending on the station assignments involved.

(f) The signals necessary to render primary service to different types of service areas are as follows:

Area:	*Field intensity groundwave* [1]
City business or factory areas	10 to 50 mv/m.
City residential areas	2 to 10 mv/m.
Rural—all areas during winter or northern areas during summer	0.1 to 0.5 mv/m.
Rural—southern areas during summer	0.25 to 1.0 mv/m.

[1] See § 73.184 for curves showing distance to various groundwave field intensity contours for different frequency and ground conductivities and § 73.183.

All these values are based on an absence of objectionable fading, either in changing intensity or selective fading, the usual noise level in the areas, and an absence of limiting interference from other broadcast stations. The values apply both day and night but generally fading or interference from other stations limits the primary service at night in all rural areas to higher values of field intensity than the values given. The Commission will authorize a directive antenna for a Class IV station for daytime operation only with power in excess of 250 watts. In computing the degrees of protection which such antenna will afford, the radiation produced by this antenna shall be assumed to be no less, in any direction, than that which would result from nondirectional operation, utilizing a single element of the directional array, with 100 watts or 250 watts, whichever is the nighttime power of the station.

NOTE: Standards have not been established for interference from atmospherics or man-made electric noise as no uniform method of measuring noise or static has been established. In any individual case objectionable interference from any source, except other broadcast signals, may be determined by comparing the actual noise interference reproduced during reception of a desired broadcast signal to the degree of interference that would be caused by another broadcast signal within 20 cycles of the desired signal and having a carrier ratio of 20 to 1 with both signals modulated 100 percent on peaks of usual programs. Standards of noise measurements and interference ratio for noise are now being studied.

(g) In determining the population of the primary service area, it may be considered that the following signals are satisfactory to overcome man-made noise in towns of the population given.

Population:	*Field intensity groundwave*
Up to 2,500	0.5 mv/m
2,500 to 10,000	2.0 mv/m
10,000 and up	Values given in paragraph (f) of this section

These values are subject to wide variations in individual areas and especial attention must be given to interference from other stations. The values are not considered satisfactory in any case for service to the city in which the main studio of the station is located. The values in paragraph (f) of this section shall apply except as individual consideration may determine.

(h) All classes of broadcast stations have primary service areas subject to limitation by fading and noise, and interference from other stations to the contours set out for each class of station.

(i) Secondary service is delivered in the areas where the sky wave for 50 percent or more of the time has a field intensity of 500 uv/m or greater. (The secondary service area of a Class 1-A station should be considered as having this limit only for determination of service in comparison with other stations.) It is not considered that satisfactory secondary service can be rendered to cities unless the sky wave approaches in value the ground wave required for primary service. The secondary service is necessarily subject to some interference and extensive fading whereas the primary service area of a station is subject to no objectionable interference or fading. Class I stations only are assigned on the basis of rendering secondary service.

NOTE: Standards have not been established for objectionable fading as such standards would necessarily depend on the receiver characteristics which have been changed considerably in this regard during the last

several years. Selective fading causing audio distortion and the signal fading below the noise level are the objectionable characteristics of fading on modern design receivers. The AVC circuits in the better designed modern receivers in general maintain the audio output sufficiently constant to be satisfactory during most fading.

(j) The intermittent service is rendered by the groundwave and begins at the outer boundary of the primary service area and extends to the value of signal where it may be considered as having no further service value. This may be down to only a few microvolts in certain areas and up to several millivolts in other areas of high noise level, interference from other stations, or objectionable fading at night. The intermittent service area may vary widely from day to night and generally varies from time to time as the name implies. Only Class I stations are assigned for protection from interference from other stations into the intermittent service area.

(k) Section 73.23 provides that the several classes of broadcast stations may be licensed to operate unlimited time, limited time, daytime, sharing time, and specified hours, with full explanation given in the section (see § 73.38 for restriction on limited time authorizations on or after November 30, 1959).

(l) Section 73.24 sets out the general requirements for obtaining an increase in facilities of a licensed station and for a new station. Section 73.24(b) concerns the matter of interference that may be caused by a new assignment or increase in facilities of an existing assignment.

(m) [Reserved]

(n) [Reserved]

(o) Objectionable interference from another broadcast station is the degree of interference produced when, at a specified field intensity contour with respect to the desired station, the field intensity of an undesired station (or the root-sum-square value of field intensities of two or more stations on the same frequency) exceeds for ten (10) percent or more of the time the values set forth in these standards. (The secondary service area of a Class I–A station should be considered as having this limit only for determination of service in comparison with other stations.)

(1) With respect to the root-sum-square values of interfering field intensities referred to in this section, except in the case of Class IV stations on local channels, calculation is accomplished by considering the signals in order of decreasing magnitude, adding the squares of the values and extracting the square root of the sum, excluding those signals which are less than 50% of the RSS value of the higher signals already included.

(2) The RSS value will not be considered to be increased when a new interfering signal is added which is less than 50% of the RSS value of the interference from existing stations, and which at the same time is not greater than the smallest signal included in the RSS value of interference from existing stations.

(3) It is recognized that application of the above "50% exclusion" method of calculating the RSS interference may result in some cases in anomalies wherein the addition of a new interfering signal or the increase in value of an existing interfering signal will cause the exclusion of a previously included signal and may cause a decrease in the calculated RSS value of interference. In order to provide the Commission with more realistic information regarding gains and losses in service (as a basis for determination of the relative merits of a proposed operation) the following alternate method for calculating the proposed RSS values of interference will be employed wherever applicable.

(4) In the cases where it is proposed to add a new interfering signal which is not less than 50% of the RSS value of interference from existing stations or which is greater than the smallest signal already included to obtain this RSS value, the RSS limitation after addition of the new signal shall be calculated without excluding any signal previously included. Similarly, in cases where it is proposed to increase the value of one of the existing interfering signals which has been included in the RSS value, the RSS limitation after the increase shall be calculated without excluding the interference from any source previously included.

(5) If the new or increased signal proposed in such cases is ultimately authorized, the RSS values of interference to other stations affected will thereafter be calculated by the "50% exclusion" method without regard to this alternate method of calculation.

(6) Examples of RSS interference calculations:

(i) Existing interferences:

Station No. 1—1.0 mv/m.
Station No. 2—0.60 mv/m.
Station No. 3—0.59 mv/m.
Station No. 4—0.58 mv/m.

The RSS value from Nos. 1, 2 and 3 is 1.31 mv/m: therefore interference from No. 4 is excluded for it is less than 50% of 1.31 mv/m.

(ii) Station A receives interference from:

Station No. 1—1.0 mv/m.
Station No. 2—0.60 mv/m.
Station No. 3—0.59 mv/m.

It is proposed to add a new limitation—0.68 mv/m. This is more than 50% of 1.31 mv/m, the RSS value of Nos. 1, 2 and 3. The RSS value of Station No. 1 and of the proposed station would be 1.21 mv/m which is more than twice as large as the limitation from Station No. 2 or No. 3. However, under the above provision the new signal and the three existing interferences are nevertheless calculated for purposes of comparative studies, resulting in an RSS value of 1.47 mv/m. However, if the proposed station is ultimately authorized, only No. 1 and the new signal are included in all subsequent calculations for the reason that Nos. 2 and 3 are less than 50% of 1.21 mv/m, the RSS value of the new signal and No. 1.

(iii) Station A receives interference from:

Station No. 1—1.0 mv/m.
Station No. 2—0.60 mv/m.
Station No. 3—0.59 mv/m.

No. 1 proposes to increase the limitation it imposes on Station A to 1.21 mv/m. Although the limitations from stations Nos. 2 and 3 are less than 50% of the 1.21 mv/m limitation, under the above provision they are nevertheless included for comparative studies, and the RSS limitation is calculated to be 1.47 mv/m. However, if the increase proposed by Station No. 1 is authorized, the RSS value then calculated is 1.21 mv/m because Stations Nos. 2 and 3 are excluded in view of the fact that the limitations they impose are less than 50% of 1.21 mv/m.

(p) Objectionable interference from a station on the same channel shall be considered to exist to a station when, at the field intensity contour specified in paragraph (v) of this section with respect to the class to which the station belongs, the field intensity of an interfering station (or the root-sum-square value of the field intensities of two or more interfering stations) operating on the same channel, exceeds for ten (10) percent or more of the time the value of the permissible interfering signal set forth opposite such class in paragraph (v) of this section.

(q) Objectionable interference from a station on an adjacent channel shall be considered to exist to a station when, at the normally protected contour of a desired station, the field intensity of the ground wave of an undesired station operating on an adjacent channel (or the root-sum-square value of the field intensities of two or more such undesired stations operating on the same adjacent channel) exceeds a value specified in paragraph (w) of this section.

(r) For the purpose of estimating the coverage and the interfering effects of stations in the absence of field intensity measurements, use shall be made of Figure 8 of § 73.190 which describes the estimated effective field for one kilowatt power input of simple vertical omnidirectional antennas of various heights with ground systems of at least 120 one-quarter wavelength radials. Certain approximations, based on the curve or other appropriate theory, may be made when other than such antennas and ground systems are employed, but in any event the effective field to be employed shall not be less than given in the following:

Class of station:	*Effective field*
I	225 mv/m
II and III	175 mv/m
IV	150 mv/m

In case a directional antenna is employed, the interfering signal of a broadcasting station will vary in different directions, being greater than the above values in certain directions and less in others, depending upon the design and adjustment of the directional antenna system. To determine the interference in any direction the measured or calculated radiated field (unabsorbed field intensity at 1 mile from the array) must be used in conjunction with the appropriate propagation curves. (See § 73.185 for further discussion and solution of a typical directional antenna case.)

(s) The existence or absence of objectionable groundwave interference from stations on the same or adjacent

channels shall be determined by actual measurements made according to the method hereinafter described, or, in the absence of such measurements, by reference to the propagation curves of § 73.184. The existence or absence of objectionable interference due to skywave propagation shall be determined by reference to the appropriate propagation curves in Figure 1 or Figure 1a or Figure 2 of § 73.190.

(t) In computing the fifty (50) percent and the ten (10) percent skywave field intensity values of a station operating on a clear channel specified in § 73.25 (a), use shall be made of the appropriate curve set forth in Figure 1a of § 73.190, "Skywave Signals for 10 percent and 50 percent of the Time." In computing the fifty (50) percent and ten (10) percent skywave field intensity values of a station operating on a clear channel specified in § 73.25(b), use shall be made of the appropriate curve set forth in Figure 1 of § 73.190, entitled "Average Skywave Field Intensity (corresponding to the second hour after sunset at the recording station)." In computing the ten (10) percent skywave field intensity values of a regional channel station, use shall be made of the appropriate curve in Figure 2 of § 73.190, entitled "10 percent Skywave Signal Range." The curves in Figure 1 of § 73.190 are drawn for a radiated field of 100 mv/m at one mile in the horizontal plane from a 0.311 wavelength antenna. The curves in Figure 1a and Figure 2 of § 73.190 are drawn for a radiated field of 100 mv/m at one mile at the vertical angle pertinent to transmission by one reflection. In computations based on Figure 1, the pertinent vertical angle shall be determined by use of Figure 6 of § 73.190. In computations based on Figures 1a or 2 of § 73.190, the pertinent vertical angle shall be determined by use of Figure 6a of § 73.190.

(u) The distance to any specified groundwave field intensity contour for any frequency may be determined from the appropriate curves in § 73.184 entitled "Ground Wave Field Intensity vs. Distance."

(v) Protected service contours and permissible interference signals for broadcast stations are as follows (for Class I and Class II–A stations, see paragraph (a) of this section):

Class of station	Class of channel used	Permissible power	Signal intensity contour of area protected from objectionable interference.[1]		Permissible interfering signal on same channel [2]	
			Day [3]	Night	Day [3]	Night [4]
I-A	Clear	50 kw	SC 100 uv/m AC 500 uv/m	SC 500 uv/m (50% skywave).[7] AC 500 uv/m [3]	5 uv/m	25 uv/m.[7]
I-B	do	10 kw to 50 kw	SC 100 uv/m AC 500 uv/m	SC 500 uv/m (50% skywave). AC 500 uv/m [3]	5 uv/m	25 uv/m.
II-A	do	0.25 kw to 50 kw (daytime). 10 kw to 50 kw (nighttime).	500 uv/m	500 uv/m [3]	25 uv/m	Do.
II-B and II-D.	do	0.25 kw to 50 kw	500 uv/m	2500 uv/m [3 5]	do	125 uv/m.
III-A	Regional	1 kw to 5 kw	do	2500 uv/m [3]	do	Do.
III-B	do	0.5 to 1 kw (night), and 5 kw (day).	do	4000 uv/m [3]	do	200 uv/m.
IV	Local	0.1 to 0.25 kw (night), and 0.1 to 1 kw (day).	do	Not prescribed [6]	do	Not prescribed.[6]

[1] When a station is already limited by interference from other stations to a contour of higher value than that normally protected for its class, this contour shall be the established standard for such station with respect to interference from all other stations.
[2] For adjacent channel, see paragraph (w) of this section.
[3] Groundwave.
[4] Skywave field intensity for 10 percent or more of the time.
[5] These values are with respect to interference from all stations except Class I–B, which stations may cause interference to a field intensity contour of higher value. However, it is recommended that Class II stations be so located that the interference received from Class I–B stations will not exceed these values. If the Class II stations are limited by Class I–B stations to higher values, then such values shall be the established standard with respect to protection from all other stations.
[6] See paragraph (a)(4) of this section.
[7] Class I–A stations on channels reserved for the exclusive use of one station during nighttime hours are protected from co-channel interference on that basis. On the frequency 770 kc/s, two Class I stations may be assigned.

SC=Same channel. AC=Adjacent channel.

(w) The following table is to be used for determining the minimum ratio of the field intensity of a desired to an undesired signal for interference free service. In the case of a desired groundwave signal interfered with by two or more skywave signals on the same frequency, the RSS value of the latter is used. From the table, it is apparent that in many cases stations operating on channels 10 and 20 kilocycles apart may be operated with antenna systems side by side or otherwise in proximity without any indications of interference if the interference is defined only in terms of permissible ratios listed in this paragraph. As a practical matter, serious interference problems may arise when two or more stations with the same general service area are operated on channels 10, 20, and 30 kilocycles apart.

Frequency separation of desired to undesired signals—	Desired groundwave to—		Desired 50 percent skywave to undesired 10 percent skywave
	Undesired groundwave	Undesired 10 percent skywave	
0 kc/s	20:1	20:1	20:1
10 kc/s	1:1	1:5	(1)
20 kc/s	1:30		

[1] The secondary service area of a Class I station is not protected from adjacent channel interference. However, if it is desired to make a determination of the area in which adjacent channel groundwave interference (10 kc/s removed) to skywave service exists, it may be considered as the area where the ratio of thedesired 50 percent skywave of the Class I station to the undesired groundwave of a station 10 kc/s removed is 1 to 4.

(x) Two stations, one with a frequency twice that of the other, should not be assigned in the same groundwave service area unless special precautions are taken to avoid interference from the second harmonic of the lower frequency. In selecting a frequency, consideration should be given to the fact that occasionally the frequency assignment of two stations in the same area may bear such a relation to the intermediate frequency of some broadcast receivers as to cause so-called "image" interference. However, since this can usually be rectified by readjustment of the intermediate frequency of such receivers, the Commission in general will not take this kind of interference into consideration in allocation problems.

(y) Two stations operating with synchronized carriers and carrying the identical program will have their groundwave service subject to some distortion in areas where the signals from the two stations are of comparable intensity. For the purpose of estimating coverage of such stations areas in which the signal ratio is between 1 to 2 and 2 to 1 will not be considered as having satisfactory service.

NOTE: Two stations are considered to be operated synchronously when the carriers are maintained within one-fifth of a cycle per second of each other and they transmit identical programs.

§ 73.183 Groundwave signals.

(a) Interference that may be caused by a proposed assignment or an existing assignment during daytime should be determined, when possible, by measurements on the frequency involved or on another frequency over the same terrain and by means of the curves in § 73.184 entitled "Ground Wave Field Intensity versus Distance."

(b) In determining interference based upon field intensity measurements, it is necessary to do the following: First, establish the outer boundary of the protected service area of the desired station in the direction of the station that may cause interference to it. Second, at this boundary, measure the interfering signal from the undesired station. The ratio of the desired to the undesired signal given in § 73.182(w) should be applied to the measured signals and if the required ratio is observed, no objectionable interference is foreseen. When measurements of both the desired and undesired stations are made in one area to determine the point where objectionable interference from groundwave signals occur or to establish other pertinent contours, several measurements of each station shall be made within a few miles of this point or contour. The effective field of the antennas in the pertinent directions of the stations must be established and all measurements must be made in accordance with § 73.186.

NOTE: International agreement in the matter of standards for good engineering practice concerning determination of ground conductivity by field intensity measurements has not been arrived at as contemplated by NARBA, and the United States has no established procedures for reciprocal considera-

tion of such measurements with any country except Canada. Therefore, groundwave field intensity measurements will not be accepted or considered for the purpose of establishing that interference to a station in a foreign country other than Canada, or that signal intensity at the border thereof, would be less than indicated by the application of the ground conductivity maps and engineering standards contained in this part and applicable international agreements. Satisfactory groundwave measurements offered for the purpose of demonstrating values of conductivity other than those shown by Figure M3 in problems involving protection of Canadian stations or the Canadian border will be considered only if, after review thereof, the appropriate agency of the Canadian government notifies the Commission that they are acceptable for such purpose.

(c) In all cases where measurements taken in accordance with the requirements are not available, the groundwave intensity must be determined by means of the pertinent map of ground conductivity and the groundwave curves of field intensity versus distance. The conductivity of a given terrain may be determined by measurements of any broadcast signal traversing the terrain involved. Figure M3 shows the conductivity throughout the United States by general areas of reasonably uniform conductivity. When it is clear that only one conductivity value is involved, Figure R3 of § 73.190, which is a replica of Figure M3 and contained in these standards, may be used; in all other situations Figure M3 must be employed. It is recognized that in areas of limited size or over a particular path, the conductivity may vary widely from the values given; therefore, these maps are to be used only when accurate and acceptable measurements have not been made. (For determinations of interference and service requiring a knowledge of ground conductivities in Mexico, Appendix H to the North American Regional Broadcasting Agreement, Washington, D.C., 1950, may be used. Similarly, for values of ground conductivities in Canada, a map issued by the Telecommunications and Electronics Branch, Department of Transport, Ottawa, Ontario, entitled "Provisional Ground Conductivity Map" and dated June 1, 1960, may be used. Where different conductivities appear in the maps of two countries on opposite sides of the border, such differences are to be considered as real, even if they are not explained by geophysical cleavages. A uniform ground conductivity of 10 millimhos per meter may be assumed for Cuba.)

NOTE 1: Figure R3 in § 73.109 is a replica of Figure M3. Figure M3, which is incorporated in these Standards by reference, was derived by indicating ground conductivity values in the United States on the United States Albers equal area projection map based on standard parallels 29½° and 45½°; North American datum; scale 1/2,500,000). Figure M3, consisting of two sections, an eastern and a western half, may be obtained from the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402.

NOTE 2: Copies of "Provisional Ground Conductivity Map" may be obtained by addressing the Director, Telecommunications and Electronics Branch, Department of Transport, Ottawa, Ontario, Canada. Single copies are priced at $5.00 (one copy consists of two sheets). Remittance should be made by check or money order payable to the Receiver General of Canada.

(d) Example of determining interference by the graphs in § 73.184:

It is desired to find whether objectionable interference exists between a 5 kw Class III station on 990 kc/s and a 1 kw Class III station on 1000 kc/s, the stations being separated by 130 miles; both stations use nondirectional antennas having such height as to produce an effective field of 1 kw of 175 mv/m. (See § 73.185 in case of use of directional antennas.) The conductivity at each station and of the intervening terrain is determined as 6 mmhos/m. The protection to Class III stations during daytime is to the 500 uv/m contour. The distance to the 500 uv/m groundwave contour of the 1 kw station is determined by the use of the appropriate curve in § 73.184, Graph 12. Since the curve is plotted for 100 mv/m at a mile, to find the distance to the 500 uv/m contour of the 1 kw station, it is necessary to determine the distance to the 285 uv/m contour ($\frac{100 \times 500}{175} = 285$). From the appropriate curve, the estimated radius of the service area for the desired station is found to be 39.5 miles. Subtracting this distance from the distance between the two stations leaves 90.5 miles for the interfering signal to travel. From the above curve it is found that the signal from the 5 kw station at this distance would be 158 uv/m. Since a one to one ratio applies for stations separated by 10 kc/s, the undesired signal at that point can have a value up to 500 uv/m without objectionable interference. If the undesired signal had been found to be greater than 500 uv/m, then objectionable interference would exist. For other channel separations, the appropriate ratio of desired to undesired signal should be used.

(e) Where a signal traverses a path over which different conductivities exist, the distance to a particular groundwave field intensity contour shall be determined by the use of the equivalent distance method. Reasonably accurate results may be expected in determining field intensities at a distance from the antenna by application of the equivalent distance method when the unattenuated field of the antenna, the various ground conductivities and the location of discontinuities are known. This method considers a wave to be propagated across a given conductivity according to the curve for a homogeneous earth of that conductivity. When the wave crosses from a region of one conductivity into a region of a second conductivity, the equivalent distance of the receiving point from the transmitter changes abruptly but the field intensity does not. From a point just inside the second region the transmitter appears to be at that distance where, on the curve for a homogeneous earth of the second conductivity, the field intensity equals the value that occurred just across the boundary in the first region. Thus the equivalent distance from the receiving point to the transmitter may be either greater or less than the actual distance. An imaginary transmitter is considered to exist at that equivalent distance. This technique is not intended to be used as a means of evaluating unattenuated field or ground conductivity by the analysis of measured data. The method to be employed for such determinations is set out in § 73.186.

(f) An example of the use of the equivalent distance method follows:

It is desired to determine the distance to the 0.5 mv/m and 0.025 mv/m contours of a station on a frequency of 1000 kc/s with an inverse distance field of 100 mv/m at one mile being radiated over a path having a conductivity of 10 mmhos/m for a distance of 15 miles, 5 mmhos/m for the next 20 miles and 15 mmhos/m thereafter. By the use of the appropriate curves in § 73.184, Graph 12, it is seen that at a distance of 15 miles on the curve for 10 mmhos/m the field is 3.45 mv/m. The equivalent distance to this field intensity for a conductivity of 5 mmhos/m is 11 miles. Continuing on the propagation curve for the second conductivity, the 0.5 mv/m contour is encountered at a distance of 27.9 miles from the imaginary transmitter. Since the imaginary transmitter was 4 miles nearer (15—11 miles) to the 0.5 mv/m contour, the distance from the contour to the actual transmitter is 31.9 miles (27.9+4 miles). The distance to the 0.025 mv/m contour is determined by continuing on the propagation curve for the second conductivity to a distance of 31 miles (11+20 miles), at which point the field is read to be 0.39 mv/m. At this point the conductivity changes to 15 mmhos/m and from the curve relating to that conductivity, the equivalent distance is determined to be 58 miles—27 miles more distant than would obtain had a conductivity of 5 mmhos/m prevailed. Using the curve representing the conductivity of 15 mmhos/m the 0.025 mv/m contour is determined to be at an equivalent distance of 172 miles. Since the imaginary transmitter was considered to be 4 miles closer at the first boundary and 27 miles farther at the second boundary, the net effect is to consider the imaginary transmitter 23 miles (27—4 miles) more distant than the actual transmitter; thus the actual distance to the 0.025 mv/m contour is determined to be 149 miles (172—23 miles).

§ 73.184 Groundwave field intensity charts.

(a) Graphs 1 to 19A show the computed values of groundwave field intensity as a function of the distance from the transmitting antenna. The groundwave field intensity is here considered to be that part of the vertical component of the electric field received on the ground which has not been reflected from the ionosphere nor the troposphere. These 20 charts were computed for 20 different frequencies, a dielectric constant of the ground equal to 15 for land and 80 for sea water (referred to air as unity) and for the ground conductivities (expressed in mmhos/m) given on the curves. The curves show the variation of the groundwave field intensity with distance to be expected for transmission from a short vertical antenna at the surface of a uniformly conducting spherical earth with the ground constants shown on the curves; the curves are for an antenna power and efficiency such that the inverse distance field is 100 mv/m at 1 mile. The curves are valid at distances large compared to the dimensions of the antenna for other than short vertical antennas.

(b) The inverse distance field (100 mv/m divided by the distance in miles) corresponds to the groundwave field intensity to be expected from an antenna with the same radiation efficiency when it is located over a perfectly conducting earth. To determine the value of the groundwave field intensity corresponding to a value of inverse distance field other than 100 mv/m at 1 mile, simply multiply the field intensity as given on these charts by the desired value of inverse distance field at 1 mile divided by 100; for example, to determine the groundwave field intensity for a station with an inverse distance field of 1700 mv/m at 1 mile, simply multiply the values given on the charts by 17. The value of the inverse distance field to be used for a particular antenna depends upon the power input to the antenna, the nature of the ground in the neighborhood of the antenna, and the geometry of the antenna. For methods of calculating the interrelations between these variables and the inverse distance field, see "The Propagation of Radio Waves Over the Surface of the Earth and in the Upper Atmosphere," Part II, by Mr. K. A. Norton, Proc. I. R. E., Vol. 25, September 1937, pp. 1203–1236.

(c) At sufficiently short distances (say less than 35 miles), such that the curvature of the earth does not introduce an additional attenuation of the waves, the graphs were computed by means of the plane earth formulas given in the paper, "The Propagation of Radio Waves Over the Surface of the Earth and in the Upper Atmosphere," Part I, by Mr. K. A. Norton, Proc. I. R. E., Vol. 24, October 1936, pp. 1367–1387. At larger distances the additional attenuation of the waves which is introduced by the effect of the curvature of the earth was introduced by the methods outlined in the papers, "The Diffraction of Electromagnetic Waves from an Electrical Point Source round a Finitely Conducting Sphere, with Applications to Radiotelegraphy and the Theory of the Rainbow," by Balth van der Pol and H. Bremmer, Part I, Phil. Mag., Vol. 24, p. 141, July 1937, Part II, Phil. Mag., Vol. 24, p. 82, Suppl., November 1937, "Ergebnisse einer Theorie ueber die Fortpflanzung elektron magnetischer Wellen ueber eine Kugel endlicher Leitfahigkeit," by Balth van der Pol and H. Bremmer, Hochfrequenztechnik und Elektroakustik, Band 51, Heft 6, June 1938, "Further Note on the Propagation of Radio Waves over a Finitely Conducting Spherical Earth," by Balth van der Pol and H. Bremmer, Phil. Mag., Vol. 27, p. 261, March 1939. In order to allow for the refraction of the radio waves in the lower atmosphere due to the variation of the dielectric constant of the air with height above the earth, a radius of the earth equal to 4/3 the actual radius was used in the computations for the effect of the earth's curvature in the manner suggested by C. R. Burrows, "Radio Propagation over Spherical Earth," Proc. I. R. E., May 1935; i. e., the distance corresponding to a given value of attenuation due to the curvature of the earth in the absence of air refraction was multiplied by the factor $(4/3)^{\frac{3}{2}}=1.21$. The amount of this refraction varies from day to day and from season to season, depending on the air mass conditions in the lower atmosphere. If k denotes the ratio between the equivalent radius of the earth and the true radius, the following table gives the values of k for several typical air masses encountered in the United States.

Air mass type	k	
	Summer	Winter
Tropical Gulf—T_c	1.53	1.43
Polar Continental—P_c	1.31	1.25
Superior—S	1.25	1.25
Average	1.33	

It is clear from this table that the use of the average value of $k=4/3$ is justified in obtaining a single correction for the systematic effects of atmospheric refraction.

(d) Provided the value of the dielectric constant is near 15, the curves of Graphs 1 to 19A may be compared with experimental data to determine the appropriate values of the ground conductivity and of the inverse distance field intensity at 1 mile. This is accomplished simply by plotting the measured fields on transparent log-log graph paper similar to that used for Graphs 1 to 19A and superimposing this chart over the graph corresponding to the frequency involved. The log-log graph sheet is then shifted vertically until the best fit is obtained with one of the curves on the graph; the intersection of the inverse distance line on the graph with the 1-mile abscissa on the chart determines the inverse distance field intensity at 1 mile. For other values of dielectric constant, the following procedure may be used for a determination of the dielectric constant of the ground, conductivity of the ground and the inverse distance field intensity at 1 mile. Graph 20 gives the relative values of groundwave field intensity over a plane earth as a function of the numerical distance p and phase angle b. On graph paper with coordinates similar to those of Graph 20, plot the measured values of field intensity as ordinates versus the corresponding distances from the antenna expressed in miles as abscissae. The data should be plotted only for distances greater than one wavelength (or, when this is greater, five times the vertical height of the antenna in the case of a single element, i. e., nondirectional antenna or 10 times the spacing between the elements of a directional antenna) and for distances less than $50/f_{Mc/s}^{\frac{1}{3}}$ miles (i.e., 50 miles at 1 Mc/s). Then, using a light box, place the sheet with the data plotted on it over the sheet with the curves of Graph 20 and shift the data sheet vertically and horizontally (making sure that the vertical lines on both sheets are parallel) until the best fit with the data is obtained with one of the curves on Graph 20. When the two sheets are properly lined up, the value of the field intensity corresponding to the intersection of the inverse distance line of Graph 20 with the 1 mile abscissa on the data sheet is the inverse distance field intensity at 1 mile, and the values of the numerical distance at 1 mile, p_1, and of b are also determined. Knowing the values of b and p_1 (the numerical distance at 1 mile), we may substitute in the following approximate formulas to determine the appropriate values of the ground conductivity and dielectric constant.

$$x\cong\frac{\pi}{p_1}\cdot(R/\lambda)_1\cos b \qquad (1)$$

$(R/\lambda)_1$=Number of wavelengths in 1 mile.

$$\sigma_{e.\,m.\,u.}=\frac{xf_{mc}}{17.9731}\cdot 10^{-14} \qquad (2)$$

$\sigma_{e.\,m.\,u.}$=Conductivity of the ground expressed in electromagnetic units.

f_{mc}=frequency expressed in megacycles.

$$\epsilon\cong x\tan b-1 \qquad (3)$$


ϵ=dielectric constant of the ground referred to air as unity.

First solve for x by substituting the known values of p_1, $(R/\lambda)_1$, and cos b in equation (1). Equation (2) may then be solved for σ and equation (3) for ϵ). At distances greater than $50/f_{Mc/s}^{\frac{1}{3}}$ miles the curves of Graph 20 do not give the correct relative values of field intensity since the curvature of the earth weakens the field more rapidly than these plane earth curves would indicate. Thus, no attempt should be made to fit experimental data to these curves at the larger distances.

(e) At sufficiently short distances (say less than 35 miles at broadcast frequencies), such that the curvature of the earth does not introduce an additional attenuation of the waves, the curves of Graph 20 may be used for determining the groundwave field intensity of transmitting and receiving antennas at the surface of the earth for any radiated power, frequency, or set of ground constants in the following manner: First, lay off the straight inverse distance line corresponding to the power radiated on transparent log-log graph paper similar to that of Graph 20, labelling the ordinates of the chart in terms of field intensity, and the abscissae in terms of distance. Next, by means of the formulas given on Graph 20, calculate the value of the numerical distance, p, at 1 mile, and the value of b. Then superimpose the log-log chart over Graph 20, shifting it vertically until the inverse distance lines on both charts coincide and shifting it horizontally until the numerical distance at 1 mile on Graph 20 coincides with 1 mile on the log-log graph paper. The curve of Graph 20 corresponding to the calculated value of b is then traced on the log-log graph paper giving the field intensity versus distance in miles.


(f) This paragraph consists of the following Graphs 1 to 19, 19A, and 20, and a "slider for use with graphs."

NOTE: The graphs as reproduced herein, due to the small scale, are not to be used in connection with material submitted to the F. C. C. and therefore the slider is not reproduced.




GRAPH 1

FCC-1954




GRAPH 2


FCC-1954




GRAPH 4




GRAPH 3




GRAPH 6




GRAPH 5




GRAPH 8




GRAPH 7



GRAPH 10




GRAPH 9




GRAPH 11

FCC-1954




GRAPH 12

FCC-1954




GRAPH 13

FCC-1954




GRAPH 14

FCC-1954




GRAPH 15

FCC-1954




GRAPH 16

FCC-1954




GRAPH 17

FCC-1954




GRAPH 18

FCC-1954




GRAPH 19-A



GRAPH 19

FCC-1954



GRAPH 20

§ 73.185 Computation of interfering signal from a directional antenna.

(a) In case of an antenna directional in the horizontal plane, the groundwave interference can be readily computed from the calculated horizontal pattern by determining the vectors toward the service area of the station to be protected and applying these values to the groundwave curves set out in § 73.183.

(b) For signals from stations operating on Class I–B clear channels (those specified in § 73.25(b)), in case of determining skywave interference from an antenna with a vertical pattern different from that on which Figure 1 of § 73.190 is predicated (the basis of the night mileage separation tables), it is necessary to compare the appropriate vectors in the vertical plane.

(c) The skywave curves entitled "Average Skywave Field Intensity" (corresponding to the second hour after sunset at the recording station) as shown in Figure 1 of § 73.190 are based on antenna systems having height of 0.311 wave length (112°) and producing a vertical pattern as shown in Figure 5 of § 73.190. A nondirectional antenna system, as well as a directional antenna system having vertical patterns other than essentially the same as shown, must be converted to the pattern of a 0.311 wave length antenna having the same field intensity at the critical angle as does the pattern of the antenna involved.

(d) Examples of the use of skywave curves on Class I–B clear channels: Figure 6 of § 73.190 is a graph entitled "Variation With Distance of Two Important Parameters in the Theory of Sky Wave Propagation." The curve for θ showing the angle above the horizon at which radiation occurs plotted against distance, must be used for this purpose. For instance, assuming the station with which interference may be expected is located at a distance of 450 miles from a proposed station, the critical angle of radiation as determined from this curve is approximately 15°. Therefore, if the vertical pattern of the proposed station in the direction of the other station is such that at 15° above the horizon the radiation is 1.3 times that from an antenna having a vertical pattern as shown in Figure 5 of § 73.190 and producing the same field intensity at 1 mile in the horizontal plane, the interfering signal would be 1.3 times that determined from Figure 1 of § 73.190 for an antenna having the same field intensity in the horizontal plane. That is, if the field intensity in the horizontal plane of the proposed station is 124 mv/m the interfering field intensity exceeded 10 percent of the time at the other station would be

$$140 \times 1.30 \times \frac{124}{100} \text{ or } 225 \text{ uv/m}$$

and would cause interference to the 4.5 mv/m ground wave contour of the existing station.

(e) For signals from stations on regional and local channels, in computing the 10% skywave (interference) field intensity values of Class III and Class IV stations, Figure 2 of § 73.190 is to be used in place of Figure 1 of § 73.190. (Certain simplifying assumptions may be made in the case of Class IV stations on local channels. See Note to § 73.182(a)(4).) Since Figure 2 of § 73.190 is predicated upon a radiated field of 100 mv/m at one mile in the pertinent direction, no comparison with the vertical pattern of a 0.311 wavelength antenna is to be made. Instead the appropriate radiated field in the vertical plane corresponding to the distance to the receiving station, divided by 100, is multiplied into the value of 10% skywave field intensity determined from Figure 2 of § 73.190. There are two new factors to be considered, however, namely the variation of received field with latitude of the path and the variation of pertinent vertical angle due to variations of ionosphere height and ionosphere scattering.

(f) Figure 2 of § 73.190, "10% Skywave Signal Range Chart," shows the 10% skywave signal as a function of the latitude of the transmission path and the distance from a transmitting antenna with a radiated field of 100 mv/m at the pertinent angle for the distance. The latitude of the transmission path is defined as the geographic latitude of the midpoint between the transmitter and the receiver. Latitude 35° should be used in case the midpoint of the path lies below 35° North and latitude 50° should be used in case the midpoint of the path lies above 50° North.

(g) Figure 6a of § 73.190, entitled "Angles of Departure vs. Transmission Range," is to be used in determining the

angles in the vertical pattern of the antenna of an interfering station to be considered as pertinent to transmission by one reflection. Corresponding to any given distance, the Curves 4 and 5 indicate the upper and lower angles within which the radiated field is to be considered. The maximum value of field intensity occurring between these angles will be used to determine the multiplying factor for the 10% skywave field intensity determined from Figure 2 of § 73.190. (Curves 2 and 3 are considered to represent the variation due to the variation of the effective height of the E-layer while Curves 4 and 5 extend the range of pertinent angles to include a factor which allows for scattering. The dotted lines are included for information only.)

(h) In the case of non-directional vertical antennas, the vertical distribution of relative fields for several heights, assuming sinusoidal distribution of current along the antenna, is shown in Figure 5 of § 73.190. In the case of directional antennas the vertical pattern in the great circle direction toward the point of reception in question must first be calculated. Then for the distance to the points, the upper and lower pertinent angles are determined from Figure 6a of § 73.190. The ratio of the largest value of radiated field occurring between these angles, to 100 mv/m (for which Figure 2 of § 73.190 is drawn) is then used as the multiplying factor for the value of the field read from the curves of Figure 2 of § 73.190. Note that while the accuracy of the curves is not as well established by measurements for distances less than 250 miles as for distances in excess of 250 miles, the curves represent the most accurate data available today. Pending accumulation of additional data to establish firm standards for skywave calculations in this range, the curves may be used. In cases where the radiation in the vertical plane, in the pertinent azimuth, contains a large lobe at a higher angle than the pertinent angle for one reflection the method of calculating interference will not be restricted to that described above, but each such case will be considered on the basis of the best knowledge available.

(i) Example, suppose it is desired to determine the amount of interference to a Class III station at Portland, Oregon, caused by another Class III station at Los Angeles, California, which is radiating a signal of 560 mv/m unattenuated at one mile in the great circle direction of Portland, using a 0.5 wavelength antenna. The distance is 825 miles. From Figure 6a of § 73.190 the upper and lower pertinent angles are 7° and 3.5° and, from Figure 5 of § 73.190 the maximum radiation within these angles is 99% of the horizontal radiation or 554 mv/m at 1 mile. The latitude of the path is 39.8° N and from Figure 2 of § 73.190, the 10% skywave field at 825 miles is 0.050 mv/m for 100 mv/m radiated. Multiplying by $\frac{554}{100}$ to adjust the value to the actual radiation gives 0.277 mv/m. At 20 to 1 ratio the limitation to the Portland station is to the 5.5 mv/m contour.

(j) When the distance is large, more than one reflection may be involved and due consideration must be given each appropriate vector in the vertical pattern, as well as the constants of the earth where reflection takes place between the transmitting station and the service area to which interference may be caused.

(k) For signals from stations operating on Class I–A clear channels (those specified in § 73.25(a)), skywave interference is determined by using the 10 percent curve of Figure 1a of § 73.190, entitled "Skywave Signals for 10 percent and 50 percent of the Time." The pertinent angle of departure is to be determined by use of Figure 6a of § 73.190, in a manner similar to that described in paragraph (g) of this section for regional stations. An example of the determination of skywave interference in this situation is as follows: Assume a Class I–A station and a proposed Class II–A station, operating on the same channel, are separated 1450 miles and that the 0.5 mv/m—50 percent skywave contour of the Class I–A station is located 740 miles from the station. The distance from the Class II–A station to the protected contour of the Class I–A station is 710 miles and from Figure 6a the critical angles of radiation are 5° to 9°. If the vertical pattern of the antenna of the proposed Class II–A station is such that between these angles the maximum radiation is 34 mv/m at one mile, the value of the 10 percent field as read from Figure 1a is multiplied by $\frac{34}{100}$ to determine the interfering 10 percent field intensity at the 0.5 mv/m—50 percent skywave contour of the I–A station, which would be 0.025 mv/m.

§ 73.186 Field intensity measurements in allocation; establishment of effective field at one mile.

(a) Section 73.45 provides that certain minimum field intensities are acceptable in lieu of the required minimum physical vertical heights of the antennas proper. Also, in other allocation problems, it is necessary to determine the effective field at 1 mile. The following requirements shall govern the taking and submission of data on the field intensity produced:

(1) Beginning as near to the antenna as possible without including the induction field and to provide for the fact that a broadcast antenna not being a point source of radiation (not less than one wave length or 5 times the vertical height in the case of a single element, i. e., nondirectional antenna or 10 times the spacing between the elements of a directional antenna), measurements shall be made on eight or more radials, at intervals of approximately one-tenth mile up to 2 miles from the antenna, at intervals of approximately one-half mile from 2 miles to 6 miles from the antenna, at intervals of approximately 2 miles from 6 miles to 15 or 20 miles from the antenna, and a few additional measurements if needed at greater distances from the antenna. Where the antenna is rurally located and unobstructed measurements can be made, there shall be as many as 18 or 20 measurements on each radial. However, where the antenna is located in a city where unobstructed measurements are difficult to make, measurements shall be made on each radial at as many unobstructed locations as possible, even though the intervals are considerably less than stated above, particularly within 2 miles of the antenna. In cases where it is not possible to obtain accurate measurements at the closer distances (even out to 5 or 6 miles due to the character of the intervening terrain), the measurements at greater distances should be made at closer intervals. (It is suggested that "wave tilt" measurements may be made to determine and compare locations for taking field intensity measurements, particularly to determine that there are no abrupt changes in ground conductivity or that reflected waves are not causing abnormal intensities.)

(2) The data required by subparagraph (1) of this paragraph should be plotted for each radial in accordance with either of the two methods set forth below:

(i) Using log-log coordinate paper, plot field intensities as ordinate and distance as abscissa.

(ii) Using semi-log coordinate paper, plot field intensity times distance as ordinate on the log scale and distance as abscissa on the linear scale.

(3) However, regardless of which of the methods in subparagraph (2) of this paragraph is employed, the proper curve to be drawn through the points plotted shall be determined by comparison with the curves in § 73.184 as follows: Place the sheet on which the actual points have been plotted over the appropriate Graph in § 73.184, hold to the light if necessary and adjust until the curve most closely matching the points is found. This curve should then be drawn on the sheet on which the points were plotted, together with the inverse distance curve corresponding to that curve. The field at 1 mile for the radial concerned shall be the ordinate on the inverse distance curve at 1 mile.

(4) When all radials have been analyzed in accordance with subparagraph (3) of this paragraph, a curve shall be plotted on polar coordinate paper from the fields obtained, which gives the inverse distance field pattern at 1 mile. The radius of a circle, the area of which is equal to the area bounded by this pattern, is the effective field. (See § 73.14.)

(5) While making the field intensity survey, the output power of the station shall be maintained at the licensed power as determined by the direct method. To do this, it is necessary to determine accurately the total antenna resistance (the resistance variation method, the substitution method or bridge method is acceptable) and to measure the antenna current by means of an ammeter of acceptable accuracy. (See §§ 73.39 and 73.54.)

(b) Complete data taken in conjunction with the field intensity measurements shall be submitted to the Commission in affidavit form including the following:

(1) Tabulation by number of each point of measurement to agree with the map required in (2) below and the field intensity meter reading, the attenuation constant, the field intensity (E), the dis-

tance from the antenna (*D*) and the product of the field intensity and distance (*ED*) (if data for each radial are plotted on semi-logarithmic paper, see above) for each point of measurement.

(2) Map showing each point of measurement numbered to agree with tabulation required above.

(3) Description of method used to take field intensity measurements.

(4) The family of theoretical curves used in determining the curve for each radial properly identified by conductivity and dielectric constants.

(5) The curves drawn for each radial and the field intensity pattern.

(6) Antenna resistance measurement:

(i) Antenna resistance at operating frequency.

(ii) Description of method employed.

(iii) Tabulation of complete data.

(iv) Curve showing antenna resistance versus frequency.

(7) Antenna current or currents maintained during field intensity measurements.

(8) Description, accuracy, date, and by whom each instrument was last calibrated.

(9) Name, address, and qualifications of the engineer making the measurements.

(10) Any other pertinent information.

§ 73.187 Limitation on daytime radiation.

(a) (1) Except as otherwise provided in subparagraphs (2) and (3) of this paragraph, no authorization will be granted for Class II facilities if the proposed facilities would radiate, during the two hours after local sunrise and the two hours before local sunset, toward any point on the 0.1 mv/m contour of a co-channel U.S. Class I station, at or below the pertinent vertical angle determined from Curve 4 of Figure 6a of § 73.190, values in excess of those obtained as provided in paragraph (b) of this section.

(2) The limitation set forth in subparagraph (1) of this paragraph shall not apply in the following cases:

(i) Any Class II facilities authorized before November 30, 1959; or

(ii) For Class II stations authorized before November 30, 1959, subsequent changes of facilities which do not involve a change in frequency, an increase in radiation toward any point on the 0.1 mv/m contour of a co-channel U.S. Class I station, or the move of transmitter site materially closer to the 0.1 mv/m contour of such Class I stations.

(3) If a Class II station authorized before November 30, 1959, is authorized to increase its daytime radiation in any direction toward the 0.1 mv/m contour of a co-channel U.S. Class I station (without a change in frequency or a move of transmitter site materially closer to such contour), it may not, during the two hours after local sunrise or the two hours before local sunset, radiate in such directions a value exceeding the higher of:

(i) The value radiated in such directions with facilities last authorized before November 30, 1959, or

(ii) The limitation specified in subparagraph (1) of this paragraph.

(b) To obtain the maximum permissible radiation for a Class II station on a given frequency ($f_{kc/s}$) from 640 kc/s through 990 kc/s, multiply the radiation value obtained for the given distance and azimuth from the 500 kc/s chart (Figure 9 of § 73.190) by the appropriate interpolation factor shown in the K_{500} column of paragraph (c) of this section; and multiply the radiation value obtained for the given distance and azimuth from the 1000 kc/s chart (Figure 10 of § 73.190) by the appropriate interpolation factor shown in the K_{1000} column of paragraph (c) of this section. Add the two products thus obtained; the result is the maximum radiation value applicable to the Class II station in the pertinent directions. For frequencies from 1010 kc/s to 1580 kc/s, obtain in a similar manner the proper radiation values from the 1000 kc/s and 1600 kc/s charts (Figures 10 and 11 of § 73.190), multiply each of these values by the appropriate interpolation factors in the K'_{1000} and K'_{1600} columns in paragraph (c) of this section, and add the products.

(c) Interpolation factors. (1) Frequencies below 1000 kc/s.

$f_{kc/s}$	K_{500}	K_{1000}	$f_{kc/s}$	K_{500}	K_{1000}
640	0.720	0.280	780	0.440	0.560
650	0.700	0.300	800	0.400	0.600
660	0.680	0.320	810	0.380	0.620
670	0.660	0.340	820	0.360	0.640
680	0.640	0.360	830	0.340	0.660
690	0.620	0.380	840	0.320	0.680
700	0.600	0.400	850	0.300	0.700
710	0.580	0.420	860	0.280	0.720
720	0.560	0.440	870	0.260	0.740
730	0.540	0.460	880	0.240	0.760
740	0.520	0.480	890	0.220	0.780
750	0.500	0.500	900	0.200	0.800
760	0.480	0.520	940	0.120	0.880
770	0.460	0.540	990	0.020	0.980

(2) Frequencies above 1000 kc/s.

$f'_{kc/s}$	K'_{1000}	K'_{1600}	$f'_{kc/s}$	K'_{1000}	K'_{1600}
1010	0.983	0.017	1170	0.717	0.283
1020	0.967	0.033	1180	0.700	0.300
1030	0.950	0.050	1190	0.683	0.317
1040	0.933	0.067	1200	0.667	0.333
1050	0.917	0.083	1210	0.650	0.350
1060	0.900	0.100	1220	0.633	0.367
1070	0.883	0.117	1500	0.167	0.833
1080	0.867	0.133	1510	0.150	0.850
1090	0.850	0.150	1520	0.133	0.867
1100	0.833	0.167	1530	0.117	0.883
1110	0.817	0.183	1540	0.100	0.900
1120	0.800	0.200	1550	0.083	0.917
1130	0.783	0.217	1560	0.067	0.933
1140	0.767	0.233	1570	0.050	0.950
1160	0.733	0.267	1580	0.033	0.967

§ 73.188 Location of transmitters.

(a) The four primary objectives to be obtained in the selection of a site for a transmitter of a broadcast station are as follows:

(1) To serve adequately the center of population in which the studio is located and to give maximum coverage to adjacent areas.

(2) To cause and experience minimum interference to and from other stations.

(3) To present a minimum hazard to air navigation consistent with objectives (1) and (2).

(4) To fulfill certain other requirements given in the following paragraphs of this section.

(b) The site selected should meet the following conditions:

(1) A minimum field intensity of 25 to 50 mv/m will be obtained over the business or factory areas of the city.

(2) A minimum field intensity of 5 to 10 mv/m will be obtained over the most distant residential section.

(3) The absorption of the signal is the minimum for any obtainable sites in the area. As a guide in this respect the absorption of the signals from other stations in that area should be followed, as well as the results of tests on other sites.

(4) The population within the blanket contour does not exceed that specified by § 73.24(g).

(c) In selecting a site in the center of a city it is usually necessary to place the radiating system on the top of a building. This building should be large enough to permit the installation of a satisfactory ground and/or counterpoise system. Great care must be taken to avoid selecting a building surrounded by taller buildings or where any nearby building higher than the antenna is located in the direction which it is desired to serve. Such a building will tend to cast "radio shadows" which may materially reduce the coverage of the station in that direction. Irrespective of the height of surrounding buildings, the building on which the antenna is located should not have height of approximately one-quarter wavelength. A study of antenna systems located on buildings tends to indicate that where the building is approximately a quarter wavelength in height, the efficiency of radiation may be materially reduced.

(d) Particular attention must be given to avoiding cross-modulation. In this connection, attention is invited to the fact that it has been found very unsatisfactory to locate broadcast stations so that high signal intensities occur in areas with overhead electric power or telephone distribution systems and sections where the wiring and plumbing are old or improperly installed. These areas are usually found in the older sections of a city. These conditions give rise to cross-modulation interference due to the nonlinear conductivity characteristics of contacts between wiring, plumbing, or other conductors. This type of interference is independent of the selectivity characteristics of the receiver and normally can be eliminated only by correction of the condition causing the interference. Cross-modulation tends to increase with frequency and in some areas it has been found impossible to eliminate all sources of cross-modulation, resulting in an unsatisfactory condition for both licensee and listeners. The Commission will not authorize (1) new stations, (2) a major change of facilities of existing stations, (3) a change in transmitter location of an existing station, or (4) auxiliary transmitters, for use with other than the authorized antenna system of the main transmitter, if such new stations, physical facilities of existing stations after a major change, transmitters or auxiliary transmitters would be located in such areas or would utilize a roof-top antenna and the operating power would be in excess of 1000 watts.

(e) If it is determined that a site should be selected removed from the city,

there are several general conditions to be followed in determining the exact site. Three maps should be given consideration if available:

(1) Map of the density of population and number of people by sections in the area. (See Bureau of Census series P–D and H–E available from Superintendent of Documents, Government Printing Office, Washington, D.C., 20402.)

(2) Geographical contour map with contour intervals of 20 to 50 feet.

(3) Map showing the type, nature and depth of the soil in the area with special reference to the condition of the moisture throughout the year.

From these maps a site should be selected with a minimum number of intervening hills between it and the center of the city. In general, because of ground conditions, it is better to select a site in a low area rather than on top of a hill, and the only condition under which a site on top of a hill should be selected is that it is only possible by this means to avoid a substantial number of hills, between the site and the center of a city with the resulting radio shadows. If a site is to be selected to serve a city which is on a general sloping area, it is generally better to select a site below the city than above the city.

(f) If a compromise must be made between probable radio shadows from intervening hills and locating the transmitter on top of a hill, it is generally better to compromise in favor of the low area, where an efficient radiating system may be installed which will more than compensate for losses due to shadows being caused by the hills, if not too numerous or too high. Several transmitters have been located on tops of hills, but so far as data has been supplied not a single installation has given superior efficiency of propagation and coverage.

(g) The ideal location of a broadcast transmitter is in a low area of marshy or "crawfishy" soil or area which is damp the maximum percentage of time and from which a clear view over the entire center of population may be had and the tall buildings in the business section of the city would cast a shadow across the minimum residential area.

(h) The type and condition of the soil or earth immediately around a site is very important. Important, to an equal extent, is the soil or earth between the site and the principal area to be served. Sandy soil is considered the worst type, with glacial deposits and mineral-ore areas next. Alluvial, marshy areas and salt-water bogs have been found to have the least absorption of the signal. One is fortunate to have available such an area and, if not available, the next best condition must be selected.

(i) Figure M3 (See Note to § 73.183 (c)) and Figure R3 of § 73.190 indicate effective conductivity values in the United States, and are to be used for determining the extent of broadcast station coverage when adequate field intensity measurements over the path in question are not available. Since the values specified are only for general areas and since conductivity values over particular paths may vary widely from those shown, caution must be exercised in using the maps for selection of a satisfactory transmitter site. Where the submission of field intensity measurements is deemed necessary or advisable, the Commission, in its discretion, may require an applicant for new or changed broadcast facilities to submit such data in support of its application.

(j) In general, broadcast transmitters operating with approximately the same power can be grouped in the same approximate area and thereby reduce the interference between them. If the city is of irregular shape, it is often possible to take advantage of this in selecting a suitable location that will give a maximum coverage. The maps giving the density of population will be a key to this. The map giving the elevation by contours will be a key to the obstructing hills between the site and city. The map of the soil conditions will assist in determining the efficiency of the radiating system that may be erected and the absorption of the signal encountered in the surrounding area.

(k) Another factor to be considered is the relation of the site to airports and airways. Procedures and standards with respect to the Commission's consideration of proposed antenna structures which will serve as a guide to persons intending to apply for radio station licenses are contained in Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures).

(l) In finally selecting the site, consideration must be given to the required space for erecting an efficient radiating system, including the ground or counterpoise. It is the general practice to use direct grounds consisting of a radial buried wire system. If the area is such that it is not possible to get such ground system in soil that remains moist throughout the year, it probably will be found better to erect a counterpoise. (Such a site should be selected only as a last resort.) It, like the antenna itself, must of course be designed properly for the operating frequency and other local conditions.

(m) While an experienced engineer can sometimes select a satisfactory site for a 100-watt station by inspection, it is necessary for a higher power station to make a field-intensity survey to determine that the site selected will be entirely satisfactory. There are several facts that cannot be determined by inspection that make a survey very desirable for all locations removed from the city. Often two or more sites may be selected that appear to be of equal promise. It is only by means of field-intensity surveys taken with a transmitter at the different sites or from measurements on the signal of nearby stations traversing the terrain involved that the most desirable site can be determined. There are many factors regarding site efficiency that cannot be determined by any other method. When making the final selection of a site, the need for a field-intensity survey to establish the exact conditions cannot be stressed too strongly. The selection of a proper site for a broadcast station is an important engineering problem and can only be done properly by experienced radio engineers.

§ 73.189 Minimum antenna heights or field intensity requirements.

(a) Section 73.45 requires that all applicants for new, additional, or different broadcast facilities and all licensees requesting authority to move the transmitter of an existing station, shall specify a radiating system, the efficiency of which complies with the requirements of good engineering practice for the class and power of the station.

(b) The specifications deemed necessary to meet the requirements of good engineering practice at the present state of the art are set out in detail below.

(1) The licensee of a standard broadcast station requesting a change in power, time of operation, frequency, or transmitter location must also request authority to install a new antenna system or to make changes in the existing antenna system which will meet the minimum height requirements, or submit evidence that the present antenna system meets the minimum requirements with respect to field intensity, before favorable consideration will be given thereto. (See § 73.186.) In the event it is proposed to make substantial changes in an existing antenna system, the changes shall be such as to meet the minimum height requirements or will be permitted subject to the submission of field intensity measurements showing that it meets the minimum requirements with respect to effective field intensity.

(2) These minimum actual physical vertical heights of antennas permitted to be installed are shown by curves A, B, and C of Figure 7 of § 73.190 as follows:

(i) Class IV stations, 150 feet or a minimum effective field intensity of 150 mv/m for 1 kilowatt (100 watts 47.5 mv/m, and 250 watts 75 mv/m). (This height applies to a Class IV station on a local channel only. In the case of a Class IV station assigned to a regional channel Curve A shall apply.)

(ii) Class II and III stations, or a minimum effective field intensity of 175 mv/m for 1 kilowatt.

(iii) Class I stations, or a minimum effective field intensity of 225 mv/m for 1 kilowatt.

(3) The heights given on the graph for the antenna apply regardless of whether the antenna is located on the ground or on a building. Except for the reduction of shadows, locating the antenna on a building does not necessarily increase the efficiency and where the height of the building is in the order of a quarter wave the efficiency may be materially reduced.

(4) To obtain the maximum efficiency of which any antenna is capable a good ground system must be employed (a counterpoise may be substituted under certain conditions).

(5) At the present development of the art, it is considered that where a vertical radiator is employed with its base on the ground, the ground system should consist of buried radial wires at least one-fourth wave length long. There should be as many of these radials evenly spaced as practicable and in no event less than 90.

(120 radials of 0.35 to 0.4 of a wave length in length and spaced 3° is considered an excellent ground system and in case of high base voltage, a base screen of suitable dimensions should be employed.)

(6) It should be borne in mind that the above specifications are the minimums and where possible better antenna and ground systems should be installed.

(7) In case it is contended that the required antenna efficiency can be obtained with an antenna of height or ground system less than the minimum specified, a complete field intensity survey must be supplied to the Commission showing that the field intensity at a mile without absorption fulfills the minimum requirements. (See § 73.186.) This field survey must be made by a qualified engineer using equipment of acceptable accuracy.

(8) The main element or elements of a directional antenna system shall meet the above minimum requirements with respect to height or effective field intensity. No directional antenna system will be approved which is so designed that the effective field of the array is less than the minimum prescribed for the class of station concerned, or in case of a Class I station less than 90 percent of the ground wave field which would be obtained from a perfect antenna of the height specified by Figure 7 of § 73.190 for operation on frequencies below 1000 kilocycles, and in the case of a Class II or III station less than 90 percent of the ground wave field which would be obtained from a perfect antenna of the height specified by Figure 7 of § 73.190 for operation on frequencies below 750 kilocycles.

(9) Before any changes are made in the antenna system, it is necessary to submit full details to the Commission for approval. These data may be submitted by letter.

§ 73.190 **Engineering charts.**

This section consists of the following figures: 1, 1a, 2, R3, 5, 6, 6a, 7, 8, 9, 10, and 11.

NOTE: The charts as reproduced herein, due to their small scale, are not to be used in connection with material submitted to the F. C. C.




FIGURE 1.




FIGURE 1a.




FIGURE 2.



ESTIMATED EFFECTIVE
GROUND CONDUCTIVITY
IN THE UNITED STATES
February 1954
NUMBERS ON MAP REPRESENT ESTIMATED EFFECTIVE GROUND CONDUCTIVITY IN MILLIMHOS PER METER
CONDUCTIVITY OF SEAWATER IS NOT SHOWN ON MAP BUT IS ASSUMED TO BE 5000 MILLIMHOS PER METER
SCALE OF MILES

FIGURE R3.




FIGURE 5.




FIGURE 6.




FIGURE 6a.




FIGURE 7.




FIGURE 8.




FIGURE 9.

PERMISSIBLE DAYTIME RADIATION
FOR CLASS II STATIONS

1000 KC




FIGURE 10.

PERMISSIBLE DAYTIME RADIATION
FOR CLASS II STATIONS

1600 KC




FIGURE 11.

Subpart B—FM Broadcast Stations

CLASSIFICATION OF FM BROADCAST STATIONS AND ALLOCATION OF FREQUENCIES

§ 73.201 Numerical designation of FM broadcast channels.

For convenience, the frequencies available for FM broadcasting (including those assigned to noncommercial educational broadcasting) are given numerical designations which are shown in the table below:

Frequency (Mc/s)	Channel No.	Frequency (Mc/s)	Channel No.
88.1	201	98.1	251
88.3	202	98.3	252
88.5	203	98.5	253
88.7	204	98.7	254
88.9	205	98.9	255
89.1	206	99.1	256
89.3	207	99.3	257
89.5	208	99.5	258
89.7	209	99.7	259
89.9	210	99.9	260
90.1	211	100.1	261
90.3	212	100.3	262
90.5	213	100.5	263
90.7	214	100.7	264
90.9	215	100.9	265
91.1	216	101.1	266
91.3	217	101.3	267
91.5	218	101.5	268
91.7	219	101.7	269
91.9	220	101.9	270
92.1	221	102.1	271
92.3	222	102.3	272
92.5	223	102.5	273
92.7	224	102.7	274
92.9	225	102.9	275
93.1	226	103.1	276
93.3	227	103.3	277
93.5	228	103.5	278
93.7	229	103.7	279
93.9	230	103.9	280
94.1	231	104.1	281
94.3	232	104.3	282
94.5	233	104.5	283
94.7	234	104.7	284
94.9	235	104.9	285
95.1	236	105.1	286
95.3	237	105.3	287
95.5	238	105.5	288
95.7	239	105.7	289
95.9	240	105.9	290
96.1	241	106.1	291
96.3	242	106.3	292
96.5	243	106.5	293
96.7	244	106.7	294
96.9	245	106.9	295
97.1	246	107.1	296
97.3	247	107.3	297
97.5	248	107.5	298
97.7	249	107.7	299
97.9	250	107.9	300

§ 73.202 Table of Assignments.

(a) *General.* The following table of assignments contains the channels (other than noncommercial educational channels) assigned to the listed communities in the 48 conterminous United States. Channels designated with an "A" are for Class A FM stations. All other listed channels are for class B stations in zones I and I–A and for class C stations in zone II.

(b) *Table of FM Assignments.*

ALABAMA

	Channel No.
Abbeville	249A
Albertville	286
Alexander City	291
Andalusia	251, 293
Anniston	263
Athens	282
Auburn	249A
Bay Minette	288A
Birmingham	229, 233, 243, 258, 284, 295, 299
Brewton	296A
Butler	232A
Carrollton	292A
Clanton	249A, 265A
Cullman	266
Decatur	245, 271
Demopolis	252A
Dothan	238, 259
Enterprise	228A
Eufaula	224A
Evergreen	280A
Fairhope	221A
Fayette	225
Florence	297
Gadsden	279
Huntsville	236, 256
Jackson	285A
Jasper	273
Mobile	225, 235, 241, 248, 260
Monroeville	257A
Montgomery	222, 255, 270, 277
Muscle Shoals	288A
Opelika	265A
Ozark	285A
Phenix City	261A
Prichard	276A
Roanoke	237A
Scottsboro	252A
Selma	261A
Sheffield	292A
Sylacauga	252A
Thomasville	237A
Troy	245, 289
Tuscaloosa	239, 288A
Tuscumbia	262

ARIZONA

Apache Junction	296A
Bisbee	221A
Casa Grande	288A
Clifton	237A
Cottonwood	240A
Douglas	237A
Flagstaff	225, 230
Glendale	222
Globe	262
Holbrook	221A
Kingman	224A
Mesa	227, 284
Miami	276A
Nogales	252A
Page	228A
Phoenix	233, 238, 245, 254, 268, 273
Prescott	252A
Safford	231, 256
Show Low	228A
Sierra Vista	261A
Sun City	278, 292A
Tempe	250
Tolleson	264
Tucson	221A, 225, 229, 235, 241, 258
Wickenburg	261A
Willcox	244A
Winslow	236, 247
Yuma	226, 236

ARKANSAS

Arkadelphia	265A
Benton	296A
Berryville	237A
Blytheville	241
Camden	246
Clarksville	224A
Conway	262, 286
Corning	285A
Dardanelle	272A
DeQueen	224A
El Dorado	257A, 276A
Fayetteville	221A, 280A
Forrest City	228A
Fort Smith	229, 256, 260, 265A
Helena	298
Harrison	275
Hope	285A
Hot Springs	244A, 248, 292A
Jonesboro	270, 300
Little Rock	226, 231, 239, 253, 279
Magnolia	224A
Malvern	269A
Mammoth Spring	236
McGehee	272A
Mena	240A
Monticello	228A
Mountain Home	252A
Nashville	288A
Newport	288A
Osceola	251
Paragould	224A
Paris	237A
Pine Bluff	222, 235
Pocahontas	280A
Rogers	232A
Searcy	257A
Siloam Springs	289
Texarkana	296A
Walnut Ridge	292A

CALIFORNIA

Alameda	224A
Alturas	233
Anaheim	240A
Anderson	232A
Apple Valley	240A
Arcata	228A
Arroyo Grande	237A
Auburn	266
Bakersfield	231, 243, 268
Banning	269A
Barstow	232A
Berkeley	231, 275
Bishop	264
Blythe	262
Brawley	233, 241
Calexico	249A
Carmel	269A
Carlsbad	240A
Chico	229, 236
Coachella	229
Crescent City	232A
Delano	253, 287
Dinuba	255, 262
El Cajon	227
El Centro	253
Escondido	221A
Eureka	222, 242
Fort Bragg	224A, 237A
Fowler	280A
Fremont	285A
Fresno	229, 233, 250, 270, 274
Garden Grove	232A
Glendale	270A
Hanford	266, 279
Hayward	269A
Hemet	288A
Indio	252A
Inglewood	280A
King City	221A
Lancaster	300
Lemoore	285A
Lodi	237A, 249A
Lompoc	224A
Long Beach	250, 272A, 288A
Los Altos	249A
Los Angeles	222, 226, 230, 234, 238, 242, 246, 254, 258, 262, 266, 274, 278, 282, 286, 290, 298
Los Banos	240A
Los Gatos	237A
Madera	221A
Marysville	260
Merced	268
Modesto	277, 281
Mojave	249A
Monterey	245
Mt. Shasta	237A
Needles	250
Newport Beach	276A
Oceanside	271
Ontario	228A
Oroville	249A
Oxnard	284
Pacific Grove	285A
Palm Springs	284
Paradise	244A
Pasadena	294
Paso Robles	232A

California—Continued

	Channel No.
Porterville	240A
Red Bluff	240A, 272A
Redding	225, 282
Redlands	244A
Redondo Beach	228A
Ridgecrest	224A
Riverside	224A, 248, 256
Roseville	228A
Sacramento	223, 241, 245, 253, 263, 286, 293, 300
Salinas	264, 273, 280A
San Bernardino	236, 260
San Diego	231, 235, 243, 247, 251, 264, 268, 275, 279, 287, 293
San Fernando	232A, 292A
San Francisco	227, 235, 239, 243, 247, 251, 255, 259, 267 271, 279, 283, 287, 291, 295.
San Jose	222, 253, 262, 293
San Luis Obispo	227, 241
San Mateo	299
San Rafael	265A
Santa Ana	244A, 292A
Santa Barbara	229, 248, 260, 277
Santa Clara	289
Santa Cruz	256
Santa Maria	256, 273
Santa Monica	276A
Santa Rosa	261A
Seaside	296A
Sierra Madre	296A
Sonora	224A
Stockton	257A, 297
Susanville	224A
Taft	280A
Tahoe Valley	276A
Thousand Oaks	224A
Tracy	265A
Truckee	269A
Tulare	235, 294
Turlock	226
Twenty Nine Palms	237A
Ukiah	228A
Ventura	236, 264
Victorville	252A
Visalia	225
Walnut Creek	221A
Wasco	249A
Weed	257A
West Covina	252A
Willows	224A
Woodland	273
Yreka	249A
Yuba City	280A

Colorado

Alamosa	228A
Aspen	249A
Boulder	247
Canon City	280A
Colorado Springs	225, 232A, 243
Cortez	250, 254
Craig	229, 236
Delta	237A
Denver	238, 253, 258, 262, 266, 278, 286, 290, 294
Durango	263, 267
Fort Collins	227, 234
Fort Morgan	232A
Glenwood Springs	224A
Grand Junction	222, 226
Greeley	222
Gunnison	252A, 272A
La Junta	221A
Lamar	227, 245
Leadville	228A
Littleton	299
Longmont	282
Loveland	272A
Manitou Springs	274
Monte Vista	244A
Montrose	231, 241
Pueblo	236, 250, 255, 260
Rocky Ford	240A
Salida	221A
Sterling	244A, 288A
Trinidad	224A
Walsenburg	272A

Connecticut

	Channel No.
Bridgeport	260
Brookfield	236
Danbury	252A
Darien	240A
Hamden	267
Hartford	229, 243, 275, 290, 295
Manchester	300
Meridan	239
Middletown	285A
New Britain	263
New Haven	232A, 256
Norwich	249A
Stamford	244A
Waterbury	223, 281
Westport	300

Delaware

Dover	234
Georgetown	228A
Milford	240A
Seaford	252A
Wilmington	229, 258

District of Columbia

Washington	230, 242, 246, 254, 258, 262, 266, 278, 297

Florida

Arcadia	252A
Atlantic Beach	285A
Belle Glade	228A
Blountstown	272A
Boca Raton	260
Bradenton	277
Clearwater	239
Clewiston	280A
Cocoa	257A
Cocoa Beach	266, 282
Coral Gables	286
Daytona Beach	233, 270
Delray Beach	274
Defuniak Springs	276A
Eau Gallie	296A
Ft. Lauderdale	264, 278, 290, 294
Ft. Meyers	245
Ft. Pierce	238, 254
Ft. Walton Beach	257A
Gainesville	279
Green Cove Springs	296A
Homestead	252A
Jacksonville	223, 236, 241, 245, 256
Key West	223, 262
Lake City	232A
Lakeland	231
Leesburg	293
Live Oak	221A
Madison	290
Marathon	232A
Marianna	265A
Melbourne	272A
Miami	226, 242, 247, 256, 268, 282
Miami Beach	230, 235
Milton	272A
Mount Dora	299
Naples	233, 270
Ocala	229, 253
Okeechobee	276A
Orlando	222, 243, 262, 286
Palatka	260
Palm Beach	250
Panama City	223, 300
Pensacola	231, 264, 268
Perry	240A
Punta Gorda	224A
Quincy	269A
St. Augustine	249A
St. Petersburg	258, 268, 297
Sanford	276A
Sarasota	273, 288A, 292A
Sebring	288A
Starke	288A
Stuart	224A
Tallahassee	235, 255
Tampa	227, 235, 264, 284
Venice	221A
Vero Beach	292A
Ward Ridge	228A
West Palm Beach	300
Windermere	237A
Winter Haven	248

Georgia

	Channel No.
Albany	242, 283
Americus	232A
Athens	238, 284
Atlanta	225, 235, 241, 253, 259, 277
Augusta	275, 282, 289
Bainbridge	247
Blackshear	228A
Brunswick	264, 268
Camilla	288A
Carrollton	272A
Cartersville	288A
Columbus	275, 285A, 297
Claxton	296A
Cordele	252A
Cornelia	257A
Covington	221A
Dalton	252A
Dawson	221A
Douglas	258, 293
Dublin	224A
Eastman	244A
Gainesville	246, 294
Griffin	249A
Hawkinsville	269A
Jesup	288A
La Grange	281
Louisville	240A
Macon	256, 287, 300
Manchester	227
Marietta	268
Milledgeville	272A
Metter	285A
Moultrie	230
Newnan	244A
Ocilla	237A
Perry	265A
Rome	249A
Sandersville	232A
Savannah	226, 231, 238, 243, 247, 271
Smyrna	231
Statesboro	261A
Swainsboro	252A
Thomasville	296A
Tifton	262
Toccoa	291
Valdosta	225, 266
Vidalia	249A
Washington	261A
Waycross	273, 277
Waynesboro	228A

Idaho

Alameda	285A
Blackfoot	249A
Boise	222, 250
Burley	252A
Caldwell	231, 276A
Coeur d'Alene	276A
Grangeville	224A
Idaho Falls	223, 241
Jerome	224A
Lewiston	231, 244A
Moscow	280A
Mountain Home	257A
Nampa	235, 245
Orofino	237A
Payette	261A
Pocatello	229, 235
Preston	244A
Rexburg	232A
Rupert	221A
Salmon	224A
Sandpoint	237A
Soda Springs	228A
Sun Valley	228A
Twin Falls	239, 243
Wallace	258, 264
Weiser	265A

Illinois

Alton	262
Anna	224A
Arlington Heights	224A
Aurora	240A, 300
Beardstown	232A
Bloomington	268
Canton	252A
Carbondale	269A
Carmi	247
Carthage	221A

ILLINOIS—Continued

	Channel No.
Centralia	237A
Champaign	233, 248
Charleston	221A
Chicago	226, 230, 234, 238, 242, 246, 250, 254, 258, 262, 266, 270, 278, 282, 298
Clinton	240A
Danville	271, 276A
Decatur	275
DeKalb	223
Dixon	269A
E. St. Louis	266
Effingham	239
Elgin	232A, 280A
Elmwood Park	290
Evanston	286
Fairfield	285A
Freeport	253
Galesburg	272A
Glen Ellyn	296A
Granite City	285A
Harrisburg	260
Havana	257A
Highland Park	276A
Jacksonville	263
Joliet	228A, 244A
Kankakee	260, 272A
Lansing	292A
LaSalle	257A
Lincoln	261A
Litchfield	291
Loves Park	244A
Macomb	261A
Marion	232A
Matoon	245
Mendota	265A
Moline	285A
Monmouth	249A
Morris	284
Mount Carmel	235
Mount Vernon	231
Murphysboro	285A
Normal	244A
Oak Park	274
Olney	225
Ottawa	252A
Paris	252A
Pekin	237A
Peoria	223, 227, 295
Peru	261A
Pittsfield	228A
Quincy	258, 286
Rantoul	237A
Robinson	269A
Rockford	248
Rock Island	255
Salem	249A
Skokie	252A
South Beloit	276A
Springfield	270, 279, 283
Sterling	232A
Streator	249A
Taylorville	224A
Urbana	280A
Watseka	231
Waukegan	272A
West Frankfort	296A
Woodstock	288A

INDIANA

Anderson	250
Bedford	237A
Bloomington	222, 279
Bluffton	261A
Brazil	232A
Columbia City	292A
Columbus	268
Connersville	262
Crawfordsville	292A
Elkhart	264, 284
Elwood	269A
Evansville	281, 287
Fort Wayne	236, 247, 269A, 288A
Frankfort	259
Franklin	240A
Goshen	232A
Greenfield	258
Greensburg	297
Hammond	222
Huntington	276A

INDIANA—Continued

	Channel No.
Indianapolis	226, 234, 238, 277, 283, 289, 300
Jasper	284
Kendallville	227
Kokomo	228A, 263
Lafayette	224A, 244A, 287
Laporte	244A
Linton	228A
Logansport	237A, 272A
Madison	244A
Marion	285A, 295
Michigan City	240A
Muncie	281
New Castle	273
North Vernon	291
Peru	252A
Plainfield	252A
Princeton	251
Richmond	241, 267
Salem	255
Seymour	229
Shelbyville	246
South Bend	225, 252A, 268, 280A
Terre Haute	260, 264, 274, 298
Valparaiso	288A
Vincennes	244A
Wabash	240A
Warsaw	297
Washington	293

IOWA

Algona	228A
Ames	281
Boone	252A, 257A
Burlington	297
Carroll	286
Cedar Rapids	238, 251, 275, 283
Centerville	232A
Charles City	224A
Cherokee	232A
Clarion	245
Clinton	241
Davenport	279, 293
Decorah	280A
Denison	296A
Des Moines	227, 235, 247, 262, 273
Dubuque	257A, 261A, 287
Estherville	240A
Fort Dodge	232A
Fort Madison	269A
Iowa City	230, 264
Keokuk	245
Knoxville	221A
Le Mars	258
Marshalltown	296A
Mason City	252A
Muscatine	225, 259
Newton	240A
Oelwin	299
Oskaloosa	292A
Ottumwa	257A, 285A
Perry	292A
Sioux City	238, 250, 277
Spencer	221A
Storm Lake	268
Waterloo	266, 270, 289
Webster City	249A

KANSAS

Arkansas City	293
Chanute	252A
Coffeyville	232A
Colby	228A
Concordia	237A
Dodge City	230, 238
Eldorado	237A
Emporia	285A
Fort Scott	280A
Garden City	247
Goodland	273
Great Bend	235
Hays	224A, 277
Hutchinson	256, 271
Independence	269A
Iola	257A
Junction City	252A
Kansas City	231, 251
Lawrence	290
Leavenworth	255
Liberal	257A, 288A

KANSAS—Continued

	Channel No.
Manhattan	269A
Marysville	276A
McPherson	244A
Newton	222
Ottawa	239
Parsons	228A
Phillipsburg	221A
Pittsburg	245
Pratt	226
Russell	240A
Salina	229, 260
Scott City	232A
Topeka	247, 262, 295, 299
Wichita	250, 262, 267, 275, 279, 297
Winfield	288A

KENTUCKY

Albany	292A
Ashland	229, 272A
Benton	272A
Bowling Green	244A
Campbellsville	280A
Central City	270
Corbin	257A
Cynthiana	292A
Elizabethtown	228A
Erlanger	265A
Fort Knox	288A
Frankfort	285A
Fulton	285A
Glasgow	236
Greenville	266
Hazard	266
Henderson	258
Hopkinsville	254, 262
Lexington	225, 233, 251
London	296A
Louisville	248, 259, 272A, 276A, 280A, 295
Madisonville	230, 292A
Manchester	276A
Mayfield	234
Maysville	240A
Middlesboro	261A
Morehead	221A
Morganfield	237A
Munfordville	272A
Neon	285A
Owensboro	223, 241
Paducah	227, 245
Paintsville	255
Paris	244A
Pikeville	221A
Prestonsburg	238, 288A
Princeton	249A
Richmond	269A
Russellville	221A
Somerset	244A
Vanceburg	285A
Whitesburg	280A
Winchester	261A

LOUISIANA

Abbeville	285A
Alexandria	245, 262
Bastrop	240A
Baton Rouge	251, 264, 268, 273, 277
Bogalusa	300
Crowley	275
DeRidder	269A
Eunice	288A
Ferriday	228A
Franklin	237A
Hammond	296A
Houma	296A
Jennings	224A
Jonesboro	285A
Lafayette	233, 260
Lake Charles	241, 258, 279
Leesville	288A
Mansfield	224A
Minden	237A
Monroe	270, 281, 291
Morgan City	244A
Natchitoches	249A
New Iberia	256
New Orleans	222, 227, 239, 246, 253, 258, 266, 270, 287
Oak Grove	244A
Opelousas	296A
Ruston	296A

LOUISIANA—Continued

	Channel No.
Shreveport	229, 233, 243, 266
Sulphur	265A
Thibodaux	292A
Ville Platte	228A
West Monroe	252A
Winnfield	221A

MAINE

Auburn	261A
Augusta	267, 272A
Bangor	225, 246
Bath	237A
Biddeford	232A
Brunswick	255
Calais	224A
Caribou	249A
Ellsworth	232A
Farmington	257A
Houlton	261A
Lewiston	230, 298
Machias	237A
Madawaska	272A
Portland	243, 250, 270
Presque Isle	237A, 241, 245
Rockland	228A
Rumford	292A
Saco	292A
Sanford	276A
Skowhegan	244A
South Paris	288A
Waterville	252A
Westbrook	285A

MARYLAND

Annapolis	256, 300
Baltimore	222, 226, 236, 250, 270, 274, 282, 293
Bethesda	234, 272A
Cambridge	292A
Catonsville	289
Cumberland	275, 291
Easton	244A
Frederick	260
Frostburg	244A
Glen Burnie	240A
Hagerstown	284, 295
Halfway	228A
Havre de Grace	279
Leonardtown	249A
Oakland	238
Oakland (western Md.)	285A
Ocean City	284
Pocomoke City	224A
Salisbury	232A
Waldorf	281
Westminster	264

MASSACHUSETTS

Boston	233, 245, 253, 264, 277, 281, 294
Brockton	249A
Brookline	225
Cambridge	237A
Fitchburg	283
Framingham	289
Gloucester	285A
Greenfield	252A
Haverhill	223
Lawrence	229
Lowell	258
Lynn	269A
Medford	300
New Bedford	247, 251
North Adams	261A
North Attleboro	227
Northampton	257A
Pittsfield	288A
Plymouth	256
Springfield	226, 234, 271
Waltham	273
West Yarmouth	235
Worcester	241, 297

MICHIGAN

Adrian	280A
Albion	285A
Alma	285A
Alpena	228A, 299
Bad Axe	221A
Battle Creek	277
Bay City	241, 273
Benton Harbor	260

MICHIGAN—Continued

	Channel No.
Big Rapids	265A
Birmingham	234
Cadillac	225, 278
Charlotte	224A
Cheboygan	232A, 286
Coldwater	253
Dearborn	262
Detroit	226, 238, 242, 246, 250, 254, 258, 266, 270, 278, 282, 286, 290, 294, 298
Dowagiac	249A
East Lansing	235, 256
Escanaba	227, 246
Flint	236, 288A, 300
Fremont	257A
Gaylord	237A, 294
Grand Haven	221A
Grand Rapids	229, 239, 245, 250, 267, 275, 281, 289
Greenville	297
Hancock	228A
Hastings	261A
Hillsdale	221A
Holland	233, 241
Hougton	249A
Hougton Lake	253
Ishpeming	261A, 296A
Iron Mountain	280A
Iron River	244A
Ironwood	226, 259
Jackson	231, 291, 296A
Kalamazoo	271, 293
Lansing	248, 264, 269A
Lincoln Park	222
Ludington	261A
Manistee	249A
Marquette	222, 239
Menominee	292A
Midland	259
Mt. Clemens	274
Mt. Pleasant	233
Munising	252A
Muskegon	295
Niles	237A
Owasso	280A
Petoskey	244A, 255
Port Huron	296A
Rogers City	249A
Saginaw	251, 292A, 296A
Saline	275
St. Helen	288A
St. Johns	221A
St. Joseph	296A
Sault Ste. Marie	224A
Sturgis	257A
Tawas City	269A
Traverse City	221A, 270
Whitehall	237A

MINNESOTA

Aitkin	232A
Albert Lea	237A
Alexandria	224A
Austin	260
Bemidji	252A, 269A
Benson	228A
Blue Earth	265A
Brainerd	239
Breckenridge	269A
Cambridge	300
Cloquet	228A
Crookston	241, 246
Detroit Lakes	237A
Duluth	235, 248, 255, 273, 277, 286
East Grand Forks	280A
Ely	221A
Eveleth	261A
Fairmont	293
Faribault	228A
Fergus Falls	243, 256
Golden Valley	223
Grand Rapids	244A
Hibbing	292A
International Falls	232A
Little Falls	221A
Mankato	256, 278
Marshall	261A
Minneapolis	233, 241, 246, 253, 258, 262, 267, 271, 275
Montevideo	287

MINNESOTA—Continued

	Channel No.
Moorhead	254, 260
Morris	232A
New Ulm	298
Ortonville	292A
Owatonna	285A
Pipestone	252A
Princeton	228A
Red Wing	288A
Redwood Falls	249A
Rochester	244A, 248, 295
St. Cloud	284, 296A
St. Louis Park	281
St. Paul	237A
Thief River Falls	257A
Virginia	296A
Wadena	264, 290
Willmar	273
Windom	285A
Winona	237A
Worthington	236

MISSISSIPPI

Aberdeen	221A
Amory	237A
Biloxi	292A
Booneville	269A
Brookhaven	224A
Canton	269A
Centerville	285A
Clarksdale	237A, 276A
Cleveland	252A, 280A
Columbia	244A
Columbus	276A
Corinth	228A
Forest	228A
Greenville	250, 264
Greenwood	256
Grenada	261A
Gulfport	272A, 296A
Hattiesburg	279, 283
Hazelhurst	296A
Houston	228A
Indianola	288A
Iuka	285A
Jackson	234, 238, 242, 259, 275
Kosciusko	286
Laurel	262
Leland	232A
Lexington	292A
Louisville	296A
Macon	280A
Magee	252A
McComb	231, 289
Meridian	246, 267
Natchez	237A
New Albany	278, 292A
Pascagoula	285A
Philadelphia	272A
Pontotoc	244A
Senatobia	232A
Starkville	249A
Tupelo	253
Vicksburg	248, 254
Waynesboro	288A
West Point	265A
Winona	240A
Yazoo City	221A

MISSOURI

Aurora	261A
Boonville	257A
Branson	292A
Brookfield	249A
Cape Girardeau	264, 275
Carrollton	266
Carthage	285A
Chillicothe	280A
Clayton	256
Clinton	237A
Columbia	244A, 288A
Crestwood	234
Eldorado Springs	296A
Fulton	224A
Hannibal	236, 254
Houston	257A
Jefferson City	261A
Joplin	223, 273
Kansas City	227, 235, 243, 259, 271, 277, 282
Kennett	255

MISSOURI—Continued

	Channel No.
Kirksville	228A
Lebanon	279
Marshall	284
Maryville	237A
Mexico	296A
Moberly	272A
Monett	240A
Mountain Grove	224A
Osage Beach	228A
Poplar Bluff	233, 297
Portageville	292A
Potosi	261A
Rolla	232A
Ste. Genevieve	289
St. Joseph	286
St. Louis	222, 229, 243, 251, 273, 277, 293, 299
Salem	240A
Sedalia	221A
Sikeston	249A
Springfield	234, 247, 254, 268
Thayer	244A
Trenton	224A
Union	269A
Waynesville	249A
West Plains	230, 272A
Willow Springs	265A

MONTANA

Anaconda	249A
Belgrade	244A
Billings	227, 246
Bozeman	229
Butte	231, 238
Dillon	252A
Glasgow	228A
Glendive	232A
Great Falls	225, 233, 255, 292A
Hamilton	240A
Hardin	237A
Havre	223, 236
Helena	221A, 276A
Kalispell	246, 253
Lewistown	240A
Libby	269A
Livingston	249A
Miles City	224A
Missoula	227, 235
Plentywood	261A
Red Lodge	257A
Shelby	242, 250
Sidney	226, 236
Wolf Point	224A

NEBRASKA

Alliance	221A
Beatrice	225
Broken Bow	252A
Chadron	228A, 234
Columbus	245
Fairbury	257A
Fremont	288A
Grand Island	233, 239
Hastings	228A
Holdrege	249A
Kearney	255, 272A
Kimbell	261A
Lexington	226
Lincoln	237A, 270, 274, 292A, 297
McCook	240A, 276A
Nebraska City	249A
Norfolk	266
North Platte	235, 246
Ogallala	228A
Omaha	222, 231, 241, 253, 260, 264, 279, 283
O'Neill	224A
Scottsbluff	225, 231
Sidney	237A
Superior	265A
Terrytown	265A
Valentine	241
York	285A

NEVADA

Carson City	234, 247
Elko	228A, 237A
Ely	224A
Fallon	257A
Henderson	231, 238
Las Vegas	222, 226, 246, 253, 270
Reno	222, 226, 230, 238

NEVADA—Continued

	Channel No.
Sparks	252A
Tonapah	224A
Winnemucca	224A

NEW HAMPSHIRE

Berlin	241, 279
Claremont	291
Conway	228A
Dover	248
Hanover	257A
Keene	279
Laconia	252A
Manchester	239, 266
Mt. Washington	235
Nashua	292A
Newport	272A
Portsmouth	262, 296A
Rochester	280A

NEW JERSEY

Asbury Park	232A
Atlantic City	236, 245, 279
Bridgeton	299
Camden	295
Dover	288A
Eatontown	288A
Franklin	272A
Long Branch	296A
Millville	247
Newark	234, 262, 290
New Brunswick	252A
Newton	279
Paterson	226
Pleasantville	285A
Princeton	277
Red Bank	292A
Toms River	224A
Trenton	233, 248, 268
Vineland	221A
Wildwood	264
Zarephath	256

NEW MEXICO

Alamagordo	232A, 288A
Albuquerque	222, 227, 231, 242, 258, 262
Artesia	225
Aztec	235
Belen	249A
Carlsbad	221A
Clayton	228A
Clovis	256, 260
Deming	232A
Espanola	272A
Farmington	225, 245
Gallup	229, 233
Grants	237A
Hobbs	231, 239
Las Cruces	237A
Las Vegas	265A
Lordsburg	249A
Los Alamos	253
Lovington	269A
Portales	237A
Raton	232A
Roswell	235, 246
Ruidoso	228A
Sante Fe	238, 247
Santa Rosa	228A
Silver City	224A
Socorro	224A
Taos	257A
Truth or Consequences	244A
Tucumcari	224A

NEW YORK

Albany	238, 265A, 276A, 280A, 293
Amsterdam	228A, 285A
Auburn	295
Babylon	232A, 272A
Baldwinsville	221A
Bath	252A
Binghamton	251, 256
Buffalo	225, 233, 241, 245, 258, 273, 277, 281, 293
Cherry Valley (Otsego Co.)	270
Corning	291
Cortland	260
Depew	229
De Ruyter	286
Dundee	240A

NEW YORK—Continued

	Channel No.
Elmira	232A
Endicott	265A
Fulton	284
Garden City	224A
Geneva	272A
Hempstead	252A
Herkimer	224A
Hornell	287
Hudson	244A
Ithaca	228A, 247, 279
Jamestown	227
Kingston	232A, 249A
Lake Success	278
Liberty	240A
Little Falls	288A
Middletown	224A
Mt. Kisco	292A, 296A
Newburgh	276A
New Rochelle	228A
New York	222, 230, 238, 242, 246, 250, 254, 258, 266, 270, 274, 282, 286, 294, 298
Niagara Falls	253
Norwich	230
Ogdensburg	244A
Olean	239
Oneida	292A
Oneonta	237A, 276A
Oswego	288A
Owego	269A
Patchogue	248, 291
Peekskill	264
Plattsburg	260
Potsdam	256
Poughkeepsie	268, 284
Riverhead	280A
Rochester	223, 243, 250, 255, 263, 267, 280A
Rome	240A
Sag Harbor	221A
Salamanca	261A
Saranac Lake	237A
Saratoga Springs	272A
Schenectady	258
South Bristol Twsp. (Ontario Co.)	236
Syracuse	226, 233, 265A, 275, 300
Troy	222
Utica	235, 245, 282, 297
Walton	221A
Watertown	224A, 248
Weathersfield Twsp. (Wyoming Co.)	299
Wellsville	257A
White Plains	280A

NORTH CAROLINA

Ahoskie	249A
Albermarle	265A
Asheboro	222
Asheville	260
Beaufort	221A
Black Mountain	295
Burlington	230, 266
Charlotte	236, 279, 284, 300
Clinton	296A
Concord	250
Durham	286, 296A
Edenton	261A
Elizabeth City	229, 295
Elkin	265A
Fairmont	292A
Fayetteville	251
Forest City	227, 287
Gastonia	270
Goldsboro	245, 274
Greensboro	246, 254
Greenville	299
Grifton	253
Havelock	285A
Henderson	223
Hendersonville	273
Hickory	239, 275
High Point	238, 258, 262
Jacksonville	288A
Kannapolis	259
Kinston	236
Laurinburg	243
Leaksville	233
Lexington	231
Lumberton	239, 272A
Morehead City	240A
Morganton	221A

NORTH CAROLINA—Continued

	Channel No.
New Bern	232A
N. Wilkesboro	247
Plymouth	257A
Raleigh	234, 241, 268
Reidsville	271
Roanoke Rapids	272A
Rocky Mount	221A, 264
Roxboro	244A
Salisbury	293
Sanford	288A
Shelby	241
Statesville	245, 289
Tabor City	285A
Tarboro	282
Thomasville	252A
Washington	227, 270
Whiteville	256
Williamston	279
Wilmington	247, 260
Wilson	291
Winston-Salem	226, 281, 298

NORTH DAKOTA

Bismarck	225, 233
Carrington	249A
Devils Lake	244A
Dickinson	221A
Fargo	229, 250
Grafton	265A
Grand Forks	225, 234
Hettinger	228A
Jamestown	227, 238
Mandan	285A
Minot	229, 246
Oakes	252A
Rugby	237A
Valley City	265A
Williston	241, 253

OHIO

Akron	243, 248
Alliance	223
Ashland	267
Ashtabula	246
Athens	252A, 288A
Barberton	235
Bellaire	263
Bowling Green	228A
Bryan	265A
Bucyrus	224A
Cambridge	244A
Canton	231, 251, 295
Celina	232A
Chillicothe	227, 232A
Cincinnati	223, 227, 231, 253, 270, 274, 282, 286
Circleville	292A
Cleveland	226, 238, 253, 258, 264, 271, 277, 281, 289, 293, 300
Cleveland Heights	222
Columbus	222, 234, 242, 246, 250, 259, 285A
Conneaut	285A
Coshocton	257A
Dayton	256, 284, 299
Defiance	240A
Dover-New Philadelphia	269A
East Liverpool	282
Eaton	225
Elyria	297
Findlay	263
Fostoria	244A
Fremont	256
Gallipolis	268
Greenville	293
Hamilton	235, 243, 278
Hillsboro	294
Ironton	296A
Jackson	249A
Kent	261A
Kenton	252A
Kettering	260
Lancaster	238
Lima	249A, 271
Lorain	285A
Mansfield	287, 291
Marietta	232A
Marion	295
Miamisburg	229
Middleport	285A
Middletown	290

OHIO—Continued

	Channel No.
Mt. Vernon	229
Newark	262
Norwalk	237A
Oxford	249A
Piqua	239
Port Clinton	233
Portsmouth	257A, 281
Salem	286
Sandusky	274
Sidney	288A
Springfield	264, 275
Steubenville	278
Tiffin	279
Toledo	223, 252A, 260, 268, 272A, 284, 288A
Urbana	269A
Van Wert	255
Wapakoneta	221A
Wash. Ct. House	288A
Waverly	265A
Wellston	244A
Wooster	283
Xenia	280A
Youngstown	227, 255, 266
Zanesville	273

OKLAHOMA

Ada	227
Altus	228A
Alva	259, 284
Ardmore	221A
Bartlesville	261A
Chickasha	285A
Clinton	237A
Duncan	293
Durant	296A
Edmond	249A
Elk City	232A
Enid	245
Frederick	240A
Guymon	224A
Henryetta	272A
Hobart	257A
Hugo	237A
Idabel	244A
Lawton	251, 268
Madill	285A
McAlester	267
Miami	265A
Muskogee	295
Oklahoma City	223, 234, 241, 255, 263, 270, 274, 281, 299
Okmulgee	285A
Ponca City	257A, 265A
Poteau	252A
Seminole	288A
Stillwater	230
Tahlequah	269A
Tulsa	225, 238, 243, 248, 253, 277
Woodward	228A

OREGON

Albany	300
Ashland	269A
Astoria	289
Baker	237A
Bend	231, 264
Brookings	237A
Burns	224A
Coos Bay	252A, 288A
Coquille	272A
Corvallis	268, 291
Cottage Grove	237A
Enterprise	244A
Eugene	233, 241, 250, 256
Gold Beach	224A
Grant's Pass	245, 260
Hermiston	257A
Hood River	288A
Klamath Falls	223, 253
La Grande	252A
Lakeview	228A
Lebanon	279
Medford	229, 237A
Newport	274
North Bend	265A
Oceanlake	244A
Ontario	226, 241
Oregon City	294
Pendleton	267, 278

OREGON—Continued

	Channel No.
Portland	222, 229, 238, 246, 253, 258, 262, 266, 270, 277
Prineville	237A
Redmond	224A
Roseburg	276A
Salem	286
Springfield	226
The Dalles	283
Tillamook	281
Toledo	296A

PENNSYLVANIA

Allentown	264, 281
Altoona	251, 261A
Beaver Falls	294
Bethlehem	236
Bloomsburg	293
Boyertown	298
Braddock	245
Bradford	280A
Butler	249A
Carbondale	232A
Carlisle	272A
Chambersburg	236
Clearfield	228A
Columbia	224A
Connellsville	280A
Coudersport	244A
Dubois	271, 297
Easton	241, 260
Ebensburg	280A
Elizabethtown	294
Emporium	224A
Ephrata	286
Erie	260, 279, 288A, 292A
Franklin	257A
Gettysburg	299
Greensburg	296A
Greenville	296A
Grove City	236
Harrisburg	235, 247, 257A, 281
Hazelton	250
Huntingdon	244A
Indiana	276A
Jenkintown	280A
Johnstown	221A, 238
Kane	292A
Lancaster	233, 245, 267
Lebanon	261A
Lewistown	240A
Lock Haven	221A
Martinsburg	224A
Meadville	262
Media	262
Milton	265A
Montrose	243
Naticoke	221A
New Kensington-Tarentum	264
Oil City	253
Palmyra	221A
Philadelphia	223, 227, 231, 239, 243, 251, 255, 266, 271, 275, 283, 287, 291
Philipsburg	257A
Pittsburgh	225, 229, 233, 241, 259, 268, 273, 284, 290, 300
Pottsville	270
Punxsutawney	288A
Reading	273
Red Lion	241
St. Mary's	232A
Sayre	272A
Scranton	267, 285A, 296A
Shamokin	237A
Sharon	275, 280A
Shenandoah	288A
Shippensburg	232A
Somerset	249A
State College	276A
Stroudsburg	228A
Sunbury	231
Towanda	237A
Tyrone	266
Uniontown	252A
Warren	222
Washington	237A
Waynesboro	268
Wellsboro	249A
Wilkes-Barre	225, 253
Williamsport	274, 286
York	253, 277, 289

RHODE ISLAND

	Channel No.
Providence	222, 231, 238, 268, 286
Westerly	279
Woonsocket	292A

SOUTH CAROLINA

Aiken	257A
Anderson	266, 297
Bamberg	224A
Barnwell	269A
Batesburg	221A
Beaufort	254
Charleston	229, 236, 245
Columbia	250, 284
Conway	281
Dillon	225
Florence	276A, 288A
Georgetown	249A, 292A
Greenville	223, 229, 233
Greenwood	244A
Lancaster	296A
Laurens	263
Manning	261A
Marion	232A
Mullins	265A
Myrtle Beach	221A
North Charleston	273
Orangeburg	294
Seneca	251
Spartanburg	255
Summerville	240A
Sumter	267
Walterboro	265A

SOUTH DAKOTA

Aberdeen	231, 235
Belle Fourche	240A
Brookings	269A
Deadwood	226, 236
Hot Springs	244A
Huron	221A
Madison	276A
Mitchell	265A
Mobridge	221A
Pierre	224A, 237A
Rapid City	230, 250
Sioux Falls	223, 228A, 243, 247
Vermillion	272A
Watertown	226, 241
Winner	228A
Yankton	255, 262

TENNESSEE

Athens	257A
Bristol	245
Carthage	272A
Centerville	285A
Chattanooga	222, 243, 288A, 293
Clarksville	300
Cleveland	264
Columbia	269A
Cookeville	232A, 252A
Covington	228A
Dayton	280A
Dickson	272A
Dyersburg	261A
Fayetteville	288A
Franklin	261A
Gallatin	283
Greeneville	235
Humboldt	272A
Jackson	222, 281
Jamestown	261A
Johnson City	268
Kingsport	253, 292A
Knoxville	227, 248, 278, 299
Lafayette	257A
LaFollette	288A
Lawrenceburg	240A
Lebanon	297
Lewisburg	232A
Lexington	257A
Livingston	240A
Manchester	259
McKenzie	295
McMinnville	269A
Memphis	246, 259, 266, 274, 283, 290
Morristown	240A
Murfreesboro	242
Nashville	225, 238, 250, 277, 290
Oak Ridge	285A
Pulaski	252A
Ripley	237A

TENNESSEE—Continued

	Channel No.
Savannah	249A
Sevierville	271
Shelbyville	275
Sparta	288A
Springfield	232A
Sweetwater	237A
Tullahoma	227

TEXAS

Abilene	239, 257A, 264, 286
Alice	272A
Alpine	224A
Alvin	271
Amarillo	226, 231, 250, 254, 270
Andrews	288A
Austin	229, 234, 238, 252A
Ballinger	276A
Bay City	284
Beaumont	236, 248, 299
Beeville	285A
Belton	292A
Big Lake	252A
Big Spring	237A
Bonham	252A
Borger	282
Brady	237A
Breckenridge	228A
Brenham	292A
Brownfield	292A
Brownsville	226, 262
Brownwood	268, 281
Bryan	252A
Burnet	276A
Cameron	269A
Canyon	296A
Carrizo Springs	228A
Childress	244A
Cleburne	235
Cleveland	295
Coleman	296A
College Station	221A
Colorado City	292A
Comanche	232A
Corpus Christi	230, 238, 243, 256, 260
Crane	265A
Crockett	224A
Cuero	249A
Dalhart	232A
Dallas	223, 238, 250, 254, 262, 266, 275, 279, 283, 287
Del Rio	232A
Denison	269A
Denton	291
Diboll	238
Dumas	237A
Eagle Pass	224A
Eastland	252A
Edinburg	273, 281
El Paso	227, 234, 242, 248, 253, 260, 264, 271, 275
Falfurrias	292A
Farwell	252A
Floydada	237A
Fort Stockton	232A
Fort Worth	230, 242, 246, 258, 271, 298
Gainesville	233
Galveston	293
Georgetown	265A
Gonzales	272A
Hamilton	221A
Harlingen	233, 241
Henderson	261A
Hereford	292A
Hillsboro	273
Houston	229, 233, 239, 243, 250, 256, 262, 266, 275, 281, 289
Huntsville	269A
Jacksonville	257A
Jasper	272A
Junction	228A
Kenedy-Karnes	296A
Kermit	292A
Killeen	227
Kingsville	249A
Lake Jackson	297
Lamesa	251, 262
Lampasas	257A
Laredo	264, 289, 300
Levelland	288A
Longview	289

TEXAS—Continued

	Channel No.
Lubbock	229, 233, 242, 258, 266, 273
Lufkin	277, 286
Marlin	244A
Marshall	280A
McAllen	245, 253
McCamey	237A
Mercedes	296A
Merkel	240A
Mexia	265A
Midland	222, 227, 271
Mission	221A
Monahans	260, 277
Mt. Pleasant	241
Muleshoe	276A
Nacogdoches	252A
New Braunfels	221A
Odessa	245, 250, 256
Orange	283, 291
Palestine	232A
Pampa	262
Paris	257A
Pasadena	223
Pecos	252A
Perryton	240A
Pharr	285A
Plainview	247
Pleasanton	252A
Port Arthur	227, 231, 253
Port Lavaca	240A
Quanah	265A
Raymondville	269A
Rusk	249A
San Angelo	225, 230, 234, 248
San Antonio	225, 241, 247, 258, 262, 270, 274, 283
San Marcos	296A
San Saba	244A
Seguin	287
Seminole	280A
Seymour	232A
Shamrock	224A
Sherman	244A
Sinton	267, 277
Slaton	224A
Snyder	269A
Sonora	221A
Spearman	252A
Stamford	221A
Sweetwater	244A
Taylor	221A
Temple	285A
Terrell Hills	292A
Texarkana	251, 273
Tulia	285A
Tyler	226, 268, 293
Uvalde	237A
Vernon	272A
Victoria	221A, 236, 254
Waco	238, 248, 260
Weslaco	247, 258
Wichita Falls	225, 236, 247, 260, 277

UTAH

Blanding	221A
Bountiful	288A
Brigham City	296A
Cedar City	223, 235
Logan	225, 233
Moab	244A
Ogden	238, 250, 266, 270
Orem	296A
Price	252A
Provo	235, 241
Richfield	229
St. George	228A
Salt Lake City	227, 231, 246, 254, 262, 282
Spanish Fork	292A
Tooele	276A
Vernal	224A

VERMONT

Barre	296A
Bennington	232A
Burlington	225, 255
Montpelier	244A, 276A
Newport	300
Rutland	246, 251
St. Albans	272A
Springfield	228A
Waterbury	287
White River Junction	237A

VIRGINIA

	Channel No.
Abington	224A
Arlington	286
Ashland	261A
Blacksburg	269A
Blackstone	228A
Charlottesville	237A, 248
Clifton Forge	280A
Covington	265A
Crewe	284
Culpeper	276A
Farmville	239
Fredericksburg	227, 268
Front Royal	280A
Galax	251
Gretna	277
Grundy	249A
Hampton	267
Harrisonburg	264, 288A
Hopewell	221A
Lawrenceville	288A
Lexington	252A
Luray	257A, 292A
Lynchburg	261A, 269A
Manassas	294
Marion	230
Martinsville	242
Norfolk-Newport News	225, 239, 247, 254, 259, 263, 275, 283, 287
Norton	296A
Orange	244A
Petersburg	257A
Pulaski	296A
Richmond	233, 251, 271, 279, 293
Roanoke	222, 235, 256
Salem	228A
South Boston	248
Staunton	228A, 272A
Warrenton	232A, 299
Warsaw	237A
Waynesboro	224A
Williamsburg	243
Winchester	223, 273
Woodbridge	290

WASHINGTON

Aberdeen	284
Bellingham	225, 282
Bremerton	295
Centralia	275
Chelan	228A
Colfax	272A
Colville	221A
Edmonds	287
Ellensburg	221A
Ephrata	240A
Grand Coulee	253, 266
Hoquiam	280A
Kennewick	287
Longview	240A
Lynden	293
Moses Lake	262
Omak	224A
Opportunity	241
Othello	249A
Prosser	272A
Pullman	285A
Quincy	232A
Richland	236, 281
Seattle	223, 227, 231, 235, 239, 243, 251, 255, 260, 264, 268, 273, 299
Spokane	225, 229, 251, 255, 260, 289, 300
Sunnyside	244A
Tacoma	247, 280A, 291
Toppenish	224A
Walla Walla	227, 246
Wenatchee	257A, 285A
Yakima	292A, 297

WEST VIRGINIA

Beckley	258, 279
Bluefield	283, 292A
Buckhannon	237A
Charleston	241, 248, 253, 260, 290
Charles Town	252A
Clarksburg	224A, 249A
Elkins	232A
Fairmont	261A, 276A
Grafton	265A
Huntington	223, 263, 277
Keyser	240A

WEST VIRGINIA—Continued

	Channel No.
Logan	270, 274
Martinsburg	248
Montgomery	265A
Morgantown	257A, 270, 293
Moundsville	288A
New Martinsville	280A
Oak Hill	231
Parkersburg	257A, 276A
Richwood	244A
Ronceverte	288A
Weston	228A
Wheeling	247, 254, 298
Williamson	243

WISCONSIN

Antigo	285A
Appleton	257A
Ashland	240A
Beloit	240A
Eagle River	232A
Eau Claire	231, 264
Fort Atkinson	297
Green Bay	253, 266
Greenfield Twsp	235
Hayward	221A
Janesville	260
Kaukauna	285A
Kenosha	236, 245
LaCrosse	227
Ladysmith	288A
Madison	251, 268, 273, 281
Manitowoc	272A, 280A
Marinette	236
Marshfield	300
Medford	257A
Menomonie	285A
Merrill	224A
Milwaukee	227, 233, 239, 243, 247, 256, 271, 275, 299
Monroe	229
Mt. Horeb	221A
Neenah-Menasha	230, 289
Neillsville	288A
Oshkosh	244A
Park Falls	252A
Prairie Du Chien	232A
Racine	221A, 264
Rhinelander	298
Rice Lake	242
Richland Center	265A
Ripon	240A
Sauk City	244A
Shawano	262, 274
Sheboygan	249A
Sparta	246
Stevens Point	250
Sturgeon Bay	240A
Tomah	255
Viroqua	272A
Watertown	284
Waukesha	291
Wausau	238, 270
Wauwatosa	279
West Bend	223
Wisconsin Rapids	277, 293

WYOMING

Buffalo	224A
Casper	233, 238
Cheyenne	250, 292A
Cody	232A
Douglas	221A
Evanston	292A
Gillette	228A
Lander	248
Laramie	241, 255
New Castle	257A
Powell	225
Rawlins	224A
Riverton	228A
Rock Springs	243, 258
Sheridan	235, 243
Thermopolis	252A, 269A
Torrington	257A
Wheatland	269A
Worland	240A

§ 73.203 Availability of channels.

(a) Subject to the provisions of paragraph (b) of this section, applications may be filed to construct FM broadcast stations in the 48 conterminous states only on the channels assigned in the table of assignments (§ 73.202(b)) and only in communities listed therein. Applications which fail to comply with this requirement, whether or not accompanied by a petition to amend the table, will not be accepted for filing: *Provided, however,* That applications specifying channels which accord with publicly announced Commission orders changing the table of assignments will be accepted for filing even though such applications are tendered before the effective dates of such channel changes.

(b) A channel assigned to a community listed in the table of assignments is available upon application in any unlisted community which is located within 25 miles of the listed community. Where channels are assigned to two or more communities listed in combination in the table of assignments the provisions of this paragraph shall apply separately to each community so listed. The distance between communities shall be determined by the distance between the respective coordinates thereof as set forth in the publication of the United States Department of Commerce entitled "Air Line Distance Between Cities in the United States". (This publication may be purchased from the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402.) If said publication does not contain the coordinates of either or both communities, the coordinates of the main post office in either or both of the communities shall be used. The method to be followed in making the measurements is set forth in § 73.208(c).

§ 73.204 International agreements and other restrictions on use of channels.

(a) Authorizations issued by the Commission for FM broadcast facilities will be subject to the provisions of any agreements entered into by the United States with Canada concerning FM assignments and authorizations. The Commission may decide after consultation with Canada that an application should not be granted; or if, pursuant to an agreement providing for timely objection after grant, Canada files such objection, the Commission may on its own motion set aside the grant pending consideration. The Commission will give notice of the filing of such objections.

(b) The frequency 89.1 Mc/s (channel 206) is reserved in the New York City metropolitan area for the use of the United Nations with the equivalent of an antenna height of 500 feet above average terrain and effective radiated power of 20 kilowatts, and the Commission will make no assignments which would cause objectionable interference with such use.

(c) In Alaska, the frequency band 88–100 Mc/s is allocated exclusively to Government radio services and the non-Government fixed service. The frequencies 83.1 through 99.9 Mc/s (channels 201 through 260) will not be assigned in Alaska for use by FM broadcast stations.

(d) In Hawaii, the frequency band 98–108 Mc/s is allocated for non-broad-

cast use. The frequencies 98.1 through 107.9 Mc/s (channels 251 through 300) will not be assigned in Hawaii for use by FM broadcast stations.

§ 73.205 Zones.

For the purpose of allocation and assignment, the United States is divided into three zones as follows:

(a) Zone I consists of that portion of the United States located within the confines of the following lines drawn on the United States Albers Equal Area Projection Map (based on standard parallels 29½° and 45½°; North American datum): Beginning at the most easterly point on the State boundary line between North Carolina and Virginia; thence in a straight line to a point on the Virginia, West Virginia boundary line located at North Latitude 37°49′ and West Longitude 80°12′30″; thence westerly along the southern boundary lines of the States of West Virginia, Ohio, Indiana, and Illinois to a point at the junction of the Illinois, Kentucky, and Missouri State boundary lines; thence northerly along the western boundary line of the State of Illinois to a point at the junction of the Illinois, Iowa, and Wisconsin State boundary lines; thence easterly along the northern State boundary line of Illinois to the 90th meridian; thence north along this meridian to the 43.5° parallel; thence east along this parallel to the 71st meridian; thence in a straight line to the intersection of the 69th meridian and the 45th parallel; thence east along the 45th parallel to the Atlantic Ocean. When any of the above lines pass through a city, the city shall be considered to be located in Zone I. (See Figure 1 of § 73.699.)

(b) Zone I–A consists of that portion of the State of California which is located south of the 40th parallel.

(c) Zone II consists of Alaska, Hawaii, Puerto Rico, the Virgin Islands, and the rest of the United States which is not located in either Zone I or Zone I–A.

§ 73.206 Classes of commercial channels, and stations operating thereon.

(a) *Class A channels and stations.* (1) Except as provided in § 73.204, the following frequencies are designated as Class A channels and are assigned for use, in all zones, by Class A stations only:

Frequency (Mc/s)	Channel No.	Frequency (Mc/s)	Channel No.
92.1	221	100.1	261
92.7	224	100.9	265
93.5	228	101.7	269
94.3	232	102.3	272
95.3	237	103.1	276
95.9	240	103.9	280
96.7	244	104.9	285
97.7	249	105.5	288
98.3	252	106.3	292
99.3	257	107.1	296

(2) A Class A station is a station which operates on a Class A channel, and is designed to render service to a relatively small community, city, or town, and the surrounding rural area.

(3) A Class A station will not be authorized to operate with effective radiated power greater than 3 kilowatts (4.8 dbk), and the coverage of a Class A station shall not exceed that obtained from 3 kilowatts effective radiated power and antenna height above average terrain of 300 feet. For provisions concerning minimum facilities, and concerning reduction in power where antenna height above average terrain exceeds 300 feet, see § 73.211.

(b) *Class B–C channels and Class B and Class C stations.* (1) Except for the channels specified in paragraph (a)(1) of this section, all of the channels listed in § 73.201 from 222 through 300 (92.3 through 107.9 Mc/s) are classified as Class B–C channels, and (subject to the restrictions set forth in § 73.204) are assigned for use in Zones I and I–A by Class B stations only, and for use in Zone II by Class C stations only (there are no Class C stations in Zones I or I–A and no Class B stations in Zone II).

(2) A Class B station is a station which operates on a Class B–C channel in Zone I or Zone I–A, and is designed to render service to a sizable community, city, or town, or to the principal city or cities of an urbanized area, and to the surrounding area.

(3) With respect to Class B stations authorized after September 10, 1962, no such station will be authorized with effective radiated power greater than 50 kilowatts (17 dbk), and the coverage of a Class B station authorized after that date shall not exceed that obtained from 50 kilowatts effective radiated power and 500 feet antenna height above average terrain. For provisions concerning minimum power, and concerning reduction in power where antenna height above average terrain exceeds 500 feet, see § 73.211.

(4) A Class C station is a station which operates on a Class B–C channel in Zone II, and is designed to render service to a community, city, or town, and large surrounding area.

(5) With respect to Class C stations authorized after September 10, 1962, no such station will be authorized with effective radiated power greater than 100 kilowatts (20 dbk), and the coverage of a Class C station authorized after that date shall not exceed that obtained from 100 kilowatts effective radiated power and antenna height above average terrain of 2,000 feet. For provisions concerning minimum power, and reduction in power where antenna height above average terrain exceeds 2,000 feet, see § 73.211.

§ 73.207 Minimum mileage separations between co-channel and adjacent-channel stations on commercial channels.

(a) Petitions to amend the table of assignments (§73.202(b)) (other than those expressly requesting amendment of this section or § 73.205) will be dismissed, and no application for a new station, change in the channel of an existing station, or (except as provided in paragraph (b) of this section) increase in antenna height or effective radiated power, or change in location of an existing station, will be accepted for filing unless the proposed facilities will be located at least as far from the transmitter sites of other co-channel and adjacent-channel stations (both existing and proposed) as the distances specified in this paragraph. Proposed stations of the respective classes shown in the left-hand column of the following table shall be located no less than the distance shown from co-channel stations and first adjacent-channel stations (200 kc/s removed) and second and third adjacent-channel stations (400 and 600 kc/s removed) of the classes shown in the remaining columns of the table. The distances shown between stations of different classes apply regardless of which is the proposed station under consideration (e.g., distances shown from a new Class A station to an existing Class C station are also the distances between a new Class C and an existing Class A station). The distances between Class B and Class C stations apply only across zone lines. The adjacent-channel spacings listed also apply: (1) To applications for noncommercial educational facilities on Channels 218, 219, or 220, with respect to other stations on Channels 221, 222, or 223; (2) to applications for facilities on Channels 221, 222, or 223 with respect to noncommercial educational stations on Channels 218, 219, or 220 (for classification of noncommercial educational stations, see § 73.504).

CLASS OF STATION AND FREQUENCY SEPARATION (kc/s)

Class of station	Class A				Class B				Class C				10-watt educational			
	Co-Ch.	200	400	600	Co-Ch.	200	400	600	Co-Ch.	200	400	600	Co-Ch.	200	400	600
A	65	40	15	15	-------	65	40	40	-------	105	65	65	-------	30	15	15
B	-------	----	----	----	150	105	40	40	170	135	65	65	-------	----	40	40
C	-------	----	----	----	-------	----	----	----	180	150	65	65	-------	----	65	65
10-watt educational	-------	----	----	----	-------	----	----	----	-------	----	----	----	-------	----	----	----

NOTE: Intermediate frequency amplifiers of most FM broadcast receivers are designed to operate on 10.7 megacycles. For this reason the assignment of two stations in the same area, one with a frequency of 10.6 or 10.8 megacycles removed from that of the other, will be avoided if possible.

(b) Where an existing station is located less than the minimum distances specified in paragraph (a) of this section with respect to co-channel or adjacent-channel stations:

(1) It may apply for increases in antenna height, or in effective radiated power up to the maximum specified in § 73.206 for its class, if the application for increase is accompanied by a request to decrease power or antenna height so that the station's 1 mv/m contour (located pursuant to Figure 1 to § 73.333) will be no further from the station's transmitter than with its present facilities.

(2) It may apply for permission to move transmitter site, but this will not be granted if it would increase the amount by which the station is located at substandard separation.

(c) The zone in which the transmitter of an FM station is located or proposed to be located determines the applicable

rules with respect to minimum required spacings.

§ 73.208 Reference points and distance computations.

(a) In considering petitions to amend the table of assignments (§ 73.202(b)), the following reference points shall be used by the Commission in determining separations between communities:

(1) Where transmitter sites for the pertinent channels have been authorized in communities involved in a petition to amend the table of assignments, separations between such communities shall be determined by the distance between the coordinates of the authorized transmitter sites in the respective communities as set forth in the Commission's authorizations therefor.

(2) Where an authorized transmitter site is available for use as a reference point in one community but not in the other for the pertinent channels, separations shall be determined by the distance between the coordinates of the transmitter site as set forth in the Commission's authorization therefor and the coordinates of the other community as set forth in the publication of the United States Department of Commerce entitled "Air Line Distances Between Cities in the United States." If said publication does not contain the coordinates for said other community, the coordinates of the main post office thereof shall be used.

(3) Where no authorized transmitter sites are available for use as reference points in both communities for the pertinent channels, the distance between the two communities listed in the above publication shall be used. If said publication does not contain such distance, the separation between the two communities shall be determined by the distance between the coordinates thereof as set forth in said publication. Where such coordinates are not contained in said publication, the coordinates of the main post offices of said communities shall be used.

(4) Where the distance between the reference point in a community to which a channel is proposed to be assigned and the reference point in another community or communities does not meet the minimum separation requirements of § 73.207, the channel may be assigned to such community upon a showing that a transmitter site is available that would meet the minimum separation requirements of § 73.207 and the minimum field intensity requirements of § 73.315. In such cases, where a station is not authorized in the community or communities to which measurements from the proposed channel assignment must be made pursuant to § 73.207, a showing should also be made that the distance between suitable transmitter sites in such other community or communities and the proposed transmitter site for the new channel meet the Commission's minimum spacing and coverage requirements.

(b) Station separations in licensing proceedings shall be determined by the distance between the coordinates of the proposed transmitter site in one community and the coordinates of an authorized site for the pertinent channel in the other community.

(c) The distance between reference points is considered to be the length of the hypotenuse of a right triangle, one side of which is the difference in latitude of the reference points and the other side the difference in longitude of the two reference points, and shall be computed by the method set forth in this paragraph. (This method is appropriate for determining distances up to 220 miles, and for such distances will normally be more accurate than using spherical trigonometry without correction for the spheroidal shape of the earth. However, its accuracy deteriorates rapidly at distances beyond 300 miles and this method should not be used to compute greater distances.)

(1) Determine the difference in latitude and the difference in longitude between the two reference points. Convert these two differences into degrees and decimal parts of a degree in accordance with Table I of § 73.698.

(2) Determine the middle latitude of the two reference points to the nearest second of latitude (average the latitudes of the two points).

(3) Multiply the difference in latitude by the number of miles per degree of latitude difference obtained from Table II of § 73.698 for the appropriate middle latitude (interpolate linearly). This determines the north-south distance in statute miles (L_a).

NOTE: In determining necessary distance computations for Alaska, Hawaii, and the Territories, the appropriate mileage per degree may be obtained by linear interpolation of the data given on pages 1246 and 1247 of the tables in publication H.O. No. 9 (Bowditch-American Practical Navigator—1958 Edition) of the U.S. Navy Department, Hydrographic Office. This publication may be purchased from the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402.

(4) Multiply the difference in longitude by the number of miles per degree of longitude difference, obtained from Table III of § 73.698, for the appropriate middle latitude (interpolate linearly). This determines the east-west distance in statute miles (L_o).

(5) Determine the distance between the two reference points by the square root of the sum of the squares of the distances obtained in subparagraphs (3) and (4) of this paragraph, using sufficient decimal figures to determine the distance to the nearest mile; i.e.,

$$D=(L_a^2+L_o^2)^{1/2}$$

where:

D=Distance in statute miles.
L_a=North-south distance in statute miles.
L_o=East-west distance in statute miles.

§ 73.209 Protection from interference.

(a) Permittees and licensees of FM broadcast stations are not protected from any interference which may be caused by the grant of a new station, or of authority to modify the facilities of an existing station, in accordance with the provisions of this subpart.

(b) The nature and extent of the protection from interference accorded to FM broadcast stations is limited solely to the protection which results from the minimum assignment and station separation requirements and the rules with respect to maximum powers and antenna heights set forth in this subpart.

§ 73.210 Station location and program origination.

(a) (1) Except as provided in paragraph (b) of this section, each FM broadcast station will be licensed to serve primarily a particular city, town, political subdivision, or community which will be specified in the station license and the station will be considered to be located in such place.

(2) Each station shall maintain a studio, which will be known as the main studio, in the place where the station is located: *Provided*, That the main studio may be located at the transmitter site whether or not the transmitter site is in the place where the station is located.

(3) A majority (computed on the basis of duration and not number) of a station's programs or, in the case of a station affiliated with a network, two-thirds of such station's non-network programs, whichever is smaller, shall originate from the main studio or from other studios or remote points situated in the place where the station is located.

(b) (1) Stations will be licensed to serve more than one city, town, political subdivision, or community only where a satisfactory showing is made that each such place meets all the requirements of this subpart with respect to the location of main studios; that the station can and will originate a substantial number of local live programs from each such place; and that the requirements as to origination of programs contained in paragraph (a) of this section would place an unreasonable burden on the station if it were licensed to serve only one city, town, political subdivision, or community.

(2) A station licensed to serve more than one place shall be considered to be located in and shall maintain main studios in each such place.

(3) With respect to such station, the requirements in paragraph (a) of this section as to origination of programs shall be satisfied by the origination of programs from any or all of the main studios, other studios, or remote points situated in any or all of the places in which the main studios are located.

(c) The transmitter of each FM broadcast station shall be so located that, on the basis of the effective radiated power and antenna height above average terrain employed, a minimum field strength of 70 decibels above 1 microvolt per meter, or 3.16 millivolts per meter, will be provided over the entire principal community to be served.

§ 73.211 Power and antenna height requirements.

(a) *Minimum requirements.* (1) Except as provided in paragraph (b) (2) of this section, the minimum effective radiated power shall be,

Class A	100 watts (−10 dbk)
Class B	5 kw (7 dbk)
Class C	25 kw (14 dbk)

(2) No minimum antenna height above average terrain is specified.

(b) *Maximum power and antenna height.* (1) The maximum effective radiated power in any direction, and maxi-

mum antenna height for equivalence purposes, shall be as follows for the various classes of stations:

Class	Maximum power	Maximum antenna height (feet above average terrain)
A	3 kw (4.8 dbk)	300
B	50 kw (17.0 dbk)	500
C	100 kw (20.0 dbk)	2,000

(2) Antenna heights may be used exceeding those specified in this paragraph for equivalence purposes, provided effective radiated power is reduced in the amount determined by use of the appropriate curves in Figure 3 of § 73.333. Where, under Figure 3 of § 73.333, effective radiated power must be reduced to an amount less than the normal minimum specified in paragraph (a) (1) of this section for the class of station involved, the effective radiated power determined by Figure 3 of § 73.333 shall be the minimum for the station involved.

(c) *Determination of applicable rules.* The zone in which the transmitter of an FM station is located or proposed to be located determines the applicable rules with respect to the class of station, and thus the minimum and maximum requirements as to facilities.

(d) *Existing stations.* Pending resolution of the issues in Docket No. 14185, stations authorized as of September 10, 1962, which do not conform to the requirements of this section, may continue to operate as authorized; but any application to change facilities will be subject to the provisions of this section, except that the minimum power specified in paragraph (a) of this section shall not apply to an application to increase facilities.

§ 73.212 Administrative changes in authorizations.

(a) In the issuance of FM broadcast station authorizations, the Commission will specify the transmitter output power and effective radiated power in accordance with the following tabulation:

Power (watts or kw)	Rounded out to nearest figure (watts or kw)
1 to 3	.05
3 to 10	.1
10 to 30	.5
30 to 100	1
100 to 300	5
300 to 1,000	10

(b) Antenna height above average terrain will be specified in accordance with the following tabulation:

Antenna height above average terrain	Rounded out to nearest figures (feet)
0 to 100	1
100 to 300	5
Over 300	10

Administrative Procedure

§ 73.214 Cross reference.

See Subpart D of Part 1 of this chapter, for general requirements as to applications, filing of applications and description of application forms, other forms and information to be filed with the Commission, the manner in which applications are processed, and provisions applying to action on applications. See § 1.1111 of Subpart G of that part for the fees to be paid in connection with applications for facilities in the service covered in this subpart.

§ 73.215 Notification of filing of applications.

In order to minimize harmful interference at the National Radio Astronomy Observatory site located at Green Bank, Pocahontas County, West Virginia, and at the Naval Radio Research Observatory at Sugar Grove, Pendleton County, West Virginia, an applicant for authority to construct a new FM broadcast station or for authority to make changes in the frequency, power, antenna height, or antenna directivity of an existing station within the area bounded by 39°15′ N on the north, 78°30′ W on the east, 37°30′ N on the south, and 80°30′ W on the west shall, at the time of filing such application with the Commission, simultaneously notify the Director, National Radio Astronomy Observatory, P.O. Box #2, Green Bank, West Virginia, 24944, in writing, of the technical particulars of the proposed station. Such notification shall include the geographical coordinates of the antenna, antenna height, antenna directivity if any, proposed frequency, type of emission, and power. In addition, the applicant shall indicate in his application to the Commission the date notification was made to the Observatory. After receipt of such applications, the Commission will allow a period of twenty (20) days for comments or objections in response to the notifications indicated. If an objection to the proposed operation is received during the twenty-day period from the National Radio Astronomy Observatory for itself or on behalf of the Naval Radio Research Observatory, the Commission will consider all aspects of the problem and take whatever action is deemed appropriate.

§ 73.216 Equipment tests.

(a) During the process of construction of an FM broadcast station, the permittee, after notifying the Commission and Engineer in Charge of the radio district in which the station is located, may without further authority of the Commission, conduct equipment tests for the purpose of such adjustments and measurements as may be necessary to assure compliance with the terms of the construction permit, the technical provisions of the application therefor, the rules and regulations, and the applicable engineering standards.

(b) The Commission may notify the permittee to conduct no tests or may cancel, suspend, or change the date for the beginning of equipment tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Equipment tests may be continued so long as the construction permit shall remain valid.

(d) Inspection of a station will ordinarily be required during the equipment test period and before the commencement of the program test. After construction and after adjustments and measurements have been completed to show compliance with the terms of the construction permit, the technical provisions of the application therefor, the rules and regulations and the applicable engineering standards, the permittee should notify the Engineer in Charge of the radio district in which the station is located that it is ready for inspection.

(e) The authorization for tests embodied in this section shall not be construed as constituting a license to operate but as a necessary part of construction.

§ 73.217 Program tests.

(a) Upon completion of construction of an FM broadcast station in accordance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations and the applicable engineering standards, and when an application for station license has been filed showing the station to be in satisfactory operating condition, the permittee may request authority to conduct program tests: *Provided,* That such request shall be filed with the Commission at least ten (10) days prior to the date on which it is desired to begin such operation and that the Engineer in Charge of the radio district in which the station is located is notified. (All data necessary to show compliance with the terms and conditions of the construction permit must be filed with the license application.)

(b) Program tests shall not commence until specific Commission authority is received. The Commission reserves the right to change the date of the beginning of such tests or to suspend or revoke the authority for program tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Unless sooner suspended or revoked, program test authority continues valid during Commission consideration of the application for license and during this period further extension of the construction permit is not required. Program test authority shall be automatically terminated by final determination upon the application for station license.

(d) All operation under program test authority shall be in strict compliance with the rules governing FM broadcast stations and in strict accordance with representations made in the application for license pursuant to which the tests were authorized.

(e) The granting of program test authority shall not be construed as approval by the Commission of the application for station license.

§ 73.218 Normal license period.

(a) Licenses for FM broadcast stations ordinarily will be issued for a period of three years and, when regularly renewed, at three year intervals thereafter: *Provided, however,* That, if the Commission finds that the public interest, convenience, and necessity will be served thereby, it may issue either an initial license or a renewal thereof for a lesser term. When regularly issued or renewed, licenses will be issued to expire at the hour of 3:00 a.m., eastern standard time, in accordance with the

following schedule, and at three year intervals thereafter.

(1) For stations located in Florida, Puerto Rico and Virgin Islands, February 1, 1964.

(2) For stations located in Alabama and Georgia, April 1, 1964.

(3) For stations located in Arkansas, Louisiana and Mississippi, June 1, 1964.

(4) For stations located in Tennessee, Kentucky and Indiana, August 1, 1964.

(5) For stations located in Ohio and Michigan, October 1, 1964.

(6) For stations located in Illinois and Wisconsin, December 1, 1964.

(7) For stations located in Iowa and Missouri, February 1, 1965.

(8) For stations located in Minnesota, North Dakota, South Dakota, Montana and Colorado, April 1, 1965.

(9) For stations located in Kansas, Oklahoma, Nebraska, June 1, 1965.

(10) For stations located in Texas, August 1, 1965.

(11) For stations located in Wyoming, Nevada, Arizona, Utah, New Mexico and Idaho, October 1, 1965.

(12) For stations located in California, December 1, 1965.

(13) For stations located in Washington, Oregon, Alaska and Hawaii, February 1, 1966.

(14) For stations located in Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island and Vermont, April 1, 1966.

(15) For stations located in New Jersey and New York, June 1, 1966.

(16) For stations located in Delaware and Pennsylvania, August 1, 1966.

(17) For stations located in Maryland, District of Columbia, Virginia, West Virginia, October 1, 1966.

(18) For stations located in North Carolina, South Carolina, December 1, 1966.

Licensing Policies

§ 73.231 Exclusive affiliation of station.

No license shall be granted to an FM broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization under which the station is prevented or hindered from, or penalized for, broadcasting the programs of any other network organization. (The term "network organization" as used herein includes national and regional network organizations. See ch. VII, J of Report on Chain Broadcasting.)

§ 73.232 Territorial exclusivity.

No license shall be granted to an FM broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which prevents or hinders another broadcast station serving substantially the same area from broadcasting the network's programs not taken by the former station, or which prevents or hinders another broacast station serving a substantially different area from broadcasting any program of the network organization. This section shall not be construed to prohibit any contract, arrangement, or understanding between a station and a network organization pursuant to which the station is granted the first call in its primary service area upon the programs of the network organization.

§ 73.233 Term of affiliation.

No license shall be granted to an FM broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which provides, by original terms, provisions for renewal, or otherwise for the affiliation of the station with the network organization for a period longer than 2 years: *Provided,* That a contract, arrangement, or understanding for a period up to 2 years, may be entered into within 6 months prior to the commencement of such period.

§ 73.234 Option time.

No license shall be granted to an FM broadcast station which options for network programs any time subject to call on less than 56 days' notice, or more time than a total of 3 hours within each of four segments of the broadcast day, as herein described. The broadcast day is divided into four segments, as follows: 8 a.m. to 1 p.m.; 1 p.m. to 6 p.m.; 6 p.m. to 11 p.m.; 11 p.m. to 8 a.m. (These segments are to be determined for each station in terms of local time at the location of the station but may remain constant throughout the year regardless of shifts from standard to daylight saving time or vice versa.) Such options may not be exclusive as against other network organizations and may not prevent or hinder the station from optioning or selling any or all of the time covered by the option, or other time, to other network organizations.

Note 1: As used in this section, an option is any contract, arrangement, or understanding, express or implied, between a station and a network organization which prevents or hinders the station from scheduling programs before the network agrees to utilize the time during which such programs are scheduled, or which requires the station to clear time already scheduled when the network organization seeks to utilize the time.

Note 2: All time options permitted under this section must be specified clock hours, expressed in terms of any time system set forth in the contract agreed upon by the station and network organization. Shifts from daylight saving to standard time or vice versa may or may not shift the specified hours correspondingly as agreed by the station and network organization.

§ 73.235 Right to reject programs.

No license shall be granted to an FM broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which (a), with respect to programs offered pursuant to an affiliation contract, prevents or hinders the station from rejecting or refusing network programs which the station reasonably believes to be unsatisfactory or unsuitable; or which (b), with respect to network programs so offered or already contracted for, prevents the station from rejecting or refusing any program which, in its opinion, is contrary to the public interest, or from substituting a program of outstanding local or national importance.

§ 73.236 Network ownership of stations.

No license shall be granted to a network organization, or to any person directly or indirectly controlled by or under common control of a network organization, for an FM broadcast station in any locality where the existing FM broadcast stations are so few or of such unequal desirability (in terms of coverage, power, frequency, or other related matters) that competition would be substantially restrained by such licensing. (The word "control" as used herein is not limited to majority stock ownership, but includes actual working control in whatever manner exercised.)

§ 73.237 Dual network operation.

No license shall be issued to an FM broadcast station affiliated with a network organization which maintains more than one network of FM broadcast stations: *Provided,* That this section shall not be applicable if such networks are not operated simultaneously, or if there is no substantial overlap in the territory served by the group of stations comprising each such network.

§ 73.238 Control by networks of station rates.

No license shall be granted to an FM broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization under which the station is prevented or hindered from, or penalized for, fixing or altering its rates for the sale of broadcast time for other than the network's programs.

§ 73.239 Use of common antenna site.

No FM broadcast station license or renewal of FM broadcast station license will be granted to any person who owns, leases, or controls a particular site which is peculiarly suitable for FM broadcasting in a particular area and (a) which is not available for use by other FM broadcast station licensees; and (b) no other comparable site is available in the area; and (c) where the exclusive use of such site by the applicant or licensee would unduly limit the number of FM broadcast stations that can be authorized in a particular area or would unduly restrict competition among FM broadcast stations.

§ 73.240 Multiple ownership.

No license for an FM broadcast station shall be granted to any party (including all parties under common control) if:

(a) Such party directly or indirectly owns, operates, or controls another FM broadcast station which serves substantially the same service area; or

(b) Such party, or any stockholder, officer or director of such party, directly or indirectly owns, operates, controls, or has any interest in, or is an officer or director of any other FM broadcast station if the grant of such license would result in a concentration of control of FM broadcasting in a manner inconsistent with public interest, convenience, or necessity. In determining whether there is such a concentration of control, consideration will be given to the facts of each case with particular reference to

such factors as the size, extent and location of areas served, the number of people served, classes of stations involved, and the extent of other competitive service to the areas in question. The Commission, however, will in any event consider that there would be such a concentration of control contrary to the public interest, convenience or necessity for any party or any of its stockholders, officers or directors to have a direct or indirect interest in, or be stockholders, officers, or directors of, more than seven FM broadcast stations.

NOTE 1: The word "control" as used herein is not limited to majority stock ownership, but includes actual working control in whatever manner exercised.

NOTE 2: In applying the foregoing provisions to the stockholders of a corporation which has more than 50 voting stockholders, only those stockholders need be considered who are officers or directors or who directly or indirectly own 1 percent or more of the outstanding voting stock.

§ 73.241 Special rules relating to contracts providing for reservation of time upon sale of a station.

No license, renewal of license, assignment of license, or transfer of control of a corporate licensee shall be granted or authorized to a FM broadcast station which has a contract, arrangement or understanding, express or implied, pursuant to which, as consideration or partial consideration for the assignment of license or transfer of control, the assignor of a station license or the transferor of stock, where transfer of a corporate licensee is involved, or the nominee of such assignor or transferor retains any right of reversion of the license or any right to the reassignment of the license in the future, or reserves the right to use the facilities of the station for any period whatsoever.

EQUIPMENT

§ 73.250 Acceptability of broadcast transmitters for licensing.

(a) In order to facilitate the filing of, and action on applications for station authorizations, transmitters will be accepted for licensing by the Commission under one of the following conditions:

(1) A transmitter may be type-accepted upon the request of any manufacturer of transmitters built in quantity by following the type acceptance procedure set forth in Part 2 of this chapter, provided that the data and information submitted indicates that the transmitter meets the requirements of § 73.317. If accepted, such transmitter will be included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment". Applicants specifying transmitters included on such a list need not submit detailed descriptions and diagrams where the correct type number is specified, provided that the equipment proposed is identical with that accepted. Copies of this list are available for inspection at the Commission's office in Washington, D. C., and at each of its field offices.

(2) An application specifying a transmitter not included on the Radio Equipment List, Part B, may be accepted upon the request of a prospective licensee submitting with the application for construction permit a complete description of the transmitter, including the circuit diagram, listing of all tubes used, function of each, multiplication in each stage, plate current and voltage applied to each tube, a description of the oscillator circuit together with any devices installed for the purpose of frequency stabilization and the means of varying output power to compensate for power supply voltage variations. However, if this data has been filed with the Commission by a manufacturer in connection with a request for type acceptance, it need not be submitted with the application for construction permit but may be referred to as "on file". Measurement data for type acceptance made in accordance with subparagraph (1) of this paragraph shall be submitted with the license application.

(3) A transmitter shown on an instrument of authorization by manufacturer and type number, or as a composite, and which was in use prior to June 30, 1955 may continue to be used by the licensee, his successors or assignees, provided such transmitter continues to comply with the rules and regulations.

(4) A permittee may, without further authority, install a transmitter other than that specifically authorized in its construction permit if such transmitter is listed in the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment" as acceptable for the transmitter output power authorized and, if operation under § 73.295 or § 73.297 is included, such transmitter is listed in the said "Radio Equipment List" as acceptable for the appropriate type of operation.

(5) A licensee may, without further authority, install and utilize a transmitter other than that specifically authorized in its station license if the transmitter so installed and utilized is listed in the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment" as acceptable for the transmitter output power authorized and, if operation under § 73.295 or § 73.297 is included, such transmitter is listed in the said "Radio Equipment List" as acceptable for the appropriate type of operation. In the event of such a transmitter substitution, the Commission and the Engineer in Charge of the radio district in which the station is located shall be notified within three days after the date of installation of the transmitter. Such notice shall specify the manufacturer and type number of the transmitter and shall include a certification by the licensee that the transmitter as installed complies with the appropriate technical provisions of this subpart.

(b) Additional rules with respect to withdrawal of type-acceptance, modification of type-accepted equipment and limitations on the findings upon which type acceptance is based are set forth in Part 2 of this chapter.

§ 73.252 Frequency monitor.

(a) The licensee of each station shall have in operation, either at the transmitter or at the place where the transmitter is controlled, a frequency monitor of a type approved by the Commission which shall be independent of the frequency control of the transmitter.

NOTE: Approved frequency monitors are included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment". Copies of this list are available for inspection at the Commission's office in Washington, D. C., and at each of its field offices.

(b) In the event that the frequency monitor becomes defective the station may be operated without the monitor pending its repair or replacement for a period not in excess of 60 days without further authority of the Commission: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the monitor was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the monitor is found to be defective and immediately after the repaired or replacement monitor has been installed and is functioning properly.

(3) The frequency of the station shall be compared with an external frequency source of known accuracy at sufficiently frequent intervals to insure that the frequency is maintained within the tolerance prescribed in § 73.269. An entry shall be made in the station log as to the method used and the results thereof.

(c) If conditions beyond the control of the licensee prevent the restoration of the monitor to service within the above allowed period, informal request in accordance with § 1.549 of this chapter may be filed with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

§ 73.253 Modulation monitor.

(a) The licensee of each station shall have in operation, either at the transmitter or at the place where the transmitter is controlled, a modulation monitor of the type approved by the Commission.

NOTE. Approved modulation monitors are included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment." Copies of this list are available for inspection at the Commission's office in Washington, D. C., and at each of its field offices.

(b) In the event that the modulation monitor becomes defective the station may be operated without the monitor pending its repair or replacement for a period not in excess of 60 days without further authority of the Commission: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the monitor was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the monitor is found to be defective and immediately after the repaired or replacement monitor has been installed and is functioning properly.

(3) During the period when the station is operated without the modulation monitor the licensee shall provide other suitable means for insuring that the modulation is maintained within the tolerance prescribed in § 73.268.

(c) If conditions beyond the control of the licensee prevent the restoration of the monitor to service within the above allowed period, informal request in accordance with § 1.549 of this chapter may be filed with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

§ 73.254 Required transmitter performance.

(a) The construction, installation, operation and performance of the FM broadcast transmitting system shall be in accordance with § 73.317.

(b) The licensee of each FM broadcast station shall make the following equipment performance measurements at least at yearly intervals. (One such set of measurements shall be made during the four-month period preceding the date of filing application for renewal of station license.)

(1) Audio frequency response from 50 to 15,000 cycles for approximately 25, 50 and 100 percent modulation. Measurements shall be made on at least the following audio frequencies: 50, 100, 400, 1000, 5000, 10,000 and 15,000 cycles. The frequency response measurements should normally be made without deemphasis; however, standard 75 microsecond deemphasis may be employed in the measuring equipment or system provided the accuracy of the deemphasis circuit is sufficient to insure that the measured response is within the prescribed limits.

(2) Audio frequency harmonic distortion for 25, 50 and 100 percent modulation for the fundamental frequencies of 50, 100, 400, 1000, and 5000 cycles. Audio frequency harmonics for 100 percent modulation for fundamental frequencies of 10,000 and 15,000 cycles. Measurements shall normally include harmonics to 30,000 cycles. The distortion measurements shall be made employing 75 microsecond deemphasis in the measuring equipment or system.

(3) Output noise level (frequency modulation) in the band of 50 to 15,000 cycles in decibels below the audio frequency level representing a frequency swing of 75 kilocycles. The noise measurements shall be made employing 75 microsecond deemphasis in the measuring equipment or system.

(4) Output noise level (amplitude modulation) in the band of 50 to 15,000 cycles in decibels below the level representing 100 percent amplitude modulation. The noise measurements shall be made employing 75 microsecond deemphasis in the measuring equipment or system. All measurements shall be made with the equipment adjusted for normal program operation and shall include all circuits between the main studio microphone terminals and the antenna output, including telephone lines, preemphasis circuits and any equalizers employed except for microphones, and without compression if a compression amplifier is installed.

(c) The data required by paragraph (b) of this section together with a description of instruments and procedure signed by the engineer making the measurements shall be kept on file at the transmitter and retained for a period of two years and shall be made available during that time upon request to any duly authorized representative of the Federal Communications Commission.

§ 73.255 Auxiliary transmitter.

Upon showing that a need exists for the use of an auxiliary transmitter in addition to the regular transmitter of an FM broadcast station, a license therefor may be issued: *Provided*, That:

(a) An auxiliary transmitter may be installed either at the same location as the main transmitter or at another location.

(b) A licensed operator shall be in control whenever an auxiliary transmitter is placed in operation.

(c) The auxiliary transmitter shall be maintained so that it may be put into immediate operation at any time for the following purposes:

(1) The transmission of the regular programs upon the failure of the main transmitter.

(2) The transmission of regular programs during maintenance or modification work on the main transmitter, necessitating discontinuance of its operation for a period not to exceed 5 days. (This includes the equipment changes which may be made without authority as set forth elsewhere in the rules and regulations or as authorized by the Commission by letter or by construction permit. Where such operation is required for periods in excess of 5 days, request therefor shall be in accordance with § 1.542 of this chapter.)

(3) Upon request by a duly authorized representative of the Commission.

(d) The auxiliary transmitter shall be tested at least once each week to determine that it is in proper operating condition and that it is adjusted to the proper frequency, except that in the case of operation in accordance with paragraph (c) of this section during any week, the test in that week may be omitted provided the operation under paragraph (c) of this section is satisfactory. Tests shall be conducted only between midnight and 6 a. m., local standard time. A record shall be kept of the time and result of each test. Such records shall be retained for a period of two years.

(e) The auxiliary transmitter shall be equipped with satisfactory control equipment which will enable the maintenance of the frequency emitted by the station within the limits prescribed by the regulations in this part.

(f) The operating power of an auxiliary transmitter may be less than the authorized power of the main transmitter, but in no event shall it be greater than such power.

§ 73.256 Alternate main transmitters.

The licensee of an FM broadcast station may be licensed for alternate main transmitters provided that a technical need for such alternate transmitters is shown (such as licensees maintaining 24-hour schedule and needing alternate operation for maintenance, or where developmental work requires alternate operation) and that the following conditions are met:

(a) Both transmitters are located at the same place.

(b) Both transmitters shall have the same power rating.

(c) Both transmitters shall meet the construction, installation, operation, and performance requirements of § 73.317.

§ 73.257 Changes in equipment and antenna system.

Licensees of FM broadcast stations shall observe the following provisions with regard to changes in equipment and antenna system:

(a) No changes in equipment shall be made:

(1) That would result in the emission of signals outside of the authorized channel.

(2) That would result in the external performance of the transmitter being in disagreement with that prescribed in § 73.317.

(b) Specific authority, upon filing formal application (FCC Form 301) therefor, is required for a change in service area or for any of the following changes:

(1) Changes involving an increase or decrease in the power rating of the transmitter.

(2) A replacement of the transmitter as a whole.

(3) Change in the location of the transmitting antenna.

(4) Change in antenna system, including transmission line.

(5) Change in location of main studio, if it is proposed to move the main studio to a different city from that specified in the license.

(6) Change in the power delivered to the antenna.

(7) Change in frequency control and/or modulation system.

(8) Change in the authorized transmitter remote control point(s).

(c) Other changes, except as above provided for in this section or in the Technical Standards of this subpart, may be made at any time without the authority of the Commission: *Provided*, That the Commission shall be promptly notified thereof and such changes shall be shown in the next application for renewal of license.

§ 73.258 Indicating instruments.

(a) Each FM broadcast station shall be equipped with indicating instruments, which conform with the specifications set forth in § 73.320, for measuring the direct plate voltage and current of the last radio stage and the transmission line radio frequency current, voltage or power.

(b) In the event that any one of these indicating instruments becomes defective when no substitute which conforms with the required specifications is available, the station may be operated without the defective instrument pending its repair or replacement for a period not in excess of 60 days: *Provided*, That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the meter was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified immediately after the instrument is found to be defective and immediately after the repaired or replaced instrument has been installed and functioning properly.

(3) If the defective instrument is a plate voltmeter or plate ammeter in the last radio stage, the operating power shall be maintained by means of the radio frequency transmission line meter.

(c) If conditions beyond the control of the licensee prevent the restoration of the meter to service within the above allowed period, informal request may be filed in accordance with § 1.549 of this chapter with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

TECHNICAL OPERATION AND OPERATORS

§ 73.261 Time of operation.

(a) All FM broadcast stations will be licensed for unlimited time operation. A minimum of 36 hours per week during the hours of 6 a.m. to midnight, consisting of not less than 5 hours in any one day, except Sunday, must be devoted to the FM broadcast operation; time devoted to operations conducted pursuant to a Subsidiary Communications Authorization (see §§ 73.293 to 73.295) shall not be included in meeting this 36-hour broadcast requirement.

(b) In the event that causes beyond a licensee's control make it impossible to adhere to the operating schedule in paragraph (a) of this section or to continue operating, the station may limit or discontinue operation for a period of not more than 10 days, without further authority of the Commission. However, the Commission and the Engineer in Charge of the radio district in which the station is located shall be immediately notified in writing if the station is unable to maintain the minimum operating schedule and shall be subsequently notified when the station resumes regular operation.

§ 73.262 Experimental operation.

The period between 1:00 a.m., and 6:00 a.m., local standard time, may be used for experimental purposes in testing and maintaining apparatus by the licensee of any FM broadcast station on its assigned frequency and not in excess of its authorized power, without specific authorization by the Commission.

§ 73.263 Station inspection.

The licensee of any FM broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 73.264 Station and operator licenses; posting of.

(a) The station license and any other instrument of station authorization shall be posted in a conspicuous place and in such manner that all terms are visible, at the place the licensee considers to be the principal control point of the transmitter. At all other control points listed on the station authorization, a photocopy of the station license and other instruments of station authorization shall be posted.

(b) The original operator license, or FCC Form 759, of each station operator shall be posted at the place where he is on duty as an operator.

§ 73.265 Operator requirements.

(a) One or more radio operators holding a valid radiotelephone first-class operator license, except as provided in paragraph (b) of this section, shall be in actual charge of the transmitting apparatus and shall be on duty either at the transmitter location or remote control point.

(b) In cases where a station is authorized to operate with a transmitter power output not in excess of 25 kilowatts, the routine operation of the transmitter may be performed by an operator holding a valid first-class or second-class radiotelephone or radiotelegraph operator license or a radiotelephone third-class operator permit which has been endorsed for broadcast station operation. The operator shall be on duty at the transmitter or authorized remote control point and in actual charge thereof. Until April 19,1964, routine operation of transmitters of such stations may be performed by persons holding valid radiotelephone operator third-class permits which are not endorsed for broadcast station operation, or valid restricted radiotelephone operator permits. Except at times when the operation of the station is under the immediate supervision of an operator holding a valid radiotelephone first-class operator license, adjustments of the transmitter shall be limited to the following:

(1) Those necessary to turn the transmitter on and off.

(2) Adjustments of external controls as may be necessary to compensate for voltage fluctuations in the power supply.

(3) Adjustments of external controls to maintain modulation of the transmitter within prescribed limits.

It shall be the responsibility of the licensee to insure that the person who may be required to perform these tasks as well as to perform other duties (such as reading meters and making log entries), is properly instructed so as to be capable of performing the duties required of him at times when not under the immediate supervision of a radiotelephone first-class operator. Where necessary, printed step-by-step instructions shall be posted for those transmitter adjustments which the lesser grade operator is authorized to make. Should the transmitting apparatus be observed to be operating in any manner inconsistent with this subpart or the station's instrument of authorization at any time when an operator holding a valid radiotelephone first-class operator license is not immediately available, and none of the above adjustments is effective in correcting the condition of improper operation, the emissions of the station shall be immediately terminated.

(c) If the routine operation of the transmitting apparatus at an FM broadcast station is performed by an operator other than a radiotelephone first-class operator pursuant to the provisions of paragraph (b) of this section, the licensee shall either employ one or more operators holding a valid radiotelephone first-class operator license as a full-time member of the station staff or, in the alternative, contract in writing for the services on a part-time basis of one or more such operators. The radiotelephone first-class operator or operators shall perform transmitter maintenance and shall be promptly available at all times to correct conditions of improper operation beyond the scope of authority of the lesser grade operator on duty. If such services are on a contract part-time basis, a signed copy of the agreement shall be kept in the files of the station and at the transmitter or control point and shall be made available for inspection upon request by any authorized representative of the Commission. A signed copy of the agreement shall also be forwarded to the Commission and to the Engineer in Charge of the radio district in which the station is located within 3 days after the agreement is signed.

NOTE: During the period prior to April 19, 1964, the alternative of contracting in writing for the services of radiotelephone first-class operators on a part-time basis may not be followed unless the routine transmitter operation under the provisions of paragraph (b) of this section is performed by operators holding at least valid radiotelephone third-class operator permits which have been endorsed for broadcast station operation. Information concerning examinations for such operator permits will be available to all applicants through the Commission's field offices after January 1, 1964.

(d) The licensed operator on duty and in charge of an FM broadcast transmitter may at the discretion of the licensee, be employed for other duties or for the operation of another radio station or stations in accordance with the class of operator's license which he holds and the rules and regulations governing such other stations: *Provided, however,* That such duties shall in nowise interfere with the proper operation of the FM broadcast transmitter.

(e) At all FM broadcast stations, a complete inspection of all transmitting equipment in use shall be made by an operator holding a valid radiotelephone first-class operator license at least once each day, five days each week, with an interval of no less than 12 hours between successive inspections. This inspection shall include such tests, adjustments, and repairs as may be necessary to insure operation in conformance with the provisions of this subpart and the current instrument of authorization for the station.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318.)

§ 73.266 Facsimile broadcasting and multiplex transmission.

(a) FM broadcast stations may transmit simplex facsimile in accordance with transmission standards set forth in § 73.318 during periods not devoted to FM aural broadcasting. Such transmissions may not exceed one hour during the period between 7 a.m. and mid-

night (no limit for the hours between midnight and 7 a.m.) and may not be counted toward the minimum operation required by § 73.261. The Commission shall be notified by the licensee of the FM broadcast station of its intent to transmit such facsimile.

(b) FM broadcast stations may, upon securing authorization from the Commission, transmit multiplex facsimile in accordance with transmission standards set forth in § 73.318: *Provided,* That the transmission of such facsimile does not reduce the quality of aural programs simultaneously transmitted by the licensee below that required by the Technical Standards of this subpart and that no degradation of such aural programs will result from such facsimile transmissions when received on FM receivers not equipped with filter or other additional equipment.

§ 73.267 Operating power; determination and maintenance of.

(a) *Determination.* The operating power of each station shall be determined by either the direct or indirect method.

(1) Using the direct method, the power shall be measured at the output terminals of the transmitter while operating into a dummy load of substantially zero reactance and a resistance equal to the transmission line characteristic impedance. The transmitter shall be unmodulated during this measurement. If electrical devices are used to determine the power output, such devices shall permit determination of this power to within an accuracy of ±5 percent of the power indicated by the full scale reading of the electrical indicating instrument of the device. If temperature and coolant flow indicating devices are used to determine the power output, such devices shall permit determination of this power to within an accuracy of 4 percent of measured average power output. During this measurement the direct plate voltage and current of the last radio stage and the transmission line meter shall be read and compared with similar readings taken with the dummy load replaced by the antenna. These readings shall be in substantial agreement.

(2) Using the indirect method, the operating power is the product of the plate voltage (E_p) and the plate current (I_p) of the last radio stage, and an efficiency factor, F, as follows:

$$\text{Operating power} = E_p \times I_p \times F$$

(3) The efficiency factor, F, shall be established by the transmitter manufacturer for each type of transmitter for which he submits data to the Commission, over the entire operating range of powers for which the transmitter is designed, and shall be shown in the instruction books supplied to the customer with each transmitter. In the case of composite equipment, the factor F shall be furnished to the Commission with a statement of the basis used in determining such factor.

(b) *Maintenance.* (1) The operating power shall be maintained as near as practicable to the authorized power and shall not be less than 90 percent nor greater than 105 percent of authorized power except as indicated in paragraph (c) of this section.

(2) When determined by the direct method, the operating power of the transmitter shall be monitored by a transmission line meter which reads proportional to the voltage, current, or power at the output terminals of the transmitter, the meter to be calibrated at intervals not exceeding 6 months. The calibration shall cover, as a minimum, the range from 90 to 105 percent of authorized power and the meter shall provide clear indications which will permit maintaining the operating power within the prescribed tolerance or the meter shall be calibrated to read directly in power units.

(c) *Reduced power.* In the event it becomes technically impossible to operate with authorized power, the station may be operated with reduced power for a period of 10 days or less without further authority of the Commission: *Provided,* That the Commission and the Engineer in Charge of the radio district in which the station is located shall be immediately notified in writing if the station is unable to maintain the minimum operating schedule (specified in § 73.261) with authorized power and shall be subsequently notified upon resumption of operation with authorized power.

§ 73.268 Modulation.

The percentage of modulation of FM broadcast stations shall be maintained as high as possible consistent with good quality of transmission and good broadcast practice and in no case less than 85 percent nor more than 100 percent on peaks of frequent recurrence during any selection which normally is transmitted at the highest level of the program under consideration.

§ 73.269 Frequency tolerance.

The center frequency of each FM broadcast station shall be maintained within 2000 cycles of the assigned center frequency.

§ 73.270 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marketing and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of that part.

§ 73.271 Discontinuance of operation.

The licensee of each station shall notify the Commission in Washington, D.C., and the Engineer in Charge of the radio district where such station is located of permanent discontinuance of operation at least two days before operation is discontinued. The licensee shall, in addition, immediately forward the station license and other instruments of authorization to the Washington, D.C., office of the Commission for cancellation.

§ 73.273 Emergency antenna.

In the event it becomes impossible to operate with the regularly authorized antenna, the station may, without further authority, be operated with an emergency antenna for a period of 10 days or less pending necessary repairs: *Provided,* That the Commission and the Engineer in Charge of the radio district in which the station is located shall be notified in writing immediately upon the beginning of such operation and upon the resumption of normal operation.

§ 73.274 Remote control authorization.

(a) Application to operate a station by remote control may be made as a part of the application for construction permit for a new station. Application to operate an authorized station shall be made on FCC Form 301–A.

(b) An authorization for remote control will be issued only after a satisfactory showing has been made in regard to the following, among others:

(1) The location of the remote control point(s);

(2) The transmitter, if the power rating is in excess of 10 kw, is reliable and capable of being operated by remote control.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 73.275 Remote control operation.

(a) Operation by remote control shall be subject to the following conditions:

(1) The equipment at the operating and transmitting positions shall be so installed and protected that it is not accessible to or capable of operation by persons other than those duly authorized by the licensee.

(2) The control circuits from the operating position to the transmitter shall provide positive on and off control and shall be such that open circuits, short circuits, grounds or other line faults will not actuate the transmitter and any fault causing loss of such control will automatically place the transmitter in an inoperative position.

(3) A malfunction of any part of the remote control equipment and associated line circuits resulting in improper control or inaccurate meter readings shall be the cause for the immediate cessation of operation by remote control.

(4) Control and monitoring equipment shall be installed so as to allow the licensed operator at the remote control point to perform all the functions in a manner required by the provisions of this part.

(b) All stations, whether operating by remote control or direct control, shall be equipped so as to be able to follow the prescribed procedure set forth in § 73.921(b).

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

Other Operating Requirements

§ 73.281 General requirements relating to logs.

(a) The licensee or permittee of each FM broadcast station shall maintain program, operating, and maintenance logs as set forth in §§ 73.282, 73.283, and 73.284. Each log shall be kept by the person or persons competent to do so, having actual knowledge of the facts required, who shall sign the appropriate log when starting duty and again when going off duty.

(b) The logs shall be kept in an orderly and legible manner, in suitable form, and in such detail that the data required for the particular class of station concerned is readily available. Key letters or abbreviations may be used if proper meaning or explanation is contained elsewhere in the log. Each sheet shall be numbered and dated. Time entries shall be either in local standard or daylight saving time and shall be indicated accordingly.

(c) No log or portion thereof shall be erased, obliterated, or willfully destroyed within the priod of retention provided by the provisions of this part. Any necessary correction may be made only by the person originating the entry who shall strike out the erroneous portion, initial the correction made, and indicate the date of correction.

(d) Original data may be recorded in rough form and later transcribed into the log, but in such case all portions of the original memoranda shall be preserved as a part of the complete log.

§ 73.282 Program log.

(a) The following entries shall be made in the program log:

(1) An entry of the time each station identification announcement (call letters and location) is made.

(2) An entry briefly describing each program broadcast, such as "music," "drama," "speech," etc., together with the name or title thereof and the sponsor's name, with the time of the beginning and ending of the complete program. If a mechanical record is used, the entry shall show the exact nature thereof, such as "record," "transcription," etc., and the time it is announced as a mechanical reproduction. If a speech is made by a political candidate, the name and political affiliations of such speaker shall be entered.

(3) An entry showing that each sponsored program broadcast has been announced as sponsored, paid for, or furnished by the sponsor.

(4) An entry showing, for each program of network origin, the name of the network originating the program.

(b) No provision of this section shall be construed as prohibiting the recording or other automatic maintenance of data required for program logs. However, where such automatic logging is used, the licensee must comply with the following requirements:

(1) The licensee, whether employing manual or automatic logging or a combination thereof, must be able accurately to furnish the Commission with all information required to be logged;

(2) Each recording, tape, or other means employed shall be accompanied by a certificate of the operator or other responsible person on duty at the time or other duly authorized agent of the licensee, to the effect that it accurately reflects what was actually broadcast. Any information required to be logged which cannot be incorporated in the automatic process shall be maintained in a separate record which shall be similarly authenticated;

(3) The licensee shall extract any required information from the recording for the days specified by the Commission or its duly authorized representative and submit it in written log form together with the underlying recording, tape or other means employed.

§ 73.283 Operating log.

(a) The following entries shall be made in the operating log:

(1) An entry of the time the station begins to supply power to the antenna and the time it stops.

(2) An entry of each interruption of the carrier wave, where restoration is not automatic, its cause and duration followed by the signature of the person restoring operation (if licensed operator other than the licensed operator on duty).

(3) An entry, at the beginning of operation and at intervals not exceeding one-half hour, of the following (actual readings observed prior to making any adjustments to the equipment) and, when appropriate, an indication of corrections made to restore parameters to normal operating values:

(i) Operating constants of last radio stage (total plate voltage and plate current).

(ii) RF transmission line meter reading.

(iii) Frequency monitor reading.

(4) Any other entries required by the instrument of authorization or the provisions of this part.

(b) Automatic devices accurately calibrated and with appropriate time, date and circuit functions may be utilized to record the entries in the operating log: *Provided,* That:

(1) They do not effect the operation of circuits or accuracy of indicating instruments of the equipment being recorded;

(2) The recording devices have an accuracy equivalent to the accuracy of the indicating instruments;

(3) The calibration is checked against the original indicators at least once a week and the results noted in the maintenance log;

(4) Provision is made to actuate automatically an aural alarm circuit located near the operator on duty if any of the automatic log readings are not within the tolerances or other requirements specified in the rules or instrument of authorization;

(5) Unless the alarm circuit operates continuously, devices which record each parameter in sequence must read each parameter at least once during each 10-minute period and clearly indicate the parameter being recorded;

(6) The automatic logging equipment is located at the remote control point if the transmitter is remotely controlled or at the transmitter location if the transmitter is manually controlled;

(7) The automatic logging equipment is located in the near vicinity of the operator on duty and inspected by him periodically during the broadcast day; and

(8) The indicating equipment conforms to the requirements of § 73.320 except that the scales need not exceed 2 inches in length. Arbitrary scales may not be used.

§ 73.284 Maintenance log.

The following entries shall be made in the maintenance log:

(a) An entry each week of the time and result of test of auxiliary transmitter.

(b) A notation of all frequency checks and measurements made independently of the frequency monitor and of the correlation of these measurements with frequency monitor indications.

(c) A notation each week of the calibration check of automatic recording devices as required by § 73.283(b)(3).

(d) An entry of the date and time of removal from and restoration to service of any of the following equipment in the event it becomes defective;

(1) Modulation monitor.

(2) Frequency monitor.

(3) Final stage plate voltmeter.

(4) Final stage plate ammeter.

(5) Transmission line radio frequency voltage, current, or power meter.

(e) Record of tower light inspections where required by § 17.38 of this chapter (Part 17—Construction, Marking, and Lighting of Antenna Structures).

(f) Entries shall be made so as to describe fully any experimental operation during the experimental period.

(g) Upon completion of the inspection required by § 73.265(e), the inspecting operator shall enter a signed statement that the required inspection has been made, noting in detail the tests, adjustments, and repairs which were accomplished in order to insure operation in accordance with the provisions of this subpart and the current instrument of authorization of the station. The statement shall also specify the amount of time, exclusive of travel time to and from the transmitter, which was devoted to such inspection duties. If complete repair could not be effected, the statement shall set forth in detail the items of equipment concerned, the manner and degree in which they are defective, and the reasons for failure to make satisfactory repairs.

(h) Any other entries required by the current instrument of authorization of the station and the provisions of this subpart.

§ 73.285 Retention of logs.

Logs of FM broadcast stations shall be retained by the licensee or permittee for a period of 2 years: *Provided, however,* That logs involving communications incident to a disaster or which include communications incident to or involved in an investigation by the Commission and concerning which the licensee or permittee has been notified, shall be retained by the licensee or permittee until he is specifically authorized in writing by the Commission to destroy them: *Provided, further,* That logs incident to or involved in any claim or complaint of which the licensee or permittee has notice shall be retained by the licensee or permittee until such claim or complaint has been fully satisfied or until the same has been barred by statute limiting the time for the filing of suits upon such claims.

§ 73.286 Availability of logs and records.

The following shall be made available upon request by an authorized representative of the Commission:

(a) Program, operating and maintenance logs.

(b) Equipment performance measurements required by § 73.254.

§ 73.287 Station identification.

(a) A licensee of an FM broadcast station shall make separate station identification announcement (call letters and location) for such station: *Provided, however,* That, if the same licensee operates an FM broadcast station and a standard broadcast station and simultaneously broadcasts the same programs over the facilities of both such stations, station identification announcements may be made jointly for both stations for periods of such simultaneous operation. If the call letters of the FM station do not clearly reveal that it is an FM station, the joint announcement shall state that one of the stations is an FM station. Station identification announcement shall be made at the beginning and ending of each time of operation and during operation (1) on the hour and (2) either on the half hour or at the quarter hour following the hour and at the quarter hour preceding the next hour: *Provided,*

(b) Such identification announcement need not be made on the hour when to make such announcement would interrupt a single consecutive speech, play, religious service, symphony concert, or operatic production of longer duration than 30 minutes. In such cases the identification announcement shall be made at the beginning of the program, at the first interruption of the entertainment continuity, and at the conclusion of the program.

(c) Such identification announcement need not be made on the half hour or quarter hours when to make such announcement would interrupt a single consecutive speech, play, religious service, symphony concert, or operatic production. In such cases an identification announcement shall be made at the first interruption of the entertainment continuity and at the conclusion of the program: *Provided,* That an announcement within 5 minutes of the times specified in paragraph (a) (2) of this section will satisfy the requirements of identification announcements.

(d) In the case of variety show programs, baseball game programs or similar programs of longer duration than 30 minutes, the identification announcement shall be made within 5 minutes of the hour and of the times specified in paragraph (a) (2) of this section.

(e) In the case of all other programs, the identification announcement shall be made within 2 minutes of the hour and of the times specified in paragraph (a) (2) of this section.

(f) In making the identification announcement the call letters shall be given only on the channel of the station identified thereby except as otherwise provided herein.

§ 73.288 Mechanical reproductions.

(a) No mechanically reproduced program consisting of a speech, news event, news commentator, forum, panel discussion, or special event in which the element of time is of special significance, or any other program in which the element of time is of special significance and presentation of which would create, either intentionally or otherwise, the impression or belief on the part of the listening audience that the event or program being broadcast is in fact occurring simultaneously with the broadcast, shall be broadcast without an appropriate announcement being made either at the beginning or end of such reproduction or at the beginning or end of the program in which such reproduction is used that it is a mechanical reproduction or a mechanically reproduced program: *Provided, however,* That each such program of one minute or less need not be announced as such.

(b) The exact form of identifying announcement is not prescribed, but the language shall be clear and in terms commonly used and understood. Any other program mechanically reproduced or series of mechanical reproductions, including a mechanical reproduction used for background music, sound effects, station identification, program identification (theme music of short duration) or identification of sponsorship of the program proper, need not be announced as provided in paragraph (a) of this section, but the licensee shall not attempt affirmatively to create the impression that any program being broadcast by mechanical reproduction consists of live talent.

(c) The requirements of paragraph (a) of this section are waived with respect to network programs, transcribed and rebroadcast at a later hour because of the time zone differential between the place where the program originates and where it is rebroadcast, this waiver being applicable whether the off-the-line recording is made by the network itself at one of its key stations or by an individual station, but only when the off-the-line recording is for broadcast at an hour not exceeding the time zone differential between the place where the program originates and where it is rebroadcast. Each station which broadcasts network programs at a later hour in accordance with this waiver shall make an appropriate announcement at least once each day between the hours of 10:00 a. m., and 10:00 p. m., stating that some or all of the network programs which are broadcast by that station are delayed broadcasts by means of transcription. This waiver provision also applies during the annual periods in which daylight saving time will be effective with respect to network programs transcribed and rebroadcast one hour later because of the time differential resulting from the adoption of daylight saving time in some areas.

§ 73.289 Sponsored programs, announcement of.

(a) When an FM broadcast station transmits any matter for which money, services, or other valuable consideration is either directly or indirectly paid or promised to, or charged or received by, such station, the station shall broadcast an announcement that such matter is sponsored, paid for, or furnished, either in whole or in part, and by whom or on whose behalf such consideration was supplied: *Provided, however,* That "service or other valuable consideration" shall not include any service or property furnished without charge or at a nominal charge for use on, or in connection with, a broadcast unless it is so furnished in consideration for an identification in a broadcast of any person, product, service, trademark, or brand name beyond an identifiation which is reasonably related to the use of such service or property on the broadcast.

(b) The licensee of each FM broadcast station shall exercise reasonable diligence to obtain from its employees, and from other persons with whom it deals directly in connection with any program matter for broadcast, information to enable such licensee to make the announcement required by this section.

(c) In any case where a report (concerning the providing or accepting of valuable consideration by any person for inclusion of any matter in a program intended for broadcasting) has been made to an FM broadcast station, as required by section 508 of the Communications Act of 1934, as amended, of circumstances which would have required an announcement under this section had the consideration been received by such FM broadcast station, an appropriate announcement shall be made by such station.

(d) In the case of any political program or any program involving the discussion of public controversial issues for which any records, transcriptions, talent, scripts, or other material or services of any kind are furnished, either directly or indirectly, to a station as an inducement to the broadcasting of such program, an announcement shall be made both at the beginning and conclusion of such program on which such material or services are used that such records, transcriptions, talent, scripts, or other material or services have been furnished to such station in connection with the broadcasting of such program: *Provided, however,* That only one such announcement need be made in the case of any such program of 5 minutes' duration or less, which announcement may be made either at the beginning or conclusion of the program.

(e) The announcement required by this section shall fully and fairly disclose the true identity of the person or persons by whom or in whose behalf such payment is made or promised, or from whom or in whose behalf such services or other valuable consideration is received or by whom the material or services referred to in paragraph (d) of this section are furnished. Where an agent or other person contracts or otherwise makes arrangements with a station on behalf of another, and such fact is known to the station, the announcement shall disclose the identity of the person or persons in whose behalf such agent is acting instead of the name of such agent.

(f) In the case of any program, other than a program advertising commercial products or services, which is sponsored, paid for, or furnished, either in whole or in part, or for which material or services referred to in paragraph (d) of this section are furnished, by a corporation, committee, association, or other unincorporated group, the announcement required by this section shall disclose the name of such corporation, committee, association, or other unincorporated group. In each such case the station shall require that a list of the chief executive officers or members of the executive committee or of the board of directors of the corporation, committee, association or other unincorporated group shall be made available for public inspection at the studios or general offices of one of the FM broadcast stations carrying the program in each community in which the program is broadcast.

(g) In the case of broadcast matter advertising commercial products or services, an announcement stating the sponsor's corporate or trade name, or the name of the sponsor's product, when it is clear that the mention of the name of the product constitutes a sponsorship identification, shall be deemed sufficient for the purposes of this section and only one such announcement need be made at any time during the course of the program.

(h) Commission interpretations in connection with the foregoing rules may be found in the Commission's Public Notice entitled "Applicability of Sponsorship Identification Rules" (FCC 63-409; 28 F.R. 4732, May 10, 1963) and such supplements thereto as are issued from time to time.

(Sec. 317, 48 Stat. 1089, as amended; 47 U.S.C. 317)

§ 73.290 Broadcasts by candidates for public office.

(a) *Definitions.* A "legally qualified candidate" means any person who has publicly announced that he is a candidate for nomination by a convention of a political party or for nomination or election in a primary, special, or general election, municipal, county, state or national, and who meets the qualifications prescribed by the applicable laws to hold the office for which he is a candidate, so that he may be voted for by the electorate directly or by means of delegates or electors, and who—

(1) Has qualified for a place on the ballot or

(2) Is eligible under the applicable law to be voted for by sticker, by writing in his name on the ballot, or other method, and (i) has been duly nominated by a political party which is commonly known and regarded as such, or (ii) makes a substantial showing that he is a bona fide candidate for nomination or office, as the case may be.

(b) *General requirements.* No station licensee is required to permit the use of its facilities by any legally qualified candidate for public office, but if any licensee shall permit any such candidate to use its facilities, it shall afford equal opportunities to all other such candidates for that office to use such facilities: *Provided,* That such licensee shall have no power of censorship over the material broadcast by any such candidate.

(c) *Rates and practices.* (1) The rates, if any, charged all such candidates for the same office shall be uniform and shall not be rebated by any means direct or indirect. A candidate shall, in each case, be charged no more than the rate the station would charge if the candidate were a commercial advertiser whose advertising was directed to promoting its business within the same area as that encompassed by the particular office for which such person is a candidate. All discount privileges otherwise offered by a station to commercial advertisers shall be available upon equal terms to all candidates for public office.

(2) In making time available to candidates for public office no licensee shall make any discrimination between candidates in charges, practices, regulations, facilities, or services for or in connection with the service rendered pursuant to this part, or make or give any preference to any candidate for public office or subject any such candidate to any prejudice or disadvantage; nor shall any licensee make any contract or other agreement which shall have the effect of permitting any legally qualified candidate for any public office to broadcast to the exclusion of other legally qualified candidates for the same public office.

(d) *Inspection of records.* Every licensee shall keep and permit public inspection of a complete record of all requests for broadcast time made by or on behalf of candidates for public office, together with an appropriate notation showing the disposition made by the licensee of such requests, and the charges made, if any, if request is granted. Such records shall be retained for a period of two years.

(e) *Time of request.* A request for equal opportunities must be submitted to the licensee within one week of the day on which the prior use occurred.

(f) *Burden of proof.* A candidate requesting such equal opportunities of the licensee, or complaining of non-compliance to the Commission shall have the burden of proving that he and his opponent are legally qualified candidates for the same public office.

(Sec. 315, 48 Stat. 1088, as amended; 47 U.S.C. 315)

§ 73.291 Rebroadcast.

(a) The term "rebroadcast" means reception by radio of the program of a radio station, and the simultaneous or subsequent retransmission of such program by a broadcast station.

NOTE 1: As used in this section, program includes any complete program or part thereof.

NOTE 2: In case a program is transmitted from its point of origin to a broadcast station entirely by telephone facilities in which a section of such transmission is by radio, the broadcasting of this program is not considered a rebroadcast.

(b) The licensee of an FM broadcast station may, without further authority of the Commission, rebroadcast the program of a United States standard, FM or noncommercial educational FM broadcast station, provided the Commission is notified of the call letters of each station rebroadcast and the licensee certifies that express authority has been received from the licensee of the station originating the program. The foregoing requirements concerning notification of call letters and certification of authority shall not apply to a station when rebroadcasting Defense Network (FM) programs. (Blanket authorizations for the rebroadcast of such programs have been filed with the Commission by all Defense Network (FM) stations.)

NOTE: The notice and certification of consent shall be given within 3 days of any single rebroadcast, but in case of the regular practice of rebroadcasting certain programs of a standard or FM broadcast station several times during a license period, notice and certification of consent shall be given for the ensuing license period with the application for renewal of license, or at the beginning of such rebroadcast practice if begun during a license period.

(c) (1) The licensee of an FM broadcast station located within a State or the District of Columbia may, without further authority of the Commission, rebroadcast on a noncommercial basis a noncommercial program of a United States international broadcast station.

(2) The licensee of an FM broadcast station located in any territory or insular possession of the United States may, without further authority of the Commission, rebroadcast any program of a United States international broadcast station.

(3) In the case of any rebroadcast under the provisions of this paragraph, the Commission shall be notified of the call letters of each station whose program is rebroadcast and the licensee shall certify that express authority has been received from the licensee of the station originating the program.

(d) No licensee of an FM broadcast station shall rebroadcast the program of any United States radio station not designated in paragraph (b) or (c) of this section without written authority having first been obtained from the Commission upon application (informal) accompanied by written consent or certification of consent of the licensee of the station originating the program.

NOTE 1: The broadcasting of a program relayed by a remote pickup broadcast station or an ST broadcast station is not considered a rebroadcast.

NOTE 2: By Order No. 82, dated and effective June 24, 1941, until further order of the Commission, § 73.291(d) is suspended only insofar as it requires prior written authority of the Commission for the rebroadcasting of programs originated for that express purpose by United States Government radio stations.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

§ 73.292 Lotteries.

(a) An application for construction permit, license, renewal of license, or any other authorization for the operation of a broadcast station, will not be granted where the applicant proposes to follow or continue to follow a policy or practice of broadcasting or permitting "the broadcasting of, any advertisement of or information concerning any lottery, gift enterprise, or similar scheme, offering prizes dependent in whole or in part upon lot or chance, or any list of the

prizes drawn or awarded by means of any such lottery, gift enterprise, or scheme, whether said list contains any part or all of such prizes." (See 18 U.S.C. 1304.)

(b) The determination whether a particular program comes within the provisions of paragraph (a) of this section depends on the facts of each case. However, the Commission will in any event consider that a program comes within the provisions of paragraph (a) of this section if in connection with such program a prize consisting of money or thing of value is awarded to any person whose selection is dependent in whole or in part upon lot or chance, if as a condition of winning or competing for such prize, such winner or winners are required to furnish any money or thing of value or are required to have in their possession any product sold, manufactured, furnished or distributed by a sponsor of a program broadcast on the station in question.

(Sec. 1304, 62 Stat. 763, 18 U.S.C. 1304)

§ 73.293 Subsidiary communications authorizations.

(a) A FM broadcast licensee or permittee may apply for a Subsidiary Communications Authorization (SCA) to provide limited types of subsidiary services on a multiplex basis. Permissible uses must fall within one or both of the following categories:

(1) Transmission of programs which are of a broadcast nature, but which are of interest primarily to limited segments of the public wishing to subscribe thereto. Illustrative services include: background music; storecasting; detailed weather forecasting; special time signals; and other material of a broadcast nature expressly designed and intended for business, professional, educational, religious, trade, labor, agricultural or other groups engaged in any lawful activity.

(2) Transmission of signals which are directly related to the operation of FM broadcast stations; for example: relaying of broadcast material to other FM and standard broadcast stations; remote cueing and order circuits; remote control telemetering functions associated with authorized STL operation, and similar uses.

(b) Applications for Subsidiary Communications Authorizations shall be submitted on FCC Form 318. An applicant for SCA shall specify the particular nature or purpose of the proposed use.

(c) SCA operations may be conducted without restriction as to time so long as the main channel is programmed simultaneously.

§ 73.294 Nature of the SCA.

(a) The SCA is of a subsidiary or secondary nature and shall not exist apart from the FM license or permit. No transfer or assignment of it shall be made separate from the FM broadcast license, and failure to transfer the SCA (through application on FCC Form 318) with the FM license or permit renders the SCA void. The licensee or permittee must seek renewal of the SCA (on FCC Form 318) at the same time it applies for its renewal of FM license or permit; failure to renew the latter automatically terminates the SCA.

(b) The grant or renewal of an FM license or permit shall not be furthered or promoted by the proposed or past operation under an SCA; the licensee must establish that his broadcast operation is in the public interest wholly apart from the SCA activities. (Violation of rules applicable to the SCA operation would, of course, reflect on the licensee's qualifications to hold its broadcast license or permit.)

§ 73.295 Operation under the SCA.

(a) The SCA holder must restrict its operation to the uses or purposes granted by the Commission in acting upon his application; prior permission to engage in any additional or new activity must be obtained from the Commission.

(b) Supersonic tones or other similar devices may be employed with respect to material transmitted during the SCA operation in order to promote or maintain its commercial marketability, with the station using appropriate actuating devices with the subscribers' receivers.

(c) In all arrangements entered into under the SCA with outside parties, the licensee or permittee must pass on all material to be transmitted over the station's facilities, with the right to reject any material which it deems inappropriate or undesirable; when the SCA operation is conducted on a simplex basis, the licensee must be able, through appropriate contractual arrangement, to substitute a broadcast program at any time it deems it in the public interest to do so.

(d) The requirements of §§ 73.290 and 73.291 are equally applicable when the FM licensee or permittee is engaged in operations pursuant to the SCA.

(e) The requirements of § 73.287 with respect to station identification announcements must be met by identification on the main carrier when a station is engaged in SCA operations. The licensee may prevent their reception on subscribers' receivers through the use of supersonic tones capable of deactivating these specialized receivers.

(f) The requirements of §§ 73.288 and 73.289 are applicable to the SCA operation when the latter is conducted on a simplex basis; provided that the station may employ supersonic tones or other devices to prevent the reception of such announcements over subscribers' receivers. The requirement of § 73.289 shall be deemed to have been met by the SCA operator by the latter's announcement that the program is being transmitted for a fee to commercial subscribers.

(g) The FM licensee or permittee shall maintain logs for the SCA operations. In the program log, the following entries shall be made:

(1) An entry of the time each station identification announcement (call letters and location) is made.

(2) An entry describing the material transmitted in each hour segment. If a speech is made by a political candidate, the name and political affiliations of such speaker shall be entered.

(3) An entry showing that sponsorship and mechanical record announcements, when required under paragraph (f) of this section, have been made, and the time of the latter announcements.

(h) The requirements of § 73.281(b), (1)–(4), inclusive and (c), and §§ 73.282 to 73.286, inclusive, are equally applicable to logs to be maintained during the SCA operation.

(i) The requirements of § 73.265 with respect to operators and the provisions of § 73.274 relating to remote control operation are equally applicable to operation during the SCA period.

(j) The licensee must observe all technical rules and standards applicable to FM broadcast stations when conducting the SCA operation. (For criteria applicable to the multiplex SCA operation, see § 73.319.)

§ 73.296 Emergency Weather Warnings.

Upon receipt of notification from the United States Weather Bureau, of an Emergency Weather Warning of a condition of immediate danger to life and property, all FM broadcast stations may, at their option, broadcast Emergency Action Notification Signal (two 5-second carrier breaks and 15 seconds of 1,000 CPS tone) followed by the Emergency Weather Warning.

(Sec. 606, 48 Stat. 1104, as amended; 47 U.S.C. 606, E.O. 11092, 28 F.R. 1847.)

§ 73.297 Stereophonic broadcasting.

FM broadcast stations may, without further authority, transmit stereophonic programs in accordance with the technical standards set forth in § 73.322: *Provided, however,* That the Commission and the Engineer in Charge of the radio district in which the station is located shall be notified within 10 days from the installation of type-accepted stereophonic transmission equipment or any change therein, and: *Provided further,* That the Commission and the Engineer in Charge shall be notified within 10 days from the commencement of stereophonic operation, scheduled hours of such operation or any change therein.

§ 73.298 Operation during emergency.

(a) The licensee of an FM broadcast station or the permittee of such a station operating under program test authority is authorized only to disseminate radio communications intended to be received by the public. However, during a period of emergency or imminent emergency in the area in which the station is located such a licensee or permittee may also utilize its station for transmitting communications directly related to the emergency which are intended to be received by specific individuals for the purpose of dispatching aid, assisting in rescue operations or otherwise promoting the safety of life and property or alleviating hardship. In the course of such operation a station may communicate with stations of other classes and in other services. For the purposes of this section, an emergency shall mean a situation that would generally and seriously endanger life and property or cause substantial hardship as a result of events such as hurricane or other severe weather conditions, flood, earthquake or wide-area forest fire. The term shall not include situations resulting from

frosts, or localized fires which are not a source of general danger.

(b) The decision to operate under the provisions of this section lies solely with the licensee or permittee of the station, requests by governmental or other officials not being controlling. However, such emergency operation shall terminate upon order of the Commission.

(c) When engaged in operation under the provisions of this section a station shall use the frequency specified in and power not in excess of that specified in its instrument of authorization.

(d) A licensee or permittee operating under the provisions of this section shall (1) as soon as possible after the beginning of such emergency use, send notice to the Commission at Washington, D.C., and to the Engineer in Charge of the district in which the station is located, stating the nature of the emergency and the use to which the station is being put; (2) discontinue such emergency operation as soon as the conditions requiring such operation are no longer present or the public has had an opportunity to be adequately informed; and (3) immediately upon cessation of such emergency operation notify the Commission in Washington, D.C., and the Engineer in Charge of the district in which the station is located, and shall in such notice justify the operation by stating the nature of the emergency, the exact times of operation, the type of emergency information transmitted, the total amount of time devoted to the transmission of emergency information, and other pertinent details.

(e) No operation under this section shall be permitted if an Emergency Action Condition, under the provisions of Part 73, Subpart G of this part, is in effect. If a station is operating under this section and an Emergency Action Condition is declared, compliance with the Emergency Action Notification shall take precedence.

FM Technical Standards

§ 73.310 Definitions.

(a) *Frequency modulation.*

Antenna height above average terrain. The average of the antenna heights above the terrain from 2 to 10 miles from the antenna for the eight directions spaced evenly for each 45 degrees of azimuth starting with True North. (In general, a different antenna height will be determined in each direction from the antenna. The average of these various heights is considered the antenna height above the average terrain. In some cases less than eight directions may be used. See § 73.313(d).) Where circular or elliptical polarization is employed, the antenna height above average terrain shall be based upon the height of the radiation center of the antenna which transmits the horizontal component of radiation.

Antenna power gain. The square of the ratio of the root-mean-square free space field strength produced at one mile in the horizontal plane, in millivolts per meter for one kilowatt antenna input power to 137.6 mv/m. This ratio should be expressed in decibels (db). (If specified for a particular direction, antenna power gain is based on the field strength in that direction only.)

Center frequency. The term "center frequency" means:

(1) The average frequency of the emitted wave when modulated by a sinusoidal signal.

(2) The frequency of the emitted wave without modulation.

Effective radiated power. The term "effective radiated power" means the product of the antenna power (transmitter output power less transmission line loss) times (1) the antenna power gain, or (2) the antenna field gain squared. Where circular or elliptical polarization is employed, the term effective radiated power is applied separately to the horizontal and vertical components of radiation. For allocation purposes, the effective radiated power authorized is the horizontally polarized component of radiation only.

FM broadcast band. The band of frequencies extending from 88 to 108 megacycles per second, which includes those assigned to noncommercial educational broadcasting.

FM broadcast channel. A band of frequencies 200 kc/s wide and designated by its center frequency. Channels for FM broadcast stations begin at 88.1 Mc/s and continue in successive steps of 200 kc/s to and including 107.9 Mc/s.

FM broadcast station. A station employing frequency modulation in the FM broadcast band and licensed primarily for the transmission of radiotelephone emissions intended to be received by the general public.

Field strength. The electric field strength in the horizontal plane.

Free space field strength. The field strength that would exist at a point in the absence of waves reflected from the earth or other reflecting objects.

Frequency Modulation. A system of modulation where the instantaneous radio frequency varies in proportion to the instantaneous amplitude of the modulating signal (amplitude of modulating signal to be measured after pre-emphasis, if used) and the instantaneous radio frequency is independent of the frequency of the modulating signal.

Frequency swing. The instantaneous departure of the frequency of the emitted wave from the center frequency resulting from modulation.

Multiplex transmission. The term "multiplex transmission" means the simultaneous transmission of two or more signals within a single channel. Multiplex transmission as applied to FM broadcast stations means the transmission of facsimile or other signals in addition to the regular broadcast signals.

Percentage modulation. The ratio of the actual frequency swing to the frequency swing defined as 100 percent modulation, expressed in percentage. For FM broadcast stations, a frequency swing of ±75 kilocycles is defined as 100 percent modulation.

(b) *Stereophonic broadcasting.*

Cross-talk. An undesired signal occurring in one channel caused by an electrical signal in another channel.

FM stereophonic broadcast. The transmission of a stereophonic program by a single FM broadcast station utilizing the main channel and a stereophonic subchannel.

Left (or right) signal. The electrical output of a microphone or combination of microphones placed so as to convey the intensity, time, and location of sounds originating predominately to the listener's left (or right) of the center of the performing area.

Left (or right) stereophonic channel. The left (or right) signal as electrically reproduced in reception of FM stereophonic broadcasts.

Main channel. The band of frequencies from 50 to 15,000 cycles per second which frequency-modulate the main carrier.

Pilot subcarrier. A subcarrier serving as a control signal for use in the reception of FM stereophonic broadcasts.

Stereophonic separation. The ratio of the electrical signal caused in the right (or left) stereophonic channel to the electrical signal caused in the left (or right) stereophonic channel by the transmission of only a right (or left) signal.

Stereophonic subcarrier. A subcarrier having a frequency which is the second harmonic of the pilot subcarrier frequency and which is employed in FM stereophonic broadcasting.

Stereophonic subchannel. The band of frequencies from 23 to 53 kilocycles per second containing the stereophonic subcarrier and its associated sidebands.

(c) *Facsimile.*

Available line. The portion of the total length of scanning line that can be used specifically for picture signals.

Index of cooperation. The product of the number of lines per inch, the available line length in inches, and the reciprocal of the line-use ratio (e.g., $105 \times 8.2 \times 8/7 = 984$).

Line-use ratio. The ratio of the available line to the total length of scanning line.

Optical density. The logarithm (to the base 10) of the ratio of incident to transmitted or reflected light.

Rectilinear scanning. The process of scanning an area in a predetermined sequence of narrow straight parallel strips.

§ 73.311 Field strength contours.

(a) Applications for FM broadcast authorization must show three field strength contours. These are the 70 dbu (3.16 mv/m), 60 dbu (1 mv/m), and 34 dbu (50 uv/m). These contours indicate only the approximate extent of coverage over average terrain and in the absence of interference. Under actual conditions, the true coverage may vary greatly from these estimates because the terrain over any specific path is expected to be different from the average terrain on which the field strength chart was based. Because of these factors the estimated contours give no assurance of service to any specific percentage of receiver locations within the distances indicated.

(b) The field strength contours provided for in this section shall be considered for the following purposes only:

(1) In the estimation of coverage resulting from the selection of a particular transmitter site by an applicant for an FM broadcast station.

(2) In connection with problems of coverage arising out of application of § 73.240.

(3) In determining compliance with paragraph (a) of this section concerning the minimum field strength to be provided over the principal community to be served.

§ 73.312 Topographic data.

(a) In the preparation of the profile graphs previously described, and in determining the location and height above mean sea level of the antenna site, the elevation or contour intervals shall be taken from United States Geological Survey Topographic Quadrangle Maps, United States Army Corps of Engineers Maps or Tennessee Valley Authority maps, whichever is the latest, for all areas for which such maps are available. If such maps are not published for the area in question, the next best topographic information should be used. Topographic data may sometimes be obtained from state and municipal agencies. The data from the Sectional Aeronautical Charts (including bench marks) or railroad depot elevations and highway elevations from road maps may be used where no better information is available. In cases where limited topographic data can be obtained, use may be made of an altimeter in a car driven along roads extending generally radially from the transmitter site.

(b) The Commission will not ordinarily require the submission of topographical maps for areas beyond 15 miles from the antenna site, but the maps must include the principal city or cities to be served. If it appears necessary, additional data may be requested.

(c) The United States Geological Survey Topography Quadrangle Sheets may be obtained from the United States Geological Survey, Department of the Interior, Washington, D.C., 20240. The Sectional Aeronautical Charts are available from the United States Coast and Geodetic Survey, Department of Commerce, Washington, D.C., 20235. These maps may also be secured from branch offices and from authorized agents or dealers in most principal cities.

§ 73.313 Prediction of coverage.

(a) All predictions of coverage made pursuant to this section shall be made without regard to interference and shall be made only on the basis of estimated field strengths.

(b) Predictions of coverage shall be made only for the same purposes as relate to the use of field strength contours as specified in § 73.311.

(c) (1) In predicting the distance to the field strength contours, the F (50, 50) field strength chart, Figure 1 of § 73.333, shall be used. The 50 percent field strength is defined as that value exceeded for 50 percent of the time. The F (50, 50) chart gives the estimated 50 percent field strengths exceeded at 50 percent of the locations in decibels above 1 microvolt per meter. The chart is based on an effective power of 1 kilowatt radiated from a half-wave dipole in free space, which produces an unattenuated field strength at 1 mile of about 103 db above 1 microvolt per meter (137.6 millivolts per meter).

(2) To use the chart for other powers, the sliding scale associated with the chart should be trimmed and used as the ordinate scale. This sliding scale is placed on the chart with the appropriate gradation for power in line with the horizontal 40 db line on the chart. The right edge of the scale is placed in line with the approprate antenna height gradations, and the chart then becomes direct reading (in uv/m and in db above 1 uv/m) for this power and antenna height. Where the antenna height is not one of those for which a scale is provided, the signal strength or distance is determined by interpolation between the curves connecting the equidistant scale. Dividers may be used in lieu of the sliding scale. In predicting the distance to the field strength contours, the effective radiated power to be used is that in the horizontal plane in the pertinent direction. In predicting other field strengths over areas not in horizontal plane, the effective radiated power to be used is the power in the direction of such areas; the appropriate vertical plane radiation pattern must, of course, be considered in determining this power.

(d) The antenna height to be used with this chart is the height of the radiation center of the antenna above the average terrain along the radial in question. In determining the average elevation of the terrain, the elevations between 2 and 10 miles from the antenna site are employed. Profile graphs shall be drawn for eight radials beginning at the antenna site and extending 10 miles therefrom. The radials should be drawn for each 45 degrees of azimuth starting with True North. At least one radial must include the principal community to be served even though such community may be more than 10 miles from the antenna site. However, in the event none of the evenly spaced radials include the principal community to be served and one or more such radials are drawn in addition to the eight evenly spaced radials, such additional radials shall not be employed in computing the antenna height above average terrain. Where the 2- to 10-mile portion of a radial extends in whole or in part over a large body of water or extends over foreign territory but the 50 uv/m contour encompasses land area within the United States beyond the 10-mile portion of the radial, the entire 2- to 10-mile portion of the radial shall be included in the computation of antenna height above average terrain. However, where the 50 uv/m contour does not so encompass United States land area and (1) the entire 2- to 10-mile portion of the radial extends over large bodies of water or foreign territory, such radial shall be completely omitted from the computation of antenna height above average terrain, and (2) where a part of the 2- to 10-mile portion of a radial extends over large bodies of water or over foreign territory, only that part of the radial extending from the 2-mile sector to the outermost portion of land area within the United States covered by the radial shall be employed in the computation of antenna height above average terrain. The profile graph for each radial should be plotted by contour intervals of from 40 to 100 feet and, where the data permits, at least 50 points of elevation (generally uniformly spaced) should be used for each radial. In instances of very rugged terrain where the use of contour intervals of 100 feet would result in several points in a short distance, 200- or 400-foot contour intervals may be used for such distances. On the other hand, where the terrain is uniform or gently sloping the smallest contour interval indicated on the topographic map should be used, although only relatively few points may be available. The profile graph should indicate the topography accurately for each radial, and the graphs should be plotted with the distance in miles as the abscissa and the elevation in feet above mean sea level as the ordinate. The profile graphs should indicate the source of the topographical data employed. The graph should also show the elevation of the center of the radiating system. The graph may be plotted either on rectangular coordinate paper or on special paper which shows the curvature of the earth. It is not necessary to take the curvature of the earth into consideration in this procedure, as this factor is taken care of in the charts showing signal strengths. The average elevation of the 8-mile distance between 2 and 10 miles from the antenna site should then be determined from the profile graph for each radial. This may be obtained by averaging a large number of equally spaced points, by using a planimeter, or by obtaining the median elevation (that exceeded for 50 percent of the distance) in sectors and averaging those values.

(e) In cases where the terrain in one or more directions from the antenna site departs widely from the average elevation of the 2- to 10-mile sector, the prediction method may indicate contour distances that are different from what may be expected in practice. For example, a mountain ridge may indicate the practical limit of service although the prediction method may indicate otherwise. In such cases the prediction method should be followed, but a supplemental showing may be made concerning the contour distances as determined by other means. Such supplemental showing should describe the procedure employed and should include sample calculations. Maps of predicted coverage should include both the coverage as predicted by the regular method and as predicted by a supplemental method. When measurements of area are required, these should include the area obtained by the regular prediction method and the area obtained by the supplemental method. In directions where the terrain is such that negative antenna heights or heights below 100 feet for the 2- to 10-mile sector are obtained, a supplemental showing of expected coverage must be included together with a description of the method employed in predicting such coverage. In special cases, the Commission may require additional information as to terrain and coverage.

§ 73.315 Transmitter location.

(a) The transmitter location shall be chosen so that, on the basis of the effective radiated power and antenna height above average terrain employed, a minimum field strength of 70 decibels above one microvolt per meter (dbu), or 3.16 millivolts per meter, will be provided over the entire principal community to be served.

(b) The transmitter location should be as near the center of the proposed service area as possible consistent with the applicant's ability to find a site with sufficient elevation to provide service throughout the area. Location of the antenna at a point of high elevation is necessary to reduce to a minimum the shadow effect on propagation due to hills and buildings which may reduce materially the intensity of the station's signals in a particular direction. The transmitting site should be selected consistent with the purpose of the station, i.e., whether it is intended to serve a small city, a metropolitan area, or a large region. Inasmuch as service may be provided by signals of 1 mv/m or greater field strengths in metropolitan areas, and inasmuch as signals as low as 50 uv/m may provide service in rural areas, considerable latitude in the geographical location of the transmitter is permitted; however, the necessity for a high elevation for the antenna may render this problem difficult. In general, the transmitting antenna of a station should be located at the most central point at the highest elevation available. In providing the best degree of service to an area, it is usually preferable to use a high antenna rather than a lower antenna with increased transmitter power. The location should be so chosen that line-of-sight can be obtained from the antenna over the principal city or cities to be served; in no event should there be a major obstruction in this path.

(c) The transmitting location should be selected so that the 1 mv/m contour encompasses the urban population within the area to be served. It is recognized that topography, shape of the desired service area, and population distribution may make the choice of a transmitter location difficult. In such cases consideration may be given to the use of a directional antenna system, although it is generally preferable to choose a site where a nondirectional antenna may be employed.

(d) In cases of questionable antenna locations it is desirable to conduct propagation tests to indicate the field intensity expected in the principal city or cities to be served and in other areas, particularly where severe shadow problems may be expected. In considering applications proposing the use of such locations, the Commission may require site tests to be made. Such tests should include measurements made in accordance with good engineering practice, and full data thereon must be supplied to the Commission. The test transmitter should employ an antenna having a height as close as possible to the proposed antenna height, using a balloon or other support if necessary and feasible. Information concerning the authorization of site tests may be obtained from the Commission upon request.

(e) Present information is not sufficiently complete to establish "blanket areas" of FM broadcast stations, which are defined as those areas adjacent to the transmitters in which the reception of other stations is subject to interference due to the strong signal from the stations. Where it is found necessary to locate the transmitter in a residential area where blanketing problems may appear to be excessive, the application must include a showing concerning the availability of other sites. The authorization of station construction in areas where blanketing problems appear to be excessive will be on the basis that the applicant will assume full responsibility for the adjustment of reasonable complaints arising from excessively strong signals of the applicant's station.

(f) Cognizance must of course be taken regarding the possible hazard of the proposed antenna structure to aviation and the proximity of the proposed site to airports and airways. Procedures and standards with respect to the Commission's consideration of proposed antenna structures which will serve as a guide to persons intending to apply for radio station licenses are contained in Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures).

§ 73.316 Antenna systems.

(a) It shall be standard to employ horizontal polarization; however, circular or elliptical polarization may be employed if desired. Clockwise or counterclockwise rotation may be used. The supplemental vertically polarized effective radiated power required for circular or elliptical polarization shall in no event exceed the effective radiated power authorized.

(b) The antenna must be constructed so that it is as clear as possible of surrounding buildings or objects that would cause shadow problems.

(c) *Directional antennas.* A directional antenna is considered to be an antenna that is designed or altered for the purpose of obtaining a noncircular radiation pattern. Directional antennas may not be used for the purpose of reducing minimum mileage separation requirements but may be employed for the purpose of improving service or for the purpose of using a particular site; directional antennas with a ratio of maximum to minimum radiation in the horizontal plane of more than 15 decibels will not be permitted.

(d) *Applications for directional antennas.* Applications proposing the use of directional antenna systems must be accompanied by the following:

(1) Complete description of the proposed antenna system, including:

(i) a description of the means whereby the directivity is proposed to be obtained, and

(ii) the means (such as a rotatable reference antenna) whereby the operational antenna pattern will be determined prior to licensed operation and maintained within proper tolerances thereafter.

(2) Horizontal and vertical plane radiation patterns showing the free space field strength in mv/m at 1 mile and effective radiated power in dbk for each direction. If directivity was computed, the showing shall include the method by which the radiation patterns were computed, including formulae used, sample calculations and tabulations of data. If the directivity was measured, the method employed shall be fully described, including the equipment used, and the resultant measured data shall be tabulated. Sufficient vertical patterns shall be included to indicate clearly the radiation characteristics of the antenna above and below the horizontal plane. Complete information and patterns shall be provided for angles of $\pm 10°$ from the horizontal plane and sufficient additional information included on that portion of the pattern lying between $+10°$ and the zenith and $-10°$ and the nadir, to conclusively demonstrate the absence of undesirable lobes in these areas. The horizontal plane pattern shall be plotted on polar coordinate paper with reference to True North. The vertical plane pattern shall be plotted on rectangular coordinate paper with reference to the horizontal plane.

(3) Name, address, and qualifications of the engineer making the calculations.

(e) Applications proposing the use of FM broadcast antennas in the immediate vicinity (i. e., 200 feet or less) of (1) other FM broadcast antennas, or (2) television broadcast antennas for frequencies adjacent to the FM broadcast band, must include a showing as to the expected effect, if any, of such proximate operation.

(f) In cases where it is proposed to use a tower of a standard broadcast station as a supporting structure for an FM broadcast antenna, an application for construction permit (or modification of construction permit) for such station must be filed for consideration with the FM application. Applications may be required for other classes of stations when their towers are to be used in connection with FM broadcast stations.

(g) When an FM broadcast antenna is mounted on a nondirectional standard broadcast antenna, new resistance measurements must be made of the standard broadcast antenna after installation and testing of the FM broadcast antenna. During the installation and until the new resistance determination is approved, the standard broadcast station licensee should apply for authority (informal application) to operate by the indirect method of power determination. The FM broadcast license application will not be considered until the application form concerning resistance measurements is filed for the standard broadcast station.

(h) When an FM broadcast antenna is mounted on an element of a standard broadcast directional antenna, a full engineering study concerning the effect of the FM broadcast antenna on the directional pattern must be filed with the application concerning the standard broadcast station. Depending upon the individual case, the Commission may require readjustment and certain field in-

tensity measurements of the standard broadcast station following the completion of the FM broadcast antenna system.

(i) When the proposed FM broadcast antenna is to be mounted on a tower in the vicinity of a standard broadcast directional array and it appears that the operation of the directional antenna system may be affected, an engineering study must be filed with the FM broadcast application concerning the effect of the FM broadcast antenna on the directional pattern. Readjustment and field intensity measurements of the standard broadcast station may be required following construction of the FM broadcast antenna.

(j) Information regarding data required in connection with standard broadcast directional antenna systems may be found in § 73.150 of this chapter. (See also Standard Broadcast Technical Standards.)

(k) In the event a common tower is used by two or more licensees for antenna and/or antenna supporting purposes, the licensee who is owner of the tower shall assume full responsibility for the installation and maintenance of any painting or lighting requirements. In the event of shared ownership, one licensee shall assume such responsibility and advise the Commission accordingly.

(l) It is recommended that an emergency FM broadcast antenna be installed, or, alternately, an auxiliary transmission line or lines if feasible in the particular circumstances. Data thereon should be supplied with the application for construction permit; if proposed after station construction, an informal application should be submitted to the Commission.

(m) When necessary for the protection of air navigation, the antenna and supporting structure shall be painted and illuminated in accordance with the specifications supplied by the Commission pursuant to section 303 (q) of the Communications Act of 1934, as amended.

§ 73.317 Transmitters and associated equipment.

(a) *Electrical performance standards.* The general design of the FM broadcast transmitting system (from input terminals of microphone preamplifier, through audio facilities at the studio, through lines or other circuits between studio and transmitter, through audio facilities at the transmitter, and through the transmitter, but excluding equalizers for the correction of deficiencies in microphone response) shall be in accordance with the following principles and specifications:

(1) The transmitter shall operate satisfactorily in the operating power range with a frequency swing of 75 kilocycles per second, which is defined as 100 percent modulation.

(2) The transmitting system shall be capable of transmitting a band of frequencies from 50 to 15,000 cycles. Preemphasis shall be employed in accordance with the impedance-frequency characteristic of a series inductance-resistance network having a time constant of 75 microseconds. (See Fig. 2 of § 73.333.) The deviation of the system response from the standard preemphasis curve shall lie between two limits as shown in Figure 2 of § 73.333. The upper of these limits shall be uniform (no deviation) from 50 to 15,000 cycles. The lower limit shall be uniform from 100 to 7,500 cycles, and 3 db. below the upper limit; from 100 to 50 cycles the lower limit shall fall from the 3 db. limit at a uniform rate of 1 db. per octave (4 db. at 50 cycles); from 7,500 to 15,000 cycles the lower limit shall fall from the 3 db. limit at a uniform rate of 2 db. per octave (5 db. at 15,000 cycles).

(3) At any modulation frequency between 50 and 15,000 cycles and at modulation percentages of 25, 50, and 100 percent, the combined audio frequency harmonics measured in the output of the system shall not exceed the root-mean-square values given in the following table:

Modulating frequency:	*Distortion percent*
50 to 100 cycles	3.5
100 to 7,500 cycles	2.5
7,500 to 15,000 cycles	3.0

(i) Measurements shall be made employing 75 microsecond deemphasis in the measuring equipment and 75 microsecond preemphasis in the transmitting equipment, and without compression if a compression amplifier is employed. Harmonics shall be included to 30 kc/s.

(ii) It is recommended that none of the three main divisions of the system (transmitter, studio to transmitter circuit, and audio facilities) contribute over one-half of these percentages since at some frequencies the total distortion may become the arithmetic sum of the distortions of the divisions.

(4) The transmitting system output noise level (frequency modulation) in the band of 50 to 15,000 cycles shall be at least 60 decibels below 100 percent modulation (frequency swing of ±75 kilocycles). The measurement shall be made using 400 cycle modulation as a reference. The noise-measuring equipment shall be provided with standard 75 microsecond deemphasis; the ballistic characteristics of the instrument shall be similar to those of the standard VU meter.

(5) The transmitting system output noise level (amplitude modulation) in the band of 50 to 15,000 cycles shall be at least 50 decibels below the level representing 100 percent amplitude modulation. The noise-measuring equipment shall be provided with standard 75-microsecond deemphasis; the ballistic characteristics of the instrument shall be similar to those of the standard VU meter.

(6) Automatic means shall be provided in the transmitter to maintain the assigned center frequency within the allowable tolerance (±2000 cycles).

(7) The transmitter shall be equipped with suitable indicating instruments for the determination of operating power and with other instruments as are necessary for proper adjustment, operation, and maintenance of the equipment (see § 73.320).

(8) Adequate provision shall be made for varying the transmitter output power to compensate for excessive variations in line voltage or for other factors affecting the output power.

(9) Adequate provision shall be provided in all component parts to avoid overheating at the rated maximum output power.

(10) Means should be provided for connection and continuous operation of approved frequency and modulation monitors.

(11) If a limiting or compression amplifier is employed, precaution should be maintained in its connection in the circuit due to the use of preemphasis in the transmitting system.

(12) Any emission appearing on a frequency removed from the carrier by between 120 kc/s and 240 kc/s inclusive shall be attenuated at least 25 decibels below the level of the unmodulated carrier. Compliance with this specification will be deemed to show the occupied bandwidth to be 240 kc/s or less.

(13) Any emission appearing on a frequency removed from the carrier by more than 240 kc/s and up to and including 600 kc/s shall be attenuated at least 35 db below the level of the unmodulated carrier.

(14) Any emission appearing on a frequency removed from the carrier by more than 600 kc/s shall be attenuated at least $43+10\ \mathrm{Log}_{10}$ (Power, in watts) decibels below the level of the unmodulated carrier, or 80 decibels, whichever is the lesser attenuation.

(b) *Construction.* In general, the transmitter shall be constructed either on racks and panels or in totally enclosed frames protected as required by article 810 of the National Electrical Code (section 8192(a), (b), and (c)), and as set forth below:

(1) Means shall be provided for making all tuning adjustments, requiring voltages in excess of 350 volts to be applied to the circuit, from the front of the panels with all access doors closed.

(2) Proper bleeder resistors or other automatic means shall be installed across all capacitor banks to lower any voltage which may remain accessible with access door open to less than 350 volts within 2 seconds after the access door is opened.

(3) All plate supply and other high voltage equipment, including transformers, filters, rectifiers and motor generators, shall be protected so as to prevent injury to operating personnel.

(i) Commutator guards shall be provided on all high voltage rotating machinery. Coupling guards should be provided on motor generators.

(ii) Power equipment and control panels of the transmitter shall meet the above requirements (exposed 220 volt AC switching equipment on the front of the power control panels is not recommended but is not prohibited).

(iii) Power equipment located at a broadcast station but not directly associated with the transmitter (not purchased as part of same), such as power distribution panels, are not under the jurisdiction of the Commission; therefore § 73.254 does not apply.

(4) Metering equipment:

(i) All instruments having more than 1,000 volts potential to ground on the movement shall be protected by a cage or cover in addition to the regular case.

(Some instruments are designed by the manufacturer to operate safely with voltages in excess of 1,000 volts on the movement. If it can be shown by the manufacturer's rating that the instrument will operate safely at the applied potential, additional protection is not necessary.)

(ii) In case the plate voltmeter is located on the low potential side of the multiplier resistor with the potential of the high potential terminal of the instrument at or less than 1,000 volts above ground, no protective case is required. However, it is good practice to protect voltmeters subject to more than 5,000 volts with suitable over-voltage protective devices across the instrument terminals in case the winding opens.

(iii) Transmission line meters and any other radio frequency instrument which may be necessary for the operator to read shall be so installed as to be easily and accurately read without the operator having to risk contact with circuits carrying high potential radio frequency energy.

(5) It is recommended that component parts comply as much as possible with the component specifications designated by the Army-Navy Electronics Standards Agency.

(c) *Wiring and shielding.* (1) The transmitter panels or units shall be wired in accordance with standard switchboard practice, either with insulated leads properly cabled and supported or with rigid bus bar properly insulated and protected.

(2) Wiring between units of the transmitter, with the exception of circuits carrying radio frequency energy, shall be installed in conduits or approved fiber or metal raceways for protection from mechanical injury.

(3) Circuits carrying radio frequency energy between units shall be coaxial, two wire balanced lines, or properly shielded.

(4) All stages or units shall be adequately shielded and filtered to prevent interaction and radiation.

(5) The frequency and modulation monitors and associated radio frequency lines to the transmitter shall be thoroughly shielded.

(d) *Installation.* (1) The installation shall be made in suitable quarters.

(2) Since an operator must be on duty at the transmitter control point during operation, suitable facilities for his welfare and comfort shall be provided at the control point.

(e) *Other technical data.* An accurate circuit diagram, as furnished by the manufacturer of the equipment, shall be retained at the transmitter location.

(f) *Operation.* In addition to specific requirements of the rules governing FM broadcast stations, the following operating requirements are specified:

(1) The maximum percentage of modulation shall be maintained in accordance with § 73.268. However, precautions shall be taken so as not to substantially alter the dynamic characteristics of musical programs.

(2) The station equipment shall be so operated, tuned, and adjusted that emissions outside of the authorized channel do not cause harmful interference to the reception of other radio stations. FM broadcast stations employing transmitters type accepted after January 1, 1960, shall maintain the bandwidth occupied by their emissions in accordance with the specifications set forth in paragraph (a) of this section. Stations employing transmitters installed or type accepted prior to January 1, 1960, shall achieve the highest degree of compliance practicable with their existing equipment. In either case, should harmful interference to the reception of other radio stations occur, the licensee may be required to take such further steps as may be necessary to eliminate the interference.

(3) If a limiting or compression amplifier is employed, care should be maintained in its use due to preemphasis in the transmitting system.

(g) *Studio equipment.* (1) Studio equipment shall be subject to all the above requirements where applicable except as follows:

(i) If properly covered by an underwriter's certificate, it will be considered as satisfying safety requirements.

(ii) Section 8192 of article 810 of the National Electrical Code shall apply for voltages only in excess of 500 volts.

(2) No specific requirements are made with regard to the microphones to be employed. However, microphone performance (including compensating networks, if employed) shall be compatible with the required performance of the transmitting system.

(3) No specific requirements are made relative to the design and acoustical treatment of studios. However, the design of studios, particularly the main studio, shall be compatible with the required performance characteristics of FM broadcast stations.

§ 73.318 Facsimile: engineering standards.

The following standards apply to facsimile broadcasting under § 73.266:

(a) Rectilinear scanning shall be employed, with scanning spot progressing from left to right and scanned lines progressing from top to bottom of subject copy.

(b) The standard index of cooperation shall be 984.

(c) The number of scanning lines per minute shall be 360.

(d) The line-use ratio shall be ⅞, or 315° of the full scanning cycle.

(e) The ⅛ cycle or 45° not included in the available scanning line shall be divided into 3 equal parts, the first 15° being used for transmission at approximately white level, the second 15° for transmission at approximately black level, and the third 15° for transmission at approximately white level.

(f) An interval of not more than 12 seconds shall be available between two pages of subject copy, for the transmission of a page-separation signal and/or other services.

(g) Amplitude or frequency (frequency-shift) modulation of the subcarrier shall be used.

(h) Subcarrier modulation shall normally vary approximately linearly with the optical density of the subject copy.

(i) Negative modulation shall be used, i. e., for amplitude modulation of subcarrier, maximum subcarrier amplitude and maximum radio frequency swing on black; for frequency modulation of subcarrier, highest instantaneous frequency of subcarrier on black.

(j) Subcarrier noise level shall be maintained at least 30 db. below maximum (black) picture modulation level, at the radio transmitter input.

(k) The facsimile subcarrier transmission shall be conducted in the frequency range between 22 and 28 kilocycles. Should amplitude modulation of the subcarrier be employed the subcarrier frequency shall be 25 kilocycles with sidebands extending not more than 3 kilocycles in either direction from the subcarrier frequency. Should frequency modulation of the subcarrier be employed the total swing of the subcarrier shall be within the range from 22 to 28 kilocycles, with 22 kilocycles corresponding to white and 28 kilocycles corresponding to black on the transmitted copy. In multiplex operation the modulation of the FM carrier by the modulated subcarrier shall not exceed 5 percent. In simplex operation the modulation of the FM carrier by the modulated subcarrier shall not exceed 30 percent.

(l) During periods of multiplex facsimile transmission, frequency modulation of the FM carrier caused by the aural signals shall, in the frequency range from 20 to 30 kilocycles, be at least 60 db. below 100 percent modulation. Frequency modulation of the FM carrier caused by the facsimile signals shall, in the frequency range from 50 to 15,000 cycles, be at least 60 db. below 100 percent modulation.

§ 73.319 Subsidiary communications multiplex operations: engineering standards.

(a) Frequency modulation of SCA subcarriers shall be used.

(b) The instantaneous frequency of SCA subcarriers shall at all times be within the range 20 to 75 kilocycles: *Provided, however,* That when the station is engaged in stereophonic broadcasting pursuant to § 73.297, the instantaneous frequency of SCA subcarriers shall at all times be within the range 53 to 75 kilocycles.

(c) The arithmetic sum of the modulation of the main carrier by SCA subcarriers shall not exceed 30 percent: *Provided, however,* That when the station is engaged in stereophonic broadcasting pursuant to § 73.297, the arithmetic sum of the modulation of the main carrier by the SCA subcarriers shall not exceed 10 percent.

NOTE: Inasmuch as presently approved FM modulation monitors have been designed to meet requirements for modulation frequencies of from 50 to 15,000 cycles, the use of such monitors for reading the modulation percentages during SCA multiplex operation may not be appropriate since the subcarriers utilized are above 20,000 cycles.

(d) The total modulation of the main carrier, including SCA subcarriers, shall meet the requirements of § 73.268.

(e) Frequency modulation of the main carrier caused by the SCA subcarrier operation shall, in the frequency range 50 to 15,000 cycles, be at least 60 db

below 100 percent modulation: *Provided, however,* That when the station is engaged in stereophonic broadcasting pursuant to § 73.297, frequency modulation of the main carrier by the SCA subcarrier operation shall, in the frequency range 50 to 53,000 cycles, be at least 60 db below 100 percent modulation.

§ 73.320 Indicating instruments—specifications.

The following requirements and specifications shall apply to indicating instruments used by FM broadcast stations:

(a) Instruments indicating the plate current or plate voltage of the last radio stage (linear scale instruments) shall meet the following specifications:

(1) Length of scale shall be not less than 2 3/10 inches.

(2) Accuracy shall be at least 2 percent of the full scale reading.

(3) Scale shall have at least 40 divisions.

(4) Full scale reading shall not be greater than five times the minimum normal indication.

(b) Instruments indicating transmission line current or voltage shall meet the following specifications:

(1) Instruments having linear scales shall meet the requirements of paragraph (a) (1), (2), (3), and (4) of this section.

(2) Instruments having logarithmic or square law scales:

(i) Shall meet the requirements of paragraph (a) (1) and (2) of this section for linear scale instruments.

(ii) Full scale reading shall not be greater than three times the minimum normal indication.

(iii) No scale division above one-third full scale reading shall be greater than one-thirtieth of the full scale reading.

(c) Radio frequency instruments having expanded scales:

(1) Shall meet the requirements of paragraph (a) (1), (2), and (4) of this section for linear scale instruments.

(2) No scale division above one-fifth full scale reading shall be greater than one-fiftieth of the full scale reading.

(3) The meter face shall be marked with the words "Expanded scale" or the abbreviation thereof (E. S.).

(d) No required instrument, the accuracy of which is questionable, shall be employed. Repairs and recalibration of instruments shall be made by the manufacturer, or by an authorized instrument repair service of the manufacturer, or by some other properly qualified and equipped instrument repair service. In any event the repaired instrument must be supplied with a certificate of calibration.

(e) [Reserved]

(f) The function of each instrument used in the equipment shall be clearly and permanently shown on the instrument itself or on the panel immediately adjacent thereto.

§ 73.321 Auxiliary transmitters.

Auxiliary transmitters may not exceed the power rating or operating power range of the main transmitter, but need not conform to the performance characteristics specified by § 73.317 (a) (2) to (a) (5) inclusive. The subsequent portions of § 73.317 apply to auxiliary transmitters.

§ 73.322 Stereophonic transmission standards.

(a) The modulating signal for the main channel shall consist of the sum of the left and right signals.

(b) A pilot subcarrier at 19,000 cycles plus or minus 2 cycles shall be transmitted that shall frequency modulate the main carrier between the limits of 8 and 10 percent.

(c) The stereophonic subcarrier shall be the second harmonic of the pilot subcarrier and shall cross the time axis with a positive slope simultaneously with each crossing of the time axis by the pilot subcarrier.

(d) Amplitude modulation of the stereophonic subcarrier shall be used.

(e) The stereophonic subcarrier shall be suppressed to a level less than one percent modulation of the main carrier.

(f) The stereophonic subcarrier shall be capable of accepting audio frequencies from 50 to 15,000 cycles.

(g) The modulating signal for the stereophonic subcarrier shall be equal to the difference of the left and right signals.

(h) The pre-emphasis characteristics of the stereophonic subchannel shall be identical with those of the main channel with respect to phase and amplitude at all frequencies.

(i) The sum of the side bands resulting from amplitude modulation of the stereophonic subcarrier shall not cause a peak deviation of the main carrier in excess of 45 percent of total modulation (excluding SCA subcarriers) when only a left (or right) signal exists; simultaneously in the main channel, the deviation when only a left (or right) signal exists shall not exceed 45 percent of total modulation (excluding SCA subcarriers).

(j) Total modulation of the main carrier including pilot subcarrier and SCA subcarriers shall meet the requirements of § 73.268 with maximum modulation of the main carrier by all SCA subcarriers limited to 10 percent.

(k) At the instant when only a positive left signal is applied, the main channel modulation shall cause an upward deviation of the main carrier frequency; and the stereophonic subcarrier and its sidebands signal shall cross the time axis simultaneously and in the same direction.

(l) The ratio of peak main channel deviation to peak stereophonic subchannel deviation when only a steady state left (or right) signal exists shall be within plus or minus 3.5 percent of unity for all levels of this signal and all frequencies from 50 to 15,000 cycles.

(m) The phase difference between the zero points of the main channel signal and the stereophonic subcarrier sidebands envelope, when only a steady state left (or right) signal exists, shall not exceed plus or minus 3 degrees for audio modulating frequencies from 50 to 15,000 cycles.

NOTE: If the stereophonic separation between left and right stereophonic channels is better than 29.7 decibels at audio modulating frequencies between 50 and 15,000 cycles, it will be assumed that paragraphs (l) and (m) of this section have been complied with.

(n) Cross-talk into the main channel caused by a signal in the stereophonic subchannel shall be attenuated at least 40 decibels below 90 percent modulation.

(o) Cross-talk into the stereophonic subchannel caused by a signal in the main channel shall be attenuated at least 40 decibels below 90 percent modulation.

(p) For required transmitter performance, all of the requirements of § 73.254 shall apply with the exception that the maximum modulation to be employed is 90 percent (excluding pilot subcarrier) rather than 100 percent.

(q) For electrical performance standards of the transmitter and associated equipment, the requirements of § 73.317 (a) (2), (3), (4), and (5) shall apply to the main channel and stereophonic subchannel alike, except that where 100 percent modulation is referred to, this figure shall include the pilot subcarrier.

§ 73.330 Frequency and modulation monitors at auxiliary transmitters.

(a) The following shall govern the installation of approved frequency and modulation monitors at auxiliary transmitters of FM broadcast stations in compliance with these rules:

(1) In case the auxiliary transmitter location is at a site different from that of the main transmitter, an approved frequency monitor shall be installed at the auxiliary transmitter except when the frequency of the auxiliary transmitter can be monitored by means of the frequency monitor at the main transmitter. When the auxiliary transmitter is operated without a frequency monitor under this exemption, it shall be monitored by means of the frequency monitor at the main transmitter.

(2) The licensee will be held strictly responsible for any center frequency deviation of the auxiliary transmitter in excess of 2,000 cycles from the assigned frequency, even though exempted by the above from installing an approved frequency monitor.

(3) Installation of an approved modulation monitor at the location of the auxiliary transmitter, when different from that of the main transmitter, is optional with the licensee. However, when it is necessary to operate the auxiliary transmitter beyond two calendar days, a modulation monitor shall be installed and operated at the auxiliary transmitter. The monitor (if taken from the main transmitter) shall be reinstalled at the main transmitter immediately upon resumption of operation of the main transmitter.

(4) In all cases where the auxiliary transmitter and the main transmitter have the same location, the same frequency and modulation monitors may be used for monitoring both transmitters, provided they are so arranged as to be readily switched from one transmitter to the other.

§ 73.331 Requirements for type approval of frequency monitors.

(a) *General requirements.* (1) Any manufacturer desiring to submit a mon-

itor for type approval shall supply the Commission with full specification details (two sworn copies) as well as the test data specified in paragraph (c) of this section. If this information appears to meet the requirements of the rules, shipping instructions will be issued to the manufacturer. The shipping charges to and from the Laboratory at Laurel, Maryland, shall be paid for by the manufacturer. Approval of a monitor will only be given on the basis of the data obtained from the sample monitor submitted to the Commission for test.

(2) In approving a monitor upon the basis of the tests conducted by the Laboratory, the Commission merely recognizes that the type of monitor has the inherent capability of functioning in compliance with the rules, if properly constructed, maintained, and operated. The Commission realizes that the frequency monitor may have limited range over which the visual indicator will determine deviations. Accordingly, it may be necessary that adjunct equipment be used to determine major deviations.

(3) Additional rules with respect to withdrawal of type approval, modification of type approval equipment and limitations of the findings upon which type approval is based are set forth in Part 2, Subpart F, of this chapter.

(b) *General specifications.* The general specifications that frequency monitors shall meet before they will be approved by the Commission are as follows:

(1) The unit shall have an accuracy of at least ±1000 cycles under ordinary conditions (temperature, humidity, power supply variations and other conditions which may affect its accuracy) encountered in FM broadcast stations throughout the United States, for any channel within the FM broadcast band.

(2) The range of the indicating device shall be at least from 2000 cycles below to 2000 cycles above the assigned center frequency.

(3) The scale of the indicating device shall be so calibrated as to be accurately read within at least 100 cycles.

(4) Means shall be provided for adjustment of the monitor indication to agree with an external standard.

(5) The monitor shall be capable of continuous operation and its circuit shall be such as to permit continuous monitoring of the transmitter center frequency.

(6) Operation of the monitor shall have no deleterious effect on the operation of the transmitter or the signal emitted therefrom.

(c) *Tests to be made for approval of FM broadcast frequency monitors.* The manufacturer of a monitor shall submit data on the following at the time of requesting approval:

(1) Constancy of oscillator frequency as measured several times in 1 month.

(2) Contancy of oscillator frequency when subjected to vibration tests which would correspond to the treatment received in shipping, handling and installing the instrument.

(3) Accuracy of readings of the frequency deviation instrument.

(4) Functioning of frequency adjustment device.

(5) Effects on frequency and readings, of the changing of tubes, of voltage variations, and of variations of room temperature through a range not to exceed 10° to 40° C.

(6) Response of indicating instrument to small changes of frequency.

(7) General information on the effect of tilting or tipping or other tests to determine ability of equipment to withstand shipment.

(d) Various other tests may be made or required, such as effects of variation of input from the transmitter depending upon the character of the apparatus.

(e) Tests shall be conducted in such a manner as to approximate actual operating conditions as nearly as possible. The equipment under test shall be operated on any channel in the FM broadcast band.

§ 73.332 Requirements for type approval of modulation monitors.

(a) Any manufacturer desiring to submit a monitor for type approval shall supply the Commission with full specification details (two sworn copies) specified in paragraph (b) of this section. If this information appears to meet the requirements of the rules, shipping instructions will be issued to the manufacturer. The shipping charges to and from the Laboratory at Laurel, Maryland, shall be paid for by the manufacturer. Approval of a monitor will only be given on the basis of the data obtained from the sample monitor submitted to the Commission for test.

(1) In approving a monitor upon the basis of the tests conducted by the Laboratory, the Commission merely recognizes that the type of monitor has the inherent capability of functioning in compliance with the rules, if properly constructed, maintained and operated.

(2) Additional rules with respect to withdrawal of type approval, modification of type approval equipment and limitations on the findings upon which type approval is based are set forth in Part 2, Subpart F, of this chapter.

(b) The specifications that the modulation monitor shall meet before it will be approved by the Commission are as follows:

(1) A means for insuring that the transmitter input to the modulation monitor is proper.

(2) A modulation peak indicating device that can be set at any predetermined value from 50 to 120 percent modulation (±75 kc/s swing is defined as 100 percent modulation) and for either positive or negative swings (i.e., either above or below transmitter center frequency).

(3) A semi-peak indicator with a meter having the characteristics given below shall be used with a circuit such that peaks of modulation of duration between 40 and 90 milliseconds are indicated to 90 percent of full value and the discharge rate adjusted so that the pointer returns from full reading to 10 percent of zero within 500 to 800 milliseconds. A switch shall be provided so that this meter will read either positive or negative swings.

(i) The characteristics of the indicating meter are: (*a*) *Damping factor.* The damping factor shall be between 16 and 200. (*b*) *Scale.* The meter scale shall be similar in appearance to that of a standard VU meter. The scale length between 0 and 100 percent modulation markings should be at least 2.3 inches. In addition to other markings a small mark for 133 percent modulation and designated as such should be included for the purpose of testing transmitters with 100 kc/s swing.

(4) The accuracy of reading of percentage of modulation shall be within ±5 percent modulation percentage at any percentage of modulation up to 100 percent modulation.

(5) The frequency characteristic curve shall not depart from a straight line more than ±½ db. from 50 to 15,000 cycles. Distortion shall be kept to a minimum.

(6) The monitor shall not absorb appreciable power from the transmitter.

(7) Operation of the monitor shall have no deleterious effect on the operation of the transmitter.


(8) General design, construction, and operation shall be in accordance with good engineering practice.

(c) The modulation monitor may be a part of the frequency monitor.

§ 73.333 Engineering charts.


This section consists of the following Figures 1, 2, and 3.

NOTE: The figures reproduced herein, due to their small scale, are not to be used in connection with material submitted to the F.C.C.



FM CHANNELS
ESTIMATED FIELD STRENGTH EXCEEDED AT 50 PERCENT OF THE POTENTIAL
RECEIVER LOCATIONS FOR AT LEAST 50 PERCENT OF THE TIME
AT A RECEIVING ANTENNA HEIGHT OF 30 FEET

FIGURE 1.



Sliding Scale for use with Figure 1, § 73.333




FIGURE 2.




FIGURE 3.

Subpart C—Noncommercial Educational FM Broadcast Stations

CLASSIFICATION OF STATIONS AND ALLOCATION OF FREQUENCIES

§ 73.501 Channels available for assignment.

(a) The following frequencies, except as provided in paragraph (b) of this section, are available for noncommercial educational FM broadcasting:

Frequency (Mc/s):	*Channel No.*	Frequency (Mc/s):	*Channel No.*
88.1	201	90.1	211
88.3	202	90.3	212
88.5	203	90.5	213
88.7	204	90.7	214
88.9	205	90.9	215
89.1	[1] 206	91.1	216
89.3	207	91.3	217
89.5	208	91.5	218
89.7	209	91.7	219
89.9	210	91.9	220

[1] The frequency 89.1 Mc/s, Channel No. 206 in the New York City metropolitan area, is reserved for the use of the United Nations with the equivalent of an antenna height of 500 feet above average terrain and effective radiated power of 20 kw, and the Commission will make no assignments which would cause objectionable interference with such use.

(b) In Alaska, the frequency band 88–100 Mc/s is allocated exclusively to Government radio services and the non-Government fixed service. The frequencies 88.1 Mc/s through 91.9 Mc/s (Channels 201 through 220, inclusive) will not be assigned in Alaska for use by noncommercial educational FM broadcast stations; however, the frequencies 100.1–107.9 Mc/s (Channels 261 through 300, inclusive) are available for such use.

§ 73.502 State-wide plans.

In considering the assignment of a channel for a noncommercial educational FM broadcast station, the Commission will take into consideration the extent to which each application meets the requirements of any state-wide plan for noncommercial educational FM broadcast stations filed with the Commission, provided that such plans afford fair treatment to public and private educational institutions, urban and rural, at the primary, secondary, higher, and adult educational levels, and appear otherwise fair and equitable.

§ 73.503 Licensing requirements and service.

The operation of, and the service furnished by noncommercial educational FM broadcast stations shall be governed by the following:

(a) A noncommercial educational FM broadcast station will be licensed only to a nonprofit educational organization and upon showing that the station will be used for the advancement of an educational program.

(1) In determining the eligibility of publicly supported educational organizations, the accreditation of their respective state departments of education shall be taken into consideration.

(2) In determining the eligibility of privately controlled educational organizations, the accreditation of state departments of education and/or recognized regional and national educational ac-

crediting organizations shall be taken into consideration.

(b) Each station may transmit programs directed to specific schools in a system or systems for use in connection with the regular courses as well as routine and administrative material pertaining thereto and may transmit educational, cultural, and entertainment programs to the public.

(c) Each station shall furnish a nonprofit and noncommercial broadcast service. No sponsored or commercial programs shall be transmitted nor shall commercial announcements of any character be made. A station shall not transmit the programs of other classes of broadcast stations unless all commercial announcements and commercial references in the continuity are eliminated. The provisions of this paragraph shall not be considered to prohibit the broadcast of programs (without commercial announcements or references) where the only consideration received by the licensee is the furnishing of the program material and/or the payment of line charges.

§ 73.504 Zones, classes of stations, use of channels, facilities, and minimum mileage separations between stations.

(a) *Zones.* For the purpose of assignment of noncommercial educational FM stations, the United States is divided into three zones, Zone I, Zone I–A, and Zone II, having the boundaries specified in § 73.205.

(b) *Classes of stations.* Noncommercial educational stations operating on the channels specified in § 73.501 are divided into four classes, as follows:

(1) A Class D educational station is one operating with no more than 10 watts transmitter power output. Class D stations may be assigned in all zones, on any of the channels specified in § 73.501.

(2) Noncommercial educational stations with more than 10 watts transmitter output are classified as Class A, Class B, or Class C, depending on the effective radiated power and antenna height above average terrain, and the zone in which the station's transmitter is located, on the same basis as provided in §§ 73.205, 73.206, and 73.211 for stations on the non-reserved FM channels. Where a station is authorized with more than 3 kilowatts (4.8 dbk) effective radiated power, or coverage greater than that obtained by the equivalent of 3 kilowatts effective radiated power and 300-foot antenna height above average terrain, it is classified as a Class B station if its transmitter is located in Zone I or Zone I–A, and as a Class C station if its transmitter is located in Zone II. Class A stations may be assigned in all zones.

(c) *Use of channels.* All classes of noncommercial educational stations may be assigned to any of the channels set forth in § 73.501.

(d) *Facilities.* (1) No minimum effective radiated power or antenna height is specified for stations operating on the channels specified in § 73.501.

(2) On Channels 218, 219, and 220 specified in § 73.501, no Class B or Class C educational station will be authorized with effective radiated power greater than that specified in § 73.211(b)(1) for the respective class of station, and the maximum effective radiated power permissible shall also be subject to the provisions of § 73.211(b)(2).

(e) *Minimum mileage separations.* No application for a new station, or change in channel or transmitter site or increase in facilities of an existing station, will be granted unless the proposed facilities will be located so as to meet the adjacent channel mileage separations specified in § 73.207(a) for the class of station involved with respect to assignment on Channels 221, 222, and 223 listed in § 73.201 (except where in the case of an existing station the proposed facilities fall within the provisions of § 73.207(b)).

(f) *Existing stations.* Stations authorized as of September 10, 1962, which do not meet the requirements of paragraphs (d) and (e) of this section, may continue to operate as authorized; but any application to change facilities will be subject to the provisions of this section.

§ 73.505 Standards of good engineering practice.

All noncommercial educational stations operating with more than 10 watts transmitter output power shall be subject to all of the provisions of the FM Technical Standards contained in Subpart B of this part. Class D educational stations shall be subject to the definitions contained in § 73.310 of Subpart B of this part, and also to those other provisions of the FM Technical Standards which are specifically made applicable to them by the provisions of this subpart.

Administrative Procedure

§ 73.514 Cross reference.

See Subpart D of Part 1 of this chapter, for general requirements as to applications, filing of applications and description of application forms, other forms and information to be filed with the Commission, the manner in which applications are processed, and provisions applying to action on applications. See § 1.1111 of Subpart G of that part for the fees to be paid in connection with applications for facilities in the service covered in this subpart.

§ 73.515 Notification of filing of applications.

In order to minimize possible harmful interference at the National Radio Astronomy Observatory site located at Green Bank, Pocahontas County, West Virginia, and the Naval Radio Research Observatory site at Sugar Grove, Pendleton County, West Virginia, an applicant for authority to construct a new noncommercial educational FM broadcast station or for authority to make changes in the frequency, power, antenna height, or antenna directivity of an existing station within the area bounded by 39°15′ N. on the north, 78°30′ W. on the east, 37°30′ N. on the south, and 80°30′ W. on the west shall, at the time of filing such application with the Commission, simultaneously notify the Director, National Radio Astronomy Observatory, P.O. Box #2, Green Bank, West Virginia, 24944, in writing, of the technical particulars of the proposed station. Such notification shall include the geographical coordinates of the antenna, antenna height, antenna directivity if any, proposed frequency, type of emission, and power. In addition, the applicant shall indicate in his application to the Commission the date notification was made to the Observatory. After receipt of such applications, the Commission will allow a period of twenty (20) days for comments or objections in response to the notifications indicated. If an objection to the proposed operation is received during the twenty-day period from the National Radio Astronomy Observatory for itself or on behalf of the Naval Radio Research Observatory, the Commission will consider all aspects of the problem and take whatever action is deemed appropriate.

§ 73.516 Equipment tests.

(a) During the process of construction of a noncommercial educational FM broadcast station, the permittee, after notifying the Commission and Engineer in Charge of the radio district in which the station is located, may without further authority of the Commission, conduct equipment tests for the purpose of such adjustments and measurements as may be necessary to assure compliance with the terms of the construction permit, the technical provisions of the application therefor, the rules and regulations, and the applicable engineering standards.

(b) The Commission may notify the permittee to conduct no tests or may cancel, suspend, or change the date for the beginning of equipment tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Equipment tests may be continued so long as the construction permit shall remain valid.

(d) Inspection of a station will ordinarily be required during the equipment test period and before the commencement of the program test. After construction and after adjustments and measurements have been completed to show compliance with the terms of the construction permit, the technical provisions of the application therefor, the rules and regulations and the applicable engineering standards, the permittee should notify the Engineer in Charge of the radio district in which the station is located that it is ready for inspection.

(e) The authorization for tests embodied in this section shall not be construed as constituting a license to operate but as a necessary part of construction.

§ 73.517 Program tests.

(a) Upon completion of construction of a noncommercial educational FM broadcast station in accordance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations and applicable engineering standards, and when an application for station license has been filed showing the station to be in satisfactory operating condition, the permittee may request authority to conduct program tests: *Provided*, That such request shall be filed with the Com-

mission at least ten (10) days prior to the date on which it is desired to begin such operation and that the Engineer in Charge of the radio district in which the station is located is notified. (All data necessary to show compliance with the terms and conditions of the construction permit must be filed with the license application.)

(b) Program tests shall not commence until specific Commission authority is received. The Commission reserves the right to change the date of the beginning of such tests, or to suspend or revoke the authority for program tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Unless sooner suspended or revoked program test authority continues valid during Commission consideration of the application for license and during this period further extension of the construction permit is not required. Program test authority shall be automatically terminated by final determination upon the application for station license.

(d) All operation under program test authority shall be in strict compliance with the rules governing noncommercial educational FM broadcast stations and in strict accordance with representations made in the application for license pursuant to which the tests were authorized.

(e) The grant of program test authority shall not be construed as approval by the Commission of the application for station license.

§ 73.518 Normal license period.

(a) Licenses for noncommercial educational FM broadcast stations ordinarily will be issued for a period of three years and, when regularly renewed, at three year intervals thereafter: *Provided, however,* That, if the Commission finds that the public interest, convenience, and necessity will be served thereby, it may issue either an initial license or a renewal thereof for a lesser term. When regularly issued or renewed, licenses will be issued to expire at the hour of 3:00 a.m., eastern standard time, in accordance with the following schedule, and at three year intervals thereafter:

(1) For stations located in Florida, Puerto Rico, and Virgin Islands, February 1, 1964.

(2) For stations located in Alabama and Georgia, April 1, 1964.

(3) For stations located in Arkansas, Louisiana, and Mississippi, June 1, 1964.

(4) For stations located in Tennessee, Kentucky, and Indiana, August 1, 1964.

(5) For stations located in Ohio and Michigan, October 1, 1964.

(6) For stations located in Illinois and Wisconsin, December 1, 1964.

(7) For stations located in Iowa and Missouri, February 1, 1965.

(8) For stations located in Minnesota, North Dakota, South Dakota, Montana, and Colorado, April 1, 1965.

(9) For stations located in Kansas, Oklahoma, and Nebraska, June 1, 1965.

(10) For stations located in Texas, August 1, 1965.

(11) For stations located in Wyoming, Nevada, Arizona, Utah, New Mexico, and Idaho, October 1, 1965.

(12) For stations located in California, December 1, 1965.

(13) For stations located in Washington, Oregon, Alaska, and Hawaii, February 1, 1966.

(14) For stations located in Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, and Vermont, April 1, 1966.

(15) For stations located in New Jersey and New York, June 1, 1966.

(16) For stations located in Delaware and Pennsylvania, August 1, 1966.

(17) For stations located in Maryland, District of Columbia, Virginia, and West Virginia, October 1, 1966.

(18) For stations located in North Carolina, and South Carolina, December 1, 1966.

EQUIPMENT

§ 73.550 Acceptability of broadcast transmitters for licensing.

(a) In order to facilitate the filing of, and action on, applications for station authorizations, transmitters will be accepted for licensing by the Commission under one of the following conditions:

(1) A transmitter may be type-accepted upon the request of any manufacturer of transmitters built in quantity by following the type acceptance procedure set forth in Part 2 of this chapter, provided that the data and information submitted indicates that the transmitter meets the requirements of § 73.317. If accepted, such transmitter will be included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment". Applicants specifying transmitters included on such a list need not submit detailed descriptions and diagrams where the correct type number is specified, provided that the equipment proposed is identical with that accepted. Copies of this list are available for inspection at the Commission's office in Washington, D. C., and at each of its field offices.

(2) An application specifying a transmitter not included on the Radio Equipment List, Part B, may be accepted upon the request of a prospective licensee submitting with the application for construction permit a complete description of the transmitter, including the circuit diagram, listing of all tubes used, function of each, multiplication in each stage, plate current and voltage applied to each tube, a description of the oscillator circuit together with any devices installed for the purpose of frequency stabilization and the means of varying output power to compensate for power supply voltage variations. However, if this data has been filed with the Commission by a manufacturer in connection with a request for type acceptance, it need not be submitted with the application for construction permit but may be referred to as "on file". Measurement data for type acceptance made in accordance with subparagraph (1) of this paragraph shall be submitted with the license application.

(3) A transmitter shown on an instrument of authorization by manufacturer and type number, or as a composite, and which was in use prior to June 30, 1955, may continue to be used by the licensee, his successors or assignees, provided such transmitter continues to comply with the rules and regulations.

(4) A permittee may, without further authority, install and utilize a transmitter other than that specifically authorized in its construction permit if such transmitter is listed in the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment" as acceptable for the transmitter output power authorized and, if operation under § 73.595 or § 73.596 is included, such transmitter is listed in the said "Radio Equipment List" as acceptable for the appropriate type of operation.

(5) A licensee may, without further authority, install and utilize a transmitter other than that specifically authorized in its station license if the transmitter so installed and so utilized is listed in the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment" as acceptable for the transmitter output power authorized and, if operation under § 73.595 or § 73.596 is included, such transmitter is listed in the said "Radio Equipment List" as acceptable for the appropriate type of operation. In the event of such a transmitter substitution, the Commission and the Engineer in Charge of the radio district in which the station is located shall be notified within three days after the date of installation of the transmitter. Such notice shall specify the manufacturer and type number of the transmitter and shall include a certification by the licensee that the transmitter as installed complies with the appropriate technical provisions of this subpart.

(b) Additional rules with respect to withdrawal of type-acceptance, modification of type-accepted equipment and limitations on the findings upon which type acceptance is based are set forth in Part 2 of this chapter.

§ 73.552 Frequency monitor.

(a) The licensee of each station licensed for transmitter power output above 10 watts shall have in operation, either at the transmitter or at the place where the transmitter is controlled, a frequency monitor of a type approved by the Commission which shall be independent of the frequency control of the transmitter.

NOTE: Approved frequency monitors are included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment". Copies of this list are available for inspection at the Commission's office in Washington, D. C., and at each of its field offices.

(b) In the event that the frequency monitor becomes defective the station may be operated without the monitor pending its repair or replacement for a period not in excess of 60 days without further authority of the Commission: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the monitor was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the monitor is found to be defective

and immediately after the repaired or replacement instrument has been installed and is functioning properly.

(3) The frequency of the station shall be compared with an external frequency source of known accuracy at sufficiently frequent intervals to insure that the frequency is maintained within the tolerance prescribed in § 73.568. An entry shall be made in the station log as to the method used and the results thereof.

(c) If conditions beyond the control of the licensee prevent the restoration of the monitor to service within the above-allowed period, informal request may be filed in accordance with § 1.549 of this chapter with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

(d) The licensee of each noncommercial educational FM broadcast station licensed for transmitter power output of 10 watts or less shall provide for the measurement of the station frequency by a means independent of the frequency control of the transmitter. The station frequency shall be measured (1) when the transmitter is initially installed, (2) at any time the frequency determining elements are changed, and (3) at any time the licensee may have reason to believe the frequency has shifted beyond the tolerance specified by the Commission's rules.

§ 73.553 Modulation monitor.

(a) The licensee of each station licensed for transmitter power output above 10 watts shall have in operation, either at the transmitter or at the place where the transmitter is controlled, a modulation monitor of a type approved by the Commission.

NOTE: Approved modulation monitors are included on the Commission's "Radio Equipment List, Part B, Aural Broadcast Equipment". Copies of this list are available for inspection at the Commission's office in Washington, D. C., and at each of its field offices.

(b) In the event that the modulation monitor becomes defective the station may be operated without the monitor pending its repair or replacement for a period not in excess of 60 days: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the monitor was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the monitor is found to be defective and immediately after the repaired or replacement monitor has been installed and is functioning properly.

(3) During the period when the station is operated without the modulation monitor the licensee shall provide other suitable means for insuring that the modulation is maintained within the tolerance prescribed in § 73.568.

(c) If conditions beyond the control of the licensee prevent the restoration of the monitor to service within the above allowed period, informal request may be filed in accordance with § 1.549 of this chapter with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

(d) The licensee of each noncommercial educational FM broadcast station licensed for transmitter power output of 10 watts or less shall provide a percentage modulation indicator or a calibrated program level meter from which a satisfactory indication of the percentage of modulation of the transmitter can be determined.

§ 73.554 Transmitter performance.

(a) The transmitter proper and associated transmitting equipment of each noncommercial educational FM broadcast station licensed for transmitter power output above 10 watts shall be designed, constructed and operated in accordance with § 73.317.

(b) The transmitter proper and associated transmitting equipment of each noncommercial educational FM broadcast station licensed for transmitter power output of 10 watts or less, although not required to meet all requirements of § 73.317 shall be constructed with safety features in accordance with the specifications of article 810 of the current National Electrical Code as approved by the American Standards Association and shall be so operated, tuned, and adjusted that emissions are not radiated outside the authorized band which cause or which are capable of causing interference to the communications of other stations. The audio distortion, audio frequency range, carrier hum, noise level, and other essential phases of the operation which control the external effects, shall at all times be capable of providing satisfactory broadcast service. Studio equipment properly covered by an underwriter's certificate will be considered as satisfying safety requirements.

§ 73.555 Auxiliary transmitter.

Upon showing that a need exists for the use of an auxiliary transmitter in addition to the regular transmitter of a broadcast station, a license therefor may be issued: *Provided,* That:

(a) An auxiliary transmitter may be installed either at the same location as the main transmitter or at another location.

(b) A licensed operator shall be in control whenever an auxiliary transmitter is placed in operation.

(c) The auxiliary transmitter shall be maintained so that it may be placed into immediate operation at any time for the following purposes:

(1) The transmission of the regular programs upon the failure of the main transmitter.

(2) The transmission of regular programs during maintenance or modification work on the main transmitter, necessitating discontinuance of its operation for a period not to exceed 5 days. (This includes the equipment changes which may be made without authority as set forth elsewhere in the rules and regulations or as authorized by the Commission by letter or by construction permit. Where such operation is required for periods in excess of 5 days, request therefor shall be in accordance with § 1.542 of this chapter.)

(3) Upon request by a duly authorized representative of the Commission.

(d) The auxiliary transmitter shall be tested at least once each week to determine that it is in proper operating condition and that it is adjusted to the proper frequency, except that in case of operation in accordance with paragraph (c) of this section during any week, the test in that week may be omitted provided the operation under paragraph (c) is satisfactory. A record shall be kept of the time and result of each test. Such records shall be retained for a period of two years.

(e) The auxiliary transmitter shall be equipped with satisfactory control equipment which will enable the maintenance of the frequency emitted by the station within the limits prescribed by the regulations in this part.

(f) The operating power of an auxiliary transmitter may be less than the authorized power of the main transmitter, but in no event shall it be greater than such power.

§ 73.556 Alternate main transmitters.

The licensee of a noncommercial educational FM broadcast station may be licensed for alternate main transmitters provided that a technical need for such alternate transmitters is shown (such as licensees maintaining 24-hour schedule and needing alternate operation for maintenance, or where developmental work requires alternate operation) and that the following conditions are met:

(a) Both transmitters are located at the same place.

(b) Both transmitters shall have the same power rating.

(c) Both transmitters shall meet the requirements of § 73.554.

§ 73.557 Changes in equipment and antenna system.

Licensees of noncommercial educational FM broadcast stations shall observe the following provisions with regard to changes in equipment and antenna system:

(a) No changes in equipment shall be made:

(1) That would result in the emission of signals outside of the authorized channel.

(2) That would result in the external performance of the transmitter being in disagreement with § 73.554.

(b) Specific authority, upon filing formal application (FCC Form 340) therefor, is required for a change in service area or for any of the following changes:

(1) Changes involving an increase or decrease in the power rating of the transmitter.

(2) A replacement of the transmitter as a whole.

(3) Change in the location of the transmitting antenna.

(4) Change in antenna system, including transmission line.

(5) Change in location of main studio, if it is proposed to move the main studio to a different city from that specified in the license.

(6) Change in the power delivered to the antenna.

(7) Change in frequency control and/or modulation system.

(8) Change in the authorized transmitter remote control point(s).

(c) Other changes, except as above provided for in this section, may be made at any time without the authority of the Commission, provided that the Commission shall be promptly notified thereof and such changes shall be shown in the next application for renewal of license.

§ 73.558 Indicating instruments.

(a) Each noncommercial FM broadcast station licensed for transmitter power above 10 watts shall be equipped with indicating instruments, which conform with the specifictions set forth in § 73.320 for measuring the direct plate voltage and current of the last radio stage and the transmission line radio frequency current, voltage, or power.

(b) In the event that any one of these indicating instruments becomes defective when no substitute which conforms with the required specifications is available, the station may be operated without the defective instrument pending its repair or replacement for a period not in excess of 60 days: *Provided*, That:

(1) Appropriate entries shall be made in the maintenance log of the station showing the date and time the meter was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the instrument is found to be defective and immediately after the repaired or replaced instrument has been installed and functioning properly.

(3) If the defective instrument is a plate voltmeter or plate ammeter in the last radio stage, the operating power shall be maintained by means of the radio frequency transmission line meter.

(c) If conditions beyond the control of the licensee prevent the restoration of the meter to service within the above allowed period, informal request may be filed in accordance with § 1.549 of this chapter with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

TECHNICAL OPERATION AND OPERATORS

§ 73.561 Operating schedule.

Noncommercial educational FM broadcast stations are not required to operate on a regular schedule and no minimum number of hours of operation is specified; but the hours of actual operation during a license period shall be taken into consideration in considering the renewal of noncommercial educational FM broadcast licenses wherever it appears that the channels available for such stations are insufficient to meet the demand.

§ 73.562 Experimental operation.

The period between 1:00 a.m., and 6:00 a.m., local standard time, may be used for experimental purposes in testing and maintaining apparatus by the licensee of any noncommercial educational FM broadcast station on its assigned frequency and not in excess of its authorized power, without specific authorization from the Commission.

§ 73.563 Station inspection.

The licensee of any noncommercial educational FM broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 73.564 Station and operator licenses; posting of.

(a) The station license and any other instrument of station authorization shall be posted in a conspicuous place and in such manner that all terms are visible at the place the licensee considers to be the principal control point of the transmitter. At all other control points listed on the station authorization, a photocopy of the station license and other instruments of station authorization shall be posted.

(b) The original operator license, or FCC Form 759, of each station operator shall be posted at the place where he is on duty as an operator.

§ 73.565 Operator requirements.

(a) One or more radio operators holding a valid radiotelephone first-class operator license, except as provided in paragraph (b) of this section, shall be in actual charge of the transmitting apparatus and shall be on duty either at the transmitter location or remote control point.

(b) In cases where a station is authorized to operate with transmitter power output not in excess of 25 kilowatts, the routine operation of the transmitter may be performed by an operator holding a valid first-class or second-class radiotelephone or radiotelegraph operator license or a radiotelephone third-class operator permit which has been endorsed for broadcast station operation. The operator shall be on duty at the transmitter or authorized remote control point and in actual charge thereof. Until April 19, 1964, routine operation of transmitters of such stations may be performed by persons holding valid radiotelephone operator third-class permits which are not endorsed for broadcast station operation, or valid restricted radiotelephone operator permits. Except at times when the operation of the station is under the immediate supervision of an operator holding a valid operator license of the grade indicated for the station in subparagraphs (1), (2), or (3) of paragraph (c) of this section, adjustments of the transmitter shall be limited to the following:

(1) Those necessary to turn the transmitter on and off.

(2) Adjustments of external controls as may be necessary to compensate for voltage fluctuations in the power supply.

(3) Adjustments of external control to maintain modulation of the transmitter within prescribed limits.

It shall be the responsibility of the licensee to insure that the person who may be required to perform these tasks, as well as to perform other duties (such as reading meters and making log entries), is properly instructed so as to be capable of performing the duties required of him at times when not under the immediate supervision of an operator of the grade indicated for the station in subparagraphs (1), (2), or (3) of paragraph (c) of this section. Where necessary, printed step-by-step instructions shall be posted for those transmitter adjustments which the lesser grade operator is authorized to make. Should the transmitting apparatus be observed to be operating in any manner inconsistent with this subpart or the current instrument of authorization for the station at any time when an operator of the grade indicated for the station in subparagraphs (1), (2), or (3) of paragraph (c) of this section is not immediately available, and none of the above adjustments is effective in correcting the condition of improper operation, the emissions of the station shall be immediately terminated.

(c) If the route operation of the transmitting apparatus at a noncommercial educational FM broadcast station is performed by a lesser grade operator pursuant to the provisions of paragraph (b) of this section, the licensee shall employ as a full-time member of the station staff (in the alternative, the licensee may contract in writing for the services on a part-time basis) one or more operators holding:

(1) A valid radiotelephone first-class operator license if the station is authorized to operate with transmitter power output of more than 1 kw but not in excess of 25 kw.

(2) A valid radiotelephone first-class or second-class operator license if the station is authorized to operate with transmitter power output of more than 10 watts but not in excess of 1 kw.

(3) A valid first-class or second-class radiotelephone or radiotelegraph operator license if the station is authorized to operate with transmitter power output of not more than 10 watts.

The operators specified in subparagraphs (1), (2), and (3) of this paragraph shall perform transmitter maintenance and shall be promptly available at all times to correct conditions of improper operation beyond the scope of authority of the lesser grade operator on duty. If the services of the operator or the operators indicated in subparagraphs (1), (2), and (3) of this paragraph are on a contract part-time basis, a signed copy of the agreement shall be kept in the files of the station and at the transmitter or control point and shall be made available for inspection upon request by any authorized representative of the Commission. A signed copy of the agreement shall also be forwarded to the Commission and to the Engineer in Charge of the radio district in which the station is located within 3 days after the agreement is signed.

NOTE: During the period prior to April 19, 1964, the alternative of contracting in writing for the services on a part-time basis of the operators mentioned in subparagraphs (1) and (2) of this paragraph may not be followed unless the routine transmitter operation under the provisions of paragraph (b) of this section is performed by operators holding at least valid radiotelephone third-class operator permits which have been

endorsed for broadcast station operation. Information concerning examinations for such operator permits will be available to all applicants through the Commission's field offices after January 1, 1964.

(d) The licensed operator on duty and in charge of a noncommercial educational FM broadcast transmitter may, at the discretion of the licensee, be employed for other duties or for the operation of another radio station or stations in accordance with the class of operator's license which he holds and the rules and regulations governing such other stations: *Provided, however,* That such duties shall in nowise interfere with the proper operation of the FM broadcast transmitter.

(e) At all noncommercial educational FM broadcast stations, a complete inspection of all transmitting equipment in use shall be made by an operator holding a valid radiotelephone first-class operator license at least once each day, 5 days each week, with an interval of no less than 12 hours between successive inspections. This inspection shall include such tests, adjustments, and repairs as may be necessary to insure operation in conformance with the provisions of this subpart and the current instrument of authorization for the station: *Provided,* That if the transmitter power output is in excess of 10 watts but not greater than 1 kw, an operator holding a radiotelephone second-class operator license may perform the required inspection: *Provided, further,* That if the transmitter power output is 10 watts or less, no such daily inspection need be made, although this shall in no way relieve such stations from the duty to operate in conformance with the provisions of this subpart and the current instrument of authorization.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 73.566 Facsimile broadcasting and multiplex transmission.

(a) Noncommercial educational FM broadcast stations may transmit simplex facsimile in accordance with transmission standards set forth in § 73.318 during periods not devoted to FM aural broadcasting. Such transmissions may not exceed one hour during the period between 7 a.m. and midnight (no limit is placed upon the hours between midnight and 7 a.m.). The Commission shall be notified by the licensee of the noncommercial educational FM broadcast station of its intent to transmit such facsimile.

(b) Noncommercial educational FM broadcast stations may, upon securing authorization from the Commission, transmit multiplex facsimile in accordance with transmission standards set forth in § 73.318: *Provided,* That the transmission of such facsimile does not reduce the quality of the aural program simultaneously transmitted by the licensee below that required by the FM Technical Standards in Subpart B of this part and that no degradation of such aural programs will result from such facsimile transmissions when received on FM receivers not equipped with filters or other additional equipment.

§ 73.567 Operating power; determination and maintenance of.

(a) *Determination.* The operating power of each station shall be determined by either the direct or indirect method.

(1) Using the direct method, the power shall be measured at the output terminals of the transmitter while operating into a dummy load of substantially zero reactance and a resistance equal to the transmission line characteristic impedance. The transmitter shall be unmodulated during this measurement. If electrical devices are used to determine the power output, such devices shall permit determination of this power to within an accuracy of ±5 percent of the power indicated by the full scale reading of the electrical indicating instrument of the device. If temperature and coolant flow indicating devices are used to determine the power output, such devices shall permit determination of this power to within an accuracy of 4 percent of measured average power output. During this measurement the direct plate voltage and current of the last radio stage and the transmission line meter shall be read and compared with similar readings taken with the dummy load replaced by the antenna. These readings shall be in substantial agreement.

(2) Using the indirect method, the operating power is the product of the plate voltage (E_p) and the plate current (I_p) of the last radio stage, and an efficiency factor, F, as follows:

$$\text{Operating power} = E_p \times I_p \times F$$

(3) The efficiency factor, F, shall be established by the transmitter manufacturer for each type of transmitter for which he submits data to the Commission, and shall be shown in the instruction books supplied to the customer with each transmitter. In the case of composite equipment, the factor F shall be furnished to the Commission with a statement of the basis used in determining such factor.

(b) *Maintenance.* The operating power of stations licensed for transmitter power output greater than 10 watts shall be maintained in accordance with subparagraph (1) of this paragraph and the operating power of stations licensed for transmitter output power of 10 watts or less shall be maintained in accordance with subparagraph (2) of this paragraph.

(1) The operating power of stations licensed for transmitter output power greater than 10 watts shall be maintained as near as practicable to the authorized power and shall not be less than 90 percent nor greater than 105 percent of authorized power except as indicated in paragraph (c) of this section.

(i) When determined by the direct method, the operating power of the transmitter shall be monitored by a transmission line meter which reads proportional to the voltage, current, or power at the output terminals of the transmitter, the meter to be calibrated at intervals not exceeding 6 months. The calibration shall cover, as a minimum, the range from 90 to 105 percent of authorized power and the meter shall provide clear indications which will permit maintaining the operating power within the prescribed tolerance or the meter shall be calibrated to read directly in power units.

(2) Stations licensed to operate with a transmitter output power of 10 watts or less may be operated at less than authorized power but in no event shall the operating power be greater than 5 percent above the authorized power. The transmitter of each such station shall be so maintained as to be capable of operation at maximum licensed power.

(c) *Reduced power.* If a station licensed for transmitter power output greater than 10 watts finds it impossible to operate with authorized power, the station may operate with reduced power for a period not to exceed 10 days. In the event the period of reduced power operation exceeds 10 days, the Commission and the Engineer in Charge of the radio district in which the station is located shall be notified in writing on the eleventh day and shall also be notified when operation with authorized power is resumed.

§ 73.568 Modulation.

The percentage of modulation of all stations shall be maintained as high as possible consistent with good quality of transmission and good broadcast practice and in no case less than 85 percent or more than 100 percent on peaks of frequent recurrence during any selection which normally is transmitted at the highest level of the program under consideration.

§ 73.569 Frequency tolerance.

(a) The center frequency of each noncommercial educational FM broadcast station licensed for transmitter power output of 10 watts or less shall be maintained within 3,000 cycles of the assigned center frequency.

(b) The center frequency of each noncommercial educational FM broadcast station licensed for transmitter power output above 10 watts shall be maintained within 2,000 cycles of the assigned center frequency.

§ 73.570 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of that part.

§ 73.571 Discontinuance of operation.

The licensee of each station shall notify the Commission in Washington, D.C., and the Engineer in Charge of the radio district in which the station is located of permanent discontinuance of operation at least two days before operation is discontinued. The licensee shall, in addition, immediately forward the station license and other instruments of authorization to the Washington, D.C., office of the Commission for cancellation.

§ 73.572 Remote control authorization.

(a) Application to operate a station by remote control may be made as a part of the application for construction permit for a new station. Application to operate an authorized station shall be made on FCC Form 301–A.

(b) An authorization for remote control will be issued only after a satisfactory showing has been made in regard to the following, among others:

(1) The location of the remote control point(s);

(2) The transmitter, if the power rating is in excess of 10 kw, is reliable and capable of being operated by remote control.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 73.573 Remote control operation.

(a) Operation by remote control shall be subject to the following conditions:

(1) The equipment at the operating and transmitting positions shall be so installed and protected that it is not accessible to or capable of operation by persons other than those duly authorized by the licensee.

(2) The control circuits from the operating position to the transmitter shall provide positive on and off control and shall be such that open circuits, short circuits, grounds or other line faults will not actuate the transmitter and any fault causing loss of such control will automatically place the transmitter in an inoperative position.

(3) A malfunction of any part of the remote control equipment and associated line circuits resulting in improper control or inaccurate meter readings shall be cause for the immediate cessation of operation by remote control.

(4) Control and monitoring equipment shall be installed so as to allow the licensed operator at the remote control point to perform all the functions in a manner required by the Commission's rules.

(b) All stations with a transmitter output power of over 10 watts, whether operating by remote control or direct control, shall be equipped so as to be able to follow the prescribed procedure set forth in § 73.921(b). Stations with a transmitter output of 10 watts or less shall be equipped so as to be able to follow the prescribed procedure set forth in § 73.921(c).

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

OTHER OPERATING REQUIREMENTS

§ 73.581 General requirements relating to logs.

(a) The licensee or permittee of each noncommercial FM broadcast station shall maintain program, operating, and maintenance logs as set forth in §§ 73.582, 73.583 and 73.584. Each log shall be kept by the person or persons competent to do so, having actual knowledge of the facts required, who shall sign the appropriate log when starting duty and again when going off duty.

(b) The logs shall be kept in an orderly and legible manner, in suitable form, and in such detail that the data required for the particular class of station concerned is readily available. Key letters or abbreviations may be used if proper meaning or explanation is contained elsewhere in the log. Each sheet shall be numbered and dated. Time entries shall be either in local standard or daylight saving time and shall be indicated accordingly.

(c) No log or portion thereof shall be erased, obliterated, or willfully destroyed within the period of retention provided by the provisions of this part. Any necessary correction may be made only by the person originating the entry who shall strike out the erroneous portion, initial the correction made, and indicate the date of correction.

(d) Original data may be recorded in rough form and later transcribed into the log, but in such case all portions of the original memoranda shall be preserved as a part of the complete log.

§ 73.582 Program log.

(a) The following entries shall be made in the program log:

(1) An entry of the time each station identification announcement (call letters and location) is made.

(2) An entry briefly describing each program broadcast, such as "music," "drama," "speech," etc., together with the name or title thereof and the sponsor's name, with the time of the beginning and ending of the complete program. If a mechanical record is used, the entry shall show the exact nature thereof, such as "record," "transcription," etc., and the time it is announced as a mechanical reproduction. If a speech is made by a political candidate, the name and political affiliations of such speaker shall be entered.

(b) No provision of this section shall be construed as prohibiting the recording or other automatic maintenance of data required for program logs. However, where such automatic logging is used, the licensee must comply with the following requirements:

(1) The licensee, whether employing manual or automatic logging or a combination thereof, must be able accurately to furnish the Commission with all information required to be logged;

(2) Each recording, tape, or other means employed shall be accompanied by a certificate of the operator or other responsible person on duty at the time or other duly authorized agent of the licensee, to the effect that it accurately reflects what was actually broadcast. Any information required to be logged which cannot be incorporated in the automatic process shall be maintained in a separate record which shall be similarly authenticated.

(3) The licensee shall extract any required information from the recording for the days specified by the Commission or its duly authorized representative and submit it in written log form, together with the underlying recording, tape or other means employed.

§ 73.583 Operating log.

(a) The following entries shall be made in the operating log:

(1) An entry of the time the station begins to supply power to the antenna and the time it stops.

(2) An entry of each interruption of the carrier wave, where restoration is not automatic, its cause and duration followed by the signature of the person restoring operation (if licensed operator other than the licensed operator on duty).

(3) An entry, at the beginning of operation and at intervals not exceeding one-half hour, of the following (actual readings observed prior to making any adjustments to the equipment) and, when appropriate, an indication of corrections made to restore parameters to normal operating values:

(i) Operating constants of last radio stage (total plate voltage and plate current).

(ii) RF transmission line meter reading.

(iii) Frequency monitor reading.

(4) Any other entries required by the instrument of authorization or the provisions of this part.

(b) Automatic devices accurately calibrated and with appropriate time, date and circuit functions may be utilized to record the entries in the operating log: *Provided*, That:

(1) They do not affect the operation of circuits or accuracy of indicating instruments of the equipment being recorded;

(2) The recording devices have an accuracy equivalent to the accuracy of the indicating instruments;

(3) The calibration is checked against the original indicators at least once a week and the results noted in the maintenance log;

(4) Provision is made to actuate automatically an aural alarm circuit located near the operator on duty if any of the automatic log readings are not within the tolerances or other requirements specified in the rules or instrument of authorization;

(5) Unless the alarm circuit operates continuously, devices which record each parameter in sequence must read each parameter at least once during each 10-minute period and clearly indicate the parameter being recorded;

(6) The automatic logging equipment is located at the remote control point if the transmitter is remotely controlled, or at the transmitter location if the transmitter is manually controlled;

(7) The automatic logging equipment is located in the near vicinity of the operator on duty and is inspected by him periodically during the broadcast day; and

(8) The indicating equipment conforms to the requirements of § 73.320 except that the scales need not exceed 2 inches in length. Arbitrary scales may not be used.

§ 73.584 Maintenance log.

The following entries shall be made in the maintenance log:

(a) An entry each week of the time and result of test of auxiliary transmitter.

(b) A notation of all frequency checks and measurements made independently of the frequency monitor and of the correlation of these measurements with frequency monitor indications.

(c) A notation each week of the calibration check of automatic recording devices as required by § 73.583(b)(3).

(d) An entry of the date and time of removal from and restoration to service of any of the following equipment in the event it becomes defective:

(1) Modulation monitor.

(2) Frequency monitor.

(3) Final stage plate voltmeter.

(4) Final stage plate ammeter.

(5) Transmission line radio frequency voltage, current, or power meter.

(e) Record of tower light inspections where required by § 17.38 of this chapter (Part 17—Construction, Marking, and Lighting of Antenna Structures).

(f) Entries shall be made so as to describe fully any experimental operation during the experimental period.

(g) Upon completion of the inspection required by § 73.565(e), the inspecting operator shall enter a signed statement that the required inspection has been made, noting in detail the tests, adjustments, and repairs which were accomplished in order to insure operation in accordance with the provisions of this subpart and the current instrument of authorization of the station. The statement shall also specify the amount of time, exclusive of travel time to and from the transmitter, which was devoted to such inspection duties. If complete repair could not be effected, the statement shall set forth in detail the items of equipment concerned, the manner and degree in which they are defective, and the reasons for failure to make satisfactory repairs.

(h) Any other entries required by the current instrument of authorization of the station and the provisions of this subpart.

§ 73.585 Retention of logs.

Logs of noncommercial educational FM broadcast stations shall be retained by the licensee or permittee for a period of 2 years: *Provided, however,* That logs involving communications incident to a disaster or which include communications incident to or involved in an investigation by the Commission and concerning which the licensee or permittee has been notified, shall be retained by the licensee or permittee until he is specifically authorized in writing by the Commission to destroy them: *Provided, further,* That logs incident to or involved in any claim or complaint of which the licensee or permittee has notice shall be retained by the licensee or permittee until such claim or complaint has been fully satisfied or until the same has been barred by statute limiting the time for the filing of suits upon such claims.

§ 73.586 Availability of logs and records.

The following shall be made available upon request by an authorized representative of the Commission:

(a) Program, operating and maintenance logs.

(b) Equipment performance measurements required by § 73.554.

§ 73.587 Station identification.

(a) A licensee of a noncommercial educational FM broadcast station shall make at least the following station identification announcements (call letters and location): (1) at the beginning and ending of each time of operation; and (2) within 2 minutes of each hour and each half hour during operation: *Provided,*

(b) Such identification announcement need not be made on the hour or half hour when to make such announcement would interrupt a single continuous program of longer duration than 30 minutes. In such cases the identification announcement shall be made at the beginning of the program, at the first interruption of the continuity, and at the conclusion of the program.

(c) In making the identification announcement, the call letters shall be given only on the channel of the station identified thereby.

§ 73.588 Mechanical reproductions.

(a) No mechanically reproduced program consisting of a speech, news event, news commentator, forum, panel discussion, or special event in which the element of time is of special significance, or any other program in which the element of time is of special significance and presentation of which would create, either intentionally or otherwise, the impression or belief on the part of the listening audience that the event or program being broadcast is in fact occurring simultaneously with the broadcast, shall be broadcast without an appropriate announcement being made either at the beginning or end of such reproduction or at the beginning or end of the program in which such reproduction is used that it is a mechanical reproduction or a mechanically reproduced program: *Provided, however,* That each such program of one minute or less need not be announced as such.

(b) The exact form of identifying announcement is not prescribed, but the language shall be clear and in terms commonly used and understood. Any other program mechanically reproduced or series of mechanical reproductions, including a mechanical reproduction used for background music, sound effects, station identification, program identification (theme music of short duration) or identification of sponsorship of the program proper, need not be announced as provided in paragraph (a) of this section, but the licensee shall not attempt affirmatively to create the impression that any program being broadcast by mechanical reproduction consists of live talent.

(c) The requirements of paragraph (a) of this section are waived with respect to network programs, transcribed and rebroadcast at a later hour because of the time zone differential between the place where the program originates and where it is rebroadcast, this waiver being applicable whether the off-the-line recording is made by the network itself at one of its key stations or by an individual station, but only when the off-the-line recording is for broadcast at an hour not exceeding the time zone differential between the place where the program originates and where it is rebroadcast. Each station which broadcasts network programs at a later hour in accordance with this waiver shall make an appropriate announcement at least once each day between the hours of 10:00 a. m., and 10:00 p. m., stating that some or all of the network programs which are broadcast by that station are delayed broadcasts by means of transcription. This waiver provision also applies during the annual periods in which daylight saving time will be effective with respect to network programs transcribed and rebroadcast one hour later because of the time differential resulting from the adoption of daylight saving time in some areas.

§ 73.590 Broadcasts by candidates for public office.

(a) *Definitions.* A "legally qualified candidate" means any person who has publicly announced that he is a candidate for nomination by a convention of a political party or for nomination or election in a primary, special, or general election, municipal, county, state, or national, and who meets the qualifications prescribed by the applicable laws to hold the office for which he is a candidate, so that he may be voted for by the electorate directly or by means of delegates or electors, and who—

(1) Has qualified for a place on the ballot or

(2) Is eligible under the applicable law to be voted for by sticker, by writing in his name on the ballot, or other method and (i) has been duly nominated by a political party which is commonly known and regarded as such, or (ii) makes a substantial showing that he is a bona fide candidate for nomination or office, as the case may be.

(b) *General requirements.* No station licensee is required to permit the use of its facilities by any legally qualified candidate for public office, but if any licensee shall permit any such candidate to use its facilities, it shall afford equal opportunities to all other such candidates for that office to use such facilities: *Provided,* That such licensee shall have no power of censorship over the material broadcast by any such candidate.

(c) *Practices.* No licensee shall make any discrimination in practices, regulations, facilities, or services for or in connection with the service rendered pursuant to this part, or make or give any preference to any candidate for public office or subject any such candidate to any prejudice or disadvantage; nor shall any licensee make any contract or other agreement which shall have the effect of permitting any legally qualified candidate for any public office to broadcast to the exclusion of other legally qualified candidates for the same public office.

(d) *Records; inspection.* Every licensee shall keep and permit public inspection of a complete record of all requests for broadcast time made by or on behalf of candidates for public office, together with an appropriate notation showing the disposition made by the licensee of such requests. Such records shall be retained for a period of two years.

(e) *Time of request.* A request for equal opportunities must be submitted

to the licensee within one week of the day on which the prior use occurred.

(f) *Burden of proof.* A candidate requesting such equal opportunities of the licensee, or complaining of non-compliance to the Commission shall have the burden of proving that he and his opponent are legally qualified candidates for the same public office.

(Sec. 315, 48 Stat. 1088, as amended; 47 U.S.C. 315.)

§ 73.591 Rebroadcast.

(a) The term "rebroadcast" means reception by radio of the program of a radio station, and the simultaneous or subsequent retransmission of such program by a broadcast station. The broadcasting of a program relayed by a remote pickup broadcast station or studio transmitter link is not considered a rebroadcast. In case a program is transmitted from its point of origin to a broadcast station entirely by telephone facilities in which a section of such transmission is by radio, the broadcasting of this program is not considered a rebroadcast.

NOTE: As used in this section, program includes any complete program or part thereof.

(b) The licensee of a noncommercial educational FM broadcast station may, without further authority of the Commission, rebroadcast the program of a United States standard, FM, noncommercial educational, or international broadcast station, provided the Commission is notified of the call letters of each station rebroadcast and the licensee certifies that express authority has been received from the licensee of the station originating the program. The foregoing requirements concerning notification of call letters and certification of authority shall not apply to a station when rebroadcasting Defense Network (FM) programs. (Blanket authorizations for the rebroadcast of such programs have been filed with the Commission by all Defense Network (FM) stations.)

NOTE 1: The notice and certification of consent shall be given within 3 days of any single rebroadcast, but in case of the regular practice of rebroadcasting certain programs several times during a license period, notice and certification of consent shall be given for the ensuing license period with the application for renewal of license, or at the beginning of such rebroadcast practice if begun during a license period.

NOTE 2: See § 73.503(c).

(c) No licensee of a noncommercial educational FM broadcast station shall rebroadcast the program of any United States radio station not designated in paragraph (b) of this section without written authority having first been obtained from the Commission upon application (informal) accompanied by written consent or certification of consent of the licensee of the station originating the program.

NOTE: By Order No. 82, dated and effective June 24, 1941, until further order of the Commission, § 73.591(c) is suspended only insofar as it requires prior written authority of the Commission for the rebroadcasting of programs originated for the express purpose by U. S. Government radio stations.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325.)

§ 73.593 Subsidiary Communications Authorizations.

(a) A noncommerical educational FM broadcast licensee or permittee may apply for a Subsidiary Communications Authorization (SCA) to provide limited types of subsidiary service on a multiplex basis. Any use of SCA by such licensee or permittee must be consistent with the limitation on the purpose and operation of noncommercial educational FM stations contained in § 73.503: *Provided,* That uses permitted under this paragraph will not be considered "commercial" as long as no consideration for such use (other than the furnishing of the material transmitted and/or payment of line charges) is received by the licensee, directly or indirectly, and no commercial announcements or references are contained in the material transmitted under the SCA. Permissible uses must fall within one or both of the following categories:

(1) Transmission of programs which are noncommercial and in furtherance of an educational purpose, and which are of a broadcast nature but of interest primarily to limited segments of the station's audience. Illustrative services include: programs for presentation in classrooms, programs designed for specialized audiences such as doctors or other professional groups, and any use which would be permitted for a commercial FM station under § 73.293(a)(1), subject to the prohibitions against commercial operations and limitation as to purpose contained in this section and in § 73.503.

(2) Transmission of signals which are directly related to the operation of FM broadcast stations; for example, relaying of broadcast material to other broadcast stations, remote cueing and order circuits, remote control telemetering functions associated with authorized STL operation, and similar uses.

(b) Applications for Subsidiary Communications Authorization shall be submitted on FCC Form 318. An applicant for SCA shall specify the particular nature or purpose of the proposed use.

(c) SCA operations may be conducted without restriction as to time so long as the main channel is programmed simultaneously.

§ 73.594 Nature of the SCA.

(a) The SCA is of a subsidiary or secondary nature and shall not exist apart from the noncommercial educational FM license or permit. No transfer or assignment of it shall be made separate from the FM license or permit, and failure to transfer the SCA (through application on FCC Form 318) with the FM license or permit renders the SCA void. The licensee or permittee must seek renewal of FM license or permit; failure to renew the latter automatically terminates the SCA.

(b) The grant or renewal of a noncommercial educational FM license or permit will not be furthered or promoted by the proposed or past operation under an SCA; the licensee must establish that its broadcast operation is in the public interest wholly apart from the SCA activities. (Violation of rules applicable to the SCA operation would, of course, reflect on the licensee's qualifications to hold its broadcast license or permit.)

§ 73.595 Operation under the SCA.

(a) The holder of the SCA must restrict its operation to the uses or purposes granted by the Commission in acting upon the SCA application; prior permission to engage in any additional or new activity must be obtained from the Commission.

(b) No consideration (other than the furnishing of the material transmitted and/or payment of line charges) may be received by the licensee, directly or indirectly, for the transmission of any matter under the SCA. No sponsored or commercial program shall be transmitted under the SCA, nor shall commercial announcements of any character be made. If programs from other stations are transmitted under the SCA, all commercial announcements and commercial references therein shall be deleted.

(c) Supersonic tones or other similar devices may be employed with respect to material transmitted under the SCA operation, with the station using appropriate actuating devices with receivers where desired.

(d) In all arrangements entered into under the SCA with outside parties, the licensee or permittee must pass on all material to be transmitted over the station's facilities, with the right to reject any material which it deems inappropriate or undesirable.

(e) The requirements of §§ 73.590 and 73.591 are equally applicable when the noncommercial educational FM licensee is engaged in operation pursuant to the SCA.

(f) The requirements of § 73.587 with respect to station identification announcements must be met by identification on the main carrier when a station is engaged in SCA operations. The licensee may prevent their reception on receivers adapted for SCA reception by the use of supersonic tones capable of deactivating these specialized receivers.

(g) The noncommercial educational FM licensee or permittee shall maintain logs for the SCA operations. In the program log, the following entries shall be made:

(1) An entry of the time each station identification announcement (call letters and location) is made.

(2) An entry describing the material transmitted in each hour segment. If a speech is made by a political candidate, the name and political affiliations of such speaker shall be entered.

(h) Operation under the SCA shall be conducted in compliance with the standards set forth in § 73.319 for SCA operation by commercial FM stations.

§ 73.596 Stereophonic broadcasting.

Noncommercial educational FM broadcast stations may, without further authority, transmit stereophonic programs in accordance with the technical standards governing commercial FM broadcast stereophonic operation as set forth

in § 73.322: *Provided, however,* That the Commission and the Engineer in Charge of the radio district in which the station is located shall be notified within 10 days from the installation of type-accepted stereophonic transmission equipment or any change therein: *And provided further,* That the Commission and the Engineer in Charge shall be notified within 10 days from the commencement of stereophonic operation, scheduled hours of such operation or any change therein.

§ 73.597 Operation during emergency.

(a) The licensee of a noncommercial educational FM broadcast station or the permittee of such a station operating under program test authority is authorized only to disseminate radio communications intended to be received by the public. However, during a period of emergency or imminent emergency in the area in which the station is located such a licensee or permittee may also utilize its station for transmitting communications directly related to the emergency which are intended to be received by specific individuals for the purpose of dispatching aid, assisting in rescue operations or otherwise promoting the safety of life and property or alleviating hardship. In the course of such operation a station may communicate with stations of other classes and in other services. For the purposes of this section, an emergency shall mean a situation that would generally and seriously endanger life and property or cause substantial hardship as a result of events such as hurricane or other severe weather conditions, flood, earthquake or wide-area forest fire. The term shall not include situations resulting from frosts, or localized fires which are not a source of general danger.

(b) The decision to operate under the provisions of this section lies solely with the licensee or permittee of the station, requests by governmental or other officials not being controlling. However, such emergency operation shall terminate upon order of the Commission.

(c) When engaged in operation under the provisions of this section a station shall use the frequency specified in and power not in excess of that specified in its instrument of authorization.

(d) A licensee or permittee operating under the provisions of this section shall (1) as soon as possible after the beginning of such emergency use, send notice to the Commission at Washington, D.C., and to the Engineer in Charge of the district in which the station is located, stating the nature of the emergency and the use to which the station is being put; (2) discontinue such emergency operation as soon as the conditions requiring such operation are no longer present or the public has had an opportunity to be adequately informed; and (3) immediately upon cessation of such emergency operation notify the Commission in Washington, D.C., and the Engineer in Charge of the district in which the station is located, and shall in such notice justify the operation by stating the nature of the emergency, the exact times of operation, the type of emergency information transmitted, the total amount of time devoted to the transmission of emergency information, and other pertinent details.

(e) No operation under this section shall be permitted if an Emergency Action Condition, under the provisions of Subpart G of this part, is in effect. If a station is operating under this section and an Emergency Action Condition is declared, compliance with the Emergency Action Notification shall take precedence.

Subpart D—[Reserved]

Subpart E—Television Broadcast Stations

General

§ 73.601 Scope of subpart.

This subpart contains the rules and regulations (incluing engineering standards) governing television broadcast stations, including noncommercial educational television broadcast stations, in the United States, its Territories and possessions.

§ 73.602 Other pertinent rules.

Other pertinent provisions of the Commission's rules and regulations relating to the television broadcast service are included in the following parts of this chapter:

Part 1—Practice and Procedure.

Part 2—Frequency Allocations and Radio Treaty Matters; General Rules and Regulations.

Part 17—Construction, Marking, and Lighting of Antenna Structures.

Part 74—Experimental, Auxiliary, and Special Broadcast Services.

§ 73.603 Numerical designation of television channels.

(a)

Channel No.	Frequency band (megacycles)	Channel No.	Frequency band (megacycles)
2	54–60	43	644–650
3	60–66	44	650–656
4	66–72	45	656–662
5	76–82	46	662–668
6	82–88	47	668–674
7	174–180	48	674–680
8	180–186	49	680–686
9	186–192	50	686–692
10	192–198	51	692–698
11	198–204	52	698–704
12	204–210	53	704–710
13	210–216	54	710–716
14	470–476	55	716–722
15	476–482	56	722–728
16	482–488	57	728–734
17	488–494	58	734–740
18	494–500	59	740–746
19	500–506	60	746–752
20	506–512	61	752–758
21	512–518	62	758–764
22	518–524	63	764–770
23	524–530	64	770–776
24	530–536	65	776–782
25	536–542	66	782–788
26	542–548	67	788–794
27	548–554	68	794–800
28	554–560	69	800–806
29	560–566	70	806–812
30	566–572	71	812–818
31	572–578	72	818–824
32	578–584	73	824–830
33	584–590	74	830–836
34	590–596	75	836–842
35	596–602	76	842–848
36	602–608	77	848–854
37	608–614	78	854–860
38	614–620	79	860–866
39	620–626	80	866–872
40	626–632	81	872–878
41	632–638	82	878–884
42	638–644	83	884–890

(b) In Alaska and Hawaii, the frequency bands 76–82 Mc/s and 82–88 Mc/s are allocated for nonbroadcast use. These frequency bands (Channels 5 and 6) will not be assigned in Alaska or Hawaii for use by television broadcast stations.

(c) Channel 37, 608–614 Mc/s, is not available for assignment prior to January 1, 1974.

Channel Utilization

§ 73.606 Table of assignments.

(a) *General.* The following table of assignments contains the channels assigned to the listed communities in the United States, its Territories, and possessions. Channels designated with an asterisk are assigned for use by noncommercial educational broadcast stations only. A station on a channel identified by a plus or minus mark is required to operate with its carrier frequencies offset 10 kc/s above or below, respectively, the normal carrier frequencies.

(b) *Table of assignments.*

	Channel No.
Alabama:	
Andalusia	*2–, *29
Anniston	70+
Auburn	*56
Bessemer	54
Birmingham	6–, *10–, 13–, 42+, *48
Brewton	23+
Clanton	77
Cullman	60+
Decatur	23–
Demopolis	*18
Dothan	4, *19–
Enterprise	40+
Eufaula	44
Florence	15, *21+
Gadsden	37–
Greenville	49–
Hamilton	17
Huntsville	19, 25+, 31+, *44–
Mobile	5+, 10+, *42, 48+
Montgomery	12, 20, *26+, 32
Munford	*7–, *24–
Opelika	*22–
Selma	8–, 58+
Sheffield	47–
Sylacauga	75
Talladega	64
Thomasville	27–
Troy	38–
Tuscaloosa	*14, 45, 51–
Tuskegee	16–
University	*74+
Alaska:	
Anchorage	2–, *7–, 11, 13–
Fairbanks	2+, 4+, 7+, *9+, 11+, 13+
Juneau	*3, 8, 10
Ketchikan	2, 4, *9
Seward	4–, 9–
Sitka	13
Arizona:	
Ajo	19–
Bisbee	54
Casa Grande	18–
Clifton	25–
Coolidge	36+
Douglas	3, 35
Eloy	24
Flagstaff	9, 13
Globe	34+
Holbrook	14
Kingman	6–
Mesa	12–
Miami	28+
Morenci	31
Nogales	11, 16, 32, 44+
Phoenix	3+, 5–, *8+, 10–
Prescott	7, 15
Safford	21

Arizona—Continued	Channel No.
Tucson	4—, *6+, 9—, 13—
Williams	25
Winslow	16—
Yuma	11—, 13+, 22+, 60
Arkansas:	
Arkadelphia	34+
Batesville	30—
Benton	40
Blytheville	64+, 74
Camden	50
Conway	62
El Dorado	10—, 26—
Fayetteville	*13—, 41—
Forrest City	22+
Fort Smith	5—, *16, 22, 39
Harrison	24
Helena	54—
Hope	15—
Hot Springs	9+, 52+
Jonesboro	8—, 39+
Little Rock	*2—, 4, 7—, 11+, 17—, 23+
Magnolia	28+
Malvern	46
Morrilton	43—
Newport	28
Paragould	58—
Pine Bluff	36
Russellville	19
Searcy	33
Springdale	35—
Stuttgart	14+
California:	
Alturas	13+
Bakersfield	17, 23—, 29, *39+, 51—
Bishop	19
Blythe	34—
Brawley	16
Chico	12—
Corona	52
Cotati	*16
Delano	45—
El Centro	7+, 9+, 26—, 48
Eureka	3—, 6—, 13—
Fresno	*18—, 24, 30+, 47, 53
Hanford	21
Indio	19+
Los Angeles	2, 4, 5, 7, 9, 11, 13, 22, *28, 34
Madera	59
Merced	34—, 66
Modesto	17—, 58
Monterey. (*See* Salinas.)	
Napa	62
Oakland. (*See* San Francisco.)	
Oxnard	32
Palm Springs	27
Petaluma	68
Port Chicago	70
Porterville	55
Red Bluff	15
Redding	7, 9
Riverside	40, 46
Sacramento	3, *6, 10, 40—, 46+
Salinas-Monterey	8+, 35
San Bernardino	18, *24—, 30
San Buenaventura	38—
San Diego	8, 10, *15+, 39, 51
San Francisco-Oakland	2+, 4—, 5+, 7—, *9+, 20—, 26—, 32+, 38, 44—
San Jose	11+, 48, *54, 60
San Luis Obispo	6+
San Mateo	*14+
Santa Barbara	3—, 20, 26
Santa Cruz	56
Santa Maria	12+, 44
Santa Paula	16+
Santa Rosa	50
Stockton	13+, 36, *42, 64
Tulare	27+
Ukiah	18
Visalia	43, 49
Watsonville	22—
Yreka City	19
Yuba City	52—
Colorado:	
Alamosa	3—, 19+
Boulder	*12, 22+
Canon City	36
Colorado Springs	11, 13, *17+, 23+
Craig	19

Colorado—Continued	Channel No.
Delta	24—
Denver	2, 4—, *6—, 7, 9—, 20, 26+
Durango	6+, 15
Fort Collins	44+
Fort Morgan	15+
Grand Junction	5—, 21+
Greeley	50
La Junta	24
Lamar	12—, 18—
Leadville	14+
Longmont	32
Loveland	38
Montrose	10+, 18
Pueblo	5, *8, 28+, 34—
Salida	25
Sterling	3, 25—
Trinidad	21—
Walsenburg	30—
Connecticut:	
Bridgeport	43—, 49—, *71
Hartford	3+, 18—, *24
Meriden	65—
New Britain	30+
New Haven	8+, 59+
New London	81
Norwalk. (*See* Stamford.)	
Norwich	57+, *63—
Stamford-Norwalk	55
Waterbury	20
Delaware:	
Dover	48—
Wilmington	12, *59—, 83+
District of Columbia:	
Washington	4—, 5—, 7+, 9, 14—, 20+, *26—, 50—
Florida:	
Belle Glade	27+
Boca Raton	*45
Bradenton	*28—, 54
Clearwater	32+, 50
Cocoa	*14
Daytona Beach	2—, 53
De Land	44+
Fort Lauderdale	39
Fort Myers	11+, *16+
Fort Pierce	19, *31+
Gainesville	*5—, 20+
Jacksonville	4+, *7, 12—, 30+, 36—
Key West	14+, 20
Lake City	*33+, 39
Lakeland	22+, 58—
Lake Wales	42+
Leesburg	*26—, 64—
Madison	*21+
Marianna	*17+, 57—
Melbourne	37—
Miami	*2, 4, 6, 7—, 10+, *17—, 23—, 33
New Smyrna Beach	*18
Ocala	*15+, 46+
Orlando	6—, 9, *24—, 47, 66
Palatka	*17, 62+
Panama City	7+, 13, *30, 36+
Pensacola	3—, 15—, *21, 46
Quincy	54+
St. Augustine	25+
St. Petersburg. (*See* Tampa.)	
Sanford	35+
Sarasota	34+
Tallahassee	*11—, 24, 51
Tampa-St. Petersburg	*3, 8—, 10—, 13—, 38
West Palm Beach	5, 12, *15, 21+
Georgia:	
Albany	10, 83
Americus	31
Ashburn	*23
Athens	*8, 60—
Atlanta	2, 5—, 11+, *30, 36, *57+
Augusta	6+, 12+
Bainbridge	35—
Brunswick	28+, 34—
Cairo	45+
Carrollton	33
Cartersville	63—
Cedartown	53—
Cochran	*15
Columbus	3, 9+, *28, 34
Cordele	43
Dalton	*18—

Georgia—Continued	Channel No.
Dawson	*25
Douglas	32—
Dublin	73
Elberton	24+
Fitzgerald	53+
Gainesville	52
Griffin	39+
La Grange	50
Macon	13+, *41+, 47+
Milledgeville	51+
Moultrie	48—
Newnan	61+
Pelham	*14—
Rome	59
Savannah	3+, *9—, 11
Statesboro	22
Swainsboro	42
Thomasville	6, 27
Tifton	72
Toccoa	35
Valdosta	37+
Vidalia	26
Warm Springs	*66+
Waycross	8+, 16
Wrens	*20—
Hawaii:	
Hilo, Hawaii	2, *4, 9, 11, 13
Honolulu, Oahu	2+, 4—, 9—, *11+, 13—
Lihue, Kauai	3+, *8—, 10+, 12—
Wailuku, Maui	3, 7, *10, 12
Idaho:	
Blackfoot	33
Boise	2, *4+, 7
Burley	15—
Caldwell	9—
Emmett	26—
Gooding	23
Idaho Falls	3, 8+
Jerome	17
Kellogg	36
Lewiston	3—
Moscow	*12—, 15
Nampa	6, 12+
Payette	14+
Pocatello	6—, 10
Preston	41
Rexburg	27+
Rupert	21
Sandpoint	23—
Twin Falls	11, 13—
Wallace	27—
Weiser	20—
Illinois:	
Alton	48
Aurora	75
Belleville	54+
Bloomington	15—
Cairo	24—
Carbondale	*8, 34, 61—
Centralia	32+, 59+
Champaign-Urbana	3+, *12—, 21, 27, 33
Chicago	2—, 5, 7, 9+, *11, *20, 26, 32, 38, 44
Danville	24
Decatur	17, 23+
De Kalb	*67
Dixon	47+
Elgin	83
Freeport	23
Galesburg	77
Harrisburg	3, 22
Jacksonville	49—
Joliet	48+
Kankakee	14
Kewanee	60—
La Salle	35
Lincoln	53+
Macomb	61+
Marion	40
Mattoon	46—
Moline. (*See* Davenport, Iowa.)	
Mt. Vernon	38—
Olney	16—
Pekin	69+
Peoria	19, 25+, 31+, *37—, 43+
Quincy	10—, 21+
Rockford	13, 39+, *45+
Rock Island. (*See* Davenport, Iowa.)	
Springfield	20+, 26—, 36—, *66+

	Channel No.
Illinois—Continued	
Streator	65—
Urbana. (*See* Champaign.)	
Vandalia	28—
Waukegan	79+
Indiana:	
Anderson	26+, 61, 83+
Angola	77
Bedford	68
Bloomington	4, *30—, 36
Columbus	42—
Connersville	38+
Elkhart. (*See* South Bend.)	
Evansville	7, *9+, 14—, 50—
Fort Wayne	15+, 21+, *27+, 33—, 69
Gary	50, *66
Hammond	56—
Indianapolis	6, 8—, 13—, *20—, 39, 67—
Jasper	19+
Kokomo	29+
Lafayette	18, *47, 59
Lebanon	79+
Logansport	51
Madison	66—
Marion	31
Michigan City	62+
Muncie	49, *55+, 71
Plymouth	34—
Princeton	44+
Shelbyville	58+
South Bend-Elkhart	16, 22, 28+, *52
Tell City	78
Terre Haute	2+, 10, *57+, 63—, 73+
Vincennes	*52+
Washington	81
Iowa:	
Algona	37+
Ames	5, 25—
Atlantic	45—
Boone	19—
Burlington	32—, 38+
Carroll	39
Cedar Rapids	2, 9—, 20—, *26+
Centerville	31—
Charles City	18—
Cherokee	14
Clinton	64
Creston	43
Davenport-Rock Island-Moline, Ill.	4+, 6+, 8, *30+, 42—, 68
Decorah	44+
Des Moines	8—, *11+, 13—, 17+, 23—
Dubuque	56+, 62—
Estherville	24+
Fairfield	54
Fort Dodge	21
Fort Madison	50+
Grinnell	71
Iowa City	*12+, 24—
Keokuk	44—
Knoxville	33—
Marshalltown	49
Mason City	3+, 35—
Muscatine	58
Newton	65+
Oelwein	28
Oskaloosa	52+
Ottumwa	15+, 63
Red Oak	32+
Shenandoah	20+
Sioux City	4—, 9, *30, 36—
Spencer	42+
Storm Lake	34+
Waterloo	7+, 16—, *22—, 46+
Webster City	27
Kansas:	
Abilene	31+
Arkansas City	49
Atchison	60+
Chanute	*21, 50—
Coffeyville	33—
Colby	22—
Concordia	47—
Dodge City	6+, 23
El Dorado	55+
Emporia	39—
Fort Scott	27
Garden City	11+, 13—
Goodland	10, 31
Great Bend	2, 28

	Channel No.
Kansas—Continued	
Hays	7—, 20—
Hutchinson	*8, 12, 18
Independence	67
Iola	44+
Junction City	29+
Lakin	*3
Larned	15—
Lawrence	17—
Leavenworth	54—
Liberal	14
Lincoln	*9
McPherson	26—
Manhattan	23+
Newton	14+
Oakley	*33
Olathe	52—
Ottawa	70
Parsons	46—
Pittsburg	7+, 38—
Pratt	36+
Salina	34
Topeka	*11, 13+, 42, *48+
Wellington	24—
Wichita	3—, 10—, 16—, *22+
Winfield	43+
Kentucky:	
Ashland	59—, *78+
Bowling Green	13, *17+
Corbin	16
Covington	*54—
Danville	35+
Elizabethtown	23
Frankfort	43—
Glasgow	28+
Harlan	73+
Hazard	*33+, 68+
Hopkinsville	20
Lexington	18+, 27—, 40+, *46+, 64
Louisville	3—, 11+, *15, 21—, 32—, 41—
Madisonville	*26
Mayfield	63
Maysville	24+
Middlesboro	57, 63+
Morehead	*36—
Murray	*33—, 83
Owensboro	56—, 62
Paducah	6+, 43, 72
Pikeville	*14—
Princeton	45—
Richmond	80
Somerset	*29—, 83—
Winchester	70+
Louisiana:	
Abbeville	27+
Alexandria	5, 62+, 74
Bastrop	53+
Baton Rouge	2, 9—, 18—, 28, *34, 40—
Bogalusa	69, 78
Crowley	76
De Ridder	70
Eunice	64—
Franklin	46+
Hammond	57
Houma	11, 30+
Jackson	59
Jennings	48
Lafayette	10, 38—, 67—
Lafayette-Lake Charles	3
Lake Charles	7—, *14, 25, 60+
Minden	30
Monroe	8+, *13, 43+
Morgan City	36+
Natchitoches	17+
New Iberia	15+
New Orleans	4+, 6+, *8, 12, 20—, 26, 32+, 61
Oakdale	54+
Opelousas	58
Ruston	20
Shreveport	3—, 12
Thibodaux	24
Winnfield	22—
Maine:	
Auburn	23+
Augusta	*10—, 29+
Bangor	2—, 5+, 7—, *16—
Bar Harbor	22—
Bath	65
Belfast	41—

	Channel No.
Maine—Continued	
Biddeford	59
Calais	*13—, 20—
Dover-Foxcroft	18+
Fort Kent	17+
Foxcroft. (*See* Dover.)	
Houlton	24
Lewiston	8—, 17
Millinocket	14+
Orono	*12—
Portland	6—, 13+, *47—, 53+
Presque Isle	8, *10+, 19
Rockland	25—
Rumford	55—
Van Buren	15—
Waterville	35+
Maryland:	
Annapolis	53—
Baltimore	2+, 11—, 13+, 24+, *66, 72—
Cumberland	17+, 30—
Frederick	62
Hagerstown	52, 63+
Salisbury	16+, 22+
Massachusetts:	
Amherst	*82
Barnstable	25+
Boston	*2+, 4—, 5—, 7+, 38, 44+, 56
Brockton	62
Easthampton	61
Fall River	46—, 68
Greenfield	32+, 58—
Holyoke. (*See* Springfield.)	
Lawrence	72
Lowell	78
New Bedford	6+, 28—, 34+
North Adams	19, *80+
Pittsfield	64+
Springfield-Holyoke	22, 40
Worcester	14, 27+
Michigan:	
Alma	41+
Alpena	*6, 11, 30—
Ann Arbor	*26—, 66—
Bad Axe	46—
Battle Creek	58—, 64—
Bay City	5—, *19+, 63—, 73+
Benton Harbor	40+
Big Rapids	39
Cadillac	9, 45
Calumet	5
Cheboygan	4+, 36+
Detroit	2+, 4, 7—, 20+, 50—, *56
East Lansing	*24—, 60+
East Tawas	21
Escanaba	3+, *49
Flint	12—, 16—, *22—
Gladstone	40—
Grand Rapids	8+, 13+, *17+, 23—
Houghton	19, *25
Iron Mountain	8—, 27
Iron River	33—
Ironwood	12+, 31—
Jackson	48
Kalamazoo	3—, *46, 74
Lansing	6—, 54
Ludington	33
Manistee	15—
Manistique	14+
Marquette	6—, 13, 17, *35
Midland	25—
Mount Pleasant	*14, 47—
Muskegon	29—, 35+
Parma-Onondaga	10—
Petoskey	31
Pontiac	44+
Port Huron	62
Rogers City	24
Saginaw	51—, 57—
Sault Ste. Marie	8, 10+, 28—, *34
Traverse City	7+, 20—, *26+
West Branch	27+
Minnesota:	
Albert Lea	57—
Alexandria	7, 36
Appleton	*10—
Austin	6—, 51+
Bemidji	9, 24—
Cloquet	44
Crookston	21—
Detroit Lakes	18+

Minnesota—Continued	Channel No.
Duluth-Superior, Wis	3, 6+, *8, 10+, 32, 38
Ely	16
Fairmont	40+
Faribault	20
Fergus Falls	16—
Grand Rapids	20—
Hastings	29+
Hibbing	13—
International Falls	11
Little Falls	14+
Mankato	12, 15—
Marshall	22+
Minneapolis-St. Paul	*2—, 4, 5—, 9+, 11—, *17, 23+
Montevideo	19
New Ulm	43—
Northfield	26
Owatonna	45
Red Wing	63—
Rochester	10, 55—
St. Cloud	33
St. Paul. (*See* Minneapolis.)	
Stillwater	39—
Thief River Falls	10, 15
Virginia	26+
Wadena	27+
Walker	12—
Willmar	31+
Winona	61
Worthington	32
Mississippi:	
Biloxi	13+, *44+, 50—
Brookhaven	37+
Canton	16
Clarksdale	32
Columbia	35+
Columbus	4—, 28—
Corinth	41
Greenville	21—, 27
Greenwood	6, 24+
Grenada	44
Gulfport	56—
Hattiesburg	17—
Jackson	3+, 12+, *19+, 25—, 47
Kosciusko	52—
Laurel	33—
Laurel-Pachuta	7
Louisville	46—
McComb	31—
Meridian	11—, 30—, *36—
Natchez	29+
Pachuta. (*See* Laurel-Pachuta.)	
Pascagoula	22
Picayune	14—
Starkville	34—
State College	*2+
Tupelo	9—, 38
University	*20+
Vicksburg	41+
West Point	56+
Yazoo City	49
Missouri:	
Cape Girardeau	12, 18+, 69
Carthage	56—
Caruthersville	27—
Chillicothe	14—
Clinton	49—
Columbia	8+, 16+, 22—
Farmington	52
Festus	25—
Fulton	24+
Hannibal	7—, 27+
Jefferson City	13, 33+
Joplin	12+, 30+
Kansas City	4, 5+, 9+, *19+, 25+, 65
Kennett	21
Kirksville	3—, 18
Lebanon	23
Marshall	40+
Maryville	26
Mexico	45
Moberly	35+
Monett	14
Nevada	18—
Poplar Bluff	15+
Rolla	46
St. Joseph	2—, 30—, *36
St. Louis	2, 4—, 5—, *9, 11—, 30, 42+

Missouri—Continued	Channel No.
Sedalia	6—, 28+
Sikeston	37
Springfield	3+, 10, *26+, 32
West Plains	20—
Montana:	
Anaconda	2+
Billings	2, 8, *11
Bozeman	*9, 22—
Butte	4, 6+, *7—, 15+
Cut Bank	20+
Deer Lodge	25+
Dillon	20
Glasgow	16
Glendive	5+, 18—
Great Falls	3+, 5+, *23—
Hamilton	17+
Hardin	4+
Havre	9+, 11+
Helena	10+, 12
Kalispell	9—
Laurel	14+
Lewistown	13
Livingston	16—
Miles City	3—, *6, 10
Missoula	8—, *11—, 13—, 21+
Polson	18
Red Lodge	18+
Shelby	14—
Sidney	14
Whitefish	16+
Wolf Point	20—
Nebraska:	
Albion	8+, *25
Alliance	*13—, 21
Bassett	*7—
Beatrice	40
Broken Bow	14—
Columbus	49+
Fairbury	35
Falls City	38
Fremont	52
Grand Island	11—, 21+
Hastings	5—, 27—
Hay Springs	4+
Hayes Center	6
Kearney	13, 19
Lexington	3+, 23—
Lincoln	10+, *12—, 18+, 24
McCook	8—, 17
Nebraska City	50
Norfolk	33+
North Platte	2—, *9+
Omaha	3, 6+, 7, *16, 22, 28—
Scottsbluff	10—, 16+
Superior	4+
York	15
Nevada:	
Boulder City	4+
Carlin	14
Carson City	37
Elko	10—
Ely	3—, 6+
Fallon	29—
Goldfield	5—
Hawthorne	31
Las Vegas	2—, 8—, *10+, 13—
Lovelock	18+
McGill	8+
Reno	2, 4, *5, 8, 21+, 27—
Tonopah	9—
Winnemucca	7+
Yerington	33
New Hampshire:	
Berlin	52
Claremont	37
Concord	76
Durham	*11
Hanover	*20+
Keene	45—
Laconia	43
Littleton	24—
Manchester	9—, 48+
Nashua	54
Portsmouth	15
Rochester	51
New Jersey:	
Andover	*69
Asbury Park	58
Atlantic City	46, 52+

New Jersey—Continued	Channel No.
Bridgeton	64—
Camden	*80
Freehold	*74
Hammonton	*70
Montclair	*77
Newark	13—
New Brunswick	*19—, 47+
Paterson	37+
Trenton	41+
Wildwood	40
New Mexico:	
Alamogordo	17
Albuquerque	4+, *5+, 7+, 13+
Artesia	21+
Atrisco-Five Points	18+
Belen	24+
Carlsbad	6—, 23
Clayton	27—
Clovis	12+, 35
Columbus	16—
Deming	14+
Farmington	12+, 17—
Five Points. (*See* Atrisco.)	
Gallup	3, *8—, 10
Hatch	*12
Hobbs	46
Hot Springs	19
Las Cruces	22—
Las Vegas	14—
Lordsburg	23+
Los Alamos	20—
Lovington	27
Portales	3+, 22+
Raton	46—, *52
Roswell	8, 10—
Santa Fe	2+, *9+, 11—
Silver City	*10+
Silver City-Truth or Consequences	6
Socorro	15+
Tucumcari	25+
New York:	
Albany-Schnectady-Troy	6, 13, *17+, *23—, 35, 41
Amsterdam	52—
Binghamton	12—, 34, 40—, *46+
Buffalo	17, *23
Buffalo-Niagara Falls	2, 4—, 7+, 29+
Carthage	7—
Clymer	37
Cortland	72
Dunkirk	46
Elmira	18+, 24—, *30
Glens Falls	39+
Hempstead	*53
Hornell	50
Ithaca	*14+
Jamestown	58+
Kingston	66—
Lake Placid	5
Malone	47, *66
Massena	14—
Middletown	60
New York	2, 4, 5+, 7, 9+, 11+, *25, 31—
Niagara Falls. (*See* Buffalo-Niagara Falls.)	
Ogdensburg	24+
Olean	54+
Oneonta	15—
Oswego	31
Patchogue	75
Plattsburg	28+
Poughkeepsie	21—, *83
Rochester	8, 10+, 13—, *21, 27+
Rome. (*See* Utica.)	
Saranac Lake	18
Schenectady. (*See* Albany.)	
Syracuse	3—, 5—, 9—, 33—, *43+
Troy. (*See* Albany.)	
Utica-Rome	2—, *25+, 54—
Vail Mills	10—
North Carolina:	
Ahoski	53
Albemarle	20
Asheville	13—, *56—, 62+, 78
Burlington	63
Chapel Hill	*4+
Charlotte	3, 9+, 36+, *42+
Durham	11+, *40—, 46+, 73—
Elizabeth City	31+

North Carolina—Continued	Channel No.
Fayetteville	18—, 54—
Gastonia	48
Goldsboro	34, 72
Greensboro	2—, *51—, 57—
Greensboro-High Point-Winston-Salem	8—
Greenville	9—
Henderson	52—
Hendersonville	27
Hickory	30—
High Point (*also see* Greensboro-High Point-Winston-Salem)	15+
Jacksonville	16
Kannapolis	59+
Kinston	45
Laurinburg	41—
Lumberton	21+
Mount Airy	55
New Bern	12+
Raleigh	5, *22—, 28—
Roanoke Rapids	30+
Rocky Mount	50+
Salisbury	80
Sanford	38
Shelby	39
Southern Pines	49
Statesville	64—
Washington	7
Wilmington	3—, 6, 29—, *35+
Wilson	56
Winston-Salem (*also see* Greensboro-High Point-Winston-Salem)	12, 26+, *32—
North Dakota:	
Bismarck	*3, 5, 12—, 18, *24
Bottineau	16+
Carrington	26—
Devils Lake	8+, 14—
Dickinson	2+, *4, 17
Fargo	6, 11+, *13, 34—, 40
Grafton	17
Grand Forks	*2
Harvey	22+
Jamestown	7—, 42
Lisbon	23
Minot	*6+, 10—, 13—
New Rockford	20+
Pembina	12
Rugby	38—
Valley City	4—, 32—
Wahpeton	45+
Williston	8—, 11—, *34+
Ohio:	
Akron	49+, *55—, 61+
Ashtabula	15
Athens	*20, 62—
Bellefontaine	63
Bowling Green	*70
Cambridge	26
Canton	29
Chillicothe	56+
Cincinnati	5—, 9, 12, *48—, 74—
Cleveland	3, 5+, 8, 19, *25+, 65+
Columbus	4—, 6+, 10+, *34, 40—
Dayton	2, 7+, *16+, 22+
Defiance	43
Findlay	53
Fremont	59+
Gallipolis	72
Hamilton-Middletown	65
Lancaster	68—
Lima	35—, 73
Lorain	31—
Mansfield	36+
Marion	17—
Massillon	23+
Middletown. (*See* Hamilton.)	
Mount Vernon	58
Newark	*28—, 60—
Oxford	*14+
Piqua	44—
Portsmouth	30
Sandusky	42+
Springfield	52—, 76
Steubenville. (*See* Wheeling, W. Va.)	
Tiffin	47+
Toledo	11—, 13, *30+, 79
Warren	67+
Youngstown	21—, 27, 33, 73—
Youngstown, Ohio-New Castle, Pa	45—
Zanesville	18—, 50+
Oklahoma:	
Ada	10+, 50+
Altus	36
Alva	30
Anadarko	58—
Ardmore	12—, 55—
Bartlesville	62—
Blackwell	51—
Chickasha	64
Claremore	15
Clinton	32—
Duncan	39—
Durant	27—
Elk City	8+, 15+, 26+
El Reno	56+
Enid	21, *27+
Frederick	44
Guthrie	48
Guymon	20+
Hobart	23+
Holdenville	14—
Hugo	21+
Lawton	7+, *28+, 34—
McAlester	47
Miami	58+
Muskogee	*45+, 66+
Norman	31—, *37—
Oklahoma City	4—, 5, 9—, *13, 19+, 25—
Okmulgee	26
Pauls Valley	61
Ponca City	40—
Pryor Creek	54
Sapulpa	42—
Seminole	59
Shawnee	53—
Stillwater	29—, *69
Tulsa	2+, 6, 8—, *11—, 17+, 23
Vinita	28—
Woodward	35+
Oregon:	
Albany	55+
Ashland	14—
Astoria	30—
Baker	37+
Bend	15—
Brookings	8+
Burns	16
Coos Bay	11
Corvallis	*7—, 49—
Eugene	9+, 13, *20+, 26
Grants Pass	30
Klamath Falls	2—, 17
La Grande	13+
Lebanon	43+
McMinnville	46—
Medford	5, 10+
North Bend	16+
Pendleton	28
Portland	2, 6+, 8—, *10, 12, 21—, 27+
Roseburg	4+, 28+
Salem	3+, *18—, 24+, 66
Springfield	37—
The Dalles	32
Pennsylvania:	
Allentown	*39, 67
Altoona	10—, 25—, *36—
Bethlehem	51—
Bradford	80—
Butler	43—
Chambersburg	46—
Clearfield	*3+
Du Bois	31+
Easton	57—
Emporium	42—
Erie	12, 24+, 35+, *41—, 66+
Harrisburg	21+, 27—, 33+, *65
Hazleton	63
Johnstown	6, 19+, 56—
Lancaster	8—, 55+
Lancaster-Lebanon	15+
Lewistown	75—
Lock Haven	32—
Meadville	62+
New Castle. (*See* Youngstown, Ohio.)	
Oil City	64
Philadelphia	3, 6—, 10, 17—, 23+, 29, *35—
Pittsburgh	2—, 4+, 11, *13—, *16, 22, 53+
Reading	61—
Scranton	16—, 22—, 44, *68—
Shamokin	71+
Shinglehouse	60+
State College	*69+
Sunbury	38
Uniontown	14
Washington	63+
Wilkes-Barre	28
Williamsport	26+
York	43, 49
Rhode Island:	
Providence	10+, 12+, 16, *36+
South Carolina:	
Aiken	54
Anderson	40, 58—
Camden	14
Charleston	2+, 4, 5+, *7—, 17+
Clemson	*68
Columbia	10—, 19+, 25—, *31—
Conway	23—
Florence	13+, 60
Georgetown	27—
Greenville	4—, 23+, *29
Greenwood	21—
Lake City	55+
Lancaster	67+
Laurens	45—
Marion	43—
Newberry	70
Orangeburg	44—
Rock Hill	61—
Spartanburg	7+, 17—, 74—
Sumter	47
Union	65—
South Dakota:	
Aberdeen	9—, 17+
Belle Fourche	23+
Brookings	*8, 25
Hot Springs	17+
Huron	12+, 15+
Lead	5—, 11+, 26
Madison	46
Mitchell	5+, 20—
Mobridge	27—
Pierre	*10+, 22+
Rapid City	3+, 7+, *9, 15—
Reliance	6—
Sioux Falls	11, 13+, 38+, *44—
Sturgis	20
Vermillion	*2+, 41
Watertown	3—, 35+
Winner	18—
Yankton	17—
Tennessee:	
Athens	14+
Bristol, Tenn.-Bristol, Va	5+, 75
Chattanooga	3+, 9, 12—, 43+, 49+, *55—
Clarksville	53
Cleveland	38+
Columbia	39—
Cookeville	24, *69
Crossville	*77
Covington	19—
Dyersburg	46+
Elizabethton	22+
Fayetteville	26+
Gallatin	48+
Harriman	67
Jackson	7+, 16+
Johnson City	11—, 34+
Kingsport	28
Knoxville	6, 10+, *20+, 26—
Lawrenceburg	50+
Lebanon	58
Lexington	*11
McMinnville	46
Maryville	51
Memphis	3—, 5+, *10+, 13+, 42—, 48—
Morristown	54+
Nashville	*2—, 4+, 5, 8+, 30+, 36+
Oak Ridge	79
Paris	51+
Shelbyville	56
Sneedville	*2+

Tennessee—Continued	Channel No.
Springfield	42
Tullahoma	68—
Union City	55
Texas:	
Abilene	9+, 33—
Alice	34+
Alpine	12—
Amarillo	*2—, 4, 7, 10
Athens	25+
Austin	7+, *18—, 24, 67
Ballinger	25
Bay City	33
Beaumont-Port Arthur	4—, 6—, 12—, 31+, *37
Beeville	38—
Big Spring	4—, 34+
Bonham	43
Boquillas	8—
Borger	33
Brady	13, 15—
Breckenridge	14+
Brenham	52—
Brownfield	15
Brownsville	26, 44
Brownsville-Harlingen-Weslaco [1]	4+, 5—
Brownwood	19
Bryan	54—
Bryan-College Station (*also see* College Station)	3+
Childress	40
Cleburne	57
Coleman	21—
College Station (*also see* Bryan-College Station)	*48—
Conroe	20+
Corpus Christi	3—, 6+, 10—, *16+, 22, 43
Corsicana	47+
Crockett	56
Crystal City	44+
Cuero	25—
Dalhart	16
Dallas	4+, 8, *13+, 23, 29, 73
Del Rio	10, 16—, 52+
Denison	52
Denton	*2, 17
Eagle Pass	22—, 64
Edinburg	60
El Campo	27
El Paso	4, *7, 9, 13, 26+, 38, 50, 62
Falfurrias	52
Floydada	45
Fort Stockton	5+, 22
Fort Worth	5+, 11—, 20—, *26—
Gainesville	49—
Galveston	35—, 41—, *47—
Gonzales	64+
Greenville	69—
Harlingen (*also see* Brownsville-Harlingen-Weslaco)	23
Hebbronville	58
Henderson	42+
Hereford	19—
Hillsboro	63
Houston	2—, *8—, 11+, 13—, 23+, 29—, 39—
Huntsville	15
Jacksonville	36—
Jasper	49+
Kermit	14
Kilgore	59—
Kingsville	40
Lamesa	28
Lampasas	40—
Laredo	8, 13, *15+, 27—, 39
Levelland	38—
Littlefield	32
Longview	32, 38+
Lubbock	*5—, 11, 13—, 20, 26
Lufkin	9, 46—
McAllen	20—
McKinney	65—
Marfa	3, 19+
Marshall	16—

[1] These assignments may be utilized in any community lying within the area of the triangle formed by Brownsville, Harlingen, and Weslaco.

Texas—Continued	Channel No.
Mercedes	66
Mexia	50—
Midland	2+, 18
Mineral Wells	38
Mission	70+
Monahans	9—
Mount Pleasant	35
Nacogdoches	19—, 40+
New Braunfels	62—
Odessa	7—, 24—
Orange	43—
Pampa	17—
Paris	33+
Pearsall	31
Pecos	16+
Perryton	22
Plainview	29+
Port Arthur. (*See* Beaumont.)	
Presidio	7+, 21
Quanah	42
Raymondville	64—
Rosenberg	17—
San Angelo	3—, 6+, 8+, 17+, *23—
San Antonio	4, 5, *9—, 12+, 35+, 41+
San Benito	48
San Marcos	75
Sequin	14—
Seymour	24+
Sherman	46+
Snyder	30+
Sonora	11+
Stephenville	32+
Sulphur Springs	41
Sweetwater	12
Taylor	58+
Temple	6, 16, 22+
Terrell	53
Texarkana	6+, *18, 24—
Tyler	7, 61+, 72
Uvalde	20
Vernon	18+
Victoria	19+
Waco	10+, *28—, 34
Waxahachie	45—
Weatherford	51
Weslaco. (*See* Brownsville-Harlingen-Weslaco.)	
Wichita Falls	3, 6—, *16+, 22—
Zapata	49
Utah:	
Brigham	36—
Cedar City	5
Logan	12—, 30, *46
Ogden	*9+, *18—, 24
Price	6
Provo	*11+, 22, 28
Richfield	13+
St. George	18+
Salt Lake City	2—, 4—, 5+, *7—, 20+, 26
Tooele	44
Vernal	3+
Vermont:	
Bennington	69—
Brattleboro	77+
Burlington	3, 16+, *22+
Montpelier	57
Newport	46
Rutland	*49+
St. Albans	34—
St. Johnsbury	*30
Windsor	*26
Virginia:	
Blacksburg	*60+
Bristol. (*See* Bristol, Tenn.)	
Charlottesville	*45+, 64+
Covington	44+
Danville	24—
Emporia	25+
Farmville	19
Fredericksburg	47
Front Royal	39—
Harrisonburg	3—, 34—
Lexington	54
Lynchburg	13, 16—
Marion	50
Martinsville	35—
Newport News. (*See* Norfolk-Portsmouth-Newport News.)	
Norfolk-Portsmouth	27

Virginia—Continued	Channel No.
Norfolk-Portsmouth-Newport News	3+, 10+, 13—, 15, *21—, 33
Norton	52+
Petersburg	8, 41
Portsmouth (*See* Norfolk-Portsmouth and *also see* Norfolk-Portsmouth-Newport News.)	
Pulaski	37—
Richmond	6+, 12—, *23, 29+
Roanoke	7—, 10, 27+, *33—
South Boston	14+
Staunton	36
Waynesboro	42
Williamsburg	17
Winchester	28+
Washington:	
Aberdeen	58
Anacortes	34
Bellingham	12+, *18+, 24—
Bremerton	44, 50
Centralia	17
Clarkston	34+, 40+
Ellensburg	49, *65
Ephrata	16—, 43
Everett	22—, 28—
Grand Coulee	37
Hoquiam	52
Kelso	39
Kennewick	31
Kennewick-Richland-Pasco	*41
Longview	33
Moses Lake	33—
Okanogan. (*See* Omak.)	
Olympia	60
Omak-Okanogan	*35—
Pasco (*also see* Kennewick-Richland-Pasco)	19—
Port Angeles	16+
Pullman	*10—, 24
Richland (*also see* Kennewick-Richland-Pasco)	25
Seattle	4, 5+, 7, *9, 20, 26+
Spokane	2—, 4—, 6—, *7+
Tacoma	11+, 13—, *56, 62
Walla Walla	22, 44—, *50
Wenatchee	27, *45, 55
Yakima	23+, 29+, *47
West Virginia:	
Beckley	4, 21, 66
Bluefield	6—, 41+
Charleston	8+, *43+, 49—
Clarksburg	12+, 69—
Elkins	40+
Fairmont	35
Hinton	31
Huntington	3+, 13+, *53—
Logan	23—
Martinsburg	58—
Morgantown	*24
Parkersburg	15—
Welch	25
Weston	5, 32
Wheeling	*57+
Wheeling-Steubenville, Ohio	7, 9+, 51+
Williamson	17
Wisconsin:	
Adams	*58+
Appleton	42+
Ashland	15+
Beaver Dam	52—
Beloit	57
Chilton	*31+
Eau Claire	13+, *19+, 25+
Fond du Lac	54+
Green Bay	2+, 5+, 11+, 70+
Janesville	63+
Kenosha	61—
La Crosse	8+, *32+, 38—, 72
Madison	3, 15, *21—, 27—, 33+
Manitowoc	65
Marinette	32—, *38+
Milwaukee	4—, 6, *10+, 12, 18+, 24+, 30, *36
Oshkosh	48—
Park Falls	*18
Portage	17—
Prairie du Chien	34
Racine	49—, 55
Rhinelander	22

	Channel No.
Wisconsin—Continued	
Rice Lake	21+
Richland Center	*66—, 76
Sheboygan	59—
Shell Lake	*30—
Sparta	50—
Stevens Point	20+, 26—
Sturgeon Bay	44—
Superior. (*See* Duluth, Minn.)	
Wausau	7—, 9, 16+, *46—
Wisconsin Rapids	14—
Wyoming:	
Buffalo	29
Casper	2+, 6+
Cheyenne	5+
Cody	24—
Douglas	14
Evanston	14—
Gillette	31—
Green River	16
Greybull	40
Lander	4, 17—
Laramie	*8+, 18+
Lovell	36+
Lusk	19—
Newcastle	28+
Powell	30+
Rawlins	11—
Riverton	10+
Rock Springs	13
Sheridan	7, 12+
Thermopolis	15
Torrington	27
Wheatland	24+
Worland	34
U.S. Territories and Possessions	
Guam:	
Agana	8, 10
Puerto Rico:	
Aguadilla	*32, 44
Arecibo-Aguadilla	12+
Arecibo	54, 80
Bayamon	36
Caguas	11—, *58
Carolina	52
Cayey	76
Fajardo	13+, *40
Guayama	46
Humacoa	68
Mayaguez	*3+, 5—, 16, 22
Ponce	7+, 9—, 14, 20, *26, 48
San Juan	2+, 4—, *6+, 18, 24, 30, *74
San Sebastion	38
Utuado	*70
Vega Baja	64
Yauco	42
Virgin Islands:	
Charlotte Amalie	10—, 17, *23, 43
Christiansted	8+, 15, *21, 27

§ 73.607 Availability of channels.

(a) Subject to the provisions of paragraph (b) of this section, applications may be filed to construct television broadcast stations only on the channels assigned in the Table of Assignments (§ 73.606(b)) and only in communities listed therein. Applications which fail to comply with this requirement, whether or not accompanied by a petition to amend the Table, will not be accepted for filing: *Provided, however,* That applications specifying channels which accord with publicly announced Commission Orders changing the Table of Assignments will be accepted for filing even though such applications are tendered before the effective dates of such channel changes.

(b) A channel assigned to a community listed in the Table of Assignments is available upon application in any unlisted community which is located within 15 miles of the listed community. In addition, a channel assigned to a community listed in the Table of Assignments and not designated for use by noncommercial educational stations only, is available upon application in any other community within 15 miles thereof which, although listed in the Table, is assigned only a channel designated for use only by noncommercial educational stations. Where channels are assigned to two or more communities listed in combination in the Table of Assignments the provisions of this paragraph shall apply separately to each community so listed. The distance between communities shall be determined by the distance between the respective coordinates thereof as set forth in the publication of the United States Department of Commerce entitled "Air Line Distance Between Cities in the United States." (This publication may be purchased from the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402.) If said publication does not contain the coordinates of either or both communities, the coordinates of the main post office in either or both of such communities shall be used. The method to be followed in making the measurements is set forth in § 73.611(d).

§ 73.608 International agreements.

Authorizations issued by the Commission for television broadcast facilities will be subject to the provisions of any agreements entered into by the United States with Canada and Mexico concerning television assignments and authorizations. Where, pursuant to such an agreement, timely objection is received from the foreign country involved to an authorization granted by the Commission, the Commission may, on its own motion, set aside such authorization pending consideration of such objection. Upon receipt of such objection, the Commission will notify the person to whom such authorization has been issued.

§ 73.609 Zones.

(a) For the purpose of allocation and assignment, the United States is divided into three zones as follows:

(1) Zone I consists of that portion of the United States located within the confines of the following lines drawn on the United States Albers Equal Area Projection Map (based on standard parallels 29½° and 45½°; North American datum): Beginning at the most easterly point on the State boundary line between North Carolina and Virginia; thence in a straight line to a point on the Virginia—West Virginia boundary line located at North Latitude 37° 49′ and West Longitude 80° 12′ 30″; thence westerly along the southern boundary lines of the States of West Virginia, Ohio, Indiana and Illinois to a point at the junction of the Illinois, Kentucky, and Missouri State boundary lines; thence northerly along the western boundary line of the State of Illinois to a point at the junction of the Illinois, Iowa, and Wisconsin State boundary lines; thence easterly along the northern State boundary line of Illinois to the 90th meridian; thence north along this meridian to the 43.5° parallel; thence east along this parallel to the 71st meridian; thence in a straight line to the intersection of the 69th meridian and the 45th parallel; thence east along the 45th parallel to the Atlantic Ocean. When any of the above lines pass through a city, the city shall be considered to be located in Zone I. (See Figure 1 of § 73.699.)

(2) Zone II consists of that portion of the United States which is not located in either Zone I or Zone III, and Puerto Rico, Alaska, Hawaiian Islands and the Virgin Islands.

(3) Zone III consists of that portion of the United States located south of a line, drawn on the United States Albers Equal Area Projection Map (based on standard parallels 29½° and 45½°; North American datum), beginning at a point on the east coast of Georgia and the 31st parallel and ending at the United States-Mexican border, consisting of arcs drawn with a 150 mile radius to the north from the following specified points:

	North latitude	West longitude
(a)	29°40′00″	83°24′00″
(b)	30°07′00″	84°12′00″
(c)	30°31′00″	86°30′00″
(d)	30°48′00″	87°58′30″
(e)	30°00′00″	90°38′30″
(f)	30°04′30″	93°19′00″
(g)	29°46′00″	95°05′00″
(h)	28°43′00″	96°39′30″
(i)	27°52′30″	97°32′00″

When any of the above arcs pass through a city, the city shall be considered to be located in Zone II. (See Figure 2 of § 73.699.)

§ 73.610 Separations.

(a) The provisions of this section relate to assignment separations and station separations. Petitions to amend the Table of Assignments (§ 73.606(b)) (other than those also expressly requesting amendment of this section or § 73.609) will be dismissed and all applications for new television broadcast stations or for changes in the transmitter sites of existing stations will not be accepted for filing if they fail to comply with the requirements specified in paragraphs (b), (c) and (d) of this section.

NOTE: Licensees and permittees of television broadcast stations which were operating on April 14, 1952 pursuant to one or more separations below those set forth in § 73.610 may continue to so operate, but in no event may they further reduce the separations below the minimum. As the existing separations of such stations are increased, the new separations will become the required minimum separations until separations are reached which comply with the requirements of § 73.610. Thereafter, the provisions of said section shall be applicable.

(b) Minimum co-channel assignment and station separations:

(1)

Zone	Channels 2–13	Channels 14–83
	Miles	Miles
I	170	155
II	190	175
III	220	205

(2) The minimum co-channel mileage separation between a station in one zone and a station in another zone shall be that of the zone requiring the lower separation.

(c) Minimum assignment and station adjacent channel separations applicable to all zones:

(1) Channels 2–13	Channels 14–83
60 miles	55 miles

(2) Due to the frequency spacing which exists between Channels 4 and 5, between Channels 6 and 7, and between Channels 13 and 14, the minimum adjacent channel separations specified above shall not be applicable to these pairs of channels (see § 73.603).

(d) In addition to the requirements of paragraphs (a), (b) and (c) of this section, the minimum assignment and station separations between stations on Channels 14–83, inclusive, as set forth in Table IV of § 73.698 must be met in either rule-making proceedings looking towards the amendment of the Table of Assignments (§ 73.606(b)) or in licensing proceedings. No channel listed in column (1) of Table IV of § 73.698 will be assigned to any city, and no application for an authorization to operate on such a channel will be granted, unless the mileage separations indicated at the top of columns (2)–(7), inclusive, are met with respect to each of the channels listed in those columns and parallel with the channel in column (1).

(e) The zone in which the transmitter of a television station is located or proposed to be located determines the applicable rules with respect to co-channel mileage separations where the transmitter is located in a different zone from that in which the channel to be employed is located.

§ 73.611 Reference points and distance computations.

(a) In considering petitions to amend the Table of Assignments (§ 73.606(b)), the following reference points shall be used by the Commission in determining assignment separations between communities:

(1) Where transmitter sites for the pertinent channels have been authorized in communities involved in a petition to amend the Table of Assignments, separations between such communities shall be determined by the distance between the coordinates of the authorized transmitter sites in the respective communities as set forth in the Commission's authorizations therefor.

(2) Where an authorized transmitter site is available for use as a reference point in one community but not in the other for the pertinent channels, separations shall be determined by the distance between the coordinates of the transmitter site as set forth in the Commission's authorization therefor and the coordinates of the other community as set forth in the publication of the United States Department of Commerce, entitled "Air Line Distances Between Cities in the United States." If said publication does not contain the coordinates for said other community, the coordinates of the main post office thereof shall be used.

(3) Where no authorized transmitter sites are available for use as reference points in both communities for the pertinent channels, the distance between the two communities listed in the above publication shall be used. If said publication does not contain such distance, the separation between the two communities shall be determined by the distance between the coordinates thereof as set forth in said publication. Where such coordinates are not contained in said publication, the coordinates of the main post offices of said communities shall be used.

(4) Where the distance between the reference point in a community to which a channel is proposed to be assigned and the reference point in another community or communities does not meet the minimum separation requirements of § 73.610, the channel may be assigned to such community upon a showing that a transmitter site is available that would meet the minimum separation requirements of § 73.610 and the minimum field intensity requirements of § 73.685. In such cases, where a station is not authorized in the community or communities to which measurements from the proposed channel assignment must be made pursuant to § 73.610, a showing should also be made that the distance between suitable transmitter sites in such other community or communities and the proposed transmitter site for the new channel meet the Commission's minimum spacing and coverage requirements.

(b) Station separations in licensing proceedings shall be determined by the distance between the coordinates of the proposed transmitter site in one community and

(1) The coordinates of an authorized transmitter site for the pertinent channel in the other community; or, where such transmitter site is not available for use as a reference point,

(2) The coordinates of the other community as set forth in the above-described publication of the United States Department of Commerce; or, if not contained therein,

(3) The coordinates of the main post office of such other community.

(4) In addition, where there are pending applications in other communities which, if granted, would have to be considered in determining station separations, the coordinates of the transmitter sites proposed in such applications must be used to determine whether the requirements with respect to minimum separations between the proposed stations in the respective cities have been met.

(c) In measuring assignment and station separations involving cities listed in the Table in combination, where there is no authorized transmitter site in any of the combination cities on the channel involved, separation measurements shall be made from the reference point which will result in the lowest separation.

(d) The distance between reference points is considered to be the length of the hypotenuse of a right triangle, one side of which is the difference in latitude of the reference points and the other side the difference in longitude of the two reference points, and shall be computed as follows. This method is appropriate for determining distances up to 220 miles, and for such distances will normally be more accurate than using spherical trigonometry without correction for the spheroidal shape of the earth. However, its accuracy deteriorates rapidly at distances beyond 300 miles and this method should not be used to compute greater distances.

(1) Determine the difference in latitude and the difference in longitude between the two reference points. Convert these two differences into degrees and decimal parts of a degree in accordance with Table I of § 73.698.

(2) Determine the middle latitude of the two reference points to the nearest second of latitude (average the latitudes of the two points).

(3) Multiply the difference in latitude by the number of miles per degree of latitude difference obtained from Table II of § 73.698 for the appropriate middle latitude (interpolate linearly). This determines the North-South distance in statute miles.

NOTE: In determining necessary distance computations for Alaska, Hawaii, and the Territories, the appropriate mileage per degree may be obtained by linear interpolation of the data given on pages 1246 and 1247 of the tables in publication H.O. No. 9 (Bowditch-American Practical Navigator—1958 Edition) of the U.S. Navy Department, Hydrographic Office. This publication may be purchased from the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402.

(4) Multiply the difference in longitude by the number of miles per degree of longitude difference obtained from Table III of § 73.698, for the appropriate middle latitude (interpolate linearly). This determines the East-West distance in statute miles.

(5) Determine the distance between the two reference points by the square root of the sum of the squares of the distances obtained in subparagraphs (3) and (4) of this paragraph, that is:

$$D=(L_a^2+L_o^2)^{1/2}$$

where:

D = Distance in statute miles
L_a = North-South distance in miles (from subparagraph (3) of this paragraph)
L_o = East-West distance in miles (from subparagraph (4) of this paragraph)

In computing the above, sufficient decimal figures shall be used to determine the distance to the nearest mile.

§ 73.612 Protection from interference.

Permittees and licensees of television broadcast stations are not protected from any interference which may be caused by the grant of a new station or of authority to modify the facilities of an existing station in accordance with the provisions of this subpart. The nature and extent of the protection from interference accorded to television broadcast stations is limited solely to the protection which results from the minimum assignment and station separation requirements and the rules and regulations with respect to maximum powers and antenna heights set forth in this subpart.

NOTE: The nature and extent of the protection from interference accorded to television broadcast stations which were authorized

prior to April 14, 1952, and which were operating on said date is limited not only as specified above but is further limited by any smaller separations existing between such stations on said date. Where, as a result of the adoption of the Table of Assignments, or of changes in transmitter sites made by such stations after said date, separations smaller than the required minimum are increased but still remain lower than the required minimum, protection accorded such stations will be limited to the new separations.

§ 73.613 Main studio location.

(a) The main studio of a television broadcast station shall be located in the principal community to be served. Where the principal community to be served is a city, town, village or other political subdivision, the main studio shall be located within the corporate boundaries of such city, town, village or other political subdivision. Where the principal community to be served does not have specifically defined political boundaries, applications will be considered on a case-to-case basis in the light of the particular facts involved to determine whether the main studio is located within the principal community to be served.

(b) Where an adequate showing is made that there is good cause for locating a main studio outside the principal community to be served and that to do so would not be inconsistent with the operation of the station in the public interest, the Commission will permit the use of a main studio location other than that specified in paragraph (a) of this section. The licensee or permittee of a television broadcast station shall not move his main studio outside the principal community in which it is located without first securing a modification of construction permit or license. Such licensee or permittee shall notify the Commission promptly of any change of the location of the main studio within the community. In any case where the main studio is located outside the principal community to be served, the licensee or permittee of a television broadcast station shall not move his main studio without first securing a modification of construction permit or license.

§ 73.614 Power and antenna height requirements.

(a) *Minimum requirements.* Applications will not be accepted for filing if they specify less than −10 dbk (100 watts) visual effective radiated power in any horizontal direction. No minimum antenna height above average terrain is specified.

(b) *Maximum power.* Applications will not be accepted for filing if they specify a power in excess of that provided for in this paragraph. Except as provided in subparagraph (1) of this paragraph, the maximum effective radiated powers of television broadcast stations operating on the channels set forth below with antenna heights not in excess of 2,000 feet above average terrain shall be as follows:

Channel Nos.	Maximum visual effective radiated power in db. above one kilowatt (dbk.)
2–6	20 dbk. (100 kw.).
7–13	25 dbk. (316 kw.).
14–83	37 dbk. (5000 kw.).[1]

[1] The maximum visual effective radiated power of television broadcast stations operating on Channels 14–83 within 250 miles of the Canadian-United States border may not be in excess of 30 dbk (1000 kw).

(1) In Zone I, on Channels 2–13, inclusive, the maximum powers specified above for these channels may be used only with antenna heights not in excess of 1,000 feet above average terrain. Where antenna heights exceeding 1,000 feet above average terrain are used on Channels 2–13, or antenna heights exceeding 2,000 feet above average terrain are used on Channels 14–83, the maximum power shall be based on the chart designated as Figure 3 of § 73.699.

NOTE: This limitation shall not apply to any licensee or permittee in Zone I who received an authorization after March 22, 1951, to relocate its transmitter site and construct a new tower and antenna to a height in excess of 1000 feet above average terrain and who constructed or who had substantially completed construction of said tower and antenna prior to April 14, 1952. In such case, maximum power may be utilized at the height above average terrain specified in the authorization. The limitation shall apply, however, where the tower or other principal supporting structure had been constructed prior to the date of such authorization.

(2) In Zones II and III, the maximum powers which may be used by television broadcast stations operating on the respective channels set forth in the above table with antenna heights exceeding 2,000 feet above average terrain shall be based on the chart designated as Figure 4 of § 73.699.

(3) The effective radiated power in any horizontal or vertical direction may not exceed the maximum values permitted by this section and Figures 3 and 4 of § 73.699.

(4) The maximum effective radiated power in any direction above the horizontal plane shall be as low as the state of the art permits and may not exceed the effective radiated power in the horizontal direction in the same vertical plane.

(c) *Determination of applicable rules.* The zone in which the transmitter of a television station is located or proposed to be located determines the applicable rules with respect to maximum antenna heights and powers for VHF stations when the transmitter is located in Zone I and the channel to be employed is located in Zone II, or the transmitter is located in Zone II and the channel to be employed is located in Zone I.

§ 73.615 Administrative changes in authorizations.

In the issuance of television broadcast station authorizations, the Commission will specify the transmitter output power and effective radiated power to the nearest 0.1 dbk. Powers specified by kilowatts shall be obtained by converting dbk to kilowatts to 3 significant figures. Antenna heights above average terrain will be specified to the nearest 10 feet. Midway figures will be authorized in the lower alternative.

APPLICATIONS AND AUTHORIZATIONS

§ 73.620 Cross reference.

See Subpart D of Part 1 of this chapter for general requirements as to applications, filing of applications and description of application forms, other forms and information to be filed with the Commission, the manner in which applications are processed, and provisions applying to action on applications. See § 1.1111 of Subpart G of that part for the fees to be paid in connection with applications for facilities in the service covered in this subpart.

§ 73.621 Noncommercial educational stations.

In addition to the other provisions of this subpart, the following shall be applicable to noncommercial educational television broadcast stations:

(a) Except as provided in paragraph (b) of this section, noncommercial educational broadcast stations will be licensed only to nonprofit educational organizations upon a showing that the proposed stations will be used primarily to serve the educational needs of the community; for the advancement of educational programs; and to furnish a nonprofit and noncommercial television broadcast service.

(1) In determining the eligibility of publicly supported educational organizations, the accreditation of their respective state departments of education shall be taken into consideration.

(2) In determining the eligibility of privately controlled educational organizations, the accreditation of state departments of education or recognized regional and national educational accrediting organizations shall be taken into consideration.

(b) Where a municipality or other political subdivision has no independently constituted educational organization such as, for example, a board of education having autonomy with respect to carrying out the municipality's educational program, such municipality shall be eligible for a noncommercial educational television broadcast station. In such circumstances, a full and detailed showing must be made that a grant of the application will be consistent with the intent and purpose of the Commission's rules and regulations relating to such stations.

(c) Noncommercial educational television broadcast stations may transmit educational, cultural and entertainment programs, and programs designed for use by schools and school systems in connection with regular school courses, as well as routine and administrative material pertaining thereto.

(d) An educational station may not broadcast programs for which a consideration is received, except programs produced by or at the expense of or furnished by others than the licensee for which no other consideration than the furnishing

of the program is received by the licensee. The payment of line charges by another station or network shall not be considered as being prohibited by this paragraph.

(e) To the extent applicable to programs broadcast by a noncommercial educational station produced by or at the expense of or furnished by others than the licensee of said station, the provisions of § 73.654 relating to announcements regarding sponsored programs shall be applicable, except that no announcements (visual or aural) promoting the sale of a product or service shall be transmitted in connection with any program: *Provided, however,* That where a sponsor's name or product appears on the visual image during the course of a simultaneous or rebroadcast program either on the backdrop or in similar form, the portions of the program showing such information need not be deleted.

§ 73.622 Applications for sharing of television channels.

Separate applications shall be filed by each applicant for the voluntary sharing of television channels. Such applications shall be accompanied by copies of the time-sharing agreement under which the applicants propose to operate.

§ 73.623 Notification of filing of applications.

In order to minimize harmful interference at the National Radio Astronomy Observatory site located at Green Bank, Pocahontas County, West Virginia, and at the Naval Radio Research Observatory at Sugar Grove, Pendleton County, West Virginia, an applicant for authority to construct a new television broadcast station or for authority to make changes in the frequency, power, antenna height, or antenna directivity of an existing station within the area bounded by 39°15′ N. on the north, 78°30′ W. on the east, 37°30′ N. on the south, and 80°30′ W. on the west shall, at the time of filing such application with the Commission, simultaneously notify the Director, National Radio Astronomy Observatory, P.O. Box #2, Green Bank, West Virginia, 24944, in writing, of the technical particulars of the proposed station. Such notification shall include the geographical coordinates of the antenna, antenna height, antenna directivity, if any, proposed frequency, type of emission, and power. In addition, the applicant shall indicate in his application to the Commission the date notification was made to the Observatory. After receipt of such application, the Commission will allow a period of twenty (20) days for comments or objections in response to the notifications indicated. If an objection to the proposed operation is received during the twenty-day period from the National Radio Astronomy Observatory for itself or on behalf of the Naval Radio Research Observatory, the Commission will consider all aspects of the problem and take whatever action is deemed appropriate.

§ 73.628 Equipment tests.

(a) During the process of construction of a television broadcast station, the permittee, after notifying the Commission and Engineer in Charge of the radio district in which the station is located, may, without further authority of the Commission, conduct equipment tests for the purpose of such adjustments and measurements as may be necessary to assure compliance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations.

(b) The Commission may notify the permittee not to conduct tests or may cancel, suspend, or change the date for the beginning of equipment tests, if and when such action may appear to be in the public interest, convenience, and necessity.

(c) Equipment tests may be continued so long as the construction permit shall remain valid.

(d) Inspection of a station will ordinarily be required during the equipment test period and before the commencement of program tests. After construction and after adjustments and measurements have been completed to show compliance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations, the permittee should notify the Engineer in Charge of the radio district in which the station is located that it is ready for inspection.

(e) The authorization for tests embodied in this section shall not be construed as constituting a license to operate but as a necessary part of construction.

§ 73.629 Program tests.

(a) Upon completion of construction of a television broadcast station in accordance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations, and when an application for station license has been filed showing the station to be in satisfactory operating condition, the permittee may request authority to conduct program tests: *Provided,* That such request shall be filed with the Commission at least ten (10) days prior to the date on which it is desired to begin such operation and that the Engineer in Charge of the radio district in which the station is located is notified. (All data necessary to show compliance with the terms and conditions of the construction permit must be filed with the license application.)

(b) Program tests shall not commence until specific Commission authority is received. The Commission reserves the right to change the date of the beginning of such tests or to suspend or revoke the authority for program tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Unless sooner suspended or revoked, the program test authority continues valid during Commission consideration of the application for license and during this period further extension of the construction permit is not required. Program test authority shall be automatically terminated by final determination upon the application for station license.

(d) All operation under program test authority shall be in strict compliance with the rules governing television broadcast stations and in strict accordance with representations made in the application for license pursuant to which the tests were authorized.

(e) The granting of program test authority shall not be construed as approval by the Commission of the application for station license.

§ 73.630 Normal license period.

(a) The license for a television broadcast station ordinarily will be issued for a period of three years and, when regularly renewed, at three year intervals thereafter: *Provided, however,* That, if the Commission finds that the public interest, convenience, and necessity will be served thereby, it may issue either an initial license or a renewal thereof for a lesser term. When regularly issued or renewed, licenses will be issued to expire at the hour of 3:00 a.m., eastern standard time, in accordance with the following schedule, and at three year intervals thereafter.

(1) For stations located in Florida, Puerto Rico, and Virgin Islands, February 1, 1964.

(2) For stations located in Alabama and Georgia, April 1, 1964.

(3) For stations located in Arkansas, Louisiana, and Mississippi, June 1, 1964.

(4) For stations located in Tennessee, Kentucky, and Indiana, August 1, 1964.

(5) For stations located in Ohio and Michigan, October 1, 1964.

(6) For stations located in Illinois and Wisconsin, December 1, 1964.

(7) For stations located in Iowa and Missouri, February 1, 1965.

(8) For stations located in Minnesota, North Dakota, South Dakota, Montana, and Colorado, April 1, 1965.

(9) For stations located in Kansas, Oklahoma, Nebraska, June 1, 1965.

(10) For stations located in Texas, August 1, 1965.

(11) For stations located in Wyoming, Nevada, Arizona, Utah, New Mexico, and Idaho, October 1, 1965.

(12) For stations located in California, December 1, 1965.

(13) For stations located in Washington, Oregon, Alaska, Guam and Hawaii, February 1, 1966.

(14) For stations located in Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, Vermont, April 1, 1966.

(15) For stations located in New Jersey, and New York, June 1, 1966.

(16) For stations located in Delaware and Pennsylvania, August 1, 1966.

(17) For stations located in Maryland, District of Columbia, Virginia, West Virginia, October 1, 1966.

(18) For stations located in North Carolina, South Carolina, December 1, 1966.

§ 73.632 Emergency Weather Warnings.

Upon receipt of notification from the United States Weather Bureau of an Emergency Weather Warning of a condition of immediate danger to life and property, all television broadcast stations

may, at their option, broadcast Emergency Action Notification Signal (two 5-second carrier breaks and 15 seconds of 1,000 CPS tone sound carrier only) followed by the Emergency Weather Warning.

(Sec. 606, 48 Stat. 1104, as amended; 47 U.S.C. 606, E.O. 11092, 28 F.R. 1847)

§ 73.635 Use of common antenna site.

No television license or renewal of a television license will be granted to any person who owns, leases, or controls a particular site which is peculiarly suitable for television broadcasting in a particular area and (a) which is not available for use by other television licensees; and (b) no other comparable site is available in the area; and (c) where the exclusive use of such site by the applicant or licensee would unduly limit the number of television stations that can be authorized in a particular area or would unduly restrict competition among television stations.

§ 73.636 Multiple ownership.

(a) No license for a television broadcast station shall be granted to any party (including all parties under common control) if:

(1) Such party directly or indirectly owns, operates, or controls another television broadcast station which serves substantially the same area; or

(2) Such party, or any stockholder, officer or director of such party, directly or indirectly owns, operates, controls, or has any interest in, or is an officer or director of any other television broadcast station if the grant of such license would result in a concentration of control of television broadcasting in a manner inconsistent with public interest, convenience, or necessity. In determining whether there is such a concentration of control, consideration will be given to the facts of each case with particular reference to such factors as the size, extent and location of area served, the number of people served, and the extent of other competitive service to the areas in question. The Commission, however, will in any event consider that there would be such a concentration of control contrary to the public interest, convenience or necessity for any party or any of its stockholders, officers or directors to have a direct or indirect interest in, or be stockholders, officers, or directors of, more than seven television broadcast stations, no more than five of which may be in the VHF band.

(b) Paragraph (a) of this section is not applicable to noncommercial educational stations.

NOTE 1: The word "control" as used herein is not limited to majority stock ownership, but includes actual working control in whatever manner exercised.

NOTE 2: In applying the provisions of paragraph (a) of this section to the stockholders of a corporation which has more than 50 voting stockholders, only those stockholders need be considered who are officers or directors or who directly or indirectly own 1 percent or more of the outstanding voting stock.

§ 73.637 Alternate main transmitters.

The licensee of a television broadcast station may be licensed for alternate main transmitters provided that a technical need for such alternate transmitters is shown and that the following conditions are met:

(a) Both transmitters are located at the same place.

(b) Both transmitters shall have the same power rating.

(c) Both transmitters shall meet the construction, installation, operation and performance requirements of this subpart.

§ 73.638 Auxiliary transmitter.

Upon showing that a need exists for the use of auxiliary transmitters in addition to the regular transmitters of a television station, a license therefor may be issued: *Provided*, That:

(a) Auxiliary transmitters may be installed either at the same location as the main transmitters or at another location.

(b) A licensed operator shall be in control whenever auxiliary transmitters are placed in operation.

(c) The auxiliary transmitters shall be maintained so that they may be put into immediate operation at any time for the following purposes:

(1) The transmission of the regular programs upon the failure of the main transmitters.

(2) The transmission of regular programs during maintenance or modification work on the main transmitters necessitating discontinuance of their operation for a period not to exceed 5 days.

NOTE: This includes the equipment changes which may be made without authority as set forth elsewhere in the rules and regulations or as authorized by the Commission by letter or by construction permit. Where such operation is required for periods in excess of 5 days, request therefor shall be in accordance with § 1.542 of the Commission's rules and regulations.

(3) Upon request by a duly authorized representative of the Commission.

(d) The auxiliary transmitters shall be tested at least once each week to determine that they are in proper operating condition and that they are adjusted to the proper frequency, except that in the case of operation in accordance with paragraph (c) of this section during any week, the test in that week may be omitted provided the operation under paragraph (c) of this section is satisfactory. A record shall be kept of the time and result of each test. Such records shall be retained for a period of two years.

(e) The auxiliary transmitters shall be equipped with satisfactory control equipment which will enable the maintenance of the frequency emitted by the station within the limits prescribed by the regulations in this subpart.

(f) The operating power of an auxiliary transmitter may be less than the authorized power of the main transmitters, but in no event shall it be greater than such power.

§ 73.639 Changes in equipment and antenna system.

Licensees of television broadcast stations shall observe the following provisions with regard to changes in equipment and antenna system:

(a) No changes in equipment shall be made:

(1) That would result in the emission of signals outside of the authorized channel.

(2) That would result in the external performance of the transmitter being in disagreement with that prescribed in this subpart.

(b) Specific authority, upon filing formal application therefor (FCC Form 301 or such other form as is provided therefor), is required for any of the following:

(1) Changes involving an increase or decrease in the power rating of the transmitters.

(2) A replacement of the transmitters as a whole.

(3) Change in the location of the transmitting antenna.

(4) Change in antenna system, including transmission line.

(5) Change in the power delivered to the antenna.

(6) Change in frequency control and/or modulation system.

(c) Other changes, except as above provided for in this section or in the provisions of this subpart, may be made at any time without the authority of the Commission, provided that the Commission shall be promptly notified thereof and such changes shall be shown in the next application for renewal of license.

§ 73.640 Acceptability of broadcast transmitters for licensing.

(a) In order to facilitate the filing of, and action on, applications for station authorizations, transmitters will be accepted for licensing by the Commission under one of the following conditions:

(1) A transmitter may be type-accepted upon the request of any manufacturer of transmitters built in quantity by following the type acceptance procedure set forth in Part 2 of this chapter, provided that the date and information submitted indicates that the transmitter meets the requirements of § 73.687. If accepted, such transmitter will be included on the Commission's "Radio Equipment List, Part A, Television Broadcast Equipment." Applicants specifying transmitters included on such a list need not submit detailed descriptions and diagrams where the correct type number is specified, if the equipment proposed is identical with that accepted. Copies of this list are available for inspection at the Commission's office in Washington, D. C., and at each of its field offices.

(2) An application specifying a transmitter not included on the Radio Equipment List, Part A, may be accepted upon the request of a prospective licensee submitting with the application for construction permit a complete description of the transmitter, including the circuit diagram, listing of all tubes used, function of each, multiplication in each stage, plate current and voltage applied to each tube, a description of the oscillator circuit together with any devices installed for the purpose of frequency stabilization and the means of varying output power to compensate for power supply voltage variations. However, if this data has been filed with the Commission by

a manufacturer in connection with a request for type acceptance, it need not be submitted with the application for construction permit but may be referred to as "on file." Measurement data for type acceptance made in accordance with subparagraph (1) of this paragraph shall be submitted with the license application.

(3) A transmitter shown on an instrument of authorization by manufacturer and type number, or as a composite, and which was in use prior to June 30, 1955, may continue to be used by the licensee, his successors or assignees, provided such transmitter continues to comply with the rules and regulations.

(b) Additional rules with respect to withdrawal of type acceptance, modification of type-accepted equipment and limitations on the findings upon which type acceptance is based are set forth in Part 2 of this chapter.

GENERAL OPERATING REQUIREMENTS

§ 73.651 Time of operation.

(a) (1) All television broadcast stations will be licensed for unlimited time operation. Each such station shall maintain a regular program operating schedule as follows: Not less than 2 hours daily in any 5 broadcast days per week and not less than a total of 12 hours per week during the first 18 months of the station's operation; not less than 2 hours daily in any 5 broadcast days per week and not less than a total of 16 hours, 20 hours and 24 hours per week for each successive 6-month period of operation, respectively; and not less than 2 hours in each of the 7 days of the week and not less than a total of 28 hours per week thereafter.

(2) "Operation" includes the period during which a station is operated pursuant to temporary authorization or during program tests, as well as during the license period. Time devoted to test patterns, or to aural presentations accompanied by the incidental use of fixed visual images which have no substantial relationship to the subject matter of such aural presentations, shall not be considered in computing periods of program service.

(3) In the event that causes beyond a licensee's control make it impossible to adhere to the operating schedule in subparagraph (1) of this paragraph or to continue operating, the station may limit or discontinue operation for a period of not more than 10 days, without further authority of the Commission. However, the Commission and the Engineer in Charge of the radio district in which the station is located shall be immediately notified in writing if the station is unable to maintain the minimum operating schedule and shall be subsequently notified when the station resumes regular operation.

(b) Noncommercial educational television broadcast stations are not required to operate on a regular schedule and no minimum number of hours of operation is specified; but the hours of actual operation during a license period shall be taken into consideration in considering the renewal of noncommercial educational television broadcast licenses.

(c) (1) The aural transmitter of a television station shall not be operated separately from the visual transmitter except for the following purposes:

(i) For actual tests of station equipment or actual experimentation in accordance with § 73.666; and

(ii) For emergency "fills" in case of visual equipment failure or unscheduled and unavoidable delays in presenting visual programs. In such situations the aural transmitter may be used to advise the audience of difficulties and to transmit for a short period program material of such nature that the audience will be enabled to remain tuned to the station; for example, music or news accompanying a test pattern or other visual presentation.

(2) During periods of transmission of a test pattern on the visual transmitter of a television station, aural transmission shall consist only of a single tone or series of variable tones. During periods when still pictures or slides are employed to produce visual transmissions which are accompanied by aural transmissions, the aural and visual transmissions shall be integral parts of a program or announcement and shall have a substantial relationship to each other: *Provided,* That nothing herein shall preclude the transmission of a test pattern, still pictures or slides for the following purposes and periods:

(i) To accompany aural announcements of the station's program schedule and aural news broadcasts or news commentaries, for a total period not to exceed one hour in any broadcast day.

(ii) To accompany aural transmissions for a period of time not to exceed fifteen minutes immediately prior to the commencement of a programming schedule.

Examples. (1) Duplication of AM or FM programs on the aural transmitter of a television station while the same program is broadcast on the visual transmitter (i. e., a "simulcast") is consistent with this paragraph.

(2) Duplication of AM or FM programs on the aural transmitter of a television station while a test pattern is broadcast on the visual transmitter is not consistent with this paragraph, except for the specific purposes and periods specified in paragraph (c) (2).

(3) A travel lecture in which the words of the lecturer are broadcast simultaneously with still pictures or slides of scenes illustrating the lecture, and a newscast in which the words of the newscaster are broadcast simultaneously with still pictures or slides of the news events, are examples of programs in which the aural and visual transmissions are integral parts of the same program having a substantial relationship to each other, within the meaning of paragraph (c) (2). Mood music unrelated to the visual transmission is not consistent with this paragraph.

(4) The broadcast of a test pattern accompanied by a musical composition for the purpose of demonstration, sale, installation or orientation of television receivers, or receiving antennas is not consistent with this paragraph.

(5) Music accompanying the transmission of a test pattern upon which is visually imposed a moving text consisting of continuous program material, such as a running newscast or news commentary, is consistent with this paragraph.

(6) Music accompanying the transmission of a test pattern upon which is visually imposed a clock indicating the time of day, or a text that is changed at spaced intervals, is not consistent with this paragraph.

§ 73.652 Station identification.

(a) A licensee of a television broadcast station shall make station identification announcement (call letters and location) at the beginning and ending of each time of operation and during the operation on the hour. The announcement at the beginning and ending of each time of operation shall be by both aural and visual means. Other announcements may be by either aural or visual means.

(b) Identification announcements during operation need not be made when to make such announcement would interrupt a single consecutive speech, play, religious service, symphony concert, or any type of production. In such cases, the identification announcement shall be made at the first interruption of the entertainment continuity and at the conclusion thereof.

§ 73.653 Mechanical reproductions.

(a) No mechanically reproduced program, whether visual or aural, consisting of a speech, news event, news commentator, forum, panel discussion, or special event in which the element of time is of special significance, or any other program in which the element of time is of special significance and presentation of which would create, either intentionally or otherwise, the impression or belief on the part of the listening audience that the event or program being broadcast is in fact occurring simultaneously with the broadcast, shall be broadcast without an appropriate announcement being made either at the beginning or end of such reproduction or at the beginning or end of the program in which such reproduction is used that it is a mechanical reproduction or a mechanically reproduced program: *Provided, however,* That each such program of one minute or less need not be announced as such.

(b) The exact form of identifying announcement is not prescribed, but the language shall be clear and in terms commonly used and understood. Any other program mechanically reproduced or series of mechanical reproductions, including a mechanical reproduction used for background music, sound effects, station identification, program identification (theme music of short duration) or identification of sponsorship of the program proper, need not be announced as provided in paragraph (a) of this section, but the licensee shall not attempt affirmatively to create the impression that any program being broadcast by mechanical reproduction consists of live talent.

(c) The requirements of paragraph (a) of this section are waived with respect to network programs, transcribed and rebroadcast at a later hour because of the time zone differential between the place where the program originates and where it is rebroadcast, this waiver being applicable whether the off-the-line recording is made by the network itself at one of its key stations or by an individual station, but only when the off-the-line recording is for broadcast at an hour not exceeding the time zone differential be-

tween the place where the program originates and where it is rebroadcast. Each station which broadcasts network programs at a later hour in accordance with this waiver shall make an appropriate announcement at least once each day between the hours of 10:00 a. m., and 10:00 p. m., stating that some or all of the network programs which are broadcast by that station are delayed broadcasts by means of transcription. This waiver provision also applies during the annual periods in which daylight saving time will be effective with respect to network programs transcribed and rebroadcast one hour later because of the time differential resulting from the adoption of daylight saving time in some areas.

§ 73.654 Sponsored programs, announcement of.

(a) When a television broadcast station transmits any matter for which money, services, or other valuable consideration is either directly or indirectly paid or promised to, or charged or received by, such station, the station shall broadcast an announcement that such matter is sponsored, paid for, or furnished, either in whole or in part, and by whom or on whose behalf such consideration was supplied: *Provided, however,* That "service or other valuable consideration" shall not include any service or property furnished without charge or at a nominal charge for use on, or in connection with, a broadcast unless it is so furnished in consideration for an identification in a broadcast of any person, product, service, trademark, or brand name beyond an identification which is reasonably related to the use of such service or property on the broadcast.

(b) The licensee of each television broadcast station shall exercise reasonable diligence to obtain from its employees, and from other persons with whom it deals directly in connection with any program matter for broadcast, information to enable such licensee to make the announcement required by this section.

(c) In any case where a report (concerning the providing or accepting of valuable consideration by any person for inclusion of any matter in a program intended for broadcasting) has been made to a television broadcast station, as required by section 508 of the Communications Act of 1934, as amended, of circumstances which would have required an announcement under this section had the consideration been received by such television broadcast station, an appropriate announcement shall be made by such station.

(d) In the case of any political program or any program involving the discussion of public controversial issues for which any films, records, transcriptions, talent, scripts, or other material or services of any kind are furnished, either directly or indirectly, to a station as an inducement to the broadcasting of such program, an announcement shall be made both at the beginning and conclusion of such program on which such material or services are used that such films, records, transcriptions, talent, scripts, or other material or services have been furnished to such station in connection with the broadcasting of such program: *Provided, however,* That only one such announcement need be made in the case of any such program of 5 minutes' duration or less, which announcement may be made either at the beginning or conclusion of the program.

(e) The announcements required by section 317(b) of the Communications Act of 1934, as amended, are waived with respect to feature motion picture films produced initially and primarily for theatre exhibition.

NOTE: The waiver heretofore granted by the Commission in its Report and Order of November 21, 1960 (FCC 60-1369; 25 FR 11224, Nov. 26, 1960), continues to apply to programs filmed or recorded on or before June 20, 1963.

(f) The announcement required by this section shall fully and fairly disclose the true identity of the person or persons by whom or in whose behalf such payment is made or promised, or from whom or in whose behalf such services or other valuable consideration is received, or by whom the material or services referred to in paragraph (d) of this section are furnished. Where an agent or other person contracts or otherwise makes arrangements with a station on behalf of another, and such fact is known to the station, the announcement shall disclose the identity of the person or persons in whose behalf such agent is acting instead of the name of such agent.

(g) In the case of any program, other than a program advertising commercial products or services, which is sponsored, paid for, or furnished, either in whole or in part, or for which material or services referred to in paragraph (d) of this section are furnished, by a corporation, committee, association, or other unincorporated group, the announcement required by this section shall disclose the name of such corporation, committee, association, or other unincorporated group. In each such case the station shall require that a list of the chief executive officers or members of the executive committee or of the board of directors of the corporation, committee, association or other unincorporated group shall be made available for public inspection at the studios or general offices of one of the television broadcast stations carrying the program in each community in which the program is broadcast.

(h) In the case of broadcast matter advertising commercial products or services, an announcement stating the sponsor's corporate or trade name, or the name of the sponsor's product, when it is clear that the mention of the name of the product constitutes a sponsorship identification, shall be deemed sufficient for the purposes of this section and only one such announcement need be made at any time during the course of the program.

(i) Commission interpretations in connection with the foregoing rules may be found in the Commission's Public Notice entitled "Applicability of Sponsorship Identification Rules" (FCC 63-409; 28 F.R. 4732, May 10, 1963) and such supplements thereto as are issued from time

(Sec. 317, 48 Stat. 1089, as amended; 47 U.S.C. 317)

§ 73.655 Rebroadcast.

(a) The term "rebroadcast" as used in this section means reception by radio of the program of a television broadcast station, and the simultaneous or subsequent retransmission of such program by a broadcast station. The broadcasting of a program relayed by an auxiliary broadcast station licensed to the television broadcast station is not considered a rebroadcast. (As used in this section, program includes any complete program or part thereof.)

(b) The licensee of a television broadcast station may, without further authority of the Commission, rebroadcast the program of a United States television broadcast station, provided the Commission is notified of the call letters of each station rebroadcast and the licensee certifies that express authority has been received from the licensee of the station originating the program.

NOTE: The notice and certification of consent shall be given within 3 days of any single rebroadcast, but in case of the regular practice of rebroadcasting certain programs of a television broadcast station several times during a license period, notice and certification of consent shall be given for the ensuing license period with the application for renewal of license, or at the beginning of such rebroadcast practice if begun during a license period.

(c) No licensee of a television broadcast station shall rebroadcast the program of any United States radio station not designated in paragraph (b) of this section without written authority having first been obtained from the Commission upon application (informal) accompanied by written consent or certification of consent of the licensee of the station originating the program. The foregoing requirements concerning notification of call letters and certification of authority shall not apply to a station when rebroadcasting Defense Network (FM) programs. (Blanket authorizations for the rebroadcast of such programs have been filed with the Commission by all Defense Network (FM) stations.)

NOTE: By Order No. 82, dated and effective June 24, 1941, until further order of the Commission, § 73.655 (c) is suspended only insofar as it requires prior written authority of the Commission for the rebroadcasting of programs originated for that express purpose by U. S. Government radio stations.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

§ 73.656 Lotteries.

(a) An application for construction permit, license, renewal of license, or any other authorization for the operation of a broadcast station, will not be granted where the applicant proposes to follow or continue to follow a policy or practice of broadcasting or permitting "the broadcasting of, any advertisement of or information concerning any lottery, gift enterprise, or similar scheme, offering prizes dependent in whole or in part upon lot or chance, or any list of the prizes drawn or awarded by means of any such lottery, gift enterprise, or scheme, whether said list contains any part or all of such prizes." (See 18 U. S. C. 1304.)

(b) The determination whether a particular program comes within the provisions of paragraph (a) of this section depends on the facts of each case. However, the Commission will in any event consider that a program comes within the provisions of paragraph (a) of this section if in connection with such program a prize consisting of money or thing of value is awarded to any person whose selection is dependent in whole or in part upon lot or chance, if as a condition of winning or competing for such prize, such winner or winners are required to furnish any money or thing of value or are required to have in their possession any product sold, manufactured, furnished or distributed by a sponsor of a program broadcast on the station in question.

(Sec. 1304, 62 Stat 763; 18 U.S.C. 1304)

§ 73.657 Broadcasts by candidates for public office.

(a) *Legally qualified candidate.* A "legally qualified candidate" means any person who has publicly announced that he is a candidate for nomination by a convention of a political party or for nomination or election in a primary, special, or general election, municipal, county, state or national, and who meets the qualifications prescribed by the applicable laws to hold the office for which he is a candidate, so that he may be voted for by the electorate directly or by means of delegates or electors, and who:

(1) Has qualified for a place on the ballot, or

(2) Is eligible under the applicable law to be voted for by sticker, by writing in his name on the ballot, or other method, and (i) has been duly nominated by a political party which is commonly known and regarded as such, or (ii) makes a substantial showing that he is a bona fide candidate for nomination or office.

(b) *General requirements.* No station licensee is required to permit the use of its facilities by any legally qualified candidate for public office, but if any licensee shall permit any such candidate to use its facilities, it shall afford equal opportunities to all other such candidates for that office to use such facilities: *Provided,* That such licensee shall have no power of censorship over the material broadcast by any such candidate.

(c) *Rates and practices.* (1) The rates, if any, charged all such candidates for the same office shall be uniform and shall not be rebated by any means direct or indirect. A candidate shall, in each case, be charged no more than the rate the station would charge if the candidate were a commercial advertiser whose advertising was directed to promoting its business within the same area as that encompassed by the particular office for which such person is a candidate. All discount privileges otherwise offered by a station to commercial advertisers shall be available upon equal terms to all candidates for public office.

(2) In making time available to candidates for public office no licensee shall make any discrimination between candidates in charges, practices, regulations, facilities, or services for or in connection with the service rendered pursuant to this part, or make or give any preference to any candidate for public office or subject any such candidate to any prejudice or disadvantage; nor shall any licensee make any contract or other agreement which shall have the effect of permitting any legally qualified candidate for any public office to broadcast to the exclusion of other legally qualified candidates for the same public office.

(d) *Inspection of records.* Every licensee shall keep and permit public inspection of a complete record of all requests for broadcast time made by or on behalf of candidates for public office, together with an appropriate notation showing the disposition made by the licensee of such requests, and the charges made, if any, if request is granted. Such records shall be retained for a period of two years.

(e) *Time of request.* A request for equal opportunities must be submitted to the licensee within one week of the day on which the prior use occurred.

(f) *Burden of proof.* A candidate requesting such equal opportunities of the licensee, or complaining of non-compliance to the Commission shall have the burden of proving that he and his opponent are legally qualified candidates for the same public office.

(Sec. 315, 48 Stat. 1088, as amended; 47 U.S.C. 315)

§ 73.658 Affiliation agreements.

(a) *Exclusive affiliation of station.* No license shall be granted to a television broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization under which the station is prevented or hindered from, or penalized for, broadcasting the programs of any other network organization. (The term "network organization" as used in this section includes national and regional network organizations. See ch. VII, J, of Report on Chain Broadcasting.)

(b) *Territorial exclusivity.* No license shall be granted to a television broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which prevents or hinders another broadcast station located in the same community from broadcasting the network's programs not taken by the former station, or which prevents or hinders another broadcast station located in a different community from broadcasting any program of the network organization. This section shall not be construed to prohibit any contract, arrangement, or understanding between a station and a network organization pursuant to which the station is granted the first call in its community upon the programs of the network organization. As employed in this paragraph, the term "community" is defined as the community specified in the instrument of authorization as the location of the station.

(c) *Term of affiliation.* No license shall be granted to a television broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which provides, by original terms, provisions for renewal, or otherwise for the affiliation of the station with the network organization for a period longer than 2 years: *Provided,* That a contract, arrangement, or understanding for a period up to 2 years may be entered into within 6 months prior to the commencement of such period.

(d) *Station commitment of broadcast time.* No license shall be granted to a television broadcast station having any contract, arrangement, or understanding, express or implied, with any network organization, which provides for optioning of the station's time to the network organization, or which has the same restraining effect as time optioning. As used in this section, time optioning is any contract, arrangement, or understanding, express or implied, between a station and a network organization which prevents or hinders the station from scheduling programs before the network agrees to utilize the time during which such programs are scheduled, or which requires the station to clear time already scheduled when the network organization seeks to utilize the time.

(e) *Right to reject programs.* No license shall be granted to a television broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization which, with respect to programs offered or already contracted for pursuant to an affiliation contract, prevents or hinders the station from (1) rejecting or refusing network programs which the station reasonably believes to be unsatisfactory or unsuitable or contrary to the public interest, or (2) substituting a program which, in the station's opinion, is of greater local or national importance.

(f) *Network ownership of stations.* No license shall be granted to a network organization, or to any person directly or indirectly controlled by or under common control of a network organization, for a television broadcast station in any locality where the existing television broadcast stations are so few or of such unequal desirability (in terms of coverage, power, frequency, or other related matters) that competition would be substantially restrained by such licensing. (The word "control" as used in this section, is not limited to full control but includes such a measure of control as would substantially affect the availability of the station to other networks.)

(g) *Dual network operation.* No license shall be issued to a television broadcast station affiliated with a network organization which maintains more than one network of television broadcast stations: *Provided,* That this section shall not be applicable if such networks are not operated simultaneously, or if there is no substantial overlap in the territory served by the group of stations comprising each such network.

(h) *Control by networks of station rates.* No license shall be granted to a television broadcast station having any contract, arrangement, or understanding, express or implied, with a network organization under which the station is

prevented or hindered from, or penalized for, fixing or altering its rates for the sale of broadcast time for other than the network's programs.

(i) No license shall be granted to a television broadcast station which is represented for the sale of non-network time by a network organization or by an organization directly or indirectly controlled by or under common control with a network organization, if the station has any contract, arrangement or understanding, express or implied, which provides for the affiliation of the station with such network organization: *Provided, however,* That this rule shall not be applicable to stations licensed to a network organization or to a subsidiary of a network organization.

§ 73.659 Special rules relating to contracts providing for reservation of time upon sale of a station.

No license, renewal of license, assignment of license, or transfer of control of a corporate licensee shall be granted or authorized to a television broadcast station which has a contract, arrangement or understanding, express or implied, pursuant to which, as consideration or partial consideration for the assignment of license or transfer of control, the assignor of a station license or the transferor of stock, where transfer of a corporate licensee is involved, or the nominee of such assignor or transferor retains any right of reversion of the license or any right to the reassignment of the license in the future, or reserves the right to use the facilities of the station for any period whatsoever.

§ 73.660 Station license, posting of.

The original of each station license shall be posted in the transmitter room.

§ 73.661 Operator requirements.

One or more operators holding a valid radiotelephone first class operator license shall be on duty at the place where the transmitting apparatus is located or at a remote control point established pursuant to the provisions of § 73.676, and in actual charge thereof whenever the transmitter is delivering power to the transmitting antenna. The original license (or FCC Form 759) of each station operator shall be posted at the place where he is on duty. The licensed operator on duty and in charge of a television broadcast transmitter may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of license which he holds and the rules and regulations governing such other stations. However, such other duties shall in nowise impair or impede the required supervision of the television broadcast transmitter.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 73.662 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (construction, marking, and lighting of antenna structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of that part.

§ 73.665 Station inspection.

The licensee of a television broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 73.666 Experimental operation.

Television broadcast stations may (upon informal application) conduct technical experimentation directed to the improvement of technical phases of operation and for such purposes may utilize a signal other than the standard television signal subject to the following conditions:

(a) That the licensee complies with the provisions of § 73.651 with regard to the minimum number of hours of transmission with a standard television signal.

(b) That no transmissions are radiated outside of the authorized channel and subject to the condition that no interference is caused to the transmissions of a standard television signal by other television broadcast stations.

(c) No charges either direct or indirect shall be made by the licensee of a television broadcast station for the production or transmission of programs when conducting technical experimentation.

§ 73.667 Discontinuance of operation.

The licensee of each station shall notify the Commission in Washington, D.C., and the Engineer in Charge of the radio district where such station is located of permanent discontinuance of operation at least two days before operation is discontinued. The licensee shall, in addition, immediately forward the station license and other instruments of authorization to the Washington, D.C., office of the Commission for cancellation.

§ 73.668 Frequency tolerance.

(a) The carrier frequency of the visual transmitter shall be maintained within ±1000 cycles of the authorized carrier frequency.

(b) The center frequency of the aural transmitter shall be maintained 4.5 megacycles, ±1000 cycles, above the visual carrier frequency.

§ 73.669 General requirements relating to logs.

(a) The licensee or permittee of each television broadcast station shall maintain program, operating, and maintenance logs as set forth in §§ 73.670, 73.671, and 73.672. Each log shall be kept by the person or persons competent to do so, having actual knowledge of the facts required, who shall sign the appropriate log when starting duty and again when going off duty.

(b) The logs shall be kept in an orderly and legible manner, in suitable form, and in such detail that the data required for the particular class of station concerned is readily available. Key letters or abbreviations may be used if proper meaning or explanation is contained elsewhere in the log. Each sheet shall be numbered and dated. Time entries shall be either in local standard or daylight saving time and shall be indicated accordingly.

(c) No log or portion thereof shall be erased, obliterated, or willfully destroyed within the period of retention provided by the rules and regulations. Any necessary correction may be made only by the person originating the entry who shall strike out the erroneous portion, initial the correction made, and indicate the date of correction.

(d) Original data may be recorded in rough form and later transcribed into the log, but in such case all portions of the original memoranda shall be preserved as a part of the complete log.

§ 73.670 Program log.

(a) The following entries shall be made in the program log:

(1) An entry of the time each station identification announcement (call letters and location) is made.

(2) An entry briefly describing each program broadcast, such as "music," "drama," "speech," etc., together with the name or title thereof and the sponsor's name, with the time of the beginning and ending of the complete program. If a mechanical reproduction, either visual or aural, is used, the entry shall show the exact nature thereof and the time it is announced as a mechanical reproduction. If a speech is made by a political candidate, the name and political affiliations of such speaker shall be entered.

(3) An entry showing that each sponsored program broadcast has been announced as sponsored, paid for, or furnished by the sponsor; or that the broadcast is under the auspices of a nonprofit educational organization other than the licensee or permittee.

(4) An entry showing, for each program of network origin, the name of the network originating the program.

(b) No provision of this section shall be construed as prohibiting the recording or other automatic maintenance of data required for program logs. However, where such automatic logging is used, the licensee must comply with the following requirements:

(1) The licensee, whether employing manual or automatic logging or a combination thereof, must be able accurately to furnish the Commission with all information required to be logged;

(2) Each recording, tape, or other means employed shall be accompanied by a certificate of the operator or other responsible person on duty at the time or other duly authorized agent of the licensee, to the effect that it accurately reflects what was actually broadcast. Any information required to be logged which cannot be incorporated in the automatic process shall be maintained in a separate record which shall be similarly authenticated; and

(3) The licensee shall extract any required information from the recording for the days specified by the Commission or its duly authorized representative and submit it in written log form, together with the underlying recording, tape or other means employed.

§ 73.671 Operating log.

(a) The following entries shall be made in the operating log:

(1) An entry of the time the station begins to supply power to the antenna and the time it stops.

(2) An entry of each interruption of the carrier wave, where restoration is not automatic, its cause and duration followed by the signature of the person restoring operation (if licensed operator other than the licensed operator on duty).

(3) An entry, at the beginning of operation and at intervals not exceeding one-half hour, of the following (actual readings observed prior to making any adjustments to the equipment) and, when appropriate, an indication of corrections made to restore parameters to normal operating values:

(i) Operating constants of last radio stage of aural transmitter (total plate voltage and plate current).

(ii) Transmission line meter readings for both transmitters.

(4) Any other entries required by the instrument of authorization or the provisions of this part.

(b) Automatic devices accurately calibrated and with appropriate time, date and circuit functions may be utilized to record the entries in the operating log: *Provided,* That:

(1) They do not affect the operation of circuits or accuracy of indicating instruments of the equipment being recorded;

(2) The recording devices have an accuracy equivalent to the accuracy of the indicating instruments;

(3) The calibration is checked against the original indicators at least once a week and the results noted in the maintenance log;

(4) Provision is made to actuate automatically an aural alarm circuit located near the operator on duty if any of the automatic log readings are not within the tolerances or other requirements specified in the rules or instrument of authorization;

(5) Unless the alarm circuit operates continuously, devices which record each parameter in sequence must read each parameter at least once during each 10-minute period and clearly indicate the parameter being recorded;

(6) The automatic logging equipment is located in the near vicinity of the operator on duty and is inspected by him periodically during the broadcast day; and

(7) The indicating equipment conforms to the requirements of § 73.681 except that the scales need not exceed 2 inches in length. Arbitrary scales may not be used.

§ 73.672 Maintenance log.

The following entries shall be made in the maintenance log:

(a) An entry each week of the time and result of test of auxiliary transmitters.

(b) A notation each week of the calibration check of automatic recording devices as required by § 73.671(b)(3).

(c) An entry of the method used and results of comparing the frequency deviation of the station with an external frequency source whenever the local visual or aural frequency reference source becomes defective.

(d) An entry of the date and time of removal from and restoration to service of any of the following equipment in the event it becomes defective:

(1) Visual modulation monitoring equipment or aural modulation monitor.

(2) Visual or aural frequency monitor.

(3) Final stage plate voltmeters of aural and visual transmitters.

(4) Final stage plate ammeters of aural and visual transmitters.

(5) Visual and aural transmitter transmission line radio frequency voltage, current or power meter.

(e) Record of tower light inspections where required by § 17.38 of this chapter (Part 17—Construction, Marking and Lighting of Antenna Structures).

(f) Entries shall be made so as to describe fully any experimental operation.

(g) Any other entries required by the instrument of authorization or the provisions of this part.

§ 73.673 Retention of logs.

Logs of television broadcast stations shall be retained by the licensee or permittee for a period of 2 years: *Provided, however,* That logs involving communications incident to a disaster or which include communications incident to or involved in an investigation by the Commission and concerning which the licensee or permittee has been notified, shall be retained by the licensee or permittee until he is specifically authorized in writing by the Commission to destroy them: *Provided, further,* That logs incident to or involved in any claim or complaint of which the licensee or permittee has notice shall be retained by the licensee or permittee until such claim or complaint has been fully satisfied or until the same has been barred by statute limiting the time for the filing of suits upon such claims.

§ 73.674 Availability of logs and records.

The program, operating, and maintenance logs shall be made available upon request by an authorized representative of the Commission.

§ 73.675 Operation during emergency.

(a) The licensee of a television broadcast station or the permittee of such a station operating under program test authority is authorized only to disseminate radio communications intended to be received by the public. However, during a period of emergency or imminent emergency in the area in which the station is located such a licensee or permittee may also utilize its station for transmitting communications directly related to the emergency which are intended to be received by specific individuals for the purpose of dispatching aid, assisting in rescue operations or otherwise promoting the safety of life and property or alleviating hardship. In the course of such operation a station may communicate with stations of other classes and in other services. For the purposes of this section, an emergency shall mean a situation that would generally and seriously endanger life and property or cause substantial hardship as a result of events such as hurricane or other severe weather conditions, flood, earthquake or wide-area forest fire. The term shall not include situations resulting from frosts, or localized fires which are not a source of general danger.

(b) The decision to operate under the provisions of this section lies solely with the licensee or permittee of the station, requests by governmental or other officials not being controlling. However, such emergency operation shall terminate upon order of the Commission.

(c) When engaged in operation under the provisions of this section a station shall use the frequency specified in and power not in excess of that specified in its instrument of authorization.

(d) A licensee or permittee operating under the provisions of this section shall (1) as soon as possible after the beginning of such emergency use, send notice to the Commission at Washington, D.C., and to the Engineer in Charge of the district in which the station is located, stating the nature of the emergency and the use to which the station is being put; (2) discontinue such emergency operation as soon as the conditions requiring such operation are no longer present or the public has had an opportunity to be adequately informed; and (3) immediately upon cessation of such emergency operation notify the Commision in Washington, D.C., and the Engineer in Charge of the district in which the station is located, and shall in such notice justify the operation by stating the nature of the emergency, the exact times of operation, the type of emergency information transmitted, the total amount of time devoted to the transmission of emergency information, and other pertinent details.

(e) No operation under this section shall be permitted if an Emergency Action Condition, under the provisions of Subpart G of this part, is in effect. If a station is operating under this section and an Emergency Action Condition is declared, compliance with the Emergency Action Notification shall take precedence.

§ 73.676 Remote control operation.

(a) Television broadcast stations operating on Channels 14–83 may be authorized to operate by remote control upon a satisfactory showing as to the manner of compliance with the following requirements:

(1) Suitable control circuits shall be installed to:

(i) Turn the transmitter on and off at will.

(ii) Determine the power output of the visual and aural final radio frequency amplifiers or the power delivered to the antenna.

(iii) Adjust the power output of the final radio frequency amplifier to compensate for variations in line voltage.

(iv) Make such adjustments as may be necessary to insure that the characteristics of the transmitted signal comply in all respects with the technical requirements of the rules.

(2) The control point shall be equipped with apparatus suitable for ob-

serving the waveform and other pertinent characteristics of the transmitted visual signal and the percent of modulation of the transmitted aural signal.

(3) The control circuits from the control point to the transmitter shall be so designed and installed that open circuits, short circuits, accidental grounding, or other line faults will not activate the transmitting apparatus and any fault which results in loss of control of the transmitting apparatus will automatically remove power from the transmitting antenna.

(4) The transmitting equipment and control equipment shall be adequately protected against tampering or activation by unauthorized persons.

(b) Where a transmitter is operated by remote control the transmitting apparatus and associated controls shall be checked as often as is necessary to insure proper operation and confirm the accuracy of the transmitter data sent to the control point over the control circuits and in all cases at least once each week until it can be demonstrated to the Commission that checks at less frequent intervals are satisfactory.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

TV Technical Standards

§ 73.681 Definitions.

Amplitude modulation (AM). A system of modulation in which the envelope of the transmitted wave contains a component similar to the wave form of the signal to be transmitted.

Antenna height above average terrain. The average of the antenna heights above the terrain from two to ten miles from the antenna for the eight directions spaced evenly for each 45 degrees of azimuth starting with True North. (In general, a different antenna height will be determined in each direction from the antenna. The average of these various heights is considered the antenna height above the average terrain. In some cases less than 8 directions may be used. See § 73.684(d)).

Antenna power gain. The square of the ratio of the root-mean-square free space field intensity produced at one mile in the horizontal plane, in millivolts per meter for one kilowatt antenna input power to 137.6 mv/m. This ratio should be expressed in decibels (db). (If specified for a particular direction, antenna power gain is based on the field strength in that direction only.)

Aspect ratio. The ratio of picture width to picture height as transmitted.

Aural transmitter. The radio equipment for the transmission of the aural signal only.

Aural center frequency. (1) The average frequency of the emitted wave when modulated by a sinusoidal signal; (2) the frequency of the emitted wave without modulation.

Blanking level. The level of the signal during the blanking interval, except the interval during the scanning synchronizing pulse and the chrominance subcarrier synchronizing burst.

Chrominance. The colorimetric difference between any color and a reference color of equal luminance, the reference color having a specific chromaticity.

Chrominance subcarrier. The carrier which is modulated by the chrominance information.

Color transmission. The transmission of color television signals which can be reproduced with different values of hue, saturation, and luminance.

Effective radiated power. The product of the antenna input power and the antenna power gain. This product should be expressed in kilowatts and in decibels above one kilowatt (dbk). (If specified for a particular direction, effective radiated power is based on the antenna power gain in that direction only. The licensed effective radiated power is based on the average antenna power gain for each horizontal plane direction.)

Field. Scanning through the picture area once in the chosen scanning pattern. In the line interlaced scanning pattern of two to one, the scanning of the alternate lines of the picture area once.

Frame. Scanning all of the picture area once. In the line interlaced scanning pattern of two to one, a frame consists of two fields.

Free space field intensity. The field intensity that would exist at a point in the absence of waves reflected from the earth or other reflecting objects.

Frequency modulation (FM). A system of modulation where the instantaneous radio frequency varies in proportion to the instantaneous amplitude of the modulating signal (amplitude of modulating signal to be measured after pre-emphasis, if used) and the instantaneous radio frequency is independent of the frequency of the modulating signal.

Frequency swing. The instantaneous departure of the frequency of the emitted wave from the center frequency resulting from modulation.

Interlaced scanning. A scanning process in which successively scanned lines are spaced an integral number of line widths, and in which the adjacent lines are scanned during successive cycles of the field frequency.

Luminance. Luminous flux emitted, reflected, or transmitted per unit solid angle per unit projected area of the source.

Monochrome transmission. The transmission of television signals which can be reproduced in gradations of a single color only.

Negative transmission. Where a decrease in initial light intensity causes an increase in the transmitted power.

Peak power. The power over a radio frequency cycle corresponding in amplitude to synchronizing peaks.

Percentage modulation. As applied to frequency modulation, the ratio of the actual frequency swing to the frequency swing defined as 100 percent modulation, expressed in percentage. For the aural transmitter of television broadcast stations, a frequency swing of ±25 kilocycles is defined as 100 percent modulation.

Polarization. The direction of the electric field as radiated from the transmitting antenna.

Reference black level. The level corresponding to the specified maximum excursion of the luminance signal in the black direction.

Reference white level of the luminance signal. The level corresponding to the specified maximum excursion of the luminance signal in the white direction.

Scanning. The process of analyzing successively, according to a predetermined method, the light values of picture elements constituting the total picture area.

Scanning line. A single continuous narrow strip of the picture area containing highlights, shadows, and half-tones, determined by the process of scanning.

Standard television signal. A signal which conforms to the television transmission standards.

Synchronization. The maintenance of one operation in step with another.

Television broadcast band. The frequencies in the band extending from 54 to 890 megacycles which are assignable to television broadcast stations. These frequencies are 54 to 72 megacycles (channels 2 through 4), 76 to 88 megacycles (channels 5 and 6), 174 to 216 megacycles (channels 7 through 13), and 470 to 890 megacycles (channels 14 through 83).

Television broadcast station. A station in the television broadcast band transmitting simultaneous visual and aural signals intended to be received by the general public.

Television channel. A band of frequencies 6 megacycles wide in the television broadcast band and designated either by number or by the extreme lower and upper frequencies.

Television transmission standards. The standards which determine the characteristics of a television signal as radiated by a television broadcast station.

Television transmitter. The radio transmitter or transmitters for the transmission of both visual and aural signals.

Vestigial sideband transmission. A system of transmission wherein one of the generated sidebands is partially attenuated at the transmitter and radiated only in part.

Visual carrier frequency. The frequency of the carrier which is modulated by the picture information.

Visual transmitter. The radio equipment for the transmission of the visual signal only.

Visual transmitter power. The peak power output when transmitting a standard television signal.

§ 73.682 Transmission standards and changes.

(a) *Transmission standards.* (1) The width of the television broadcast channel shall be 6 Mc/s.

(2) The visual carrier frequency shall be nominally 1.25 Mc/s above the lower boundary of the channel.

(3) The aural center frequency shall be 4.5 Mc/s higher than the visual carrier frequency.

(4) The visual transmission amplitude characteristic shall be in accordance with the chart designated as Figure 5 of § 73.699: *Provided, however,* That for stations operating on Channel 15–83 and employing a transmitter with maximum

peak visual power output of 1 kilowatt or less the visual transmission amplitude characteristic may be in accordance with the chart designated as Figure 5a of § 73.699.

(5) The chrominance subcarrier frequency shall be 3.579545 Mc/s ± 10 cycles per second with a maximum rate of change not to exceed one-tenth cycle per second per second.

(6) For monochrome and color transmissions the number of scanning lines per frame shall be 525, interlaced two to one in successive fields. The horizontal scanning frequency shall be $\frac{2}{455}$ times the chrominance subcarrier frequency; this corresponds nominally to 15,750 cycles per second (with an actual value of 15,734.264 ± 0.044 cycles per second). The vertical scanning frequency is $\frac{2}{525}$ times the horizontal scanning frequency; this corresponds nominally to 60 cycles per second (the actual value is 59.94 cycles per second). For monochrome transmissions only, the nominal values of line and field frequencies may be used.

(7) The aspect ratio of the transmitted television picture shall be 4 units horizontally to 3 units vertically.

(8) During active scanning intervals, the scene shall be scanned from left to right horizontally and from top to bottom vertically, at uniform velocities.

(9) A carrier shall be modulated within a single television channel for both picture and synchronizing signals. For monochrome transmission, the two signals comprise different modulation ranges in amplitude, in accordance with the charts designated as Figures 5 and 7 of § 73.699 for stations operating on Channels 2–14 or Figures 5a and 7 for stations operating on Channels 15–83 and employing a transmitter with maximum peak visual power output of 1 kilowatt or less. For color transmission, the two signals comprise different modulation ranges in amplitude except where the chrominance penetrates the synchronizing region and the burst penetrates the picture region, in accordance with the charts designated as Figures 5 and 6 of § 73.699 for stations operating on Channels 2–14 or Figures 5a and 6 for stations operating on Channels 15–83 and employing a transmitter with maximum peak visual power output of 1 kilowatt or less.

(10) A decrease in initial light intensity shall cause an increase in radiated power (negative transmission).

(11) The reference black level shall be represented by a definite carrier level, independent of light and shade in the picture.

(12) The blanking level shall be transmitted at 75±2.5 percent of the peak carrier level.

(13) The reference white level of the luminance signal shall be 12.5±2.5 percent of the peak carrier level.

(14) The signals radiated shall have horizontal polarization.

(15) The effective radiated power of the aural transmitter of stations operating on Channels 2–13 shall not be less than 50 percent nor more than 70 percent of the peak radiated power of the visual transmitter. The effective radiated power of the aural transmitter of stations operating on Channels 14–83 shall not be less than 10 percent nor more than 70 percent of the peak radiated power of the visual transmitter.

(16) The peak-to-peak variation of transmitter output within one frame of video signal due to all causes, including hum, noise, and low-frequency response, measured at both scanning synchronizing peak and blanking level, shall not exceed 5 percent of the average scanning synchronizing peak signal amplitude. This provision is subject to change but is considered the best practice under the present state of the art. It will not be enforced pending a further determination thereof.

(17) The reference black level shall be separated from the blanking level by the setup interval, which shall be 7.5±2.5 percent of the video range from blanking level to the reference white level.

(18) For monochrome transmission, the transmitter output shall vary in substantially inverse logarithmic relation to the brightness of the subject. No tolerances are set at this time. This provision is subject to change but is considered the best practice under the present state of the art. It will not be enforced pending a further determination thereof.

(19) the color picture signal shall correspond to a luminance component transmitted as amplitude modulation of the picture carrier and a simultaneous pair of chrominance components transmitted as the amplitude modulation sidebands of a pair of suppressed subcarriers in quadrature.

(20) Equation of complete color signal.

(i) The color picture signal has the following composition:

$$E_M = E_Y' + \{E_Q' \sin(\omega t + 33°) + E_I' \cos(\omega t + 33°)\}$$

Where:

$$E_Q' = 0.41(E_B' - E_Y') + 0.48(E_R' - E_Y').$$
$$E_I' = -0.27(E_B' - E_Y') + 0.74(E_R' - E_Y').$$
$$E_Y' = 0.30E_R' + 0.59E_G' + 0.11E_B'.$$

For color-difference frequencies below 500 kc (see (iii) below), the signal can be represented by:

$$E_M = E_Y' + \left\{\frac{1}{1.14}\left[\frac{1}{1.78}(E_B' - E_Y')\sin\omega t + (E_R' - E_Y')\cos\omega t\right]\right\}$$

(ii) The symbols in subdivision (i) of this subparagraph have the following significance:

E_M is the total video voltage, corresponding to the scanning of a particular picture element, applied to the modulator of the picture transmitter.

E_Y' is the gamma-corrected voltage of the monochrome (black-and-white) portion of the color picture signal, corresponding to the given picture element.

NOTE: Forming of the high frequency portion of the monochrome signal in a different manner is permissible and may in fact be desirable in order to improve the sharpness on saturated colors.

E_Q' and E_I' are the amplitudes of two orthogonal components of the chrominance signal corresponding respectively to narrow-band and wide-band axes.

E_R', E_G', and E_B' are the gamma-corrected voltages corresponding to red, green, and blue signals during the scanning of the given picture element.

ω is the angular frequency and is 2π times the frequency of the chrominance subcarrier.

The portion of each expression between brackets in (i) represents the chrominance subcarrier signal which carries the chrominance information.

The phase reference in the E_M equation in (i) is the phase of the burst+180°, as shown in Figure 8 of § 73.699. The burst corresponds to amplitude modulation of a continuous sine wave.

(iii) The equivalent bandwidth assigned prior to modulation to the color difference signals E_Q' and E_I' are as follows:

Q-channel bandwidth:
- At 400 kc/s less than 2 db down.
- At 500 kc/s less than 6 db down.
- At 600 kc/s at least 6 db down.

I-channel bandwidth:
- At 1.3 Mc/s less than 2 db down.
- At 3.6 Mc/s at least 20 db down.

(iv) The gamma corrected voltages E_R', E_G', and E_B' are suitable for a color picture tube having primary colors with the following chromaticities in the CIE system of specification:

	x	y
Red (R)	0.67	0.33
Green (G)	0.21	0.71
Blue (B)	0.14	0.08

and having a transfer gradient (gamma exponent) of 2.2 associated with each primary color. The voltages E_R', E_G', and E_B' may be respectively of the form $E_R^{1/\gamma}$, $E_G^{1/\gamma}$, and $E_B^{1/\gamma}$ although other forms may be used with advances in the state of the art.

NOTE: At the present state of the art it is considered inadvisable to set a tolerance on the value of gamma and correspondingly this portion of the specification will not be enforced.

(v) The radiated chrominance subcarrier shall vanish on the reference white of the scene.

NOTE: The numerical values of the signal specification assume that this condition will be reproduced as CIE Illuminant C (x=0.310, y=0.316).

(vi) E_Y', E_Q', E_I', and the components of these signals shall match each other in time to 0.05 μsecs.

(vii) The angles of the subcarrier measured with respect to the burst phase, when reproducing saturated primaries and their complements at 75 percent of full amplitude, shall be within ±10° and their amplitudes shall be within ±20 percent of the values specified above. The ratios of the measured amplitudes of the subcarrier to the luminance signal for the same saturated primaries and their complements shall fall between the limits of 0.8 and 1.2 of the values specified for their ratios. Closer tolerances may prove to be practicable and desirable with advance in the art.

(21) The interval beginning with the last 12 microseconds of line 17 and continuing through line 20 of the vertical

blanking interval of each field may be used for the transmission of test signals subject to the conditions set forth below. Test signals may include signals used to supply reference modulation levels so that variations in light intensity of the scene viewed by the camera will be faithfully transmitted; signals designed to check the performance of the overall transmission system or its individual components; and cue and control signals related to the operation of the television broadcast station. Figures 6 and 7 of § 73.699 identify the numbered lines referred to in this subparagraph.

(i) Modulation of the television transmitter by such test signals shall be confined to the area between the reference white level and the blanking level except where such test signals are composed of chrominance subcarrier frequencies, in which case their negative excursions may extend into the synchronizing peak amplitude. In no case may the modulation excursions produced by test signals extend beyond peak-of-sync level.

(ii) The use of test signals shall not result in significant degradation of the program transmissions of the television broadcast station nor create emission components in excess of those permitted for normal program transmissions.

(iii) Test signals may not be transmitted during that portion of each line devoted to horizontal blanking.

(iv) A guard interval of no less than one-half line shall be maintained at all times between the last test signal and the beginning of the first picture scanning line.

(b) *Changes in transmission standards.* The Commission will consider the question whether a proposed change or modification of transmission standards adopted for television would be in the public interest, convenience and necessity, upon petition being filed by the person proposing such change or modification, setting forth the following:

(1) The exact character of the change or modification proposed;

(2) The effect of the proposed change or modification upon all other transmission standards that have been adopted by the Commission for television broadcast stations;

(3) The experimentation and field tests that have been made to show that the proposed change or modification accomplishes an improvement and is technically feasible;

(4) The effect of the proposed change or modification in the adopted standards upon operation and obsolescence of receivers;

NOTE: Should a change or modification in the transmission standards be adopted by the Commission, the effective date thereof will be determined in the light of the considerations mentioned in this subparagraph.

(5) The change in equipment required in existing television broadcast stations for incorporating the proposed change or modification in the adopted standards; and

(6) The facts and reasons upon which the petitioner bases his conclusion that the proposed change or modification would be in the public interest, convenience, and necessity.

§ 73.683 Field intensity contours.

(a) In the authorization of television broadcast stations, two field intensity contours are considered. These are specified as Grade A and Grade B and indicate the approximate extent of coverage over average terrain in the absence of interference from other television stations. Under actual conditions, the true coverage may vary greatly from these estimates because the terrain over any specific path is expected to be different from the average terrain on which the field strength charts were based. The required field intensities, F(50,50), in decibels above one microvolt per meter (dbu) for the Grade A and Grade B contours are as follows:

NOTE: It should be realized that the F(50,50) curves when used for Channels 14–83 are not based on measured data at distances beyond about 30 miles. Theory would indicate that the field intensities for Channels 14–83 should decrease more rapidly with distance beyond the horizon than for Channels 2–6, and modification of the curves for Channels 14–83 may be expected as a result of measurements to be made at a later date. For these reasons, the curves should be used with appreciation of their limitations in estimating levels of field intensity. Further, the actual extent of service will usually be less than indicated by these estimates due to interference from other stations. Because of these factors, the predicted field intensity contours give no assurance of service to any specific percentage of receiver locations within the distances indicated. In licensing proceedings these variations will not be considered.

	Grade A (dbu)	Grade B (dbu)
Channels 2–6	68	47
Channels 7–13	71	56
Channels 14–83	74	64

(b) The field intensity contours provided for herein shall be considered for the following purposes only:

(1) In the estimation of coverage resulting from the selection of a particular transmitter site by an applicant for a television station.

(2) In connection with problems of coverage arising out of application of § 73.636.

(3) In determining compliance with § 73.685(a) concerning the minimum field intensity to be provided over the principal community to be served.

§ 73.684 Prediction of coverage.

(a) All predictions of coverage made pursuant to this section shall be made without regard to interference and shall be made only on the basis of estimated field intensities. The peak power of the visual signal is used in making predictions of coverage.

(b) Predictions of coverage shall be made only for the same purposes as relate to the use of field intensity contours as specified in § 73.683(b).

(c) In predicting the distance to the field intensity contours, the F(50,50) field intensity charts (Figures 9 and 10 of § 73.699) shall be used. If the 50 percent field intensity is defined as that value exceeded for 50 percent of the time, these F(50,50) charts give the estimated 50 percent field intensities exceeded at 50 percent of the locations in decibels above one microvolt per meter. The charts are based on an effective power of one kilowatt radiated from a half-wave dipole in free space, which produces an unattenuated field strength at one mile of about 103 db above one microvolt per meter (137.6 millivolts per meter). To use the charts for other powers, the sliding scale associated with the charts should be trimmed and used as the ordinate scale. This sliding scale is placed on the charts with the appropriate gradation for power in line with the horizontal 40 db line on the charts. The right edge of the scale is placed in line with the appropriate antenna height gradations, and the charts then become direct reading (in uv/m and in db above 1 uv/m) for this power and antenna height. Where the antenna height is not one of those for which a scale is provided, the signal strength or distance is determined by interpolation between the curves connecting the equidistant points. Dividers may be used in lieu of the sliding scale. In predicting the distance to the Grade A and Grade B field intensity contours, the effective radiated power to be used is that in the horizontal plane in the pertinent direction. In predicting other field intensities over areas not in the horizontal plane, the effective radiated power to be used is the power in the direction of such areas; the appropriate vertical plane radiation pattern must, of course, be considered in determining this power.

(d) The antenna height to be used with these charts is the height of the radiation center of the antenna above the average terrain along the radial in question. In determining the average elevation of the terrain, the elevations between 2 and 10 miles from the antenna site are employed. Profile graphs shall be drawn for 8 radials beginning at the antenna site and extending 10 miles therefrom. The radials should be drawn for each 45 degrees of azimuth starting with True North. At least one radial must include the principal community to be served even though such community may be more than 10 miles from the antenna site. However, in the event none of the evenly spaced radials include the principal community to be served and one or more such radials are drawn in addition to the 8 evenly spaced radials, such additional radials shall not be employed in computing the antenna height above average terrain. Where the 2 to 10 mile portion of a radial extends in whole or in part over large bodies of water as specified in paragraph (e) of this section or extends over foreign territory but the Grade B intensity contour encompasses land area within the United States beyond the 10 mile portion of the radial, the entire 2 to 10 mile portion of the radial shall be included in the computation of antenna height above average terrain. However, where the Grade B contour does not so encompass United States land area and (1) the entire 2 to 10 mile portion of the radial extends over large bodies of water or foreign territory, such radial shall be completely omitted from the computation of antenna height above average terrain, and

(2) where a part of the 2 to 10 mile portion of a radial extends over large bodies of water or over foreign territory, only that part of the radial extending from the 2 mile sector to the outermost portion of land area within the United States covered by the radial shall be employed in the computation of antenna height above average terrain. The profile graph for each radial should be plotted by contour intervals of from 40 to 100 feet and, where the data permits, at least 50 points of elevation (generally uniformly spaced) should be used for each radial. In instances of very rugged terrain where the use of contour intervals of 100 feet would result in several points in a short distance, 200- or 400-foot contour intervals may be used for such distances. On the other hand, where the terrain is uniform or gently sloping the smallest contour interval indicated on the topographic map (see paragraph (g) of this section) should be used, although only relatively few points may be available. The profile graphs should indicate the topography accurately for each radial, and the graphs should be plotted with the distance in miles as the abscissa and the elevation in feet above mean sea level as the ordinate. The profile graphs should indicate the source of the topographical data employed. The graph should also show the elevation of the center of the radiating system. The graph may be plotted either on rectangular coordinate paper or on special paper which shows the curvature of the earth. It is not necessary to take the curvature of the earth into consideration in this procedure, as this factor is taken care of in the charts showing signal intensities. The average elevation of the 8-mile distance between 2 and 10 miles from the antenna site should then be determined from the profile graph for each radial. This may be obtained by averaging a large number of equally spaced points, by using a planimeter, or by obtaining the median elevation (that exceeded for 50 percent of the distance) in sectors and averaging those values.

NOTE: The Commission will, upon a proper showing by an existing station that the application of this rule will result in an unreasonable power reduction in relation to other stations in close proximity, consider requests for adjustment in power on the basis of a common average terrain figure for the stations in question as determined by the Commission.

(e) In instances where it is desired to determine the area in square miles within the Grade A and Grade B field intensity contours, the area may be determined from the coverage map by planimeter or other approximate means; in computing such areas, exclude (1) areas beyond the borders of the United States, and (2) large bodies of water, such as ocean areas, gulfs, sounds, bays, large lakes, etc., but not rivers.

(f) In cases where the terrain in one or more directions from the antenna site departs widely from the average elevation of the 2 to 10 mile sector, the prediction method may indicate contour distances that are different from what may be expected in practice. For example, a mountain ridge may indicate the practical limit of service although the prediction method may indicate otherwise. In such cases the prediction method should be followed, but a supplemental showing may be made concerning the contour distances as determined by other means. Such supplemental showing should describe the procedure employed and should include sample calculations. Maps of predicted coverage should include both the coverage as predicted by the regular method and as predicted by a supplemental method. When measurements of area are required, these should include the area obtained by the regular prediction method and the area obtained by the supplemental method. In directions where the terrain is such that negative antenna heights or heights below 100 feet for the 2 to 10 mile sector are obtained, a supplemental showing of expected coverage must be included together with a description of the method employed in predicting such coverage. In special cases, the Commission may require additional information as to terrain and coverage.

(g) In the preparation of the profile graphs previously described, and in determining the location and height above sea level of the antenna site, the elevation or contour intervals shall be taken from the United States Geological Survey Topographic Quadrangle Maps, United States Army Corps of Engineers maps or Tennessee Valley Authority maps, whichever is the latest, for all areas for which such maps are available. If such maps are not published for the area in question, the next best topographic information should be used. Topographic data may sometimes be obtained from State and municipal agencies. Data from Sectional Aeronautical Charts (including bench marks) or railroad depot elevations and highway elevations from road maps may be used where no better information is available. In cases where limited topographic data is available, use may be made of an altimeter in a car driven along roads extending generally radially from the transmitter site. Ordinarily the Commission will not require the submission of topographical maps for areas beyond 15 miles from the antenna site, but the maps must include the principal community to be served. If it appears necessary, additional data may be requested. United States Geological Survey Topographic Quadrangle Maps may be obtained from the United States Geological Survey, Department of the Interior, Washington, D.C., 20240. Sectional Aeronautical Charts are available from the United States Coast and Geodetic Survey, Department of Commerce, Washington, D.C., 20235.

§ 73.685 Transmitter location and antenna system.

(a) The transmitter location shall be chosen so that, on the basis of the effective radiated power and antenna height above average terrain employed, the following minimum field intensity in decibels above one microvolt per meter (dbu) will be provided over the entire principal community to be served:

Channels 2–6	Channels 7–13	Channels 14–83
74 dbu	77 dbu	80 dbu

(b) Location of the antenna at a point of high elevation is necessary to reduce to a minimum the shadow effect on propagation due to hills and buildings which may reduce materially the intensity of the station's signals. In general, the transmitting antenna of a station should be located at the most central point at the highest elevation available. To provide the best degree of service to an area, it is usually preferable to use a high antenna rather than a low antenna with increased transmitter power. The location should be so chosen that line-of-sight can be obtained from the antenna over the principal community to be served; in no event should there be a major obstruction in this path. The antenna must be constructed so that it is as clear as possible of surrounding buildings or objects that would cause shadow problems. It is recognized that topography, shape of the desired service area, and population distribution may make the choice of a transmitter location difficult. In such cases, consideration may be given to the use of a directional antenna system, although it is generally preferable to choose a site where a non-directional antenna may be employed.

(c) In cases of questionable antenna locations it is desirable to conduct propagation tests to indicate the field intensity expected in the principal community to be served and in other areas, particularly where severe shadow problems may be expected. In considering applications proposing the use of such locations, the commission may require site tests to be made. Such tests should be made in accordance with the measurement procedure in § 73.686, and full data thereon must be supplied to the Commission. Test transmitters should employ an antenna having a height as close as possible to the proposed antenna height, using a balloon or other support if necessary and feasible. Information concerning the authorization of site tests may be obtained from the Commission upon request.

(d) Present information is not sufficiently complete to establish "blanket areas" of television broadcast stations. A "blanket area" is that area adjacent to a transmitter in which the reception of other stations is subject to interference due to the strong signal from this station. The authorization of station construction in areas where blanketing is found to be excessive will be on the basis that the applicant will assume full responsibility for the adjustment of reasonable complaints arising from excessively strong signals of the applicant's station or take other corrective action.

(e) An antenna designed or altered to produce a non-circular radiation pattern in the horizontal plane is considered to be a directional antenna. Directional antennas may be employed for the pur-

pose of improving service upon an appropriate showing of need. Stations operating on Channels 2–13 will not be permitted to employ a directional antenna having a ratio of maximum to minimum radiation in the horizontal plane in excess of 10 decibels. Stations operating on Channels 14–83 with transmitters delivering a peak visual power output of more than 1 kilowatt may employ directive transmitting antennas with a maximum to minimum radiation in the horizontal plane of not more than 15 decibels. Stations operating on Channels 14–83 and employing transmitters delivering a peak visual power output of 1 kilowatt or less are not limited as to the ratio of maximum to minimum radiation.

(f) Applications proposing the use of directional antenna systems must be accompanied by the following:

(1) Complete description of the proposed antenna system.

(2) Orientation of array with respect to true north; time phasing of fields from elements (degrees leading or lagging); space phasing of elements (in feet and degrees); and ratio of fields from elements.

(3) Horizontal and vertical plane radiation patterns showing the free space field intensity in millivolts per meter at 1 mile and the effective radiated power, in dbk, for each direction. The method by which the radiation patterns were computed or measured shall be fully described, including formulas used, equipment employed, sample calculations and tabulations of data. Sufficient vertical plane patterns shall be included to indicate clearly the radiation characteristics of the antenna above and below the horizontal plane. The horizontal plane pattern shall be plotted on polar coordinate paper with reference to true north. The vertical plane patterns shall be plotted on rectangular coordinate paper with reference to the horizontal plane.

(4) Name, address, and qualifications of the engineer making the calculations.

(g) Applications proposing the use of television broadcast antennas within 200 feet of other television broadcast antennas operating on a channel within 20 percent in frequency of the proposed channel, or proposing the use of television broadcast antennas on Channels 5 or 6 within 200 feet of FM broadcast antennas, must include a showing as to the expected effect, if any, of such proximate operation.

(h) Where simultaneous use of antennas or antenna structures is proposed, the following provisions shall apply:

(1) In cases where it is proposed to use a tower of a standard broadcast station as a supporting structure for a television broadcast antenna, an appropriate application for changes in the radiating system of the standard broadcast station must be filed by the licensee thereof. A formal application (FCC Form 301, or FCC Form 340 for a noncommercial educational station) will be required if the proposal involves substantial change in the physical height or radiation characteristics of the standard broadcast antennas; otherwise an informal application will be acceptable. (In case of doubt, an informal application (letter) together with complete engineering data should be submitted.) An application may be required for other classes of stations when the tower is to be used in connection with a television station.

(2) When the proposed television antenna is to be mounted on a tower in the vicinity of a standard broadcast directional array and it appears that the operation of the directional antenna system may be affected, an engineering study must be filed with the television application concerning the effect of the television antenna on the directional pattern. Readjustment and field intensity measurements of the standard broadcast station may be required following construction of the television antenna.

(i) The provisions of Part 17 of this chapter shall govern the construction, marking and lighting requirements of antenna structures used by television broadcast stations. In the event a common tower is used by two or more licensees or permittees for antenna and/or antenna supporting purposes, the licensee or permittee who is owner of the tower shall assume full responsibility for the installation and maintenance of any painting and/or lighting requirements. In the event of shared ownership, one licensee or permittee shall assume such responsibility and advise the Commission accordingly.

§ 73.686 Measurements for rule making purposes and upon request of the Commission.

(a) Except as provided for in § 73.612, television broadcast stations shall not be protected against any type of interference or propagation effect. Persons desiring to submit testimony, evidence, or data to the Commission for the purpose of showing that the technical standards contained in this subpart do not properly reflect any given types of interference or propagation effects may do so only in appropriate rule making proceedings to amend such technical standards. Persons making field intensity measurements for formal submission to the Commission in rule making proceedings, or making such measurements upon the request of the Commission, should comply with the procedure for making such measurements as outlined in the following paragraphs of this section.

(b) Measurements made to determine field intensities of television broadcast stations should be made with mobile equipment along roads which are as close and similar as possible to the radials showing topography which were submitted with the application for construction permit. Cluster and spot measurements may also be submitted, if accompanied by a complete showing of the procedures employed. Suitable measuring equipment and a continuous recording device must be employed, the chart of which is either directly driven from the speedometer of the automobile in which the equipment is mounted or so arranged that distances and identifying landmarks can be readily noted. The measuring equipment must be calibrated against recognized standards of field intensity and so constructed that it will maintain an acceptable accuracy of measurement while in motion or when stationary. The equipment should be so operated that the recorder chart can be calibrated directly in field intensity in order to facilitate analysis of the chart. The receiving antenna must be horizontally polarized and should be nondirectional.

(c) Mobile measurements should be made with a minimum chart speed of 3 inches per mile and preferably 5 or 6 inches per mile. Locations shall be noted on the recorder chart as frequently as necessary to fix definitely the relation between the measured field intensity and the location. The time constant of the equipment should be such as to permit adequate analysis of the charts, and the time constant employed shall be shown. Measurements should be made to a point on each radial well beyond the particular contour under investigation.

(d) While making field intensity measurements either the visual or the aural transmitter may be used. If the visual transmitter is used, it is recommended that a black picture be transmitted or that the transmitter be operated at black level without synchronization peaks. Operation at a power somewhat less than black level is permissible but too great a reduction in power is not recommended due to the difficulty of recording weak signals. In any event, an appropriate factor shall be used to convert the readings obtained to the field strength that would exist on synchronization peaks while operating at the authorized power.

(e) After the measurements are completed, the recorder chart should be divided into not less than 15 sections on each equivalent radial from the station. The field intensity in each section of the chart should be analyzed to determine the field intensity received 50 percent of the distance (median field) throughout the section, and this median field intensity associated with the corresponding sector of the radial. The field intensity figures must be corrected for a receiving antenna elevation of 30 feet and for any directional effects of the automobile and receiving antenna not otherwise compensated. This data should be plotted for each radial, using log-log coordinate paper with distance as the abscissa and field intensity as the ordinate. A smooth curve should be drawn through these points (of median fields for all sectors) and this curve used to determine the distance to the desired contour. The distances obtained for each radial may then be plotted on the map of predicted coverage or on polar coordinate paper (excluding water areas, etc.) to determine the service and interference areas of a station.

(f) In certain cases the Commission may desire more information or recordings and in these instances special instructions will be issued.

(g) Data obtained in conjunction with field intensity measurements shall be submitted to the Commission in affidavit form in triplicate, including the following:

(1) Map or maps showing the roads or points where measurements were made, the service and/or interference

areas determined by the prediction method and by the measurements, and any unusual terrain characteristics existing in these areas. The maps, preferably of a type showing topography in the area, should show the Grade A and Grade B field intensity contours.

(2) If a directional transmitting antenna is employed, a diagram on polar coordinate paper showing the predicted free space field intensity in millivolts per meter at 1 mile in all directions.

(3) A full description of the procedures and methods employed, including the type of equipment, the method of installation and operation, and calibration procedures.

(4) Complete data obtained during the survey, including calibration. (Only the original or one photostatic copy of the recording tapes, or representative samples, need be submitted.)

(5) Antenna system and power employed during the survey.

(6) Name, address, and qualifications of the engineer or engineers making the measurements.

§ 73.687 Transmitters and associated equipment.

(a) *Visual transmitter.* (1) For monochrome transmission only, the overall attenuation characteristics of the transmitter, measured in the antenna transmission line after the vestigial sideband filter (if used), shall not be greater than the following amounts below the ideal demodulated curve. (See Figure 11 of § 73.699.)

2 db at 0.5 Mc/s
2 db at 1.25 Mc/s
3 db at 2.0 Mc/s
6 db at 3.0 Mc/s
12 db at 3.5 Mc/s

The curve shall be substantially smooth between these specified points, exclusive of the region from 0.75 to 1.25 Mc/s. Output measurement shall be made with the transmitter operating into a dummy load of pure resistance and the demodulated voltage measured across this load. The ideal demodulated curve is that shown in Figure 11 of § 73.699. Stations operating on Channels 15–83 and employing a transmitter delivering maximum peak visual power output of 1 kilowatt or less will not be required to comply with the provisions of this subparagraph.

(2) For color transmission, the standard given by subparagraph (1) of this paragraph applies except as modified by the following: A sine wave of 3.58 Mc/s introduced at those terminals of the transmitter which are normally fed the composite color picture signal shall produce a radiated signal having an amplitude (as measured with a diode on the R.F. transmission line supplying power to the antenna) which is down 6±2 db with respect to a signal produced by a sine wave of 200 kc/s. In addition, between the modulating frequencies of 2.1 and 4.1 Mc/s, the amplitude of the radiated signal shall not vary by more than ±2 db from its value at 3.58 Mc/s. At the modulating frequency of 4.18 Mc/s, the amplitude of the radiated signal shall not be down more than 4 db below its value of 3.58 Mc/s. Stations operating on Channels 15–83 and employing a transmitter delivering maximum peak visual power output of 1 kilowatt or less are not required to comply with the provisions of this subparagraph.

(3) The field strength or voltage of the lower sideband, as radiated or dissipated and measured as described in subparagraph (4) of this paragraph, shall not be greater than −20 db for a modulating frequency of 1.25 Mc/s or greater and in addition, for color, shall not be greater than −42 db for a modulating frequency of 3.579545 Mc/s (the color subcarrier frequency). For both monochrome and color, the field strength or voltage of the upper sideband as radiated or dissipated and measured as described in subparagraph (4) of this paragraph shall not be greater than −20 db for a modulating frequency of 4.75 Mc/s or greater. For stations operating on Channels 15–83 and employing a transmitter delivering maximum peak visual power output of 1 kilowatt or less, the field strength or voltage of the upper and lower sidebands, as radiated or dissipated and measured as described in subparagraph (4) of this paragraph, shall depart from the visual amplitude characteristic (Figure 5a of § 73.699) by no more than the following amounts:

−2 db at 0.5 Mc/s below visual carrier frequency;
−2 db at 0.5 Mc/s above visual carrier frequency;
−2 db at 1.25 Mc/s above visual carrier frequency;
−3 db at 2.0 Mc/s above visual carrier frequency;
−6 db at 3.0 Mc/s above visual carrier frequency;
−12 db at 3.5 Mc/s above visual carrier frequency;
−8 db at 3.58 Mc/s above visual carrier frequency (for color transmission only).

The field strength or voltage of the upper and lower sidebands, as radiated or dissipated and measured as described in subparagraph (4) of this paragraph, shall not exceed a level of −20 db for a modulating frequency of 4.75 Mc/s or greater. If interference to the reception of other stations is caused by out-of-channel lower sideband emission, the technical requirements applicable to stations operating on Channels 2–13 shall be met.

(4) The attenuation characteristics of a visual transmitter shall be measured by application of a modulating signal to the transmitter input terminals in place of the normal composite television video signal. The signal applied shall be a composite signal composed of a synchronizing signal to establish peak output voltage plus a variable frequency sine wave voltage occupying the interval between synchronizing pulses. (The "synchronizing signal" referred to in this section means either a standard synchronizing wave form or any pulse that will properly set the peak.) The axis of the sine wave in the composite signal observed in the output monitor shall be maintained at an amplitude 0.5 of the voltage at synchronizing peaks. The amplitude of the sine wave input shall be held at a constant value. This constant value should be such that at no modulating frequency does the maximum excursion of the sine wave, observed in the composite output signal monitor, exceed the value 0.75 of peak output voltage. The amplitude of the 200 kilocycle sideband shall be measured and designated zero db as a basis for comparison. The modulation signal frequency shall then be varied over the desired range and the field strength or signal voltage of the corresponding sidebands measured. As an alternate method of measuring, in those cases in which the automatic d-c insertion can be replaced by manual control, the above characteristic may be taken by the use of a video sweep generator and without the use of pedestal synchronizing pulses. The d-c level shall be set for midcharacteristic operation.

(5) A sine wave, introduced at those terminals of the transmitter which are normally fed the composite color picture signal, shall produce a radiated signal having an envelope delay, relative to the average envelope delay between 0.05 and 0.20 Mc/s, of zero microseconds up to a frequency of 3.0 Mc/s; and then linearly decreasing to 4.18 Mc/s so as to be equal to −0.17 μsecs at 3.58 Mc/s. The tolerance on the envelope delay shall be ±0.05 μsecs at 3.58 Mc/s. The tolerance shall increase linearly to ±0.1 μsec down to 2.1 Mc/s, and remain at ±0.1 μsec down to 0.2 Mc/s. (Tolerances for the interval of 0.0 to 0.2 Mc/s are not specified at the present time.) The tolerance shall also increase linearly to ±0.1 μsec at 4.18 Mc/s.

(6) The radio frequency signal, as radiated, shall have an envelope as would be produced by a modulating signal in conformity with § 73.682 and Figure 6 or 7 of § 73.699, as modified by vestigial sideband operation specified in Figure 5 of § 73.699. For stations operating on Channels 15–83 the radio frequency signal as radiated, shall have an envelope as would be produced by a modulating signal in conformity with § 73.682 and Figures 6 or 7 of § 73.699.

(7) The time interval between the leading edges of successive horizontal pulses shall vary less than one half of one percent of the average interval. However, for color transmissions, § 73.682 (a) (5) and (6) shall be controlling.

(8) The rate of change of the frequency of recurrence of the leading edges of the horizontal synchronizing signals shall be not greater than 0.15 percent per second, the frequency to be determined by an averaging process carried out over a period of not less than 20, nor more than 100 lines, such lines not to include any portion of the blanking interval. However, for color transmissions, § 73.682(a) (5) and (6) shall be controlling.

(9) For color transmission the transfer characteristic (that is the relationship between the transmitter RF output and video signal input) shall be substantially linear between the reference black and reference white levels.

(b) *Aural transmitter.* (1) The transmitter shall operate satisfactorily with a frequency swing of ±25 kilocycles, which is considered 100 percent modulation. It is recommended, however, that the transmitter be designed to

operate satisfactorily with a frequency swing of at least ±40 kilocycles.

(2) The transmitting system (from input terminals of microphone pre-amplifier, through audio facilities at the studio, through telephone lines or other circuits between studio and transmitter, through audio facilities at the transmitter, and through the transmitter, but excluding equalizers for the correction of deficiencies in microphone response) shall be capable of transmitting a band of frequencies from 50 to 15,000 cycles. Pre-emphasis shall be employed in accordance with the impedance-frequency characteristic of a series inductance-resistance network having a time constant of 75 microseconds. (See Figure 12 of § 73.699.) The deviation of the system response from the standard pre-emphasis curve shall lie between two limits as shown by Figure 12 of § 73.699. The upper of these limits shall be uniform (no deviation) from 50 to 15,000 cycles. The lower limit shall be uniform from 100 to 7,500 cycles, and three db below the upper limit; from 100 to 50 cycles the lower limit shall fall from three db limit at a uniform rate of one db per octave (4 db at 50 cycles); from 7,500 to 15,000 cycles the lower limit shall fall from three db limit at a uniform rate of two db per octave (5 db at 15,000 cycles).

(3) At any modulating frequency between 50 and 15,000 cycles and at modulation percentages of 25 percent, 50 percent, and 100 percent, the combined audio frequency harmonics measured in the output of the system shall not exceed the root-mean-square values given in the following table:

Modulation frequency	*Distortion (percent)*
50 to 100 cycles	3.5
100 to 7,500 cycles	2.5
7,500 to 15,000 cycles	3.0

(i) Measurement shall be made employing 75 microsecond de-emphasis in the measuring equipment and 75 microsecond pre-emphasis in the transmitting equipment, and without compression if a compression amplifier is employed. Harmonics shall be included to 30 kc/s.

NOTE: Measurements of distortion using de-emphasis in the measuring equipment are not practical at the present time for the range 7,500 to 15,000 cycles for 25 and 50 percent modulation. Therefore, measurements should be made at 100 percent modulation and on at least the following modulating frequencies: 50, 100, 400, 1,000, 5,000, 10,000, and 15,000 cycles. At 25 and 50 percent modulation, measurements should be made on at least the following modulating frequencies: 50, 100, 400, 1,000 and 5,000 cycles.

(ii) It is recommended that none of the three main divisions of the system (transmitter, studio to transmitter circuit, and audio facilities) contribute over one-half of these percentages, since at some frequencies the total distortion may become the arithmetic sum of the distortions of the divisions.

(4) The transmitting system output noise level (frequency modulation) in the band of 50 to 15,000 cycles shall be at least 55 db below the audio frequency level representing a frequency swing of ±25 kc/s.

NOTE: For the purpose of these measurements, the visual transmitter should be inoperative since the exact amount of noise permissible from that source is not known at this time.

(5) The transmitting system output noise level (amplitude modulation) in the band of 50 to 15,000 cycles shall be at least 50 db below the level representing 100 percent amplitude modulation.

NOTE: For the purpose of these measurements, the visual transmitter should be inoperative since the exact amount of noise permissible from that source is not known at this time.

(6) If a limiting or compression amplifier is employed, precaution should be maintained in its connection in the circuit due to the use of pre-emphasis in the transmitting system.

(7) The percentage of modulation of the aural transmissions shall be maintained as high as possible consistent with good quality of transmission and good broadcast practice and in no case less than 85 percent nor more than 100 percent on peaks of frequent recurrence during any selection which normally is transmitted at the highest level of the program under consideration.

(c) *Requirements applicable to both visual and aural transmitters.* (1) Automatic means shall be provided in the visual transmitter to maintain the carrier frequency within ±one kilocycle of the authorized frequency; automatic means shall be provided in the aural transmitter to maintain the carrier frequency 4.5 megacycles above the actual visual carrier frequency within ±one kilocycle.

(2) The transmitters shall be equipped with suitable indicating instruments for the determination of operating power and with other instruments necessary for proper adjustment, operation, and maintenance of the equipment.

(3) Adequate provision shall be made for varying the output power of the transmitters to compensate for excessive variations in line voltage or for other factors affecting the output power.

(4) Adequate provisions shall be provided in all component parts to avoid overheating at the rated maximum output powers.

(d) *Construction.* In general, the transmitters shall be mounted either on racks and panels or in totally enclosed frames protected as required by article 810 of the National Electrical Code (section 8192(a), (b), and (c)), and as set forth below:

(1) Means shall be provided for making all tuning adjustments, requiring voltages in excess of 350 volts to be applied to the circuit, from the front of the panels with all access doors closed.

(2) Proper bleeder resistors or other automatic means shall be installed across all the capacitor banks to lower any voltage which may remain accessible with access door open to less than 350 volts within two seconds after the access door is opened.

(3) All plate supply and other high voltage equipment, including transformers, filters, rectifiers and motor generators, shall be protected so as to prevent injury to operating personnel.

(i) Commutator guards shall be provided on all high voltage rotating machinery. Coupling guards should be provided on motor generators.

(ii) Power equipment and control panels of the transmitters shall meet the above requirements (exposed 220-volt A. C. switching equipment on the front of the power control panels is not recommended but is not prohibited).

(iii) Power equipment located at a television broadcast station not directly associated with the transmitters (not purchased as part of same), such as power distribution panels, are not subject to the provisions of this subpart.

(4) The following provisions shall be applicable to metering equipment:

(i) All instruments having more than 1,000 volts potential to ground on the movement shall be protected by a cage or cover in addition to the regular case. (Some instruments are designed by the manufacturers to operate safely with voltages in excess of 1,000 volts on the movement. If it can be shown by the manufacturer's rating that the instrument will operate safely at the applied potential, additional protection is not necessary.)

(ii) In case the plate voltmeters are located on the low potential side of the multiplier resistors with the high potential terminal of the instruments at or less than 1,000 volts above ground, no protective case is required. However, it is good practice to protect voltmeters subject to more than 5,000 volts with suitable over-voltage protective devices across the instrument terminals in case the winding opens.

(iii) Transmission line meters and any other radio frequency instrument which may be necessary for the operator to read shall be so installed as to be read easily and accurately without the operator having to risk contact with circuits carrying high potential radio frequency energy.

(e) *Wiring and shielding.* (1) The transmitter panels or units shall be wired in accordance with standard practice, such as insulated leads properly cabled and supported, coaxial cables, or rigid bus bar properly insulated and protected.

(2) Wiring between units of the transmitters, with the exception of circuits carrying radio frequency energy or video energy, shall be installed in conduits or approved fiber or metal raceways to protect it from mechanical injury.

(3) Circuits carrying radio frequency or video energy between units shall be coaxial cables, two wire balanced lines, or properly shielded lines.

(4) All stages or units shall be adequately shielded and filtered to prevent interaction and radiation.

(5) The frequency and modulation monitors and associated radio frequency lines to the transmitter shall be thoroughly shielded.

(f) *Auxiliary transmitters.* Auxiliary transmitters may not exceed the power rating of the main transmitters. As a general guide, specifications for auxiliary transmitters should conform as much as possible to those of the main transmit-

ters. No requirements are set forth at this time.

(g) *Installation.* (1) The installation of transmitting equipment shall be made in suitable quarters.

(2) Suitable facilities shall be provided for the welfare and comfort of the operator.

(h) *Other technical data.* An accurate circuit diagram, as furnished by the manufacturer of the equipment, shall be retained at the transmitter location.

(i) *Operation.* (1) Spurious emissions, including radio frequency harmonics, shall be maintained at as low a level as the state of the art permits. As measured at the output terminals of the transmitter (including harmonic filters, if required) all emissions removed in frequency in excess of 3 Mc/s above or below the respective channel edge shall be attenuated no less than 60 db. below the visual transmitted power. (The 60 db. value for television transmitters specified in this rule should be considered as a temporary requirement which may be increased at a later date, especially when more higher-powered equipment is utilized. Stations should, therefore, give consideration to the installation of equipment with greater attenuation than 60 db.) In the event of interference caused to any service greater attenuation will be required.

(2) If a limiting or compression amplifier is used in conjunction with the aural transmitter, due operating precautions should be maintained because of pre-emphasis in the transmitting system.

(j) *Studio equipment.* Studio equipment shall be subject to all the above requirements where applicable, except as follows:

(1) If properly covered by an underwriter's certificate, it will be considered as satisfying safety requirements.

(2) Section 8192 of article 810 of the National Electrical Code shall apply for voltages only in excess of 500 volts.

(3) No specific requirements are made relative to the design and acoustical treatment of studios. However, the design of studios, particularly the main studio, shall be compatible with the required performance characteristics of television broadcast stations.

§ 73.688 Indicating instruments.

(a) Each television broadcast station shall be equipped with indicating instruments for measuring the direct plate voltage and current of the last radio stage of the visual and aural transmitters and the transmission line radio frequency current, voltage, or power of both transmitters; such instruments shall conform to the specifications therefor set forth in this subpart.

(b) The following requirements and specifications shall apply to indicating instruments used by television broadcast stations in compliance with paragraph (a) of this section:

(1) Length of scale shall be not less than $2\frac{3}{10}$ inches.

(2) Accuracy shall be at least 2 percent of the full scale reading.

(3) Scale shall have at least 40 divisions.

(4) Full scale reading shall be not greater than five times the minimum normal indication.

(5) No specifications are prescribed at this time regarding the peak indicating device required by § 73.689(b).

(c) Any required instrument, the accuracy of which is questionable, shall not be employed. Repairs and calibration of instruments shall be made by the manufacturer, or by an authorized instrument repair service of the manufacturer, or by some other properly qualified or equipped instrument repair service. In any case, the repaired instrument must be supplied with a certificate of calibration.

(d) [Reserved]

(e) The function of each instrument used in the equipment shall be clearly and permanently shown on the instrument itself or on the panel immediately adjacent thereto.

(f) In the event that any one of the indicating instruments required by paragraph (a) of this section becomes defective when no substitute which conforms with the required specifications is available, the station may be operated without the defective instrument pending its repair or replacement for a period not in excess of 60 days: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station to show the date and time the equipment was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the instrument is found to be defective and immediately after the repaired or replacement instrument has been installed and is functioning properly.

(3) If the defective instrument is a plate voltmeter or plate ammeter in the last radio stage, the operating power shall be maintained by means of the radio frequency transmission line meter.

(4) If conditions beyond the control of the licensee prevent the restoration of the meter to service within the above allowed period, informal request may be filed in accordance with § 1.549 of this chapter with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument.

§ 73.689 Operating power.

(a) *Determination*—(1) *Visual transmitter.* The operating power of the visual transmitter shall be determined at the output terminals of the transmitter, which includes any vestigial sideband and harmonic filters which may be used during normal operation. For this determination the average power output shall be measured while operating into a dummy load of substantially zero reactance and a resistance equal to the transmission line characteristic impedance. During this measurement the transmitter shall be modulated only by a standard synchronizing signal with blanking level set at 75 percent of peak amplitude as observed in an output monitor, and with this blanking level amplitude maintained throughout the time interval between synchronizing pulses. If electrical devices are used to determine the output power, such devices shall permit determination of this power to within an accuracy of ±5 percent of the power indicated by the full scale reading of the electrical indicating instrument of the device. If temperature and coolant flow indicating devices are used to determine the power output, such devices shall permit determination of this power to within an accuracy of 4 percent of measured average power output. The peak power output shall be the power so measured in the dummy load multiplied by the factor 1.68. During this measurement the direct plate voltage and current of the last radio stage and the transmission line meter shall be read and compared with similar readings taken with the dummy load replaced by the antenna. These readings shall be in substantial agreement.

(2) *Aural transmitter.* The operating power of the aural transmitter shall be determined by either the direct or indirect method.

(i) Using the direct method, the power shall be measured at the output terminals of the transmitter while operating into a dummy load of substantially zero reactance and a resistance equal to the transmission line characteristic impedance. The transmitter shall be unmodulated during this measurement. If electrical devices are used to determine the output power, such devices shall permit determination of this power to within an accuracy of ±5 percent of the power indicated by the full scale reading of the electrical indicating instrument of the device. If temperature and coolant flow indicating devices are used to determine the power output, such devices shall permit determination of this power to within an accuracy of 4 percent of measured average power output. During this measurement the direct plate voltage and current of the last radio stage and the transmission line meter shall be read and compared with similar readings taken with the dummy load replaced by the antenna. These readings shall be in substantial agreement.

(ii) Using the indirect method, the operating power is the product of the plate voltage (E_p) and the plate current (I_p) of the last radio stage, and an efficiency factor, F, as follows:

$$\text{Operating power} = E_p \times I_p \times F$$

(iii) The efficiency factor, F, shall originally be established by the transmitter manufacturer for each type of transmitter for which he submits data to the Commission, and shall be shown in the instruction books supplied to the customer with each transmitter. In the case of composite equipment, the factor F shall be furnished to the Commission by the applicant along with a statement of the basis used in determining such factor.

(b) *Maintenance*—(1) *Visual transmitter.* The peak power shall be monitored by a peak reading meter which reads proportional to voltage, current, or power at the output terminals of the

transmitter, this meter to be calibrated at intervals not exceeding 6 months. The meter shall cover, as a minimum, the range from 80 to 110 percent of authorized power and it shall be of sufficient accuracy and clarity of indication to permit maintaining the operating power within the prescribed tolerance or the meter shall be calibrated to read directly in power units. The operating power so monitored shall be maintained as near as practicable to the authorized power and shall not be less than 80 percent nor greater than 110 percent of authorized power except as indicated in subparagraph (3) of this paragraph.

(2) *Aural transmitter.* (i) The operating power shall be maintained as near as practicable to the authorized power and shall not be less than 80 percent nor greater than 110 percent of authorized power except as indicated in subparagraph (3) of this paragraph.

(ii) When determined by the direct method, the operating power of the transmitter shall be monitored using a transmission line meter which reads proportional to the voltage, current, or power at the output terminals of the transmitter, the meter to be calibrated at intervals not exceeding 6 months. The calibration shall cover, as a minimum, the range from 80 to 110 percent of authorized power and the meter shall provide clear indications which will permit maintaining the operating power within the prescribed tolerance or the meter shall be calibrated to read directly in power units.

(3) *Reduced power.* In the event it becomes technically impossible to operate with the authorized power, the station may be operated with reduced power for a period of 10 days or less without further authority of the Commission: *Provided,* That the Commission and the Engineer in Charge of the radio district in which the station is located shall be immediately notified in writing if the station is unable to maintain the minimum operating schedule (specified in § 73.651) with authorized power and shall be subsequently notified upon resumption of operation with authorized power.

MONITORING EQUIPMENT

§ 73.690 Frequency monitors.

(a) The licensee of each television broadcast station shall have in operation at the transmitter approved frequency monitors independent of the frequency control of the transmitters. (The requirement of this paragraph is postponed pending final decision in Docket 13854.)

NOTE: Approved frequency monitors are included on the Commission's "Radio Equipment List, Part A, Television Broadcast Equipment." Copies of this list are available for inspection at the Commission's office in Washington, D.C., and at each of its field offices.

(b) In the event the visual or aural frequency monitor becomes defective, the station may be operated without such equipment pending its repair or replacement for a period not in excess of 60 days without further authority of the Commission: *Provided,* That:

(1) Appropriate entries shall be made in the maintenance log of the station to show the date and time the equipment was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the equipment is found to be defective and immediately after the repaired or replacement equipment has been installed and is functioning properly.

(3) During the period when the station is operated without the visual or aural frequency monitor, the respective carrier frequency shall be compared with an external frequency source of known accuracy at sufficiently frequent intervals to insure that the frequency is maintained within the tolerance prescribed in § 73.687 (c) (1). An entry shall be made in the station log as to the method used and the results thereof.

(4) If conditions beyond the control of the licensee or permittee prevent the restoration of the monitor or monitoring equipment to service within the period specified above, an informal request in accordance with § 1.549 of this chapter may be filed with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument or equipment.

§ 73.691 Modulation monitors.

(a) The licensee of each television broadcast station shall have in operation at the transmitter an approved modulation monitor for the aural transmitter. There shall also be employed sufficient monitoring equipment for the visual signal to determine that the signal complies with the requirements of this subpart. (The requirement for use of type-approved aural modulation monitors is postponed pending final decision in Docket 13854.)

NOTE: Approved aural modulation monitors are included on the Commission's "Radio Equipment List, Part A, Television Broadcast Equipment." Copies of this list are available for inspection at the Commission's office in Washington, D. C., and at each of its field offices.

(b) In the event the visual monitoring equipment or the aural modulation monitor becomes defective, the station may be operated without such equipment pending its repair or replacement for a period not in excess of 60 days without further authority of the Commission: *Provided,* That:

(1) Appropriate entries shall be made in the operating log of the station to show the date and time the equipment was removed from and restored to service.

(2) The Engineer in Charge of the radio district in which the station is located shall be notified both immediately after the equipment is found to be defective and immediately after the repaired or replacement equipment has been installed and is functioning properly.

(3) During the period when the station is operated without the aural modulation monitor or the visual monitoring equipment, the licensee shall provide other suitable means for insuring that the aural modulation is maintained within the tolerance prescribed in § 73.687 (b) (7) and that the visual signal is maintained in accordance with the requirements of this subpart.

(4) If conditions beyond the control of the licensee or permittee prevent the restoration of the monitor or monitoring equipment to service within the period specified above, an informal request in accordance with § 1.549 of this chapter may be filed with the Engineer in Charge of the radio district in which the station is located for such additional time as may be required to complete repairs of the defective instrument or equipment.

§ 73.692 General requirements for type approval of frequency and modulation monitors.

(a) Any manufacturer desiring to submit a monitor for type approval shall supply the Commission with full specification details (two sworn copies) as well as the test data specified in §§ 73.693 and 73.694. If this information appears to meet the requirements of the rules, shipping instructions will be issued to the manufacturer. The shipping charges to and from the Laboratory at Laurel, Maryland, shall be paid for by the manufacturer. Approval of a monitor will only be given on the basis of the data obtained from the sample monitor submitted to the Commission for test.

(b) In approving a monitor upon the basis of the tests conducted by the Laboratory, the Commission merely recognizes that the type of monitor has the inherent capability of functioning in compliance with the rules, if properly constructed, maintained, and operated. The Commission realizes that the frequency monitor may have limited range over which the visual indicator will determine deviations. Accordingly, it is necessary that adjunct equipment be used to determine major deviations.

(c) Additional rules with respect to withdrawal of type approval, modification of type approved equipment and limitations on the findings upon which type approval is based are set forth in Part 2, Subpart F, of this chapter.

§ 73.693 Requirements for type approval of frequency monitors.

(a) The specifications that frequency monitors shall meet before they will be approved by the Commission are as follows:

(1) The monitors shall have an accuracy of better than 500 cycles for 30 days of VHF operation, or for 10 days of UHF operation, and under ordinary conditions (ambient temperature from 10° centigrade to 40° centigrade above zero, humidity from 10 percent to 95 percent relative humidity, power supply variations from 90 percent to 110 percent, and other conditions which may affect its accuracy) encountered in television broadcast stations throughout the United States.

(2) The range of the indicating device for the aural monitor shall be at least 3000 cycles below to 3000 cycles above the assigned center frequency. Alternatively, the aural monitor may use an indicating device with a similar scale to indicate the difference-frequency be-

tween the aural and visual carriers. The range of the indicating device for the visual monitor shall be at least 1500 cycles below to 1500 cycles above the assigned carrier frequency.

(3) The scale of the indicating device shall be calibrated in divisions of not more than 100 cycles.

(4) Means shall be provided for adjustment of the monitor indication to agree with an external standard.

(5) The monitors shall be capable of continuous operation and the circuits shall be such as to permit continuous monitoring of the transmitter carrier frequencies, and the difference-frequency between the visual and aural carriers if this method of measurement is used.

(6) Operation of the monitors shall have no adverse effect on the operation of either the aural or visual transmitters or the signals emitted therefrom and shall be independent of the frequency control of the transmitters.

(7) Means shall be provided for insuring power input level.

(8) General design, construction and operation shall be in accordance with good engineering practice.

(b) Tests to be made for approval of television broadcast frequency monitors. The manufacturer of a monitor shall submit data on the following at the time of requesting approval:

(1) Constancy of oscillator frequency, as measured daily for one month, or more.

(2) Constancy of oscillator frequency when subject to vibration tests which would correspond to the treatment received in shipping, handling and installing the instrument.

(3) Accuracy of reading of the frequency deviation instrument.

(4) Functioning of frequency adjustment device.

(5) Effects on frequency readings, of the changing of tubes, of voltage variations, and of variations of room temperature through a range from 10° to 40° C.

(6) Response of indicating instrument to small changes of frequency.

(7) General information on the effect of tilting or tipping or other tests to determine ability of equipment to withstand shipment.

(c) Various other tests may be made or required, such as effects of variation of input from the transmitter depending upon the character of the apparatus.

(d) Tests shall be conducted in such a manner as to approximate actual operating conditions as nearly as possible. The equipment shall be tested on the highest channel for which it is designed.

§ 73.694 Requirements for type approval of aural modulation monitors.

(a) The required aural modulation monitor may or may not be a part of the frequency monitor.

(b) The specifications that the aural modulation monitor shall meet before it will be approved by the Commission are as follows:

(1) Means shall be provided for indicating that the signal input to the modulation monitor is in the range required for proper operations.

(2) A modulation peak indicating device shall be provided that can be set at any pre-determined value from 50 to 120 percent modulation (±25 kc/s swing is defined as 100 percent modulation) and for either positive or negative swings (i.e., either above or below transmitter center frequency).

(3) A quasi-peak indicator with a meter having the characteristics given below shall be used with a circuit such that peaks of modulation of duration between 40 and 90 milliseconds are indicated to 90 percent of full value and the discharge rate adjusted so that the pointer returns from full reading to within 10 percent of zero within 500 to 800 milliseconds. A switch shall be provided so that this meter will read either positive or negative swings.

(4) When modulation of a magnitude necessary to produce a deflection equivalent to 100 percent modulation is suddenly applied and left on, the indicating instrument shall not deflect beyond 110 percent on the first passage of the 100 percent mark and shall have excursion from the final value of less than 1 percent after one second or more.

(5) The meter scale shall be similar in appearance to that of a standard VU meter. The scale length between 0 and 100 percent modulation markings shall be at least 2.3 inches. In addition to other markings a small marker for 133 percent modulation, designated as such, should be included for the purpose of testing the transmitter with 33.3 kc/s swing.

(6) The indicated reading in percentage shall be accurate within ±5 (based on 100 percent modulation) at any percentage of modulation up to 100.

(7) The frequency characteristic curve as measured at 50 percent modulation shall not depart from a straight line more than ±½ db from 50 to 15,000 cycles Distortion shall be kept to a minimum.

(8) The monitor shall not absorb appreciable power from the transmitter.

(9) Operation of the monitor shall have no adverse effect on the operation of the transmitter.

(10) General design, construction, and operation shall be in accordance with good engineering practice.

(c) Tests to be made for approval of television broadcast aural modulation monitors. The manufacturer of a monitor shall submit data on the following at the time of requesting approval:

(1) Audio frequency response of the monitor from 50 to 15,000 cycles in db from the response at 400 cycles.

(2) Distortion in the response.

(3) Input signal power required.

(4) Permissible tolerance on input signal power to keep the meter reading correct within 5 percent units.

(5) Ballistic characteristics of the monitor indicator.

(d) Various other tests may be made or required depending on the character of the apparatus.

(e) Tests shall be conducted in such a manner as to approximate actual operating conditions as nearly as possible. The equipment shall be tested on the highest channel for which it is designed.

§ 3.698 Tables

TABLE I

MINUTES TO DECIMAL PARTS OF A DEGREE

Minutes	Degrees	Minutes	Degrees
1	0.01667	31	0.51667
2	.03333	32	.53333
3	.05	33	.55
4	.06667	34	.56667
5	.08333	35	.58333
6	.10	36	.60
7	.11667	37	.61667
8	.13333	38	.63333
9	.15	39	.65
10	.16667	40	.66667
11	.18333	41	.68333
12	.20	42	.70
13	.21667	43	.71667
14	.23333	44	.73333
15	.25	45	.75
16	.26667	46	.76667
17	.28333	47	.78333
18	.30	48	.80
19	.31667	49	.81667
20	.33333	50	.83333
21	.35	51	.85
22	.36667	52	.86667
23	.38333	53	.88333
24	.40	54	.90
25	.41667	55	.91667
26	.43333	56	.93333
27	.45	57	.95
28	.46667	58	.96667
29	.48333	59	.98333
30	.50	60	1.00

SECONDS TO DECIMAL PARTS OF A DEGREE

Seconds	Degrees	Seconds	Degrees
1	0.00028	31	0.00861
2	.00056	32	.00889
3	.00083	33	.00917
4	.00111	34	.00944
5	.00139	35	.00972
6	.00167	36	.01
7	.00194	37	.01028
8	.00222	38	.01056
9	.0025	39	.01083
10	.00278	40	.01111
11	.00306	41	.01139
12	.00333	42	.01167
13	.00361	43	.01194
14	.00389	44	.01222
15	.00417	45	.0125
16	.00444	46	.01278
17	.00472	47	.01306
18	.005	48	.01333
19	.00528	49	.01361
20	.00556	50	.01389
21	.00583	51	.01417
22	.00611	52	.01444
23	.00639	53	.01472
24	.00667	54	.015
25	.00694	55	.01528
26	.00722	56	.01556
27	.0075	57	.01583
28	.00778	58	.01611
29	.00806	59	.01639
30	.00833	60	.01667

TABLE II

MILES PER DEGREE OF LATITUDE DIFFERENCE

Middle latitude	Statute miles	Middle latitude	Statute miles
° ′		° ′	
25 0	68.828	38 0	68.968
30	68.833	30	68.974
26 0	68.837	39 0	68.980
30	68.842	30	68.986
27 0	68.847	40 0	68.992
30	68.852	30	68.998
28 0	68.857	41 0	69.004
30	68.862	30	69.011
29 0	68.867	42 0	69.017
30	68.873	30	69.023
30 0	68.878	43 0	69.029
30	68.883	30	69.035
31 0	68.889	44 0	69.041
30	68.894	30	69.047
32 0	68.899	45 0	69.053
30	68.905	30	69.060
33 0	68.911	46 0	69.066
30	68.916	30	69.072
34 0	68.922	47 0	69.078
30	68.928	30	69.084
35 0	68.933	48 0	69.090
30	68.939	30	69.096
36 0	68.945	49 0	69.102
30	68.951	30	69.108
37 0	68.957	50 0	69.115
30	68.962		

TABLE III

Middle latitude degrees	Miles per degree of longitude difference (statute miles)									
	25	26	27	28	29	30	31	32	33	34
Minutes										
0	62.728	62.211	61.675	61.120	60.547	59.955	59.345	58.716	58.070	57.406
1	62.720	62.202	61.666	61.111	60.537	59.945	59.335	58.706	58.059	57.395
2	62.712	62.193	61.657	61.101	60.528	59.935	59.324	58.695	58.048	57.384
3	62.703	62.184	61.648	61.092	60.517	59.925	59.314	58.684	58.037	57.373
4	62.694	62.176	61.639	61.082	60.508	59.915	59.303	58.674	58.026	57.362
5	62.686	62.167	61.630	61.073	60.498	59.905	59.293	58.663	58.015	57.350
6	62.677	62.158	61.621	61.064	60.488	59.895	59.282	58.652	58.004	57.339
7	62.669	62.149	61.611	61.054	60.478	59.885	59.272	58.642	57.994	57.328
8	62.660	62.140	61.602	61.045	60.469	59.875	59.262	58.631	57.983	57.316
9	62.652	62.132	61.593	61.035	60.459	59.865	59.252	58.620	57.972	57.305
10	62.644	62.123	61.584	61.026	60.449	59.855	59.241	58.610	57.961	57.294
11	62.635	62.114	61.575	61.017	60.440	59.845	59.231	58.599	57.950	57.283
12	62.627	62.105	61.566	61.007	60.430	59.835	59.221	58.588	57.939	57.271
13	62.618	62.096	61.557	60.997	60.420	59.825	59.210	58.578	57.928	57.260
14	62.609	62.088	61.547	60.988	60.410	59.814	59.200	58.567	57.917	57.249
15	62.601	62.079	61.538	60.979	60.400	59.804	59.189	58.556	57.906	57.238
16	62.592	62.070	61.529	60.969	60.390	59.794	59.179	58.546	57.895	57.227
17	62.583	62.061	61.520	60.959	60.381	59.784	59.168	58.535	57.884	57.215
18	62.575	62.052	61.510	60.950	60.371	59.774	59.158	58.524	57.873	57.204
19	62.567	62.044	61.501	60.940	60.361	59.764	59.147	58.514	57.862	57.192
20	62.559	62.035	61.492	60.931	60.352	59.754	59.137	58.503	57.851	57.181
21	62.550	62.026	61.483	60.921	60.342	59.744	59.127	58.492	57.840	57.170
22	62.541	62.017	61.474	60.912	60.332	59.734	59.116	58.481	57.829	57.159
23	62.532	62.008	61.465	60.902	60.322	59.723	59.106	58.470	57.818	57.147
24	62.524	61.999	61.455	60.893	60.312	59.713	59.095	58.460	57.807	57.136
25	62.515	61.990	61.446	60.883	60.302	59.703	59.085	58.449	57.796	57.125
26	62.507	61.981	61.437	60.874	60.292	59.693	59.074	58.438	57.785	57.113
27	62.498	61.972	61.428	60.865	60.282	59.683	59.064	58.428	57.774	57.102
28	62.489	61.963	61.419	60.855	60.273	59.672	59.054	58.417	57.763	57.090
29	62.480	61.955	61.409	60.845	60.263	59.662	59.043	58.406	57.752	57.079
30	62.472	61.946	61.400	60.836	60.253	59.652	59.033	58.396	57.741	57.068
31	62.463	61.937	61.391	60.826	60.243	59.642	59.022	58.385	57.729	57.057
32	62.455	61.928	61.381	60.817	60.233	59.632	59.012	58.374	57.718	57.045
33	62.446	61.918	61.372	60.807	60.223	59.622	59.001	58.363	57.707	57.034
34	62.438	61.909	61.363	60.798	60.213	59.611	58.991	58.352	57.696	57.022
35	62.429	61.900	61.354	60.788	60.203	59.601	58.980	58.341	57.685	57.011
36	62.420	61.891	61.344	60.778	60.194	59.591	58.970	58.331	57.674	56.999
37	62.412	61.882	61.335	60.768	60.184	59.581	58.960	58.320	57.663	56.988
38	62.403	61.874	61.325	60.759	60.174	59.571	58.949	58.309	57.652	56.977
39	62.395	61.865	61.316	60.750	60.164	59.561	58.939	58.298	57.641	56.966
40	62.386	61.856	61.307	60.740	60.154	59.550	58.928	58.288	57.629	56.954
41	62.377	61.847	61.298	60.730	60.144	59.540	58.917	58.277	57.618	56.943
42	62.369	61.838	61.289	60.721	60.134	59.530	58.907	58.266	57.607	56.931
43	62.360	61.829	61.279	60.711	60.124	59.520	58.896	58.255	57.596	56.919
44	62.351	61.820	61.270	60.701	60.114	59.510	58.886	58.244	57.585	56.908
45	62.342	61.811	61.261	60.692	60.104	59.500	58.875	58.233	57.574	56.897
46	62.334	61.802	61.252	60.682	60.094	59.489	58.865	58.223	57.563	56.885
47	62.325	61.793	61.242	60.672	60.084	59.479	58.854	58.212	57.552	56.874
48	62.316	61.784	61.233	60.663	60.074	59.468	58.843	58.201	57.541	56.863
49	62.308	61.775	61.223	60.654	60.065	59.458	58.833	58.190	57.529	56.851
50	62.299	61.766	61.214	60.644	60.055	59.448	58.822	58.179	57.518	56.840
51	62.290	61.757	61.205	60.634	60.045	59.438	58.812	58.168	57.507	56.829
52	62.281	61.748	61.195	60.625	60.035	59.427	58.801	58.157	57.496	56.817
53	62.272	61.739	61.186	60.615	60.025	59.417	58.790	58.147	57.485	56.805
54	62.264	61.730	61.176	60.605	60.015	59.406	58.780	58.136	57.473	56.794
55	62.255	61.721	61.167	60.595	60.005	59.396	58.769	58.125	57.462	56.782
56	62.246	61.712	61.158	60.586	59.995	59.386	58.759	58.114	57.451	56.771
57	62.237	61.702	61.148	60.576	59.985	59.376	58.748	58.103	57.440	56.759
58	62.228	61.693	61.139	60.566	59.975	59.365	58.737	58.092	57.429	56.748
59	62.220	61.684	61.129	60.557	59.965	59.355	58.727	58.081	57.418	56.737

TABLE III—Continued

Middle latitude degrees	Miles per degree of longitude difference (statute miles)														
	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49
Minutes															
0	56.725	56.026	55.311	54.578	53.828	53.063	52.280	51.482	50.669	49.839	48.995	48.135	47.260	46.371	45.468
1	56.713	56.014	55.299	54.565	53.816	53.050	52.267	51.469	50.655	49.825	48.980	48.120	47.245	46.356	45.453
2	56.702	56.002	55.286	54.553	53.803	53.037	52.254	51.455	50.641	49.811	48.966	48.106	47.231	46.341	45.438
3	56.690	55.991	55.274	54.541	53.791	53.024	52.241	51.442	50.627	49.797	48.952	48.091	47.216	46.326	45.422
4	56.678	55.979	55.262	54.528	53.778	53.011	52.229	51.429	50.614	49.783	48.937	48.077	47.201	46.311	45.407
5	56.667	55.967	55.250	54.516	53.765	52.998	52.215	51.415	50.600	49.769	48.923	48.063	47.187	46.296	45.392
6	56.655	55.955	55.238	54.503	53.753	52.985	52.201	51.402	50.586	49.755	48.909	48.048	47.172	46.281	45.377
7	56.644	55.943	55.226	54.491	53.740	52.972	52.188	51.388	50.573	49.741	48.895	48.034	47.158	46.266	45.362
8	56.632	55.931	55.213	54.479	53.727	52.959	52.175	51.375	50.559	49.727	48.881	48.019	47.143	46.252	45.346
9	56.621	55.920	55.201	54.466	53.715	52.946	52.162	51.361	50.545	49.713	48.867	48.005	47.128	46.237	45.331
10	56.610	55.908	55.189	54.454	53.702	52.933	52.149	51.348	50.531	49.699	48.852	47.990	47.114	46.222	45.317
11	56.598	55.896	55.177	54.441	53.689	52.920	52.135	51.335	50.517	49.685	48.838	47.975	47.099	46.207	45.301
12	56.586	55.884	55.165	54.429	53.677	52.907	52.122	51.321	50.504	49.671	48.824	47.961	47.084	46.192	45.286
13	56.575	55.872	55.153	54.417	53.664	52.894	52.109	51.307	50.490	49.657	48.809	47.946	47.069	46.177	45.270
14	56.563	55.860	55.141	54.404	53.651	52.881	52.096	51.294	50.476	49.643	48.795	47.932	47.054	46.162	45.255
15	56.552	55.849	55.128	54.392	53.639	52.868	52.082	51.280	50.462	49.629	48.781	47.917	47.040	46.147	45.240
16	56.540	55.837	55.116	54.380	53.626	52.855	52.069	51.267	50.449	49.615	48.767	47.903	47.025	46.132	45.225
17	56.529	55.825	55.104	54.367	53.613	52.842	52.056	51.253	50.435	49.601	48.752	47.888	47.010	46.117	45.210
18	56.517	55.813	55.093	54.354	53.601	52.830	52.043	51.240	50.421	49.587	48.738	47.874	46.995	46.102	45.194
19	56.505	55.802	55.080	54.342	53.588	52.817	52.030	51.226	50.408	49.573	48.724	47.859	46.980	46.087	45.179
20	56.493	55.790	55.068	54.330	53.575	52.804	52.016	51.213	50.394	49.559	48.709	47.845	46.966	46.072	45.164
21	56.482	55.778	55.056	54.317	53.562	52.791	52.003	51.199	50.380	49.545	48.695	47.830	46.951	46.057	45.149
22	56.470	55.766	55.043	54.304	53.549	52.778	51.990	51.185	50.366	49.531	48.681	47.816	46.936	46.042	45.134
23	56.459	55.754	55.031	54.292	53.536	52.765	51.977	51.172	50.352	49.517	48.667	47.801	46.921	46.027	45.118
24	56.447	55.742	55.019	54.280	53.524	52.752	51.963	51.159	50.338	49.503	48.653	47.787	46.906	46.012	45.103
25	56.435	55.730	55.007	54.267	53.511	52.739	51.950	51.145	50.325	49.489	48.638	47.772	46.891	45.997	45.088
26	56.424	55.718	54.995	54.255	53.498	52.726	51.936	51.132	50.311	49.475	48.623	47.758	46.877	45.982	45.073
27	56.412	55.706	54.983	54.242	53.486	52.713	51.923	51.118	50.297	49.461	48.609	47.743	46.862	45.967	45.057
28	56.401	55.694	54.970	54.230	53.473	52.700	51.910	51.104	50.283	49.447	48.595	47.729	46.847	45.952	45.042
29	56.389	55.682	54.958	54.217	53.460	52.687	51.897	51.091	50.270	49.433	48.581	47.714	46.832	45.937	45.026
30	56.378	55.671	54.946	54.205	53.448	52.674	51.883	51.077	50.256	49.419	48.567	47.699	46.818	45.922	45.011
31	56.366	55.659	54.934	54.192	53.435	52.661	51.870	51.064	50.242	49.405	48.552	47.685	46.803	45.906	44.996
32	56.354	55.647	54.922	54.180	53.422	52.648	51.857	51.050	50.228	49.391	48.538	47.671	46.788	45.891	44.981
33	56.343	55.635	54.909	54.167	53.409	52.635	51.843	51.036	50.214	49.377	48.524	47.656	46.773	45.876	44.965
34	56.331	55.623	54.897	54.155	53.396	52.622	51.830	51.023	50.200	49.362	48.509	47.641	46.759	45.861	44.950
35	56.319	55.611	54.885	54.142	53.384	52.608	51.817	51.010	50.186	49.348	48.494	47.627	46.744	45.846	44.935
36	56.308	55.599	54.872	54.130	53.371	52.595	51.804	50.996	50.173	49.334	48.480	47.612	46.729	45.831	44.920
37	56.296	55.587	54.861	54.117	53.358	52.582	51.790	50.982	50.159	49.320	48.466	47.597	46.714	45.816	44.904
38	56.284	55.575	54.848	54.104	53.345	52.569	51.777	50.968	50.145	49.306	48.452	47.583	46.699	45.801	44.889
39	56.273	55.563	54.836	54.092	53.332	52.556	51.763	50.955	50.131	49.292	48.437	47.568	46.684	45.786	44.874
40	56.261	55.551	54.824	54.080	53.320	52.543	51.750	50.942	50.117	49.277	48.423	47.553	46.669	45.771	44.858
41	56.249	55.539	54.811	54.067	53.307	52.530	51.736	50.928	50.103	49.263	48.409	47.539	46.654	45.756	44.843
42	56.238	55.527	54.799	54.054	53.294	52.517	51.723	50.914	50.089	49.249	48.395	47.524	46.639	45.741	44.827
43	56.226	55.515	54.787	54.042	53.281	52.504	51.710	50.901	50.076	49.235	48.380	47.509	46.624	45.726	44.812
44	56.214	55.503	54.775	54.030	53.268	52.491	51.697	50.887	50.062	49.221	48.365	47.495	46.609	45.710	44.797
45	56.202	55.491	54.762	54.017	53.255	52.478	51.684	50.873	50.048	49.207	48.351	47.480	46.595	45.695	44.782
46	56.191	55.479	54.750	54.005	53.243	52.465	51.670	50.860	50.034	49.193	48.336	47.465	46.580	45.680	44.766
47	56.179	55.467	54.738	53.992	53.230	52.452	51.657	50.846	50.020	49.179	48.322	47.451	46.565	45.665	44.751
48	56.167	55.455	54.726	53.979	53.217	52.438	51.643	50.833	50.006	49.165	48.308	47.436	46.551	45.650	44.736
49	56.156	55.443	54.713	53.967	53.204	52.425	51.630	50.819	49.992	49.151	48.293	47.421	46.536	45.635	44.720
50	56.144	55.431	54.701	53.955	53.191	52.412	51.616	50.805	49.978	49.136	48.279	47.407	46.521	45.620	44.705
51	56.132	55.419	54.688	53.942	53.178	52.399	51.603	50.792	49.965	49.122	48.265	47.392	46.506	45.604	44.689
52	56.120	55.407	54.676	53.929	53.165	52.386	51.590	50.778	49.951	49.108	48.250	47.377	46.491	45.589	44.674
53	56.109	55.395	54.664	53.917	53.152	52.373	51.576	50.764	49.937	49.094	48.236	47.363	46.476	45.574	44.659
54	56.097	55.383	54.652	53.904	53.140	52.359	51.563	50.751	49.923	49.080	48.222	47.348	46.461	45.559	44.643
55	56.085	55.371	54.639	53.891	53.127	52.346	51.549	50.737	49.909	49.066	48.207	47.333	46.446	45.544	44.628
56	56.073	55.359	54.627	53.879	53.114	52.333	51.536	50.723	49.895	49.051	48.192	47.319	46.431	45.529	44.613
57	56.061	55.347	54.614	53.867	53.101	52.320	51.523	50.710	49.881	49.037	48.178	47.304	46.416	45.514	44.597
58	56.050	55.335	54.602	53.854	53.088	52.307	51.509	50.696	49.867	49.023	48.163	47.289	46.401	45.499	44.582
59	56.038	55.323	54.590	53.841	53.075	52.294	51.496	50.682	49.853	49.009	48.149	47.275	46.386	45.484	44.566

TABLE IV

(1) Channel	(2) 20 miles (IF beat)	(3) 20 miles (intermodulation)	(4) 55 miles (adjacent channel)	(5) 60 miles (oscillator)	(6) 60 miles (sound image)	(7) 75 miles (picture image)
14	22	16–19	15	21	28	29
15	23	17–20	14, 16	22	29	30
16	24	14, 18–21	15, 17	23	30	31
17	25	14–15, 19–22	16, 18	24	31	32
18	26	14–16, 20–23	17, 19	25	32	33
19	27	14–17, 21–24	18, 20	26	33	34
20	28	15–18, 22–25	19, 21	27	34	35
21	29	16–19, 23–26	20, 22	28, 14	35	36
22	30, 14	17–20, 24–27	21, 23	29, 15	36	37
23	31, 15	18–21, 25–28	22, 24	30, 16	37	38
24	32, 16	19–22, 26–29	23, 25	31, 17	38	39
25	33, 17	20–23, 27–30	24, 26	32, 18	39	40
26	34, 18	21–24, 28–31	25, 27	33, 19	40	41
27	35, 19	22–25, 29–32	26, 28	34, 20	41	42
28	36, 20	23–26, 30–33	27, 29	35, 21	42, 14	43
29	37, 21	24–27, 31–34	28, 30	36, 22	43, 15	44, 14
30	38, 22	25–28, 32–35	29, 31	37, 23	44, 16	45, 15
31	39, 23	26–29, 33–36	30, 32	38, 24	45, 17	46, 16
32	40, 24	27–30, 34–37	31, 33	39, 25	46, 18	47, 17
33	41, 25	28–31, 35–38	32, 34	40, 26	47, 19	48, 18
34	42, 26	29–32, 36–39	33, 35	41, 27	48, 20	49, 19
35	43, 27	30–33, 37–40	34, 36	42, 28	49, 21	50, 20
36	44, 28	31–34, 38–41	35, 37	43, 29	50, 22	51, 21
37	45, 29	32–35, 39–42	36, 38	44, 30	51, 23	52, 22
38	46, 30	33–36, 40–43	37, 39	45, 31	52, 24	53, 23
39	47, 31	34–37, 41–44	38, 40	46, 32	53, 25	54, 24
40	48, 32	35–38, 42–45	39, 41	47, 33	54, 26	55, 25
41	49, 33	36–39, 43–46	40, 42	48, 34	55, 27	56, 26
42	50, 34	37–40, 44–47	41, 43	49, 35	56, 28	57, 27
43	51, 35	38–41, 45–48	42, 44	50, 36	57, 29	58, 28
44	52, 36	39–42, 46–49	43, 45	51, 37	58, 30	59, 29
45	53, 37	40–43, 47–50	44, 46	52, 38	59, 31	60, 30
46	54, 38	41–44, 48–51	45, 47	53, 39	60, 32	61, 31
47	55, 39	42–45, 49–52	46, 48	54, 40	61, 33	62, 32
48	56, 40	43–46, 50–53	47, 49	55, 41	62, 34	63, 33
49	57, 41	44–47, 51–54	48, 50	56, 42	63, 35	64, 34
50	58, 42	45–48, 52–55	49, 51	57, 43	64, 36	65, 35
51	59, 43	46–49, 53–56	50, 52	58, 44	65, 37	66, 36
52	60, 44	47–50, 54–57	51, 53	59, 45	66, 38	67, 37
53	61, 45	48–51, 55–58	52, 54	60, 46	67, 39	68, 38
54	62, 46	49–52, 56–59	53, 55	61, 47	68, 40	69, 39
55	63, 47	50–53, 57–60	54, 56	62, 48	69, 41	70, 40
56	64, 48	51–54, 58–61	55, 57	63, 49	70, 42	71, 41
57	65, 49	52–55, 59–62	56, 58	64, 50	71, 43	72, 42
58	66, 50	53–56, 60–63	57, 59	65, 51	72, 44	73 43
59	67, 51	54–57, 61–64	58, 60	66, 52	73, 45	74 44
60	68, 52	55–58, 62–65	59, 61	67, 53	74, 46	75, 45
61	69, 53	56–59, 63–66	60, 62	68, 54	75, 47	76, 46
62	70, 54	57–60, 64–67	61, 63	69, 55	76, 48	77, 47
63	71, 55	58–61, 65–68	62, 64	70, 56	77, 49	78, 48
64	72, 56	59–62, 66–69	63, 65	71, 57	78, 50	79, 49
65	73, 57	60–63, 67–70	64, 66	72, 58	79, 51	80, 50
66	74, 58	61–64, 68–71	65, 67	73, 59	80, 52	81, 51
67	75, 59	62–65, 69–72	66, 68	74, 60	81, 53	82, 52
68	76, 60	63–66, 70–73	67, 69	75, 61	82, 54	83, 53
69	77, 61	64–67, 71–74	68, 70	76, 62	83, 55	54
70	78, 62	65–68, 72–75	69, 71	77, 63	56	55
71	79, 63	66–69, 73–76	70, 72	78, 64	57	56
72	80, 64	67–70, 74–77	71, 73	79, 65	58	57
73	81, 65	68–71, 75–78	72, 74	80, 66	59	58
74	82, 66	69–72, 76–79	73, 75	81, 67	60	59
75	83, 67	70–73, 77–80	74, 76	82, 68	61	60
76	68	71–74, 78–81	75, 77	83, 69	62	61
77	69	72–75, 79–82	76, 78	70	63	62
78	70	73–76, 80–83	77, 79	71	64	63
79	71	74–77, 81–83	78, 80	72	65	64
80	72	75–78, 82–83	79, 81	73	66	65
81	73	76–79, 83	80, 82	74	67	66
82	74	77–80	81, 83	75	68	67
83	75	78–81	82	76	69	68

NOTE: The parenthetical reference beneath the mileage figures in columns 2 through 7, inclusive, indicate, in abbreviated form, the bases for the required mileage separations. For a discussion of these bases, see the "Sixth Report and Order" of the Commission (FCC 52–294; 17 F.R. 3905, May 2, 1952). The hyphenated numbers listed in column (3) are both inclusive.

§ 73.699 **Engineering charts.**

This section consists of the following Figures 1–5, 5a, and 6–12, and "slider for use with Figures 9 and 10."


NOTE: The charts as reproduced herein, due to their small scale, are not to be used in connection with material submitted to the F.C.C.



Figure 1

Feb. 1954

ZONE I.



ZONE III

Figure 2

MARCH 1957




Figure 4




Figure 3




FIGURE 5.





FIGURE 5(a).

TELEVISION SYNCHRONIZING WAVEFORM
FOR COLOR TRANSMISSION




NOTES

1. H = Time from start of one line to start of next line.
2. V = Time from start of one field to start of next field.
3. Leading and trailing edges of vertical blanking should be complete in less than 0.1H.
4. Leading and trailing slopes of horizontal blanking must be steep enough to preserve minimum and maximum values of (x+y) and (z) under all conditions of picture content.
5. * Dimensions marked with asterisk indicate that tolerances given are permitted only for long time variations and not for successive cycles.
6. Equalizing pulse area shall be between 0.45 and 0.5 of area of a horizontal sync pulse.
7. Color burst follows each horizontal pulse, but is omitted following the equalizing pulses and during the broad vertical pulses.
8. Color bursts to be omitted during monochrome transmission.
9. The burst frequency shall be 3.579545 mc. The tolerance on the frequency shall be ±10 cycles with a maximum rate of change of frequency not to exceed 1/10 cycle per second per second.
10. The horizontal scanning frequency shall be 2/455 times the burst frequency.
11. The dimensions specified for the burst determine the times of starting and stopping the burst, but not its phase. The color burst consists of amplitude modulation of a continuous sine wave.
12. Dimension "P" represents the peak excursion of the luminance signal from blanking level, but does not include the chrominance signal. Dimension "S" is the sync amplitude above blanking level. Dimension "C" is the peak carrier amplitude.
13. Start of Field 1 is defined by a whole line between first equalizing pulse and preceding H sync pulses.
14. Start of Field 2 is defined by a half line between first equalizing pulse and preceding H sync pulses.
15. Field 1 line numbers start with first equalizing pulse in Field 1.
16. Field 2 line numbers start with second equalizing pulse in Field 2.
17. Refer to text for further explanations and tolerances.

FIGURE 6

TELEVISION SYNCHRONIZING WAVEFORM
FOR MONOCHROME TRANSMISSION ONLY



NOTES

1. H = Time from start of one line to start of next line.
2. V = Time from start of one field to start of next field.
3. Leading and trailing edges of vertical blanking should be complete in less than 0.1H.
4. Leading and trailing slopes of horizontal blanking must be steep enough to preserve minimum and maximum values of (x+y) and (z) under all conditions of picture content.
5. * Dimensions marked with asterisk indicate that tolerances given are permitted only for long time variations and not for successive cycles.
6. Equalizing pulse area shall be between 0.45 and 0.5 of area of a horizontal sync pulse.
7. Start of Field 1 is defined by a whole line between first equalizing pulse and preceding H sync pulses.
8. Start of Field 2 is defined by a half line between first equalizing pulse and preceding H sync pulses.
9. Field 1 line numbers start with first equalizing pulse in Field 1.
10. Field 2 line numbers start with second equalizing pulse in Field 2.
11. Refer to text for further explanations and tolerances.

FIGURE 7






FIGURE 8.



Television Channels 2–6, 14–83. **Estimated field strength exceeded at 50 percent of the potential receiver locations for at least 50 percent of the time at a receiving antenna height of 30 feet.**


FIGURE 9.



Television Channels 7–13. Estimated field strength exceeded at 50 percent of the potential receiver locations for at least 50 percent of the time at a receiving antenna height of 30 feet.

FIGURE 10.

Sliding scale for use with Figures 9 and 10.



ASSUMED IDEAL DETECTOR OUTPUT




FIGURE 11.




FIGURE 12.

Subpart F—International Broadcast Stations

Definitions and Allocation of Facilities

§ 73.701 Definitions.

The following definitions apply to terminology employed in this subpart:

(a) *International broadcast station.* A broadcasting station employing frequencies allocated to the broadcasting service between 5950 and 26100 kc/s, whose transmissions are intended to be received directly by the general public in foreign countries.

(b) *Frequency-hour.* One frequency used for one hour.

(c) *Day.* Any twenty-four hour period beginning 0000 EST and ending 2400 EST.

(d) *Sunspot number.* The predicted 12-month running average of the number of sunspots for any month as indicated in the National Bureau of Standards CRPL Series D publications.

(e) *Vernal equinox season.* That period of any calendar year starting at 0000 EST on 1 February and ending at 2400 EST on 30 April.

(f) *Summer season.* That period of any calendar year starting at 0000 EST on 1 May and ending at 2400 EST on 31 July.

(g) *Autumnal equinox season.* That period of any calendar year starting at 0000 EST on 1 August and ending at 2400 EST on 31 October.

(h) *Winter season.* That period of any calendar year starting at 0000 EST on 1 November and ending at 2400 EST on 31 January.

(i) *Maximum usable frequency (MUF).* The highest frequency which is returned to the surface of the earth for a particular path and time of day on 50 percent of the days of the reference month.

(j) *Optimum working frequency (OWF).* The frequency which is returned to the surface of the earth for a particular path and time of day on 90 percent of the days of the reference month.

(k) *Reference month.* The middle month of any season listed in § 73.704 "Daily Frequency Hour Availability Table."

(l) *Delivered median field intensity or field intensity.* The field intensity incident upon the target area expressed in microvolts per meter, or decibels above one microvolt per meter, which is exceeded by the hourly median value on 50 percent of the days of the reference month.

(m) *Target area.* Geographic area in which the reception of particular programs is specifically intended and in which adequate broadcast coverage is contemplated.

(n) *Contract operation.* Any non-Government operation of an international broadcast station pursuant to a contract with an agency of the United States Government and subject to Governmental control as to program content, target areas to be covered, and time of broadcast.

(o) *Private operation.* Any non-Government operation of an International Broadcast station which is not contract operation.

§ 73.702 Assignment and use of frequencies.

NOTE: Paragraphs (c) through (k) do not apply to stations when engaged in contract operations as defined in § 73.701.

(a) Frequencies will be assigned by the Commission from time to time and in accordance with the provisions of this section, to authorized international broadcast stations for use at specified hours and for transmission to specified target areas. Licensees may request the assignment of specific frequencies for transmission during given hours of operation to specified target areas by filing informal requests in triplicate with the Commission no less than 15 days prior to the start of a new season. Such requests will be honored to the extent that interference and propagation conditions permit and that they are otherwise in accordance with the provisions of this section. Requests for changes in frequency or hour assignments at other times during the year or which are received less than 15 days before the start of a new season will be processed as rapidly as practical. All specific frequency authorizations will be made only on the express understanding that they are subject to immediate cancellation or change without hearing whenever the Commission determines that interference or propagation conditions so require and that each assignment of frequency hours for a given season is unique unto itself and not subject to renewal, with the result that completely new assignments must be secured for the forthcoming season. Where a station is simultaneously engaged in both private and contract broadcasting, as defined in § 73.701, it must receive separate frequency hour authorizations for each of these operations.

(b) Any foreign standard target areas shown in Figure 1 of § 73.792 may be specified by the licensee, in which case field intensity calculations should be based on the transmission path between the corresponding reference points listed in § 73.703. In the event a broadcast is to be directed to more than one target area in the same region, the *primary* target area should be specified and the reasons for selecting that particular target area given, with special reference to the nature and special suitability, if any, of the programming proposed. Field intensity calculations should be based on the transmission path to the standard reference point in § 73.703 for the primary target area. In the event a licensee wishes to specify target areas other than those shown in Figure 1 of § 73.792, adequate justification must be given to show that the use of standard target areas is inappropriate, with special reference given to any specialized programming proposed which appears suitable only for the nonstandard target areas designated. When nonstandard target areas are proposed, special reference points must be specified (by geographical coordinates) and reasonably chosen so as to insure complete and adequate coverage of the target areas.

(c) Frequencies assigned by the Commission will be within the following bands:

	Kilocycles
Band A	5950–6200
Band B	9500–9775
Band C	11700–11975
Band D	15100–15450
Band E	17700–17900
Band F	21450–21750
Band G	25600–26100

(d) No frequency will be assigned which would provide a Delivered Median Field Intensity, either measured or calculated, of less than 150 uv/m—50 percent or 43.5 decibels above one uv/m at the distant foreign target area. (This value of Delivered Median Field Intensity is expected to provide protection against atmospheric and industrial noise for at least 90 percent of each hour during 90 percent of the days of the month.) With each request for frequency assignment, licensees must submit computations which adequately show that this requirement would be met.

NOTE: Standard OWF propagation curves and Delivered Median Field Intensity curves for the various hours and seasons throughout the eleven year sunspot cycle have been computed for transmission paths between standard reference points listed in § 73.703 for the standard target areas shown in Figure 1 of § 73.792. These curves, which were developed and used at the Mexico City High Frequency Broadcasting Conference (1948-1949), are available at the Commission's Washington offices and may be used in calculating the propagation data which licensees are required to provide under these Rules. The methods used in computing these data are described in Chapter 7, paragraph 7.7 of the National Bureau of Standards Circular 462. In lieu of that data, and in all cases where nonstandard target areas are specified as provided in paragraph (b) of this section, licensees must develop their own propagation curves for use in computing values of OWF and Delivered Median Field Intensity for the particular transmission paths involved. In doing so, use may be made of the published propagation data of the National Bureau of Standards known as CRPL Series D, "Basic Radio Propagation Predictions", published monthly in conjunction with National Bureau of Standards Circular 465, "Instructions for the use of Basic Radio Propagation Predictions." These publications are available from the Superintendent of Documents, Washington 25, D. C. A typical example of a computation for a transmission path between standard target areas is from New York (Area 8) to Buenos Aires (Area 15). The Delivered Median Field Intensity for the equinox season, sunspot 5, and for the 6 Mc band for the hours 0200 to 0400 GMT is indicated by the appropriate propagation curve as 24 decibels above one microvolt per meter for 1 kw radiated power. The transmitter power output of 20 decibels (100 kw) is added. The transmitting antenna gain of 12 decibels is added. The resultant total (56 decibels) exceeds the level of 43.5 decibels required to deliver a median field intensity of 150 uv/m at the distant target area.

(e) Frequencies assigned will be as near as possible to the Optimum Working Frequency. In no case will they exceed the Maximum Usable Frequency for more than a total of 15 minutes during any period of transmission. With each request for frequency assignment, licensees must submit computations which adequately show that this requirement would be met. (See note in paragraph

(d) of this section regarding methods for computation.)

(f) Not more than one frequency will be authorized for use at any one time for any one program transmission except in instances where a program is intended for reception in more than one target area and the intended target areas cannot be served by a single frequency.

(g) No authorization for use of a particular frequency will be issued which fails to provide a minimum co-channel Delivered Median Field Intensity protection ratio of 40 db to the transmissions of other broadcasting stations at the reference point in the target area being served by such stations which, in the opinion of the Commission, have priority of assignment.

(h) Authorization for use of a particular frequency will not be issued which does not provide a minimum adjacent channel Delivered Median Field Intensity protection ratio of 11 db to the transmissions of other international broadcasting stations at the reference points in the target areas being served by such stations which, in the opinion of the Commission, have priority of assignment.

(i) Any frequency authorized to an international broadcast station shall also be available for assignment to other international broadcast stations.

(j) Not more than one frequency shall be used simultaneously under the same authorization and call letter and equipment installation number designation.

(k) Subject to all other pertinent provisions of this subpart, the total maximum number of frequency-hours which will be authorized to all licensees of private international broadcast stations for private operation combined in any frequency band for any pertinent season during any one day will be those in § 73.704 less the number of frequency-hours in these bands scheduled for use by both (1) government international broadcasting stations, and (2) international broadcast stations licensed by the Commission to use frequencies in these bands for contract operations.

(l) In the event the total number of frequency hours in any band scheduled for both (1) government international broadcasting stations, and (2) international broadcast stations licensed by the Commission to use frequencies in these bands for contract operations equals or exceeds 75 percent of the frequency hour figures given in § 73.704, the maximum number of frequency-hours which will be authorized to all licensees of international broadcast stations for private operation in any frequency band for any pertinent season during any one day will be 25 percent of the frequency hours shown in § 73.704.

(m) If the requests for international broadcasting frequency-hours for private operation in any band or bands exceed those available under the terms of these Rules, in the absence of any voluntary agreement for reduction of frequency-hours requested, the Commission will designate all requests for frequency-hours in the band or bands in question for hearing. Pending such hearing the Commission will temporarily assign the available frequency-hours equally among the several applicants: *Provided, however,* That with respect to such temporary allocation:

(1) An existing license shall not, to the extent such frequency hours are available, receive less than the number of frequency-hours utilized during the preceding season or requested for the forthcoming season, whichever is lesser.

(2) Where the number of frequency-hours available for private international broadcasting during a forthcoming season are insufficient to permit existing licensees to secure a temporary allocation equal to that previously utilized or requested, whichever is lesser, the allocation shall be pro-rated among such persons in a manner which will give them a share of the available frequency-hours proportionate to that utilized in the preceding season.

(3) In any event, where an applicant's share of the available frequency hours would be more than requested, the surplus shall be divided among the remaining applicants in the manner herein prescribed.

§ 73.703 Latitude and longitude of areas used for field intensity calculations.

Area No.	Latitude degrees	Longitude degrees
1	65 N.	150 W.
2	60 N.	125 W.
3	60 N.	100 W.
4	60 N.	80 W.
5	70 N.	40 W.
6	40 N.	120 W.
7	40 N.	100 W.
8	40 N.	80 W.
9	50 N.	60 W.
10	20 N.	100 W.
11	10 N.	80 W.
12	10 S.	70 W.
13	10 S.	50 W.
14	30 S.	60 W.
15	25 S.	50 W.
16	45 S.	70 W.
17	65 N.	20 W.
18	65 N.	15 E.
19	65 N.	40 E.
20	70 N.	60 E.
21	70 N.	80 E.
22	70 N.	100 E.
23	70 N.	120 E.
24	65 N.	140 E.
25	65 N.	160 E.
26	65 N.	180 E.
27	50 N.	0°
28	50 N.	20 E.
29	50 N.	40 E.
30	50 N.	60 E.
31	50 N.	80 E.
32	50 N.	100 E.
33	50 N.	120 E.
34	55 N.	140 E.
35	55 N.	160 E.
36	40 N.	25 W.
37	30 N.	0°
38	30 N.	20 E.
39	30 N.	40 E.
40	30 N.	60 E.
41	20 N.	80 E.
42	40 N.	85 E.
43	35 N.	100 E.
44	30 N.	120 E.
45	35 N.	140 E.
46	10 N.	5 W.
47	10 N.	20 E.
48	10 N.	40 E.
49	15 N.	100 E.
50	10 N.	120 E.
51	0°	140 E.
52	10 S.	20 E.
53	10 S.	40 E.
54	5 S.	105 E.
55	15 S.	140 E.
56	20 S.	165 E.
57	30 S.	25 E.
58	25 S.	120 E.
59	35 S.	150 E.
60	40 S.	170 E.
61	20 N.	160 W.
62	20 S.	170 W.
63	20 S.	150 W.
64	15 N.	145 E.
65	10 N.	170 E.

§ 73.704 Daily frequency hour availability table.

Band	Season	Sunspot Numbers								
		0–20	20–35	35–50	50–65	65–80	80–95	95–110	110–125	125–140
Mc/s										
6	June	0	0	0	0	0	0	0	0	0
	March–September	29	21	14	7	0	0	0	0	0
	December	45	47	48	49	50	------	------	------	32
9	June	34	30	27	24	21	16	11	5	2
	March–September	52	42	36	31	27	23	19	12	10
	December	54	50	47	44	42	39	36	33	32
11	June	53	50	48	46	45	39	31	23	14
	March–September	47	50	52	54	55	49	40	31	24
	December	31	34	36	38	39	34	30	26	22
15	June	84	88	91	94	96	87	79	69	58
	March–September	49	54	58	61	64	47	33	21	7
	December	35	35	35	35	35	33	31	29	27
17	June	23	32	40	47	53	59	66	75	84
	March–September	23	22	22	21	20	24	29	34	39
	December	14	18	21	23	25	23	20	17	16
21	June	2	9	14	18	22	39	52	68	80
	March–September	0	9	16	22	27	36	45	56	65
	December	6	11	15	18	21	29	36	47	53
26	------	(1)	(1)	(1)	(1)	(1)	(1)	(1)	(1)	(1)
Totals	June	196	209	220	229	237	240	239	239	238
	March–September	200	198	196	193	179	166	154	145	
	December	185	195	202	207	212	158	153	152	181

[1] No limit.

Administrative Procedure

§ 73.710 Cross reference.

See Subpart D of Part 1 of this chapter, for general requirements as to applications, filing of applications, and description of application forms, other forms and information to be filed with the Commission, the manner in which applications are processed, and provisions applying to action on applications. See § 1.1111 of Subpart G of that part for the fees to be paid in connection with applications for facilities in the service covered in this subpart.

§ 73.711 Application for international broadcast stations.

(a) If the application is for a construction permit or for modification of an existing authorization, FCC Form 309 shall be filed; if for a license, FCC Form 310 shall be filed; if for a renewal of license, FCC Form 311 shall be filed.

NOTE: Until these forms are revised, information required by these Rules and not required by the forms shall be submitted as a supplement to the application and will be considered a part thereof.

(b) Authorizations issued to international broadcast stations by the Commission will not specify the frequencies or hours of use, but will be authorizations to permit the construction or use of a particular transmitting equipment combination and related antenna systems for international broadcasting.

NOTE: Requests for the use of frequencies and frequency hours for transmissions to specific target areas should be submitted separately as provided in § 73.702.

(c) In the case of applications for authorizations to permit contract operations, as defined in § 73.701(n), the contracting agency and contract number should be indicated for each operation.

§ 73.712 Notification of filing of applications.

In order to minimize harmful interference at the National Radio Astronomy Observatory site located at Green Bank, Pocahontas County, West Virginia, and at the Naval Radio Research Observatory at Sugar Grove, Pendleton County, West Virginia, an applicant for authority to construct a new international broadcast station or for authority to make changes in the frequency, power, antenna height, or antenna directivity of an existing station within the area bounded by 39°15′ N on the north, 78°30′ W on the east, 37°30′ N on the south, and 80°30′ W on the west shall, at the time of filing such application with the Commission, simultaneously notify the Director, National Radio Astronomy Observatory, P.O. Box #2, Green Bank, West Virginia, 24944, in writing, of the technical particulars of the proposed station. Such notification shall include the geographical coordinates of the antenna, antenna height, antenna directivity if any, proposed frequency, type of emission, and power. In addition, the applicant shall indicate in his application to the Commission the date notification was made to the Observatory. After receipt of such applications, the Commission will allow a period of twenty (20) days for comments or objections in response to the notifications indicated. If an objection to the proposed operation is received during the twenty-day period from the National Radio Astronomy Observatory for itself or on behalf of the Naval Radio Research Observatory, the Commission will consider all aspects of the problem and take whatever action is deemed appropriate.

§ 73.716 Equipment tests.

(a) During the process of construction of an international broadcast station, the permittee after notifying the Commission and Engineer in Charge of the radio district in which the station is located may, without further authority of the Commission, conduct equipment tests for the purpose of such adjustments and measurements as may be necessary to assure compliance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations. No programming shall be conducted during equipment tests.

(b) The Commission may notify the permittee to conduct no tests or may cancel, suspend, or change the date for the beginning of equipment tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Equipment tests may be continued so long as the construction permit shall remain valid.

(d) Inspection of a station will ordinarily be required during the equipment test period. After construction and after adjustments and measurements have been completed to show compliance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations, the permittee should notify the Engineer in Charge of the radio district in which the station is located that it is ready for inspection.

(e) The authorization for tests embodied in this section shall not be construed as constituting a license to operate but as a necessary part of construction.

§ 73.718 Normal license period.

All international broadcast station licenses will be issued so as to expire at the hour of 3 a.m. eastern standard time and will be issued for a normal license period of 1 year expiring November 1.

LICENSING POLICIES

§ 73.731 Licensing requirements; necessary showing.

A license for an international broadcast station will be issued only after a satisfactory showing has been made in regard to the following, among others:

(a) That there is a need for the international broadcast service proposed to be rendered.

(b) That the necessary program sources are available to the applicant to render an effective international service.

(c) That directive antennas and other technical facilities will be employed to deliver maximum signals to the target area or areas for which the service is designed.

(d) That the production of the program service and the technical operation of the proposed station will be conducted by qualified persons.

(e) That the applicant is technically and financially qualified and possesses adequate technical facilities to carry forward the service proposed.

(f) That the public interest, convenience and necessity will be served through the operation of the proposed station.

EQUIPMENT

§ 73.751 Power requirement.

No international broadcast station will be authorized to install equipment or licensed for operation with a power less than 50 kilowatts.

§ 73.752 Frequency control.

The transmitter of each international broadcast station shall be equipped with automatic frequency control apparatus so designed and constructed that it is capable of maintaining the operating frequency within 0.003 percent of the assigned frequency.

§ 73.753 Antenna.

The antenna shall be so designed and operated that the signal (field intensity) toward the specific foreign country or countries served shall be at least 3.16 times the average effective signal from the station (power gain of 10).

§ 73.754 Frequency monitors.

(a) The licensee of each international broadcast station shall operate at the transmitter a frequency monitor independent of the frequency control of the transmitter.

(b) The frequency monitor shall be designed and constructed in accordance with good engineering practice and shall have an accuracy sufficient to determine that the operating frequency is within one-half of the allowed tolerance.

§ 73.755 Modulation monitors.

The licensee of each international broadcast station shall have in operation at the transmitter a modulation monitor.

§ 73.756 Required transmitter performance.

(a) The construction, installation, operation, and performance of the international broadcast transmitter system shall be in accordance with good engineering practice.

NOTE: The establishment of specific levels of attenuation for spurious emissions will be the subject of further Rule Making in Docket 10962 pending the completion of additional studies of this matter.

(b) In addition to the requirements of paragraph (a) of this section in the event spurious emissions cause harmful interference, such additional steps as may be necessary to eliminate the interference must be taken immediately by the licensee.

§ 73.757 Auxiliary transmitters.

Upon showing that a need exists for the use of auxiliary transmitters in addition to the regular transmitters of an international broadcast station, a license therefor may be issued provided that:

(a) Auxiliary transmitters may be installed either at the same location as the main transmitters or at another location.

(b) A licensed operator shall be in control whenever auxiliary transmitters are placed in operation.

(c) The auxiliary transmitters shall be maintained so that they may be put into immediate operation at any time for the following purposes:

(1) The transmission of the regular programs upon the failure of the main transmitters.

(2) The transmission of regular programs during maintenance or modification work on the main transmitter, necessitating discontinuance of its operation for a period not to exceed 5 days. (This includes the equipment changes which may be made without authority as set forth elsewhere in the rules and regulations or as authorized by the Commission by letter or by construction permit. Where such operation is required for periods in excess of 5 days, request therefor shall be in accordance with § 1.542 of this chapter.)

(3) Upon request by a duly authorized representative of the Commission.

(d) The auxiliary transmitters shall be tested at least once each week to determine that they are in proper operating condition and that they are adjusted to the proper frequency except that in the case of operation in accordance with paragraph (c) of this section during any week, the test in that week may be omitted provided the operation under paragraph (c) of this section is satisfactory. A record shall be kept of the time and result of each test. Such records shall be retained for a period of two years.

(e) The auxiliary transmitters shall be equipped with satisfactory control equipment which will enable the maintenance of the frequency emitted by the station within the limits prescribed by the regulations in this part.

(f) The operating power of an auxiliary transmitter may be less than the authorized power of the main transmitters, but in no event shall it be greater than such power.

§ 73.758 Alternate main transmitters.

The licensee of an international broadcast station may be licensed for alternate main transmitters provided that a technical need for such alternate transmitters is shown and that the following conditions are met:

(a) Both transmitters are located at the same place.

(b) Both transmitters shall have the same power rating.

(c) Both transmitters shall meet the construction, installation, operation, and performance requirements of good engineering practice.

§ 73.759 Changes in equipment and antenna system.

Licensees of international broadcast stations shall observe the following provisions with regard to changes in equipment and antenna system:

(a) No changes in equipment shall be made:

(1) That would result in the emission of signals outside of the authorized channel.

(b) Specific authority, upon filing formal application (FCC Form 309) therefor, is required for any of the following changes:

(1) Changes involving an increase or decrease in the power rating of the transmitters.

(2) A replacement of the transmitters as a whole.

(3) Change in the location of the transmitting antenna.

(4) Change in location of main studio, if it is proposed to move the main studio to a different city from that specified in the license.

(5) Change in the power delivered to the antenna.

(6) Change in frequency control and/or modulation system.

(c) Other changes, except as above provided for in this section, may be made at any time without the authority of the Commission, provided that the Commission shall be promptly notified thereof and such changes shall be shown in the next application for renewal of license.

TECHNICAL OPERATION AND OPERATORS

§ 73.761 Time of operation.

(a) All international broadcast stations will be licensed for unlimited time operation except as may be directed by the Commission from time to time. In an emergency however, when, due to causes beyond the control of the licensee, it becomes impossible to continue operation, the station may cease operation for a period not to exceed 10 days, provided that the Commission and the Engineer in Charge of the radio district in which the station is located shall be notified in writing immediately after the emergency develops.

(b) Persons desiring to enter into a voluntary sharing arrangement of an international channel may file application therefor with the Commission. Copies of the time-sharing agreement should be filed with the application.

§ 73.762 Station inspection.

The licensee of any international broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 73.763 Station license, posting of.

The original of each station license shall be posted in the transmitter room.

§ 73.764 Operator requirements.

One or more licensed radiotelephone first-class operators shall be on duty at the place where the transmitting apparatus of each station is located and in actual charge thereof whenever it is being operated. The original license (or FCC Form 759) of each station operator shall be posted at the place where he is on duty. The licensed operator on duty and in charge of an international broadcast transmitter may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of operator's license which he holds and by the rules and regulations governing such stations. However, such duties shall in nowise interfere with the operation of the broadcast transmitter.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 73.765 Operating power; how determined.

The operating power, and its maintenance, of each international broadcast station shall be in conformity with good engineering practice.

§ 73.766 Modulation.

The percentage of modulation of the transmissions shall be maintained as high as possible consistent with good quality of transmission and good broadcast practice and in no case less than 50 percent nor more than 100 percent on peaks of frequent recurrence during any selection which normally is transmitted at the highest level of the program under consideration.

§ 73.767 Frequency tolerance.

The operating frequencies of international broadcast station transmitters shall, at all times, be maintained within the frequency tolerances specified in § 73.752.

§ 73.768 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of that part.

§ 73.769 Discontinuance of operation.

The licensee of each station, except stations operating in Alaska, shall notify the Engineer in Charge of the radio district in which the station is located of any of the following changes in the status of such station at least two days before such change:

(a) Temporary discontinuance of operation for a period of ten days or more;

(b) The date of resumption of operation after temporary discontinuance of operation for a period of ten days or more;

(c) Permanent discontinuance of operation.

In all cases of permanent discontinuance of operation the licensee shall, in addition to notifying the Engineer in Charge of the radio district in which the station is located of intention to discontinue operation, immediately forward the station license to the Washington, D. C., office of the Commission for cancellation.

OTHER OPERATING REQUIREMENTS

§ 73.781 Logs.

The licensee or permittee of each international broadcast station shall maintain program and operating logs in the following manner:

(a) In the program log:

(1) An entry of the time each station identification announcement (call letters and location) is made.

(2) An entry briefly describing each program broadcast, such as "music", "drama", "speech", etc., together with the name or title thereof, language, and the sponsor's name, with the time of the beginning and ending of the complete program.

(3) An entry showing, for each program of network origin, the name of the network originating the program.

(b) In the operating log:

(1) An entry of the time the station begins to supply power to the antenna, and the time it stops.

(2) An entry of the time the program begins and ends.

(3) An entry of each interruption to the carrier wave, its cause, and duration.

(4) An entry of the following each 30 minutes:

(i) Operating constants of last radio stage of the transmitter (total plate current and plate voltage).

(ii) Frequency monitor reading.

(5) A log must be kept of all experimental operation. If the entries required above are not applicable thereto, then the entries shall be made so as to fully describe the operation.

(c) Where an antenna structure(s) is required to be illuminated, see § 17.38, *Recording of tower light inspections in the station record,* of Part 17 of this chapter (Construction, Marking and Lighting of Antenna Structures).

§ 73.782 Retention of logs.

Logs of international broadcast stations shall be retained by the licensee or permittee for a period of two years: *Provided, however,* That logs involving communications incident to a disaster or which include communications incident to or involved in an investigation by the Commission and concerning which the licensee or permittee has been notified, shall be retained by the licensee or permittee until he is specifically authorized in writing by the Commission to destroy them: *Provided, further,* That logs incident to or involved in any claim or complaint of which the licensee or permittee has notice shall be retained by the licensee or permittee until such claim or complaint has been fully satisfied or until the same has been barred by statute limiting the time for the filing of suits upon such claims.

§ 73.783 Logs; by whom kept.

Each log shall be kept by the person or persons competent to do so, having actual knowledge of the facts required, who shall sign the log when starting duty and again when going off duty. The logs shall be made available upon request by an authorized representative of the Commission.

§ 73.784 Log form.

The log shall be kept in an orderly manner, in suitable form, and in such detail that the data required for the particular class of station concerned are readily available. Key letters or abbreviations may be used if proper meaning or explanation is contained elsewhere in the log.

§ 73.785 Correction of logs.

No log or portion thereof shall be erased, obliterated, or willfully destroyed within the period of retention provided by the rules. Any necessary correction may be made only by the person originating the entry who shall strike out the erroneous portion, initial the correction made, and indicate the date of correction.

§ 73.786 Rough logs.

Rough logs may be transcribed into condensed form, but in such case, the original log or memoranda and all portions thereof shall be preserved and made a part of the complete log.

§ 73.787 Station identification.

(a) A licensee of an international broadcast station shall make station identification announcement (call letters and location), at the beginning and ending of each time of operation and during the operation on the hour.

(b) Station identification, program announcements, and oral continuity shall be made with international significance (language particularly) which is designed for the foreign country or countries for which the service is primarily intended.

(c) Identification announcements during operation need not be made when to make such announcement would interrupt a single consecutive speech, play, religious service, symphony concert, or any type of production. In such cases the identification announcement shall be made at the first interruption of the entertainment continuity and at the conclusion thereof.

§ 73.788 Service; commercial or sponsored programs.

(a) A licensee of an international broadcast station shall render only an international broadcast service which will reflect the culture of this country and which will promote international goodwill, understanding, and cooperation. Any program solely intended for, and directed to an audience in the continental United States does not meet the requirements for this service.

(b) Such international broadcast service may include commercial or sponsored programs: *Provided,* That:

(1) Commercial program continuities give no more than the name of the sponsor of the program and the name and general character of the commodity, utility or service, or attraction advertised.

(2) In case of advertising a commodity, the commodity is regularly sold or is being promoted for sale on the open market in the foreign country or countries to which the program is directed in accordance with paragraph (c) of this section.

(3) In case of advertising an American utility or service to prospective tourists or visitors to the United States, the advertisement continuity is particularly directed to such persons in the foreign country or countries where they reside and to which the program is directed in accordance with paragraph (c) of this section.

(4) In case of advertising an international attraction (such as a world fair, resort, spa, etc.) to prospective tourists or visitors to the United States, the oral continuity concerning such attraction is consistent with the purpose and intent of this section.

(5) In case of any other type of advertising, such advertising is directed to the foreign country or countries to which the program is directed and is consistent with the purpose and intent of this section.

(c) The geographic areas to be served by international broadcast stations are the foreign standard target areas shown in Figure 1 of § 73.792, or foreign nonstandard target areas as provided in § 73.702(d), and directive antennas shall be employed to direct the transmission to these specific target areas.

(d) An international broadcast station may transmit the program of a standard broadcast station or network system: *Provided,* The conditions in paragraph (b) of this section in regard to any commercial continuities are observed and when station identifications are made, only the call letter designation of the international station is given on its assigned frequency: *And provided further,* That in the case of chain broadcasting the program is not carried simultaneously by another international station (except another station owned by the same licensee operated on a frequency in a different group to obtain continuity of signal service), the signals from which are directed to the same area. (See section 3 (p) of the Communications Act of 1934 for the definition of "chain broadcasting.")

§ 73.789 Sponsored programs, announcement of.

(a) When an international broadcast station transmits any matter for which money, services, or other valuable consideration is either directly or indirectly paid or promised to, or charged or received by, such station, the station shall broadcast an announcement that such matter is sponsored, paid for, or furnished, either in whole or in part, and by whom or on whose behalf such consideration was supplied: *Provided, however,* That "service or other valuable consideration" shall not include any service or property furnished without charge or at a nominal charge for use on, or in connection with, a broadcast unless it is so furnished in consideration for an identification in a broadcast of any person, product, service, trademark, or brand name beyond an identification which is reasonably related to the use of such service or property on the broadcast.

(b) The licensee of each international broadcast station shall exercise reasonable diligence to obtain from its employees, and from other persons with whom it deals directly in connection with any program matter for broadcast, information to enable such licensee to make the announcement required by this section.

(c) In any case where a report (concerning the providing or accepting of valuable consideration by any person for inclusion of any matter in a program intended for broadcasting) has been made to an international broadcast station, as required by section 508 of the Communications Act of 1934, as amended, of circumstances which would have required an announcement under this section had the consideration been received by such international broadcast station, an appropriate announcement shall be made by such station.

(d) In the case of any political program or any program involving the discussion of public controversial issues for which any records, transcriptions, talent, scripts, or other material or services of any kind are furnished, either directly or indirectly, to a station as an inducement to the broadcasting of such program, an announcement shall be made both at the beginning and conclusion of such program on which such material or services are used that such records, transcriptions, talent, scripts, or other material or services have been furnished to such station in connection with the broadcasting of such programs: *Provided, however,* That only one such announcement need be made in the case of any such program of 5 minutes' duration or less, which announcement may be made either at the beginning or conclusion of the program.

(e) The announcement required by this section shall fully and fairly disclose the true identity of the person or

persons by whom or in whose behalf such payment is made or promised, or from whom or in whose behalf such services or other valuable consideration is received, or by whom the material or services referred to in paragraph (d) of this section are furnished. Where an agent or other person contracts or otherwise makes arrangements with a station on behalf of another, and such fact is known to the station, the announcement shall disclose the identity of the person or persons in whose behalf such agent is acting instead of the name of such agent.

(f) In the case of any program, other than a program advertising commercial products or services, which is sponsored, paid for or furnished, either in whole or in part, or for which material or services referred to in paragraph (d) of this section are furnished, by a corporation, committee, association, or other unincorporated group, the announcement required by this section shall disclose the name of such corporation, committee, association, or other unincorporated group. In each such case the station shall require that a list of the chief executive officers or members of the executive committee or of the board of directors of the corporation, committee, association or other unincorporated group shall be made available for public inspection at the studios or general offices of one of the international broadcast stations carrying the program in each community in which the program is broadcast.

(g) In the case of broadcast matter advertising commercial products or services, an announcement stating the sponsor's corporate or trade name, or the name of the sponsor's product, when it is clear that the mention of the name of the product constitutes a sponsorship identification, shall be deemed sufficient for the purposes of this section and only one such announcement need be made at any time during the course of the program.

(h) Commission interpretations in connection with the foregoing rules may be found in the Commission's Public Notice entitled "Applicability of Sponsorship Identification Rules" (FCC 63–409; 28 F.R. 4732, May 10, 1963) and such supplements as are issued from time to time.

(Sec. 317, 48 Stat. 1089, as amended; 47 U.S.C. 317)

§ 73.790 Rebroadcast.

(a) The licensee of an international broadcast station may, without further authority of the Commission, rebroadcast the program of a United States standard, FM noncommercial educational, or FM broadcast station, provided the Commission is notified of the call letters of each station rebroadcast and the licensee certifies that express authority has been received from the licensee of the station originating the program. The notice and certification of consent must be given within 3 days of any single rebroadcast, but in case of the regular practice of rebroadcasting certain programs of another broadcast station several times during a license period, notice and certification of consent must be given for the ensuing license period with the application for renewal of license, or at the beginning of such rebroadcast practice if begun during a license period.

NOTE: The broadcasting of a program relayed by a remote pickup broadcast station is not considered a rebroadcast.

(b) No licensee of an international broadcast station shall rebroadcast the programs of any other class of United States radio station without written authority having first been obtained from the Commission.

(c) A licensee of an international broadcast station may authorize the rebroadcast of its programs by any station outside the limits of the North American continent without permission from the Commission: *Provided*, That the station rebroadcasting the programs cannot be received consistently in the United States.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

§ 73.791 Supplemental report with renewal application.

A supplemental report shall be filed with and made a part of each application for renewal of license and shall include statements of the following:

(a) The number of hours operated on each frequency, listing contract operations and private operations separately.

(b) Outline of reports of reception and interference and conclusions with regard to propagation characteristics of assigned frequencies. (If such information is not available to the applicant in the case of contract operations, a statement to this effect will be considered adequate.)

§ 73.792 Engineering chart.




Figure 1

Subpart G—Emergency Broadcast System

AUTHORITY: §§ 73.901 to 73.971 issued under sec. 606, 48 Stat. 1104, as amended; 47 U.S.C. 606; E.O. 11092, 28 F.R. 1847.

SCOPE AND OBJECTIVE

§ 73.901 Scope of subpart.

This subpart applies to all broadcast stations governed by this part and is for the purpose of providing for operation of certain stations located within the United States, including Guam, Puerto Rico, and the Virgin Islands, during periods of a National Emergency.

§ 73.902 Object of subpart.

The object of this subpart is to fulfill national security requirements while at the same time providing for transmission of vital information to the public.

DEFINITIONS

§ 73.911 Emergency Broadcast System (EBS).

The Emergency Broadcast System consists of broadcast stations and interconnecting facilities which have been authorized by the Commission to operate in a controlled manner during a war, threat of war, state of public peril or disaster, or other national emergency.

§ 73.912 National Defense Emergency Authorization (NDEA).

An authorization issued by the Commission permitting controlled operation of a station operating in the Radio Broadcast Services during an Emergency Action Condition.

§ 73.913 Emergency Action Notification.

The Emergency Action Notification is the notice to stations in the Radio Broadcast Services to operate in accordance with the Emergency Broadcast System Plan.

§ 73.914 Emergency Action Termination.

The Emergency Action Termination is the notice to stations in the Radio Broadcast Services to discontinue controlled operations imposed by an outstanding Emergency Action Notification and return to normally licensed operations.

§ 73.915 Emergency Action Condition.

The condition which exists after the the transmission of an Emergency Action Notification and before the transmission of the Emergency Action Termination.

§ 73.916 Emergency Broadcast System Plan.

The Emergency Broadcast System Plan is the document containing the detailed description of how stations operating in the Radio Broadcast Services will be notified and operated in the Emergency Broadcast System.

EMERGENCY ACTIONS

§ 73.921 Emergency Action Notification.

(a) All Emergency Action Notifications shall be issued by an appropriate Federal authority. These Emergency Action Notifications will be accomplished in accordance with the Emergency Broadcast System Plan.

(b) Immediately upon receipt of an Emergency Action Notification, all standard, commercial FM, and noncommercial educational FM broadcast stations with a transmitter output of over 10 watts, and television broadcast stations, including all such stations operating under equipment or program test authority, will proceed as follows:

(1) Discontinue normal program and make the following announcement: We interrupt this program for a nationwide alert.

(2) Transmit the Emergency Action Notification Attention Signal as follows:

(i) Cut the transmitter carrier for 5 seconds. (Sound carrier only for TV stations.)

(ii) Return carrier to the air for 5 seconds.

(iii) Cut transmitter carrier for 5 seconds. (Sound carrier only for TV stations.)

(iv) Return carrier to the air.

(v) Broadcast 1000 cycle steady state tone for 15 seconds.

(3) Broadcast the following Emergency Action Notification Message:

(i) For NDEA stations:

This station has interrupted its regular program at the request of the United States Government to participate in the Emergency Broadcast System, serving the _____ area. During this period many radio stations will remain on the air, broadcasting news and official information for areas assigned to them. This station will remain on the air and will serve the _____ area. If you are not located in the _____ area, you should now tune your radio to other stations until you hear one which is broadcasting news and information for your area. You are listening to the Emergency Broadcast System serving the_____ area.

I repeat—

This station has interrupted its regular program at the request of the United States Government to participate in the Emergency Broadcast System, serving the _____ area. During this period many radio stations will remain on the air, broadcasting news and official information for areas assigned to them. This station will remain on the air and will serve the _____ area. If you are not located in the _____ area, you should now tune your radio to other stations until you hear one which is broadcasting news and information for your area. You are listening to the Emergency Broadcast System serving the _____ area.

NOTE: REPEAT THE ENTIRE MESSAGE ABOVE. THEN BROADCAST COMMON LOCAL, STATE, REGIONAL, OR NATIONAL PROGRAMMING IN ACCORDANCE WITH THE EMERGENCY BROADCAST SYSTEM PLAN.

(ii) For non-NDEA Standard, FM, and TV stations.

This station has interrupted its regular program at the request of the United States Government to participate in the Emergency Broadcast System. During this period, this station will go off the air, but some radio stations will remain on the air broadcasting news and official information for their areas. You should now tune your radio until you hear a radio station which is broadcasting news and information for your area.

I repeat—

This station has interrupted its regular program at the request of the United States Government to participate in the Emergency Broadcast System. During this period, this station will go off the air, but some radio stations will remain on the air broadcasting news and official information for their areas. You should now tune your radio until you hear a radio station which is broadcasting news and information for your area.

NOTE: REPEAT ENTIRE MESSAGE ABOVE AND TURN OFF THE TRANSMITTER. TV STATIONS SHOULD DISPLAY CD EMBLEM DURING ABOVE ANNOUNCEMENT.

(c) Noncommercial educational FM broadcast stations with a transmitter power output of 10 watts or less, upon receipt of an Emergency Action Notification, will interrupt the program in progress, and broadcast the Emergency Action Notification Message as in § 73.921 (b) (3) (ii). The station will then discontinue its carrier and maintain radio silence in accordance with the Emergency Broadcast System Plan.

(d) International broadcast stations upon receipt of an Emergency Action Notification will interrupt the program in progress, may make a brief sign-off announcement not longer than one minute and, except for those stations specifically authorized by the Federal Communications Commission to continue transmitting, will leavc the air and maintain radio silence in accordance with the Emergency Broadcast System Plan.

(e) During the experimental period (midnight to 6:00 a.m., local time) many standard broadcast stations may be off the air. All broadcast licensees will be supplied with a list of 24-hour broadcast stations at least one of which must be monitored during any period of operation when the station regularly monitored is not on the air.

§ 73.922 Reception of an Emergency Action Notification.

All broadcast station licensees must install, unless specifically exempt, the necessary equipment to receive Emergency Action Notifications or Terminations by means of reception of radio broadcast messages, and must maintain this equipment in a state of readiness for reception, including arrangements for human listening watch or automatic alarm devices, or both. Such equipment shall have its termination at the transmitter control point.

§ 73.923 Operation during an Emergency Action Condition.

(a) Those stations which are authorized to participate in the Emergency Broadcast System upon receipt of an Emergency Action Notification will immediately begin operations in accordance with the terms of their National Defense Emergency Authorizations and current operating instructions. Except as provided in paragraph (b) of this section, all other broadcast stations will observe radio silence in accordance with the Emergency Broadcast System Plan.

(b) Stations in the International Broadcast Service operating under the

jurisdiction of the Federal Communications Commission will under certain conditions be issued an NDEA by the Federal Communications Commission with concurrence of the Director, Office of Emergency Planning, and will transmit only Federal Government broadcasts or communications. The station's carrier must be removed from the air during periods of no broadcast or communications transmissions.

(c) No broadcast of the call letters of the station shall be made during an Emergency Action Condition. Area identification shall be given.

(d) All stations identified by a particular area will carry the same program.

(e) Prior to commencing routine operation or originating any emissions under program test, equipment test, experimental or other authorizations or for any other purpose, licensees or permittees shall first ascertain whether an Emergency Action Condition exists and if so, shall refrain from operation or shall operate in the Emergency Broadcast System, whichever is appropriate.

EMERGENCY ACTION CONDITION TERMINATION

§ 73.931 Notification of termination of Emergency Action Condition.

The notification of the termination of an Emergency Action Condition will be transmitted through the same channels as the Emergency Action Notification. Unlimited time stations operating in the Emergency Broadcast System will transmit the Termination Message twice, and then resume normal operation. Daytime Only and Limited Time broadcast stations operating in the Emergency Broadcast System shall also broadcast the Termination Message twice, then operate in accordance with their regular authorization.

§ 73.932 Termination Message.

This concludes operations under the Emergency Broadcast System. All broadcast stations may now resume normal broadcast operations.

SYSTEM OPERATION

§ 73.941 Procedure.

Each licensee operating in the Radio Broadcast Services permitted to operate during an Emergency Action Condition must observe the Emergency Broadcast operating procedures.

§ 73.942 Participation.

(a) Any licensee desiring to participate in the Emergency Broadcast System should advise the FCC Field Supervisor in writing of its willingness to participate and to cooperate in making such technical modification of the station equipment as might be necessary. Based upon the criteria set forth in the Emergency Broadcast System Plan, the Commission may then issue a National Defense Emergency Authorization to the licensee authorizing participation in the Emergency Broadcast System.

(b) Any station participating in the Emergency Broadcast System may withdraw from the system by giving 30 days written notice and by submitting its National Defense Emergency Authorization to the Commission through the appropriate FCC Field Supervisor for cancellation.

(c) Broadcast stations are specifically exempt from complying with § 73.57 while operating under their National Defense Emergency Authorization.

TESTS

§ 73.951 Emergency Action Notification System Tests.

(a) Tests of the Emergency Action Notification System will be made at regular intervals and results submitted by the licensee to the Commission in accordance with detailed instructions.

(b) Tests involving transmission of the Emergency Action Notification Attention Signal and test message by standard, FM, and television broadcast stations, shall be made once each week on an unscheduled basis between the hours of 8:30 a.m. and local sunset. Results of these tests shall be forwarded to the Commission by the licensees concerned, in accordance with detailed instructions.

The procedure is as follows:

(1) Make the following announcement:

This is a test. For the next sixty seconds this station will conduct a test of the Emergency Broadcast System. This is only a test.

(2) Transmit the Emergency Action Notification Attention Signal as follows:

(i) Cut the transmitter carrier for 5 seconds. (Sound carrier only for TV stations.)

(ii) Return carrier to the air for 5 seconds.

(iii) Cut transmitter carrier for 5 seconds. (Sound carrier only for TV stations.)

(iv) Return carrier to the air.

(v) Broadcast 1000 cycle steady state tone for 15 seconds.

(3) Broadcast the following test message:

This has been a test of the Emergency Broadcast System. If this had been an actual emergency, normal broadcasting would have been discontinued and only designated Emergency Broadcast System radio stations would continue in operation. You would have been instructed to tune to one of your area stations for official information. This concludes this test of the Emergency Broadcast System.

WEATHER WARNINGS

§ 73.961 Emergency Weather Warnings.

Upon receipt of notification from the United States Weather Bureau of an Emergency Weather Warning of a condition of immediate danger to life and property, all standard, commercial FM, and television broadcast stations may, at their option, during authorized hours of operation only, transmit the Emergency Action Notification Signal, as set forth in § 73.921(b)(2), prior to broadcasting the Emergency Weather Warning, as provided in §§ 73.90, 73.296, and 73.632, respectively. Nothing in this section shall be construed as permitting a standard broadcast station licensed to operate daytime only or limited time to operate during unauthorized hours.

NETWORK CONNECTION

§ 73.971 Participation by telephone companies.

(a) Telephone companies that have facilities available in place may, without charge, connect an unaffiliated commercial radio broadcast station to a commercial radio network operated by ABC, CBS, MBS, NBC, or any other network, for the duration of an Emergency Action Condition: *Provided*, That

(1) The radio station is authorized by the Commission to participate in the Emergency Broadcast System under § 73.942;

(2) The radio station has in service a local channel from the radio station studio or radio transmitter to the telephone company principal central office (toll test).

(b) During an Emergency Action Condition or for the purpose of testing the communications facilities provided for in National Industry Advisory Committee orders, telephone companies that have facilities available in place may, without charge, connect an originating source designated by a National Industry Advisory Committee order to the nearest accessible commercial radio network and, at the expiration of such condition or test, may disconnect such authorized originating source: *Provided*, (1) That the originating point has in service a telephone company local channel from the originating point to the telephone company principal central office (toll test); and (2) That the National Industry Advisory Committee order covering this service is placed in effect.

(c) Every such carrier rendering any such free service shall make and file, in duplicate, with the Commission, on or before the 31st day of July and on or before the 31st day of January in each year, reports covering the periods of six months ending on the 30th day of June and the 31st day of December, respectively, next prior to said dates. These reports shall show the call letters and locations of the broadcast stations to which free service was rendered pursuant to this rule and the charges in dollars which would have accrued to the carrier for such service rendered if charges therefor had been collected at the published tariff rates.

PART 74—EXPERIMENTAL, AUXILIARY, AND SPECIAL BROADCAST SERVICES

GENERAL

Sec.
74.1 Services covered by this part.

ADMINISTRATIVE PROCEDURE

74.11 Cross reference.
74.12 Notification of filing of applications.
74.13 Equipment tests.
74.14 Service or program tests.
74.15 License period.
74.16 Temporary extension of station licenses.

SPECIAL PROVISIONS

74.21 Operation during an emergency.

Subpart A—Experimental Television Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

Sec.
74.101 Experimental television broadcast station.
74.102 Purpose.
74.103 Frequency assignment.

ADMINISTRATIVE PROCEDURE

74.111 Cross reference.
74.112 Supplementary statement with application for construction permit.
74.113 Supplementary reports with application for renewal of license.

LICENSING POLICIES

74.131 Licensing requirements, necessary showing.
74.132 Power limitations.
74.133 Emission authorized.
74.134 Multiple ownership.

EQUIPMENT

74.151 Equipment changes.

TECHNICAL OPERATION AND OPERATORS

74.161 Frequency tolerance.
74.162 Frequency monitors and measurements.
74.163 Time of operation.
74.164 Station inspection.
74.165 Station and operator licenses; posting of.
74.166 Operator requirements.
74.167 Antenna structure, marking and lighting.
74.168 Additional orders.

OTHER OPERATING REQUIREMENTS

74.181 Station records.
74.182 Charges.
74.183 Station identification.
74.184 Rebroadcasts.

Subpart B—Experimental Facsimile Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

74.201 Facsimile broadcast station.
74.202 Frequency assignment.

ADMINISTRATIVE PROCEDURE

74.211 Cross reference.
74.212 Supplementary statement with application for construction permit.
74.213 Supplemental report with renewal application.

LICENSING POLICIES

74.231 Licensing requirements, necessary showing.
74.232 Power limitations.
74.233 Emission authorized.
74.234 Multiple ownership.

EQUIPMENT

74.251 Equipment changes.

TECHNICAL OPERATION AND OPERATORS

74.261 Frequency tolerance.
74.262 Frequency monitors and measurements.
74.263 Time of operation.
74.264 Station inspection.
74.265 Station and operator licenses; posting of.
74.266 Operator requirements.
74.267 Antenna structure, marking and lighting.
74.268 Additional orders.

OTHER OPERATING REQUIREMENTS

74.281 Station records.
74.282 Charges.
74.283 Station identification.
74.284 Rebroadcasts.

Subpart C—Developmental Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

Sec.
74.301 Developmental broadcast station.
74.302 Frequency assignment.

ADMINISTRATIVE PROCEDURE

74.311 Cross reference.
74.312 Supplementary statement with application for construction permit.
74.313 Supplemental report with renewal application.

LICENSING POLICIES

74.331 Licensing requirements; necessary showing.
74.332 Power limitations.
74.333 Emission authorized.

EQUIPMENT

74.351 Equipment changes.

TECHNICAL OPERATION AND OPERATORS

74.361 Frequency tolerance.
74.362 Frequency monitors and measurements.
74.363 Time of operation.
74.364 Station inspection.
74.365 Station and operator licenses; posting of.
74.366 Operator requirements.
74.367 Antenna structure, marking and lighting.
74.368 Additional orders.

OTHER OPERATING REQUIREMENTS

74.381 Station records.
74.382 Program service; charges prohibited; announcements.
74.383 Station identification.
74.384 Rebroadcasts.

Subpart D—Remote Pickup Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

74.401 Definitions.
74.402 Frequency assignment.
74.403 Frequency selection to avoid interference.

ADMINISTRATIVE PROCEDURE

74.411 Cross reference.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

74.431 Permissible service.
74.432 Licensing requirements.
74.433 Temporary authorizations.
74.434 Remote control operation.
74.435 Power limitations.
74.436 Emission authorized.
74.437 Special rules relating to low power broadcast auxiliary stations.

EQUIPMENT

74.451 Equipment changes.

TECHNICAL OPERATION AND OPERATORS

74.461 Frequency tolerance.
74.462 Frequency monitors and measurements.
74.463 Station inspection.
74.464 Station and operator licenses; posting of.
74.465 Operator requirements.
74.466 Antenna structure, marking and lighting.
74.467 Additional orders.

OTHER OPERATING REQUIREMENTS

74.481 Station records.
74.482 Station identification.

Subpart E—Aural Broadcast STL and Intercity Relay Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

74.501 Classes of stations.
74.502 Frequency assignment.
74.503 Frequency selection.

ADMINISTRATIVE PROCEDURE

Sec.
74.511 Cross reference.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

74.531 Permissible service.
74.532 Licensing requirements.
74.533 Remote control and unattended operation.
74.534 Power limitations.
74.535 Emission and bandwidth.
74.536 Directional antenna required.

EQUIPMENT

74.551 Equipment changes.

TECHNICAL OPERATION AND OPERATORS

74.561 Frequency tolerance.
74.562 Frequency monitors and measurements.
74.563 Station inspection.
74.564 Station and operator licenses; posting of.
74.565 Operator requirements.
74.566 Antenna structure, marking and lighting.
74.567 Additional orders.

OTHER OPERATING REQUIREMENTS

74.581 Station records.
74.582 Station identification.

Subpart F—Television Auxiliary Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

74.601 Classes of television auxiliary broadcast stations.
74.602 Frequency assignment.
74.603 Sound channels.
74.604 Frequency selection to avoid interference.

ADMINISTRATIVE PROCEDURE

74.621 Cross reference.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

74.631 Permissible service.
74.632 Licensing requirements.
74.633 Temporary authorizations.
74.634 Remote control operation.
74.635 Unattended operation.
74.636 Power limitations.
74.637 Emission and bandwidth.

EQUIPMENT

74.651 Equipment changes.

TECHNICAL OPERATION AND OPERATORS

74.661 Frequency tolerance.
74.662 Frequency monitors and measurements.
74.663 Station inspection.
74.664 Station and operator licenses; posting of.
74.665 Operator requirements.
74.666 Antenna structure, marking and lighting.
74.667 Additional orders.

OTHER OPERATING REQUIREMENTS

74.681 Station logs.
74.682 Station indentification.

Subpart G—Television Broadcast Translator Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

74.701 Definitions.
74.702 Frequency assignment.
74.703 Interference.

ADMINISTRATIVE PROCEDURE

74.711 Cross reference.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

74.731 Purpose and permissible service.
74.732 Eligibility and licensing requirements.

Sec.
74.733 UHF translator signal boosters.
74.734 Unattended operation.
74.735 Power limitation.
74.736 Emissions and bandwidth.
74.737 Antenna location.

EQUIPMENT

74.750 Equipment and installation.
74.751 Equipment changes.

TECHNICAL OPERATION AND OPERATORS

74.761 Frequency tolerance.
74.762 Frequency monitors and measurements.
74.763 Time of operation.
74.764 Station inspection.
74.765 Posting of station license.
74.766 Operator requirements.
74.767 Marking and lighting of antenna structures.
74.768 Additional orders.
74.769 Copies of rules.

OTHER OPERATING REQUIREMENTS

74.781 Station records.
74.783 Station identification.
74.784 Rebroadcasts.

PRE-EXISTING REPEATERS

74.790 Special requirements for pre-existing VHF repeaters.

Subpart H—Television Broadcast Booster Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

74.801 Definitions.
74.802 Frequency assignment.
74.803 Interference to primary station.
74.804 Interference to other stations and services.

ADMINISTRATIVE PROCEDURE

74.811 Administrative procedure.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

74.831 Purpose and permissible service.
74.832 Eligibility and licensing requirements.
74.834 Remote control operation.
74.835 Power limitations.
74.836 Emissions and bandwidth.
74.837 Antenna location.

EQUIPMENT

74.850 Equipment and installation.
74.851 Equipment changes.

TECHNICAL OPERATION AND OPERATORS

74.861 Frequency tolerance.
74.862 Frequency monitors and measurements.
74.863 Time of operation.
74.864 Station inspection.
74.865 Posting of station and operator licenses.
74.866 Operator requirements.
74.867 Marking and lighting of antenna structures.
74.868 Additional orders.
74.869 Copies of rules.

OTHER OPERATING REQUIREMENTS

74.881 Station records.
74.883 Station identification.
74.884 Rebroadcasts.

Subpart I—Instructional Television Fixed Services

DEFINITIONS AND ALLOCATION OF FREQUENCIES

74.901 Definitions.
74.902 Frequency assignments.
74.903 Interference.

ADMINISTRATIVE PROCEDURE

74.911 Cross reference.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

Sec.
74.931 Purpose and permissible service.
74.932 Eligibility and licensing requirements.
74.933 Remote control operation.
74.934 Unattended operation.
74.935 Power limitations.
74.936 Emissions and bandwidth.
74.937 Antennas.
74.938 Transmission standards.

EQUIPMENT

74.950 Equipment performance and installation.
74.951 Equipment changes.
74.952 Acceptability of equipment for licensing.

TECHNICAL OPERATION AND OPERATORS

74.961 Frequency tolerance.
74.962 Frequency monitors and measurements.
74.963 Time of operation.
74.964 Station inspection.
74.965 Posting of station and operator licenses.
74.966 Operator requirements.
74.967 Marking and lighting of antenna structures.
74.968 Additional orders.
74.969 Copies of the rules.
74.970 Modulation limits.
74.971 Modulation monitors and measurements.

OTHER OPERATING REQUIREMENTS

74.981 Logs.
74.982 Station identification.
74.984 Retransmissions.

AUTHORITY: §§ 74.1 to 74.984 issued under sec. 4, 303, 48 Stat. 1066, as amended, 1082, as amended; 47 U.S.C. 4, 303. Interpret or apply secs. 301, 303, 307, 48 Stat. 1081, 1082, as amended, 1083, as amended; 47 U.S.C. 301, 303, 307. Other statutory provisions constituting authority for or interpreted or applied by specific sections are cited to text.

GENERAL

§ 74.1 Services covered by this part.

(a) *Experimental and developmental broadcast.* (1) Experimental television broadcast (Subpart A).

(2) Experimental facsimile broadcast (Subpart B).

(3) Developmental broadcast (Subpart C).

(b) *Auxiliary broadcast.* (1) Remote pickup broadcast (Subpart D).

(2) Standard and FM broadcast STL and FM intercity relay (Subpart E).

(3) Television pickup (Subpart F).

(4) Television STL (Subpart F).

(5) Television inter-city relay (Subpart F).

(c) *Special broadcast.* (1) Television broadcast translator (Subpart G).

(2) Television broadcast booster (Subpart H).

(3) Instructional television fixed (Subpart I).

ADMINISTRATIVE PROCEDURE

§ 74.11 Cross reference.

See Subpart D of Part 1 of this chapter for general requirements as to applications, filing of applications, and description of forms; and see § 1.1111 of Subpart G of that part for the fees to be paid in connection with applications for facilities in the services covered in this part.

§ 74.12 Notification of filing of applications.

In order to minimize harmful interference at the National Radio Astronomy Observatory site located at Green Bank, Pocahontas County, West Virginia, and at the Naval Radio Research Observatory at Sugar Grove, Pendleton County, West Virginia, an applicant for authority to construct any class of station covered in § 4.1 except remote pickup broadcast mobile and TV pickup stations, or for authority to make changes in the frequency, power, antenna height, or antenna directivity of an existing station within the area bounded by 39°15′ N on the north, 78°30′ W on the east, 37°30′ N on the south and 80°30′ W on the west shall, at the time of filing such application with the Commission, simultaneously notify the Director, National Radio Astronomy Observatory, P.O. Box #2, Green Bank, West Virginia, 24944, in writing, of the technical particulars of the proposed station. Such notification shall include the geographical coordinates of the antenna, antenna height, antenna directivity if any, proposed frequency, type of emission, and power. In addition, the applicant shall indicate in his application to the Commission the date notification was made to the Observatory. After receipt of such applications, the Commission will allow a period of twenty (20) days for comments or objections in response to the notifications indicated. If an objection to the proposed operation is received during the twenty day period from the National Radio Astronomy Observatory for itself or on behalf of the Naval Radio Research Observatory, the Commission will consider all aspects of the problem and take whatever action is deemed appropriate.

§ 74.13 Equipment tests.

(a) During the process of construction of any class of radio station listed in this part, the permittee, after notifying the Commission and Engineer in Charge of the district in which the station is located, may, without further authority of the Commission, conduct equipment tests for the purpose of such adjustments and measurements as may be necessary to assure compliance with the terms of the construction permit, the technical provisions of the application therefor, the rules and regulations, and the applicable engineering standards.

(b) The Commission may notify the permittee to conduct no tests or may cancel, suspend, or change the date for the beginning of equipment tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Equipment tests may be continued so long as the construction permit shall remain valid.

(d) The authorization for tests embodied in this section shall not be construed as constituting a license to operate but as a necessary part of construction.

§ 74.14 Service or program tests.

(a) Upon completion of construction of a radio station in accordance with the terms of the construction permit, the technical provisions of the application therefor, and the rules and regulations and applicable engineering standards, and when an application for station license has been filed showing the station to be in satisfactory operating condition, the permittee of any class of station listed in this part may, without further authority of the Commission, conduct service or program tests: *Provided,* That the Engineer in Charge of the district in which the station is located and the Commission are notified at least two (2) days (not including Sundays and Saturdays and legal holidays when the offices of the Commission are not open) in advance of the beginning of such operation.

(b) The Commission may notify the permittee to conduct no tests or may cancel, suspend, or change the date for the beginning of such tests as and when such action may appear to be in the public interest, convenience, and necessity.

(c) Unless sooner suspended or revoked, program test authority will continue valid during Commission consideration of the application for license and during this period further extension of the construction permit is not required. Program test authority shall be automatically terminated by final determination upon the application for station license.

(d) The authorization for tests embodied in this section shall not be construed as approval by the Commission of the application for station license.

§ 74.15 License period.

(a) Licenses for the following classes of stations normally will be issued for a period of one year expiring as follows:

(1) Experimental television broadcast station: April 1.

(2) Experimental facsimile broadcast station: March 1.

(3) Developmental broadcast station: May 1.

(b) Licenses for stations in the Auxiliary Broadcast Services will be issued for a period running concurrently with the licenses of the broadcast station with which such auxiliary stations are used. A remote pickup broadcast station licensed for use with more than one broadcast station will be licensed for a period running concurrently with the license of the broadcast station having the longer license period.

(c) The license of a television broadcast booster station will be issued for a period running concurrently with the license of the television broadcast station (Primary Station) with which it is used.

(d) On and after the dates specified in this paragraph for stations located in the various States, licenses for television broadcast translator stations ordinarily will be issued for a period of three years, and, when regularly renewed, at three year intervals thereafter (initial licenses and renewals issued prior to the applicable date specified in this paragraph will normally run until such applicable date): *Provided, however,* That if the Commission finds that the public interest, convenience, and necessity will be served thereby, it may issue either an initial license or a renewal thereof for a lesser term. When regularly issued or renewed, licenses will be issued to expire at the hour of 3:00 a.m., eastern standard time, in accordance with the following schedule, and at three year intervals thereafter:

(1) For stations located in Maine, Vermont, New Hampshire, Massachusetts, Connecticut, Rhode Island, New York, New Jersey, Pennsylvania, Maryland, Delaware, West Virginia, Ohio, and the District of Columbia: June 1, 1965.

(2) For stations located in Virginia, North Carolina, South Carolina, Georgia, Florida, Alabama, Mississippi, Louisiana, Arkansas, Missouri, Kentucky, Tennessee, Indiana, Illinois, Michigan, Wisconsin, Puerto Rico, and the Virgin Islands: August 1, 1965.

(3) For stations located in Oklahoma and Texas: October 1, 1965.

(4) For stations located in Kansas and Nebraska: December 1, 1965.

(5) For stations located in Iowa and South Dakota: February 1, 1966.

(6) For stations located in Minnesota and North Dakota: April 1, 1966.

(7) For stations located in Wyoming: June 1, 1966.

(8) For stations located in Montana: August 1, 1966.

(9) For stations located in Idaho: October 1, 1966.

(10) For stations located in Washington: December 1, 1966.

(11) For stations located in Oregon: February 1, 1964.

(12) For stations located in Alaska, Hawaii and Guam: April 1, 1964.

(13) For stations located in Colorado: June 1, 1964.

(14) For stations located in New Mexico: August 1, 1964.

(15) For stations located in Utah: October 1, 1964.

(16) For stations located in Arizona: December 1, 1964.

(17) For stations located in Nevada: February 1, 1965.

(18) For stations located in California: April 1, 1965.

(e) Licenses issued before June 1, 1962, for television translator stations located in the states listed in paragraph (d) (2) through (13) of this section, regardless of the expiration date specified in the license, will expire at 3:00 a.m., eastern standard time, on the dates specified in those subparagraphs for the respective states.

(f) Licenses for instructional television fixed stations will be issued for a period of 5 years beginning with the date of the grant.

§ 74.16 Temporary extension of station licenses.

Where there is pending before the Commission any application, investigation or proceeding which, after hearing, might lead to or make necessary the modification of, revocation of, or the refusal to renew an existing auxiliary or experimental broadcast station license or a television broadcast translator station license, the Commission may, in its discretion, grant a temporary extension of such license: *Provided, however,* That no such temporary extension shall be construed as a finding by the Commission that the operation of any radio station thereunder will serve public interest, convenience, and necessity beyond the express terms of such temporary extension of license: *And provided further,* That such temporary extension of license will in no wise affect or limit the action of the Commission with respect to any pending application or proceeding.

SPECIAL PROVISIONS

§ 74.21 Operation during an emergency.

(a) In an emergency where normal communication facilities have been disrupted or destroyed by storms, floods or other disasters, the stations licensed under the rules of this part may be operated for the purpose of transmitting essential communications intended to alleviate distress, dispatch aid, assist in rescue operations, maintain order, or otherwise promote the safety of life and property. In the course of such operation, a station of any class may communicate with stations of other classes and in other services. However, such operation shall be conducted only on the frequency or frequencies for which the station is licensed and the power used shall not exceed the maximum power authorized in the station license. In cases where such operation involves the use of frequencies shared with other stations, licensees are expected to cooperate fully to avoid unnecessary or disruptive interference.

(b) Whenever such operation involves communications of a nature other than those for which the station is licensed to perform, the licensee shall, at the earliest practicable time, notify the Commission in Washington, D.C., and the Engineer-in-charge of the radio district in which the operation occurs, of the nature of the emergency and the use to which the station is being put and shall subsequently notify the same offices when the emergency operation has been terminated.

(c) Emergency operation undertaken pursuant to the provisions of this section shall be discontinued as soon as substantially normal communications facilities have been restored. The Commission may at any time order discontinuance of such operation.

Subpart A—Experimental Television Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

§ 74.101 Experimental television broadcast station.

The term "experimental television broadcast station" means a station licensed for experimental transmission of transient visual images of moving or fixed objects for simultaneous reception and reproduction by the general public.

NOTE: The transmission of synchronized sound (aural broadcast) is considered an essential phase of television broadcast and one license will authorize both visual and aural broadcast.

§ 74.102 Purpose.

A license for an experimental television broadcast station will be issued for the purpose of carrying on research and experimentation for the advancement of television broadcasting which may include tests of equipment, training of personnel, and experimental programs as are necessary for the experimentation.

§ 74.103 Frequency assignment.

(a) Frequencies allocated to television broadcasting and the various categories of television auxiliary stations, in the Commission's Table of Frequency Allocations (Part 2 of this chapter), may be assigned respectively to experimental television broadcast and experimental television auxiliary stations.

(b) More than one frequency may be assigned upon a satisfactory showing of the need therefor.

(c) Frequencies best suited to the purpose of the experimentation and on which there appears to be the least likelihood of interference to established stations shall be selected.

(d) In a case of important experimentation which cannot be feasibly conducted on frequencies allocated to television broadcasting or the various categories of television auxiliary stations, the Commission may authorize an experimental television station of any class to operate on other frequencies upon a satisfactory showing of the need therefor and a showing that the proposed operation can be conducted without causing harmful interference to established services: *Provided, however,* That experimental operation which looks toward the development of radio transmitting apparatus or the rendition of any type of regular service using such frequencies will not be authorized prior to a determination by the Commission that the development of such apparatus or the rendition of such service would serve the public interest.

ADMINISTRATIVE PROCEDURE

§ 74.111 Cross reference.

See §§ 74.11 to 74.16.

§ 74.112 Supplementary statement with application for construction permit.

A supplementary statement shall be filed with and made a part of each application for construction permit for any experimental television broadcast station confirming the applicant's understanding:

(a) That all operation upon the frequency requested is for experimental purposes only.

(b) That the frequency requested may not be the best suited to the particular experimental work to be carried on.

(c) That the frequency requested need not be allocated for any service that may be developed as a result of the experimental operation.

(d) That any frequency which may be assigned is subject to change without advance notice or hearing.

(e) That any authorization issued pursuant to the application may be cancelled at any time without notice or hearing.

(Sec. 319, 48 Stat. 1089, as amended; 47 U.S.C. 319)

§ 74.113 Supplementary reports with application for renewal of license.

(a) A report shall be filed with each application for renewal of experimental television broadcast station license which shall include a statement of each of the following:

(1) Number of hours operated.

(2) Full data on research and experimentation conducted including the types of transmitting and studio equipment used and their mode of operation.

(3) Data on expense of research and operation during the period covered.

(4) Power employed, field intensity measurements and visual and aural observations and the types of instruments and receivers utilized to determine the station service area and the efficiency of the respective types of transmissions.

(5) Estimated degree of public participation in reception and the results of observations as to the effectiveness of types of transmission.

(6) Conclusions, tentative and final.

(7) Program for further developments in television broadcasting.

(8) All developments and major changes in equipment.

(9) Any other pertinent developments.

(b) Special or progress reports shall be submitted from time to time as the Commission shall direct.

(Sec. 308, 48 Stat. 1084, as amended; 47 U.S.C. 308)

LICENSING POLICIES

§ 74.131 Licensing requirements, necessary showing.

(a) An applicant for a new experimental television broadcast station, change in facilities of any existing station, or modification of license is required to make a satisfactory showing of compliance with the general requirements of the Communications Act of 1934, as amended, as well as the following:

(1) That the applicant has a definite program of research and experimentation in the technical phases of television broadcasting which indicates reasonable promise of substantial contribution to the developments of the television art.

(2) That upon the authorization of the proposed station the applicant can and will proceed immediately with its program of research and experimentation.

(3) That the transmission of signals by radio is essential to the proposed program of research and experimentation.

(4) That the program of research and experimentation will be conducted by qualified personnel.

(b) A license for an experimental television broadcast station will not authorize exclusive use of any frequency. In case interference would be caused by simultaneous operation of stations licensed experimentally, such licensees shall endeavor to arrange satisfactory time division. If such agreement cannot be reached, the Commission will determine and specify the time division.

(c) A license for an experimental television broadcast station will be issued only on the condition that no objectionable interference will result from the transmissions of the station to the regular program transmissions of television broadcast stations. It shall at all times be the duty of the licensee of an experimental television broadcast station to ascertain that no interference will result from the transmissions of its station. With regard to interference with the transmissions of an experimental television broadcast station or the experimental or test transmissions of a television broadcast station, the licensees shall make arrangements for operations to avoid interference.

§ 74.132 Power limitations.

Experimental television broadcast stations will be licensed with a power output not in excess of that necessary to render satisfactory service. The license for these stations will specify the maximum authorized power. The operating power shall not be greater than necessary to carry on the service and in no event more than 5 percent above the maximum power specified. Engineering standards have not been established for these stations. The efficiency factor for the last radio stage of transmitters employed will be subject to individual determination but shall be in general agreement with values normally employed for similar equipment operated within the frequency range authorized.

§ 74.133 Emission authorized.

In case emission of a different type than that specified in the license is necessary or desirable in carrying on any phases of experimentation, application setting out fully the needs shall be made by informal application.

§ 74.134 Multiple ownership.

No persons (including all persons under common control) shall control, directly or indirectly, two or more experimental television broadcast stations (other than television relay broadcast stations) unless a showing is made that the character of the programs of research requires a licensing of two or more separate stations.

EQUIPMENT

§ 74.151 Equipment changes.

The licensee of an experimental television broadcast station may make any changes in the equipment that are deemed desirable or necessary provided:

(a) That the operating frequency is not permitted to deviate more than the allowed tolerance;

(b) That the emissions are not permitted outside the authorized band;

(c) That the power output complies with the license and the regulations governing the same; and

(d) That the transmitter as a whole or output power rating of the transmitter is not changed.

TECHNICAL OPERATION AND OPERATORS

§ 74.161 Frequency tolerance.

The licensee of an experimental television broadcasting station shall maintain the operating frequency of its station within the tolerance specified in the instrument of authorization.

§ 74.162 Frequency monitors and measurements.

The licensee of an experimental television broadcast station shall provide the

necessary means for determining that the frequency of the station is within the allowed tolerance. The date and time of each frequency check, the frequency as measured, and a description or identification of the method employed shall be entered in the station log. Sufficient observations shall be made to insure that the assigned carrier frequency is maintained within the prescribed tolerance.

§ 74.163 Time of operation.

(a) A licensee of an experimental television broadcast station is not required to adhere to a regular schedule of operation but shall actively conduct a program of research and experimentation.

(b) The program of research and experimentation as offered by an applicant in compliance with the requirements for obtaining a license for an experimental television broadcast station shall be adhered to in the main, unless the licensee is authorized to do otherwise by the Commission.

(c) The Commission may from time to time require that a station licensed experimentally conduct such experiments as are deemed desirable and reasonable for the development of the service.

§ 74.164 Station inspection.

The licensee of each experimental television broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 74.165 Station and operator licenses; posting of.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the equipment or manner of operation of the station shall be posted so that all terms thereof are visible in a conspicuous place in the room in which the transmitter is located. However, if the station is licensed for portable-mobile operation, the station license or a photo copy thereof shall be affixed to the equipment or kept in the possession of the operator on duty at the transmitter. If a photo copy is used, the original license shall be available for inspection by an authorized Government representative.

(b) The orignal license of each station operator shall be posted at the place where he is on duty: *Provided, however,* If the original license of a station operator is posted at another radio transmitting station in accordance with the rules governing that class of station and is there available for inspection by an authorized Commission representative, or if the station operated is licensed for portable-mobile operation, a verification card (Form 758–F) is acceptable in lieu of the posting of such license.

NOTE: The term portable-mobile as here used is intended to include any type of portable or mobile operation.

§ 74.166 Operator requirements.

One or more radio operators holding radiotelephone first-class or radiotelephone second-class operator licenses shall be on duty at the place where the transmitting apparatus of any experimental television broadcast station is located and in actual charge of its operation. The licensed operator on duty and in charge of a broadcast transmitter may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of operator's license which he holds and the rules and regulations governing such stations. However, such duties shall in no wise interfere with the operation of the broadcast transmitter.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.167 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41 and 17.42 of this chapter.

§ 74.168 Additional orders.

In case the rules contained in this part do not cover all phases of operation or experimentation with respect to external effects, the Commission may make supplemental or additional orders in each case as may be deemed necessary.

OTHER OPERATING REQUIREMENTS

§ 74.181 Station records.

(a) The licensee of each experimental television broadcast station shall maintain adequate records of the operation, including:

(1) Hours of operation.
(2) Program transmitted.
(3) Frequency check.
(4) Pertinent remarks concerning transmission.
(5) In case of relay or pickup station, an entry giving points of program origination and receiver location shall be included.
(6) Research and experimentation conducted.

(b) Where an antenna structure(s) is required to be illuminated, see § 17.38 of this chapter.

(c) Station records shall be retained for a period of two years.

§ 74.182 Charges.

No charges, either direct or indirect, shall be made by the licensee of an experimental television broadcast station for the production or transmission of either aural or visual programs transmitted by such station except that this section shall not apply to the transmission of commercial programs by an experimental television relay or pickup broadcast station for retransmission by a television broadcast station.

§ 74.183 Station identification.

Each experimental television broadcast station shall make aural and visual announcements of its call letters and location at the beginning and end of each period of operation, and during operation, at least once every hour.

§ 74.184 Rebroadcasts.

(a) The term "rebroadcast" means reception by radio of the program of a radio station (including a television station), and the simultaneous or subsequent retransmission of such program by a broadcast station.

NOTE 1: As used in this section, the word "program" includes any complete program or part thereof.

NOTE 2: In case a program is transmitted from its point of origin to a broadcast station primarily by telephone facilities in which a section of such transmission is by radio, the broadcasting of this program is not considered a rebroadcast. The broadcasting of a program relayed by a remote pickup broadcast station is not considered a rebroadcast.

(b) No licensee of any experimental television broadcast station shall rebroadcast the program of any radio station without written authority having first been obtained from the Commission upon application. Informal application may be employed.

(c) An application for authority to rebroadcast the program of any radio station shall be accompanied by written consent or certification of consent of the licensee of the station originating the program.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

Subpart B—Experimental Facsimile Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

§ 74.201 Facsimile broadcast station.

The term "facsimile broadcast station" means a station licensed to transmit images of still objects for record reception by the general public.

§ 74.202 Frequency assignment.

(a) Frequencies allocated to broadcasting and the various categories of broadcast auxiliary stations, in the Commission's Table of Frequency Allocations (Part 2 of this chapter), may be assigned respectively to experimental facsimile broadcast or experimental facsimile broadcast auxiliary stations.

(b) More than one frequency may be assigned upon a satisfactory showing of the need therefor.

(c) Frequencies best suited to the purpose of the experimentation and on which there appears to be the least likelihood of interference to established stations shall be selected.

(d) In a case of important experimentation which cannot be feasibly conducted on frequencies allocated to broadcasting or the various categories of broadcast auxiliary stations, the Commission may authorize an experimental facsimile broadcast station of any class to operate on other frequencies upon a satisfactory showing of the need therefor and a showing that the proposed operation can be conducted without causing harmful interference to established services: *Provided, however,* That experimental operation which looks toward the development of radio transmitting apparatus or the rendition of any type of regular service using such frequencies will not be authorized prior to a determination by the Commission that the

development of such apparatus or the rendition of such service would serve the public interest.

ADMINISTRATIVE PROCEDURE

§ 74.211 Cross reference.

See §§ 74.11 to 74.16.

§ 74.212 Supplementary statement with application for construction permit.

A supplementary statement shall be filed with and made a part of each application for construction permit for any experimental facsimile broadcast station confirming the applicant's understanding:

(a) That all operation upon the frequency requested is for experimental purposes only.

(b) That the frequency requested may not be the best suited to the particular experimental work to be carried on.

(c) That the frequency requested need not be allocated for any service that may be developed as a result of the experimental operation.

(d) That any frequency which may be assigned is subject to change without advance notice or hearing.

(e) That any authorization issued pursuant to the application may be cancelled at any time without notice or hearing.

(Sec. 319, 48 Stat. 1089, as amended; 47 U.S.C. 319)

§ 74.213 Supplemental report with renewal application.

A supplemental report shall be filed with and made a part of each application for renewal of license and shall include statements of the following:

(a) Number of hours operated for transmission of facsimile programs.

(b) Comprehensive report of research and experimentation conducted.

(c) Conclusions and program for further developments of the facsimile broadcast service.

(d) All developments and major changes in equipment.

(e) Any other pertinent developments.

(Sec. 308, 48 Stat. 1084, as amended; 47 U.S.C. 308)

LICENSING POLICIES

§ 74.231 Licensing requirements, necessary showing.

(a) An applicant for a construction permit for a new experimental facsimile broadcast station, change in facilities of any existing station, or modification of license is required to make a satisfactory showing of compliance with the general requirements of the Communications Act of 1934, as amended, as well as with regard to the following:

(1) That the applicant has a program of research and experimentation which indicates reasonable promise of substantial contribution to the development of the facsimile broadcast service.

(2) That sufficient facsimile recorders will be distributed to accomplish the experimental program proposed.

(3) That the program of research and experimentation will be conducted by qualified personnel.

(b) A license for an experimental facsimile broadcast station will not authorize exclusive use of any frequency. In case interference would be caused by simultaneous operation of stations licensed experimentally, such licensees shall endeavor to arrange satisfactory time division. If such agreement cannot be reached, the Commission will determine and specify the time division.

§ 74.232 Power limitations.

Experimental facsimile broadcast stations will be licensed with a power output not in excess of that necessary to render satisfactory service. The license for these stations will specify the maximum authorized power. The operating power shall not be greater than necessary to carry on the service and in no event more than 5 percent above the maximum power specified. Engineering standards have not been established for these stations. The efficiency factor for the last radio stage of transmitters employed will be subject to individual determination but shall be in general agreement with values normally employed for similar equipment operated within the frequency range authorized.

§ 74.233 Emission authorized.

In case emission of a different type than that specified in the license is necessary or desirable in carrying on any phases of experimentation, application setting out fully the needs shall be made by informal application.

§ 74.234 Multiple ownership.

No persons (including all persons under common control) shall control, directly or indirectly, two or more experimental facsimile broadcast stations unless a showing is made that the character of the programs of research requires a licensing of two or more separate stations.

EQUIPMENT

§ 74.251 Equipment changes.

The licensee of an experimental facsimile broadcast station may make any changes in the equipment that are deemed desirable or necessary provided:

(a) That the operating frequency is not permited to deviate more than the allowed tolerance;

(b) That the emissions are not permitted outside the authorized band;

(c) That the power output complies with the license and the regulations governing the same; and

(d) That the transmitter as a whole or output power rating of the transmitter is not changed.

TECHNICAL OPERATION AND OPERATORS

§ 74.261 Frequncy tolerance.

The licensee of an experimental facsimile broadcasting station shall maintain the operating frequency of its station within the tolerance specified in the instrument of authorization.

§ 74.262 Frequency monitors and measurements.

The licensee of an experimental facsimile broadcast station shall provide the necessary means for determining that the frequency of the station is within the allowed tolerance. The date and time of each frequency check, the frequency as measured, and a description or identification of the method employed shall be entered in the station log. Sufficient observations shall be made to insure that the assigned carrier frequency is maintained within the prescribed tolerance.

§ 74.263 Time of operation.

(a) A licensee of an experimental facsimile broadcast station is not required to adhere to a regular schedule of operation but shall actively conduct a program of research and experimentation.

(b) The program of research and experimentation as offered by an applicant in compliance with the requirements for obtaining a license for an experimental facsimile broadcast station shall be adhered to in the main, unless the licensee is authorized to do otherwise by the Commission.

(c) The Commission may from time to time require that a station licensed experimentally conduct such experiments as are deemed desirable and reasonable for the development of the service.

§ 74.264 Station inspection.

The licensee of each experimental facsimile broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 74.265 Station and operator licenses; posting of.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the equipment or manner of operation of the station shall be posted so that all terms thereof are visible in a conspicuous place in the room in which the transmitter is located.

(b) The original license of each station operator shall be posted at the place where he is on duty: *Provided, however,* If the original license of a station operator is posted at another radio transmitting station in accordance with the rules governing that class of station and is there available for inspection by an authorized Commission representative, a verification card (Form 758–F) is acceptable in lieu of the posting of such license.

§ 74.266 Operator requirements.

One or more radio operators holding radiotelephone first-class or radiotelephone second-class operator licenses shall be on duty at the place where the transmitting apparatus of any experimental facsimile broadcast station is located and in actual charge of its operation. The licensed operator on duty and in charge of a broadcast transmitter may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of operator's license which he holds and the rules and regulations governing such stations. However, such duties shall in no wise interfere with the operation of the broadcast transmitter.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.267 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of this chapter.

§ 74.268 Additional orders.

In case the rules contained in this part do not cover all phases of operation or experimentation with respect to external effects, the Commission may make supplemental or additional orders in each case as may be deemed necessary.

OTHER OPERATING REQUIREMENTS

§ 74.281 Station records.

(a) The licensee of each experimental facsimile broadcast station shall maintain adequate records of the operation, including:

(1) Hours of operation.

(2) Program transmitted.

(3) Frequency check.

(4) Pertinent remarks concerning transmission.

(5) Research and experimentation conducted.

(b) When an antenna structure(s) is required to be illuminated, see § 17.38 of this chapter.

(c) Station records shall be retained for a period of two years.

§ 74.282 Charges.

(a) A licensee of an experimental facsimile broadcast station shall not make any charge, directly or indirectly, for the transmission of programs.

(b) No licensee of any standard or FM broadcast station shall make any additional charge, directly or indirectly, for the transmission of some phase of its programs by an associated experimental facsimile broadcast station.

§ 74.283 Station identification.

Each experimental facsimile broadcast station shall transmit visual information which will permit it to be identified at the beginning and end of each period of operation, and during operation, at least once every hour.

§ 74.284 Rebroadcasts.

(a) The term "rebroadcast" means reception by radio of the program of a radio station (including a television station), and the simultaneous or subsequent retransmission of such program by a broadcast station.

NOTE 1: As used in this section, the word "program" includes any complete program or part thereof.

NOTE 2: In case a program is transmitted from its point of origin to a broadcast station primarily by telephone facilities in which a section of such transmission is by radio, the broadcasting of this program is not considered a rebroadcast. The broadcasting of a program relayed by a remote pickup broadcast station is not considered a rebroadcast.

(b) No licensee of any experimental facsimile broadcast station shall rebroadcast the program of any radio station without written authority having first been obtained from the Commission upon application. Informal application may be employed.

(c) An application for authority to rebroadcast the program of any radio station shall be accompanied by written consent or certification of consent of the licensee of the station originating the program.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

Subpart C—Developmental Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

§ 74.301 Developmental broadcast station.

The term "developmental broadcast station" means a station licensed experimentally to carry on development and research primarily in radiotelephony for the advancement of the broadcast services.

§ 74.302 Frequency assignment.

(a) Frequencies allocated to the various classes of aural broadcasting stations and broadcast auxiliary stations, in the Commission's Table of Frequency Allocations (Part 2 of this chapter), may be assigned to developmental broadcast stations.

(b) More than one frequency may be assigned upon a satisfactory showing of the need therefor.

(c) Frequencies best suited to the purpose of the experimentation and on which there appears to be the least likelihood of interference to established stations shall be selected.

(d) In a case of important experimentation which cannot be feasibly conducted on frequencies allocated to the various classes of aural broadcasting stations and broadcast auxiliary stations, the Commission may authorize a developmental broadcast station to operate on other frequencies upon a satisfactory showing of the need therefor and a showing that the proposed operation can be conducted without causing harmful interference to established services: *Provided, however,* That experimental operation which looks toward the development of radio transmitting apparatus or the rendition of any type of regular service using such frequencies will not be authorized prior to a determination by the Commission that the development of such apparatus or the rendition of such service would serve the public interest.

ADMINISTRATIVE PROCEDURE

§ 74.311 Cross reference.

See §§ 74.11 to 74.16.

§ 74.312 Supplementary statement with application for construction permit.

A supplementary statement shall be filed with and made a part of each application for construction permit for any developmental broadcast station confirming the applicant's understanding:

(a) That all operation upon the frequency requested is for experimental purposes only.

(b) That the frequency requested may not be the best suited to the particular experimental work to be carried on.

(c) That the frequency requested need not be allocated for any service that may be developed as a result of the experimental operation.

(d) That any frequency which may be assigned is subject to change without advance notice or hearing.

(e) That any authorization issued pursuant to the application may be canceled at any time without notice or hearing.

(Sec. 319, 48 Stat. 1089, as amended; 47 U.S.C. 319)

§ 74.313 Supplemental report with renewal application.

A supplemental report shall be filed with and made a part of each application for renewal of license and shall include statements of the following, among others:

(a) The number of hours operated.

(b) Comprehensive report on research and experiments conducted.

(c) Conclusions and program for further development of the broadcast service.

(d) All developments and major changes in equipment.

(e) Any other pertinent developments.

(Sec. 308, 48 Stat. 1084, as amended, 47 U.S.C. 308)

LICENSING POLICIES

§ 74.331 Licensing requirements; necessary showing.

(a) An applicant for a construction permit for a new developmental broadcast station, change of facilities or modification of an existing license is required to make a satisfactory showing of compliance with the general requirements of the Communications Act of 1934, as amended, as well as with regard to the following:

(1) That the applicant has a program of research and experimentation which can best be carried on under the license requested.

(2) That the program of research has reasonable promise of substantial contribution to the development of broadcasting.

(3) That the program of research and experimentation will be conducted by qualified personnel.

(b) A license for a developmental broadcast station will not authorize exclusive use of any frequency. In case interference would be caused by simultaneous operation of stations licensed experimentally, such licensees shall endeavor to arrange satisfactory time division. If such agreement cannot be reached, the Commission will determine and specify the time division.

§ 74.332 Power limitations.

Developmental broadcast stations will be licensed with a power output not in excess of that necessary to render satisfactory service. The license for these stations will specify the maximum authorized power. The operating power shall not be greater than necessary to carry on the service and in no event

more than 5 percent above the maximum power specified. Engineering standards have not been established for these stations. The efficiency factor for the last radio stage of transmitters employed will be subject to individual determination but shall be in general agreement with values normally employed for similar equipment operated within the frequency range authorized.

§ 74.333 Emission authorized.

In case emission of a different type than that specified in the license is necessary or desirable in carrying on any phases of experimentation, application setting out fully the needs shall be made by informal application.

EQUIPMENT

§ 74.351 Equipment changes.

The licensee of a developmental broadcast station may make any changes in the equipment that are deemed desirable or necessary provided:

(a) That the operating frequency is not permitted to deviate more than the allowed tolerance;

(b) That the emissions are not permitted outside the authorized band;

(c) That the power output complies with the license and the regulations governing the same; and

(d) That the transmitter as a whole or output power rating of the transmitter is not changed. This limitation shall not apply to developmental broadcast stations licensed to operate in connection with the development and testing of commercial broadcast equipment.

TECHNICAL OPERATION AND OPERATORS

§ 74.361 Frequency tolerance.

The licensee of a developmental broadcasting station shall maintain the operating frequency of its station within the tolerance specified in the instrument of authorization.

§ 74.362 Frequency monitors and measurements.

The licensee of a developmental broadcast station shall provide the necessary means for determining that the frequency of the station is within the allowed tolerance. The date and time of each frequency check, the frequency as measured, and a description or identification of the method employed shall be entered in the station log. Sufficient observations shall be made to insure that the assigned carrier frequency is maintained within the prescribed tolerance.

§ 74.363 Time of operation.

(a) A licensee of a developmental broadcast station is not required to adhere to a regular schedule of operation but shall actively conduct a program of research and experimentation. However, licensees of developmental broadcast stations which are licensed to conduct special intermittent experiments, such as the development and testing of commercial broadcast equipment, are authorized to operate only when there is a need therefor.

(b) The program of research and experimentation as offered by an applicant in compliance with the requirements for obtaining a license for a developmental broadcast station shall be adhered to in the main, unless the licensee is authorized to do otherwise by the Commission.

(c) The Commission may from time to time require that a station licensed experimentally conduct such experiments as are deemed desirable and reasonable for the development of the service.

§ 74.364 Station inspection.

The licensee of each developmental broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 74.365 Station and operator licenses; posting of.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the equipment or manner of operation of the station shall be posted so that all terms thereof are visible in a conspicuous place in the room in which the transmitter is located. However, if the station is licensed for portable-mobile operation, the station license or a photo copy thereof shall be affixed to the equipment or kept in the possession of the operator on duty at the transmitter. If a photo copy is used, the original license shall be available for inspection by an authorized Government representative.

(b) The original license of each station operator shall be posted at the place where he is on duty: *Provided, however,* If the original license of a station operator is posted at another radio transmitting station in accordance with the rules governing that class of station and is there available for inspection by an authorized Commission representative, or if the station operated is licensed for portable-mobile operation, a verification card (Form 758–F) is acceptable in lieu of the posting of such license.

NOTE: The term portable-mobile as here used is intended to include any type of portable or mobile operation.

§ 74.366 Operator requirements.

One or more radio operators holding radiotelephone first-class or radiotelephone second-class operator licenses shall be on duty at the place where the transmitting apparatus of any developmental broadcast station is located and in actual charge of its operation. The licensed operator on duty and in charge of a broadcast transmitter may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of operator's license which he holds and the rules and regulations governing such stations. However, such duties shall in no wise interfere with the operation of the broadcast transmitter.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.367 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of this chapter.

§ 74.368 Additional orders.

In case the rules contained in this part do not cover all phases of operation or experimentation with respect to external effects, the Commission may make supplemental or additional orders in each case as may be deemed necessary.

OTHER OPERATING REQUIREMENTS

§ 74.381 Station records.

(a) The licensee of each developmental broadcast station shall maintain adequate records of the operation, including:

(1) Hours of operation.

(2) Program transmitted.

(3) Frequency check.

(4) Pertinent remarks concerning transmission.

(5) In case of relay or remote pickup station, an entry giving points of program origination and receiver location shall be included.

(6) Research and experimentation conducted.

(b) Where an antenna structure(s) is required to be illuminated, see § 17.38 of this chapter.

(c) Station records shall be retained for a period of two years.

§ 74.382 Program service; charges prohibited; announcements.

(a) A licensee of a developmental broadcast station shall broadcast programs only when they are necessary to the experiments being conducted. No regular program service shall be broadcast unless specifically authorized. If the license authorizes the carrying of programs, the developmental broadcast station may transmit the programs of a standard or FM broadcast station or networks provided that during the broadcast a statement is made identifying the station or network originating the program (by giving the call letters of the station or name of the network) and announcing that the program is being broadcast in connection with the experimental operation of a developmental broadcast station.

(b) No licensee of any standard or FM broadcast station shall make any additional charge, directly or indirectly, for the transmission of programs by a developmental broadcast station.

(c) The provisions of paragraphs (a) and (b) of this section shall be applicable to rebroadcasts of the programs of a standard or FM broadcast station or network by a developmental broadcast station.

§ 74.383 Station identification.

Each developmental broadcast station shall announce its call letters at the beginning and end of each period of operation, and during operation, at least once every hour.

§ 74.384 Rebroadcasts.

(a) The term "rebroadcast" means reception by radio of the program of a radio station (including a television station), and the simultaneous or sub-

sequent retransmission of such program by a broadcast station.

NOTE 1: As used in this section, the word "program" includes any complete program or part thereof.

NOTE 2: In case a program is transmitted from its point of origin to a broadcast station primarily by telephone facilities in which a section of such transmission is by radio, the broadcasting of this program is not considered a rebroadcast. The broadcasting of a program relayed by a remote pickup broadcast station is not considered a rebroadcast.

(b) No licensee of any developmental broadcast station shall rebroadcast the program of any radio station without written authority having first been obtained from the Commission upon application. Informal application may be employed.

(c) An application for authority to rebroadcast the program of any radio station shall be accompanied by written consent or certification of consent of the licensee of the station originating the program.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

Subpart D—Remote Pickup Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

§ 74.401 Definitions.

Associated broadcasting station. The broadcasting station with which a remote pickup broadcast base or mobile station is licensed as an auxiliary and with which it is principally used.

Attended operation. Operation of a station by a qualified operator on duty at the place where the transmitting apparatus is located with the transmitter in plain view of the operator.

Operational communications. Communications related to the technical operation of a broadcasting station and its auxiliaries, other than the transmission of program material and cues and orders directly concerned therewith.

Remote control operation. Operation of a station by a qualified operator at a control position from which the transmitter is not visible but which control position is equipped with suitable control and telemetering circuits so that the essential functions which could be performed at the transmitter can also be performed from the control point.

Remote pickup broadcast base station. A base station licensed for communicating with remote pickup broadcast mobile stations.

Remote pickup broadcast mobile station. A land mobile station licensed for the transmission of program material and related communications from the scene of events, which occur outside a studio, to broadcasting stations and for communicating with other remote pickup broadcast base and mobile stations. (As used in this part, land mobile station includes hand-carried, pack-carried, and other portable transmitters.)

Remote pickup broadcast stations. The term "remote pickup broadcast station" as used in this subpart includes "remote pickup broadcast base station" and "remote pickup broadcast mobile station" as defined in this section.

Studio. Any room or series of rooms equipped for the regular production of broadcast programs of various kinds. A broadcasting booth at a stadium, convention hall, church, or other similar place is not considered to be a studio.

§ 74.402 Frequency assignment.

(a) The following frequencies are allocated for assignment to remote pickup broadcast base and mobile stations:

(1)

Group A (kc/s)
[1] 1606
1622
1646

(2)

Group D (Mc/s)	Group E (Mc/s)	Group F (Mc/s)	Group G (Mc/s)	Group H (Mc/s)
[2] 25.87	[2] 25.91	[2] 25.95	[2] 25.99	[2] 26.03
26.15	26.17	26.19	26.21	26.23
26.25	26.27	26.29	26.31	26.33
26.35	26.37	26.39	26.41	26.43

(3)

Group I (Mc/s)	Group J (Mc/s)
[2] 26.07	[2] 26.09
26.11	26.13
26.45	26.47

(4)

Group K (Mc/s)		
[3] 152.87	[3] 153.17	[5] 161.64
[3] 152.93	[3] 153.23	[5] 161.67
[3] 152.99	[3] 153.29	[5] 161.70
[3] 153.05	[3] 153.35	[5] 161.73
[3] 153.11		[5] 161.76

(5)

Group L (Mc/s)	Group M (Mc/s)
[4] 166.25	[4] 170.15

(6)

Group N (Mc/s)			
450.05	450.55	455.05	455.55
450.15	450.65	455.15	455.65
450.25	450.75	455.25	455.75
450.35	450.85	455.35	455.85
450.45	450.95	455.45	455.95

[1] Subject to the condition that no harmful interference is caused to the reception of standard broadcast stations.

[2] Subject to the condition that no harmful interference is caused to the reception of broadcasting stations.

[3] Subject to the condition that no harmful interference is caused to the Industrial Radio Services.

[4] Operation on the frequencies 166.25 Mc/s and 170.15 Mc/s is not authorized (i) within the area bounded on the west by the Mississippi River, on the north by the parallel of latitude 37°30′ N., and on the east and south by that arc of the circle with center at Springfield, Ill., and radius equal to the airline distance between Springfield, Ill., and Montgomery, Alabama, subtended between the foregoing west and north boundaries; (ii) within 150 miles of New York City; and (iii) in Alaska or outside the continental United States; and is subject to the condition that no harmful interference is caused to government radio stations in the band 162–174 Mc/s.

[5] These frequencies may not be used by remote pickup stations in Puerto Rico or the Virgin Islands. In other areas, certain existing stations in the Public Safety and Land Transportation Radio Services have been permitted to continue operation on these frequencies on condition that no harmful interference is caused to remote pickup broadcast stations.

(b) The following frequencies are allocated for assignment to remote pickup base and mobile stations in Puerto Rico and the Virgin Islands only:

(Mc/s)	(Mc/s)	(Mc/s)
160.89	161.07	161.25
160.95	161.13	161.31
161.01	161.19	161.37

NOTE 1: These frequencies are shared with the Land Transportation Radio Service.

(c) A licensee is not limited with respect to the number of remote pickup broadcast stations which may be licensed for operation in a single area and each such station may be assigned one or more frequencies: *Provided, however,* That such frequency assignments shall be limited to those within a single frequency Group in any subparagraph of paragraph (a) of this section. This limitation does not preclude the assignment of frequencies listed in different subparagraphs to the same licensee. Applicants shall request the assignment of only those frequencies on which operation is contemplated and the transmitter shall be suitably equipped to operate on all assigned frequencies.

(d) Remote pickup broadcast stations will not be granted exclusive frequency assignments, and the same frequency or frequencies may be assigned to other licensees in the same area.

§ 74.403 Frequency selection to avoid interference.

(a) Where two or more remote pickup broadcast stations are licensed for the same frequency or group of frequencies in the same area and when simultaneous operation is contemplated, the licensees shall endeavor to select frequencies or schedule operation in such manner as to avoid mutual interference. If a mutual agreement to this effect cannot be reached the Commission shall be notified and it will specify the frequency or frequencies on which each station is to be operated.

(b) The following order of priority of transmissions shall be observed on all frequencies except those listed in § 74.402 (a) (3):

(1) The transmission of program material for broadcast.

(2) The transmission of cues and orders immediately necessary thereto.

(3) Operational communications.

(4) Tests or drills to check the performance of stand-by emergency circuits.

NOTE: During an emergency or impending emergency, transmissions directly related to the safety of life and property shall take precedence over all other transmissions.

ADMINISTRATIVE PROCEDURE

§ 74.411 Cross reference.

See § 74.11 to 74.16.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

§ 74.431 Permissible service.

(a) Remote pickup broadcast mobile stations may be used for the transmission of broadcast program material from the scene of events which occur outside a studio and for the transmission of cues and orders and other related com-

munications necessary to the accomplishment of such broadcasts. The program material transmitted over a remote pickup broadcast mobile station shall be intended for simultaneous or delayed broadcast either by its associated broadcasting station or some other broadcasting station or stations. Editing or rearranging such material to suit the needs of the broadcasting station is not precluded. A remote pickup broadcast mobile station may communicate with the broadcasting station with which it is operating, with the base station or stations with which it is associated, and with other remote pickup broadcast mobile stations. Remote pickup broadcast mobile stations may relay the transmissions of an associated base station and other remote pickup broadcast mobile station.

(b) Remote pickup broadcast base stations may be used for the transmission of cues, orders, and instructions to remote pickup broadcast mobile stations for the purpose of dispatching them to the scenes of events to be broadcast, and directing their operation on the scene. Cueing may include the transmission of program material to the remote pickup unit, if necessary. Remote pickup broadcast base stations may also be used to relay transmissions to and from remote pickup broadcast mobile stations. Remote pickup broadcast base stations licensed pursuant to the provisions of § 74.432(d) (2) and (4) may communicate with other remote pickup broadcast base stations.

(c) Remote pickup broadcast base and mobile stations in Alaska, Guam, Hawaii, Puerto Rico, and the Virgin Islands may be used for any purpose related to the operation of the broadcasting station except for transmissions intended for direct reception by the general public.

(d) Remote pickup broadcast base and mobile stations may be used for operational communications on condition that such use does not interfere with the transmission of program material or preparations for the transmission of program material by other remote pickup stations.

(e) In the event of damage or impairment of the regular communication and program circuits of a broadcasting station due to storms, floods, fires, strikes, equipment failures, or other similar causes, remote pickup broadcast base and mobile stations may be used to provide such temporary circuits as may be needed to continue the broadcasting operation, pending the restoration of the regular circuits.

(f) Remote pickup base and mobile stations associated with broadcasting stations participating in the Emergency Broadcast System, or a similar emergency survival communications system, may be used: (1) For the transmission, for broadcasting, of warnings, instructions, and information relating to war, threat of war, a state of public peril or disaster, or other national, state, or local emergency constituting a threat to the safety of life or property; (2) for coordination of effort in connection with such broadcasts; and (3) for periodic tests or drills to ascertain the reliability of the circuit. Drills should not be conducted more than once a week and should be completed as quickly as possible. Individual transmitters may be turned on for alignment, adjustment, and repair whenever necessary. The conduct of a test or drill is subject to the condition that no interference will be caused to remote pickup broadcast base or mobile stations engaged in the transmission of program material, the preparation for such transmission, or other authorized operation.

(g) A remote pickup broadcast mobile station may be operated in conjunction with other broadcasting stations in the area in which it is licensed, at the discretion of the licensee. Remote pickup broadcast mobile stations may be operated in conjunction with broadcasting stations in other areas without prior authority of the Commission, provided that whenever the transmitting equipment will be out of the area in which it is licensed to operate, for more than one day, the Commission in Washington, D.C., the Engineer-in-charge of the radio district in which the remote pickup station is licensed to operate, and the Engineer-in-charge of the radio district in which the operation will occur, are notified in writing in advance of such operation. In cases where the decision to continue operation for more than one day is not made until the operation has begun, the advance notice requirement is waived and the written notice shall be given when such decision is made. The same Commission offices shall be notified when the transmitting equipment has been returned to its licensed area. The licensee of the remote pickup station shall be responsible for the proper use and operation of the equipment regardless of whether it is used with its associated broadcasting station or with other broadcasting stations in the same or in other areas.

(h) The license of a remote pickup broadcast base or mobile station authorizes operation on only one of the assigned frequencies at any one time. A licensee may operate two or more remote pickup broadcast base or mobile stations simultaneously on different frequencies.

§ 74.432 Licensing requirements.

(a) A license for a remote pickup broadcast base or mobile station will be issued only to the licensee of a standard, FM, or television broadcasting station. More than one remote pickup broadcast base and mobile station may be authorized to a single licensee. A separate license is required for each transmitter. An application for a new remote pickup broadcast base or mobile station shall specify the frequency or frequencies desired and the transmitter shall be capable of operating on each frequency requested.

(b) The applicant shall specify the broadcasting station with which the remote pickup station is to be used principally and the area of operation shall be considered to be the community which the associated broadcasting station is licensed to serve and the surrounding area considered to be served by the broadcast station. In cases where the applicant is the licensee of more than one class of broadcasting station (standard, FM, or television) in the same area, it may select one for designation as the associated broadcasting station; such designation does not preclude use with other broadcasting stations in the same area at the discretion of the licensee. Remote pickup broadcast mobile stations will not be licensed for operation in more than one area; such operation may be conducted pursuant to the provisions of § 74.431(f).

(c) Portable transmitters designed to be carried to the scene of events to be broadcast, and mobile transmitters, i.e., those permanently installed in mobile vehicles and capable of being operated while in motion as well as during halts at unspecified places, will both be licensed as remote pickup mobile stations. Portable transmitters should normally be stored at the studio or transmitter location of the associated broadcasting station when not in use. Vehicles equipped with mobile transmitters should be stored, when not in use, so as to be available for inspection upon request by any authorized representative of the Commission. In cases where a series of broadcasts are to be made from the same location, portable or mobile transmitters may be left at such locations for the duration of the series of broadcasts, provided that the transmitting apparatus is properly secured so that it may not be operated by unauthorized persons when unattended and it can be made available for inspection upon request by any authorized representatives of the Commission. Prior Commission authority shall be obtained for the installation of any transmitting antenna which will result in any increase in the height of an existing antenna supporting structure or will increase the height of any natural formation or manmade structure by more than 20 feet and will be in existence for more than 2 days.

(d) Transmitters permanently installed at fixed locations will be licensed as remote pickup broadcast base stations. The location of the transmitter will be specified in the station license and it may not be operated at any other location without prior authority of the Commission. Base stations will be licensed only for the following purposes:

(1) To provide communication with remote pickup broadcast mobile stations. Base stations licensed for this purpose will normally be located at the studio or transmitter location of the associated broadcasting station. Any of the frequencies listed in § 74.402 may be requested for this purpose.

(2) To provide one-way or two-way voice communication between the studio and transmitter of a broadcasting station which is the licensee of an aural or television broadcast STL station used for program transmission between the same two points, or to provide such voice communication between the point of origin and the destination of an aural or television broadcast intercity relay system operated by the same licensee. Such operation is limited to the frequencies listed in Groups I and J of § 74.402.

Automatic relay stations will not be authorized.

(3) To operate as program circuits between the studio and the transmitter, or to relay programs between broadcasting stations in Alaska, Guam, Hawaii, Puerto Rico, or the Virgin Islands. Except in emergencies, such uses are not permitted within the 48 contiguous United States or the District of Columbia. Any of the frequencies listed in § 74.402 as available in the above places may be requested by applicant.

(4) Base stations may be authorized at suitable locations to provide:

(i) Stand-by program circuits from places where official broadcasts may be made during a war, threat of war, or a state of public peril or disaster or other national, state, or local emergency constituting a threat to the safety of life and property; and

(ii) Circuits to interconnect broadcasting stations participating in the Emergency Broadcast System or a similar emergency survival communications system. An applicant may request the assignment of any of the frequencies listed in § 74.402 for this purpose.

§ 74.433 Temporary authorizations.

(a) Special temporary authority may be granted for operation, as a remote pickup broadcast station, of equipment already licensed to another class of station or equipment in use by a class of station which under the Communications Act of 1934 does not require a construction permit.

(b) An application for special temporary authority for the operation of a remote pickup broadcast station shall be filed with the Commission at least 10 days previous to the date of operation. Any application received within less than 10 days may be accepted upon due showing of sufficient reasons for the delay in submitting such request. The application shall set forth full particulars of the purpose for which the request is made and shall show the licensee, call letters, and type of equipment of the station proposed to be used and specify the frequency or frequencies, time and date, location, transmitter power, and type emission proposed and the purpose of the operation requested.

(c) An application for special temporary authority to operate another class of station as a remote pickup broadcast station shall specify a frequency or frequencies allocated in § 74.402: *Provided, however,* In case of events of national interest and importance which cannot be transmitted successfully on these frequencies, other frequencies under the jurisdiction of the Commission may be requested if it is shown that the operation thereon will not cause interference to established stations: *And provided further,* That no remote pickup operation will be authorized on frequencies employed in the emergency service or otherwise employed for the safety of life and property.

(d) An application for special temporary authority to operate equipment as a remote pickup broadcast station filed by a person other than the licensee of such equipment shall contain a statement to show that temporary control of the transmissions therefrom has been secured for the duration of the special operation proposed. An application for special temporary authority to operate another class of station as a remote pickup broadcast station filed by a person other than the licensee of a standard or FM broadcast station shall contain a statement to show which broadcast station or stations contemplate broadcast of the program proposed to be transmitted.

NOTE: Informal application may be employed under this section.

§ 74.434 Remote control operation.

Remote-control operation of remote pickup stations will be permitted subject to the following conditions.

(a) A percentage modulation indicator or calibrated program level meter shall be provided at the operating position.

(b) The operator shall have off-and-on control of the power to the last radio stage.

(c) The transmitter shall be so installed and protected that it is not accessible to other than duly authorized persons.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.435 Power limitations.

Remote pickup broadcast stations will be licensed with a power output not in excess of that necessary to render satisfactory service. The license for these stations will specify the maximum authorized power. The operating power shall not be greater than necessary to carry on the service and in no event more than 5 percent above the maximum power specified. Engineering standards have not been established for these stations. The efficiency factor for the last radio stage of transmitters employed will be subject to individual determination but shall be in general agreement with values normally employed for similar equipment operated within the frequency range authorized.

§ 74.436 Emission authorized.

(a) The license for a remote pickup broadcast station operating on frequencies below 25 Mc/s will normally authorize A3 emission and may in addition authorize A1 and A2 emission where a need therefor is shown. A license for a remote pickup broadcast station operating on frequencies above 25 Mc/s will authorize A3 or F3 emission, depending upon the equipment employed. Stations licensed to employ F3 emission shall limit the frequency swing so that the bandwidth of emission will conform to the requirements of the channel widths authorized as follows:

(1) For stations operating on the frequencies 25.87 to 26.03 Mc/s, 40 kilocycles.

(2) For stations operating on the frequencies 26.07 to 26.47 Mc/s, 20 kilocycles.

(3) For stations operating on the frequencies 152.87 to 153.35, 160.89 to 161.37, 166.25, and 170.15 Mc/s, 60 kilocycles.

(4) For stations operating on the frequencies 450.05 to 450.95 and 455.05 to 455.95 Mc/s, 100 kilocycles.

(5) For stations operating on the frequencies 161.64 to 161.76 Mc/s, 30 kilocycles.

NOTE: The term "frequency swing" means the instantaneous departure of the frequency of the emitted wave from the center frequency resulting from modulation.

(b) Any emissions outside the authorized channel shall be limited to such an extent as not to constitute a source of potential interference to other stations and in no event shall such emissions be in excess of minus 40 decibels as compared to the emissions within the authorized channel.

§ 74.437 Special rules relating to low power broadcast auxiliary stations.

(a) The devices which will be licensed under this section are those which are normally intended to be operated over distances not in excess of a few hundred feet and will fall into two general categories: studio cueing transmitters and wireless microphones. Paragraphs (b) to (j) of this section will govern the licensing of such devices.

(b) A license for a low power broadcast auxiliary station will be issued only to the licensee of a standard, FM, or television broadcast station and for use with a specific station or combination of such broadcast stations within the same city. Such stations may be operated at other locations from time to time in accordance with the provisions of paragraph (f) of this section.

(c) The license of a low power broadcast auxiliary station authorizes the transmission of cues and orders to production personnel and participants in broadcast programs and in the preparation therefor, the transmission of program material by means of a wireless microphone worn by a performer or other participant in a program during rehearsal and during the actual broadcast, or the transmission of comments, interviews, and reports from the scene of a remote broadcast. Such transmissions shall be intended for reception at a receiving point within the same studio, building, stadium, or similar limited indoor or outdoor area or at the location of a nearby remote pickup broadcast mobile station where they will be relayed to a broadcasting station for simultaneous or delayed broadcast.

(d) An application for a new low power broadcast auxiliary station or for a change in an existing authorization shall specify the broadcast station or combination of stations in the same city, as set forth in paragraph (b) of this section, with which it is to be used principally. A single application, filed on FCC Form 313, in duplicate, may be used in applying for authority to construct and operate one or more low power broadcast auxiliary transmitting units provided that such transmitting units are designed for operation in a common frequency band and will be normally operated with the same broadcast station or combination of stations in a single city.

(e) The operation of low power broadcast auxiliary stations will be authorized only in the bands 26.10–26.48 Mc/s and 450–451 Mc/s. Transmitting units may be operated on any frequencies within the band of frequencies for which the station is licensed, provided that the emissions are confined to the authorized band. Transmitting units are not required to maintain a constancy of frequency beyond that necessary to insure compliance with the requirement of this paragraph.

(f) A low power broadcast auxiliary station may be used in conjunction with broadcast stations of other licensees located in the same area as the broadcast station or stations with which it is licensed without further authority of the Commission, provided that such operation is conducted by the licensee of the low power broadcast auxiliary station. Low power broadcast auxiliary stations may also be operated in conjunction with broadcast stations of its licensee or other licensees in other locations provided that such operation is conducted by the licensee of the low power broadcast auxiliary station and provided further that, if such operation is to be conducted over a consecutive period of more than one day, the Engineer in Charge of the radio district in which the low power broadcast auxiliary station is licensed and the Engineer in Charge of the radio district in which the operation is to be conducted shall be notified in writing at least two days in advance of such operation and of the expected duration of the proposed operation.

(g) Low power broadcast auxiliary stations will not be licensed for a power input to the plate of the final radio frequency amplifier in excess of 1 watt and all operation thereof is subject to the condition that no harmful interference is caused to remote pickup broadcast base and mobile stations. Unusual transmitting antennas or antenna elevations shall not be used to extend the range of these low power devices beyond the limited areas defined in paragraph (c) of this section.

(h) No operator's license is required of the person actually using a low power broadcast auxiliary transmitting unit, provided that an operator holding any commercial radio operator license or permit, except an aircraft radiotelephone operator authorization or a temporary radiotelegraph second-class operator license, is on duty at the place where the transmitting unit is being operated to take immediate steps to correct any condition of improper operation observed. Any adjustments or repairs that could affect the proper operation of transmitting units shall be made by or under the immediate supervision of an operator holding a valid first or second-class radiotelephone license.

(i) Call signs will not be assigned to low power broadcast auxiliary stations. In lieu thereof, an announcement shall be made at the beginning and end of each period of operation at a single location, over the transmitting unit being operated, identifying the type of transmitting unit, its location, and the call sign of the broadcast station with which it is being used. Transmitting units will normally fall into one of two types: a cueing transmitter or a wireless microphone. A period of operation may consist of a continuous transmission or intermittent transmissions in connection with a single program.

(j) The licensee of each low power broadcast auxiliary station shall maintain adequate records at the main studio or transmitter of the broadcast station with which the auxiliary is principally used, which will accurately show the current location of all transmitting units, the periods of operation at such locations and any other pertinent remarks concerning transmissions.

EQUIPMENT

§ 74.451 Equipment changes.

The licensee of a remote pickup broadcast station may make any changes in the equipment that are deemed desirable or necessary provided:

(a) That the operating frequency is not permitted to deviate more than the allowed tolerance;

(b) That the emissions are not permitted outside the authorized band;

(c) That the power output complies with the license and the regulations governing the same; and

(d) That the transmitter as a whole or output power rating of the transmitter is not changed.

TECHNICAL OPERATION AND OPERATORS

§ 74.461 Frequency tolerance.

The licensee of a remote pickup broadcast station shall maintain the operating frequency of its station in accordance with the following:

Frequency range	Tolerance (percent)	
	Base station	Mobile station
1,605 to 4,000 kc/s:		
200 watts or less	0.01	0.02
Over 200 watts [1]	.005	.02
4,000 to 30,000 kc/s:		
5 watts or less	.005	.02
Over 5 watts	.005	.005
30 Mc/s to 300 Mc/s:		
5 watts or less	.005	.01
Over 5 watts	.005	.005
300 Mc/s to 500 Mc/s: All powers	.01	.01

[1] The listing of tolerance for power over 200 watts is in accordance with treaty values and shall not be construed as a finding that such power will be authorized.

§ 74.462 Frequency monitors and measurements.

(a) The licensee of a remote pickup broadcast station shall provide the necessary means for determining that the frequency of the station is within the allowed tolerance. The date and time of each frequency check, the frequency as measured, and a description or identification of the method employed shall be entered in the station log. Sufficient observations shall be made to insure that the assigned carrier frequency is maintained within the prescribed tolerance.

(b) Each frequency for which the remote pickup broadcast station is licensed shall be measured at least once during each calendar year.

§ 74.463 Station inspection.

The licensee of each remote pickup broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 74.464 Station and operator licenses; posting of.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the equipment or manner of operation of the station shall be posted so that all terms thereof are visible in a conspicuous place in the room in which the transmitter is located: *Provided:*

(1) If the transmitter operator is located at a distance from the transmitter pursuant to § 74.434 the station license shall be posted in the above-described manner at the operating position.

(2) If the station is licensed for portable-mobile operation, the station license or a photo copy thereof shall be affixed to the equipment or kept in the possession of the operator on duty at the transmitter. If a photo copy is used the original license shall be available for inspection by an authorized Government representative.

(b) The original license of each station operator shall be posted at the place where he is on duty: *Provided, however,* If the original license of a station operator is posted at another radio transmitting station in accordance with the rules governing that class of station and is there available for inspection by an authorized Commission representative, or if the station operated is licensed for portable-mobile operation, a verification card (Form 758–F) is acceptable in lieu of the posting of such license: *Provided further, however,* That if the operator on duty holds a restricted radiotelephone operator permit of the card form (as distinguished from the diploma form) he shall not post that permit but shall keep it in his personal possession.

NOTE: The term portable-mobile as here used is intended to include any type of portable or mobile operation.

§ 74.465 Operator requirements.

(a) Except as provided in paragraph (b) of this section, an operator holding a valid radiotelephone first-class or second-class operator license or a valid radiotelegraph first-class or second-class operator license or a valid restricted radiotelephone operator permit shall be on duty at the place where the transmitting apparatus is located or at a remote control point established pursuant to the provisions of § 74.434, and in actual charge of the operation at all times when the transmitter is operating.

(b) In cases where a remote pickup broadcast mobile station is taken to the scene of an event to be broadcast and the operator-reporter wishes to leave the location of the transmitter in order to move about freely at the scene with a hand-carried or pack-carried transmitter in order to conduct interviews, obtain a better vantage point to view the scene or otherwise more effectively cover the event, the mobile station may be oper-

ated as a temporarily unattended automatic relay station subject to the following conditions:

(1) The input power to the plate of the final radio frequency amplifier of the hand-carried or pack-carried transmitter shall not exceed 1 watt.

(2) The unattended transmitter shall be so equipped that it will be activated by the carrier of the hand-carried or pack-carried transmitter and will transmit only when relaying the transmissions of the hand-carried or pack-carried transmitter or when relaying the transmissions of an associated base station operating on the same frequency as the hand-carried or pack-carried transmitter and directed to the operator-reporter at the scene of the event.

(3) Unless the operator-reporter is equipped to monitor continuously the frequency on which the unattended transmitter operates, while moving about at the scene of the event, he shall observe the frequency before leaving the location of the mobile transmitter to ascertain whether it is in use so as to avoid interference to other users.

(c) The operator on duty and in charge of the operation of a remote pickup broadcast station may, at the discretion of the station licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of operator license held and the rules and regulations governing such other stations. However, such extra duties shall in no way interfere with the duties connected with the operation of the remote pickup station.

(d) Further provisions and restrictions concerning the operator's authority are contained in Part 13 of this chapter.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.466 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of that part.

§ 74.467 Additional orders.

In case the rules contained in this part do not cover all phases of operation or experimentation with respect to extrnal effects, the Commission may make supplemental or additional orders in each case as may be deemed necessary.

OTHER OPERATING REQUIREMENTS

§ 74.481 Station records.

(a) The licensee of each remote pickup broadcast station shall maintain adequate records of the operation, including:

(1) Hours of operation.

(2) Program transmitted.

(3) Frequency check.

(4) Pertinent remarks concerning transmission.

(5) An entry giving points of program origination and receiver location.

(b) Where an antenna structure(s) is required to be illuminated, see § 17.38 of this chapter.

(c) Station records shall be retained for a period of two years.

§ 74.482 Station identification.

Each remote pickup broadcast station shall announce its call letters at the beginning and end of each period of operation, and during operation, at least once every hour it shall either announce its call letters or make an announcement which will permit it to be identified (such as announcement during program operation of the call letters of the broadcast station with which the remote pickup broadcast station is regularly affiliated).

Subpart E—Aural Broadcast STL and Intercity Relay Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

§ 74.501 Classes of stations.

(a) *Aural broadcast STL station.* A fixed station utilizing telephony for the transmission of aural program material between a studio and the transmitter of a broadcasting station other than an international broadcasting station, for simultaneous or delayed broadcast.

(b) *Aural broadcast intercity relay station.* A fixed station utilizing telephony for the transmission of aural program material between broadcasting stations other than international broadcasting stations, for simultaneous or delayed broadcast.

§ 74.502 Frequency assignment.

(a) The frequency band 942–952 Mc/s is divided into nineteen 500 kc/s channels for assignment to aural broadcast STL and intercity relay stations. Each of the following frequencies is the center frequency of a channel:

Mc/s	*Mc/s*	*Mc/s*	*Mc/s*
942.5	945.0	947.5	950.0
943.0	945.5	948.0	950.5
943.5	946.0	948.5	951.0
944.0	946.5	949.0	951.5
944.5	947.0	949.5	

A single broadcast station licensee will normally be limited to the assignment of one 500 kc/s channel between the same point of origin and destination. If the circuit carries only one aural program channel, the center frequency of the channel will be assigned. If a single licensee requires more than one aural program channel between the same point of origin and destination, more than one transmitter may be authorized to operate within a single 500 kc/s channel, employing carrier frequencies above and below the center frequency listed in this paragraph. Where such assignments are made the operating frequencies selected shall be such that the unmodulated carrier frequency plus or minus the sum of M+D does not extend beyond the upper or lower channel edge. M is the maximum modulating frequency and D is the maximum excursion of the carrier from the unmodulated carrier frequency due to modulation. Under these circumstances, the operating frequencies of the unmodulated carriers shall be maintained within .001 percent of the assigned frequencies.

(b) The use of the frequencies listed in paragraph (a) of this section by aural broadcast intercity relay stations is subject to the condition that no harmful interference is caused to other classes of stations operating in accordance with the Table of Frequency Allocations contained in § 2.106 of this chapter.

(c) Any aural broadcast STL or intercity relay station for which there was outstanding a valid construction permit or license on April 16, 1958, specifying operation on any frequency between 890 Mc/s and 942 Mc/s, may continue to be operated on such frequencies for the remainder of the term specified in such authorization and may, upon appropriate application therefor, be granted a renewal of such license, subject to the condition that no harmful interference shall be caused to the radiolocation service operating in the band 890–942 Mc/s and subject to the further condition that the licensee must accept any interference which may be caused by the operation of radiolocation stations in the band 890–942 Mc/s and industrial, scientific, and medical (ISM) equipment in the band 890–940 Mc/s.

§ 74.503 Frequency selection.

(a) Each application for a new station or change in an existing station shall be specific with regard to frequency. In general, the lowest suitable frequency will be assigned which, on an engineering basis, will not cause harmful interference to other stations operating in accordance with existing frequency allocations.

(b) Where it appears that interference may result from the operation of a new station or a change in the facilities of an existing station, the Commission may require a showing that harmful interference will not be caused to existing stations or that if interference will be caused the need for the proposed service outweighs the loss of service due to the interference.

ADMINISTRATIVE PROCEDURE

§ 74.511 Cross reference.

See §§ 74.11 to 74.16.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

§ 74.531 Permissible service.

(a) An aural broadcast STL station is authorized to transmit aural program material between the studio and transmitter location of a broadcasting station, except an international broadcasting station, for simultaneous or delayed broadcast.

(b) An aural broadcast intercity relay station is authorized to transmit aural program material between broadcasting stations, except international broadcasting stations, for simultaneous or delayed broadcast.

(c) Multiplexing of the STL or intercity relay transmitter may be employed to provide additional communication channels for the transmission of aural program material, operational communications, or material authorized to be transmitted over an FM broadcast

station under a valid Subsidiary Communications Authorization (SCA). An aural broadcast STL or intercity relay station may not, however, be operated solely for the transmission of operational or subsidiary communications. Operational communications include cues, orders, and other communications directly related to the operation of the broadcast station as well as special signals used for telemetry or the control of apparatus used in conjunction with the broadcasting operation.

(d) All program material, including subsidiary communications, transmitted over an aural broadcast STL or intercity relay station shall be intended for use by broadcast stations owned or under common control of the licensee or licensees of the STL or intercity relay station. Other broadcast stations may simultaneously utilize such program material with permission of the STL or intercity relay station licensee.

(e) In any case where multiplexing is employed on an aural broadcast STL station for the simultaneous transmission of more than one aural channel, the STL transmitter must be capable of transmitting the multiple channels within the channel on which the STL station is authorized to operate and with adequate technical quality so that each broadcast station utilizing the circuit can meet the technical performance standards stipulated in the rules governing that class of broadcasting station. If multiplex operation is employed during the regular operation of the STL station, the additional circuits shall be in operation at the time that the required periodic performance measurements are made of the overall broadcasting system from the studio microphone input circuit to the broadcast transmitter output circuit.

§ 74.532 Licensing requirements.

(a) An aural broadcast STL or intercity relay station will be licensed only to the licensee or licensees of broadcasting stations other than international broadcasting stations, and for use with broadcast stations owned entirely by or under common control of the licensee or licensees.

(b) More than one aural broadcast STL or intercity relay station may be licensed to a single licensee upon a satisfactory showing that the additional stations are needed to provide different program circuits to more than one broadcast station, to provide program circuits from other studios, or to provide one or more intermediate relay stations over a path which cannot be covered with a single station due to terrain or distance.

(c) If more than one broadcast station or class of broadcast station is proposed to be served by a single STL or intercity relay station, this information shall be clearly set forth in the application for construction permit or license.

(d) Each aural broadcast STL or intercity relay station will be licensed at a specified transmitter location to communicate with a specified receiving location, and the direction of the main radiation lobe of the transmitting antenna will be one of the terms of the license.

§ 74.533 Remote control and unattended operation.

(a) Aural broadcast STL and intercity relay stations may be operated by remote control: *Provided,* That such operation is conducted in accordance with the conditions listed in this section: *And provided further,* That the Commission is notified at least 10 days prior to such operation and that such notification is accompanied by a detailed description of the proposed remote control installation showing the manner of compliance with the following conditions:

(1) The operating position shall be under the control and supervision of the licensee and shall be the place at which a licensed operator meeting the requirements of § 74.565 and responsible for the operation of the transmitter is stationed;

(2) A carrier operated device shall be provided at the operating position which shall give a continuous visual indication when the transmitter is radiating; or, in lieu thereof, a device shall be provided which will give a continuous visual indication when any transmitter control circuits have been placed in a condition to produce radiation;

(3) Facilities shall be provided at the operating position which will permit the operator to turn the transmitter carrier on and off at will; and

(4) The transmitter and all of its operating controls shall be so installed and protected that they are not accessible to other than authorized personnel.

(b) In cases where intermediate relay stations are employed in aural broadcast STL or intercity relay systems, such intermediate relay stations may be operated unattended if the following requirements are met:

(1) The transmitter shall be equipped with automatic circuits that will cause it to cease radiating at times when no signal is being received from the station which it is relaying.

(2) The transmitter shall be provided with adequate safeguards to prevent improper operation of the equipment.

(3) The transmitter installation shall be adequately protected against tampering by unauthorized persons.

(4) Whenever an intermediate relay station is in operation, appropriate observations shall be made at the receiving end of the STL or intercity relay circuits at intervals not exceeding one hour by a person holding a valid first or second class radiotelephone operator license, who shall take immediate steps to correct any condition of improper operation that may be observed.

(5) It shall be the responsibility of the licensee to insure that any repairs or adjustments that may be necessary are made by a person technically qualified to do so.

(c) The Commission may notify the licensee not to commence remote control or unattended operation, or to cancel, suspend; or change the date of the beginning of such operation as and when such action may appear to be in the public interest, convenience, and necessity.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.534 Power limitations.

Aural broadcast STL and intercity relay stations will be licensed with a power output not in excess of that necessary to render satisfactory service. The license for these stations will specify the maximum authorized power. The operating power shall not be greater than necessary to carry on the service and in no event more than 5 percent above the maximum power specified. Engineering standards have not been established for these stations. The efficiency factor for the last radio stage of transmitters employed will be subject to individual determination but shall be in general agreement with values normally employed for similar equipment operated within the frequency range authorized.

§ 74.535 Emission and bandwidth.

(a) Aural broadcast STL and intercity relay stations normally will be authorized to employ frequency modulation only. The maximum frequency excursion of the carrier resulting from modulation shall not exceed 200 kc/s above or below the assigned frequency.

(b) If multiplexing by means of one or more sub-carriers is employed, the maximum sub-carrier frequency used shall be such that $2M+2D$ does not exceed 500 kc/s, where M is the maximum modulating frequency in cycles per second and 2D equals the total carrier frequency excursion as the result of modulation, expressed in cycles per second.

(c) The channels assigned to aural broadcast STL and intercity relay stations are 500 kc/s in width, the assigned frequency being at the center of the channel. Emissions appearing outside the assigned channel shall be attenuated as follows:

(1) Any emission appearing on a frequency removed from the assigned frequency by between 250 and 500 kc/s shall be attenuated at least 25 decibels below the level of the unmodulated carrier. Compliance with this specification will be deemed to show the occupied bandwidth to be 500 kc/s or less.

(2) Any emission appearing on a frequency removed from the assigned frequency by more than 500 kc/s and up to and including 750 kc/s shall be attenuated at least 35 decibels below the level of the unmodulated carrier.

(3) Any emission appearing on a frequency removed from the assigned frequency by more than 750 kc/s shall be attenuated at least $43+10 \log_{10}$ (power, in watts) decibels below the level of the unmodulated carrier.

§ 74.536 Directional antenna required.

Each aural broadcast STL and intercity relay station is required to employ a directional antenna. Considering one kilowatt of radiated power as a standard for comparative purposes, such antenna shall provide a free space field intensity at one mile of not less than 435 mv/m in the main lobe of radiation toward the receiver and not more than 20 percent of the maximum value in any azimuth 30 degrees or more off the line to the receiver. Where more than one antenna is authorized for use with a single sta-

tion, the radiation pattern of each shall be in accordance with the foregoing requirement.

EQUIPMENT

§ 74.551 Equipment changes.

(a) Prior Commission approval, upon appropriate application (FCC Form 313) therefor, is required for any of the following changes:

(1) A change in the transmitter as a whole (except replacement with an identical transmitter), or a change in power output.

(2) A change of frequency assignment.

(3) A change in the location of the STL transmitter (except relocation of the equipment within the same building).

(4) Any change in the antenna system which will increase the height of the antenna above the natural formation or man-made structure upon which it is mounted by more than 20 feet or will result in an overall height above ground of more than 170 feet (except where the antenna is mounted below the top of an existing structure which is more than 170 feet high).

(5) Any change in the direction of the main radiation lobe of the transmitting antenna.

(b) Other equipment changes not specifically referred to in this section may be made at the discretion of the licensee, provided that the Engineer-in-charge of the radio district in which the station is located and the Commission in Washington, D.C., are promptly notified in writing upon the completion of such changes, and provided that the changes are set forth in the next application for renewal of license. Where such changes include the installation of multiplex equipment to provide additional aural channels, the purpose for which these added channels will be used shall be stated.

TECHNICAL OPERATION AND OPERATORS

§ 74.561 Frequency tolerance.

The licensee of each aural broadcast STL and intercity relay station shall maintain the operating frequency of the station within plus or minus 0.005 percent of the assigned frequency.

§ 74.562 Frequency monitors and measurements.

The licensee of each aural broadcast STL and intercity relay station shall provide the necessary means for determining that the frequency of the station is within the allowed tolerance. The date and time of each frequency check, the frequency as measured, and a description or identification of the method employed shall be entered in the station log. Sufficient observations shall be made to insure that the assigned carrier frequency is maintained within the prescribed tolerance.

§ 74.563 Station inspection.

The licensee of each aural broadcast STL and intercity relay station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 74.564 Station and operator licenses; posting of.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the equipment or manner of operation of the station shall be posted so that all terms thereof are visible, in a conspicuous place in the room in which the transmitter is located: *Provided,* That if the transmitter operator is located at a distance from the transmitter pursuant to § 74.533 the station license shall be posted in the above-described manner at the operating position.

(b) The original license of each station operator shall be posted at the place where he is on duty: *Provided, however,* If the original license of a station operator is posted at another radio transmitting station in accordance with the rules governing that class of station and is there available for inspection by an authorized Commission representative, a verification card (Form 758–F) is acceptable in lieu of the posting of such license: *Provided further, however,* That if the operator on duty holds a restricted radiotelephone operator permit of the card form (as distinguished from the diploma form) he shall not post that permit but shall keep it in his personal possession.

§ 74.565 Operator requirements.

One or more radio operators holding any class of commercial radio operator license or permit shall be on duty at the place where the transmitting apparatus is located, except as provided in § 4.533, and in actual charge of its operation. Further provisions and restrictions concerning the operator's authority are contained in Part 13 of this chapter. The licensed operator on duty and in charge of a broadcast transmitter may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of operator's license which he holds and the rules and regulations governing such stations. However, such duties shall in no wise interfere with the operation of the broadcast transmitter.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.566 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of this chapter.

§ 74.567 Additional orders.

In case the rules contained in this part do not cover all phases of operation or experimentation with respect to external effects, the Commission may make supplemental or additional orders in each case as may be deemed necessary.

OTHER OPERATING REQUIREMENTS

§ 74.581 Station records.

(a) The licensee of each aural broadcast STL and intercity relay station shall maintain adequate records of the operation, including:

(1) Hours of operation.

(2) Program transmitted.

(3) Frequency check.

(4) Pertinent remarks concerning transmission.

(b) Where an antenna structure(s) is required to be illuminated, see § 17.38 of this chapter.

(c) Station records shall be retained for a period of two years.

§ 74.582 Station identification.

(a) Each aural broadcast STL or intercity relay station shall transmit its call sign at the beginning and end of each period of operation, and during operation, at least once every hour, it shall either transmit its call sign or the call sign of the broadcast station with which it is associated. In cases when an unattended intercity relay system is operated as an "off-the-air" pickup and relay, the transmission of the call sign of the broadcast station which it is relaying will satisfy the hourly identification requirement.

(b) Station identification transmissions during operation need not be made when to make such transmission would interrupt a single consecutive speech, play, religious service, symphony concert, or other such productions. In such cases, the identification transmission shall be made at the first interruption of the entertainment continuity and at the conclusion thereof.

(c) Where more than one aural broadcast STL or intercity relay station is employed in an integrated relay system, the station at the point of origination may originate the transmission of the call signs of all of the stations in the relay system.

(d) Voice transmissions shall normally be employed for station identification. However, other methods of station identification may be permitted or required by the Commission.

Subpart F—Television Auxiliary Broadcast Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

§ 74.601 Classes of television auxiliary broadcast stations.

(a) *Television pickup station.* A land mobile station used for the transmission of television program material and related communications from the scenes of events occurring at points removed from television broadcast station studios to television broadcast stations.

(b) *Television STL station (studio-transmitter link).* A fixed station used for the transmission of television program material and related communications from the studio to the transmitter of a television broadcast station.

(c) *Television intercity relay station.* A fixed station used for intercity transmission of television program material

and related communications for use by television broadcast stations.

NOTE: Wherever used in this subpart, the term "television broadcast station licensee" includes a television broadcast station permittee.

§ 74.602 Frequency assignment.

(a) The following frequencies are available for assignment to television pickup, television STL, and television intercity relay stations:

Band A (Mc/s)	Band B (Mc/s)	Band D (Mc/s)	
1990–2008	6875–6900	12700–12725	12975–13000
2008–2025	6900–6925	12725–12750	13000–13025
2025–2042	6925–6950	12750–12775	13025–13050
2042–2059	6950–6975	12775–12800	13050–13075
2059–2076	6975–7000	12800–12825	13075–13100
2076–2093	7000–7025	12825–12850	13100–13125
2093–2110	7025–7050	12850–12875	13125–13150
2450–2467	7050–7075	12875–12900	13150–13175
2467–2484	7075–7100	12900–12925	13175–13200
2484–2500	7100–7125	12925–12950	13200–13225
		12950–12975	13225–13250

Frequencies in the bands 17700–19300 Mc/s, 19400–19700 Mc/s, 27525–31300 Mc/s, and 38600–40000 Mc/s are available for assignment on a case-by-case basis for television pickup, STL and intercity relay purposes. Channel widths and frequency tolerance will be specified in individual authorizations. Frequencies shown above between 2450 and 2500 Mc/s in band A are allocated to accommodate the incidental radiations of industrial, scientific, and medical (ISM) equipment, and stations operating therein must accept any interference that may be caused by the operation of such equipment. Frequencies between 2450 and 2500 Mc/s are also shared with other communication services and exclusive channel assignments will not be made, nor is the channeling shown above necessarily that which will be employed by such other services.

(b) Except as provided in paragraph (a) of this section, each television broadcast station licensee in an area may request the assignment of one channel in Band A or Band B and one channel in Band D on an exclusive basis. In making such exclusive assignments, priority will be based on the filing date of an appropriate application (FCC Form 313) completed in accordance with the instructions thereon. Frequency assignments will normally be made as requested if the requested frequency is not assigned to another licensee on an exclusive basis. However, the Commission reserves the right to assign frequencies other than those requested if, in its opinion, such action is warranted.

(c) Where the relative locations of the studio and transmitter are such as to permit co-channel operation of television STL stations by two or more licensees in the same area, such licensees may, by mutual agreement, request the assignment of a common channel for STL use on an exclusive basis. In the event that such a shared assignment is made, each participating licensee may request the assignment of an individual exclusive channel in Band A, Band B, or Band D in addition to the shared STL channel.

(d) A television broadcast station licensee will normally be limited to the assignment of not more than three channels in Bands A and B combined, only one of which will be assigned on an exclusive basis: *Provided, however,* That additional channels in Bands A and B may be assigned on a non-exclusive basis upon a satisfactory showing that additional channels are necessary and that such additional channels, if assigned, will not be needed to provide an exclusive channel to some other licensee in the same area within the foreseeable future. The number of channels in Band D that may be assigned to a licensee in a single area is not restricted.

(e) Non-exclusive channel assignments are subject to withdrawal without advance notice to provide an exclusive channel assignment to a licensee pursuant to the provisions of paragraph (b) of this section. The Commission reserves the right to select the non-exclusive channel assignment to be withdrawn; however, withdrawals will normally be made in the following order:

(1) The most recent channel assignment to the licensee having the greatest number of assignments in Band A, B, or D. Determination as to whether the withdrawal shall be made in Band A, Band B, or Band D will be based on the design of the equipment proposed to be used by the applicant for whom the exclusive channel is required.

(2) Where two or more licensees are assigned individually an equal number of non-exclusive channels in the same band and a greater number of channels in that band than any one of the other licensees, the assignment of most recent date.

(3) In all other cases the assignment of most recent date of a non-exclusive channel.

(f) The use of frequencies in the bands 1990–2110 Mc/s, 6875–7125 Mc/s and 12700–13200 Mc/s by television intercity relay stations shall be on a secondary basis, i.e., subject to the condition that no harmful interference is caused to stations operating in accordance with the table of frequency allocations in § 2.106 of this chapter.

(g) In the event that a television broadcast station licensee engages a communications common carrier to provide television pickup or television STL service, the frequencies available to that licensee may be assigned to the communications common carrier for the purpose of providing such service to that licensee. For the purpose of applying the provisions with respect to exclusive channel assignments and the withdrawal of channels, channels assigned to communications common carriers to provide television pickup or television STL service to an individual television broadcast station licensee will be considered to be assigned to that television broadcast licensee.

§ 74.603 Sound channels.

(a) The frequencies listed in § 74.602 (a) may be used for the simultaneous transmission of the picture and sound portions of television broadcast programs and for cue and order circuits, either by means of multiplexing or by the use of a separate transmitter within the same channel. When multiplexing of a television STL station is contemplated, consideration should be given to the requirements of § 73.687 of this chapter regarding the overall system performance requirements. Applications for new television pickup, television STL, and television intercity relay stations shall clearly indicate the nature of any multiplexing proposed. Multiplexing equipment may be installed on licensed equipment without further authority of the Commission: *Provided,* That the Commission in Washington, D.C., and the Commission's engineer-in-charge of the radio district in which the station is located shall be promptly notified of the installation of such apparatus: *And provided further,* That the installation of such apparatus on a television STL station shall not result in degradation of the overall system performance of the television broadcast station below that permitted by § 73.687 of this chapter.

(b) The aural portion of television broadcast program material may be transmitted over an aural broadcast STL or intercity relay station licensed under the provisions of Subpart E of this part.

(c) Any television STL station or television intercity relay station used for the transmission of the sound portion only of television program material and for which there was outstanding a valid construction permit or license on April 16, 1958, specifying operation on any frequency between 890 Mc/s and 940 Mc/s may continue to be operated on such frequencies for the remainder of the term specified in such authorization and may, upon appropriate application therefor, be granted a renewal of license subject to the condition that no harmful interference shall be caused to the radiopositioning service operating in the band 890–942 Mc/s and subject to the further condition that the licensee must accept any interference which may be caused by the operation of radiopositioning stations in the band 890–942 Mc/s and industrial, scientific, and medical (ISM) equipment operating in the band 890–940 Mc/s.

(d) Remote pickup broadcast stations may be used in conjunction with television pickup stations for the transmission of the aural portion of television programs or events that occur outside a television studio and for the transmission of cues, orders, and other related communications necessary thereto. The rules governing remote pickup broadcast stations are contained in Subpart D of this part.

§ 74.604 Frequency selection to avoid interference.

(a) Applicants for new television pickup, television STL, and television intercity relay stations shall endeavor to select frequency assignments which will be least likely to result in mutual interference with other licensees in the same area. Consideration should be given to the relative locations of receiving points, normal transmission path, and nature of the contemplated operation.

(b) Because of the more or less continuous nature of the operation of television STL stations, frequency assignments to such stations will normally be designated as the exclusive channel of the licensee pursuant to § 74.602(b).

(c) Where two or more licensees are assigned a common channel for television pickup, television STL, or television intercity relay purposes in the same area and simultaneous operation is contemplated, they shall take such steps as may be necessary to avoid mutual interference. If a mutual agreement to this effect cannot be reached, the Commission shall be notified and it will take such action as may be necessary, including time-sharing arrangements, to assure an equitable distribution of available facilities.

ADMINISTRATIVE PROCEDURE

§ 74.621 Cross reference.

See §§ 74.11 to 74.16.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

§ 74.631 Permissible service.

(a) The license of a television pickup station authorizes the transmission of program material, orders concerning such program material, and related communications necessary to the accomplishment of such transmissions, from the scenes of events occurring in places other than a television studio, to its associated television broadcast station, to such other stations as are broadcasting the same program material, or to the network or networks with which the television broadcast station is affiliated. Television pickup stations may be operated in conjunction with other television broadcast stations not aforementioned in this paragraph: *Provided,* That the transmissions by the television pickup station are under the control of the licensee of the television pickup station and that such operation shall not exceed a total of 10 days in any 30-day period. Television pickup stations may be used to provide temporary studio-transmitter links or intercity relay circuits consistent with § 74.632 without further authority of the Commission: *Provided, however,* That prior Commission authority shall be obtained if the transmitting antenna to be installed will increase the height of any natural formation or man-made structure by more than 20 feet and will be in existence for a period of more than 2 consecutive days.

NOTE: As used in this subpart, "associated television broadcast station" means a television broadcast station licensed to the licensee of the television auxiliary broadcast station and with which the television auxiliary station is licensed as an auxiliary facility.

(b) A television broadcast STL station is authorized to transmit visual program material between the studio and the transmitter of a television broadcast station for simultaneous or delayed broadcast.

(c) A television intercity relay station is authorized to transmit visual program material between television broadcast stations for simultaneous or delayed broadcast.

(d) Multiplexing of an STL or intercity relay transmitter may be employed to provide additional communication channels for the transmission of aural program material and operational communications. A television broadcast STL or intercity relay station may not, however, be operated solely for the transmission of aural programs or operational communications. Operational communications include cues, orders, and other communications directly related to the operation of the television broadcast station as well as special signals used for telemetry or the control of apparatus used in conjunction with the broadcasting operation. Aural program material may include the sound accompanying the visual program material transmitted and aural program material for broadcast by AM and FM broadcast stations.

(e) All program material transmitted over a television broadcast STL or intercity relay station shall be intended for use by broadcast stations owned by or under common control of the licensee or licensees of the STL or intercity relay station. Other broadcast stations may simultaneously utilize such program material with permission of the STL or intercity relay station licensee.

§ 74.632 Licensing requirements.

(a) A license for a television pickup, television STL, or television intercity relay station will be issued only to the licensee of a television broadcast station. A separate application is required for each transmitter and the application shall be specific with regard to the frequency requested. Except as provided in § 74.604(b), the first channel assigned in Band A or Band B to a licensee will be considered to be the exclusive assignment provided in § 74.602(b). Exclusive channel assignments in Band D will be designated only upon request. A licensee may request a change in its exclusive channel assignment only where there are unassigned channels available. In making such changes, the priority set forth in § 74.602(b) will be observed.

(b) A license for a television intercity relay station may be issued in any case where the circuit will operate between television broadcast stations either by means of "off-the-air" pickup and relay or location of the initial relay station at the studio or transmitter of a television broadcast station.

(c) An application for construction permit for a new television pickup station or for renewal of license of an existing station shall designate the television broadcast station with which it is to be operated and specify the area in which the proposed operation is intended.

(d) In case a licensee has two or more television broadcast stations located in different cities, it shall, in applying for a new television pickup station or for renewal of license of an existing station, designate the television broadcasting station in conjunction with which it is to be operated principally, and it shall not thereafter operate the television pickup station in conjunction with another of its television broadcast stations located in a different city for a total of more than 10 days in any 30-day period.

§ 74.633 Temporary authorizations.

(a) Special temporary authority may be granted for the operation, as a television auxiliary broadcast station, of equipment licensed to another television broadcast station, or other class of station, or equipment of suitable design not heretofore licensed. Such authority will normally be granted only for special operation of a temporary nature.

(b) A request for special temporary authority for the operation of a television auxiliary broadcast station may be made by informal application, which shall be filed with the Commission at least 10 days prior to the date of the proposed operation: *Provided,* That an application filed within less than 10 days of the proposed operation may be accepted upon a satisfactory showing of the reasons for the delay in submitting the request.

(c) An application for special temporary authority shall set forth full particulars of the purpose for which the request is made, and shall show the type of equipment, power output, emission, and frequency or frequencies proposed to be used, as well as the time, date and location of the proposed operation. In the event that the proposed antenna installation will increase the height of any natural formation, or existing man-made structure, by more than 20 feet, a vertical plan sketch showing the height of the structure proposed to be erected, the height above ground of any existing structure, the elevation of the site above mean sea level, and the geographic coordinates of the proposed site, shall be submitted with the application.

(d) A request for special temporary authority shall specify a channel or channels consistent with the provisions of § 74.602: *Provided,* That in the case of events of wide-spread interest and importance which cannot be transmitted successfully on these frequencies, frequencies assigned to other services may be requested upon a showing that operation thereon will not cause interference to established stations: *And provided further,* That in no case will a television auxiliary broadcast operation be authorized on frequencies employed for the safety of life and property.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.634 Remote control operation.

(a) A television auxiliary station may be operated by remote control provided that such operation is conducted in accordance with the conditions listed below, and provided further that the Commission is notified at least 10 days prior to such operation and that such notification is accompanied by a detailed description of the proposed remote control installation showing the manner of compliance with the following conditions:

(1) The operating position shall be under the control and supervision of the licensee and shall be the place at which a licensed operator meeting the requirements of § 74.665 and responsible for the operation of the transmitter is stationed;

(2) A carrier operated device shall be provided at the operating position which shall give a continuous visual indication when the transmitter is radiating; or, in lieu thereof, a device shall be provided which will give a continuous visual indication when any transmitter control

circuits have been placed in a condition to produce radiation;

(3) Facilities shall be provided at the operating position which will permit the operator to turn the transmitter carrier on and off at will; and

(4) The transmitter and all of its operating controls shall be so installed and protected that they are not accessible to other than duly authorized personnel.

(b) The Commission may notify the licensee not to commence remote control operation, or to cancel, suspend, or change the date of beginning for such operation as and when such action may appear to be in the public interest, convenience, and necessity.

§ 74.635 Unattended operation.

(a) Television intercity relay stations and television STL stations, where the circuit requires the use of more than one STL transmitter, may be operated unattended: *Provided,* That such operation is conducted in accordance with the conditions listed below: *And provided further,* That the Commission is notified at least 10 days prior to the beginning of such operation and that such notification is accompanied by a detailed description of the proposed installation showing the manner of compliance with the following conditions:

(1) The transmitter is capable of retransmitting by self-actuating means a radio signal received from another radio station or stations;

(2) The transmitter shall be provided with adequate safeguards to prevent improper operation of the equipment;

(3) The transmitter shall be so installed and protected that it is not accessible to other than duly authorized persons;

(4) Appropriate observations shall be made, at intervals not exceeding one hour during the period of its operation, at the receiving end of the circuit by a person holding a valid first or second class radiotelephone operator license who shall immediately institute measures sufficient to assure prompt correction of any condition of improper operation that is observed; and

(5) The station licensee shall remain responsible for the proper operation of the station, and all adjustments or tests during or coincident with the installation, servicing, or maintenance of the station which may affect its proper operation shall be performed by or under the immediate supervision and responsibility of a licensed operator as provided in § 74.665.

(b) The Commission may notify the licensee not to commence unattended operation, or to cancel, suspend, or change the date of the beginning of such operation as and when such action may appear to be in the public interest, convenience, and necessity.

§ 74.636 Power limitations.

Television auxiliary broadcast stations will be licensed with a power output not in excess of that necessary to render satisfactory service. The license for these stations will specify the maximum authorized power. The operating power shall not be greater than necessary to carry on the service and in no event more than 10 percent above the maximum power specified. Engineering standards have not been established for these stations. The efficiency factor for the last radio stage of transmitters employed will be subject to individual determination but shall be in general agreement with values normally employed for similar equipment operated within the frequency range authorized.

§ 74.637 Emission and bandwidth.

(a) Television broadcast auxiliary stations operating on frequencies above 1000 Mc/s may be authorized to employ any type of emission suitable for the transmission of the visual and such accompanying aural signals as may be permitted under the rules of this subpart.

(b) The channels assigned to television broadcast auxiliary stations are designated by upper and lower frequency limits. Emissions outside of these frequency limits shall be attenuated as follows:

(1) Any emission appearing on a frequency above the upper channel limit or below the lower channel limit by between zero and 50 percent of the assigned channel width shall be attenuated at least 25 decibels below the level of the unmodulated carrier. Compliance with this specification will be deemed to show that the occupied bandwidth is no greater than the assigned channel width.

(2) Any emission appearing on a frequency above the upper channel limit or below the lower channel limit by between 50 percent and 150 percent of the assigned channel width shall be attenuated at least 35 decibels below the level of the unmodulated carrier.

(3) Any emission appearing on a frequency above the upper channel limit or below the lower channel limit by more than 150 percent of the assigned channel width shall be attenuated at least $43+10 \log_{10}$ (power, in watts) decibels below the level of the unmodulated carrier.

EQUIPMENT

§ 74.651 Equipment changes.

(a) Commission authority, upon appropriate formal application (FCC Form 313) therefor, is required for any of the following equipment changes:

(1) A change of the transmitter as a whole (except replacement with an identical transmitter), or a change in the power output.

(2) A change of frequency assignment.

(3) A change in the location of a television STL or television intercity relay station (except relocation of the equipment within the same building) or a change in the area of operation of a television pickup station.

(4) Any change in the antenna system of a television STL or television intercity relay station which will result in a change of more than 20 feet in the height above ground of the antenna and supporting structure, or that will result in a change of the direction of the main radiation lobe.

(b) Other equipment changes not specifically referred to above may be made at the discretion of the licensee provided that the Engineer in Charge of the radio district in which the station is located, and the Commission at its Washington office, are notified in writing upon the completion of such changes, and provided that the changes are appropriately reflected in the next application for renewal of license of the television auxiliary broadcast station filed by the licensee.

(c) Multiplexing equipment may be installed on any licensed television broadcast STL or intercity relay station without further authority of the Commission, provided that the Engineer in Charge of the radio district in which the station is located and the Commission in Washington, D.C., are promptly notified in writing of such addition and the use which will be made of the additional aural circuits, and that the changes are shown in the next application for renewal of license for the station.

TECHNICAL OPERATION AND OPERATORS

§ 74.661 Frequency tolerance.

(a) The licensee of a television auxiliary broadcast station shall maintain the operating frequency of its station so that the normal sideband energy shall fall within the assigned channel. If transmission is by asymmetrical sideband operation, suitable filters or other devices shall be employed to insure a minimum of radiated energy outside the assigned channel.

(b) Television STL stations operating on frequencies shown in § 74.603(b) shall maintain their operating frequency within 0.005 percent of the assigned frequency.

§ 74.662 Frequency monitors and measurements.

The licensee of a television auxiliary broadcast station shall provide means for measuring the operating frequency in order to insure that the emissions are confined to the authorized channel. The date and time of each frequency check, the frequency as measured and a description or identification of the method employed shall be entered in the station log.

§ 74.663 Station inspection.

The licensee of each television auxiliary broadcast station shall make the station available for inspection by representatives of the Commission at any reasonable hour.

§ 74.664 Station and operator licenses; posting of.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the equipment or manner of operation of the station shall be posted so that all terms thereof are visible in a conspicuous place in the room in which the transmitter is located: *Provided:*

(1) If the transmitter operator is located at a distance from the transmitter pursuant to § 74.634, the station license shall be posted in the above-described manner at the operating position.

(2) If the station is licensed for mobile operation, the station license or a photo copy thereof shall be affixed to the equipment or kept in the possession

of the operators on duty at the transmitter. If a photo copy is used, the original license shall be available for inspection by an authorized government representative.

(b) The original license of each station operator shall be posted at the place where he is on duty: *Provided, however,* That if the original license of a station operator is posted at another radio transmitting station in accordance with the rules governing that class of station and is there available for inspection by an authorized Commission representative, a duly issued verified statement (Form 759) may be posted at the television auxiliary broadcast station in lieu of such original license: *And provided further,* That if the television auxiliary broadcast station is licensed for mobile operation, a duly issued verification card (Form 758–F) attesting to the existence of such original license may be carried on the person of the operator in lieu of the posting of such license or verified statement.

NOTE: The term mobile as here used is intended to include any type of mobile operation.

§ 74.665 Operator requirements.

(a) One or more radio operators holding valid radiotelephone first-class or radiotelephone second-class operator licenses shall be on duty at the place where the transmitting apparatus of any television auxiliary broadcast station is located and in actual charge of its operation: *Provided, however,* That if a station is operated by remote control as provided in § 74.634, such operator or operators must be on duty at the control point in lieu of the transmitting location: *And provided further,* That, in case a station is operated unattended as provided in § 74.635 such an operator shall be on duty at the receiving end of the circuit and shall be responsible for the required observations and the proper operation of the station within the terms of its license.

(b) The licensed operator on duty and in charge of a television auxiliary broadcast station may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of operator license which he holds and the regulations governing such stations; however, such duties shall in nowise interfere with the operation of the television auxiliary broadcast station.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.666 Antenna structure, marking and lighting.

The provisions of Part 17 of this chapter (Construction, Marking, and Lighting of Antenna Structures) require that certain antenna structures be painted and/or lighted in accordance with the provisions of that part. Where the antenna structure of a facility authorized under this subpart is required to be painted or lighted, see §§ 17.37, 17.39, 17.40, 17.41, and 17.42 of this chapter.

§ 74.667 Additional orders.

In case the rules contained in this part do not cover all phases of operation or experimentation with respect to external effects, the Commission may make supplemental or additional orders in each case as may be deemed necessary.

OTHER OPERATING REQUIREMENTS

§ 74.681 Station logs.

(a) The licensee of each television auxiliary broadcast station shall maintain adequate records of the operation including:

(1) Hours of operation.

(2) Call letters of broadcast station to which program transmitted.

(3) Frequency check.

(4) Pertinent remarks concerning transmission.

(b) Where an antenna structure(s) is required to be illuminated, see § 17.38 of this part.

(c) Station records shall be retained for a period of two years.

§ 74.682 Station identification.

(a) Each television auxiliary broadcast station shall identify itself by transmitting its call sign at the beginning and end of each period of operation; and during operation, shall identify itself on the hour by transmitting its own call sign or the call sign of the television broadcast station with which it is associated.

(b) Identification transmissions during operation need not be made when to make such transmission would interrupt a single consecutive speech, play, religious service, symphony concert, or any type of production. In such cases, the identification transmission shall be made at the first interruption of the entertainment continuity and at the conclusion thereof.

(c) Where more than one television auxiliary broadcast station is employed in an integrated relay system, the station at the point of origination may originate the transmission of the call signs of all the stations in the relay system.

(d) The transmission of the call sign shall normally employ the type of emission for which the station is authorized, i.e., a visual transmitter shall employ visual identification and an aural transmitter shall employ aural identification: *Provided, however,* When the transmitter is used for visual transmission only, the identifying call sign may be transmitted in international Morse code by keying the radio frequency carrier or a modulating signal impressed on the carrier. The Commission may, at its discretion, specify other methods of identification.

Subpart G—Television Broadcast Translator Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

§ 74.701 Definitions.

(a) *Television broadcast translator station.* A station in the broadcasting service operated for the purpose of retransmitting the signals of a television broadcast station or another television broadcast translator station, by means of direct frequency conversion and amplification of the incoming signals without significantly altering any characteristic of the incoming signal other than its frequency and amplitude, for the purpose of providing television reception to the general public.

(b) *Primary station.* The television broadcasting station radiating the signals which are retransmitted by a television broadcast translator station.

(c) *VHF translator.* A television broadcast translator station operating on a VHF television broadcast channel.

(d) *UHF translator.* A television broadcast translator station operating on a UHF television broadcast channel.

(e) *UHF translator signal booster.* A station in the broadcasting service operated for the sole purpose of retransmitting the signals of a UHF translator station by amplifying and reradiating such signals which have been received directly through space, without significantly altering any characteristic of the incoming signal other than its amplitude.

§ 74.702 Frequency assignment.

(a) An applicant for a new television broadcast translator station or for changes in the facilities of an authorized station shall endeavor to select a channel on which its operation is not likely to cause interference to the reception of other stations. The application must be specific with regard to the frequency requested. Only one channel will be assigned to each station.

(b) Any one of the 12 standard VHF channels (2–13 inclusive) may be assigned to a VHF translator on condition that no interference is caused to the direct reception of any television broadcast station operating on the same or an adjacent channel: *Provided, however,* That channels 5 and 6 are allocated for nonbroadcast use in Alaska and Hawaii and will not be assigned to VHF translators in those states.

(c) Any one of the upper 14 standard UHF channels (70–83 inclusive) may be assigned to a UHF translator provided that the proposed translator site is not located:

(1) Within 20 miles of a television broadcast station or city which is assigned the second, third, fourth, fifth, or eighth channel above or below the requested channel.

(2) Within 55 miles of a television broadcast station or city which is assigned an adjacent channel.

(3) Within 60 miles of a television broadcast station or city which is assigned the seventh channel above or the seventh or fourteenth channel below the requested channel.

(4) Within 75 miles of a television broadcast station or city which is assigned the fifteenth channel below the requested channel.

(5) Within 155 miles of a television broadcast station or city which is assigned the same channel as the requested channel unless the requested channel is assigned in the Table of Assignments appearing in § 73.606(b) of this chapter,

to the city in which the proposed translator is to be operated and has not been assigned to a television broadcast station in that city.

(d) The distances specified in paragraph (c) of this section are to be determined between the proposed site of the television broadcast translator station and the main Post Office location in any city listed in § 73.606(b) of this chapter unless the channel shown therein has been assigned to a television broadcast station, in which case the distance shall be determined between the proposed site of the translator and the transmitter site of the television broadcast station. Changes in the Table of Assignment of § 73.606(b) of this chapter may be made without regard to existing or proposed television broadcast translator stations and, where such changes result in minimum separations less than those specified above, the licensee of an affected UHF television broadcast translator station shall file an application for a change in channel assignment to comply with the required separations. In the case of changes in the Table of Assignments affecting VHF channels, existing VHF television broadcast translator stations causing interference to reception of VHF broadcast channels shall eliminate the interference or file an application for a change in channel assignment.

(e) No minimum distance separation between TV translators operating on the same channel is specified. However, assignments which will obviously result in mutual interference between translators will not be made.

(f) Adjacent channel assignments will not be made to television broadcast translator stations intended to serve all or a part of the same area.

§ 74.703 Interference.

(a) An application for a new television broadcast translator station or for changes in the facilities of an authorized station will not be granted where it is apparent that inteference will be caused. In general, the licensee of a new UHF translator shall protect existing UHF translators from interference resulting from its operation. If interference develops between VHF translators, the problem shall be resolved by mutual agreement among the licensees involved.

(b) It shall be the responsibility of the licensee of a VHF translator to correct at its expense any condition of interference to the direct reception of the signals of a television broadcast station operating on the same channel as that used by the VHF translator or on an adjacent channel, which occurs as the result of the operation of the translator. Interference will be considered to occur whenever reception of a regularly used signal is impaired by the signals radiated by the translator, regardless of the quality of such reception or the strength of the signal so used. If the interference cannot be promptly eliminated by the application of suitable techniques, operation of the offending translator shall be suspended and shall not be resumed until the interference has been eliminated. If the complainant refuses to permit the translator licensee to apply remedial techniques which demonstrably will eliminate the interference without impairment of the original reception, the licensee of the translator is absolved of further responsibility.

(c) It shall be the responsibility of the licensee of a television broadcast translator station to correct any condition of interference which results from the radiation of radio frequency energy by its equipment on any frequency outside the assigned channel. Upon notice by the Commission to the station licensee or operator that such interference is being caused, the operation of the television broadcast translator station shall be suspended immediately and shall not be resumed until the interference has been eliminated or it can be demonstrated that the interference is not due to spurious emissions by the television broadcast translator station: *Provided, however,* That short test transmissions may be made during the period of suspended operation to check the efficacy of remedial measures.

(d) In each instance where suspension of operation is required, the licensee shall submit a full report to the Commission after operation is resumed, containing details of the nature of the interference, the source of the interfering signals, and the remedial steps taken to eliminate the interference.

ADMINISTRATIVE PROCEDURE

§ 74.711 Cross reference.

See §§ 74.11 to 74.16.

LICENSING POLICIES AND GENERAL OPERATING REQUIREMENTS

§ 74.731 Purpose and permissible service.

(a) Television broadcast translator stations provide a means whereby the signals of television broadcast stations may be retransmitted to areas in which direct reception of such television broadcast stations is unsatisfactory due to distance or intervening terrain barriers.

(b) A television broadcast translator station may be used only for the purpose of retransmitting the signals of a television broadcast station or another television broadcast translator station which have been received directly through space, converted to a different channel by simple heterodyne frequency conversion, and suitably amplified.

(c) The transmissions of each television broadcast translator station shall be intended for direct reception by the general public and any other use shall be incidental thereto. A television broadcast translator station shall not be operated solely for the purpose of relaying signals to one or more fixed receiving points for retransmission, distribution, or further relaying.

(d) The technical characteristics of the retransmitted signals shall not be deliberately altered so as to hinder reception on conventional television broadcast receivers.

(e) A television broadcast translator station shall not deliberately retransmit the signals of any station other than the station it is authorized by license to retransmit. Precautions shall be taken to avoid unintentional retransmission of such other signals.

§ 74.732 Eligibility and licensing requirements.

(a) Subject to the restrictions set forth in paragraph (e) of this section, a license for a television broadcast translator station may be issued to any qualified individual, organized group of individuals, broadcast station licensee, or local civil governmental body, upon an appropriate showing that plans for financing the installation and operation of the station are sufficiently sound to insure prompt construction of the station and dependable service for the duration of the licensed period.

(b) More than one television broadcast translator station may be licensed to the same applicant, whether or not such stations serve substantially the same area, upon an appropriate showing of need for such additional stations. TV translators operated by TV broadcast station licensees are not counted as TV stations for purposes of § 73.636 of this chapter, concerning multiple ownership.

(c) Only one channel will be assigned to each television broadcast translator station. Additional television broadcast translator stations may be authorized to provide additional reception. A separate application is required for each television broadcast translator station and each application shall be complete in all respects.

(d) A VHF translator will not be authorized to serve an area which is receiving satisfactory service from one or more UHF television broadcast stations or UHF translators unless, upon consideration of all applicable public interest factors, it is determined that, exceptionally, such intermixture of VHF and UHF service is justified.

(e) The licensee or permittee of a television broadcasting station, an applicant financially supported by such licensee or permittee, or any person associated with the licensee or permittee, either directly or indirectly, will not be authorized to operate a VHF translator under any of the following circumstances:

(1) Where the proposed translator is intended to provide reception beyond the Grade B contour of the television broadcast station proposed to be rebroadcast.

(2) Where the proposed VHF translator is intended to provide reception to all or a part of any community located within the Grade A contour of any other television broadcast station for which a construction permit or license has been granted and the programs rebroadcast by the proposed VHF translator will duplicate all or any part of the programs broadcast by such other television broadcast station or stations: *Provided, however,* That this will not preclude the authorization of a VHF translator intended to improve reception of the parent station's signal to any community, any part of the corporate limits of which is within the principal city service contour of such station.

NOTE: The contours of a television broadcast station shall be determined in accordance with the procedures set forth in § 73.684 of this chapter.

(f) Any authorization for a VHF translator issued to an applicant described in paragraph (e) of this section will be issued subject to the condition that it may be terminated at any time, upon not less than sixty (60) days notice where the circumstances in the community or area served are so altered as to have prohibited grant of the application had such circumstances existed at the time of its filing.

(g) Paragraphs (e) and (f) of this section will not be applicable to noncommercial educational stations.

(h) The Commission will not act on applications for new television broadcast translator stations or for changes in the facilities of an existing station where such changes will result in an increase in signal range in any horizontal direction until 30 days have elapsed since the date on which "Public Notice" is given by the Commission of acceptance for filing of such application, in order to afford licensees of existing television broadcast stations an opportunity to comment with respect to the effect of the proposed translator on their operations.

§ 74.733 UHF translator signal boosters.

(a) The licensee of a UHF television broadcast translator station may be authorized to operate one or more signal boosters for the purpose of providing reception to small shadowed areas within the area intended to be served by the translator.

(b) The transmitting apparatus shall consist of a simple linear radio frequency amplifier, with one or more amplifying stages, which is capable of receiving, amplifying, and retransmitting the signals of the parent translator without significantly altering any electrical characteristic of the received signal other than its amplitude. The maximum power input to the plate of the final radio frequency amplifier shall not exceed 5 watts.

(c) The amplifier shall be equipped with suitable circuits which will automatically cause it to cease radiating if no signal is being received from the parent translator station. Care shall be taken in the design of the apparatus to insure that out-of-band radiation is not excessive and that adequate isolation is maintained between the input and output circuits to prevent unstable operation.

(d) The installation of the apparatus and its associated receiving and transmitting antennas shall be in accordance with accepted principles of good engineering practice. Either horizontal, vertical, or circular polarization of the electric field of the radiated signal may be employed. If the isolation between the input and output circuits depends in part upon the polarization or directive properties of the transmitting and receiving antennas, the installation shall be sufficiently rugged to withstand the normal hazards of the environment.

(e) The operation of a UHF translator signal booster is subject to the condition that no harmful interference is caused to the reception of any station, broadcast or non-broadcast, other than the parent translator. The licensee of the UHF translator signal booster is expected to use reasonable diligence to minimize interference to the direct reception of the parent translator station.

(f) UHF translator signal boosters may be operated unattended. Repairs and adjustments shall be made by a qualified person. The required qualifications are set forth in § 74.750 (g) and (h).

(g) An individual call sign will not be assigned to a UHF translator booster station. The retransmission of the call sign of the parent translator will serve as station identification.

(h) Applications for authority to construct and operate a UHF translator signal booster shall be submitted on FCC Form 346A. No construction of facilities or installation of apparatus at the proposed transmitter site shall be made until a construction permit therefor has been issued by the Commission.

(i) The provisions of § 74.765 concerning posting of station license shall apply to a UHF translator signal booster except that the parent UHF translator call sign, followed by the word "Booster", shall be displayed at the signal booster site.

(j) The provisions of §§ 74.767 and 74.781 concerning marking and lighting of antenna structures and station records, respectively, apply to UHF translator signal boosters.

§ 74.734 Unattended operation.

(a) A television broadcast translator station may be operated without a licensed radio operator in attendance if the following requirements are met:

(1) If the transmitter site cannot be reached promptly at all hours and in all seasons, means shall be provided so that the transmitting apparatus can be turned on and off at will from a point which is readily accessible at all hours and in all seasons.

(2) The transmitter shall also be equipped with suitable automatic circuits which will place it in a non-radiating condition in the absence of a signal on the input channel.

(3) The transmitting apparatus and the on-and-off control, if at a location other than the transmitter site, shall be adequately protected against tampering by unauthorized persons.

(4) The Commission shall be supplied with the name, address, and telephone number of a person or persons who may be contacted to secure prompt suspension of operation of the translator should such action be deemed necessary by the Commission.

(5) In cases where the antenna and supporting structure are considered to be a hazard to air navigation and are required to be painted and lighted under the provisions of Part 17 of this chapter, the licensee shall make suitable arrangements for the daily inspection and logging of the hazard markings required by §§ 17.37 and 17.38 of this chapter.

(b) An application for authority to construct a new television broadcast translator station or to make changes in the facilities of an authorized station, and which proposes unattended operation, shall include an adequate showing as to the manner of compliance with this section.

(c) Unless the applicant specifically requests unattended operation and makes the showing required by paragraph (b) of this section, a licensed radio operator meeting the requirements of § 74.766 shall be on duty at the transmitter site whenever the station is operated.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.735 Power limitation.

(a) The power output of the final radio frequency amplifier of a VHF translator shall not exceed 1 watt peak visual power. This power may be fed into a single transmitting antenna or may be divided between two or more transmitting antennas or antenna arrays in any manner found useful or desirable by the licensee. In individual cases, the Commission may authorize the use of more than one 1-watt final radio frequency amplifier at a single VHF translator station under the following conditions:

(1) Each such amplifier shall be used to serve a different community or area. More than one final radio frequency amplifier will not be authorized to provide service to all or a part of the same community or area.

(2) Each final radio frequency amplifier shall feed a separate transmitting antenna or antenna array. The transmitting antennas or antenna arrays shall be so designed and installed that the outputs of the separate radio frequency amplifiers will not combine to reinforce the signals radiated by the separate antennas or otherwise achieve the effect of radiated power in any direction in excess of that which could be obtained with a single antenna of the same design fed by a 1-watt radio frequency amplifier.

(3) VHF translators employing multiple final radio frequency amplifiers will be licensed as a single station. The separate final radio frequency amplifiers will not be licensed to different licensees.

(b) The transmitter power output of a UHF translator shall be limited to a maximum of 100 watts peak visual power. In no event shall the transmitting apparatus be operated with power output in excess of the manufacturer's rating.

(c) No limit is placed upon the effective radiated power which may be obtained by the use of horizontally or vertically directive transmitting antennas.

§ 74.736 Emissions and bandwidth.

(a) The license of a television broadcast translator station authorizes the transmission of the visual signal by amplitude modulation (A5) and the accompanying aural signal by frequency modulation (F3).

(b) Standard width television channels will be assigned and the transmitting apparatus shall be operated so as to limit spurious emissions to the lowest practicable value. Any emissions including intermodulation products and radio frequency harmonics which are not essential for the transmission of the desired picture and sound information shall be considered to be spurious emissions.

(c) Any emissions appearing on frequencies more than 3 megacycles above or below the upper and lower edges re-

spectively of the assigned channel shall be attenuated no less than 30 decibels below the peak power of the visual signal.

(d) Greater attenuation than that specified in paragraph (c) of this section may be required if interference results from emissions outside the assigned channel.

§ 74.737 Antenna location.

(a) An applicant for a new television broadcast translator station or for a change in the facilities of an authorized station shall endeavor to select a site which will provide a line-of-sight transmission path to the entire area intended to be served and at which there is available a suitable signal from the primary station. The transmitting antenna should be placed above growing vegetation and trees lying in the direction of the area intended to be served, to minimize the possibility of signal absorption by foliage.

(b) A site within 5 miles of the area intended to be served is to be preferred if the conditions in paragraph (a) of this section can be met.

(c) Consideration should be given to accessibility of the site at all seasons of the year and to the availability of facilities for the maintenance and operation of the television broadcast translator station.

(d) The transmitting antenna should be located as near as is practical to the transmitter to avoid the use of long transmission lines and the associated power losses.

(e) Consideration should be given to the existence of strong radio frequency fields from other transmitters at the translator site and the possibility that such fields may result in the retransmission of signals originating on frequencies other than that of the primary station.

EQUIPMENT

§ 74.750 Equipment and installation.

(a) The transmitting apparatus employed at a television broadcast translator station must meet the requirements for type acceptance by the Commission. These requirements are set forth in paragraph (c) of this section.

(b) Transmitting antennas, antennas used to receive the signals to be rebroadcast, and transmission lines do not have to be type accepted. External preamplifiers may also be used provided that they do not cause improper operation of the translator and compliance with specifications in paragraph (c) of this section does not depend upon the use of such preamplifiers.

(c) The following requirements must be met before translator equipment will be type accepted by the Commission:

(1) The frequency converter and associated amplifiers shall be so designed that the electrical characteristics of a standard television signal introduced into the input terminals will not be significantly altered by passage through the apparatus except as to frequency and amplitude. The overall response of the apparatus within its assigned channel when operating at its rated power output and measured at the output terminals, shall provide a smooth curve, varying within limits separated by no more than 4 decibels: *Provided, however,* That means may be provided to reduce the amplitude of the aural carrier below those limits, if necessary to prevent intermodulation which would mar the quality of the retransmitted picture or result in emissions outside of the assigned channel.

(2) Radio frequency harmonics of the visual and aural carriers, measured at the output terminals of the transmitter, shall be attenuated no less than 60 decibels below the peak visual output power within the assigned channel. All other emissions appearing on frequencies more than 3 megacycles above or below the upper and lower edges, respectively, of the assigned channel shall be attenuated no less than:

(i) 30 decibels for transmitters rated at less than 10 watts power output.

(ii) 40 decibels for transmitters rated at 10 watts or more power output.

(3) The local oscillator employed in the frequency converter shall maintain its operating frequency within 0.02 percent of its rated frequency when subjected to variations in ambient temperature between minus 30 degrees and plus 50 degrees Centigrade and variations in power main voltage between 85 percent and 115 percent of the rated supply voltage.

(4) The apparatus shall contain automatic circuits which will maintain the peak visual power output constant within 2 decibels when the strength of the input signal is varied over a range of 30 decibels and which will not permit the peak visual power output to exceed the maximum rated power output under any condition. If a manual adjustment is provided to compensate for different average signal intensities, provision shall be made for determining the proper setting for the control, and if improper adjustment of the control could result in improper operation, a label shall be affixed at the adjustment control bearing a suitable warning.

(5) The apparatus shall be equipped with automatic controls which will place it in a non-radiating condition when no signal is being received on the input channel, either due to absence of a transmitted signal or failure of the receiving portion of the translator. The automatic control may include a time delay feature to prevent interruptions in the translator operation caused by fading or other momentary failures of the incoming signal.

(6) The tube or tubes employed in the final radio frequency amplifier shall be of the appropriate power rating to provide the rated power output of the translator. The normal operating constants for operation at the rated power output shall be specified. The apparatus shall be equipped with suitable meters or meter jacks so that appropriate voltage and current measurements may be made while the apparatus is in operation.

(7) The transmitter shall be equipped with an automatic keying device which will transmit the call sign assigned to the station, in international Morse Code, within 5 minutes of the hour and half-hour. Transmission of the call sign shall be accomplished either by interrupting the radiated signals in the proper code sequence or by amplitude modulating the radiated signals with an audio frequency tone containing the telegraphic identification. The modulating signal may be inserted at any suitable stage in the apparatus but shall result in at least 30 percent amplitude modulation of the aural carrier. If an audio frequency tone is used it shall not be within 200 cycles of the 1,000 cycle tone used for Emergency Broadcast System alerting: *Provided, however,* That apparatus intended to be used solely for rebroadcasting the signals of another translator need not be equipped for such automatic transmission of its call sign if its call sign will be transmitted by the translator which it is rebroadcasting.

(8) Wiring, shielding, and construction shall be in accordance with accepted principles of good engineering practice.

(d) Type acceptance will be granted only upon a satisfactory showing that the apparatus is capable of meeting the requirements of paragraph (c) of this section. The following procedures shall apply:

(1) Any manufacturer of apparatus intended for use at television broadcast translator stations may request type acceptance by following the procedures set forth in Part 2, Subpart F, of this chapter. Equipment found to be acceptable by the Commission will be listed in the "Radio Equipment List, Part A, Television Broadcast Equipment," published by the Commission. These lists are available for inspection at any Field Office of the Commission and at the Washington, D.C., offices of the Commission.

(2) Television broadcast translator apparatus which has been type accepted by the Commission will normally be authorized without additional measurements by the applicant.

(3) Construction permits may be granted for the installation of custom-built apparatus which has not been type accepted by the Commission. In such cases, the permittee shall submit the information required by Part 2, Subpart F, of this chapter, together with sufficient measurements and data to show that the apparatus meets the requirements of paragraph (c) of this section. The measurements shall be made by a qualified electronic engineer with instruments of sufficient accuracy to insure the reliability of the data.

(4) Other rules concerning type acceptance, including information regarding withdrawal of type acceptance, modification of type accepted equipment and limitations on the findings upon which type acceptance is based, are set forth in Part 2, Subpart F, of this chapter.

(e) The installation of a television broadcast translator station employing custom-built apparatus or apparatus which has not been type accepted by the Commission, shall be made by or under the direct supervision of a person having the technical skill and engineering knowledge required to make a proper installation.

(f) The installation of a television broadcast translator station employing type accepted apparatus may be made by a person with sufficient technical

knowledge and skill to correctly follow the manufacturer's instructions.

(g) Simple repairs such as the replacement of tubes, fuses, or other plug-in components and the adjustment of non-critical circuits which require no particular technical skill may be made by an unskilled person. Repairs which require the replacement of attached components, adjustment of critical circuits, or technical measurements shall be made only by a person with the knowledge and skill to perform such tasks.

(h) Any tests or adjustments which require the radiation of signals for their completion and which could result in improper operation of the apparatus, shall be made by or under the immediate supervision of a licensed first or second class radiotelephone operator.

(i) The transmitting antenna may be designed to produce either horizontal, vertical, or circular polarization.

§ 74.751 Equipment changes.

(a) No change, either mechanical or electrical, may be made in apparatus which has been type accepted by the Commission without prior authority of the Commission. If such prior authority has been given to the manufacturer of type accepted equipment, the manufacturer may issue instructions for such changes citing its authority. In such cases, individual licensees are not required to secure prior Commission approval but shall notify the Commission when such changes are completed.

(b) Formal application (FCC Form 346) is required for any of the following changes:

(1) Replacement of the transmitter as a whole, except by one of an identical type.

(2) A change in the transmitting antenna system, including the direction of radiation, directive antenna pattern, or transmission line.

(3) Any change in the antenna which will increase the overall height above ground by more than 20 feet or will result in an overall height of more than 170 feet above ground.

(4) Any change in the location of the transmitter except a move within the same building or upon the same pole or tower.

(5) Any horizontal change in the location of the transmitting antenna of more than 500 feet.

(6) A change of frequency assignment.

(7) A change of the primary TV station being retransmitted.

(8) A change of authorized operating power.

(c) Other equipment changes not specifically referred to above may be made at the discretion of the licensee, provided that the Engineer in Charge of the radio district in which the television broadcast translator station is located and the Commission's Washington, D.C., office are notified in writing upon completion of such changes, and provided further that the changes are appropriately reflected in the next application for renewal of license of the television broadcast translator station.

Technical Operation and Operators

§ 74.761 Frequency tolerance.

The licensee of a television broadcast translator station shall maintain the visual carrier frequency and the aural center frequency at the output of the translator within 0.02 percent of its assigned frequencies when the primary station is operating exactly on its assigned frequency. This tolerance shall not be exceeded, at times when the primary station is not exactly on its assigned frequencies, by more than the amount of departure by the primary station.

§ 74.762 Frequency monitors and measurements.

(a) The licensee of a television broadcast translator station is not required to provide means for measuring the operating frequencies of the transmitter. However, only equipment having the required stability will be approved for use at a television broadcast translator station.

(b) In the event that a television broadcast translator station is found to be operating beyond the frequency tolerance prescribed in § 74.761, the licensee shall promptly suspend operation of the translator and shall not resume operation until the translator has been restored to its assigned frequencies. Adjustment of the frequency determining circuits of a television broadcast translator station shall be made only by a qualified person in accordance with § 74.750(g).

§ 74.763 Time of operation.

(a) A television broadcast translator station is not required to adhere to any regular schedule of operation. However, the licensee of a television translator station is expected to provide a dependable service to the extent that such is within its control and to avoid unwarranted interruptions to the service provided.

(b) If causes beyond the control of the licensee require that a television broadcast translator station remain inoperative for a period in excess of 10 days, the Engineer in Charge of the radio district in which the station is located shall be notified promptly in writing, describing the cause of failure and the steps taken to place the station in operation again, and shall be notified promptly when the operation is resumed.

(c) Failure of a television broadcast translator station to operate for a period of 30 days or more, except for causes beyond the control of the licensee, shall be deemed evidence of discontinuance of operation and the license of the station will be cancelled.

(d) A television broadcast translator station shall not be permitted to radiate during extended periods when signals of the primary station are not being retransmitted.

§ 74.764 Station inspection.

The licensee of a television broadcast translator station shall make the station and the records required to be kept by the rules in this subpart available for inspection by representatives of the Commission.

§ 74.765 Posting of station license.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the station or the manner of operation shall be kept in the station record file maintained by the licensee so as to be available for inspection upon request to any authorized representative of the Commission.

(b) The call sign of the translator together with the name, address, and telephone number of the licensee or local representative of the licensee if the licensee does not reside in the community served by the translator, shall be displayed at the translator site on the structure supporting the transmitting antenna, so as to be visible to a person standing on the ground at the transmitter site. The display shall be prepared so as to withstand normal weathering for a reasonable period of time and shall be maintained in a legible condition by the licensee.

§ 74.766 Operator requirements.

(a) No licensed radio operator is required for the routine operation of a television broadcast translator station provided that the requirements of § 74.734 are met. Otherwise, an operator holding a valid restricted radiotelephone operator permit or a first or second class radiotelephone operator license shall be on duty at the place where the transmitting apparatus is located at all times when the apparatus is being operated.

(b) A licensed operator employed to operate a TV translator may, at the discretion of the licensee, be employed for other duties or for the operation of another class of station or stations in accordance with the class of license which he holds and the rules and regulations governing such other stations. However, such duties shall in nowise interfere with the operation of the TV translator station.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.767 Marking and lighting of antenna structures.

The marking and lighting of antenna structures employed at a television broadcast translator station, where required, will be specified in the authorization issued by the Commission. Part 17 of this chapter sets forth the conditions under which such marking and lighting will be required and the responsibility of the licensee with regard thereto.

§ 74.768 Additional orders.

In cases where the rules contained in this part do not cover all phases of operation or experimentation with respect to external effects, the Commission may make supplemental or additional orders in each case as may be deemed necessary.

§ 74.769 Copies of rules.

The licensee of a television broadcast translator station shall have current copies of Part 73, Part 74, and in cases where antenna marking is required, Part 17 of this chapter available for use by the operator in charge, and is expected to be familiar with those rules relating to

the operation of a television broadcast translator station. Copies of the Commission's rules may be obtained from the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, at nominal cost.

OTHER OPERATING REQUIREMENTS

§ 74.781 Station records.

(a) The licensee of a television broadcast translator station shall maintain adequate station records, including the current instrument of authorization, official correspondence with the Commission, maintenance records, contracts, permission for rebroadcasts, and other pertinent documents.

(b) Where an antenna structure is required to be painted or illuminated, see § 17.38 of this chapter.

(c) The station records shall be made available upon request to any authorized representative of the Commission.

(d) Station records shall be retained for a period of two years.

§ 74.783 Station identification.

(a) Each television broadcast translator station shall transmit its call sign in international Morse Code at the beginning of each period of operation and during operation, within 5 minutes of the hour and half-hour. The transmission may be accomplished either by means of an automatic device incorporated in the translator apparatus, which will modulate the local oscillator or a suitable amplifier stage in the translator with an audio frequency tone keyed in the proper sequence so as to cause the modulation to appear on the visual and aural carriers emitted by the translator; or by rebroadcasting the signals of another translator which transmits the call signs of translators which are rebroadcasting its signals. The audio frequency tone shall produce no less than 30 percent amplitude modulation of the emitted aural carrier and shall not be within 200 cycles of the 1,000 cycle tone used for Emergency Broadcast System alerting. In cases where a translator transmits more than one call sign, the individual call signs shall be separated by the international Morse Code character for the fraction bar composed of a dash, two dots, a dash, and a dot, sent as a single character (—..—.). Call sign transmissions shall be made at a code speed not in excess of 20 words per minute. At this speed the transmission of each individual call sign will require approximately 4 seconds.

(b) The Commission may, in its discretion, specify other methods of identification.

(c) Call signs for television broadcast translator stations will be made up of the initial letter K or W followed by the channel number assigned to the translator and two letters. The use of the initial letter will generally follow the pattern used in the broadcast service, i.e., stations west of the Mississippi River will be assigned an initial letter K and those east of the Mississippi River the letter W. The two letter combinations following the channel number will be assigned in order and requests for the assignment of particular combinations of letters will not be considered. The channel number designator for Channels 2 through 9 will be incorporated in the call sign as a two-digit number, i.e., Ø2, Ø3, Ø4, Ø5, Ø6, Ø7, Ø8, or Ø9, to avoid similarities with call signs assigned to Amateur Radio Stations.

§ 74.784 Rebroadcasts.

(a) The term "rebroadcast" means the reception by radio of the programs or other signals of a radio or television station and the simultaneous or subsequent retransmission of such programs or signals for direct reception by the general public.

(b) The licensee of a television broadcast translator station shall not rebroadcast the programs of any television broadcast station or other television broadcast translator station without obtaining prior consent of the station whose signals or programs are proposed to be retransmitted. The Commission shall be notified of the call letters of each station rebroadcast and the licensee of the television broadcast translator station shall certify that written consent has been received from the licensee of the station whose programs are retransmitted.

(c) A television broadcast translator station is not authorized to rebroadcast the transmissions of any class of station other than a television broadcast station or another television broadcast translator station.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

PRE-EXISTING REPEATERS

§ 74.790 Special requirements for pre-existing VHF repeaters.

(a) Until July 31, 1962, the provisions of this section shall apply to repeater stations which are rebroadcasting TV signals on VHF Channels 2–13, and which were constructed on or before July 7, 1960. The term "repeater station" is used in this section to refer to low power devices for the reception, amplification and retransmission of television signals, irrespective of whether the output channel is the same as the input channel, or is a different channel as in the case of VHF translators.

(b) On or before December 30, 1960, the operators of all devices covered in paragraph (a) of this section shall file with the Commission at its Washington offices an application for temporary authorization to continue operation. Such application shall be filed on FCC Form 347–A in accordance with instructions accompanying that form.

(c) Applicants must comply with requirements imposed by law, including those found in the following sections of the Communications Act of 1934:

(1) Section 308(b) which requires that the application be signed by the applicant under oath or affirmation.

(2) Section 310 which, among other things, prohibits the issuance of a license to an alien or an organization of which any officer or director is an alien.

(3) Section 325 which prohibits rebroadcasting of the programs of another broadcasting station without the express authority of the other station. Applicants must certify that such consent has been obtained in writing and is available for inspection by the Commission.

(d) An applicant for a temporary authorization under this section shall certify in his application that on or before June 1, 1961, he will file an application on FCC Form 346 for authority to replace or modify the facility for which temporary authorization is sought, so as to conform to all the requirements set out in §§ 74.701 through 74.784 with respect to television broadcast translators.

(e) Existing repeaters may not be modified, and no new translator may be constructed, prior to the issuance of Commission approval of an application filed on FCC Form 346 for authorization to make a desired modification or to construct a new translator.

(f) Temporary authorizations issued under this section will be valid until July 31, 1962, provided that the holder of such authorization has filed on or before October 31, 1961, an application on FCC Form 346 for authority to replace or modify the facility for which the temporary authority is held, so as to conform in all respects with the requirements of §§ 74.701 through 74.784. The replacement or modification authorized under the construction permit so issued shall be completed by July 31, 1962.

(Sec. 319, 48 Stat. 1089, as amended by 74 Stat. 363; 47 U.S.C. 319)

Subpart H—Television Broadcast Booster Stations

DEFINITIONS AND ALLOCATION OF FREQUENCIES

§ 74.801 Definitions.

(a) *Television broadcast booster station.* A station in the broadcasting service operated for the sole purpose of retransmitting the signals of a television broadcast station by amplifying and reradiating such signals which have been received directly through space, without significantly altering any characteristic of the incoming signal other than its amplitude.

(b) *Primary station.* The television broadcast station radiating the signals which are retransmitted by a television broadcast booster station.

§ 74.802 Frequency assignment.

A television broadcast booster station will be assigned the channel and carrier frequencies assigned to its primary station.

§ 74.803 Interference to primary station.

(a) An application for a new television broadcast booster station or for a change in the facilities of an existing station shall be accompanied by a detailed showing and discussion of the areas of potential interference. The showing shall include:

(1) A suitable map of the area in which the booster is proposed to be operated showing the location of the booster, the direction from the booster toward the primary station and the distance to the primary station, the radiation pattern of the booster, and the areas in which an unfavorable ratio is likely to exist between the direct signal and the

boosted signal. If certain terrain features are expected to confine or otherwise minimize interference, these shall be clearly marked.

(2) A statement as to the approximate number of existing receiving installations which may be adversely affected by the proposed booster operation and the measures which will be employed by the applicant to restore reception, including an estimate of the cost of such restoration and how this cost will be borne.

(b) It shall be the responsibility of the licensee of a television broadcast booster station to correct any condition of interference resulting from the operation of the booster to a receiving installation existing at the time the booster is placed in operation, which causes loss or degradation of on otherwise acceptable service from the primary station if requested to do so by the owner of the affected TV receiver. The licensee of the booster is expected to provide such advice, technical assistance, and materials as may be required to restore the lost service either by rejecting the booster signals to the extent necessary to restore the direct service to its original condition or by utilizing the booster service to replace the lost direct service. Refusal of the complainant to permit the application of remedies which are demonstrably capable of restoring the lost service will relieve the booster licensee of further responsibility for the correction of interference to that complainant.

§ 74.804 Interference to other stations and services.

(a) The licensee of a television broadcast booster station is responsible for the correction of interference to reception of other television broadcast stations or stations in other services, caused by:

(1) Radiation of radio frequency energy outside the channel assigned to the booster.

(2) Radiation of spurious emissions, i.e., emissions not contained in the visual and sound signal received from the primary TV station, within the channel assigned to the booster.

(3) Authorized emissions which produce a field strength at the affected receiver in excess of the theoretical field which would be produced at that same location by the primary TV station if the primary TV station were operating with 5 megawatts effective radiated power from an antenna 2,000 feet above average terrain over a path of normal terrain. The theoretical value of field strength which could be produced by the primary station, under the conditions stipulated, shall be determined by the use of the F(50,50) field strength charts for Channels 14–83, contained in § 73.699 of this chapter.

(b) Upon notification by the Commission that such interference has been reported, operation of the booster shall be suspended and shall not be resumed until the interference has been eliminated or it can be demonstrated that the interference is not due to any of the above causes: *Provided, however,* That short test transmissions may be made during the period of suspended operation to check the efficacy of remedial measures. In each case where suspension of operation is required, the licensee of the TV booster shall, within 10 days after operation is resumed, submit a full report to the Commission of the cause and nature of the interference and the remedial steps taken to eliminate the interference.

(c) An application for a new television broadcast booster station shall contain a suitable map showing the locations of the proposed booster and all other TV boosters and television broadcast stations within 75 miles of the proposed booster site and operating on the same channel as the proposed booster or on any related channel shown in the columns opposite the proposed booster channel in Table IV of § 73.698 of this chapter.

Administrative Procedure

§ 74.811 Administrative procedure.

See §§ 74.11 to 74.16 inclusive.

Licensing Policies and General Operating Requirements

§ 74.831 Purpose and permissible service.

Television broadcast booster stations provide a means whereby the licensees of television broadcast stations operating in the UHF television broadcast band may provide service to areas of low signal intensity in any region which would be encompassed by the theoretical Grade A contour if the station were assumed to be operating with an effective radiated power of 5,000 kilowatts from an antenna 2,000 feet above average terrain over a transmission path of normal terrain. For the purpose of this section, the distance from a UHF television broadcast station to its theoretical Grade A contour under the above assumptions is 68 miles.

(a) A television broadcast booster station is authorized to retransmit only the signals of its primary station. It shall not retransmit the signals of any other station nor make independent transmissions: *Provided, however,* That locally generated signals may be used to excite the booster apparatus for the purpose of conducting tests and measurements essential to the proper installation and maintenance of the apparatus.

(b) A television broadcast booster station will not be authorized to operate at any location more than 68 miles from its primary station and shall not be operated to produce a field strength greater than 5 millivolts per meter at a height of 30 feet above ground at a distance of more than 68 miles from its primary station.

(c) The transmissions of a television broadcast booster station shall be intended for direct reception by the general public. Such stations may not be used to establish a point-to-point television relay system.

§ 74.832 Eligibility and licensing requirements.

(a) A license for a television broadcast booster station will be issued only to the licensee of a television broadcast station operating in the UHF television broadcast band, and solely for the purpose of retransmitting the signals of such television broadcast station.

(b) An application for a television broadcast booster station shall contain an adequate showing that:

(1) The proposed booster can be installed and operated so as to provide satisfactory reception without causing harmful interference to existing service, by the application of acceptable techniques.

(2) That a signal of sufficient magnitude is available from the primary station at the site of the proposed booster.

(c) No numerical limit is placed upon the number of boosters which may be licensed to a single licensee. A separate application is required for each booster transmitter. Television broadcast booster stations will not be counted as TV stations in applying the multiple ownership provisions of § 73.636 of this chapter.

§ 74.834 Remote control operation.

(a) A television broadcast booster station may be operated by remote control provided that such operation is conducted in accordance with the conditions set forth in subparagraphs (1) through (4) of this paragraph:

(1) The transmitter shall be equipped with automatic devices, which, in the absence of a signal from the primary station, will render the transmitter incapable of emitting radio frequency energy.

(2) The transmitter shall be further equipped with a device, which may be actuated by a coded signal or tone transmitted by the primary station, and which will permit turning the transmitter on and off at will from the primary station. The signal required to be transmitted by the primary station for this purpose shall be of such nature or of duration so short that it will not appreciably degrade normal reception of the primary station.

(3) As a precaution against loss of control due to failure of the control circuit, the circuit shall be designed so as to require reception of a cue signal from the primary station at intervals of one hour or less and failure to receive the cue signal will automatically place the booster transmitter in an inoperative condition.

(4) The transmitter and its associated controls shall be so installed and protected as to be inaccessible to unauthorized persons.

(b) An application for a new television broadcast booster station, or for a change in the facilities of an existing station which proposes remote control operation, shall be accompanied by a satisfactory showing as to the manner of compliance with the above conditions. Unless remote control is specifically authorized pursuant to the above requirements, the booster transmitter shall be under the direct supervision of a qualified operator in accordance with § 74.866.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.835 Power limitations.

(a) A television broadcast booster station will not be authorized to operate with power in excess of that required to

provide an adequate signal over the area intended to be served by the booster. Due consideration should be given to the provisions of § 74.804 which requires the licensee of a television broadcast booster station to correct any condition of interference which results from field strengths in excess of those which could be produced by the primary station at the place where interference occurs.

(b) In no event will a television broadcast booster station be authorized to operate with an effective radiated power of more than 5 kilowatts peak visual.

(c) In no event will a television broadcast booster station be authorized to operate at a location, and with an effective radiated power, and antenna height above average terrain, which would produce a predicted field strength of more than 5 millivolts per meter at any location more than 68 miles from the primary station. The predicted field strength of a television broadcast booster station shall be determined in accordance with the procedure set forth in § 74.684 of this chapter. If a directive transmitting antenna is to be used to suppress radiation so as to comply with this requirement, the proposed directive pattern shall be supported with adequate engineering data.

(d) No minimum power is specified for television broadcast booster stations.

§ 74.836 Emissions and bandwidth.

(a) The license of a television broadcast booster station authorizes the transmission of the visual signal by amplitude modulation (A5) and the accompanying aural signal by frequency modulation (F3).

(b) Standard width television channels will be assigned and the emission of a television broadcast booster station shall be confined to the authorized channel in accordance with the Television Technical Standards contained in Part 7[illegible], Subpart E, of this chapter, except as provided in paragraph (c) of this section.

(c) Radio frequency harmonics of the visual and aural carriers shall be attenuated no less than 60 decibels for transmitters operating with more than 1 kilowatt power output. For transmitters operating with power output of 1 kilowatt or less, the power in such radio frequency harmonics shall not exceed 1 milliwatt. Other spurious emissions on frequencies more than 3 megacycles outside the assigned channel, including intermodulation products, signals other than those received from the primary station, and radio frequency energy generated within the booster apparatus, shall be attenuated no less than 40 decibels below the peak visual carrier amplitude. Greater attenuation of all spurious emissions may be required if interference is caused to any radio service.

§ 74.837 Antenna location.

(a) The transmitting antenna of a television broadcast booster station shall be located within the Grade A contour of the primary station, as defined in § 74.831.

(b) An applicant for a new television broadcast booster station or for changes in an existing station shall endeavor to select a site which will provide a line-of-sight transmission path to the area intended to be served and at which there is a suitable signal available from the primary station. The transmitting antenna should be placed above growing vegetation lying in the direction of the area intended to be served to minimize the possibility of signal absorption by foliage.

(c) Consideration should be given to accessibility of the site at all seasons of the year and to the availability of facilities for the maintenance and operation of the television broadcast booster station.

(d) Consideration should be given to the existence of strong radio frequency fields from other transmitters at the booster site and possibility that such fields may result in the retransmission of signals originating on frequencies other than that of the primary station.

EQUIPMENT

§ 74.850 Equipment and installation.

(a) An application for a new television broadcast booster station or for changes in the facilities of an existing station shall supply complete technical details of the apparatus to be employed and the overall installation. The functioning of such automatic features or other safeguards as may be incorporated to prevent improper operation shall be fully described. If the apparatus is to be remotely controlled, a detailed description of the control features shall be included.

(b) The overall characteristics of the complete installation shall be essentially linear so as to accomplish retransmission of the incoming signals of the primary station without significantly altering any electrical characteristics other than the overall amplitude. Intermodulation products which may be generated shall be adequately removed from the transmissions of the booster so as not to constitute a source of potential interference. Provision shall be made, in the circuits employed, to prevent the amplifier being driven into a non-linear condition over the full range of signal intensities within which the booster may be called upon to operate, or to cause it to cease radiating should non-linear operation or oscillation of any stage occur.

(c) The isolation between the input and output circuits of the booster, including the receiving and transmitting antenna systems, shall be at least 20 decibels greater than the maximum overall gain of the booster amplifier.

(d) The overall response of the amplifier shall not vary by more than 2 decibels over the entire assigned channel: *Provided, however,* That the amplitude of the aural signal may be decreased by a suitable amount if necessary to minimize intermodulation effects or eliminate interference between the sound and picture signals. The apparatus shall be capable of complying with the requirements of § 74.836(c) with respect to spurious emissions.

(e) In general, the transmitter shall be mounted on racks and panels or in totally enclosed frames protected as required by Article 810 of the National Electrical Code.

(f) The installation of a television broadcast booster station shall be made only by, or under the direct supervision of, a qualified electronics engineer and any repairs or adjustments made during or subsequent to the installation, which could result in improper operation, shall be made by or under the direct supervision of such an engineer or an operator holding a valid first or second class radiotelephone operator license issued by the Commission.

(g) In cases where the electrical characteristics of the transmitting and receiving antennas of a booster station are used to provide the required degree of isolation between the input and output circuits, the installation of such antennas shall be sufficiently rugged and protected as to withstand such hazards as may reasonably be expected to be encountered due to their exposure to the elements and the local environment.

(h) Prior to placing a television broadcast booster station in regular operation, the permittee shall perform sufficient measurements of the completed installation to insure compliance with this section. These measurements together with a detailed description of the methods used in obtaining the measurements shall be submitted with the application for license for the booster station.

(i) Type acceptance of television booster amplifiers may be granted upon request in accordance with the type acceptance procedure set forth in Part 2 of this chapter, provided that measurement data and descriptive information submitted shows that the amplifier is capable of meeting the technical requirements of this subpart. The following measurement data must be supplied:

(1) Radio frequency power output (visual peak power).

(2) Over-all gain of the amplifier vs. frequency throughout the entire channel in which it is designed to operate.

(3) Spurious emissions appearing on frequencies outside the channel in which it is designed to operate, including radio frequency harmonics up to 2,000 megacycles.

§ 74.851 Equipment changes.

(a) Formal application (FCC Form 343) is required for any of the following changes:

(1) Replacement of the transmitter as a whole, except replacement with an identical transmitter, or any modification which could result in a change in the electrical characteristics or overall performance of the booster installation.

(2) A change in the transmitting antenna system, including the direction of radiation, directive pattern, or transmission line.

(3) An increase in the authorized overall height of the antenna above ground of more than 20 feet or which will result in an overall height above ground of more than 170 feet.

(4) A change in the control system.

(5) Any change in the location of the transmitter except a move within the same building or upon the same tower

or pole, and any horizontal change in the antenna location of the transmitting antenna in excess of 500 feet.

(6) A change of frequency assignment.

(7) A change of authorized operating power.

(b) Other equipment changes not specifically referred to above may be made at the discretion of the licensee, provided that the Engineer in Charge of the radio district in which the television broadcast booster station is located and the Commission's Washington, D.C., office are notified in writing upon completion of such changes, and provided, further, that the changes are appropriately reflected in the next application for renewal of license of the television broadcast booster station.

TECHNICAL OPERATION AND OPERATORS

§ 74.861 Frequency tolerance.

The visual carrier frequency and the aural center frequency of the television signals transmitted by a television broadcast booster station shall be identical with those of the primary station.

§ 74.862 Frequency monitors and measurements.

The licensee of a television broadcast booster is not required to provide means for measuring the operating frequencies of the booster transmitter.

§ 74.863 Time of operation.

(a) A television broadcast booster station is not required to adhere to any regular schedule of operation. However, the licensee of a television booster station is expected to provide a dependable service to the extent that such is within its control and to avoid unwarranted interruptions to the service provided.

(b) If causes beyond the control of the licensee require that a television broadcast booster station remain inoperative for a period in excess of 10 days, the Engineer in Charge of the radio district in which the station is located shall be notified promptly in writing, describing the cause of failure and the steps taken to place the station in operation again, and shall be notified promptly when the operation is resumed.

(c) Failure of a television broadcast booster station to operate for a period of 30 days or more, except for causes beyond the control of the licensee, shall be deemed evidence of discontinuance of operation and the license of the station will be automatically forfeited.

(d) A television broadcast booster station shall not be operated during periods when the primary station is not operating.

§ 74.864 Station inspection.

The licensee of a television broadcast booster station shall make the station and the records required to be kept available for inspection upon request by representatives of the Commission.

§ 74.865 Posting of station and operator licenses.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the equipment or manner of operation shall be posted at the place where the transmitter is located, so that all of the terms thereof are visible: *Provided, however,* That if the booster transmitter is operated by remote control and is located more than 20 miles from the primary station, the station license and other instruments of authorization shall be posted in the above-described manner at the transmitter of the primary station.

(b) The call letters and assigned channel of the primary station shall be displayed at the booster site on the structure supporting the transmitting antenna so as to be visible to a person standing on the ground at the booster transmitter site. The display shall be prepared so as to withstand normal weathering for a reasonable period of time and shall be maintained in a legible condition by the licensee.

(c) The original of each station operator license shall be posted at the place where he is on duty: *Provided, however,* That if the original license of a station operator is posted at another radio transmitting station in accordance with the rules governing that class of station and is there available for inspection by a representative of the Commission, a verification card (Form 758–F) is acceptable in lieu of the posting of such license: *Provided further, however,* That if the operator in charge holds a restricted radiotelephone operator permit of the card form (as distinguished from the diploma form), he shall not post that permit but shall keep it in his personal possession.

§ 74.866 Operator requirements.

(a) The actual operation of the transmitting apparatus at a television broadcast booster station shall be carried on only by a person holding a valid first or second class radiotelephone operator license: *Provided, however,* That where the booster transmitter is remotely controlled by the transmission of coded signals from the primary station, an unlicensed person may turn the power supplied to the booster by the power mains, on and off upon instructions from the operator on duty at the primary station.

(b) The licensed operator on duty and in charge of a television broadcast booster station may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of license which he holds and the rules and regulations governing such stations. However, such duties shall in no wise interfere with the operation of the television broadcast booster station.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.867 Marking and lighting of antenna structures.

The marking and lighting of antenna structures employed at a television broadcast booster station, where required, will be specified in the authorization issued by the Commission. Part 17 of this chapter sets forth the conditions under which such marking and lighting will be required and the responsibility of the licensee with regard thereto.

§ 74.868 Additional orders.

In case the rules contained in this part do not cover all phases of operation or experimentation with respect to external effects, the Commission may make supplemental or additional orders, in each case as may be deemed necessary.

§ 74.869 Copies of rules.

The licensee of a television broadcast booster station shall have current copies of Part 73 and Part 74, and in cases where antenna marking is required, Part 17 of this chapter, available for use by the operator in charge, and is expected to be familiar with those rules relating to the operation of a television broadcast booster station. Copies of the Commission's rules may be obtained from the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, at nominal cost.

OTHER OPERATING REQUIREMENTS

§ 74.881 Station records.

(a) The licensee of a television broadcast booster station shall maintain an operating log showing the following:

(1) Hours of operation.

(2) A record of all repairs, adjustments, maintenance, tests, and equipment changes, showing the date of such events, the name and qualifications of the person performing the operation, and a brief description of the matter logged.

(b) Where an antenna structure is required to be illuminated, see § 17.38 of this chapter.

(c) The operating log shall be made available upon request to any authorized representative of the Commission.

(d) Station records shall be retained for a period of two years.

§ 74.883 Station identification.

(a) Television broadcast booster stations will not be assigned individual call signs. Station identification will be accomplished by the retransmission of the call sign of the primary station.

(b) The Commission may request the operator on duty at the primary station to interrupt the transmissions of the booster station for short intervals of time in order to facilitate identification of a particular booster.

§ 74.884 Rebroadcasts.

(a) The term "rebroadcast" means the reception by radio of the programs or other signals of a radio or television station and the simultaneous or subsequent retransmission of such programs or signals for direct reception by the general public.

(b) A television broadcast booster station is authorized to rebroadcast only the signals of the primary station with which it is associated. In cases where the booster is located at a site where the signals of other television broadcast stations or other classes of stations may be received, care shall be exercised in the installation to insure that such other signals are not retransmitted: *Provided, however,* That occasional inadvertent retransmission of the signals of other co-channel TV stations, caused by abnormal propagation conditons, will not be considered to be noncompliance.

Subpart I—Instructional Television Fixed Stations

Definitions and Allocation of Frequencies

§ 74.901 Definitions.

Attended operation. Operation of a station by a qualified operator on duty at the place where the transmitting apparatus is located with the transmitter in plain view of the operator.

Instructional television fixed station. A fixed station operated by an educational organization and used primarily for the transmission of visual and aural instructional, cultural, and other types of educational material to one or more fixed receiving locations.

Remote control. Operation of a station by a qualified operator on duty at a control position from which the transmitter is not visible but which control position is equipped with suitable control and telemetering circuits so that the essential functions that could be performed at the transmitter can also be performed from the control point.

Unattended operation. Operation of a station by automatic means whereby the transmitter is turned on and off and performs its functions without attention by a qualified operator.

§ 74.902 Frequency assignments.

(a) The following frequencies may be assigned to instructional television fixed stations:

Group A		Group B		Group C	
Channel No.	Band limit Mc/s	Channel No.	Band limit Mc/s	Channel No.	Band limit Mc/s
A-1	2500–2506	B-1	2506–2512	C-1	2512–2518
A-2	2536–2542	B-2	2542–2548	C-2	2548–2554
A-3	2572–2578	B-3	2578–2584	C-3	2584–2590
A-4	2608–2614	B-4	2614–2620	C-4	2620–2626
A-5	2644–2650	B-5	2650–2656	C-5	2656–2662
A-6	2680–2686				

Group D		Group E		Group F	
Channel No.	Band limit Mc/s	Channel No.	Band limit Mc/s	Channel No.	Band limit Mc/s
D-1	2518–2524	E-1	2524–2530	F-1	2530–2536
D-2	2554–2560	E-2	2560–2566	F-2	2566–2572
D-3	2590–2596	E-3	2596–2602	F-3	2602–2608
D-4	2626–2632	E-4	2632–2638	F-4	2638–2644
D-5	2662–2668	E-5	2668–2674	F-5	2674–2680

(b) The frequency band 2500–2690 Mc/s is shared with operational fixed and international control stations. Assignments to new instructional television fixed stations will not be made where interference will be caused to existing stations operating in accordance with the Table of Frequency Allocations in § 2.106 of this chapter. Similarly, assignments to new operational fixed or international control stations will not be made where interference will be caused to existing instructional television fixed stations. Operational fixed and international control stations may employ different channelling and this fact should be kept in mind in assessing potential interference.

(c) A single licensee will be normally limited to the assignment of not more than five channels selected from one of the groups listed in paragraph (a) of this section, for use in a given area. The Commission may limit the total number of channels to less than five if such is found to be necessary in order to assure a fair and equitable distribution of the channels among several potential applicants. In individual cases, more than five channels may be assigned to a single licensee upon a satisfactory showing of need and after a determination has been made that such additional assignments may be made without depriving other eligible users of adequate availability of channels.

(d) The same channel may be assigned to more than one station or more than one licensee in the same area if the geometric arrangement of the transmitting and receiving points or the times of operation are such that interference is not likely to occur.

§ 74.903 Interference.

(a) Since interference in this service will occur only when an unfavorable desired-to-undesired signal ratio exists at the antenna input terminals of the affected receiver, the directive properties of receiving antennas can be used to minimize the hazard of such interference. Interference may also be controlled through the use of directive transmitting antennas, geometric arrangement of transmitters and receivers, and the use of the minimum power required to provide the needed service.

(b) An applicant for a new instructional television fixed station is expected to take full advantage of such techniques to prevent interference to the reception of any existing operational fixed, international control station or instructional television fixed station at authorized receiving locations. In cases where it can be demonstrated that potential interference could be effectively controlled with practical refinements at such existing receiving locations, the user of the receiving installation is expected to make the needed refinements if intereference-free reception is desired.

(c) Existing licensees and prospective applicants are expected to cooperate fully in attempting to resolve problems of potential interference before bringing the matter to the attention of the Commission.

Administrative Procedure

§ 74.911 Cross reference.

See §§ 74.11 to 74.16.

Licensing Policies and General Operating Requirements

§ 74.931 Purpose and permissible service.

(a) Instructional television fixed stations are intended primarily to provide a means for the transmission of instructional and cultural material in visual form with an associated aural channel to specified receiving locations for the primary purpose of providing a formal education and cultural development to students enrolled in accredited public and private schools, colleges, and universities.

(b) Such stations may also be used for the additional purpose of transmitting visual and aural material to selected receiving locations for in-service training and instruction in special skills and safety programs, extension of professional training, informing persons and groups engaged in professional and technical activities of current developments in their particular fields, and other similar endeavors.

(c) During periods when the circuits provided by these stations are not being used for the transmission of instructional and cultural material, they may be used for the transmission of material directly related to the administrative activities of the licensee such as the holding of conferences with personnel, distribution of reports and assignments, exchange of data and statistics, and other similar uses. Stations will not be licensed in this service solely for the transmission of administrative traffic.

(d) Stations may be licensed in this service for operation as relay stations to interconnect instructional television fixed station systems in adjacent areas, to deliver instructional and cultural material to commercial and noncommercial educational television broadcast stations, to obtain program material from commercial and noncommercial educational television broadcast stations for use on the instructional television fixed system, and to deliver instructional and cultural material to, and obtain such material from, nearby terminals or connection points of closed circuit educational television systems employing wired distribution systems or radio facilities authorized under other parts of this chapter.

(e) Material transmitted by these stations may be intended for simultaneous reception and display or may be recorded for use at a later time.

§ 74.932 Eligibility and licensing requirements.

(a) A license for an instructional television fixed station will be issued only to an institutional or governmental organization engaged in the formal education of enrolled students or to a nonprofit organization formed for the purpose of providing instructional television material to such institutional or governmental organizations, and which is otherwise qualified under the statutory provisions of the Communications Act of 1934, as amended. A nonprofit organization which would be eligible for a license for a noncommercial educational television broadcast station is considered to be eligible for a license for an instructional television fixed station.

(1) In determining the eligibility of publicly supported educational organizations, the accreditation of the appropriate state department of education will be taken into consideration.

(2) In determining the eligibility of privately controlled educational organizations, the accreditation of the appropriate state department of education or the recognized regional and national accrediting organizations will be taken into consideration.

(b) No numerical limit is placed on the number of stations which may be licensed to a single licensee. However, individual licensees will be governed by the limitation of § 74.902 as to the num-

ber of channels which may be used. A single license may be issued for more than one transmitter if they are to be located at a common site and operated by the same licensee. Applicants are expected to accomplish the proposed operation by the use of the smallest number of channels required to provide the needed service.

(c) An application for a new instructional television fixed station or for changes in the facilities of an existing station shall specify the location of the transmitter and all proposed receiving installations which will be under the control of the applicant or will be equipped for reception by the applicant. If reception is also intended at unspecified locations, i.e., if power is deliberately radiated to locations or areas so that voluntary reception will be possible, the applications shall include a complete statement as to the purpose of such additional reception.

§ 74.933 Remote control operation.

(a) An instructional television fixed station may be operated by remote control if the following conditions are met:

(1) The transmitter and associated control system shall be installed and protected in a manner designed to prevent tampering or operation by unauthorized persons.

(2) An operator meeting the requirements of § 74.965 shall be on duty at the remote control position and in actual charge thereof at all times when the station is in operation.

(3) Facilities shall be provided at the control position which will permit the operator to turn the transmitter on and off at will. The control position shall also be equipped with devices suitable for observing the overall characteristics of the transmissions and a carrier-operated device which will give a continuous visual indication whenever the transmitting antenna is radiating a signal. The transmitting apparatus shall be inspected as often as may be necessary to insure proper operation and in any event at least once a day.

(4) The control circuits shall be so designed and installed that short circuits, open circuits, other line faults, or any other cause which would result in loss of control of the transmitter, will automatically cause the transmitter to cease radiating.

(b) An application for authority to construct a new station or to make changes in the facilities of an existing station and which proposes operation by remote control shall include an adequate showing of the manner of compliance with the requirements of this section.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.934 Unattended operation.

(a) Unattended operation of an instructional television fixed station will be permitted only when it is used for relaying the signals of another station which is employing the transmission standards specified for stations operating in this service and then only if the following requirements are met:

(1) The transmitter shall be equipped with automatic circuits which will permit it to radiate only when a signal on the channel which it is intended to retransmit is present at the input terminals of the apparatus. The automatic circuit may be provided with a reasonable time-delay factor to prevent the transmitter from being turned off during momentary failures of the incoming signal.

(2) The transmitter shall accomplish the relaying of the incoming signal by direct heterodyne frequency conversion to a different channel, or linear amplification of the incoming signal. The use of a common oscillator to convert the incoming signal to a low frequency for amplification and to reconvert it to its original channel will be considered to be the same as linear amplification. In cases where frequency conversion to a different channel is employed, the electrical characteristics of the incoming signal when retransmitted shall not be significantly altered except as to frequency and amplitude. In cases where linear amplification is employed, the electrical characteristics of the incoming signal when retransmitted shall not be significantly altered except as to amplitude. Care shall be taken in the design and installation of an unattended relay station to prevent instability which could result in spurious or other unwanted radiation.

(3) If the transmitting apparatus is located at a site which is not readily accessible at all hours and in all seasons, means shall be provided for turning the transmitter on and off at will from a location which can be reached promptly at all hours and in all seasons.

(4) The transmitter and any associated control circuits shall be installed and protected in a manner designed to prevent tampering or operation by unauthorized persons.

(5) In cases where the antenna supporting structure of an unattended station is required to have aeronautical hazard markings pursuant to the provisions of Part 17 of this chapter, the licensee shall provide for inspection and logging of observations of such markings as required by §§ 17.37 and 17.38 of this chapter.

(b) An application for authority to construct a new station or to make changes in the facilities of an existing station and which proposes unattended operation shall include an adequate showing as to the manner of compliance with the requirements of this section.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.935 Power limitations.

(a) The power of an instructional television fixed station will be limited to that required to perform the proposed service. Applicants are expected to take full advantage of the power-concentrating properties of directive transmitting antennas and the collective properties of directive receiving antennas to provide the needed service.

(b) An application for a new instructional television fixed station or for changes in the facilities of an existing station proposing a peak visual power output from the transmitter in excess of 10 watts shall include a showing as to the distance and direction to each specified receiving point, the elevation above ground and the power gain of each receiving antenna at such receiving points, the vertical and horizontal directive patterns of the proposed transmitting antenna system in terms of power gain, the elevation of the transmitting antenna above ground and the nature of significant terrain features over the transmission path or paths.

(c) The operating power (peak visual) of an instructional television fixed station shall not be permitted to exceed the authorized power by more than 10 percent at any time.

(d) The transmitter power output of the aural signal shall not be more than 70 percent nor less than 10 percent of the peak power output of the visual signal.

§ 74.936 Emissions and bandwidth.

(a) An instructional television fixed station shall normally employ amplitude modulation (A5) for the transmission of the visual signal and frequency modulation (F3) for the transmission of the aural signal.

(b) The average power of radio frequency harmonics of the visual and aural carriers, measured at the output terminals of the transmitter, shall be attenuated no less than 60 decibels below the peak visual output power within the assigned channel. All other emissions appearing on frequencies more than 3 Mc/s above or below the upper and lower edges, respectively, of the assigned channel shall be attenuated no less than:

(1) 30 decibels for transmitters rated at less than 10 watts visual peak power output.

(2) 40 decibels for transmitters rated at 10 watts or more visual peak power output.

(c) Should interference occur as the result of emissions outside the assigned channel, greater attenuation may be required.

§ 74.937 Antennas.

(a) In order to minimize the hazard of harmful interference from other stations, directive receiving antennas should be used at all receiving points. The choice of receiving antennas is left to the discretion of the licensee. However, should interference occur and it can be demonstrated that such interference could be eliminated through the use of a more suitable yet practical directive receiving antenna, the licensee of the station causing the interference is absolved of the responsibility of correcting the interference condition.

(b) Directive transmitting antennas shall be used wherever feasible so as to minimize the hazard of harmful interference to other licensees. The radiation pattern shall be designed to minimize radiation in directions where no reception is intended.

(c) In selecting a location for the transmitting antenna, it should be borne in mind that interference to the reception of its transmission is most likely to come from the direction in which receiving antennas must be aimed to receive its transmissions. Whenever possible the location should be chosen so

that the receiving antennas in its system are aimed in directions from which interfering signals are least likely to come.

(d) The use of elevated receiving antennas is preferable to the use of elevated transmitting antennas or greater power to provide the desired service.

(e) The use of vertical or horizontal plane polarization or right-hand or left-hand rotating (circular) polarization may be used to minimize the hazard of harmful interference between systems. The Commission reserves the right to specify the polarization to be used.

(f) The power gain compared to an isotropic antenna and the directive properties of the transmitting and receiving antennas proposed to be employed, as well as the geometric distribution of the transmitting and receiving points, shall be supplied with each application for a new educational television fixed station or for changes in the antenna facilities of an existing station.

§ 74.938 Transmission standards.

(a) Except as otherwise provided in this section, the transmission standards employed by television broadcast stations and set forth in § 73.682 of this chapter shall apply to instructional television fixed stations.

(b) Instructional television fixed stations are not required to attenuate the lower sideband by any specified amount unless interference to the reception of another station results from emissions in excess of those permitted television broadcast stations, in which case the attenuation specified in § 73.687(a)(3) of this chapter shall apply. However, in no case shall the amplitude of any lower sideband component exceed the amplitude of the upper sideband component having the highest amplitude.

(c) The visual transmission amplitude characteristics may vary from those specified in § 73.682 of this chapter to the extent that such variations result from permissible lower sideband radiation. Care should be exercised in the adjustment of the transmitter to insure correct overall response of the transmitter for transmission of the upper and vestigial lower sideband.

(d) The provisions of § 74.937 in lieu of § 73.682(a)(14) of this chapter apply with respect to polarization of the radiated signal.

(e) The provisions of § 74.935(d) in lieu of § 73.682(a)(15) of this chapter apply with respect to the ratio of visual to aural power.

EQUIPMENT

§ 74.950 Equipment performance and installation.

(a) Except as otherwise provided in this section, the requirements of § 73.687 of this chapter regarding the installation and performance of television broadcast transmitters and associated equipment shall apply to instructional television fixed stations.

(b) The overall attenuation characteristics of the transmitter may vary from those specified in § 73.687 of this chapter to the extent that such variations result from permissible lower sideband radiation. However, care should be exercised in the adjustment of the transmitter to insure correct overall response of the transmitter for proper transmission of the upper and vestigial lower sideband.

(c) The provisions of § 74.961 in lieu of § 73.687(c)(1) of this chapter apply with respect to the frequency tolerance for the visual carrier.

(d) The provisions of § 74.936 in lieu of § 73.687(i)(1) of this chapter apply with respect to spurious emissions and radio frequency harmonics.

(e) The requirements of § 73.687(c)(2) of this chapter will be considered to be met insofar as measurements of operating power are concerned, if the transmitter is equipped with instruments for determining the combined visual and aural operating power. However, licensees are expected to maintain the operating powers within the limits specified in the rules of this part. Measurements of the separate visual and aural operating powers should be made at sufficiently frequent intervals to insure compliance with the rules and in no event less often than once a month.

(f) Transmitting apparatus used solely for relaying signals received from other stations and operating in the manner described in § 74.934(a)(2) shall, in lieu of the requirements of § 73.687 of this chapter, comply with the requirements of § 74.750 (c), (e), and (f).

§ 74.951 Equipment changes.

(a) Formal application (FCC Form 330P) is required for any of the following changes:

(1) Replacement of the transmitter as a whole, except replacement with an identical transmitter, or any change in equipment which could result in a change in the electrical characteristics or performance of the station.

(2) Any change in the transmitting antenna system, including the direction of radiation, directive pattern, antenna gain, or transmission line.

(3) Any change in the height of the antenna above ground or any horizontal change in the location of the antenna in excess of 500 feet.

(4) Any change in the transmitter control system.

(5) Any change in the location of the transmitter except a move within the same building or upon the same tower or pole.

(6) Any change of frequency assignment.

(7) Any change of authorized operating power.

(b) Other equipment changes not specifically referred to in paragraph (a) of this section may be made at the discretion of the licensee, provided that the Engineer in Charge of the radio district in which the station is located and the Commission in Washington, D.C., are notified in writing upon the completion of such changes and provided further, that the changes are appropriately reflected in the next application for renewal of license of the station.

§ 74.952 Acceptability of equipment for licensing.

(a) Transmitters employed in this service must have type acceptance by the Commission. Type acceptance may be given under either of the following conditions:

(1) A transmitter or translator may be type accepted upon the request of any manufacturer of such equipment built in quantity by following the type acceptance procedure set forth in Part 2 of this chapter, provided that the date and information submitted indicate that the equipment meets all technical requirements applicable to this service. If accepted, such transmitting equipment will be included on the Commission's "Radio Equipment List, Part C, Equipment Acceptable for Licensing in the Radio Services Other than Broadcast." Applicants specifying equipment included on such a list need not submit detailed descriptions and diagrams where the correct type number is specified, provided that the equipment proposed is identical with that accepted. Copies of the Radio Equipment List, Part C, are available for inspection at the Commission's office in Washington, D.C., and at each of its field offices.

(2) An application specifying a transmitter or translator not included on the Radio Equipment List, Part C, may be accepted upon the request of a prospective licensee submitting, with the application for construction permit, a complete description of the equipment, including the circuit diagram, listing of all tubes used, function of each, multiplication in each stage, plate current and voltage applied to each tube, and a description of the oscillator circuit together with any devices installed for the purpose of frequency stabilization. However, if this data has been filed with the Commission by a manufacturer in connection with a request for type acceptance, it need not be submitted with the application for construction permit but may be referred to as "on file." Measurement data for type acceptance made in accordance with subparagraph (1) of this paragraph shall be submitted with the license application.

(b) Additional rules with respect to withdrawal of type acceptance, modification of type accepted equipment, and limitations on the findings upon which type acceptance is based are set forth in Part 2 of this chapter.

TECHNICAL OPERATION AND OPERATORS

§ 74.961 Frequency tolerance.

(a) The frequency of the visual carrier shall be maintained within 60 kilocycles of the assigned frequency at all times when the station is in operation.

(b) The frequency of the aural carrier shall be maintained in accordance with the provisions of § 73.687(c)(1) of this chapter.

§ 74.962 Frequency monitors and measurements.

(a) Suitable means shall be provided to insure that the operating frequencies of the station are within the prescribed tolerances.

(b) The operating frequencies shall be checked as often as is necessary to insure that they are within the prescribed tolerances at all times and in all cases the operating frequencies shall be

checked at intervals of no more than 1 month.

(c) A determination of the operating frequencies of the visual and aural carriers may be made by measuring any exact submultiple of the actual output frequency. Any crude but suitable device, including a roughly calibrated receiver, may be used to determine that the output frequency is the correct multiple of the frequency controlling element in the transmitter.

§ 74.963 Time of operation.

(a) An instructional television fixed station is not required to adhere to any regular schedule of operation. Unless otherwise specified in the license, the hours of operation are not limited.

(b) Except for purposes of tests and adjustments, the transmitter shall not be permitted to radiate unmodulated carriers or otherwise make unnecessary transmissions for extended periods of time.

§ 74.964 Station inspection.

The station and all records required to be kept by the licensee shall be made available for inspection upon request by any authorized representative of the Commission.

§ 74.965 Posting of station and operator licenses.

(a) The station license and any other instrument of authorization or individual order concerning the construction of the equipment or manner of operation shall be posted at the place where the transmitter is located, so that all terms thereof are visible, except as otherwise provided in paragraphs (b) and (c) of this section.

(b) In cases where the transmitter is operated by remote control, the documents referred to in paragraph (a) of this section shall be posted in the manner described at the control point of the transmitter, and

(c) In cases where the transmitter is operated unattended, the name of the licensee and the call sign of the unattended station shall be displayed at the transmitter site on the structure supporting the transmitting antenna, so as to be visible to a person standing on the ground at the transmitter site. The display shall be prepared so as to withstand normal weathering for a reasonable period of time and shall be maintained in a legible condition at all times by the licensee. The station license and other documents referred to in paragraph (a) of this section shall be kept at the nearest attended station operated by the licensee of the unattended station or in cases where the licensee of the unattended station does not operate attended stations, at the point of destination of the signals relayed by the unattended station.

(d) The original of each station operator license shall be posted at the place where he is on duty: *Provided, however,* That if the original license of a station operator is posted at another radio transmitting station in accordance with the rules governing the class of station and is there available for inspection by a representative of the Commission, a verification card (FCC Form 758–F) is acceptable in lieu of the posting of such license: *Provided further, however,* That if the operator on duty holds an operator permit of the card form (as distinguished from the diploma form), he shall not post that permit but shall keep it in his personal possession.

§ 74.966 Operator requirements.

(a) An instructional television fixed station, used for the origination of visual and aural program material or the transmitter of which is modulated with visual and aural program material received from other sources, shall not be operated unless there is one (or more) operators holding a valid radiotelephone first-class or second-class operator license or radiotelephone third-class operator permit, on duty at the place where the transmitter is located or at an authorized control point established pursuant to the provisions of § 74.933, and in actual charge thereof.

(b) Except when under the immediate supervision of a radiotelephone first-class or second-class operator, the radiotelephone third-class operator permit holder may perform only the following functions:

(1) Those necessary to turn the transmitter on and off.

(2) Such adjustments as may be made by means of external controls and which are necessary to maintain modulation of the transmitter within the prescribed limits.

(3) Such adjustments as may be made by means of external controls and which are necessary to compensate for fluctuations of the power supply voltage which would otherwise result in changes in the authorized operating power.

(4) Make routine meter readings and inspection of antenna hazard marking for logging purposes.

(c) In cases where a transmitter is operated unattended pursuant to the provisions of § 74.934, an operator of the grade specified in paragraph (a) of this section shall observe the transmissions at the receiving point for the station or some other suitable place where the transmissions of the unattended station can be observed, at intervals of no more than 1 hour whenever the station is in operation. Should any condition of improper operation be observed, immediate measures shall be instituted to correct the condition of improper operation.

(d) Any tests, adjustments, or repairs made while the transmitter is in operation and which require technical skill and knowledge to avoid improper operation, shall be made by or under the immediate supervision of an operator holding a valid radiotelephone first-class or second-class operator license.

(e) The licensed operator on duty and in charge of an instructional television fixed station may, at the discretion of the licensee, be employed for other duties or for the operation of another station or stations in accordance with the class of operator license or permit which he holds and the rules and regulations governing such stations. However, such duties shall in no way impair or impede the required supervision of the instructional television fixed station.

(Sec. 318, 48 Stat. 1089, as amended; 47 U.S.C. 318)

§ 74.967 Marking and lighting of antenna structures.

The marking and lighting of antenna structures authorized by the Commission, where required, will be specified in the authorization issued by the Commission. Part 17 of this chapter sets forth the circumstances under which such marking and lighting will be required and the responsibility of the licensee with regard thereto.

§ 74.968 Additional orders.

In case the rules of this part do not cover all phases of operation with respect to external effects, the Commission may make supplemental or additional orders in each case as may be deemed necessary.

§ 74.969 Copies of the rules.

The licensee of an instructional television fixed station shall have current copies of Parts 73 and 74, and in cases where aeronautical hazard marking of antennas is required, Part 17 of this chapter available for use by the operator in charge. Both the licensee and the operator or operators responsible for the proper operation of the station are expected to be familiar with the pertinent rules governing instructional television fixed stations.

§ 74.970 Modulation limits.

(a) *Visual transmitter.* The maximum excursion of the luminance signal in the white direction shall not exceed the value specified in § 73.682(a)(13) of this chapter for the reference white level.

(b) *Aural transmitter.* The maximum frequency swing of the aural carrier shall not be permitted to exceed ±25 kc/s on peaks of frequent occurrence during any transmission. This is defined as 100 percent modulation.

§ 74.971 Modulation monitors and measurements.

Suitable means shall be provided to insure that the modulation limits specified in § 74.970 are observed.

OTHER OPERATING REQUIREMENTS

§ 74.981 Logs.

(a) The licensee of an instructional television fixed station shall maintain an operating log showing the following:

(1) The date and time of the beginning of each period of operation of the transmitter.

(2) The date and time of any unscheduled interruptions to the transmissions of the station, the duration of such interruptions, and the causes thereof.

(3) The date and time of the end of each period of operation of the transmitter.

(4) A record of all repairs, adjustments, maintenance, tests, and equipment changes, showing the date and time of such events, the name and qualifications of the person or persons performing such tasks, and a brief description of the matter logged.

(5) Where an antenna structure is required to have aeronautical hazard

markings, the information required by § 17.38 of this chapter.

(b) The log entries shall be made by the person or persons competent to do so, having actual knowledge of the facts required, who shall sign the log when starting duty and again when going off duty.

(c) The log shall be kept in an orderly and legible manner, in suitable form, and in such detail that the data required are readily available. Key letters or abbreviations may be used if proper meaning or explanation is contained elsewhere in the log.

(d) No log or portion thereof shall be erased, obliterated, or willfully destroyed within the period of retention required by rule. Any necessary correction may be made only by the person who made the original entry who shall strike out the erroneous portion, initial the correction made, and show the date the correction was made.

(e) Operating logs shall be retained for a period of not less than 2 years. The Commission reserves the right to order, in individual cases, retention of logs for a longer period of time. In cases where the licensee has notice of any claim or complaint to which information contained in the log may be pertinent, the log shall be retained until such claim or complaint has been fully satisfied or until the same has been barred by statute limiting the time for the filing of suits upon such claims.

§ 74.982 Station identification.

(a) Call signs for instructional television fixed stations will consist of three letters and two digits pursuant to the provisions of § 2.302 of this chapter relating to fixed stations.

(b) Except as otherwise provided in paragraphs (c) and (d) of this section, each instructional television fixed station shall transmit its call sign at the beginning and end of each period of operation and, during operation, on the hour. Visual or aural transmissions shall be employed.

(c) The hourly station identification announcement during operation may be deferred if it would interrupt a single consecutive demonstration, lecture, or other similar discourse or otherwise impair the continuity of a program in progress. In such cases the station identification announcement shall be made at the first normal break in the continuity of the program.

(d) In cases where an instructional television fixed station is operating as a relay for signals originating at some other station operated by the same licensee, its call sign shall be announced by the originating station at the times and in the manner prescribed in paragraph (b) of this section.

(e) In cases where an instructional television fixed station is operating as a relay for signals originating at a station operated by some other licensee, its call sign may be transmitted by the originating station if suitable arrangements can be made with the other licensee or in lieu thereof, means shall be provided for the transmission of the call sign by the relay transmitter itself. If the transmitter is operating unattended or if it is not equipped for direct modulation by a locally generated signal, the transmission of the call sign may be made automatically in the manner prescribed in § 74.783(a).

§ 74.984 Retransmissions.

An instructional television fixed station may not retransmit the signals of any class of station without consent of the station originating the signals to be retransmitted.

(Sec. 325, 48 Stat. 1091; 47 U.S.C. 325)

[F.R. Doc. 63-12998; Filed, Dec. 13, 1963; 8:45 a.m.]