

ENVIRONMENTAL PROTECTION AGENCY

40 CFR Parts 141 and 142

[FRL-7530-5]

RIN 2040-AD37

National Primary Drinking Water Regulations: Long Term 2 Enhanced Surface Water Treatment Rule

AGENCY: Environmental Protection Agency.

ACTION: Proposed rule.

SUMMARY: In this document, the Environmental Protection Agency (EPA) is proposing National Primary Drinking Water Regulations that require the use of treatment techniques, along with monitoring, reporting, and public notification requirements, for all public water systems (PWSs) that use surface water sources. The purposes of the Long Term 2 Enhanced Surface Water Treatment Rule (LT2ESWTR) are to improve control of microbial pathogens, including specifically the protozoan *Cryptosporidium*, in drinking water and to address risk-risk trade-offs with the control of disinfection byproducts. Key provisions in today's proposed LT2ESWTR include the following: source water monitoring for *Cryptosporidium*, with reduced monitoring requirements for small systems; additional *Cryptosporidium* treatment for filtered systems based on source water *Cryptosporidium* concentrations; inactivation of *Cryptosporidium* by all unfiltered systems; disinfection profiling and benchmarking to ensure continued levels of microbial protection while PWSs take the necessary steps to comply with new disinfection byproduct standards; covering, treating, or implementing a risk management plan for uncovered finished water storage facilities; and criteria for a number of treatment and management options (*i.e.*, the microbial toolbox) that PWSs may implement to meet additional *Cryptosporidium* treatment requirements. The LT2ESWTR will build upon the treatment technique requirements of the Interim Enhanced Surface Water Treatment Rule and the Long Term 1 Enhanced Surface Water Treatment Rule.

EPA believes that implementation of the LT2ESWTR will significantly reduce levels of *Cryptosporidium* in finished drinking water. This will substantially lower rates of endemic cryptosporidiosis, the illness caused by *Cryptosporidium*, which can be severe and sometimes fatal in sensitive

subpopulations (*e.g.*, AIDS patients, the elderly). In addition, the treatment technique requirements of this proposal are expected to increase the level of protection from exposure to other microbial pathogens (*e.g.*, *Giardia lamblia*).

DATES: EPA must receive public comment on the proposal by November 10, 2003.

ADDRESSES: Comments may be submitted by mail to: Water Docket, Environmental Protection Agency, Mail Code 4101T, 1200 Pennsylvania Ave., NW., Washington, DC 20460, Attention Docket ID No. OW-2002-0039.

Comments may also be submitted electronically or through hand delivery/courier by following the detailed instructions as provided in section I.C. of the **SUPPLEMENTARY INFORMATION** section.

FOR FURTHER INFORMATION CONTACT: For technical inquiries, contact Daniel Schmelling, Office of Ground Water and Drinking Water (MC 4607M), U.S. Environmental Protection Agency, 1200 Pennsylvania Ave., NW., Washington, DC 20460; telephone (202) 564-5281. For regulatory inquiries, contact Jennifer McLain at the same address; telephone (202) 564-5248. For general information contact the Safe Drinking Water Hotline, Telephone (800) 426-4791. The Safe Drinking Water Hotline is open Monday through Friday, excluding legal holidays, from 9 a.m. to 5:30 p.m. Eastern Time.

SUPPLEMENTARY INFORMATION:

I. General Information

A. Who Is Regulated by This Action?

Entities potentially regulated by the LT2ESWTR are public water systems (PWSs) that use surface water or ground water under the direct influence of surface water (GWUDI). Regulated categories and entities are identified in the following chart.

Category	Examples of regulated entities
Industry	Public Water Systems that use surface water or ground water under the direct influence of surface water.
State, Local, Tribal or Federal Governments.	Public Water Systems that use surface water or ground water under the direct influence of surface water.

This table is not intended to be exhaustive, but rather provides a guide for readers regarding entities likely to be regulated by this action. This table lists the types of entities that EPA is now

aware could potentially be regulated by this action. Other types of entities not listed in this table could also be regulated. To determine whether your facility is regulated by this action, you should carefully examine the definition of public water system in § 141.3 of Title 40 of the Code of Federal Regulations and applicability criteria in §§ 141.76 and 141.501 of today's proposal. If you have questions regarding the applicability of the LT2ESWTR to a particular entity, consult one of the persons listed in the preceding section entitled **FOR FURTHER INFORMATION CONTACT**

B. How Can I Get Copies of This Document and Other Related Information?

1. *Docket.* EPA has established an official public docket for this action under Docket ID No. OW-2002-0039. The official public docket consists of the documents specifically referenced in this action, any public comments received, and other information related to this action. Although a part of the official docket, the public docket does not include Confidential Business Information (CBI) or other information whose disclosure is restricted by statute. The official public docket is the collection of materials that is available for public viewing at the Water Docket in the EPA Docket Center, (EPA/DC) EPA West, Room B102, 1301 Constitution Ave., NW., Washington, DC. The EPA Docket Center Public Reading Room is open from 8:30 a.m. to 4:30 p.m., Monday through Friday, excluding legal holidays. The telephone number for the Public Reading Room is (202) 566-1744, and the telephone number for the Water Docket is (202) 566-2426. For access to docket material, please call (202) 566-2426 to schedule an appointment.

2. *Electronic Access.* You may access this **Federal Register** document electronically through the EPA Internet under the "**Federal Register**" listings at <http://www.epa.gov/fedrgstr/>.

An electronic version of the public docket is available through EPA's electronic public docket and comment system, EPA Dockets. You may use EPA Dockets at <http://www.epa.gov/edocket/> to submit or view public comments, access the index listing of the contents of the official public docket, and to access those documents in the public docket that are available electronically. Once in the system, select "search," then key in the appropriate docket identification number.

Certain types of information will not be placed in the EPA Dockets. Information claimed as CBI and other

information whose disclosure is restricted by statute, which is not included in the official public docket, will not be available for public viewing in EPA's electronic public docket. EPA's policy is that copyrighted material will not be placed in EPA's electronic public docket but will be available only in printed, paper form in the official public docket. Although not all docket materials may be available electronically, you may still access any of the publicly available docket materials through the docket facility identified in section I.B.1.

For public commenters, it is important to note that EPA's policy is that public comments, whether submitted electronically or in paper, will be made available for public viewing in EPA's electronic public docket as EPA receives them and without change, unless the comment contains copyrighted material, CBI, or other information whose disclosure is restricted by statute. When EPA identifies a comment containing copyrighted material, EPA will provide a reference to that material in the version of the comment that is placed in EPA's electronic public docket. The entire printed comment, including the copyrighted material, will be available in the public docket.

Public comments submitted on computer disks that are mailed or delivered to the docket will be transferred to EPA's electronic public docket. Public comments that are mailed or delivered to the Docket will be scanned and placed in EPA's electronic public docket. Where practical, physical objects will be photographed, and the photograph will be placed in EPA's electronic public docket along with a brief description written by the docket staff.

C. How and to Whom Do I Submit Comments?

You may submit comments electronically, by mail, or through hand delivery/courier. To ensure proper receipt by EPA, identify the appropriate docket identification number in the subject line on the first page of your comment. Please ensure that your comments are submitted within the specified comment period. Comments received after the close of the comment period will be marked "late." EPA is not required to consider these late comments.

1. *Electronically.* If you submit an electronic comment as prescribed below, EPA recommends that you include your name, mailing address, and an e-mail address or other contact information in the body of your

comment. Also include this contact information on the outside of any disk or CD ROM you submit, and in any cover letter accompanying the disk or CD ROM. This ensures that you can be identified as the submitter of the comment and allows EPA to contact you in case EPA cannot read your comment due to technical difficulties or needs further information on the substance of your comment. EPA's policy is that EPA will not edit your comment, and any identifying or contact information provided in the body of a comment will be included as part of the comment that is placed in the official public docket, and made available in EPA's electronic public docket. If EPA cannot read your comment due to technical difficulties and cannot contact you for clarification, EPA may not be able to consider your comment.

a. *EPA Dockets.* Your use of EPA's electronic public docket to submit comments to EPA electronically is EPA's preferred method for receiving comments. Go directly to EPA Dockets at <http://www.epa.gov/edocket>, and follow the online instructions for submitting comments. Once in the system, select "search," and then key in Docket ID No. OW-2002-0039. The system is an "anonymous access" system, which means EPA will not know your identity, e-mail address, or other contact information unless you provide it in the body of your comment.

b. *E-mail.* Comments may be sent by electronic mail (e-mail) to OW-Docket@epa.gov, Attention Docket ID No. OW-2002-0039. In contrast to EPA's electronic public docket, EPA's e-mail system is not an "anonymous access" system. If you send an e-mail comment directly to the Docket without going through EPA's electronic public docket, EPA's e-mail system automatically captures your e-mail address. E-mail addresses that are automatically captured by EPA's e-mail system are included as part of the comment that is placed in the official public docket, and made available in EPA's electronic public docket.

c. *Disk or CD ROM.* You may submit comments on a disk or CD ROM that you mail to the mailing address identified in section I.C.2. These electronic submissions will be accepted in WordPerfect or ASCII file format. Avoid the use of special characters and any form of encryption.

2. *By Mail.* Send three copies of your comments and any enclosures to: Water Docket, Environmental Protection Agency, Mail Code 4101T, 1200 Pennsylvania Ave., NW., Washington, DC, 20460, Attention Docket ID No. OW-2002-0039.

3. *By Hand Delivery or Courier.* Deliver your comments to: Water Docket, EPA Docket Center, Environmental Protection Agency, Room B102, 1301 Constitution Ave., NW, Washington, DC, Attention Docket ID No. OW-2002-0039. Such deliveries are only accepted during the Docket's normal hours of operation as identified in section I.B.1.

D. What Should I Consider as I Prepare My Comments for EPA?

You may find the following suggestions helpful for preparing your comments:

1. Explain your views as clearly as possible.
2. Describe any assumptions that you used.
3. Provide any technical information and/or data you used that support your views.
4. If you estimate potential burden or costs, explain how you arrived at your estimate.
5. Provide specific examples to illustrate your concerns.
6. Offer alternatives.
7. Make sure to submit your comments by the comment period deadline identified.
8. To ensure proper receipt by EPA, identify the appropriate docket identification number in the subject line on the first page of your response. It would also be helpful if you provided the name, date, and **Federal Register** citation related to your comments.

Abbreviations Used in This Document

AIPC	All Indian Pueblo Council
ASDWA	Association of State Drinking Water Administrators
ASTM	American Society for Testing and Materials
AWWA	American Water Works Association
AWWARF	American Water Works Association Research Foundation
°C	Degrees Centigrade
CCP	Composite Correction Program
CDC	Centers for Disease Control and Prevention
CFE	Combined Filter Effluent
CFR	Code of Federal Regulations
COI	Cost-of-Illness
CT	The Residual Concentration of Disinfectant (mg/L) Multiplied by the Contact Time (in minutes)
CWS	Community Water Systems
DAPI	4',6-Diamindino-2-phenylindole
DBPs	Disinfection Byproducts
DBPR	Disinfectants/Disinfection Byproducts Rule
DE	Diatomaceous Earth
DIC	Differential Interference Contrast (microscopy)
EA	Economic Analysis

EPA United States Environmental Protection Agency
 GAC Granular Activated Carbon
 GWUDI Ground Water Under the Direct Influence of Surface Water
 HAA5 Haloacetic acids (Monochloroacetic, Dichloroacetic, Trichloroacetic, Monobromoacetic and Dibromoacetic Acids)
 HPC Heterotrophic Plate Count
 ICR Information Collection Request
 ICRSS Information Collection Rule Supplemental Surveys
 ICRSSM Information Collection Rule Supplemental Survey of Medium Systems
 ICRSSL Information Collection Rule Supplemental Survey of Large Systems
 IESWTR Interim Enhanced Surface Water Treatment Rule
 IFA Immunofluorescence Assay
 Log Logarithm (common, base 10)
 LRAA Locational Running Annual Average
 LRV Log Removal Value
 LT1ESWTR Long Term 1 Enhanced Surface Water Treatment Rule
 LT2ESWTR Long Term 2 Enhanced Surface Water Treatment Rule
 MCL Maximum Contaminant Level
 MCLG Maximum Contaminant Level Goal
 MGD Million Gallons per Day
 M-DBP Microbial and Disinfectants/Disinfection Byproducts
 MF Microfiltration
 NCWS Non-community water systems
 NF Nanofiltration
 NODA Notice of Data Availability
 NPDWR National Primary Drinking Water Regulation
 NTNCWS Non-transient Non-community Water System
 NTTAA National Technology Transfer and Advancement Act
 NTU Nephelometric Turbidity Unit
 OMB Office of Management and Budget
 PE Performance Evaluation
 PWS Public Water System
 QC Quality Control
 QCRV Quality Control Release Value
 RAA Running Annual Average
 RFA Regulatory Flexibility Act
 RO Reverse Osmosis
 RSD Relative Standard Deviation
 SAB Science Advisory Board
 SBAR Small Business Advocacy Review
 SERs Small Entity Representatives
 SDWA Safe Drinking Water Act
 SWTR Surface Water Treatment Rule
 TCR Total Coliform Rule
 TTHM Total Trihalomethanes
 TNCWS Transient Non-community Water Systems
 UF Ultrafiltration
 UMRA Unfunded Mandates Reform Act

Table of Contents

I. Summary	D. Treatment
A. Why Is EPA Proposing the LT2ESWTR?	1. Overview
B. What Does the LT2ESWTR Proposal Require?	2. Treatment Information Considered for the IESWTR and LT1ESWTR
1. Treatment Requirements for <i>Cryptosporidium</i>	a. Physical Removal
2. Disinfection Profiling and Benchmarking	b. Inactivation
3. Uncovered Finished Water Storage Facilities	3. New Information on Treatment for Control of <i>Cryptosporidium</i>
C. Will This Proposed Regulation Apply to My Water System?	a. Conventional Filtration Treatment and Direct Filtration
II. Background	i. Dissolved Air Flotation.
A. What Is the Statutory Authority for the LT2ESWTR?	b. Slow Sand Filtration
B. What Current Regulations Address Microbial Pathogens in Drinking Water?	c. Diatomaceous Earth Filtration
1. Surface Water Treatment Rule	d. Other Filtration Technologies
2. Total Coliform Rule	e. Inactivation
3. Interim Enhanced Surface Water Treatment Rule	i. Ozone and Chlorine Dioxide
4. Long Term 1 Enhanced Surface Water Treatment Rule	ii. Ultraviolet Light
5. Filter Backwash Recycle Rule	iii. Significance of New Information on Inactivation
C. What Public Health Concerns Does This Proposal Address?	IV. Discussion of Proposed LT2ESWTR Requirements
1. Introduction	A. Additional <i>Cryptosporidium</i> Treatment Technique Requirements for Filtered Systems
2. <i>Cryptosporidium</i> Health Effects and Outbreaks	1. What Is EPA Proposing Today?
a. Health Effects	a. Overview of Framework Approach
b. Waterborne <i>Cryptosporidiosis</i> Outbreaks.	b. Monitoring Requirements
3. Remaining Public Health Concerns Following the IESWTR and LT1ESWTR	c. Treatment Requirements
a. Adequacy of Physical Removal To Control <i>Cryptosporidium</i> and the Need for Risk Based Treatment Requirements.	i. Bin Classification
b. Control of <i>Cryptosporidium</i> in Unfiltered Systems	ii. Credit for Treatment in Place
c. Uncovered Finished Water Storage Facilities	iii. Treatment Requirements Associated With LT2ESWTR Bins
D. Federal Advisory Committee Process	d. Use of Previously Collected Data
III. New Information on <i>Cryptosporidium</i> Health Risks and Treatment	2. How Was This Proposal Developed?
A. Overview of Critical Factors for Evaluating Regulation of Microbial Pathogens	a. Basis for Targeted Treatment Requirements
B. <i>Cryptosporidium</i> Infectivity	b. Basis for Bin Concentration Ranges and Treatment Requirements
1. <i>Cryptosporidium</i> Infectivity Data Evaluated for IESWTR	i. What Is the Risk Associated With a Given Level of <i>Cryptosporidium</i> in a Drinking Water Source?
2. New Data on <i>Cryptosporidium</i> Infectivity	ii. What Degree of Additional Treatment Should Be Required for a Given Source Water <i>Cryptosporidium</i> Level?
3. Significance of New Infectivity Data	c. Basis for Source Water Monitoring Requirements
C. <i>Cryptosporidium</i> Occurrence	i. Systems Serving at Least 10,000 People
1. Occurrence Data Evaluated for IESWTR	ii. Systems Serving Fewer Than 10,000 People
a. Filtered Systems.	iii. Future Monitoring and Reassessment
b. Unfiltered Systems	d. Basis for Accepting Previously Collected Data
2. Overview of the Information Collection Rule and Information Collection Rule Supplemental Surveys (ICRSS)	3. Request for Comment
a. Scope of the Information Collection Rule	B. Unfiltered System Treatment Technique Requirements for <i>Cryptosporidium</i>
b. Scope of the ICRSS	1. What Is EPA Proposing Today?
3. Analytical Methods for Protozoa in the Information Collection Rule and ICRSS	a. Overview
a. Information Collection Rule Protozoan Method	b. Monitoring Requirements
b. Method 1622 and Method 1623	c. Treatment Requirements
4. <i>Cryptosporidium</i> Occurrence Results from the Information Collection Rule and ICRSS	2. How Was This Proposal Developed?
a. Information Collection Rule Results	a. Basis for <i>Cryptosporidium</i> Treatment Requirements
b. ICRSS Results	b. Basis for Requiring the Use of Two Disinfectants
5. Significance of New <i>Cryptosporidium</i> Occurrence Data	c. Basis for Source Water Monitoring Requirements
6. Request for Comment on Information Collection Rule and ICRSS Data Sets	3. Request for Comment
	C. Options for Systems to Meet <i>Cryptosporidium</i> Treatment Requirements
	1. Microbial Toolbox Overview
	2. Watershed Control Program
	a. What Is EPA Proposing Today?
	b. How Was This Proposal Developed?
	c. Request for Comment
	3. Alternative Source

- a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 4. Off-stream Raw Water Storage
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 5. Pre-sedimentation With Coagulant
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - i. Published Studies of *Cryptosporidium* Removal by Conventional Sedimentation Basins
 - ii. Data Supplied by Utilities on the Removal of Spores by Presedimentation
 - c. Request for Comment
 - 6. Bank Filtration
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 7. Lime Softening
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 8. Combined Filter Performance
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 9. Roughing Filter
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 10. Slow Sand Filtration
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 11. Membrane Filtration
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 12. Bag and Cartridge Filtration
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 13. Secondary Filtration
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 14. Ozone and Chlorine Dioxide
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comments
 - 15. Ultraviolet Light
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 16. Individual Filter Performance
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 17. Other Demonstration of Performance
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - D. Disinfection Benchmarks for *Giardia lamblia* and Viruses
 - 1. What Is EPA Proposing Today?
 - a. Applicability and Schedule
 - b. Developing the Disinfection Profile and Benchmark
 - c. State Review
 - 2. How Was This Proposal Developed?
 - 3. Request for Comments
 - E. Additional Treatment Technique Requirements for Systems with Uncovered Finished Water Storage Facilities
 - 1. What Is EPA Proposing Today?
 - 2. How Was This Proposal Developed?
 - 3. Request for Comments
 - F. Compliance Schedules
 - 1. What Is EPA Proposing Today?
 - a. Source Water Monitoring
 - i. Filtered Systems
 - ii. Unfiltered Systems
 - b. Treatment Requirements
 - c. Disinfection Benchmarks for *Giardia lamblia* and Viruses
 - 2. How Was This Proposal Developed?
 - 3. Request for Comments
 - G. Public Notice Requirements
 - 1. What Is EPA Proposing Today?
 - 2. How Was This Proposal Developed?
 - 3. Request for Comment
 - H. Variances and Exemptions
 - 1. Variances
 - 2. Exemptions
 - 3. Request for Comment
 - a. Variances
 - b. Exemptions
 - I. Requirements for Systems To Use Qualified Operators
 - J. System Reporting and Recordkeeping Requirements
 - 1. Overview
 - 2. Reporting Requirements for Source Water Monitoring
 - a. Data Elements To Be Reported
 - b. Data System
 - c. Previously Collected Monitoring Data
 - 3. Compliance With Additional Treatment Requirements
 - 4. Request for Comment
 - K. Analytical Methods
 - 1. *Cryptosporidium*
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 2. *E. coli*
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - 3. Turbidity
 - a. What Is EPA Proposing Today?
 - b. How Was This Proposal Developed?
 - c. Request for Comment
 - L. Laboratory Approval
 - 1. *Cryptosporidium* Laboratory Approval
 - 2. *E. coli* Laboratory Approval
 - 3. Turbidity Analyst Approval
 - 4. Request for Comment
 - M. Requirements for Sanitary Surveys Conducted by EPA
 - 1. Overview
 - 2. Background
 - 3. Request for Comment
 - V. State Implementation
 - A. Special State Primacy Requirements
 - B. State Recordkeeping Requirements
 - C. State Reporting Requirements
 - D. Interim Primacy
 - VI. Economic Analysis
 - A. What Regulatory Alternatives Did the Agency Consider?
 - B. What Analyses Support Selecting the Proposed Rule Option?
 - C. What Are the Benefits of the Proposed LT2ESWTR?
 - 1. Non-quantifiable Health and Non-health Related Benefits
 - 2. Quantifiable Health Benefits
 - a. Filtered Systems
 - b. Unfiltered Systems
 - 3. Timing of Benefits Accrual (latency)
 - D. What Are the Costs of the Proposed LT2ESWTR?
 - 1. Total Annualized Present Value Costs
 - 2. Water System Costs
 - a. Source Water Monitoring Costs
 - b. Filtered Systems Treatment Costs
 - c. Unfiltered Systems Treatment Costs
 - d. Uncovered Finished Water Storage Facilities
 - e. Future Monitoring Costs
 - f. Sensitivity Analysis—influent Bromide Levels on Technology Selection for Filtered Plants
 - 3. State/Primacy Agency Costs
 - 4. Non-quantified Costs
 - E. What Are the Household Costs of the Proposed Rule?
 - F. What Are the Incremental Costs and Benefits of the Proposed LT2ESWTR?
 - G. Are There Benefits From the Reduction of Co-occurring Contaminants?
 - H. Are There Increased Risks From Other Contaminants?
 - I. What Are the Effects of the Contaminant on the General Population and Groups Within the General Populations That Are Identified as Likely to be at Greater Risk of Adverse Health Effects?
 - J. What Are the Uncertainties in the Baseline, Risk, Benefit, and Cost Estimates for the Proposed LT2ESWTR as well as the Quality and Extent of the Information?
 - K. What Is the Benefit/Cost Determination for the Proposed LT2ESWTR?
 - L. Request for Comment
- VII. Statutory and Executive Order Reviews
 - A. Executive Order 12866: Regulatory Planning and Review
 - B. Paperwork Reduction Act
 - C. Regulatory Flexibility Act
 - D. Unfunded Mandates Reform Act
 - 1. Summary of UMRA Requirements
 - 2. Written Statement for Rules With Federal mandates of \$100 million or more
 - a. Authorizing Legislation
 - b. Cost-benefit Analysis
 - c. Estimates of Future Compliance Costs and Disproportionate Budgetary Effects
 - d. Macro-economic Effects
 - e. Summary of EPA Consultation With State, local, and Tribal Governments and Their Concerns
 - f. Regulatory Alternatives Considered
 - g. Selection of the Least Costly, Most Cost-effective, or Least Burdensome Alternative That Achieves the Objectives of the Rule
 - 3. Impacts on Small Governments
 - E. Executive Order 13132: Federalism
 - F. Executive Order 13175: Consultation and Coordination With Indian Tribal Governments
 - G. Executive Order 13045: Protection of Children from Environmental Health and Safety Risks
 - H. Executive Order 13211: Actions that Significantly Affect Energy Supply, Distribution, or Use
 - I. National Technology Transfer and Advancement Act
 - J. Executive Order 12898: Federal Actions to Address Environmental Justice in Minority Populations or Low-Income Populations

K. Consultations With the Science Advisory Board, National Drinking Water Advisory Council, and the Secretary of Health and Human Services
L. Plain Language
VIII. References

I. Summary

A. Why Is EPA Proposing the LT2ESWTR?

EPA is proposing the Long Term 2 Enhanced Surface Water Treatment Rule (LT2ESWTR) to provide for increased protection against microbial pathogens in public water systems that use surface water sources. The proposed LT2ESWTR focuses on *Cryptosporidium*, which is a protozoan pathogen that is widespread in surface water. EPA is particularly concerned about *Cryptosporidium* because it is highly resistant to inactivation by standard disinfection practices like chlorination. Ingestion of *Cryptosporidium* oocysts can cause acute gastrointestinal illness, and health effects in sensitive subpopulations may be severe, including risk of mortality. *Cryptosporidium* has been identified as the pathogenic agent in a number of waterborne disease outbreaks across the U.S. and in Canada (details in section II).

The intent of the LT2ESWTR is to supplement existing microbial treatment requirements for systems where additional public health protection is needed. Currently, the Interim Enhanced Surface Water Treatment Rule (IESWTR) requires large systems that filter to remove at least 99% (2 log) of *Cryptosporidium* (63 FR 69478, December 16, 1998) (USEPA 1998a). The Long Term 1 Enhanced Surface Water Treatment Rule (LT1ESWTR) extends this requirement to small systems (67 FR 1812, January 14, 2002) (USEPA 2002a). Subsequent to promulgating these regulations, EPA has evaluated significant new data on *Cryptosporidium* infectivity, occurrence, and treatment (details in section III). These data indicate that current treatment requirements achieve adequate protection for the majority of systems, but there is a subset of systems with higher vulnerability to *Cryptosporidium* where additional treatment is necessary.

Specifically, national survey data show that average *Cryptosporidium* occurrence in filtered systems is lower than previously estimated. However, these data also demonstrate that *Cryptosporidium* concentrations vary widely among systems, and that a fraction of filtered systems have relatively high levels of source water

Cryptosporidium contamination. Based on this finding, along with new data suggesting that the infectivity (*i.e.*, virulence) of *Cryptosporidium* may be substantially higher than previously understood, EPA has concluded that the current 2 log removal requirement does not provide an adequate degree of treatment in filtered systems with the highest source water *Cryptosporidium* levels. Consequently, EPA is proposing targeted additional treatment requirements under the LT2ESWTR for filtered systems with the highest *Cryptosporidium* risk.

Under current regulations, unfiltered systems are not required to provide any treatment for *Cryptosporidium*. New occurrence data suggest that typical *Cryptosporidium* levels in the treated water of unfiltered systems are substantially higher than in the treated water of filtered systems. Hence, *Cryptosporidium* treatment by unfiltered systems is needed to achieve equivalent public health protection. Recent treatment studies have allowed EPA to develop criteria for systems to inactivate *Cryptosporidium* with ozone, ultraviolet (UV) light, and chlorine dioxide. As a result, EPA has concluded that it is feasible and appropriate to propose under the LT2ESWTR that all unfiltered systems treat for *Cryptosporidium*.

In addition to concern with *Cryptosporidium*, the LT2ESWTR proposal is intended to ensure that systems maintain adequate protection against microbial pathogens as they take steps to reduce formation of disinfection byproducts (DBPs). Along with the LT2ESWTR, EPA is also developing a Stage 2 Disinfection Byproducts Rule (DBPR), which will further limit allowable levels of trihalomethanes and haloacetic acids. The proposed LT2ESWTR contains disinfection profiling and benchmarking requirements to ensure that microbial protection is maintained as systems comply with the Stage 2 DBPR. Also in the proposed LT2ESWTR are requirements to limit risk associated with existing uncovered finished water storage facilities. Uncovered storage facilities are subject to contamination if not properly managed or treated.

Today's proposed LT2ESWTR reflects consensus recommendations from the Stage 2 Microbial and Disinfection Byproducts (M-DBP) Federal Advisory Committee. These recommendations are set forth in the Stage 2 M-DBP Agreement in Principle (65 FR 83015, December 29, 2000) (USEPA 2000a).

B. What Does the LT2ESWTR Proposal Require?

1. Treatment Requirements for *Cryptosporidium*

EPA is proposing risk-targeted treatment technique requirements for *Cryptosporidium* control in filtered systems that are based on a microbial framework approach. Under this approach, systems that use a surface water or ground water under the direct influence of surface water (referred to collectively as surface water systems) will conduct source water monitoring to determine an average *Cryptosporidium* concentration. Based on monitoring results, filtered systems will be classified in one of four possible risk categories (bins). A filtered system's bin classification determines the extent of any additional *Cryptosporidium* treatment requirements beyond the requirements of current regulations.

EPA expects that the majority of filtered systems will be classified in the Bin 1, which carries no additional treatment requirements. Those systems classified Bins 2–4 will be required to provide from 1.0 to 2.5 log of treatment (*i.e.*, 90 to 99.7 percent reduction) for *Cryptosporidium* in addition to conventional treatment that complies with the IESWTR or LT1ESWTR (details in section IV.A). Filtered systems will meet additional *Cryptosporidium* treatment requirements by using one or more treatment or control steps from a "microbial toolbox" of options (details in section IV.C). Rather than monitoring, filtered systems may elect to comply with the treatment requirements of Bin 4 directly.

Under the proposed LT2ESWTR, all surface water systems that are not required to filter (*i.e.*, unfiltered systems) must provide at least 2 log (*i.e.*, 99 percent) inactivation of *Cryptosporidium*. In addition, unfiltered systems will monitor for *Cryptosporidium* in their source water and must achieve at least 3 log (*i.e.*, 99.9 percent) inactivation of *Cryptosporidium* if the mean level exceeds 0.01 oocysts/L. Alternatively, unfiltered systems may elect to provide 3 log *Cryptosporidium* inactivation directly, instead of monitoring. All requirements established under the Surface Water Treatment Rule (SWTR) (54 FR 27486, June 29, 1989) (USEPA 1989a) for unfiltered systems will remain in effect, including 3 log inactivation of *Giardia lamblia* and 4 log inactivation of viruses. However, the LT2ESWTR proposal requires that unfiltered systems achieve their overall inactivation requirements using a

minimum of two disinfectants (details in section IV.B).

2. Disinfection Profiling and Benchmarking

The purpose of disinfection profiling and benchmarking is to ensure that when a system makes a significant change to its disinfection practice, it does not compromise the adequacy of existing microbial protection. EPA established the disinfection benchmark under the IESWTR and LT1ESWTR for the Stage 1 M-DBP rules, and the LT2ESWTR proposal extends disinfection benchmark requirements to apply to the Stage 2 M-DBP rules.

The proposed profiling and benchmarking requirements are similar to those promulgated under IESWTR and LT1ESWTR. Systems that meet specified criteria must prepare disinfection profiles that characterize current levels of virus and *Giardia lamblia* inactivation over the course of one year. Systems with valid operational data from profiling conducted under the IESWTR or LT1ESWTR are not required to collect additional data. If a system that is required to prepare a profile proposes to make a significant change to its disinfection practice, the system must calculate a disinfection benchmark and must consult with the State regarding how the proposed change will affect the current benchmark (details in section IV.D).

3. Uncovered Finished Water Storage Facilities

The proposed LT2ESWTR also includes requirements for systems with uncovered finished water storage facilities. The IESWTR and LT1ESWTR require systems to cover all new storage facilities for finished water, but these rules do not address existing uncovered finished water storage facilities. Under the LT2ESWTR proposal, systems with uncovered finished water storage facilities must cover the storage facility or treat the storage facility discharge to achieve 4 log virus inactivation unless the State determines that existing risk mitigation is adequate. Where the State makes such a determination, systems must develop and implement a risk mitigation plan that addresses physical access, surface water run-off, animal and bird wastes, and on-going water quality assessment (details in section IV.E).

C. Will This Proposed Regulation Apply to My Water System?

All community and non-community water systems that use surface water or ground water under the direct influence

of surface water are affected by the proposed LT2ESWTR.

II. Background

A. What Is the Statutory Authority for the LT2ESWTR?

This section discusses the Safe Drinking Water Act (SDWA or the Act) sections that direct the development of the LT2ESWTR.

The Act, as amended in 1996, requires EPA to publish a maximum contaminant level goal (MCLG) and promulgate a national primary drinking water regulation (NPDWR) with enforceable requirements for any contaminant that the Administrator determines may have an adverse effect on the health of persons, is known to occur or there is a substantial likelihood that the contaminant will occur in public water systems (PWSs) with a frequency and at levels of public health concern, and for which in the sole judgement of the Administrator, regulation of such contaminant presents a meaningful opportunity for health risk reduction for persons served by PWSs (section 1412 (b)(1)(A)).

MCLGs are non-enforceable health goals, and are to be set at a level at which no known or anticipated adverse effect on the health of persons occur and which allows an adequate margin of safety (sections 1412(b)(4) and 1412(a)(3)). EPA established an MCLG of zero for *Cryptosporidium* under the IESWTR (63 FR 69478, December 16, 1998) (USEPA 1998a). The Agency is not proposing any changes to the current MCLG for *Cryptosporidium*.

The Act also requires that at the same time EPA publishes an NPDWR and MCLG, it must specify in the NPDWR a maximum contaminant level (MCL) which is as close to the MCLG as is feasible (sections 1412(b)(4) and 1401(1)(c)). The Agency is authorized to promulgate an NPDWR that requires the use of a treatment technique in lieu of establishing an MCL if the Agency finds that it is not economically or technologically feasible to ascertain the level of the contaminant (sections 1412(b)(7)(A) and 1401(1)(C)). The Act specifies that in such cases, the Agency shall identify those treatment techniques that would prevent known or anticipated adverse effects on the health of persons to the extent feasible (section 1412(b)(7)(A)).

The Agency has concluded that it is not currently economically or technologically feasible for PWSs to determine the level of *Cryptosporidium* in finished drinking water for the purpose of compliance with a finished water standard (the performance of

available analytical methods for *Cryptosporidium* is described in section III.C; the treated water *Cryptosporidium* levels that the LT2ESWTR will achieve are described in section IV.A). Consequently, today's proposal for the LT2ESWTR relies on treatment technique requirements to reduce health risks from *Cryptosporidium* in PWSs.

When proposing an NPDWR that includes an MCL or treatment technique, the Act requires EPA to publish and seek public comment on an analysis of health risk reduction and cost impacts. This includes an analysis of quantifiable and nonquantifiable costs and health risk reduction benefits, incremental costs and benefits of each alternative considered, the effects of the contaminant upon sensitive subpopulations (e.g., infants, children, pregnant women, the elderly, and individuals with a history of serious illness), any increased risk that may occur as the result of compliance, and other relevant factors (section 1412 (b)(3)(C)). EPA's analysis of health benefits and costs associated with the proposed LT2ESWTR is presented in "Economic Analysis of the LT2ESWTR" (USEPA 2003a) and is summarized in section VI of this preamble. However, the Act does not authorize the Administrator to use additional health risk reduction and cost considerations to establish MCL or treatment technique requirements for the control of *Cryptosporidium* (section 1412 (b)(6)(C)).

Finally, section 1412 (b)(2)(C) of SDWA requires EPA to promulgate a Stage 2 Disinfectants and Disinfection Byproducts Rule within 18 months after promulgation of the LT1ESWTR, which occurred on January 14, 2002. Consistent with statutory requirements for risk balancing (section 1412(b)(5)(B)), EPA will finalize the LT2ESWTR with the Stage 2 DBPR to ensure parallel protection from microbial and DBP risks.

B. What Current Regulations Address Microbial Pathogens in Drinking Water?

This section summarizes the existing regulations that apply to control of pathogenic microorganisms in surface water systems. These rules form the baseline of regulatory protection that will be supplemented by the LT2ESWTR.

1. Surface Water Treatment Rule

The SWTR (54 FR 27486, June 29, 1989) (USEPA 1989a) applies to all PWSs using surface water or ground water under the direct influence (GWUDI) of surface water as sources (Subpart H systems). It established

MCLGs of zero for *Giardia lamblia*, viruses, and Legionella, and includes treatment technique requirements to reduce exposure to pathogenic microorganisms, including: (1)

Filtration, unless specified avoidance criteria are met; (2) maintenance of a disinfectant residual in the distribution system; (3) removal and/or inactivation of 3 log (99.9%) of *Giardia lamblia* and 4 log (99.99%) of viruses; (4) combined filter effluent turbidity of 5 nephelometric turbidity units (NTU) as a maximum and 0.5 NTU at 95th percentile monthly for treatment plants using conventional treatment or direct filtration (with separate standards for other filtration technologies); and (5) watershed protection and source water quality requirements for unfiltered systems.

2. Total Coliform Rule

The Total Coliform Rule (TCR) (54 FR 27544, June 29, 1989) (USEPA 1989b) applies to all PWSs. It established an MCLG of zero for total and fecal coliform bacteria, and an MCL based on the percentage of positive samples collected during a compliance period. Coliforms are used as a screen for fecal contamination and to determine the integrity of the water treatment process and distribution system. Under the TCR, no more than 5 percent of distribution system samples collected in any month may contain coliform bacteria (no more than 1 sample per month may be coliform positive in those systems that collect fewer than 40 samples per month). The number of samples to be collected in a month is based on the number of people served by the system.

3. Interim Enhanced Surface Water Treatment Rule

The IESWTR (63 FR 69477, December 16, 1998) (USEPA 1998a) applies to PWSs serving at least 10,000 people and using surface water or GWUDI sources. Key provisions established by the IESWTR include the following: (1) An MCLG of zero for *Cryptosporidium*; (2) *Cryptosporidium* removal requirements of 2 log (99 percent) for systems that filter; (3) strengthened combined filter effluent turbidity performance standards of 1.0 NTU as a maximum and 0.3 NTU at the 95th percentile monthly for treatment plants using conventional treatment or direct filtration; (4) requirements for individual filter turbidity monitoring; (5) disinfection benchmark provisions to assess the level of microbial protection provided as facilities take steps to comply with new DBP standards; (6) inclusion of *Cryptosporidium* in the definition of GWUDI and in the watershed control

requirements for unfiltered public water systems; (7) requirements for covers on new finished water storage facilities; and (8) sanitary surveys for all surface water systems regardless of size.

The IESWTR was developed in conjunction with the Stage 1 Disinfectants and Disinfection Byproducts Rule (Stage 1 DBPR) (63 FR 69389; December 16, 1998) (USEPA 1998b), which reduced allowable levels of certain DBPs, including trihalomethanes, haloacetic acids, chlorite, and bromate.

4. Long Term 1 Enhanced Surface Water Treatment Rule

The LT1ESWTR (67 FR 1812, January 14, 2002) (USEPA 2002a) builds upon the microbial control provisions established by the IESWTR for large systems, through extending similar requirements to small systems. The LT1ESWTR applies to PWSs using surface water or GWUDI as sources that serve fewer than 10,000 people. Like the IESWTR, the LT1ESWTR established the following: 2 log (99 percent) *Cryptosporidium* removal requirements for systems that filter; individual filter turbidity monitoring and more stringent combined filter effluent turbidity standards for conventional and direct filtration plants; disinfection profiling and benchmarking; inclusion of *Cryptosporidium* in the definition of GWUDI and in the watershed control requirements for unfiltered systems; and the requirement that new finished water storage facilities be covered.

5. Filter Backwash Recycle Rule

EPA promulgated the Filter Backwash Recycling Rule (FBRR) (66 FR 31085, June 8, 2001) (USEPA 2001a) to increase protection of finished drinking water supplies from contamination by *Cryptosporidium* and other microbial pathogens. The FBRR requirements will reduce the potential risks associated with recycling contaminants removed during the filtration process. The FBRR provisions apply to all systems that recycle, regardless of population served. In general, the provisions include the following: (1) Recycling systems must return certain recycle streams prior to the point of primary coagulant addition unless the State specifies an alternative location; (2) direct filtration systems recycling to the treatment process must provide detailed recycle treatment information to the State; and (3) certain conventional systems that practice direct recycling must perform a one-month, one-time recycling self assessment.

C. What Public Health Concerns Does This Proposal Address?

This section presents the basis for the public health concern associated with *Cryptosporidium* in drinking water by summarizing information on *Cryptosporidium* health effects and outbreaks. This is followed by a description of the specific areas of public health concern that remain after implementation of the IESWTR and LT1ESWTR and that are addressed in the LT2ESWTR proposal. More detailed information about *Cryptosporidium* health effects may be found in the following criteria documents: *Cryptosporidium*: Human Health Criteria Document (USEPA 2001b), *Cryptosporidium*: Drinking Water Advisory (USEPA 2001c), and *Cryptosporidium*: Risks for Infants and Children (USEPA 2001d).

1. Introduction

While modern water treatment systems have substantially reduced waterborne disease incidence, drinking water contamination remains a significant health risk management challenge. EPA's Science Advisory Board in 1990 cited drinking water contamination, particularly contamination by pathogenic microorganisms, as one of the most important environmental risks (USEPA 1990). This risk is underscored by information from the Centers for Disease Control and Prevention (CDC) which indicates that between 1980 and 1998 a total of 419 outbreaks associated with drinking water were reported, with greater than 511,000 estimated cases of disease. A number of agents were implicated in these outbreaks, including viruses, bacteria, and protozoa, as well as several chemicals (Craun and Calderon 1996, Levy *et al.* 1998, Barwick *et al.* 2000). The majority of cases were associated with surface water, and specifically with the 1993 *Cryptosporidium* outbreak in Milwaukee, WI with an estimated 403,000 cases (Mac Kenzie *et al.* 1994). A recent study by McDonald *et al.* (2001), which used blood samples from Milwaukee children collected during and after the 1993 outbreak, suggests that *Cryptosporidium* infection, including asymptomatic infection, was more widespread than might be inferred from the illness estimates by Mac Kenzie *et al.* (1994).

It is important to note that the number of identified and reported outbreaks in the CDC database is believed to substantially understate the actual incidence of waterborne disease outbreaks and cases (Craun and

Calderon 1996, National Research Council 1997). This under reporting is due to a number of factors. Many people experiencing gastrointestinal illness do not seek medical attention. Where medical attention is provided, the pathogenic agent may not be identified through routine testing. Physicians often lack sufficient information to attribute gastrointestinal illness to any specific origin, such as drinking water, and few States have an active outbreak surveillance program. Consequently, outbreaks are often not recognized in a community or, if recognized, are not traced to a drinking water source.

In addition, an unknown but probably significant portion of waterborne disease is endemic (*i.e.* isolated cases not associated with an outbreak) and, thus, is even more difficult to recognize. The Economic Analysis for the proposed LT2ESWTR (USEPA 2003a) uses data on *Cryptosporidium* occurrence, infectivity, and treatment to estimate the baseline endemic incidence of cryptosporidiosis attributable to drinking water, as well as the reductions projected as a result of this rule.

Most waterborne pathogens cause gastrointestinal illness with diarrhea, abdominal discomfort, nausea, vomiting, and other symptoms. The effects of waterborne disease are usually acute, resulting from a single or small number of exposures. Such illnesses are generally of short duration in healthy people. However, some pathogens, including *Giardia lamblia* and *Cryptosporidium*, may cause disease lasting weeks or longer in otherwise healthy individuals, though this is not typical for *Cryptosporidium*. Waterborne pathogens also cause more serious disorders such as hepatitis, peptic ulcers, myocarditis, paralysis, conjunctivitis, swollen lymph glands, meningitis, and reactive arthritis, and have been associated with diabetes, encephalitis, and other diseases (Lederberg 1992).

There are populations that are at greater risk from waterborne disease. These sensitive subpopulations include children (especially infants), the elderly, the malnourished, pregnant women, the disease impaired (*e.g.*, diabetes, cystic fibrosis), and a broad category of those with compromised immune systems, such as AIDS patients, those with autoimmune disorders (*e.g.*, rheumatoid arthritis, lupus erythematosus, multiple sclerosis), transplant recipients, and those on chemotherapy (Rose 1997). This sensitive segment represents almost 20% of the population in the United States (Gerba *et al.* 1996). The severity and duration of illness is often greater in sensitive subpopulations than

in healthy individuals, and in a small percentage of such cases, death may result.

2. *Cryptosporidium* Health Effects and Outbreaks

Cryptosporidium is a protozoan parasite that exists in warm-blooded hosts and, upon excretion, may survive for months in the environment (Kato *et al.*, 2001). Ingestion of *Cryptosporidium* can lead to cryptosporidiosis, a gastrointestinal illness. Transmission of cryptosporidiosis often occurs through consumption of feces contaminated food or water, but may also result from direct or indirect contact with infected persons or animals (Casemore 1990). Surveys (described in Section III) indicate that *Cryptosporidium* is common in surface waters used as drinking water supplies. Sources of *Cryptosporidium* contamination include animal agriculture, wastewater treatment plant discharges, slaughterhouses, birds, wild animals, and other sources of fecal matter.

EPA is particularly concerned about *Cryptosporidium* because, unlike pathogens such as bacteria and most viruses, *Cryptosporidium* oocysts are highly resistant to standard disinfectants like chlorine and chloramines. Consequently, control of *Cryptosporidium* in most treatment plants is dependent on physical removal processes. Finished water monitoring data indicate that *Cryptosporidium* is sometimes present in filtered, treated drinking water (LeChevallier *et al.* 1991; Aboytes *et al.* 2002). Moreover, as noted later, many of the individuals sickened by waterborne outbreaks of cryptosporidiosis were served by filtered surface water supplies (Solo-Gabriele and Neumeister, 1996). In some cases, these outbreaks were attributed to treatment deficiencies, while in other cases the cause was unidentified (see Table II-1).

These data suggest that surface water systems that filter and disinfect may still be vulnerable to *Cryptosporidium*, depending on the source water quality and treatment effectiveness. Today's proposed rule addresses concern with passage of *Cryptosporidium* through physical removal processes during water treatment, as well as in systems lacking filtration.

a. *Health effects.* *Cryptosporidium* infection is characterized by mild to severe diarrhea, dehydration, stomach cramps, and/or a slight fever. Symptoms typically last from several days to two weeks, though in a small percentage of cases, the symptoms may persist for months or longer in otherwise healthy individuals. Human feeding studies

have demonstrated that a low dose of *Cryptosporidium parvum* (*C. parvum*) is sufficient to cause infection in healthy adults (DuPont *et al.* 1995, Chappell *et al.* 1999, Messner *et al.* 2001). Studies of immunosuppressed adult mice have demonstrated that a single viable oocyst can induce patent *C. parvum* infections (Yang *et al.* 2000).

There is evidence that an immune response to *Cryptosporidium* exists, but the degree and duration of this immunity is not well characterized. In a study by Chappell *et al.* (1999), individuals with a blood serum antibody (IgG), which can develop from exposure to *C. parvum*, demonstrated immunity to low doses of oocysts. The investigators found the ID50 dose (*i.e.*, dose that infects 50% of the challenged population) of one *C. parvum* isolate for adult volunteers who had pre-existing serum IgG to be 1,880 oocysts in comparison to 132 oocysts for individuals reported as serologically negative. However, the implications of these data for studies of *Cryptosporidium* infectivity are unclear. Earlier work did not observe a correlation between the development of antibodies after *Cryptosporidium* exposure and subsequent protection from illness (Okhuysen *et al.* 1998). A subsequent investigation by Muller *et al.* (2001) observed serological responses to *Cryptosporidium* antigens in samples from individuals reported by Chappell *et al.* as serologically negative.

Cryptosporidium parvum was first recognized as a human pathogen in 1976 (Juraneck 1995). Cases of illness from *Cryptosporidium* were rarely reported until 1982 when documented disease incidence increased due to the AIDS epidemic (Current 1983). As laboratory diagnostic techniques improved during subsequent years, outbreaks among immunocompetent persons were recognized as well. Human, cattle, dog and deer types of *C. parvum* have been found in healthy individuals (Ong *et al.* 2002, Morgan-Ryan *et al.* 2002). Other *Cryptosporidium* species (*C. felis*, *C. meleagridis*, and possibly *C. muris*) have infected healthy individuals, primarily children (Xiao *et al.* 2001, Chalmers *et al.* 2002, Katsumata *et al.* 2000). Cross-species infection occurs. The human type of *C. parvum* (now named *C. hominis* (Morgan-Ryan *et al.* 2002)) has infected a dugong and monkeys (Spano *et al.* 1998). The cattle type of *C. parvum* infects humans, wild animals, and other livestock, such as sheep, goats and deer (Ong *et al.* 2002).

As noted earlier, there are sensitive populations that are at greater risk from pathogenic microorganisms.

Cryptosporidiosis symptoms in immunocompromised subpopulations are much more severe, including debilitating voluminous diarrhea that may be accompanied by severe abdominal cramps, weight loss, and low grade fever (Juranek 1995). Mortality is a significant threat to the immunocompromised infected with *Cryptosporidium*:

the duration and severity of the disease are significant: whereas 1 percent of the immunocompetent population may be hospitalized with very little risk of mortality, *Cryptosporidium* infections are associated with a high rate of mortality in the immunocompromised (Rose 1997)

A follow-up study of the 1993 Milwaukee, WI outbreak reported that at least 50 *Cryptosporidium*-associated deaths occurred among the severely immunocompromised (Hoxie *et al.* 1997).

b. *Waterborne cryptosporidiosis outbreaks.* *Cryptosporidium* has caused a number of waterborne disease outbreaks since 1984 when the first one was reported in the U.S. Table II-1 lists reported outbreaks in community water systems (CWS) and non-community water systems (NCWS). Between 1984-1998, nine outbreaks caused by *Cryptosporidium* were reported in the U.S. with approximately 421,000 cases associated cases of illness (CDC 1993, 1996, 1998, 2000, and 2001). Solo-Gabriele and Neumeister (1996) characterized water supplies associated with U.S. outbreaks of cryptosporidiosis. They determined that almost half of the outbreaks were associated with ground water (untreated or chlorinated springs and wells), but that the majority of affected individuals were served by filtered surface water supplies (rivers and lakes). They found

that during outbreaks involving treated spring or well water, the chlorination systems were apparently operating satisfactorily, with a measurable chlorine residual.

Although the occurrence of *Cryptosporidium* in U.S. drinking water supplies has been substantiated by data collected during outbreak investigations, the source and density of oocysts associated with the outbreak have not always been detected or reported. Furthermore, because of limitations and uncertainties of the immunofluorescence assay (IFA) method used in earlier studies, negative results in source or finished water during these outbreaks do not necessarily mean that there were no oocysts in the water at the time of sampling.

TABLE II-1.—OUTBREAKS CAUSED BY *Cryptosporidium* IN PUBLIC WATER SYSTEMS: 1984-1998

Year	State	Cases	System	Deficiency	Source
1984	TX	117	CWS	3	Well.
1987	GA	13,000	CWS	3	River.
1991	PA	551	NCWS	3	Well.
1992	OR	††	CWS	3	Spring.
1992	OR	††	CWS	3	River.
1993	NV	103	CWS	5	Lake.
1993	WI	403,000	CWS	3	Lake.
1994	WA	134	CWS	2	Well.
1998	TX	1,400	CWS	3	Well.

††=Total estimated cases were 3,000. The locations were nearby and cases overlapped in time Definitions of deficiencies = (1) untreated surface water; (2) untreated ground water; (3) treatment deficiency (e.g., temporary interruption of disinfection, chronically inadequate disinfection, and inadequate or no filtration); (4) distribution system deficiency (e.g., cross connection, contamination of water mains during construction or repair, and contamination of a storage facility); and (5) unknown or miscellaneous deficiency.

3. Remaining Public Health Concerns Following the IESWTR and LT1ESWTR

This section presents the areas of remaining public health concern following implementation of the IESWTR and LT1ESWTR that EPA proposes to address in the LT2ESWTR. These are as follows: (a) Adequacy of physical removal to control *Cryptosporidium* and the need for risk based treatment requirements; (b) control of *Cryptosporidium* in unfiltered systems; and (c) uncovered finished water storage facilities.

EPA recognized each of these issues as a potential public health concern during development of the IESWTR, but could not address them at that time due to the absence of key data. Accordingly, this section begins with a description of how EPA considered these issues during development of the IESWTR, including the data gaps that were identified at that time. This is followed by a statement of the extent to which new information has filled these data gaps, thereby allowing

EPA to address these public health concerns in the LT2ESWTR proposal.

a. *Adequacy of physical removal to control Cryptosporidium and the need for risk based treatment requirements.* A question that received significant consideration during development of the IESWTR is whether physical removal by filtration plants provides adequate protection against *Cryptosporidium* in drinking water, or whether certain systems should be required to provide inactivation of *Cryptosporidium* based on source water pathogen levels. As discussed in the proposal, notice of data availability (NODA), and final IESWTR, EPA and stakeholders concluded that data available during IESWTR development were not adequate to support risk based inactivation requirements for *Cryptosporidium*. However, the Agency maintained that a risk based approach to *Cryptosporidium* control would be considered for the LT2ESWTR when data collected under the Information Collection Rule were available and other

critical information needs had been addressed.

The IESWTR proposal (59 FR 38832, July 29, 1994) (USEPA 1994) included two treatment alternatives, labeled B and C, that specifically addressed *Cryptosporidium*. Under Alternative B, the level of required treatment would be based on the density of *Cryptosporidium* in the source water. The proposal noted concerns with this approach, though, due to uncertainty in the risk associated with *Cryptosporidium* and the feasibility of achieving higher treatment levels through disinfection. Consequently, EPA also proposed Alternative C, which would require 2 log (99%) removal of *Cryptosporidium* by filtration. This was based on the determination that 2 log *Cryptosporidium* removal is feasible using conventional treatment.

In the 1996 Information Collection Rule (61 FR 24354, May 14, 1996) (USEPA 1996a), EPA concluded that the analytical method prescribed for measuring *Cryptosporidium* was

adequate for making national occurrence estimates, but would not suffice for making site specific source water density estimates. This finding further contributed to the rationale supporting Alternative C under the proposed IESWTR.

The NODA for the IESWTR (62 FR 59498, Nov. 3, 1997) (USEPA 1997a) presented the recommendations of the Stage 1 MDBP Federal Advisory Committee for the IESWTR. As stated in the NODA, the Committee engaged in extensive discussions regarding the adequacy of relying solely on physical removal to control *Cryptosporidium* and the need for inactivation. There was an absence of consensus on whether it was possible at that time to adequately measure *Cryptosporidium* inactivation efficiencies for various disinfection technologies. This was a significant impediment to addressing inactivation in the IESWTR. However, the Committee recognized that inactivation requirements may be necessary under future regulatory scenarios, as shown by the following consensus recommendation from the Stage 1 MDBP Agreement in Principle:

EPA should issue a risk based proposal of the Final Enhanced Surface Water Treatment Rule for *Cryptosporidium* embodying the multiple barrier approach (e.g., source water protection, physical removal, inactivation, etc.), including, where risks suggest appropriate, inactivation requirements (62 FR 59557, Nov. 3, 1997) (USEPA 1997a).

The preamble to the final IESWTR (63 FR 69478, Dec. 16, 1998) (USEPA 1998a) states that EPA was unable to consider the proposed Alternative B (treatment requirements for *Cryptosporidium* based on source water occurrence levels) for the IESWTR because occurrence data from the Information Collection Rule survey and related analysis were not available in time to meet the statutory promulgation deadline. The Agency affirmed, though, that further control of *Cryptosporidium* would be addressed in the LT2ESWTR.

In today's notice, EPA is proposing a risk based approach for control of *Cryptosporidium* in drinking water. Under this approach, the required level of additional *Cryptosporidium* treatment relates to the source water pathogen density. EPA believes many of the data gaps that prevented the adoption of this approach under the IESWTR have been addressed. As described in Section III of this preamble, information on *Cryptosporidium* occurrence from the Information Collection Rule and Information Collection Rule Supplemental Surveys, along with new data on *Cryptosporidium* infectivity, have provided EPA with a better

understanding of the magnitude and distribution of risk for this pathogen. Improved analytical methods allow for a more accurate assessment of source water *Cryptosporidium* levels, and recent disinfection studies with UV, ozone, and chlorine dioxide provide the technical basis to support *Cryptosporidium* inactivation requirements.

b. *Control of Cryptosporidium in unfiltered systems.* There is particular concern about *Cryptosporidium* in the source waters of unfiltered systems because this pathogen has been shown to be resistant to conventional disinfection practices. In the IESWTR, EPA extended watershed control requirements for unfiltered systems to include the control of *Cryptosporidium*. EPA did not establish *Cryptosporidium* treatment requirements for unfiltered systems because available data suggested an equivalency of risk in filtered and unfiltered systems. This is described in the final IESWTR as follows:

it appears that unfiltered water systems that comply with the source water requirements of the SWTR have a risk of cryptosporidiosis equivalent to that of a water system with a well operated filter plant using a water source of average quality (63 FR 69492, Dec. 16, 1998) (USEPA 1998a)

The Agency noted that data from the Information Collection Rule would provide more information on *Cryptosporidium* levels in filtered and unfiltered systems, and that *Cryptosporidium* treatment requirements would be re-evaluated when these data became available.

In today's notice, EPA is proposing *Cryptosporidium* inactivation requirements for unfiltered systems. These proposed requirements stem from an assessment of *Cryptosporidium* source water occurrence in both filtered and unfiltered systems using data from the Information Collection Rule and other surveys, as described in Section III of this preamble. These new data do not support the finding described in the IESWTR of equivalent risk in filtered and unfiltered systems. Rather, *Cryptosporidium* treatment by unfiltered systems is necessary to achieve a finished water risk level equivalent to that of filtered systems. In addition, the development of *Cryptosporidium* inactivation criteria for UV, ozone, and chlorine dioxide in the LT2ESWTR has made it feasible for unfiltered systems to provide *Cryptosporidium* treatment.

c. *Uncovered finished water storage facilities.* In the IESWTR proposal, EPA solicited comment on a requirement that systems cover finished water storage

facilities to reduce the potential for contamination by pathogens and hazardous chemicals. Potential sources of contamination to uncovered storage facilities include airborne chemicals, runoff, animal carcasses, animal or bird droppings, and growth of algae and other aquatic organisms (59 FR 38832, July 29, 1994) (USEPA 1994).

The final IESWTR established a requirement to cover all new storage facilities for finished water for which construction began after February 16, 1999 (63 FR 69493, Dec. 16, 1998) (USEPA 1998a). In preamble to the final IESWTR, EPA described future regulation of existing uncovered finished water storage facilities as follows:

EPA needs more time to collect and analyze additional information to evaluate regulatory impacts on systems with existing uncovered reservoirs on a national basis . . . EPA will further consider whether to require the covering of existing reservoirs during the development of subsequent microbial regulations when additional data and analysis to develop the national costs of coverage are available.

EPA continues to be concerned about contamination resulting from uncovered finished water storage facilities, particularly the potential for virus contamination via bird droppings, and now has sufficient data to estimate national cost implications for various regulatory control strategies. Therefore, EPA is proposing control measures for all systems with uncovered finished water storage facilities in the LT2ESWTR. New data and proposed requirements are described in section IV.E of this preamble.

D. Federal Advisory Committee Process

In March 1999, EPA reconvened the M-DBP Federal Advisory Committee to develop recommendations for the Stage 2 DBPR and LT2ESWTR. The Committee consisted of organizational members representing EPA, State and local public health and regulatory agencies, local elected officials, Indian Tribes, drinking water suppliers, chemical and equipment manufacturers, and public interest groups. Technical support for the Committee's discussions was provided by a technical workgroup established by the Committee at its first meeting. The Committee's activities resulted in the collection and evaluation of substantial new information related to key elements for both rules. This included new data on pathogenicity, occurrence, and treatment of microbial contaminants, specifically including *Cryptosporidium*, as well as new data on DBP health risks, exposure, and control. New information relevant to the

LT2ESWTR is summarized in Section III of this proposal.

In September 2000, the Committee signed an Agreement in Principle reflecting the consensus recommendations of the group. The Agreement was published in a December 29, 2000 **Federal Register** notice (65 FR 83015, December 29, 2000) (USEPA 2000a). The Agreement is divided into Parts A & B. The entire Committee reached consensus on Part A, which contains provisions that directly apply to the Stage 2 DBPR and LT2ESWTR. The full Committee, with the exception of one member, agreed to Part B, which has recommendations for future activities by EPA in the areas of distribution systems and microbial water quality criteria.

The Committee reached agreement on the following major issues discussed in this notice and the proposed Stage 2 DBPR:

LT2ESWTR: (1) Additional *Cryptosporidium* treatment based on source water monitoring results; (2) Filtered systems that must comply with additional *Cryptosporidium* treatment requirements may choose from a "toolbox" of treatment and control options; (3) Reduced monitoring burden for small systems; (4) Future monitoring to confirm source water quality assessments; (5) *Cryptosporidium* inactivation by all unfiltered systems; (6) Unfiltered systems meet overall inactivation requirements using a minimum of 2 disinfectants; (7) Development of criteria and guidance for UV disinfection and other toolbox options; (8) Cover or treat existing uncovered finished water reservoirs (*i.e.*, storage facilities) or implement risk mitigation plans.

Stage 2 DBPR: (1) Compliance calculation for total trihalomethanes (TTHM) and five haloacetic acids (HAA5) revised from a running annual average (RAA) to a locational running annual average (LRAA); (2) Compliance carried out in two phases of the rule; (3) Performance of an Initial Distribution System Evaluation; (4) Continued importance of simultaneous compliance with DBP and microbial regulations; (5) Unchanged MCL for bromate.

III. New Information on *Cryptosporidium* Health Risks and Treatment

The purpose of this section is to describe information related to health risks and treatment of *Cryptosporidium* in drinking water that has become available since EPA developed the IESWTR. Much of this information was evaluated by the Stage 2 M-DBP Federal Advisory Committee when considering

whether and to what degree existing microbial standards should be revised to protect public health. It serves as a basis for the recommendations made by the Advisory Committee and for provisions in today's proposed rule. This section begins with an overview of critical factors that EPA considers when evaluating regulation of microbial pathogens. New information is then presented on three key topics: *Cryptosporidium* infectivity, occurrence, and treatment.

A. Overview of Critical Factors for Evaluating Regulation of Microbial Pathogens

When proposing a national primary drinking water regulation that includes a maximum contaminant level or treatment technique, SDWA requires EPA to analyze the health risk reduction benefits and costs likely to result from alternative regulatory levels that are being considered. For assessing risk, EPA follows the paradigm described by the National Academy of Science (NRC, 1983) which involves four steps: (1) Hazard identification, (2) dose-response assessment, (3) exposure assessment, and (4) risk characterization. The application of these steps to microbial pathogens is briefly described in this section, followed by a summary of how EPA estimates the health benefits and costs of regulatory alternatives.

Hazard identification for microbial pathogens is a description of the nature, severity, and duration of the health effects stemming from infection. Under SDWA, EPA must consider health effects on the general population and on subpopulations that are at greater risk of adverse health effects. See section II.C.2 of this preamble for health effects associated with *Cryptosporidium*.

Dose-response assessment with microorganisms is commonly termed infectivity and is a description of the relationship between the number of pathogens ingested and the probability of infection. Information on *Cryptosporidium* infectivity is presented in section III.B of this preamble.

Exposure to microbial pathogens in drinking water is generally a function of the concentration of the pathogen in finished water and the volume of water ingested (exposure also occurs through secondary routes involving infected individuals). Because it is difficult to directly measure pathogens at the low levels typically present in finished water, EPA's information on pathogen exposure is primarily derived from surveys of source water occurrence. EPA estimates the concentration of pathogens in treated water by combining source water pathogen

occurrence data with information on the performance of treatment plants in reducing pathogen levels. Data on the occurrence of *Cryptosporidium* are described in section III.C of this preamble and in Occurrence and Exposure Assessment for the LT2ESWTR (USEPA 2003b). *Cryptosporidium* treatment studies are described in section III.D of this preamble.

Risk characterization is the culminating step of the risk assessment process. It is a description of the nature and magnitude of risk, and characterizes strengths, weaknesses, and attendant uncertainties of the assessment. EPA's risk characterization for *Cryptosporidium* is described in Economic Analysis for the LT2ESWTR (USEPA 2003a).

Estimating the health benefits and costs that would result from a new regulatory requirement involves a number of steps, including evaluating the efficacy and cost of treatment strategies to reduce exposure to the contaminant, forecasting the number of systems that would implement different treatment strategies to comply with the regulatory standard, and projecting the reduction in exposure to the contaminant and consequent health risk reduction benefits stemming from regulatory compliance. EPA's estimates of health benefits and costs associated with the proposed LT2ESWTR are presented in Economic Analysis for the LT2ESWTR (USEPA 2003a) and are summarized in section VI of this preamble.

B. *Cryptosporidium* Infectivity

This section presents information on the infectivity of *Cryptosporidium* oocysts. Infectivity relates the probability of infection by *Cryptosporidium* with the number of oocysts that a person ingests, and it is used to predict the disease burden associated with different *Cryptosporidium* levels in drinking water. Information on *Cryptosporidium* infectivity comes from dose-response studies where healthy human subjects ingest different numbers of oocysts and are subsequently evaluated for signs of infection and illness.

Data from a human dose-response study of one *Cryptosporidium* isolate (the IOWA study, conducted at the University of Texas-Houston Health Science Center) had been published prior to the IESWTR (DuPont *et al.* 1995). Following IESWTR promulgation, a study of two additional isolates (TAMU and UCP) was completed and published (Okhuysen *et al.* 1999). This study also presented a

reanalysis of the IOWA study results. As described in more detail later in this section, this new study indicates that the infectivity of *Cryptosporidium* oocysts varies over a wide range. The UCP oocysts appeared less infective than those of the IOWA study while the TAMU oocysts were much more infective. Although the occurrence of these isolates among environmental oocysts is unknown, a meta-analysis of these data conducted by EPA suggests the overall infectivity of *Cryptosporidium* may be significantly greater than was estimated for the IESWTR (USEPA 2003a).

This section begins with a description of the infectivity data considered for the IESWTR. This is followed by a presentation of additional data that have been evaluated for the proposed LT2ESWTR and a characterization of the significance of these new data.

1. *Cryptosporidium* Infectivity Data Evaluated for IESWTR

Data from the IOWA study (DuPont *et al.* 1995) were evaluated for the IESWTR. In that study, 29 individuals were given single doses ranging from 30 oocysts to 1 million oocysts. This oocyst isolate was originally obtained from a naturally infected calf. Seven persons received doses above 500, and all were infected. Eleven of the twenty two individuals receiving doses of 500 or fewer were classified as infected based on oocysts detected in stool samples.

The IOWA study data were analyzed using an exponential dose-response model established by Haas *et al.* (1996) for *Cryptosporidium*:

$$\text{Probability \{Infection / Dose\} = } \frac{1}{1 + e^{-\text{Dose}/k}}$$

Based on the maximum likelihood estimate of k (238), the probability of infection from ingesting a single oocyst (1/k) is approximately 0.4% (4 persons infected for every 1,000 who each ingest one oocyst). Based on the same estimate, the dose at which 50% of persons

become infected (known as the median infectious dose or ID50) is 165.

2. New Data on *Cryptosporidium* Infectivity

A study of two additional *Cryptosporidium* isolates was conducted at the University of Texas-Houston Health Science Center (Okhuysen *et al.* 1999). One of the isolates (UCP) was originally collected from naturally infected calves. The other isolate (TAMU) was originally collected from a veterinary student who became infected during necropsy on an infected foal.

The TAMU and UCP studies were conducted with 14 and 17 subjects, respectively. Because thousands of oocysts per gram of stool can go undetected, researchers elected to use both stool test results and symptoms as markers of infection (only stool test results had been used for the IOWA study). Under this definition, two additional IOWA subjects were regarded as having been infected. As shown in Table III-1, all but two of the TAMU subjects were presumed infected and all but six of the UCP subjects were presumed infected following ingestion of the indicated oocyst doses.

TABLE III-1.—*Cryptosporidium Parvum* INFECTIVITY IN HEALTHY ADULT VOLUNTEERS

Isolate and dose (# of oocysts)	Number of subjects ¹	Number infected ¹
IOWA:		
30	5	2
100	8	4
300	3	2
500	6	5
1,000	2	2
10,000	3	3
100,000	1	1
1,000,000	1	1
TAMU:		
10	3	2
30	3	2
100	3	3

TABLE III-1.—*Cryptosporidium Parvum* INFECTIVITY IN HEALTHY ADULT VOLUNTEERS—Continued

Isolate and dose (# of oocysts)	Number of subjects ¹	Number infected ¹
UCP:		
500	5	5
500	5	3
1,000	3	2
5,000	5	2
10,000	4	4

¹ The two right columns list the number of subjects belonging to each category.

EPA conducted a meta-analysis of these results in which the three isolates were considered as a random sample (of size three) from a larger population of environmental oocysts (Messner *et al.* 2001). This meta analysis was reviewed by the Science Advisory Board (SAB). In written comments from a December 2001 meeting of the Drinking Water Committee, SAB members recommended the following: (1) two assumed infectivity distributions (of parameter r = 1/k as logit normal and logit-t) should be used in order to characterize uncertainty and (2) EPA should consider excluding the UCP data set because it seems to be an outlier (see Section VII.K). In response, EPA has used the two recommended distributions for infectivity and has conducted the meta-analysis both with and without the UCP data due to uncertainty about whether it is appropriate to exclude these data.

Table III-2 presents meta-analysis estimates of the probability of infection given one oocyst ingested. Results are shown for the four different analysis conditions (log normal and log-t distributions; with and without UCP data) as well as a combined result derived by sampling equally from each distribution. A more complete description of the infectivity analysis is provided in Economic Analysis for the LT2ESWTR (USEPA 2003a).

TABLE III-2.—RISK OF INFECTION, GIVEN ONE OOCYST INGESTED

Basis for analysis		Probability of infection, one oocyst ingested	
Studies used	Distributional model	Mean	80% Credible interval
IOWA, TAMU, and UCP	Normal	0.07	0.007–0.19
IOWA, TAMU, and UCP	Student's t (3df) ¹	0.09	0.015–0.20
IOWA and TAMU	Normal	0.09	0.011–0.23
IOWA and TAMU	Student's t (3df) ¹	0.10	0.014–0.25
Equal Mix of the Four Above	0.09	0.011–0.22

¹ Student's t distribution with 3 degrees of freedom (3df).

The results in Table III–2 show that the mean probability of infection from ingesting a single infectious oocyst ranges from 7% to 10% depending on the assumptions used. In comparison, the best estimate in the IESWTR of this probability was 0.4%, based on the IOWA isolate alone, and using the earlier definition of infection. Thus, these data suggest that both the range and magnitude of *Cryptosporidium* infectivity is higher than was estimated in the final IESWTR.

It should be noted that although significantly more data on *Cryptosporidium* infectivity are available now than when EPA established the IESWTR, there remains uncertainty about this parameter in several areas. It is unknown how well the oocysts used in the feeding studies represent *Cryptosporidium* naturally occurring in the environment, and the analyses do not fully account for variability in host susceptibility and the effect of previous infections. Furthermore, the sample sizes are relatively small, and the confidence bands on the estimates span more than an order of magnitude. Another limitation is that none of the studies included doses below 10 oocysts, while when people ingest oocysts in drinking water it is usually a single oocyst.

3. Significance of New Infectivity Data

The new infectivity data reveal that oocysts vary greatly in their ability to infect human hosts. Moreover, due to this variability and the finding of a highly infectious isolate, TAMU, the overall population of oocysts appears to be more infective than assumed for the IESWTR. The meta-analysis described earlier indicates the probability of infection at low *Cryptosporidium* concentrations may be about 20 times as great as previously estimated (which was based on the IOWA isolate alone and using the earlier definition of infection (stool-confirmed infections)).

C. *Cryptosporidium* Occurrence

This section presents information on the occurrence of *Cryptosporidium* oocysts in drinking water sources. Occurrence information is important because it is used in assessing the risk associated with *Cryptosporidium* in both filtered and unfiltered systems, as well as in estimating the costs and benefits of the proposed LT2ESWTR.

For the IESWTR, EPA had no national survey data and relied instead on several studies that were local or regional. Those data suggested that a typical (median) filtered surface water source had approximately 2 *Cryptosporidium* oocysts per liter, while

a typical unfiltered surface water source had about 0.01 oocysts per liter, a difference of two orders of magnitude.

Subsequent to promulgating the IESWTR, EPA obtained data from two national surveys: the Information Collection Rule and the Information Collection Rule Supplemental Surveys (ICRSS). These surveys were designed to provide improved estimates of occurrence on a national basis. As described in more detail later in this section, the Information Collection Rule and ICRSS results show three main differences in comparison to *Cryptosporidium* occurrence data used for the IESWTR:

(1) Average *Cryptosporidium* occurrence is lower. Median oocyst levels for the Information Collection Rule and ICRSS data are approximately 0.05/L, which is more than an order of magnitude lower than IESWTR estimates.

(2) *Cryptosporidium* occurrence is more variable from location to location than was shown by the data considered for the IESWTR. This indicates that although median occurrence levels are below those assumed for the IESWTR, there is a subset of systems whose levels are considerably greater than the median.

(3) There is a smaller difference in *Cryptosporidium* levels between typical filtered and unfiltered system water sources. The Information Collection Rule data do not support the IESWTR finding that unfiltered water systems have a risk of cryptosporidiosis equivalent to that of a filter plant with average quality source water.

This section begins with a summary of occurrence data that were used to assess risk under the IESWTR (these data were also used in the main risk assessment for the LT1ESWTR). This is followed by a discussion of the Information Collection Rule and ICRSS that covers the scope of the surveys, analytical methods, results, and a characterization of how these new data impact current understanding of *Cryptosporidium* exposure. A more detailed description of occurrence data is available in Occurrence and Exposure Assessment for the Long Term 2 Enhanced Surface Water Treatment Rule (USEPA 2003b).

1. Occurrence Data Evaluated for IESWTR

Occurrence information evaluated for the IESWTR is detailed in Occurrence and Exposure Assessment for The Interim Enhanced Surface Water Treatment Rule (USEPA 1998c). This information is summarized in the next two paragraphs.

a. *Filtered systems.* In developing the IESWTR, EPA evaluated *Cryptosporidium* occurrence data from a number of studies. Among these studies,

LeChevallier and Norton (1995) produced the largest data set and data from this study were used for the IESWTR risk assessment. This study provided estimates of mean occurrence at 69 locations from the eastern and central U.S. Although limited by the small number of samples per site (one to sixteen samples; most sites were sampled five times), variation within and between sites appeared to be lognormal. The study's median measured source water concentration was 2.31 oocysts/L and the interquartile range (i.e., 25th and 75th percentile) was 1.03 to 5.15 oocysts/L.

b. *Unfiltered systems.* To assess *Cryptosporidium* occurrence in unfiltered systems under the IESWTR, EPA evaluated *Cryptosporidium* monitoring results from several unfiltered water systems that had been summarized by the Seattle Water Department (Montgomery Watson, 1995). The median (central tendency) of these data was approximately 0.01 oocysts/L. Thus, the median concentration in these data set was about 2 orders of magnitude less than the median concentration in the data set used for filtered systems. These data, coupled with the assumption that filtered systems will remove at least 2 log of *Cryptosporidium* as required by the IESWTR, suggested that unfiltered systems that comply with the source water requirements of the SWTR may have a risk of cryptosporidiosis equivalent to that of a filter plant using a water source of average quality (62 FR 59507, November 3, 1997) (USEPA 1997a).

2. Overview of the Information Collection Rule and Information Collection Rule Supplemental Surveys (ICRSS)

The Information Collection Rule and the Information Collection Rule Supplemental Surveys (ICRSS) were national monitoring studies. They were designed to provide EPA with a more comprehensive understanding of the occurrence of microbial pathogens in drinking water sources in order to support regulatory decision making. The surveys attempted to control protozoa measurement error through requiring that (1) laboratories meet certain qualification criteria, (2) standardized methods be used to collect data, and (3) laboratories analyze performance evaluation samples throughout the duration of the study to ensure adequate analytical performance. Information Collection Rule monitoring took place from July 1997 to December 1998; ICRSS *Cryptosporidium* monitoring

began in March 1999 and ended in February 2000.

a. *Scope of the Information Collection Rule.* The Information Collection Rule (61 FR 24354, May 14, 1996) (USEPA 1996a) required large PWSs to collect water quality and treatment data related to DBPs and microbial pathogens over an 18-month period. PWSs using surface water or ground water under the direct influence of surface water as sources and serving at least 100,000 people were required to monitor their raw water monthly for *Cryptosporidium*, Giardia, viruses, total coliforms, and *E. coli*. Approximately 350 plants monitored for microbial parameters.

b. *Scope of the ICRSS.* The ICRSS were designed to complement the Information Collection Rule data set with data from systems serving fewer than 100,000 people and by employing an improved analytical method for protozoa (described later). The ICRSS included 47 large systems (serving greater than 100,000 people), 40 medium systems (serving 10,000 to 100,000 people) and 39 small systems (serving fewer than 10,000 people). Medium and large systems conducted 1 year of twice-per-month sampling for *Cryptosporidium*, Giardia, temperature, pH, turbidity, and coliforms. Other water quality measurements were taken once a month. Small systems did not test for protozoa but tested for all other water quality parameters.

3. Analytical Methods for Protozoa in the Information Collection Rule and ICRSS

This subsection describes analytical methods for *Cryptosporidium* that were used in the Information Collection Rule and ICRSS. Information on *Cryptosporidium* analytical methods is important for the LT2ESWTR for several reasons: (1) It is relevant to the quality of *Cryptosporidium* occurrence data used to assess risk and economic impact of the LT2ESWTR proposal, (2) it provides a basis for the statistical procedures employed to analyze the occurrence data, and (3) it is used to assess the adequacy of *Cryptosporidium* methods to support source-specific decisions under the LT2ESWTR.

The Information Collection Rule and ICRSS data sets were generated using different analytical methods. The Information Collection Rule Protozoan Method (ICR Method) was used to analyze water samples for *Cryptosporidium* during the Information Collection Rule. For the ICRSS, a similar but improved method, EPA Method 1622 (later 1623), was used for protozoa analyses (samples were analyzed for *Cryptosporidium* using Method 1622 for

the first 4 months; then Method 1623 was implemented so that Giardia concentrations could also be measured).

a. *Information Collection Rule Protozoan Method.* With the Information Collection Rule Method (USEPA 1996b), samples were collected by passing water through a filter, which was then delivered to an EPA-approved Information Collection Rule laboratory for analysis. The laboratory eluted the filter, centrifuged the eluate, and separated *Cryptosporidium* oocysts and Giardia cysts from other debris by density-gradient centrifugation. The oocysts and cysts were then stained and counted. Differential interference contrast (DIC) microscopy was used to examine internal structures.

The Information Collection Rule Method provided a quantitative measurement of *Cryptosporidium* oocysts and Giardia cysts, but it is believed to have generally undercounted the actual occurrence (modeling, described later, adjusted for undercounting). This undercounting was due to low volumes analyzed and low method recovery. The volume analyzed directly influences the sensitivity of the analytical method and the Information Collection Rule Method did not require a specific volume analyzed. As a result, sample volumes analyzed during the Information Collection Rule varied widely, depending on the water matrix and analyst discretion, with a median volume analyzed of only 3 L.

Method recovery characterizes the likelihood that an oocyst present in the original sample will be counted. Loss of organisms may occur at any step of the analytical process, including filtration, elution, concentration of the eluate, and purification of the concentrate. To assess the performance of the Information Collection Rule Method, EPA implemented the Information Collection Rule Laboratory Spiking Program. This program involved collection of duplicate samples on two dates from 70 plants. On each occasion, one of the duplicate samples was spiked with a known quantity of Giardia cysts and *Cryptosporidium* oocysts (the quantity was unknown to the laboratory performing the analysis), and both samples were processed according to the method. Recovery of spiked *Cryptosporidium* oocysts ranged from 0% to 65% with a mean of 12% and a standard deviation nearly equal to the mean (relative standard deviation (RSD) approximately 100%) (Scheller *et al.* 2002).

b. *Method 1622 and Method 1623.* EPA developed Method 1622 (detects *Cryptosporidium*) and 1623 (detects

Cryptosporidium and Giardia) to achieve higher recovery rates and lower inter- and intra-laboratory variability than previous methods. These methods incorporate improvements in the concentration, separation, staining, and microscope examination procedures. Specific improvements include the use of more effective filters, immunomagnetic separation (IMS) to separate the oocysts and cysts from extraneous materials present in the water sample, and the addition of 4, 6-diamidino-2-phenylindole (DAPI) stain for microscopic analysis. The performance of these methods was tested through single-laboratory studies and validated through multiple-laboratory validation (round robin) studies.

The per-sample volume analyzed for *Cryptosporidium* during the ICRSS was larger than in the Information Collection Rule, due to a requirement that laboratories analyze a minimum of 10 L or 2 mL of packed pellet with Methods 1622/23 (details in section IV.K). To assess method recovery, matrix spike samples were analyzed on five sampling events for each plant. The protozoa laboratory spiked the additional sample with a known quantity of *Cryptosporidium* oocysts and Giardia cysts (the quantity was unknown to the laboratory performing the analysis) and filtered and analyzed both samples using Methods 1622/23. Recovery in the ICRSS matrix spike study averaged 43% for *Cryptosporidium* with an RSD of 47% (Connell *et al.* 2000). Thus, mean *Cryptosporidium* recovery with Methods 1622/23 under the ICRSS was more than 3.5 times higher than mean recovery in the Information Collection Rule lab spiking program and relative standard deviation was reduced by more than half.

Although Methods 1622 and 1623 have several advantages over the Information Collection Rule method, they also have some of the same limitations. These methods do not determine whether a cyst or oocyst is viable and infectious, and both methods require a skilled microscopist and several hours of sample preparation and analyses.

4. *Cryptosporidium* Occurrence Results from the Information Collection Rule and ICRSS

This section describes *Cryptosporidium* monitoring results from the Information Collection Rule and ICRSS. The focus of this discussion is the national distribution of mean *Cryptosporidium* occurrence levels in the sources of filtered and unfiltered plants.

The observed (raw, unadjusted) *Cryptosporidium* data from the Information Collection Rule and ICRSS do not accurately characterize true concentrations because of (a) the low and variable recovery of the analytical method, (b) the small volumes analyzed, and (c) the relatively small number of sample events. EPA employed a statistical treatment to estimate the true underlying occurrence that led to the data observed in the surveys and to place uncertainty bounds about that estimation.

A hierarchical model with Bayesian parameter estimation techniques was used to separately analyze filtered and unfiltered system data from the Information Collection Rule and the

large and medium system data from the ICRSS. The model included parameters for location, month, source water type, and turbidity. Markov Chain Monte Carlo methods were used to estimate these parameters, producing a large number of estimate sets that represent uncertainty. This analysis is described more completely in Occurrence and Exposure Assessment for the Long Term 2 Enhanced Surface Water Treatment Rule (USEPA 2003b).

a. *Information Collection Rule results.* Figure III-1 presents plant-mean *Cryptosporidium* levels for Information Collection Rule plants as a cumulative distribution. Included in Figure III-1 are distributions of both the observed raw data adjusted for mean analytical

method recovery of 12% and the modeled estimate of the underlying distribution, along with 90% confidence bounds. The two distributions (observed and modeled) are similar for plants where *Cryptosporidium* was detected (196 of 350 Information Collection Rule plants did not detect *Cryptosporidium* in any source water samples). The modeled distribution allows for estimation of *Cryptosporidium* concentrations in sources where oocysts may have been present but were not detected due to low sample volume and poor method recovery (this concept is explained further later in this section).

BILLING CODE 6560-50-P




Figure III-1.-- Plant-Mean *Cryptosporidium* Levels for Information Collection Rule Plants

BILLING CODE 6560-50-P

The results shown in Figure III-1 indicate that mean *Cryptosporidium* levels among Information Collection Rule plants vary widely, with many plants having relatively little

contamination and a fraction of plants with elevated source water pathogen levels. The median and 90th percentile estimates of Information Collection Rule plant-mean *Cryptosporidium* levels are

0.048 and 1.3 oocysts/L, respectively. These levels are lower than *Cryptosporidium* occurrence estimates used in the IESWTR (USEPA 1998c), and the distribution of Information

Collection Rule data is broader (*i.e.*, more source-to-source variability). Also, the occurrence of *Cryptosporidium* in flowing stream sources was greater and more variable than in reservoir/lake sources (shown in USEPA 2003b).

The fact that only 44% of Information Collection Rule plants had one or more samples positive for *Cryptosporidium* and that only 7% of all Information Collection Rule samples were positive for *Cryptosporidium* suggests that oocyst levels were relatively low in many source waters. However, as noted earlier, it is expected that *Cryptosporidium* oocysts were present in many more source waters at the time

of sampling and were not detected due to poor analytical method recovery and low sample volumes.

This concept is illustrated by Figure III-2, which shows the likelihood of no oocysts being detected by the Information Collection Rule method as a function of source water concentration (assumes median Information Collection Rule sample volume of 3 L). As can be seen in Figure III-2, when the source water concentration is 1 oocyst/L, which is a relatively high level, the probability of no oocysts being detected in a 3 L sample is 73%; for a source water with 0.1 oocyst/L, which is close to the median occurrence level, the

probability of a non-detect is 97%. Consequently, EPA has concluded that it is appropriate and necessary to use a statistical model to estimate the underlying distribution.

EPA modeled *Cryptosporidium* occurrence separately for filtered and unfiltered plants that participated in the Information Collection Rule because unfiltered plants comply with different regulatory requirements than filtered plants. As shown in Table III-3, the occurrence of *Cryptosporidium* was lower for unfiltered sources.

BILLING CODE 6560-50-P




Figure III-2.-- Probability of No Oocysts Being Detected by the Information Collection Rule Method as a Function of Source Water *Cryptosporidium* Concentration

BILLING CODE 6560-50-C

TABLE III-3.—SUMMARY OF INFORMATION COLLECTION RULE *Cryptosporidium* MODELED SOURCE WATER DATA FOR UNFILTERED AND FILTERED PLANTS

Source	Information collection rule modeled plant-mean (oocysts/L)		
	Mean	Median	90th percentile
Unfiltered	0.014	0.0079	0.033
Filtered	0.59	0.052	1.4

The median *Cryptosporidium* occurrence level for unfiltered systems in the Information Collection Rule was 0.0079 oocysts/L, which is close to the median level of 0.01 oocysts/L reported for unfiltered systems in the IESWTR (Montgomery Watson, 1995). However, the Information Collection Rule data do not show the 2 log difference in median *Cryptosporidium* levels between filtered and unfiltered systems that was observed for the data used in the IESWTR. The ratio of median plant-mean occurrence in unfiltered plants to filtered plants is about 1:7 (see Table III-3). Thus, based on an assumption of a minimum 2 log removal of *Cryptosporidium* by filtration plants (as required by the IESWTR and LT1ESWTR), these data indicate that, on average, finished water oocysts levels are higher in unfiltered systems than in filtered systems.

b. *ICRSS results.* Figures III-3 and III-4 present plant-mean *Cryptosporidium*

levels for ICRSS medium and large systems, respectively, as cumulative distributions. Medium and large system data were analyzed separately to identify differences between the two data sets. Similar to the Information Collection Rule data plot, Figures III-3 and III-4 include distributions for both the observed raw data adjusted for mean analytical method recovery of 43% and the modeled estimate of the underlying distribution, along with 90% confidence bounds. The observed and modeled distributions are similar for the 85% of ICRSS plants that detected *Cryptosporidium*, and the modeled distribution allows for estimation of *Cryptosporidium* concentrations for source waters where oocysts may have been present but were not detected.

Plant-mean *Cryptosporidium* concentrations for large and medium systems in the ICRSS are similar at the mid and lower range of the distribution and differ at the upper end. ICRSS

medium and large systems both had median plant-mean *Cryptosporidium* levels of approximately 0.05 oocysts/L, which is close to the median oocyst level in the Information Collection Rule data set as well. However, the 90th percentile plant-mean was 0.33 oocysts/L for ICRSS medium systems and 0.24 oocysts/L for ICRSS large systems. Note that in the Information Collection Rule distribution, the 90th percentile *Cryptosporidium* concentration is 1.3 oocysts/L, which is significantly higher than either the ICRSS medium or large system distribution.

The reasons for different results between the surveys are not well understood, but may stem from year-to-year variation in occurrence, systematic differences in the sampling or measurement methods employed, and differences in the populations sampled. This topic is discussed further at the end of this section.

BILLING CODE 6560-50-P




Figure III-3.-- Plant-Mean *Cryptosporidium* Levels for ICRSS Medium Plants




Figure III-4.-- Plant-Mean *Cryptosporidium* Levels for ICRSS Large Plants

BILLING CODE 6560-50-C

5. Significance of new *Cryptosporidium* occurrence data.

The Information Collection Rule and ICRSS data substantially improve overall knowledge of the occurrence distribution of *Cryptosporidium* in drinking water sources. They provide data on many more water sources than were available when the IESWTR was developed and the data are of more uniform quality. In regard to filtered systems, these new data demonstrate two points:

(1) The occurrence of *Cryptosporidium* in many drinking water sources is lower than was indicated by the data used in IESWTR. Median plant-mean levels for the Information Collection Rule and ICRSS data sets are approximately 0.05 oocysts/L, whereas the median oocyst concentration in the LeChevallier and Norton (1995) data used in the IESWTR risk assessment was 2.3 oocysts/L.

(2) *Cryptosporidium* occurrence is more variable from plant to plant than was indicated by the data considered for the IESWTR (*i.e.*, occurrence distribution is

broader). This is illustrated by considering the ratio of the 90th percentile to the median plant-mean concentration. In the LeChevallier and Norton (1995) data used for the IESWTR, this ratio was 4.6, whereas in the Information Collection Rule data, this ratio is 27.

These data, therefore, support the finding that *Cryptosporidium* levels are relatively low in most water sources, but there is a subset of sources with relatively higher concentrations where additional treatment may be appropriate.

In regard to unfiltered plants, the Information Collection Rule data are consistent with the *Cryptosporidium* occurrence estimates for unfiltered systems in the IESWTR. However, due to the lower occurrence estimates for filtered systems noted previously, the Information Collection Rule data do not support the IESWTR finding that unfiltered water systems in compliance with the source water requirements of the SWTR have a risk of cryptosporidiosis equivalent to that of a

well-operated filter plant using a water source of average quality (63 FR 69492, December 16, 1998) (USEPA 1998a). Rather, these data indicate that Agency conclusions regarding the risk comparison between unfiltered and filtered drinking waters must be revised. For protection equivalent to that provided by filtered systems, unfiltered systems must take additional steps to strengthen their microbial barriers.

6. Request for Comment on Information Collection Rule and ICRSS Data Sets

EPA notes that there are significant differences in the Information Collection Rule and ICRSS medium and large system data sets. The median values for these data sets are 0.048, 0.050, and 0.045 oocysts/L, respectively, while the 90th percentile values are 1.3, 0.33, and 0.24 oocysts/L. The reasons for these differences are not readily apparent. The ICRSS used a newer method with better quality control that yields significantly higher recovery, and this suggests that these data are more

reliable for estimating concentrations at individual plants. However, the Information Collection Rule included a much larger number of plants (350 v. 40 each for the ICRSS medium and large system surveys) and, consequently, may be more reliable for estimating occurrence nationally. The surveys included a similar number of samples per plant (18 v. 24 in the ICRSS). The two surveys cover different time periods (7/97–12/98 for the Information Collection Rule and 3/99–2/00 for the ICRSS).

In order to better understand the factors that may account for the differences in the three data sets, EPA conducted several additional analyses. First, EPA compared results for the subset of 40 plants that were in both the Information Collection Rule and ICRSS large system surveys. The medians for the two data sets were 0.13 and 0.045 oocysts/L, respectively, while the 90th percentiles were 1.5 and 0.24 oocysts/L. Clearly, the discrepancy between the two surveys persists for the subsample of data from plants that participated in both surveys. This suggests that the different sample groups in the full data sets are not the primary factor that accounts for the different results.

Next, EPA looked at the six month period (July through December) that was sampled in two consecutive years (1997 and 1998) during the Information Collection Rule survey to investigate year-to-year variations at the same plants. Estimated medians for 1997 and 1998 were 0.062 and 0.040 oocysts/L, respectively, while the 90th percentiles were 1.1 and 1.3 oocysts/L. While these comparisons show some interyear variability, it is less than the variability observed between the Information Collection Rule and ICRSS data sets. EPA has no data comparing the same plants using the same methods for the time periods in question (1997–98 and 1999–2000) so it is not known if the variation between these time periods was larger than the apparent variation between 1997 and 1998 in the Information Collection Rule data set.

The choice of data set has a significant effect on exposure, cost, and benefit estimates for the LT2ESWTR. Due to the lack of any clear criterion for favoring one data set over the other, EPA has conducted the analyses for this proposed rule separately for each, and presents a range of estimates based on the three data sets. EPA requests comment on this approach. EPA will continue to evaluate the relative strengths and limitations of the three data sets, as well as any new data that may become available for the final rule.

D. Treatment

1. Overview

This section presents information on treatment processes for reducing the risk from *Cryptosporidium* in drinking water. Treatment information is critical to two aspects of the LT2ESWTR: (1) estimates of the efficiency of water filtration plants in removing *Cryptosporidium* are used in assessing risk in treated drinking water and (2) the performance and availability of treatment technologies like ozone, UV light, and membranes that effectively inactivate or remove *Cryptosporidium* impact the feasibility of requiring additional treatment for this pathogen.

The majority of plants treating surface water use conventional filtration treatment, which is defined in 40 CFR 141.2 as a series of processes including coagulation, flocculation, sedimentation, and filtration. Direct filtration, which is typically used on sources with low particulate levels, includes coagulation and filtration but not sedimentation. Other common filtration processes are slow sand, diatomaceous earth (DE), membranes, and bag and cartridge filters.

For the IESWTR (and later the LT1ESWTR), EPA evaluated results from pilot and full scale studies of *Cryptosporidium* removal by various types of filtration plants. Based on these studies, EPA concluded that conventional and direct filtration plants meeting IESWTR filter effluent turbidity standards will achieve a minimum 2 log (99%) removal of *Cryptosporidium*. The Agency reached the same conclusion for slow sand and DE filtration plants meeting SWTR turbidity standards. Treatment credit for technologies like membranes and bag and cartridge filters was to be made on a product-specific basis.

Subsequent to promulgating the IESWTR and LT1ESWTR, EPA has reviewed additional studies of the performance of treatment plants in removing *Cryptosporidium*, as well as other micron size particles (e.g., aerobic spores) that may serve as indicators of *Cryptosporidium* removal. As discussed later in this section, the Agency has concluded that these studies support an estimate of 3 log (99.9%) for the average *Cryptosporidium* removal efficiency of conventional treatment plants in compliance with the IESWTR or LT1ESWTR. Section IV.A describes how this estimate of average removal efficiency is used in determining the need for additional *Cryptosporidium* treatment under the LT2ESWTR. Further, this estimate is consistent with

the Stage 2 M–DBP Agreement in Principle, which states as follows:

The additional treatment requirements in the (LT2ESWTR) bin requirement table are based, in part, on the assumption that conventional treatment plants in compliance with the IESWTR achieve an average of 3 logs removal of *Cryptosporidium*.

In addition, the Agency finds that available data support an estimate of 3 log average *Cryptosporidium* removal for well operated slow sand and DE plants. Direct filtration plants are estimated to achieve a 2.5 log average *Cryptosporidium* reduction, in consideration of the absence of a sedimentation process in these plants.

The most significant developments in the treatment of *Cryptosporidium* since IESWTR promulgation are in the area of inactivation. During IESWTR development, EPA determined that available data were not sufficient to identify criteria for awarding *Cryptosporidium* treatment credit for any disinfectant. As presented in section IV.C.14, EPA has now acquired the necessary data to specify the disinfectant concentrations and contact times necessary to achieve different levels of *Cryptosporidium* inactivation with chlorine dioxide and ozone. Additionally, recent studies have demonstrated that UV light will produce high levels of *Cryptosporidium* and *Giardia lamblia* inactivation at low doses. Section IV.C.15 provides criteria for systems to achieve credit for disinfection of *Cryptosporidium*, *Giardia lamblia*, and viruses by UV.

This section begins with a summary of treatment information considered for the IESWTR and LT1ESWTR, followed by a discussion of additional data that EPA has evaluated since promulgating those regulations. Further information on treatment of *Cryptosporidium* is available in Technologies and Costs for Control of Microbial Contaminants and Disinfection Byproducts (USEPA 2003c), Occurrence and Exposure Assessment for the Long Term 2 Enhanced Surface Water Treatment Rule (USEPA 2003b) and section IV.C of this preamble.

2. Treatment information considered for the IESWTR and LT1ESWTR

Treatment studies that were evaluated during development of the IESWTR are described in the IESWTR NODA (62 FR 59486, November 3, 1997) (USEPA 1997b), the Regulatory Impact Analysis for the IESWTR (USEPA 1998d), and Technologies and Costs for the Microbial Recommendations of the M/DBP Advisory Committee (USEPA 1997b). Treatment information considered in development of the

LT1ESWTR is described in the proposed rule (65 FR 59486, April 10, 2000) (USEPA 2000b). Pertinent information is summarized in the following paragraphs.

a. *Physical removal.* EPA evaluated eight studies on removal of *Cryptosporidium* by rapid granular filtration for the IESWTR. These were Patania *et al.* (1995), Nieminski and Ongerth (1995), Ongerth and Pecoraro (1995), LeChevallier and Norton (1992), LeChevallier *et al.* (1991), Foundation for Water Research (1994), Kelley *et al.* (1995), and West *et al.* (1994). These studies included both pilot and full scale plants.

Full scale plants in these studies typically demonstrated 2–3 log removal of *Cryptosporidium*, and pilot plants achieved up to almost 6 log removal under optimized conditions. In general, the degree of removal that can be quantified in full scale plants is limited because *Cryptosporidium* levels following filtration are often below the detection limit of the analytical method. Pilot scale studies overcome this limitation by seeding high concentrations of oocysts to the plant influent, but extrapolation of the performance of a pilot plant to the routine performance of full scale plants is uncertain.

Cryptosporidium removal efficiency in these studies was observed to depend on a number of factors including: water matrix, coagulant application, treatment optimization, filtered water turbidity, and the filtration cycle. The highest removal rates were observed in plants that achieved very low effluent turbidities.

EPA also evaluated studies of *Cryptosporidium* removal by slow sand (Schuler and Ghosh 1991, Timms *et al.* 1995) and DE filtration (Schuler and Gosh 1990) for the IESWTR. These studies indicated that a well designed and operated plant using these processes could achieve 3 log or greater removal of *Cryptosporidium*.

After considering these studies, EPA concluded that conventional and direct filtration plants in compliance with the effluent turbidity criteria of the IESWTR, and slow sand and DE plants in compliance with the effluent turbidity criteria established for these processes by the SWTR, would achieve at least 2 log removal of *Cryptosporidium*. Recognizing that many plants will achieve more than the minimum 2 log reduction, EPA estimated median *Cryptosporidium* removal among filtration plants as near 3 log (99.9%) for the purpose of assessing risk.

The LT1ESWTR proposal included summaries of additional studies of *Cryptosporidium* removal by conventional treatment (Dugan *et al.* 1999), direct filtration (Swertfeger *et al.* 1998), and DE filtration (Ongerth and Hutton 1997). These studies supported IESWTR conclusions stated previously regarding the performance of these processes. The LT1ESWTR proposal also summarized studies of membranes, bag filters, and cartridge filters (Jacangelo *et al.* 1995, Drozd and Schartzbrod 1997, Hirata and Hashimoto 1998, Goodrich *et al.* 1995, Collins *et al.* 1996, Lykins *et al.* 1994, Adham *et al.* 1998). This research demonstrated that these technologies may be capable of achieving 2 log or greater removal of *Cryptosporidium*. However, EPA concluded that variation in performance among different manufacturers and models necessitates that determinations of treatment credit be made on a technology-specific basis (65 FR 19065, April 10, 2000) (USEPA 2000b).

b. *Inactivation.* In the IESWTR NODA (62 FR 59486) (USEPA 1997a), EPA cited studies that demonstrated that chlorine is ineffective for inactivation of *Cryptosporidium* at doses practical for treatment plants (Korich *et al.* 1990, Ransome *et al.* 1993, Finch *et al.* 1997). The Agency also summarized studies of *Cryptosporidium* inactivation by UV, ozone, and chlorine dioxide. EPA evaluated these disinfectants to determine if sufficient data were available to develop prescriptive disinfection criteria for *Cryptosporidium*.

The studies of UV disinfection of *Cryptosporidium* that were available during IESWTR development were inconclusive due to methodological factors. These studies included: Lorenzo-Lorenzo *et al.* (1993), Ransome *et al.* (1993), Campbell *et al.* (1995), Finch *et al.* (1997), and Clancy *et al.* (1997). A common limitation among these studies was the use of in vitro assays, such as excystation and vital dye staining, to measure loss of infectivity. These assays subsequently were shown to overestimate the UV dose needed to inactivate protozoa (Clancy *et al.* 1998, Craik *et al.* 2000). In another case, a reactor vessel that blocked germicidal light was used (Finch *et al.* 1997).

EPA evaluated the following studies of ozone inactivation of *Cryptosporidium* for the IESWTR: Peeters *et al.* (1989), Korich *et al.* (1990), Parker *et al.* (1993), Ransome *et al.* (1993), Finch *et al.* (1997), Daniel *et al.* (1993), and Miltner *et al.* (1997). These studies demonstrated that ozone could achieve high levels of *Cryptosporidium*

inactivation, albeit at doses much higher than those required to inactivate *Giardia*. Results of these studies also exhibited significant variability due to factors like different infectivity assays and methods of dose calculation.

The status of chlorine dioxide inactivation of *Cryptosporidium* during IESWTR development was similar to that of ozone. EPA evaluated a number of studies that indicated that relatively high doses of chlorine dioxide could achieve significant inactivation of *Cryptosporidium* (Peeters *et al.* 1989, Korich *et al.* 1990, Ransome *et al.* 1993, Finch *et al.* 1995 and 1997, and LeChevallier *et al.* 1997). Data from these studies showed a high level of variability due to methodological differences, and the feasibility of high chlorine dioxide doses was uncertain due to the MCL for chlorite that was established by the Stage 1 DBPR.

After reviewing these studies, EPA and the Stage 1 Federal Advisory Committee concluded that available data were not adequate to award *Cryptosporidium* inactivation credit for UV, ozone, or chlorine dioxide.

3. New Information on Treatment for Control of *Cryptosporidium*

a. *Conventional filtration treatment and direct filtration.* This section provides brief descriptions of seven recent studies of *Cryptosporidium* removal by conventional treatment and direct filtration, followed by a summary of key points.

Dugan *et al.* (2001) evaluated the ability of conventional treatment to control *Cryptosporidium* under varying water quality and treatment conditions, and assessed turbidity, total particle counts (TPC), and aerobic endospores as indicators of *Cryptosporidium* removal. Fourteen runs were conducted on a small pilot scale plant that had been determined to provide equivalent performance to a larger plant. Under optimal coagulation conditions, oocyst removal across the sedimentation basin ranged from 0.6 to 1.8 log, averaging 1.3 log, and removal across the filters ranged from 2.9 to greater than 4.4 log, averaging greater than 3.7 log. Removal of aerobic spores, TPC, and turbidity all correlated with removal of *Cryptosporidium* by sedimentation, and these parameters were conservative indicators of *Cryptosporidium* removal across filtration. Sedimentation removal under optimal conditions related to raw water quality, with the lowest *Cryptosporidium* removals observed when raw water turbidity was low.

Suboptimal coagulation conditions (underdosed relative to jar test predictions) significantly reduced plant

performance. Oocyst removal in the sedimentation basin averaged 0.2 log, and removal by filtration averaged 1.5 log. Under suboptimal coagulation conditions, low sedimentation removals of *Cryptosporidium* were observed regardless of raw water turbidity.

Nieminski and Bellamy (2000) investigated surrogates as indicators of *Giardia* and *Cryptosporidium* in source water and as measures of treatment plant effectiveness. It involved sampling for microbial pathogens (*Giardia*, *Cryptosporidium*, and enteric viruses), potential surrogates (bacteria, bacteria spores, bacterial phages, turbidity, particles), and other water quality parameters in the source and finished waters of 23 surface water filtration facilities and one unfiltered system.

While *Giardia* and *Cryptosporidium* were found in the majority of source water samples, the investigators could not establish a correlation between either occurrence or removal of these protozoa and any of the surrogates tested. This was attributed, in part, to low concentrations of *Giardia* and *Cryptosporidium* in raw water and high analytical method detection limits. Removal of *Cryptosporidium* and *Giardia* averaged 2.2 and 2.6 log, respectively, when conservatively estimated using detection limits in filtered water. Aerobic spores were found in 85% of filtered water samples and were considered a measure of general treatment effectiveness. Average reduction of aerobic spores was 2.84 log. Direct filtration plants removed fewer aerobic spores than conventional or softening plants.

McTigue *et al.* (1998) conducted an on-site survey of 100 treatment plants for particle counts, pathogens (*Cryptosporidium* and *Giardia*), and operational information. The authors also performed pilot scale spiking studies. Median removal of particles greater than 2 mm was 2.8 log, with values ranging from 0.04 to 5.5 log. Removal generally increased with increasing raw water particle concentration. Results were consistent with previously collected data. *Cryptosporidium* and *Giardia* were found in the majority of raw water sources, but calculation of their log removal was limited by the concentration present. River sources had a higher incidence of pathogen occurrence. Direct filtration plants had higher levels of pathogens in the filtered water than others in the survey.

Nearly all of the filter runs evaluated in the survey exhibited spikes where filtered water particle counts increased, and pilot work showed that pathogens are more likely to be released during

these spike events. *Cryptosporidium* removal in the pilot scale spiking study averaged nearly 4 log, regardless of the influent oocyst concentration. Pilot study results indicated a strong relationship between removal of *Cryptosporidium* and removal of particles (> 3 µm) during runs using optimal coagulation and similar temperatures.

Patania *et al.* (1999) evaluated removal of *Cryptosporidium* at varied raw water and filter effluent turbidity levels using direct filtration. Runs were conducted with both low (2 NTU) and high (10 NTU) raw water turbidity. Targeted filtered water turbidity was either 0.02 or 0.05 NTU. At equivalent filtered water turbidity, *Cryptosporidium* removal was slightly higher when the raw water turbidity was higher. Also, *Cryptosporidium* removal was enhanced by an average of 1.5 log when steady-state filtered water turbidity was 0.02 NTU compared to 0.05 NTU.

Huck *et al.* (2000) evaluated filtration efficiency during optimal and suboptimal coagulation conditions with two pilot scale filtration plants. One plant employed a high coagulation dose for both total organic carbon (TOC) and particle removal, and the second plant used a low dose intended for particle removal only. Under optimal operating conditions, which were selected to achieve filtered water turbidity below 0.1 NTU, median *Cryptosporidium* removal was 5.6 log at the high coagulant dose plant and 3 log at the low dose plant. Under suboptimal coagulation conditions, where the coagulant dose was reduced to achieve filtered water turbidity of 0.2 to 0.3 NTU, median *Cryptosporidium* removals dropped to 3.2 log and 1 log at the high dose and low dose plants, respectively. Oocyst removal also decreased substantially at the end of the filter cycle, although this was not always indicated by an increase in turbidity. Runs conducted with no coagulant resulted in very little *Cryptosporidium* removal.

Emelko *et al.* (2000) investigated *Cryptosporidium* removal during vulnerable filtration periods using a pilot scale direct filtration system. The authors evaluated four different operational conditions: stable, early breakthrough, late breakthrough, and end of run. During stable operation, effluent turbidity was approximately 0.04 NTU and *Cryptosporidium* removal ranged from 4.7 to 5.8 log. In the early breakthrough period, effluent turbidity increased from approximately 0.04 to 0.2 NTU, and *Cryptosporidium* removal decreased significantly, averaging 2.1

log. For the late breakthrough period, where effluent turbidity began at approximately 0.25 NTU and ended at 0.35 NTU, *Cryptosporidium* removal dropped to an average of 1.4 log. Two experiments tested *Cryptosporidium* removal during the end-of-run operation, when effluent turbidities generally start increasing. Turbidity started at about 0.04 NTU for both experiments and ended at 0.06 NTU for the first experiment and 0.13 NTU for the second. Reported *Cryptosporidium* removal ranged from 1.8 to 3.3 log, with an average of 2.5 log for both experiments.

Harrington *et al.* (2001) studied the removal of *Cryptosporidium* and emerging pathogens by filtration, sedimentation, and dissolved air flotation (DAF) using bench scale jar tests and pilot scale conventional treatment trains. In the bench scale experiments, all run at optimized coagulant doses, mean log removal of *Cryptosporidium* was 1.2 by sedimentation and 1.7 by DAF. *Cryptosporidium* removal was similar in all four water sources that were evaluated and was not significantly affected by lower pH or coagulant aid addition. However, removal of *Cryptosporidium* was greater at 22°C than at 5°C, and was observed to be higher with alum coagulant than with either polyaluminum hydroxychlorosulfate or ferric chloride.

In the pilot scale experiments, mean log removal of *Cryptosporidium* was 1.9 in filtered water with turbidity of 0.2 NTU or less. Removal increased as filtered water turbidity dropped below 0.3 NTU. There was no apparent effect of filtration rate on removal efficiency. In comparing *Cryptosporidium* removal by sand, dual media (anthracite/sand), and trimedia (anthracite/sand/garnet) filters, no difference was observed near neutral pH. However, at pH 5.7, removal increased significantly in the sand filter and it outperformed the other filter media configurations. The authors found no apparent explanation for this behavior. There was no observable effect of a turbidity spike on *Cryptosporidium* removal.

Significance of Conventional and Direct Filtration Studies

The performance of treatment plants under current regulations is a significant factor in determining the need for additional treatment. As described in section IV.A, the proposed *Cryptosporidium* treatment requirements associated with LT2ESWTR risk bins for filtered systems are based, in part, on an estimate that conventional plants in compliance with

the IESWTR achieve an average of 3 log *Cryptosporidium* removal. The following discussion illustrates why EPA believes that available data support this estimate.

While *Cryptosporidium* removal at full scale plants is difficult to quantify due to limitations with analytical methods, pilot scale studies show that reductions in aerobic spores and total particle counts are often conservative indicators of filtration plant removal efficiency for *Cryptosporidium* (Dugan *et al.* 2001, McTigue *et al.* 1998, Yates *et al.* 1998, Emelko *et al.* 1999 and 2000). Surveys of full scale plants have reported average reductions near 3 log for both aerobic spores (Niemiński and Bellamy, 2000) and total particle counts (McTigue *et al.* 1998). Consequently, these findings are consistent with an estimate that average removal of *Cryptosporidium* by filtration plants is approximately 3 log.

Pilot scale *Cryptosporidium* spiking studies (Dugan *et al.* 2001, Huck *et al.* 2000, Emelko *et al.* 2000, McTigue *et al.* 1998, Patania *et al.* 1995) suggest that a conventional treatment plant has the potential to achieve greater than 5 log removal of *Cryptosporidium* under optimal conditions. However, these high removals are typically observed at very low filter effluent turbidity values, and the data show that removal efficiency can decrease substantially over the course of a filtration cycle or if coagulation is not optimized (Dugan *et al.* 2001, Huck *et al.* 2000, Emelko *et al.* 2000, Harrington *et al.* 2001). Removal efficiency also appears to be impacted by source water quality (Dugan *et al.* 2001, McTigue *et al.* 1998). Given these considerations, EPA believes that 3 log is a reasonable estimate of average *Cryptosporidium* removal efficiency for conventional treatment plants in compliance with the IESWTR or LT1ESWTR.

The Stage 2 M-DBP Advisory Committee did not address direct filtration plants, which lack the sedimentation basin of a conventional treatment train, but recommended that EPA address these plants in the LT2ESWTR proposal (65 FR 83015, December 29, 2000) (USEPA 2000a). While some studies have observed similar levels of *Cryptosporidium* removal in direct and conventional filtration plants (Niemiński and Ongerth, 1995, Ongerth and Pecoraro 1995), EPA has concluded that the majority of available data support a lower estimate of *Cryptosporidium* removal efficiency for direct filtration plants.

As described in section IV.C.5, pilot and full scale studies demonstrate that

sedimentation basins, which are absent in direct filtration, can achieve 0.5 log or greater *Cryptosporidium* reduction (Dugan *et al.* 2001, Patania *et al.* 1995, Edzwald and Kelly 1998, Payment and Franco 1993, Kelley *et al.* 1995). In addition, Patania *et al.* (1995) observed direct filtration to achieve less *Cryptosporidium* removal than conventional treatment, and McTigue *et al.* (1998) found a higher incidence of *Cryptosporidium* in the treated water of direct filtration plants. Given these findings, EPA has estimated that direct filtration plants achieve an average of 2.5 log *Cryptosporidium* reduction (*i.e.*, 0.5 log less than conventional treatment).

i. Dissolved air flotation. Dissolved air flotation (DAF) is a solid-liquid separation process that can be used in conventional treatment trains in place of gravity sedimentation. DAF takes advantage of the buoyancy of oocysts by floating oocyst/particle complexes to the surface for removal. In DAF, air is dissolved in pressurized water, which is then released into a flotation tank containing flocculated particles. As the water enters the tank, the dissolved air forms small bubbles that collide with and attach to floc particles and float to the surface (Gregory and Zabel, 1990).

In comparing DAF with gravity sedimentation, Plummer *et al.* (1995) observed up to 0.81 log removal of oocysts in the gravity sedimentation process, while DAF achieved 0.38 to 3.7 log removal, depending on coagulant dose. Edzwald and Kelley (1998) demonstrated a 3 log removal of oocysts using DAF, compared with a 1 log removal using gravity sedimentation in the clarification process before filtration. In bench scale testing by Harrington *et al.* (2001), DAF averaged 0.5 log higher removal of *Cryptosporidium* than gravity sedimentation. Based on these results, EPA has concluded that a treatment plant using DAF plus filtration can achieve levels of *Cryptosporidium* removal equivalent to or greater than a conventional treatment plant with gravity sedimentation.

b. *Slow sand filtration.* Slow sand filtration is a process involving passage of raw water through a bed of sand at low velocity (generally less than 0.4 m/h) resulting in substantial particulate removal by physical and biological mechanisms. For the LT2ESWTR proposal, EPA has reviewed two additional studies of slow sand filtration.

Fogel *et al.* (1993) evaluated removal efficiencies for *Cryptosporidium* and *Giardia* with a full scale slow sand filtration plant. The removals ranged

from 0.1–0.5 log for *Cryptosporidium* and 0.9–1.4 log for *Giardia*. Raw water turbidity ranged from 1.3 to 1.6 NTU and decreased to 0.35–0.31 NTU after filtration. The authors attributed the low *Cryptosporidium* and *Giardia* removals to the relatively poor grade of filter media and lower water temperature. The sand had a higher uniformity coefficient than recommended by design standards. This creates larger pore spaces within the filter bed that retard biological removal capacity. Lower water temperatures (1 °C) also decreased biological activity in the filter media.

Hall *et al.* (1994) examined the removal of *Cryptosporidium* with a pilot scale slow sand filtration plant. *Cryptosporidium* removals ranged from 2.8 to 4.3 log after filter maturation, with an average of 3.8 log (at least one week after filter scraping). Raw water turbidity ranged from 3.0 NTU to 7.5 NTU for three of four runs and 15.0 NTU for a fourth run. Filtered water turbidity was 0.2 to 0.4 NTU, except for the fourth run which had 2.5 NTU filtered water turbidity. This study also included an investigation of *Cryptosporidium* removal during filter start-up where the filtration rate was slowly increased over a 4 day period. Results indicate that filter ripening did not appear to affect *Cryptosporidium* removal.

The study by Fogel *et al.* is significant because it indicates that a slow sand filtration plant may achieve less than 2 log removal of *Cryptosporidium* removal while being in compliance with the effluent turbidity requirements of the IESWTR and LT1ESWTR. The authors attributed this poor performance to the filter being improperly designed, which, if correct, illustrates the importance of proper design for removal efficiency in slow sand filters. In contrast, the study by Hall *et al.* (1994) supports other work (Schuler and Ghosh 1991, Timms *et al.* 1995) in finding that slow sand filtration can achieve *Cryptosporidium* removal greater than 3 log. Overall, this body of work appears to show that slow sand filtration has the potential to achieve *Cryptosporidium* removal efficiencies similar to that of a conventional plant, but proper design and operation are critical to realizing treatment goals.

c. *Diatomaceous earth filtration.* Diatomaceous earth filtration is a process in which a precoat cake of filter media is deposited on a support membrane and additional filter media is continuously added to the feed water to maintain the permeability of the filter cake. Since the IESWTR and LT1ESWTR, EPA has reviewed one new study of DE filtration (Ongerth and Hutton 2001). It supports the findings of

earlier studies (Schuler and Gosh 1990, Ongerth and Hutton 1997) in showing that a well designed and operated DE plant can achieve *Cryptosporidium* removal equivalent to a conventional treatment plant (*i.e.*, average of 3 log).

d. *Other filtration technologies.* In today's proposal, information about bag filters, cartridge filters, and membranes, including criteria for awarding *Cryptosporidium* treatment credit, is presented in section IV.C as part of the microbial toolbox. Section IV.C also addresses credit for pretreatment options like presedimentation basins and bank filtration.

e. *Inactivation.* Substantial advances in understanding of *Cryptosporidium* inactivation by ozone, chlorine dioxide, and UV have been made following the IESWTR and LT1ESWTR. These advances have allowed EPA to develop criteria to award *Cryptosporidium* treatment credit for these disinfectants. Relevant information is summarized next, with additional information sources noted.

i. Ozone and chlorine dioxide. With the completion of several major studies, EPA has acquired sufficient information to develop standards for the inactivation of *Cryptosporidium* by ozone and chlorine dioxide. For both of these disinfectants, today's proposal includes CT tables that specify a level of *Cryptosporidium* treatment credit based on the product of disinfectant concentration and contact time.

For ozone, the CT tables in today's proposal were developed through considering four sets of experimental data: Li *et al.* (2001), Owens *et al.* (2000), Oppenheimer *et al.* (2000), and Rennecker *et al.* (1999). Chlorine dioxide CT tables are based on three experimental data sets: Li *et al.* (2001), Owens *et al.* (1999), and Ruffell *et al.* (2000). Together these studies provide a large body of data that covers a range of water matrices, both laboratory and natural. While the data exhibit variability, EPA believes that collectively they are sufficient to determine appropriate levels of

treatment credit as a function of disinfection conditions. CT tables for ozone and chlorine dioxide inactivation of *Cryptosporidium* are presented in Section IV.C.14 of this preamble.

ii. Ultraviolet light. A major recent development is the finding that UV light is highly effective for inactivating *Cryptosporidium* and *Giardia* at low doses. Research prior to 1998 had indicated that very high doses of UV light were required to achieve substantial disinfection of protozoa. However, as noted previously, these results were largely based on the use of in vitro assays, which were later shown to substantially overestimate the UV doses required to prevent infection (Clancy *et al.* 1998, Bukhari *et al.* 1999, Craik *et al.* 2000). Recent research using in vivo assays (*e.g.*, neonatal mouse infectivity) and cell culture techniques to measure infectivity has provided strong evidence that both *Cryptosporidium* and *Giardia* are highly sensitive to low doses of UV.

BILLING CODE 6560-50-P

for *Cryptosporidium* in future rulemaking (62 FR 59498, November 3, 1997) (USEPA 2000b). The CT tables for ozone and chlorine dioxide provide such criteria. In addition, the availability of UV furnishes another relatively low cost tool to achieve *Cryptosporidium* inactivation and DBP control.

While no single treatment technology is appropriate for all systems, EPA believes that these disinfectants, along with the other management and treatment options in the microbial toolbox presented in section IV.C, make it feasible for systems to meet the additional *Cryptosporidium* treatment requirements in today's proposal.

IV. Discussion of Proposed LT2ESWTR Requirements

A. Additional *Cryptosporidium* Treatment Technique Requirements for Filtered Systems

1. What Is EPA Proposing Today?

a. *Overview of framework approach.* EPA is proposing treatment technique requirements to supplement the existing requirements of the SWTR, IESWTR, and LT1ESWTR (see section II.B). The proposed requirements will achieve increased protection against *Cryptosporidium* in public water systems that use surface water or ground water under the direct influence of surface water as sources. Under this proposal, filtered systems will be assigned to one of four risk categories (or "bins"), based on the results of source water *Cryptosporidium* monitoring. Systems assigned to the lowest risk bin incur no additional treatment requirements, while systems assigned to higher risk bins must reduce *Cryptosporidium* levels beyond IESWTR and LT1ESWTR requirements. Systems will comply with additional *Cryptosporidium* treatment requirements by selecting treatment and management strategies from a "microbial toolbox" of control options.

Today's proposal reflects recommendations from the Stage 2 M-

DBP Federal Advisory Committee (65 FR 83015, December 29, 2000) (USEPA 2000a), which described this approach as a "microbial framework". This approach targets additional treatment requirements to those systems with the highest source water *Cryptosporidium* levels and, consequently, the highest vulnerability to this pathogen. In so doing, today's proposal builds upon the current treatment technique requirement for *Cryptosporidium* under which all filtered systems must achieve at least a 2 log reduction, regardless of source water quality. The intent of this proposal is to assure that public water systems with the higher risk source water achieve a level of public health protection commensurate with systems with less contaminated source water.

b. *Monitoring requirements.* Today's proposal requires systems to monitor their source water (influent water prior to treatment plant) for *Cryptosporidium*, *E. coli*, and turbidity. The purpose of the monitoring is to assess source water *Cryptosporidium* levels and, thereby, classify systems in different risk bins. Proposed monitoring requirements for large and small systems are summarized in Table IV-1 and are characterized in the following discussion.

Large Systems

Large systems (serving at least 10,000 people) must sample their source water at least monthly for *Cryptosporidium*, *E. coli*, and turbidity for a period of 2 years, beginning no later than 6 months after LT2ESWTR promulgation. Systems may sample more frequently (e.g., twice-per-month, once-per-week), provided the same sampling frequency is used throughout the 2-year monitoring period. As described in section IV.A.1.c, systems that sample more frequently (at least twice-per-month) use a different calculation that is potentially less conservative to determine their bin classification.

The purpose of requiring large systems to collect *E. coli* and turbidity data is to further evaluate these parameters as indicators to identify

drinking water sources that are susceptible to high concentrations of *Cryptosporidium*. As described next, these data will be applied to small system LT2ESWTR monitoring.

Small Systems

EPA is proposing a 2-phase monitoring strategy for small systems (serving fewer than 10,000 people) to reduce their monitoring burden. This approach is based on Information Collection Rule and ICRSS data indicating that systems with low source water *E. coli* levels are likely to have low *Cryptosporidium* levels, such that additional treatment would not be required under the LT2ESWTR. Under this approach, small systems must initially conduct one year of bi-weekly sampling (one sample every two weeks) for *E. coli*, beginning 2.5 years after LT2ESWTR promulgation. Small systems are triggered into *Cryptosporidium* monitoring only if the initial *E. coli* monitoring indicates a mean concentration greater than 10 *E. coli*/100 mL for systems using a reservoir or lake as their primary source or greater than 50 *E. coli*/100 mL for systems using a flowing stream as their primary source. Small systems that exceed these *E. coli* trigger values must conduct one year of twice-per-month *Cryptosporidium* sampling, beginning 4 years after LT2ESWTR promulgation.

The analysis supporting the proposed *E. coli* values that trigger *Cryptosporidium* monitoring by small systems is presented in Section IV.A.2. However, as recommended by the Stage 2 M-DBP Advisory Committee, EPA will evaluate *Cryptosporidium* indicator relationships in the LT2ESWTR monitoring data collected by large systems. If these data support the use of different indicator levels to trigger small system *Cryptosporidium* monitoring, EPA will issue guidance with recommendations. The proposed LT2ESWTR allows States to specify alternative indicator values for small systems, based on EPA guidance.

TABLE IV-1.—LT2ESWTR MONITORING REQUIREMENTS

Public water systems	Monitoring begins	Monitoring duration	Monitoring parameters and sample frequency requirements		
			<i>Cryptosporidium</i>	<i>E. coli</i>	Turbidity
Large systems (serving 10,000 or more people).	6 months after promulgation of LT2ESWTR ^a .	2 years	minimum 1 sample/month ^b .	minimum 1 sample/month ^b .	minimum 1 measurement/month ^b .
Small systems (serving fewer than 10,000 people).	30 months (2½ years) after promulgation of LT2ESWTR.	1 year	See following rows	1 sample every two weeks.	N/A

TABLE IV-1.—LT2ESWTR MONITORING REQUIREMENTS—Continued

Public water systems	Monitoring begins	Monitoring duration	Monitoring parameters and sample frequency requirements		
			<i>Cryptosporidium</i>	<i>E. coli</i>	Turbidity
Possible additional monitoring requirement for <i>Cryptosporidium</i> . If small systems exceed <i>E. coli</i> trigger levels ^c , then * * *					
Small systems (serving fewer than 10,000 people) ^c .	48 months (4 years) after promulgation of LT2ESWTR.	1 year	2 samples/month	N/A	N/A.

^aPublic water systems may use equivalent previously collected (grandfathered) data to meet LT2ESWTR requirements. See section IV.A.1.d for details.

^bPublic water systems may sample more frequently (e.g., twice-per-month, once-per-week).

^cSmall systems must monitor for *Cryptosporidium* for one year, beginning 6 months after completion of *E. coli* monitoring, if the *E. coli* annual mean concentration exceeds 10/100 mL for systems using lakes/reservoir sources or 50/100 mL for systems using flowing stream sources.

N/A = Not applicable. No monitoring required.

Sampling Location

Source water samples must be representative of the intake to the filtration plant. Generally, sampling must be performed individually for each plant that treats a surface water source. However, where multiple plants receive all of their water from the same influent (e.g., multiple plants draw water from the same pipe), the same set of monitoring results may be applicable to each plant. Typically, samples must be collected prior to any treatment, with exceptions for certain pretreatment processes. Directions on sampling location for plants using off-stream storage, presedimentation, and bank filtration are provided in section IV.C.

Systems with plants that use multiple water sources at the same time must collect samples from a tap where the sources are combined prior to treatment if available. If a blended source tap is not available, systems must collect samples from each source and either analyze a weighted composite (blended) sample or analyze samples from each source separately and determine a weighted average of the results.

Sampling Schedule

Large systems must submit a sampling schedule to EPA within 3 months after promulgation of the LT2ESWTR. Small systems must submit a sampling schedule for *E. coli* monitoring to their primacy agency within 27 months after rule promulgation; small systems required to monitor for *Cryptosporidium* must submit a *Cryptosporidium* sampling schedule within 45 months after promulgation. The sampling schedules must specify the calendar date on which the system will collect each sample required under the LT2ESWTR. Scheduled sampling dates should be evenly distributed throughout the monitoring period, but may be arranged to accommodate holidays, weekends, and other events when

collecting or analyzing a sample would be problematic.

Systems must collect samples within 2 days before or 2 days after a scheduled sampling date. If a system does not sample within this 5-day window, the system will incur a monitoring violation unless either of the following two conditions apply:

(1) If extreme conditions or situations exist that may pose danger to the sample collector, or which are unforeseen or cannot be avoided and which cause the system to be unable to sample in the required time frame, the system must sample as close to the required date as feasible and submit an explanation for the alternative sampling date with the analytical results.

(2) Systems that are unable to report a valid *Cryptosporidium* analytical result for a scheduled sampling date due to failure to comply with analytical method quality control requirements (described in section IV.K) must collect a replacement sample within 14 days of being notified by the laboratory or the State that a result cannot be reported for that date. Systems must submit an explanation for the replacement sample with the analytical results. Where possible, the replacement sample collection date should not coincide with any other scheduled LT2ESWTR sampling dates.

Approved Analytical Methods and Laboratories

To ensure the quality of LT2ESWTR monitoring data, today's proposal requires systems to use approved methods for *Cryptosporidium*, *E. coli*, and turbidity analyses (see section IV.K for sample analysis requirements), and to have these analyses performed by approved laboratories (described in section IV.L).

Reporting

Because source water monitoring by large systems will begin 6 months after promulgation of the LT2ESWTR, EPA is proposing that monitoring results for large systems be reported directly to the Agency through an electronic data system (described in section IV.J),

similar to the approach currently used under the Unregulated Contaminants Monitoring Rule (64 FR 50555, September 17, 1999) (USEPA 1999c). Small systems will report data to EPA or States, depending on whether States have assumed primacy for the LT2ESWTR.

Previously Collected Monitoring Results

EPA is proposing to allow systems to use previously collected (i.e., grandfathered) *Cryptosporidium* monitoring data to meet LT2ESWTR monitoring requirements if the data are equivalent to data that will be collected under the rule (e.g., sample volume, sampling frequency, analytical method quality control). Criteria for acceptance of previously collected data are specified in section IV.A.1.d.

Providing Additional Treatment Instead of Monitoring

Filtered systems are not required to conduct source water monitoring under the LT2ESWTR if the system currently provides or will provide a total of at least 5.5 log of treatment for *Cryptosporidium*, equivalent to meeting the treatment requirements of Bin 4 as shown in Table IV-4 (i.e., the maximum required in today's proposal). Systems must notify EPA or the State not later than the date the system is otherwise required to submit a sampling schedule for monitoring and must install and operate technologies to provide a total of at least 5.5 log of treatment for *Cryptosporidium* by the applicable date in Table IV-23. Any filtered system that fails to complete LT2ESWTR monitoring requirements must meet the treatment requirements for Bin 4.

Ongoing Source Assessment and Second Round of Monitoring

Because LT2ESWTR treatment requirements are related to the degree of source water contamination, today's proposal contains provisions to assess changes in a system's source water

quality following initial risk bin classification. These provisions include source water assessment during sanitary surveys and a second round of monitoring.

Under 40 CFR 142.16(b)(3)(i), source water is one of the components that States must address during the sanitary surveys that are required for surface water systems. These sanitary surveys must be conducted every 3 years for community systems and every 5 years for non-community systems. EPA is proposing that if the State determines during the sanitary survey that significant changes have occurred in the watershed that could lead to increased contamination of the source water, the State may require systems to implement specific actions to address the contamination. These actions include implementing options from the microbial toolbox discussed in section IV.C.

EPA is proposing that systems conduct a second round of source water monitoring, beginning six years after systems are initially classified in LT2ESWTR risk bins. To prepare for this second round of monitoring, the Advisory Committee recommended that EPA initiate a stakeholder process four years after large systems complete initial bin classification. The purpose of the stakeholder process would be to review risk information, and to determine the appropriate analytical method, monitoring frequency, monitoring location, and other criteria for the second round of monitoring.

If EPA does not modify LT2ESWTR requirements through issuing a new regulation prior to the second round of monitoring, systems must carry out this monitoring according to the requirements that apply to the initial round of source water monitoring. Moreover, systems will be reclassified in LT2ESWTR risk bins based on the second round monitoring results and using the criteria specified in this section for initial bin classification. However, if EPA changes the LT2ESWTR risk bin structure to reflect a new analytical method or new risk information, systems will undergo a site specific risk characterization in accordance with the revised rule.

c. Treatment Requirements

i. Bin classification. Under the proposed LT2ESWTR, surface water systems that use filtration will be classified in one of four *Cryptosporidium* concentration categories (bins) based on the results of source water monitoring. As shown in Table IV-2, bin classification is determined by averaging the

Cryptosporidium concentrations measured for individual samples.

TABLE IV-2.— BIN CLASSIFICATION TABLE FOR FILTERED SYSTEMS

If your average <i>Cryptosporidium</i> concentration ¹ is . . .	Then your bin classification is . . .
<i>Cryptosporidium</i> <0.075/L 0.075/L ≤ <i>Cryptosporidium</i> < 1.0/L.	Bin 1. Bin 2.
1.0/L ≤ <i>Cryptosporidium</i> < 3.0/L.	Bin 3.
<i>Cryptosporidium</i> ≥ 3.0/L ...	Bin 4.

¹All concentrations shown in units of oocysts/L

The approach that systems will use to average individual sample concentrations to determine their bin classification depends on the number of samples collected and the length of the monitoring period. Systems serving at least 10,000 people are required to monitor for 24 months, and their bin classification must be based on the following:

- (1) Highest twelve month running annual average for monthly sampling, or
- (2) two year mean if system conducts twice-per-month or more frequent sampling for 24 months (*i.e.*, at least 48 samples).

Systems serving fewer than 10,000 people are required to collect 24 *Cryptosporidium* samples over 12 months if they exceed the *E. coli* trigger level, and their bin classification must be based on the mean of the 24 samples. As noted earlier, systems that fail to complete the required *Cryptosporidium* monitoring will be classified in Bin 4.

When determining LT2ESWTR bin classification, systems must calculate individual sample concentrations using the total number of oocysts counted, unadjusted for method recovery, divided by the volume assayed (see section IV.K for details). As described in Section IV.A.2, the ranges of *Cryptosporidium* concentrations that define LT2ESWTR bins reflect consideration of analytical method recovery and the percent of *Cryptosporidium* oocysts that are infectious. Consequently, sample analysis results will not be adjusted for these factors.

ii. Credit for treatment in place. A key parameter in determining additional *Cryptosporidium* treatment requirements is the credit that plants receive for treatment currently provided (*i.e.*, treatment in place). For baseline treatment requirements established by the SWTR, IESWTR, and LT1ESWTR that apply uniformly to filtered systems, the Agency has awarded credit based on

the minimum removal that plants will achieve. Specifically, in the IESWTR and LT1ESWTR, EPA determined that filtration plants, including conventional, direct, slow sand, and DE, meeting the required filter effluent turbidity criteria will achieve at least 2 log removal of *Cryptosporidium*. Consequently, these plants were awarded a 2 log *Cryptosporidium* removal credit, which equals the maximum treatment required under these regulations.

The LT2ESWTR will supplement existing regulations by mandating additional treatment at certain plants based on site specific conditions (*i.e.*, source water *Cryptosporidium* level). When assessing the need for additional treatment beyond baseline requirements for higher risk systems, the Agency has determined that it is appropriate to consider the average removal efficiency achieved by treatment plants. As described in section III.D, EPA has concluded that conventional, slow sand, and DE plants in compliance with the SWTR, IESWTR, and LT1ESWTR achieve an average *Cryptosporidium* reduction of 3 log. Consequently, EPA is proposing to award these plants a 3 log credit towards *Cryptosporidium* treatment requirements under the LT2ESWTR. As noted previously, this approach is consistent with the Stage 2 M-DBP Agreement in Principle.

For other types of filtration plants, treatment credit under the LT2ESWTR differs. Conventional treatment is defined in 40 CFR 141.2 as a series of processes including coagulation, flocculation, sedimentation, and filtration, with sedimentation defined as a process for removal of solids before filtration by gravity or separation. Thus, plants with separation (*i.e.*, clarification) processes other than gravity sedimentation between flocculation and filtration, such as DAF, may be regarded as conventional treatment for purposes of awarding treatment credit under the LT2ESWTR. However, for direct filtration plants, which lack a sedimentation process, EPA is proposing a 2.5 log *Cryptosporidium* removal credit. Studies that support awarding direct filtration plants less treatment credit than conventional plants are summarized in section III.D.

EPA is unable to estimate an average log removal for other filtration technologies like membranes, bag filters, and cartridge filters, due to variability among products. As a result, credit for these devices must be determined by the State, based on product specific testing described in section IV.C or other criteria approved by the State.

Table IV-3 presents the credit proposed for different types of plants towards LT2ESWTR *Cryptosporidium* treatment requirements. As described in section IV.C.18, a State may award greater credit to a system that

demonstrates through a State-approved protocol that it reliably achieves a higher level of *Cryptosporidium* removal. Conversely, a State may award less credit to a system where the State determines, based on site specific

information, that the system is not achieving the degree of *Cryptosporidium* removal indicated in Table IV-3.

TABLE IV-3.—*Cryptosporidium* TREATMENT CREDIT TOWARDS LT2ESWTR REQUIREMENTS ¹

Plant type	Conventional treatment (includes softening)	Direct filtration	Slow sand or diatomaceous earth filtration	Alternative filtration technologies
Treatment credit	3.0 log	2.5 log	3.0 log	Determined by State ² .

¹ Applies to plants in full compliance with the SWTR, IESWTR, and LT1ESWTR as applicable
² Credit must be determined through product or site specific assessment

iii. Treatment requirements associated with LT2ESWTR bins
 The treatment requirements associated with LT2ESWTR risk bins are shown in Table IV-4. The total *Cryptosporidium* treatment required for Bins 2, 3, and 4 is 4.0 log, 5.0 log, and 5.5 log, respectively. For conventional (including softening), slow sand, and DE plants that receive 3.0 log credit for

compliance with current regulations, additional *Cryptosporidium* treatment of 1.0 to 2.5 log is required when classified in Bins 2-4. Direct filtration plants that receive 2.5 log credit for compliance with current regulations must achieve 1.5 to 3.0 log of additional *Cryptosporidium* treatment in Bins 2-4. For systems using alternative filtration technologies, such as

membranes or bag/cartridge filters, and classified in Bins 2-4, the State must determine additional treatment requirements based on the credit awarded to a particular technology. The additional treatment must be such that plants classified in Bins 2, 3, and 4 achieve the total required *Cryptosporidium* reductions of 4.0, 5.0, and 5.5 log, respectively.

TABLE IV-4.—TREATMENT REQUIREMENTS PER LT2ESWTR BIN CLASSIFICATION

If your bin classification is . . .	And you use the following filtration treatment in full compliance with the SWTR, IESWTR, and LT1ESWTR (as applicable), then your additional treatment requirements are . . .			
	Conventional filtration treatment (includes softening)	Direct filtration	Slow sand or diatomaceous earth filtration	Alternative filtration technologies
Bin 1	No additional treatment	No additional treatment	No additional treatment	No additional treatment.
Bin 2	1 log treatment ¹	1.5 log treatment ¹	1 log treatment ¹	As determined by the State ^{1,3} .
Bin 3	2 log treatment ²	2.5 log treatment ²	2 log treatment ²	As determined by the State ^{2,4} .
Bin 4	2.5 log treatment ²	3 log treatment ²	2.5 log treatment ²	As determined by the State ^{2,5} .

¹ Systems may use any technology or combination of technologies from the microbial toolbox.
² Systems must achieve at least 1 log of the required treatment using ozone, chlorine dioxide, UV, membranes, bag/cartridge filters, or bank filtration.
³ Total *Cryptosporidium* removal and inactivation must be at least 4.0 log.
⁴ Total *Cryptosporidium* removal and inactivation must be at least 5.0 log.
⁵ Total *Cryptosporidium* removal and inactivation must be at least 5.5 log.

Plants can achieve additional *Cryptosporidium* treatment credit through implementing pretreatment processes like presedimentation or bank filtration, by developing a watershed control program, and by applying additional treatment steps like UV, ozone, chlorine dioxide, and membranes. In addition, plants can receive additional credit for existing treatment through achieving very low filter effluent turbidity or through a demonstration of performance. Section IV.C presents criteria for awarding *Cryptosporidium* treatment credit to a host of treatment and control options, including those listed here and others, which are collectively termed the “microbial toolbox”.

Systems in Bin 2 can meet additional *Cryptosporidium* treatment requirements through using any option or combination of options from the microbial toolbox. In Bins 3 and 4, systems must achieve at least 1 log of the additional treatment requirement through using ozone, chlorine dioxide, UV, membranes, bag filtration, cartridge filtration, or bank filtration.
 d. *Use of previously collected data.* Today’s proposal allows systems with previously collected *Cryptosporidium* data (i.e., data collected prior to the required start of monitoring under the LT2ESWTR) that are equivalent in sample number, frequency, and data quality to data that will be collected under the LT2ESWTR to use those data in lieu of conducting new monitoring.

Specifically, EPA is proposing that *Cryptosporidium* sample analysis results collected prior to promulgation of the LT2ESWTR must meet the following criteria to be used for bin classification:

- Samples were analyzed by laboratories using validated versions of EPA Methods 1622 or 1623 and meeting the quality control criteria specified in these methods (USEPA 1999a, USEPA 1999b, USEPA 2001e, USEPA 2001f).
- Samples were collected no less frequently than each calendar month on a regular schedule, beginning no earlier than January 1999 (when EPA Method 1622 was first released as an interlaboratory-validated method).
- Samples were collected in equal intervals of time over the entire collection period (e.g., weekly,

monthly). The allowances for deviations from a sampling schedule specified under IV.A.1.b for LT2ESWTR monitoring apply to grandfathered data.

- Samples were collected at the correct location as specified for LT2ESWTR monitoring. Systems must report the use of bank filtration, presedimentation, and raw water off-stream storage during sampling.

- For each sample, the laboratory analyzed at least 10 L of sample or at least 2 mL of packet pellet volume or as much volume as two filters could accommodate before clogging (applies only to filters that have been approved by EPA for use with Methods 1622 and 1623).

- The system must certify that it is reporting all *Cryptosporidium* monitoring results generated by the system during the time period covered by the previously collected data. This applies to samples that were (a) collected from the sampling location used for LT2ESWTR monitoring, (b) not spiked, and (c) analyzed using the laboratory's routine process for Method 1622 or 1623 analyses.

- The system must also certify that the samples were representative of a plant's source water(s) and the source water(s) have not changed.

If a system has at least two years of *Cryptosporidium* data collected before promulgation of the LT2ESWTR and the system does not intend to conduct new monitoring under the rule, the system must submit the data and the required supporting documentation to EPA no later than two months following promulgation of the rule. EPA will notify the system within four months following LT2ESWTR promulgation as to whether the data are sufficient for bin determination. Unless EPA notifies the system in writing that the previously collected data are sufficient for bin determination, the system must conduct source water *Cryptosporidium* monitoring as described in section IV.A.1.b of this preamble.

If a system intends to grandfather fewer than two years of *Cryptosporidium* data, or if a system intends to grandfather 2 or more years of previously collected data and also to conduct new monitoring under the rule, the system must submit the data and the required supporting documentation to EPA no later than eight months following promulgation of the rule. Systems must conduct monitoring as described in section IV.A.1.b until EPA notifies the system in writing that it has at least 2 years of acceptable data. See section IV.J for additional information on reporting requirements associated with previously collected data.

2. How Was This Proposal Developed?

The monitoring and treatment requirements for filtered systems proposed under the LT2ESWTR stem from the data and analyses described in this section and reflect recommendations made by the Stage 2 M-DBP Federal Advisory Committee (65 FR 83015) (USEPA 2000a).

a. *Basis for targeted treatment requirements.* Under the IESWTR, EPA established an MCLG of zero for *Cryptosporidium* at the genus level based on the public health risk associated with this pathogen. The IESWTR included a 2 log treatment technique requirement for medium and large filtered systems that controlled for *Cryptosporidium* as close to the MCLG as was then deemed technologically feasible, taking costs into consideration. The LT1ESWTR extended this requirement to small systems. Given the advances that have occurred subsequent to the IESWTR in available technology to measure and treat for *Cryptosporidium*, a key question for the LT2ESWTR was the extent to which *Cryptosporidium* should be further controlled to approach the MCLG of zero, considering technical feasibility, costs, and potential risks from DBPs.

The data and analysis presented in Section III of this preamble suggest wide variability in possible risk from *Cryptosporidium* among public water systems. This variability is largely due to three factors: (1) The broad distribution of *Cryptosporidium* occurrence levels among source waters, (2) disparities in the efficacy of treatment provided by plants, and (3) differences in the infectivity among *Cryptosporidium* isolates. EPA and the Advisory Committee considered this wide range of possible risks and the desire to address systems where the 2 log removal requirement established by the IESWTR and LT1ESWTR may not provide adequate public health protection.

A number of approaches were evaluated for furthering control of *Cryptosporidium*. One approach was to require all systems to provide the same degree of additional treatment for *Cryptosporidium* (i.e., beyond that required by the IESWTR and LT1ESWTR). This approach could ensure that most systems, including those with poor quality source water, would be adequately protective. The uniformity of this approach has the advantage of minimizing transactional costs for determining what must be done by a particular system to comply. However, a significant downside is that it may require more treatment, with

consequent costs, than is needed by many systems with low source water *Cryptosporidium* levels. In addition, there were concerns with the feasibility of requiring almost all surface water treatment plants to install additional treatment processes for *Cryptosporidium*.

A second approach was to base additional treatment requirements on a plant's source water *Cryptosporidium* level. Under this approach, systems monitor their source water for *Cryptosporidium*, and additional treatment is required only from those systems that exceed specified oocyst concentrations. This has the advantage of targeting additional public health protection to those systems with higher vulnerability to *Cryptosporidium*, while avoiding the imposition of higher treatment costs on systems with the least contaminated source water. In consideration of these advantages, the Advisory Committee recommended and EPA is proposing this second approach for filtered systems under the LT2ESWTR.

b. *Basis for bin concentration ranges and treatment requirements.* The proposed LT2ESWTR will classify plants into different risk bins based on the source water *Cryptosporidium* level, and the bin classification will determine the extent to which additional treatment beyond IESWTR and LT1ESWTR is required. Two questions were central in developing the proposed bin concentration ranges and additional treatment requirements:

- What is the risk associated with a given level of *Cryptosporidium* in a drinking water source?
- What degree of additional treatment should be required for a given source water *Cryptosporidium* level?

This section addresses these two questions by first summarizing how EPA assessed the risk associated with *Cryptosporidium* in drinking water, followed by a description of how EPA and the Advisory Committee used this type of information in identifying LT2ESWTR bin concentration ranges and treatment requirements. For additional information on these topics, see Economic Analysis for the LT2ESWTR (USEPA 2003a).

i. What is the risk associated with a given level of *Cryptosporidium* in a drinking water source? The risk of infection from *Cryptosporidium* in drinking water is a function of infectivity (i.e., dose-response associated with ingestion) and exposure. Section III.B summarizes available data on *Cryptosporidium* infectivity. EPA conducted a meta-analysis of reported infection rates from human feeding

studies with 3 *Cryptosporidium* isolates. This analysis produced an estimate for the mean probability of infection given a dose of one oocyst near 0.09 (9%), with 10th and 90th percentile confidence values of 0.011 and 0.22, respectively.

Exposure to *Cryptosporidium* depends on the concentration of oocysts in the source water, the efficiency of treatment plants in removing oocysts, and the volume of water ingested (exposure can also occur through interactions with infected individuals). Based on data presented in section III.D, EPA has estimated that filtration plants in compliance with the IESWTR or LT1ESWTR reduce source water *Cryptosporidium* levels by 2 to 5 log (99% to 99.999%), with an average

reduction near 3 log. For drinking water consumption, EPA uses a distribution, derived from the United States Department of Agriculture's (USDA) 1994–96 Continuing Survey of Food Intakes by Individuals, with a mean value of 1.2 L/day. Average annual days of exposure to drinking water in CWS, non-transient non-community water systems (NTNCWS), and transient non-community water systems (TNCWS) are estimated at 350 days, 250 days, and 10 days, respectively. (The Economic Analysis for the LT2ESWTR (USEPA 2003a) provides details on all parameters listed here, as well as morbidity, mortality, and other risk factors.)

Using an estimate of 1.2 L/day consumption and a mean probability of

infection of 0.09 for one oocyst ingested, the daily risk of infection (DR) is as follows:

$$DR = (\text{oocysts/L in source water}) \times (\text{percent remaining after treatment}) \times (1.2 \text{ L/day}) \times (0.09).$$

The annual risk (AR) of infection for a CWS is

$$AR = 1 - (1 - DR)^{350}$$

where 350 represents days of exposure in a CWS.

Table IV–5 presents estimates of the mean annual risk of infection by *Cryptosporidium* in CWSs for selected source water infectious oocyst concentrations and filtration plant removal efficiencies.

TABLE IV–5.—ANNUAL RISK OF *Cryptosporidium* INFECTION IN CWSs THAT FILTER, AS A FUNCTION OF SOURCE WATER INFECTIOUS OOCYST CONCENTRATION AND TREATMENT EFFICIENCY

Source water concentration (infectious oocysts per liter)	Mean annual risk of infection for different levels of treatment efficiency (log removal) ¹			
	2 log	3 log	4 log	5 log
0.0001	3.8E–05	3.8E–06	3.8E–07	3.8E–08
0.001	3.7E–04	3.8E–05	3.8E–06	3.8E–07
0.01	3.7E–03	3.7E–04	3.8E–05	3.8E–06
0.1	3.7E–02	3.7E–03	3.7E–04	3.8E–05
1	0.31	3.7E–02	3.7E–03	3.7E–04
10	0.89	0.31	3.7E–02	3.7E–03

¹ Scientific notation (E^{-x}) designates 10^{-x}

For example, Table IV–5 shows that if a filtration plant had a mean concentration of infectious *Cryptosporidium* in the source water of 0.01 oocysts/L, and the filtration plant averaged 3 log removal, the mean annual risk of infection by *Cryptosporidium* is estimated as 3.7×10^{-4} (3.7 infections per 10,000 consumers).

ii. What degree of additional treatment should be required for a given source water *Cryptosporidium* level? In order to develop targeted treatment requirements for the LT2ESWTR, it was necessary to identify a source water *Cryptosporidium* level above which additional treatment by filtered systems would be required. Based on the type of risk information shown in Table IV–5, EPA and Advisory Committee deliberations focused on mean source water *Cryptosporidium* concentrations in the range of 0.01 to 0.1 oocysts/L as appropriate threshold values for prescribing additional treatment.

Analytical method and sampling constraints were a significant factor in setting the specific *Cryptosporidium* level that triggers additional treatment by filtered systems. The number of samples that systems can be required to

analyze for *Cryptosporidium* is limited. Consequently, if the bin threshold concentration for additional treatment was set near 0.01 oocysts/L, systems could exceed this level due to a very low number of oocysts being detected. For example, if systems took monthly 10 L samples and bin classification was based on a maximum running annual average, then a system would exceed a mean concentration of 0.01 oocysts/L by counting only 2 oocysts in 12 samples. Given the variability associated with *Cryptosporidium* analytical methods, the Advisory Committee did not support requiring additional treatment for filtered systems based on so few counts.

Another concern related to analytical method limitations was systems being misclassified in a lower bin. For example, if a system had a true mean concentration at or just above 0.1 oocysts/L, the mean that the system would determine through monitoring might be less than 0.1 oocyst/L. Thus, if the bin threshold for additional treatment was set at 0.1 oocysts/L, a number of systems with true mean concentrations above this level would be misclassified in the lower bin with no additional treatment required. This type of error, described in more detail

in the next section, is a function of the number of samples collected and variability in method performance.

In consideration of the available information on *Cryptosporidium* risk, as well as the performance and feasibility of analytical methods, EPA is proposing that the source water threshold concentration for requiring additional *Cryptosporidium* treatment by filtered systems be established at a mean level of 0.075 oocysts/L. This is the level recommended by the Advisory Committee, and it affords a high likelihood that systems with true mean *Cryptosporidium* concentrations of 0.1 oocysts/L or higher will provide additional treatment under the rule.

Beyond identifying this first threshold, it was also necessary to determine *Cryptosporidium* concentrations that would demarcate higher risk bins. With respect to the concentration range that each bin should comprise, EPA and the Advisory Committee dealt with two opposing factors: bin misclassification and equitable risk reduction.

As described in the next section, a monthly monitoring program involving EPA Methods 1622 or 1623 can characterize a system's mean *Cryptosporidium* concentration within a

0.5 log (factor of 3.2) margin with a high degree of accuracy. However, the closer a system's true mean concentration is to a bin boundary, the greater the likelihood that the system will be misclassified into the wrong bin due to limitations in sampling and analysis. Accordingly, by establishing bins that cover a wide concentration range, the likelihood of system misclassification is reduced.

However, a converse factor relates to equitable protection from risk. Because identical treatment requirements will apply to all systems in the same bin, systems at the higher concentration end of a bin will achieve less risk reduction relative to their source water pathogen levels than systems at the lower concentration end of a bin. Thus, bins with a narrow concentration range provide a more uniform level of public health protection.

In balancing these factors and to account for the wide range of possible source water concentrations among different systems as indicated by Information Collection Rule and ICRSS data, the Advisory Committee recommended and EPA is proposing a second bin threshold at a mean level of 1.0 oocysts/L and a third bin threshold at a mean level of 3.0 oocysts/L. Information Collection Rule and ICRSS data indicate that few, if any, systems would measure mean *Cryptosporidium* concentrations greater than 3.0 oocysts/L, so there was not a need to establish a bin threshold above this value. Thus, the LT2ESWTR proposal includes the following four bins for classifying filtered systems: Bin 1: <0.075/L; Bin 2: ≥0.075 to <1.0/L; Bin 3: ≥1.0/L to <3.0/L; and Bin 4: ≥3.0/L (oocysts/L).

With respect to additional *Cryptosporidium* treatment for systems in Bins 2–4, values were considered ranging from 0.5 to 2.5 log and greater. As recommended by the Advisory Committee, EPA is proposing 1.0 log additional treatment for conventional plants in Bin 2. This level of treatment will ensure that systems classified in Bin 2 will achieve treated water *Cryptosporidium* levels comparable to systems in Bin 1, the lowest risk bin. In contrast, if systems in Bin 2 provided only 0.5 log additional treatment then those systems with mean source water concentrations in the upper part of Bin 2 would have higher levels of *Cryptosporidium* in their finished water than systems in Bin 1.

In consideration of the much greater potential vulnerability of systems in the highest risk bins, the Advisory Committee recommended additional treatment requirements of 2.0 log and 2.5 log for conventional plants in Bins

3 and 4, respectively. The Agency concurs with these recommendations and has incorporated them in today's proposal.

An important aspect of the proposed additional treatment requirements is that they are based, in part, on the current level of treatment provided by filtration plants. As noted earlier, the Advisory Committee assumed when developing its recommendations that conventional treatment plants in compliance with the IESWTR achieve an average of 3 log removal of *Cryptosporidium*. EPA has determined that available data, discussed in section III.D, support this assumption and has proposed a 3 log *Cryptosporidium* treatment credit for conventional plants under the LT2ESWTR. Thus, the additional treatment requirements for conventional plants in Bins 2, 3, and 4 translate to total requirements of 4.0, 5.0, and 5.5 log, respectively.

The Advisory Committee did not address additional treatment requirements for plants with treatment trains other than conventional, but recommended that EPA address such plants in the proposed LT2ESWTR and take comment. Based on treatment studies summarized in section III.D, EPA has concluded that plants with slow sand or DE filtration are able to achieve 3 log or greater removal of *Cryptosporidium* when in compliance with the IESWTR or LT1ESWTR. Because these plants can achieve comparable levels of performance to conventional treatment plants, EPA is proposing that slow sand and DE filtration plants also apply 1 to 2.5 log of additional treatment when classified in Bins 2–4.

Direct filtration differs from conventional treatment in that it does not include sedimentation or an equivalent clarification process prior to filtration. As described in section III.D, EPA has concluded that a sedimentation process can consistently achieve 0.5 log or greater removal of *Cryptosporidium*. The Agency is proposing that direct filtration plants in compliance with the IESWTR or LT1ESWTR receive a 2.5 log *Cryptosporidium* removal credit towards LT2ESWTR requirements. Accordingly, proposed additional treatment requirements for direct filtration plants in bins 2, 3, and 4 are 1.5 log, 2.5 log, and 3 log, respectively.

Section IV.C of this notice describes proposed criteria for determining *Cryptosporidium* treatment credits for other filtration technologies like membranes, bag filters, and cartridge filters. Due to the proprietary and product specific nature of these filtration devices, EPA is not able to

propose a generally applicable credit for them. Rather, the criteria in section IV.C focus on challenge testing to establish treatment credit. Systems using these technologies that are classified in Bins 2–4 must work with their States to assess appropriate credit for their existing treatment trains. This will determine the level of additional treatment necessary to achieve the total treatment requirements for their assigned bins. EPA has developed guidance on challenge testing of bag and cartridge filters and membranes, which is available in draft form in the docket (<http://www.epa.gov/edocket/>).

In order to give systems flexibility in choosing strategies to meet additional *Cryptosporidium* treatment requirements, the Advisory Committee identified a number of management and treatment options, collectively called the microbial toolbox. The toolbox, which is described in section IV.C, contains components relating to watershed control, intake management, pretreatment, additional filtration processes, inactivation, and demonstrations of enhanced performance.

As recommended by the Advisory Committee, EPA is proposing that systems in Bin 2 can meet additional *Cryptosporidium* treatment requirements under the LT2ESWTR using any component or combination of components from the microbial toolbox. However, systems in Bins 3 and 4 must achieve at least 1 log of the additional treatment requirement using inactivation (UV, ozone, chlorine dioxide), membranes, bag filters, cartridge filters, or bank filtration. These specific control measures are proposed due to their ability to serve as significant additional treatment barriers for systems with high levels of pathogens.

c. *Basis for source water monitoring requirements.* The goal of monitoring under the LT2ESWTR is to correctly classify filtration plants into the four LT2ESWTR risk bins. The proposed sampling frequency, time frame, and averaging procedure for bin classification are intended to ensure that systems are accurately assigned to appropriate risk bins while limiting the burden of monitoring costs. The basis for the proposed monitoring requirements for large and small systems is presented in the following discussion.

i. Systems serving at least 10,000 people.

Sample Number and Frequency

Systems serving at least 10,000 people have two options for sampling under the

LT2ESWTR: (1) They can collect 24 monthly samples over a 2 year period and calculate their bin classification using the highest 12 month running annual average, or (2) They can collect 2 or more samples per month over the 2 year period and use the mean of all samples for bin classification.

These proposed requirements reflect recommendations by the Advisory Committee and are based on analyses of misclassification rates associated with different monitoring programs that were considered. EPA is concerned about systems with high concentrations of *Cryptosporidium* being misclassified in lower bins as well as systems with low concentrations being misclassified in higher bins. The first type of error could lead to systems not providing an adequate level of treatment while the second type of error could lead to systems incurring additional costs for unnecessary treatment.

A primary way that EPA analyzed misclassification rates was by considering the likelihood that a system with a true mean *Cryptosporidium* concentration that is a factor of 3.2 (0.5 log) above or below a bin boundary would be assigned to the wrong bin.

Probabilities were assessed for two cases:

- False negative: a system with a mean concentration of 0.24 oocysts/L (*i.e.*, factor of 3.2 above the Bin 1 boundary of 0.075 oocysts/L) is misclassified low in Bin 1.
- False positive: a system with a mean concentration of 0.024 oocysts/L (*i.e.*, factor of 3.2 below the Bin 1 boundary of 0.075 oocysts/L) is misclassified high in Bin 2.

Table IV-6 provides false negative and false positive rates as defined previously for different approaches to monitoring and bin classification that were evaluated. Results are shown for the following approaches:

- 48 samples with bin assignment based on arithmetic mean (*i.e.*, average of all samples).
- 24 samples with bin assignment based on highest 12 sample average, equivalent to the maximum running annual average (Max-RAA).
- 24 samples with bin assignment based on arithmetic mean.
- 12 samples with bin assignment based on the second highest sample result.
- 8 samples with bin assignment based on the maximum sample result.

These estimated misclassification rates were generated with a Monte Carlo analysis that accounted for the volume assayed, variation in source water *Cryptosporidium* occurrence, and variable method recovery. See Economic

Analysis for the LT2ESWTR (USEPA 2003a) for details.

TABLE IV-6.—FALSE POSITIVE AND FALSE NEGATIVE RATES FOR MONITORING AND BINNING STRATEGIES CONSIDERED FOR THE LT2ESWTR
[In percentages]

Strategy	False positive ¹	False negative ²
48 sample arithmetic mean	1.7	1.4
24 sample Max-RAA	5.3	1.7
24 sample arithmetic mean	2.8	6.2
12 sample second highest	47	1.1
8 sample maximum	66	1.0

¹ False positive rates calculated for systems with *Cryptosporidium* concentrations 0.5 log below the Bin 1 boundary of 0.075 oocysts/L.

² False negative rates calculated for systems with *Cryptosporidium* concentrations 0.5 log above the Bin 1 boundary of 0.075 oocysts/L.

The first two of these approaches, the 48 sample arithmetic mean and 24 sample Max-RAA, were recommended by the Advisory Committee and are proposed for bin classification under the LT2ESWTR because they have low false positive and false negative rates. As shown in Table IV-6, these strategies have false negative rates of 1 to 2%, meaning there is a 98 to 99% likelihood that a plant with an oocyst concentration 0.5 log above the Bin 1 boundary would be correctly assigned to Bin 2. The false positive rate is near 2% for the 48 sample arithmetic mean and 5% for the 24 sample Max-RAA. These rates indicate that a plant with an oocyst concentration 0.5 log below the Bin 1 boundary would have a 95 to 98% probability of being correctly assigned to Bin 1. Bin misclassification rates across a wide range of concentrations are shown in Economic Analysis for the LT2ESWTR (USEPA 2003a).

The 24 sample arithmetic mean had a slightly lower false positive rate than the 24 sample Max-RAA (2.8% vs. 5.3%) but the false negative rate of the arithmetic mean was almost 4 times higher. Consequently, a plant with a mean *Cryptosporidium* level above the Bin 1 boundary would be much more likely to be misclassified in Bin 1 using a 24 sample arithmetic mean than with a 24 sample Max-RAA. In order to increase the probability that systems with mean *Cryptosporidium* concentrations above 0.075 oocysts/L will provide additional treatment, EPA is proposing that if only 24 samples are taken, the maximum 12 month running annual average must be used to determine bin assignment.

Monitoring strategies involving only 12 and 8 samples were evaluated to determine if lower frequency monitoring could provide satisfactory bin classification. The results of this analysis indicate that these lower sample numbers are not adequate and could unfairly bias excessive treatment requirements. For example, results in Table IV-6 show that if plants were classified in bins based on the second highest of 12 samples or the highest of eight samples then low false negative rates could be achieved. A system with a mean *Cryptosporidium* level 0.5 log above the Bin 1 boundary would have a 99% chance of being appropriately classified in a bin requiring additional treatment under either strategy. However, the false positive rates associated with these low sample numbers are very high. A system with a mean oocyst concentration 0.5 log below the Bin 1 boundary would have a 47% probability of being incorrectly classified in Bin 2 using the second highest result among 12 samples, or a 66% likelihood of being misclassified in Bin 2 using the maximum result among 8 samples. Due to high false positive rates, these strategies are not proposed.

EPA also evaluated lower frequency monitoring strategies that had lower false positive rates, such as bin classification based on the mean of 12 samples, the third highest result of 12 samples, and the second highest of 8 samples. Each of these strategies, though, had an unacceptably high false negative rate, meaning that many systems with mean oocyst concentrations greater than the Bin 1 boundary would be misclassified low in Bin 1. Consequently, these strategies are inconsistent with the public health goal of the LT2ESWTR for systems with mean levels above 0.075 oocysts/L to provide additional treatment.

Increasing the number of samples used to compute the maximum running annual average above 24 also increased the number of annual averages computed, so it did not reduce the likelihood of false positives. Raising the number of samples used to compute an arithmetic mean above 48 did reduce bin misclassification rates, but the rates were already very small (1 to 2% for plants with levels 0.5 log above or below bin boundaries). For sources with *Cryptosporidium* concentrations very near or at bin boundaries, increasing the number of samples did not markedly improve the error rates, which remained near 50% at the bin boundaries.

In summary, EPA believes that the proposed sampling designs perform well for the purpose of classifying plants in LT2ESWTR risk bins and,

thereby, achieving the public health protection intended for the rule. More costly designs, involving more frequent sampling and analysis, provide only marginally improved performance. Less frequent sampling, though lower in cost, creates unacceptably high misclassification rates and would not provide for the targeted risk reduction goals of the rule.

No Adjustments for Method Recovery or Percent of Oocysts That Are Infectious

Two considerations in using *Cryptosporidium* monitoring data to project risk are (1) Fewer than 100% of oocysts in a sample are recovered and counted by the analyst and (2) not all the oocysts measured with Methods 1622/23 are viable and capable of causing infection. These two factors are offsetting in sign, in that oocyst counts not adjusted for recovery tend to underestimate the true concentration, while the total oocyst count may overestimate the infectious concentration that presents a health risk. Based on information described in this section, EPA is proposing that *Cryptosporidium* monitoring results be used directly to assign systems to LT2ESWTR risk bins and not be adjusted for either factor.

As described in section III.C, ICRSS matrix spike data indicate that average recovery of *Cryptosporidium* oocysts with Methods 1622/23 in a national monitoring program will be about 40%. There is no similar direct measure of the fraction of environmental oocysts that are infectious, but information related to this value can be derived from two sources: (1) A study where samples were analyzed with both Method 1623 and a cell culture-polymerase chain reaction (CC-PCR) test for oocyst infectivity, and (2) the structure of oocysts counted with Methods 1622 and 1623.

LeChevallier *et al.* (2003) conducted a study in which six natural waters were frequently tested for *Cryptosporidium* using both Method 1623 and a CC-PCR method to test for infectivity. *Cryptosporidium* oocysts were detected in 60 of 593 samples (10.1%) by Method 1623 and infectious oocysts were detected in 22 of 560 samples (3.9%) by the CC-PCR procedure. Recovery efficiencies for the two methods were similar. According to the authors, these results suggest that approximately 37% (22/60) of the *Cryptosporidium* oocysts detected by Method 1623 were viable and infectious.

In regard to oocyst structure, *Cryptosporidium* oocysts counted with Methods 1622/23 are characterized in one of three ways: (1) Internal

structures, (2) amorphous structures, or (3) empty. Oocysts with internal structures are considered to have the highest likelihood of being infectious, while empty oocysts are believed to be non-viable (LeChevallier *et al.* 1997). During the ICRSS, 37% of the oocysts counted were characterized as having internal structures, 47% had amorphous structures, and 16% were empty. If it is assumed that empty oocysts could not be infectious, the mid-point value within the percentage range of counted oocysts that could have been infectious is 42%.

After considering this type of information, the Advisory Committee recommended that monitoring results not be adjusted upward for percent recovery, nor adjusted downward to account for the fraction of oocysts that are not infectious. While it is not possible to establish a precise value for either factor in individual samples, the data suggest that they may be of similar magnitude. EPA concurs with this recommendation and is proposing that systems be classified in bins under the LT2ESWTR using the total *Cryptosporidium* oocyst count, uncorrected for recovery, as measured using EPA Method 1622/23. The proposed LT2ESWTR risk bins are constructed to reflect this approach.

Data Collection To Support Use of a Microbial Indicator by Small Systems

As described in the next section, small systems will monitor for an indicator, currently proposed to be *E. coli*, to determine if they are required to sample for *Cryptosporidium*. The proposed *E. coli* levels that will trigger *Cryptosporidium* monitoring are based on Information Collection Rule and ICRSS data. However, to provide for a more extensive evaluation of *Cryptosporidium* indicator criteria, EPA is proposing that large systems measure *E. coli* and turbidity in their source water when they sample for *Cryptosporidium*. This was recommended by the Advisory Committee and will allow for possible development of alternative indicator levels or parameters (*e.g.*, turbidity in combination with *E. coli*) to serve as triggers for small system *Cryptosporidium* monitoring.

Time Frame for Monitoring

In recommending a time frame for LT2ESWTR monitoring, the Agency considered the trade-off between monitoring over a long period to better capture year-to-year fluctuations, and the desire to prescribe additional treatment quickly to systems identified as having high source water pathogen

levels. Reflecting Advisory Committee recommendations, EPA is proposing that large systems evaluate their source water *Cryptosporidium* levels using 2 years of monitoring. This will account for some degree of yearly variability, without significantly delaying additional public health protection where needed.

ii. Systems serving fewer than 10,000 people.

Indicator Monitoring

In recognition of the relatively high cost of analyzing samples for *Cryptosporidium*, EPA and the Advisory Committee explored the use of indicator criteria to identify drinking water sources that may have high levels of *Cryptosporidium* occurrence. The goal was to find one or more parameters that could be analyzed at low cost and identify those systems likely to exceed the Bin 1 boundary of 0.075 oocysts/L. Data from the Information Collection Rule and ICRSS were evaluated for possible indicator parameters, including fecal coliforms, total coliforms, *E. coli*, viruses (Information Collection Rule only), and turbidity. Based on available data, *E. coli* was found to provide the best performance as a *Cryptosporidium* indicator, and the inclusion of other parameters like turbidity was not found to improve accuracy.

The next part of this section presents data that support *E. coli* mean concentrations of 10/100 mL and 50/100 mL as proposed screening levels that will trigger *Cryptosporidium* monitoring in reservoir/lake and flowing stream systems, respectively. It describes how *E. coli* and *Cryptosporidium* data from the Information Collection Rule and ICRSS were analyzed and shows the performance of different concentrations of *E. coli* as an indicator for systems that will exceed the Bin 1 boundary of 0.075 oocysts/L.

Information Collection Rule data were evaluated as maximum running annual averages (Information Collection Rule samples were collected once per month for 18 months) while ICRSS data were evaluated using an annual mean (ICRSS samples were collected twice per month for 12 months). In addition, as indicators were being evaluated it became apparent that it was necessary to analyze plants separately based on source water type, due to a significantly different relationship between *E. coli* and *Cryptosporidium* in reservoir/lake systems compared to flowing stream systems.

Analyzing the performance of an *E. coli* level as a screen to trigger *Cryptosporidium* monitoring under the proposed LT2ESWTR involved

evaluating each water treatment plant in the data set relative to two factors: (1) Did the plant *E. coli* level exceed the trigger value being assessed? and (2) Did the plant mean *Cryptosporidium* concentration exceed 0.075 oocysts/L? Accordingly, plants were sorted into four categories, based on *Cryptosporidium* and *E. coli* concentrations:

- Plants with *Cryptosporidium* < 0.075 oocysts/L that did not exceed the *E. coli* trigger level (Figure IV-1, box A)
- Plants with *Cryptosporidium* < 0.075 oocysts/L that exceeded the *E. coli* trigger level (Figure IV.1, box B)
- Plants with *Cryptosporidium* ≥ 0.075 oocysts/L that did not exceed the *E. coli* trigger level (Figure IV.1, box C)
- Plants with *Cryptosporidium* ≥ 0.075 oocysts/L that exceeded the *E. coli* trigger level (Figure IV.1, box D)

Summary data with *E. coli* trigger concentrations ranging from 5 to 100 per 100 mL are presented for Information Collection Rule and ICRSS data in Figures IV-2 and IV-3.

The performance of each *E. coli* level as a trigger for *Cryptosporidium* monitoring was evaluated based on false negative and false positive rates. False negatives occur when plants do not exceed the *E. coli* trigger value, but exceed a *Cryptosporidium* level of 0.075 oocysts/L. False positives occur when plants exceed the *E. coli* trigger value but do not exceed a *Cryptosporidium* level of 0.075 oocysts/L. The false negative rate is critical because it characterizes the ability of the indicator to identify those plants with high *Cryptosporidium* levels. In general, low false negative rates can be achieved by lowering the *E. coli* trigger concentration. However, when the *E. coli* trigger concentration is decreased, more plants with low *Cryptosporidium* levels in their source water exceed it. As a result, more plants incur false

positives. Consequently, identifying an appropriate *E. coli* concentration to trigger *Cryptosporidium* monitoring involves balancing false negatives and false positives to minimize both.

Results of the indicator analysis for plants with flowing stream sources are shown in Figure IV-2. An *E. coli* trigger concentration of 50/100 mL produced zero false negatives for both data sets. This means that in these data sets, all plants that exceeded mean *Cryptosporidium* concentrations of 0.075 oocysts/L also exceeded the *E. coli* trigger concentration and would, therefore, be required to monitor. However, this trigger concentration had a significant false positive rate (*i.e.*, it was not highly specific in targeting only those plants with high *Cryptosporidium* levels). False positive rates were 57% (24/42) and 53% (9/17) with Information Collection Rule and ICRSS data, respectively. At a higher *E. coli* trigger concentration, such as 100/100 mL, the false negative rate increased to 12.5% (3/24) with Information Collection Rule data and 50% (2/4) with ICRSS data, while the false positive rate decreased to 43% (18/42) and 35% (6/17), respectively. Consequently, EPA is proposing a mean *E. coli* concentration of 50/100 mL as a trigger for *Cryptosporidium* monitoring by small systems with flowing stream sources.

Results of the indicator analysis for plants with reservoir/lake sources are shown in Figure IV-3. An *E. coli* trigger of 10/100 mL resulted in a false negative rate of 20% (2/10) with Information Collection Rule data and 67% (2/3) with ICRSS data (misclassified 2 out of 3 plants over 0.075 oocysts/L). Going to a lower concentration *E. coli* trigger, such as 5 per 100 mL, decreased the false negative rate in both the Information Collection Rule and ICRSS data sets by one plant, but increased the false positive rate from 20% to 43% (13/30)

in the ICRSS data and from 24% to 39% (44/114) in the Information Collection Rule data. Based on these results, EPA is proposing that a mean *E. coli* concentration of 10/100 mL trigger small systems using lake/reservoir sources into monitoring for *Cryptosporidium*. While the false negative rate associated with this trigger value in the ICRSS data set is high, the ICRSS data set contains only 3 reservoir/lake plants that exceeded a *Cryptosporidium* level of 0.075 oocysts/L.

Due to limitations in the available data, the Advisory Committee did not recommend that large systems use the *E. coli* indicator screen, as *Cryptosporidium* monitoring is less of an economic burden for large systems. Rather, the Advisory Committee recommended that large systems sample for *E. coli* and turbidity when they monitor for *Cryptosporidium* under the LT2ESWTR. These data will then be used to verify or, if necessary, further refine the proposed indicator trigger values for small systems. EPA concurs with these recommendations and they are reflected in today's proposal.

The proposed monitoring schedule under the LT2ESWTR is set up to allow EPA and stakeholders to evaluate large system monitoring data for indicator relationships prior to the start of small system *E. coli* monitoring. After one year of large system monitoring is completed, EPA will begin analyzing monitoring data to assess whether alternative indicator strategies would be appropriate. Depending on the findings of this analysis, EPA may issue guidance to States on approving alternative indicator trigger strategies for small systems. Therefore, the proposed rule is written with the allowance for States to approve alternative indicator strategies.

BILLING CODE 6560-50-P

Breakdown of Plants into <i>Cryptosporidium</i> "bin"	Breakdown of Plants Using <i>E. coli</i> "Trigger"	
	Did not exceed trigger value	Exceeds trigger value
< 0.075 <i>Cryptosporidium</i> per L	A	B
≥ 0.075 <i>Cryptosporidium</i> per L	C	D
Calculations used to Assess Indicator Performance		
What percent of plants with ≥ 0.075 <i>Cryptosporidium</i> per L exceed the <i>E. coli</i> trigger?	D / (C + D)	
What percent of plants would be required to monitor for <i>Cryptosporidium</i> ?	(B + D) / (A + B + C + D)	

Figure IV-1.— Microbial Indicator System Template

Flowing Streams												
E. coli trigger level: Study: Did plant exceed E. coli trigger level? < 0.075 <i>Cryptosporidium</i> per L ≥ 0.075 <i>Cryptosporidium</i> per L What percent of plants with ≥ 0.075 <i>Cryptosporidium</i> per L exceed the E. coli trigger? What percent of plants would be required to monitor for <i>Cryptosporidium</i> ?	5 E. coli / 100 mL			10 E. coli / 100 mL			50 E. coli / 100 mL			100 E. coli / 100 mL		
	ICR		ICRSS	ICR		ICRSS	ICR		ICRSS	ICR		ICRSS
	No	Yes	No	Yes	No	Yes	No	Yes	No	Yes	No	Yes
	6	36	2	15	7	35	5	12	18	24	8	9
	0	24	0	4	0	24	0	4	0	24	0	4
	100%		100%		100%		100%		100%		100%	
	91%		90%		89%		76%		73%		62%	
											50%	
											88%	
											59%	
											21	
											3	
											2	
											11	
											6	

Figure IV-2.— Summary of Flowing Stream Indicator Analysis for Information Collection Rule and ICRSS Data at

Bin 1 Boundary of 0.075 Oocysts/L and E. coli Triggers of 5, 10, 50, and 100 per 100 mL

Reservoir / lakes												
E. coli trigger level: Study: Did plant exceed E. coli trigger level? < 0.075 <i>Cryptosporidium</i> per L ≥ 0.075 <i>Cryptosporidium</i> per L What percent of plants with ≥ 0.075 <i>Cryptosporidium</i> per L exceed the E. coli trigger? What percent of plants would be required to monitor for <i>Cryptosporidium</i> ?	5 E. coli / 100 mL			10 E. coli / 100 mL			50 E. coli / 100 mL			100 E. coli / 100 mL		
	ICR		ICRSS	ICR		ICRSS	ICR		ICRSS	ICR		ICRSS
	No	Yes	No	Yes	No	Yes	No	Yes	No	Yes	No	Yes
	70	44	17	13	87	27	24	6	107	7	28	2
	1	9	1	2	2	8	2	1	8	2	3	0
	90%		67%		80%		33%		20%		0%	
	43%		45%		28%		21%		7%		6%	
											10%	
											6%	
											29	
											1	
											3	
											0	

Figure IV-3.— Summary of Reservoir/lake Indicator Analysis Results for Information Collection Rule and ICRSS

Data at Bin 1 Boundary of 0.075 Oocysts/L and Using E. coli Triggers of 5, 10, 50, and 100 per 100 mL

BILLING CODE 6560-50-C

Cryptosporidium Monitoring

Small systems that exceed the *E. coli* trigger must conduct *Cryptosporidium* monitoring, beginning 6 months after completion of *E. coli* monitoring. As recommended by the Advisory Committee, EPA is proposing that small systems collect 24 *Cryptosporidium* samples over a period of one year. This number of samples is the same as required for large systems, but the monitoring burden is targeted only on those plants that *E. coli* monitoring indicates to have elevated levels of fecal matter in the source water. By completing *Cryptosporidium* monitoring in one year, small systems will conduct a total of 2 years of monitoring to determine LT2ESWTR bin classification (including the one year of *E. coli* monitoring). This time frame is equivalent to the requirement for large systems, which monitor for *Cryptosporidium*, *E. coli*, and turbidity for 2 years.

The Stage 2 M-DBP Agreement in Principle recommended that EPA explore the feasibility of alternative, lower frequency, *Cryptosporidium* monitoring criteria for providing a conservative mean estimate in small systems. As described earlier, EPA has evaluated smaller sample sizes, such as systems taking 12 or 8 samples instead of 24 (see Table IV-6). However, EPA has concluded that these smaller sample sizes result in unacceptably high misclassification rates. For example, bin classification based on the second highest of 12 samples produces an estimated false positive rate of 47% for systems with a mean *Cryptosporidium* concentration 0.5 log below the Bin 1 boundary of 0.075/L. In comparison, bin classification based on the mean of 24 samples achieves a false positive rate of 2.8% for systems at this *Cryptosporidium* concentration. Consequently, EPA is proposing no alternatives to the requirement that small systems take at least 24 samples.

Small system bin classification will be determined by the arithmetic mean of the 24 samples collected over one year. Because the bin structure in the LT2ESWTR is based on annual mean *Cryptosporidium* levels, it is necessary that bin classification involve averaging samples over at least one year. Consequently, small systems will determine their bin classification by averaging results from all *Cryptosporidium* samples collected during their one year of monitoring.

iii. Future monitoring and reassessment. EPA is proposing that beginning 6 years after the initial bin

classification, large and small systems conduct another round of monitoring to determine if source water conditions have changed to a degree that may warrant a revised bin classification. The Advisory Committee recommended that EPA convene a stakeholder process within 4 years after the initial bin classification to develop recommendations on how best to proceed with implementing this second round of monitoring. Unless EPA modifies the LT2ESWTR to allow for an improved analytical method or a revised bin structure based on new risk information, the second round of monitoring will be conducted under the same requirements that apply to the initial round of monitoring.

In addition, EPA is proposing to use the required assessment of the water source during sanitary surveys as an ongoing measure of whether significant changes in watersheds have occurred that may lead to increased contamination. Where the potential for increased contamination is identified, States must determine what follow-up actions by the system are necessary, including the possibility of the system providing additional treatment from the microbial toolbox.

d. *Basis for accepting previously collected data.* Members of the Advisory Committee had multiple objectives in recommending that EPA allow the use of previously collected (grandfathered) *Cryptosporidium* data. These include (1) giving credit for data collected by proactive utilities, (2) facilitating early determination of LT2ESWTR compliance needs and, thereby, allowing for early planning of appropriate treatment selection, (3) increasing laboratory capacity to meet demand for *Cryptosporidium* analysis under the LT2ESWTR, and (4) allowing utilities to improve their data set for bin determination by considering more than 2 years of data (*i.e.*, include data collected prior to effective date of LT2ESWTR). The latter objective incorporates the assumption that occurrence can vary from year to year, so that if more years of data are used in the bin determination, the source water concentration estimate will be a more accurate representation of the overall mean.

A significant issue with accepting previously collected data for making bin determinations is ensuring that the data are of equivalent quality to data that will be collected following LT2ESWTR promulgation. As noted previously, EPA is establishing requirements so that data collected under the LT2ESWTR will be similar in quality to data that were generated under the ICRSS. These

requirements include the use of approved analytical methods and compliance with method quality control (QC) criteria, use of approved laboratories, minimum sample volume, and a sampling schedule with minimum frequency. For example, under the ICRSS, laboratories analyzed 10 L samples and (considered collectively) achieved a mean *Cryptosporidium* recovery of approximately 43% in spiked source water with a relative standard deviation (RSD) of 50%. EPA anticipates that laboratories conducting *Cryptosporidium* analysis for the LT2ESWTR will collectively achieve similar analytical method performance. Consequently, EPA expects previously collected data sets used under the LT2ESWTR to meet these standards and has established criteria for accepting previously collected data accordingly (see section IV.A.1.d).

Systems are requested, but not required, to notify EPA prior to promulgation of the LT2ESWTR of their intent to submit previously collected data. This will help EPA allocate the resources that will be needed to evaluate these data in order to make a decision on adequacy for bin determination. Systems that have at least 2 years of previously collected data to grandfather when the LT2ESWTR is promulgated and do not intend to conduct new monitoring under the rule are required to submit the previously collected data to EPA within 2 months following promulgation. This will enable EPA to evaluate the data and report back to the utility in sufficient time to allow, if needed, the utility to contract with a laboratory to conduct monitoring under the LT2ESWTR.

Systems that have fewer than 2 years of previously collected data to grandfather when the LT2ESWTR is promulgated, or that intend to grandfather 2 or more years of previously collected data and also conduct new monitoring under the rule, are required to submit the previously collected data to EPA within 8 months following promulgation. This will allow these utilities to continue to collect previously collected data in the 6 month period between promulgation and the date when monitoring under the LT2ESWTR must begin, plus a 2 month period for systems to compile the data and supporting documentation. Utilities may submit the data earlier than 8 months after promulgation if they acquire 2 years of previously collected data before this date.

Submitted grandfathered data sets must include all routine source water monitoring results for samples collected during the time period covered by the

grandfathered data set (*i.e.*, the time period between collection of the first and last samples in the data set). However, systems are not required under the LT2ESWTR to submit previously collected data for samples outside of this time period.

3. Request for Comment

EPA requests comments on all aspects of the monitoring and treatment requirements proposed in this section. In addition, EPA requests comment on the following issues:

Requirements for Systems That Use Surface Water for Only Part of the Year

Bin classification for the LT2ESWTR is based on the mean annual sourcewater *Cryptosporidium* level. Consequently, today's proposal requires *E. coli* and *Cryptosporidium* monitoring to be conducted over the full year. However, EPA recognizes that some systems use surface water for only part of the year. This occurs with systems that use surface water for part of the year (*e.g.*, during the summer) to supplement ground water sources and with systems like campgrounds that are in operation for only part of the year. Year round monitoring for these systems may present both logistic and economic difficulties. EPA is requesting comment on how to apply LT2ESWTR monitoring requirements to surface water systems that operate or use surface water for only part of the year. Possible approaches that may be considered for comment include the following:

Small public water systems that operate or use surface water for only part of the year could be required to collect *E. coli* samples at least bi-weekly during the period when they use surface water. If the mean *E. coli* concentration did not exceed the trigger level (*e.g.*, 10/100 mL for reservoirs/lakes or 50/100mL for flowing streams), systems could apply to the State to waive any additional *E. coli* monitoring. The State could grant the waiver, require additional *E. coli* monitoring, or require monitoring of an alternate indicator. If the mean *E. coli* concentration exceeded the trigger level, the State could require the system to provide additional treatment for *Cryptosporidium* consistent with Bin 4 requirements, or require monitoring of *Cryptosporidium* or an indicator, with the results potentially leading to additional *Cryptosporidium* treatment requirements.

Large public water systems that operate or use surface water for only part of the year could be required to collect *Cryptosporidium* samples (along with *E. coli* and turbidity) either twice-

per-month during the period when they use surface water or 12 samples per year, whichever is smaller. Samples would be collected during the two years of the required monitoring period, and bin classification would be based on the highest average of the two years.

EPA requests comment on these and other approaches for both small and large systems.

Previously Collected Monitoring Data That Do Not Meet QC Requirements

EPA is proposing requirements for acceptance of previously collected monitoring data that are equivalent to requirements for data generated under the LT2ESWTR. The Agency is aware that systems will have previously collected *Cryptosporidium* data that do not meet all sampling and analysis requirements (*e.g.*, quality control, sample frequency, sample volume) proposed for data collected under the LT2ESWTR. However, the Agency has been unable to develop an approach for allowing systems to use such data for LT2ESWTR bin classification. This is due to uncertainty regarding the impact of deviations from proposed sampling and analysis requirements on data quality and reliability. For example, Methods 1622 and 1623 have been validated within the limits of the QC criteria specified in these methods. While very minor deviations from required QA/QC criteria may have only a minor impact on data quality, the Agency has not identified a basis for establishing alternative standards for data acceptability.

EPA requests comment on whether or under what conditions previously collected data that do not meet the proposed criteria for LT2ESWTR monitoring data should be accepted for use in bin determination. Specifically, EPA requests comment on the sampling frequency requirement for previously collected data, and whether EPA should allow samples collected at lower or varying frequencies to be used as long as the data are representative of seasonal variation and include the required number of samples. If so, how should EPA determine whether such a data set is unbiased and representative of seasonal variation? How should data collected at varying frequency be averaged?

Monitoring for Systems That Recycle Filter Backwash

Plants that recycle filter backwash water may, in effect, increase the concentration of *Cryptosporidium* in the water that enters the filtration treatment train. Under the LT2ESWTR proposal, microbial sampling may be conducted

on source water prior to the addition of filter backwash water. EPA requests comment on how the effect of recycling filter backwash should be considered in LT2ESWTR monitoring.

Bin Assignment for Systems That Fail To Complete Required Monitoring

Today's proposal classifies systems that fail to complete required monitoring in Bin 4, the highest treatment bin. EPA requests comment on alternative approaches for systems that fail to complete required monitoring, such as classifying the system in a bin based on data the system has collected, or classifying the system in a bin one level higher than the bin indicated by the data the system has collected. The shortcoming to these alternative approaches is that bin classification becomes more uncertain, and the likelihood of bin misclassification increases, as systems collect fewer than the required 24 *Cryptosporidium* samples. Consequently, the proposed approach is for systems to collect all required samples.

Note that under today's proposal, systems may provide 5.5 log of treatment for *Cryptosporidium* (*i.e.*, comply with Bin 4 requirements) as an alternative to monitoring. Where systems notify the State that they will provide treatment instead of monitoring, they will not incur monitoring violations.

Monitoring Requirements for New Plants and Sources

The proposed LT2ESWTR would establish calendar dates when the initial and second round of source water monitoring must be conducted to determine bin classification. EPA recognizes that new plants will begin operation, and that existing plants will access new sources, after these dates. EPA believes that new plants and plants switching sources should conduct monitoring equivalent to that required of existing plants to determine the required level of *Cryptosporidium* treatment. The monitoring could be conducted before a new plant or source is brought on-line, or initiated within some time period afterward. EPA requests comment on monitoring and treatment requirements for new plants and sources.

Determination of LT2ESWTR Bin Classification

In today's proposal, EPA expects that systems will be assigned to LT2ESWTR risk bins based on their reported *Cryptosporidium* monitoring results and the calculations proposed for bin

assignment described in this section. EPA requests comment on whether bin classifications should formally be made or reviewed by States.

Source Water Type Classification for Systems That Use Multiple Sources

In today's proposal, the *E. coli* concentrations that trigger small system *Cryptosporidium* monitoring are different for systems using lake/reservoir and flowing stream sources. However, EPA recognizes that some systems use multiple sources, potentially including both lake/reservoir and flowing stream sources, and that the use of different sources may vary during the year. Further, some systems use sources that are ground water under the direct influence (GWUDI) of surface water. EPA requests comment on how to apply the *E. coli* criteria for triggering *Cryptosporidium* monitoring to systems using multiple sources and GWUDI sources.

B. Unfiltered System Treatment Technique Requirements for *Cryptosporidium*

1. What Is EPA Proposing Today?

a. *Overview.* EPA is proposing treatment technique requirements for *Cryptosporidium* in unfiltered systems. Today's proposal requires all unfiltered systems using surface water or ground water under the direct influence of surface water to achieve at least 2 log (99%) inactivation of *Cryptosporidium* prior to the distribution of finished water. Further, unfiltered systems must monitor for *Cryptosporidium* in their source water, and where monitoring demonstrates a mean level above 0.01 oocysts/L, systems must provide at least 3 log *Cryptosporidium* inactivation. Disinfectants that can be used to meet this treatment requirement include ozone, ultraviolet (UV) light, and chlorine dioxide.

All current requirements for unfiltered systems under 40 CFR 141.71 and 141.72(a) remain in effect, including requirements to inactivate at least 3 log of *Giardia lamblia* and 4 log of viruses. In addition, unfiltered systems must meet their overall disinfection requirements using a minimum of two disinfectants. These proposed requirements reflect recommendations of the Stage 2 M-DBP Federal Advisory Committee. Details of the proposed requirements are described in the following sections.

b. *Monitoring requirements.* Requirements for *Cryptosporidium* monitoring by unfiltered systems are similar to requirements for filtered systems of the same size, as given in

section IV.A.1. Unfiltered systems serving at least 10,000 people must sample their source water for *Cryptosporidium* at least monthly for two years, beginning no later than 6 months after promulgation of this rule. Samples may be collected more frequently (e.g., semi-monthly, weekly) as long as a consistent frequency is maintained throughout the monitoring period.

Unfiltered systems serving fewer than 10,000 people must conduct source water sampling for *Cryptosporidium* at least twice-per-month for one year, beginning no later than 4 years following promulgation of this rule (i.e., on the same schedule as small filtered systems). However, unlike small filtered systems, small unfiltered systems cannot monitor for an indicator (e.g., *E. coli*) to determine if they are required to monitor for *Cryptosporidium*. EPA has not identified indicator criteria that can effectively screen for plants with *Cryptosporidium* concentrations below 0.01 oocysts/L. Consequently, all small unfiltered systems must conduct *Cryptosporidium* monitoring.

As described in section IV.K and IV.L, *Cryptosporidium* analyses must be performed on at least 10 L per sample with EPA Methods 1622 or 1623, and must be conducted by laboratories approved for these methods by EPA. Analysis of larger sample volumes is allowed, provided the laboratory has demonstrated comparable method performance to that achieved on a 10 L sample. Section IV.J describes requirements for reporting sample analysis results. All *Cryptosporidium* samples must be collected in accordance with a schedule that is developed by the system and submitted to EPA or the State at least 3 months prior to initiation of sampling. Refer to section IV.A.1 for requirements pertaining to any failure to report a valid sample analysis result for a scheduled sampling date and procedures for collecting a replacement sample.

Unfiltered systems are required to participate in future *Cryptosporidium* monitoring on the same schedule as filtered systems of the same size. Future monitoring requirements for filtered systems are described in section IV.A.1.

Unfiltered systems are not required to conduct source water *Cryptosporidium* monitoring under the LT2ESWTR if the system currently provides or will provide a total of at least 3 log *Cryptosporidium* inactivation, equivalent to meeting the treatment requirements for unfiltered systems with a mean *Cryptosporidium* concentration of greater than 0.01

oocysts/L. Systems must notify the State not later than the date the system is otherwise required to submit a sampling schedule for monitoring. Systems must install and operate technologies to provide a total of at least 3 log *Cryptosporidium* inactivation by the applicable date in Table IV-24.

c. *Treatment requirements.* All unfiltered systems must provide treatment for *Cryptosporidium*, and the degree of required treatment depends on the level of *Cryptosporidium* in the source water as determined through monitoring. Unfiltered systems must calculate their average source water *Cryptosporidium* concentration using the arithmetic mean of all samples collected during the required two year monitoring period (or one year monitoring period for small systems). For unfiltered systems with mean source water *Cryptosporidium* levels of less than or equal to 0.01 oocysts/L, 2 log *Cryptosporidium* inactivation is required. Where the mean source water level is greater than 0.01 oocysts/L, 3 log inactivation is required.

In addition, unfiltered systems are required to use at least two different disinfectants to meet their overall inactivation requirements for viruses (4 log), *Giardia lamblia* (3 log), and *Cryptosporidium* (2 or 3 log). Further, each of the two disinfectants must achieve by itself the total inactivation required for one of these three pathogen types. For example, a system could use UV light to achieve 2 log inactivation of *Cryptosporidium* and *Giardia lamblia*, and use chlorine to inactivate 1 log *Giardia lamblia* and 4 log viruses. In this case, chlorine would achieve the total inactivation required for viruses while UV light would achieve the total inactivation required for *Cryptosporidium*, and the two disinfectants together would meet the overall treatment requirements for viruses, *Giardia lamblia*, and *Cryptosporidium*. In all cases unfiltered systems must continue to meet disinfectant residual requirements for the distribution system.

EPA has developed criteria, described in sections IV.C.14-15, for systems to determine *Cryptosporidium* inactivation credits for chlorine dioxide, ozone, and UV light. Unfiltered systems are allowed to use any of these disinfectants to meet the 2 (or 3) log *Cryptosporidium* inactivation requirement. The following paragraphs describe standards for demonstrating compliance with the proposed *Cryptosporidium* treatment technique requirement. For systems using ozone and chlorine dioxide, these standards are similar to current standards for compliance with *Giardia*

lamblia and virus treatment requirements, as established by the SWTR in 40 CFR 141.72 and 141.74. However, for systems using UV light, modified compliance standards are proposed, due to the different way in which UV disinfection systems will be monitored.

Each day a system using ozone or chlorine dioxide serves water to the public, the system must calculate the CT value(s) from the system's treatment parameters, using the procedures specified in 40 CFR 141.74(b)(3). The system must determine whether this value(s) is sufficient to achieve the required inactivation of *Cryptosporidium* based on the CT criteria specified in section IV.C.14. The disinfection treatment must ensure at least 99 percent (or 99.9 percent if required) inactivation of *Cryptosporidium* every day the system serves water to the public, except any one day each month. Systems are required to report daily CT values on a monthly basis, as described in section IV.J.

Each day a system using UV light serves water to the public, the system must monitor for the parameters, including flow rate and UV intensity, that demonstrate whether the system's UV reactors are operating within the range of conditions that have been validated to achieve the required UV dose, as specified in section IV.C.15. Systems must monitor each UV reactor while in use and must record periods when any reactor operates outside of validated conditions. The disinfection treatment must ensure at least 99 percent (or 99.9 percent if required) inactivation of *Cryptosporidium* in at least 95 percent of the water delivered to the public every month. Systems are required to report periods when UV reactors operate outside of validated conditions on a monthly basis, as described in section IV.J.

Unfiltered systems currently must comply with requirements for DBPs as a condition of avoiding filtration under 40 CFR 141.71(b)(6). As described earlier, EPA is developing a Stage 2 DBPR, which will further limit allowable levels of certain DBPs, specifically trihalomethanes and haloacetic acids. EPA intends to incorporate new standards for DBPs established under the Stage 2 DBPR into the criteria for filtration avoidance.

2. How Was This Proposal Developed?

a. *Basis for Cryptosporidium treatment requirements.* The intent of the proposed treatment requirements for unfiltered systems is to achieve public health protection against

Cryptosporidium equivalent to filtration systems. As described in section III.C, an assessment of survey data indicates that under current treatment requirements, finished water *Cryptosporidium* levels are higher in unfiltered systems than in filtered systems.

Information Collection Rule data show an average plant-mean *Cryptosporidium* level of 0.59 oocysts/L in the source water of filtered plants and 0.014 oocysts/L in unfiltered systems. Median plant-mean concentrations were 0.052 and 0.0079 oocysts/L in filtered and unfiltered system sources, respectively. Thus, these results suggest that typical *Cryptosporidium* occurrence in filtered system sources is approximately 10 times higher than in unfiltered system sources.

In translating these data to assess finished water risk, EPA and the Advisory Committee estimated that conventional plants in compliance with the IESWTR achieve an average *Cryptosporidium* removal of 3 log (see discussion in section III.D). Hence, if the median source water *Cryptosporidium* level at conventional plants is approximately 10 times higher than at unfiltered systems, and it is estimated that conventional plants achieve an average reduction of 3 log (99.9%), then the median finished water *Cryptosporidium* concentration at conventional plants is lower by a factor of 100 than at unfiltered systems. Therefore, to ensure equivalent public health protection, unfiltered systems should reduce *Cryptosporidium* levels by 2 log.

Due to the development of criteria for *Cryptosporidium* inactivation with ozone, chlorine dioxide, and UV light, EPA has determined that it is feasible for unfiltered systems to comply with a *Cryptosporidium* treatment technique requirement. Consequently, EPA is proposing that all unfiltered systems provide at least 2 log inactivation of *Cryptosporidium*.

The proposed treatment requirements for unfiltered systems with higher source water *Cryptosporidium* levels are consistent with proposed treatment requirements for filtered systems. As discussed previously, EPA is proposing that filtered plants with mean source water *Cryptosporidium* levels between 0.075 and 1.0 oocysts/L, as measured by Methods 1622 and 1623, provide at least a 4 log reduction (with greater treatment required for higher source water pathogen levels). These requirements will achieve average treated water *Cryptosporidium* concentrations below 1 oocyst/10,000 L in filtered systems. An unfiltered system with a mean

source water *Cryptosporidium* concentration above 0.01 oocyst/L would need to provide more than 2 log inactivation in order to achieve an equivalent finished water oocyst level. Therefore, EPA is proposing that unfiltered systems provide at least 3 log inactivation where mean concentrations exceed 0.01 oocysts/L.

For unfiltered systems using UV disinfection to meet these proposed *Cryptosporidium* treatment requirements, EPA is proposing that compliance be based on a 95th percentile standard (*i.e.*, at least 95 percent of the water must be treated to the required UV dose). This standard is intended to be comparable with the "every day except any one day per month" compliance standard established by the SWTR for chemical disinfection (see 40 CFR 141.72(a)(1)). Because UV disinfection systems will typically consist of multiple parallel reactors that will be monitored continuously, the Agency has determined that it is more appropriate to base a compliance determination on the percentage of water disinfected to the required level, rather than a single daily measurement. The UV Disinfection Guidance Manual (USEPA 2003d) will provide advice on meeting this proposed standard. A draft of this guidance is available in the docket for today's proposal (<http://www.epa.gov/edocket/>).

b. *Basis for requiring the use of two disinfectants.* EPA is proposing that unfiltered systems use at least two different disinfectants to meet the 2 (or 3), 3, and 4 log inactivation requirements for *Cryptosporidium*, *Giardia lamblia*, and viruses, respectively. The purpose of this requirement is to provide for multiple barriers of protection against pathogens. One benefit of this approach is that if one barrier were to fail then there would still be one remaining barrier to provide protection against some of the pathogens that might be present. For example, if a plant used UV to inactivate *Cryptosporidium* and *Giardia lamblia*, along with chlorine to inactivate viruses, and the UV system were to malfunction, the chlorine would still meet the treatment requirement for viruses and would provide some degree of protection against *Giardia lamblia*.

Another benefit of multiple barriers is that they will typically provide more effective protection against a broad spectrum of pathogens than a single disinfectant. Because the efficacy of disinfectants against different pathogens varies widely, using multiple disinfectants will generally provide more efficient inactivation of a wide

range of pathogens than a single disinfectant.

EPA is aware, though, that this requirement would not result in a redundant barrier for each type of pathogen. In the example of a plant using chlorine and UV, the chlorine would provide essentially no protection against *Cryptosporidium* and might achieve only a small amount of *Giardia lamblia* inactivation if it was designed primarily to inactivate viruses. However, since the watersheds of unfiltered systems are required to be protected (40 CFR 141.71), the probability is low that high levels of *Cryptosporidium* or *Giardia lamblia* would occur during the time frame necessary to address a short period of treatment failure.

Note the request for comment on this topic at the end of this section.

c. *Basis for source water monitoring requirements.* Monitoring by unfiltered systems is necessary to identify those with mean source water *Cryptosporidium* levels above 0.01 oocysts/L. In order to allow for simultaneous compliance with other microbial and disinfection byproduct regulatory requirements, EPA is proposing that unfiltered systems monitor for *Cryptosporidium* on the same schedule as filtered systems of the same size. Because EPA was not able to identify indicator criteria, such as *E. coli*, that can discriminate among systems above and below a mean *Cryptosporidium* concentration of 0.01 oocysts/L, EPA is proposing that all unfiltered systems monitor for *Cryptosporidium*.

Consistent with requirements for filtered systems, unfiltered systems are required to analyze at least 24 samples of at least 10 L over the two year monitoring period (one year for small systems). However, if an unfiltered system collected and analyzed only 24 samples of 10 L then a total count of 3 oocysts among all samples would result in a source water concentration exceeding 0.01 oocysts/L. To avoid a relatively small number of counts determining an additional treatment implication, unfiltered systems may consider conducting more frequent sampling or analyzing larger sample volumes (e.g., 50 L). Since the water sources of unfiltered systems tend to have very low turbidity (compared to average sources in filtered systems), it is typically more feasible to analyze larger sample volumes in unfiltered systems. Filters have been approved for *Cryptosporidium* analysis of 50 L samples. Note that analysis of larger sample volumes would not reduce the required sampling frequency.

3. Request for Comment

EPA solicits comment on the proposed monitoring and treatment technique requirements for unfiltered systems. Specifically, the Agency seeks comment on the following issues:

Use of Two Disinfectants

EPA requests comment on the proposed requirement for unfiltered systems to use two disinfectants and for each disinfectant to meet by itself the inactivation requirement for at least one regulated pathogen. The requirement for unfiltered systems to use two disinfectants was recommended by the Advisory Committee because (1) disinfectants vary in their efficacy against different pathogens, so that the use of multiple disinfectants can provide more effective protection against a broad spectrum of pathogens, and (2) multiple disinfectants provide multiple barriers of protection, which can be more reliable than a single disinfectant.

An alternate approach would be to allow systems to meet the inactivation requirements using any combination of one or more disinfectants that achieved the required inactivation level for all pathogens. This would give systems greater flexibility and could spur the development of new disinfection techniques that would be applicable to a wide range of pathogens. However, this approach might be less protective against unregulated pathogens. A related question is whether the proposed requirements for use of two disinfectants establish an adequate level of multiple barriers in the treatment provided by unfiltered systems.

Treatment Requirements for Unfiltered Systems With Higher *Cryptosporidium* Levels

Under the proposed LT2ESWTR, a filtered system that measures a mean source water *Cryptosporidium* level of 0.075 oocysts/L or higher is required to provide a total of 4 log or more reduction of *Cryptosporidium*. However, if an unfiltered system, meeting the criteria for avoiding filtration were to measure *Cryptosporidium* at this level, it would be required to provide only 3 log treatment. Available occurrence data indicate that very few, if any, unfiltered systems will measure mean source water *Cryptosporidium* concentrations above 0.075 oocysts/L. However, EPA requests comment on whether or how this possibility should be addressed.

C. Options for Systems To Meet *Cryptosporidium* Treatment Requirements

1. Microbial Toolbox Overview

The LT2ESWTR proposal contains a list of treatment processes and management practices for water systems to use in meeting additional *Cryptosporidium* treatment requirements under the LT2ESWTR. This list, termed the microbial toolbox, was recommended by the Stage 2 M-DBP Advisory Committee in the Agreement in Principle. Components of the microbial toolbox include watershed control programs, alternative sources, pretreatment processes, additional filtration barriers, inactivation technologies, and enhanced plant performance. The intent of the microbial toolbox is to provide water systems with broad flexibility in selecting cost-effective LT2ESWTR compliance strategies. Moreover, the toolbox allows systems that currently provide additional pathogen barriers or that can demonstrate enhanced performance to receive additional *Cryptosporidium* treatment credit.

A key feature of the microbial toolbox is that many of the components carry presumptive credits towards *Cryptosporidium* treatment requirements. Plants will receive these credits for toolbox components by demonstrating compliance with required design and implementation criteria, as described in the sections that follow. Treatment credit greater than the presumptive credit may be awarded for a toolbox component based on a site-specific or technology-specific demonstration of performance, as described in section IV.C.17.

While the Advisory Committee made recommendations for the degree of presumptive treatment credit to be granted to different toolbox components, the Committee did not specify the design and implementation conditions under which the credit should be awarded. EPA has identified and is proposing such conditions in today's notice, based on an assessment of available data. For certain toolbox components, such as raw water storage and roughing filters, the Agency concluded that available data do not support the credit recommended by the Advisory Committee. Consequently, EPA is not proposing a presumptive credit for these options.

For each microbial toolbox component, EPA is requesting comment on: (1) Whether available data support the proposed presumptive credits, including the design and implementation conditions under which

the credit would be awarded, (2) whether available data are consistent with the decision not to award presumptive credit for roughing filters and raw water off-stream storage, and (3) whether additional data are available on treatment effectiveness of toolbox components for reducing *Cryptosporidium* levels. EPA will consider modifying today's proposal for microbial toolbox components based on new information that may be provided.

EPA particularly solicits comment on the performance of alternative filtration technologies that are currently being used, as well as ones that systems are considering for use in the future, specifically including bag filters,

cartridge filters, and bank filtration, in removing *Cryptosporidium*. The Agency requests both laboratory and field data that will support a determination of the appropriate level of *Cryptosporidium* removal credit to award to these technologies. In addition, the Agency requests information on the applicability of these technologies to different source water types and treatment scenarios. Data submitted in response to this request for comment should include, where available, associated quality assurance and cost information. This preamble discusses bank filtration in section IV.C.6 and bag and cartridge filters in section IV.C.12.

Table IV-7 summarizes presumptive credits and associated design and implementation criteria for microbial toolbox components. Each component is then described in more detail in the sections that follow. EPA is also developing guidance to assist systems with implementing toolbox components. Pertinent guidance documents include: UV Disinfection Guidance Manual (USEPA 2003d), Membrane Filtration Guidance Manual (USEPA 2003e), and Toolbox Guidance Manual (USEPA 2003f). Each is available in draft form in the docket for today's proposal (<http://www.epa.gov/edocket/>).

TABLE IV-7.—MICROBIAL TOOLBOX: PROPOSED OPTIONS, LOG CREDITS, AND DESIGN/IMPLEMENTATION CRITERIA¹

Toolbox option	Proposed <i>Cryptosporidium</i> log credit with design and implementation criteria ¹
Watershed control program	0.5 log credit for State-approved program comprising EPA specified elements. Does not apply to unfiltered systems.
Alternative source/Intake management	No presumptive credit. Systems may conduct simultaneous monitoring for LT2ESWTR bin classification at alternative intake locations or under alternative intake management strategies.
Off-stream raw water storage	No presumptive credit. Systems using off-stream storage must conduct LT2ESWTR sampling after raw water reservoir to determine bin classification.
Pre-sedimentation basin with coagulation	0.5 log credit with continuous operation and coagulant addition; basins must achieve 0.5 log turbidity reduction based on the monthly mean of daily measurements in 11 of the 12 previous months; all flow must pass through basins. Systems using existing pre-sed basins must sample after basins to determine bin classification and are not eligible for presumptive credit.
Lime softening	0.5 log additional credit for two-stage softening (single-stage softening is credited as equivalent to conventional treatment). Coagulant must be present in both stages—includes metal salts, polymers, lime, or magnesium precipitation. Both stages must treat 100% of flow.
Bank filtration (as pretreatment)	0.5 log credit for 25 ft. setback; 1.0 log credit for 50 ft. setback; aquifer must be unconsolidated sand containing at least 10% fines; average turbidity in wells must be < 1 NTU. Systems using existing wells followed by filtration must monitor well effluent to determine bin classification and are not eligible for presumptive credit.
Combined filter performance	0.5 log credit for combined filter effluent turbidity ≤ 0.15 NTU in 95% of samples each month.
Roughing filters	No presumptive credit proposed.
Slow sand filters	2.5 log credit as a secondary filtration step; 3.0 log credit as a primary filtration process. No prior chlorination.
Second stage filtration	0.5 log credit for second separate filtration stage; treatment train must include coagulation prior to first filter. No presumptive credit for roughing filters.
Membranes	Log credit equivalent to removal efficiency demonstrated in challenge test for device if supported by direct integrity testing.
Bag filters	1 log credit with demonstration of at least 2 log removal efficiency in challenge test.
Cartridge filters	2 log credit with demonstration of at least 3 log removal efficiency in challenge test.
Chlorine dioxide	Log credit based on demonstration of log inactivation using CT table.
Ozone	Log credit based on demonstration of log inactivation using CT table.
UV	Log credit based on demonstration of inactivation with UV dose table; reactor testing required to establish validated operating conditions.
Individual filter performance	1.0 log credit for demonstration of filtered water turbidity < 0.1 NTU in 95 percent of daily max values from individual filters (excluding 15 min period following backwashes) and no individual filter > 0.3 NTU in two consecutive measurements taken 15 minutes apart.
Demonstration of performance	Credit awarded to unit process or treatment train based on demonstration to the State, through use of a State-approved protocol.

¹ Table provides summary information only; refer to following preamble and regulatory language for detailed requirements.

2. Watershed Control Program

a. *What is EPA proposing today?* EPA is proposing a 0.5 log credit towards *Cryptosporidium* treatment requirements under the LT2ESWTR for

filtered systems that develop a State-approved watershed control program designed to reduce the level of *Cryptosporidium*. The watershed control program credit can be added to

the credit awarded for any other toolbox component. However, this credit is not available to unfiltered systems, as they are currently required under 40 CFR 141.171 to maintain a watershed control

program that minimizes the potential for contamination by *Cryptosporidium* as a criterion for avoiding filtration.

There are many potential sources of *Cryptosporidium* in watersheds, including sewage discharges and non-point sources associated with animal feces. The feasibility, effectiveness, and sustainability of control measures to reduce *Cryptosporidium* contamination of water sources will be site-specific. Consequently, the proposed watershed control program credit centers on systems working with stakeholders in the watershed to develop a site-specific program, and State review and approval are required. In the Toolbox Guidance Manual (USEPA 2003f), available in draft in the docket for today's proposal, EPA provides information on management practices that systems may consider in developing their watershed control programs.

Initial State approval of a system's watershed control program will be based on State review of the system's proposed watershed control plan and supporting documentation. The initial approval can be valid until the system completes the second round of *Cryptosporidium* monitoring described in section IV.A (systems begin a second round of monitoring six years after the initial bin assignment). During this period, the system is responsible for implementing the approved plan and complying with other general requirements, such as an annual watershed survey and program status report. These requirements are further described later in this section.

The period during which State approval of a watershed control program is in effect is referred to as the approval period. Systems that want to continue their eligibility to receive the 0.5 log *Cryptosporidium* treatment credit must reapply for State approval of the program for each subsequent approval period. In general, the re-approval will be based on the State's review of the system's reapplication package, as well as the annual status reports and watershed surveys. Subsequent approval(s) by the State of the watershed control program typically will be for a time equivalent to the first approval period, but States have the discretion to renew approval for a longer or shorter time period.

Requirements for Initial State Approval of Watershed Control Programs

Systems that intend to pursue a 0.5 log *Cryptosporidium* treatment credit for a watershed control program are required to notify the State within one year following initial bin assignment that the system proposes to develop a

watershed control plan and submit it for State approval.

The application to the State for initial program approval must include the following minimum elements:

- An analysis of the vulnerability of each source to *Cryptosporidium*. The vulnerability analysis must address the watershed upstream of the drinking water intake, including: A characterization of the watershed hydrology, identification of an "area of influence" (the area to be considered in future watershed surveys) outside of which there is no significant probability of *Cryptosporidium* or fecal contamination affecting the drinking water intake, identification of both potential and actual sources of *Cryptosporidium* contamination, the relative impact of the sources of *Cryptosporidium* contamination on the system's source water quality, and an estimate of the seasonal variability of such contamination.

- An analysis of control measures that could address the sources of *Cryptosporidium* contamination identified during the vulnerability analysis. The analysis of control measures must address their relative effectiveness in reducing *Cryptosporidium* loading to the source water and their sustainability.
- A plan that specifies goals and defines and prioritizes specific actions to reduce source water *Cryptosporidium* levels. The plan must explain how actions are expected to contribute to specified goals, identify partners and their role(s), present resource requirements and commitments including personnel, and include a schedule for plan implementation.

The proposed watershed control plan and a request for program approval and 0.5 log *Cryptosporidium* treatment credit must be submitted by the system to the State no later than 24 months following initial bin assignment.

The State will review the system's initial proposed watershed control plan and either approve, reject, or "conditionally approve" the plan. If the plan is approved, or if the system agrees to implementing the State's conditions for approval, the system will be awarded 0.5 log credit towards LT2ESWTR *Cryptosporidium* treatment requirements. A final decision on approval must be made no later than three years following the system's initial bin assignment.

The initial State approval of the system's watershed control program can be valid until the system completes the required second round of *Cryptosporidium* monitoring. The system is responsible for taking the

required steps, described as follows, to maintain State program approval and the 0.5 log credit during the approval period.

Requirements for Maintaining State Approval of Watershed Control Programs

Systems that have obtained State approval of their watershed control program are required to meet the following ongoing requirements within each approval period to continue their eligibility for the 0.5 log

Cryptosporidium treatment credit:

- Submit an annual watershed control program status report to the State during each year of the approval period.
- Conduct an annual State-approved watershed survey and submit the survey report to the State.
- Submit to the State an application for review and re-approval of the watershed control program and for a continuation of the 0.5 log treatment credit for a subsequent approval period.

The annual watershed control program status report must describe the system's implementation of the approved plan and assess the adequacy of the plan to meet its goals. It must explain how the system is addressing any shortcomings in plan implementation, including those previously identified by the State or as the result of the watershed survey. If it becomes necessary during implementation to make substantial changes in its approved watershed control program, the system must notify the State and provide a rationale prior to making any such changes. If any change is likely to reduce the level of source water protection, the system must also include the actions it will take to mitigate the effects in its notification.

The watershed survey must be conducted according to State guidelines and by persons approved by the State to conduct watershed surveys. The survey must encompass the area of the watershed that was identified in the State-approved watershed control plan as the area of influence and, as a minimum, assess the priority activities identified in the plan and identify any significant new sources of *Cryptosporidium*.

The application to the State for review and re-approval of the system's watershed control program must be provided to the State at least six months before the current approval period expires or by a date previously determined by the State. The request must include a summary of activities and issues identified during the previous approval period and a revised

plan that addresses activities for the next approval period, including any new actual or potential sources of *Cryptosporidium* contamination and details of any proposed or expected changes from the existing State-approved program. The plan must address goals, prioritize specific actions to reduce source water *Cryptosporidium*, explain how actions are expected to contribute to achieving goals, identify partners and their role(s), resource requirements and commitments, and the schedule for plan implementation.

The annual program status reports, watershed control plan and annual watershed sanitary surveys must be made available to the public upon request. These documents must be in a plain language format and include criteria by which to evaluate the success of the program in achieving plan goals. If approved by the State, the system may withhold portions of the annual status report, watershed control plan, and watershed sanitary survey based on security considerations.

b. *How was this proposal developed?* The M-DBP Advisory Committee recommended that systems be awarded 0.5 log *Cryptosporidium* treatment credit for implementing a watershed control program. This recommendation was based on the Committee's recognition that some systems will be able to reduce the level of *Cryptosporidium* in their source water by implementing a well-designed and focused watershed control program. Moreover, the control measures used in the watershed to reduce levels of *Cryptosporidium* are likely to reduce concentrations of other pathogens as well.

EPA concurs that well designed watershed control programs that focus on reducing levels of *Cryptosporidium* contamination of water sources should be encouraged, and that implementation of such programs will likely reduce overall microbial risk. A broad reduction in microbial risk will occur through the application of control measures and best management practices that are effective in reducing fecal contamination in the watershed. In addition, plant management practices may be enhanced by the knowledge systems acquire regarding the watershed and factors that affect microbial risk, such as sources, fate, and transport of pathogens.

Given the highly site-specific nature of a watershed control program, including the feasibility and effectiveness of different control measures, EPA believes that systems should demonstrate their eligibility for

0.5 log *Cryptosporidium* treatment credit by developing targeted programs that account for site-specific factors. As part of developing a watershed control program, systems will be required to assess a number of these factors, including watershed hydrology, sources of *Cryptosporidium* in the watershed, human impacts, and fate and transport of *Cryptosporidium*. Furthermore, EPA believes that the State is well positioned to judge whether a system's watershed control program is likely to achieve a substantial reduction of *Cryptosporidium* in source water. Consequently, EPA is proposing that approval of watershed control programs and allowance for an associated 0.5 log treatment credit be made by the State on a system specific basis.

A watershed control program could include measures such as (1) the elimination, reduction, or treatment of wastewater or storm water discharges, (2) treatment of *Cryptosporidium* contamination at the sites of waste generation or storage, (3) prevention of *Cryptosporidium* migration from sources, or (4) any other measures that are effective, sustainable, and likely to reduce *Cryptosporidium* contamination of source water. EPA recognizes that many public water systems do not directly control the watersheds of their sources of supply. EPA expects that systems will need to develop and maintain partnerships with landowners within watersheds, as well as with State governments and regional agencies that have authority over activities in the watershed that may contribute *Cryptosporidium* to the water supply. Stakeholders that have some level of control over activities that could contribute to *Cryptosporidium* contamination include municipal government and private operators of wastewater treatment plants, livestock farmers and persons who spread manure, individuals with failing septic systems, logging operations, and other government and commercial organizations.

EPA has initiated a number of programs that address watershed management and source water protection. In 2002, EPA launched the Watershed Initiative (67 FR 36172, May 23, 2002) (USEPA 2002b), which will provide grants to support innovative watershed based approaches to preventing, reducing, and eliminating water pollution. In addition, EPA has recently promulgated new regulations for Concentrated Animal Feeding Operations (CAFOs), which through the NPDES permit process will limit discharges that contribute microbial pathogens to watersheds.

SDWA section 1453 requires States to carry out a source water quality assessment program for the protection and benefit of public water systems. EPA issued program guidance in August of 1997, and expects that most States will complete their source water assessments of surface water systems by the end of 2003. These assessments will establish a foundation for watershed vulnerability analyses by providing the preliminary analyses of watershed hydrology, a starting point for defining the area of influence, and an inventory and hierarchy of actual and potential contamination sources. In some cases, these portions of the source water assessment may fully satisfy those analytical needs.

As noted earlier, EPA has published and is continuing to develop guidance material that addresses contamination by *Cryptosporidium* and other pathogens from both non-point sources (e.g., agricultural and urban runoff, septic tanks) and point sources (e.g., sewer overflows, POTWs, CAFOs). The Toolbox Guidance Manual, available in draft with today's proposal, includes a list of programmatic resources and guidance available to assist systems in building partnerships and implementing watershed protection activities. In addition, this guidance manual incorporates available information on the effectiveness of different control measures to reduce *Cryptosporidium* levels and provides case studies of watershed control programs. This guidance is intended to assist water systems in developing their watershed control programs and States in their assessment and approval of these programs.

In addition to guidance documents, demonstration projects, and technical resources, EPA provides funding for watershed and source water protection through the Drinking Water State Revolving Fund (DWSRF) and Clean Water State Revolving Fund (CWSRF). Under the DWSRF program, States may provide funding directly to public water systems for source water protection, including watershed management and pathogen source reduction plans. CWSRF funds have been used to develop and implement agricultural best management practices for reducing pathogen loading to receiving waters and to fund directly, or provide incentives for, the replacement of failing septic systems. EPA encourages the use of CWSRF for source protection and has developed guidelines for the award of funds to address non-point sources of pollution (CWA section 319 Non Point Source Pollution Program). Further, the Agency is promoting the broader use of

SRF funds to implement measures to prevent and control non-point source pollution. Detailed sanitary surveys, with a specific analysis of sources of *Cryptosporidium* in the watershed, will facilitate the process of targeting funding available under SRF programs to eliminate or mitigate these sources.

c. *Request for comment.* EPA requests comment on the proposed watershed control program credit and associated program components.

- Should the State be allowed to reduce the frequency of the annual watershed survey requirement for certain systems if systems engage in alternative activities like public outreach?

- The effectiveness of a watershed control program may be difficult to assess because of uncertainty in the efficacy of control measures under site-specific conditions. In order to provide constructive guidance, EPA welcomes reports on scientific case studies and research that evaluated methods for reducing *Cryptosporidium* contamination of source waters.

- Are there confidential business information (CBI) concerns associated with making information on the watershed control program available to the public? If so, what are these concerns and how should they be addressed?

- How should the “area of influence” (the area to be considered in future watershed surveys) be delineated, considering the persistence of *Cryptosporidium*?

3. Alternative Source

a. *What is EPA proposing today?* Plant intake refers to the works or structures at the head of a conduit through which water is diverted from a source (e.g., river or lake) into the treatment plant. Plants may be able to reduce influent *Cryptosporidium* levels by changing the intake placement (either within the same source or to an alternate source) or managing the timing or level of withdrawal.

Because the effect of changing the location or operation of a plant intake on influent *Cryptosporidium* levels will be site specific, EPA is not proposing any presumptive credit for this option. Rather, if a system is concerned that *Cryptosporidium* levels associated with the current plant intake location and/or operation will result in a bin assignment requiring additional treatment under the LT2ESWTR, the system may conduct concurrent *Cryptosporidium* monitoring reflecting a different intake location or different intake management strategy. The State will then make a determination as to whether the plant

may be classified in an LT2ESWTR bin using the alternative intake location or management monitoring results.

Thus, systems that intend to be classified in an LT2ESWTR bin based on a different intake location or management strategy must conduct concurrent *Cryptosporidium* monitoring. The system is still required to monitor its current plant intake in addition to any alternative intake location/management monitoring, and must submit the results of all monitoring to the State. In addition, the system must provide the State with supporting information documenting the conditions under which the alternative intake location/management samples were collected. The concurrent monitoring must conform to the sample frequency, sample volume, analytical method, and other requirements that apply to the system for *Cryptosporidium* monitoring as stated in Section IV.A.1.

If a plant's LT2ESWTR bin classification is based on monitoring results reflecting a different intake location or management strategy, the system must relocate the intake or implement the intake management strategy within the compliance time frame for the LT2ESWTR, as specified in section IV.F.

b. *How was this proposal developed?* In the Stage 2 M-DBP Agreement in Principle, the Advisory Committee identified several actions related to the intake which potentially could reduce the concentration of *Cryptosporidium* entering a treatment plant. These actions were included in the microbial toolbox under the heading Alternative Source, and include: (1) Intake relocation, (2) change to alternative source of supply, (3) management of intake to reduce capture of oocysts in source water, (4) managing timing of withdrawal, and (5) managing level of withdrawal in water column.

It is difficult to predict in advance the efficacy of any of these activities in reducing levels of *Cryptosporidium* entering the treatment plant. However, if a system relocates the plant intake or implements a different intake management strategy, it is appropriate for the plant to be assigned to an LT2ESWTR bin using monitoring results reflecting the new intake strategy.

EPA believes that the requirements specified for monitoring to determine bin placement are necessary to characterize a plant's mean source water *Cryptosporidium* level. Consequently, any concurrent monitoring carried out to characterize a different intake location or management strategy should be equivalent. For this reason, the sampling and analysis requirements

which apply to the current intake monitoring also apply to any concurrent monitoring used to characterize a new intake location or management strategy.

EPA also recognizes that if plant's bin assignment is based on a new intake operation strategy then it is important for the plant to continue to use this new strategy in routine operation. Therefore, EPA is proposing that the system document the new intake operation strategy when submitting additional monitoring results to the State and that the State approve that new strategy.

c. *Request for comment.* EPA requests comment on the following issues:

- What are intake management strategies by which systems could reduce levels of *Cryptosporidium* in the plant influent?

- Can representative *Cryptosporidium* monitoring to demonstrate a reduction in oocyst levels be accomplished prior to implementation of a new intake strategy (e.g., monitoring a new source prior to constructing a new intake structure)?

- How should this option be applied to plants that use multiple sources which enter a plant through a common conduit, or which use separate sources which enter the plant at different points?

4. Off-Stream Raw Water Storage

a. *What is EPA proposing today?* Off-stream raw water storage reservoirs are basins located between a water source (typically a river) and the coagulation and filtration processes in a treatment plant. EPA is not proposing presumptive treatment credit for *Cryptosporidium* removal through off-stream raw water storage. Systems using off-stream raw water storage must conduct *Cryptosporidium* monitoring after the reservoir for the purpose of determining LT2ESWTR bin placement. This will allow reductions in *Cryptosporidium* levels that occur through settling during off-stream storage to be reflected in the monitoring results and consequent LT2ESWTR bin assignment.

The use of off-stream raw water storage reservoirs during LT2ESWTR monitoring must be consistent with routine plant operation and must be recorded by the system. Guidance on monitoring locations is provided in Public Water System Guidance Manual for Source Water Monitoring under the LT2ESWTR (USEPA 2003g), which is available in draft in the docket for today's proposal.

b. *How was this proposal developed?* The Stage 2 M-DBP Agreement in Principle recommends a 0.5 log credit for off-stream raw water storage

reservoirs with detention times on the order of days and 1.0 log credit for reservoirs with detention times on the order of weeks. After a review of the available literature, EPA is unable to determine criteria that provide reasonable assurance of achieving a 0.5 or 1 log removal of oocysts. Consequently, EPA is not proposing a presumptive treatment credit for this process.

This proposal for off-stream raw water storage represents a change from the November 2001 pre-proposal draft of the LT2ESWTR (USEPA 2001g), which described 0.5 log and 1 log presumptive credits for reservoirs with hydraulic detention times of 21 and 60 days, respectively. These criteria were based on a preliminary assessment of reported studies, described later in this section,

that evaluated *Cryptosporidium* and *Giardia* removal in raw water storage reservoirs.

Subsequent to the November 2001 pre-proposal draft, the Science Advisory Board (SAB) reviewed the data that EPA had acquired to support *Cryptosporidium* treatment credits for off-stream raw water storage (see section VII.K). In written comments from a December 2001 meeting of the SAB Drinking Water Committee, the panel concluded that the available data were not adequate to demonstrate the treatment credits for off-stream raw water storage described in the pre-proposal draft, and recommended that no presumptive credits be given for this toolbox option. The panel did agree, though, that a utility should be able to take advantage of off-stream raw water

storage by sampling after the reservoir for appropriate bin placement. EPA concurs with this finding by the SAB and today's proposal is consistent with their recommendation.

Off-stream raw water storage can improve the microbial quality of water in a number of ways. These include (1) reduced microbial and particulate loading to the plant due to settling in the reservoir, (2) reduced viability of pathogens due to die-off, and (3) dampening of water quality and hydraulic spikes. EPA has evaluated a number of studies that investigated the removal of *Cryptosporidium* and other microorganisms and particles in raw water storage basins. These studies are summarized in the following paragraphs, and selected results are presented in Table IV-8.

TABLE IV-8.—STUDIES OF *Cryptosporidium* AND GIARDIA REMOVAL FROM OFF-STREAM RAW WATER STORAGE

Researcher	Reservoir	Residence time	Log reductions
Ketelaars et al. 1995	Biesbosch reservoir system: man-made pumped storage (Netherlands).	24 weeks (average)	<i>Cryptosporidium</i> -1.4 <i>Giardia</i> -2.3.
Van Breeman et al. 1998	Biesbosch reservoir system: man-made pumped storage (Netherlands).	24 weeks (average)	<i>Cryptosporidium</i> -2.0 <i>Giardia</i> -2.6.
Bertolucci et al. 1998	PWN (Netherlands)	10 weeks (average)	<i>Cryptosporidium</i> -1.3 <i>Giardia</i> -0.8.
	Abandoned gravel quarry used for storage (Italy).	18 days (theoretical)	<i>Cryptosporidium</i> -1.0 <i>Giardia</i> -0.8.
Ongerth, 1989	Three impoundments on rivers with limited public access (Seattle, WA).	40, 100 and 200 days (respectively).	No <i>Giardia</i> removal observed.

Ketelaars *et al.* (1995) evaluated *Cryptosporidium* and *Giardia* removal across a series of three man-made pumped reservoirs, named the Biesbosch reservoirs, with reported hydraulic retention times of 11, 9, and 4 weeks (combined retention time of 24 weeks). To prevent algal growth and hypolimnetic deoxygenation, the reservoirs were destratified by air-injection. Based on weekly sampling over one year, mean influent and effluent concentrations of *Cryptosporidium* were 0.10 and 0.004 oocysts/100 L, respectively, indicating an average removal across the three reservoirs of 1.4 log. Mean removal of *Giardia* was 2.3 log.

Van Breeman *et al.* (1998) continued the efforts of Ketelaars *et al.* (1995) in evaluating pathogen removal across the Biesbosch reservoir system. Using a more sensitive analytical method, Van Breeman *et al.* measured mean *Cryptosporidium* levels of 6.3 and 0.064 oocysts/100 L at the inlet and outlet, respectively, indicating an average removal of 2.0 log. For *Giardia*, the

average reduction was 2.6 log. In addition, Van Breeman *et al.* (1998) evaluated removal of *Cryptosporidium*, *Giardia*, and other microorganisms in a reservoir designated PWN, which had a hydraulic retention time of 10 weeks. Passage through this storage reservoir was reported to reduce the mean concentration of *Cryptosporidium* by 1.3 log and of *Giardia* by 0.8 log.

Bertolucci *et al.* (1998) investigated removal of *Cryptosporidium*, *Giardia*, and nematodes in a reservoir derived from an abandoned gravel quarry with a detention time reported as around 18 days. Over a 2 year period, average influent and effluent concentrations of *Cryptosporidium* were 70 and 7 oocysts/100 L, respectively, demonstrating a mean reduction of 1 log. Average *Giardia* levels decreased from 137 cysts/100L in the inlet to 46 cysts/100L at the outlet, resulting in a mean 0.5 log removal.

Ongerth (1989) studied concentrations of *Giardia* cysts in the Tolt, Cedar, and Green rivers, which drain the western slope of the Cascade Mountains in Washington. The watersheds of each

river are controlled by municipal water departments for public water supply, and public access is limited. The Cedar, Green, and Tolt rivers each have impoundments with reported residence times of 100, 30-50, and 200 days, respectively, in the reach studied. Ongerth found no statistically significant difference in cyst concentrations above and below any of the reservoirs. Median cyst concentrations above and below the Cedar, Green, and Tolt reservoirs were reported as 0.12 and 0.22, 0.27 and 0.32, and 0.16 and 0.21 cysts/L, respectively. It is unclear why no decrease in cyst levels was observed. It is possible that contamination of the water in the impoundments by *Giardia* from animal sources, either directly or through runoff, may have occurred.

EPA has also considered results from studies which evaluated the rate at which *Cryptosporidium* oocysts lose viability and infectivity over time. Two studies are summarized next, with selected results presented in Table IV-9.

TABLE IV-9.—STUDIES OF *Cryptosporidium* DIE-OFF DURING RAW WATER STORAGE

Researcher	Type of experiment	Log reduction
Medema <i>et al.</i> 1997	River water was inoculated with <i>Cryptosporidium</i> and bacteria and incubated.	0.5 log reduction over 50 days at 5 °C; 0.5 log reduction over 20–80 days at 15 °C.
Sattar <i>et al.</i> 1999	Synthetic hard water and natural water from several rivers inoculated with <i>Giardia</i> and <i>Cryptosporidium</i> .	<i>In vitro</i> conditions showed 0.7 to 2.0 log reduction over 30 days at 20 °C. Little reduction at 4 °C. <i>In situ</i> conditions showed 0.4 to 1.5 log reduction at 21 days.

Medema *et al.* (1997) conducted bench scale studies of the influence of temperature and the presence of biological activity on the die-off rate of *Cryptosporidium* oocysts. Die-off rates were determined at 5°C and 15°C, and in both natural and sterilized (autoclaved) river water. Both excystation and vital dye staining were used to determine oocyst viability. At 5°C, the die-off rate under all conditions was 0.010 log₁₀/day, assuming first-order kinetics. This translates to 0.5 log reduction at 50 days. At 15°C, the die-off rate in natural river water approximately doubled to 0.024 log₁₀/day (excystation) and 0.018 log₁₀/day (dye staining). However, in autoclaved water at 15°C, the die-off rate was only 0.006 log₁₀/day (excystation) and 0.011 log₁₀/day (dye staining). These results suggest that oocyst die-off is more rapid at higher temperatures in natural water, and this behavior may be caused by increased biological or biochemical activity.

Sattar *et al.* (1999) evaluated factors impacting *Cryptosporidium* and *Giardia* survival. Microtubes containing untreated water from the Grand and St. Lawrence rivers (Ontario) were inoculated with purified oocysts and cysts. Samples were incubated at temperatures ranging from 4°C to 30°C, viability of oocysts and cysts was measured by excystation. At 20°C and 30°C, reductions in viable *Cryptosporidium* oocysts ranged from approximately 0.6 to 2.0 log after 30 days. However, relatively little inactivation took place when oocysts were incubated at 4°C (as low as 0.2 log at 100 days).

To evaluate oocyst survival under dynamic environmental conditions, Sattar *et al.* seeded dialysis cassettes with *Cryptosporidium* oocysts and placed them in overflow tanks receiving water from different rivers in Canada and the United States. Reductions in the concentration of viable oocysts ranged from approximately 0.4 to 1.5 log after 21 days. Survival of oocysts was enhanced by pre-filtering the water, suggesting that microbial antagonism was involved in the natural inactivation of the parasites.

Overall these studies indicate that off-stream storage of raw water has the potential to effect significant reductions in the concentration of viable *Cryptosporidium* oocysts, both through sedimentation and degradation of oocysts (*i.e.*, die-off). However, these data also illustrate the challenge in reliably estimating the amount of removal that will occur in any particular storage reservoir. Removal and die-off rates reported in these studies varied widely, and were observed to be influenced by factors like temperature, contamination, hydraulic short circuiting, and biological activity (Van Breeman *et al.* 1998, Medema *et al.* 1997, Sattar *et al.* 1999). Because of this variability and the relatively small amount of available data, it is difficult to extrapolate from these studies to develop nationally applicable criteria for awarding removal credits to raw water storage.

c. Request for comment. EPA requests comment on the finding that the available data are not adequate to support a presumptive *Cryptosporidium* treatment credit for off-stream raw water storage, and that systems using off-stream storage should conduct LT2ESWTR monitoring at the reservoir outlet. This monitoring approach would account for reductions in oocyst concentrations due to settling, but would not provide credit for die-off, since non-viable oocysts could still be counted during monitoring. In addition, EPA would also appreciate comment on the following specific issues:

- Is additional information available that either supports or suggests modifications to this proposal concerning off-stream raw water storage?
- How should a system address the concern that water in off-stream raw water storage reservoirs may become contaminated through processes like algal growth, run-off, roosting birds, and activities on the watershed?

5. Pre-Sedimentation With Coagulant

a. *What is EPA proposing today?* Presedimentation is a preliminary treatment process used to remove particulate material from the source water before the water enters primary

sedimentation and filtration processes in a treatment plant. EPA is proposing to award a presumptive 0.5 log *Cryptosporidium* treatment credit for presedimentation that is installed after LT2ESWTR monitoring and meets the following three criteria:

(1) The presedimentation basin must be in continuous operation and must treat all of the flow reaching the treatment plant.

(2) The system must continuously add a coagulant to the presedimentation basin.

(3) The system must demonstrate on a monthly basis at least 0.5 log reduction of influent turbidity through the presedimentation process in at least 11 of the 12 previous consecutive months. This monthly demonstration of turbidity reduction must be based on the arithmetic mean of at least daily turbidity measurements in the presedimentation basin influent and effluent, and must be calculated as follows:

$$\text{Monthly mean turbidity log reduction} = \log_{10}(\text{monthly mean of daily influent turbidity}) - \log_{10}(\text{monthly mean of daily effluent turbidity}).$$

If the presedimentation process has not been in operation for 12 months, the system must verify on a monthly basis at least 0.5 log reduction of influent turbidity through the presedimentation process, calculated as specified in this paragraph, for at least all but one of the months of operation.

Systems with presedimentation in place at the time they begin LT2ESWTR *Cryptosporidium* monitoring are not eligible for the 0.5 log presumptive credit and must sample after the basin when in use for the purpose of determining their bin assignment. The use of presedimentation during LT2ESWTR monitoring must be consistent with routine plant operation and must be recorded by the system. Guidance on monitoring is provided in Public Water System Guidance Manual for Source Water Monitoring under the LT2ESWTR (USEPA 2003g), which is available in draft in the docket for today's proposal.

b. *How was this proposal developed?* Presedimentation is used to remove gravel, sand, and other gritty material

from the raw water and dampen particle loading to the rest of the treatment plant. Presedimentation is similar to conventional sedimentation, except that presedimentation may be operated at higher loading rates and may not involve use of chemical coagulants. Also, some systems operate the presedimentation process periodically and only in response to periods of high particle loading.

Because presedimentation reduces particle concentrations, it is expected to reduce *Cryptosporidium* levels. In addition, by dampening variability in source water quality, presedimentation may improve the performance of subsequent treatment processes. In general, the efficacy of presedimentation in lowering particle levels is influenced by a number of water quality and treatment parameters including surface loading rate, temperature, particle concentration, coagulation, and characteristics of the sedimentation basin.

The Stage 2–M–DBP Agreement in Principle recommends 0.5 log presumptive *Cryptosporidium* treatment credit for presedimentation with the use of coagulant. Today’s proposal is consistent with this recommendation. However, the proposed requirement for demonstrated turbidity reduction as a condition for presedimentation credit represents a change from the November 2001 pre-proposal draft of the LT2ESWTR (USEPA 2001g). Rather than a requirement for turbidity removal, the 2001 pre-proposal draft included criteria for maximum overflow rate and minimum influent turbidity as conditions for the 0.5 log presedimentation credit.

The Science Advisory Board (SAB) reviewed the criteria and supporting information for presedimentation credit

in the November 2001 pre-proposal draft (see section VII.K). In written comments from a December 2001 meeting of the SAB Drinking Water Committee, the panel concluded that available data were minimal to support a 0.5 log presumptive credit and recommended that no credit be given for presedimentation. Additionally, the panel stated that performance criteria other than overflow rate need to be included if credit is to be given for presedimentation.

Due to this finding by the SAB, EPA further reviewed data on removal of aerobic spores (as an indicator of *Cryptosporidium* removal) and turbidity in full-scale presedimentation basins. As shown later in this section, these data indicate that presedimentation basins achieving a monthly mean reduction in turbidity of at least 0.5 log have a high likelihood of reducing mean *Cryptosporidium* levels by 0.5 log or more. Consequently, EPA has determined that it is appropriate to use turbidity reduction as a performance criterion for awarding *Cryptosporidium* treatment credit to presedimentation basins. The Agency believes this performance criterion addresses the concerns raised by the SAB.

The Agency has concluded that it is appropriate to limit eligibility for the 0.5 log presumptive *Cryptosporidium* treatment credit to systems that install presedimentation after LT2ESWTR monitoring. Systems with presedimentation in place prior to initiation of LT2ESWTR *Cryptosporidium* monitoring may sample after the presedimentation basin to determine their bin assignment. In this case, the effect of presedimentation in reducing *Cryptosporidium* levels will be reflected in the monitoring results

and bin assignment. Systems that monitor after presedimentation are not subject to the operational and performance requirements associated with the 0.5 log credit. The SAB agreed that a system should be able to sample after the presedimentation treatment process for appropriate bin placement.

In considering criteria for awarding *Cryptosporidium* removal credit to presedimentation, EPA has evaluated both published studies and data submitted by water systems using presedimentation. There is relatively little published data on the removal of *Cryptosporidium* by presedimentation. Consequently, EPA has reviewed studies that investigated *Cryptosporidium* removal by conventional sedimentation basins. These studies are informative regarding potential levels of performance, the influence of water quality parameters, and correlation of *Cryptosporidium* removal with removal of potential surrogates. However, removal efficiency in conventional sedimentation basins may be greater than in presedimentation due to lower surface loading rates, higher coagulant doses, and other factors. To supplement these studies, EPA has evaluated data provided by utilities on removal of other types of particles, primarily aerobic spores, in the presedimentation processes of full scale plants. Data indicate that aerobic spores may serve as a surrogate for *Cryptosporidium* removal by sedimentation (Dugan *et al.* 2001).

i. Published studies of *Cryptosporidium* removal by conventional sedimentation basins. Table IV–10 summarizes results from published studies of *Cryptosporidium* removal by conventional sedimentation basins.

TABLE IV–10.—SUMMARY OF PUBLISHED STUDIES OF *Cryptosporidium* REMOVAL BY CONVENTIONAL SEDIMENTATION BASINS

Author(s)	Plant/process type	<i>Cryptosporidium</i> removal by sedimentation
Dugan <i>et al.</i> (2001)	Pilot scale conventional	0.6 to 1.6 log (average 1.3 log).
States <i>et al.</i> (1997)	Full scale conventional with primary and secondary sedimentation.	0.41 log.
Edzwald and Kelly (1998)	Bench scale sedimentation	0.8 to 1.2 log.
Payment and Franco (1993)	Full scale conventional (2 plants)	3.8 log and 0.7 log.
Kelly <i>et al.</i> (1995)	Full scale conventional (two stage lime softening)	0.8 log.
	Full scale conventional (two stage sedimentation)	0.5 log.
Patania <i>et al.</i> (1995)	Pilot scale conventional (3 plants)	2.0 log (median).

Dugan *et al.* (2001) evaluated the ability of conventional treatment to control *Cryptosporidium* under different water quality and treatment conditions on a small pilot scale plant that had

been demonstrated to provide equivalent performance to a larger plant. Under optimal coagulation conditions, oocyst removal across the sedimentation basin ranged from 0.6 to 1.6 log,

averaging 1.3 log. Suboptimal coagulation conditions (underdosed relative to jar test predictions) significantly reduced plant performance with oocyst removal in the

sedimentation basin averaging 0.20 log. Removal of aerobic spores, total particle counts, and turbidity all correlated well with removal of *Cryptosporidium* by sedimentation.

States *et al.* (1997) monitored *Cryptosporidium* removal at the Pittsburgh Drinking Water Treatment Plant (65–70 million gallons per day (MGD)). The clarification process included ferric chloride coagulation, flocculation, and settling in both a small primary basin and a 120 MG secondary sedimentation basin. Geometric mean *Cryptosporidium* levels in the raw and settled water were 31 and 12 oocysts/100 L, respectively, indicating a mean reduction of 0.41 log.

Edzwald and Kelly (1998) conducted a bench-scale study to determine the optimal coagulation conditions with different coagulants for removing *Cryptosporidium* oocysts from spiked raw waters. Under optimal coagulation conditions, the authors observed oocysts reductions through sedimentation ranging from 0.8 to 1.2 log.

Payment and Franco (1993) measured *Cryptosporidium* and other microorganisms in raw, settled, and filtered water samples from drinking water treatment plants in the Montreal area. The geometric mean of raw and settled water *Cryptosporidium* levels in one plant were 742 and 0.12 oocysts/100 L, respectively, suggesting a mean removal of 3.8 log. In a second plant, mean removal by sedimentation was reported as 0.7 log, with raw and settled water *Cryptosporidium* levels reported as <2 and <0.2 oocysts/L, respectively.

Kelley *et al.* (1995) monitored *Cryptosporidium* levels in the raw, settled, and filtered water of two water treatment plants (designated site A and B). Both plants included two-stage sedimentation. At site A, mean raw and settled water *Cryptosporidium* levels were 60 and 9.5 oocysts/100 L, respectively, suggesting a mean removal of 0.8 log by sedimentation. At site B, mean raw and settled water *Cryptosporidium* levels were 53 and 16 oocysts/100 L, respectively, for an average removal by sedimentation of 0.5 log. Well water was intermittently blended in the second stage of sedimentation at site B, which may have reduced settled and filtered water pathogen levels.

Patania *et al.* (1995) evaluated removal of *Cryptosporidium* in four pilot scale plants. Three of these were conventional and one used in-line filtration (rapid mix followed by filtration). *Cryptosporidium* removal was generally 1.4 to 1.8 log higher in the process trains with sedimentation compared to in-line filtration. While the

effectiveness of sedimentation for organism removal varied widely under the conditions tested, the median removal of *Cryptosporidium* by sedimentation was approximately 2.0 log.

ii. Data supplied by utilities on the removal of spores by presedimentation. Data on the removal of *Cryptosporidium* and spores (*Bacillus subtilis* and total aerobic spores) during operation of full-scale presedimentation basins were collected independently and reported by three utilities: St. Louis, MO, Kansas City, MO, and Cincinnati, OH. *Cryptosporidium* oocysts were not detected in raw water at these locations at levels sufficient to calculate log removals of oocysts directly. However, aerobic spores were present in the raw water of these utilities at high enough concentrations to measure log removals through presedimentation as a surrogate for *Cryptosporidium* removal. As noted earlier, data from Dugan *et al.* (2001) demonstrate a correlation between removal of aerobic spores and *Cryptosporidium* through sedimentation under optimal coagulation conditions. A summary of the spore removal data supplied by these utilities is shown in Table IV–11.

TABLE IV–11.—MEAN SPORE REMOVAL FOR FULL-SCALE PRESEDIMENTATION BASINS REPORTED BY THREE UTILITIES

Reporting utility	Mean spore removal
St. Louis Water Division.	1.1 log (<i>B. subtilis</i>).
Kansas City Water Services Department.	0.8 log (<i>B. subtilis</i>) (with coagulant).
Cincinnati Water Works.	0.46 log (<i>B. subtilis</i>) (without coagulant).
	0.6 log (total aerobic spores).

The St. Louis Water Division operates four presedimentation basins at one facility. Coagulant addition prior to presedimentation includes polymer and occasional dosages of ferric sulfate. *Bacillus subtilis* spore samples were collected from June 1998 to September 2000. Reported mean spore concentrations in the raw water and following presedimentation were 108,326 and 8,132 cfu/100 mL, respectively, showing an average removal of 1.1 log by presedimentation.

The Kansas City Water Services Department collected *Bacillus subtilis* spore samples from January to November 2000 from locations before and after one of the facility's six presedimentation basins. Sludge

generated by the primary clarifier of a softening process was recycled to the head of the presedimentation basins during the entire study period. In addition, coagulant (polymer and/or ferric sulfate) was added prior to presedimentation when raw water turbidity was higher. During periods when coagulant was added, mean spore levels before and after presedimentation were 102,292 and 13,154 cfu/100 mL, respectively, demonstrating a mean removal of 0.9 log. When no ferric sulfate or polymer was used, mean presedimentation influent and effluent spore levels were 13,296 and 4,609 cfu/100 mL, respectively, for an average reduction of 0.46 log.

The Cincinnati Water Works operates a treatment plant using lamella plate settlers for presedimentation. Lamella plate settlers are inclined plates added to a sedimentation basin to significantly increase the surface area available for particle settling. Coagulant (alum and polymer) is added to the raw water prior to presedimentation. Total aerobic spore samples were collected from January 1998 through December 2000. The mean concentration of spores decreased from 20,494 cfu/100 mL in the raw water to 4,693 cfu/100 mL in the presedimentation effluent, indicating a mean spore removal of 0.64 log.

In conclusion, literature studies clearly establish that sedimentation basins are capable of achieving greater than 0.5 log reduction in *Cryptosporidium* levels. Further, the data supplied by utilities on reduction in aerobic spore counts across full scale presedimentation basins demonstrate that presedimentation can achieve mean reductions of greater than 0.5 log under routine operating conditions and over an extended time period. Thus, these data suggest that a 0.5 log presumptive credit for *Cryptosporidium* removal by presedimentation is appropriate under certain conditions.

With respect to the conditions under which the 0.5 log presumptive credit for presedimentation is appropriate, the data do not demonstrate that this level of removal can be achieved consistently without a coagulant. In addition, available data do not establish aerobic spores as an effective indicator of *Cryptosporidium* removal in the absence of a coagulant. Thus, supporting data are consistent with a requirement that systems apply a coagulant to be eligible for the presumptive 0.5 log presedimentation credit. Moreover, such a requirement is consistent with the Agreement in Principle, which recommends 0.5 log credit for presedimentation basins with a coagulant.

EPA also has concluded that presedimentation basins need to be operated continuously and treat 100% of the plant flow in order to reasonably ensure that the process will reduce influent *Cryptosporidium* levels by at least 0.5 log over the course of a full year. The Agency recognizes that, depending on influent water quality, some systems may determine it is more prudent to operate presedimentation basins intermittently in response to fluctuating turbidity levels. By

proposing these conditions for the presumptive presedimentation credit, EPA is not recommending against intermittent operation of presedimentation basins. Rather, EPA is attempting to identify the conditions under which a 0.5 log presumptive credit for presedimentation is warranted.

In response to the SAB panel recommendation that performance criteria other than overflow rate be included if credit is to be given for

presedimentation, EPA analyzed the relationship between removal of spores and reduction in turbidity through presedimentation for the three utilities that supplied these data. Results of this analysis are summarized in Table IV-12, which shows the relationship between monthly mean turbidity reduction and the percent of months when mean spore removal was at least 0.5 log.

BILLING CODE 6560-50-P

Table IV-12.-- Relationship Between Mean Turbidity Reduction and the

Percent of Months When Mean Spore Removal Was at Least 0.5 Log

Log Reduction in Turbidity (monthly mean)	Percent of Months with at least 0.5 Log Mean Reduction in Spores
>= 0.1	64%
>= 0.2	68%
>= 0.3	73%
>= 0.4	78%
>= 0.5	89%
>= 0.6	91%
>= 0.7	90%
>= 0.8	89%
>= 0.9	95%
>= 1.0	96%

Source: Data from Cincinnati Water Works, Kansas City Water Services Department, and St. Louis Water Division

BILLING CODE 6560-50-C

Within the available data set, achieving a mean turbidity reduction of at least 0.5 log appears to provide approximately a 90% assurance that average spore removal will be 0.5 log or greater. The underlying data are shown graphically in Figure IV-4. Based on

this information, EPA has concluded that it is appropriate to require 0.5 log turbidity reduction, determined as a monthly mean of daily turbidity readings, as an operating condition for the 0.5 log presumptive *Cryptosporidium* treatment credit for

presedimentation. Further, EPA is proposing that systems must meet the 0.5 log turbidity reduction requirement in at least 11 of the 12 previous months on an ongoing basis to remain eligible for the presedimentation credit.

BILLING CODE 6560-50-P




Figure IV-4.-- Monthly Mean Log Removal of Spores from Presedimentation vs. Monthly Mean Turbidity Log Reduction

BILLING CODE 6560-50-C

c. Request for comment. EPA requests comment on the proposed criteria for awarding credit to presedimentation. EPA would particularly appreciate comment on the following issues:

- Whether the information cited in this proposal supports the proposed credit for presedimentation and the operating conditions under which the credit will be awarded;
- Additional information that either supports or suggest modifications to the proposed performance criteria and presumptive credit;
- Today's proposal requires systems using presedimentation to sample after the presedimentation basin, and these systems are not eligible to receive additional presumptive *Cryptosporidium* removal credit for presedimentation. However, systems are also required to collect samples prior to chemical treatment, and EPA recognizes that some plants provide chemical treatment to water prior to, or during, presedimentation. EPA requests

comment on how this situation should be handled under the LT2ESWTR.

- Whether and under what conditions factors like low turbidity raw water, infrequent sludge removal, and wind would make compliance with the 0.5 log turbidity removal requirement infeasible.

6. Bank Filtration

a. *What is EPA proposing today?* EPA is proposing to award additional *Cryptosporidium* treatment credit (0.5 or 1.0 log) for systems that implement bank filtration as a pre-treatment technique if it meets the design criteria specified in this section. To be eligible for credit as a pre-treatment technique, bank filtration collection devices must meet the following criteria:

- Wells are drilled in an unconsolidated, predominantly sandy aquifer, as determined by grain-size analysis of recovered core material—the recovered core must contain greater than 10% fine-grained material (grains less than 1.0 mm diameter) in at least 90% of its length;

- Wells are located at least 25 feet (in any direction) from the surface water source to be eligible for 0.5 log credit; wells located at least 50 feet from the source surface water are eligible for 1.0 log credit;

- The wellhead must be continuously monitored for turbidity to ensure that no system failure is occurring. If the monthly average of daily maximum turbidity values exceeds 1 NTU then the system must report this finding to the State. The system must also conduct an assessment to determine the cause of the high turbidity levels in the well and consult with the State regarding whether previously allowed credit is still appropriate.

Systems using existing bank filtration as pretreatment to a filtration plant at the time the systems are required to conduct *Cryptosporidium* monitoring, as described in section IV.A, must sample the well effluent for the purpose of determining bin classification. Where bin classification is based on monitoring the well effluent, systems are not eligible to receive additional credit for

bank filtration. In these cases, the performance of the bank filtration process in reducing *Cryptosporidium* levels will be reflected in the monitoring results and bin classification.

Systems using bank filtered water without additional filtration typically must collect source water samples in the surface water (*i.e.*, prior to bank filtration) to determine bin classification. This applies to systems using bank filtration to meet the *Cryptosporidium* removal requirements of the IESWTR or LT1ESWTR under the provisions for alternative filtration demonstration in 40 CFR 141.173(b) or 141.552(a). Note that the proposed bank filtration criteria for *Cryptosporidium* removal credit under the LT2ESWTR do not apply to existing State actions to provide alternative filtration *Cryptosporidium* removal credit for IESWTR or LT1ESWTR compliance.

In the case of systems that use GWUDI sources without additional filtration and that meet all the criteria for avoiding filtration in 40 CFR 141.71, samples must be collected from the ground water (*e.g.*, the well). Further, such systems must comply with the requirements of the LT2ESWTR that apply to unfiltered systems, as described in section IV.B.

b. *How was this proposal developed?*
This section describes the bank filtration treatment process, provides more detail on the aquifer types and ground water collection devices that are eligible for bank filtration credit, and describes the data supporting the proposed requirements.

Bank filtration is a water treatment process that makes use of surface water that has naturally infiltrated into ground water via the river bed or bank(s) and is recovered via a pumping well. Stream-bed infiltration is typically enhanced by the pumping action of near-stream wells (*e.g.*, water supply, irrigation). Bank filtrate is water drawn into a pumping well from a nearby surface water source which has traveled through the subsurface, either vertically, horizontally or both, mixing to some degree with other ground water. Through bank filtration, microorganisms and other particles are removed by contact with the aquifer materials.

The bank filtration removal process performs most efficiently when the aquifer is comprised of granular materials with open pore-space for water flow around the grains. In these granular porous aquifers, the flow path is meandering, thereby providing ample opportunity for the organism to come into contact with and attach to a grain surface. Although detachment can occur, it typically occurs at a very slow

rate so that organisms remain attached to a grain for long periods. When ground water travel times from source water to well are long or when little or no detachment occurs, most organisms will become inactivated before they can enter a well. Thus, bank filtration relies on removal, but also, in some cases, on inactivation to protect wells from pathogen contamination.

Only Wells Located in Unconsolidated, Predominantly Sandy Aquifers Are Eligible

Only granular aquifers are eligible for bank filtration credit. Granular aquifers are those comprised of sand, clay, silt, rock fragments, pebbles or larger particles and minor cement. The aquifer material is required to be unconsolidated, with subsurface samples friable upon touch. Uncemented granular aquifers are typically formed by alluvial or glacial processes. Such aquifers are usually identified on a detailed geologic map (*e.g.*, labeled as Quaternary alluvium).

Under today's proposal, a system seeking *Cryptosporidium* removal credit must characterize the aquifer at the well site to determine aquifer properties. At a minimum, the aquifer characterization must include the collection of relatively undisturbed, continuous, core samples from the surface to a depth equal to the bottom of the well screen. The proposed site must have substantial core recovery during drilling operations; specifically, the recovered core length must be at least 90% of the total projected depth to the well screen.

Samples of the recovered core must be submitted to a laboratory for sieve analysis to determine grain size distribution over the entire recovered core length. Each sieve sample must be acquired at regular intervals over the length of the recovered core, with one sample representing a composite of each two feet of recovered core. A two-foot sampling interval reflects the necessity to sample the core frequently without imposing an undue burden. Because it is anticipated that wells will range from 50 to 100 foot in depth, a two-foot sampling interval will result in about 25 to 50 samples for analysis. Each sampled interval must be examined to determine if more than ten percent of the grains in that interval are less than 1.0 mm in diameter (#18 sieve size). In the U.S. Department of Agriculture soil classification system, the #18 sieve separates very coarse sands from coarse sands. The length of core (based on the samples from two-foot intervals) with more than ten percent of the grains less than 1.0 mm in diameter must be summed to determine the overall core

length with sufficient fine-grained material so as to provide adequate removal. An aquifer is eligible for removal credit if at least 90% of the sampled core length contains sufficient fine-grained material as defined in this section.

Cryptosporidium oocysts have a natural affinity for attaching to fine-grained material. A study of oocyst removal in sand columns shows greater oocyst removal in finer-grained sands than in coarser-grained sands (Harter *et al.* 2000). The core sampling procedure described in this section is designed to measure the proportion of fine-grained sands (grains less than 1.0 mm in diameter) so as to ensure that a potential bank filtration site is capable of retarding transport (or removing) oocysts during ground water flow from the source surface water to the water supply well. The value of 1.0 mm for the bounding size of the sand grains was determined based on calculations performed by Harter using data from Harter *et al.* (2000). Harter showed that, for ground water velocities typical of a bank filtration site (1.5 to 15 m/day), a typical bank filtration site composed of grains with a diameter of 1.0 mm would achieve at least 1.0 log removal over a 50 foot transport distance. Larger-sized grains would achieve less removal, all other factors being equal.

Alluvial and glacial aquifers are complex mixtures of sand, gravel and other sized particles. Particles of similar size are often grouped together in the subsurface, due to sorting by flowing water that carries and then deposits the particles. Where there exists significant thickness of coarse-grained particles, such as gravels, with few finer materials, there is limited opportunity for oocyst removal. When the total gravel thickness, as measured in a core, exceeds 10%, it is more likely (based on analysis of ground water flow within mixtures containing differing-sized grains) that the gravel-rich intervals are interconnected. Interconnected gravel can form a continuous, preferential flow path from the source surface water to the water supply well. Where such preferential flow paths exist, a preponderance of the total ground water flow occurs within the preferential flow path, ground water velocity is higher, and natural filtration is minimal. A proposed bank filtration site is acceptable if at least 90% of the core length contains grains with sufficient fine-grained material (diameter less than 1.0 mm); that is, it is acceptable if the core contains less than 10% gravel-rich intervals.

Aquifer materials with significant fracturing are capable of transmitting

ground water at high velocity in a direct flow path with little time or opportunity for die-off or removal of microbial pathogens. Consolidated aquifers, fractured bedrock, and karst limestone are aquifers in which surface water may enter into a pumping well by flow along a fracture, a solution-enhanced fracture conduit, or other preferential pathway. Microbial pathogens found in surface water are more likely to be transported to a well via these direct or preferential pathways. *Cryptosporidium* outbreaks have been associated with consolidated aquifers, such as a fractured chalk aquifer (Willocks *et al.* 1998) or a karst limestone (solution-enhanced fractured) aquifer (Bergmire-Sweat *et al.* 1999). These outbreaks show that the oocyst removal performance of consolidated aquifers is undermined by preferential water flow and oocyst transport through rock fractures or through rock dissolution zones. Wells located in these aquifers are not eligible for bank filtration credit because the flow paths are direct and the average ground water velocity is high, so that little inactivation or removal would be expected. Therefore, only unconsolidated aquifer are eligible for bank filtration oocyst removal credit.

A number of devices are used for the collection of ground water including horizontal and vertical wells, spring boxes, and infiltration galleries. Among these, only horizontal and vertical wells are eligible for log removal credit. The following discussion presents characteristics of ground water collection devices and the basis for this proposed requirement.

Horizontal wells are designed to capture large volumes of surface water recharge. They typically are constructed by the excavation of a central vertical caisson with laterals that extend horizontally from the caisson bottom in all directions or only under the riverbed. Horizontal wells are usually shallower than vertical wells because of the construction expense. Ground water flow to a horizontal well that extends under surface water is predominantly downward. In contrast, ground water flow to a vertical well adjacent to surface water may be predominantly in the horizontal direction. Surface water may have a short ground water flow path to a horizontal well if the well extends out beyond the bank.

Hancock *et al.* (1998) analyzed samples from eleven horizontal wells and found *Cryptosporidium*, *Giardia* or both in samples from five of those wells. These data suggest that some horizontal wells may not be capable of achieving effective *Cryptosporidium* removal by bank filtration. Insufficient data are

currently available to suggest that horizontal well distances from surface water should be greater than distances established for vertical wells. Two ongoing studies in Wyoming (Clancy Environmental Consultants 2002) and Nebraska (Rice 2002) are collecting data at horizontal well sites.

A spring box is located at the ground surface and is designed to contain spring outflow and protect it from surface contamination until the water is utilized. Spring boxes are typically located where natural processes have enhanced and focused ground water discharge into a smaller area and at a faster volumetric flow rate than elsewhere (*i.e.*, a spring). Often, localized fracturing or solution enhanced channels are the cause of the focused discharge to the spring orifice. Fractures and solution channels have significant potential to transport microbial contaminants so that natural filtration may be poor. Thus, spring boxes are not proposed to be eligible for bank filtration credit.

Cryptosporidium monitoring results (Hancock *et al.* 1998) and outbreaks are used to evaluate ground water collection devices. Hancock *et al.* sampled thirty five springs for *Cryptosporidium* oocysts and *Giardia* cysts. Most springs were used as drinking water sources and sampling was conducted to determine if the spring should be considered as a GWUDI source. *Cryptosporidium* oocysts were found in seven springs; *Giardia* cysts were found in five springs; and either oocysts or cysts were found in nine springs (26%). A waterborne cryptosporidiosis outbreak in Medford, Oregon (Fraun *et al.* 1998) is associated with a spring water supply collection device. Also, a more recent, smaller outbreak of giardiasis in an Oregon campground is associated with a PWS using a spring. The high percentage of springs contaminated with pathogenic protozoan, the association with recent outbreaks, and an apparent lack of bank filtration capability indicate that spring boxes must not be eligible for bank filtration credit.

An infiltration gallery (or filter crib) is typically a slotted pipe installed horizontally into a trench and backfilled with granular material. The gallery is designed to collect water infiltrating from the surface or to intercept ground water flowing naturally toward the surface water (Symons *et al.* 2000). In some treatment plants, surface water is transported to a point above an infiltration gallery and then allowed to infiltrate. The infiltration rate may be manipulated by varying the properties of the backfill or the nature of the soil-water interface. Because the filtration

properties of the material overlying an infiltration gallery may be designed or purposefully altered to optimize oocyst removal or for other reasons, this engineered system is not bank filtration, which relies solely on the natural properties of the system.

A 1992 cryptosporidiosis outbreak in Talent, Oregon was associated with poor performance of an infiltration gallery underneath Bear Creek (Leland *et al.* 1993). In this case, the ground water-surface water interface and the engineered materials beneath did not sufficiently reduce the high oocyst concentration present in the source water. The association of an infiltration gallery with an outbreak, the design that relies on engineered materials rather than the filtration properties of natural filtration media, and the shallow depth of constructed infiltration galleries, such that they typically are not located greater than 25 feet from the surface and surface water recharge, all indicate that infiltration galleries must not be eligible for bank filtration credit.

EPA notes that under the demonstration of performance credit described in section IV.C.17, States may consider awarding *Cryptosporidium* removal credit to infiltration galleries where the State determines, based on site-specific testing with a State-approved protocol, that such credit is appropriate (*i.e.*, that the process reliably achieves a specified level of *Cryptosporidium* removal on a continuing basis).

Wells Located 25 Feet From the Surface Water Source Are Eligible for 0.5 Log Credit; Wells Located 50 Feet From the Surface Water Source Are Eligible for 1.0 Log Credit

A vertical or horizontal well located adjacent to a surface water body is eligible for bank filtration credit if there is sufficient ground water flow path length to effectively remove oocysts. For vertical wells, the wellhead must be located at least 25 horizontal feet from the surface water body for 0.5 log *Cryptosporidium* removal credit and at least 50 horizontal feet from the surface water body for 1.0 log *Cryptosporidium* removal credit. For horizontal wells, the laterals must be located at least 25 feet distant from the normal-flow surface water riverbed for 0.5 log *Cryptosporidium* removal credit and at least 50 feet distant from the normal-flow surface water riverbed for 1.0 log *Cryptosporidium* removal credit.

The ground water flow path to a vertical well is the measured distance from the edge of the surface water body, under high flow conditions (determined by the mapped extent of the 100 year

floodplain elevation boundary or floodway, as defined in Federal Emergency Management Agency (FEMA) flood hazard maps), to the wellhead. The ground water flow path to a horizontal well is the measured distance from the bed of the river under normal flow conditions to the closest horizontal well lateral.

The floodway is defined by FEMA as the area of the flood plain where the water is likely to be deepest and fastest. The floodway is shown on FEMA digital maps (known as Q3 flood data maps), which are available for 11,990 communities representing 1,293 counties in the United States. Systems may identify the distance to surface water using either the 100 year return period flood elevation boundary or by determining the floodway boundary using methods similar to those used in preparing FEMA flood hazard maps. The 100 year return period flood elevation boundary is expected to be wider than the floodway but that difference may vary depending on local conditions. Approximately 19,200 communities in the United States have flood hazard maps that show the 100 year return period flood elevation boundary. If local FEMA floodway hazard maps are unavailable or do not show the 100 year flood elevation boundary, then the utility must determine either the floodway or 100 year flood elevation boundary.

The separation distance proposed for *Cryptosporidium* removal credit is based, in part, on measured data for the removal of oocyst surrogate biota in full-scale field studies. A variety of surrogate and indicator organisms were analyzed in each study evaluated for today's proposal. However, only two non-pathogenic organisms, anaerobic clostridia spores and aerobic endospores, are resistant to inactivation in the subsurface, approximately similar in size and shape to oocysts, and sufficiently ubiquitous in both surface water and ground water so that log removal can be calculated during passage across the surface water—ground water interface and during transport within the aquifer.

Anaerobic spores are typically estimated at about 0.3–0.4 μm in diameter as compared with 4–6 μm for oocysts. Aerobic spores, such as endospores of the bacterium *Bacillus subtilis*, are slightly larger than anaerobic spores, typically $0.5 \times 1.0 \times 2.0 \mu\text{m}$ in diameter (Rice *et al.* 1996). Experiments conducted by injecting *Bacillus subtilis* spores into a gravel aquifer show that they can be very mobile in the subsurface environment (Pang *et al.* 1998). As presented in the

following discussion, available data indicate similar removal of both aerobic and anaerobic spores, either during passage across the surface water—ground water interface or during ground water flow. These data suggest that anaerobic spores, like aerobic spores, may be suitable surrogate measures of *Cryptosporidium* removal by bank filtration.

Available data establish that during bank filtration, significant removal of anaerobic and aerobic spores can occur during passage across the surface water-ground water interface, with lesser removal occurring during ground water transport within the aquifer away from that interface. The ground water-surface water interface is typically comprised of finer grained material that lines the bottom of the riverbed. Typically, the thickness of the interface is small, typically a few inches to a foot. The proposed design criteria of 25 and 50 feet for 0.5 and 1.0 log *Cryptosporidium* removal credit, respectively, are based on EPA's analysis of pathogen and surrogate monitoring data from bank filtration sites. Most of these data are from studies of aquifers developed in Dutch North Sea margin sand dune fields and, therefore, represent optimal removal conditions consistent with a homogenous, well sorted (by wind), uniform sand filter.

Medema *et al.* (2000) measured 3.3 log removal of anaerobic spores during transport over a 13 m distance from the Meuse River into adjacent ground water. Arora *et al.* (2000) measured greater than 2.0 log removal of anaerobic spores during transport from the Wabash River to a horizontal collector well. Havelaar *et al.* (1995) measured 3.1 log removal of anaerobic spores during transport over a 30 m distance from the Rhine River to a well and 3.6 log removal over a 25 m distance from the Meuse River to a well. Schijven *et al.* (1998) measured 1.9 log removal of anaerobic spores over a 2 m distance from a canal to a monitoring well. Using aerobic spores, Wang *et al.* (2001) measured 1.8 log removal over a 2 foot distance from the Ohio river to a monitoring well beneath the river.

During transport solely within shallow ground water (*i.e.*, not including removal across the surface water-ground water interface), Medema *et al.* (2000) measured approximately 0.6 log removal of anaerobic spores over a distance of 39 feet. Using aerobic spores, Wang *et al.* (2001) measured 1.0 log removal of aerobic spores over a 48 foot distance from a monitoring well beneath a river to a horizontal well lateral.

At distances relatively far from an injection well in a deep, anaerobic aquifer, thereby minimizing the effects of injection, Schijven *et al.* measured negligible removal of anaerobic spores over a 30 m distance. However, few bank filtration systems occur in deeper, anaerobic ground water so these data may not apply to a typical bank filtration system in the United States.

These data demonstrate that during normal and low surface water elevations, the surface water-ground water interface performs effectively to remove microbial contamination. However, there will typically be high water elevation periods during the year, especially on uncontrolled rivers, that alter the nature and performance of the interface due to flood scour, typically for short periods. During these periods, lower removals would be expected to occur.

Averaging *Cryptosporidium* oocyst removal over the period of a year requires consideration of both high and low removal periods. During most of the year, high log removal rates would be expected to predominate (*e.g.*, 3.3 log removal over 42 feet) due to the removal achieved during passage across the surface water-ground water interface. During short periods of flooding, substantially lower removal rates may occur (*e.g.*, 0.5 log removal over 39 feet) due to scouring of the riverbed and removal of the protective, fine-grained material. By considering all time intervals with differing removal rates over the period of a year, EPA is proposing that 0.5 log removal over 25 feet (8 m) and 1.0 log removal over 50 feet (16 m) are reasonable estimates of the average performance of a bank filtration system over a year. This proposal is generally supported by colloidal filtration theory modeling results using data characteristic of the aquifers in Louisville and Cincinnati and column studies of oocyst transport in sand (Harter *et al.* 2000).

Wells must be continuously monitored for turbidity

Under the Surface Water Treatment Rule (40 CFR 141.73(b)(1)) the turbidity level of slow sand filtered water must be 1 NTU or less in 95% of the measurements taken each month. Turbidity sampling is required once every four hours, but may be reduced to once per day under certain conditions. Although slow sand filtration is not bank filtration, similar pathogen removal mechanisms are expected to occur in both processes. Just as turbidity monitoring is used to provide assurance that the removal credit assigned to a slow sand filter is being realized, EPA

is proposing continuous turbidity monitoring for all bank filtration wells that receive credit.

If monthly average turbidity levels (based on daily maximum values in the well) exceed 1 NTU, the system is required to report to the State and

present an assessment of whether microbial removal has been compromised. If the State determines that microbial removal has been compromised, the system must not receive credit for bank filtration until the problem has been remediated. The

turbidity performance requirement for bank filtration is less strict than that for slow sand filtration because, unlike slow sand filtration, bank filtration is a pre-treatment technique followed by conventional or direct filtration.

BILLING CODE 6560-50-P

Table IV-13.-- Summary Table Showing All Requirements for Bank Filtration Pre-treatment Log Removal Credit

Eligible for Bank Filtration Credit?	Yes, eligible for bank filtration credit (with continuous turbidity monitoring*) and State approval	No, not eligible for bank filtration credit
Some GWUDI Sites Eligible	<ul style="list-style-type: none"> • Unconsolidated, young, sandy**, granular aquifer 	<ul style="list-style-type: none"> • Located in a hydrogeologic setting consisting of consolidated material
Some Water Collection Devices Eligible	<ul style="list-style-type: none"> • Vertical wells located greater than 25 feet (0.5 log credit) or 50 feet (1.0 log credit) from surface water • Horizontal wells with laterals that are no closer than 25 feet (0.5 log credit) or 50 feet (1.0 log credit) from the river channel under normal flow conditions 	<ul style="list-style-type: none"> • Spring boxes • Infiltration galleries • Horizontal wells with laterals that extend within 25 feet of the river channel under normal flow conditions • Vertical wells located fewer than 25 feet from surface water (measured from the mapped FEMA floodway boundary)

*Average monthly turbidity values (based on daily maximum values) exceeding 1 NTU trigger an investigation by the system and consultation with the primacy agency

**Based on laboratory analysis of continuous core samples collected at the site; At least 90% of the recovered core length must contain intervals in which more than 10% of the grains are less than 1.0 mm in diameter.

BILLING CODE 6560-50-C

In summary, EPA believes that the measured full-scale field data from operating bank filtration systems, the turbidity monitoring provision, and the design criteria for aquifer material, collection device type, and setback distance, together provide assurance that the presumptive log removal credit will be achieved by bank filtration systems that conform to the requirements in today's proposal.

c. Request for comment. The Agency requests comment on the following issues concerning bank filtration:

- The performance of bank filtration in removing *Cryptosporidium* or surrogates to date at sites currently using this technology (e.g. sites with horizontal wells).
- The use of other methods (e.g., geophysical methods such as ground penetrating radar) to complement or

supplant core drilling to determine site suitability for bank filtration credit.

- The number of GWUDI systems in each State (i.e., the number of systems having at least one GWUDI source) where bank filtration has been utilized as the primary filtration barrier (e.g., no other physical removal technologies follow); also, the method that was used by the State to determine that each

system was achieving 2 log removal of *Cryptosporidium*.

- For GWUDI systems where natural or alternative filtration (e.g. bank filtration or artificial recharge) is used in combination with a subsequent filtration barrier (e.g., bag or cartridge filters) to meet the 2 log *Cryptosporidium* removal requirement of the IESWTR or LT1ESWTR, how much *Cryptosporidium* removal credit has the State awarded (or is the State willing to grant if the bags/cartridges were found to be achieving < 2.0 logs) for the natural or alternative filtration process and how did the State determine this value?

- The proposed *Cryptosporidium* removal credit and associated design criteria, including any additional information related to this topic.

- Suitable separation distance(s) to be required between vertical or horizontal wells and adjacent surface water.

- Testing protocols and procedures for making site specific determinations of the appropriate level of *Cryptosporidium* removal credit to award to bank filtration processes.

- Information on the data and methods suitable for predicting *Cryptosporidium* removal based on the available data from surrogate and indicator measurements in water collection devices.

- The applicability of turbidity monitoring or other process monitoring procedures to indicate the ongoing performance of bank filtration processes.

7. Lime Softening

a. *What is EPA proposing today?* Lime softening is a drinking water treatment process that uses precipitation with lime and other chemicals to reduce hardness and enhance clarification prior to filtration. Lime softening can be categorized into two general types: (1) Single-stage softening, which is used to remove calcium hardness and (2) two-stage softening, which is used to remove magnesium hardness and greater levels of calcium hardness. A single-stage softening plant includes a primary clarifier and filtration components. A two-stage softening plant also includes a secondary clarifier located between the primary clarifier and filter. In some two-stage softening plants, a portion of the flow bypasses the first clarifier.

EPA has determined that lime softening plants in compliance with IESWTR or LT1ESWTR achieve a level of *Cryptosporidium* removal equivalent

to conventional treatment plants (i.e., average of 3 log). Consequently, lime softening plants that are placed in Bins 2–4 as a result of *Cryptosporidium* monitoring incur the same additional treatment requirements as conventional plants. However, EPA is proposing that two-stage softening plants be eligible for an additional 0.5 log *Cryptosporidium* treatment credit. To receive the 0.5 log credit, the plant must have a second clarification stage between the primary clarifier and filter that is operated continuously, and both clarification stages must treat 100% of the plant flow. In addition, a coagulant must be present in both clarifiers (may include metal salts, polymers, lime, or magnesium precipitation).

b. *How was this proposal developed?* The lime softening process is used to remove hardness, primarily calcium and magnesium, through chemical precipitation followed by sedimentation and filtration. The addition of lime increases pH, causing the metal ions to precipitate. Other contaminants can coalesce with the precipitates and be removed in the subsequent settling and filtration processes. While elevated pH has been shown to inactivate some microorganisms like viruses (Battigelli and Sobsey, 1993, Logsdon *et al.* 1994), current research indicates that *Cryptosporidium* and *Giardia* are not inactivated by high pH (Logsdon *et al.* 1994, Li *et al.* 2001). A two-stage lime softening plant has the potential for additional *Cryptosporidium* removal because of the additional sedimentation process.

Limited data are available on the removal of *Cryptosporidium* by the lime softening treatment process. EPA has evaluated data from a study by Logsdon *et al.* (1994), which investigated removal of *Giardia* and *Cryptosporidium* in full scale lime softening plants. In addition, the Agency has considered data provided by utilities on the removal of aerobic spores in softening plants. These data are summarized in the following paragraphs.

Logsdon *et al.* (1994) measured levels of *Cryptosporidium* and *Giardia* in the raw, settled, and filtered water of 13 surface water plants using lime softening. *Cryptosporidium* was detected in the raw water at 5 utilities: one single-stage plant and four two-stage plants. Using measured oocyst levels, *Cryptosporidium* removal by sedimentation was 1.0 log in the single-stage plant and 1.1 to 2.3 log in the two-

stage plants. *Cryptosporidium* was found in two filtered water samples of the single stage plant, leading to calculated removals from raw to filtered water of 0.6 and 2.2 log. None of the two-stage plants had *Cryptosporidium* detected in the filtered water. Based on detection limits, calculated *Cryptosporidium* removals from raw to filtered water in the two-stage plants ranged from >2.67 to >3.85 log.

Giardia removal across sedimentation was >0.9 log for a single-stage plant and ranged from 0.8 to 3.2 log for two-stage plants, based on measured cyst levels. Removal of *Giardia* from raw water through filtration was calculated using detection limits as >1.5 log in a single-stage plant and ranged from >0.9 to >3.3 log in two-stage plants.

While results from the Logsdon *et al.* study are constrained by sample number and method detection limits, they suggest that two-stage softening plants may achieve greater removal of *Cryptosporidium* than single-stage plants. The authors concluded that two stages of sedimentation, each preceded by effective flocculation of particulate matter, may increase removal of protozoa. Additionally, the authors stated that consistent achievement of flocculation that results in effective settling in each sedimentation basin is the key factor in this treatment process.

Removal of Aerobic Spores by Softening Plants

Additional information on the microbial removal efficiency of the lime softening process comes from data provided by softening plants on removal of aerobic spores. While few treatment plants have sufficient concentrations of oocysts to directly calculate a *Cryptosporidium* removal efficiency, some plants have high concentrations of aerobic spores in the raw water. Spores may serve as an indicator of *Cryptosporidium* removal by sedimentation and filtration (Dugan *et al.* 2001).

The following two-stage softening plants provided data on removal of aerobic spores: St. Louis, MO, Kansas City, MO, and Columbus, OH (2 plants). *Cryptosporidium* data were also collected at these utilities, but it was not possible to calculate oocyst removal due to low raw water detection rates. Data on removal of aerobic spores by these softening plants is summarized in Table IV–14.

TABLE IV-14.—SUMMARY OF AEROBIC SPORE REMOVAL DATA FROM SOFTENING PLANTS

Plant	Mean log removal of aerobic spores		
	Primary clarifier	Secondary clarifier	Across plant *
St. Louis	1.7	1.1	3.8
Kansas City	2.4	0	3.4
Columbus Plant 1	1.2	1.6	3.1
Columbus Plant 2	1.3	2.4	4.2

* Excludes removal in pre-sedimentation basins; calculated spore removal may underestimate actual removal due to filter effluent levels below quantitation limits.

The City of St. Louis Water Division operates a two-stage lime softening process preceded by presedimentation. Ferric sulfate and polymer coagulants are added at various points in the process. St. Louis collected *Bacillus subtilis* spore samples between June 1998 and September 2000. During this time period, the mean spore concentration entering the softening process (*i.e.*, after presedimentation) was 8,132 cfu/100 mL. The log removal values shown in Table IV-14 are based on average spore concentrations following primary clarification, secondary clarification, and filtration. However, spore levels in some filtered water samples were below the method detection limit, so that the true mean spore removal across the plant may have been higher than indicated by the calculated value.

The Kansas City Water Services Department plant includes two-stage lime softening with pre-sedimentation and sludge recycle. *Bacillus subtilis* spore data were collected from this plant during January through November 2000. The mean spore concentration entering the lime softening process (after presedimentation) was 5,965 cfu/100 mL. Mean spore levels following primary clarification, secondary clarification, and filtration were 21.1, 25.7, and 2.6 cfu/100 mL, respectively. Corresponding log removal values are shown in Table IV-14. Note that the average spore concentration in the effluent of the secondary clarifier was essentially equivalent to the effluent of the primary clarifier, indicating that little removal occurred in the secondary clarifier. This result may have been due to the high removal achieved in the primary clarifier and, consequently, the relatively low concentration of spores entering the second clarifier. As with the St. Louis plant, many of the filtered water observations were below method detection limits, so actual log removal across the plant may have been higher than the calculated value.

The City of Columbus operates two lime softening plants, each of which has two clarification stages. Coagulant is

added prior to the first clarification stage but lime is not added until the second clarifier (*i.e.*, first clarifier is not a softening stage). Between 1997 and 2000, samples for total aerobic spores were collected approximately monthly at each plant from raw water, following each clarification basin, and after filtration. Mean spore concentrations in the raw water sources for the two plants were 10,619 cfu/100 mL (Plant 1) and 22,595 cfu/100 mL (Plant 2). Mean log removals occurring in the two clarification stages and across the plant are shown for each plant in Table IV-14.

These data indicate that two-stage softening plants can remove high levels of *Cryptosporidium*, and, in particular, that a second clarification stage can achieve 0.5 log or greater removal. Three of the four plants that provided data on removal of aerobic spores achieved greater than 1 log reduction in the second clarifier. Kansas City, the one plant which achieved little removal in the second clarifier, achieved a mean 2.4 log removal in the primary clarifier. This was approximately 1 log more reduction than achieved in the primary clarifiers of the other three plants, so that the spore concentration entering the second clarifier in Kansas City may have been too low to serve as an indicator of removal efficiency. Consequently, EPA has concluded that these data support an additional *Cryptosporidium* treatment credit of 0.5 log for a two-stage softening plant.

EPA is proposing as a condition of the 0.5 log additional credit that a coagulant, which could include excess lime and soda ash or precipitation of magnesium hydroxide, be present in both clarifiers. This requirement is necessary to ensure that significant particulate removal occurs in both clarification stages. Logsdon *et al.* (1994) identified effective flocculation as being a key factor for removal of protozoa in softening plants. Among the softening plants that provided data on aerobic spore removal, St. Louis added ferric and polymer coagulants at different points in the process, and the

two Columbus plants added lime to the second clarifier. Consequently, a requirement that plants add a coagulant, which may be lime, in the secondary clarifier is consistent with the data used to support the 0.5 log additional credit.

The Science Advisory Board (SAB) reviewed the proposed *Cryptosporidium* treatment credit for lime softening and supporting information, as presented in the November 2001 pre-proposal draft of the LT2ESWTR (USEPA 2001g). In written comments from a December 2001 meeting of the Drinking Water Committee, the SAB panel concluded that both single- and two-stage softening generally outperform conventional treatment due to the heavy precipitation that occurs. Further, the panel found that 0.5 log of additional *Cryptosporidium* removal is an average value for a two-stage lime softening plant. However, the SAB stated that the additional credit for two-stage softening should be given only if all the water passes through both stages. Today's proposal is consistent with these recommendations by the SAB.

EPA notes that by including a presumptive credit for softening plants, today's proposal differs from the Stage 2 M-DBP Agreement in Principle, which recommends up to 1 log additional *Cryptosporidium* treatment credit for softening plants based on demonstration of performance, but no additional presumptive credit.

c. Request for comment. EPA requests comment on the proposed criteria for awarding credit to lime softening plants. EPA would particularly appreciate comment on the following issues:

- Whether the information and analyses presented in this proposal supports an additional 0.5 log credit for two-stage softening, and the associated criteria necessary for credit.
- Additional information that either support or suggest modifications to the proposed criteria and credit.

8. Combined Filter Performance

a. What is EPA proposing today? This toolbox component will grant additional credit towards *Cryptosporidium*

treatment requirements to certain plants that maintain finished water turbidity at levels significantly lower than currently required. EPA is proposing to award an additional 0.5 log *Cryptosporidium* treatment credit to conventional and direct filtration plants that demonstrate a turbidity level in the combined filter effluent (CFE) less than or equal to 0.15 NTU in at least 95 percent of the measurements taken each month. Compliance with this criterion must be based on measurements of the CFE every four hours (or more frequently) that the system serves water to the public. This credit is not available to membrane, bag/cartridge, slow sand, or DE plants, due to the lack of documented correlation between effluent turbidity and *Cryptosporidium* removal in these processes.

b. *How was this proposal developed?* Turbidity is an optical property measured from the amount of light scattered by suspended particles in a solution. It is a method defined parameter that can detect the presence of a wide variety of particles in water (e.g., clay, silt, mineral particles, organic

and inorganic matter, and microorganisms), but it cannot provide specific information on particle type, number, or size. Turbidity is used as an indicator of raw and finished water quality and treatment performance. Turbidity spikes in filtered water indicate a potential for breakthrough of pathogens.

Under the IESWTR and LT1ESWTR, combined filter effluent turbidity in conventional and direct filtration plants must be less than or equal to 0.3 NTU in 95% of samples taken each month and must never exceed 1 NTU. These plants are also required to conduct continuous monitoring of turbidity for each individual filter, and provide an exceptions report to the State when certain criteria for individual filter effluent turbidity are exceeded (described in 63 FR 69487, December 16, 1998) (USEPA 1998a).

The Stage 2 M-DBP Advisory Committee recommended that systems receive an additional 0.5 log *Cryptosporidium* removal credit for maintaining 95th percentile combined filter effluent turbidity below 0.15 NTU,

which is one half of the current required level of 0.3 NTU. In considering the technical basis to support this recommendation, EPA has reviewed studies that evaluated the efficiency of granular media filtration in removing *Cryptosporidium* when operating at different effluent turbidity levels.

For the IESWTR, EPA estimated that plants would target filter effluent turbidity in the range of 0.2 NTU in order to ensure compliance with a turbidity standard of 0.3 NTU. Similarly, EPA has estimated that plants relying on meeting a turbidity standard of 0.15 NTU in 95% of samples will consistently operate below 0.1 NTU in order to ensure compliance. Consequently, to assess the impact of compliance with the lower finished water turbidity standard, EPA compared *Cryptosporidium* removal efficiency when effluent turbidity is below 0.1 NTU with removal efficiency when effluent turbidity is in the range of 0.1 to 0.2 NTU. Results from applicable studies are summarized in Table IV-15 and are discussed in the following paragraphs.

TABLE IV-15.—STUDIES OF *Cryptosporidium* REMOVAL AT DIFFERENT EFFLUENT TURBIDITY LEVELS

Microorganism	Average of log removals	Filtered effluent turbidity	Experiment design	Researcher
<i>Cryptosporidium</i>	4.39	≤0.1 NTU	Pilot-scale	Patania et al. (1995).
	3.55	>0.1 and ≤0.2 NTU		
<i>Giardia</i>	4.23	≤0.1 NTU	Bench-scale	Emelko et al. (1999).
	3.22	>0.1 and ≤0.2 NTU		
<i>Cryptosporidium</i>	4.09	≤0.1 NTU	Pilot-scale	Dugan et al. (2001).
	3.58	>0.1 and ≤0.2 NTU		
<i>Cryptosporidium</i>	3.76	≤0.1 NTU		
	2.56	>0.1 and ≤0.2 NTU		

Patania *et al.* (1995) conducted pilot-scale studies at four locations to evaluate the removal of seeded *Cryptosporidium* and *Giardia*, turbidity, and particles. Treatment processes, coagulants, and coagulant doses differed among the four locations. Samples of filter effluent were taken at times of stable operation and filter maturation. Analysis of summary data from the seeded runs at all locations shows that average *Cryptosporidium* removal was greater by more than 0.5 log when effluent turbidity was less than 0.1 NTU, in comparison to removal with effluent turbidity in the range 0.1 to 0.2 NTU (see Table IV-15).

Emelko *et al.* (1999) used a bench scale dual media filter to study *Cryptosporidium* removal during both optimal and challenged operating conditions. Water containing a suspension of kaolinite (clay) was spiked with oocysts, coagulated in-line

with alum, and filtered. Oocyst removal was evaluated during stable operation when effluent turbidity was below 0.1 NTU. Removal was also measured after a hydraulic surge that caused process upset, and with coagulant addition terminated. These later two conditions resulted in effluent turbidities greater than 0.1 NTU and decreased removal of *Cryptosporidium*. As shown in Table IV-15, average removal of *Cryptosporidium* during periods with effluent turbidity below 0.1 NTU was approximately 0.5 log greater than when effluent turbidity was between 0.1 to 0.2 NTU.

Dugan *et al.* (2001) evaluated *Cryptosporidium* removal in a pilot scale conventional treatment plant. Sixteen filtration runs seeded with *Cryptosporidium* were conducted at different raw water turbidities and coagulation conditions. Eleven of the runs had an effluent turbidity below 0.1

NTU, and five runs had effluent turbidity between 0.1 and 0.2 NTU. For runs where the calculated *Cryptosporidium* removal was concentration limited (*i.e.*, effluent values were non-detect), the method detection limit was used to calculate the values shown in Table IV-15. Using this conservative estimate, average *Cryptosporidium* removal with effluent turbidity below 0.1 NTU exceeded by more than 1 log the average removal observed with effluent turbidity between 0.1 to 0.2 NTU.

In summary, these three studies all support today's proposal in showing that plants consistently operating below 0.1 NTU can achieve an additional 0.5 log or greater removal of *Cryptosporidium* than when operating between 0.1 and 0.2 NTU. Because EPA expects plants relying on compliance with a 0.15 NTU standard will consistently operate below 0.1 NTU, the

Agency has determined it is appropriate to propose an additional 0.5 log treatment credit for plants meeting this standard.

The SAB reviewed the proposed additional 0.5 log *Cryptosporidium* removal credit for systems maintaining very low CFE turbidity, as presented in the November 2001 pre-proposal draft of the LT2ESWTR (USEPA 2001g). The SAB also reviewed a potential additional 1.0 log *Cryptosporidium* removal credit for systems achieving very low individual filter effluent (IFE) turbidity, which is addressed in section IV.C.16 of today's proposal.

In written comments from a December 2001 meeting of the Drinking Water Committee, the SAB panel stated that additional credit for lower finished water turbidity is consistent with what is known in both pilot and full-scale operational experiences for *Cryptosporidium* removal. Recognizing that IESWTR requirements for lowering turbidity in the treated water will result in lower concentrations of *Cryptosporidium*, the panel affirmed that even further lowering of turbidity will result in further reductions in *Cryptosporidium* in the filter effluent. However, the SAB concluded that limited data were presented to show the exact removal that can be achieved, and recommended that no additional credit be given to plants that demonstrate CFE

turbidity of 0.15 NTU or less. The SAB recommended that 0.5 log credit be given to plants achieving IFE turbidity in each filter less than 0.15 NTU in 95% of samples each month.

In responding to this recommendation from the SAB, EPA acknowledges the difficulty in precisely quantifying *Cryptosporidium* removal through filtration based on effluent turbidity levels. Nevertheless, EPA finds that available data consistently show that removal of *Cryptosporidium* is increased by 0.5 log or greater when filter effluent turbidity is reduced to levels reflecting compliance with a 0.15 NTU standard, in comparison to compliance with a 0.3 NTU standard. Consequently, EPA has concluded that it is appropriate to propose this 0.5 log presumptive treatment credit for systems achieving very low CFE turbidity.

Measurement of Low Level Turbidity

Another important aspect of proposing to award additional removal credit for lower finished water turbidity is the performance of turbidimeters in measuring turbidity below 0.3 NTU. The following paragraphs summarize results from several studies that evaluated low level measurement of turbidity by different on-line and bench top instruments. Note that because compliance with the CFE turbidity limit

is based on 4-hour readings, either on-line or bench top turbidimeters may be used. EPA believes that results from these studies indicate that currently available turbidity monitoring equipment is capable of reliably assessing turbidity at levels below 0.1 NTU, provided instruments are well calibrated and maintained.

The 1997 NODA for the IESWTR (67 FR 59502, Nov. 3, 1997) (USEPA 1997a) discusses issues relating to the accuracy and precision of low level turbidity measurements. This document cites studies (Hart *et al.* 1992, Sethi *et al.* 1997) suggesting that large tolerances in instrument design criteria have led to turbidimeters that provide different turbidity readings for a given suspension.

At the time of IESWTR NODA, EPA had conducted performance evaluation (PE) studies of turbidity samples above 0.3 NTU. A subsequent PE study (USEPA 1998e), labeled WS041, was carried out to address concern among the Stage 1 M-DBP Federal Advisory Committee regarding the ability to reliably measure lower turbidity levels. The study involved distribution of different types of laboratory prepared standard solutions with reported turbidity values of 0.150 NTU or 0.160 NTU. The results of this study are summarized in Table IV-16.

BILLING CODE 6560-50-P

Table IV-16.-- Performance Evaluation - WS041 Data for Low Level Turbidity

Analysis (USEPA 1998e)

Type of Instrument	Sample Solution Type	"True" Value (NTU)	No. of Results Available	Mean* (NTU)	Std. Dev* (NTU)	95% Prediction Interval (NTU)
Bench Top	Polystyrene Spheres	0.150	292	0.203	0.0558	0.093-0.313
Portable or IR	Polystyrene Spheres	0.150	340	0.200	0.0439	0.113-0.286
Portable or IR	Formazin	0.160	335	0.176	0.0431	0.091-0.261
On-Line	Polystyrene Spheres	0.150	52	0.228	0.0773	0.072-0.385

*Calculated using biweight transformation

BILLING CODE 6560-50-C

The data summarized in Table IV-16 indicate a positive bias for all instruments when compared against a reported "true value." On-line

instruments in this study had a larger positive bias and higher standard deviation (RSD approximately 50 percent). The positive bias is consistent

with previous PE studies (USEPA 1998e) and suggests that error in turbidimeter readings may be generally conservative (*i.e.*, systems will operate

at lower than required effluent turbidity levels).

Letterman *et al.* (2001) evaluated the effect of turbidimeter design and calibration methods on *inter*-instrument performance, comparing bench top to on-line instruments and instruments within each of those categories from different manufacturers. The study used treated water collected from the filter effluent of water treatment plants. Reported sample turbidity values ranged from 0.05 to 1 NTU. Samples were analyzed in a laboratory environment. The results are consistent with those of the WS041 study, specifically the positive bias of on-line instruments. However, Letterman *et al.* found generally poor agreement among different on-line instruments and between bench-top and on-line instruments. The authors also observed that results were independent of the calibration method, though certain experiments suggested that analyst experience may have some effect on turbidity readings from bench-top instruments.

Sadar (1999) conducted an *intra*-instrument study of low level turbidity measurements among instruments from the same manufacturer. This study was performed under well-controlled laboratory conditions. *Intra*-instrument variation among different models and between bench top and on-line instruments occurred but at significantly lower levels than the Letterman *et al.* *inter*-instrument study. Newer instruments also tended to read lower than older instruments, which the author attributed to a reduction in stray light and lower sensitivities in the newer instruments. Sadar also found a generally positive bias when comparing on-line to bench-top and when comparing all instruments to a prepared standard.

The American Society for Testing and Materials (ASTM) has issued standard test methods for measurement of turbidity below 5 NTU by on-line (ASTM 2001) and static (ASTM 2003) instrument modes. The methods specify that the instrument should permit detection of turbidity differences of 0.01 NTU or less in waters having turbidities of less than 1.00 NTU (ASTM 2001) and 5.0 NTU (ASTM 2003), respectively. *Inter*-laboratory study data included with the method for a known turbidity standard of 0.122 NTU show an analyst relative deviation of 7.5% and a laboratory relative deviation of 16% (ASTM 2003).

In summary, the data collected in these studies of turbidity measurement indicate that currently available monitoring equipment can reliably

measure turbidity at levels of 0.1 NTU and lower. However, this requires rigorous calibration and verification procedures, as well as diligent maintenance of turbidity monitoring equipment (Burlingame 1998, Sadar 1999). Systems that pursue additional treatment credit for lower finished water turbidity must develop the procedures necessary to ensure accurate and reliable measurement of turbidity at levels of 0.1 NTU and less. EPA guidance for the microbial toolbox will provide direction to water systems on developing these procedures.

c. *Request for comment.* EPA invites comment on the following issues regarding the proposed *Cryptosporidium* treatment credit for combined filter performance:

- Do the studies cited here support awarding 0.5 log credit for CFE \leq 0.15 NTU 95% of the time?
- Does currently available turbidity monitoring technology accurately distinguish differences between values measured near 0.15 NTU?

9. Roughing Filter

a. *What is EPA proposing today?* The Stage 2 M-DBP Agreement in Principle recommends a 0.5 log presumptive credit towards additional *Cryptosporidium* treatment requirements for roughing filters. However, the Agreement further specifies that EPA is to determine the design and implementation criteria under which the credit would be awarded. Upon subsequent review of available literature, EPA is unable to identify design and implementation conditions for roughing filters that would provide reasonable assurance of achieving a 0.5 log removal of oocysts. Consequently, EPA is not proposing presumptive credit for *Cryptosporidium* removal by roughing filters. Today's proposal does, though, include a 0.5 log credit for a second granular media filter following coagulation and primary filtration (see section IV.C.13).

b. *How was this proposal developed?* Roughing filtration is a technique used primarily in developing countries to remove solids from high turbidity source waters prior to treatment with slow sand filters. Typically, roughing filters consist of a series of sedimentation tanks filled with progressively smaller diameter media in the direction of flow. The media can be gravel, plastic, crushed coconut, rice husks, or a similar locally available material. The flow direction in roughing filters can be either horizontal or vertical, and vertical roughing filters can be either upflow or downflow. The media in the tanks effectively reduce the

vertical settling distance of particles to a distance of a few millimeters. As sediment builds on the media, it eventually sloughs off and begins to accumulate in the lower section of the filter, while simultaneously regenerating the upper portions of the filter. The filters require periodic cleaning to remove the collected silt.

Review of the scientific and technical literature pertaining to roughing filters has identified no information on removal of *Cryptosporidium*. Information is available on removal of suspended solids, turbidity, particles, fecal coliforms and some algae, but none of these has been demonstrated to be an indicator of *Cryptosporidium* removal by roughing filters. Moreover, roughing filters are not preceded by a coagulation step, and studies have found that some potential surrogates, such as aerobic spores, are not conservative indicators of *Cryptosporidium* removal by filtration when a coagulant is not present (Yates *et al.* 1998, Dugan *et al.* 2001). Thus, it is unclear how to relate results from studies of the removal of other particles by roughing filters to potential removal of *Cryptosporidium*.

In addition, some studies have observed very poor removal of *Cryptosporidium* by rapid sand filters when a coagulant is not used (Patania *et al.* 1995, Huck *et al.* 2000). Based on these findings, it is expected that there would be situations where a roughing filter would not achieve 0.5 log *Cryptosporidium* removal. Because available data are insufficient to determine the conditions that would be necessary for a roughing filter to achieve 0.5 log *Cryptosporidium* removal, EPA is unable to propose this credit. The following discussion describes four studies that analyzed the effectiveness of roughing filters for removing solids, turbidity, particles, fecal coliforms, and algae.

Wegelin *et al.* (1987) conducted pilot-scale studies on the use of horizontal roughing filters to reduce solids, turbidity, and particles. Testing was performed to determine the influence of different design parameters on filter performance. Data from the parameter testing was used to establish an empirical model to simulate filtrate quality as a function of filter length and time for a given filter configuration. Using the mathematical model, the researchers found that long filters (10 m) at low filtration rates (0.5 m/h) were capable of reducing high suspended solids concentrations (1000 mg/L TSS) down to less than 3 mg/L.

Further work by Wegelin (1988) evaluated roughing filters as pretreatment for slow sand filters for

waters with variable and seasonably high suspended solids concentrations. This study collected data on roughing filters in Peru, Colombia, Sudan, and Ghana. Table IV-17 summarizes data for three of the roughing filters. These filters were capable of reducing peak turbidities by 80 to 90 percent. Further, the Peruvian and Colombian filters

reduced fecal coliforms by 77 and 89 percent, respectively. The Sudanese filter may have removed around 90 percent of the fecal coliforms, but specific values were not given. Data collected from roughing filters in Ghana on algae removal indicate that the Merismopedia (0.5 µm) and Chlorophyta (2–10 µm), which are comparable in size

to *Cryptosporidium* oocysts, were completely removed from the water in mature filters, and that some removal of Chlorophyta, but not Merismopedia, occurred in filters after three days of operation. However, the removal of these organisms has not been correlated with *Cryptosporidium* oocyst removal.

TABLE IV-17.—ROUGHING FILTER DATA FROM WEGELIN, 1988

Location	Azpita, Peru	El Retiro, Colombia	Blue Nile Health Project, Sudan
Roughing Filter Type	Downflow	Upflow (multi-layer filter)	Horizontal-flow.
Filtration Rate	0.30 m/h (0.98 ft/hr)	0.74 m/h (2.43 f/hr)	0.3 m/h (0.98 ft/hr).
Design Capacity	35 m ³ /d	790 m ³ /d	5 m ³ /d.
Turbidity (NTU)			
Raw Water	50–200	10–150	40–500
Roughing Filter Effluent	15–40	5–15	5–50
Fecal Coliforms (/100 mL)			
Raw Water	700	16,000	>300
Roughing Filter Effluent	160	1,680	<25

oller (1993) details the mechanisms of particle removal that occur in roughing filters. The conclusions are similar to those drawn by Wegelin *et al.* (1987). Particle analysis reviewed by Boller indicates that after seven days of operation, the four stage pilot filter utilized by Wegelin *et al.* (1987) removed more than 98 percent of particles sized 1.1 µm, and greater than 99 percent of particles sized 3.6 µm. After 62 days, only 80 percent of particles sized 1.1 µm were removed, while 90 percent of particles sized 3.6 µm were removed. Boller did not give the solids loading on the tested filter, and particle removal was not correlated to *Cryptosporidium* oocyst removal.

Collins *et al.* (1994) investigated solids and algae removal with pilot scale vertical downflow roughing filters. Gravel media size, filter depth, and flow rate were varied to determine which design variables had the greatest effect on filter performance. Results indicated that the most influential design parameters for removing solids from water, in order of importance, were filter length, gravel size, and hydraulic flow rate. For algae removal, the most influential design parameters were hydraulic flow rate, filter length, and gravel size. Solids removal was better in filters that had been ripened with algae for 5–7 days. However, extrapolation of these results to *Cryptosporidium* removal could not be made.

c. *Request for comment.* The Agency requests comment on the information that has been presented about roughing

filters, and specifically the question of whether and under what conditions roughing filters should be awarded a 0.5 log credit for removal of *Cryptosporidium*. EPA also requests information on specific studies of *Cryptosporidium* oocyst removal by roughing filters, or from studies of the removal of surrogate parameters that have been shown to correlate with oocyst removal in roughing filters.

10. Slow Sand Filtration

a. *What is EPA proposing today?* Slow sand filtration is defined in 40 CFR 141.2 as a process involving passage of raw water through a bed of sand at low velocity (generally less than 0.4 m/h) resulting in substantial particulate removal by physical and biological mechanisms. Today's proposal allows systems using slow sand filtration as a secondary filtration step following a primary filtration process (e.g., conventional treatment) to receive an additional 2.5 log *Cryptosporidium* treatment credit. There must be no disinfectant residual in the influent water to the slow sand filtration process to be eligible for credit.

Note that this proposed credit differs from the credit proposed for slow sand filtration as a primary filtration process. EPA has concluded, based on treatment studies described in section III.D, that plants using well designed and well operated slow sand filtration as a primary filtration process can achieve an average *Cryptosporidium* removal of 3 log (Schuler and Ghosh, 1991, Timms

et al. 1995, Hall *et al.* 1994). Consequently, as described in section IV.A, EPA is proposing that plants using slow sand filtration as a primary filtration process receive a 3 log credit towards *Cryptosporidium* treatment requirements associated with Bins 2–4 under the LT2ESWTR (i.e., credit equivalent to a conventional treatment plant).

The proposed 2.5 log credit for slow sand filtration as part of the microbial toolbox applies only when it is used as a secondary filtration step, following a primary filtration process like conventional treatment. While the removal mechanisms that make slow sand filtration effective as a primary filtration process would also be operative when used as a secondary filtration step, EPA has little data on this specific application. The Agency is proposing 2.5 log credit for slow sand filtration as a secondary filtration step, in comparison to 3 log credit as a primary filtration process, as a conservative measure reflecting greater uncertainty. In addition, the proposed 2.5 log credit for slow sand filtration as part of the microbial toolbox is consistent with the recommendation in the Stage 2 M-DBP Agreement in Principle.

b. *How was this proposal developed?* The Stage 2 M-DBP Agreement in Principle recommends that slow sand filtration receive 2.5 log or greater *Cryptosporidium* treatment credit when used in addition to existing treatment that achieves compliance with the

IESWTR or LT1ESWTR. Slow sand filtration is not typically used as a secondary filtration step following conventional treatment or other primary filtration processes of similar efficacy. However, EPA expects that slow sand filtration would achieve significant removal of *Cryptosporidium* in such a treatment train.

While there is a significant body of data demonstrating the effectiveness of slow sand filtration for *Cryptosporidium* removal as a primary filtration process, as described in section III.D, EPA has limited data on the effectiveness of slow sand filtration when used as a secondary filtration step. Hall *et al.* (1994) evaluated oocyst removal for a pilot scale slow sand filter following a primary filtration process identified as a rapid gravity filter. The combined treatment train of a primary filtration process followed by slow sand filtration achieved greater than 3 log *Cryptosporidium* removal in three of five experimental runs, while approximately 2.5 log reduction was observed in the other two runs. In comparison, Hall *et al.* (1994) reported slow sand filtration alone to achieve at least a 3 log removal of oocysts in each of four experimental runs when not preceded by a primary filtration process. The authors offered no explanation for these results, but measured oocyst removals may have been impacted by limitations with the analytical method.

Removal of microbial pathogens in slow sand filters is complex and is believed to occur through a combination of physical, chemical, and biological mechanisms, both on the surface (schmutzdecke) and in the interior of the filter bed. It is unknown if the higher quality of the water that would be influent to a slow sand filter when used as a secondary filtration step would impact the efficiency of the filter in removing *Cryptosporidium*. Based on the limited data on the performance of slow sand filtration as a secondary filtration step, and in consideration of the recommendation of the Advisory Committee, EPA is proposing only a 2.5 log additional *Cryptosporidium* treatment credit for this application.

c. Request for comment. The Agency requests comment on whether the available data are adequate to support awarding a 2.5 log *Cryptosporidium* removal credit for slow sand filtration applied as a secondary filtration step, along with any additional information related to this application.

11. Membrane Filtration

a. What is EPA proposing today? EPA is proposing criteria for awarding credit to membrane filtration processes for

removal of *Cryptosporidium*. To receive removal credit, the membrane filtration process must: (1) Meet the basic definition of a membrane filtration process, (2) have removal efficiency established through challenge testing and verified by direct integrity testing, and (3) undergo periodic direct integrity testing and continuous indirect integrity monitoring during use. The maximum removal credit that a membrane filtration process is eligible to receive is equal to the lower value of either:

- The removal efficiency demonstrated during challenge testing OR
- The maximum log removal value that can be verified through the direct integrity test (*i.e.*, integrity test sensitivity) used to monitor the membrane filtration process.

By the criteria in today's proposal, a membrane filtration process could potentially meet the Bin 4 *Cryptosporidium* treatment requirements of this proposal. These criteria are described in more detail below. EPA is developing a Membrane Filtration Guidance Manual that provides additional information and procedures for meeting these criteria (USEPA 2003e). A draft of this guidance is available in the docket for today's proposal (<http://www.epa.gov/edocket/>).

Definition of a Membrane Filtration Process

For the purpose of this proposed rule, membrane filtration is defined as a pressure or vacuum driven separation process in which particulate matter larger than 1 µm is rejected by a nonfibrous, engineered barrier, primarily through a size exclusion mechanism, and which has a measurable removal efficiency of a target organism that can be verified through the application of a direct integrity test. This definition is intended to include the common membrane technology classifications: microfiltration (MF), ultrafiltration (UF), nanofiltration (NF), and reverse osmosis (RO). MF and UF are low-pressure membrane filtration processes that are primarily used to remove particulate matter and microbial contaminants. NF and RO are membrane separation processes that are primarily used to remove dissolved contaminants through a variety of mechanisms, but which also remove particulate matter via a size exclusion mechanism.

In today's proposal, the critical distinction between membrane filtration processes and bag and cartridge filters, described in section IV.C.12, is that the integrity of membrane filtration processes can be directly tested. Based

on this distinction, EPA is proposing that membrane material configured into a cartridge filtration device that meets the definition of membrane filtration and that can be direct integrity tested according to the criteria specified in this section is eligible for the same removal credit as a membrane filtration process.

Membrane devices can be designed in a variety of configurations including hollow-fiber modules, hollow-fiber cassettes, spiral-wound elements, cartridge filter elements, plate and frame modules, and tubular modules among others. In today's proposal, the generic term module is used to refer to all of these various configurations and is defined as the smallest component of a membrane unit in which a specific membrane surface area is housed in a device with a filtrate outlet structure. A membrane unit is defined as a group of membrane modules that share common valving that allows the unit to be isolated from the rest of the system for the purpose of integrity testing or other maintenance.

Challenge Testing

A challenge test is defined as a study conducted to determine the removal efficiency (*i.e.*, log removal value) of the membrane filtration media. The removal efficiency demonstrated during challenge testing establishes the maximum removal credit that a membrane filtration process is eligible to receive, provided this value is less than or equal to the maximum log removal value that can be verified by the direct integrity test (as described in the following subsection). Challenge testing is a product specific rather than a site specific requirement. At the discretion of the State, data from challenge studies conducted prior to promulgation of this regulation may be considered in lieu of additional testing. However, the prior testing must have been conducted in a manner that demonstrates a removal efficiency for *Cryptosporidium* commensurate with the treatment credit awarded to the process. Guidance for conducting challenge testing to meet the requirements of the rule is provided in the Membrane Filtration Guidance Manual (USEPA 2003e). Challenge testing must be conducted according to the following criteria:

- Challenge testing must be conducted on a full-scale membrane module identical in material and construction to the membrane modules proposed for use in full-scale treatment facilities. Alternatively, challenge testing may be conducted on a smaller membrane module, identical in material and similar in construction to the full-

scale module, if testing meets the other requirements listed in this section.

- Challenge testing must be conducted using *Cryptosporidium* oocysts or a surrogate that has been determined to be removed no more efficiently than *Cryptosporidium* oocysts. The organism or surrogate used during challenge testing is referred to as the challenge particulate. The concentration of the challenge particulate must be determined using a method capable of discretely quantifying the specific challenge particulate used in the test. Thus, gross water quality measurements such as turbidity or conductivity cannot be used.

- The maximum allowable feed water concentration used during a challenge test is based on the detection limit of the challenge particulate in the filtrate, and is determined according to the following equation:

$$\text{Maximum Feed Concentration} = 3.16 \times 10^6 \times (\text{Filtrate Detection Limit})$$

This will allow the demonstration of up to 6.5 log removal during challenge testing if the challenge particulate is removed to the detection limit.

- Challenge testing must be conducted under representative hydraulic conditions at the maximum design flux and maximum design system recovery as specified by the manufacturer. Flux is defined as the flow per unit of membrane area. Recovery is defined as the ratio of filtrate volume produced by a membrane to feed water volume applied to a membrane over the course of an uninterrupted operating cycle. An operating cycle is bounded by two consecutive backwash or cleaning events. In the context of this rule, recovery does not consider losses that occur due to the use of filtrate in backwashing or cleaning operations.

- Removal efficiency of a membrane filtration process is determined from the results of the challenge test, and expressed in terms of log removal values as defined by the following equation:

$$\text{LRV} = \text{LOG}_{10}(C_f) - \text{LOG}_{10}(C_p)$$

where LRV = log removal value demonstrated during challenge testing; C_f = the feed concentration used during the challenge test; and C_p = the filtrate concentration observed during the challenge test. For this equation to be valid, equivalent units must be used for the feed and filtrate concentrations. If the challenge particulate is not detected in the filtrate, then the term C_p is set equal to the detection limit. A single LRV is calculated for each membrane module evaluated during the test.

- The removal efficiency of a membrane filtration process demonstrated during challenge testing is expressed as a log removal value ($\text{LRV}_{C-\text{Test}}$). If fewer than twenty modules are tested, then $\text{LRV}_{C-\text{Test}}$ is assigned a value equal to the lowest of the representative LRVs among the various modules tested. If twenty or more modules are tested, then $\text{LRV}_{C-\text{Test}}$ is assigned a value equal to the 10th percentile of the representative LRVs among the various modules tested. The percentile is defined by $[i/(n+1)]$ where i is the rank of n individual data points ordered lowest to highest. It may be necessary to calculate the 10th percentile using linear interpolation.

- A quality control release value (QCRV) must be established for a non-destructive performance test (*e.g.*, bubble point test, diffusive airflow test, pressure/vacuum decay test) that demonstrates the *Cryptosporidium* removal capability of the membrane module. The performance test must be applied to each production membrane module that did not undergo a challenge test in order to verify *Cryptosporidium* removal capability. Production membrane modules that do not meet the established QCRV are not eligible for the removal credit demonstrated during challenge testing.

- Any significant modification to the membrane filtration device (*e.g.*, change in the polymer chemistry of the membrane) requires additional challenge testing to demonstrate removal efficiency of the modified module and to define a new QCRV for the nondestructive performance test.

Direct Integrity Testing

In order to receive removal credit for *Cryptosporidium*, the removal efficiency of a membrane filtration process must be routinely verified through direct integrity testing. A direct integrity test is defined as a physical test applied to a membrane unit in order to identify and isolate integrity breaches. An integrity breach is defined as one or more leaks that could result in contamination of the filtrate. The direct integrity test method must be applied to the physical elements of the entire membrane unit including membranes, seals, potting material, associated valving and piping, and all other components which under compromised conditions could result in contamination of the filtrate.

The direct integrity tests commonly used at the time of this proposal include those that use an applied pressure or vacuum (such as the pressure decay test and diffusive airflow test), and those that measure the rejection of a particulate or molecular marker (such as

spiked particle monitoring). Today's proposal does not stipulate the use of a particular direct integrity test. Instead, the direct integrity test must meet performance criteria for resolution, sensitivity, and frequency.

Resolution is defined as the smallest leak that contributes to the response from a direct integrity test. Any direct integrity test applied to meet the requirements of this proposed rule must have a resolution of 3 μm or less. The manner in which the resolution criterion is met will depend on the type of direct integrity test used. For example, a pressure decay test can meet the resolution criterion by applying a net test pressure great enough to overcome the bubble point of a 3 μm hole. A direct integrity test that uses a particulate or molecular marker can meet the resolution criterion by applying a marker of 3 μm or smaller.

Sensitivity is defined as the maximum log removal value that can be reliably verified by the direct integrity test (LRV_{DIT}). The sensitivity of the direct integrity test applied to meet the requirements of this proposed rule must be equal to or greater than the removal credit awarded to the membrane filtration process. The manner in which LRV_{DIT} is determined will depend on the type of direct integrity test used. Direct integrity tests that use an applied pressure or vacuum typically measure the rate of pressure/vacuum decay or the flow of air through an integrity breach. The response from this type of integrity test can be related to the flow of water through an integrity breach (Q_{breach}) during normal operation, using procedures such as those described in the Membrane Filtration Guidance Manual (USEPA 2003e). Once Q_{breach} has been determined, a simple dilution model is used to calculate LRV_{DIT} for the specific integrity test application, as shown by the following equation:

$$\text{LRV}_{\text{DIT}} = \text{LOG}_{10}(Q_p / (\text{VCF} \times Q_{\text{breach}}))$$

where LRV_{DIT} = maximum log removal value that can be verified by a direct integrity test; Q_p = total design filtrate flow from the membrane unit; Q_{breach} = flow of water from an integrity breach associated with the smallest integrity test response that can be reliably measured; and VCF = volumetric concentration factor.

The volumetric concentration factor is the ratio of the suspended solids concentration on the high pressure side of the membrane relative to the feed water, and is defined by the following equation:

$$\text{VCF} = C_m / C_f$$

where C_m is the concentration of particulate matter on the high pressure

side of the membrane that remains in suspension; and C_f is the concentration of suspended particulate matter in the feed water. The magnitude of the concentration factor depends on the mode of system operation and typically ranges from 1 to 20. The Membrane Filtration Guidance Manual presents approaches for determining the volumetric concentration factor for different operating modes (USEPA 2003e).

Sensitivity of direct integrity tests that use a particulate or molecular marker is determined from the feed and filtrate concentrations of the marker. The LRV_{DIT} for this type of direct integrity test is calculated according to the following equation:

$$LRV_{DIT} = \text{LOG}_{10}(C_f) - \text{LOG}_{10}(C_p)$$

where LRV_{DIT} = maximum log removal value that can be verified by a direct integrity test; C_f = the typical feed concentration of the marker used in the test; and C_p = the filtrate concentration of the marker from an integral membrane unit. For this equation to be valid, equivalent units must be used for the feed and filtrate concentrations. An ideal particulate or molecular marker would be completely removed by an integral membrane unit.

If the sensitivity of the direct integrity test is such that LRV_{DIT} is less than LRV_{C-Test} , LRV_{DIT} establishes the maximum removal credit that a membrane filtration process is eligible to receive. Conversely, if LRV_{DIT} for a direct integrity test is greater than LRV_{C-Test} , LRV_{C-Test} establishes the maximum removal credit.

A control limit is defined as an integrity test response which, if exceeded, indicates a potential problem with the system and triggers a response. Under this proposal, a control limit for a direct integrity test must be established that is indicative of an integral membrane unit capable of meeting the *Cryptosporidium* removal credit awarded by the State. If the control limit for the direct integrity test is exceeded, the membrane unit must be taken off-line for diagnostic testing and repair. The membrane unit could only be returned to service after the repair has been completed and confirmed through the application of a direct integrity test.

The frequency of direct integrity testing specifies how often the test is performed over an established time interval. Most direct integrity tests available at the time of this proposal are applied periodically and must be conducted on each membrane unit at a frequency of not less than once every 24 hours while the unit is in operation. If

continuous direct integrity test methods become available that also meet the sensitivity and resolution criteria described earlier, they may be used in lieu of periodic testing.

EPA is proposing that at a minimum, a monthly report must be submitted to the State summarizing all direct integrity test results above the control limit associated with the *Cryptosporidium* removal credit awarded to the process and the corrective action that was taken in each case.

Continuous Indirect Integrity Monitoring

The majority of currently available direct integrity test methods are applied periodically since the membrane unit must be taken out of service to conduct the test. In order to provide some measure of process performance between direct integrity testing events, continuous indirect integrity monitoring is required. Indirect integrity monitoring is defined as monitoring some aspect of filtrate water quality that is indicative of the removal of particulate matter. If a continuous direct integrity test is implemented that meets the resolution and sensitivity criteria described previously, continuous indirect integrity monitoring is not required. Continuous indirect integrity monitoring must be conducted according to the following criteria:

- Unless the State approves an alternative parameter, continuous indirect integrity monitoring must include continuous filtrate turbidity monitoring.
- Continuous monitoring is defined as monitoring conducted at a frequency of no less than once every 15 minutes.
- Continuous monitoring must be separately conducted on each membrane unit.
- If indirect integrity monitoring includes turbidity and if the filtrate turbidity readings are above 0.15 NTU for a period greater than 15 minutes (*i.e.*, two consecutive 15-minute readings above 0.15 NTU), direct integrity testing must be performed on the associated membrane units.
- If indirect integrity monitoring includes a State-approved alternative parameter and if the alternative parameter exceeds a State-approved control limit for a period greater than 15 minutes, direct integrity testing must be performed on the associated membrane units.

• EPA is proposing that at a minimum, a monthly report must be submitted to the primacy agency summarizing all indirect integrity monitoring results triggering direct

integrity testing and the corrective action that was taken in each case.

b. *How was this proposal developed?* The Stage 2 M-DBP Agreement in Principle recommends that EPA develop criteria to award *Cryptosporidium* removal credit to membrane filtration processes. Today's proposal and the supporting guidance are consistent with the Agreement.

A number of studies have been conducted which have demonstrated the ability of membrane filtration processes to remove pathogens, including *Cryptosporidium*, to below detection levels. A literature review summarizing the results of several comprehensive studies was conducted by EPA and is presented in Low-Pressure Membrane Filtration for Pathogen Removal: Application, Implementation, and Regulatory Issues (USEPA 2001h). Many of these studies used *Cryptosporidium* seeding to demonstrate removal efficiencies as high as 7 log. The collective results from these studies demonstrate that an integral membrane module, *i.e.*, a membrane module without any leaks or defects, with an exclusion characteristic smaller than *Cryptosporidium*, is capable of removing this pathogen to below detection in the filtrate, independent of the feed concentration.

Some filtration devices have used membrane media in a cartridge filter configuration; however, few data are available documenting their ability to meet the requirements for membrane filtration described in section IV.C.11.a of this preamble. However, in one study reported by Dwyer *et al.* (2001), a membrane cartridge filter demonstrated *Cryptosporidium* removal efficiencies in excess of 6 log. This study illustrates the potentially high removal capabilities of membrane filtration media configured into a cartridge filtration device, thus providing a basis for awarding removal credits to these devices under the membrane filtration provision of the rule, assuming that the device meets the definition of a membrane filtration process as well as the direct integrity test requirements.

Today's proposal requires challenge testing of membrane filtration processes used to remove *Cryptosporidium*. As noted in section III.D, EPA believes this is necessary due to the proprietary nature of these systems and the lack of any uniform criteria for establishing the exclusion characteristic of a membrane. Challenge testing addresses the lack of a standard approach for characterizing membranes by requiring direct verification of removal efficiency. The proposed challenge testing is product-specific and not site-specific since the

intent of this testing is to demonstrate the removal capabilities of the membrane product rather than evaluate the feasibility of implementing membrane treatment at a specific plant.

Testing can be conducted using a full-scale module or a smaller module if the results from the small-scale module test can be related to full-scale module performance. Most challenge studies presented in the literature have used full-scale modules, which provide results that can be directly related to full-scale performance. However, use of smaller modules is considered feasible in the evaluation of removal efficiency, and a protocol for challenge testing using small-scale modules has been proposed (NSF, 2002a). Since the removal efficiency of an integral membrane is a direct function of the membrane material, it may be possible to use a small-scale module containing the same membrane fibers or sheets used in full-scale modules for this evaluation. However, it will be necessary to relate the results of the small-scale module test to the nondestructive performance test quality control release value that will be used to validate full-scale production modules.

Challenge testing with either *Cryptosporidium* oocysts or a surrogate is permitted. Challenge testing with *Cryptosporidium* clearly provides direct verification of removal efficiency for this pathogen; however, several studies have demonstrated that surrogates can provide an accurate or conservative measure of *Cryptosporidium* removal efficiency. Since removal of particulate matter larger than 1 μm by a membrane filtration process occurs primarily via a size exclusion mechanism, the shape and size distribution of the surrogate must be selected such that the surrogate is not removed to a greater extent than the target organism. Surrogates that have been successfully used in challenge studies include polystyrene microspheres and bacterial endospores. The bacterial endospore, *Bacillus subtilis*, has been used as a surrogate for *Cryptosporidium* oocysts during challenge studies evaluating pathogen removal by physical treatment processes, including membrane filtration (Rice *et al.* 1996, Fox *et al.* 1998, Trimboli *et al.* 1999, Owen *et al.* 1999). Studies evaluating cartridge filters have demonstrated that polystyrene microspheres can provide an accurate or conservative measure of removal efficiency (Long, 1983, Li *et al.* 1997). Furthermore, the National Sanitation Foundation (NSF) Environmental Technology Verification (ETV) protocol for verification testing

for physical removal of microbiological and particulate contaminants specifies the use of polymeric microspheres of a known size distribution (NSF 2002b). Guidance on selection of an appropriate surrogate for establishing a removal efficiency for *Cryptosporidium* during challenge testing is presented in the Membrane Filtration Guidance Manual (USEPA 2003e).

The design of the proposed challenge studies is similar to the design of the seeding studies described in the literature cited earlier. Seeding studies are used to challenge the membrane module with pathogen levels orders of magnitude higher than those encountered in natural waters. However, elevated feed concentrations can lead to artificially high estimates of removal efficiency. To address this issue, the feed concentration applied to the membrane during challenge studies is capped at a level that will allow the demonstration of up to 6.5 log removal efficiency if the challenge particulate is removed to the detection level.

Because challenge testing with *Cryptosporidium* or a surrogate is not conducted on every membrane module, it is necessary to establish criteria for a non-destructive performance test that can be applied to all production membrane modules. Results from a non-destructive test, such as a bubble point test, that are correlated with the results of challenge testing can be used to establish a quality control release value (QCRV) that is indicative of the ability of a membrane filtration process to remove *Cryptosporidium*. The non-destructive test and QCRV can be used to verify the *Cryptosporidium* removal capability of modules that are not challenge tested. Most membrane manufacturers have already adapted some form of non-destructive testing for product quality control purposes and have established a quality control release value that is indicative of an acceptable product. It may be possible to apply these existing practices for the purpose of verifying the capability of a membrane filtration process to remove *Cryptosporidium*.

Challenge testing provides a means of demonstrating the removal efficiency of an integral membrane module; however, defects or leaks in the membrane or other system components can result in contamination of the filtrate unless they are identified, isolated, and repaired. In order to verify continued performance of a membrane system, today's proposal requires direct integrity testing of membrane filtration processes used to meet *Cryptosporidium* treatment requirements. Direct integrity testing is required because it is a test applied to

the physical membrane module and, thus, a direct evaluation of integrity. Furthermore, direct integrity methods are the most sensitive integrity monitoring methods commonly used at the time of this proposal (Adham *et al.* 1995).

The most common direct integrity tests apply a pressure or a vacuum to one side of a fully wetted membrane and monitor either the pressure decay or the volume of displaced fluid over time. However, the proprietary nature of these systems makes it impractical to define a single direct integrity test methodology that is applicable to all existing and future membrane products. Therefore, performance criteria have been established for any direct integrity test methodology used to verify the removal efficiency of a membrane system. These performance criteria are resolution, sensitivity, and frequency.

As stated previously, the resolution of an integrity test refers to the smallest leak that contributes to the response from an integrity test. For example, in a pressure decay integrity test, resolution is the smallest leak that contributes to pressure loss during the test. Today's proposal specifies a resolution of 3 μm or less, which is based on the size of *Cryptosporidium* oocysts. This requirement ensures that a leak that could pass a *Cryptosporidium* oocyst would contribute to the response from an integrity test.

The sensitivity of an integrity test refers to the maximum log removal that can be reliably verified by the test. Again using the pressure decay integrity test as an example, the method sensitivity is a function of the smallest pressure loss that can be detected over a membrane unit. Today's proposal limits the log removal credit that a membrane filtration process is eligible to receive to the maximum log removal value that can be verified by a direct integrity test.

In order to serve as a useful process monitoring tool for assuring system integrity, it is necessary to establish a site-specific control limit for the integrity test that corresponds to the log removal awarded to the process. A general approach for establishing this control limit for some integrity test methods is presented in guidance; however, the utility will need to work with the membrane manufacturer and State to establish a site-specific control limit appropriate for the integrity test used and level of credit awarded. Excursions above this limit indicate a potential integrity breach and would trigger removal of the suspect unit from service followed by diagnostic testing and subsequent repair, as necessary.

Most direct integrity tests available at the time of this proposal must be applied periodically since it is necessary to take the membrane unit out of service to conduct the test. Today's proposal establishes the minimum frequency for performing a direct integrity test at once per 24 hours. Currently, there is no standard frequency for direct integrity testing that has been adopted by all States and membrane treatment facilities. In a recent survey, the required frequency of integrity testing was found to vary from once every four hours to once per week; however, the most common frequency for conducting a direct integrity test was once every 24 hours (USEPA 2001h). Specifically, 10 out of 14 States that require periodic direct integrity testing specify a frequency of once every 24 hours. Furthermore, many membrane manufacturers of systems with automated integrity test systems set up the membrane units to automatically perform a direct integrity test once per 24 hours. EPA has concluded that the 24 hour direct integrity test frequency ensures that removal efficiency is verified on a routine basis without resulting in excessive system downtime.

Since most direct integrity tests are applied periodically, it is necessary to implement some level of continuous monitoring to assess process performance between direct integrity test events. In the absence of a continuous direct integrity test, continuous indirect integrity monitoring is required. Although it has been shown that commonly used indirect integrity monitoring methods lack the sensitivity to detect small integrity breaches that are of concern (Adham *et al.* 1995), they can detect large breaches and provide some assurance that a major failure has not occurred between direct integrity test events. Turbidity monitoring is proposed as the method of indirect integrity monitoring unless the State approves an alternate approach. Available data indicate that an integral membrane filtration process can consistently produce water with a turbidity less than 0.10 NTU, regardless of the feedwater quality. Consequently, EPA is proposing that exceedance of a filtrate turbidity value of 0.15 NTU triggers direct integrity testing to verify and isolate the integrity breach.

c. *Request for comment.* EPA requests comment on the following issues:

- EPA is proposing to include membrane cartridge filters that can be direct integrity tested under the definition of a membrane filtration process since one of the key differences between membrane filtration processes and bag and cartridge filters, within the

context of this regulation, is the applicability of direct integrity test methods to the filtration process. EPA requests comment on the inclusion of membrane cartridge filters that can be direct integrity tested under the definition of a membrane filtration process in this rule.

- The applicability of the proposed *Cryptosporidium* removal credits and performance criteria to *Giardia lamblia*.

- Appropriate surrogates, or the characteristics of appropriate surrogates, for use in challenge testing. EPA requests data or information demonstrating the correlation between removal of a proposed surrogate and removal of *Cryptosporidium* oocysts.

- The use of a non-destructive performance test and associated quality control release values for demonstrating the *Cryptosporidium* removal capability of membrane modules that are not directly challenge tested.

- The appropriateness of the minimum direct integrity test frequency of once per 24 hours.

- The proposed minimum reporting frequency for direct integrity testing results above the control limit and indirect integrity monitoring results that trigger direct integrity monitoring.

12. Bag and Cartridge Filtration

a. *What is EPA proposing today?* EPA is proposing criteria for awarding *Cryptosporidium* removal credit of 1 log for bag filtration processes and 2 log for cartridge filtration processes. To receive removal credit the process must: (1) Meet the basic definition of a bag or cartridge filter and (2) have removal efficiency established through challenge testing.

Definition of a Bag or Cartridge Filter

For the purpose of this rule, bag and cartridge filters are defined as pressure driven separation processes that remove particulate matter larger than 1 μm using an engineered porous filtration media through either surface or depth filtration.

The distinction between bag filters and cartridge filters is based on the type of filtration media used and the manner in which the devices are constructed. Bag filters are typically constructed of a non-rigid, fabric filtration media housed in a pressure vessel in which the direction of flow is from the inside of the bag to outside. Cartridge filters are typically constructed as rigid or semi-rigid, self-supporting filter elements housed in pressure vessels in which flow is from the outside of the cartridge to the inside.

Although all filters classified as cartridge filters share similarities with

respect to their construction, there are significant differences among the various commercial cartridge filtration devices. From a public health perspective, an important distinction among these filters is the ability to directly test the integrity of the filtration system in order to verify that there are no leaks that could result in contamination of the filtrate. Any membrane cartridge filtration device that can be direct integrity tested according to the criteria specified in section IV.C.11.a is eligible for removal credit as a membrane, subject to the criteria specified in that section. Section IV.C.12 applies to all bag filters, as well as to cartridge filters which cannot be direct integrity tested.

Challenge Testing

In order to receive 1 log removal credit, a bag filter must have a demonstrated removal efficiency of 2 log or greater for *Cryptosporidium*. Similarly, to receive 2 log removal credit, a cartridge filter must have a demonstrated removal efficiency of 3 log or greater for *Cryptosporidium*. The 1 log factor of safety is applied to the removal credit awarded to these filtration devices based on two primary considerations. First, the removal efficiency of some bag and cartridge filters has been observed to vary by more than 1 log over the course of operation (Li *et al.* 1997, NSF 2001a, NSF 2001b). Second, bag and cartridge filters are not routinely direct integrity tested during operation in the field; hence, there is no means of verifying the removal efficiency of filtration units during routine use. Based on these considerations, a conservative approach to awarding removal credit based on challenge test results is warranted.

Removal efficiency must be demonstrated through a challenge test conducted on the bag or cartridge filter proposed for use in full-scale drinking water treatment facilities for removal of *Cryptosporidium*. Challenge testing is required for specific products and is not intended to be site specific. At the discretion of the State, data from challenge studies conducted prior to promulgation of this regulation may be considered in lieu of additional testing. However, the prior testing must have been conducted in a manner that demonstrates a removal efficiency for *Cryptosporidium* commensurate with the treatment credit awarded to the process. Guidance on conducting challenge studies to demonstrate the *Cryptosporidium* removal efficiency of filtration units is presented in the Membrane Filtration Guidance Manual (USEPA 2003e). Challenge testing must

be conducted according to the following criteria:

- Challenge testing must be conducted on a full-scale filter element identical in material and construction to the filter elements proposed for use in full-scale treatment facilities.

- Challenge testing must be conducted using *Cryptosporidium* oocysts or a surrogate which is removed no more efficiently than

Cryptosporidium oocysts. The organism or surrogate used during challenge testing is referred to as the challenge particulate. The concentration of the challenge particulate must be determined using a method capable of discretely quantifying the specific organism or surrogate used in the test, *i.e.*, gross water quality measurements such as turbidity cannot be used.

- The maximum allowable feed water concentration used during a challenge test is based on the detection limit of the challenge particulate in the filtrate and calculated using one of the following equations.

For bag filters:

$$\text{Maximum Feed Concentration} = 3.16 \times 10^3 \times (\text{Filtrate Detection Limit})$$

For cartridge filters:

$$\text{Maximum Feed Concentration} = 3.16 \times 10^4 \times (\text{Filtrate Detection Limit})$$

This will allow the demonstration of up to 3.5 log removal for bag filters and 4.5 log removal for cartridge filters during challenge testing if the challenge particulate is removed to the detection limit.

- Challenge testing must be conducted at the maximum design flow rate specified by the manufacturer.

- Each filter must be tested for a duration sufficient to reach 100% of the terminal pressure drop, a parameter specified by the manufacturer which establishes the end of the useful life of the filter. In order to achieve terminal pressure drop during the test, it will be necessary to add particulate matter to the test solution, such as fine carbon test dust or bentonite clay particles.

- Each filter must be challenged with the challenge particulate during three periods over the filtration cycle: within 2 hours of start-up after a new bag or cartridge filter has been installed, when the pressure drop is between 45 and 55% of the terminal pressure drop, and at the end of the run after the pressure drop has reached 100% of the terminal pressure drop.

- Removal efficiency of a bag or cartridge filtration process is determined from the results of the challenge test, and expressed in terms of log removal values as defined by the following equation:

$$\text{LRV} = \text{LOG}_{10}(C_f) - \text{LOG}_{10}(C_p)$$

where LRV = log removal value demonstrated during challenge testing; C_f = the feed concentration used during the challenge test; and C_p = the filtrate concentration observed during the challenge test. For this equation to be valid, equivalent units must be used for the feed and filtrate concentrations. If the challenge particulate is not detected in the filtrate, then the term C_p is set equal to the detection limit. An LRV is calculated for each filter evaluated during the test.

- In order to receive treatment credit for *Cryptosporidium* under this

proposed rule, challenge testing must demonstrate a removal efficiency of 2 log or greater for bag filtration and 3 log or greater for cartridge filtration. If fewer than twenty filters are tested, then removal efficiency of the process is set equal to the lowest of the representative LRVs among the various filters tested. If twenty or more filters are tested, then removal efficiency of the process is set equal to the 10th percentile of the representative LRVs among the various filters tested. The percentile is defined by $[i/(n+1)]$ where i is the rank of n individual data points ordered lowest to highest. It may be necessary to calculate the 10th percentile using linear interpolation.

- Any significant modification to the filtration unit (*e.g.*, changes to the filtration media, changes to the configuration of the filtration media, significant modifications to the sealing system) would require additional challenge testing to demonstrate removal efficiency of the modified unit.

b. *How was this proposal developed?*

The Stage 2 M-DBP Agreement in Principle recommended that EPA develop criteria for awarding *Cryptosporidium* removal credits of 1 log for bag filters and 2 log for cartridge filters. Today's proposal is consistent with the Agreement.

A limited amount of published data are available regarding the removal efficiency of bag and cartridge filters with respect to *Cryptosporidium* oocysts or suitable surrogates. The relevant studies identified in the literature are summarized in Table IV-18.

TABLE IV-18.—RESULTS FROM STUDIES OF *Cryptosporidium* OR SURROGATE REMOVAL BY BAG AND CARTRIDGE FILTERS

Process	Log removal	Organism/surrogate	Reference
Bag and cartridge filtration in series.	1.1 to 2.1	3 to 6 μm spheres	NSF 2001a.
Cartridge filtration	3.5 (average)	<i>Cryptosporidium</i>	Enriquez et al. 1999.
Cartridge filtration	3.3 (average)	<i>Cryptosporidium</i>	Roessler, 1998.
Cartridge filtration	1.1 to 3.3	<i>Cryptosporidium</i>	Schaub et al. 1993.
Cartridge filtration	0.5 to 3.6	5.7 μm spheres	Long, 1983.
Cartridge filtration	2.3 to 2.8	<i>Cryptosporidium</i>	Ciardelli, 1996a.
Cartridge filtration	2.7 to 3.7	<i>Cryptosporidium</i>	Ciardelli, 1996b.
Pre-filter and bag filter in series	1.9 to 3.2	3.7 μm spheres	NSF 2001b.
Bag filtration	~3.0	<i>Cryptosporidium</i>	Cornwell and LeChevallier, 2002.
Bag filtration	0.5 to 3.6	<i>Cryptosporidium</i>	Li et al. 1997.
Bag filtration	0.5 to 2.0	4.5 μm spheres	Goodrich et al. 1995.

These data demonstrate highly variable removal performance for these processes, ranging from 0.5 log to 3.6 log for both bag and cartridge filtration. Results of these studies also show no correlation between the pore size rating established by the manufacturer and the

removal efficiency of a filtration device. In a study evaluating two cartridge filters, both with a pore size rating of 3 μm, a 2 log difference in *Cryptosporidium* oocyst removal was observed between the two filters (Schaub *et al.* 1993). Another study

evaluated seventeen cartridge filters with a range of pore size ratings from 1 μm to 10 μm and found no correlation with removal efficiency (Long, 1983). Li *et al.* (1997) evaluated three bag filters with similar pore size ratings and observed a 3 log difference in

Cryptosporidium oocyst removal among them. These results indicate that bag and cartridge filters may be capable of achieving removal of oocysts in excess of 3 log; however, performance can vary significantly among products and there appears to be no correlation between pore size rating and removal efficiency.

Based on available data, specific design criteria that correlate to removal efficiency cannot be derived for bag and cartridge filters. Furthermore, the removal efficiency of these proprietary devices can be impacted by product variability, increasing pressure drop over the filtration cycle, flow rate, and other operating conditions. The data in Table IV–18 were generated from studies performed under a variety of operating conditions, many of which could not be considered conservative (or worst-case) operation. These considerations lead to the proposed challenge testing requirements which are intended to establish a product-specific removal efficiency.

The proposed challenge testing is product-specific and not site-specific since the intent of this testing is to demonstrate the removal capabilities of the filtration device rather than evaluate the feasibility of implementing the technology at a specific plant. Challenge testing must be conducted using full-scale filter elements in order to evaluate the performance of the entire unit, including the filtration media, seals, filter housing and other components integral to the filtration system. This will improve the applicability of challenge test results to full-scale performance. Multiple filters of the same type can be tested to provide a better statistical basis for estimating removal efficiency.

Either *Cryptosporidium* oocysts or a suitable surrogate could be used as the challenge particulate during the test. Challenge testing with *Cryptosporidium* provides direct verification of removal efficiency; however, some studies have demonstrated that surrogates, such as polystyrene microspheres, can provide an accurate or conservative measure of removal efficiency (Long 1983, Li *et al.* 1997). Furthermore, the National Sanitation Foundation (NSF) Environmental Technology Verification (ETV) protocol for verification testing for physical removal of microbiological and particulate contaminants specifies the use of polymeric microspheres of a known size distribution (NSF 2002b). Guidance on selection of an appropriate surrogate for establishing a removal efficiency for *Cryptosporidium* during challenge testing is presented in the Membrane Filtration Guidance Manual (USEPA 2003e).

In order to demonstrate a removal efficiency of at least 2 or 3 log for bag or cartridge filters, respectively, it will likely be necessary to seed the challenge particulate into the test solution. A criticism of published studies that use this approach is that the seeded levels are orders of magnitude higher than those encountered in natural waters and this could potentially lead to artificially high estimates of removal efficiency. To address this issue, the feed concentration applied to the filter during challenge studies is capped at a level that will allow the demonstration of a removal efficiency up to 4.5 log for cartridge filters and 3.5 log for bag filters if the challenge particulate is removed to the detection level.

The removal efficiency of some bag and cartridge filtration devices has been shown to decrease over the course of a filtration cycle due to the accumulation of solids and resulting increase in pressure drop. As an example, Li *et al.* (1997) observed that the removal of 4.5 μm microspheres by a bag filter decreased from 3.4 log to 1.3 log over the course of a filtration cycle. Studies evaluating bag and cartridge filtration under the NSF ETV program have also shown a degradation in removal efficiency over the course of the filtration cycle (NSF 2001a and 2001b). In order to evaluate this potential variability, the challenge studies are designed to assess removal efficiency during three periods of a filtration cycle: within two hours of startup following installation of a new filter, between 45% and 55% of terminal pressure drop, and at the end of the run after 100% of terminal pressure drop is realized.

Although challenge testing can provide an estimate of removal efficiency for a bag or cartridge filtration process, it is not feasible to conduct a challenge test on every production filter. This, coupled with variability within a product line, could result in some production filters that do not meet the removal efficiency demonstrated during challenge testing. For membrane filtration processes, this problem is addressed through the use of a quality control release value established for a non-destructive test, such as a bubble point test or pressure hold test, that is correlated to removal efficiency. Since the non-destructive test can be applied to all production membrane modules, this provides a feasible means of verifying the performance of every membrane module used by a PWS. However, the non-destructive tests applied to membrane filtration processes cannot be applied to most bag and cartridge filtration devices, and EPA is not aware of an alternative non-

destructive test that can be used with these devices.

Typical process monitoring for bag and cartridge filtration systems includes turbidity and pressure drop to determine when filters must be replaced. However, the applicability of either of these process monitoring parameters as tools for verifying removal of *Cryptosporidium* has not been demonstrated. Only a few bag or cartridge filtration studies have attempted to correlate turbidity removal with removal of *Cryptosporidium* oocysts or surrogates. Li *et al.* (1997) found that the removal efficiency for turbidity was consistently lower than removal efficiency for oocysts or microspheres for the three bag filters evaluated. Furthermore, none of the filters was capable of consistently producing a filtered water turbidity below 0.3 NTU for the waters evaluated. The contribution to turbidity from particles much smaller than *Cryptosporidium* oocysts, and much smaller than the mesh size of the filter, make it difficult to correlate removal of turbidity with removal of *Cryptosporidium*. Consequently, EPA is proposing a 1 log factor of safety to be applied to challenge test results in awarding treatment credit to bag and cartridge filters, and is not proposing integrity monitoring requirements for these devices.

c. *Request for comment.* EPA requests comment on the following issues concerning bag and cartridge filters:

- The performance of bag and cartridge filters in removing *Cryptosporidium* through all differential pressure ranges in a filter run—EPA requests laboratory and field data, along with associated quality assurance and quality control information, that will support a determination of the appropriate level of *Cryptosporidium* removal credit to award to these technologies.

- The performance of bag and cartridge filters in removing *Cryptosporidium* when used in series with other bag or cartridge filters—EPA requests laboratory and field data, along with associated quality assurance and quality control information, that will support a determination of the appropriate level of *Cryptosporidium* removal credit to award to these technologies when used in series.

- Appropriate surrogates, or the characteristics of appropriate surrogates, for use in challenge testing bag and cartridge filters—EPA requests data or information demonstrating the correlation between removal of a proposed surrogate and removal of *Cryptosporidium* oocysts.

- The availability of non-destructive tests that can be applied to bag and cartridge filters to verify the removal efficiency of production filters that are not directly challenge tested—EPA requests data or information demonstrating the correlation between a proposed non-destructive test and the removal of *Cryptosporidium* oocysts.

- The applicability of pressure drop monitoring, filtrate turbidity monitoring, or other process monitoring and process control procedures to verify the integrity of bag and cartridge filters—EPA requests data or information demonstrating the correlation between a proposed process monitoring tool and the removal of *Cryptosporidium* oocysts.

- The applicability of bag and cartridge filters to different source water types and treatment scenarios.

- The applicability of the proposed *Cryptosporidium* removal credits and testing criteria to *Giardia lamblia*.

- The use of a 1 log factor of safety for awarding credit to bag and cartridge filters—EPA requests comment on whether this is an appropriate factor of safety to account for the inability to conduct integrity monitoring of these devices, as well as the variability in removal efficiency observed over the course of a filtration cycle for some filtration devices. This inability creates uncertainty regarding both changes in the performance of a given filter during use and variability in performance among filters in a given product line. If the 1 log factor of safety is higher than necessary to account for these factors, should the Agency establish a lower value, such as a 0.5 log factor of safety?

13. Secondary Filtration

a. What is EPA proposing today?

Today's proposal allows systems using a second filtration stage to receive an additional 0.5 log *Cryptosporidium* removal credit. To be eligible for this credit, the secondary filtration must consist of rapid sand, dual media, granular activated carbon (GAC), or other fine grain media in a separate stage following rapid sand or dual media filtration. A cap, such as GAC, on a single stage of filtration will not qualify for this credit. In addition, the first stage of filtration must be preceded by a coagulation step, and both stages must treat 100% of the flow.

b. How was this proposal developed?

Although not addressed in the Agreement in Principle, EPA has determined that secondary filtration meeting the criteria described in this section will achieve additional removal of *Cryptosporidium* oocysts. Consequently, additional removal credit

may be appropriate. As reported in section III.D, many studies have shown that rapid sand filtration preceded by coagulation can achieve significant removal of *Cryptosporidium* (Patania *et al.* 1995, Nieminski and Ongerth 1995, Ongerth and Pecoraro 1995, LeChevallier and Norton 1992, LeChevallier *et al.* 1991, Dugan *et al.* 2001, Nieminski and Bellamy 2000, McTigue *et al.* 1998, Patania *et al.* 1999, Huck *et al.* 2000, Emelko *et al.* 2000). While these studies evaluated only a single stage of filtration, the same mechanisms of removal are expected to occur in a second stage of granular media filtration.

EPA received data from the City of Cincinnati, OH, on the removal of aerobic spores through a conventional treatment facility that employs GAC contactors for DBP, taste, and odor control after rapid sand filtration. As described previously, a number of studies (Dugan *et al.* 2001, Emelko *et al.* 1999 and 2000, Yates *et al.* 1998, Mazounie *et al.* 2000) have demonstrated that aerobic spores are a conservative indicator of *Cryptosporidium* removal by granular media filtration when preceded by coagulation.

During the period of 1999 and 2000, the mean values of reported spore concentrations in the influent and effluent of the Cincinnati GAC contactors were 35.7 and 6.4 cfu/100 mL, respectively, indicating an average removal of 0.75 log across the contactors. Approximately 16% of the GAC filtered water results were below detection limit (1 cfu/100 mL) so the actual log spore removal may have been greater than indicated by these results.

In summary, studies in the cited literature demonstrate that a fine granular media filter preceded by coagulation can achieve high levels of *Cryptosporidium* removal. Data on increased removal resulting from a second stage of filtration are limited, and there is uncertainty regarding how effective a second stage of filtration will be in reducing levels of microbial pathogens that are not removed by the first stage of filtration. However, EPA has concluded that a secondary filtration process can achieve 0.5 log or greater removal of *Cryptosporidium* based on (1) the theoretical consideration that the same mechanisms of pathogen removal will be operative in both a primary and secondary filtration stage, and (2) data from the City of Cincinnati showing aerobic spore removal in GAC contactors following rapid sand filtration. Therefore, EPA believes it is appropriate to propose 0.5 log additional *Cryptosporidium*

treatment credit for systems using secondary filtration which meets the criteria of this section.

c. *Request for comment.* The Agency requests comment on awarding a 0.5 log *Cryptosporidium* removal credit for systems using secondary filtration, including the design and operational criteria required to receive the log removal credit. EPA specifically requests comment on the following issues:

- Should there be a minimum required depth for the secondary filter (e.g., 24 inches) in order for the system to receive credit?

- Should systems be eligible to receive additional *Cryptosporidium* treatment credit within the microbial toolbox for both a second clarification stage (e.g., secondary filtration, second stage sedimentation) and lower finished water turbidity, given that additional particle removal achieved by the second clarification stage will reduce finished water turbidity?

14. Ozone and Chlorine Dioxide

a. What is EPA proposing today?

Similar to the methodology used for estimating log inactivation of *Giardia lamblia* by various chemical disinfectants in 40 CFR 141.74, EPA is proposing the CT concept for estimating log inactivation of *Cryptosporidium* by chlorine dioxide or ozone. In today's proposal, systems must determine the total inactivation of *Cryptosporidium* each day the system is in operation, based on the CT values in Table IV-19 for ozone and Table IV-20 for chlorine dioxide. The parameters necessary to determine the total inactivation of *Cryptosporidium* must be monitored as stated in 40 CFR 141.74(b)(3)(i), (iii), and (iv), which is as follows:

- The temperature of the disinfected water must be measured at least once per day at each residual disinfectant concentration sampling point.

- The disinfectant contact time(s) ("T") must be determined for each day during peak hourly flow.

- The residual disinfectant concentration(s) ("C") of the water before or at the first customer must be measured each day during peak hourly flow.

Systems may have several disinfection segments (the segment is defined as a treatment unit process with a measurable disinfectant residual level and a liquid volume) in sequence along the treatment train. In determining the total log inactivation, the system may calculate the log inactivation for each disinfection segment and use the sum of the log inactivation estimates of *Cryptosporidium* achieved through the

plant. The Toolbox Guidance Manual, available in draft with today's proposal, provides guidance on methodologies for

determining CT values and estimating log inactivation for different

disinfection reactor designs and operations.

TABLE IV-19.—CT VALUES FOR *Cryptosporidium* INACTIVATION BY OZONE

Log credit	Water Temperature, °C ¹									
	<=0.5	1	2	3	5	7	10	15	20	25
0.5	12	12	10	9.5	7.9	6.5	4.9	3.1	2.0	1.2
1.0	24	23	21	19	16	13	9.9	6.2	3.9	2.5
1.5	36	35	31	29	24	20	15	9.3	5.9	3.7
2.0	48	46	42	38	32	26	20	12	7.8	4.9
2.5	60	58	52	48	40	33	25	16	9.8	6.2
3.0	72	69	63	57	47	39	30	19	12	7.4

¹ CT values between the indicated temperatures may be determined by interpolation.

TABLE IV-20.—CT VALUES FOR *Cryptosporidium* INACTIVATION BY CHLORINE DIOXIDE

Log credit	Water Temperature, °C ¹									
	<=0.5	1	2	3	5	7	10	15	20	25
0.5	319	305	279	256	214	180	138	89	58	38
1.0	637	610	558	511	429	360	277	179	116	75
1.5	956	915	838	767	643	539	415	268	174	113
2.0	1275	1220	1117	1023	858	719	553	357	232	150
2.5	1594	1525	1396	1278	1072	899	691	447	289	188
3.0	1912	1830	1675	1534	1286	1079	830	536	347	226

¹ CT values between the indicated temperatures may be determined by interpolation.

The system may demonstrate to the State, through the use of a State-approved protocol for on-site disinfection challenge studies or other information satisfactory to the State, that CT values other than those specified in Tables IV-19 or IV-20 are adequate to demonstrate that the system is achieving the required log inactivation of *Cryptosporidium*. Protocols for making such demonstrations are available in the Toolbox Guidance Manual.

b. *How was this proposal developed?* EPA relied in part on analyses by Clark *et al.* (2002a and 2002b) to develop the CT values for ozone and chlorine dioxide inactivation of *Cryptosporidium* in today's proposal. Clark *et al.* (2002a) used data from studies of ozone inactivation of *Cryptosporidium* in laboratory water to develop predictive equations for estimating inactivation (Rennecker *et al.* 1999, Li *et al.* 2001) and data from studies in natural water to validate the equations (Owens *et al.* 2000, Oppenheimer *et al.* 2000). For chlorine dioxide, Clark *et al.* (2002b) employed data from Li *et al.* (2001) to develop equations for predicting inactivation, and used data from Owens *et al.* (1999) and Ruffell *et al.* (2000) to validate the equations.

Another step in developing the CT values for *Cryptosporidium* inactivation in today's proposal involved consideration of the appropriate

confidence bound to apply when analyzing the inactivation data. A confidence bound represents a safety margin that accounts for variability and uncertainty in the data that underlie the analysis. Confidence bounds are intended to provide a high likelihood that systems operating at a given CT value will achieve at least the corresponding log inactivation level in the CT table.

Two types of confidence bounds that are used when assessing relationships between variables, such as disinfectant dose (CT) and log inactivation, are confidence in the regression and confidence in the prediction. Confidence in the regression accounts for uncertainty in the regression line (*e.g.*, a linear relationship between temperature and the log of the ratio of CT to log inactivation). Confidence in the prediction accounts for both uncertainty in the regression line and variability in experimental observations—it describes the likelihood of a single future data point falling within a range. Bounds for confidence in prediction are wider (*i.e.*, more conservative) than those for confidence in the regression. Depending on the degree of confidence applied, most points in a data set typically will fall within the bounds for confidence in the prediction, while a significant fraction will fall outside the bounds for confidence in the regression.

In developing earlier CT tables, EPA has used bounds for confidence in the prediction. This was a conservative approach that was taken with consideration of the limited inactivation data that were available and that reasonably ensured systems would achieve the required inactivation level. The November 2001 draft of the LT2ESWTR included CT tables for *Cryptosporidium* inactivation by ozone and chlorine dioxide that were derived using confidence in prediction (USEPA 2001g). However, based on comments received on those draft tables, along with further analyses described next, EPA has revised this approach in today's proposal.

The underlying *Cryptosporidium* inactivation data used to develop the CT tables exhibit significant variability. This variability is due to both experimental error and potential true variability in the inactivation rate. Experimental error is associated with the assays used to measure loss of infectivity, measurement of the disinfectant concentration, differences in technique among researchers, and other factors. True variability in the inactivation rate would be associated with variability in resistance to the disinfectant between different populations of oocysts and variability in the effect of water matrix on the inactivation process.

In considering the appropriate confidence bounds to use for developing the CT tables in today's proposal, EPA was primarily concerned with accounting for uncertainty in the regression and for true variability in the inactivation rate. Variability associated with experimental error was a lesser concern, as the purpose of the CT tables is to ensure a given level of inactivation and not predict the measured result of an individual experiment.

Because confidence in the prediction accounts for all variability in the data sets (both true variability and experimental error), it may provide a higher margin of safety than is necessary. Nevertheless, in other disinfection applications, the use of confidence in the prediction may be appropriate, given limited data sets and uncertainty in the source of the variability. However, the high doses of ozone and chlorine dioxide that are needed to inactivate *Cryptosporidium* create an offsetting concern with the formation of DBPs (e.g., bromate and chlorite). In consideration of these factors and the statutory provision for balancing risks among contaminants, EPA attempted to exclude experimental error from the confidence bound when developing the CT tables in today's proposal (i.e., used a less conservative approach than confidence in the prediction).

In order to select confidence bounds reflecting potential true variability between different oocyst populations (lots) but not variability due to measurement and experimental imprecision, it was necessary to estimate the relative contributions of these variance components. This was done by first separating inactivation data points into groups having the same *Cryptosporidium* oocyst lot and experimental conditions (e.g., water matrix, pH, temperature). Next, the variance within each group was determined. It was assumed that this within-group variance could be attributed entirely to experimental error, as neither of the factors expected to account for true variability in the inactivation rate (i.e., oocyst lot or water matrix) changed within a group. Finally, comparing the average within-group variance to the total variance in a data set provided an indication of the fraction of total variance that was due to experimental error (see Sivaganesan 2003 and Messner 2003 for details).

In carrying out this analysis on the Li *et al.* (2001) and Rennecker *et al.* (1999) data sets for ozone inactivation of *Cryptosporidium*, EPA estimated that 87.5% of the total variance could be attributed to experimental error

(Sivaganesan 2003). A similar analysis done by Najm *et al.* (2002) on the Oppenheimer *et al.* (2000) data set for ozone produced an estimate of 89% of the total variance due to experimental error. For chlorine dioxide inactivation of *Cryptosporidium*, EPA estimated that 62% of the total variance in the Li *et al.* (2001) and Ruffle *et al.* (1999) data sets could be attributed to experimental error (Messner 2003). The different fractions attributed to experimental error between the chlorine dioxide and ozone data sets presumably relates to the use of different experimental techniques (e.g., infectivity assays).

EPA employed estimates of the fraction of variance not attributable to experimental error (12.5% for ozone and 38% for chlorine dioxide) in a modified form of the equation used to calculate a bound for confidence in prediction (Messner 2003). These were applied to the regression equations developed by Clark *et al.* (2002a and 2002b) in order to estimate CT values for an upper 90% confidence bound (Sivaganesan 2003, Messner 2003). These are the CT values shown in Tables IV-19 and IV-20 for ozone and chlorine dioxide, respectively.

Since the available data are not sufficient to support the CT calculation for an inactivation level greater than 3 log, the use of Tables IV-19 and IV-20 is limited to inactivation less than or equal to 3 log. In addition, the temperature limitation for these tables is 1 to 25 °C. If the water temperature is higher than 25 °C, temperature should be set to 25 °C for the log inactivation calculation.

EPA recognizes that inactivation rates may be sensitive to water quality and operational conditions in the plant. To reflect this potential, systems are given the option to perform a site specific inactivation study to determine CT requirements. The State must approve the protocols or other information used to derive alternative CT values. However, EPA has provided guidance for systems in making such demonstrations in the Toolbox Guidance Manual.

During meetings of the Stage 2 M-DBP Advisory Committee, CT values were used in the model for impact analysis of different regulatory options (the model Surface Water Analytical Tool (SWAT), as described in Economic Analysis for the LT2ESWTR, USEPA 2003a). Those preliminary CT values were based on a subset of the data from the Li *et al.* (2001) study with laboratory waters and were adjusted with a factor to match the mean CT values derived from the Oppenheimer *et al.* (2000) study with natural waters. In comparison, the CT

values in today's proposal are higher. However, the current CT values are based on larger data sets and more comprehensive analyses. Consequently, they provide more confidence in estimates of *Cryptosporidium* log inactivation than the preliminary estimates used in earlier SWAT modeling. EPA has subsequently re-run analyses for LT2ESWTR impact assessments with the updated CT values (USEPA 2003a).

c. *Request for comments.* EPA requests comment on the proposed approach to awarding credit for inactivation of *Cryptosporidium* by chlorine dioxide and ozone, including the following specific issues:

- Determination of CT and the confidence bounds used for estimating log inactivation of *Cryptosporidium*;
- The ability of systems to apply these CT tables in consideration of the MCLs for bromate and chlorite; and
- Any additional data that may be used to confirm or refine the proposed CT tables.

15. Ultraviolet Light

a. *What is EPA proposing today?* EPA is proposing criteria for awarding credit to ultraviolet (UV) disinfection processes for inactivation of *Cryptosporidium*, *Giardia lamblia*, and viruses. The inactivation credit a system can receive for each target pathogen is based on the UV dose applied by the system in relation to the UV dose requirements in this section (see Table IV-21).

To receive UV disinfection credit, a system must demonstrate a UV dose using the results of a UV reactor validation test and ongoing monitoring. The reactor validation test establishes the operating conditions under which a reactor can deliver a required UV dose. Monitoring is used to demonstrate that the system maintains these validated operating conditions during routine use.

UV dose (fluence) is defined as the product of the UV intensity over a surface area (fluence rate) and the exposure time. In practice, UV reactors deliver a distribution of doses due to variation in light intensity and flow path as particles pass through the reactor. However, for the purpose of determining compliance with the dose requirements in Table IV-21, UV dose must be assigned to a reactor based on the degree of inactivation of a microorganism achieved during a reactor validation test. This assigned UV dose is determined through comparing the reactor validation test results with a known dose-response relationship for the test microorganism. The State may

designate an alternative basis for awarding UV disinfection credit.

EPA is developing the UV Disinfection Guidance Manual (USEPA 2003d) to assist systems and States with implementing UV disinfection, including validation testing of UV reactors. This guidance is available in draft in the docket for today's proposal (<http://www.epa.gov/edocket/>).

UV Dose Tables

Table IV-21 shows the UV doses that systems must apply to receive credit for up to 3 log inactivation of *Cryptosporidium* and *Giardia lamblia* and up to 4 log inactivation of viruses. These dose values are for UV light at a wavelength of 254 nm as delivered by a low pressure mercury vapor lamp. However, the dose values can be

applied to other UV lamp types (e.g., medium pressure mercury vapor lamps) through reactor validation testing, such as is described in the draft UV Disinfection Guidance Manual (USEPA 2003d). In addition, the dose values in Table IV-21 are intended for post-filter application of UV in filtration plants and for systems that meet the filtration avoidance criteria in 40 CFR 141.71.

BILLING CODE 6560-50-P

Table IV-21.-- UV Dose Requirements for *Cryptosporidium*, *Giardia lamblia*, and Virus Inactivation Credit

Log credit	<i>Cryptosporidium</i> UV dose (mJ/cm ²)	<i>Giardia lamblia</i> UV dose (mJ/cm ²)	Virus UV dose (mJ/cm ²)
0.5	1.6	1.5	39
1.0	2.5	2.1	58
1.5	3.9	3.0	79
2.0	5.8	5.2	100
2.5	8.5	7.7	121
3.0	12	11	143
3.5	NA	NA	163
4.0	NA	NA	186

BILLING CODE 6560-50-C

Reactor Validation Testing

For a system to receive UV disinfection credit, the UV reactor type used by the system must undergo validation testing to demonstrate the operating conditions under which the reactor can deliver the required UV dose. Unless the State approves an alternative approach, this testing must involve the following: (1) Full scale testing of a reactor that conforms uniformly to the UV reactors used by the system and (2) inactivation of a test microorganism whose dose response characteristics have been quantified with a low pressure mercury vapor lamp.

Validation testing must determine a set of operating conditions that can be monitored by the system to ensure that the required UV dose is delivered under the range of operating conditions applicable to the system. At a minimum, these operating conditions must include flow rate, UV intensity as measured by

a UV sensor, and UV lamp status. The validated operating conditions determined by testing must account for the following factors: (1) UV absorbance of the water, (2) lamp fouling and aging, (3) measurement uncertainty of on-line sensors, (4) dose distributions arising from the velocity profiles through the reactor, (5) failure of UV lamps or other critical system components, and (6) inlet and outlet piping or channel configurations of the UV reactor. In the draft UV Disinfection Guidance Manual (USEPA 2003d), EPA describes testing protocols for reactor validation that are intended to meet these criteria.

Reactor Monitoring

Systems must monitor for parameters necessary to demonstrate compliance with the operating conditions that were validated for the required UV dose. At a minimum systems must monitor for UV intensity as measured by a UV sensor, flow rate, and lamp outage. As part of this, systems must check the calibration of UV sensors and recalibrate

in accordance with a protocol approved by the State.

b. *How was this proposal developed?* UV disinfection is a physical process relying on the transference of electromagnetic energy from a source (lamp) to an organism's cellular material (USEPA 1986). In the Stage 2 M-DBP Agreement in Principle, the Advisory Committee recommended that EPA determine the UV doses needed to achieve up to 3 log inactivation of *Giardia lamblia* and *Cryptosporidium* and up to 4 log inactivation of viruses.

The Agreement further recommends that EPA develop standards to determine if UV systems are acceptable for compliance with drinking water disinfection requirements, including (1) a validation protocol for drinking water applications of UV technology and (2) on-site monitoring requirements to ensure ongoing compliance with UV dose tables. EPA also agreed to develop a UV guidance manual to facilitate design and operation of UV installations. Today's proposal and

accompanying guidance for UV are consistent with the Agreement.

UV Dose Tables

The UV dose values in Table IV–21 are based on meta-analyses of UV inactivation studies with *Cryptosporidium parvum*, *Giardia lamblia*, *Giardia muris*, and adenovirus (Qian *et al.* 2003, USEPA 2003d). Proposed UV doses for inactivation of viruses are based on the dose-response of adenovirus because, among viruses that have been studied, it appears to be the most UV resistant and is a widespread waterborne pathogen (health effects of adenovirus are described in Embrey 1999).

The data supporting the dose values in Table IV–21 are from bench-scale studies using low pressure mercury vapor lamps. These data were chosen because the experimental conditions allow UV dose to be accurately quantified. Low pressure lamps emit light primarily at a single wavelength (254 nm) within the germicidal range of 200–300 nm. However, as noted earlier, these dose tables can be applied to reactors with other lamp types through reactor challenge testing, as described in the draft guidance manual. Bench scale studies are preferable for determining pathogen dose-response characteristics, due to the uniform dose distribution.

The data sets and statistical evaluation that were used to develop the UV dose table for *Cryptosporidium*, *Giardia lamblia*, and viruses are described in the draft UV Disinfection Guidance Manual (USEPA 2003d) and Qian *et al.* 2003.

Reactor Validation Testing

Today's proposal requires testing of full-scale UV reactors because of the difficulty in predicting reactor disinfection performance based on modeled results or on the results of testing at a reduced scale. All flow-through UV reactors deliver a distribution of doses due to variation in light intensity within the reactor and the different flow paths of particles passing through the reactor. Moreover, the reactor dose distribution varies temporally due to processes like lamp aging and fouling, changes in UV absorbance of the water, and fluctuations in flow rate. Consequently, it is more reliable to evaluate reactor performance through a full scale test under conditions that can be characterized as "worst case" for a given application. Such conditions include maximum and minimum flow rate and reduced light intensity within the reactor that accounts for lamp aging, fouling, and UV absorbance of the

water. Protocols for reactor validation testing are presented in the draft UV guidance manual.

c. *Request for comment.* The Agency requests comment on whether the criteria described in this section for awarding treatment credit for UV disinfection are appropriate, and whether additional criteria, or more specific criteria, should be included.

16. Individual Filter Performance

a. *What is EPA proposing today?* EPA is proposing an additional 1.0 log *Cryptosporidium* treatment credit for systems that achieve individual filter performance consistent with the goals established for the Partnership for Safe Water Phase IV in August 2001 (AWWA *et al.* 2001). Specifically, systems must demonstrate ongoing compliance with the following turbidity criteria, based on continuous monitoring of turbidity for each individual filter as required under 40 CFR 141.174 or 141.560, as applicable:

(1) Filtered water turbidity less than 0.1 NTU in at least 95% of the maximum daily values recorded at each filter in each month, excluding the 15 minute period following backwashes, and

(2) No individual filter with a measured turbidity level of greater than 0.3 NTU in two consecutive measurements taken 15 minutes apart.

Note that today's proposal does not include a required peer review step as a condition for receiving additional credit. Rather, EPA is proposing to award additional credit to systems that meet the performance goals of a peer review program (Phase IV). Systems that receive the 1 log additional treatment credit for individual filter performance, as described in this section, cannot also receive an additional 0.5 log additional credit for lower finished water turbidity as described in section IV.C.8.

b. *How was this proposal developed?* In the Stage 2 M–DBP Agreement in Principle, the Advisory Committee recommended a peer review program as a microbial toolbox component that should receive a 1.0 log *Cryptosporidium* treatment credit. The Committee specified Phase IV of the Partnership for Safe Water (Partnership) as an example of the type of peer review program where a 1.0 log credit would be appropriate.

The Partnership is a voluntary cooperative program involving EPA, the Association of Metropolitan Water Agencies (AMWA), the American Water Works Association (AWWA), the National Association of Water Companies (NAWC), the Association of State Drinking Water Administrators (ASDWA), the American Water Works

Association Research Foundation (AWWARF), and surface water utilities throughout the United States. The intent of the Partnership is to increase protection against microbial contaminants by optimizing treatment plant performance.

At the time of the Advisory Committee recommendation, Phase IV was under development by the Partnership. It was to be based on Composite Correction Program (CCP) (USEPA 1991) procedures and performance goals, and was to be awarded based on an on-site evaluation by a third-party team. The performance goals for Phase IV were such that, over a year, each sedimentation basin and each filter would need to produce specified turbidity levels based on the maximum of all the values recorded during the day. Sedimentation performance goals were set at 2.0 NTU if the raw water was greater than 10 NTU on an annual basis and 1.0 NTU if the raw water was less than 10 NTU. Each filter was to meet 0.1 NTU 95% of the time except for the 15 minute period following placing the filter in operation. In addition, filters were expected to have maximum turbidity of 0.3 NTU and return to less than 0.1 NTU within 15 minutes of the filter being placed in service.

The primary purpose of the on-site evaluation was to confirm that the performance of the plant was consistent with Phase IV performance goals and that the system had the administrative support and operational capabilities to sustain the performance long-term. The on-site evaluation in Phase IV also allowed utilities that could not meet the desired performance goals to demonstrate to the third-party that they had achieved the highest level of performance given their unique raw water quality.

After the signing of the Stage 2 M–DBP Agreement in Principle in September 2000, the Partnership decided to eliminate the on-site third-party evaluation as a component of Phase IV. Instead, the requirement for Phase IV is for the water system to complete an application package that will be reviewed by trained utility volunteers. Included in the application package is an Optimization Assessment Spreadsheet in which the system enters water quality and treatment data to demonstrate that Phase IV performance levels have been achieved. The application also requires narratives related to administrative support and operational capabilities to sustain performance long-term.

Today's proposal is consistent with the performance goals of Phase IV.

Rather than require systems to complete an application package with historical data and narratives, the LT2ESWTR requires systems to demonstrate to the State that they meet the individual filter performance goals of Phase IV on an ongoing basis to receive the 1.0 log additional *Cryptosporidium* treatment credit. EPA is not requiring systems to demonstrate that they meet sedimentation performance goals of Phase IV. While EPA recognizes that settled water turbidity is an important operational performance measure for a plant, the Agency does not have data directly relating it to finished water quality and pathogen risk.

The November 2001 pre-proposal draft of the LT2ESWTR described a potential 1.0 log credit for systems that achieved individual filter effluent (IFE) turbidity below 0.15 NTU in 95 percent of samples (USEPA 2001g). The Science Advisory Board (SAB) subsequently reviewed this credit and supporting data on the relationship between filter effluent turbidity and *Cryptosporidium* removal efficiency (described in section IV.C.8). In written comments from a December 2001 meeting of the Drinking Water Committee, an SAB panel recommended only a 0.5 log credit for 95th percentile IFE turbidity below 0.15 NTU.

To address this recommendation from the SAB, EPA is proposing that systems meet the individual filter performance criteria of Phase IV of the Partnership in order to be eligible for a 1.0 log additional *Cryptosporidium* treatment credit. This proposed approach responds to the concerns raised by the SAB because the Phase IV criteria are more stringent than those in the 2001 pre-proposal draft of the LT2ESWTR. For example, today's proposal sets a maximum limit on individual filter effluent turbidity of 0.3 NTU, whereas no such upper limit was described in the 2001 pre-proposal draft.

In summary, EPA has concluded that it is appropriate to award additional *Cryptosporidium* treatment credit for systems meeting stringent individual filter performance standards. Modestly elevated turbidity from a single filter may not significantly impact combined filter effluent turbidity levels, which are regulated under IESWTR and LT1ESWTR, but may indicate a substantial reduction in the overall pathogen removal efficiency of the filtration process. Consequently, systems that continually achieve very low turbidity in each individual filter are likely to provide a significantly more effective microbial barrier. EPA expects that systems that select this toolbox option will have achieved a high level

of treatment process optimization and process control, and will have both a history of consistent performance over a range of raw water quality conditions and the capability and resources to maintain this performance long-term.

c. *Request for comment.* The Agency invites comment on the following issues related to the proposed credit for individual filter performance.

- Are there different or additional performance measures that a utility should be required to meet for the 1 log additional credit?
- Are there existing peer review programs for which treatment credit should be awarded under the LT2ESWTR? If so, what role should primacy agencies play in establishing and managing any such peer review program?
- The individual filter effluent turbidity criterion of 0.1 NTU is proposed because it is consistent with Phase IV Partnership standards, as based on CCP goals. However, with allowable rounding, turbidity levels less than 0.15 NTU are in compliance with a standard of 0.1. Consequently, EPA requests comment on whether 0.15 NTU should be the standard for individual filter performance credit, as this would be consistent with the standard of 0.15 NTU that is proposed for combined filter performance credit in section IV.C.8.

17. Other Demonstration of Performance

a. *What is EPA proposing today?* The purpose of the "demonstration of performance" toolbox component is to allow a system to demonstrate that a plant, or a unit process within a plant, should receive a higher *Cryptosporidium* treatment credit than is presumptively awarded under the LT2ESWTR. For example, as described in section IV.A, plants using conventional treatment receive a presumptive 3 log credit towards the *Cryptosporidium* treatment requirements in Bins 2–4 of the LT2ESWTR. This credit is based on a determination by EPA that conventional treatment plants achieve an average *Cryptosporidium* removal of 3 log when in compliance with the IESWTR or LT1ESWTR. However, EPA recognizes that some conventional treatment plants may achieve average *Cryptosporidium* removal efficiencies greater than 3 log. Similarly, some systems may achieve *Cryptosporidium* reductions with certain toolbox components that are greater than the presumptive credits awarded under the LT2ESWTR, as described in this section (IV.C).

Where a system can demonstrate that a plant, or a unit process within a plant,

achieves a *Cryptosporidium* reduction efficiency greater than the presumptive credit specified in the LT2ESWTR, it may be appropriate for the system to receive a higher *Cryptosporidium* treatment credit. Today's proposal does not include specific protocols for systems to make such a demonstration, due to the potentially complex and site specific nature of the testing that would be required. Rather, today's proposal allows a State to award a higher level of *Cryptosporidium* treatment credit to a system where the State determines, based on site-specific testing with a State-approved protocol, that a treatment plant or a unit process within a plant reliably achieves a higher level of *Cryptosporidium* removal on a continuing basis. Also, States may award a lower level of *Cryptosporidium* treatment credit to a system where a State determines, based on site specific information, that a plant or a unit process within a plant achieves a *Cryptosporidium* removal efficiency less than a presumptive credit specified in the LT2ESWTR.

Systems receiving additional *Cryptosporidium* treatment credit through a demonstration of performance may be required by the State to report operational data on a monthly basis to establish that conditions under which demonstration of performance credit was awarded are maintained during routine operation. The Toolbox Guidance Manual (USEPA 2003f) will describe potential approaches to demonstration of performance testing. This guidance is available in draft in the docket for today's proposal (<http://www.epa.gov/edocket/>).

Note that as described in section IV.C, today's proposal allows treatment plants to achieve additional *Cryptosporidium* treatment credit through meeting the design and/or operational criteria of microbial toolbox components, such as combined and individual filter performance, presedimentation, bank filtration, two-stage softening, secondary filtration, etc. Plants that receive additional *Cryptosporidium* treatment credit through a demonstration of performance are not also eligible for the presumptive credit associated with microbial toolbox components if the additional removal due to the toolbox component is captured in the demonstration of performance credit. For example, if a plant receives a demonstration of performance credit based on removal of *Cryptosporidium* or an indicator while operating under conditions of lower finished water turbidity, the plant may not also receive additional presumptive credit for lower

finished water turbidity toolbox components.

This demonstration of performance credit does not apply to the use of chlorine dioxide, ozone, or UV light, because today's proposal includes specific provisions allowing the State to modify the standards for awarding disinfection credit to these technologies. As described in section IV.C.14, States can approve site-specific CT values for inactivation of *Cryptosporidium* by chlorine dioxide and ozone; as described in section IV.C.15, States can approve an alternative approach for validating the performance of UV reactors.

b. *How was this proposal developed?* The Stage 2 M-DBP Agreement in Principle recommends demonstration of performance as a process for systems to receive *Cryptosporidium* treatment credit higher than the presumptive credit for many microbial toolbox components, as well as credit for technologies not listed in the toolbox. EPA is aware that there may be plants where particular unit processes, or combinations of unit processes, achieve greater *Cryptosporidium* removal than the presumptive credit awarded under the LT2ESWTR. In addition, the Agency would like to allow for the use of *Cryptosporidium* treatment processes not addressed in the LT2ESWTR, where such processes can demonstrate a reliable specific log removal. Due to these factors, EPA is proposing a demonstration of performance component in the microbial toolbox, consistent with the Advisory Committee recommendation.

The Agreement in Principle makes no recommendations for how a demonstration of performance should be conducted. It is generally not practical for systems to directly quantify high log removal of *Cryptosporidium* in treatment plants because of the relatively low occurrence of *Cryptosporidium* in many raw water sources and limitations with analytical methods. Consequently, if systems are to demonstrate the performance of full scale plants in removing *Cryptosporidium*, this typically will require the use of indicators, where the removal of the indicator has been correlated with the removal of *Cryptosporidium*. As described previously, a number of studies have shown that aerobic spores are an indicator of *Cryptosporidium* removal by sedimentation and filtration (Dugan *et al.* 2001, Emelko *et al.* 1999 and 2000, Yates *et al.* 1998, Mazounie *et al.* 2000).

The nature of demonstration of performance testing that will be appropriate at a given facility will

depend on site specific factors, such as water quality, the particular process(es) being evaluated, resources and infrastructure, and the discretion of the State. Consequently, EPA is not proposing specific criteria for demonstration of performance testing. Instead, systems must develop a testing protocol that is approved by the State, including any requirements for ongoing reporting if demonstration of performance credit is approved. EPA has developed a draft document, Toolbox Guidance Manual (USEPA 2003f), that is available with today's proposal and provides guidance on demonstration of performance testing.

c. *Request for comment.* The Agency requests comment on today's proposal for systems to demonstrate higher *Cryptosporidium* removal levels. EPA specifically requests comment on the following issues:

- Approaches that should be considered or excluded for demonstration of performance testing;
- Whether EPA should propose minimum elements that demonstration of performance testing must include;
- Whether a factor of safety should be applied to the results of demonstration of performance testing to account for potential differences in removal of an indicator and removal of *Cryptosporidium*, or uncertainty in the application of pilot-scale results to full-scale plants;
- Whether or under what conditions a demonstration of performance credit should be allowed for a unit process within a plant—a potential concern is that certain unit processes, such as a sedimentation basin, can be operated in a manner that will increase removal in the unit process but decrease removal in subsequent treatment processes and, therefore, lead to no overall increase in removal through the plant. An approach to address this concern is to limit demonstration of performance credit to removal demonstrated across the entire treatment plant.

D. Disinfection Benchmarks for *Giardia lamblia* and Viruses

1. What Is EPA Proposing Today?

EPA proposes to establish the disinfection benchmark under the LT2ESWTR as a procedure to ensure that systems maintain protection against microbial pathogens as they implement the Stage 2 M-DBP rules (*i.e.*, Stage 2 DBPR and LT2ESWTR). The disinfection benchmark serves as a tool for systems and States to evaluate the impact on microbial risk of proposed changes in disinfection practice. EPA established the disinfection benchmark

under the IESWTR and LT1ESWTR for the Stage 1 M-DBP rules, as recommended by the Stage 1 M-DBP Advisory Committee. Today's proposal extends disinfection benchmark requirements to apply to the Stage 2 M-DBP rules.

Under the proposed LT2ESWTR, the disinfection benchmark procedure involves a system charting levels of *Giardia lamblia* and virus inactivation at least once per week over a period of at least one year. This creates a profile of inactivation performance that the System must use to determine a baseline or benchmark of inactivation against which proposed changes in disinfection practice can be measured. Only certain systems are required to develop profiles and keep them on file for State review during sanitary surveys. When those systems that are required to develop a profile plan a significant change in disinfection practice (defined later in this section), they must submit the profile and an analysis of how the proposed change will affect the current disinfection benchmark to the State for review.

Systems that developed disinfection profiles under the IESWTR or LT1ESWTR and have not made significant changes in their disinfection practice or changed sources are not required to collect additional operational data to create disinfection profiles under the LT2ESWTR. Systems that produced a disinfection profile for *Giardia lamblia* but not viruses under the IESWTR or LT1ESWTR may be required to develop a profile for viruses under the LT2ESWTR. Where a previously developed *Giardia lamblia* profile is acceptable, systems may develop a virus profile using the same operational data (*i.e.*, CT values) on which the *Giardia lamblia* profile is based. Spreadsheets developed by EPA and States automatically calculate *Giardia lamblia* and virus profiles using the same operational data. EPA believes that virus profiling is necessary because many of the disinfection processes that systems will select to comply with the Stage 2 DBPR and LT2ESWTR (*e.g.*, chloramines, UV, MF/UF) are relatively less effective against viruses than *Giardia lamblia* in comparison to free chlorine.

The disinfection benchmark provisions contain three major components: (a) Applicability requirements and schedule, (b) characterization of disinfection practice, and (c) State review of proposed changes in disinfection practice. Each of these components is discussed in the following paragraphs.

a. *Applicability and schedule.* Proposed disinfection profiling and benchmarking requirements apply to surface water systems only. Systems serving only ground water are not subject to the requirements of the LT2ESWTR. The determination of whether a surface water system is required to develop a disinfection profile is based on whether DBP levels (TTHM or HAA5) exceed specified values, described later in this section, and whether a system is required to monitor for *Cryptosporidium*. These criteria trigger profiling because they identify systems that may be required to make treatment changes under the Stage 2 DBPR or LT2ESWTR. Note that it is not practical to wait until a system has completed *Cryptosporidium* monitoring to identify which systems should prepare a disinfection profile. A completed disinfection profile should be available at the point when a system is classified in a treatment bin and must begin developing plans to comply with any additional treatment requirements.

Unless the system developed a disinfection profile under the IESWTR or LT1ESWTR, all systems required to

monitor for *Cryptosporidium* must develop *Giardia lamblia* and virus disinfection profiles under the LT2ESWTR. This includes all surface water systems except (1) systems that provide 5.5 log total treatment for *Cryptosporidium*, equivalent to meeting the treatment requirements of Bin 4 and (2) small systems (<10,000 people served) that do not exceed the *E. coli* trigger (see section IV.A for details). Systems not required to monitor for *Cryptosporidium* as a result of providing 5.5 log of treatment are not required to prepare disinfection profiles. However, small systems that do not exceed the *E. coli* trigger are required to prepare *Giardia lamblia* and virus disinfection profiles if one of the following criteria apply, based on DBP levels in their distribution systems:

(1)* TTHM levels in the distribution system, based on samples collected for compliance with the Stage 1 DBPR, are at least 80% of the MCL (0.064 mg/L) at any Stage 1 DBPR sampling point based on a locational running annual average (LRAA).

(2)* HAA5 levels in the distribution system, based on the samples collected

for compliance with the Stage 1 DBPR, are at least 80% of the MCL (0.048 mg/L) at any Stage 1 DBPR sampling point based on an LRAA.

*These criteria only apply to systems that are required to comply with the DBP rules, *i.e.*, community and non-transient non-community systems.

Table IV–22 presents a summary schedule of the required deadlines for disinfection profiling activities, categorized by system size and whether a small system is required to monitor for *Cryptosporidium*. The deadlines are based on the expectation that a system should have a disinfection profile at the time the system is classified in a *Cryptosporidium* treatment bin under LT2ESWTR and/or has determined the need to make treatment changes for the Stage 2 DBPR. Systems have three years from this date, with a possible two year extension for capital improvements if granted by the State, within which to complete their evaluation, design, and implementation of treatment changes to meet the requirements of the LT2ESWTR and the Stage 2 DBPR.

TABLE IV–22.—SCHEDULE OF IMPLEMENTATION DEADLINES RELATED TO DISINFECTION PROFILING ¹

Activity	Systems serving ≥10,000 people ²	Systems serving <10,000 people	
		Required to monitor for <i>Cryptosporidium</i>	Not required to monitor for <i>Cryptosporidium</i> ^{2,3,6}
Complete 1 year of <i>E. coli</i> monitoring	NA	42	42
Determine whether required to profile based on DBP levels and notify State ⁶	NA	NA	42
Begin disinfection profiling ⁴	24	54	42
Complete <i>Cryptosporidium</i> monitoring	30	60	NA
Complete disinfection profiling based on at least one year's data ⁵	36	66	54

¹ Numbers in table indicate months following promulgation of the LT2ESWTR.

² Systems providing a total of 5.5 log *Cryptosporidium* treatment (equivalent to meeting Bin 4 treatment requirements) are not required to develop disinfection profiles.

³ Systems serving fewer than 10,000 people are not required to monitor for *Cryptosporidium* if mean *E. coli* levels are less than 10/100 mL for systems using lake/reservoir sources or less than 50/100 mL for systems using flowing stream sources.

⁴ Unless system has existing disinfection profiling data that are acceptable.

⁵ This deadline coincides with the start of the 3 year period at the end of which compliance with the LT2ESWTR and Stage 2 DBPR is required.

⁶ Not required to conduct profiling unless TTHM or HAA5 exceeds trigger values of 80% of MCL at any sampling point based on LRAA.

As described in the next section, systems can meet profiling requirements under the proposed LT2ESWTR using previously collected data (*i.e.*, grandfathered data). Use of grandfathered data is allowed if the system has not made a significant change in disinfection practice or changed sources since the data were collected. This will permit most systems that prepared a disinfection profile under the IESWTR or the LT1ESWTR to avoid collecting any new operational data to develop profiles under the LT2ESWTR.

The locational running annual average (LRAA) of TTHM and HAA5 levels used by small systems that do not monitor for *Cryptosporidium* to determine whether profiling is required must be based on one year of DBP data collected during the period following promulgation of the LT2ESWTR, or as determined by the State. By the date indicated in Table IV–22, these systems must report to the State on their DBP LRAAs and whether the disinfection profiling requirements apply. If either DBP LRAA meets the criteria specified previously, the system must begin

disinfection profiling by the date proposed in Table IV–22.

b. *Developing the disinfection profile and benchmark.* Under the LT2ESWTR, a disinfection profile consists of a compilation of *Giardia lamblia* and virus log inactivation levels computed at least weekly over a period of at least one year, as based on operational and water quality data (disinfectant residual concentration(s), contact time(s), temperature(s), and, where necessary, pH). The system may create the profile by conducting new weekly (or more frequent) monitoring and/or by using

grandfathered data. A system that created a *Giardia lamblia* disinfection profile under the IESWTR or LT1ESWTR may use the operational data collected for the *Giardia lamblia* profile to create a virus disinfection profile.

Grandfathered data are those operational data that a system has previously collected at a treatment plant during the course of normal operation. Those systems that have all the necessary information to determine profiles using existing operational data collected prior to the date when the system is required to begin profiling may use these data in developing profiles. However, grandfathered data must be substantially equivalent to operational data that would be collected under this rule. These data must be representative of inactivation through the entire treatment plant and not just of certain treatment segments.

To develop disinfection profiles under this rule, systems are required to exercise one of the following three options:

Option 1—Systems conduct monitoring at least once per week following the process described later in this section.

Option 2—Systems that conduct monitoring under this rule, as described under Option 1, can also use one or two years of acceptable grandfathered data, in addition to one year of new operational data, in developing the disinfection profile.

Option 3—Systems that have at least one year of acceptable existing operational data are not required to conduct new monitoring to develop the disinfection profile under this rule. Instead, they can use a disinfection profile based on one to three years of grandfathered data.

Process to be followed by PWS for developing the disinfection profile:

- Measure disinfectant residual concentration (C, in mg/L) before or at the first customer and just prior to each additional point of disinfectant addition, whether with the same or a different disinfectant.
- Determine contact time (T, in minutes) for each residual disinfectant monitoring point during peak flow conditions. T could be based on either a tracer study or assumptions based on contactor basin geometry and baffling. However, systems must use the same method for both grandfathered data and new data.
- Measure water temperature (°C) (for disinfectants other than UV).
- Measure pH (for chlorine only).

To determine the weekly log inactivation, the system must convert

operational data from one day each week to the corresponding log inactivation values for *Giardia lamblia* and viruses. The procedure for *Giardia lamblia* is as follows:

- Determine CT_{calc} for each disinfection segment.
- Determine $CT_{99.9}$ (i.e., 3 log inactivation) from tables in the SWTR (40 CFR 141.74) using temperature (and pH for chlorine) for each disinfection segment. States can allow an alternate calculation procedure (e.g., use of a spreadsheet).
- For each segment, $\log \text{ inactivation} = (CT_{calc}/CT_{99.9}) \times 3.0$.
- Sum the log inactivation values for each segment to get the log inactivation for the day (or week).

For calculating the virus log inactivation, systems should use the procedures approved by States under the IESWTR or LT1ESWTR. Log inactivation benchmark is calculated as follows:

- Determine the calendar month with the lowest log inactivation.
- The lowest month becomes the critical period for that year.
- If acceptable data from multiple years are available, the average of critical periods for each year becomes the benchmark.
- If only one year of data is available, the critical period for that year is the benchmark.

c. *State review.* If a system that is required to produce a disinfection profile proposes to make a significant change in disinfection practice, it must calculate *Giardia lamblia* and virus inactivation benchmarks and must notify the State before implementing such a change. Significant changes in disinfection practice are defined as (1) moving the point of disinfection (this is not intended to include routine seasonal changes already approved by the State), (2) changing the type of disinfectant, (3) changing the disinfection process, or (4) making other modifications designated as significant by the State. When notifying the State, the system must provide a description of the proposed change, the disinfection profiles and inactivation benchmarks for *Giardia lamblia* and viruses, and an analysis of how the proposed change will affect the current inactivation benchmarks. In addition, the system should have disinfection profiles and, if applicable, inactivation benchmarking documentation, available for the State to review as part of its periodic sanitary survey.

EPA developed for the IESWTR, with stakeholder input, the Disinfection Profiling and Benchmarking Guidance

Manual (USEPA 1999d). This manual provides guidance to systems and States on the development of disinfection profiles, identification and evaluation of significant changes in disinfection practices, and considerations for setting an alternative benchmark. If necessary, EPA will produce an addendum to reflect changes in the profiling and benchmarking requirements necessary to comply with LT2ESWTR.

2. How Was This Proposal Developed?

A fundamental premise in the development of the M-DBP rules is the concept of balancing risks between DBPs and microbial pathogens. Disinfection profiling and benchmarking were established under the IESWTR and LT1ESWTR, based on a recommendation by the Stage 1 M-DBP Federal Advisory Committee, to ensure that systems maintained adequate control of pathogen risk as they reduced risk from DBPs. Today's proposal would extend disinfection benchmarking requirements to the LT2ESWTR.

EPA believes this extension is necessary because some systems will make significant changes in their current disinfection practice to meet more stringent limits on TTHM and HAA5 levels under the Stage 2 DBPR and additional *Cryptosporidium* treatment requirements under the LT2ESWTR. In order to ensure that these systems continue to provide adequate protection against the full spectrum of microbial pathogens, it is appropriate for systems and States to evaluate the effects of such treatment changes on microbial drinking water quality. The disinfection benchmark serves as a tool for making such evaluations.

EPA projects that to comply with the Stage 2 DBPR, systems will make changes to their disinfection practice, including switching from free chlorine to chloramines and, to a lesser extent, installing technologies like ozone, membranes, and UV. Similarly, to provide additional treatment for *Cryptosporidium*, some systems will install technologies like UV, ozone, and microfiltration. While these processes are all effective disinfectants, chloramines are a weaker disinfectant than free chlorine for *Giardia lamblia*. Ozone, UV, and membranes can provide highly effective treatment for *Giardia lamblia*, but they, as well as chloramines, are less efficient for treating viruses than free chlorine, relative to their efficacy for *Giardia lamblia*. Because of this, a system switching from free chlorine to one of these alternative disinfection

technologies could experience a reduction in the level of virus and/or *Giardia lamblia* (for chloramines) treatment it is achieving. Consequently, EPA believes that systems making significant changes in their disinfection practice under the Stage 2 M-DBP rules should assess the impact of these changes with disinfection benchmarks for *Giardia lamblia* and viruses.

Changes in the proposed benchmarking requirements under the LT2ESWTR in comparison to IESWTR requirements include decreasing the frequency of calculating CT values for the disinfection profile from daily to weekly and requiring all systems to prepare a profile for viruses as well as *Giardia lamblia*. The proposal of a weekly frequency for CT calculations was made to accommodate existing profiles from small systems, which are required to make weekly CT calculations for profiling under the LT1ESWTR. As described earlier, EPA would like for systems that have prepared a disinfection profile under the IESWTR or LT1ESWTR and have not subsequently made significant changes in disinfection practice to be able to grandfather this profile for the LT2ESWTR. Allowing weekly calculation of CT values under the LT2ESWTR will make this possible.

The IESWTR and LT1ESWTR required virus inactivation profiling only for systems using ozone or chloramine as their primary disinfectant. However, as noted earlier, EPA has projected that under the Stage 2 DBPR and LT2ESWTR, systems will switch from free chlorine to disinfection processes like chloramines, UV, ozone, and microfiltration. The efficiency of these processes for virus treatment relative to protozoa treatment is lower in comparison to free chlorine. As a result, a disinfection benchmark for *Giardia lamblia* would not necessarily provide an indication of the level or adequacy of treatment for viruses. Consequently, EPA believes it is appropriate for systems to develop profiles for both *Giardia lamblia* and viruses. Moreover, developing a profile for viruses involves a minimal increase in effort and no additional data collection for those systems that have disinfection profiles for *Giardia lamblia*. Systems will use the same calculated CT values for viruses as would be used for the *Giardia lamblia* profile.

The strategy of disinfection profiling and benchmarking stemmed from data provided to the Stage 1 M-DBP Advisory Committee, in which the baseline of microbial inactivation (expressed as logs of *Giardia lamblia* inactivation) demonstrated high variability.

Inactivation varied by several logs (*i.e.*, orders of magnitude) on a day-to-day basis at particular treatment plants and by as much as tens of logs over a year due to changes in water temperature, flow rate, seasonal changes, pH, and disinfectant demand. There were also differences between years at individual plants. To address these variations, M-DBP stakeholders developed the procedure of profiling a plant's inactivation levels over a period of at least one year, and then establishing a benchmark of minimum inactivation as a way to characterize disinfection practice.

Benchmarking of inactivation levels, an assessment of the impact of proposed changes on the level of microbial inactivation of *Giardia lamblia* and viruses, and State review prior to approval of substantial changes in treatment are important steps in avoiding conditions that present an increase in microbial risk. In its assessment of the microbial risk associated with the proposed changes, States could consider site-specific knowledge of the watershed and hydrologic factors as well as variability, flexibility and reliability of treatment to ensure that treatment for both protozoan and viral pathogens is appropriate.

EPA emphasizes that benchmarking is not intended to function as a regulatory standard. Rather, the objective of the disinfection benchmark is to facilitate interactions between the States and systems for the purpose of assessing the impact on microbial risk of proposed significant changes to current disinfection practices. Final decisions regarding levels of disinfection for *Giardia lamblia* and viruses beyond those required by the SWTR that are necessary to protect public health will continue to be left to the States. For this reason EPA has not mandated specific evaluation protocols or decision matrices for analyzing changes in disinfection practice. EPA, however, will provide support to the States in making these analyses through the issuance of guidance.

3. Request for Comments

EPA requests comment on the proposed provisions of the inactivation profiling and benchmarking requirement.

E. Additional Treatment Technique Requirements for Systems With Uncovered Finished Water Storage Facilities

1. What Is EPA Proposing Today?

EPA is proposing requirements for systems with uncovered finished water

storage facilities. The proposed rule requires that systems with uncovered finished water storage facilities must (1) cover the uncovered finished water storage facility, or (2) treat storage facility discharge to the distribution system to achieve a 4 log virus inactivation, unless (3) the system implements a State-approved risk mitigation plan that addresses physical access and site security, surface water runoff, animal and bird waste, and ongoing water quality assessment, and includes a schedule for plan implementation. Where applicable, the plans should account for cultural uses by Indian Tribes.

Systems must notify the State if they use uncovered finished water storage facilities no later than 2 years following LT2ESWTR promulgation. Systems must cover or treat uncovered finished facilities or have a State-approved risk mitigation plan within 3 years following LT2ESWTR promulgation, with the possibility of a two year extension granted by States for systems making capital improvements. Systems seeking approval for a risk mitigation plan must submit the plan to the State within 2 years following LT2ESWTR promulgation.

These provisions apply to uncovered tanks, reservoirs, or other facilities where water is stored after it has undergone treatment to satisfy microbial treatment technique requirements for *Giardia lamblia*, *Cryptosporidium*, and viruses. In most cases, this refers to storage of water following all filtration steps, where required, and primary disinfection.

2. How Was This Proposal Developed?

Today's proposal is intended to mitigate the water quality degradation and increased health risks that can result from uncovered finished water storage facilities. In addition, these proposed requirements for uncovered finished water storage facilities are consistent with recommendations of the Stage 2 M-DBP Advisory Committee in the Agreement in Principle (USEPA 2000a).

The use of uncovered finished water storage facilities has been questioned since 1930 due to their susceptibility to contamination and subsequent threats to public health (LeChevallier *et al.* 1997). Many potential sources of contamination can lead to the degradation of water quality in uncovered finished water storage facilities. These include surface water runoff, algal growth, insects and fish, bird and animal waste, airborne deposition, and human activity.

Algal blooms are the most common problem in open reservoirs and can become a public health risk, as they increase the presence of bacteria in the water. Algae growth also leads to the formation of disinfection byproducts and causes taste and odor problems. Some algae produce toxins that can induce headache, fever, diarrhea, abdominal pain, nausea, and vomiting. Bird and animal wastes are also common and significant sources of contamination. These wastes may carry microbial contaminants such as coliform bacteria, viruses, and human pathogens, including *Vibrio cholera*, *Salmonella*, *Mycobacteria*, *Typhoid*, *Giardia lamblia*, and *Cryptosporidium* (USEPA 1999e). Microbial pathogens are found in surface water runoff, along with agricultural chemicals, automotive wastes, turbidity, metals, and organic matter (USEPA 1999e, LeChevallier *et al.* 1997).

In an effort to minimize contamination, systems have implemented various controls such as reservoir covers and liners, regular draining and washing, security and monitoring, bird and insect control programs, and drainage design to prevent surface runoff from entering the facility (USEPA 1999e).

A number of studies have evaluated the degradation of water quality in uncovered finished water storage facilities. LeChevallier *et al.* (1997) compared influent and effluent samples from six uncovered finished water storage reservoirs in New Jersey for a one year period. There were significant increases in the turbidity, particle count, total coliform, fecal coliform, and heterotrophic plate count bacteria in the effluent relative to the influent. Of particular concern were fecal coliforms, which were detected in 18 percent of effluent samples (no influent samples were positive for coliforms). Fecal coliforms are used as an indicator of the potential for contamination by pathogens. *Giardia* and/or *Cryptosporidium* were detected in 15% of inlet samples and 25% of effluent samples, demonstrating a significant increase in the effluent. There was a significant decrease in the chlorine residual concentration in some effluent samples.

Increases in algal cells, heterotrophic plate count (HPC) bacteria, turbidity, color, particle counts, and biomass, and decreases in residual chlorine levels, have been reported in other studies of uncovered finished water reservoirs as well (Pluntze 1974, AWWA Committee 1983, Silverman *et al.* 1983). Researchers have shown that small mammals, birds, fish, and algal growth

contribute to the microbial degradation of an open finished water reservoir (Graczyk *et al.* 1996, Geldreich 1990, Fayer and Ungar 1986, Current 1986).

As described in section II, the IESWTR and LT1ESWTR require water systems to cover all new reservoirs, holding tanks, or other storage facilities for finished water. However, these rules do not require systems to cover existing finished water storage facilities. EPA stated in the preamble to the final IESWTR (63 FR 69494, December 16, 1998) (USEPA 1998a) that with respect to requirements for existing uncovered finished water storage facilities, the Agency needed more time to collect and analyze additional information to evaluate regulatory impact. The IESWTR preamble affirmed that EPA would consider whether to require the covering of existing storage facilities during the development of subsequent microbial regulations when additional data to estimate national costs were available.

Since promulgation of the IESWTR, EPA has collected sufficient data to estimate national cost implications of regulatory control strategies for uncovered finished water storage facilities. Based on information provided by States, EPA estimates that there are approximately 138 uncovered finished water storage facilities in the United States and territories, not including reservoirs that systems currently plan to cover or take off-line. Costs for covering these storage facilities or treating the effluent, consistent with today's proposed requirements, are presented in section VI of this preamble and in the Economic Analysis for the LT2ESWTR (USEPA 2003a). Briefly, total capital costs were estimated as \$64.4 million, resulting in annualized present value costs of \$5.4 million at a three percent discount rate and \$6.4 million at a seven percent discount rate.

Based on the findings of studies cited in this section, EPA continues to be concerned about contamination occurring in uncovered finished water storage facilities. Therefore, as recommended by the Advisory Committee, EPA is proposing control measures for all systems with uncovered finished water storage facilities. This proposal is intended to represent a balanced approach, recognizing both the potentially significant but uncertain risks associated with uncovered finished water storage facilities and the substantial costs of either covering them or building alternative storage. Today's proposal allows systems to treat the storage facility effluent instead of providing a cover. Alternatively, States may determine that existing risk

mitigation is adequate, provided a system implements a risk mitigation plan as described in this section.

3. Request for Comments

EPA requests comment on the proposed requirements pertaining to uncovered finished water storage facilities. Specifically, the Agency would like comment on the following issues, and requests that comments include available supporting data or other technical information:

- Is it appropriate to allow systems with uncovered finished water storage facilities to implement a risk management plan or treat the effluent to inactivate viruses instead of covering the facility?

- If systems treat the effluent of an uncovered finished water storage facility instead of covering it, should systems be required to inactivate *Cryptosporidium* and *Giardia lamblia*, since these protozoa have been found to increase in uncovered storage facilities?

- Additional information on contamination or health risks that may be associated with uncovered finished water storage facilities.

- Additional data on how climatological conditions affect water quality, including daily fluctuations in the stability of the water related to corrosion control.

- The definition of an uncovered finished water storage facility in 40 CFR 141.2 is a tank, reservoir, or other facility used to store water that will undergo no further treatment except residual disinfection and is open to the atmosphere. There is a concern that this definition may not include certain systems using what would generally be considered an uncovered finished water storage facility. An example is a system that applies a corrosion inhibitor compound to the effluent of an uncovered storage facility where water is stored after filtration and primary disinfection. In this case, the system may claim that the corrosion inhibitor constitutes additional treatment and, consequently, the reservoir does not meet EPA's definition of an uncovered finished water storage facility. EPA requests comment on whether the definition of an uncovered finished water storage facility should be revised to specifically include systems that apply a treatment such as corrosion control to water stored in an uncovered reservoir after the water has undergone filtration, where required, and primary disinfection.

F. Compliance Schedules

Today's proposal includes deadlines for public water systems to comply with

the proposed monitoring, reporting, and treatment requirements. These deadlines stem from the microbial framework approach of the proposed LT2ESWTR, which involves a system-specific risk characterization through monitoring to determine the need for additional treatment.

1. What Is EPA Proposing Today?

a. Source water monitoring.

i. Filtered systems. Under today's proposal, filtered systems conduct source water *Cryptosporidium* monitoring for the purpose of being classified in one of four risk bins that determine the extent of any additional treatment requirements. Small filtered systems first monitor for *E. coli* as a screening analysis and are only required to monitor for *Cryptosporidium* if the mean *E. coli* level exceeds specified trigger values. Note that systems that currently provide or will provide a total of at least 5.5 log of treatment for *Cryptosporidium* are exempt from monitoring requirements.

Large surface water systems (serving at least 10,000 people) that filter must

sample at least monthly for *Cryptosporidium*, *E. coli*, and turbidity in their source water for 24 months, beginning 6 months after promulgation of the LT2ESWTR. Large systems must submit a sampling schedule to their primacy agency (in this case, EPA) no later than 3 months after promulgation of the LT2ESWTR.

Small surface water systems (fewer than 10,000 people served) that filter must conduct biweekly *E. coli* sampling in their source water for 1 year, beginning 30 months after LT2ESWTR promulgation. States may designate an alternate indicator monitoring strategy based on EPA guidance, but compliance schedules will not change. Small systems that exceed the indicator trigger value (i.e., mean *E. coli* > 10/100 mL for lake/reservoir sources or > 50/100 mL for flowing stream sources) must conduct source water *Cryptosporidium* sampling twice-per-month for 1 year, beginning 48 months after LT2ESWTR promulgation (i.e., beginning 6 months following the completion of *E. coli* sampling). Small systems must submit

an *E. coli* sampling schedule to their primacy agency no later than 27 months after LT2ESWTR promulgation. If *Cryptosporidium* monitoring is required, small systems must submit a *Cryptosporidium* sampling schedule no later than 45 months after LT2ESWTR promulgation.

Large systems must carry out a second round of source water monitoring beginning 108 months after LT2ESWTR promulgation, which is 6 years after initial bin classification. Similarly, small systems must conduct a second round of indicator monitoring (*E. coli* or other as designated by the State) beginning 138 months after LT2ESWTR promulgation, which is 6 years after their initial bin classification. Small systems that exceed the indicator trigger value in the second round of indicator monitoring must conduct a second round of *Cryptosporidium* monitoring, beginning 156 months after LT2ESWTR promulgation.

Compliance dates for filtered systems are summarized in Table IV-23.

TABLE IV-23.—SUMMARY OF COMPLIANCE DATES FOR FILTERED SYSTEMS

System type	Requirement	Compliance date
Large Systems (serve ≥10,000 people).	Submit sampling schedule ^{1,2}	No later than 3 months after promulgation.
	Source water <i>Cryptosporidium</i> , <i>E. coli</i> and turbidity monitoring. Comply with additional <i>Cryptosporidium</i> treatment requirements. Second round of source water <i>Cryptosporidium</i> , <i>E. coli</i> , and turbidity monitoring ² .	Begin monthly monitoring 6 months after promulgation for 24 months. No later than 72 months after promulgation. ³ Begin monthly monitoring 108 months after promulgation for 24 months.
Small Systems (serve <10,000 people).	Submit <i>E. coli</i> sampling schedule ²	No later than 27 months after promulgation.
	Source water <i>E. coli</i> monitoring	Begin biweekly monitoring 30 months after promulgation for 1 year.
	Second round of source water <i>E. coli</i> monitoring ² ...	Begin biweekly monitoring 138 months after promulgation for 1 year.
	Additional requirements if indicator (e.g., <i>E. coli</i>) trigger level is exceeded ⁴	
Submit <i>Cryptosporidium</i> sampling schedule ^{1,2}	No later than 45 months after promulgation.	
Source water <i>Cryptosporidium</i> monitoring	Begin twice-per-month monitoring no later than 48 months after promulgation for 1 year. No later than 102 months after promulgation. ^{3,5}	
Comply with additional <i>Cryptosporidium</i> treatment requirements. Second round of source water <i>Cryptosporidium</i> monitoring.	Begin twice-per-month monitoring no later than 156 months after promulgation for 1 year.	

¹ Systems may be eligible to use previously collected (grandfathered) data to meet LT2ESWTR requirements if specified quality control criteria are met (described in section IV.A.1.d).

² Systems are not required to monitor if they will provide at least 5.5 log *Cryptosporidium* treatment and notify EPA or the State.

³ States may grant up to an additional two years for systems making capital improvements.

⁴ If the *E. coli* annual mean concentration exceeds 10/100 mL for systems using lakes/reservoir sources or exceeds 50/100 mL for systems using flowing stream sources, *Cryptosporidium* monitoring is required.

⁵ Systems that do not exceed the *E. coli* trigger level are classified in Bin 1 and are not required to provide *Cryptosporidium* treatment beyond LT1ESWTR levels.

ii. *Unfiltered systems*. Surface water systems that do not filter and meet the criteria for avoidance of filtration (40 CFR 141.71) (i.e., unfiltered systems) are

required to conduct source water *Cryptosporidium* monitoring to determine if their mean source water *Cryptosporidium* level exceeds 0.01

oocysts/L. There is no *E. coli* screening analysis available to small unfiltered systems. However, both large and small unfiltered systems conduct

Cryptosporidium monitoring on the same schedule as filtered systems of the same size. Note that unfiltered systems that currently provide or will provide a total of at least 3 log *Cryptosporidium* inactivation are exempt from monitoring requirements.

Large unfiltered systems (serving at least 10,000 people) must conduct at least monthly *Cryptosporidium* sampling for 24 months, beginning 6 months after LT2ESWTR promulgation. Small unfiltered systems (serving fewer

than 10,000 people) must conduct at least twice-per-month *Cryptosporidium* sampling for 12 months, beginning 48 months after LT2ESWTR promulgation. Large systems must submit a *Cryptosporidium* sampling schedule to EPA no later than 3 months after LT2ESWTR promulgation, and small systems must submit a sampling schedule to their State no later than 45 months after LT2ESWTR promulgation.

Unfiltered systems are required to conduct a second round of

Cryptosporidium monitoring on the same schedule as filtered systems of the same size. Large systems must carry out a second round of *Cryptosporidium* monitoring, beginning 108 months after LT2ESWTR promulgation. Small systems must perform a second round of *Cryptosporidium* monitoring, beginning 156 months after LT2ESWTR promulgation.

Compliance dates for unfiltered systems are summarized in Table IV–24.

TABLE IV–24.—SUMMARY OF COMPLIANCE DATES FOR UNFILTERED SYSTEMS

System type	Requirement	Compliance date
Large Systems (serve ≥10,000 people).	Submit sampling schedule ¹	No later than 3 months after promulgation.
	Source water <i>Cryptosporidium</i> monitoring	Begin monthly monitoring [6 months after promulgation for 24 months. No later than 72 months after promulgation. ²
	Comply with <i>Cryptosporidium</i> inactivation requirements. Second round of source water <i>Cryptosporidium</i> monitoring.	Begin monthly monitoring 108 months after promulgation for 24 months.
Small Systems (serve < 10,000 people).	Submit sampling schedule ¹	No later than 45 months after promulgation.
	Source water <i>Cryptosporidium</i> monitoring	Begin twice-per-month monitoring no later than 48 months after promulgation for 1 year. No later than 102 months after promulgation. ²
	Comply with <i>Cryptosporidium</i> inactivation requirements. Second round of source water <i>Cryptosporidium</i> monitoring.	Begin twice-per-month monitoring no later than 156 months after promulgation for 1 year.

¹ Systems may be eligible to use previously collected (grandfathered) data to meet LT2ESWTR requirements if specified quality control criteria are met (described in section IV.A.1.d).

² States may grant up to an additional two years for systems making capital improvements.

b. *Treatment requirements.* Filtered systems must determine their bin classification and unfiltered systems must determine their mean source water *Cryptosporidium* level within 6 months of the scheduled month for collection of their final *Cryptosporidium* sample in the first round of monitoring. This 6 month period provides time for systems to receive all sample analysis results from the laboratory, analyze the data, and work with their primacy agency.

Filtered systems have 3 years following initial bin classification to meet any additional *Cryptosporidium* treatment requirements. This equates to compliance dates of 72 months after LT2ESWTR promulgation for large systems and 102 months after LT2ESWTR promulgation for small systems (see Table IV–23). Unfiltered systems must comply with *Cryptosporidium* treatment requirements on the same schedule as filtered systems of the same size (see Table IV–24). The State may grant systems an additional two years to comply when capital investments are necessary, as specified in the Safe Drinking Water Act (section 1412(b)(10)).

Systems with uncovered finished water storage facilities are required to comply with the provisions described in section IV.E by 36 months following LT2ESWTR promulgation, with the possibility of a 2 year extension granted by the State for systems making capital improvements. Systems seeking approval for a risk mitigation plan must submit the plan to the State within 24 months following LT2ESWTR promulgation.

Systems must comply with additional *Cryptosporidium* treatment requirements by implementing one or more treatment processes or control strategies from the microbial toolbox. Most of the toolbox components require submission of documentation to the State demonstrating compliance with design and/or implementation criteria required to receive credit. Compliance dates for reporting requirements associated with microbial toolbox components are presented in detail in section IV.J, Reporting and Recordkeeping Requirements.

c. *Disinfection benchmarks for Giardia lamblia and viruses.* Today’s proposed LT2ESWTR includes disinfection profiling and benchmarking requirements, which consist of three

major components: applicability determination, characterization of disinfection practice, and State review of proposed changes in disinfection practice. Each of these components is discussed in detail in section IV.D. Compliance deadlines associated with each of these components, including associated reporting requirements, are stated in section IV.J, Reporting and Recordkeeping Requirements.

2. How Was This Proposal Developed?

The compliance dates in today’s proposal reflects the risk-targeted approach of the proposed LT2ESWTR, wherein additional treatment requirements are based on a system specific risk characterization as determined through source water monitoring. Additionally, they are designed to allow for systems to simultaneously comply with the LT2ESWTR and Stage 2 DBPR in order to balance risks in the control of microbial pathogens and DBPs. These dates are consistent with recommendations from the Stage 2 M–DBP Federal Advisory Committee.

Under the LT2ESWTR, large systems will sample for *Cryptosporidium* for a period of two years in order to

characterize source water pathogen levels and capture a degree of annual variability. To expedite the date by which systems will provide additional treatment where high risk source waters are identified, large system *Cryptosporidium* monitoring will begin six months after promulgation of the LT2ESWTR. Upon completion of *Cryptosporidium* monitoring, systems will have six months to work with their primacy agency to determine their bin classification. Beginning at this point, which is three years following LT2ESWTR promulgation, large systems will have three years to implement the treatment processes or control strategies necessary to comply with any additional treatment requirements stemming from bin classification.

Other large system compliance dates in areas like approval of grandfathered monitoring data, disinfection profiling and benchmarking, and reporting deadlines associated with microbial toolbox components all stem from the *Cryptosporidium* monitoring and treatment compliance schedule.

With respect to small systems under the LT2ESWTR, EPA is proposing that small systems first monitor for *E. coli* as a screening analysis in order to reduce the number of small systems that incur the cost of *Cryptosporidium* monitoring. However, due to limitations in available data, the Agency has determined that it is necessary to use data generated by large systems under the LT2ESWTR to confirm or refine the *E. coli* indicator criteria that will trigger small system *Cryptosporidium* monitoring. Consequently, small system indicator monitoring will begin at the conclusion of large system monitoring. This approach was recommended by the Advisory Committee.

Accordingly, small systems will monitor for *E. coli* for one year, beginning 30 months after LT2ESWTR promulgation. Following this, small systems will have six months to determine if they are required to monitor for *Cryptosporidium* and, if so, contract with an approved analytical laboratory. *Cryptosporidium* monitoring by small systems will be conducted for one year, which, when added to the one year of *E. coli* monitoring, equals two years of source water monitoring. This is equivalent to the time period large systems spend in source water monitoring.

The time periods associated with bin assignment and compliance with additional treatment requirements for small systems are the same as those proposed for large systems. Specifically, small systems will have six months to work with their States to determine

their bin classification following the conclusion of *Cryptosporidium* sampling. From this point, which is 5.5 years after LT2ESWTR promulgation, small systems have three years to meet any additional treatment requirements resulting from bin classification. States can grant additional time to small systems for compliance with treatment technique requirements through granting exemptions (see SDWA section 1416).

3. Request for Comments

EPA requests comments on the treatment technique compliance schedules for large and small systems in today's proposal, including the following issues:

Time Window Between Large and Small System Monitoring

Under the current proposal, small filtered system *E. coli* monitoring begins in the month following the end of large system *Cryptosporidium*, *E. coli*, and turbidity monitoring. EPA plans to evaluate large system monitoring results on an ongoing basis as the data are reported to determine if any refinements to the *E. coli* levels that trigger small system *Cryptosporidium* monitoring are necessary. If such refinements were deemed appropriate, EPA would issue guidance to States, which can establish alternative trigger values for small system monitoring under the LT2ESWTR.

This implementation schedule does not leave any time between the end of large system monitoring and the initiation of small system monitoring. Consequently, if it is necessary to provide guidance on alternative trigger values prior to when small system monitoring begins, such guidance would be based on less than the full set of large system results (e.g., first 18 months of large system data). EPA requests comment on whether an additional time window between the end of large system monitoring and the beginning of small system monitoring is appropriate and, if so, how long such a window should be.

Implementation Schedule for Consecutive Systems

The Stage 2 M-DBP Agreement in Principle (65 FR 83015, December 29, 2000) (USEPA 2000a) continues the principle of simultaneous compliance to address microbial pathogens and disinfection byproducts. Systems are generally expected to address LT2ESTWR requirements concurrently with those of the Stage 2 DBPR (as noted earlier, the Stage 2 DBPR is scheduled to be proposed later this year and to be

promulgated at the same time as the LT2ESWTR).

As with the LT2ESWTR, small water systems (< 10,000 served) generally begin monitoring and must be in compliance with the Stage 2 DBPR at a date later than that for large systems. However, the Advisory Committee recommended that small systems that buy/receive from or sell/deliver finished water to a large system (that is, they are part of the same "combined distribution system") comply with Stage 2 DBPR requirements on the same schedule as the largest system in the combined distribution system. This approach is intended to ensure that systems consider impacts throughout the combined distribution system when making compliance decisions (e.g. selecting new technologies or making operational modifications) and to facilitate all systems meeting the compliance deadlines for the rule.

The issue of combined distribution systems associated with systems buying and selling water is expected to be of less significance for the LT2ESWTR. The requirements of the LT2ESWTR apply to systems treating raw surface water and generally will not involve compliance steps when systems purchase treated water. Consequently, the compliance schedule for today's proposal does not address combined distribution systems. However, this proposed approach raises the possibility that a small system treating surface water and selling it to a large system could be required to take compliance steps at an earlier date under the Stage 2 DBPR than under the LT2ESWTR. While a small system in this situation could choose to comply with the LT2ESWTR on an earlier schedule, the two rules would not require simultaneous compliance. EPA requests comment on how this scenario should be addressed in the LT2ESWTR.

G. Public Notice Requirements

1. What Is EPA Proposing Today?

EPA is proposing that under the LT2ESWTR, a Tier 2 public notice will be required for violations of additional treatment requirements and a Tier 3 public notice will be required for violations of monitoring and testing requirements. Where systems violate LT2ESWTR treatment requirements, today's proposal requires the use of the existing health effects language for microbiological contaminant treatment technique violations, as stated in 40 CFR 141 Subpart Q, Appendix B.

2. How Was This Proposal Developed?

In 2000, EPA published the Public Notification Rule (65 FR 25982, May 4, 2000) (USEPA 2000d), which revised the general public notification regulations for public water systems in order to implement the public notification requirements of the 1996 SDWA amendments. This regulation established the requirements that public water systems must follow regarding the form, manner, frequency, and content of a public notice. Public notification of violations is an integral part of the public health protection and consumer right-to-know provisions of the 1996 SDWA Amendments.

Owners and operators of public water systems are required to notify persons served when they fail to comply with the requirements of a NPDWR, have a variance or exemption from the drinking water regulations, or are facing other situations posing a risk to public health. The public notification requirements divide violations into three categories (Tier 1, Tier 2 and Tier 3) based on the seriousness of the violations, with each tier having different public notification requirements.

EPA has limited its list of violations and situations routinely requiring a Tier 1 notice to those with a significant potential for serious adverse health effects from short term exposure. Tier 1 violations contain language specified by EPA that concisely and in non-technical terms conveys to the public the adverse health effects that may occur as a result of the violation. States and water utilities may add additional information to each notice, as deemed appropriate for specific situations. A State may elevate to Tier 1 other violations and situations with significant potential to have serious adverse health effects from short-term exposure, as determined by the State.

Tier 2 public notices address other violations with potential to have serious adverse health effects on human health. Tier 2 notices are required for the following situations:

- All violations of the MCL, maximum residual disinfectant level (MRDL) and treatment technique requirements, except where a Tier 1 notice is required or where the State determines that a Tier 1 notice is required; and
- Failure to comply with the terms and conditions of any existing variance or exemption.

Tier 3 public notices include all other violations and situations requiring public notice, including the following situations:

- A monitoring or testing procedure violation, except where a Tier 1 or 2

notice is already required or where the State has elevated the notice to Tier 1 or 2; and

- Operation under a variance or exemption.

The State, at its discretion, may elevate the notice requirement for specific monitoring or testing procedures from a Tier 3 to a Tier 2 notice, taking into account the potential health impacts and persistence of the violation.

As part of the IESWTR, EPA established health effects language for violations of treatment technique requirements for microbiological contaminants. EPA believes this language, which was developed with consideration of *Cryptosporidium* health effects, is appropriate for violations of additional *Cryptosporidium* treatment requirements under the LT2ESWTR.

3. Request for Comment

EPA requests comment on whether the violations of additional treatment requirements for *Cryptosporidium* under the LT2ESWTR should require a Tier 2 public notice and whether the proposed health effects language is appropriate.

H. Variances and Exemptions

SDWA section 1415 allows States to grant variances from national primary drinking water regulations under certain conditions; section 1416 establishes the conditions under which States may grant exemptions to MCL or treatment technique requirements. For the reasons presented in the following discussion, EPA has determined that systems will not be eligible for variances or exemptions to the requirements of the LT2ESWTR.

1. Variances

Section 1415 specifies two provisions under which general variances to treatment technique requirements may be granted:

(1) A State that has primacy may grant a variance to a system from any requirement to use a specified treatment technique for a contaminant if the system demonstrates to the satisfaction of the State that the treatment technique is not necessary to protect public health because of the nature of the system's raw water source. EPA may prescribe monitoring and other requirements as conditions of the variance (section 1415(a)(1)(B)).

(2) EPA may grant a variance from any treatment technique requirement upon a showing by any person that an alternative treatment technique not included in such requirement is at least

as efficient in lowering the level of the contaminant (section 1415(a)(3)).

EPA does not believe the first provision for granting a variance is applicable to the LT2ESWTR because *Cryptosporidium* treatment technique requirements under this rule account for the degree of source water contamination. Systems initially comply with the LT2ESWTR by conducting source water monitoring for *Cryptosporidium*. Filtered systems are required to provide additional treatment for *Cryptosporidium* only if the source water concentration exceeds a level where current treatment does not provide sufficient protection. All unfiltered systems are required to provide a baseline of 2 log inactivation of *Cryptosporidium* to achieve finished water risk levels comparable to filtered systems; however, unfiltered systems are required to achieve 3 log inactivation only if the source water level exceeds 0.01 oocysts/L.

The second provision for granting a variance is not applicable to the LT2ESWTR because the treatment technique requirements of this rule specify the degree to which systems must lower their source water *Cryptosporidium* level (e.g., 4, 5, and 5.5 log reduction in Bins 2, 3, and 4, respectively). The LT2ESWTR provides broad flexibility in how systems achieve the required level of *Cryptosporidium* reduction, as shown in the discussion of the microbial toolbox in section VI.C. Moreover, the microbial toolbox contains an option for Demonstration of Performance, under which States can award treatment credit based on the demonstrated efficiency of a treatment process in reducing *Cryptosporidium* levels. Thus, there is no need for this type of variance under the LT2ESWTR.

SDWA section 1415(e) describes small system variances, but these cannot be granted for a treatment technique for a microbial contaminant. Hence, small system variances are not allowed for the LT2ESWTR.

2. Exemptions

Under SDWA section 1416(a), a State may exempt any public water system from a treatment technique requirement upon a finding that (1) due to compelling factors (which may include economic factors such as qualification of the system as serving a disadvantaged community), the system is unable to comply with the requirement or implement measures to develop an alternative source of water supply; (2) the system was in operation on the effective date of the treatment technique requirement, or for a system that was not in operation by that date, no

reasonable alternative source of drinking water is available to the new system; (3) the exemption will not result in an unreasonable risk to health; and (4) management or restructuring changes (or both) cannot reasonably result in compliance with the Act or improve the quality of drinking water.

If EPA or the State grants an exemption to a public water system, it must at the same time prescribe a schedule for compliance (including increments of progress or measures to develop an alternative source of water supply) and implementation of appropriate control measures that the State requires the system to meet while the exemption is in effect. Under section 1416(b)(2)(A), the schedule shall require compliance as expeditiously as practicable (to be determined by the State), but no later than three years after the otherwise applicable compliance date for the regulations established pursuant to section 1412(b)(10). For public water systems that do not serve more than a population of 3,300 and that need financial assistance for the necessary improvements, EPA or the State may renew an exemption for one or more additional two-year periods, but not to exceed a total of six years.

A public water system shall not be granted an exemption unless it can establish that: (1) The system cannot meet the standard without capital improvements that cannot be completed prior to the date established pursuant to section 1412(b)(10); or (2) in the case of a system that needs financial assistance for the necessary implementation, the system has entered into an agreement to obtain financial assistance pursuant to section 1452 or any other Federal or state program; or (3) the system has entered into an enforceable agreement to become part of a regional public water system.

EPA believes that granting an exemption to the *Cryptosporidium* treatment requirements of the LT2ESWTR would result in an unreasonable risk to health. As described in section II.C, *Cryptosporidium* causes acute health effects, which may be severe in sensitive subpopulations and include risk of mortality. Moreover, the additional *Cryptosporidium* treatment requirements of the LT2ESWTR are targeted to systems with the highest degree of risk. Due to these factors, EPA is not proposing to allow exemptions under the LT2ESWTR.

3. Request for Comment

a. *Variations*. EPA requests comment on the determination that the provisions for granting variations are not applicable

to the proposed LT2ESWTR, specifically including *Cryptosporidium* inactivation requirements for unfiltered systems.

In theory it would be possible for an unfiltered system to demonstrate raw water *Cryptosporidium* levels that were 3 log lower than the cutoff for bin 1 for filtered systems and, thus, that it may be providing comparable public health protection without additional inactivation. However, EPA has determined that in practice it is not currently economically or technologically feasible for systems to ascertain the level of *Cryptosporidium* at this concentration. This is due to the extremely large number and volume of samples that would be necessary to make this demonstration with sufficient confidence. Based on this determination and the *Cryptosporidium* occurrence data described in section III.C, EPA is not proposing to allow unfiltered systems to demonstrate raw water *Cryptosporidium* levels low enough to avoid inactivation requirements. EPA requests comment on this approach.

b. *Exemptions*. EPA requests comment on the determination that granting an exemption to the *Cryptosporidium* treatment requirements of the LT2ESWTR would result in an unreasonable risk to health.

I. Requirements for Systems To Use Qualified Operators

The SWTR established a requirement that each public water system using a surface water source or a ground water source under the direct influence of surface water must be operated by qualified personnel who meet the requirements specified by the State (40 CFR 141.70). The Stage 1 DBPR extended this requirement to include all systems affected by that rule, and required that States maintain a register of qualified operators (40 CFR 141.130(c)). While the proposed LT2ESWTR establishes no new requirements regarding the operation of systems by qualified personnel, the Agency would like to emphasize the important role that qualified operators play in delivering safe drinking water to the public. EPA encourages States that do not already have operator certification programs in effect to develop such programs. States should also review and modify, as required, their qualification standards to take into account new technologies (e.g., ultraviolet disinfection) and new compliance requirements.

J. System Reporting and Recordkeeping Requirements

1. Overview

Today's proposal includes reporting and recordkeeping requirements associated with proposed monitoring and treatment requirements. As described earlier, systems must conduct source water monitoring to determine a treatment bin classification for filtered systems or a mean *Cryptosporidium* level for unfiltered systems. Systems with previously collected monitoring data may be able to use (i.e., grandfather) those data in lieu of conducting new monitoring. Following source water monitoring, systems will be required to comply with any additional *Cryptosporidium* treatment requirements by implementing treatment and control strategies from a microbial toolbox of options. Systems must conduct a second round of source water monitoring six years after bin classification.

In addition, systems using uncovered finished water storage facilities must cover the facility or provide treatment unless the system implements a State-approved risk management strategy. Certain systems will be required to conduct disinfection profiling and benchmarking.

The proposed rule requires public water systems to submit schedules for *Cryptosporidium*, *E. coli*, and turbidity sampling at least 3 months before monitoring must begin. Source water sample analysis results must be reported not later than ten days after the end of first month following the month when the sample is collected. As described later, large systems (at least 10,000 people served) will report monitoring results from the initial round of monitoring directly to EPA through an electronic data system. Small systems will report monitoring results to the State. Both small and large systems will report monitoring results from the second round of monitoring to the State.

Systems must report a bin classification (filtered systems) or mean *Cryptosporidium* level (unfiltered systems) within six months following the month when the last sample in a particular round of monitoring is scheduled to be collected. If systems are required to provide additional treatment for *Cryptosporidium*, they must report regarding the use of microbial toolbox components. Systems must notify the State within 24 months following promulgation of the rule if they use uncovered finished water storage facilities. Systems must also make reports related to disinfection profiling and benchmarking. Reporting

requirements associated with these activities are summarized in Tables IV–25 to IV–28.

TABLE IV–25.— SUMMARY OF INITIAL LARGE FILTERED SYSTEM REPORTING REQUIREMENTS

You must report the following items	On the following schedule
Sampling schedule for <i>Cryptosporidium</i> , <i>E. coli</i> , and turbidity monitoring.	No later than 3 months after promulgation.
Results of <i>Cryptosporidium</i> , <i>E. coli</i> , and turbidity analyses	No later than 10 days after the end of the first month following the month in which the sample is collected.
Bin determination	No later than 36 months after promulgation.
Demonstration of compliance with additional treatment requirements.	Beginning 72 months after promulgation ¹ (See table IV–34).
Disinfection profiling component reports	See Table IV–35.

¹ States may grant an additional two years for systems making capital improvements.

TABLE IV–26.—SUMMARY OF INITIAL SMALL FILTERED SYSTEM REPORTING REQUIREMENTS

You must report the following items	On the following schedule
Sampling schedule for <i>E. coli</i> monitoring	No later than 27 months after promulgation.
Results of <i>E. coli</i> analyses (unless State approves a different indicator).	No later than 10 days after the end of the first month following the month in which the sample was collected.
Mean <i>E. coli</i> concentration (unless State approves a different indicator).	No later than 45 months after promulgation.
Disinfection profiling component reports	See Table IV–36.

Additional requirements if *E. coli* trigger level is exceeded¹

Sampling schedule for <i>Cryptosporidium</i> monitoring	No later than 45 months after promulgation.
Results of <i>Cryptosporidium</i> analyses	No later than 10 days after the end of the first month following the month in which the sample is collected.
Bin determination	No later than 66 months after promulgation.
Demonstration of compliance with additional treatment requirements.	Beginning 102 months after promulgation ² (See Table IV–34).

¹ If the *E. coli* annual mean concentration exceeds 10/100 mL for systems using lakes/reservoirs or exceeds 50/100 mL for systems using flowing streams, then systems must conduct *Cryptosporidium* monitoring. States may approve alternative indicator criteria to trigger *Cryptosporidium* monitoring.

² States may grant an additional two years for systems making capital improvements.

TABLE IV–27.—SUMMARY OF INITIAL LARGE UNFILTERED SYSTEM REPORTING REQUIREMENTS

You must report the following items	On the following schedule
<i>Cryptosporidium</i> sampling schedule	No later than 3 months after promulgation.
Results of <i>Cryptosporidium</i> analyses	No later than 10 days after the end of the first month following the month in which the sample was collected.
Determination of mean <i>Cryptosporidium</i> concentration	No later than 36 months after promulgation.
Disinfection profiling component reports	See Table IV–35.
Demonstration of compliance with <i>Cryptosporidium</i> inactivation requirements.	Beginning 72 months after promulgation ¹ (see Table IV–34).

¹ States may grant an additional two years for systems making capital improvements.

TABLE IV–28.—SUMMARY OF INITIAL SMALL UNFILTERED SYSTEM REPORTING REQUIREMENTS

You must report the following items	On the following schedule
<i>Cryptosporidium</i> sampling schedule	No later than 45 months after promulgation.
Results of <i>Cryptosporidium</i> analyses	No later than 10 days after the end of the first month following the month in which the sample was collected.
Determination of mean <i>Cryptosporidium</i> concentration	No later than 66 months after promulgation.
Disinfection profiling component reports	See Table IV–35.
Demonstration of compliance with <i>Cryptosporidium</i> inactivation requirements.	Beginning 102 months after promulgation ¹ (see Table IV–34).

¹ States may grant an additional two years for systems making capital improvements.

2. Reporting Requirements for Source Water Monitoring

a. *Data elements to be reported.* Proposed reporting requirements for LT2ESWTR monitoring stem from proposed analytical method requirements. As stated in sections IV.K and IV.L, systems must have *Cryptosporidium* analyses conducted by EPA-approved laboratories using Methods 1622 or 1623. *E. coli* analyses must be performed by State-approved laboratories using the *E. coli* methods proposed for approval in section IV.K. Systems are required to report the data

elements specified in Table IV–29 for each *Cryptosporidium* analysis. To comply with LT2ESWTR requirements, only the sample volume filtered and the number of oocysts counted must be reported for samples in which at least 10 L is filtered and all of the sample volume is analyzed. Additional information is required for samples where the laboratory analyzes less than 10 L or less than the full sample volume collected. Table IV–30 presents the data elements that systems must report for *E. coli* analyses.

As described in the following section, EPA is developing a data system to

manage and analyze the microbial monitoring data that will be reported by large systems under the LT2ESWTR. EPA is exploring approaches for application of this data system to support small system data reporting as well. Systems, or laboratories acting as the systems' agents, must keep Method 1622/1623 bench sheets and slide examination report forms until 36 months after an equivalent round of source water monitoring has been completed (e.g., second round of *Cryptosporidium* monitoring).

TABLE IV–29.—PROPOSED *Cryptosporidium* DATA ELEMENTS TO BE REPORTED

Data element	Reason for data element
Identifying information	
• PWSID	Needed to associate plant with public water system.
• Facility ID	Needed to associate sample result with facility.
• Sample collection point	Needed to associate sample result with sampling point.
• Sample collection date	Needed to determine that utilities are collecting samples at the frequency required.
• Sample type (field or matrix spike) ¹	Needed to distinguish field samples from matrix samples for recovery calculations.
Sample results	
• Sample volume filtered (L), to nearest ¼ L ²	Needed to verify compliance with sample volume requirements.
• Was 100% of filtered volume examined? ³	Needed to calculate the final concentration of oocysts/L and determine if volume analyzed requirements are met.
• Number of oocysts counted	Needed to calculate the final concentration of oocysts/L.

¹ For matrix spike samples, sample volume spiked and estimated number of oocysts spiked must be reported. These data are not required for field samples.

² For samples in which <10 L is filtered or <100% of the sample volume is examined, the number of filters used and the packed pellet volume must also be reported to verify compliance with LT2ESWTR sample volume analysis requirements. These data are not required for most samples.

³ For samples in which <100% of sample is examined, the volume of resuspended concentrate and volume of this resuspension processed through IMS must be reported to calculate the sample volume examined. These data will not be required for most samples.

TABLE IV–30.—PROPOSED *E. coli* DATA ELEMENTS TO BE REPORTED

Data element	Reason for collecting data element
Identifying Information	
PWS ID	Needed to associate analytical result with public water system.
Facility ID	Needed to associate plant with public water system.
Sample collection point	Needed to associate sample result with sampling point.
Sample collection date	Needed to determine that utilities are collecting samples at the frequency required.
Analytical method number	Needed to associate analytical result with analytical method.
Method Type	Needed to verify that an approved method was used and call up correct web entry form.
Source water type	Needed to assess <i>Cryptosporidium</i> indicator relationships.
<i>E. coli</i> /100 mL	Sample result (although not required, the laboratory also will have the option of entering primary measurements for a sample into the LT2ESWTR internet-based database to have the database automatically calculate the sample result).
Turbidity Information	
Turbidity result	Needed to assess <i>Cryptosporidium</i> indicator relationships.

b. Data system. Because source water monitoring by large systems (serving at least 10,000 people) will begin 6 months following promulgation of the LT2ESWTR, EPA expects to act as the primacy agency with oversight responsibility for large system sampling,

analysis, and data reporting. To facilitate collection and analysis of large system monitoring data, EPA is developing an Internet-based electronic data collection and management system. This approach is similar to that used under the Unregulated Contaminants

Monitoring Rule (UCMR) (64 FR 50556, September 17, 1999) (USEPA 1999c).

Analytical results for *Cryptosporidium*, *E. coli*, and turbidity analyses will be reported directly to this database using web forms and software that can be downloaded free of charge.

The data system will perform logic checks on data entered and calculate final results from primary data (where necessary). This is intended to reduce reporting errors and limit the time involved in investigating, checking, and correcting errors at all levels. EPA will make large system monitoring data available to States when States assume primacy for the LT2ESWTR or earlier under State agreements with EPA.

Large systems should instruct their laboratories to electronically enter monitoring results into the EPA data system using web-based manual entry forms or by uploading XML files from laboratory information management systems (LIMS). After data are submitted by a laboratory, systems may review the results on-line. If a system believes that a result was entered into the data system erroneously, the system may notify the laboratory to rectify the entry. In addition, if a system believes that a result is incorrect, the system may submit the result as a contested result

and petition EPA or the State to invalidate the sample. If a system contests a sample result, the system must submit a rationale to the primacy agency, including a supporting statement from the laboratory, providing a justification. Systems may arrange with laboratories to review their sample results prior to the results being entered into the EPA data system. Also, if a system determines that its laboratory does not have the capability to report data electronically, the system can submit a request to EPA to use an alternate reporting format.

Regardless of the reporting process used, systems are required to report an analytical monitoring result to the primacy agency no later than 10 days after the end of the first month following the month when the sample was collected. As described in section IV.A.1, if a system is unable to report a valid *Cryptosporidium* analytical result for a scheduled sampling date due to failure to comply with the analytical

method requirements (e.g., violation of quality control requirements), the system must collect a replacement sample within 14 days of being notified by the laboratory or the State that a result cannot be reported for that date and must submit an explanation for the replacement sample with the analytical results. A system will not incur a monitoring violation if the State determines that the failure to report a valid analysis result was due to circumstances beyond the control of the system. However, in all cases the system must collect a replacement sample.

The data elements to be collected by the electronic data system will enhance the reliability of the microbial data generated under the LT2ESWTR, while reducing the burden on the analytical laboratories and public water systems. Tables IV-31 and IV-32 summarize the system's data analysis functions for *Cryptosporidium* measurements.

TABLE IV-31.— LT2ESWTR DATA SYSTEM FUNCTIONS FOR *Cryptosporidium* DATA

Value calculated	Formula	Applicability to sample types	
		Field	Matrix spike
Calculation of sample volume analyzed.	(Volume filtered) * (resuspended concentrate volume transferred to IMS/resuspended concentrate volume).	Yes	Yes.
Pellet volume analyzed	(pellet volume)*(resuspended concentrated volume transferred to IMS/resuspended concentrate volume).	Yes	Yes.
Calculation of oocysts/L	(Number of oocysts counted)/(sample volume analyzed)	Yes	Yes.
Calculation of estimated number of oocysts spiked/L.	(Number of oocysts spiked)/(sample volume spiked)	No	Yes.
Calculation of percent recoveries for MS samples.	((Calculated # of oocysts/L for the MS sample)—(Calculated # of oocysts/L in the associated field sample)) / (Estimated number of oocysts spiked/L) * 100%.	No	Yes.

TABLE IV-32.—LT2ESWTR DATA SYSTEM FUNCTIONS FOR *Cryptosporidium* COMPLIANCE CHECKS

LT2 requirements	Description
Sample volume analysis	<p>Specifies that the LT2 requirements for sample volume analyzed were met when:</p> <ul style="list-style-type: none"> • volume analyzed is > 10 L. • volume analyzed is < 10 L and pellet volume analyzed is at least 2 mL. • volume analyzed < 10 L and pellet volume analyzed < 2 mL and 100% of filtered volume examined= Y and two filters were used. <p>Specifies that the LT2 requirements for sample volume analyzed were not met when:</p> <ul style="list-style-type: none"> • volume analyzed < 10 L and pellet volume analyzed is < 2 mL and 100% of filtered volume examined= N. • volume analyzed is < 10 L and pellet volume analyzed < 2 mL and only 1 filter used.
Schedule met	Specifies that the predetermined sampling schedule is met when the sample collection data is within ± 2 days of the scheduled date.

c. *Previously collected monitoring data.* Table IV-33 provides a summary of the items that systems must report to EPA for consideration of previously collected (grandfathered) monitoring data under the LT2ESWTR. For each field and matrix spike (MS) sample, systems must report the data elements specified in Table IV-29. In addition,

the laboratory that analyzed the samples must submit a letter certifying that all Method 1622 and 1623 quality control requirements (including ongoing precision and recovery (OPR) and method blank (MB) results, holding times, and positive and negative staining controls) were performed at the required frequency and were acceptable.

Alternatively, the laboratory may provide for each field, MS, OPR, and MB sample a bench sheet and sample examination report form (Method 1622 and 1623 bench sheets are shown in USEPA 2003h).

Systems must report all routine source water *Cryptosporidium* monitoring results collected during the

period covered by the previously collected data that have been submitted. This applies to all samples that were collected from the sampling location used for monitoring, not spiked, and analyzed using the laboratory's routine process for Method 1622 or 1623 analyses, including analytical technique

and QA/QC. Other requirements associated with use of previously collected data are specified in section IV.A.1.d. Where applicable, systems must provide documentation addressing the dates and reason(s) for re-sampling, as well as the use of presedimentation, off-stream storage, or bank filtration

during monitoring. Review of the submitted information, along with the results of the quality assurance audits of the laboratory that produced the data, will be used to determine whether the data meet the requirements for grandfathering.

TABLE IV-33.—ITEMS THAT MUST BE REPORTED FOR CONSIDERATION OF GRANDFATHERED MONITORING DATA

The following items must be reported ¹	On the following schedule ¹
Data elements listed in Table IV-29 for each field and MS sample	No later than 2 months after promulgation if the system does not intend to conduct new monitoring under the LT2ESWTR.
Letter from laboratory certifying that method-specified QC was performed at required frequency and was acceptable. OR Method 1622/1623 bench sheet and sample examination report form for each field, MS, OPR, and method blank sample. Letter from system certifying (1) that all source water data collected during the time period covered by the previously collected data have been submitted and (2) that the data represent the plant's current source water. Where applicable, documentation addressing the dates and reason(s) for re-sampling, as well as the use of presedimentation, off-stream storage, or bank filtration during monitoring.	OR No later than 8 months after promulgation if the system intends to conduct new monitoring under the LT2ESWTR.

¹ See section IV.A.1. for details.

3. Compliance With Additional Treatment Requirements

Under the proposed LT2ESWTR, systems may choose from a "toolbox" of management and treatment options to meet their additional *Cryptosporidium* treatment requirements. In order to

receive credit for toolbox components, systems must initially demonstrate that they comply with any required design and implementation criteria, including performance validation testing. Additionally, systems must provide monthly verification of compliance with any required operational criteria, as

shown through ongoing monitoring. Required design, implementation, operational, and monitoring criteria for toolbox components are described in section IV.C. Proposed reporting requirements associated with these criteria are shown in Table IV-34 for both large and small systems.

TABLE IV-34.—TOOLBOX REPORTING REQUIREMENTS

Toolbox option (potential <i>Cryptosporidium</i> reduction log credit)	You must submit the following items	On the following schedule ¹ (systems serving ≥10,000 people)	On the following schedule ¹ (systems serving < 10,000 people)
Watershed Control Program (WCP) (0.5 log)	Notify State of intention to develop WCP Submit initial WCP plan to State Annual program status report and State-approved watershed survey report. Request for re-approval and report on the previous approval period.	No later than 48 months after promulgation No later than 60 months after promulgation By a date determined by the State, every 12 months, beginning 84 months after promulgation No later than 6 months prior to the end of the current approval period or by a date previously determined by the State	No later than 78 months after promulgation. No later than 90 months after promulgation. By a date determined by the State, every 12 months, beginning 114 months after promulgation. No later than 6 months prior to the end of the current approval period or by a date previously determined by the State.
Pre-sedimentation (0.5 log) (new basins)	Monthly verification of: Continuous basin operation Treatment of 100% of the flow Continuous addition of a coagulant At least 0.5 log removal of influent turbidity based on the monthly mean of daily turbidity readings for 11 of the 12 previous months	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning 72 months after promulgation	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning 102 months after promulgation.
Two-Stage Lime Softening (0.5 log)	Monthly verification of: Continuous operation of a second clarification step between the primary clarifier and filter Presence of coagulant (may be lime) in first and second stage clarifiers Both clarifiers treat 100% of the plant flow	No later than 72 months after promulgation	No later than 102 months after promulgation.

TABLE IV-34.—TOOLBOX REPORTING REQUIREMENTS—Continued

Toolbox option (potential <i>Cryptosporidium</i> re- duction log credit)	You must submit the following items	On the following sched- ule ¹ (systems serving $\geq 10,000$ people)	On the following sched- ule ¹ (systems serving < 10,000 people)
Bank filtration (0.5 or 1.0 log) (new)	Initial demonstration of: Unconsolidated, predominantly sandy aquifer Setback distance of at least 25 ft. (0.5 log) or 50 ft. (1.0 log) If monthly average of daily max turbidity is greater than 1 NTU then system must report result and submit an assessment of the cause	Initial demonstration no later than 72 months after promulgation Report within 30 days following the month in which the monitoring was conducted, beginning 72 months after promulgation	Initial demonstration no later than 102 months after promulgation. Report within 30 days following the month in which the monitoring was conducted, beginning 102 months after promulgation.
Combined filter performance (0.5 log)	Monthly verification of: Combined filter effluent (CFE) turbidity levels less than or equal to 0.15 NTU in at least 95 percent of the 4 hour CFE measurements taken each month	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on 72 months after promulgation	Monthly reporting: within 10 days following the month in which the monitoring was conducted, beginning on 102 months after promulgation.
Membranes (MF, UF, NF, RO) (2.5 log or greater based on verification/integrity testing)	Initial demonstration of: Removal efficiency through challenge studies Methods of challenge studies meet rule criteria Integrity test results and baseline Monthly report summarizing: All direct integrity test results above the control limit and the corrective action that was taken All indirect integrity monitoring results triggering direct integrity testing and the corrective action that was taken	No later than 72 months after promulgation Within 10 days following the month in which monitoring was conducted, beginning 72 months after promulgation	No later than 102 months after promulgation. Within 10 days following the month in which monitoring was conducted, beginning 102 months after promulgation.
Bag filters (1.0 log) and Cartridge filters (2.0 log)	Initial demonstration that the following criteria are met: Process meets the basic definition of bag or cartridge filtration; Removal efficiency established through challenge testing that meets rule criteria Challenge test shows at least 2 and 3 log removal for bag and cartridge filters, respectively	No later than 72 months after promulgation	No later than 102 months after promulgation.
Chlorine dioxide (log credit based on CT)	Summary of CT values for each day and log inactivation based on tables in section IV.C.14	Within 10 days following the month in which monitoring was conducted, beginning 72 months after promulgation	Within 10 days following the month in which monitoring was conducted, beginning 102 months after promulgation.
Ozone (log credit based on CT)	Summary of CT values for each day and log inactivation based on tables in section IV.C.14	Within 10 days following the month in which monitoring was conducted, beginning 72 months after promulgation	Within 10 days following the month in which monitoring was conducted, beginning 102 months after promulgation.
UV (log credit based UV dose and operating within validated conditions)	Results from reactor validation testing demonstrating operating conditions that achieve required UV dose Monthly report summarizing the percentage of water entering the distribution system that was not treated by UV reactors operating within validated conditions for the required UV dose in section IV.C.15	No later than 72 months after promulgation Within 10 days following the month in which monitoring was conducted, beginning 72 months after promulgation	No later than 102 months after promulgation. Within 10 days following the month in which monitoring was conducted, beginning 102 months after promulgation.
Individual filter performance (1.0 log)	Monthly verification of the following, based on continuous monitoring of turbidity for each individual filter: Filtered water turbidity less than 0.1 NTU in at least 95 percent of the daily maximum values from individual filters (excluding 15 minute period following start up after backwashes) No individual filter with a measured turbidity greater than 0.3 NTU in two consecutive measurements taken 15 minutes apart	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on 72 months after promulgation	Monthly reporting: within 10 days following the month in which the monitoring was conducted, beginning 102 months after promulgation.
Demonstration of Performance	Results from testing following State approved protocol	No later than 72 months after promulgation	No later than 102 months after promulgation.

TABLE IV-34.—TOOLBOX REPORTING REQUIREMENTS—Continued

Toolbox option (potential <i>Cryptosporidium</i> re- duction log credit)	You must submit the following items	On the following sched- ule ¹ (systems serving ≥10,000 people)	On the following sched- ule ¹ (systems serving < 10,000 people)
	Monthly verification of operation within State-approved condi- tions for demonstration of performance credit	Within 10 days following the month in which monitoring was con- ducted, beginning 72 months after promulga- tion	Within 10 days following the month in which monitoring was con- ducted, beginning 102 months after promulga- tion.

¹ States may allow an additional two years for systems making capital improvements.

Reporting requirements associated with disinfection profiling and benchmarking are summarized in Table IV-35 for large systems and in Table IV-36 for small systems.

TABLE IV-35.—DISINFECTION BENCHMARKING REPORTING REQUIREMENTS FOR LARGE SYSTEMS

System type	Benchmark component	Submit the following items	On the following schedule
Systems required to conduct <i>Cryptosporidium</i> monitoring.	Characterization of Disinfection Practices	<i>Giardia lamblia</i> and virus inactiva- tion profiles must be on file for State review during sanitary survey.	No later than 36 months after pro- mulgation.
Systems not required to conduct <i>Cryptosporidium</i> monitoring ¹ .	State Review of Proposed Changes to Dis- infection Practices.	Inactivation profiles and bench- mark determinations.	Prior to significant modification of disinfection practice.
	Applicability	None	None.
	Characterization of Disinfection Practices	None	None.
	State Review of Proposed Changes to Dis- infection Practices.	None	None.

¹Systems that provide at least 5.5 log of *Cryptosporidium* treatment consistent with a Bin 4 treatment implication are not required to conduct *Cryptosporidium* monitoring.

TABLE IV-36.—DISINFECTION BENCHMARKING REPORTING REQUIREMENTS FOR SMALL SYSTEMS

System type	Benchmark component	Submit the following items	On the following schedule
Systems required to conduct <i>Cryptosporidium</i> monitoring.	Characterization of Disinfection Practices	<i>Giardia lamblia</i> and virus inactiva- tion profiles must be on file for State review during sanitary survey.	No later than 66 months after pro- mulgation.
Systems not required to conduct <i>Cryptosporidium</i> monitoring and that exceed DBP trig- gers ^{1,2,3} .	State Review of Proposed Changes to Dis- infection Practices.	Inactivation profiles and bench- mark determinations.	Prior to significant modification of disinfection practice.
	Applicability Period	Notify State that profiling is re- quired based on DBP levels.	No later than 42 months after pro- mulgation.
Systems not required to conduct <i>Cryptosporidium</i> monitoring and that do not exceed DBP triggers ^{2,3} .	Characterization of Disinfection Practices	<i>Giardia lamblia</i> and virus inactiva- tion profiles must be on file for State review during sanitary survey.	No later than 54 months after pro- mulgation.
	State Review of Proposed Changes to Dis- infection Practices.	Inactivation profiles and bench- mark determinations.	Prior to significant modification of disinfection practice.
	Applicability Period	Notify State that profiling is not re- quired based on DBP levels.	No later than 42 months after pro- mulgation.
	Characterization of Disinfection Practices	None	None.
	State Review of Proposed Changes to Dis- infection Practices.	None	None.

¹ Systems that provide at least 5.5 log of *Cryptosporidium* treatment consistent with a Bin 4 treatment implication are not required to conduct *Cryptosporidium* monitoring.

² If the *E. coli* annual mean concentration is ≤ 10/100 mL for systems using lakes/reservoir sources or ≤ 50/100 mL for systems using flowing stream sources, the system is not required to conduct *Cryptosporidium* monitoring and will only be required to characterize disinfection practices if DBP triggers are exceeded.

³If the system is a CWS or NTNCWSs and TTHM or HAA5 levels in the distribution system are at least 0.064 mg/L or 0.048 mg/L, respectively, calculated as an LRAA at any Stage 1 DBPR sampling site, then the system is triggered into disinfection profiling.

4. Request for Comment

EPA requests comment on the reporting and recordkeeping requirements proposed for the LT2ESWTR.

Specifically, the Agency requests comment on the proposed requirement that systems report monthly on the use of microbial toolbox components to demonstrate compliance with their *Cryptosporidium* treatment requirements. An alternative may be for systems to keep records on site for State review instead of reporting the data.

K. Analytical Methods

EPA is proposing to require public water systems to conduct LT2ESWTR monitoring using approved methods for *Cryptosporidium*, *E. coli*, and turbidity analyses. This includes meeting quality control criteria stipulated by the approved methods and additional method-specific requirements, as stated later in this section. Related requirements on the use of approved laboratories are discussed in section IV.L, and proposed requirements for reporting of data were stated previously in section IV.J. EPA has developed draft guidance for sampling and analyses under the LT2ESWTR (see USEPA 2003g and 2003h). This guidance is available in draft form in the docket for today's proposal (<http://www.epa.gov/edocket/>).

1. *Cryptosporidium*

a. *What is EPA proposing today?*
Method 1622: "*Cryptosporidium* in Water by Filtration/IMS/FA" (EPA-821-R-01-026, April 2001) (USEPA 2001e) and Method 1623: "*Cryptosporidium* and *Giardia* in Water by Filtration/IMS/FA" (EPA 821-R-01-025, April 2001) (USEPA 2001f) are proposed for *Cryptosporidium* analysis under this rule. Methods 1622 and 1623 require filtration, immunomagnetic separation (IMS) of the oocysts from the captured material, and examination based on IFA, DAPI staining results, and differential interference contrast (DIC) microscopy for determination of oocyst concentrations.

Method Requirements

For each *Cryptosporidium* sample under this proposal, all systems must analyze at least a 10-L sample volume. Systems may collect and analyze greater than a 10-L sample volume. If a sample is very turbid, it may generate a large packed pellet volume upon centrifugation (a packed pellet refers to

the concentrated sample after centrifugation has been performed in EPA Methods 1622 and 1623). Based on IMS purification limitations, samples resulting in large packed pellets will require that the sample concentrate be aliquoted into multiple "subsamples" for independent processing through IMS, staining, and examination. Because of the expense of the IMS reagents and analyst time to examine multiple slides per sample, systems are not required to analyze more than 2 mL of packed pellet volume per sample.

In cases where it is not feasible for a system to process a 10-L sample for *Cryptosporidium* analysis (e.g., filter clogs prior to filtration of 10 L) the system must analyze as much sample volume as can be filtered by 2 filters, up to a packed pellet volume of 2 mL. This condition applies only to filters that have been approved by EPA for nationwide use with Methods 1622 and 1623—the Pall Gelman Envirochek™ and Envirochek™ HV filters, the IDEXX Filta-Max™ foam filter, and the Whatman CrypTest™ cartridge filter.

Methods 1622 and 1623 include fluorescein isothiocyanate (FITC) as the primary antibody stain for *Cryptosporidium* detection, DAPI staining to detect nuclei, and DIC to detect internal structures. For purposes of the LT2ESWTR, systems must report total *Cryptosporidium* oocysts as detected by FITC as determined by the color (apple green or alternative stain color approved for the laboratory under the Lab QA Program described in section VI.L), size (4–6 µm) and shape (round to oval). This total includes all of the oocysts identified as described here, less atypical organisms identified by FITC, DIC, or DAPI (e.g., possessing spikes, stalks, appendages, pores, one or two large nuclei filling the cell, red fluorescing chloroplasts, crystals, spores, etc.).

Matrix Spike Samples

As required by Method 1622 and 1623, systems must have 1 matrix spike (MS) sample analyzed for each 20 source water samples. The volume of the MS sample must be within ten percent of the volume of the unspiked sample that is collected at the same time, and the samples must be collected by splitting the sample stream or collecting the samples sequentially. The MS sample and the associated unspiked sample must be analyzed by the same procedure. MS samples must be spiked and filtered in the laboratory. However,

if the volume of the MS sample is greater than 10 L, the system is permitted to filter all but 10 L of the MS sample in the field, and ship the filtered sample and the remaining 10 L of source water to the laboratory. In this case, the laboratory must spike the remaining 10 L of water and filter it through the filter used to collect the balance of the sample in the field.

EPA is proposing to require the use of flow cytometer-counted spiking suspensions for spiked QC samples during the LT2ESWTR. This provision is based on the improved precision expected for spiking suspensions counted with a flow cytometer, as compared to those counted using well slides or hemacytometers. During the Information Collection Rule Supplemental Surveys, the mean relative standard deviation (RSD) across 25 batches of flow cytometer-sorted *Cryptosporidium* spiking suspensions was 1.8%, with a median of 1.7% (Connell *et al.* 2000). In EPA Performance Evaluation (PE) studies, the mean RSD for flow cytometer sorted *Cryptosporidium* spiking suspensions was 3.4%. In comparison, the mean RSD for *Cryptosporidium* spiking suspensions enumerated manually by 20 laboratories using well slides or hemacytometers was 17% across 108 rounds of 10-replicate counts.

QC requirements in Methods 1622 and 1623 must be met by laboratories analyzing *Cryptosporidium* samples under the LT2ESWTR. The QC acceptance criteria are the same as stipulated in the method. For the initial precision and recovery (IPR) test, the mean *Cryptosporidium* recovery must be 24% to 100% with maximum relative standard deviation (*i.e.*, precision) of 55%. For each ongoing precision and recovery (OPR) sample, recovery must be in the range of 11% to 100%. For each method blank, oocysts must be undetected.

Methods 1622 and 1623 are performance-based methods and, therefore, allow multiple options to perform the sample processing steps in the methods if a laboratory can meet applicable QC criteria and uses the same determinative technique. If a laboratory uses the same procedures for all samples, then all field samples and QC samples must be analyzed in that same manner. However, if a laboratory uses more than one set of procedures for *Cryptosporidium* analyses under LT2ESWTR then the laboratory must analyze separate QC samples for each

option to verify compliance with the QC criteria. For example, if the laboratory analyzes samples using both the Envirochek™ and Filita-Max™ filters, a separate set of IPR, OPR, method blank, and MS samples must be analyzed for each filtration option.

b. *How was this proposal developed?* EPA is proposing EPA Methods 1622 and 1623 for *Cryptosporidium* analyses under the LT2ESWTR because these are the best available methods that have undergone full validation testing. In addition, these methods have been used successfully in a national source water monitoring program as part of the Information Collection Rule Supplemental Surveys (ICRSS). The minimum sample volume and other quality control requirements are intended to ensure that data are of sufficient quality to assign systems to LT2ESWTR risk bins. Further, the proposed method requirements for analysis of *Cryptosporidium* are consistent with recommendations by the Stage 2 M-DBP Advisory Committee. In the Agreement in Principle, the Committee recommended that source water *Cryptosporidium* monitoring under the LT2ESWTR be conducted using EPA Methods 1622 and 1623 with no less than 10 L samples. EPA also has proposed these methods for approval for ambient water monitoring under Guidelines Establishing Test Procedures for the Analysis of Pollutants; Analytical Methods for Biological Pollutants in Ambient Water (66 FR 45811, August 30, 2001) (USEPA 2001i).

When considering the method performance that could be achieved for analysis of *Cryptosporidium* under the LT2ESWTR, EPA and the Advisory Committee evaluated the *Cryptosporidium* recoveries reported for Methods 1622 and 1623 in the ICRSS. As described in section III.C, the ICRSS was a national monitoring program that involved 87 utilities sampling twice per month over 1 year for *Cryptosporidium* and other microorganisms and water quality parameters. During the ICRSS, the mean recovery and relative standard deviation associated with enumeration of MS samples for total oocysts by Methods 1622 and 1623 were 43% and 47%, respectively (Connell *et al.* 2000).

EPA believes that with provisions like the Laboratory QA Program for *Cryptosporidium* laboratories (see section IV.L), comparable performance to that observed in the ICRSS can be achieved in LT2ESWTR monitoring with the use of Methods 1622 and 1623, and that this level of performance will be sufficient to realize the public health goals intended by EPA and the Advisory Committee for the LT2ESWTR. Other

methods would need to achieve comparable performance to be considered for use under the LT2ESWTR. For example, EPA does not expect the Information Collection Rule Method, which resulted in 12% mean recovery for MS samples during the Information Collection Rule Laboratory Spiking Program (Scheller, 2002), to meet LT2ESWTR data quality objectives.

For systems collecting samples larger than 10 L, EPA is proposing the approach of allowing systems to filter all but 10 L of the corresponding MS sample in the field, and ship the filtered sample and the remaining 10 L of source water to the laboratory for spiking and analysis. The Agency has determined that the added costs associated with shipping entire high-volume (*e.g.* 50-L) samples to a laboratory for spiking and analysis are not merited by improved data quality relative to the use of *Cryptosporidium* MS data under the LT2ESWTR. EPA estimates that the average cost for shipping a 50-L bulk water sample is \$350 more than the cost of shipping a 10-L sample and a filter. A study comparing these two approaches (*i.e.*, spiking and filtering 50 L vs. field filtering 40 L and spiking 10 L) indicated that spiking the 10-L sample produced somewhat higher recoveries (USEPA 2003i). However, the differences were not significant enough to offset the greatly increased shipping costs, given the limited use of MS data in LT2ESWTR monitoring.

c. *Request for comment.* EPA requests comment on the proposed method requirements for *Cryptosporidium* analysis, including the following specific issues:

Minimum Sample Volume

It is the intent of EPA that LT2ESWTR sampling provide representative annual mean source water concentrations. If systems were unable to analyze an entire sample volume during certain periods of the year due to elevated turbidity or other water quality factors, this could result in systems analyzing different volumes in different samples. Today's proposal requires systems to analyze at least 10 L of sample or the maximum amount of sample that can be filtered through two filters, up to a packed pellet volume of 2 mL. EPA requests comment on whether these requirements are appropriate for systems with source waters that are difficult to filter or that generate a large packed pellet volume. Alternatively, systems could be required to filter and analyze at least 10 L of sample with no exceptions.

Approval of Updated Versions of EPA Methods 1622 and 1623

EPA has developed draft revised versions of EPA Methods 1622 and 1623 in order to consolidate several method-related changes EPA believes may be necessary to address LT2ESWTR monitoring requirements (see USEPA 2003j and USEPA 2003k). EPA is requesting comment on whether these revised versions should be approved for monitoring under the LT2ESWTR, rather than the April 2001 versions proposed in today's rule. If the revised versions were approved, previously collected data generated using the earlier versions of the methods would still be acceptable for grandfathering, provided the other criteria described in section IV.A.1.d were met. Drafts of the updated methods are provided in the docket for today's rule, and differences between these versions and the April 2001 versions of the methods are clearly indicated for evaluation and comment. Changes to the methods include the following:

(1) Increased flexibility in matrix spike (MS) and initial precision and recovery (IPR) requirements—the requirement that the laboratory must analyze an MS sample on the first sampling event for a new PWS would be changed to a recommendation; the revised method would allow the IPR test to be performed across four different days, rather than restrict analyses to 1 day;

(2) Clarification of some method procedures, including the spiking suspension vortexing procedure and the buffer volumes used during immunomagnetic separation (IMS); requiring (rather than recommending) that laboratories purchase HCl and NaOH standards at the normality specified in the method; and clarification that the use of methanol during slide staining in section 14.2 of the method is as per manufacturer's instructions;

(3) Additional recommendations for minimizing carry-over of debris onto microscope slides after IMS and information on microscope cleaning;

(4) Clarification in the method of the actions to take in the event of QC failures, such as that any positive sample in a batch associated with an unacceptable method blank is unacceptable and that any sample in a batch associated with an unacceptable ongoing precision and recovery (OPR) sample is unacceptable;

(5) Changes to the sample storage and shipping temperature to “less than 10°C and not frozen”, and additional guidance on sample storage and shipping procedures that addresses time of collection, and includes suggestions for monitoring sample temperature during shipment and upon receipt at the laboratory.

(6) Additional analyst verification procedures—adding examination using differential interference contrast (DIC) microscopy to the analyst verification requirements.

(7) Addition of an approved method modification using the Pall Gelman Envirochek HV filter. This approval was based on an interlaboratory validation study demonstrating that three laboratories, each analyzing reagent water and a different source water, met all method acceptance criteria for *Cryptosporidium*. EPA issued a letter (dated March 21, 2002) under the Alternative Test Procedures program approving the procedure as an acceptable version of Method 1623 for *Cryptosporidium* (but not for *Giardia*). EPA also noted in the letter that the procedure was considered to be an acceptable modification of EPA Method 1622.

(8) Incorporation of detailed procedures for concentrating samples using an IDEXX Filta-Max™ foam filter. A method modification using this filter already is approved by EPA in the April 2001 versions of the methods.

(9) Addition of BTF EasySeed™ irradiated oocysts and cysts as acceptable materials for spiking routine QC samples. EPA approved the use of EasySeed™ based on side-by-side comparison tests of method recoveries using EasySeed™ and live, untreated organisms. EPA issued a letter (dated August 1, 2002) approving EasySeed™ for use in routine QC samples for EPA Methods 1622 and 1623 and

for demonstrating comparability of method modifications in a single laboratory.

(10) Removal of the Whatman Nuclepore CrypTest™ cartridge filter. Although a method modification using this filter was approved by EPA in the April 2001 versions of the methods, the filter is no longer available from the manufacturer, and so is no longer an option for sample filtration.

The changes in the June 2003 draft revisions of EPA Methods 1622 and 1623 reflect method-related clarifications, modifications, and additions that EPA believes should be addressed for LT2ESWTR *Cryptosporidium* monitoring. Alternatively, these issues could be addressed through regulatory requirements in the final LT2ESWTR (for required changes and additions) and through guidance (for recommended changes and clarifications). However, EPA believes that addressing these issues through a single source in updated versions of EPA Methods 1622 and 1623 (which could be approved in the final LT2ESWTR) may be more straightforward and easier for systems

and laboratories to follow than addressing them in multiple sources (*i.e.*, existing methods, the final rule, and laboratory guidance).

2. *E. coli*

a. *What is EPA proposing today?* For enumerating source water *E. coli* density under the LT2ESWTR, EPA is proposing to approve the same methods that were proposed by EPA under Guidelines Establishing Test Procedures for the Analysis of Pollutants; Analytical Methods for Biological Pollutants in Ambient Water (66 FR 45811, August 30, 2001) (USEPA 2001i). These methods are summarized in Table IV–37. Methods are listed within the general categories of most probable number tests and membrane filtration tests. Method identification numbers are provided for applicable standards published by EPA and voluntary consensus standards bodies (VCSB) including Standard Methods, American Society of Testing Materials (ASTM), and the Association of Analytical Chemists (AOAC).

TABLE IV–37.— PROPOSED METHODS FOR *E. COLI* ENUMERATION ¹

Technique	Method ¹	EPA	VCSB methods			Commercial example
			Standard methods ²	ASTM ³	AOAC ⁴	
Most Probable Number (MPN).	LTB, EC-MUG	9221B.1/ 9221F			Colilert® ⁵ . Colilert-18® ^{5 7} .
	ONPG-MUG	9223B	991.15	
	ONPG-MUG	9223B	
Membrane Filter (MF) ..	mFC→NA–MUG	9222D/ 9222G			m-ColiBlue24 ⁶ .
	mENDO or LES- ENDO→NA–MUG.	9222B/ 9222G			
	mTEC agar	1103.1	9213D	D5392–93		
	Modified mTEC agar	1603				
	MI medium	1604				
	m-ColiBlue24 broth	

¹ Tests must be conducted in a format that provides organism enumeration.

² Standard Methods for the Examination of Water and Wastewater. American Public Health Association. 20th, 19th, and 18th Editions. Amer. Publ. Hlth. Assoc., Washington, DC.

³ Annual Book of ASTM Standards—Water and Environmental Technology. Section 11.02. ASTM. 100 Barr Harbor Drive, West Conshohocken, PA 19428.

⁴ Official Methods of Analysis of AOAC International, 16th Edition, Volume I, Chapter 17. AOAC International. 481 North Frederick Avenue, Suite 500, Gaithersburg, Maryland 20877–2417.

⁵ Manufactured by IDEXX Laboratories, Inc., One IDEXX Drive, Westbrook, Maine 04092.

⁶ Manufactured by Hach Company, 100 Dayton Ave., Ames, IA 50010.

⁷ Acceptable version of method approved as a drinking water alternative test procedure.

EPA is proposing to allow a holding time of 24 hours for *E. coli* samples. The holding time refers to the time between sample collection and initiation of analysis. Currently, 40 CFR 141.74(a) limits the holding time for source water coliform samples to 8 hours and requires that samples be kept below 10°C during transit. EPA believes that new studies, described later in this section, demonstrate that *E. coli* analysis results for samples held for 24 hours

will be comparable to samples held for 8 hours, provided the samples are held below 10°C and are not allowed to freeze. This proposed increase in holding time is significant for the LT2ESWTR because typically it is not feasible for systems to meet an 8-hour holding time when samples cannot be analyzed on-site. Many small systems that will conduct *E. coli* monitoring under the LT2ESWTR lack a certified on-site laboratory for *E. coli* analyses

and will be required to ship samples to a certified laboratory. EPA believes that it is feasible for these systems to comply with a 24 hour holding time for *E. coli* samples through using overnight delivery services.

b. *How was this proposal developed?* As noted, EPA recently proposed methods for ambient water *E. coli* analysis under Guidelines Establishing Test Procedures for the Analysis of Pollutants; Analytical Methods for

Biological Pollutants in Ambient Water (66 FR 45811, August 30, 2001) (USEPA 2001i). These proposed methods were selected based on data generated by EPA laboratories, submissions to the alternate test procedures (ATP) program and voluntary consensus standards bodies, published peer reviewed journal articles, and publicly available study reports.

The source water analysis for *E. coli* that will be conducted under the LT2ESWTR is similar to the type of ambient water analyses for which these methods were previously proposed (66 FR 45811, August 30, 2001) (USEPA 2001i). EPA continues to support the findings of this earlier proposal and believes that these methods have the necessary sensitivity and specificity to meet the data quality objectives of the LT2ESWTR.

New Information on *E. coli* Sample Holding Time

It is generally not feasible for systems that must ship *E. coli* samples to an off-site laboratory to comply with an 8-hour holding time requirement. During the ICRSS, 100% of the systems that shipped samples off-site for *E. coli* analysis exceeded the 8 hour holding time; 12% of these samples had holding times in excess of 30 hours. Most large systems that will be required to monitor for *E. coli* under the LT2ESWTR could conduct these analyses on-site, but many small systems will need to ship samples off-site to a certified contract laboratory.

EPA participated in three phases of studies to assess the effect of increased sample holding time on *E. coli* analysis results. These are summarized as follows, and are described in detail in Pope *et al.* (2003).

- Phase 1—EPA, the Wisconsin State Laboratory of Hygiene (WSLH), and DynCorp conducted a study to evaluate *E. coli* sample concentrations from four sites at 8, 24, 30, and 48 hours after sample collection for samples stored at 4°C, 10°C, 20°C, and 35°C. Temperature was varied to assess the effect of different shipping conditions. Samples were analyzed in triplicate by membrane filtration (mFC followed by transfer to NA—MUG) and Colilert (Quanti-Tray 2000) (Pope *et al.* 2003).

- Phase 2—EPA conducted a study to evaluate *E. coli* sample concentrations from seven sites at 8, 24, 30, and 48 hours after sample collection for samples stored in coolers containing wet ice or Utek ice packs (to assess real-world storage conditions). Samples were analyzed in triplicate by membrane filtration (mFC followed by transfer to

NA—MUG) and Colilert (Quanti-Tray 2000) (Pope *et al.* 2003).

- Phase 3—EPA, through cooperation with AWWA, obtained *E. coli* holding time data from ten drinking water utilities that evaluated samples from 12 source waters. Each utility used an *E. coli* method of its choice (Colilert, mTEC, mEndo to NA—MUG, or mFC to NA—MUG). Samples were stored in coolers with wet ice, Utek ice packs, or Blue ice (Pope *et al.* 2003).

Phase 1 results indicated that *E. coli* concentrations were not significantly different after 24 hours at most sites when samples were stored at lower temperatures. Results from Phase 2, which evaluated actual sample storage practices, verified the Phase 1 observations at most sites. Similar results were observed during Phase 3, which evaluated a wider variety of surface waters from different regions throughout the U.S. During Phase 3, *E. coli* concentrations were not significantly different after 24 hours at most sites when samples were maintained below 10°C and did not freeze during storage. At longer holding times (*e.g.*, 48 hours), larger differences were observed.

Based on these studies, EPA has concluded that *E. coli* samples can be held for up to 24 hours prior to analysis without compromising the data quality objectives of LT2ESWTR *E. coli* monitoring. Further, EPA believes that it is feasible for systems that must ship *E. coli* samples to an off-site laboratory for analysis to meet a 24 hour holding time. EPA is developing guidance for systems on packing and shipping *E. coli* samples so that samples are maintained below 10°C and not allowed to freeze (USEPA 2003g). This guidance is available in draft in the docket for today's proposal (<http://www.epa.gov/edocket/>).

c. *Request for comment.* EPA requests comment on whether the *E. coli* methods proposed for approval under the LT2ESWTR are appropriate, and whether there are additional methods not proposed that should be considered. Comments concerning method approval should be accompanied by supporting data where possible.

EPA also requests comment on the proposal to extend the holding time for *E. coli* source water sample analyses to 24 hours, including any data or other information that would support, modify, or repudiate such an extension. Should EPA limit the extended holding time to only those *E. coli* analytical methods that were evaluated in the holding time studies noted in this section? The results in Pope *et al.* (2003) indicate that most *E. coli* samples analyzed using ONPG-MUG (see methods in Table IV—

37) incurred no significant degradation after a 30 to 48 hour holding time. As a result, should EPA increase the source water *E. coli* holding time to 30 or 48 hours for samples evaluated by ONPG-MUG, and retain a 24-hour holding time for samples analyzed by other methods? EPA also requests comment on the cost and availability of overnight delivery services for *E. coli* samples, especially in rural areas.

3. Turbidity

a. *What is EPA proposing today?* For turbidity analyses that will be conducted under the LT2ESWTR, EPA is proposing to require systems to use the analytical methods that have been previously approved by EPA for analysis of turbidity in drinking water, as listed in 40 CFR Part 141.74. These are Method 2130B as published in Standard Methods for the Examination of Water and Wastewater (APHA 1992), EPA Method 180.1 (USEPA 1993), and Great Lakes Instruments Method 2 (Great Lakes Instruments, 1992), and Hach FilterTrak Method 10133.

EPA method 180.1 and Standard Method 2130B are both nephelometric methods and are based upon a comparison of the intensity of light scattered by the sample under defined conditions with the intensity of light scattered by a standard reference suspension. Great Lakes Instruments Method 2 is a modulated four beam infrared method using a ratiometric algorithm to calculate the turbidity value from the four readings that are produced. Hach Filter Trak (Method 10133) is a laser-based nephelometric method used to determine the turbidity of finished drinking waters.

Turbidimeters

Systems are required to use turbidimeters described in EPA-approved methods for measuring turbidity. For regulatory reporting purposes, either an on-line or a bench top turbidimeter can be used. If a system chooses to use on-line units for monitoring, the system must validate the continuous measurements for accuracy on a regular basis using a protocol approved by the State.

b. *How was this proposal developed?* EPA believes the currently approved methods for analysis of turbidity in drinking water are appropriate for turbidity analyses that will be conducted under the LT2ESWTR.

c. *Request for comment.* EPA requests comment on whether the turbidity methods proposed today for the LT2ESWTR should be approved, and whether there are additional methods not proposed that should be approved.

L. Laboratory Approval

Given the potentially significant implications in terms of both cost and public health protection of microbial monitoring under the LT2ESWTR, laboratory analyses for *Cryptosporidium*, *E. coli*, and turbidity must be accurate and reliable within the limits of approved methods. Therefore, EPA proposes to require public water systems to use laboratories that have been approved to conduct analyses for these parameters by EPA or the State. The following criteria are proposed for laboratory approval under the LT2ESWTR:

- For *Cryptosporidium* analyses under the LT2ESWTR, EPA proposes to approve laboratories that have passed a quality assurance evaluation under EPA's Laboratory Quality Assurance Evaluation Program (Lab QA Program) for Analysis of *Cryptosporidium* in Water (described in 67 FR 9731, March 4, 2002) (USEPA 2002c). If States adopt an equivalent approval process under State laboratory certification programs, then systems can use laboratories approved by the State.

- For *E. coli* analyses, EPA proposes to approve laboratories that have been certified by EPA, the National Environmental Laboratory Accreditation Conference, or the State for total coliform or fecal coliform analysis in source water under 40 CFR 141.74. The laboratory must use the same analytical technique for *E. coli* that the laboratory uses for total coliform or fecal coliform analysis under 40 CFR 141.74.

- Turbidity analyses must be conducted by a person approved by the State for analysis of turbidity in drinking water under 40 CFR 141.74.

These criteria are further described in the following paragraphs.

1. *Cryptosporidium* Laboratory Approval

Because States do not currently approve laboratories for *Cryptosporidium* analyses and LT2ESWTR monitoring will begin 6 months after rule promulgation, EPA will initially assume responsibility for *Cryptosporidium* laboratory approval. EPA expects, however, that States will include *Cryptosporidium* analysis in their State laboratory certification programs in the future. EPA has established the Lab QA Program for *Cryptosporidium* analysis to identify laboratories that can meet LT2ESWTR data quality objectives. This is a voluntary program open to laboratories involved in analyzing *Cryptosporidium* in water. Under this program, EPA assesses the ability of laboratories to

reliably measure *Cryptosporidium* occurrence with EPA Methods 1622 and 1623, using both performance testing samples and an on-site evaluation.

EPA initiated the Lab QA Program for *Cryptosporidium* analysis prior to promulgation of the LT2ESWTR to ensure that adequate sample analysis capacity will be available at qualified laboratories to support the required monitoring. The Agency is monitoring sample analysis capacity at approved laboratories through the Lab QA Program, and does not plan to implement LT2ESWTR monitoring until the Agency determines that there is adequate laboratory capacity. In addition, utilities that choose to conduct *Cryptosporidium* monitoring prior to LT2ESWTR promulgation with the intent of grandfathering the data may elect to use laboratories that have passed the EPA quality assurance evaluation.

Laboratories seeking to participate in the EPA Lab QA Program for *Cryptosporidium* analysis must submit an interest application to EPA, successfully analyze a set of initial performance testing samples, and undergo an on-site evaluation. The on-site evaluation includes two separate but concurrent assessments: (1) Assessment of the laboratory's sample processing and analysis procedures, including microscopic examination, and (2) evaluation of the laboratory's personnel qualifications, quality assurance/quality control program, equipment, and recordkeeping procedures.

Laboratories that pass the quality assurance evaluation will be eligible for approval for *Cryptosporidium* analysis under the LT2ESWTR. The Lab QA Program is described in detail in a **Federal Register** Notice (67 FR 9731, March 4, 2002) (USEPA 2002c) and additional information can be found online at: www.epa.gov/safewater/lt2/cla_int.html.

Laboratories in the Lab QA Program will receive a set of three ongoing proficiency testing (OPT) samples approximately every four months. EPA will evaluate the precision and recovery data for OPT samples to determine if the laboratory continues to meet the performance criteria of the Laboratory QA Program.

2. *E. coli* Laboratory Approval

Public water systems are required to have samples analyzed for *E. coli* by laboratories certified under the State drinking water certification program to perform total coliform and fecal coliform analyses under 40 CFR 141.74. EPA is proposing that the general

analytical techniques the laboratory is certified to use under the drinking water certification program (e.g., membrane filtration, multiple-well, multiple-tube) will be the methods the laboratory can use to conduct *E. coli* source water analyses under the LT2ESWTR.

3. Turbidity Analyst Approval

Measurements of turbidity must be conducted by a party approved by the State. This is consistent with current requirements for turbidity measurements in drinking water (40 CFR 141.74).

4. Request for Comment

EPA requests comment on the laboratory approval requirements proposed today, including the following specific issues:

Analyst Experience Criteria

The Lab QA Program, which EPA will use to approve laboratories for *Cryptosporidium* analyses under the LT2ESWTR, includes criteria for analyst experience. Principal analyst/supervisors (minimum of one per laboratory) should have a minimum of one year of continuous bench experience with *Cryptosporidium* and immunofluorescent assay (IFA) microscopy, a minimum of six months experience using EPA Method 1622 and/or 1623, and a minimum of 100 samples analyzed using EPA Method 1622 and/or 1623 (minimum 50 samples if the person was an analyst approved to conduct analysis for the Information Collection Rule Protozoan Method) for the specific analytical procedure they will be using.

Under the Lab QA Program, other analysts (no minimum number of analysts per laboratory) should have a minimum of six months of continuous bench experience with *Cryptosporidium* and IFA microscopy, a minimum of three months experience using EPA Method 1622 and/or 1623, and a minimum of 50 samples analyzed using EPA Method 1622 and/or 1623 (minimum 25 samples if the person was an analyst approved to conduct analysis for the Information Collection Rule Protozoan Method) for the specific analytical procedures they will be using.

The Lab QA Program criteria for principal analyst/supervisor experience are more rigorous than those in Methods 1622 and 1623, which are as follows: the analyst must have at least 2 years of college lecture and laboratory course work in microbiology or a closely related field. The analyst also must have at least 6 months of continuous bench experience with environmental protozoa detection techniques and IFA

microscopy, and must have successfully analyzed at least 50 water and/or wastewater samples for *Cryptosporidium*. Six months of additional experience in the above areas may be substituted for two years of college.

In seeking approval for an Information Collection Request, EPA requested comment on the Lab QA Program (67 FR 9731, March 4, 2002) (USEPA 2002c). A number of commenters stated that the analyst qualification criteria are restrictive and could make it difficult for laboratories to maintain adequate analyst staffing (and, hence, sample analysis capacity) in the event of staff turnover or competing priorities. Some commenters suggested that laboratories and analysts should be evaluated based on proficiency testing, and that analyst experience standards should be reduced or eliminated. (Comments are available in Office of Water docket, number W-01-17).

Another aspect of the analyst experience criteria is that systems may generate *Cryptosporidium* data for grandfathering under the LT2ESWTR using laboratories that meet the analyst experience requirement of Methods 1622 or 1623 but not the more rigorous principal analyst/supervisor experience requirement of the Lab QA Program.

EPA requests comment on whether the criteria for analyst experience in the Lab QA Program are necessary, whether systems are experiencing difficulty in finding laboratories that have passed the Lab QA Program to conduct *Cryptosporidium* analysis, and whether any of the Lab QA Program criteria should be revised to improve the LT2ESWTR lab approval process.

State Programs To Approve Laboratories for *Cryptosporidium* Analysis

Under today's proposal, systems must have *Cryptosporidium* samples analyzed by a laboratory approved under EPA's Lab QA Program, or an equivalent State laboratory approval program. Because States do not currently approve laboratories for *Cryptosporidium* analyses, EPA will initially assume responsibility for *Cryptosporidium* laboratory approval. EPA expects, however, that States will adopt equivalent approval programs for *Cryptosporidium* analysis under State laboratory certification programs. EPA requests comment on how to establish that a State approval program for *Cryptosporidium* analysis is equivalent to the Lab QA Program.

Specifically, should EPA evaluate State Approval programs to determine if they are equivalent to the Lab QA Program? EPA also requests comment

on the elements that would constitute an equivalent State approval program for *Cryptosporidium* analyses, including the following: (1) Successful analysis of initial and ongoing blind proficiency testing samples prepared using flow cytometry, including a matrix and meeting EPA's pass/fail criteria (described in USEPA 2002c); (2) an on-site evaluation of the laboratory's sample processing and analysis procedures, including microscopic examination skills, by auditors who meet the qualifications of a principal analyst as set forth in the Lab QA Program (described in USEPA 2002c); (3) an on-site evaluation of the laboratory's personnel qualifications, quality assurance/quality control program, equipment, and recordkeeping procedures; (4) a data audit of the laboratories' QC data and monitoring data; and (5) use of the audit checklist used in the Lab QA Program or equivalent.

M. Requirements for Sanitary Surveys Conducted by EPA

1. Overview

In today's proposal, EPA is requesting comment on establishing requirements for public water systems with significant deficiencies as identified in a sanitary survey conducted by EPA under SDWA section 1445. These requirements would apply to surface water systems for which EPA is responsible for directly implementing national primary drinking water regulations (*i.e.*, systems not regulated by States with primacy). As described in this section, these requirements would ensure that systems in non-primacy States, currently Wyoming, and systems not regulated by States, such as Tribal systems, are subject to standards for sanitary surveys similar to those that apply to systems regulated by States with primacy.

2. Background

As established by the IESWTR in 40 CFR 142.16(b)(3), primacy States must conduct sanitary surveys for all surface water systems no less frequently than every three years for community water systems and no less frequently than every five years for noncommunity water systems. The sanitary survey is an onsite review and must address the following eight components: (1) Source, (2) treatment, (3) distribution system, (4) finished water storage, (5) pumps, pump facilities, and controls, (6) monitoring, reporting, and data verification, (7) system management and operation, and (8) operator compliance with State requirements.

Under the IESWTR, primacy States are required to have the appropriate rules or other authority to assure that systems respond in writing to significant deficiencies outlined in sanitary survey reports no later than 45 days after receipt of the report, indicating how and on what schedule the system will address significant deficiencies noted in the survey (40 CFR 142.16(b)(1)(ii)). Further, primacy States must have the authority to assure that systems take necessary steps to address significant deficiencies identified in sanitary survey reports if such deficiencies are within the control of the system and its governing body (40 CFR 142.16(b)(1)(iii)). The IESWTR did not define a significant deficiency, but required that primacy States describe in their primacy applications how they will decide whether a deficiency identified during a sanitary survey is significant for the purposes of the requirements stated in this paragraph (40 CFR 142.16(b)(3)(v)).

EPA conducts sanitary surveys under SDWA section 1445 for public water systems not regulated by primacy States (*e.g.*, Tribal systems, Wyoming). However, EPA does not have the authority required of primacy States under 40 CFR 142 to ensure that systems address significant deficiencies identified during sanitary surveys. Consequently, the sanitary survey requirements established by the IESWTR create an unequal standard. Systems regulated by primacy States are subject to the States' authority to require correction of significant deficiencies noted in sanitary survey reports, while systems for which EPA has direct implementation authority do not have to meet an equivalent requirement.

3. Request for Comment

In order to ensure that systems for which EPA has direct implementation authority address significant deficiencies identified during sanitary surveys, EPA requests comment on establishing either or both of the following requirements under 40 CFR 141 as part of the NPDWR established in the final LT2ESWTR:

(1) For sanitary surveys conducted by EPA under SDWA section 1445, systems would be required to respond in writing to significant deficiencies outlined in sanitary survey reports no later than 45 days after receipt of the report, indicating how and on what schedule the system will address significant deficiencies noted in the survey.

(2) Systems would be required to correct significant deficiencies identified in sanitary survey reports if such deficiencies are within the control of the system and its governing body.

For the purposes of these requirements, a sanitary survey, as conducted by EPA, is an onsite review of the water source (identifying sources of contamination by using results of source water assessments where available), facilities, equipment, operation, maintenance, and monitoring compliance of a public water system to evaluate the adequacy of the system, its sources and operations, and the distribution of safe drinking water. A significant deficiency includes a defect in design, operation, or maintenance, or a failure or malfunction of the sources, treatment, storage, or distribution system that EPA determines to be causing, or has the potential for causing the introduction of contamination into the water delivered to consumers.

V. State Implementation

This section describes the regulations and other procedures and policies States will be required to adopt to implement the LT2ESWTR, if finalized as proposed today. States must continue to meet all other conditions of primacy in 40 CFR Part 142.

The Safe Drinking Water Act (Act) establishes requirements that a State or eligible Indian tribe must meet to assume and maintain primary enforcement responsibility (primacy) for its public water systems. These requirements include: (1) Adopting drinking water regulations that are no less stringent than Federal drinking water regulations, (2) adopting and implementing adequate procedures for enforcement, (3) keeping records and making reports available on activities that EPA requires by regulation, (4) issuing variances and exemptions (if allowed by the State), under conditions no less stringent than allowed under the Act, and (5) adopting and being capable of implementing an adequate plan for the provisions of safe drinking water under emergency situations.

40 CFR part 142 sets out the specific program implementation requirements for States to obtain primacy for the public water supply supervision program as authorized under section 1413 of the Act. In addition to adopting basic primacy requirements specified in 40 CFR Part 142, States may be required to adopt special primacy provisions pertaining to specific regulations where implementation of the rule involves activities beyond general primacy provisions. States must include these regulation specific provisions in an application for approval of their program revision. Primacy requirements for today's proposal are discussed below.

To implement the proposed LT2ESWTR, States will be required to adopt revisions to:

- § 141.2—Definitions
- § 141.71—Criteria for avoiding filtration
- § 141.153—Content of the reports
- § 141.170—Enhanced filtration and disinfection
- Subpart Q—Public Notification
- New Subpart W—Additional treatment technique requirements for *Cryptosporidium*
- § 142.14—Records kept by States
- § 142.15—Reports by States
- § 142.16—Special primacy requirements

A. Special State Primacy Requirements

To ensure that a State program includes all the elements necessary for an effective and enforceable program under today's rule, a State primacy application must include a description of how the State will perform the following:

- (1) Approve watershed control programs for the 0.5 log watershed control program credit in the microbial toolbox (see section IV.C.2);
- (2) Assess significant changes in the watershed and source water as part of the sanitary survey process and determine appropriate follow-up action (see section IV.A);
- (3) Determine that a system with an uncovered finished water storage facility has a risk mitigation plan that is adequate for purposes of waiving the requirement to cover the storage facility or treat the effluent (see section IV.E);
- (4) Approve protocols for removal credits under the Demonstration of Performance toolbox option (see section IV.C.17) and for site specific chlorine dioxide and ozone CT tables (see section IV.C.14); and
- (5) Approve laboratories to analyze for *Cryptosporidium*.

Note that a State program can be more, but not less, stringent than Federal regulations. As such, some of the elements listed here may not be applicable to a specific State program. For example, if a State chooses to require all finished water storage facilities to be covered or provide treatment and not to allow a risk mitigation plan to substitute for this requirement, then the description for item (3) would be inapplicable.

B. State Recordkeeping Requirements

The current regulations in § 142.14 require States with primacy to keep various records, including the following: Analytical results to determine compliance with MCLs, MRDLs, and treatment technique requirements; system inventories; State approvals; enforcement actions; and the

issuance of variances and exemptions. The proposed LT2ESWTR will require States to keep additional records of the following, including all supporting information and an explanation of the technical basis for each decision:

- Results of source water *E. coli* and *Cryptosporidium* monitoring;
- *Cryptosporidium* bin classification for each filtered system, including any changes to initial bin classification based on review of the watershed during sanitary surveys or the second round of monitoring;
- Determination of whether each unfiltered system has a mean source water *Cryptosporidium* level above 0.01 oocysts/L;
- The treatment processes or control measures that each system employs to meet *Cryptosporidium* treatment requirements under the LT2ESWTR; this includes documentation to demonstrate compliance with required design and implementation criteria for receiving credit for microbial toolbox options, as specified in section IV.C;
- A list of systems required to cover or treat the effluent of an uncovered finished water storage facilities; and
- A list of systems for which the State has waived the requirement to cover or treat the effluent of an uncovered finished water storage facility, along with supporting documentation of the risk mitigation plan.

C. State Reporting Requirements

EPA currently requires in § 142.15 that States report to EPA information such as violations, variance and exemption status, and enforcement actions. The LT2ESWTR, as proposed, will add additional reporting requirements in the following area:

- The *Cryptosporidium* bin classification for each filtered system, including any changes to initial bin classification based on review of the watershed during sanitary surveys or the second round of monitoring;
- The determination of whether each unfiltered system has a mean source water *Cryptosporidium* level above 0.01 oocysts/L, including any changes to this determination based on the second round of monitoring.

D. Interim Primacy

On April 28, 1998, EPA amended its State primacy regulations at 40 CFR 142.12 to incorporate the new process identified in the 1996 SDWA Amendments for granting primary enforcement authority to States while their applications to modify their primacy programs are under review (63 FR 23362, April 28, 1998) (USEPA 1998f). The new process grants interim

primary enforcement authority for a new or revised regulation during the period in which EPA is making a determination with regard to primacy for that new or revised regulation. This interim enforcement authority begins on the date of the primacy application submission or the effective date of the new or revised State regulation, whichever is later, and ends when EPA makes a final determination. However, this interim primacy authority is only available to a State that has primacy (including interim primacy) for every existing NPDWR in effect when the new regulation is promulgated.

As a result, States that have primacy for every existing NPDWR already in effect may obtain interim primacy for this rule, beginning on the date that the State submits the application for this rule to USEPA, or the effective date of its revised regulations, whichever is later. In addition, a State that wishes to obtain interim primacy for future NPDWRs must obtain primacy for this rule. As described in Section IV.A, EPA expects to oversee the initial source water monitoring that will be conducted under the LT2ESWTR by systems serving at least 10,000 people, beginning 6 months following rule promulgation.

VI. Economic Analysis

This section summarizes the economic analysis (EA) for the LT2ESWTR proposal. The EA is an assessment of the benefits, both health and non-health related, and costs to the regulated community of the proposed regulation, along with those of regulatory alternatives that the Agency considered. EPA developed this EA to meet the requirement of SDWA section 1412(b)(3)(C) for a Health Risk Reduction and Cost Analysis (HRRCA), as well as the requirements of Executive Order 12866, Regulatory Planning and Review, under which EPA must estimate the costs and benefits of the LT2ESWTR. The full EA is presented in Economic Analysis for the Long Term 2 Enhanced Surface Water Treatment Rule (USEPA 2003a), which is available in the docket for today's proposal (www.epa.gov.edocket/).

Today's proposed LT2ESWTR is the second in a staged set of rules that

address public health risks from microbial contamination of surface and GWUDI drinking water supplies and, more specifically, prevent *Cryptosporidium* from reaching consumers. As described in section I, the Agency promulgated the IESWTR and LT1ESWTR to provide a baseline of protection against *Cryptosporidium* in large and small drinking water systems, respectively. Today's proposed rule would achieve further reductions in *Cryptosporidium* exposure for systems with the highest vulnerability. This economic analysis considers only the incremental reduction in exposure from the two previously promulgated rules (IESWTR and LT1ESWTR) to the alternatives evaluated for the LT2ESWTR.

Both benefits and costs are determined as annualized present values. The process allows comparison of cost and benefit streams that are variable over a given time period. The time frame used for both benefit and cost comparisons is 25 years; approximately five years account for rule implementation and 20 years for the average useful life of the equipment used to comply with treatment technique requirements. The Agency uses social discount rates of both three percent and seven percent to calculate present values from the stream of benefits and costs and also to annualize the present value estimates (see EPA's Guidelines for Preparing Economic Analyses (USEPA 2000c) for a discussion of social discount rates). The LT2ESWTR EA (USEPA 2003a) also shows the undiscounted stream of both benefits and costs over the 25 year time frame.

A. What Regulatory Alternatives Did the Agency Consider?

Regulatory alternatives considered by Agency for the LT2ESWTR were developed through the deliberations of the Stage 2 M-DBP Federal Advisory Committee (described in section II). The Committee considered several general approaches for reducing the risk from *Cryptosporidium* in drinking water. As discussed in section IV.A.2, these approaches included both additional treatment requirements for all systems

and risk-targeted treatment requirements for systems with the highest vulnerability to *Cryptosporidium* following implementation of the IESWTR and LT1ESWTR. In addition, the Committee considered related factors such as surrogates for *Cryptosporidium* monitoring and alternative monitoring strategies to minimize costs to small drinking water systems.

After considering these general approaches, the Committee focused on four specific regulatory alternatives for filtered systems (see Table VI-1). With the exception of Alternative 1, which requires all systems to achieve an additional 2 log (99%) reduction in *Cryptosporidium* levels, these alternatives incorporate a microbial framework approach. In this approach, systems are classified in different risk bins based on the results of source water monitoring. Additional treatment requirements are directly linked to the risk bin classification. Accordingly, these rule alternatives are differentiated by two criteria: (1) The *Cryptosporidium* concentrations that define the bin boundaries and (2) the degree of treatment required for each bin.

In assessing regulatory alternatives, EPA and the Advisory Committee were concerned with the following questions: (1) Do the treatment requirements adequately control *Cryptosporidium* concentrations in finished water? (2) How many systems will be required to add treatment? (3) What is the likelihood that systems with high source water *Cryptosporidium* concentrations will not be required to provide additional treatment (i.e., be misclassified in a low risk bin)? and (4) What is the likelihood that systems with low source water *Cryptosporidium* concentrations will be required to provide unnecessary additional treatment (i.e., misclassified in a high risk bin)?

The Committee reached consensus regarding additional treatment requirements for unfiltered systems and uncovered finished water storage facilities without formally identifying regulatory alternatives. Table VI-1 summarizes the four alternatives that were considered for filtered systems.

TABLE VI-1.—SUMMARY OF REGULATORY ALTERNATIVES FOR FILTERED SYSTEMS

Average source water <i>Cryptosporidium</i> monitoring result (oocysts/L)	Additional treatment requirements ¹
Alternative A1	
2.0 log inactivation required for all systems	
Alternative A2	
< 0.03	No action.
≥ 0.03 and < 0.1	0.5 log.
≥ 0.1 and < 1.0	1.5 log.
≥ 1.0	2.5 log.
Alternative A3—Preferred Alternative	
< 0.075	No action.
≥ 0.075 and < 1.0	1 log.
≥ 1.0 and < 3.0	2 log.
≥ 3.0	2.5 log.
Alternative A4	
< 0.1	No action.
≥ 0.1 and < 1.0	0.5-log.
≥ 1.0	1.0 log.

¹ Note: “Additional treatment requirements” are in addition to levels already required under existing rules (e.g., the IESWTR and LT1ESWTR).

B. What Analyses Support Selecting the Proposed Rule Option?

EPA has quantified benefits and costs of each of the regulatory alternatives in Table VI-1, as well as for the proposed requirements for unfiltered systems. Quantified benefits stem from estimated reductions in the incidence of cryptosporidiosis resulting from the regulation. To make these estimates, the Agency developed a two-dimensional Monte Carlo model that accounts for uncertainty and variability in key parameters like *Cryptosporidium* occurrence, infectivity, and treatment efficiency. Analyses involved estimating the baseline (pre-LT2ESWTR) risk from *Cryptosporidium* in drinking water, and then projecting the reductions in exposure and risk resulting from the additional treatment requirements of the LT2ESWTR. Costs result largely from the installation of additional treatment, with lesser costs due to monitoring and other implementation activities. Results of these analyses are summarized in the following subsections, and details are shown in the LT2ESWTR EA (USEPA 2003a).

Cryptosporidium occurrence significantly influences the estimated benefits and costs of regulatory alternatives. As discussed in section III.C, EPA analyzed data collected under the Information Collection Rule, the Information Collection Rule Supplemental Surveys of medium systems (ICRSSM), and the Information Collection Rule Supplemental Surveys of large systems (ICRSSL) to estimate the national occurrence distribution of

Cryptosporidium in surface water. EPA evaluated these distributions independently when assessing benefits and costs for different regulatory alternatives. In most cases, results from the ICRSSM data set are within the range of results of the Information Collection Rule and ICRSSL data sets.

EPA selected a Preferred Regulatory Alternative for the LT2ESWTR, consistent with the recommendations of the Advisory Committee. As described next, this selection was based on the estimated impacts and feasibility of the alternatives shown in Table VI-1.

Alternative A1 (across-the-board 2-log inactivation) was not selected because it was the highest cost option and imposed costs but provided few benefits to systems with high quality source water (i.e., relatively low *Cryptosporidium* risk). In addition, there were concerns about the feasibility of requiring almost every surface water treatment plant to install additional treatment processes (e.g., UV or ozone) for *Cryptosporidium*.

Alternatives A2–A4 were evaluated based on several factors, including predictions of costs and benefits, performance of analytical methods for classifying systems in the risk bins, and other specific impacts (e.g., impacts on small systems or sensitive subpopulations). Alternative A3 was recommended by the Advisory Committee because it provides significant health benefits in terms of avoided illnesses and deaths for an acceptable cost. In addition, the Agency believes this alternative is feasible with

available analytical methods and treatment technologies.

Incremental costs and benefits of regulatory alternatives for the LT2ESWTR are shown in section VI.F, and the LT2ESWTR EA contains more detailed information about the benefits and costs of each regulatory option (USEPA 2003a).

C. What Are the Benefits of the Proposed LT2ESWTR?

As discussed previously, the LT2ESWTR is expected to substantially reduce drinking water related exposure to *Cryptosporidium*, thereby reducing both illness and death associated with cryptosporidiosis. As described in section II, cryptosporidiosis is an infection caused by *Cryptosporidium* and is an acute, typically self-limiting, illness with symptoms that include diarrhea, abdominal cramping, nausea, vomiting, and fever (Juranek, 1995). Cryptosporidiosis patients in sensitive subpopulations, such as infants, the elderly, and AIDS patients, are at risk for severe illness, including risk of death. While EPA has quantified and monetized the health benefits for reductions in endemic cryptosporidiosis that would result from the LT2ESWTR, the Agency was unable to quantify or monetize other health and non-health related benefits associated with this rule. These unquantified benefits are characterized next, followed by a summary of the quantified benefits.

1. Non-Quantifiable Health and Non-health Related Benefits
 Although there are substantial monetized benefits that result from this rule due to reduced rates of endemic cryptosporidiosis, other potentially significant benefits of this rule remain unquantified and non-monetized. The unquantified benefits that result from this rule are summarized in Table VI-2 and are described in greater detail in the LT2ESWTR EA (USEPA 2003a).

TABLE VI-2.—SUMMARY OF NONQUANTIFIED BENEFITS

Benefit type	Potential effect on benefits	Comments
Reducing outbreak risks and response costs	Increase	Some outbreaks are caused by human or equipment failures that may occur even with the proposed new requirements; however, by adding barriers of protection for some systems, the rule will reduce the possibility of such failures leading to outbreaks.
Reducing averting behavior (e.g., boiling tap water or purchasing bottled water).	Increase / No Change	Averting behavior is associated with both out-of-pocket costs (e.g., purchase of bottled water) and opportunity costs (e.g., time requiring to boil water) to the consumer. Reductions in averting behavior are expected to have a positive impact on benefits from the rule.
Improving aesthetic water quality	Increase	Some technologies installed for this rule (e.g., ozone) are likely to reduce taste quality and odor problems.
Reducing risk from co-occurring and emerging pathogens.	Increase	Although focused on removal of <i>Cryptosporidium</i> from drinking water, systems that change treatment processes will also increase removal of pathogens that the rule does not specifically regulate. Additional benefits will accrue.
Increased source water monitoring	Increase	The greater understanding of source water quality that results from monitoring may enhance the ability of plants to optimize treatment operations in ways other than those addressed in this rule.
Reduced contamination due to covering on treating finished water storage facilities.	Increase	Although insufficient data were available to quantify benefits, the reduction of contaminants introduced through uncovered finished water storage facilities would produce positive public health benefits.

Source: Chapter 5 of the LT2ESWTR Economic Analysis (USEPA 2003a).

2. Quantifiable Health Benefits

EPA quantified benefits for the LT2ESWTR based on reductions in the risk of endemic cryptosporidiosis. Several categories of monetized benefits were considered in this analysis.

First, EPA estimated the number of cases expected to result in premature mortality (primarily for members of sensitive subpopulations such as AIDS patients). In order to estimate the benefits from deaths avoided as a result of the rule, EPA multiplied the estimates for number of illnesses avoided by a projected mortality rate. This mortality rate was developed using mortality data from the Milwaukee cryptosporidiosis outbreak of 1993 (described in section II), with adjustments to account for the subsequent decrease in the mortality rate among people with AIDS and for the difference between the 1993 Milwaukee AIDS rate and the current national rate. EPA estimated a mortality rate of 16.6 deaths per 100,000 illnesses for those served by unfiltered systems and a mortality rate of 10.6 deaths per 100,000 illnesses for those served by filtered systems. These different rates are associated with the incidence of AIDS in populations served by

unfiltered and filtered systems. A complete discussion on how EPA derived these rates can be found in subchapter 5.2 of the LT2ESWTR EA (USEPA 2003a).

Reductions in mortalities were monetized using EPA's standard methodology for monetizing mortality risk reduction. This methodology is based on a distribution of value of statistical life (VSL) estimates from 26 labor market and stated preference studies, with a mean VSL of \$6.3M in 2000, and a 5th to 95th percentile range of \$1.0 to \$14.5. A more detailed discussion of these studies and the VSL estimate can be found in EPA's Guidelines for Preparing Economic Analyses (USEPA 2000c). A real income growth factor was applied to these estimates of approximately 2.3% per year for the 20 year time span following implementation. Income elasticity for VSL was estimated as a triangular distribution that ranged from 0.08 to 1.00, with a mode of 0.40. VSL values for the 20 year span are shown in the LT2 EA in Exhibit C.13 (USEPA 2003a).

The substantial majority of cases are not expected to be fatal and the Agency separately estimated the value of non-fatal illnesses avoided that would result from the LT2ESWTR. For these, EPA

first divided projected cases into three categories, mild, moderate, and severe, and then calculated a monetized value per case avoided for each severity level. These were then combined into a weighted average value per case based on the relative frequency of each severity level. According to a study conducted by Corso *et al.* (2003), the majority of illness falls into the mild category (88 percent). Approximately 11 percent of illness falls into the moderate category, which is defined as those who seek medical treatment but are not hospitalized. The final one percent have severe symptoms that result in hospitalization. EPA estimated different medical expenses and time losses for each category.

Benefits for non-fatal cases were calculated using a cost-of-illness (COI) approach. Traditional COI valuations focus on medical costs and lost work time, and leave out significant categories of benefits, specifically the reduced utility from being sick (*i.e.*, lost personal or non-work time, including activities such as child care, homemaking, community service, time spent with family, and recreation), although some COI studies also include an estimate for unpaid labor (household production) valued at an estimated wage

rate designed to reflect the market value of such labor (e.g., median wage for household domestic labor). This reduced utility is variously referred to as lost leisure or a component of pain and suffering. Ideally, a comprehensive willingness to pay (WTP) estimate would be used that includes all categories of loss in a single number. However, a review of the literature indicated that the available studies were not suitable for valuing

cryptosporidiosis; hence, estimates from this literature are inappropriate for use in this analysis. Instead, EPA presents two COI estimates: a traditional approach that only includes valuation for medical costs and lost work time (including some portion of unpaid household production); and an enhanced approach that also factors in valuations for lost unpaid work time for employed people, reduced utility (or sense of well-being) associated with

decreased enjoyment of time spent in non-work activities, and lost productivity at work on days when workers are ill but go to work anyway.

Table VI-3 shows the various categories of loss and how they were valued for each estimate for a “typical” case (weighted average of severity level—see LT2ESWTR EA—Chapter 5 for more details (USEPA 2003a).

TABLE VI-3.—TRADITIONAL AND ENHANCED COI FOR CRYPTOSPORIDIOSIS

Loss category	Traditional COI	Enhanced COI
Direct Medical Costs	\$93.82	\$93.82
Lost Paid Work Days	109.88	109.88
Lost Unpaid Work Days ¹	20.22	40.44
Lost Caregiver Days ²	20.70	54.31
Lost Leisure Time ³	⁵	333.96
Lost Productivity at Work	⁵	112.49
Total ⁴	244.62	744.89

¹ Assigned to 38.2% of the population not engaged in market work; assumes 40 hr. unpaid work week, valued at \$5.46/hr in traditional COI and \$10.92/hr in enhanced COI. Does not include lost unpaid work for employed people and may not include all unpaid work for people outside the paid labor force.

² Values lost work or leisure time for people caring for the ill. Traditional approach does not include lost leisure time.

³ Includes child care and homemaking (to the extent not covered in lost unpaid work days above), time with family, and recreation for people within and outside the paid labor force.

⁴ Detail may not calculate to totals due to independent rounding; Source: Appendix L in LT2ESWTR EA (USEPA 2003a).

⁵ Not included.

The various loss categories were calculated as follows: Medical costs are a weighted average across the three illness severity levels of actual costs for doctor and emergency room visits, medication, and hospital stays. Lost paid work represents missed work time of paid employees, valued at the median pre-tax wage, plus benefits of \$18.47 hour. The average number of lost work hours per case is 5.95 (this assumes that 62 percent of the population is in the paid labor force and the loss is averaged over seven days). Medical costs and lost work days reflect market transactions. Medical costs are always included in COI estimates and lost work days are usually included in COI estimates.

In the traditional COI estimate, an equivalent amount of lost unpaid work time was assigned to the 38% of the population that are not in the paid labor force. This includes homemakers, students, children, retirees, and unemployed persons. EPA did not attempt to calculate what percent of cases falls in each of these five groups, or how many hours per week each group works, but rather assumed an across-the-board 40 hour unpaid work week. This time is valued at \$5.46 per hour, which is one half the median post-tax wage, (since work performed by these groups is not taxed). This is approximately the median wage for paid household domestic labor.

In the enhanced COI estimate, all time other than paid work and sleep (8 hours per day) is valued at the median after tax wage, or \$10.92 per hour. This includes lost unpaid work (e.g., household production) and leisure time for people within and outside the paid labor force. Implicit in this approach, is that people would pay the same amount not to be sick during their leisure time as they require to give up their leisure time to work (i.e., the after tax wage). In reality, people might be willing to pay either more than this amount (if they were very sick and suffering a lot) or less than this amount (if they were not very sick and still got some enjoyment out of activities such as resting, reading and watching TV), not to be sick. Multiplying 16 hours by \$10.92 gives a value of about \$175.00 for a day of “lost” unpaid work and leisure (i.e., lost utility of being sick).

An estimate of lost unpaid work days for the enhanced approach was made by assigning the value of \$10.92 per hour to the same number of unpaid work hours valued in the traditional COI approach (i.e., 40 unpaid work hours per week for people outside the paid labor force). Lost unpaid work for employed people and any unpaid labor beyond 40 hours per week for those not in the labor market is shown as lost leisure time in Table VI-3 for the enhanced approach and is not included

in the traditional approach. In addition, for days when an individual is well enough to work but still experiencing symptoms, such as diarrhea, the enhanced estimate also includes a 30% loss of work and leisure productivity, based on a study of giardiasis illness (Harrington *et al.* 1985) which is similar to cryptosporidiosis. Appendix P in the EA describes similar productivity losses for other illnesses such as influenza (35%–73% productivity losses). In the traditional COI analysis, productivity losses are not included for either work or non-work time.

The Agency believes that losses in productivity and lost leisure time are unquestionably present and that these categories have positive value; consequently, the traditional COI estimate understates the true value of these loss categories. EPA notes that these estimates should not be regarded as upper and lower bounds. In particular, the enhanced COI estimate may not fully incorporate the value of pain and suffering, as people may be willing to pay more than \$201 to avoid a day of illness. The traditional COI estimate includes a valuation for a lost 40 hour work week for all persons not in the labor force, including children and retirees. This may be an overstatement of lost productivity for these groups, which would depend on the impact of such things as missed

school work or volunteer activities that may be affected by illness.

As with the avoided mortality valuation, the real wages used in the COI estimates were increased by a real income growth factor that varies by year, but is the equivalent of about 2.3% over the 20 year period. This approach of adjusting for real income growth was recommended by the SAB (USEPA 2000e) because the median real wage is expected to grow each year (by approximately 2.3%)—the median real wage is projected to be \$38,902 in 2008

and \$59,749 in 2027. Correspondingly, the real income growth factor of the COI estimates increases by the equivalent of 2.3% per year (except for medical costs, which are not directly tied to wages). This approach gives a total COI valuation in 2008 of \$268.92 for the traditional COI estimate and \$931.06 for the enhanced COI estimate; the valuation in 2027 is \$362.75 for the traditional COI estimate and \$1,429.99 for the enhanced COI estimate. There is no difference in the methodology for calculating the COI over this 20 year

period of implementation; the change in valuation is due to the underlying change in projected real wages.

Table VI-4 summarizes the annual cases of cryptosporidiosis illness and associated deaths avoided due to the LT2ESWTR proposal. The proposed rule, on average, is expected to reduce 256,000 to 1,019,000 illnesses and 37 to 141 deaths annually after full implementation (range based on the ICRSSL, ICRSSM, and Information Collection Rule data sets).

TABLE VI-4.—SUMMARY OF ANNUAL AVOIDED ILLNESS AND DEATHS

Data set	Annual illnesses avoided			Annual deaths avoided		
	Mean	90 percent confidence bound		Mean	90 percent confidence bound	
		Lower (5th %ile)	Upper (95th %ile)		Lower (5th %ile)	Upper (95th %ile)
Annual Total After Full Implementation						
ICR	1,018,915	169,358	2,331,467	141	25	308
ICRSSL	256,173	45,292	560,648	37	7	78
ICRSSM	498,363	84,724	1,177,415	70	13	157
Annual Average Over 25 years						
ICR	720,668	119,694	1,647,796	100	18	218
ICRSSL	181,387	32,179	396,845	26	5	55
ICRSSM	352,611	59,942	833,290	50	9	111

Source: The LT2ESWTR Economic Analysis (USEPA 2003a).

Tables VI-5a and VI-5b show the monetized present value of the benefit for reductions in endemic cryptosporidiosis estimated to result from the LT2ESWTR for the enhanced and traditional COI values, respectively. Estimates are given for the Information Collection Rule, ICRSSL, and ICRSSM occurrence data sets.

With the enhanced COI and a three percent discount rate, the annual present value of the mean benefit estimate ranges from \$374 million to \$1.4 billion, with a 90 percent

confidence bound of \$52 million to \$198 million at the lower 5th percentile and \$959 million to \$3.7 billion at the upper 95th percentile; at a seven percent discount rate, this estimate ranges from \$318 million to \$1.2 billion, with a 90 percent confidence bound of \$44 million to \$168 million at the lower 5th percentile and \$816 million to \$3.1 billion at the upper 95th percentile. With the traditional COI, the corresponding benefit estimate at a three percent discount rate ranges from \$253 million to \$967 million, with a 90

percent confidence bound of \$27 million to \$105 million at the lower 5th percentile and \$713 million to \$2.7 billion at the upper 95th percentile; for a seven percent discount rate, this estimate ranges from \$216 million to \$826 million, with a 90 percent confidence bound of \$23 million to \$89 million at the lower 5th percentile and \$610 million to \$2.3 billion at the upper 95th percentile. None of these values include the unquantified and non-monetized benefits discussed previously.

TABLE VI-5A.—SUMMARY OF QUANTIFIED BENEFITS—ENHANCED COI
[\$millions, 2000\$]

Data set	Value of benefits—Enhanced COI ¹		
	Mean	90 percent confidence bound	
		Lower (5th %ile)	Upper (95th %ile)
Annualized Value (at 3%, 25 Years)			
ICR	\$1,445	\$198	3,666
ICRSSL	374	52	959
ICRSSM	715	96	1,849
Annualized Value (at 7%, 25 Years)			
ICR	1,230	168	3,120

TABLE VI-5A.—SUMMARY OF QUANTIFIED BENEFITS—ENHANCED COI—Continued
[\$millions, 2000\$]

Data set	Value of benefits—Enhanced COI ¹		
	Mean	90 percent confidence bound	
		Lower (5th %ile)	Upper (95th %ile)
ICRSSL	318	44	816
ICRSM	609	81	1,577

¹ The traditional COI only includes valuation for medical costs and lost work time (including some portion of unpaid household production). The enhanced COI also factors in valuations for lost personal time (non-worktime) such as child care and homemaking (to the extent not covered by the traditional COI), time with family, and recreation, and lost productivity at work on days when workers are ill but go to work anyway. Source: The LT2ESWR Economic Analysis (USEPA 2003a).

TABLE VI-5B.—SUMMARY OF QUANTIFIED BENEFITS—TRADITIONAL COI
[(Millions, 2000\$)]

Data Set	Value of Benefits—Traditional COI ¹		
	Mean	90 percent confidence bound	
		Lower (5th %ile)	Upper (95th %ile)
Annualized Value (at 3%, 25 Years)			
ICR	\$967	\$105	\$2,713
ICRSSL	253	27	713
ICRSM	481	50	1,372
Annualized Value (at 7%, 25 Years)			
ICR	826	89	2,315
ICRSSL	216	23	610
ICRSM	411	43	1,172

¹ The traditional COI only includes valuation for medical costs and lost work time (including some portion of unpaid household production). The enhanced COI also factors in valuations for lost personal time (non-worktime) such as child care and homemaking (to the extent not covered by the traditional COI), time with family, and recreation, and lost productivity at work on days when workers are ill but go to work anyway. Source: The LT2ESWTR Economic Analysis (USEPA 2003a).

a. *Filtered systems.* Benefits to the approximately 161 million people served by filtered surface water and GWUDI systems range from 88,000 to 472,000 reduction in mean annual cases of endemic illness based on ICRSSL, ICRSM, and ICR data sets. In addition, premature mortality is expected to be reduced by an average of 9 to 50 deaths annually.

b. *Unfiltered systems.* The 12 million people served by unfiltered surface water or GWUDI systems will see a significant reduction in cryptosporidiosis as a result of the LT2ESWTR. In this population, the rule is expected to reduce approximately 168,000 to 547,000 cases of illness and 28 to 91 premature deaths annually.

For unfiltered systems, only the Information Collection Rule data set is used to directly calculate illness reduction because it is the only data set that includes sufficient information on unfiltered systems. Illness reduction in unfiltered systems was estimated for the

ICRSSL and ICRSM data sets by multiplying the Information Collection Rule unfiltered system result by the ratio, for the quantity estimated, between filtered system results from the supplemental survey data set (SSM or SSL) and filtered system results from the Information Collection Rule.

3. *Timing of Benefits Accrual (Latency)*

In previous rulemakings, some commenters have argued that the Agency should consider an assumed time lag or latency period in its benefits calculations. The Agency has not conducted a latency analysis for this rule because cryptosporidiosis is an acute illness; therefore, very little time elapses between exposure, illness, and mortality. However, EPA does account for benefits and costs that occur in future years by converting these to present value estimates.

D. *What Are the Costs of the Proposed LT2ESWTR?*

In order to estimate the costs of today's proposed rule, the Agency considered impacts on public water systems and on States (including territories and EPA implementation in non-primacy States). EPA assumed that systems would be in compliance with the IESWTR, which has a compliance date of January 2002 for large systems and the LT1ESWTR, which has a compliance date of January 2005 for small systems. Therefore, this cost estimate only considers the additional requirements that are a direct result of the LT2ESWTR. More detailed information on cost estimates are described next and a complete discussion can be found in chapter 6 of the LT2ESWTR EA (USEPA 2003a). An detailed discussion of the proposed rule provisions is located in section IV of this preamble.

1. Total Annualized Present Value Costs

Tables VI-6a and VI-6b summarize the annualized present value cost estimates for the proposed LT2ESWTR at three percent and seven percent discount rates, respectively. The mean annualized present value costs of the proposed LT2ESWTR are estimated to range from approximately \$73 to \$111 million using a three percent discount rate and \$81 to \$121 million using a seven percent discount rate. This range in mean cost estimates is associated with the ICRSSL and Information Collection Rule *Cryptosporidium* occurrence data sets. Using different occurrence data sets results in different

bin classifications and, thus, impacts the cost of the rule. Results for the ICRSSM fall within the range of results for the Information Collection Rule and ICRSSL. In addition to mean estimates of costs, the Agency calculated 90 percent confidence bounds by considering the uncertainty in *Cryptosporidium* occurrence estimates and around the mean unit technology costs (USEPA 2003a).

Public water systems will incur approximately 99 percent of the rule's total annualized present value costs. States incur the remaining rule costs. Table VI-7 shows the undiscounted initial capital and one-time costs broken

out by rule component. A comparison of annualized present value costs among the rule alternatives considered by the Agency is located in subsection VI.F. and in the LT2ESWTR EA (USEPA 2003a). Using a present value allows costs and benefits that occur during different time periods to be compared. For any future cost, the higher the discount rate, the lower the present value. Specifically, a future cost evaluated at a seven percent discount rate will always result in a lower total present value cost than the same future cost evaluated at a three percent discount rate.

BILLING CODE 6560-50-P

Table VI-6a.-- Annualized Present Value Costs for the Proposed LT2ESWTR
(three percent discount rate, \$ millions, 2000\$)

Type of Cost	Range of Occurrence Means with Cost Uncertainty (\$Millions, 2000\$)				Bounds of Occurrence Range with Cost Uncertainty (\$Millions, 2000\$)									
	Serving ≤ 10k		Serving > 10K		Serving ≤ 10k		Serving > 10K		Serving ≤ 10k		Serving > 10K		Total	
	Mean ICRSSL	Mean ICR	Mean ICRSSL	Mean ICR	5th Percentile ICRSSL	95th Percentile ICR	5th Percentile ICRSSL	95th Percentile ICR	5th Percentile ICRSSL	95th Percentile ICR	5th Percentile ICRSSL	95th Percentile ICR	5th Percentile ICRSSL	95th Percentile ICR
	A	B	C	D	E = A + C	F = B + D	G	H	I	J	K = G + I	L = H + J		
Treatment Mean	\$5.32	\$9.56	\$56.79	\$88.82	\$62.10	\$98.38	\$3.48	\$10.33	\$38.40	\$96.48	\$41.88	\$106.81		
Treatment Uncertainty Bound	\$4.83	\$10.29	\$49.69	\$99.56	\$54.51	\$109.85	\$3.15	\$11.12	\$33.46	\$108.26	\$36.62	\$119.38		
Uncovered Reservoirs Mean	\$0.01	\$0.01	\$5.40	\$5.40	\$5.40	\$5.40	\$0.01	\$0.01	\$5.40	\$5.40	\$5.40	\$5.40		
Uncovered Reservoirs Uncertainty Bound	\$0.00	\$0.01	\$4.60	\$6.20	\$4.61	\$6.20	\$0.00	\$0.01	\$4.60	\$6.20	\$4.61	\$6.20		
Implementation	\$0.07	\$0.07	\$0.02	\$0.02	\$0.09	\$0.09	\$0.07	\$0.07	\$0.02	\$0.02	\$0.09	\$0.09		
Monitoring	\$1.48	\$1.99	\$1.48	\$1.48	\$2.95	\$3.46	\$1.11	\$2.14	\$1.48	\$1.48	\$2.59	\$3.62		
Future Monitoring	\$1.06	\$1.35	\$0.94	\$0.82	\$2.00	\$2.17	\$0.81	\$1.44	\$1.02	\$0.79	\$1.82	\$2.24		
Benchmarking	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.01	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.01		
State Implementation	--	--	--	--	\$0.38	\$0.38	--	--	--	--	\$0.38	\$0.38		
State Monitoring	--	--	--	--	\$0.47	\$0.47	--	--	--	--	\$0.47	\$0.47		
State Benchmarking	--	--	--	--	\$0.00	\$0.00	--	--	--	--	\$0.00	\$0.00		
State Technology Reporting	--	--	--	--	\$0.09	\$0.15	--	--	--	--	\$0.07	\$0.15		
TOTALS														
National (System + State)					\$73.48	\$110.51							\$52.70	\$119.16
System	\$7.92	\$12.97	\$64.62	\$96.54	\$72.54	\$109.51	\$5.48	\$13.98	\$46.31	\$104.17	\$51.79	\$118.16		
State/Primacy Agency					\$0.94	\$0.99					\$0.92	\$1.00		

Source: Chapter 6 of the LT2ESWTR Economic Analysis (USEPA 2003a)

Table VI-6b.- Annualized Present Value Costs for the Proposed LT2ESWTR
(seven percent discount rate, \$ millions, 2000\$)

Type of Cost	Range of Occurrence Means with Cost Uncertainty (\$Millions, 2000\$)						Bounds of Occurrence Range with Cost Uncertainty (\$Millions, 2000\$)					
	Serving ≤ 10k		Serving > 10K		Total		Serving ≤ 10k		Serving > 10K		Total	
	Mean ICRSSL	Mean ICR	Mean ICRSSL	Mean ICR	Mean ICRSSL	Mean ICR	5th Percentile ICRSSL	95th Percentile ICR	5th Percentile ICRSSL	95th Percentile ICR	5th Percentile ICRSSL	95th Percentile ICR
	A	B	C	D	E = A + C	F = B + D	G	H	I	J	K = G + I	L = H + J
Treatment Mean	\$5.07	\$9.10	\$62.26	\$97.13	\$67.33	\$106.24	\$3.33	\$9.83	\$42.10	\$105.53	\$45.43	\$115.36
Treatment Uncertainty Bound	\$4.58	\$9.84	\$54.11	\$109.46	\$58.69	\$119.30	\$2.99	\$10.63	\$36.44	\$119.06	\$39.43	\$129.69
Uncovered Reservoirs Mean	\$0.01	\$0.01	\$6.41	\$6.41	\$6.42	\$6.42	\$0.01	\$0.01	\$6.41	\$6.41	\$6.42	\$6.42
Uncovered Reservoirs Uncertainty Bound	\$0.01	\$0.01	\$5.41	\$7.42	\$5.41	\$7.43	\$0.01	\$0.01	\$5.41	\$7.42	\$5.41	\$7.43
Implementation	\$0.09	\$0.09	\$0.03	\$0.03	\$0.12	\$0.12	\$0.09	\$0.09	\$0.03	\$0.03	\$0.12	\$0.12
Monitoring	\$1.90	\$2.54	\$2.08	\$2.08	\$3.99	\$4.63	\$1.44	\$2.74	\$2.08	\$2.08	\$3.53	\$4.82
Future Monitoring	\$0.97	\$1.22	\$0.96	\$0.84	\$1.93	\$2.07	\$0.74	\$1.31	\$1.04	\$0.81	\$1.78	\$2.12
Benchmarking	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.01	\$0.00	\$0.00	\$0.00	\$0.01	\$0.00	\$0.01
State Implementation	--	--	--	--	\$0.55	\$0.55	--	--	--	--	\$0.55	\$0.55
State Monitoring	--	--	--	--	\$0.52	\$0.52	--	--	--	--	\$0.52	\$0.52
State Benchmarking	--	--	--	--	\$0.00	\$0.00	--	--	--	--	\$0.00	\$0.00
State Technology Reporting	--	--	--	--	\$0.08	\$0.12	--	--	--	--	\$0.06	\$0.13
TOTALS												
National (System + State)					\$80.93	\$120.68					\$58.41	\$130.05
System	\$8.04	\$12.97	\$71.74	\$106.50	\$79.78	\$119.48	\$5.61	\$13.98	\$51.66	\$114.86	\$57.28	\$128.84
State/Privacy Agency					\$1.15	\$1.20					\$1.13	\$1.21

Source: Chapter 6 of the LT2ESWTR Economic Analysis (USEPA 2003a)

Table VI-7.— Initial Capital and One-time Costs for the LT2ESWTR

Type of Cost	Range of Occurrence Means with Cost Uncertainty (\$Millions, 2000\$)						Bounds of Occurrence Range with Cost Uncertainty (\$Millions, 2000\$)					
	Serving ≤ 10k		Serving > 10K		Total		Serving ≤ 10k		Serving > 10K		Total	
	Mean ICRSSL	Mean ICR	Mean ICRSSL	Mean ICR	Mean ICRSSL	Mean ICR	5th Percentile ICRSSL	95th Percentile ICR	5th Percentile ICRSSL	95th Percentile ICR	5th Percentile ICRSSL	95th Percentile ICR
A	B	C	D	E = A + C	F = B + D	G	H	I	J	K = G + I	L = H + J	
Treatment Mean	\$68.72	\$122.30	\$951.14	\$1,469.50	\$1,019.86	\$1,591.80	\$45.49	\$132.02	\$643.23	\$1,597.51	\$688.72	\$1,729.52
Treatment Uncertainty Bound	\$59.87	\$135.98	\$805.46	\$1,690.02	\$865.33	\$1,826.00	\$39.48	\$146.63	\$542.26	\$1,840.04	\$581.74	\$1,986.67
Uncovered Reservoirs Mean	\$0.07	\$0.07	\$64.28	\$64.28	\$64.35	\$64.35	\$0.07	\$0.07	\$64.28	\$64.28	\$64.35	\$64.35
Uncovered Reservoirs Uncertainty Bound	\$0.05	\$0.08	\$52.09	\$76.56	\$52.15	\$76.65	\$0.05	\$0.08	\$52.09	\$76.56	\$52.15	\$76.65
Implementation	\$1.23	\$1.23	\$0.33	\$0.33	\$1.56	\$1.56	\$1.23	\$1.23	\$0.33	\$0.33	\$1.56	\$1.56
Monitoring	\$28.90	\$39.05	\$26.88	\$26.88	\$55.78	\$65.93	\$21.67	\$42.07	\$26.88	\$26.88	\$48.55	\$68.95
Future Monitoring	\$26.99	\$34.54	\$22.01	\$19.29	\$49.01	\$53.83	\$20.46	\$37.02	\$23.80	\$18.55	\$44.26	\$55.57
Benchmarking	\$0.02	\$0.06	\$0.05	\$0.08	\$0.08	\$0.14	\$0.02	\$0.06	\$0.03	\$0.09	\$0.05	\$0.15
State Implementation	--	--	--	--	\$6.68	\$6.68	--	--	--	--	\$6.68	\$6.68
State Monitoring	--	--	--	--	\$10.45	\$10.45	--	--	--	--	\$10.45	\$10.45
State Benchmarking	--	--	--	--	\$0.04	\$0.07	--	--	--	--	\$0.03	\$0.08
TOTALS												
National (System + State)	\$125.93		\$1,064.70		\$1,190.63		\$88.93	\$212.47	\$758.55	\$1,707.63	\$864.63	\$1,937.30
System	\$197.24		\$1,580.37		\$1,777.60		\$88.93	\$212.47	\$758.55	\$1,707.63	\$847.48	\$1,920.10
State/Primacy Agency					\$17.17						\$17.15	\$17.20

Source: Chapter 6 of the LT2ESWTR Economic Analysis (USEPA 2003a)

BILLING CODE 6560-50-C

2. Water System Costs

The proposed LT2ESWTR applies to all community, non-transient non-community, and transient non-community water systems that use surface water or GWUDI as a source (including both filtered and unfiltered systems). EPA has estimated the cost impacts for these three types of public drinking water systems. As shown in Table VI-6a and VI-6b, the mean annualized present value costs for all drinking water systems range from

approximately \$73 to \$111 million using a three percent discount rate (\$81 to \$121 million using a seven percent discount rates).

The majority of costs of the rule result from treatment changes incurred by filtered and unfiltered systems. Table VI-8 shows the number of filtered and unfiltered systems that will incur costs by rule provision. Subsection VI.D.2.b discusses treatment costs for filtered system and subsection VI.D.2.c discusses treatment options for unfiltered systems. All non-purchased surface water and GWUDI systems

subject to the LT2ESWTR (including filtered and unfiltered systems) will incur one-time costs that include time for staff training on rule requirements. Systems will incur monitoring costs to assess source water *Cryptosporidium* levels, though monitoring requirements vary by system size (large vs. small) and system type (filtered vs. unfiltered). A discussion of future monitoring that will occur six years after initial bin assignments can be found in subsection VI.D.2.e.

BILLING CODE 6560-50-P

Table VI-8.— Number of Filtered and Unfiltered Systems and Plants Expected to Incur Costs¹

Dataset	Nonpurchased Systems and Plants							Systems with Uncovered Reservoirs
	System Size (population served)	Systems Incurring Implementation Costs	Source Water Monitoring - Plants				Plants Adding Treatment	
			Initial <i>E. Coli</i> Monitoring	Initial <i>Crypto</i> Monitoring	Future <i>E. coli</i> Monitoring	Future <i>Crypto</i> Monitoring		
	A	B	C	D	E	F	G	
ICR	≤ 10,000	5,682	5,792	2,016	5,122	1,782	2,251	32
	> 10,000	1,384	1,774	1,774	1,273	1,273	733	106
	Total	7,066	7,565	3,789	6,395	3,056	2,984	138
ICRSSL	≤ 10,000	Same as ICR		1,295	5,409	1,209	1,463	Same as ICR
	> 10,000			1,774	1,453	1,453	481	
	Total			3,069	6,862	2,662	1,944	
ICRSSM	≤ 10,000	Same as ICR		1,575	5,347	1,454	1,768	Same as ICR
	> 10,000			1,774	1,386	1,386	578	
	Total			3,349	6,733	2,840	2,346	

¹Numbers shown for plants monitoring include nonpurchased plants only. Numbers shown for plants adding treatment include both nonpurchased plants and a fraction of plants purchasing water that could not be linked to a nonpurchased plant. Source: Chapter 6 of the *LT2ESWTR Economic Analysis* (USEPA 2003a)

BILLING CODE 6560-50-C

a. *Source water monitoring costs.* Source water monitoring costs are structured on a per-plant basis. Also, as with implementation activities, purchased plants are assumed not to treat source water and will not have any monitoring costs. There are three types of monitoring that plants may be required to conduct—turbidity, *E. coli* and *Cryptosporidium*. Source water turbidity is a common water quality parameter used for plant operational control. Also, to meet SWTR, LT1ESWTR and IESWTR requirements, most water systems have turbidity analytical equipment in-house and operators are experienced with turbidity

measurement. Thus, EPA assumes that the incremental turbidity monitoring burden associated with the LT2ESWTR is negligible.

Filtered plants in small systems initially will be required to conduct one year of biweekly *E. coli* source water monitoring. These plants will be required to monitor for *Cryptosporidium* if, as a result of initial bin classification, *E. coli* levels exceed the following concentrations: (1) Annual mean > 10 *E. coli*/100 mL for lakes and reservoir sources, and (2) annual mean > 50 *E. coli*/100 mL for flowing stream sources. EPA estimated the percent of small plants that would be triggered into *Cryptosporidium* monitoring as being

equal to the percent of large plants that would fall into any bin requiring additional treatment.

Estimates of laboratory fees, shipping costs, labor hours for sample collection, and hours for reporting results were used to predict system costs for initial source water monitoring under the LT2ESWTR. Table VI-9 summarizes the present value of monitoring costs for initial bin classification. Total present value monitoring costs for initial bin classification range from \$46 million to \$60 million depending on the occurrence data set and discount rate. Appendix D of the LT2ESWTR EA provides a full explanation of how these costs were developed (USEPA 2003a).

TABLE VI-9.—SUMMARY OF PRESENT VALUE MONITORING COSTS FOR INITIAL BIN CLASSIFICATION
(\$millions, 2000\$)

System Size	ICR (3%) A	ICR (7%) B	ICRSSL (3%) C	ICRSSL (7%) D	ICRSSM (3%) E	ICRSSM (7%) F
≤10K	\$34.6	\$29.7	\$25.7	\$22.2	\$29.2	\$25.1
10K	25.7	24.3	25.7	24.3	25.7	24.3
Total	60.3	54.0	51.4	46.5	54.9	49.4

Source: Chapter 6 of the LT2ESWTR Economic Analysis (USEPA 2003a).

b. *Filtered systems treatment costs.* The Agency calculated treatment costs by estimating the number of plants that will be adding treatment technologies and coupling these estimates with unit costs (\$/plant) of the selected technologies. Table VI-10 shows the number of plants estimated to select different treatment technologies; Table VI-11 summarizes the present value treatment costs and annualized present value costs for both filtered and unfiltered systems.

To estimate the number of filtered plants that would select a particular treatment technology, the Agency followed a two step process. First, the

number of plants that must make treatment changes to meet the proposed LT2ESWTR requirement was determined by the binning process. Second, EPA predicted the treatment technologies that plants would choose to meet the proposed requirements. The Agency used a “least-cost decision tree” as the basic framework for determining the treatment technology selection. In other words, EPA assumed that drinking water plants would select the least expensive technology or combination of technologies to meet the log removal requirements of a given action bin. However, these technology selections were constrained by maximum use

percentages, which recognize that some plants will not be able to implement certain technologies because of site-specific conditions. In addition, certain potentially lower cost components of the microbial toolbox, such as changes to the plant intake, were not included because the Agency lacked data to estimate the number of plants that could select it. These limitations on technology use may result in an overestimate of costs. An in-depth discussion of the technology selection methodology and unit cost estimates can be found in appendices E and F of the proposed LT2ESWTR EA (USEPA 2003a).

TABLE VI-10.—TECHNOLOGY SELECTION FORECASTS FOR FILTERED PLANTS

Technology Selections	Data set		
	ICR	ICRSSL	ICRSSM
Bag Filter 1.0 Log	1,545	1,236	1,441
Cartridge Filter 2.0 Log	190	17	52
CL02 0.5 Log	77	60	70
Combined Filter Performance 0.5 Log	16	12	14
In-bank Filtration 1.0 Log	5	3	4
MF/UF 2.5 Log	10	3	5
Technology Selections ¹			
03 0.5 Log	26	17	21
03 1.0 Log	24	18	21
03 2.0 Log	9	1	2
Secondary Filter 1.0 Log	0	0	0
UV 2.5 Log	998	490	632
WS Control 0.5 Log	0	0	0
Total Plants Selecting Technologies	2,893	1,852	2,255

¹ Some plants are projected to select more than one technology to meet LT2ESWTR bin requirements; consequently, the value for total plants does not equal the sum of all technologies selected. Source: Chapter 6 of the LT2ESWTR Economic Analysis (USEPA 2003a).

c. *Unfiltered systems treatment costs.* The proposed LT2ESWTR requires all unfiltered plants to achieve 2 logs of inactivation if their mean source water *Cryptosporidium* concentration is less than or equal to 0.01 oocysts/L and 3 logs of inactivation if it is greater than 0.01 oocysts/L. For most systems, UV appears to be the least expensive technology that can achieve the required log inactivation of *Cryptosporidium*, and it is expected to be widely used by unfiltered systems to meet the rule requirement. However, as with filtered

systems, EPA estimated that a small percentage of plants would elect to install a technology more expensive than UV due to the configuration of existing equipment or other factors. Ozone is the next least expensive technology that will meet the inactivation requirements for some systems, and is estimated to be used by plants that do not use UV.

All unfiltered plants must meet requirements of the LT2ESWTR; therefore, the percent of plants adding technology is 100 percent. This also

assumes that no unfiltered systems currently use these additional treatment technologies. For this cost analysis, the Agency assumed 100 percent of very small unfiltered systems will use UV; for all other unfiltered system sizes, the Agency estimated that 90 percent would install UV and 10 percent would add ozone. This analysis is discussed in more detail in the LT2ESWTR EA (USEPA 2003a). Treatment costs for unfiltered systems are included in Table VI-11.

TABLE VI-11.—TOTAL PRESENT VALUE AND ANNUALIZED PRESENT VALUE TREATMENT COSTS FOR FILTERED AND UNFILTERED PLANTS

Data Set	System Size (population served)	Present Value Capital Costs at 3% A	Present Value Capital Costs at 7% B	Annualized O&M Costs at 3% C	Annualized O&M Costs at 7% D	Total Annualized Costs at 3% E	Total Annualized Costs at 7% F
ICR	≤10,000	\$76.1	\$56.0	\$5.2	\$4.3	\$9.6	\$9.1
	>10,000	1,092.4	868.0	26.1	22.7	88.8	97.1
TOTAL		1,168.5	924.0	31.3	26.9	98.4	106.2
ICRSSL	≤10,000	42.8	31.5	2.9	2.4	5.3	5.1
	>10,000	707.1	561.8	16.2	14.0	56.8	62.3
TOTAL		749.8	593.3	19.0	16.4	62.1	67.3
ICRSSM	≤10,000	52.6	38.7	3.5	2.9	6.6	6.2
	>10,000	842.4	669.3	19.4	16.9	67.8	74.3
TOTAL		894.9	708.0	23.0	19.8	74.4	80.6

Source: Chapter 6 of the LT2ESWTR Economic Analysis (USEPA 2003a)

d. *Uncovered finished water storage facilities.* As part of the LT2ESWTR, systems with uncovered finished water storage facilities have the option to cover the storage facility or provide disinfection after the storage facility, unless the State has determined that existing risk mitigation is adequate. Disinfection alternatives must achieve at least four logs of virus inactivation. To develop national cost estimates for systems to comply with this provision of the LT2ESWTR, unit costs for each treatment alternative and the percentage of systems selecting each alternative were estimated for the inventory of systems with uncovered finished water storage facilities. A full description of the unit costs and other assumptions

used in this analysis is presented in Chapter 6 and Appendix I of the LT2ESWTR EA (USEPA 2003a).

The Agency assumed that all systems with uncovered finished water storage facilities will have to either install a cover or treat their discharge. This overestimates the cost of this provision because States can determine that systems with uncovered finished storage facilities do not need to take these additional measures. The technology selection for the uncovered finished water storage facilities was developed through a least-cost approach.

For systems with uncovered storage facility capacities of five million gallons (MG) or less, covering the storage facilities is the least expensive alternative. Although chlorination is the

least expensive alternative for the remaining systems, the ability of a system to use booster chlorination depends on their current residual disinfectant type. Less than half of all surface water systems are predicted to use chloramination following implementation of the Stage 2 DBPR. Adding chlorine to water that has been treated with chloramines is not a feasible alternative; therefore, the fraction of systems projected to add booster chlorination to the effluent from the storage facility was estimated at 50 percent, with the remaining 50 percent estimated to add covers. The technology selection for uncovered finished water storage facilities is presented in Table VI-12.

TABLE VI-12.—ESTIMATED TECHNOLOGY SELECTION FOR UNCOVERED STORAGE FACILITIES

Size category (MG)	Number of uncovered storage facilities	Floating cover (%)	Booster chlorination (%)
0-0.1	25	100	
0.1-1	7	100	
>1-5	44	100	
>5-10	12	100	
>10-20	10	100	
>20-40	9	50	50
>40-60	4	50	50
>60-80	4	50	50
>80-100	6	50	50
>100-150	6	50	50
>150-200	2	50	50
>200-250	4	50	50
>250-1,000	4	50	50
>1,000	1	50	50

Source: Appendix I of the LT2ESWTR Economic Analysis (USEPA 2003a)

Table VI-13 summarizes total annualized present value costs for the uncovered storage facility provision using both three and seven percent

discount rates. The Agency estimates the total annualized present value cost for covering or treating uncovered finished water storage facilities to be

approximately \$5.4 million at a three percent discount rate and \$6.4 million at a seven percent discount rate.

TABLE VI-13.—ESTIMATED ANNUALIZED PRESENT VALUE COST FOR UNCOVERED FINISHED WATER STORAGE FACILITY PROVISION (2000\$)

System size (population served)	Annualized cost at 3%			Annualized cost at 7%		
	Capital	O&M	Total	Capital	O&M	Total
≤10,000	\$3,520	\$1,649	\$5,169	\$4,713	\$1,552	\$6,264
>10,000	3,349,320	2,046,425	5,395,745	4,483,927	1,925,203	6,409,129
Total	3,352,840	2,048,074	5,400,915	4,488,639	1,926,754	6,415,393

Source: Appendix I of the LT2ESWTR Economic Analysis (USEPA 2003a)

e. *Future monitoring costs.* Six years after initial bin classification, filtered and unfiltered plants will be required to conduct a second round of monitoring to assess whether source water *Cryptosporidium* levels have changed significantly. EPA will evaluate new analytical methods and surrogate indicators of microbial water quality in the interim. While the costs of monitoring are likely to change in the six years following rule promulgation, it is difficult to predict how they will change. In the absence of any other

information, it was assumed that the laboratory costs would be the same as for the initial monitoring.

All plants that conducted initial monitoring were assumed to conduct the second round of monitoring as well, except for those systems that installed treatment that reduces 2.5 logs of *Cryptosporidium* or greater as a result of the rule. These systems are exempt from monitoring under the LT2ESWTR. Table VI-8 shows the number of systems that are estimated to conduct the second round of monitoring (listed as “future”

monitoring in the table). EPA estimates the cost of re-binning will range from \$23 million to \$38 million depending on the occurrence data set and discount rate used in the estimate (see Table VI-14). Costs differ among *Cryptosporidium* occurrence data sets due to differences in estimates of the number of plants that will add technologies to achieve at least 2.5 log *Cryptosporidium* reduction and the number of small plants that will be triggered into monitoring for *Cryptosporidium*. Appendix D of the EA provides further details (USEPA 2003a).

TABLE VI-14.—PRESENT VALUE OF MONITORING COSTS OF FUTURE RE-BINNING
[\$millions, 2000\$]

System size	ICR (3%)	ICR (7%)	ICRSSL (3%)	ICRSSL (7%)	ICRSSM (3%)	ICRSSM (7%)
	A	B	C	D	E	F
≤10K	\$23.5	\$14.3	\$18.4	\$11.3	\$20.7	\$12.6
>10k	14.4	9.8	16.4	11.2	15.6	10.7
Total	37.8	24.1	34.8	22.5	36.3	23.3

Source: Chapter 6 of the LT2ESWTR Economic Analysis (USEPA 2003a)

f. Sensitivity analysis—influent bromide levels on technology selection for filtered plants. One concern about the ICR data set was that it may not actually reflect influent bromide levels in some plants during droughts. High influent bromide levels (the precursor for bromate formation) limits ozone use because the plant would not be able to meet the MCL for bromate. The Agency conducted a sensitivity analysis to estimate an impact of higher influent bromide levels would have on technology decisions. The sensitivity analysis assumes influent bromide concentrations of 50 parts per billion (ppb) above the ICR concentrations. Overall, the impact of these assumptions have a minimal impact on costs. A complete discussion of this sensitivity analysis is located in LT2ESWTR EA (USEPA 2003a).

3. State/Primacy Agency Costs

The Agency estimates that States and primacy agencies will incur an annualized present value cost of \$0.9 to

\$1.0 million using a three percent discount rate and \$1.2 million at seven percent. State implementation activities include regulation adoption and program implementation, training State staff, training PWS staff, providing technical assistance to PWSs, and updating the management system. To estimate implementation costs to States/Primacy Agencies, the number of full-time employees (FTEs) per activity is multiplied by the number of labor hours per FTE, the cost per labor hour, and the number of States and Territories.

In addition to implementation costs, States and primacy agencies will also incur costs associated with monitoring data management. Because EPA will directly manage the first round of monitoring by large systems (serving at least 10,000 people), States are not predicted to incur costs for these activities. States will, however, incur costs associated with small system monitoring. This is a result of the delayed start of small system monitoring, which will mean that some

States will assume primacy for small system monitoring. In addition, States will review of the second round of monitoring results. States will also incur costs in reviewing technology compliance data and consulting with systems regarding benchmarking for systems that change their disinfection procedures to comply with the rule. Appendix D of the LT2ESWTR EA provides more information about the State and primacy agency cost analysis (USEPA 2003a).

4. Non-Quantified Costs

EPA has quantified all the major costs for this rule and has provided uncertainty analyses to bound the over or underestimates in the costs. There are some costs that EPA has not quantified, however, because of lack of data. For example, some systems may merge with neighboring systems to comply with this rule. Such changes have both costs (legal fees and connecting infrastructure) and benefits (economies of scale). Likewise, systems would incur

costs for procuring a new source of water that may result in lower overall treatment costs.

In addition, the Agency was unable to predict the usage or estimate the costs of several toolbox options. These options include intake management and demonstrations of performance. They have not been included in the quantified analysis because data are not available to estimate the number of systems that may use these toolbox options to comply with the LT2ESWTR. Not including these generally low-cost options may result in overestimation of costs.

E. What Are the Household Costs of the Proposed Rule?

Another way to assess a rule's impact is to consider how it might impact residential water bills. This analysis considers the potential increase in a household's water bill if a CWS passed the entire cost increase resulting from this rule on to its customers. It is a tool to gauge potential impacts and should not be construed as precise estimates of potential changes to individual water bills.

Included in this analysis are all CWS costs, including rule implementation, initial and future monitoring for bin classification, additional *Cryptosporidium* treatment, and treating or covering uncovered finished water

storage facilities. Costs for small systems *Cryptosporidium* monitoring, additional *Cryptosporidium* treatment, and uncovered finished water storage facilities are assigned only to the subset of systems expected to incur them. Although implementation and monitoring represent relatively small, one-time costs, they have been included in the analysis to provide a complete distribution of the potential household cost. A detailed description of the derivation of household costs is in section 6.10 and Appendix J of the LT2ESTWR EA (USEPA 2003a).

For purchased systems that are linked to larger nonpurchased systems, the households costs are calculated based on the unit costs of the larger system but included in the distribution from the size category of the purchased system. Households costs for these purchased systems are based on the household usage rates appropriate for the retail system and not the system selling the water. This approach for the purchased systems reflects the fact that although they will not face increased costs from adding their own treatment, whatever costs the wholesale utility incurs would likely be passed on as higher water costs.

Table VI-15 shows the results of the household cost analysis. In addition to mean and median estimates, the Agency calculated the 90th and 95th percentile.

EPA estimates that all households served by surface and GWUDI sources will face some increase in household costs due to implementation of the LT2ESWTR (except for those few served by systems that have already installed 5.5 logs of treatment for *Cryptosporidium*). Of all the households subject to the rule, from 24 to 35 percent are projected to incur costs for adding treatment, depending on the *Cryptosporidium* occurrence data set used.

Approximately 95 percent of the households potentially subject to the rule are served by systems serving at least 10,000 people; these systems experience the lowest increases in costs due to significant economies of scale. Over 90 percent of all households will face an annual cost increase of less than \$5. Households served by small systems that install advanced technologies will face the greatest increases in annual costs. EPA expects that the model's projections for these systems are, in some cases, overstated. Some systems are likely to find alternative treatment techniques such as other toolbox options not included in this analysis, or sources of water (ground water, purchased water, or consolidating with another system) that would be less costly than installing more expensive treatment techniques.

TABLE VI-15.—POTENTIAL ANNUAL HOUSEHOLD COSTS IMPACTS FOR THE PREFERRED REGULATORY OPTION (2000\$)

System: type/size	Households	Mean	Median	90th Percentile	95th Percentile	Percent of systems with household cost increase < \$12	Percent of systems with household cost increase < \$120
All Systems—ICR							
All CWS	65,816,979	\$1.68	\$0.13	\$4.06	\$7.57	98.37	99.99
CWS ≤ 10,000	3,318,012	4.61	1.34	13.04	14.92	87.88	99.88
All Systems—ICRSSL							
All CWS	65,816,979	\$1.07	\$0.03	\$3.24	\$5.43	98.31	100.00
CWS ≤ 10,000	3,318,012	2.68	0.80	6.10	9.39	95.71	99.95
All Systems—ICRSSM							
All CWS	65,816,979	\$1.28	\$0.03	\$3.48	\$6.47	99.07	100.00
CWS ≤ 10,000	3,318,012	3.27	0.80	6.62	13.04	93.90	99.93

Source: Chapter 6 of the LT2ESWTR Economic Analysis (USEPA 2003a).

F. What Are the Incremental Costs and Benefits of the Proposed LT2ESWTR?

Incremental costs and benefits are those that are incurred or realized in reducing *Cryptosporidium* exposures from one alternative to the next. Estimates of incremental costs and benefits are useful in considering the economic efficiency of different

regulatory options considered by the Agency. Generally, the goal of an incremental analysis is to identify the regulatory option where incremental benefits most closely equal incremental costs. However, the usefulness of this analysis is limited because many benefits from this rule are unquantified and not monetized. Incremental

analyses should consider both quantified and non-quantified (where possible) benefits and costs.

Usually an incremental analysis implies increasing levels of stringency along a single parameter, with each alternative providing all the protection of the previous alternative, plus additional protection. However, the

regulatory alternatives in this rule vary by multiple parameters (e.g. risk bin boundaries, treatment requirements). The comparison between any two alternatives is, therefore, between two separate sets of benefits, in the sense that they may be distributed to somewhat different population groups.

The regulatory alternatives, however, do achieve increasing levels of benefits at increasing levels of costs. As a result, it is possible to display incremental net

benefits from the baseline and alternative to alternative. Tables VI-16a and VI-16b show incremental costs, benefits, and net benefits for the four regulatory alternatives shown in Table VI-1, using the enhanced and traditional COI, respectively. All values are annualized present values expressed in Year 2000 dollars. The displayed values are the mean estimates for the different occurrence distributions.

With the enhanced COI, incremental costs are generally closest to incremental benefits for A2, a more stringent alternative than the Preferred Alternative, A3. For the traditional COI, incremental costs most closely equal incremental benefits for A3, the Preferred Alternative, under the majority of conditions evaluated.

BILLING CODE 6560-50-P

Table VI-16a.- Incremental Net Benefits by Rule Alternative—Enhanced COI
(Annualized Present Value, \$millions, 2000\$)

Data Set	Rule Alternative	Annual Costs	Annual Benefits	Incremental Costs[1]	Incremental Benefits	Incremental Net Benefits
		A	B	C	D	E=D-C
3 Percent Discount Rate						
ICR	A4	\$ 58	\$ 1,349	\$ 58	\$ 1,349	\$ 1,290
	A3 - Preferred	\$ 111	\$ 1,445	\$ 52	\$ 96	\$ 44
	A2	\$ 134	\$ 1,461	\$ 23	\$ 16	\$ -8
	A1	\$ 361	\$ 1,482	\$ 227	\$ 21	\$ -206
ICRSSL	A4	\$ 37	\$ 328	\$ 37	\$ 328	\$ 291
	A3 - Preferred	\$ 73	\$ 374	\$ 37	\$ 46	\$ 9
	A2	\$ 100	\$ 397	\$ 26	\$ 24	\$ -2
	A1	\$ 361	\$ 457	\$ 261	\$ 59	\$ -202
ICRSSM	A4	\$ 44	\$ 635	\$ 44	\$ 635	\$ 592
	A3 - Preferred	\$ 86	\$ 715	\$ 42	\$ 80	\$ 38
	A2	\$ 113	\$ 742	\$ 26	\$ 27	\$ 1
	A1	\$ 361	\$ 796	\$ 248	\$ 53	\$ -195
7 Percent Discount Rate						
ICR	A4	\$ 65	\$ 1,148	\$ 65	\$ 1,148	\$ 1,083
	A3 - Preferred	\$ 121	\$ 1,230	\$ 56	\$ 82	\$ 26
	A2	\$ 145	\$ 1,243	\$ 25	\$ 13	\$ -11
	A1	\$ 388	\$ 1,260	\$ 242	\$ 18	\$ -225
ICRSSL	A4	\$ 41	\$ 279	\$ 41	\$ 279	\$ 238
	A3 - Preferred	\$ 81	\$ 318	\$ 40	\$ 39	\$ -1
	A2	\$ 108	\$ 338	\$ 27	\$ 20	\$ -7
	A1	\$ 388	\$ 389	\$ 279	\$ 50	\$ -229
ICRSSM	A4	\$ 48	\$ 541	\$ 48	\$ 541	\$ 493
	A3 - Preferred	\$ 94	\$ 609	\$ 47	\$ 68	\$ 21
	A2	\$ 122	\$ 632	\$ 28	\$ 23	\$ -5
	A1	\$ 388	\$ 677	\$ 265	\$ 45	\$ -220

Table VI-16b.— Incremental Net Benefits by Rule Alternative—Traditional COI
(Annualized Present Value, \$millions, 2000\$)

Data Set	Rule Alternative	Annual Costs	Annual Benefits	Incremental Costs[1]	Incremental Benefits	Incremental Net Benefits
		A	B	C	D	E=D-C
3 Percent Discount Rate						
ICR	A4	\$ 58	\$ 907	\$ 58	\$ 907	\$ 848
	A3 - Preferred	\$ 111	\$ 967	\$ 52	\$ 60	\$ 8
	A2	\$ 134	\$ 977	\$ 23	\$ 10	\$ -14
	A1	\$ 361	\$ 989	\$ 227	\$ 13	\$ -214
ICRSSL	A4	\$ 37	\$ 225	\$ 37	\$ 225	\$ 188
	A3 - Preferred	\$ 73	\$ 253	\$ 37	\$ 29	\$ -8
	A2	\$ 100	\$ 268	\$ 26	\$ 15	\$ -11
	A1	\$ 361	\$ 305	\$ 261	\$ 37	\$ -225
ICRSSM	A4	\$ 44	\$ 432	\$ 44	\$ 432	\$ 388
	A3 - Preferred	\$ 86	\$ 481	\$ 42	\$ 50	\$ 7
	A2	\$ 113	\$ 498	\$ 26	\$ 17	\$ -10
	A1	\$ 361	\$ 531	\$ 248	\$ 33	\$ -215
7 Percent Discount Rate						
ICR	A4	\$ 65	\$ 775	\$ 65	\$ 775	\$ 710
	A3 - Preferred	\$ 121	\$ 826	\$ 56	\$ 51	\$ -5
	A2	\$ 145	\$ 834	\$ 25	\$ 8	\$ -16
	A1	\$ 388	\$ 845	\$ 242	\$ 11	\$ -231
ICRSSL	A4	\$ 41	\$ 192	\$ 41	\$ 192	\$ 151
	A3 - Preferred	\$ 81	\$ 216	\$ 40	\$ 24	\$ -16
	A2	\$ 108	\$ 229	\$ 27	\$ 12	\$ -15
	A1	\$ 388	\$ 260	\$ 279	\$ 31	\$ -248
ICRSSM	A4	\$ 48	\$ 369	\$ 48	\$ 369	\$ 321
	A3 - Preferred	\$ 94	\$ 411	\$ 47	\$ 42	\$ -4
	A2	\$ 122	\$ 425	\$ 28	\$ 14	\$ -14
	A1	\$ 388	\$ 454	\$ 265	\$ 28	\$ -237

¹The traditional COI only includes valuation for medical costs and lost work time (including some portion of unpaid household production). The enhanced COI also factors in valuations for lost personal time (non-worktime) such as child care and homemaking (to the extent not covered by the traditional COI), time with family, and recreation, and lost productivity at work on days when workers are ill but go to work anyway. Source: Chapter 8 of the *LT2ESWTR Economic Analysis* (USEPA 2003a)

BILLING CODE 6560-50-C

G. Are There Benefits From the Reduction of Co-Occurring Contaminants?

This section presents information on the unquantified benefits that will accrue from removal of other contaminants, primarily pathogens, due to improved control of *Cryptosporidium*. While the benefits analysis for the LT2ESWTR only includes reductions in illness and mortality attributable to

Cryptosporidium, the LT2ESWTR is expected to reduce exposure to other parasitic protozoans that EPA regulates, or is considering for future regulation. For example, it is expected that the LT2ESWTR will improve control of *Giardia lamblia*, *Cyclospora* sp. and members of the Microsporididae class, seven genera (10 species) of which have been recovered in humans (Mota *et al.*, 2000). In addition, greater *Cryptosporidium* control may improve control of the pathogenic bacteria and

viruses. Chemical contaminants such as arsenic, DBPs and atrazine may also be controlled, in part, by control of *Cryptosporidium*, depending on the technologies selected.

Giardia lamblia and *Cyclospora* sp. are larger than *Cryptosporidium*, while Microsporididae, bacteria, and the viruses are smaller than *Cryptosporidium*. The expected removal of co-occurring microorganisms can often be predicted for those treatment unit processes whose removal efficiency

depends in part, or entirely, on the size of the organism. For example, a study by Goodrich and Lykins (1995) evaluating bag filters showed that any microbe or object greater than 4.5 microns in size (the average size of *Cryptosporidium*) would be subject to removal ranging from 0.5 to 2.0 logs.

Although not directly dependent on organism size, other treatment technologies identified in the LT2ESWTR should also provide additional control of co-occurring microbial pathogens. Membrane processes that remove *Cryptosporidium* are shown to achieve equivalent log removal of *Giardia* under worst-case and normal operating conditions (USEPA 2003c). Reduction in individual filter turbidities will reduce concentrations of other pathogens as well as *Cryptosporidium*. For example, in Dutch surface water, *Giardia* and *Cryptosporidium* occurrence appeared to correlate well with each other and for the Rhine River, with turbidity (Medema *et al.* 2001). Thus, improved control of *Cryptosporidium* should also result in improved control of *Giardia lamblia*.

Some membrane technologies that might be installed to comply with the LT2ESWTR can also reduce or eliminate chemical contaminants including arsenic, DBPs and atrazine. EPA has recently finalized a rule to further control arsenic levels in drinking water and is concurrently proposing the Stage 2 DBPR to address DBP control.

The extent to which the LT2ESWTR can reduce the overall risk from other contaminants has not been quantitatively evaluated because of the Agency's lack of data regarding the co-occurrence among *Cryptosporidium* and other microbial pathogens and contaminants. Because of the difficulties in establishing which systems would have multiple problems, such as microbial contamination, arsenic, and DBPs or any combination of the three, no estimate was made of the potential cost savings from addressing more than one contaminant simultaneously.

H. Are There Increased Risks From Other Contaminants?

It is unlikely that the LT2ESWTR will result in a significant increase in risk from other contaminants. Many of the options that systems will select to comply with the LT2ESWTR, such as UV, improved filtration performance, and watershed control, do not form DBPs. Other technologies that are effective against *Cryptosporidium*, such as ozone and chlorine dioxide, do form DBPs. However, these DBPs are currently regulated under the Stage 1

DBPR, and systems will have to comply with these regulations when implementing technologies to meet the LT2ESWTR.

I. What Are The Effects of the Contaminant on the General Population and Groups Within the General Populations That Are Identified as Likely To Be at Greater Risk of Adverse Health Effects?

Section II of this preamble discusses the health effects associated with *Cryptosporidium* on the general population as well as the effects on other sensitive sub-populations. In addition, health effects associated with children and pregnant women are discussed in greater detail in section VII.G of this preamble.

J. What Are the Uncertainties in the Baseline, Risk, Benefit, and Cost Estimates for the Proposed LT2ESWTR as Well as the Quality and Extent of the Information?

Today's proposal models the current baseline risk from *Cryptosporidium* exposure, as well as the reduction in risk and the cost for various rule options. There is uncertainty in the risk calculation, the benefit estimate, the cost estimates, and the interaction of other upcoming rules. Section IV of the proposed rule considers the uncertainty with the risk estimates; however, a brief summary of the major risk uncertainties as they relate to benefit estimation is provided next. In addition, the LT2ESWTR EA has a more extensive discussion of all of the uncertainties (USEPA 2003a).

In addition, the Agency conducted sensitivity analyses to address uncertainty. The sensitivity analyses focus on various occurrence, benefit and cost factors that may have a significant effect on the estimated impacts of the rule. All of these sensitivity analyses are explained in more detail in the EA for the LT2ESWTR (USEPA 2003a).

One area of uncertainty is associated with the estimate of *Cryptosporidium* occurrence on a national basis. The Information Collection Rule plant-mean data were higher than the ICRSS medium or large system plant-mean data at the 90th percentile. The reasons for these differing results are not well understood but may stem from differences in the populations sampled, year-to-year variation in occurrence, and systematic differences in the sampling and measurement methods employed. These data suggest that *Cryptosporidium* levels are relatively low in most water sources, but there is a subset of sources with significantly higher concentrations. Additional

uncertainty is associated with estimating finished water occurrence because the analysis is based on assumptions about treatment plant performance. To account for these uncertainties, the Agency used Monte Carlo simulation models that allow substantial variation in each estimate and computed finished water occurrence values based on statistical sampling of the variable estimates.

The risk associated with finished water occurrence is of lesser uncertainty than is typical for many contaminants because the health effects are measured based on *Cryptosporidium* challenge studies to human volunteer populations. Nevertheless, there is significant uncertainty about the dose-response associated with *Cryptosporidium* because there exists considerable differences in infectivity among the various tested *Cryptosporidium parvum* isolates. As described in section III.B, the Agency accounted for these differences using Monte Carlo simulations that randomly sampled from infectivity distributions for the three tested isolates. The different simulations were designed to account for the limited number of challenge studies and the variability in the infectivity of the isolates themselves. In addition, because the *Cryptosporidium* dosing levels in the human feeding studies were above typical drinking water exposure levels (e.g., one oocyst), there remains significant uncertainty that could not be quantified into the analysis.

While all of the significant costs of today's proposed rule have been identified by EPA, there are uncertainties about some of the estimates. However, the Agency explored the impact of the uncertainties that might have the greatest impact by conducting sensitivity analyses and using Monte Carlo techniques. For example, section VI.D.2.f of today's rule explores the impact of influent bromide levels on technology selection. As shown in the EA for this rule, the impact of higher influent bromide levels will not have a significant impact on the rule's costs. In addition, subsection 6.12 of the EA summarizes other cost uncertainties including the Agency's inability to include some lower cost toolbox options in the cost analysis (USEPA 2003a).

Last, EPA has recently finalized new regulations for arsenic, radon, *Cryptosporidium* in small surface water systems, and filter backwash in all system sizes (LT1ESWTR and Filter Backwash Rule); proposed a rule for microbials in ground water systems (Ground Water Rule); and is

concurrently proposing additional control of disinfection byproducts (Stage 2 Disinfection Byproducts Rule). These rules may have overlapping impacts on some drinking water systems but the extent is not possible to estimate because of lack of information on co-occurrence. However, it is possible for a system to choose treatment technologies that would address multiple contaminants. Therefore, while the total cost impact of these drinking water rules is uncertain, it is most likely less than the estimated total cost of all individual rules combined.

K. What is the Benefit/Cost Determination for the Proposed LT2ESWTR?

The Agency has determined that the benefits of the proposed LT2ESWTR justify the costs. As discussed in section VI.C, the proposed rule provides a large reduction in endemic cryptosporidiosis illness and mortalities. More stringent alternatives provide greater reductions but at higher costs. Alternative A1 provides the greatest overall reduction in illnesses and mortalities but the incremental benefits between this

option and the preferred option are relatively small while the incremental costs are significant. In addition, the preferred regulatory option, unlike option A1, specifically targets those systems whose source water requires higher levels of treatment.

Tables VI-17a and VI-17b present net benefits for the four regulatory alternatives that were evaluated. Generally, analysis of net benefits is used to identify alternatives where benefits exceed costs, as well as the alternative that maximizes net benefits. However, as with the analysis of incremental net benefits discussed previously, the usefulness of this analysis in evaluating regulatory alternatives for the LT2ESWTR is limited because many benefits from this rule are un-quantified and non-monetized. Analyses of net benefits should consider both quantified and non-quantified (where possible) benefits and costs.

Also, as noted earlier, the regulatory alternatives considered for the LT2ESWTR vary both in the population that experiences benefits and costs (*i.e.*,

risk bin boundaries) and the magnitude of the benefits and costs (*i.e.*, treatment requirements). Consequently, the more stringent regulatory alternatives provide benefits to population groups that do not experience any benefit under less stringent alternatives.

As shown by Tables VI-17a and VI-17b, net benefits are positive for all four regulatory alternatives evaluated. With the enhanced COI (Table VI-17a), net benefits are highest for the Preferred Alternative, A3, under the majority of occurrence distributions and discount rates evaluated. When the traditional COI (Table VI-17b) is used, the Preferred Alternative has the highest net benefits at a three percent discount rate for the two of the occurrence distributions, the Information Collection Rule and ICRSSM, while the least stringent alternative, A4, is highest for the ICRSSL. At a seven percent discount rate, A4 maximizes net benefits under all occurrence distributions.

Table VI-17a.— Mean Net Benefits by Rule Option—Enhanced COI (\$millions, 2000\$)

Data Set	Rule Alternative	Annualized Value	
		3%, 25 Years	7%, 25 Years
ICR	A1	\$ 1,121	\$ 873
	A2	\$ 1,327	\$ 1,098
	A3 - Preferred	\$ 1,335	\$ 1,109
	A4	\$ 1,290	\$ 1,083
ICRSSL	A1	\$ 96	\$ 1
	A2	\$ 298	\$ 230
	A3 - Preferred	\$ 300	\$ 237
	A4	\$ 291	\$ 238
ICRSSM	A1	\$ 435	\$ 289
	A2	\$ 630	\$ 509
	A3 - Preferred	\$ 629	\$ 514
	A4	\$ 592	\$ 493

Table VI-17b.-- Mean Net Benefits by Rule Option—Traditional COI (\$millions, 2000\$)

Data Set	Rule Alternative	Annualized Value	
		3%, 25 Years	7%, 25 Years
ICR	A1	\$ 628	\$ 457
	A2	\$ 843	\$ 688
	A3 - Preferred	\$ 856	\$ 705
	A4	\$ 848	\$ 710
ICRSSL	A1	\$ -56	\$ -128
	A2	\$ 168	\$ 120
	A3 - Preferred	\$ 180	\$ 135
	A4	\$ 188	\$ 151
ICRSSM	A1	\$ 170	\$ 66
	A2	\$ 386	\$ 303
	A3 - Preferred	\$ 395	\$ 317
	A4	\$ 388	\$ 321

¹The traditional COI only includes valuation for medical costs and lost work time (including some portion of unpaid household production). The enhanced COI also factors in valuations for lost personal time (non-worktime) such as child care and homemaking (to the extent not covered by the traditional COI), time with family, and recreation, and lost productivity at work on days when workers are ill but go to work anyway. Source: Chapter 8 of the *LT2ESWTR Economic Analysis* (USEPA 2003a)

BILLING CODE 6560-50-C

In addition to the net benefits of the proposed LT2ESWTR, the Agency used several other techniques to compare

costs and benefits. For example, EPA calculated the cost of the rule per case avoided. Table VI-18 shows both the cost of the rule per illness avoided and

cost of the rule per death avoided. This cost effectiveness measure is another way of examining the benefits and costs of the rule but should not be used to

compare alternatives because an alternative with the lowest cost per illness/death avoided may not result in the highest net benefits. With the exception of alternative A1, the rule options look favorable from a cost

effectiveness analysis when you compare them to both the average cost of cryptosporidiosis illness (\$745 and \$245 for the two COI approaches) and the mean value of a death avoided—approximately \$7 million dollars.

Additional information about this analysis and other methods of comparing benefits and costs can be found in chapter 8 to the LT2ESWTR EA (USEPA 2003a).

TABLE VI-18.—COST PER ILLNESS OR DEATH AVOIDED

Data set	Rule alternative	Cost per illness avoided (\$)		Cost per death avoided (\$ millions, 2000\$)	
		3%	7%	3%	7%
ICR	A1	339	244	2.5	1.8
	A2	128	93	0.9	0.7
	A3—Preferred	107	78	0.8	0.6
	A4	62	45	0.4	0.3
ICRSSL	A1	1,098	789	8.0	5.7
	A2	356	259	2.5	1.8
	A3—Preferred	282	208	1.9	1.4
	A4	165	122	1.1	0.8
ICRSSM	A1	631	453	4.6	3.3
	A2	213	155	1.6	1.1
	A3—Preferred	170	125	1.2	0.9
	A4	99	73	0.7	0.5

Source: Chapter 8 of the LT2ESWTR Economic Analysis (USEPA 2003a)

L. Request for Comment

The Agency requests comment on all aspects of the proposed rule’s economic impact analysis. Specifically, EPA seeks input into the following issues:

- Both of the methodologies for valuing non-fatal cryptosporidiosis and the use of a real income growth factor to adjust these estimates for the years 2008 through 2027;
- How can the Agency fully incorporate all toolbox options into the economic analysis?
- How can the Agency estimate the potential benefits from reduced epidemic outbreaks of cryptosporidiosis?

VII. Statutory and Executive Order Reviews

A. Executive Order 12866: Regulatory Planning and Review

Under Executive Order 12866, (58 FR 51735, October 4, 1993) the Agency must determine whether the regulatory action is “significant” and therefore subject to OMB review and the requirements of the Executive Order. The Order defines “significant regulatory action” as one that is likely to result in a rule that may:

- (1) Have an annual effect on the economy of \$100 million or more or adversely affect in a material way the economy, a sector of the economy, productivity, competition, jobs, the environment, public health or safety, or

State, local, or Tribal governments or communities;

- (2) Create a serious inconsistency or otherwise interfere with an action taken or planned by another agency;
- (3) Materially alter the budgetary impact of entitlements, grants, user fees, or loan programs or the rights and obligations of recipients thereof; or
- (4) Raise novel legal or policy issues arising out of legal mandates, the President’s priorities, or the principles set forth in the Executive Order.

Pursuant to the terms of Executive Order 12866, it has been determined that this rule is a “significant regulatory action.” As such, this action was submitted to OMB for review. Changes made in response to OMB suggestions or recommendations will be documented in the public record.

B. Paperwork Reduction Act

The information collection requirements in this proposed rule have been submitted for approval to the Office of Management and Budget (OMB) under the *Paperwork Reduction Act*, 44 U.S.C. 3501 *et seq.* The Information Collection Request (ICR) document prepared by EPA has been assigned EPA ICR number 2097.01.

The information collected as a result of this rule will allow the States and EPA to determine appropriate requirements for specific systems, and to evaluate compliance with the rule. For the first 3 years after LT2ESWTR promulgation, the major information

requirements concern monitoring activities and compliance tracking. The information collection requirements are mandatory (part 141), and the information collected is not confidential.

The estimate of annual average burden hours for the LT2ESWTR during the first three years following promulgation is 145,854 hours. The annual average cost estimate is \$3.9 million for labor and \$9.8 million per year for operation and maintenance including lab costs (which is a purchase of service). The burden hours per response is 1.47 hours and the cost per response is \$138.12. The frequency of response (average responses per respondent) is 39, annually. The estimated number of likely respondents is 2,560 (the product of burden hours per response, frequency, and respondents does not total the annual average burden hours due to rounding). Note that the burden hour estimates for the first 3-year cycle include large system but not small system monitoring. Conversely, burden estimate for the second 3-year cycle will include small system monitoring but not large system, which will have been completed by then.

Burden means the total time, effort, or financial resources expended by persons to generate, maintain, retain, or disclose or provide information to or for a Federal agency. This includes the time needed to review instructions; develop, acquire, install, and utilize technology

and systems for the purposes of collecting, validating, and verifying information, processing and maintaining information, and disclosing and providing information; adjust the existing ways to comply with any previously applicable instructions and requirements; train personnel to be able to respond to a collection of information; search data sources; complete and review the collection of information; and transmit or otherwise disclose the information.

An agency may not conduct or sponsor, and a person is not required to respond to a collection of information unless it displays a currently valid OMB control number. The OMB control numbers for EPA's regulations in 40 CFR are listed in 40 CFR part 9.

To comment on the Agency's need for this information, the accuracy of the provided burden estimates, and any suggested methods for minimizing respondent burden, including the use of automated collection techniques, EPA has established a public docket for this rule, which includes this ICR, under Docket ID No. OW-2002-0039. Submit any comments related to the ICR for this proposed rule to EPA and OMB. See **ADDRESSES** section at the beginning of this notice for where to submit comments to EPA. Send comments to OMB at the Office of Information and Regulatory Affairs, Office of Management and Budget, 725 17th Street, NW., Washington, DC 20503,

Attention: Desk Office for EPA. Since OMB is required to make a decision concerning the ICR between 30 and 60 days after August 11, 2003, a comment to OMB is best assured of having its full effect if OMB receives it by September 10, 2003. The final rule will respond to any OMB or public comments on the information collection requirements contained in this proposal.

C. Regulatory Flexibility Act

The Regulatory Flexibility Act (RFA) generally requires an agency to prepare a regulatory flexibility analysis for any rule subject to notice and comment rulemaking requirements under the Administrative Procedure Act or other statute unless the agency certifies that the rule will not have a significant economic impact on a substantial number of small entities. Small entities include small businesses, small organizations, and small governmental jurisdictions.

The RFA provides default definitions for each type of small entity. It also authorizes an agency to use alternative definitions for each category of small entity, "which are appropriate to the activities of the agency" after proposing the alternative definition(s) in the **Federal Register** and taking comment. 5 U.S.C. secs. 601(3)-(5). In addition to the above, to establish an alternative small business definition, agencies must consult with SBA's Chief Council for Advocacy.

For purposes of assessing the impacts of today's proposed rule on small entities, EPA considered small entities to be public water systems serving 10,000 or fewer persons. This is the cut-off level specified by Congress in the 1996 Amendments to the Safe Drinking Water Act for small system flexibility provisions. In accordance with the RFA requirements, EPA proposed using this alternative definition in the **Federal Register**, (63 FR 7620, February 13, 1998), requested public comment, consulted with the Small Business Administration (SBA), and expressed its intention to use the alternative definition for all future drinking water regulations in the Consumer Confidence Reports regulation (63 FR 44511, August 19, 1998). As stated in that final rule, the alternative definition is applied to this proposed regulation.

After considering the economic impacts of today's proposed rule on small entities, I certify that this action will not have a significant economic impact on a substantial number of small entities. We have determined that 274 small systems, which are 2.32% of the 11,820 small systems regulated by the LT2ESWTR, will experience an impact of one percent or greater of average annual revenues; further, 31 systems, which are 0.26% of the systems regulated by this rule, will experience an impact of three percent or greater of average annual revenues (see Table VII-1).

TABLE VII-1.—ANNUALIZED COMPLIANCE COST AS A PERCENTAGE OF REVENUES FOR SMALL ENTITIES (\$2000)

Entity by system size	Number of small systems (Percent)	Average annual estimated revenues per system (\$)	Systems experiencing costs of >% their revenues		Systems experiencing costs of >% of their revenues	
			Percent of system	Number of systems	Percent of systems	Number of systems
			E	F=A*E	G	H=A*G
Small Governments	5,910 50	2,434,200	2.4	140	0.3	15
Small Businesses	4,846 41	2,391,978	2.4	115	0.3	13
Small Organizations	1,064 9	4,446,165	1.2	13	0.1	1
All Small Entities	11,820 100	2,597,966	2.3	274	0.3	31

Note: Detail may not add due to independent rounding. Data are based on the means of the highest modeled distributions using Information Collection Rule occurrence data set. Costs are discounted at 3 percent, summed to present value, and annualized over 25 years. Source: Chapter 7 of the LT2ESWTR EA (USEPA 2003a).

The LT2ESWTR contains provisions that will affect systems serving fewer than 10,000 people that use surface water or GWUDI as a source. In order to meet the LT2ESWTR requirements, approximately 1,382 to 2,127 small systems would need to make capital improvements. Impacts on small entities

are described in more detail in Chapters 6 and 7 of the Economic Analysis for the LT2ESWTR (USEPA 2003a). Table VII-2 shows the annual compliance costs of the LT2ESWTR on the small entities by system size and type based on a three percent discount rate (other estimates based on different data sets and

discount rates produce lower costs). EPA has determined that in each size category, fewer than 20% of systems and fewer than 1000 systems will experience an impact of one percent or greater of average annual revenues (USEPA 2003a).

TABLE VII-2.—ANNUAL COMPLIANCE COSTS FOR THE PROPOSED LT2ESWTR BY SYSTEM SIZE AND TYPE
[\$Millions, 2000\$]

System type	System size (population served)					Total
	<100	101–500	501–1,000	1,001–3,300	3,301–10,000	
Public owned	\$0.46	\$0.88	\$0.94	\$2.62	\$5.57	\$10.37
Privately owned	1.00	0.71	0.22	0.31	0.36	2.60
All systems	1.45	1.59	1.07	2.92	5.93	12.97

Note: Results are based on the mean of the Information Collection Rule *Cryptosporidium* occurrence distribution. Costs are annualized at a three percent discount rate.
Source: Appendix D and Q of the LT2ESWTR EA (USEPA 2003a).

Although this proposed rule will not have a significant economic impact on a substantial number of small entities, EPA nonetheless has tried to reduce the impact of this rule on small entities. The LT2ESWTR contains a number of provisions to minimize the impact of the rule on systems generally, and on small systems in particular. The risk-targeted approach of the LT2ESWTR will impose additional treatment requirements only on the subset of systems with the highest vulnerability to *Cryptosporidium*, as indicated by source water pathogen levels. This approach will spare the majority of systems from the cost of installing additional treatment. Also, development of the microbial toolbox under the LT2ESWTR will provide both large and small systems with broad flexibility in selecting cost-effective compliance options to meet additional treatment requirements.

Small systems will monitor for *E. coli* as a screening analysis for source waters with low levels of fecal contamination. *Cryptosporidium* monitoring will only be required of small systems if they exceed the *E. coli* trigger value. Because *E. coli* analysis is much cheaper than *Cryptosporidium* analysis, the use of *E. coli* as a screen will significantly reduce monitoring costs for the majority of small systems. In order to allow EPA to review *Cryptosporidium* indicator relationships in large system monitoring data, small systems will not be required to initiate their monitoring until large system monitoring has been completed. This will provide small systems with additional time to become familiar with the rule and to prepare for monitoring and other compliance activities.

Funding would be available from programs administered by EPA and other Federal agencies to assist small public water systems (PWSs) in complying with the LT2ESWTR. The Drinking Water State Revolving Fund (DWSRF) assists PWSs with financing the costs of infrastructure needed to achieve or maintain compliance with

SDWA requirements. Through the DWSRF, EPA awards capitalization grants to States, which in turn can provide low-cost loans and other types of assistance to eligible PWSs. Loans made under the program can have interest rates between 0 percent and market rate and repayment terms of up to 20 years. States prioritize funding based on projects that address the most serious risks to human health and assist systems most in need. Congress provided \$1.275 billion for the DWSRF program in fiscal year 1997, and has provided an additional \$3.145 billion for the DWSRF program for fiscal years 1998 through 2001.

The DWSRF places an emphasis on small and disadvantaged communities. States must provide a minimum of 15% of the available funds for loans to small communities. A State has the option of providing up to 30% of the grant awarded to the State to furnish additional assistance to State-defined disadvantaged communities. This assistance can take the form of lower interest rates, principal forgiveness, or negative interest rate loans. The State may also extend repayment terms of loans for disadvantaged communities to up to 30 years. A State can set aside up to 2% of the grant to provide technical assistance to systems serving communities with populations fewer than 10,000.

In addition to the DWSRF, money is available from the Department of Agriculture's Rural Utility Service (RUS) and Housing and Urban Development's Community Development Block Grant (CDBG) program. RUS provides loans, guaranteed loans, and grants to improve, repair, or construct water supply and distribution systems in rural areas and towns of up to 10,000 people. In fiscal year 2002, RUS had over \$1.5 billion of available funds for water and environmental programs. The CDBG program includes direct grants to States, which in turn are awarded to smaller communities, rural areas, and colon as

in Arizona, California, New Mexico, and Texas and direct grants to U.S. territories and trusts. The CDBG budget for fiscal year 2002 totaled over \$4.3 billion.

Although not required by the RFA to convene a Small Business Advocacy Review (SBAR) Panel because EPA determined that this proposal would not have a significant economic impact on a substantial number of small entities, EPA did convene a panel to obtain advice and recommendations from representatives of the small entities potentially subject to this rule's requirements.

Before convening the SBAR Panel, EPA consulted with a group of 24 small entity stakeholders likely to be impacted by the LT2ESWTR and who were asked to serve as Small Entity Representatives (SERs) after the Panel was convened. The small entity stakeholders included small system operators, local government representatives, and representatives of small nonprofit organizations. The small entity stakeholders were provided with background information on SDWA and potential alternatives for the LT2ESWTR in preparation for teleconferences on January 28, 2000, February 25, 2000, and April 7, 2000. This information package included data on preliminary unit costs for treatment enhancements under consideration.

During these three conference calls, the information that had been provided to the small entity stakeholders was discussed and EPA responded to questions and recorded initial comments. Following the three calls, the small entity stakeholders were asked to provide input on the potential impacts of the rule from their perspective. Seven small entity stakeholders provided written comments on these materials.

The SBAR Panel convened on April 25, 2000. The small entity stakeholders comments were provided to the SBAR Panel when it convened. After a teleconference between the SERs and the SBAR Panel on May 25, 2000, the SERs were invited to provide additional

comments on the information provided. Seven SERs provided additional comments on the rule components.

The SBAR Panel's report, Final Report of the Small Business Advocacy Review Panel on Stage 2 Disinfectants and Disinfection Byproducts Rule (Stage 2 DBPR) and Long Term 2 Enhanced Surface Water Treatment Rule (LT2ESWTR) (USEPA 2000f), the SERs comments on the LT2ESWTR, and the background information provided to the SBAR Panel and the SERs are available for review in the docket for today's proposal (<http://www.epa.gov.edocket/>).

In general, the SERs who were consulted on the LT2ESWTR were concerned about the impact of these proposed rules on small water systems, the ability of small systems to acquire the technical and financial capability to implement requirements while maintaining flexibility to tailor the requirements to their needs, and the limitations of small systems. The SBAR Panel evaluated information and small-entity comments on issues related to the impact of the LT2ESWTR.

The LT2ESWTR takes into consideration the recordkeeping and reporting concerns identified by the SBAR Panel and the SERs. The SBAR Panel recommended that EPA evaluate ways to minimize the recordkeeping and reporting burdens under the rule by ensuring that the States have appropriate capacity for rule implementation, and that EPA provide as much monitoring flexibility as possible to small systems. EPA believes that the continuity with the IESWTR and LT1ESWTR was maintained to the extent possible to ease the transition to the LT2ESWTR, especially for small systems. The LT2ESWTR builds on the protection afforded under the IESWTR and LT1ESWTR, while minimizing the impact on small systems by using a risk-targeted approach (*i.e.*, source water monitoring) to identify systems that are still at risk from *Cryptosporidium* exposure.

The SBAR Panel noted the concern of several SERs that flexibility be provided in the compliance schedule of the rule. SERs commented on the technical and financial limitations of some small systems, the significant learning curve for operators with limited experience, and the need to continue providing uninterrupted service as reasons why additional compliance time may be needed for small systems. The SBAR Panel encouraged EPA to keep these limitations in mind in developing the proposed rule and provide as much compliance flexibility to small systems as is allowable under SDWA.

EPA has concluded that the proposed schedule for the LT2ESWTR provides sufficient time for small systems to achieve compliance. The schedule for small system monitoring and compliance with additional treatment requirements lags behind the schedule for large systems. The basis for the lagging schedule for small systems is that it allows EPA to confirm or refine the *E. coli* screening criteria that small systems will use to reduce monitoring costs. However, the lagging schedule also provides greater time for small systems to become knowledgeable about the LT2ESWTR, including the new monitoring requirements, and to become familiar with innovative technologies, like UV, that may be used by some small systems to meet additional treatment requirements.

Some SERs emphasized that EPA needs to maintain an appropriate balance between control of known microbial risks through adequate disinfection and for the more uncertain risks that may be associated with DBPs. The SBAR Panel did not foresee any potential conflict between rules regulating control of microbial contaminants and those regulating DBPs. EPA also believes that today's proposal and the accompanying proposed Stage 2 DBPR achieve an appropriate balance between microbial and DBP risks. The profiling and benchmarking requirements described in section IV.D of this preamble will ensure that systems maintain protection against pathogens as they make treatment changes to control the formation of DBPs.

The SBAR Panel considered a wide range of options and regulatory alternatives for providing small businesses with flexibility in complying with the LT2ESWTR. The SBAR Panel was concerned with the option of an across-the-board additional *Cryptosporidium* inactivation requirement because of the potential high cost to small systems and the uncertainty regarding the extent to which implementation of the LT1ESWTR will adequately address *Cryptosporidium* contamination at small systems. The SBAR Panel noted that, at the time, the Stage 2 M-DBP Federal Advisory Committee was exploring a targeted approach to *Cryptosporidium* control based on limited monitoring and system assessment, which would identify a subset of vulnerable systems to provide additional treatment in the range of 0.5- to 2.5-log reduction. Further, this approach would allow *E. coli* monitoring in lieu of *Cryptosporidium* monitoring as a screening device for small systems. The

SBAR Panel was also encouraged by recent developments suggesting that UV is a viable, cost-effective means of fulfilling any additional inactivation requirements.

The SBAR Panel recommended that, in developing any additional inactivation requirements based on a targeted approach, EPA carefully consider the potential impacts on small systems and attempt to structure the regulatory requirements in a way that would minimize burden on this group. The SBAR Panel supported *E. coli* as an indicator parameter if additional monitoring is required. The SBAR Panel further recommended that, among the options EPA analyzes, the Agency also evaluate the option of not imposing any additional *Cryptosporidium* control requirements on small systems at this time, as it considers various options to address microbial concerns. Under this option, EPA would evaluate the effects of LT1ESWTR, once implemented, and then consider whether to impose additional requirements during its next 6-year review of the standard, as required by SDWA.

EPA considered these recommendations and has concluded that available information on the health risk associated with *Cryptosporidium* in drinking water warrant moving forward with today's proposal to address higher risk systems. In developing the proposed LT2ESWTR, EPA has implemented the Advisory Committee's recommendations to minimize burden on small systems. Specifically, the risk-targeted treatment requirements will substantially reduce overall costs for small systems in comparison to requiring additional treatment by all systems, and the use of *E. coli* screening will allow most small systems to avoid the cost of *Cryptosporidium* monitoring. Consequently, the Agency has concluded that today's proposal achieves an appropriate balance between public health protection and limiting the economic burden imposed on small entities.

We continue to be interested in the potential impacts of the proposed rule on small entities and welcome comments on issues related to such impacts.

D. Unfunded Mandates Reform Act

1. Summary of UMRA Requirements

Title II of the Unfunded Mandates Reform Act of 1995 (UMRA), Public Law 104-4, establishes requirements for Federal agencies to assess the effects of their regulatory actions on State, local, and Tribal governments and the private sector. Under section 202 of UMRA,

EPA generally must prepare a written statement, including a cost-benefit analysis, for proposed and final rules with "Federal mandates" that may result in expenditures to State, local and Tribal governments, in the aggregate, or to the private sector, of \$100 million or more in any one year. Before promulgating an EPA rule for which a written statement is needed, section 205 of the UMRA generally requires EPA to identify and consider a reasonable number of regulatory alternatives and adopt the least costly, most cost-effective or least burdensome alternative that achieves the objectives of the rule. The provisions of section 205 do not apply when they are inconsistent with applicable law. Moreover, section 205

allows EPA to adopt an alternative other than the least costly, most cost-effective or least burdensome alternative if the Administrator publishes with the final rule an explanation why that alternative was not adopted.

Before EPA establishes any regulatory requirements that may significantly or uniquely affect small governments, including Tribal governments, it must have developed under section 203 of the UMRA a small government agency plan. The plan must provide for notifying potentially affected small governments, enabling officials of affected small governments to have meaningful and timely input in the development of EPA regulatory proposals with significant Federal intergovernmental mandates,

and informing, educating, and advising small governments on compliance with the regulatory requirements.

2. Written Statement for Rules With Federal Mandates of \$100 Million or More

EPA has determined that this rule contains a Federal mandate that may result in expenditures of \$100 million or more for State, local, and Tribal governments, in the aggregate, or the private sector in any one year. Accordingly, EPA has prepared under section 202 of the UMRA a written statement which is summarized in this section. Table VII-3 illustrates the annualized public and private costs for the LT2ESWTR.

TABLE VII-3.—PUBLIC AND PRIVATE COSTS OF THE PROPOSED LT2ESWTR

	Range of annualized costs (Million \$, 2000\$)		Percent of total cost
	3% Discount rate	7% Discount rate	
PWS Costs	\$45.7–69.0	\$50.2–75.2	62.2–62.4
State Costs	0.9–1.0	1.2–1.2	1.3–0.9
Tribal Costs	0.1–0.2	0.1–0.2	0.1–0.1
Total Public Costs	46.7–70.1	51.5–76.6	63.6–63.4
Total Private Costs	26.8–40.4	29.4–44.1	36.4–36.6
Total Costs	73.5–110.5	80.9–120.7	100.0–100.0

Note: The ranges represent the ICRSSL (lowest) and Information Collection Rule (highest) modeled *Cryptosporidium* occurrence distributions. Detail may not add due to independent rounding. Source: The LT2ESWTR Economic Analysis (USEPA 2003a).

A more detailed description of this analysis is presented in Economic Analysis for the LT2ESWTR (USEPA 2003a).

a. *Authorizing legislation.* As noted in section II, today's proposed rule is promulgated pursuant to section 1412 (b)(1)(A) of the Safe Drinking Water Act (SDWA), as amended in 1996, which directs EPA to promulgate a national

primary drinking water regulation for a contaminant if EPA determines that the contaminant may have an adverse effect on the health of persons, occurs in public water systems with a frequency and at levels of public health concern, and regulation presents a meaningful opportunity for health risk reduction.

b. *Cost-benefit analysis.* Section VI of this preamble discusses the cost and

benefits associated with the LT2ESWTR. Details are presented in the Economic Analysis for the LT2ESTWR (USEPA 2003a). For the LT2ESWTR proposal, EPA quantified costs and benefits for four regulatory alternatives. The four alternatives are described in section VI. Table VII-4 summarizes the range of annual costs and benefits for each alternative.

TABLE VII-4.—ANNUAL BENEFITS AND COSTS OF RULE ALTERNATIVES
[\$Million]

Regulatory Alternative	Enhanced COI range of annualized benefits (3%)	Traditional COI range of annualized benefits (3%)	Enhanced COI range of annualized benefits (7%)	Traditional COI range of annualized benefits (7%)	Range of annualized costs (3%)	Range of annualized costs (7%)
Alternative A1	\$457–1,492	\$305–989	\$389–1,260	\$260–845	\$361	\$388
Alternative A2	397–1,461	268–977	338–1,243	229–834	100–134	108–145
Alternative A3	374–1,445	253–967	318–1,230	216–826	73–111	81–121
(Preferred Alternative)	328–1,349	225–907	279–1,148	192–775	37–59	41–65

Source: The LT2ESWTR Economic Analysis (USEPA 2003a).

c. *Estimates of future compliance costs and disproportionate budgetary effects.* To meet the UMRA requirement

in section 202, EPA analyzed future compliance costs and possible disproportionate budgetary effects. The

Agency believes that the cost estimates, indicated earlier and discussed in more detail in section VI of this preamble,

accurately characterize future compliance costs of the proposed rule.

In analyzing disproportionate impacts, the Agency considered the impact on (1) different regions of the United States, (2) State, local, and Tribal governments, (3) urban, rural and other types of communities, and (4) any segment of the private sector. This analysis is presented in section 7 of Economic Analysis for the LT2ESWTR (USEPA 2003a).

EPA has concluded that the LT2ESWTR will not cause a disproportionate budgetary effect. This rule imposes the same requirements on systems nationally and does not disproportionately affect any segment. This rule will treat similarly situated systems (in terms of size, water quality, available data, installed technology, and presence of uncovered finished storage facilities) in similar (proportionate) ways, without regard to geographic location, type of community, or segment of industry. The LT2ESWTR is a rule where requirements are proportionate to risk. Although some groups may have differing budgetary effects as a result of LT2ESWTR, those costs are proportional to the need for greater information (monitoring) and risk posed (degree of treatment required). The variation in cost between large and small systems is due to economies of scale (a larger system can distribute cost across more customers). Regions will have varying impacts due to the number of affected systems.

d. *Macro-economic effects.* Under UMRA section 202, EPA is required to estimate the potential macro-economic effects of the regulation. These types of effects include those on productivity, economic growth, full employment, creation of productive jobs, and international competitiveness. Macro-economic effects tend to be measurable in nationwide econometric models only if the economic impact of the regulation reaches 0.25 percent to 0.5 percent of Gross Domestic Product (GDP). In 2000, real GDP was \$9,224 billion, so a rule would have to cost at least \$23 billion to have a measurable effect. A regulation with a smaller aggregate effect is unlikely to have any measurable impact unless it is highly focused on a particular geographic region or economic sector.

The macro-economic effects on the national economy from the LT2ESWTR should not have a measurable effect because the total annual costs for the proposed option range from \$73 million to \$111 million based on median *Cryptosporidium* occurrence distributions from the ICRSSL and Information Collection Rule data sets

and a discount rate of 3 percent (\$81 to \$121 million at a 7 percent discount rate). These annualized figures will remain constant over the 25-year implementation period that was evaluated, while GDP will probably continue to rise. Thus, LT2ESWTR costs measures as a percentage of the national GDP will only decline over time. Costs will not be highly focused on a particular geographic region or sector.

e. *Summary of EPA consultation with State, local, and Tribal governments and their concerns.* Consistent with the intergovernmental consultation provisions of section 204 of UMRA, EPA has already initiated consultations with the governmental entities affected by this rule. A variety of stakeholders, including small governments, were provided the opportunity for timely and meaningful participation in the regulatory development process. EPA used these opportunities to notify potentially affected governments of regulatory requirements being considered.

The Stage 2 M-DBP Federal Advisory Committee included representatives from State government (Association of State Drinking Water Administrators, Environmental Commissioners of States), local government (National League of Cities), and Tribes (All Indian Pueblo Council (AIPC)). Government and Tribal representatives on the Advisory Committee were generally concerned with ensuring that drinking water regulations are adequately protective of public health and that any additional public health expenditures due to new regulations achieve significant risk reduction. The proposed LT2ESWTR reflects the consensus recommendations of the Advisory Committee, as stated in the Agreement in Principle (65 FR 83015, December 29, 2000). Consequently, EPA believes that the risk-targeted approach for additional *Cryptosporidium* treatment requirements and other provisions in today's proposal satisfies the concerns of the government and Tribal representatives on the Advisory Committee.

As described in section VII.C of this preamble, the Agency convened a Small Business Advocacy Review (SBAR) Panel in accordance with the Regulatory Flexibility Act (RFA) as amended by the Small Business Regulatory Enforcement Fairness Act to address the concerns of small entities, including small local governments specifically. Small entity representatives (SERs) to the SBAR panel, including representatives of small local governments, were concerned about the cost of the rule, the technical capability of small systems to

implement requirements, and flexibility in regulatory requirements and in the compliance schedule. SERs also emphasized that EPA needs to balance the control of known microbial risks with the risks associated with DBPs.

Today's proposal is responsive to these concerns, as stated in section VII.C. The LT2ESWTR will impose costs for additional treatment on only the fraction of systems identified through monitoring as being at higher risk, and overall monitoring costs for small systems will be greatly reduced through use of the *E. coli* screening to waive small systems from *Cryptosporidium* monitoring. The microbial toolbox of treatment options will provide significant flexibility to systems to identify cost-effective solutions for meeting additional *Cryptosporidium* treatment requirements. The compliance schedule for small systems is delayed in relation to large systems, which will allow small systems additional time to become knowledgeable about and prepare to implement the LT2ESWTR. The intent of the proposed disinfection profiling provisions is to ensure that when systems make treatment changes to control DBP formation, they maintain protection against pathogens.

EPA held a meeting on the LT2ESWTR in February 2001 with representatives of State and local governments. Representatives of the following organizations attended: Association of State Drinking Water Administrators (ASDWA), the National Governors' Association (NGA), the National Conference of State Legislatures (NCSL), the International City/County Management Association (ICMA), the National League of Cities (NLC), the County Executives of America, and health departments. Representatives asked questions regarding how *Cryptosporidium* gets into the water, whether EPA would add laboratory approval for *Cryptosporidium* to State certification programs, the effectiveness of ozone and UV, and the development of ambient water quality criteria for *Cryptosporidium*.

EPA has largely addressed these questions in this preamble. Section II characterizes sources of *Cryptosporidium*. As described in section IV.K, EPA is currently carrying out a laboratory approval program for *Cryptosporidium* analyses but expects that this will be included in State laboratory certification programs in the future. In section IV.C., EPA describes the effectiveness of ozone and UV for *Cryptosporidium* inactivation and provides criteria for how these technologies may be used to comply with the treatment requirements in

today's proposal. The Agency is currently exploring the development of ambient water quality criteria for *Cryptosporidium*, but such criteria are not available at this time and are not included in today's proposal.

In addition to the Tribal representative on the Advisory Committee, EPA conducted outreach and consultation with Tribal representatives on a number of occasions regarding the LT2ESWTR. EPA presented the LT2ESWTR at the following forums: the 16th Annual Consumer Conference of the National Indian Health Board, which included over 900 representatives of Tribes across the nation; the annual conference of the National Tribal Environmental Council, at which over 100 Tribes were represented; and the 1999 EPA/Inter-Tribal Council of Arizona, which included representatives from 15 Tribes. EPA also sent the presentation materials used in the first two meetings and meeting summaries to over 500 Tribes and Tribal organizations.

Fact sheets describing the requirements of the LT2ESWTR and requesting Tribal input were distributed at an annual EPA Tribal meeting in San Francisco and at a Native American Water Works Association meeting in Scottsdale, Arizona. EPA also worked through its Regional Indian Coordinators and the National Tribal Operations Committee to raise awareness of the development of the proposed rule. EPA mailed all Federal Tribes LT2ESWTR fact sheets in November 2000. The Tribal representative to the Advisory Committee also presented the Stage 2 Agreement in Principle prior to signature in at least one political forum for various Tribes not affiliated with AIPC.

EPA held a teleconference in January 2002 with 12 Tribal representatives and four Regional Tribal Program Coordinators. Prior to the teleconference, EPA sent invitations to all Federal Tribes, along with a fact sheet explaining the LT2ESWTR.

Through this consultation, Tribal representatives expressed concern about implementing new regulations without additional funding sources. However, they also stated that the LT2ESWTR would have a benefit, and asserted that people served by small systems should receive equivalent public health protection. Questions were asked regarding the impact of the rule (e.g., number of Tribal surface water systems) and the date for finalizing the rule. The Tribal representative to the M-DBP Advisory Committee advocated that risk mitigation plans for uncovered finished

water storage facilities should account for cultural uses by Tribes.

In response to the concerns expressed by Tribal representatives, EPA noted that the LT2ESWTR proposal is designed to minimize costs by targeting higher risk systems, and includes other provisions, described earlier, to reduce burden. Moreover, the projected benefits of the rule substantially exceed costs. EPA also explained that capital projects related to the rule would be eligible for Federal funding sources, such as the Drinking Water State Revolving Fund, due to the health risks associated with *Cryptosporidium*. The LT2ESWTR Economic Analysis (USEPA 2003a) provides an analysis of the impact of the LT2ESWTR on Tribes. EPA has identified 67 Tribal water systems that would be subject to the LT2ESWTR.

In addition to these direct consultations with State, local, and Tribal governments, EPA posted a pre-proposal draft of the LT2ESWTR proposal on an EPA Internet site (<http://www.epa.gov/safewater/>) in November 2001. EPA received comments on this pre-proposal draft from ASDWA and six States, several public water systems owned by local governments, as well as private water systems, laboratories, and other stakeholders. Among the concerns raised by commenters representing State and local governments were the following: early implementation of monitoring by large systems; flexibility for States in awarding treatment credits to different *Cryptosporidium* control technologies; and the added burden of the rule on systems and States.

EPA has addressed these concerns in developing the LT2ESWTR proposal. As described in section IV.J, EPA is planning to directly implement the large system monitoring requirements that occur during the first 2.5 years after promulgation. The planned approach is similar to that used for the UCMR, including an electronic data reporting system for storing monitoring results and tracking compliance. With this approach, States will be able to access data reported by their systems, thereby allowing States to exercise oversight of their systems during early implementation if they chose. However, EPA will take primary responsibility for providing technical assistance to systems and assessing compliance with monitoring requirements.

In regard to treatment credit for *Cryptosporidium* control technologies, the Agency has made substantial efforts to ensure that the criteria in today's proposal are based on the best available data. EPA has worked in partnership with industry and researchers to gather information, and proposed criteria for

several microbial toolbox options reflect comments by the Science Advisory Board. In addition, today's proposal gives flexibility to States by allowing them to award different levels of *Cryptosporidium* treatment credit to their systems based on site-specific demonstrations.

With respect to the burden the LT2ESWTR would place on water systems and States, EPA has, as described previously in this preamble, attempted to minimize overall costs under the proposed LT2ESWTR. This is achieved through risk-targeting of additional treatment requirements, allowing most small systems to avoid *Cryptosporidium* monitoring costs through *E. coli* screening, and facilitating the use of lower cost treatment technologies like UV.

In summary, EPA has concluded that the proposed option for the LT2ESWTR is needed to provide a significant public health benefit by reducing exposure to *Cryptosporidium*. While many public water systems achieve adequate control of *Cryptosporidium*, additional treatment should be required for filtered systems with elevated source water pathogen levels and for unfiltered systems. The availability of improved analytical methods allows additional treatment requirements to be targeted to higher risk systems, and the development of technologies like UV makes it feasible for systems to provide additional treatment. The monetized benefits of today's proposal significantly exceed total costs, and EPA believes there will be substantial unquantified benefits as well.

f. *Regulatory alternatives considered.* As required under section 205 of UMRA, EPA considered several regulatory alternatives to address systems at risk for contamination by microbial pathogens, specifically including *Cryptosporidium*. A detailed discussion of these alternatives can be found in section VI of the preamble and also in the Economic Analysis for the LT2ESWTR (USEPA 2003a).

g. *Selection of the least costly, most cost-effective, or least burdensome alternative that achieves the objectives of the rule.* Among the regulatory alternatives considered for the LT2ESWTR, as described in section VI, the Agency believes the proposed alternative is the most cost-effective that achieves the objectives of the rule. The objective of the LT2ESWTR is to reduce risk from *Cryptosporidium* and other pathogens in systems where current regulations do not provide sufficient protection.

The Agency evaluated a less costly and less burdensome alternative.

However, this alternative would provide no benefit to several thousand consumers who, under the proposed alternative, would receive benefits that most likely exceed their costs, based on Agency estimates. This is illustrated in the LT2ESWTR Economic Analysis (USEPA 2003a). By failing to reduce risk for consumers where additional treatment requirements would be cost-effective, the less costly alternative does not appear to achieve the objectives of the LT2ESWTR.

The other alternatives considered by the Agency achieve the objectives of the rule, but are more costly, more burdensome, and potentially less cost-effective. The proposed alternative targets additional treatment requirements to systems with the highest vulnerability to *Cryptosporidium*, and maximizes net benefits under a broad range of conditions (USEPA 2003a). Consequently, the Agency has found the proposed alternative to be the most cost-effective among those that achieve the objectives of the rule.

3. Impacts on Small Governments

EPA has determined that this rule contains no regulatory requirements that might significantly or uniquely affect small governments. Thus, today's rule is not subject to the requirements of section 203 of UMRA. As described in section VII.C, EPA has certified that this proposed rule will not have a significant economic impact on a substantial number of small entities. Estimated annual expenditures by small systems for the LT2ESWTR range from \$7.9 to \$13.0 million at a 3% discount rate and \$8.0 to \$13.0 million at a 7% discount rate. While the treatment requirements of the LT2ESWTR apply uniformly to both small and large public water systems, large systems bear a majority of the total costs of compliance with the rule. This is due to the fact that large systems treat a majority of the drinking water that originates from surface water sources.

E. Executive Order 13132: Federalism

Executive Order 13132, entitled "Federalism" (64 FR 43255, August 10, 1999), requires EPA to develop an accountable process to ensure "meaningful and timely input by State and local officials in the development of regulatory policies that have federalism implications." "Policies that have federalism implications" is defined in the Executive Order to include regulations that have "substantial direct effects on the States, on the relationship between the national government and the States, or on the distribution of

power and responsibilities among the various levels of government."

Under Executive Order 13132, EPA may not issue a regulation that has federalism implications, that imposes substantial direct compliance costs, and that is not required by statute, unless the Federal government provides the funds necessary to pay the direct compliance costs incurred by State and local governments, or EPA consults with State and local officials early in the process of developing the proposed regulation.

EPA has concluded that this proposed rule may have federalism implications, because it may impose substantial direct compliance costs on State or local governments, and the Federal government will not provide the funds necessary to pay those costs. The proposed rule may result in expenditures by State, local, and Tribal governments, in the aggregate of \$100 million or more in any one year. Costs are estimated to range from \$73 to \$111 million at a 3 percent discount rate and \$81 to \$121 million using a 7 percent discount rates based on the median distribution modeled from ICRSSL and Information Collection Rule *Cryptosporidium* occurrence data sets. Accordingly, EPA provides the following federalism summary impact statement as required by section 6(b) of Executive Order 13132.

EPA consulted with representatives of State and local officials early in the process of developing the proposed regulation to permit them to have meaningful and timely input into its development. Section VII.D.2.e describes EPA's consultation with representatives of State and local officials. This consultation included State and local government representatives on the Stage 2 M-DBP Federal Advisory Committee, the representatives from small local governments to the SBAR panel, a meeting with representatives from ASDWA, NGA, NCSL, ICMA, NLC, the County Executives of America, and health departments, consultation with Tribal governments at four meetings, and comments from State and local governments on a pre-proposal draft of the LT2ESWTR.

Representatives of State and local officials were generally concerned with ensuring that drinking water regulations are adequately protective of public health and that any additional regulations achieve significant health benefits in return for required expenditures. They were specifically concerned with the burden of the proposed rule, both in cost and technical complexity, giving flexibility

to systems and States, balancing the control of microbial risks and DBP risks, funding for implementing new regulations, equal protection for small systems, and early implementation of monitoring by large systems.

EPA has concluded that the proposed LT2ESWTR is needed to reduce the public health risk associated with *Cryptosporidium* in drinking water. Estimated benefits for the rule are significantly higher than costs. Further, as described in this section and in section VII.D.2.e, the Agency believes that today's proposal addresses many of the concerns expressed by representatives of government officials.

Under the proposed LT2ESWTR, expenditures for additional treatment are targeted to the fraction of systems with the highest vulnerability to *Cryptosporidium*, thereby minimizing burden for the majority of systems that will not be required to provide additional treatment. The microbial toolbox of compliance options will provide flexibility to systems in meeting additional treatment requirements, and States have the flexibility to award treatment credits based on site-specific demonstrations. Disinfection profiling provisions are intended to ensure that systems do not reduce microbial protection as they take steps to reduce exposures to DBPs.

The LT2ESWTR achieves equal public health protection for small systems. However, the use of *E. coli* monitoring by small systems as a screening analysis to determine the need for *Cryptosporidium* monitoring will reduce monitoring costs for most small systems. Capital projects related to the rule would be eligible for funding from the Drinking Water State Revolving Fund, which includes specific funding for small communities. EPA is planning to support the initial monitoring by large systems that takes place within the first 2.5 years after promulgation. This will substantially reduce the burden on States associated with early implementation of monitoring requirements.

In the spirit of Executive Order 13132, and consistent with EPA policy to promote communications between EPA and State and local governments, EPA specifically solicits comment on this proposed rule from State and local officials.

F. Executive Order 13175: Consultation and Coordination With Indian Tribal Governments

Executive Order 13175, entitled "Consultation and Coordination with Indian Tribal Governments" (65 FR 67249, November 9, 2000), requires EPA

to develop “an accountable process to ensure meaningful and timely input by Tribal officials in the development of regulatory policies that have Tribal implications.” “Policies that have Tribal implications” is defined in the Executive Order to include regulations that have “substantial direct effects on one or more Indian tribes, on the relationship between the Federal government and the Indian tribes, or on the distribution of power and responsibilities between the Federal government and Indian tribes.”

Under Executive Order 13175, EPA may not issue a regulation that has Tribal implications, that imposes substantial direct compliance costs, and that is not required by statute, unless the Federal government provides the funds necessary to pay the direct compliance costs incurred by Tribal governments, or EPA consults with Tribal officials early in the process of developing the proposed regulation and develops a Tribal summary impact statement.

EPA has concluded that this proposed rule may have Tribal implications, because it may impose substantial direct compliance costs on Tribal governments, and the Federal government will not provide the funds necessary to pay those costs. EPA has identified 67 Tribal water systems serving a total population of 78,956 that may be subject to the LT2ESWTR. They will bear an estimated total annualized cost of \$135,974 at a 3 percent discount rate (\$138,910 at 7 percent) to implement this rule as proposed. Estimated mean annualized cost per system ranges from \$792 to \$23,979 at a 3 percent discount rate (\$844 to \$26,194 at 7 percent) depending on system size (see section 7 of the LT2ESWTR Economic Analysis (USEPA 2003a) for details). Accordingly, EPA provides the following Tribal summary impact statement as required by section 5(b) of Executive Order 13175.

EPA consulted with representatives of Tribal officials early in the process of developing this regulation to permit them to have meaningful and timely input into its development. Section VII.D.2.e describes EPA's outreach and consultation with Tribes, which included presentations on the LT2ESWTR at four Tribal conferences and meetings, mailing fact sheets and presentation materials regarding the proposal to Tribes on several occasions, and a teleconference with representatives of Tribal officials to comment on the proposed rule.

As discussed in section VII.D.2.e, Tribal representatives stated that protection of public health is important

regardless of the number of people a system is serving, and they recognized that the LT2ESWTR would provide a public health benefit. However, Tribal representatives were concerned about the availability of funding to implement the regulation and asked about the projected impact on Tribes (e.g., number of Tribal surface water systems that would be affected). Also, the Tribal representative to the Federal Advisory Committee was concerned that risk mitigation plans for uncovered finished water storage facilities account for cultural uses by Tribes.

EPA has concluded that the proposed LT2ESWTR is needed to reduce the risk associated with *Cryptosporidium* in public water systems using surface water sources. Projected benefits for today's proposal are substantially greater than costs. Moreover, as described in this section and in section VII.D.2.e, today's proposal addresses many of the concerns stated by Tribal representatives.

The LT2ESWTR will provide equivalent public health protection to all system sizes, including Tribal systems. By targeting additional treatment requirements to higher risk systems, the LT2ESWTR will minimize overall burden in comparison with requiring additional treatment by all systems. In addition, the provision in the proposal allowing *E. coli* screening to determine if *Cryptosporidium* monitoring is necessary will reduce monitoring costs for many small Tribal systems. (EPA notes that 66 of the 67 Tribal systems identified by the Agency as subject to the LT2ESWTR are small systems.) Due to the health risks associated with *Cryptosporidium*, capital expenditures needed for compliance with the rule will be eligible for Federal funding sources, specifically the Drinking Water State Revolving Fund. EPA is developing guidance that will address consideration of Tribal cultural uses of uncovered finished water storage facilities.

In the spirit of Executive Order 13175, and consistent with EPA policy to promote communications between EPA and Tribal governments, EPA specifically solicits additional comment on this proposed rule from Tribal officials.

G. Executive Order 13045: Protection of Children from Environmental Health and Safety Risks

Executive Order 13045: “Protection of Children from Environmental Health Risks and Safety Risks” (62 FR 19885, April 23, 1997) applies to any rule that: (1) Is determined to be “economically significant” as defined under Executive

Order 12866, and (2) concerns an environmental health or safety risk that EPA has reason to believe may have a disproportionate effect on children. If the regulatory action meets both criteria, the Agency must evaluate the environmental health or safety effects of the planned rule on children and explain why the planned regulation is preferable to other potentially effective and reasonably feasible alternatives considered by the Agency.

This proposed rule is subject to the Executive Order because it is an economically significant regulatory action as defined in Executive Order 12866, and we believe that the environmental health or safety risk addressed by this action may have a disproportionate effect on children. Accordingly, we have evaluated the environmental health or safety effects of *Cryptosporidium* on children. The results of this evaluation are contained in *Cryptosporidium: Risk for Infants and Children* (USEPA 2001d) and described in this section of this preamble. Further, while available information is not adequate to conduct a quantitative risk assessment specifically on children, EPA has assessed the risk associated with *Cryptosporidium* in drinking water for the general population, including children. This assessment is described in the Economic Analysis for the LT2ESWTR (USEPA 2003a) and is summarized in section VI of this preamble. Copies of these documents and supporting information are available in the public docket for today's proposal.

Cryptosporidiosis in children is similar to adult disease (USEPA 2001d). Diarrhea is the most common symptom. Other common symptoms in otherwise healthy (i.e., immunocompetent) children include anorexia, vomiting, abdominal pain, fever, dehydration and weight loss.

The risk of illness and death due to cryptosporidiosis depends on several factors, including age, nutrition, exposure, genetic variability, disease and the immune status of the individual. Mortality resulting from diarrhea generally occurs at a greater rate among the very young and elderly (Gerba *et al.*, 1996). During the 1993 Milwaukee drinking water outbreak, associated mortalities in children were reported. Also, children with laboratory-confirmed cryptosporidiosis were more likely to have an underlying disease that altered their immune status (Cicirello *et al.*, 1997). In that study, the observed association between increasing age of children and increased numbers of laboratory-confirmed cryptosporidiosis suggested to the authors that the data

are consistent with increased tap water consumption of older children. However, due to data limitations, this observation could not be adequately analyzed. Asymptomatic infection, especially in underdeveloped communities, can have a substantial effect on childhood growth (Bern *et al.*, 2002).

Cryptosporidiosis appears to be more prevalent in populations, such as children, that may not have established immunity against the disease and may be in greater contact with environmentally contaminated surfaces (DuPont *et al.*, 1995). In the United States, children aged one to four years are more likely than adults to have the disease. The most recent reported data on cryptosporidiosis shows the occurrence rate (for the year 1999) is higher in children ages one to four (3.03 incidence rate per 100,000) than in any adult age group (CDC, 2001). Evidence from blood sera antibodies collected from children during the 1993 Milwaukee outbreak suggest that children had greater levels of *Cryptosporidium* infection than predicted for the general community (based on the random-digit dialing telephone survey method) (McDonald *et al.*, 2001).

Data indicate a lower incidence of cryptosporidiosis infection during the first year of life. This is attributed to breast-fed infants consuming less tap water and, hence, having less exposure to *Cryptosporidium*, as well as the possibility that mothers confer short term immunity to their children. For example, in a survey of over 30,000 stool sample analyses from different patients in the United Kingdom, the one to five year age group suffered a much higher infection rate than individuals less than one year of age. For children under one year of age, those older than six months of age showed a higher rate of infection than individuals aged less than six months (Casemore, 1990). Similarly, in the U.S., of 2,566 reported *Cryptosporidium* illnesses in 1999, 525 occurred in ages one to four (incidence rate of 3.03 per 100,000) compared with 58 cases in infants under one year (incidence rate of 1.42 per 100,000) (CDC, 2001).

An infected child may spread the disease to other children or family members (Heijbel *et al.*, 1987, Osewe *et al.*, 1996). Millard *et al.* (1994) documented greater household secondary transmission of cryptosporidiosis from children than from adults to household and other close contacts. Children continued to shed oocysts for more than two weeks

(mean 16.5 days) after diarrhea cessation (Tangerman *et al.*, 1991).

While *Cryptosporidium* may have a disproportionate effect on children, available data are not adequate to distinctly assess the health risk for children resulting from *Cryptosporidium*-contaminated drinking water. In assessing risk to children when evaluating regulatory alternatives for the LT2ESWTR, EPA assumed the same risk for children as for the population as a whole.

Section VI of this preamble presents the regulatory alternatives that EPA evaluated for the proposed LT2ESWTR. Among the four alternatives the Agency considered, three involved a risk-targeting approach in which additional *Cryptosporidium* treatment requirements are based on source water monitoring results. A fourth alternative involved additional treatment requirements for all systems.

The alternative requiring additional treatment by all systems was not selected because of concerns about feasibility and because it imposed costs but provided few benefits to systems with high quality source water (*i.e.*, relatively low *Cryptosporidium* risk). The three risk-targeting alternatives were evaluated based on several factors, including costs, benefits, net benefits, feasibility of implementation, and other specific impacts (*e.g.*, impacts on small systems or sensitive subpopulations).

The proposed alternative was recommended by the M-DBP Federal Advisory Committee and selected by EPA as the Preferred Regulatory Alternative because it was deemed feasible and provides significant public health benefits in terms of avoided illnesses and deaths. EPA's analysis of benefits and costs indicates that the proposed alternative ranks highly among those evaluated with respect to maximizing net benefits, as shown in the LT2ESWTR Economic Analysis (USEPA 2003a). This document is available in the docket for this action.

The result of the LT2ESWTR will be a reduction in the risk of illness for the entire population, including children. Because available evidence indicates that children may be more vulnerable to cryptosporidiosis than the rest of the population, the LT2ESWTR may, therefore, result in greater risk reduction for children than for the general population.

The public is invited to submit or identify peer-reviewed studies and data, of which EPA may not be aware, that assessed results of early life exposure to *Cryptosporidium*.

H. Executive Order 13211: Actions That Significantly Affect Energy Supply, Distribution, or Use

This rule is not a "significant energy action" as defined in Executive Order 13211, "Actions Concerning Regulations That Significantly Affect Energy Supply, Distribution, or Use" (66 FR 28355 (May 22, 2001)) because it is not likely to have a significant adverse effect on the supply, distribution, or use of energy. This determination is based on the following analysis.

The first consideration is whether the LT2ESWTR would adversely affect the supply of energy. The LT2ESWTR does not regulate power generation, either directly or indirectly. The public and private utilities that the LT2ESWTR regulates do not, as a rule, generate power. Further, the cost increases borne by customers of water utilities as a result of the LT2ESWTR are a low percentage of the total cost of water, except for a very few small systems that might install advanced technologies and then need to spread that cost over a narrow customer base. Therefore, the customers that are power generation utilities are unlikely to face any significant effects as a result of the LT2ESWTR. In sum, the LT2ESWTR does not regulate the supply of energy, does not generally regulate the utilities that supply energy, and is unlikely to affect significantly the customer base of energy suppliers. Thus, the LT2ESWTR would not translate into adverse effects on the supply of energy.

The second consideration is whether the LT2ESWTR would adversely affect the distribution of energy. The LT2ESWTR does not regulate any aspect of energy distribution. The utilities that are regulated by the LT2ESWTR already have electrical service. As derived later in this section, the proposed rule is projected to increase peak electricity demand at water utilities by only 0.02 percent. Therefore, EPA estimates that the existing connections are adequate and that the LT2ESWTR has no discernable adverse effect on energy distribution.

The third consideration is whether the LT2ESWTR would adversely affect the use of energy. Because some drinking water utilities are expected to add treatment technologies that use electrical power, this potential impact is evaluated in more detail. The analyses that underlay the estimation of costs for the LT2ESWTR are national in scope and do not identify specific plants or utilities that may install treatment in response to the rule. As a result, no analysis of the effect on specific energy suppliers is possible with the available

data. The approach used to estimate the impact of energy use, therefore, focuses on national-level impacts. The analysis estimates the additional energy use due to the LT2ESWTR, and compares that to the national levels of power generation in terms of average and peak loads.

The first step in the analysis is to estimate the energy used by the technologies expected to be installed as a result of the LT2ESWTR. Energy use is not directly stated in Technologies and Costs for Control of Microbial Contaminants and Disinfection By-Products (USEPA 2003c), but the annual cost of energy for each technology

addition or upgrade necessitated by the LT2ESWTR is provided. An estimate of plant-level energy use is derived by dividing the total energy cost per plant for a range of flows by an average national cost of electricity of \$0.076/kWh (USDOE EIA, 2002). These calculations are shown in detail in Chapter 7 of the Economic Analysis for the LT2ESWTR (USEPA 2003a). The energy use per plant for each flow range and technology is then multiplied by the number of plants predicted to install each technology in a given flow range. The energy requirements for each flow range are then added to produce a

national total. No electricity use is subtracted to account for the technologies that may be replaced by new technologies, resulting in a conservative estimate of the increase in energy use. Results of the analysis are shown in Table VII-5 for each of the modeled *Cryptosporidium* occurrence distributions. The results range from an incremental national annual energy usage of 0.12 million megawatt-hours (mW) for the modeled Information Collection Rule occurrence distribution to 0.07 million mW for the modeled ICRSSL occurrence distribution.

TABLE VII-5.—TOTAL INCREASED ANNUAL NATIONAL ENERGY USAGE ATTRIBUTABLE TO THE LT2ESWTR

Technology	ICR		ICRSSL		ICRSSM	
	Plants selecting technology	Total annual energy required (kWh/yr)	Plants selecting technology	Total annual energy required (kWh/yr)	Plants selecting technology	Total annual energy required (kWh/yr)
	A	B	C	D	E	F
ClO ₂	77	343,297	61	268,861	70	312,036
UV	998	86,827,218	490	52,212,046	632	64,515,863
O ₃ (0.5 log)	26	12,524,670	19	10,328,359	21	11,467,703
O ₃ (1.0 log)	24	12,456,132	12	6,119,824	21	10,759,696
O ₃ (2.0 log)	9	7,324,561	0	35,259	2	1,787,144
MF/UF	10	5,691,144	8	4,507,577	5	2,790,401
Bag Filters	1,545	1,631,873	1,236	1,306,067	1,441	1,522,243
Cartridge Filters	190	76,793	17	6,254	52	19,686
Total	2,878	126,875,687	1,844	74,784,249	2,244	93,174,772

Source: The LT2ESWTR Economic Analysis (USEPA 2003a).

To determine if the additional energy required for systems to comply with the rule would have a significant adverse effect on the use of energy, the numbers in Table VII-5 are compared to the national production figures for electricity. According to the U.S. Department of Energy's Information Administration, electricity producers generated 3,800 million mW of electricity in 2001 (USDOE EIA, 2002). Therefore, even using the highest assumed energy use for the LT2ESWTR, the rule when fully implemented would result in only a 0.003 percent increase in annual average energy use.

In addition to average energy use, the impact at times of peak power demand is important. To examine whether increased energy usage might significantly affect the capacity margins of energy suppliers, their peak season generating capacity reserve was compared to an estimate of peak incremental power demand by water utilities.

Both energy use and water use are highest in the summer months, so the most significant effects on supply would be seen then. In the summer of 2001, U.S. generation capacity exceeded

consumption by 15 percent, or approximately 120,000 mW (USDOE EIA 2002). Assuming around-the-clock operation of water treatment plants, the total energy requirement can be divided by 8,760 hours per year to obtain an average power demand of 15 mW for the modeled Information Collection Rule occurrence distribution. A more detailed derivation of this value is shown in Appendix P of the Economic Analysis for the LT2ESWTR (USEPA 2003a). Assuming that power demand is proportional to water flow through the plant, and that peak flow can be as high as twice the average daily flow during the summer months, about 30 mW could be needed for treatment technologies installed to comply with the LT2ESWTR. This is only 0.024 percent of the capacity margin available at peak use.

Although EPA recognizes that not all areas have a 15 percent capacity margin and that this margin varies across regions and through time, this analysis reflects the effect of the rule on national energy supply, distribution, or use. While certain areas, notably California, have experienced shortfalls in generating capacity in the recent past, a

peak incremental power requirement of 30 mW nationwide is not likely to significantly change the energy supply, distribution, or use in any given area. Considering this analysis, EPA has concluded that LT2ESWTR is not likely to have a significant adverse effect on the supply, distribution, or use of energy.

I. National Technology Transfer and Advancement Act

Section 12(d) of the National Technology Transfer and Advancement Act (NTTAA) of 1995, Public Law 104-113, section 12(d) (15 U.S.C. 272 note), directs EPA to use voluntary consensus standards in its regulatory activities unless to do so would be inconsistent with applicable law or otherwise impractical. Voluntary consensus standards are technical standards (e.g., material specifications, test methods, sampling procedures, and business practices) that are developed or adopted by voluntary consensus standard bodies. The NTTAA directs EPA to provide Congress, through OMB, explanations when the Agency decides not to use available and applicable voluntary consensus standards.

The proposed rulemaking involves technical standards. EPA proposes to use several voluntary consensus standards (VCS) methods for enumerating *E. coli* in surface waters. These methods are listed in section IV.K.2, Table IV-37, and were developed or adopted by the following organizations: American Public Health Association in Standard Methods for the Examination of Water and Wastewater, 20th, 19th, and 18th Editions, the American Society of Testing Materials in Annual Book of ASTM Standards—Water and Environmental Technology, and the Association of Analytical Chemists in Official Methods of Analysis of AOAC International, 16th Edition. These methods are available in the docket for today's proposal. EPA has concluded that these methods have the necessary sensitivity and specificity to meet the data quality objectives of the LT2ESWTR.

The Agency conducted a search to identify potentially applicable voluntary consensus standards for analysis of *Cryptosporidium*. However, we identified no such standards. Therefore, EPA proposes to use the following methods for *Cryptosporidium* analysis: Method 1622: "*Cryptosporidium* in Water by Filtration/IMS/FA" (EPA-821-R-01-026, April 2001) (USEPA 2001e) and Method 1623: "*Cryptosporidium* and Giardia in Water by Filtration/IMS/FA" (EPA 821-R-01-025, April 2001) (USEPA 2001f).

EPA welcomes comments on this aspect of the proposed rulemaking and, specifically, invites the public to identify additional potentially applicable voluntary consensus standards, and to explain why such standards should be used in this regulation.

J. Executive Order 12898: Federal Actions To Address Environmental Justice in Minority Populations or Low-Income Populations

Executive Order 12898 establishes a Federal policy for incorporating environmental justice into Federal agency missions by directing agencies to identify and address disproportionately high and adverse human health or environmental effects of its programs, policies, and activities on minority and low-income populations. The Agency has considered environmental justice related issues concerning the potential impacts of this action and consulted with minority and low-income stakeholders.

Two aspects of the LT2ESWTR comply with the order that requires the Agency to consider environmental justice issues in the rulemaking and to

consult with stakeholders representing a variety of economic and ethnic backgrounds. These are: (1) The overall nature of the rule, and (2) the convening of a stakeholder meeting specifically to address environmental justice issues.

The Agency built on the efforts conducted during the development of the IESWTR to comply with Executive Order 12898. On March 12, 1998, the Agency held a stakeholder meeting to address various components of pending drinking water regulations and how they might impact sensitive subpopulations, minority populations, and low-income populations. This meeting was a continuation of stakeholder meetings that started in 1995 to obtain input on the Agency's Drinking Water Programs. Topics discussed included treatment techniques, costs and benefits, data quality, health effects, and the regulatory process. Participants were national, State, Tribal, municipal, and individual stakeholders. EPA conducted the meeting by video conference call between eleven cities. The major objectives for the March 12, 1998, meeting were the following:

- Solicit ideas from stakeholders on known issues concerning current drinking water regulatory efforts;
- Identify key areas of concern to stakeholders; and
- Receive suggestions from stakeholders concerning ways to increase representation of communities in OGWDW regulatory efforts.

In addition, EPA developed a plain-English guide for this meeting to assist stakeholders in understanding the multiple and sometimes complex issues surrounding drinking water regulations.

The LT2ESWTR and other drinking water regulations promulgated or under development are expected to have a positive effect on human health regardless of the social or economic status of a specific population. The LT2ESWTR serves to provide a similar level of drinking water protection to all groups. Where water systems have high *Cryptosporidium* levels, they must treat their water to achieve a specified level of protection. Further, to the extent that levels of *Cryptosporidium* in drinking water might be disproportionately high among minority or low-income populations (which is unknown), the LT2ESWTR will work to remove those differences. Thus, the LT2ESWTR meets the intent of Federal policy requiring incorporation of environmental justice into Federal agency missions.

The LT2ESWTR applies uniformly to CWSs, NTNCWSs, and TNCWSs that use surface water or GWUDI as their

source. Consequently, this rule provides health protection from pathogen exposure equally to all income and minority groups served by surface water and GWUDI systems.

K. Consultations with the Science Advisory Board, National Drinking Water Advisory Council, and the Secretary of Health and Human Services

In accordance with sections 1412 (d) and (e) of SDWA, the Agency has consulted with the Science Advisory Board (SAB), the National Drinking Water Advisory Council (NDWAC), and will consult with the Secretary of Health and Human Services regarding the proposed LT2ESWTR during the public comment period. EPA charged the SAB panel with reviewing the following aspects of the LT2ESWTR proposal:

- The analysis of *Cryptosporidium* occurrence, as described in Occurrence and Exposure Assessment for the LT2ESWTR (USEPA 2003b);
- The pre- and post-LT2ESWTR *Cryptosporidium* risk assessment, as described in Economic Analysis for the LT2ESWTR (USEPA 2003a); and
- The treatment credits for the following four microbial toolbox components: raw water off-stream storage, pre-sedimentation, lime softening, and lower finished water turbidity (described in section IV.C of this preamble).

EPA met with the SAB to discuss the LT2ESWTR on June 13, 2001 (Washington, DC), September 25-26, 2001 (teleconference), and December 10-12, 2001 (Los Angeles, CA). Written comments from the December 2001 meeting of the SAB addressing the occurrence analysis and risk assessment were generally supportive. EPA has responded to the SAB's recommendations for *Cryptosporidium* occurrence analysis in the current draft of Occurrence and Exposure Assessment for the LT2ESWTR (USEPA 2003b), and EPA has addressed the SAB's comments on risk assessment in the current draft of Economic Analysis for the LT2ESWTR (USEPA 2003a). Comments from the SAB on the microbial toolbox components and the Agency's responses to those comments are described in section IV.C of this preamble.

EPA met with the NDWAC on November 8, 2001, in Washington, DC, to discuss the LT2ESWTR proposal. EPA specifically requested comments from the NDWAC on the regulatory approach taken in the proposed microbial toolbox (e.g., proposal of specific design and implementation criteria for treatment credits). The Council was generally supportive of EPA establishing criteria for awarding

treatment credit to toolbox components, but recommended that EPA provide flexibility for States to address system specific situations. EPA believes that the demonstration of performance credit, described in section IV.C.17, provides this flexibility by allowing States to award higher or lower levels of treatment credit for microbial toolbox components based on site specific conditions. Minutes of the NDWAC and SAB meetings are in the docket for today's proposal.

L. Plain Language

Executive Order 12866 encourages Federal agencies to write rules in plain language. EPA invites comments on how to make this proposed rule easier to understand. For example: Has EPA organized the material to suit commenters' needs? Are the requirements in the rule clearly stated? Does the rule contain technical language or jargon that is not clear? Would a different format (grouping and ordering of sections, use of headings, paragraphs) make the rule easier to understand? Could EPA improve clarity by adding tables, lists, or diagrams? What else could EPA do to make the rule easier to understand?

VIII. References

- Aboytes R., F.A. Abrams, W.E. McElroy, C. Rheinecker, G.D. DiGiovanni, R. Seeny, M. LeChevallier, and R. Kozik. 2002. Continuous monitoring for detection of infectious *Cryptosporidium parvum* oocysts in drinking water. Abstracts of the 102nd General Meeting of the American Society for Microbiology, Salt Lake City, UT, May 19–22.
- Adham, S., J. Jacangelo, and J. Laine. 1995. Low pressure membranes: assessing integrity. J. AWWA. 83:3:62.
- Adham, S., P. Gagliardo, D. Smith, D. Ross, K. Gramith, and R. Trussell. 1998. Monitoring of reverse osmosis for virus rejection. Proceedings of the Water Quality Technology Conference of the American Water Works Association, Denver, CO.
- APHA. 1992. Standard Methods for the Examination of Water and Wastewater; 18th Edition. American Public Health Association, Washington D.C.
- Arora, H., M. LeChevallier, R. Aboytes, E. Bouwer, C. O'Melia, W. Ball, W. Weiss, and T. Speth. 2000. Full-scale evaluation of riverbank filtration at three Midwest water treatment plants. Proceedings of the Water Quality Technology Conference, Salt Lake City, Utah, American Water Works Association, Denver, Colorado.
- ASTM. 2001. Standard test method for on-line measurement of turbidity below 5 NTU in water. D-6698-01.
- ASTM. 2003. Standard test method for determination of turbidity below 5 NTU in static mode. D-6855-03.
- AWWA Committee. 1983. Deterioration of water quality in large distribution reservoirs (open reservoirs). AWWA Committee on Control of Water Quality in Transmission and Distribution Systems. J. AWWA. June, pg. 313–8.
- AWWA, USEPA, AWWARF, AMWA, ASDWA, and NAWC. 2001. Partnership for Safe Water, Phase IV Procedures and Application Package. August.
- Barwick, R.S., D.A. Levy, G.F. Craun, M.J. Beach, and R.L. Calderon. 2000. Surveillance for waterborne-disease outbreaks—United States, 1997–1998. Morbidity and Mortality Weekly Report. 49(SS04):1–35.
- Battigelli, D. and M. Sobsey. 1993. The inactivation of Hepatitis A virus, poliovirus, and coliphage MS2 by lime softening and chlorine/monochloramine disinfection. Proceedings of the Water Quality Technology Conference of the American Water Works Association, Denver, CO.
- Bergmire-Sweat, D., K. Wilson, L. Marengo, Y. Lee, W. MacKenzie, J. Morgan, K. Von Alt, T. Bennett, V. Tsang, and B. Furness. 1999. Cryptosporidiosis in Brush Creek: Describing the epidemiology and causes of a large outbreak in Texas. Proceedings, International Conference on Emerging Infectious Diseases, Milwaukee, WI, American Water Works Association, Denver, Colorado.
- Bern, C., Y. Ortega, W. Checkley, J. Roberts, A. Lescano, L. Cabrera, M. Verastegui, E. Black, C. Sterling, and H. Gilman. 2002. Epidemiologic differences between cyclosporiasis and cryptosporidiosis in Peruvian children. Emerging Infectious Diseases. 8:6:581–5.
- Bertolucci, G., G. Gilli, E. Carraro, D. Giacosa, and M. Puppo. 1998. Influence of raw water storage on Giardia, *Cryptosporidium* and nematodes. Wat. Sci. Technol. 37:2:261–7.
- Boller, M. 1993. Filter mechanisms in roughing filters. Aqua. 42:3.
- Bukhari, Z., T. Hargy, J. Bolton, B. Dussert, and J. Clancy. 1999. Medium-pressure UV for oocyst inactivation. J. AWWA. 91:3:86–94.
- Burlingame, G., M. Pickel, and J. Roman. 1998. Practical applications of turbidity monitoring. J. AWWA. 90:8:57–69.
- Campbell, A., L. Robertson, M. Snowball, and H. Smith. 1995. Inactivation of oocysts of *Cryptosporidium parvum* by ultraviolet irradiation. Wat. Res. 29:11:2583–6.
- Campbell, A. and P. Wallis. 2002. The effect of UV irradiation on human derived *Giardia lamblia* cysts. Wat. Res. 36:4:963–9.
- Casemore, D. 1990. Epidemiological aspects of human cryptosporidiosis. Epidemiol. Infect. 104:1–28.
- CDC. 1993. Surveillance for Waterborne-Disease Outbreaks—United States, 1991–1992. MMWR. 42/SS-5:1–22.
- CDC. 1996. Surveillance for Waterborne-Disease Outbreaks—United States, 1993–1994. MMWR. 45/SS-1:1–33.
- CDC. 1998. Surveillance for Waterborne-Disease Outbreaks—United States, 1995–1996. MMWR. 47/SS-5:1–33.
- CDC. 2000. Surveillance for Waterborne-Disease Outbreaks—United States, 1997–1998. MMWR. 49/SS-4:1–36.
- CDC. 2001. Preliminary FoodNet Data on the Incidence of Foodborne Illnesses—Selected Sites, United States, 2000. MMWR. 50(13):241–246.
- CEC (Clancy Environmental Consultants). 2002. UV Disinfection of *Cryptosporidium* and MS2 coliphage in Catskill-Delaware Water. Report to Hazen and Sawyer.
- Chalmers, R., K. Elwin, A. Thomas, and D. Joynson. 2002. Infection with unusual types of *Cryptosporidium* is not restricted to immunocompromised patients. J. Infectious Disease. 185:270–1.
- Chappell, C., P. Okhuysen, C. Sterling, C. Wang, W. Jakubowski and H. Dupont. 1999. Infectivity of *Cryptosporidium parvum* in healthy adults with pre-existing anti-C. Parvum serum immunoglobulin G. Am. J. Trop. Med. Hyg. 60:157–164.
- Giardelli, C. 1996a. Giardia and *Cryptosporidium* challenge of the HIF-14 vessel and PP-D-1 cartridges. Analytical Services, Inc., Williston, VT.
- Giardelli, C. 1996b. Giardia and *Cryptosporidium* challenge of the HUR-170-HP filter. Analytical Services, Inc., Williston, VT.
- Cicirello, H., K. Kehl, D. Addiss, M. Chusid, R. Glass, J. Davis, and P. Havens. 1997. Cryptosporidiosis in children during a massive waterborne outbreak in Milwaukee, Wisconsin: Clinical, laboratory and epidemiologic findings. Epidemiol. Infect. 119 (1): 53–60.
- Clancy Environmental Consultants. 2002. CWRWS MPA, Giardia, and *Cryptosporidium* results, July-Oct. Draft report.
- Clancy, J., M. Marshall, and J. Dyksen. 1997. Innovative electrotechnologies for inactivation of *Cryptosporidium*. Abstract, International Symposium on Waterborne *Cryptosporidium*. March 2–5, 1997. Newport Beach, CA.
- Clancy, J., Z. Bukhari, T. Hargy, M. Thomas, J. Bolton, B. Dussert. 1998. Inactivation of *Cryptosporidium parvum* Oocysts Using Medium-Pressure Ultraviolet Light in Bench and Pilot Scale Studies. Proceedings 1998 American Water Works Association Water Quality Technology Conference, San Diego, CA, November 1–4.
- Clancy, J., Z. Bukhari, T. Hargy, J. Bolton, B. Dussert, and M. Marhsall. 2000. Using UV to inactivate *Cryptosporidium*. J. AWWA. 92:9:97–104.
- Clancy, J., T. Hargy, D. Battigelli, M. Marshall, D. Korich, and W. Nicholson. 2002. Susceptibility of Multiple Strains of *C. parvum* to UV Light. Published by the American Water Works Association Research Foundation, Denver, CO.
- Clark, R., M. Sivagansan, E. Rice, and J. Chen. 2002a. Development of a Ct equation for the inactivation of *Cryptosporidium* oocysts with ozone. Wat. Res. 36: 3141–3149.
- Clark, R., M. Sivagansan, E. Rice, and J. Chen. 2002b. Development of a Ct equation for the inactivation of *Cryptosporidium* oocysts with chlorine dioxide. Wat. Res. (in press).
- Collins, M., J. Cole, C. Westerund, and D. Paris. 1994. Assessing roughing filtration design variables. Water Supply. 12:1–2.
- Collins, M., P. Dwyer, A. Margolin, and S. Hogan. 1996. Assessment of MS2 bacteriophage virus, *Giardia cyst*, and

- Cryptosporidium* oocyst removal by hollow fiber microfiltration (polysulfone) membranes. Proceedings AWWA Membrane Conference, Reno, NV.
- Connell, K. C. Rodgers, H. Shank-Givens, J. Scheller, M. Pope, and K. Miller. 2000. Building a better protozoa data set. J. AWWA. 92(10):30-43.
- Cornwell, D. and M. LeChevallier (2002). Treatment options for removal of *Giardia*, *Cryptosporidium*, and other contaminants in recycled backwash water. American Water Works Association Research Foundation, Denver, CO.
- Corso, P., M. Kramer, K. Blair, D. Addiss, J. Davis, A. Haddix. 2003. The cost of illness associated with the massive waterborne outbreak of *Cryptosporidium* infections in 1993 in Milwaukee, Wisconsin. Emerging Infectious Diseases. 9:4:426-31.
- Craik, S., G. Finch, J. Bolton, and M. Belosevic. 2000. Inactivation of *Giardia muris* cysts using medium-pressure ultraviolet radiation in filtered drinking water. Wat. Res. 34:18:4325-32.
- Craik, S., D. Weldon, G. Finch, J. Bolton, and M. Belosevic. 2001. Inactivation of *Cryptosporidium parvum* oocysts using medium- and low-pressure ultraviolet radiation. Wat. Res. 35:1387-98
- Craun, F., and R. Calderon. 1996. Microbial risks in groundwater systems: Epidemiology of waterborne outbreaks. Under the Microscope: Examining microbes in groundwater. Proceedings of the Groundwater Foundation's 12th Annual Fall Symposium, Boston, September.
- Craun, G., S. Hubbs, F. Frost, R. Calderon, and S. Via. 1998. Waterborne outbreaks of cryptosporidiosis. J. AWWA. 90(9):81-91.
- Current, W., L. Reese, N. Ernst, J. Bailey, M. Heyman, and W. Weinstein. 1983. Human cryptosporidiosis in immunocompetent and immunodeficient persons: studies of an outbreak and experimental transmission. New England Journal of Medicine. 308(21):1252-7.
- Current, W. 1986. *Cryptosporidium*: Its biology and potential for environmental transmission. Crit. Rev. in Env. Control. 17:1:21-51.
- Drozd, C. and J. Scharzbrod. 1997. Removal of *Cryptosporidium* from river water by crossflow microfiltration: a pilot scale study. Wat. Sci. and Tech. 35(11-12):391-5.
- Dugan, N., K. Fox, R. Miltner, D. Lytle, D. Williams, C. Parrett, C. Feld, and J. Owens. 1999. Control of *Cryptosporidium* oocysts by steady-state conventional treatment. Proceedings of the U.S. Environmental Protection Agency 6th National Drinking Water and Wastewater Treatment Technology Transfer Workshop, Kansas City, MO, August 2-4.
- Dugan, N., K. Fox, J. Owens, and R. Miltner. 2001. Controlling *Cryptosporidium* oocysts using conventional treatment. J. AWWA. 93:12::64-76.
- DuPont, H., C. Chappell, C. Sterling, P. Okhuysen, J. Rose, and W. Jakubowski. 1995. The Infectivity of *Cryptosporidium parvum* in healthy volunteers. New Eng. J. Med. 332(13):855-859.
- Dwyer, P., S. Heffron, M. Arenberg, and R. Collins. 2001. High level *Cryptosporidium parvum* oocyst challenge of Aria Septra CB filter module with respect to filter membrane bubble point and pressure-hold integrity test data. University of New Hampshire, Durham, NH.
- Edzwald, J. and M. Kelly. 1998. Control of *Cryptosporidium* from reservoirs to clarifiers to filters. Wat. Sci. Technol. 37(2):1-8.
- Embrey, M. 1999. Adenovirus in drinking water, literature summary. Final report. Prepared by The George Washington University School of Public Health and Health Services, Department of Environmental and Occupational Health, Washington, DC.
- Emelko, M., P. Huck, and R. Slawson. 1999. Design and Operational Strategies for Optimizing *Cryptosporidium* Removal by Filters. Proceedings of 1999 Water Quality Technology Conference, American Water Works Association, Denver, CO.
- Emelko, M., P. Huck, and I. Douglas, and J. van den Oever. 2000. *Cryptosporidium* and Microsphere Removal During Low Turbidity End-of-Run and Early Breakthrough Filtration. Proceeding Of Water Quality Technology Conference, American Water Works Association, Denver, CO.
- Enriquez, C. and C. Greba. 1999. Evaluation of the Osmonic Water Purification Filters FGF, FAP and SXE in their Ability to Remove *Cryptosporidium parvum* Oocysts. Final Report. University of Arizona, Tuscon, AZ.
- Fayer, R., and B. Ungar. 1986. *Cryptosporidium spp.* and cryptosporidiosis. Microbial Review. 50(4):458-483.
- Fogel, D., J. Isaac-Renton, R. Guasparini, W. Moorehead, and J. Ongerth. 1993. Removing *Giardia* and *Cryptosporidium* by slow sand filtration. J. AWWA. 85:11:77-84.
- Fox, K., N. Dugan, R. Miltner, D. Lytle, D. Williams, C. Parrett, C. Feld, J. Owens, E. Rice, and C. Johnson. 1998. Comparative removal of *Cryptosporidium* and surrogates in a low flow pilot plant system. Proceedings of the Water Quality Technology Conference, American Water Works Association, Denver, CO.
- Gerba, C., J. Rose, and C. Haas. 1996. Sensitive populations: who is at the greatest risk? International Journal of Food Microbiology: 30(1-2), 10pp.
- Geldreich, E. 1990. Microbiological Quality, Control in Distribution Systems In: Water Quality and Treatment 4th Edition. FW Pontius, ed. McGraw-Hill, Inc., New York, NY.
- Goodrich, J., S. Li, and B. Lykins. 1995. Cost and Performance Evaluations of Alternative Filtration Technologies for Small Communities. Proceedings of the Annual Conference of the American Water Works Association, Denver, CO.
- Graczyk, T.K. Cranfield, M.R., Fayer, R. and Anderson, M.S. 1996. Viability and Infectivity of *Cryptosporidium parvum* Oocysts are Retained Upon Intestinal Passage Through a Refractory Avian Host. Applied and Environmental Microbiology 62(9):3234-3237.
- Great Lakes Instruments, 1992. Analytical Method for Turbidity Measurement: Great Lakes Instrument Method 2, GLL, Milwaukee, WI. 8pp.
- Gregory, R. and T. Zabel. 1990. Sedimentation and Flotation in Water Quality and Treatment: A Handbook of Community Water Supplies. F.W. Pontious, ed. American Water Works Assoc. 4th ed. New York: McGraw Hill. 427-444.
- Haas, C.N., C.S. Crockett, J.B. Rose, C.P. Gerba and A.M. Fazil. 1996. Assessing the Risk Posed by Oocystsin Drinking Water. J. AWWA. 88:9:131-136.
- Hall T., J. Pressdee, and E. Carrington. 1994. Removal of *Cryptosporidium* oocysts by water treatment processes. Report No. FR0457, Foundation for Water Research, Bucks, UK.
- Hancock, C., J. Rose, and M. Callahan. 1998. Crypto and *Giardia* in U.S. groundwater. J. AWWA. 90(3):58-61.
- Harrington W., A. Krupnick, and W. Spofford. 1985. The benefits of preventing an outbreak of giardiasis due to drinking water contamination. Resources for the Future Report.
- Harrington, G., H. Chen, A. Harris, I. Xagoraki, D. Battigelli, and J. Standridge. 2001. Removal of Emerging Waterborne Pathogens. American Water Works Association Research Foundation, Denver, CO.
- Hart, V., C. Johnson, and R. Letterman. 1992. An analysis of low-level turbidity measurements. J. AWWA. 84(12):40-45.
- Harter, T., S. Wagner and E. Atwill. 2000. Colloid transport and filtration of *Cryptosporidium parvum* in sandy soils and aquifer sediments. Environ. Sci. Technol. 34:62-70.
- Havelaar, A., M. van Olphen, and J. Schijven. 1995. Removal and inactivation of viruses by drinking water treatment processes under full scale conditions, Wat. Sci. Technol. 31:55062.
- Hayes, S., E. Rice, M. Ware, and F. Schaefer, III. 2003. Low pressure ultraviolet studies for inactivation of *Giardia muris* cysts. Journal of Applied Microbiology. 94:54-59.
- Heijbel, H., K. Slaine, B. Seigel, P. Wall, S. McNabb, W. Gibbons, and G. Istre. 1987. Outbreak of diarrhea in a day care center with spread to household members: The role of *Cryptosporidium*. Pediatr. Infect. Dis. J. 6(6):532-535.
- Hirata, T. and A. Hashimoto. 1998. Experimental assessment of the efficacy of microfiltration and ultrafiltration for *Cryptosporidium* removal. Wat. Sci. Tech. 38(12):103-7.
- Hoxie, N., J. Davis, J. Vergeront, R. Nashold, and K. Blair. 1997. Cryptosporidiosis-associated mortality following a massive waterborne outbreak in Milwaukee, Wisconsin. Amer. J. Publ. Health. 87(12):2032-2035.
- Huck, P.M., B. Coffey, C. O'Melia, and M. Emelko. 2000. Removal of *Cryptosporidium* by Filtration Under Conditions of Process Challenge. Proceedings from the Water Quality Technology Conference of the American Water Works Association, Denver, CO.
- Jacangelo, J., S. Adham and J. Laine. 1995. Mechanism of *Cryptosporidium*, *Giardia*, and MS2 virus removal by MF and UF. J. AWWA 87(9):107-21.

- Juraneck, D. 1995. Cryptosporidiosis: sources of infection and guidelines for prevention. *Clinical Infectious Diseases*: 21(1).
- Kashinkunti, R., D. Metz, K. Linden, M. Sobsey, M. Moran, and A. Samuelson. 2002. Microbial Inactivation Strategies for the Future: UV, Chlorine, and DBPs. Proceedings of the American Water Works Association Water Quality Technology Conference, Seattle, WA, Nov. 10–14.
- Kato, S., M. Jenkins, W. Ghiorse, E. Fogarty, and D. Bowman. 2001. Inactivation of *Cryptosporidium parvum* oocysts in field soil. *Southeast Asian J. Trop. Med. Public Health*. 32(2):183–9.
- Katsumata, T., D. Hosea, I. Ranuh, S. Uga, T. Yanagi, and S. Kohno. 2000. Short report: possible *Cryptosporidium muris* infection in humans. *Am. J. Trop. Med. Hyg.* 62:1:70–2.
- Kelley, M., P. Warrier, J. Brokaw, K. Barrett, and S. Komisar. 1995. A study of two U.S. Army installation drinking water sources and treatment systems for the removal of *Giardia* and *Cryptosporidium*. Proceedings of the Annual Conference of the American Water Works Association, Denver, CO.
- Ketelaars, H., G. Medema, L. van Breemen, D. Van der Kooij, P. Nobel, and P. Nuhn. 1995. Occurrence of *Cryptosporidium* Oocysts and *Giardia* Cysts in the River Meuse and removal in the Biesbosch Reservoirs. *Aqua*. 44:108–111.
- Landis, H., J. Thompson, J. Robinson, and E. Bltachley. 2000. Inactivation responses of *Cryptosporidium parvum* to UV radiation and gamma radiation. Proceedings AWWA Water Quality Technical Conference, Salt Lake City, UT, November 5–9.
- LeChevallier, M., W. Norton, and R. Lee. 1991. *Giardia* and *Cryptosporidium* spp. in filtered drinking water supplies. *Appl. Environ. Microbiol.* 57(9):2617–2621.
- LeChevallier, M. and W. Norton. 1992. Examining relationships between particle counts and *Giardia*, *Cryptosporidium* and turbidity. *J. AWWA*. 84(120):52–60.
- LeChevallier, M. and W. Norton. 1995. *Giardia* and *Cryptosporidium* in raw and finished water. *J. AWWA*. 87(9):54–68.
- LeChevallier, M., W. Norton, and T. Atherholt. 1997. Protozoa in open reservoirs. *J. AWWA*. 89(9):84–96.
- LeChevallier, M.W., G. D. Di Giovanni, J.L. Clancy, Z. Bukhari, S. Bukhari, J.S. Rosen, J. Sobrinho, M.M. Frey. 2003. Comparison of Method 1623 and Cell Culture-PCR for Detection of *Cryptosporidium* spp. in Source Waters. *J. Appl. Environ. Microbiol.* 69:2:971–979.
- Lederberg, J. Editor. 1992. *Encyclopedia of Microbiology*. Vol 2. Academic Press, Inc. New York. Enteroviruses. pp. 69–75.
- Leland, D., J. McAnulty, W. Keene, and G. Stevens. 1993. A cryptosporidiosis outbreak in a filtered-water supply. *J. AWWA*. 85(6):34–42.
- Letterman R., C. Johnson, S. Viswanathan, and J. Dwarakanathan. 2001. A study of low level turbidity measurements. Published by the American Water Works Association Research Foundation, Denver, CO.
- Li, S., J. Goodrich, J. Owens, G. Willeke, F. Schaefer and R. Clark. 1997. Reliability of surrogates for determining *Cryptosporidium* removal. *J. AWWA*. 89(5):90.
- Li, H., G. Finch, D. Smith, and M. Belosevic. 2001. Sequential Disinfection Design Criteria for Inactivation of *Cryptosporidium* Oocysts in Drinking Water. American Water Works Association Research Foundation, Denver, CO.
- Linden, K., G. Shin, G. Faubert, W. Cairns, and M. Sobsey. 2002. UV disinfection of *Giardia lamblia* in water. *Environ. Sci. Technol.* 36(11):2519–2522.
- Logsdon, G., M. Frey, T. Stefanich, S. Johnson, D. Feely, J. Rose, and M. Sobsey. 1994. The removal and disinfection efficiency of lime softening processes for *Giardia* and viruses. American Water Works Association Research Foundation, Denver, CO.
- Long, W.R. 1983. Evaluation of Cartridge Filters for the Removal of *Giardia lamblia* Cyst Models from Drinking Water Systems. *Journal of Environmental Health*. 45(5):220.
- Lykins, B., J. Adams, J. Goodrich, and R. Clark. 1994. Meeting federal regulations with MF/UF—EPA ongoing projects. Microfiltration II Conference. San Diego, CA. November 12–13.
- MacKenzie, W.R. and N.J. Hoxie, M.E. Proctor, M.S. Gradus, K.A. Blair, D.E. Peterson, J.J. Kazmierczak, D.A. Addiss, K.R. Fox, J.B. Rose, and J.P. Davis. 1994. A massive outbreak of *Cryptosporidium* infection transmitted through the public water supply. *New England Journal of Medicine* 331(3): 161–167.
- Malley, J., J. Shaw, and J. Ropp. 1995. Evaluation of the by-products produced by the treatment of groundwaters with ultraviolet radiation. American Water Works Association Research Foundation, Denver, CO.
- Mazounie, P., F. Bernazeau, and P. Alla. 2000. Removal of *Cryptosporidium* by High Rate Contact Filtration: The Performance of the Prospect Water Filtration Plant During the Sydney Water Crisis. *Water Science and Technology*. 41(7):93–101.
- McDonald, A., W. MacKenzie, D. Addiss, M. Gradus, G. Linke, E. Zembowski, M. Hurd, M. Arrowood, P. Lammie, and J. Priest. 2001. *Cryptosporidium parvum*-specific antibody responses among children residing in Milwaukee during the 1993 waterborne outbreak. *Jour. Infectious Diseases* 183:1373–1379.
- McTigue, N., M. LeChevallier, H. Arora, and J. Clancy. 1998. National assessment of particle removal by filtration. American Water Works Association Research Foundation, Denver, CO.
- Medema, G., M. Bahar, and F. Schets. 1997. Survival of *Cryptosporidium parvum*, *Escherichia Coli*, Faecal Enterococci, and *Clostridium perfringens* in river water: Influence of temperature and autochthonous microorganisms. *Wat. Sci. Technol.* 35(11–12):249–252.
- Medema, G., M. Juhasz-Hoterman, and J. Luitjen. 2000. Removal of micro-organisms by bank filtration in a gravel-sand soil. Proceedings of the International Riverbank Filtration Conference, November 2–4, Dusseldorf, W. Julich and J. Schubert, eds., Internationale Arbeitsgemeinschaft der Wasserwerke im Rheineinzugsgebiet, Amsterdam.
- Medema, G., and J. Schijven. 2001. Modeling the sewage discharge and dispersion of *Cryptosporidium* and *Giardia* in surface water. *Wat. Res.* 35(18):4307–16.
- Messner, M., C. Chappell, and P. Okhuysen. 2001. Risk assessment for *Cryptosporidium*: A hierarchical Bayesian analysis of human dose-response data. *Wat. Res.* 35(16):3934–3940.
- Messner, M. 2003. Estimating lot variability (Chlorine dioxide CT table). USEPA Report. April 30, 2003.
- Millard, P., K. Gensheimer, D. Addiss, D. Sosin, G. Beckett, A. Houck-Jankoski, and A. Hudson. 1994. An outbreak of cryptosporidiosis from fresh-pressed apple cider. *JAMA*. 272:1592–1596.
- Mofidi, A., E. Meyer, P. Wallis, C. Chou, B. Meyer, S. Ramalingam, and B. Coffey. 2002. The effect of UV light on the inactivation of *Giardia lamblia* and *Giardia muris* cysts as determined by animal infectivity assay. *Wat. Res.* 36(8):2098–2108.
- Morgan-Ryan, U., A. Fall, L. Ward, N. Hijjawi, I. Sulaiman, R. Fayer, R. Thompson, M. Olson, A. Lal, and L. Xiao. 2002. *Cryptosporidium hominis* n. sp. (Apicomplexa: Cryptosporidiidae) from *Homo sapiens*. *Journal of Eukaryotic Microbiology*. 49:6:443–440.
- Muller T.B., F.J. Frost, G.F. Craun, and R.L. Calderon. 2001. Serological Responses to *Cryptosporidium* Infection. *Letters to the Editor. Infection and Immunity*. 69:3.
- Najm, I., J. Rosen, S. Via, and J. Sobrinho. 2002. Quantifying the Contribution of Experimental and Analytical Errors to the Overall Data Scatter Observed During the Inactivation of *Cryptosporidium* with Ozone. Draft report. July 23.
- Nieminski, E. and J. Ongerth. 1995. Removing *Giardia* and *Cryptosporidium* by conventional treatment and direct filtration. *J. AWWA* 87(9):96–106.
- Nieminski, E. and W. Bellamy. 2000. Application of Surrogate Measures to Improve Treatment Plant Performance. American Water Works Association Research Foundation, Denver, CO.
- NSF International. 2001a. Environmental technology verification report, physical removal of *Giardia*- and *Cryptosporidium*-sized particles in drinking water: Rosedale Products, Inc. Bag and Cartridge Filter System Model GFS–302P2–150S-ESBB. (01/08/PEADW395), Ann Arbor, MI.
- NSF International. 2001b. Environmental technology verification report, physical removal of *Giardia*- and *Cryptosporidium*-sized particles in drinking water: Lapoint Industries Aqua-Rite Potable Water Filtration System. (01/08/PEADW395), Ann Arbor, MI.
- NSF International. 2002a. Proposed Modification to ETV Protocol for Equipment Verification Testing for Physical Removal of Microbiological and Particulate Contaminants, Test Plan for Membrane Filtration. Ann Arbor, MI.
- NSF International. 2002b. Environmental Technology Verification Protocol for Equipment Verification Testing for Physical Removal of Microbiological and

- Particulate Contaminants. (40CFR35.6450), Ann Arbor, MI.
- Okhuysen, P.C., C.L. Chappell, C.R. Sterling, W. Jakubowski, and H.L. DuPont. 1998. Susceptibility and Serologic Response of Healthy Adults to Reinfection with *Cryptosporidium parvum*. American Society for Microbiology. 66:2:441-443.
- Okhuysen, P.C., C.L. Chappell, J.H. Crabb, C.R. Sterling, and H.L. DuPont. 1999. Virulence of three distinct *Cryptosporidium parvum* isolates for healthy adults. Journal of Infectious Diseases. 180:4:1275-1281.
- Ong, C., D. Eisler, A. Alikhani, V. Fung, J. Tomblin, W. Bowie, and J. Isaac-Renton. 2002. Novel *Cryptosporidium* genotypes in sporadic cryptosporidiosis cases: first report of human infections with a cervine genotype. Emerg. Infect. Diseases 8:3:263-268.
- Ongerth, J., 1989. *Giardia* cyst concentration in river water. J. AWWA. 81(9):81-86.
- Ongerth, J. and J. Pecoraro. 1995. Removing *Cryptosporidium* using multimedia filters. J. AWWA. 87(12):83-89.
- Ongerth, J. and P. Hutton. 1997. DE filtration to remove *Cryptosporidium*. J. AWWA. 89(12):39-46.
- Ongerth, J. and P. Hutton. 2001. Testing of diatomaceous earth filtration for removal of *Cryptosporidium* oocysts. J. AWWA. 93(12): 54-63.
- Oppenheimer J., E. Aieta, R. Trussell, J. Jacangelo, and N. Najim. 2000. Evaluation of *Cryptosporidium* inactivation in natural waters. American Water Works Association Research Foundation, Denver, CO.
- Oppenheimer, J., T. Gillogly, G. Sotarlik, and R. Ward. 2002. Comparing the efficiency of low and medium pressure UV light for inactivating *Giardia muris* and *Cryptosporidium parvum* in waters with low and high levels of turbidity. Proceedings of the Annual Conference of the American Water Works Association, Denver, CO.
- Osewe, P., D. Addis, K. Blair, A. Hightower, M. Kamb, and J. Davis. 1996. Cryptosporidiosis in Wisconsin: A case-control study of post-outbreak transmission. Epidemiol. Infect. 117:297-304.
- Owen, C.A., J.S. Taylor, C. Robert, and C.R. Reiss. 1999. Microbial Challenge of Integrated Membrane System Large Scale Pilot Plants Treating a Highly Organic Surface Water. Proceedings of the Water Quality Technology Conference of the American Water Works Association, Tampa, FL.
- Owens J., R. Miltner, T. Slifko, and J. Rose. 1999. In vitro excystation and infectivity in mice and cell culture to assess chlorine dioxide inactivation of *Cryptosporidium* oocysts, in Proceedings of the Water Quality Technology Conference of the American Water Works Association, Denver, CO.
- Owens J., R. Miltner, E. Rice, C. Johnson, D. Dahling, F. Schaefer, and H. Shukairy. 2000. Pilot-scale ozone inactivation of *Cryptosporidium* and other microorganisms in natural water. Ozone Sci. Eng. 22:5:501-517.
- Pang, L., M. Close and M. Noonan. 1998. Rhodamine WT and *Bacillus subtilis* transport through an alluvial gravel aquifer. Ground Water. 36:112-122.
- Patania, N., Jacangelo, J., Cummings, L., Wilczak, A., Riley, K., and Oppenheimer, J. 1995. Optimization of Filtration for Cyst Removal. AWWARF. Denver, CO. 178pp.
- Patania, N., P. Mazounie, F. Bernazeau, G. Maclean, and P. Alla. 1999. Removal of *Cryptosporidium* by contact filtration: The Sydney experience. Proceedings of the Annual Conference of the American Water Works Association, Denver, CO.
- Payment, P. and E. Franco. 1993. Clostridium perfringens and somatic coliphages as indicators of the efficiency of drinking water treatment for viruses and protozoan cysts. Appl. Environ. Micro. 59(8):2418-2424.
- Peldszus, S., R. Souza, J. Bolton, B. Dussert, F. Smith, and S. Andrews. 2000. Impact of medium pressure UV-disinfection on the formation of low molecular weight organic by-products and nitrite, and the reduction of bromate. Proceedings, Water Quality Technology Conference of the American Water Works Association, Denver, CO.
- Pluntz, J. 1974. Health aspects of uncovered reservoirs. J. AWWA. August, pg. 432-7.
- Pope, M., M. Bussen, M. Feige, L. Shadix, S. Gonder, C. Rodgers, Y. Chambers, J. Pulz, K. Miller, K. Connell, and J. Standridge. 2003. Assessment of the effects of holding time and temperature on *E. coli* densities in surface water samples. Appl. Environ. Micro. (submitted).
- Qian S., M. Donnelly, D. Schmelling, M. Messner, K. Linden, and C. Cotton. 2003. Ultraviolet light inactivation of *Cryptosporidium* and *Giardia* in drinking water: a Bayesian meta-analysis. Environ. Sci. Technol. (submitted).
- Rennecker J., B. Marinas, J. Owens and E. Rice. 1999. Inactivation of *Cryptosporidium parvum* oocysts with ozone. Wat. Res. 33(11):2481-2488.
- Rice, E., K. Fox, R. Miltner, D. Lytle, and C. Johnson. 1996. Evaluating Plant Performance with Endospores. J. AWWA. 88(9):122-130.
- Rice, E. 2002. Nebraska aerobic spore and discharge results, Dec. 2001-Nov. 2002, unpublished data.
- Roessler, N. 1998. Control of *Cryptosporidium* in bottled water using cartridge filtration systems. Filtration & Separation. 35(1):37-39.
- Rose, J. 1997. Environmental ecology of *Cryptosporidium* and public health implications. Annual Rev. Public Health. 18:135-61.
- Ruffell K., J. Rennecker, and B. Marinas. 2000. Inactivation of *Cryptosporidium parvum* oocysts with chlorine dioxide. Wat. Res. 34(3):868-876.
- Sadar, M. 1999. Turbidimeter Instrument Comparison: Low-level Sample Measurements Technical Information Series. Hach Company. ap/dp 4/99 1ed rev1 D90.5 Lit No. 7063.
- Sattar, S., C. Chauvet, V. Springthorpe, D. Battigelli, M. Abbaszadegan, and M. LeChevallier. 1999. *Giardia* cyst and *Cryptosporidium* oocyst survival in watersheds and factors affecting inactivation. American Water Works Association Research Foundation, Denver, CO.
- Schaub, S., H. Hargett, M. Schmidt and W. Burrows. 1993. Reverse osmosis water purification unit: Efficacy of cartridge filters for removal of bacteria and protozoan cysts when RO elements are bypassed. U.S. Army Biomedical Research and Development Laboratory, Fort Detrick, Frederick, MD.
- Scheller, J. K. Connell, H. Shank-Givens, and C. Rodgers. 2002. Design, Implementation, and Results of USEPA's 70-utility ICR Laboratory Spiking Program. Information Collection Rule Data Analysis. McGuire, M., J. McLain, and A. Obolensky, eds.
- Schijven, J., W. Hoogenboezem, P. Nobel, G. Medema and A. Stakelbeek. 1998. Reduction of FRNA-bacteriophages and faecal indicator bacteria by dune infiltration and estimation of sticking efficiencies. Wat. Sci. Technol. 38:127-131.
- Schuler, P. and M. Ghosh. 1990. Diatomaceous earth filtration of cysts and other particulates using chemical additives. J. AWWA 82(12):67-75.
- Schuler, P. and M. Ghosh. 1991. Slow sand filtration of cysts and other particulates. Proceedings of the annual conference of the American Water Works Association, Denver, CO.
- Sethi V., P. Patnaik, P. Biswas, R. Clark, and E. Rice. 1997. Evaluation of optical detection methods for waterborne suspensions, J. AWWA. 89(2):98-112.
- Sharpless, C. and K. Linden. 2001. UV photolysis of nitrate: Effects of natural organic matter and dissolved inorganic carbon and implications for UV water disinfection. Environ. Sci. Technol. 35(14):2949-1955.
- Shin, G., K. Linden, M. Arrowood, and M. Sobsey. 2001. Low-Pressure UV Inactivation and DNA Repair Potential of *Cryptosporidium parvum* Oocysts. Appl. Environ. Microbiol. 67(7):3029-3032.
- Silverman, G., L. Nagy, and B. Olson. 1983. Variations in particulate matter, algae, and bacteria in an uncovered finished-drinking-water reservoir. J. AWWA. 75(4):191-5.
- Sivaganesan, M. 2003. Estimating lot variability for development of ozone CT table. USEPA Report. February 24, 2003.
- Solo-Gabriele, H. and S. Neumeister. 1996. U.S. outbreaks of cryptosporidiosis. J. AWWA. 88:76-86.
- Sommer, R., S. Appelt, W. Pribil, and T. Slifko. 2001. UV Irradiation in a Standard Laboratory Batch Apparatus (Wavelength 253.7 nm). Draft Report.
- Spano, F. L. Putignani, A. Crisanti, P. Sallicandro, U. Morgan, S. Le Blanco, L. Tchack, S. Tzipori, and G. Widmer. 1998. Multilocus genotype analysis of *Cryptosporidium parvum* isolates from different hosts and geographical origins. J. Clinical Microbiol. 36:11:3255-3259.
- States, S., K. Stadterman, L. Ammon, p. Vogel, J. Baldizar, D. Wright, L. Conley, and J. Sykora. 1997. Protozoa in river water: sources, occurrence, and treatment. J. AWWA. 89(9):74-83.
- Symons, J., L. Bradley, Jr., and T. Cleveland. 2000. The drinking water dictionary. American Water Works Association, Denver, CO.
- Tangerman, R., S. Gordon, P. Wiesner, and L. Kreckmanet. 1991. An outbreak of

- cryptosporidiosis in a day-care center in Georgia, *American Jour. of Epidemiology*. 133:471–476.
- Timms, S., J. Slade, and C. Fricker. 1995. Removal of *Cryptosporidium* by slow sand filtration. *Wat. Sci. Technol.* 31(5–6):81–84.
- Trimboli, P., J. Lozier, and W. Johnson. 1999. Demonstrating the integrity of a full scale microfiltration plant using a *Bacillus* spore challenge test. Proceedings of the American Water Works Association Membrane Technology Conference, Long Beach, CA.
- USEPA. 1986. Design Manual, Municipal Wastewater Disinfection. EPA/626/1–86/021.
- USEPA. 1989a. National Primary Drinking Water Regulations; Filtration, Disinfection; Turbidity, *Giardia lamblia*, Viruses, *Legionella*, and Heterotrophic Bacteria; Final Rule. Part II. Federal Register, 54:124:27486. (June 29, 1989).
- USEPA. 1989b. National Interim Primary Drinking Water Regulations; Total Coliform Rule; Final Rule. Part II. Federal Register, 54:124:27544. (June 29, 1989).
- USEPA. 1990. Reducing Risk: Setting Priorities and Strategies for Environmental Protection. USEPA Science Advisory Board (A–101), Washington, DC. Report No. SAB–EC–90–021 (September).
- USEPA. 1991. Optimizing Water Treatment Plant Performance Using the Composite Correction Program. EPA 625–6–91–027.
- USEPA. 1993. EPA Method 180.1. Nephelometric Method. EPA 600/R–93–100.
- USEPA. 1994. National Primary Drinking Water Regulations; Enhanced Surface Water Treatment Requirements. 59 FR 38832; July 29, 1994.
- USEPA. 1996a. National Interim Primary Drinking Water Regulations; Monitoring Requirements for Public Drinking Water Supplies; Final Rule. 61 FR 24354; May 14, 1996.
- USEPA. 1996b. ICR Microbial Laboratory Manual. EPA 600/R–95/178. April 1996.
- USEPA. 1997a. National Primary Drinking Water Regulations: Interim Enhanced Surface Water Treatment Rule Notice of Data Availability; Proposed Rule. 62 FR 59486, November 3, 1997.
- USEPA. 1997b. Technologies and Costs for the Microbial Recommendations of the MDBP Advisory Committee; Final Draft. Prepared for the Office of Ground Water and Drinking Water, Washington, DC by Science Applications International Corporation, McLean, VA. 185 pp.
- USEPA. 1998a. National Primary Drinking Water Regulations; Interim Enhanced Surface Water Treatment Rule. 63 FR 69477, December 16, 1998.
- USEPA. 1998b. National Primary Drinking Water Regulations; Stage 1 Disinfectants and Disinfection Byproducts Rule. 63 FR 69389; December 16, 1998.
- USEPA. 1998c. *Cryptosporidium* and *Giardia* Occurrence Assessment for the Interim Enhanced Surface Water Treatment Rule. EPA 815–B–98–005.
- USEPA. 1998d. Regulatory Impact Analysis for the Interim Enhanced Surface Water Treatment Rule. EPA–815–R–98–003.
- USEPA. 1998e. Water Supply Performance Evaluation Study #41. National Exposure Research Laboratory. Office of Research and Development.
- USEPA. 1998f. Revisions to State Primacy Requirements To Implement Safe Drinking Water Act Amendments; Final Rule. 63 FR 23361; April 28, 1998.
- USEPA. 1999a. Method 1622: *Cryptosporidium* in Water by Filtration/IMS/FA. EPA–821–R–99–001.
- USEPA. 1999b. Method 1623: *Cryptosporidium* and *Giardia* in Water by Filtration/IMS/FA. EPA–821–R–99–006.
- USEPA. 1999c. Revisions to the Unregulated Contaminant Monitoring Regulation for Public Water Systems. 64 FR 50556; September 17, 1999.
- USEPA. 1999d. Disinfection Profiling and Benchmarking Guidance Manual. EPA 815–R–99–013.
- USEPA. 1999e. Uncovered Finished Water Reservoirs Guidance Manual. EPA 815–R–99–011.
- USEPA. 2000a. Stage 2 Microbial and Disinfection Byproducts Federal Advisory Committee Agreement in Principle. 65 FR 83015; December 29, 2000.
- USEPA. 2000b. National Primary Drinking Water Regulations: Long Term 1 Enhanced Surface Water Treatment Rule; Proposed Rule. 65 FR 19046; April 10, 2000.
- USEPA. 2000c. U.S. Environmental Protection Agency. Guidelines for Preparing Economic Analyses. Washington, DC. EPA 240–R–00–003, September 2000.
- USEPA. 2000d. National Primary Drinking Water Regulations: Public Notification Rule; Final Rule. 65 FR 25982; May 4, 2000.
- USEPA. 2000e. SAB Report from the Environmental Economics Advisory Committee (EEAC) on EPA’s White Paper “Valuing the Benefits of Fatal Cancer Risk Reduction”. EPA–SAB–EEAC–00–013. July 27.
- USEPA. 2000f. Final Report of the Small Business Advocacy Review Panel on Stage 2 Disinfectants and Disinfection Byproducts Rule (Stage 2 DBPR) and Long Term 2 Enhanced Surface Water Treatment Rule (LT2ESWTR). June 23, 2000.
- USEPA. 2001a. National Primary Drinking Water; Filter Backwash Recycling Rule; Final Rule. 66 FR 31086; June 8, 2001. EPA–815–Z–01–001.
- USEPA. 2001b. *Cryptosporidium*: Human Health Criteria Document. EPA–822–R–01–008. March 2001.
- USEPA. 2001c. *Cryptosporidium*: Drinking Water Advisory. EPA–822–R–01–009. March 2001.
- USEPA. 2001d. *Cryptosporidium*: Risks for Infants and Children. February 23, 2001.
- USEPA. 2001e. Method 1622: “*Cryptosporidium* in Water by Filtration/IMS/FA” EPA–821–R–01–026, April 2001.
- USEPA. 2001f. Method 1623: “*Cryptosporidium* and *Giardia* in Water by Filtration/IMS/FA” EPA 821–R–01–025, April 2001.
- USEPA. 2001g. Pre-proposal Draft Preamble: Long Term 2 Enhanced Surface Water Treatment. November 27, 2001.
- USEPA. 2001h. Low-Pressure Membrane Filtration for Pathogen Removal: Application, Implementation and Regulatory Issues. EPA 815–C–01–001.
- USEPA. 2001i. Guidelines Establishing Test Procedures for the Analysis of Pollutants; Analytical Methods for Biological Pollutants in Ambient Water; Proposed Rule. **Federal Register**. August 30, 2001.
- USEPA. 2002a. National Primary Drinking Water Regulations: Long Term 1 Enhanced Surface Water Treatment Rule; Final Rule. **Federal Register**. January 14, 2002. 67 FR 1812. EPA 815–Z–02–001.
- USEPA. 2002b. Process for Designing a Watershed Initiative. 67 FR 36172, May 23, 2002.
- USEPA. 2002c. Laboratory Quality Assurance Evaluation Program for Analysis of *Cryptosporidium* Under the Safe Drinking Water Act; Agency Information Collection: Proposed Collection; Comment Request. **Federal Register**: March 4, 2002. 67 FR 9731.
- USEPA. 2003a. Economic Analysis for the Long Term 2 Enhanced Surface Water Treatment Rule Proposal. Prepared by The Cadmus Group USEPA. 2003b. Occurrence and Exposure Assessment for the Long Term 2 Enhanced Surface Water Treatment Rule Proposal. Prepared by The Cadmus Group.
- USEPA. 2003c. Technologies and Costs for Control of Microbial Pathogens and Disinfection Byproducts. Prepared by the Cadmus Group and Malcolm Pirnie.
- USEPA. 2003d. Ultraviolet Disinfection Guidance Manual. June 2003 Draft. Prepared by The Cadmus Group, Malcolm Pirnie, and Carollo Engineers.
- USEPA. 2003e. Membrane Filtration Guidance Manual. June 2003 Draft. Prepared by the Cadmus Group and Malcolm Pirnie.
- USEPA. 2003f. Long Term 2 Enhanced Surface Water Treatment Rule Toolbox Guidance Manual. June 2003 Draft. Prepared by The Cadmus Group.
- USEPA. 2003g. Source Water Monitoring Guidance Manual for Public Water System under the Long Term 2 Enhanced Surface Water Treatment Rule. June 2003 Draft. Prepared by Dyncorp.
- USEPA. 2003h. Microbial Laboratory Manual for the Long-Term 2 Enhanced Surface Water Treatment Rule. June 2003 Draft. Prepared by Dyncorp.
- USEPA. 2003i. Comparison of Method 1623 Recoveries Using Two Protozoa Matrix Spiking Procedures and the IDEXX Filtamax™ and Pall Gelman Envirochek™ HV Filters. Draft Report. February 2003.
- USEPA 2003j. Revised Method 1622: *Cryptosporidium* in Water by Filtration/IMS/FA. Draft for Comment. June 2003.
- USEPA. 2003k. Revised Method 1623: *Cryptosporidium* and *Giardia* in Water by Filtration/IMS/FA. Draft for Comment. June 2003.
- Van Breemen, L., H. Ketelaars, W. Hoogenboezem, and G. Medema. 1998. Storage reservoirs—a first barrier for pathogenic micro-organisms in The Netherlands. *Water Science and Technology*. 37(2):253–260.
- Wang, J., R. Song, and S. Hubbs. 2001. Particle removal through riverbank filtration process, in W. Julich and J.

Schubert, eds., Proceedings of the International Riverbank Filtration Conference, November 2-4, 2000, Dusseldorf, Germany, Internationale Arbeitsgemeinschaft der Wasserwerk im Rheineinzugsgebiet.

Wegelin, M., M. Boller, and R. Schertenleib. 1987. Particle Removal by Horizontal-Flow Roughing Filtration. *Aqua*. 35(2): 115-125.

Wegelin, M. 1988. Rouging gravel filters for suspended solids removal. *Slow Sand Filtration: Recent Developments in Water Treatment Technology*, N.J.D. Graham (Ed.) Ellis Horwood Ltd., Chichester, UK: 103-122.

West, T., P. Daniel, P. Meyerhofer, A. DeGraca, S. Leonard, and C. Gerba. 1994. Evaluation of *Cryptosporidium* Removal through High-Rate Filtration. Proceedings, Annual Conference of the American Water Works Association, Denver, CO.

Willocks, L., A. Crampin, L. Milne, C. Seng, M. Susman, R. Gair, M. Mouldsdales, S. Shafi, R. Wall, R. Wiggins, and N. Lightfoot. 1998. A large outbreak of cryptosporidiosis associated with a public water supply from a deep chalk borehole. *Communicable Disease and Public Health*. 1(4):239-43.

Yates, R., K. Scott, J. Green, J. Bruno, and R. De Leon. 1998. Using Aerobic Spores to Evaluate Treatment Plant Performance. Proceedings, Annual Conference of the American Water Works Association, Denver, CO.

Zheng, M., S. Andrews, and J. Bolton. 1999. Impacts of medium-pressure UV on THM and HAA formation in pre-UV chlorinated drinking water. Proceedings, Water Quality Technology Conference of the American Water Works Association, Denver, CO.

List of Subjects

40 CFR Part 141

Environmental protection, Chemicals, Indians-lands, Intergovernmental relations, Radiation protection, Reporting and recordkeeping requirements, Water supply.

40 CFR Part 142

Environmental protection, Administrative practice and procedure, Chemicals, Indians-lands, Radiation protection, Reporting and recordkeeping requirements, Water supply.

Dated: July 11, 2003.

Linda J. Fisher,

Acting Administrator.

For the reasons set forth in the preamble, title 40 chapter I of the Code

of Federal Regulations is proposed to be amended as follows:

PART 141—NATIONAL PRIMARY DRINKING WATER REGULATIONS

1. The authority citation for Part 141 continues to read as follows:

Authority: 42 U.S.C. 300f, 300g-1, 300g-2, 300g-3, 300g-4, 300g-5, 300g-6, 300j-4, 300j-9, and 300j-11.

2. Section 141.2 is amended by adding, in alphabetical order, definitions for Bag filters, Bank filtration, Cartridge filters, Flowing stream, Lake/reservoir, Membrane filtration, Off-stream raw water storage, Plant intake, Presedimentation, and Two-stage lime softening to read as follows:

§ 141.2 Definitions.

* * * * *

Bag filters are pressure-driven separation devices that remove particulate matter larger than 1 µm using an engineered porous filtration media through either surface or depth filtration. Bag filters are typically constructed of a non-rigid, fabric filtration media housed in a pressure vessel in which the direction of flow is from the inside of the bag to outside.

Bank filtration is a water treatment process that uses a pumping well to recover surface water that has naturally infiltrated into ground water through a river bed or bank(s). Infiltration is typically enhanced by the hydraulic gradient imposed by a nearby pumping water supply or other well(s).

* * * * *

Cartridge filters are pressure-driven separation devices that remove particulate matter larger than 1 µm using an engineered porous filtration media through either surface or depth filtration. Cartridge filters are typically constructed as rigid or semi-rigid, self-supporting filter elements housed in pressure vessels in which flow is from the outside of the cartridge to the inside.

* * * * *

Flowing stream is a course of running water flowing in a definite channel.

* * * * *

Lake/reservoir refers to a natural or man made basin or hollow on the Earth's surface in which water collects or is stored that may or may not have a current or single direction of flow.

* * * * *

Membrane filtration is a pressure-driven or vacuum-driven separation process in which particulate matter larger than 1 µm is rejected by an engineered barrier primarily through a size exclusion mechanism, and which has a measurable removal efficiency of a target organism that can be verified through the application of a direct integrity test. This definition includes the common membrane technologies of microfiltration (MF), ultrafiltration (UF), nanofiltration (NF), and reverse osmosis (RO).

* * * * *

Off-stream raw water storage refers to an impoundment in which water is stored prior to treatment and from which outflow is controlled.

* * * * *

Plant intake refers to the works or structures at the head of a conduit through which water is diverted from a source (e.g., river or lake) to the treatment plant.

* * * * *

Presedimentation is a preliminary unit process used to remove gravel, sand and other particulate material from the source water through settling before it enters the main treatment plant.

* * * * *

Two-stage lime softening refers to a process for the removal of hardness by the addition of lime and consisting of two distinct unit clarification processes in series prior to filtration.

* * * * *

3. Appendix A to Subpart Q of part 141 is amended in section I, Part A by adding entry number 10:

Subpart Q—Public Notification of Drinking Water Violations.

APPENDIX A TO SUBPART Q OF PART 141—NPDWR VIOLATIONS AND OTHER SITUATIONS REQUIRING PUBLIC NOTICE ¹

Contaminant	MCL/MRDL/TT violations ²		Monitoring and testing procedure violations	
	Tier of public notice required	Citation	Tier of public notice required	Citation

I. Violations of National Primary Drinking Water Regulations (NPDWR)³:

A. Microbiological Contaminants

APPENDIX A TO SUBPART Q OF PART 141—NPDWR VIOLATIONS AND OTHER SITUATIONS REQUIRING PUBLIC NOTICE¹—Continued

Contaminant	MCL/MRDL/TT violations ²		Monitoring and testing procedure violations	
	Tier of public notice required	Citation	Tier of public notice required	Citation
10. LT2ESWTR violations	2	141.720–141.729	3	141.701–141.707; 141.713; 141.730

¹Violations and other situations not listed in this table (e.g., reporting violations and failure to prepare Consumer Confidence Reports) do not require notice, unless otherwise determined by the primary agency. Primary agencies may, at their option, also require a more stringent public notice tier (e.g., Tier 1 instead of Tier 2 or Tier 2 instead of Tier 3) for specific violations and situations listed in this Appendix, as authorized under § 141.202(a) and § 141.203(a).

²MCL—Maximum contaminant level, MRDL—Maximum residual disinfectant level, TT—Treatment technique

³The term Violations of National Primary Drinking Water Regulations (NPDWR) is used here to include violations of MCL, MRDL, treatment technique, monitoring, and testing procedure requirements.

4. Part 141 is amended by adding a new subpart W to read as follows:

Subpart W—Enhanced Filtration and Disinfection for *Cryptosporidium*

General Requirements

- 141.700 Applicability.
- 141.701 General requirements.

Source Water Monitoring Requirements

- 141.702 Source water monitoring.
- 141.703 Sampling schedules.
- 141.704 Sampling locations.
- 141.705 Analytical methods.
- 141.706 Requirements for use of an approved laboratory.
- 141.707 Reporting source water monitoring results.
- 141.708 Previously collected data.
- 141.709 Bin classification for filtered systems.

Disinfection Profiling and Benchmarking Requirements

- 141.710 [Reserved]
- 141.711 Determination of systems required to profile.
- 141.712 Schedule for disinfection profiling requirements.
- 141.713 Developing a profile.
- 141.714 Requirements when making a significant change in disinfection practice.

Treatment Technique Requirements

- 141.720 Treatment requirements for filtered systems.
- 141.721 Treatment requirements for unfiltered systems.
- 141.722 Microbial toolbox options for meeting *Cryptosporidium* treatment requirements.
- 141.723 [Reserved]

141.724 Requirements for uncovered finished water storage facilities.

Requirements for Microbial Toolbox Components

- 141.725 Source toolbox components.
- 141.726 Pre-filtration treatment toolbox components.
- 141.727 Treatment performance toolbox components.
- 141.728 Additional filtration toolbox components.
- 141.729 Inactivation toolbox components.

Reporting and Recordkeeping Requirements

- 141.730 Reporting requirements.
- 141.731 Recordkeeping requirements.

Subpart W—Enhanced Filtration and Disinfection for *Cryptosporidium*

General Requirements

§ 141.700 Applicability.

The requirements of this subpart apply to all subpart H systems. Failure to comply with any requirement of this subpart is a violation and requires public notification.

§ 141.701 General requirements.

(a) All subpart H systems, including wholesale systems, must characterize their source water to determine what (if any) additional treatment is necessary for *Cryptosporidium*, unless they meet the criteria in either paragraph (f) or (g) of this section.

(b) Systems serving at least 10,000 people that currently provide filtration or that are unfiltered and required to install filtration must conduct source water monitoring that includes

Cryptosporidium, *E. coli*, and turbidity sampling and comply with the treatment requirements in § 141.720.

(c) Systems serving fewer than 10,000 people that currently provide filtration or that are unfiltered and required to install filtration must conduct source water monitoring consisting of *E. coli* sampling or sampling of an alternative indicator approved by the State. If the annual mean concentration of *E. coli* exceeds the levels specified in § 141.702(b), or if the level of a State-approved alternate indicator exceeds a State-approved alternative indicator trigger level, systems must conduct *Cryptosporidium* monitoring to complete the source water monitoring requirements and comply with the treatment requirements in § 141.720.

(d) Systems that are unfiltered and meet all the filtration avoidance criteria of § 141.71 must conduct source water monitoring consisting of *Cryptosporidium* sampling and comply with the treatment requirements in § 141.721.

(e) Systems must comply with the requirements in this subpart based on the schedule in the following table, except that systems are not required to conduct source water monitoring if they meet the criteria in paragraph (f) of this section for systems that currently provide filtration or that are unfiltered and required to install filtration or paragraph (g) of this section for systems that are unfiltered and meet all the filtration avoidance criteria of § 141.71:

COMPLIANCE REQUIREMENTS TABLE

Systems that are . . .	Must perform . . . ^{a,b}	And comply by . . .
(1) Subpart H systems serving $\geq 10,000$ people that currently provide filtration or that are unfiltered and required to install filtration.	(i) 24 months of source water monitoring for <i>Cryptosporidium</i> , <i>E. coli</i> and turbidity at least once each month beginning no later than [Date 6 Months After Date of Publication of Final Rule in the Federal Register]. (ii) Treatment technique implementation, if necessary.	Submitting a monthly report to EPA no later than ten days after the end of the first month following the month when the sample is taken. Installing treatment and complying with the treatment technique no later than [Date 72 Months After Date of Publication of Final Rule in the Federal Register] ^c .
(2) Subpart H systems serving $\geq 10,000$ people that are unfiltered and meet the filtration avoidance criteria of § 141.71.	(i) 24 months of source water monitoring for <i>Cryptosporidium</i> at least once each month beginning no later than [Date 6 Months After Date of Publication of Final Rule in the Federal Register]. (ii) Treatment technique implementation, if necessary.	Submitting a monthly report to EPA no later than ten days after the end of the first month following the month when the sample is taken. Installing treatment and complying with the treatment technique no later than [Date 72 Months After Date of Publication of Final rule in the Federal Register] ^c .
(3) Subpart H systems serving <10,000 people that currently provide filtration or that are unfiltered and required to install filtration and are not required to monitor for <i>Cryptosporidium</i> based on <i>E. coli</i> or other indicator monitoring results ^d .	12 months of source water monitoring for <i>E. coli</i> at least once every two weeks beginning no later than [Date 30 Months After Date of Publication of Final Rule in the Federal Register].	Submitting a monthly report to the State no later than ten days after the end of the first month following the month when the sample is taken.
(4) Subpart H systems serving <10,000 people that currently provide filtration or that are unfiltered and required to install filtration and must perform <i>Cryptosporidium</i> monitoring based on <i>E. coli</i> or other indicator monitoring results ^d .	(i) 12 months of source water monitoring for <i>E. coli</i> at least once every two weeks beginning no later than [Date 30 Months After Date of Publication of Final Rule in the Federal Register] and 12 months of source water monitoring for <i>Cryptosporidium</i> at least twice each month beginning no later than [Date 48 Months After Date of Publication of Final Rule in the Federal Register]. (ii) Treatment technique implementation, if necessary.	Submitting a monthly report to the State no later than ten days after the end of the first month following the month when the sample is taken. Installing treatment and complying with the treatment technique no later than [Date 102 Months After Date of Publication of Final Rule in the Federal Register] ^c .
(5) Subpart H systems serving <10,000 people that are unfiltered and meet the filtration avoidance criteria of § 141.71.	(i) 12 months of source water monitoring for <i>Cryptosporidium</i> at least twice each month beginning no later than [Date 48 Months After Date of Publication of Final Rule in the Federal Register]. (ii) Treatment technique implementation, if necessary.	Submitting a monthly report to the State no later than ten days after the end of the first month following the month when the sample is taken. Installing treatment and complying with the treatment technique no later than [Date 102 Months After Date of Publication of Final Rule in the Federal Register] ^c .

^a Any sampling performed more frequently than required must be evenly distributed over the sampling period.

^b Systems may use data that meet the requirements in § 141.708 collected prior to the monitoring start date to substitute for an equivalent number of months at the end of the monitoring period.

^c States may allow up to an additional two years for complying with the treatment technique requirement for systems making capital improvements.

^d See § 141.702(b) to determine if *Cryptosporidium* monitoring is required.

(f) Systems that currently provide filtration or that are unfiltered and required to install filtration are not required to conduct source water monitoring under this subpart if the system currently provides or will provide a total of at least 5.5 log of treatment for *Cryptosporidium*, equivalent to meeting the treatment requirements of Bin 4 in § 141.720. Systems must notify the State not later than the date the system is otherwise required to submit a sampling schedule for monitoring under § 141.703 and must install and operate technologies to provide a total of at least 5.5 log of

treatment for *Cryptosporidium* by the applicable date in paragraph (e) of this section.

(g) Systems that are unfiltered and meet all the filtration avoidance criteria of § 141.71 are not required to conduct source water monitoring under this subpart if the system currently provides or will provide a total of at least 3 log *Cryptosporidium* inactivation, equivalent to meeting the treatment requirements for unfiltered systems with a mean *Cryptosporidium* concentration of greater than 0.01 oocysts/L in § 141.721. Systems must notify the State not later than the date

the system is otherwise required to submit a sampling schedule for monitoring under § 141.703. Systems must install and operate technologies to provide a total of at least 3 log *Cryptosporidium* inactivation by the applicable date in paragraph (e) of this section.

(h) Systems must comply with the uncovered finished water storage facility requirements in § 141.724 no later than [Date 36 Months After Date of Publication of Final Rule in the **Federal Register**].

Source Water Monitoring Requirements

§ 141.702 Source water monitoring.

(a) Systems must conduct initial source water monitoring as specified in § 141.701(b) through (f).

(b) Systems serving fewer than 10,000 people that provide filtration or that are unfiltered and required to install filtration must perform *Cryptosporidium* monitoring in accordance with § 141.701(e) if they meet any of the criteria in paragraphs (b)(1) through (4) of this section.

(1) For systems using lake/reservoir sources, an annual mean *E. coli* concentration greater than 10 *E. coli*/100 mL, based on monitoring conducted under this section, unless the State approves an alternative indicator trigger.

(2) For systems using flowing stream sources, an annual mean *E. coli* concentration greater than 50 *E. coli*/100 mL, based on monitoring conducted under this section, unless the State approves an alternative indicator trigger.

(3) If the State approves an alternative to the indicator trigger in paragraph (b)(1) or (b)(2) of this section, an annual concentration that exceeds a State-approved trigger level, including an alternative *E. coli* level, based on monitoring conducted under this section.

(4) The system does not conduct *E. coli* or other State-approved indicator monitoring as specified in § 141.701(e).

(c) Systems may submit *Cryptosporidium* data collected prior to the monitoring start date to meet the initial source water monitoring requirements of paragraphs (a) through (b) of this section. Systems may also use *Cryptosporidium* data collected prior to the monitoring start date to substitute for an equivalent number of months at the end of the monitoring period. All data submitted under this paragraph must meet the requirements in § 141.708.

(d) Systems must conduct a second round of source water monitoring in accordance with the requirements in § 141.701(b) through (e) of this section, beginning no later than the dates specified in paragraphs (d)(1) through (3) of this section, unless they meet the criteria in either paragraph § 141.701(f) or (g).

(1) Systems that serve at least 10,000 people must begin a second round of source water monitoring no later than [Date 108 Months After Date of Publication of Final Rule in the **Federal Register**].

(2) Systems serving fewer than 10,000 people that provide filtration or that are unfiltered and required to install filtration must begin a second round of

source water monitoring no later than [Date 138 Months After Date of Publication of Final Rule in the **Federal Register**] and, if required to monitor for *Cryptosporidium* under paragraph (b) of this section, must begin *Cryptosporidium* monitoring no later than [Date 156 Months After Date of Publication of Final Rule in the **Federal Register**].

(3) Systems serving fewer than 10,000 people that are unfiltered and meet the filtration avoidance requirements of § 141.71 must begin a second round of source water monitoring no later than [Date 156 Months After Date of Publication of Final Rule in the **Federal Register**].

§ 141.703 Sampling schedules.

(a) Systems required to sample under §§ 141.701 through 141.702 must submit a sampling schedule that specifies the calendar dates that all required samples will be taken.

(1) Systems serving at least 10,000 people must submit their sampling schedule for initial source water monitoring to EPA electronically at [insert Internet address] no later than [Date 3 Months After Date of Publication of Final Rule in the **Federal Register**].

(2) Systems serving fewer than 10,000 people that are filtered or that are unfiltered and required to install filtration must submit a sampling schedule for initial source water monitoring of *E. coli* or an alternative State-approved indicator to the State no later than [Date 27 Months After Date of Publication of Final Rule in the **Federal Register**].

(3) Filtered systems serving fewer than 10,000 people that are required to conduct *Cryptosporidium* monitoring and unfiltered systems serving fewer than 10,000 people must submit a sampling schedule for initial source water *Cryptosporidium* monitoring to the State no later than [Date 45 Months After Date of Publication of Final Rule in the **Federal Register**].

(4) Systems must submit a sampling schedule for the second round of source water monitoring to the State no later than 3 months prior to the date the system is required to begin the second round of monitoring under § 141.702(d).

(b) Systems must collect samples within two days of the dates indicated in their sampling schedule.

(c) If extreme conditions or situations exist that may pose danger to the sample collector, or which are unforeseen or cannot be avoided and which cause the system to be unable to sample in the required time frame, the system must sample as close to the required date as feasible and submit an explanation for

the alternative sampling date with the analytical results.

(d) Systems that are unable to report a valid *Cryptosporidium* analytical result for a scheduled sampling date due to failure to comply with the analytical method requirements, including the quality control requirements in § 141.705, must collect a replacement sample within 14 days of being notified by the laboratory or the State that a result cannot be reported for that date and must submit an explanation for the replacement sample with the analytical results.

§ 141.704 Sampling locations.

(a) Unless specified otherwise in this section, systems required to sample under §§ 141.701 through 141.702 must collect source water samples from the plant intake prior to any treatment. Where treatment is applied in an intake pipe such that sampling in the pipe prior to treatment is not feasible, systems must collect samples as close to the intake as is feasible, at a similar depth and distance from shore.

(b) *Presedimentation*. Systems using a presedimentation basin must collect source water samples after the presedimentation basin but before any other treatment. Use of presedimentation basins during monitoring must be consistent with routine operational practice and the State may place reporting requirements to verify operational practices. Systems collecting samples after a presedimentation basin may not receive credit for the presedimentation basin under § 141.726(a).

(c) *Raw water off-stream storage*. Systems using an off-stream raw water storage reservoir must collect source water samples after the off-stream storage reservoir. Use of off-stream storage during monitoring must be consistent with routine operational practice and the State may place reporting requirements to verify operational practices.

(d) *Bank filtration*. The required sampling location for systems using bank filtration differs depending on whether the bank filtered water is treated by subsequent filtration for compliance with § 141.173(b) or § 141.552(a), as applicable.

(1) Systems using bank filtered water that is treated by subsequent filtration for compliance with § 141.173(b) or § 141.552(a), as applicable, must collect source water samples from the well (*i.e.*, after bank filtration), but before any other treatment. Use of bank filtration during monitoring must be consistent with routine operational practice and the State may place reporting

requirements to verify operational practices. Systems collecting samples after a bank filtration process may not receive credit for the bank filtration under § 141.726(c).

(2) Systems using bank filtration as an alternative filtration demonstration to meet their *Cryptosporidium* removal requirements under § 141.173(b) or § 141.552(a), as applicable, must collect source water samples in the surface water (*i.e.*, prior to bank filtration).

(3) Systems using a ground water source under the direct influence of surface water that meet all the criteria for avoiding filtration in § 141.71 and that do not provide filtration treatment must collect source water samples from the ground water (*e.g.*, the well).

(e) *Multiple sources.* Systems with plants that use multiple water sources at the same time, including multiple surface water sources and blended surface water and ground water sources, must collect samples as specified in paragraph (e)(1) or (2) of this section. The use of multiple sources during monitoring must be consistent with routine operational practice and the State may place reporting requirements to verify operational practices.

(1) If a sampling tap is available where the sources are combined prior to treatment, the sample must be collected from the tap.

(2) If there is not a sampling tap where the sources are combined prior to treatment, systems must collect samples at each source near the intake on the same day and must follow either paragraph (e)(2)(i) or (e)(2)(ii) of this section for sample analysis.

(i) Composite samples from each source into one sample prior to analysis. In the composite, the volume of sample from each source must be weighted according to the proportion of the

source in the total plant flow at the time the sample is collected.

(ii) Analyze samples from each source separately as specified in § 141.705, and calculate a weighted average of the analysis results for each sampling date. The weighted average must be calculated by multiplying the analysis result for each source by the fraction the source contributed to total plant flow at the time the sample was collected, and then summing these values.

§ 141.705 Analytical methods.

(a) *Cryptosporidium.* Systems must use Method 1622 *Cryptosporidium in Water by Filtration/IMS/FA*, EPA 821-R-01-026, April 2001, or Method 1623 *Cryptosporidium and Giardia in Water by Filtration/IMS/FA*, EPA 821-R-01-025, April 2001, for *Cryptosporidium* analysis.

(1) Systems are required to analyze at least a 10 L sample or a packed pellet volume of at least 2 mL as generated by the methods listed in paragraph (a) of this section. Systems unable to process a 10 L sample must analyze as much sample volume as can be filtered by two filters approved by EPA for the methods listed in paragraph (a) of this section, up to a packed pellet volume of 2 mL.

(2)(i) Matrix spikes (MS) samples as required by the methods in paragraph (a) of this section must be spiked and filtered by a laboratory approved for *Cryptosporidium* analysis under § 141.706. The volume of the MS sample must be within 10 percent of the volume of the unspiked sample that is collected at the same time, and the samples must be collected by splitting the sample stream or collecting the samples sequentially. The MS sample and the associated unspiked sample must be analyzed by the same procedure.

(ii) If the volume of the MS sample is greater than 10 L, the system is permitted to filter all but 10 L of the MS sample in the field, and ship the filtered sample and the remaining 10 L of source water to the laboratory. In this case, the laboratory must spike the remaining 10 L of water and filter it through the filter used to collect the balance of the sample in the field.

(3) Each sample batch must meet the quality control criteria for the methods listed in paragraph (a) of this section. Flow cytometer-counted spiking suspensions must be used for MS samples and ongoing precision and recovery (OPR) samples; recovery for OPR samples must be 11% to 100%; for each method blank, oocysts must not be detected.

(4) Total *Cryptosporidium* oocysts as detected by fluorescein isothiocyanate (FITC) must be reported as determined by the color (apple green or alternative stain color approved under § 141.706(a) for the laboratory), size (4–6 µm) and shape (round to oval). This total includes all of the oocysts identified, less any atypical organisms identified by FITC, differential interference contrast (DIC) or 4',6-diamindino-2-phenylindole (DAPI), including those possessing spikes, stalks, appendages, pores, one or two large nuclei filling the cell, red fluorescing chloroplasts, crystals, and spores.

(b) *E. coli.* Systems must use the following methods listed in this paragraph for enumeration of *E. coli* in source water (table will be replaced with CFR cite from Guidelines Establishing Test Procedures for the Analysis of Pollutants; Analytical Methods for Biological Pollutants in Ambient Water when finalized—expected 2003):

METHODS FOR *E. coli* ENUMERATION ¹

Technique	Method ¹	EPA	VCSB methods		
			Standard methods	ASTM	AOAC
Most Probable Number (MPN)	LTB, EC-MUG	9221B.1/9221F		
	ONPG-MUG	9223B	991.15
	ONPG-MUG	9223B		
Membrane Filter (MF)	mFC→NA-MUG	9222D/9222G		
	ENDO→NA-MUG	9222B/9222G		
	mTEC agar	1103.1	9213D	D5392-93	
	Modified mTEC agar	Modified 1103.1			
	MI agar	EPA-600-R-013			
	m-ColiBlue24 broth				

¹ Tests must be conducted in a format that provides organism enumeration.

(1) The time from sample collection to initiation of analysis may not exceed 24

hours. Systems must maintain samples between 0°C and 10°C during transit.

(2) [Reserved]

(c) *Turbidity.* Systems must use methods for turbidity measurement approved in § 141.74.

§ 141.706 Requirements for use of an approved laboratory.

(a) *Cryptosporidium*. Systems must have *Cryptosporidium* samples analyzed by a laboratory that has passed a quality assurance evaluation under EPA's Laboratory Quality Assurance Evaluation Program for Analysis of *Cryptosporidium* in Water or a laboratory that has been certified for *Cryptosporidium* analysis by an equivalent State laboratory certification program.

(b) *E. coli*. Any laboratory certified by the EPA, the National Environmental Laboratory Accreditation Conference or the State for total coliform or fecal coliform analysis in source water under § 141.74 is deemed approved for *E. coli* analysis under this subpart when the laboratory uses the same technique for *E. coli* that the laboratory uses for source water in § 141.74.

(c) Turbidity. Measurements of turbidity must be made by a party approved by the State.

§ 141.707 Reporting source water monitoring results.

(a) All systems serving at least 10,000 people must submit the results of all initial source water monitoring required under § 141.702(a) to EPA electronically at [insert Internet address]. Systems that do not have the ability to submit data electronically may use an alternative format approved by EPA.

(b) Systems serving fewer than 10,000 people must submit the results of all initial source water monitoring required under § 141.702(a)–(b) to the State.

(c) All systems must submit the results from the second round of source water monitoring required under § 141.702(d) to the State.

(d) Source water monitoring analysis results must be submitted not later than ten days after the end of first month following the month when the sample is collected. The submission must include the applicable information in paragraphs (e)(1) and (2) of this section.

(e)(1) Systems must report the following data elements for each *Cryptosporidium* analysis:

- (i) PWS ID
- (ii) Facility ID
- (iii) Sample collection point
- (iv) Sample collection date
- (v) Sample type (field or matrix spike)
- (vi) Sample volume filtered (L), to nearest ¼ L
- (vii) Was 100% of filtered volume examined
- (viii) Number of oocysts counted

(i) For matrix spike samples, systems must also report the sample volume spiked and estimated number of oocysts spiked. These data are not required for field samples.

(ii) For samples in which less than 10 L is filtered or less than 100% of the sample volume is examined, systems must also report the number of filters used and the packed pellet volume.

(iii) For samples in which less than 100% of sample volume is examined, systems must also report the volume of resuspended concentrate and volume of this resuspension processed through immunomagnetic separation.

(2) Systems must report the following data elements for each *E. coli* analysis:

- (i) PWS ID
- (ii) Facility ID
- (iii) Sample collection point
- (iv) Sample collection date
- (v) Analytical method number
- (vi) Method type
- (vii) Source type
- (viii) *E. coli*/100 mL
- (ix) Turbidity (Systems serving fewer than 10,000 people that are not required to monitor for turbidity under § 141.701(c) are not required to report turbidity with their *E. coli* results.)

§ 141.708 Previously collected data.

(a) Systems may comply with the initial monitoring requirements of § 141.702(a) using *Cryptosporidium* data collected before the system is required to begin monitoring if the system meets the conditions in paragraphs (b) through (h) of this section and EPA notifies the system that the data are acceptable.

(b) To be accepted, previously collected *Cryptosporidium* data must meet the conditions in paragraphs (b)(1) through (5) of this section.

(1) Samples were analyzed by laboratories using one of the analytical methods in paragraphs (b)(1)(i) through (iv) of this section.

(i) *Method 1623: Cryptosporidium and Giardia in Water by Filtration/IMS/FA, 2001, EPA-821-R-01-025.*

(ii) *Method 1622: Cryptosporidium in Water by Filtration/IMS/FA, 2001, EPA-821-R-01-026.*

(iii) *Method 1623: Cryptosporidium and Giardia in Water by Filtration/IMS/FA, 1999, EPA-821-R-99-006.*

(iv) *Method 1622: Cryptosporidium in Water by Filtration/IMS/FA, 1999, EPA-821-R-99-001.*

(2) Samples were collected no less frequently than each calendar month on a regular schedule, beginning no earlier than January 1999.

(3) Samples were collected in equal intervals of time over the entire collection period (e.g., weekly, monthly). Sample collection interval may vary for the conditions specified in § 141.703(c) and (d) if the system provides documentation of the condition.

(4) Samples met the conditions for sampling location specified in § 141.704. The system must report the use of bank filtration, presedimentation, and raw water off-stream storage during sampling.

(5) For each sample, the laboratory analyzed at least 10 L of sample or at least 2 mL of packed pellet or as much volume as could be filtered by 2 filters approved by EPA for the methods listed in paragraph (b)(1) of this section, up to a packed pellet volume of 2 mL.

(c) The system must submit a letter to EPA concurrent with the submission of previously collected data certifying that the data meet the conditions in paragraphs (c)(1) and (2) of this section.

(1) The reported *Cryptosporidium* analysis results include all results generated by the system during the time period beginning with the first reported result and ending with the final reported result. This applies to samples that were collected from the sampling location specified for source water monitoring under this subpart, not spiked, and analyzed using the laboratory's routine process for the analytical methods listed in paragraph (a)(1) of this section.

(2) The samples were representative of a plant's source water(s) and the source water(s) have not changed.

(d) For each sample, the system must report the data elements in § 141.707(e)(1).

(e) The laboratory or laboratories that generated the data must submit a letter to EPA concurrent with the submission of previously collected data certifying that the quality control criteria specified in the methods listed in paragraph (b)(1) of this section were met for each sample batch associated with the previously collected data. Alternatively, the laboratory may provide bench sheets and sample examination report forms for each field, matrix spike, IPR, OPR, and method blank sample associated with the previously collected data.

(f) If a system has at least two years of *Cryptosporidium* data collected before [Date of Publication of Final Rule in the **Federal Register**] and the system intends to use these data to comply with the initial source water monitoring required under § 141.702(a) in lieu of conducting new monitoring, the system must submit to EPA, no later than [Date 2 Months After Date of Publication of Final Rule in the **Federal Register**], the previously collected data and the supporting information specified in this section. EPA will notify the system by [Date 4 Months After Date of Publication of Final Rule in the **Federal Register**] as to whether the data are acceptable. If EPA does not notify the system that the

submitted data are acceptable, the system must carry out initial source water as specified in §§ 141.701 through 141.707 until EPA notifies the system that it has at least two years of acceptable data.

(g) If a system has fewer than two years of *Cryptosporidium* data collected before [Date of Publication of Final Rule in the **Federal Register**] and the system intends to use these data to meet, in part, the initial source water monitoring required under § 141.702(a), the system must submit to EPA, no later than [Date 8 Months After Date of Publication of Final Rule in the **Federal Register**], the previously collected data and the supporting information specified in this section. The system must carry out initial source water monitoring according to the requirements in §§ 141.701 through 141.707 until EPA notifies the system that it has at least two years of acceptable data.

(h) If a system has two or more years of previously collected data and the system intends to use these data to comply with the initial source water monitoring required under § 141.702(a), but the system also intends to carry out

additional initial source water monitoring in order to base its determination of average *Cryptosporidium* concentration under § 141.709 or § 141.721 on more than two years of monitoring data, the system must submit to EPA, no later than [Date 8 Months After Date of Publication of Final Rule in the **Federal Register**], the previously collected data and the supporting information specified in this section. The system must carry out initial source water monitoring according to the requirements in §§ 141.701 through 141.707 until EPA notifies the system that it has at least two years of acceptable data.

§ 141.709 Bin classification for filtered systems.

(a) Following completion of the initial source water monitoring required under § 141.702(a), filtered systems and unfiltered systems that are required to install filtration must calculate their initial *Cryptosporidium* bin concentration using the *Cryptosporidium* results reported under § 141.702(a), along with any previously collected data that satisfy the

requirements of § 141.708, and following the procedures in paragraphs (b)(1) through (3) of this section.

(b)(1) For systems that collect a total of at least 48 samples, the *Cryptosporidium* bin concentration is equal to the arithmetic mean of all sample concentrations.

(2) For systems that serve at least 10,000 people and collect a total of at least 24 samples, but not more than 47 samples, the *Cryptosporidium* bin concentration is equal to the highest arithmetic mean of all sample concentrations in any 12 consecutive months during which *Cryptosporidium* samples were collected.

(3) For systems that serve fewer than 10,000 people and take at least 24 samples, the *Cryptosporidium* bin concentration is equal to the arithmetic mean of all sample concentrations.

(c) Filtered systems and unfiltered systems that are required to install filtration must determine their initial bin classification from the following table and using the *Cryptosporidium* bin concentration calculated under paragraph (a) of this section:

BIN CLASSIFICATION TABLE FOR FILTERED SYSTEMS

For systems that are:	With a <i>Cryptosporidium</i> bin concentration of . . . ¹	The bin classification is . . .
* * * required to monitor for <i>Cryptosporidium</i> under §§ 141.701 to 141.702.	<i>Cryptosporidium</i> < 0.075 oocysts/L	Bin 1
	0.075 oocysts/L ≤ <i>Cryptosporidium</i> < 1.0 oocysts/L	Bin 2
	1.0 oocysts/L ≤ <i>Cryptosporidium</i> < 3.0 oocysts/L	Bin 3
	<i>Cryptosporidium</i> ≥ 3.0 oocysts/L	Bin 4
* * * serving fewer than 10,000 people and NOT required to monitor for <i>Cryptosporidium</i> under § 142.702(b).	NA	Bin 1

¹ Based on calculations in paragraph (a) or (d) of this section, as applicable.

(d) Following completion of the second round of source water monitoring required under § 141.702(d), filtered systems and unfiltered systems that are required to install filtration must recalculate their *Cryptosporidium* bin concentration using the *Cryptosporidium* results reported under § 141.702(d) and following the procedures in paragraphs (b)(1) through (3) of this section. Systems must then determine their bin classification a second time using this *Cryptosporidium* bin concentration and the table in paragraph (c) of this section.

(e) Any filtered system or unfiltered system that is required to install filtration that fails to complete the monitoring requirements of § 141.701 through 141.707 or chooses not to monitor pursuant to § 141.701(f) must meet the treatment requirements for Bin

4 under § 141.720 by the date applicable under § 141.701(e).

Disinfection Profiling and Benchmarking Requirements

§ 141.710 [Reserved].

§ 141.711 Determination of systems required to profile.

(a) Subpart H of this part community and nontransient noncommunity water systems serving at least 10,000 people that do not have at least 5.5 log of *Cryptosporidium* treatment, equivalent to compliance with Bin 4 in § 141.720, in place prior to the date when the system is required to begin profiling in § 141.712 are required to develop *Giardia lamblia* and virus disinfection profiles.

(b) Subpart H community and nontransient noncommunity water

systems serving fewer than 10,000 people that do not have at least 5.5 log of *Cryptosporidium* treatment, equivalent to compliance with Bin 4 in § 141.720, in place prior to the date when the system is required to begin profiling in § 141.712 are required to develop *Giardia lamblia* and virus disinfection profiles if any of the criteria in paragraphs (b)(1) through (3) of this section apply.

(1) TTHM levels in the distribution system are at least 0.064 mg/L as a locational running annual average (LRAA) at any monitoring site. Systems must base their TTHM LRAA calculation on data collected for compliance under subpart L of this part after [Date of Publication of Final Rule in the **Federal Register**], or as determined by the State.

(2) HAA5 levels in the distribution system are at least 0.048 mg/L as an LRAA at any monitoring site. Systems must base their HAA5 LRAA calculation on data collected for compliance under subpart L of this part after [Date of

Publication of Final Rule in the **Federal Register**], or as determined by the State.
 (3) The system is required to monitor for *Cryptosporidium* under § 141.701(c).
 (c) In lieu of developing a new profile, systems may use the profile(s) developed under § 141.172 or §§ 141.530 through 141.536 if the

profile(s) meets the requirements of § 141.713(c).

§ 141.712 Schedule for disinfection profiling requirements.

(a) Systems must comply with the following schedule in the table in this paragraph:

SCHEDULE OF REQUIRED DISINFECTION PROFILING MILESTONES ¹

Activity	Date		
	Subpart H systems serving at least 10,000 people	Subpart H systems serving fewer than 10,000 people	
		Required to monitor for <i>Cryptosporidium</i>	Not required to monitor for <i>Cryptosporidium</i>
1. Report TTHM and HAA5 LRAA results to State.	NA	NA	[Date 42 Months After Date of Publication of Final Rule in the Federal Register].
2. Begin disinfection profiling ^{1,2} ..	[Date 24 Months After Date of Publication of Final Rule in the Federal Register].	[Date 54 Months After Date of Publication of Final Rule in the Federal Register].	[Date 42 Months After Date of Publication of Final Rule in the Federal Register] if required ³ .
3. Complete disinfection profiling based on at least one year of data.	[Date 36 Months After Date of Publication of Final Rule in the Federal Register].	[Date 66 Months After Date of Publication of Final Rule in the Federal Register].	[Date 54 Months After Date of Publication of Final Rule in the Federal Register] if required ³ .

¹ Systems with at least 5.5 log of *Cryptosporidium* treatment in place are not required to do disinfection profiling.
² Systems may use existing operational data and profiles as described in § 141.713(c).
³ Systems serving fewer than 10,000 people are not required to conduct disinfection profiling if they are not required to monitor for *Cryptosporidium* and if their TTHM and HAA5 LRAAs do not exceed the levels specified in § 141.711(b).

(b) [Reserved]

§ 141.713 Developing a profile.

(a) Systems required to develop disinfection profiles under § 141.711 must follow the requirements of this section. Systems must monitor at least weekly for a period of 12 consecutive months to determine the total log inactivation for *Giardia lamblia* and viruses. Systems must determine log inactivation for *Giardia lamblia* through the entire plant, based on CT_{99.9} values in Tables 1.1 through 1.6, 2.1 and 3.1 of § 141.74(b) as applicable. Systems must determine log inactivation for viruses through the entire treatment plant based on a protocol approved by the State.

(b) Systems with a single point of disinfectant application prior to the entrance to the distribution system must conduct the monitoring in paragraphs (b)(1) through (4) of this section. Systems with more than one point of disinfectant application must conduct the monitoring in paragraphs (b)(1) through (4) of this section for each disinfection segment. Systems must monitor the parameters necessary to determine the total inactivation ratio, using analytical methods in § 141.74(a).

(1) For systems using a disinfectant other than UV, the temperature of the disinfected water must be measured at each residual disinfectant concentration sampling point during peak hourly flow or at an alternative location approved by the State.

(2) For systems using chlorine, the pH of the disinfected water must be measured at each chlorine residual disinfectant concentration sampling point during peak hourly flow or at an alternative location approved by the State.

(3) The disinfectant contact time(s) (T) must be determined during peak hourly flow.

(4) The residual disinfectant concentration(s) (C) of the water before or at the first customer and prior to each additional point of disinfection must be measured during peak hourly flow.

(c) In lieu of conducting new monitoring under paragraph (b) of this section, systems may elect to meet the requirements of paragraphs (c)(1) or (2) of this section.

(1) Systems that have at least 12 consecutive months of existing operational data that are substantially equivalent to data collected under the provisions of paragraph (b) of this section may use these data to develop disinfection profiles as specified in this section if the system has neither made a significant change to its treatment practice nor changed sources since the data were collected. Systems using existing operational data may develop disinfection profiles for a period of up to three years.

(2) Systems may use disinfection profile(s) developed under § 141.172 or §§ 141.530 through 141.536 in lieu of developing a new profile if the system

has neither made a significant change to its treatment practice nor changed sources since the profile was developed. Systems that have not developed a virus profile under § 141.172 or §§ 141.530 through 141.536 must develop a virus profile using the same monitoring data on which the *Giardia lamblia* profile is based.

(d) Systems must calculate the total inactivation ratio for *Giardia lamblia* as specified in paragraphs (d)(1) through (3) of this section.

(1) Systems using only one point of disinfectant application may determine the total inactivation ratio for the disinfection segment based on either of the methods in paragraph (d)(1)(i) or (ii) of this section.

(i) Determine one inactivation ratio (CT_{calc}/CT_{99.9}) before or at the first customer during peak hourly flow.

(ii) Determine successive CT_{calc}/CT_{99.9} values, representing sequential inactivation ratios, between the point of disinfectant application and a point before or at the first customer during peak hourly flow. The system must calculate the total inactivation ratio by determining (CT_{calc}/CT_{99.9}) for each sequence and then adding the (CT_{calc}/CT_{99.9}) values together to determine (Σ (CT_{calc}/CT_{99.9})).

(2) Systems using more than one point of disinfectant application before the first customer must determine the CT value of each disinfection segment immediately prior to the next point of

disinfectant application, or for the final segment, before or at the first customer, during peak hourly flow. The $(CT_{calc}/CT_{99.9})$ value of each segment and $(\Sigma CT_{calc}/CT_{99.9})$ must be calculated using the method in paragraph (d)(1)(ii) of this section.

(3) The system must determine the total logs of inactivation by multiplying the value calculated in paragraph (d)(1) or (d)(2) of this section by 3.0.

(4) Systems must calculate the log of inactivation for viruses using a protocol approved by the State.

(5) Systems must retain the disinfection profile data in graphic form, as a spreadsheet, or in some other format acceptable to the State for review as part of sanitary surveys conducted by the State.

§ 141.714 Requirements when making a significant change in disinfection practice.

(a) A system that is required to develop a disinfection profile under the provisions of this subpart and that plans to make a significant change to its disinfection practice must calculate a disinfection benchmark and must notify the State prior to making such a change. Significant changes to disinfection

practice are defined in paragraphs (a)(1) through (4) of this section.

(1) Changes to the point of disinfection;

(2) Changes to the disinfectant(s) used in the treatment plant;

(3) Changes to the disinfection process; and

(4) Any other modification identified by the State.

(5) Systems must use the procedures specified in paragraphs (a)(5)(i) and (ii) of this section to calculate a disinfection benchmark.

(i) For the year of profiling data collected and calculated under § 141.713, or for each year with profiles covering more than one year, systems must determine the lowest mean monthly level of both *Giardia lamblia* and virus inactivation. Systems must determine the mean *Giardia lamblia* and virus inactivation for each calendar month for each year of profiling data by dividing the sum of daily or weekly *Giardia lamblia* and virus log inactivation by the number of values calculated for that month.

(ii) The disinfection benchmark is the lowest monthly mean value (for systems with one year of profiling data) or the mean of the lowest monthly mean

values (for systems with more than one year of profiling data) of *Giardia lamblia* and virus log inactivation in each year of profiling data.

(6) Systems must submit the information in paragraphs (a)(6)(i) through (iii) of this section when notifying the State that they are planning to make a significant change in disinfection practice.

(i) A description of the proposed change.

(ii) The disinfection profile and benchmark for *Giardia lamblia* and viruses determined under §§ 141.713 and 141.714.

(iii) An analysis of how the proposed change will affect the current level of disinfection.

Treatment Technique Requirements

§ 141.720 Treatment requirements for filtered systems.

(a) Filtered systems or systems that are unfiltered and required to install filtration must provide the level of treatment for *Cryptosporidium* specified in this paragraph, based on their bin classification as determined under § 141.709 and their existing treatment:

If the system bin classification is . . .	And the system uses the following filtration treatment in full compliance with subpart H, P, and T of this section (as applicable), then the additional treatment requirements are . . .			
	Conventional filtration treatment (including softening)	Direct filtration	Slow sand or diatomaceous earth filtration	Alternative filtration technologies
(1) Bin 1	No additional treatment	No additional treatment	No additional treatment	No additional treatment
(2) Bin 2	1 log treatment	1.5 log treatment	1 log treatment	(1)
(3) Bin 3	2 log treatment	2.5 log treatment	2 log treatment	(2)
(4) Bin 4	2.5 log treatment	3 log treatment	2.5 log treatment	(3)

¹ As determined by the State such that the total *Cryptosporidium* removal and inactivation is at least 4.0 log.

² As determined by the State such that the total *Cryptosporidium* removal and inactivation is at least 5.0 log.

³ As determined by the State such that the total *Cryptosporidium* removal and inactivation is at least 5.5 log.

(b) Filtered systems must use one, or a combination, of the management and treatment options listed in § 141.722, termed the microbial toolbox, to meet the additional *Cryptosporidium* treatment requirements identified for each bin in paragraph (a) of this section.

(c) Systems classified in Bin 3 and Bin 4 must achieve at least 1 log of the additional treatment required under paragraph (a) of this section using either one or a combination of the following: bag filters, bank filtration, cartridge filters, chlorine dioxide, membranes, ozone, and/or UV as specified in § 141.722.

§ 141.721 Treatment requirements for unfiltered systems.

(a) Following completion of the initial source water monitoring required under § 141.702(a), unfiltered systems that

meet all filtration avoidance criteria of § 141.71 must calculate the arithmetic mean of all *Cryptosporidium* sample concentrations reported under § 141.702(a), along with any previously collected data that satisfy the requirements of § 141.708, and must meet the treatment requirements in paragraph (b)(1) or (2) of this section, as applicable, based on this concentration.

(b)(1) Unfiltered systems with a mean *Cryptosporidium* concentration of 0.01 oocysts/L or less must provide at least 2 log *Cryptosporidium* inactivation.

(2) Unfiltered systems with a mean *Cryptosporidium* concentration of greater than 0.01 oocysts/L must provide at least 3 log *Cryptosporidium* inactivation.

(c) Unfiltered systems must use chlorine dioxide, ozone, or UV as specified in § 141.722 to meet the

Cryptosporidium inactivation requirements of this section.

(1) Unfiltered systems that use chlorine dioxide or ozone and fail to achieve the *Cryptosporidium* log inactivation required in paragraph (b)(1) or (2) of this section, as applicable, on more than one day in the calendar month are in violation of the treatment technique requirement.

(2) Unfiltered systems that use UV light and fail to achieve the *Cryptosporidium* log inactivation required in paragraph (b)(1) or (2) of this section, as applicable, in at least 95% of the water that is delivered to the public during each calendar month, based on monitoring required under paragraph § 141.729(d)(4), are in violation of the treatment technique requirement.

(d) Unfiltered systems must meet the combined *Cryptosporidium*, *Giardia*

lamblia, and virus inactivation requirements of this section and § 141.72(a) using a minimum of two disinfectants, and each disinfectant must separately achieve the total inactivation required for either *Cryptosporidium*, *Giardia lamblia*, or viruses.

(e) Following completion of the second round of source water monitoring required under § 141.702(d), unfiltered systems that meet all filtration avoidance criteria of § 141.71 must calculate the arithmetic mean of

all *Cryptosporidium* sample concentrations reported under § 141.702(d) and must meet the treatment requirements in paragraph (b)(1) or (2) of this section, as applicable, based on this concentration.

(f) Any unfiltered system that meets all filtration avoidance criteria of § 141.71 and fails to complete the monitoring requirements of §§ 141.701 through 141.707 or chooses not to monitor pursuant to § 141.701(g) must meet the treatment requirements of

paragraph (b)(2) of this section by the date applicable under § 141.701(e).

§ 141.722 Microbial toolbox options for meeting *Cryptosporidium* treatment requirements.

(a) To meet the additional *Cryptosporidium* treatment requirements of §§ 141.720 and 141.721, systems must use microbial toolbox options listed in this following table that are designed, implemented, and operated in accordance with the requirements of this subpart.

MICROBIAL TOOLBOX: OPTIONS, CREDITS AND CRITERIA

Toolbox option	Proposed <i>Cryptosporidium</i> treatment credit with design and implementation criteria
Source Toolbox Components	
(1) Watershed control program	0.5 log credit for State approved program comprising EPA specified elements. Specific criteria are in § 141.725(a).
(2) Alternative source/intake management.	Bin classification based on concurrent <i>Cryptosporidium</i> monitoring. No presumptive credit. Specific criteria are in § 141.725(b).
Pre-Filtration Toolbox Components	
(3) Presedimentation basin with coagulation.	0.5 log credit for new basins with continuous operation and coagulant addition. No presumptive credit for basins existing when monitoring is required under § 141.702. Specific criteria are in § 141.726(a).
(4) Two-stage lime softening	0.5 log credit for two-stage softening with coagulant addition. Specific criteria are in § 141.726(b).
(5) Bank filtration	0.5 log credit for 25 foot setback; 1.0 log credit for 50 foot setback. No presumptive credit for bank filtration existing when monitoring is required under § 141.704(d)(1). Specific criteria are in § 141.726(c).
Treatment Performance Toolbox Components	
(6) Combined filter performance	0.5 log credit for combined filter effluent turbidity ≤ 0.15 NTU in 95% of samples each month. Specific criteria are in § 141.727(a).
(7) Individual filter performance	1.0 log credit for individual filter effluent turbidity ≤ 0.1 NTU in 95% of daily maximum samples each month and no filter >0.3 NTU in two consecutive measurements. Specific criteria are in § 141.727(b).
(8) Demonstration of performance ..	Credit based on a demonstration to the State through State approved protocol. Specific criteria are in § 141.727(c).
Additional Filtration Toolbox Components	
(9) Bag filters	1 log credit with demonstration of at least 2 log removal efficiency in challenge test; Specific criteria are in § 141.728(a).
(10) Cartridge filters	2 log credit with demonstration of at least 3 log removal efficiency in challenge test; Specific criteria are in § 141.728(a).
(11) Membrane filtration	Log removal credit up to the lower value of the removal efficiency demonstrated during the challenge test or verified by the direct integrity test applied to the system. Specific criteria are in § 141.728(b).
(12) Second stage filtration	0.5 log credit for a second separate filtration stage in treatment process following coagulation. Specific criteria are in § 141.728(c).
(13) Slow sand filters	2.5 log credit for second separate filtration process. Specific criteria are in § 141.728(d).
Inactivation Toolbox Components	
(14) Chlorine dioxide	Log credit based on demonstration of compliance with CT table. Specific criteria are in § 141.729(b).
(15) Ozone	Log credit based on demonstration of compliance with CT table. Specific criteria are in § 141.729(c).
(16) UV	Log credit based on demonstration of compliance with UV dose table. Specific criteria are in § 141.729(d).

(b) Failure to comply with the requirements of this section in accordance with the schedule in § 141.701(e) is a treatment technique violation.

§ 141.723 [Reserved]

§ 141.724 Requirements for uncovered finished water storage facilities.

(a) Systems using uncovered finished water storage facilities must comply

with the conditions of one of the paragraphs (a)(1) through (3) of this section for each facility no later than the date specified in § 141.701(h).

(1) Systems must cover any uncovered finished water storage facility.

(2) Systems must treat the discharge from the uncovered finished water storage facility to the distribution system to achieve at least 4 log virus

inactivation using a protocol approved by the State.

(3) Systems must have a State-approved risk mitigation plan for the uncovered finished water storage facility that addresses physical access and site security, surface water runoff, animal and bird waste, and ongoing water quality assessment, and includes a schedule for plan implementation. Systems must implement the risk

mitigation plan approved by the State. Systems must submit risk mitigation plans to the State for approval no later than [Date 24 Months After Date of Publication of Final Rule in the **Federal Register**].

(b) Failure to comply with the requirements of this section in accordance with the schedule in § 141.701(h) is a treatment technique violation.

Requirements for Microbial Toolbox Components

§ 141.725 Source toolbox components.

(a) Watershed control program.

(1) Systems that intend to qualify for a 0.5 log credit for *Cryptosporidium* removal for a watershed control program must notify the State no later than one year after completing the source water monitoring requirements of § 141.702(b) that they intend to develop a watershed control program and to submit it for State approval.

(2) Systems must submit a proposed initial watershed control plan and a request for plan approval and 0.5 log *Cryptosporidium* removal credit to the State no later than two years after completing the source water monitoring requirements of § 141.702(b). Based on a review of the initial proposed watershed control plan, the State may approve, reject, or conditionally approve the plan. If the plan is approved, or if the system agrees to implement the State's conditions for approval, the system is awarded a 0.5 log credit for *Cryptosporidium* removal to apply against additional treatment requirements.

(3) The application to the State for initial program approval must include elements in paragraphs (a)(3)(i) through (iii) of this section.

(i) An analysis of the vulnerability of each source to *Cryptosporidium*. The vulnerability analysis must address the watershed upstream of the drinking water intake and must include the following: a characterization of the watershed hydrology, identification of an "area of influence" (the area to be considered in future watershed surveys) outside of which there is no significant probability of *Cryptosporidium* or fecal contamination affecting the drinking water intake, identification of both potential and actual sources of *Cryptosporidium* contamination, the relative impact of the sources of *Cryptosporidium* contamination on the system's source water quality, and an estimate of the seasonal variability of such contamination.

(ii) An analysis of control measures that could mitigate the sources of

Cryptosporidium contamination identified during the vulnerability analysis. The analysis of control measures must address their relative effectiveness in reducing *Cryptosporidium* loading to the source water and their feasibility and sustainability.

(iii) A plan that establishes goals and defines and prioritizes specific actions to reduce source water *Cryptosporidium* levels. The plan must explain how the actions are expected to contribute to specific goals, identify watershed partners and their role(s), identify resource requirements and commitments, and include a schedule for plan implementation.

(4) Initial State approval of a watershed control plan and its associated 0.5 log *Cryptosporidium* removal credit is valid until the system completes the second round of *Cryptosporidium* monitoring required under § 141.702(d). Systems must complete the actions in paragraphs (a)(4)(i) through (iv) of this section to maintain State approval and the 0.5 log credit.

(i) Submit an annual watershed control program status report to the State by a date determined by the State. The annual watershed control program status report must describe the system's implementation of the approved plan and assess the adequacy of the plan to meet its goals. It must explain how the system is addressing any shortcomings in plan implementation, including those previously identified by the State or as the result of the watershed survey conducted under paragraph (a)(4)(ii) of this section. If it becomes necessary during implementation to make substantial changes in its approved watershed control program, the system must notify the State and provide a rationale prior to making any such changes. If any change is likely to reduce the level of source water protection, the system must also include the actions it will take to mitigate the effects in its notification.

(ii) Conduct an annual watershed sanitary survey and submit the survey report to the State for approval. The survey must be conducted according to State guidelines and by persons approved by the State to conduct watershed surveys. The survey must encompass the area of the watershed that was identified in the State-approved watershed control plan as the area of influence and, at a minimum, assess the priority activities identified in the plan and identify any significant new sources of *Cryptosporidium*.

(iii) Submit to the State a request for review and re-approval of the watershed

control program and for a continuation of the 0.5 log removal credit for a subsequent approval period. The request must be provided to the State at least six months before the current approval period expires or by a date previously determined by the State. The request must include a summary of activities and issues identified during the previous approval period and a revised plan that addresses activities for the next approval period, including any new actual or potential sources of *Cryptosporidium* contamination and details of any proposed or expected changes from the existing State-approved program. The plan must address goals, prioritize specific actions to reduce source water *Cryptosporidium*, explain how actions are expected to contribute to achieving goals, identify partners and their role(s), resource requirements and commitments, and the schedule for plan implementation.

(iv) The annual status reports, watershed control plan and annual watershed sanitary surveys must be made available to the public upon request. These documents must be in a plain language style and include criteria by which to evaluate the success of the program in achieving plan goals. If approved by the State, the system may withhold portions of the annual status report, watershed control plan, and watershed sanitary survey based on security considerations.

(5) Unfiltered systems may not claim credit for *Cryptosporidium* removal under this option.

(b) Alternative source. (1) If approved by the State, a system may be classified in a bin under § 141.709 based on monitoring that is conducted concurrently with source water monitoring under § 141.701 and reflects a different intake location (either in the same source or for an alternate source) or a different procedure for managing the timing or level of withdrawal from the source.

(2) Sampling and analysis of *Cryptosporidium* in the concurrent round of monitoring must conform to the requirements for monitoring conducted under this subpart to determine bin classification. Systems must submit the results of all monitoring to the State, along with supporting information documenting the operating conditions under which the samples were collected.

(3) If the State classifies the system in a bin based on monitoring that reflects a different intake location or a different procedure for managing the timing or level of withdrawal from the source, the system must relocate the intake or use

the intake management strategy, as applicable, no later than the applicable date for treatment technique implementation in § 141.701. The State may specify reporting requirements to verify operational practices.

§ 141.726 Pre-filtration treatment toolbox components.

(a) *Presedimentation.* New presedimentation basins that meet the criteria in paragraphs (a)(1) through (4) of this section are eligible for 0.5 log *Cryptosporidium* removal credit. Systems with presedimentation basins existing when the system is required to conduct monitoring under § 141.702(a) may not claim this credit and, during periods when the basins are in use, must collect samples after the basins for the purpose of determining bin classification under § 141.709.

(1) The presedimentation basin must be in continuous operation and must treat all of the flow reaching the treatment plant.

(2) The system must continuously add a coagulant to the presedimentation basin.

(3) Presedimentation basin influent and effluent turbidity must be measured at least once per day or more frequently as determined by the State.

(4) The system must demonstrate on a monthly basis at least 0.5 log reduction of influent turbidity through the presedimentation process in at least 11 of the 12 previous consecutive months.

(i) The monthly demonstration of turbidity reduction must be based on the mean of daily turbidity readings collected under paragraph (a)(3) of this section and calculated as follows: $\log_{10}(\text{monthly mean of daily influent turbidity}) - \log_{10}(\text{monthly mean of daily effluent turbidity})$.

(ii) If the presedimentation process has not been in operation for 12 months, the system must verify on a monthly basis at least 0.5 log reduction of influent turbidity through the presedimentation process, calculated as specified in this paragraph, for at least all but any one of the months of operation.

(b) *Two-stage lime softening.* Systems that operate a two-stage lime softening plant are eligible for an additional 0.5 log *Cryptosporidium* removal credit if there is a second clarification step between the primary clarifier and filter(s) that is operated continuously. Both clarifiers must treat all of the plant flow and a coagulant, which may be excess lime or magnesium hydroxide, must be present in both clarifiers.

(c) *Bank filtration.* New bank filtration that serves as pretreatment to a filtration

plant is eligible for either a 0.5 or a 1.0 log *Cryptosporidium* removal credit towards the requirements of this subpart if it meets the design criteria specified in paragraphs (c)(1) through (c)(5) of this section and the monitoring and reporting criteria of paragraph (c)(6) of this section. Wells with a ground water flow path of at least 25 feet are eligible for 0.5 log removal credit; wells with a ground water flow path of at least 50 feet are eligible for 1.0 log removal credit. The ground water flow path must be determined as specified in paragraph (c)(5) of this section.

(1) Only horizontal and vertical wells are eligible for bank filtration removal credit.

(2) Only wells in granular aquifers are eligible for bank filtration removal credit. Granular aquifers are those comprised of sand, clay, silt, rock fragments, pebbles or larger particles, and minor cement. The aquifer material must be unconsolidated as demonstrated by the aquifer characterization specified in paragraph (c)(3) of this section, unless the system meets the conditions of paragraph (c)(4) of this section. Wells located in consolidated aquifers, fractured bedrock, karst limestone, and gravel aquifers are not eligible for bank filtration removal credit.

(3) A system seeking removal credit for bank filtration must characterize the aquifer at the well site to determine aquifer properties. The aquifer characterization must include the collection of relatively undisturbed continuous core samples from the surface to a depth at least equal to the bottom of the well screen. The recovered core length must be at least 90 percent of the total projected depth to the well screen, and each sampled interval must be a composite of no more than 2 feet in length. A well is eligible for removal credit if at least 90 percent of the composited intervals from the aquifer contain at least 10 percent fine grained material, which is defined as grains less than 1.0 mm in diameter.

(4) Wells constructed in partially consolidated granular aquifers are eligible for removal credit if approved by the State based on a demonstration by the system that the aquifer provides sufficient natural filtration. The demonstration must include a characterization of the extent of cementation and fractures present in the aquifer.

(5) For vertical wells, the ground water flow path is the measured horizontal distance from the edge of the surface water body to the well. This horizontal distance to the surface water must be determined using the floodway

boundary or 100 year flood elevation boundary as delineated on Federal Emergency Management Agency (FEMA) Flood Insurance Rate maps. If the floodway boundary or 100 year flood elevation boundary is not delineated, systems must determine the floodway or 100 year flood elevation boundary using methods substantially equivalent to those used in preparing FEMA Flood Insurance Rate maps. For horizontal wells, the ground water flow path is the closest measured distance from the bed of the river under normal flow conditions to the closest horizontal well lateral intake.

(6) Turbidity measurements must be performed on representative samples from each wellhead at least every four hours that the bank filtration is in operation. Continuous turbidity monitoring at each wellhead may be used if the system validates the continuous measurement for accuracy on a regular basis using a protocol approved by the State. If the monthly average of daily maximum turbidity values at any well exceeds 1 NTU, the system must report this finding to the State within 30 days. In addition, within 30 days of the exceedance, the system must conduct an assessment to determine the cause of the high turbidity levels and submit that assessment to the State for a determination of whether any previously allowed credit is still appropriate.

(7) Systems with bank filtration that serves as pretreatment to a filtration plant and that exists when the system is required to conduct monitoring under § 141.702(a) may not claim this credit. During periods when the bank filtration is in use, systems must collect samples after the bank filtration for the purpose of determining bin classification under § 141.709.

§ 141.727 Treatment performance toolbox components.

(a) *Combined filter performance.* Systems using conventional filtration treatment or direct filtration treatment may claim an additional 0.5 log *Cryptosporidium* removal credit for any month at each plant that demonstrates that combined filter effluent (CFE) turbidity levels are less than or equal to 0.15 NTU in at least 95 percent of the measurements taken each month, based on sample measurements collected under §§ 141.73, 141.173(a) and 141.551. Systems may not claim credit under this paragraph and paragraph (b) in the same month.

(b) *Individual filter performance.* Systems using conventional filtration treatment or direct filtration treatment

may claim an additional 1.0 log *Cryptosporidium* removal credit for any month at each plant that meets both the individual filter effluent (IFE) turbidity requirements of paragraphs (b)(1) and (2) of this section, based on monitoring conducted under §§ 141.174(a) and 141.560.

(1) IFE turbidity must be less than 0.1 NTU in at least 95% of the maximum daily values recorded at each filter in each month, excluding the 15 minute period following return to service from a filter backwash.

(2) No individual filter may have a measured turbidity greater than 0.3 NTU in two consecutive measurements taken 15 minutes apart.

(c)(1) *Demonstration of performance.* Systems may demonstrate to the State, through the use of State-approved protocols, that a plant, or unit process of a plant, achieves a mean *Cryptosporidium* removal efficiency greater than any presumptive credit specified under § 141.720 or §§ 141.725 through 141.728. Systems are eligible for an increased *Cryptosporidium* removal credit if the State determines that the plant or process can reliably achieve such a removal efficiency on a continuing basis and the State provides written notification of its determination to the system. States may establish ongoing monitoring and/or performance requirements the State determines are necessary to demonstrate the greater credit and may require the system to report operational data on a monthly basis to verify that conditions under which the demonstration of performance was awarded are maintained during routine operations. If the State determines that a plant, or unit process of a plant, achieves an average *Cryptosporidium* removal efficiency less than any presumptive credit specified under § 141.720 or § 141.725 through 141.728, the State may assign the lower credit to the plant or unit process.

(2) Systems may not claim presumptive credit for any toolbox box component in §§ 141.726, 141.727(a) and (b), or 141.728 if that component is also included in the demonstration of performance credit.

§ 141.728 Additional filtration toolbox components.

(a) *Bag and cartridge filters.* Systems are eligible for a 1 log *Cryptosporidium* removal credit for bag filters and a 2 log *Cryptosporidium* removal credit for cartridge filters by meeting the criteria in paragraphs (a)(1) through (a)(10) of this section. The request to the State for this credit must include the results of challenge testing that meets the

requirements of paragraphs (a)(2) through (a)(9) of this section.

(1) To receive a 1 log *Cryptosporidium* removal credit for a bag filter, the filter must demonstrate a removal efficiency of 2 log or greater for *Cryptosporidium*. To receive a 2 log *Cryptosporidium* removal credit for a cartridge filter, the filter must demonstrate a removal efficiency of 3 log or greater for *Cryptosporidium*. Removal efficiency must be demonstrated through challenge testing conducted according to the criteria in paragraphs (a)(2) through (a)(9) of this section. The State may accept data from challenge testing conducted prior to [Date of Publication of Final Rule in the **Federal Register**] in lieu of additional testing if the prior testing was consistent with the criteria specified in paragraphs (a)(2) through (a)(9) of this section.

(2) Challenge testing must be performed on full-scale bag or cartridge filters that are identical in material and construction to the filters proposed for use in full-scale treatment facilities for removal of *Cryptosporidium*.

(3) Challenge testing must be conducted using *Cryptosporidium* oocysts or a surrogate that is removed no more efficiently than *Cryptosporidium* oocysts. The organism or surrogate used during challenge testing is referred to as the challenge particulate. The concentration of the challenge particulate must be determined using a method capable of discreetly quantifying the specific organism or surrogate used in the test; gross measurements such as turbidity may not be used.

(4) The maximum feed water concentration that can be used during a challenge test must be based on the detection limit of the challenge particulate in the filtrate (*i.e.*, filtrate detection limit) and must be calculated using the equation in either paragraph (a)(4)(i) or (a)(4)(ii) of this section as applicable.

(i) For cartridge filters: Maximum Feed Concentration = $3.16 \times 10^4 \times$ (Filtrate Detection Limit).

(ii) For bag filters: Maximum Feed Concentration = $3.16 \times 10^3 \times$ (Filtrate Detection Limit).

(5) Challenge testing must be conducted at the maximum design flow rate for the filter as specified by the manufacturer.

(6) Each filter evaluated must be tested for a duration sufficient to reach 100 percent of the terminal pressure drop, which establishes the maximum pressure drop under which the filter may be used to comply with the requirements of this subpart.

(7) Each filter evaluated must be challenged with the challenge particulate during three periods over the filtration cycle: within two hours of start-up after a new bag or cartridge filter has been installed; when the pressure drop is between 45 and 55 percent of the terminal pressure drop; and at the end of the run after the pressure drop has reached 100 percent of the terminal pressure drop.

(8) Removal efficiency of a bag or cartridge filter must be determined from the results of the challenge test and expressed in terms of log removal values using the following equation:

$$LRV = \text{LOG}_{10}(C_f) - \text{LOG}_{10}(C_p)$$

where LRV = log removal value demonstrated during challenge testing; C_f = the feed concentration used during the challenge test; and C_p = the filtrate concentration observed during the challenge test. In applying this equation, the same units must be used for the feed and filtrate concentrations. If the challenge particulate is not detected in the filtrate, then the term C_p must be set equal to the detection limit. An LRV must be calculated for each filter evaluated during the testing.

(9) If fewer than 20 filters are tested, the removal efficiency for the filtration device must be set equal to the lowest of the representative LRVs among the filters tested. If 20 or more filters are tested, then removal efficiency of the filtration device must be set equal to the 10th percentile of the representative LRVs among the various filters tested. The percentile is defined by $(i/(n+1))$ where i is the rank of n individual data points ordered lowest to highest. If necessary, the system may calculate the 10th percentile using linear interpolation.

(10) If a previously tested bag or cartridge filter is modified in a manner that could change the removal efficiency of the filter, additional challenge testing to demonstrate the removal efficiency of the modified filter must be conducted and submitted to the State.

(b) *Membrane filtration.* (1) Systems using a membrane filtration process, including a membrane cartridge filter that meets the definition of membrane filtration and the integrity testing requirements of this subpart, are eligible for a *Cryptosporidium* removal credit equal to the lower value of paragraph (b)(1)(i) or (b)(1)(ii) of this section:

(i) The removal efficiency demonstrated during challenge testing conducted under the conditions in paragraph (b)(2) of this section.

(ii) The maximum removal efficiency that can be verified through direct integrity testing used with the

membrane filtration process under the conditions in paragraph (b)(3) of this section.

(2) *Challenge Testing.* The membrane used by the system must undergo challenge testing to evaluate removal efficiency, and the system must submit the results of challenge testing to the State. Challenge testing must be conducted according to the criteria in paragraphs (b)(2)(i) through (b)(2)(vii) of this section. The State may accept data from challenge testing conducted prior to [Date of Publication of Final Rule in the **Federal Register**] in lieu of additional testing if the prior testing was consistent with the criteria in paragraphs (b)(2)(i) through (b)(2)(vii) of this section.

(i) Challenge testing must be conducted on either a full-scale membrane module, identical in material and construction to the membrane modules used in the system's treatment facility, or a smaller-scale membrane module, identical in material and similar in construction to the full-scale module.

(ii) Challenge testing must be conducted using *Cryptosporidium* oocysts or a surrogate that is removed no more efficiently than *Cryptosporidium* oocysts. The organism or surrogate used during challenge testing is referred to as the challenge particulate. The concentration of the challenge particulate must be determined using a method capable of discretely quantifying the specific challenge particulate used in the test; gross measurements such as turbidity may not be used.

(iii) The maximum feed water concentration that can be used during a challenge test is based on the detection limit of the challenge particulate in the filtrate and must be determined according to the following equation:

$$\text{Maximum Feed Concentration} = 3.16 \times 10^6 \times (\text{Filtrate Detection Limit})$$

(iv) Challenge testing must be conducted under representative hydraulic conditions at the maximum design flux and maximum design process recovery specified by the manufacture for the membrane module. Flux is defined as the rate of flow per unit of membrane area. Recovery is defined as the ratio of filtrate volume produced by a membrane to feed water volume applied to a membrane over the course of an uninterrupted operating cycle. An operating cycle is bounded by two consecutive backwash or cleaning events. For the purpose of challenge testing in this section, recovery does not consider losses that occur due to the use

of filtrate in backwashing or cleaning operations.

(v) Removal efficiency of a membrane module during challenge testing must be determined as a log removal using the following equation:

$$\text{LRV} = \text{LOG}_{10}(C_f) - \text{LOG}_{10}(C_p)$$

where LRV = log removal value demonstrated during challenge testing; C_f = the feed concentration used during the challenge test; and C_p = the filtrate concentration observed during the challenge test. Equivalent units must be used for the feed and filtrate concentrations. If the challenge particulate is not detected in the filtrate, the term C_p is set equal to the detection limit. An LRV must be calculated for each membrane module evaluated during the test.

(vi) The removal efficiency of a membrane filtration process demonstrated during challenge testing must be expressed as a log removal value ($\text{LRV}_{\text{C-Test}}$). If fewer than 20 modules are tested, then $\text{LRV}_{\text{C-Test}}$ is equal to the lowest of the representative LRVs among the applicable modules tested. If 20 or more modules are tested, then $\text{LRV}_{\text{C-Test}}$ is equal to the 10th percentile of the representative LRVs among the applicable modules tested. The percentile is defined by $(i/(n+1))$ where i is the rank of n individual data points ordered lowest to highest. If necessary, the 10th percentile may be calculated using linear interpolation.

(vii) The challenge test must establish a quality control release value (QCRV) for a non-destructive performance test that demonstrates the *Cryptosporidium* removal capability of the membrane filtration process. This performance test must be applied to each production membrane module used by the system that did not undergo a challenge test in order to verify *Cryptosporidium* removal capability. Production modules that do not meet the established QCRV are not eligible for the removal credit demonstrated during the challenge test.

(viii) If a previously tested membrane is modified in a manner that could change the removal efficiency of the membrane or the applicability of the non-destructive performance test and associated QCRV, additional challenge testing to demonstrate the removal efficiency of, and determine a new QCRV for, the modified membrane must be conducted and submitted to the State.

(3) *Direct integrity testing.* Systems must conduct direct integrity testing in a manner that demonstrates a removal efficiency equal to or greater than the removal credit awarded to the membrane filtration process and meets

the requirements described in paragraphs (b)(3)(i) through (b)(3)(vi) of this section.

(i) The direct integrity test must be independently applied to each membrane unit in service. A membrane unit is a group of membrane modules that share common valving that allows the unit to be isolated from the rest of the system for the purpose of integrity testing or maintenance.

(ii) The direct integrity method must have a resolution of 3 μm or less, where resolution is defined as the smallest leak size that contributes to a response from the direct integrity test.

(iii) The system must demonstrate that the direct integrity test can verify the log removal credit awarded to the membrane filtration process by the State using the approach in either paragraph (b)(2)(iii)(A) or (b)(2)(iii)(B) of this section as applicable based on the type of direct integrity test.

(A) For direct integrity tests that use an applied pressure or vacuum, the maximum log removal value that can be verified by the test must be calculated according to the following equation:

$$\text{LRV}_{\text{DIT}} = \text{LOG}_{10}(Q_p / (\text{VCF} \times Q_{\text{breach}}))$$

where LRV_{DIT} = maximum log removal value that can be verified by a direct integrity test; Q_p = total design filtrate flow from the membrane unit; Q_{breach} = flow of water from an integrity breach associated with the smallest integrity test response that can be reliably measured, and VCF = volumetric concentration factor. The volumetric concentration factor is the ratio of the suspended solids concentration on the high pressure side of the membrane relative to that in the feed water.

(B) For direct integrity tests that use a particulate or molecular marker, the maximum log removal value that can be verified by the test must be calculated according to the following equation:

$$\text{LRV}_{\text{DIT}} = \text{LOG}_{10}(C_f) - \text{LOG}_{10}(C_p)$$

where LRV_{DIT} = maximum log removal value that can be verified by a direct integrity test; C_f = the typical feed concentration of the marker used in the test; and C_p = the filtrate concentration of the marker from an integral membrane unit.

(iv) Systems must establish a control limit for the direct integrity test that is indicative of an integral membrane unit capable of meeting the removal credit awarded by the State.

(v) If the result of a direct integrity test is outside the control limit established under paragraphs (b)(3)(i) through (b)(3)(iv) of this section, the membrane unit must be removed from service. A direct integrity test must be

conducted to verify any repairs, and the membrane unit may be returned to service only if the direct integrity test is within the established control limit.

(vi) Direct integrity testing must be conducted on each membrane unit at a frequency of not less than once each day that the membrane unit is in operation.

(4) *Indirect integrity monitoring.*

Systems must conduct continuous indirect integrity monitoring on each membrane unit according to the criteria in paragraphs (b)(4)(i) through (b)(4)(v) of this section. A system that implements continuous direct integrity testing of membrane units in accordance with the criteria in paragraphs (b)(3)(i) through (b)(3)(v) of this section is not subject to the requirements for continuous indirect integrity monitoring.

(i) Unless the State approves an alternative parameter, continuous indirect integrity monitoring must include continuous filtrate turbidity monitoring.

(ii) Continuous monitoring must be conducted at a frequency of no less than once every 15 minutes.

(iii) Continuous monitoring must be separately conducted on each membrane unit.

(iv) If indirect integrity monitoring includes turbidity and if the filtrate turbidity readings are above 0.15 NTU

for a period greater than 15 minutes (*i.e.*, two consecutive 15-minute readings above 0.15 NTU), direct integrity testing must be performed on the associated membrane units as specified in paragraphs (b)(3)(i) through (b)(3)(v) of this section.

(v) If indirect integrity monitoring includes a State-approved alternative parameter and if the alternative parameter exceeds a State-approved control limit for a period greater than 15 minutes, direct integrity testing must be performed on the associated membrane units as specified in paragraphs (b)(3)(i) through (b)(3)(v) of this section.

(c) *Second stage filtration.* Systems are eligible for an additional 0.5 log *Cryptosporidium* removal credit if they have a separate second stage filtration process consisting of rapid sand, dual media, GAC, or other fine grain media in a separate stage following rapid sand or dual media filtration. To be eligible for this credit, the first stage of filtration must be preceded by a coagulation step and both filtration stages must treat 100% of the flow. A cap, such as GAC, on a single stage of filtration is not eligible for this credit.

(d) *Slow sand filtration.* Systems may claim a 2.5 log *Cryptosporidium* removal credit for a slow sand filtration process that follows another separate filtration process if all the flow is

treated by both processes and no disinfectant residual is present in the influent water to the slow sand filtration process.

§ 141.729 Inactivation toolbox components.

(a) *Calculation of CT values.* (1) CT is the product of the disinfectant contact time (T, in minutes) and disinfectant concentration (C, in milligrams per liter). Systems must calculate CT at least once each day, with both C and T measured during peak hourly flow as specified in §§ 141.74(a) and 141.74(b).

(2) Systems with several disinfection segments (a segment is defined as a measurable disinfectant residual level and a liquid volume) in sequence along the treatment train, may calculate the CT for each disinfection segment and use the sum of the *Cryptosporidium* log inactivation values achieved through the plant.

(b) *CT values for chlorine dioxide.* (1) Systems using chlorine dioxide must calculate CT in accordance with § 141.729(a).

(2) Unless the State approves alternative CT values for a system under paragraph (b)(3) of this section, systems must use the following table to determine *Cryptosporidium* log inactivation credit:

CT VALUES FOR *Cryptosporidium* INACTIVATION BY CHLORINE DIOXIDE

Log credit	Water Temperature, °C ¹									
	<=0.5	1	2	3	5	7	10	15	20	25
0.5	319	305	279	256	214	180	138	89	58	38
1.0	637	610	558	511	429	360	277	179	116	75
1.5	956	915	838	767	643	539	415	268	174	113
2.0	1275	1220	1117	1023	858	719	553	357	232	150
2.5	1594	1525	1396	1278	1072	899	691	447	289	188
3.0	1912	1830	1675	1534	1286	1079	830	536	347	226

¹ CT values between the indicated temperatures may be determined by interpolation.

(3) Systems may conduct a site-specific inactivation study to determine the CT values necessary to meet a specified *Cryptosporidium* log inactivation level, using a State-approved protocol. The alternative CT

values determined from the site-specific study and the method of calculation must be approved by the State.

(c) *CT values for ozone.* (1) Systems using ozone must calculate CT in accordance with § 141.729(a).

(2) Unless the State approves alternative CT values for a system under paragraph (c)(3) of this section, systems must use the following table to determine *Cryptosporidium* log inactivation credit:

CT VALUES FOR *Cryptosporidium* INACTIVATION BY OZONE

Log credit	Water Temperature, °C ¹									
	<=0.5	1	2	3	5	7	10	15	20	25
0.5	12	12	10	9.5	7.9	6.5	4.9	3.1	2.0	1.2
1.0	24	23	21	19	16	13	9.9	6.2	3.9	2.5
1.5	36	35	31	29	24	20	15	9.3	5.9	3.7
2.0	48	46	42	38	32	26	20	12	7.8	4.9
2.5	60	58	52	48	40	33	25	16	9.8	6.2

CT VALUES FOR *Cryptosporidium* INACTIVATION BY OZONE—Continued

Log credit	Water Temperature, °C ¹									
	<=0.5	1	2	3	5	7	10	15	20	25
3.0	72	69	63	57	47	39	30	19	12	7.4

¹ CT values between the indicated temperatures may be determined by interpolation

(3) Systems may conduct a site-specific inactivation study to determine the CT values necessary to meet a specified *Cryptosporidium* log inactivation level, using a State-approved protocol. The alternative CT values determined from the site-specific study and the method of calculation must be approved by the State.

(d) *Ultraviolet light.* (1) Systems may claim credit for ultraviolet (UV) processes for inactivation of

Cryptosporidium, *Giardia lamblia*, and viruses. The allowable inactivation credit for each pathogen must be based on the UV dose delivered by the system's UV reactors in relation to the UV dose table in paragraph (d)(2) of this section.

(2) *UV dose table.* The log credits given in this UV dose table are for UV light at a wavelength of 254 nm as produced by a low pressure mercury vapor lamp. Systems may apply this

table to UV reactors with other lamp types through reactor validation testing (*i.e.*, performance demonstration) as described in paragraph (d)(3) of this section. The UV dose values in this table are applicable only to post-filter application of UV in systems that filter under subpart H of this part and to unfiltered systems meeting the filtration avoidance criteria in subparts H, P, and T of this part:

UV DOSE TABLE FOR *Cryptosporidium*, GIARDIA LAMBLIA, AND VIRUS INACTIVATION CREDIT

Log credit	<i>Cryptosporidium</i> UV Dose (mJ/cm ²)	<i>Giardia lamblia</i> UV dose (mJ/cm ²)	Virus UV dose (mJ/cm ²)
0.5	1.6	1.5	39
1.0	2.5	2.1	58
1.5	3.9	3.0	79
2.0	5.8	5.2	100
2.5	8.5	7.7	121
3.0	12	11	143
3.5	NA	NA	163
4.0	NA	NA	186

(3) *Reactor validation testing.* For a system to receive inactivation credit for a UV reactor, the reactor must undergo the validation testing in paragraphs (d)(3)(i) and (d)(3)(ii) of this section, unless the State approves an alternative approach. The validation testing must demonstrate the operating conditions under which the reactor can deliver the UV dose required in paragraph (d)(2) of this section.

(i) Validation testing of UV reactors must determine a range of operating conditions that can be monitored by the system and under which the reactor delivers the required UV dose. At a minimum, these operating conditions must include flow rate, UV intensity as measured by a UV sensor, and UV lamp status. The validated operating conditions determined by this testing must account for the following: UV absorbance of the water; lamp fouling and aging; measurement uncertainty of on-line sensors; UV dose distributions arising from the velocity profiles through the reactor; failure of UV lamps or other critical system components; and inlet and outlet piping or channel configurations of the UV reactor.

(ii) Validation testing must include the following: full scale testing of a reactor that conforms uniformly to the UV reactors used by the system; and inactivation of a test microorganism whose dose response characteristics have been quantified with a low pressure mercury vapor lamp.

(4) *Reactor monitoring.* Systems must monitor their UV reactors to demonstrate that they are operating within the range of conditions that were validated by the testing described in paragraphs (d)(3)(i) and (d)(3)(ii) of this section to achieve the required UV dose in paragraph (d)(2) of this section. Systems must monitor for UV intensity as measured by a UV sensor, flow rate, and lamp outage and for any other parameters required by the State. Systems must verify the calibration of UV sensors and must recalibrate sensors in accordance with a protocol approved by the State.

Reporting and Recordkeeping Requirements

§ 141.730 Reporting requirements.

(a) Systems must follow the requirements for reporting sampling schedules under § 141.703 and for

reporting source water monitoring results under § 141.707 unless they notify the State that they will not conduct source water monitoring due to meeting the criteria of § 141.701(f) or (g).

(b) Systems using uncovered finished water storage facilities must notify the State of the use of each facility no later than [Date 24 Months After Date of Publication of Final Rule in the **Federal Register**].

(c) Filtered systems and unfiltered systems that are required to install filtration must report their *Cryptosporidium* bin classification, as determined under using the procedures in § 141.709, to the State by the applicable dates in paragraph (c)(1) or (2) of this section.

(1) Systems that serve at least 10,000 people must report their initial bin classification no later than [Date 36 Months After Date of Publication of Final Rule in the **Federal Register**] and must report their bin classification determined using results from the second round of source water monitoring no later than [Date 138 Months After Date of Publication of Final Rule in the **Federal Register**].

(2) Systems that serve fewer than 10,000 people must report their initial bin classification no later than [Date 66 Months After Date of Publication of Final Rule in the **Federal Register**] and must report their bin classification determined using results from the second round of source water monitoring no later than [Date 174 Months After Date of Publication of Final Rule in the **Federal Register**].

(d) Unfiltered systems that meet all filtration avoidance criteria of § 141.71 must report their mean *Cryptosporidium* concentration, as determined under § 141.721, to the State by the applicable dates in paragraph (d)(1) or (2) of this section.

(1) Systems that serve at least 10,000 people must report their initial mean *Cryptosporidium* concentration no later than [Date 36 Months After Date of Publication of Final Rule in the **Federal Register**] and must report their mean *Cryptosporidium* concentration determined using results from the second round of source water monitoring no later than [Date 138 Months After Date of Publication of Final Rule in the **Federal Register**].

(2) Systems that serve fewer than 10,000 people must report their initial mean *Cryptosporidium* concentration no later than [Date 66 Months After Date of Publication of Final Rule in the **Federal Register**] and must report their mean

Cryptosporidium concentration determined using results from the second round of source water monitoring no later than [Date 174 Months After Date of Publication of Final Rule in the **Federal Register**].

(e) Systems must report to the State in accordance with the following table in this paragraph for any toolbox options used to comply with the *Cryptosporidium* treatment technique requirements under § 141.720 or § 141.721. The State may place additional reporting requirements it determines to be necessary to verify operation in accordance with required criteria for all toolbox options:

MICROBIAL TOOLBOX REPORTING REQUIREMENTS

Toolbox option	Systems must submit the following information	On the following schedule ¹ —systems serving ≥ 10,000 people	On the following schedule ¹ —systems serving < 10,000 people
(1) Watershed control program (WCP).	(i) Notify State of intention to develop WCP. (ii) Submit initial WCP plan to State. (iii) Annual report and State-approved watershed survey report. (iv) Request for re-approval and report on the previous approval period.	No later than [Date 48 Months After Date of Publication of Final Rule in the Federal Register]. No later than [Date 60 Months After Date of Publication of Final Rule in the Federal Register]. By a date determined by the State, every 12 months, beginning on [Date 84 Months After Date of Publication of Final Rule in the Federal Register]. Six months prior to the end of the current approval period or by a date previously determined by the State.	No later than [Date 78 Months After Date of Publication of Final Rule in the Federal Register]. No later than [Date 90 Months After Date of Publication of Final Rule in the Federal Register]. By a date determined by the State, every 12 months, beginning on [Date 114 Months After Date of Publication of Final Rule in the Federal Register]. Six months prior to the end of the current approval period or by a date previously determined by the State.
(2) Bank filtration	(i) Initial demonstration of the following: unconsolidated, predominantly sandy aquifer and setback distance of at least 25 ft. (0.5 log credit) or 50 ft. (1.0 log credit). (ii) If monthly average of daily max turbidity is greater than 1 NTU then system must report result and submit an assessment of the cause.	Initial demonstration no later than [Date 72 Months after Date of Publication of Final Rule in the Federal Register]. Report within 30 days following the month in which the monitoring was conducted, beginning on [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Initial demonstration no later than [Date 102 Months after Date of Publication of Final Rule in the Federal Register]. Report within 30 days following the month in which the monitoring was conducted, beginning on [Date 102 Months After Date of Publication of Final Rule in the Federal Register].
(3) Presedimentation	Monthly verification of the following; Continuous basin operation; treatment of 100% of the flow; continuous addition of a coagulant; and at least 0.5 log removal of influent turbidity based on the monthly mean of daily turbidity readings for 11 of the 12 previous months.	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on [Date 102 Months After Date of Publication of Final Rule in the Federal Register].
(4) Two-stage lime softening	Monthly verification of the following: Continuous operation of a second clarification step between the primary clarifier and filter; continuous presence of a coagulant in both primary and secondary clarifiers; and both clarifiers treated 100% of the plant flow.	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on [Date 102 Months After Date of Publication of Final Rule in the Federal Register].

MICROBIAL TOOLBOX REPORTING REQUIREMENTS—Continued

Toolbox option	Systems must submit the following information	On the following schedule ¹ —systems serving ≥ 10,000 people	On the following schedule ¹ —systems serving < 10,000 people
(5) Combined filter performance	Monthly verification of combined filter effluent (CFE) turbidity levels less than or equal to 0.15 NTU in at least 95 percent of the 4 hour CFE measurements taken each month.	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on [Date 102 Months After Date of Publication of Final Rule in the Federal Register].
(6) Individual filter performance	Monthly verification of the following: Individual filter effluent (IFE) turbidity levels less than or equal to 0.1 NTU in at least 95 percent of all daily maximum IFE measurements taken each month (excluding 15 min period following start-up after backwash); and no individual filter greater than 0.3 NTU in two consecutive readings 15 minutes apart.	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Monthly reporting within 10 days following the month in which the monitoring was conducted, beginning on [Date 102 Months After Date of Publication of Final Rule in the Federal Register].
(7) Membrane filtration	<p>(i) Results of verification testing demonstrating the following: Removal efficiency established through challenge testing that meets criteria in this subpart; and integrity testing and associated baseline.</p> <p>(ii) Monthly report summarizing all direct integrity tests above the control limit and, if applicable, any indirect integrity monitoring results triggering direct integrity testing and the corrective action that was taken.</p>	<p>No later than [Date 72 Months After Date of Publication of Final Rule in the Federal Register].</p> <p>Within 10 days following the month in which monitoring was conducted, beginning [Date 72 Months After Date of Publication of Final Rule in the Federal Register].</p>	<p>No later than [Date 102 Months After Date of Publication of Final Rule in the Federal Register].</p> <p>Within 10 days following the month in which monitoring was conducted, beginning [Date 102 Months After Date of Publication of Final Rule in the Federal Register].</p>
(8) Bag filters and cartridge filters	<p>(i) Demonstration that the following criteria are met: process meets the definition of bag or cartridge filtration; removal efficiency established through challenge testing that meets criteria in this subpart; and challenge test shows at least 2 log removal for bag filters and 3 log removal for cartridge filters.</p> <p>(ii) Monthly verification that 100% of flow was filtered.</p>	<p>No later than [Date 72 Months After Date of Publication of Final Rule in the Federal Register].</p> <p>Within 10 days following the month in which monitoring was conducted, beginning [Date 72 Months After Date of Publication of Final Rule in the Federal Register].</p>	<p>No later than [Date 102 Months After Date of Publication of Final Rule in the Federal Register].</p> <p>Within 10 days following the month in which monitoring was conducted, beginning [Date 102 Months After Date of Publication of Final Rule in the Federal Register].</p>
(9) Second stage filtration	Monthly verification that 100% of flow was filtered through both stages.	Within 10 days following the month in which monitoring was conducted, beginning [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Within 10 days following the month in which monitoring was conducted, beginning [Date 102 Months After Date of Publication of Final Rule in the Federal Register].
(10) Slow and filtration	Monthly verification that 100% of flow was filtered.	Within 10 days following the month in which monitoring was conducted, beginning [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Within 10 days following the month in which monitoring was conducted, beginning [Date 102 Months After Date of Publication of Final Rule in the Federal Register].
(11) Chlorine dioxide	Summary of CT values for each day based on Table in § 141.729(b).	Within 10 days following the month in which monitoring was conducted, beginning [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Within 10 days following the month in which monitoring was conducted, beginning [Date 102 Months After Date of Publication of Final Rule in the Federal Register].

MICROBIAL TOOLBOX REPORTING REQUIREMENTS—Continued

Toolbox option	Systems must submit the following information	On the following schedule ¹ —systems serving ≥ 10,000 people	On the following schedule ¹ —systems serving < 10,000 people
(12) Ozone	Summary of CT values for each day based on Table in § 141.729(c).	Within 10 days following the month in which monitoring was conducted, beginning [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	Within 10 days following the month in which monitoring was conducted, beginning [Date 102 Months After Date of Publication of Final Rule in the Federal Register].
(13) UV	(i) Validation test results demonstrating operating conditions that achieve required UV dose. (ii) Monthly report summarizing the percentage of water entering the distribution system that was not treated by UV reactors operating within validated conditions for the required dose as specified in § 141.729(d).	No later than [Date 72 Months After Date of Publication of Final Rule in the Federal Register]. Within 10 days following the month in which monitoring was conducted, beginning [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	No later than [Date 102 Months After Date of Publication of Final Rule in the Federal Register]. Within 10 days following the month in which monitoring was conducted, beginning [Date 102 Months After Date of Publication of Final Rule in the Federal Register].
(14) Demonstration of performance	(i) Results from testing following a State approved protocol. (ii) As required by the State, monthly verification of operation within conditions of State approval for demonstration of performance credit.	No later than [Date 72 Months After Date of Publication of Final Rule in the Federal Register]. Within 10 days following the month in which monitoring was conducted, beginning [Date 72 Months After Date of Publication of Final Rule in the Federal Register].	No later than [Date 102 Months After Date of Publication of Final Rule in the Federal Register]. Within 10 days following the month in which monitoring was conducted, beginning [Date 102 Months After Date of Publication of Final Rule in the Federal Register].

¹States may allow up to an additional two years to the date when the first submittal must be completed for systems making capital improvements.

(f) Systems must report to the State the information associated with disinfection profiling and benchmarking requirements of §§ 141.711 to 141.714 in accordance with the tables in this paragraph.

TABLE 1.—DISINFECTION PROFILING REPORTING REQUIREMENTS FOR LARGE SYSTEMS
[Serving ≥10,000 people]

System type	Benchmark component	Submit the following items	On the following schedule
(1) Systems required to conduct <i>Cryptosporidium</i> monitoring.	(i) Characterization of disinfection practices. See § 141.713.	<i>Giardia lamblia</i> and virus inactivation profiles must be on file for State review during sanitary survey.	No later than [Date 36 Months After Date of Publication of Final Rule in the Federal Register].
	(ii) State review of proposed significant changes to disinfection practice. See § 141.714.	Inactivation profile and benchmark determinations.	Prior to significant modification of disinfection practice.
(2) Systems not required to conduct <i>Cryptosporidium</i> monitoring ^a .	(i) Applicability	None	None.
	(ii) Characterization of Disinfection Practices.	None	None.
	(iii) State Review of Proposed Changes to Disinfection Practices.	None	None.

^aSystems that provide at least 5.5 log of *Cryptosporidium* treatment, consistent with a Bin 4 treatment requirement, are not required to conduct *Cryptosporidium* monitoring.

TABLE 2.—DISINFECTION PROFILING REPORTING REQUIREMENTS FOR SMALL SYSTEMS
[Serving < 10,000 people]

System type	Benchmark component	Submit the following items	On the following schedule
(1) Systems required to conduct <i>Cryptosporidium</i> monitoring.	(i) Characterization of disinfection practices. See § 141.713.	<i>Giardia lamblia</i> and virus disinfection profiles must be on file for State review during sanitary survey.	No later than [Date 66 Months After Date of Publication of Final Rule in the Federal Register].

TABLE 2.—DISINFECTION PROFILING REPORTING REQUIREMENTS FOR SMALL SYSTEMS—Continued
[Serving < 10,000 people]

System type	Benchmark component	Submit the following items	On the following schedule
(2) Systems not required to conduct <i>Cryptosporidium</i> monitoring and that exceed DBP triggers ^{a,b,c} .	(ii) State review of proposed significant changes to disinfection practices. See § 141.714.	Disinfection profiles and benchmark determinations.	Prior to significant modification of disinfection practice.
	(i) Determination of requirement to profile. See § 141.711(b).	Report on TTHM and HAA5 LRAA values from monitoring under subpart L.	No later than [Date 42 Months After Date of Publication of Final Rule in the Federal Register].
(3) Systems not required to conduct <i>Cryptosporidium</i> monitoring and that do not exceed DBP triggers ^{b,c} .	(ii) Characterization of disinfection practices. See § 141.713.	<i>Giardia lamblia</i> and virus disinfection profiles must be on file for State review during sanitary survey.	No later than [Date 54 Months after Date of Publication of Final Rule in the Federal Register].
	(iii) State review of proposed significant changes to disinfection practices. See § 141.714.	Disinfection profiles and benchmark determinations.	Prior to significant modification of disinfection practice.
	(i) Determination of no requirement to profile. See § 141.711(b).	Report on TTHM and HAA5 LRAA values from monitoring under subpart L.	No later than [Date 42 Months After Date of Publication of Final Rule in the Federal Register].
	(ii) Characterization of disinfection practices. See § 141.713.	None	None.
	(iii) State review of proposed significant changes to disinfection practice. See § 141.714.	None	None.

^a Systems that provide at least 5.5 log of *Cryptosporidium* treatment, consistent with a Bin 4 treatment requirement, are not required to conduct *Cryptosporidium* monitoring.

^b See § 141.702(b) to determine if *Cryptosporidium* monitoring is required.

^c See § 141.711(b) to determine if disinfection profiling is required based on TTHM or HAA5 LRAA.

§ 141.731 Recordkeeping requirements.

(a) Systems must keep results from monitoring required under § 141.702 until 36 months after all source water monitoring required under this section has been completed.

(b) Systems must keep a record of any notification to the State that they will not conduct source water monitoring due to meeting the criteria of § 141.701(f) or (g).

(c) Systems required to develop disinfection profiles under § 141.711 must keep disinfection profiles on file for State review during sanitary surveys.

PART 142—NATIONAL PRIMARY DRINKING WATER REGULATIONS IMPLEMENTATION

5. The authority citation for part 142 continues to read as follows:

Authority: 42 U.S.C. 300f, 300g-1, 300g-2, 300g-3, 300g-4, 300g-5, 300g-6, 300j-4, 300j-9 and 300j-11.

6. Section 142.14 is amended by adding paragraphs (a)(8) and (a)(9) to read as follows:

§ 142.14 Records kept by States.

* * * * *

(a) * * *

(8) [Reserved]

(9) Any decisions made pursuant to the provisions of part 141, subpart W of this chapter.

(i) Results of source water *E. coli* and *Cryptosporidium* monitoring.

(ii) Initial bin classification for each system that currently provides filtration or that is unfiltered and required to install filtration, along with any change in bin classification due to watershed assessment during sanitary surveys or the second round of source water monitoring.

(iii) A determination of whether each system that is unfiltered and meets all the filtration avoidance criteria of § 141.71 of this chapter has a mean source water *Cryptosporidium* level above 0.01 oocysts/L, along with any changes in this determination due to the second round of source water monitoring.

(iv) The treatment or control measures that systems use to meet their *Cryptosporidium* treatment requirements under § 141.720 or § 141.721 of this section.

(v) A list of systems required to cover or treat the effluent of an uncovered finished water reservoir.

(vi) A list of systems for which the State has waived the requirement to cover or treat the effluent of uncovered finished water storage facilities and supporting documentation of the risk mitigation plan.

* * * * *

7. Section 142.15 is amended by adding paragraph (c)(6) to read as follows:

§ 142.15 Reports by States.

(c) * * *

(6) *Subpart W.* (i) The initial bin classification for each system that currently provides filtration or that is unfiltered and required to install filtration, along with any change in bin classification due to watershed assessment during sanitary surveys or the second round of source water monitoring.

(ii) A determination of whether each system that is unfiltered and meets all the filtration avoidance criteria of § 141.71 of this chapter has a mean source water *Cryptosporidium* level above 0.01 oocysts/L, along with any changes in this determination due to the second round of source water monitoring.

* * * * *

8. Section 142.16 is amended by adding paragraphs (m) and (n) to read as follows:

§ 142.16 Special primacy conditions.

* * * * *

(m) [Reserved]

(n) *Requirements for States to adopt 40 CFR part 141, subpart W.* In addition to the general primacy requirements elsewhere in this part, including the requirements that State regulations be at least as stringent as federal requirements, an application for approval of a State program revision that adopts 40 CFR part 141, subpart W,

must contain a description of how the State will accomplish the following program requirements where allowed in State programs.

(1) Assess significant changes in the watershed and source water as part of the sanitary survey process and determine appropriate follow-up action.

(2) Approve watershed control programs for the 0.5 log watershed control program credit in the microbial toolbox.

(3) Approval protocols for treatment credits under the Demonstration of Performance toolbox option and for alternative ozone and chlorine dioxide CT values.

(4) Determine that a system with an uncovered finished water reservoir has a risk mitigation plan that is adequate for purposes of waiving the requirement to cover or treat the reservoir.

[FR Doc. 03-18295 Filed 8-8-03; 8:45 am]

BILLING CODE 6560-50-P